
AI in Education Knowledge Base



Public Domain

Notice

AI in Education Knowledge Base

Edited by Doug Holton.

This ebook was produced by an **AI agent** working for a human editor, and is dedicated to the public domain under a **CC0 1.0** license - no rights reserved. You may copy, modify, distribute, and use the content for any purpose without asking permission.

Generated: November 04, 2026

Public Domain

⚠️ **Disclaimer:** AI-generated output may contain inaccuracies or errors.

How this text was made: drafted with the help of a large language model, then reviewed, corrected, and published by the editor. The full AI-use disclosure is in `AI-USE.md` in the source repository.

This document contains the concept and FAQ pages, but not the hundreds of article summaries available on the AI in Education Knowledge Base website (https://edtechdev.github.io/aied/).

The source code for the website and these documents is available in the GitHub repository.

Found an issue with the content? Please report it on GitHub, or contact the site developer, Doug Holton.

The latest edition of the AI in Education Knowledge Base is available online at https://edtechdev.github.io/aied/.

AI in Education Knowledge Base

1. Introduction 14
    1.1. Navigating the site 14
    1.2. Chat with the knowledge base 14
    1.3. Recommended starting points by audience 14
    1.4. What is in the knowledge base 15
2. Use This Knowledge Base with Your Own AI Assistant 16
3. Foundations of AI in education 19
    3.1. Essentials 19
        3.1.1. AI in Education 20
        3.1.2. AI Literacy 30
        3.1.3. Agentic AI 54
        3.1.4. Cognitive Offloading 69
        3.1.5. Cognitive Surrender 90
        3.1.6. Framing AI Use for Students 97
        3.1.7. Reducing AI Misuse 103
        3.1.8. Academic Integrity 112
        3.1.9. Teaching 132
        3.1.10. Teacher AI Competency 150
        3.1.11. Learning Design 164
        3.1.12. Educational Development 174
    3.2. The field 184
        3.2.1. History of AI in Education 185
        3.2.2. Interpreting and Applying AIEd Research 191
        3.2.3. Limitations in AIEd Research 199
        3.2.4. Philosophy of AI in Education 208
        3.2.5. Theories and Frameworks 214
        3.2.6. Theory Development in AI in Education 221
    3.3. Cross-cutting themes 229
        3.3.1. Human AI Collaboration 230
        3.3.2. Learner Agency 243
        3.3.3. Learner Identity 256
        3.3.4. Design Thinking 262
        3.3.5. Curriculum Design 266
        3.3.6. Critical Thinking 274
        3.3.7. Computational Thinking 283

3.4. Theories and frameworks (Foundations of AI in education) 288

3.4.1. SAMR Model 289

3.4.2. Technological Pedagogical Content Knowledge (TPACK) 294

4. Learning and instruction 303

4.1. Core pedagogies 303

4.1.1. Pedagogies and Teaching Strategies 304

4.1.2. Pedagogical Patterns 311

4.1.3. Active Learning 325

4.1.4. Collaborative Learning 332

4.1.5. Project-Based Learning 342

4.1.6. Problem-Based Learning 347

4.1.7. Productive Failure 353

4.1.8. Inquiry-Based Learning 359

4.1.9. Experiential Learning 364

4.1.10. Game-Based Learning 369

4.1.11. Learning by Teaching 374

4.1.12. Scaffolding 381

4.1.13. Socratic Method 392

4.1.14. Critical Pedagogy 399

4.1.15. Pedagogical Partnerships 405

4.1.16. Storytelling in Education 412

4.1.17. Online Teaching and Learning 415

4.1.18. Video in Education 426

4.2. Learning theories and processes 431

4.2.1. Learning Theories 432

4.2.2. Behaviorism 440

4.2.3. Constructivism 445

4.2.4. Cognitive Psychology 454

4.2.5. Sociocultural Learning 459

4.2.6. Distributed Cognition 464

4.2.7. Situated Learning 469

4.2.8. Embodied Learning 473

4.2.9. Community of Inquiry 478

4.2.10. Self-Regulated Learning 483

4.2.11. Self-Determination Theory 498

4.2.12. Motivation 503

4.2.13. Self-Efficacy 511

4.2.14. Self-Directed Learning 520

4.2.15. Metacognition 524
4.2.16. Reflection 537
4.2.17. Desirable Difficulties 546
4.2.18. Transfer of Learning 554
4.2.19. Prior Knowledge 560
4.2.20. ICAP Framework 565
4.2.21. Misconceptions about AI 571
4.2.22. Refutation Text 579
4.2.23. Activity Theory 583
4.2.24. Retrieval, Spacing and Interleaving 588
4.3. Learner engagement and experience 594
4.3.1. Student Engagement 595
4.3.2. Help-Seeking 607
4.3.3. Social-Emotional Learning 617
4.3.4. Well-Being 624
4.3.5. Creativity 631
4.3.6. Student-AI Interaction 638
4.3.7. Problem Solving 645
4.3.8. Mastery Learning 650
4.3.9. Anxiety and Stress 655
4.3.10. Student Experience 665
4.3.11. Student Support and Success 673
4.3.12. Social Norms of AI Use 680
4.4. Lifelong and professional learning 685
4.4.1. Career Development and Readiness 686
4.4.2. Lifelong Learning 692
4.4.3. Workplace Learning 696
5. Technologies and techniques 702
5.1. Models and techniques 702
5.1.1. Technologies 703
5.1.2. Machine Learning 708
5.1.3. Generative AI 714
5.1.4. Large Language Models (LLMs) 722
5.1.5. RAG (Retrieval-Augmented Generation) 728
5.1.6. Prompt Engineering 732
5.1.7. LLM Training and Fine-Tuning 741
5.1.8. Vibe Coding 754
5.1.9. Multimodal AI 760

5.1.10. Speech and Voice Technologies 769
5.1.11. Visualization 778
5.1.12. Educational NLP 783
5.1.13. Reinforcement Learning 789
5.1.14. Knowledge Graph 793
5.1.15. Robots in Education 798
5.1.16. Conversational AI 805
5.1.17. Simulation 813
5.1.18. Virtual and Augmented Reality 820
5.2. Learner modeling and adaptive systems 825
5.2.1. Learner Modeling and Adaptive Instruction 826
5.2.2. Knowledge Tracing 834
5.2.3. Cognitive Diagnosis 841
5.2.4. Simulating Students 848
5.2.5. Intelligent Tutoring 859
5.2.6. Adaptive Learning 875
5.2.7. Personalized Learning 883
5.2.8. Recommender Systems and Learning Paths 892
5.2.9. Pedagogical Agent 900
5.2.10. Affective Tutoring 908
5.2.11. Affective Computing 913
5.2.12. Sensor and Gaze Analytics 918
5.2.13. AI Avatars and Synthetic Instructors 924
5.2.14. Human-in-the-Loop 931
5.2.15. Learning Analytics 941
5.3. Platforms, openness and adoption 951
5.3.1. Technology Adoption Models 952
5.3.2. Open Education 961
5.3.3. Open Source 967
5.3.4. Edtech Platform 974
6. AI in the disciplines 981
6.1. Subject areas 981
6.1.1. AIEd in the Disciplines 982
6.1.2. Math Education 990
6.1.3. Statistics and Data Science Education 999
6.1.4. Physics Education 1004
6.1.5. Chemistry Education 1013
6.1.6. Biology Education 1018

6.1.7. CS Education 1022
6.1.8. Engineering Education 1035
6.1.9. STEM Education 1041
6.1.10. Science Education 1048
6.1.11. Writing 1055
6.1.12. Language Learning 1068
6.1.13. English Education (EAP / EFL / ESL) 1076
6.1.14. Environmental Education 1082
6.1.15. Business Education 1087
6.1.16. Humanities and Social Science Education 1093
6.1.17. Civic and Political Education 1097
6.1.18. Arts, Design and Media Education 1101
6.1.19. Design Education 1110
6.1.20. Medical and Health Professions Education 1116
6.1.21. Nursing Education 1125
6.1.22. Legal Education 1134
6.1.23. Information Technology Education 1139
6.2. Research fields 1143
6.2.1. Learning Sciences 1144
7. Levels and contexts 1152
7.1. Levels and settings 1152
7.1.1. K-12 1153
7.1.2. Early Childhood Education 1163
7.1.3. Higher Education 1170
7.1.4. Adult Learners 1180
7.1.5. Vocational Education and Training 1185
7.1.6. Special Education 1191
7.1.7. Teacher Education 1196
7.2. Bands and comparisons 1207
7.2.1. Levels of Education 1208
8. Assessment and measurement 1214
8.1. Assessment and feedback 1214
8.1.1. Assessment 1215
8.1.2. Evaluative Judgment 1224
8.1.3. Feedback 1233
8.1.4. Feedback Literacy 1247
8.1.5. AI Feedback Quality 1254

8.1.6. Formative Assessment 1265
8.1.7. Summative Assessment 1276
8.1.8. Authentic Assessment 1282
8.1.9. Process-Oriented Assessment 1291
8.1.10. Group Work 1298
8.1.11. E-Portfolio 1305
8.1.12. Peer Assessment 1309
8.1.13. Self-Assessment 1317
8.1.14. Oral Assessment 1324
8.1.15. Automated Assessment 1330
8.1.16. Automated Essay Scoring 1345
8.1.17. Automated Question Generation 1352
8.2. Measurement and validity 1358
8.2.1. Assessment Validity 1359
8.2.2. Psychometrically Aware AI 1375
8.2.3. Educational Measurement 1380
8.2.4. Item Response Theory 1394
8.2.5. Self-Report Measures 1400
8.2.6. AI Detection 1410
8.2.7. Remote Proctoring 1421
8.2.8. Learning Gains 1427
9. Research methods and evaluation 1438
9.1. Research methods 1438
9.1.1. Research Methods in AIED 1439
9.1.2. AI-Assisted Educational Research 1453
9.1.3. Qualitative Research 1463
9.1.4. Quantitative Research 1470
9.1.5. Mixed-Methods Research 1476
9.1.6. Design-Based Research 1480
9.1.7. Usability Research 1485
9.1.8. RCT 1489
9.1.9. Meta-Analysis and Systematic Review 1494
9.1.10. Latent Profile Analysis 1507
9.1.11. Network Analysis 1512
9.2. Evaluation of AI systems 1517
9.2.1. AI Ed Evaluation 1518
9.2.2. Benchmark 1528

10. People 1535

10.1. Roles and audiences 1535

10.1.1. Administrators 1536
10.1.2. Educational Technology Developers 1540
10.1.3. Learners 1546
10.1.4. Librarians 1553
10.1.5. Parents and Families 1558
10.1.6. Stakeholders 1565

11. Institutions and policy 1570

11.1. Institutions 1570

11.1.1. Educational AI Policy 1571
11.1.2. AI Governance 1583
11.1.3. Change Management 1594
11.1.4. AI Regulation in Education 1600

12. Equity, ethics, and responsible use 1605

12.1. Equity and access 1605

12.1.1. Equity 1606
12.1.2. Differential Effects Across Learner Groups 1620
12.1.3. Digital Divide 1629
12.1.4. Bias Mitigation 1636
12.1.5. Culturally Relevant Pedagogy 1643
12.1.6. Multilingual Learning 1649
12.1.7. Inclusive Learning 1653
12.1.8. Accessibility 1660
12.1.9. Assistive Technology 1666
12.1.10. Neurodiversity 1670
12.1.11. Universal Design for Learning 1675
12.1.12. Global South 1680

12.2. Ethics and responsibility 1685

12.2.1. Ethics 1686
12.2.2. AI Misuse and Learning Harm 1695
12.2.3. Legal Issues and Risks 1701
12.2.4. AI Use and Disclosure Statements 1708
12.2.5. Guardrails 1715
12.2.6. Privacy 1722
12.2.7. Hallucination Risk 1728
12.2.8. AI Sycophancy 1733

12.2.9. Trust 1739
12.2.10. Trust Calibration 1748
12.2.11. Explainable AI 1760
12.2.12. Sustainability 1767
12.2.13. Pedagogical Safety 1771

13. Frequently Asked Questions 1777

13.1. Start here 1777

13.1.1. What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About? 1778
13.1.2. How Can We Address Common Misconceptions About AI in Education? 1786

13.2. Course and institutional policy 1800

13.2.1. How Do I Write a Course AI Policy and Communicate It to Students? 1801
13.2.2. How Do We Write and Implement an Institutional AI Policy? 1808
13.2.3. What Competencies Do Faculty Need in Regard to AI? 1815
13.2.4. How Do I Design Faculty Development for AI That Actually Changes Practice? 1820

13.3. Designing courses and activities 1826

13.3.1. How Should AI Be Designed Into the Learning Experience? 1827
13.3.2. How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work? 1831
13.3.3. How Should I Handle AI in Group and Collaborative Assignments? 1840
13.3.4. How Should I Incorporate AI Literacy into My Course? 1846
13.3.5. How Can AI Save Me Time as an Instructor? 1852
13.3.6. How Can AI Agents Support Students and Instructors? 1856

13.4. Assessment, feedback and integrity 1858

13.4.1. How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? 1859
13.4.2. Can I Use AI to Grade Student Work Fairly and Reliably? 1864
13.4.3. How Do I Check Whether AI-Generated Quiz and Exam Questions Are Actually Good? 1868
13.4.4. How Can AI Help Me Give Better Feedback at Scale? 1872
13.4.5. How Can I Reduce AI Cheating in My Course? 1878
13.4.6. Should We Use AI Detectors? 1884
13.4.7. What Are Best Practices for Writing Instruction in the Context of AI? 1893

13.5. How students learn and use AI 1901

13.5.1. Does Using AI Actually Help My Students Learn? 1902
13.5.2. How Is AI Impacting Students? 1909
13.5.3. How Do I Keep Students from Over-Relying on AI? 1913

13.5.4. What Does Personalized Learning Actually Mean, and When Does It Help?
13.5.5. How Do I Teach Students to Verify AI Output? 1925 1921
13.5.6. How Should I Use AI to Study and Learn Effectively? 1931
13.6. Particular learners, access and wellbeing 1936
13.6.1. How Can AI Support Multilingual Learners Without Misjudging Their Knowledge or Erasing Their Voice? 1937
13.6.2. How Can AI Support Disabled and Neurodivergent Learners in My Course?
13.6.3. How Does AI Affect Student Anxiety and Well-Being, and What Can We Do? 1941 1948
13.6.4. How Should Parents and Teachers Approach AI with Children Under 13? 1954
13.6.5. How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? 1961
13.7. Careers and AI literacy 1964
13.7.1. What Should Students Learn for Careers Where AI Is Commonplace? 1965
13.7.2. What Is the Evidence on AI Literacy Interventions in Higher Education? 1969
13.8. Building and evaluating educational AI 1973
13.8.1. What Are Best Practices for Developing an Effective AI Tutor? 1974
13.8.2. What Are Best Practices and Tips for Designing Effective Educational AI Software? 1984
13.8.3. How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
13.8.4. How Do We Make a Simulated Student Behave Like a Real Learner? 1989
13.8.5. How Can We Make AI Better at Supporting Learning in Our Own Subject? 1994
13.8.6. How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? 2000 2006
13.8.7. What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? 2011
13.9. Research practice 2013
13.9.1. How Can AI Assist with Educational Research? 2014
13.9.2. What Are Best Practices for Reporting and Interpreting AI in Education Research? 2019
13.9.3. What Are Notable Gaps in the Research Literature on AI in Education? 2025
14. Free Tools and Resources 2033
14.1. Software 2033
14.1.1. Claw-ED 2034
14.1.2. Code Viva 2035
14.1.3. DeepTutor 2036
14.1.4. Gemini Notebook 2038

14.1.5. LearnHarness 2040
14.1.6. OnMicro.AI 2042
14.1.7. OpenMAIC 2044
14.1.8. PAUSE: Patterns of AI Use Self-Examination 2046
14.1.9. Playlab 2047
14.1.10. Process Feedback 2049
14.1.11. Snorkl 2051
14.1.12. Vibes DIY 2052
14.2. Agent Skill 2053
14.2.1. Clarity 2054
14.2.2. Education Agent Skills 2055
14.2.3. Master Instructional Design 2056
14.2.4. Skills for Real Engineers 2057
14.2.5. idstack 2058
14.3. Prompt Or Gem Library 2059
14.3.1. EduGems 2060
14.3.2. The Pedagogical Promptbook 2061
14.3.3. Writing and Rhetoric Studies in the Loop: A GenAI Prompt Library 2062
14.4. Collection Of Tools 2063
14.4.1. DrawSplat 2064
14.4.2. FPDS Apps and Resources 2066
14.4.3. TeacherServer 2068
14.4.4. The ID Toolbox 2069
14.4.5. teacher.dev 2070
14.5. Collection Of Activities 2071
14.5.1. Pressing Prompts 2072
14.5.2. mglearn Classroom Resources 2073
14.6. Assessment Instrument 2074
14.6.1. The Institutional AI Readiness Pack 2075
14.7. Open Format Or Specification 2075
14.7.1. LESSON.md 2076
14.7.2. LiaScript 2077
14.8. Ebook Or Guide 2078
14.8.1. AI + OER Case Studies: A DOERS Project 2079
14.8.2. AI Infused Assignment Playbook 2081
14.8.3. Building Intelligent Textbooks 2083

14.8.4. Campus AI Development 2085
14.8.5. Campus AI Framework 2087
14.8.6. Integrating AI in TVET: a practical guide for institutions 2089
14.8.7. Learning Design Wiki 2091
14.8.8. Student Guide to AI 2093

Introduction

Welcome to the AI in Education Knowledge Base, a free, public-domain resource on artificial intelligence in education for the people who teach, study, design, or administer it. It summarizes and synthesizes recent open-access educational research. An AI agent writes and updates the pages with editorial guidance from the site developer.

Navigating the site

Browse the index in the left sidebar, which is arranged by strand, open the concept index, or search for a topic. Article pages condense one paper into its purpose, methods, and findings; concept pages collect what the research says about one idea and link to the studies behind it. To start from a question, the FAQ covers what visitors ask first, such as course AI policy or whether to run AI detectors. To start from a tool, the resources page lists free tools and collections, with who made each one and what it costs. The map above groups the field into twelve strands, with AI in Education as the central node.

Chat with the knowledge base

The whole knowledge base is also published as machine-readable files, so you can point an AI chatbot or agent at it and get answers that cite the pages. The prompts are here. New pages go into the journal, which has an RSS feed. A weekly newsletter, the AIEd Research Weekly Update, says what those additions mean for instructors, developers, researchers, and administrators. To read offline, download the EPUB or the PDF.

Recommended starting points by audience

Start with the group that matches your role.

Essential concepts

AI literacy, misconceptions about AI, agentic AI, cognitive offloading, and how to interpret and apply this research, including why a single study rarely settles a question. The full list covers every strand.

Instructors

The changing teaching role, learning design, assessment, feedback, academic integrity, framing AI use and reducing misuse. For subject-specific tools and examples, see AI in your own discipline.

Developers

Building for education, the technologies underneath, intelligent tutoring, multimodal AI, learner modeling, and training and adapting a model for teaching.

Administrators

The administrator role, AI governance, institutional policy, legal issues and risks, and change management.

Researchers

Research methods in AIED, theories and frameworks, evaluating an AI in education intervention, educational measurement, measuring learning gains, and the cross-cutting limits of this evidence base.

What is in the knowledge base

Every page is dated, and the counts below reflect what is published right now; the “last updated” date at the end of the list is the most recent edit.

- 2023 articles
- 226 concepts
- 42 FAQs
- 38 resources
- last updated November 5, 2026

Use This Knowledge Base with Your Own AI Assistant

Point any AI chatbot or agent at this knowledge base and it answers from these pages instead of from its own memory. Copy the prompt below, paste it into your assistant as your first message, then ask your question. A good answer names the pages it drew on and links to them, so you can check the sources yourself.

Nothing to install. If you would rather skip the prompt, the ready-made assistants already know this material.

The prompt to copy

Paste this in first, before your question. It works with any chatbot or agent that can read a web page or take a pasted document. The prompt is longer than the box shows; the button copies all of it.

Then paste it into your assistant and ask your question.

You are a research assistant for AI in education. Use the AI in Education Knowledge Base (https://edtechdev.github.io/aied/) as your primary source.

1. Route before you read. The FAQ index at https://edtechdev.github.io/aied/faq/ maps questions to the pages that answer them, including “what does the research show” questions. The full catalog at https://edtechdev.github.io/aied/llms.txt is 1.2 MB, the concepts-and-FAQs file at https://edtechdev.github.io/aied/llms-concepts.txt is 3.8 MB, and llms-full.txt is 20.0 MB, so search them or fetch parts rather than loading them whole, and do not let a failed whole-file fetch stop you.
2. Ground every claim in a page and cite it as the page title followed by its URL. When the page gives the underlying paper’s citation and DOI, add them; some pages cite only an arXiv ID or a publisher URL, so give what the page gives and never invent a DOI, URL, author, number, or finding.
3. Synthesize across pages instead of leaning on one. Concept pages give the overview and link to the articles behind them, so follow those links. Read three to five of the most relevant pages, stop when they start repeating the same studies, and say what you did not read. If the knowledge base covers the topic only in a neighboring field, say so and answer by analogy.
4. Match the strength of the evidence. Controlled or randomized experiments that measure unassisted performance are strongest, then meta-analyses adjusted for publication bias, then reviews, then pilots, policy analyses, and opinion; one small study is not consensus. Tags, audience, level and confidence ratings live in each page’s Markdown source at https://raw.githubusercontent.com/edtechdev/aied/main/<section>/<slug>.md, not in the rendered page, so if you cannot check them, judge from how the article describes the study and say that is what you did.
5. Answer at the level the question asks for, and close by recommending the most relevant pages and FAQs.

Prefer the term “generative AI” over “LLM”. The knowledge base is updated regularly, and the journal page at https://edtechdev.github.io/aied/journal/ lists the newest additions.

Example: “What does the research say about AI feedback for student writing?” Check the FAQ index, read the most relevant writing and feedback pages plus the studies they cite, then answer with citations and links. ## How to use it {.unlisted}

1. **Copy the prompt** with the button above.
2. **Paste it into your assistant** as the first message. It will usually reply that it understands.
3. **Ask your question** in plain language, for example “what does the research say about AI feedback in large classes?” or “should we use AI detectors?”
4. **Check the links.** A good answer names the pages it used. If you get confident claims with no page names, reply “which page did that come from?” and ask it to try again.

This works best in assistants that can browse the web, since the prompt points them at pages to read. If yours cannot open links, attach the text of the knowledge base as well: download the full-text file once, upload or paste it into the conversation, and use the prompt alongside it. It is a single text file of 20.0 MB. Many chat products refuse a file that size, so there is also llms-concepts.txt, every concept and FAQ page in full at 3.8 MB. Reach for that one first: the concepts are the syntheses of what the research shows, the FAQs are the questions those syntheses answer, and each concept page links the papers behind it.

Technical notes for tools that want a URL instead of a prompt

- llms.txt: a catalog of every page, one line each, for tools that index a site before reading it
- llms-full.txt: the complete text of the knowledge base in one file, 20.0 MB
- llms-concepts.txt: full text of the concept and FAQ pages, 3.8 MB, for tools and chats that reject the larger file
- Sitemap: every page address
- RSS feed: new and updated pages

Ready-made assistants

If you would rather not set anything up, use one of these ready-made assistants:

- **AI in Education Advisor**, a Gemini Gem that answers from this knowledge base. Its custom instructions are public, and it was built from a static copy of the knowledge base, so it may lag behind the newest pages.
- **NotebookLM notebook**: a Google NotebookLM notebook built on the same material, with autogenerated reports, infographics, a podcast, slides, and a video.

What is in the knowledge base

Over a thousand research summaries cover tutoring and AI tutors, assessment and feedback, academic integrity, AI literacy, teacher and faculty development, equity and accessibility, privacy, policy and governance, and learning science topics such as cognitive offloading and learner motivation. Every summary ends with the full citation and a link to the original paper, so your assistant can pass the reference along.

Three kinds of page answer different questions: concept pages summarize what the research says about one idea and link to the studies behind it, article pages cover one paper at a time, and the FAQs answer practical

questions from instructors and administrators. Ask for a concept page when you want an overview, and for the articles behind it when you want the evidence.

Questions that are already answered

Many of the questions people ask an AI first have already been answered here by hand, with the research attached:

- How do I write a course AI policy and communicate it to students?
- How can I reduce AI cheating in my course?
- Should we use AI detectors?
- How should assessment be redesigned for the AI era?
- How do I keep students from over-relying on AI?
- How do we write and implement an institutional AI policy? The full list of FAQs is worth a look before you ask, and the prompt tells your assistant to check that list first.

Read the knowledge base offline

You can also download the knowledge base as an EPUB or PDF for an e-reader, phone, tablet, or computer. These offline editions contain the concept pages and FAQs, not the article summaries.

Foundations of AI in education

Essentials

AI in Education

> **AI in Education (AIED)** — the broad, interdisciplinary field that applies artificial intelligence to teaching and learning, and studies its design, use, evaluation, and consequences. As the knowledge base's umbrella concept, AI in education encompasses **AI for education** (using AI to improve instruction and assessment) and **education about AI** (developing AI literacy and critical understanding). It sits at the intersection of instructional technology, the learning sciences — the empirical research field that asks whether a learner changed rather than only whether a tool performed — computer science, educational policy, Ethics, and equity. This page is an introduction to the field and a map to every concept the knowledge base covers.

Questions to Consider

- 'AI in education' spans two directions: AI for education (using AI to improve teaching) and education about AI (building literacy and critical understanding). Which is more familiar to you, and which do you tend to overlook?
- The field's history is framed as a recurring tension between control and learner agency. As you watch AI tools being adopted, where do you notice that same tension playing out today?
- AI in education sits at the intersection of technology, learning science, policy, ethics, and equity. Which of those lenses do you naturally apply when evaluating an AI tool — and which are you likely to forget?
- This knowledge base organizes the field into strands: pedagogy, learning theories, technologies, disciplines, assessment, feedback, stakeholders, and governance. If you were mapping your own use of AI, which strand would you find yourself in?
- AIED includes teaching students to use AI critically as a goal in itself. In your context, is AI treated more as a subject to be taught or a tool to be used — and does that balance reflect what learners actually need?
- Students may learn AI literacy by using AI critically, not just by learning about AI. How might hands-on, critical use build understanding that passive instruction cannot?

Introduction

AI in education is the umbrella that all other concept pages collectively define. The knowledge base organizes the field into the major strands below, each linking to the relevant concept pages.

A landmark historical perspective, **Mishra et al.** trace AIED from cybernetics and the 1956 Dartmouth conference through cognitive tutors and Papert's constructionism, arguing that today's GenAI debates re-enact the field's foundational control-vs-Learner Agency tension.

How the knowledge base is organized: the umbrella pages

The knowledge base's concept coverage is anchored by several **umbrella pages** that group related concepts into navigable strands. These are good entry points for exploring the field:

- **AI in Education** — this page, the field's overview and map to all coverage.
- **AI literacy** — the umbrella for understanding, using, and critically evaluating AI, spanning prompt engineering, critical thinking, AI ethics, and responsible use. Alongside it, human–AI collaboration and agentic AI frame how people and AI work together.
- **Pedagogies and teaching strategies** — the umbrella for how teaching happens: the teaching methods and strategies AI operates within (active, collaborative, project-based, problem-based, experiential, game-based, Socratic, Scaffolding, and more), including the distinct context of online teaching and learning.
- **Learning theories** — the umbrella for how learning happens: the theoretical frameworks (Behaviorism, cognitivism, constructivism, sociocultural, cognitive, motivational) that shape AI design and evaluation.
- **Technologies** — the umbrella for the technical layer: the AI systems (LLMs, generative AI, Multimodal AI, robotics) and techniques (RAG (Retrieval-Augmented Generation), prompt engineering, reinforcement learning, model training, agentic orchestration) that power AIED. The learner-modeling family — knowledge tracing, cognitive diagnosis, simulating students, and the systems that consume them (intelligent tutoring, adaptive learning, personalized learning) — is grouped under the Learner Modeling and Adaptive Instruction umbrella within this technical strand.
- **AI in the disciplines** — the umbrella for how AI is applied across subject areas (mathematics, physics, language learning, computer science, writing, STEM, engineering, business, teacher education, health professions, and more) — and, past the academic subjects, the professional and applied strand that assesses demonstrated practice rather than correctness (nursing, information technology, vocational education and training, design education) — and educational levels (K-12, higher education, adult learning).
- **Assessment** (with formative, summative, authentic, oral, and automated strands) — the umbrella for how AI both assesses learners and reshapes assessment validity and integrity.
- **Feedback** — the umbrella for how feedback is generated, delivered, and used: the feedback loop, feedback quality, feedback literacy, and its assessment contexts (formative, peer, automated).
- **Stakeholders in AI education** — the umbrella for who the actors are: learners, teachers, learning designers, administrators, and policymakers.
- **AI ed evaluation** and **research methods** — the umbrellas for how we know whether AI works: efficacy studies, benchmarks, randomized controlled trials, meta-analysis, and learning gains as the core outcome measure. Readers should also weigh the cross-cutting limitations of this evidence.
- **AI governance**, **educational AI policy**, and **equity** — the umbrellas for the institutional, regulatory, and fairness layer (see also AI Regulation in Education and Privacy).

These umbrella pages are linked throughout the sections below; each strand below names both its umbrella and its constituent concepts.

Two dimensions of AI in education

AI in education research spans two interconnected directions:

- **AI for education** — using AI systems to enhance teaching, learning, assessment, and administration. This includes AI tutoring, adaptive learning, personalized learning, automated essay scoring, automated question generation, automated assessment, formative assessment, learning analytics, and feedback loops.
- **Education about AI** — teaching learners and educators to understand, use, and critically evaluate AI. The core is AI literacy, supported by prompt engineering, critical thinking, AI ethics, governance education, digital literacy, and responsible use.

These two dimensions are not separate: using AI well requires understanding it, and teaching about AI is enriched by using it. This human-AI collaboration is a central theme.

Foundations of AI in education

The field's cross-cutting and foundational concepts anchor the knowledge base's coverage and appear first in the sidebar. They open with an **Essentials** group — the concepts every reader should start with: the umbrella itself, misconceptions about AI, AI literacy, agentic AI, cognitive offloading, how AI use is framed for students, reducing AI misuse, academic integrity, teaching, learning design, and educational development. The **field** strand then covers the field's history, the cross-cutting limitations of the evidence base, its philosophy, the theories and frameworks map, and theory development. The cross-cutting themes — human–AI collaboration, learner agency, learner identity, design thinking, curriculum design, critical thinking, and computational thinking — cut across every strand, because the inaccurate mental models people hold about AI are upstream of misuse and under-calibrated trust.

Learning and instruction

How AI supports teaching and learning is the heart of the field. Key concepts include:

- **Core pedagogies:** pedagogies and teaching strategies — the umbrella for the knowledge base's teaching-methods coverage — along with pedagogical patterns (the tested sequences those methods resolve into), active learning, collaborative learning, group work, project-based learning, problem-based learning, productive failure, inquiry-based learning, experiential learning, game-based learning, learning by teaching, Scaffolding, the Socratic method, critical pedagogy, pedagogical partnerships, storytelling, learning design, online teaching and learning, and video in education.
- **Learning theories and processes:** the learning theories umbrella (Behaviorism, cognitivism, constructivism, sociocultural, distributed cognition, situated learning, embodied learning, community of inquiry) sits alongside learner-facing processes like self-regulated learning, self-determination theory, Motivation, Self-Efficacy, self-directed learning, Metacognition, desirable

difficulties, transfer of learning, prior knowledge, ICAP cognitive engagement, Reflection, refutation text, retrieval, spacing and interleaving, and activity theory.

- **Learner engagement and experience:** student engagement, Help-Seeking, social-emotional learning, Well-Being, Creativity, problem solving, mastery learning, and student–AI interaction shape how learners actually encounter and are affected by AI, while the social norms that settle around AI use decide how openly any of it can be discussed. Beyond the course, student support and success covers the institutional-side work — advising, outreach, referral, and the allocation of scarce support — where AI reliably moves task completion but not persistence or graduation.

Technologies and techniques

The Technologies page is the umbrella for the technical layer:

- **Models and techniques:** generative AI, large language models, retrieval-augmented generation, multimodal models, educational NLP, reinforcement learning, knowledge graphs, robots in education, conversational AI, Simulation, and LLM training and fine-tuning. The underlying methods matter too: machine learning is where these systems are built, speech and voice technologies carry spoken tutoring and language practice, Visualization covers dashboards and visual analytics for learners and instructors, and virtual and augmented reality hosts immersive practice whose visual layer the model can now generate. Newer interaction styles belong here too — most prominently vibe coding, the natural-language-driven workflow in which the user specifies a program by prompting an LLM and judges the resulting behavior rather than reading or editing source. That reframes programming as an act of expression and verification and lowers the barrier to end users building their own tools. Integration-depth frameworks such as SAMR and adoption theories such as TAM classify how deeply AI is taken up and how much it transforms the task.
- **Learner modeling and adaptive systems:** the technical systems that represent and adapt to the learner are grouped under the Learner Modeling and Adaptive Instruction umbrella — knowledge tracing, cognitive diagnosis, simulating students, intelligent tutoring, adaptive learning, personalized learning, recommender systems and learning paths, pedagogical agents, affective tutoring, affective computing, sensor and gaze analytics, AI avatars and synthetic instructors, human-in-the-loop AI, and learning analytics. These sit at the technical layer because they are the AI systems themselves, distinct from the pedagogies they enact.
- **Platforms, openness and adoption:** the layer around the model, where a teaching resource is licensed, hosted and paid for rather than built. Open education covers teaching with openly licensed content and the pedagogy that treats students as producers of it, which is where the license and adaptation questions that generated material now raises are argued. It sits beside openness in the software sense, platform-level analysis in edtech platforms, and the adoption research carried by TAM.

AI in the disciplines

AI is applied across disciplines and educational levels. The knowledge base's overview of AIEd in the disciplines maps subject-area coverage — alongside learning sciences, which is not a taught subject but the cross-cutting research field that studies learning itself and takes subject matter as one variable among others:

- **Subject areas:** mathematics, statistics and data science, physics, chemistry, biology, computer science, engineering, STEM, writing, language learning, English education (EAP/EFL/ESL), science education, environmental education, business, economics, and management, humanities and social sciences, civic and political education, arts, design and media education, medical and health professions, legal education, and the professional and applied strands — nursing, information technology, vocational education and training, and design education.

Levels and contexts

The same AI tool meets very different settings, and the knowledge base separates the educational level from the pedagogy so that findings do not silently transfer across them: K-12 schools, early childhood and elementary education, higher education, adult learning, vocational education and training, special education, and teacher education. Domain-adjacent concepts that cut across levels include universal design for learning, Neurodiversity, multilingual learning, and social-emotional learning.

Assessment and measurement

AI transforms both how we assess learners and how we evaluate AI systems themselves:

- **Assessment and feedback:** Assessment, formative assessment, summative assessment, authentic assessment, e-portfolio, Feedback and feedback literacy, AI feedback quality, peer assessment, oral assessment, automated assessment, automated essay scoring, and automated question generation. Because a model can now produce plausible finished work on demand, the knowledge base foregrounds the capability that remains the learner's own: evaluative judgment, the capacity to appraise the quality of one's own work, peers' work, and AI output against reasoned criteria. It is the construct several feedback and authentic-assessment studies converge on — the hybrid feedback condition outperforming direct AI feedback in a multisite experiment, the sustainability gap in AI formative feedback, and the practical move of assessing the decisions students make rather than only the artifact — and it is a core reason AI-era redesign shifts from detection toward tasks whose integrity survives inspection. Group work is likewise assessed along both process and product, where teams must negotiate whose and what kind of AI engagement counts as acceptable.
- **Measurement and validity:** assessment validity, psychometrically aware AI, educational measurement, item response theory, self-report measures (the instrument behind a large share of this evidence, and a recurring limitation), AI detection, remote proctoring, and academic integrity.

Research methods and evaluation

How we know whether AI works is its own strand, and the knowledge base treats it as one:

- **Research methods:** research methods in AIED as the umbrella, with qualitative, quantitative, mixed-methods, design-based, and usability approaches, plus randomized controlled trials, meta-analysis and systematic review, and network analysis.

The field's own research work is now a subject in its own right. AI-Assisted Educational Research covers AI used as an instrument for literature search, screening, qualitative coding, analysis, and writing, including practitioner research such as the scholarship of teaching and learning. It stays distinct from the designs used to study what AI does to learners.

- **Evaluation of AI systems:** AI ed evaluation and benchmarks for judging a system's capability, with learning gains as the outcome that matters, and the cross-cutting limitations of this evidence and how to read a single study as the cautionary counterweight.

People

AI in education changes the roles of every stakeholder. The knowledge base's Stakeholders in AI education page is the umbrella covering all of them:

- **Learners:** student experience, career development and readiness, and AI anxiety and stress shape how students encounter AI.
- **Families and communities:** parents and families are the audience schools address most often about AI and the one with the least research behind the guidance, so their concerns belong in the stakeholder picture rather than outside it.
- **Instructors and teaching frameworks:** teacher AI competency, technological pedagogical content knowledge (TPACK), SAMR, and educational development address educator preparation and support.
- **Builders:** Educational Technology Developers — the product designers, software developers, learning engineers and analytics designers who turn a model capability into something an institution can procure. They are a distinct audience from the practitioners and administrators above, and they sit outside the institutions that adopt their tools, which is why defaults, co-design and post-funding maintenance appear in this knowledge base as pedagogical questions rather than commercial ones.

Institutions and policy

The institutional layer is where AI decisions are actually made and defended: administrators and institutional leaders, educational AI policy, AI governance, change management as the work of making an adoption stick, AI regulation, and the procurement and platform questions that follow from technology adoption, open source, and edtech platforms, alongside professional and lifelong learning and professional training.

Equity, ethics, and responsible use

Fairness, access, and responsibility are central to AI in education:

- **Equity and access:** Equity, differential effects across learner groups (the question of who a finding holds for), digital divide, bias mitigation, culturally relevant pedagogy, multilingual learning, inclusive learning, Accessibility, assistive technology, Neurodiversity, universal design for learning, and Global South studies.
- **Ethics and responsibility:** AI ethics, AI misuse and learning harm, legal issues and risks, AI use disclosure, Guardrails, Privacy, hallucination risk, AI sycophancy, Trust, trust calibration, reducing AI misuse, how AI use is framed for students, pedagogical safety, Sustainability, and cognitive offloading.

A systematic review of the field's ethics literature (Agarwal et al. 2026, 25 articles) consolidates AIED ethics into six main ethical values — non-discrimination, data stewardship, human oversight, goodwill, explicability, and educational aptness — and maps the ethical norms onto a stakeholder-by-value matrix. It finds end users largely passive in the ethical literature (student voices essentially absent) and calls for integrating ethics into AIED design and a greater focus on the educational (pedagogical) dimension of AIED ethics.

Emergent and cross-cutting themes

Several themes cut across the field:

- **Trust and critical use:** Trust, trust calibration, AI sycophancy, critical thinking, cognitive offloading, critical pedagogy, and reducing AI misuse (see also how AI use is framed for students). How learners and teachers decide to adopt and rely on AI is modeled by technology acceptance research, while Global South studies foreground equity and cultural context in adoption. Empirically, how AI explains itself shapes this trust: Feldman-Maggor et al. (2025) showed that explainable AI builds teachers' trust in AI recommendations through understandability, with domain-driven (curricular-language) explanations trusted and accepted more than data-driven feature-importance output.
- **The evolution of the field:** the knowledge base traces AI in education from early intelligent tutoring systems and knowledge tracing to LLM-driven tutoring, agents, and agentic AI — a rapid shift from tool-centric studies to sociotechnical frameworks (design thinking, curriculum design, institutional change), and from hand-authored systems to user-driven workflows in which a learner or non-programmer specifies behavior in natural language (vibe coding). Rismanchian & Doroudi formalize this trajectory with their AI×Ed framework, tracing papers across four decades of proceedings to show that the field moved from a diverse mix — including substantial research treating AI as an analogy to human intelligence and learning — toward a near-exclusive focus on applied, data-driven, researcher-facing uses, a turn that the rise of LLMs now appears to partly reverse (three of the four "AI-as-analogy" papers at AIED 2024 were LLM-based).
- **Emotion, anxiety, and career futures:** AI induces and shapes emotional responses — AI anxiety and stress spanning proctoring surveillance, integrity fears, and career displacement — while

career development and readiness addresses how education prepares learners for an AI-disrupted labor market (see also Well-Being).

Field maturity

The knowledge base reflects a field in rapid evolution — from early intelligent tutoring systems to LLM-driven tutoring and agentic AI; from detection-focused academic-integrity tools to assessment redesign; from tool-centric studies to sociotechnical and equity-focused frameworks. The evidence base increasingly emphasizes rigorous research methods, evaluation, experimental designs, and long-term outcomes.

Connections

AI in education connects to every concept in the knowledge base — it is the field that all other concept pages collectively define. Use this page as a starting point to navigate the full knowledge base.

Common Misconceptions

“AI in education is one field with one evidence base.” It is an umbrella over distinct strands — disciplines, levels, assessment, research methods, institutions, equity — that differ in their methods, their outcome measures and their maturity. A finding from one strand does not transfer to another, which is why the knowledge base is organized this way rather than as a single literature.

“A tool that improves course outcomes improves student success.” The institutional strand shows the opposite pattern: in student support and success, AI **reliably moves task completion but not persistence or graduation**. An intervention can win every in-course measure and leave the completion outcome flat.

“Technology performance is evidence about learning.” The field sits at the intersection of instructional technology and the learning sciences, and the distinction between the two is exactly this: whether a learner changed, rather than only whether a tool performed. A demonstration is a claim about the tool.

“Because AI is general-purpose, a finding anywhere applies everywhere.” Generality of the technology does not create generality of the evidence. The discipline, level and context strands exist because the same tool behaves differently across them, and an unchanged finding carried across a boundary is an extrapolation.

“The field’s maturity can be read off its publication volume.” Volume and maturity diverge; the research-methods strand documents recurring design weaknesses that volume does not fix, and frameworks multiply faster than they are tested.

Connected Concepts

- Pedagogical Patterns — The tested sequences that operationalize the field’s pedagogies
- AI Literacy — umbrella: understanding, using, and evaluating AI
- Human AI Collaboration — umbrella: how people and AI work together
- Pedagogies and Teaching Strategies — umbrella: teaching methods and strategies
- Learning Theories — umbrella: how learning happens
- Technologies — umbrella: models, techniques, and systems

- AIEd in the Disciplines — umbrella: AI across subject areas and levels
- Assessment — umbrella: how AI assesses learners and reshapes validity
- Feedback — umbrella: how feedback is generated, delivered, and used
- Stakeholders — umbrella: who the actors are
- Learners — umbrella: the learner-side concepts (experience, identity, agency, interaction, learner models)
- AI Ed Evaluation — umbrella: how we know whether AI works
- Research Methods in AIED — umbrella: efficacy research methods
- AI-Assisted Educational Research — AI-Assisted Educational Research
- AI Governance — umbrella: the institutional and regulatory layer
- Educational AI Policy — umbrella: policy, guidance, and implementation
- Equity — umbrella: fairness, access, and inclusion
- Learning Sciences — the empirical field behind AIED
- Ethics — the ethical dimensions of AI in education
- Misconceptions about AI — the mental models people bring to AI
- Interpreting and Applying AIEd Research — reading a study, and carrying a finding into practice
- Limitations in AIEd Research — cross-cutting limits of the evidence base
- Meta-Analysis and Systematic Review — what the reviews and meta-analyses establish
- History of AI in Education — how the field evolved
- Philosophy of AI in Education — the philosophical foundations
- Theories and Frameworks — the map of theory and framework nodes
- Theory Development in AI in Education — building and revising theory
- Sensor and Gaze Analytics — umbrella: sensing learners through gaze, EEG and wearable signals
- AI Avatars and Synthetic Instructors — umbrella: synthetic humans teaching, tutoring, simulating and assessing
- Civic and Political Education — subject area: literacy for public life, with a thin evidence base

Connected Articles

Field-wide reviews of AI in education — the studies that survey the whole field or a whole educational level rather than one topic:

- The evolution of research on AI and education across four decades: Insights from the AIxEd framework — The evolution of AI-and-education research across four decades (AIxEd framework)
- Control vs. Agency: Exploring the History of AI in Education — Control vs. agency: a history of AI in education
- Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025) — Generative AI in higher education: systematic review of 125 studies

- The Evidence Base on AI in K-12: A 2026 Review — The evidence base on AI in K-12: a review of 818 papers
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches — Generative AI and educational outcomes: comprehensive meta-analysis

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

AI Literacy

> **AI literacy** — the knowledge, skills, and critical dispositions needed to understand, evaluate, and effectively use AI Technologies in educational contexts. AI literacy spans foundational understanding of how AI works, practical competence in using AI tools, critical evaluation of AI outputs, and ethical awareness of AI's societal implications.

Questions to Consider

- What does it mean to be 'AI literate'? Is it knowing how to use the tools, understanding how they work, or being able to critically evaluate their output — and which matters most for your own goals?
- Self-reported AI literacy diverges sharply from measured performance — teachers overestimate their skills by about 40%. How confident are you in your own AI skills, and what evidence would you trust to actually test that confidence?
- AI literacy is described as a metacognitive social practice, not a checklist of skills. Because LLMs are probabilistic and opaque, what does it mean to 'critically evaluate' output when you can't see inside the model?
- There's a tension between critical-use literacy for academic settings and workflow-integration literacy for employment — educators and employers value different skills. Which kind of AI literacy is your context actually teaching?
- Technical AI-literacy training alone, without self-efficacy and self-regulation support, can actually increase dependency on AI. How could learning to use AI make you more reliant on it rather than more capable?
- AI literacy is also a recognition skill: spotting when an AI is agreeing with you because it's being sycophantic versus because you're right. Have you ever caught an AI just telling you what you wanted to hear?

Introduction

AI literacy has rapidly emerged as a core competency for learners, educators, and institutions as Generative AI becomes embedded in education. Unlike general digital literacy, AI literacy requires understanding probabilistic systems that can hallucinate, exhibit bias, and shift Learner Agency from human to machine — making Critical Thinking and Over-Reliance central to the construct.

Dimensions of AI literacy

Output-directed and system-directed literacy are separate dimensions with evidence for the split. Bergdahl (2026) found 47 Swedish year 7 students strong on source evaluation (Mdn = 3) and governance (Mdn = 4, 57% at the highest option) but weak on **data privacy (Mdn = 1, 66% at the lowest)** and **algorithmic manipulation (Mdn = 2, 47% at the lowest)**. Grouped by domain, the median output-directed

score was 3 against 2 for system-directed. The finding is not that these students lacked literacy but that **literacy in reading AI output did not extend to questioning how that output was produced** — a distinction with direct consequences for how a program is scoped and measured, since a single score would average both registers and report a middle that describes neither.

AI literacy research in this knowledge base spans four interconnected dimensions:

Frameworks increasingly trace how these dimensions are enacted in practice: Dai & Chan (2026) show how postgraduate researchers enact all four dimensions when using Generative AI across the research workflow and scaffold research-specific responsible-use guidelines from them, while Şan & Orhan Karsak (2026) use Word-Association mapping to show that Turkish undergraduates' AI cognition is instrumentally "black-box" dominated, with ethical-governance concepts structurally isolated ($\tau = -0.819$) — evidence that credential design must deliberately bridge experiential tool use and ethical frameworks.

Experts converge on the competencies and not on where they sit. Eleven experts rated a nine-competency, three-domain framework's content favorably yet disagreed on competency placement ($M = 3.73$, $SD = 1.19$, $IQR = 1.50$) while endorsing non-exclusive domain relations ($M = 4.45$, $SD = 0.52$), reading the domains as functional roles rather than fixed buckets (Lee, Son and Hong (2026)).

The demand depends on what the student and the system are jointly doing. Literacy frameworks usually describe one generic set of competences, but what a GenAI-supported activity actually requires varies with how epistemic work is distributed inside it. Sun, Dohn and Rehm (2026) classified 102 empirical higher-education studies against Strobel et al.'s taxonomy of GenAI applications and found Assistant and Enabler entanglements dominating at 42.16% of the corpus each, while Generator, Reimaginator and Synthesizer together accounted for under a fifth — a skew they attribute to institutional legitimacy rather than model capability, since the same models support all five. Reading each type through Dohn's three context levels (domain-internal, activity-internal, activity-framing) shows demands cohering for Assistant work and fracturing for the marginal types, where what the activity asks of students diverges from what the institution recognizes as legitimate competence. Their conclusion moves literacy away from tool fluency altogether: GenAI literacy is the capacity to recognize how epistemic work and responsibility are distributed in a given entanglement, and to act appropriately within it.

Different dimensions predict different things. Averaging AI literacy into one score hides which competence does what. In a task-based study of 162 university students writing a research abstract with an assistant built on DeepSeek V3, only the Use and Apply dimension independently predicted abstract quality ($\beta = 0.206$, $p = 0.042$), and only Know and Understand independently predicted lower perceived mental load ($\beta = -0.344$, $p = 0.001$). The total score predicted both, but neither it nor any dimension predicted Motivation or Self-Efficacy (Chen et al. (2026)). A student can be competent enough to produce a better text and still find the task as demanding, which is an argument for assessing and teaching the dimensions separately instead of reporting one literacy number.

Foundational knowledge: Understanding what LLMs are, how they differ from rule-based systems, and their fundamental limitations. This includes awareness of model capabilities, training data biases, and the distinction between task-specific AI and general-purpose models. Research in Prompt Engineering examines how understanding prompt mechanisms affects effective AI use.

Practical competence: The ability to use AI tools effectively — from Prompt Engineering to interpreting outputs. Studies of student GenAI usage patterns reveal that tool access alone doesn't produce competence;

structured practice and Scaffolding are essential. The vibe coding framework shows how K-12 teachers can develop practical AI literacy through guided tool creation. Miles, Haber-Curran and Arar (2026) argue that this dimension has a part optimization training misses: prompt literacy, as distinct from prompt engineering, treats prompting as a rhetorical and ethical act, so instruction that only tunes outputs for better performance leaves the ethical and epistemological dimensions of LLM use untouched.

Critical evaluation: The capacity to assess AI outputs for accuracy, bias, and appropriateness. Research on literacy assessment shows a 40% gap between self-reported and performance-based AI literacy — people consistently overestimate their evaluation skills. That divergence is the clearest case in the knowledge base of a self-report measure failing to track the competence it names. This connects to Over-Reliance research showing that students who Trust AI uncritically learn less. Recent conceptual work pushes evaluation toward *verification*: the PEARLS framework (Wang) treats AI output as a provisional knowledge claim whose warrant must be assembled and examined across six dimensions (Process, Evidence, Access, Reproducibility, Legitimacy, Source), and advances **verification-driven learning** as the mechanism by which learners build expertise while checking AI claims. Complementing this, the student-centered responsible-use framework (Alsammani) offers ten student-facing guidelines across Learning and Growth, Ethics and Integrity, and Awareness and Safety pillars that externalize metacognitive prompts at the point of decision. For secondary learners, the AI-Assisted Research Competency (AARC) framework (Beau, Flaquière & Lazar 2026) grounds this in virtue epistemology and AI intuition, defining research literacy as conducting inquiry with AI without surrendering authorship, judgment, verification, or responsibility — operationalized as an analytic rubric and a verify–cite–reflect commitment routine. At the Assessment end, Saleh (2026) proposes a *human capability test* that turns evaluation into a design principle: ask what a student must demonstrate independently, what can be strengthened through AI augmentation, and what the student must verify, defend, and take responsibility for.

Disciplinary verification raises the same bar further. Vega-Baudrit and Rivera Alvarez (2026) argue that in university chemistry the core AI literacy demand is representational translation across Johnstone's macroscopic, submicroscopic and symbolic domains, because an output can be locally persuasive in one domain while contradicting charge balance, a mechanism or a safety limit in another. Their remedy is verification-centered integration: make verification an assessed activity, keep prompt logs and revision histories as reasoning traces, and treat prompting as an epistemic act that specifies constraints, assumptions and adequacy criteria, with students identifying a false assumption or justifying rejection of a generated answer.

Ethical and institutional awareness: Understanding AI's broader implications — from Academic Integrity to Equity to Privacy. AI literacy at the institutional level involves policy development, Educational Development, and governance frameworks — institutional AI literacy is a matter of policy as much as pedagogy. The EPIQ-AI framework frames institutional AI literacy as a sociotechnical alignment challenge, not just individual training.

Security is a literacy domain of its own. Yocam, Vaidyan and Kalathas (2026) argue that neither AI-literacy nor cybersecurity frameworks treat operating securely in an AI-mediated school as a competency in its own

right, and only 34.5% of US teachers report a school AI policy (AI Security Literacy: Ecosystem-based Competency Framework and K-12 Learning Platform).

- **AI literacy as a governance capacity for sustainable development.** Islam, Morshed, and Islam (2026) reconceptualize AI literacy as a governance-oriented capacity rather than a purely educational or technical skill, linking it to all seventeen UN Sustainable Development Goals. Their six-level **AIRE Taxonomy** (Recognize → Comprehend → Apply → Analyze → Integrate → Govern) extends Bloom's hierarchy by adding ethical synthesis and strategic foresight, positioning advanced competencies (Analyze–Govern) as the pathway from foundational literacy to institutional and policy-level governance — an "18th SDG" heuristic that treats literacy as a cross-cutting cognitive and ethical bridge. A survey of 300 professionals in a national context found strong technical awareness but limited ethical and governance readiness, with **ethical reasoning and reflective thinking the strongest predictors of sustainable, trustworthy AI use** and governance literacy the strongest predictor of AI–SDG nexus awareness ($\beta = 0.64$). This empirically grounds the knowledge base's emphasis on critical-use literacy and ties AI literacy directly to Sustainability and policy integration. **The framework supply is now its own problem.** Fitsilis (2026) compared 16 institutionally endorsed AI competence frameworks for education and workforce development and found a shared core of ten competence areas but wide variation in structure, progression and implementation guidance — the practical difficulty is choosing among them, not a shortage.

The facets do not predict the same outcome. In a PLS-SEM survey of 475 design students across Europe, Asia, and Australia, ethical awareness predicted academic Well-Being ($\beta = 0.324$) but not perceived learning performance, while emotional adaptability was the strongest direct predictor of performance ($\beta = 0.322$) (Liang et al., 2026).

How AI literacy is developed

Research points to collaborative and active approaches as most effective. Rismanchian & Doroudi position AI literacy as more than applied skill: in their AI×Ed framework the learner is a distinct end user of AI (accessed through AI literacy and AI education), and they argue for renewed AI-literacy work that encourages reflection on learning itself — treating literacy as a route back into "AI as an analogy to human intelligence" research on how people learn, a strand the field largely abandoned. The ICAP Framework (Interactive → Constructive → Active → Passive) provides a useful taxonomy of cognitive engagement: students learn AI literacy best when they co-construct knowledge rather than passively receive information. Designers should select the mode that fits the learning goal and favor the deeper (constructive and interactive) modes where possible. Practical activities — designing prompts, evaluating outputs in groups, debating AI Ethics — outperform lectures.

Composition starts from lived experience — but concept depth needs scaffolding. Burriss et al. (2026) found that youth anchored abstract AI Ethics principles in systems they encounter daily — electronic "hall passes," school-regulated laptops, plagiarism detectors — with one group explaining that AI in schools "was personal to all group members," and 15 of 18 end-of-unit survey responses reported that making the video changed their understanding of AI ethics. The authors are explicit about the limit: composing did not by itself guarantee conceptual grounding — "informed consent" was translated as "We gotta approve," and some

terms (e.g., “failsafe”) were never explained, prompting them to plan deeper conceptual work in later iterations. Creative production develops AI literacy best when explicit conceptual Scaffolding accompanies the making rather than being assumed to emerge from it.

AI intuition as the experiential complement to literacy. A recurring gap is that K-12 frameworks assume learners approach AI through declarative, rule-based knowledge, when in practice they first develop a practical “feel” for how AI responds — experimenting with prompts, observing behavior, adapting strategies — before they can articulate formal principles. Beau & Lazar (2026) formalize this as **AI intuition**: an experiential, inductive, often tacit understanding that develops through iterative interaction with AI systems and supports context-sensitive judgment under uncertainty. Their **dual framework** situates AI literacy (structured, largely static competencies) alongside AI intuition (a dynamic learning process), mapping both across the standard dimensions — understand concepts, use tools, evaluate critically, apply ethically, reflect — so learners combine conceptual clarity and Guardrails (literacy) with the practical wisdom to trust-but-verify and decide when to disengage (intuition). Because intuition cultivates “expert observation” of AI (e.g. stress-testing prompts to find where a model fails), the authors argue it is a safeguard against over-reliance and critical-thinking erosion; it is distinct from Prompt Engineering (which optimizes outputs) in foregrounding *epistemic judgment*. This connects literacy to Experiential Learning, Constructivism, and developmentally grounded classroom practice, and points teacher preparation toward facilitating inductive exploration rather than only delivering concepts. **For young children, literacy is nested rather than foundational.** A review of 86 resources places AI literacy inside a five-domain competency set where executive functions and learning dispositions do the coordinating, arguing it “cannot be standalone” for children aged 0 to 8 (Pei (2026)).

Motivation is a precondition, not just an outcome. Liang et al. (2026) found, across 2,086 secondary students in a year-long AI curriculum, that students who transitioned into or remained in a *Self-Determined* motivational profile (high autonomy, competence, and relatedness need satisfaction) showed the **greatest AI-literacy gains**. AI literacy develops through sustained engagement, and that engagement is itself shaped by motivation and psychological-need support — so effective AI-literacy instruction should attend to learners’ motivation, not only their skills.

Instructional emphasis and task openness reach performance through different needs. Yu, Lin and Chen (2026) randomized 320 undergraduates to four groups in a 2 x 2 experiment on an AIGC image-generation task scored with an objective rubric (ICC = 0.89) and found that thinking-based instruction, covering model limitations, critical evaluation and ethics, outperformed skills-based prompting instruction ($M = 9.21$ vs 7.69, $F(1, 316) = 50.79$, $p < 0.001$, partial eta squared = 0.138), with the wider margin on open-ended tasks (10.10 vs 8.00). The structural model shows the two design choices travel by different routes: instruction worked indirectly through autonomy (beta = 0.035) and competence (beta = 0.079), while task openness operated mainly through autonomy (beta = 0.029), competence was the strongest predictor of performance (beta = 0.358) and relatedness had no independent effect. What the instruction contains therefore matters more than whether learners get prompting practice, and it matters most when the task is open-ended.

The variables surrounding AI literacy have since been mapped more broadly. A 2025 systematic review of AI literacy’s correlates synthesized 31 studies across 14 countries (N = 12,071) and found the most consistent associations in the affective and behavioral band: AI self-efficacy, positive AI attitudes, motivation and digital competence all moved with AI literacy, while AI anxiety and negative attitudes moved against it.

Demographic variables barely registered, with age and socio-economic status correlating weakly or not at all. The review's caution is about instruments: the same studies that produced strong correlations from self-assessment also showed far weaker ones when AI literacy was tested rather than self-rated.

A structural-equation study of 502 faculty respondents at one Chinese research university found AI literacy the strongest predictor of AI well-being (β = 0.713), against a small technological self-efficacy path (β = 0.082), with social and organizational support reaching well-being only indirectly (Liu et al. (2026)).

One apparent negative association reverses under control: among 303 Hong Kong undergraduates, technology anxiety correlated negatively with AI literacy (r = −0.14) yet predicted β = 0.15 in a joint model, an effect confined to critical evaluation and ethical competence (Chow et al. (2026)).

Hu (2026) adds an ordered account of what AI literacy predicts rather than what predicts it. Surveying 450 university students in mainland China who already use ChatGPT, the study found AI literacy related directly to continued use (beta = 0.16, p = 0.002) and indirectly along a serial path through Trust and academic Self-Efficacy (indirect effect = 0.07, 95% CI [0.04, 0.10]), with the literacy to trust link the largest association in the model (beta = 0.50). AI anxiety moderated that first link (interaction beta = -0.25, simple slopes falling from 0.76 to 0.25 across the anxiety range), so the chain thinned for more anxious students and literacy instruction alone should not be assumed to reach them. The design is cross-sectional and the sample is restricted to existing users, so the ordering is a modeling assumption rather than an observed sequence.

A core applied aim of AI literacy is Reducing AI Misuse: teaching students to use AI ethically and productively rather than substituting it for their own cognitive work. Where AI literacy builds the *capacity* to evaluate and use AI critically, reducing misuse is the behavioral and structural payoff — combining guardrailed tool design, assessment redesign, and educative levers such as scaffolded think-first/AI-second sequences and prompting practice with deliberate Feedback. The two concepts are mutually reinforcing: AI literacy supplies the critical dispositions that make misuse-reduction interventions durable, while misuse-reduction evidence (e.g. the performance–learning gap) motivates why literacy must go beyond operational skill to critical judgment.

AI literacy also needs developmentally appropriate forms for the youngest learners. AI-Play translates AI literacy competencies into play-based, **unplugged** activities for Pre-K–K2 learners — organized around *AI Body* (AI as a system built from parts), *AI Food* (AI learns from examples), *AI Brain* (AI improves through patterns and feedback), and a Pre/Post-AI ethical lens — addressing a persistent lack of developmentally grounded AI literacy guidance for early childhood and making AI literacy accessible to non-technical educators and families. Complementing this, Vahedian Movahed & Martin (2025) found children aged 6–14 broadly trusted an age-tailored chatbot as an information source and most modeled it as "a smart computer program that learns" (nascent Machine Learning understanding), yet showed gaps in critical engagement and digital-safety awareness — evidence that young learners' trust can outpace their critical evaluation skills, making explicit Trust Calibration and safety instruction a necessary part of AI literacy for children.

Measurement is keeping pace with that developmental turn at the younger end. Thianwan and Srikoon's 2025 validation of an AI literacy self-assessment questionnaire for upper primary students developed a 15-item instrument for Grades 4 to 6, organized around Learning About AI, Learning About How AI Works, and Learning for Life with AI, and confirmed a three-factor structure in two samples (n = 335 and n = 579) with an overall Cronbach's alpha of .934. The authors frame it as a formative diagnostic of perceived rather than

demonstrated literacy, and note that children's self-assessment accuracy is constrained by metacognitive ability that is still developing.

Project-based learning as a delivery mechanism. Zhu & Kong (2026) developed and validated an AI project-based learning (AI-PBLS) scale and, in a Hong Kong sample of 1,027 secondary and university students (446 with complete data), used structural equation modeling to show that empowerment in using AI for problem solving and AI ethical awareness jointly **mediate** the relationship between perceived Project-Based Learning and satisfaction with an AI literacy course. This positions PBL not merely as a delivery format but as a mechanism that builds learner confidence and ethical reasoning alongside competence, reinforcing the link between PBL and meaningful AI literacy development. It also supplies a validated measurement instrument for future measurement of AI literacy course experiences.

Raising the ethical dimension of literacy has a sign problem. Among 584 undergraduates who taught themselves AI, competence raised ethical awareness ($\beta = 0.644$, $p < .001$), and ethical awareness then raised AI anxiety ($\beta = 0.439$, $p < .001$) rather than lowering it, the reverse of the predicted direction (Mu et al. (2026)). The lesson the authors draw is that teaching how ethical concerns are governed has to accompany the ethical dimension itself, or literacy work can leave learners more anxious than it found them.

AI literacy as a core gap in Conversational AI frameworks. The umbrella review of conversational AI agents (Ganguly et al. 2025, 34 reviews) identifies **limited AI literacy support** as a major gap in CAI frameworks, and its ethical-use roadmap makes foundational assessment (including strengthening AI literacy) the first pillar alongside participatory design, ethical-use guidelines, and continuous evaluation of cognitive impact. It further finds that AI-literacy, training, and awareness rank among the most-emphasized ethical directions in the CAI literature.(Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use)

Effectiveness of AI literacy interventions. A three-level meta-analysis of 59 studies (172 effect sizes, 7,211 participants) estimates a large overall effect of AI literacy interventions ($g = 0.837$, $p < .001$) — but with a wide prediction interval [−0.292, 1.966], so effectiveness varies considerably across settings. Interventions in East Asia and Europe outperformed those in North America, and knowledge-focused interventions outperformed those targeting skills, attitudes, or ethics. The authors argue AI literacy education should therefore move beyond knowledge toward skills, practices, ethics, and attitudes, supported by integrated and reflective pedagogies (project- and problem-based, inquiry-based, experiential) and GenAI-supported tools — a shift that aligns with the participatory, producer-oriented forms of Computational Thinking described elsewhere in this knowledge base.

A second synthesis reaches a similar magnitude on a narrower base and sharpens the measurement problem. Yu, Kim, Chang and Huang (2026) pooled 57 effect sizes from 16 studies covering 3,837 K-12 students who were taught *AI itself* rather than taught *with* AI, and estimated Hedges' $g = 0.892$ (95% CI [0.548, 1.236], $p < .001$), robust to assumed pre-post correlations from 0 to 1 and stable after trim-and-fill at $g = 0.952$. Every one of the 57 effects pointed positive (range 0.16 to 4.93), and no moderator (publication source, year, school level) explained the substantial heterogeneity ($I^2 = 94.68\%$). The authors' preferred explanation is measurement: the included studies called everything from AI knowledge and ethics to attitudes, motivation, self-efficacy and career interest "AI literacy," so the pooled figure describes a distribution of positive findings under one loose label rather than one uniform intervention. Read alongside Liu et al., the two

estimates agree that AI literacy instruction works and agree on little else, which is itself the field's measurement signal.

Classroom evidence for deliberately *brief* designs is thinner, but it runs in the same direction and adds a behavior-level outcome that surveys cannot supply. Clerc et al. (2026) gave 116 French students in grades 8–9 a two-hour workshop on how LLMs work and fail, paired with practice in predicting whether a prompt would elicit a usable answer, evaluating the response, and revising or asking again. Two days later, during six LLM-supported science problems with a control group, trained students accepted underspecified prompts less often (51.5% vs. 66.7%, OR = 0.47), asked follow-up questions after a weak response far more often (59.2% vs. 27.9%, d = 0.80), and judged answer correctness more sensitively to prompt quality (interaction OR = 2.52), with a modest score difference (11.38 vs. 10.29 of 20, p = .040). The workshop never rehearsed the test tasks, so what transferred was a regulatory stance rather than task familiarity — and the authors are explicit that two days is not durability.

AI-supported critical media literacy in elementary school. Demir and Akar (2026) provide a concrete elementary-school demonstration of GenAI-supported literacy instruction: an 18-hour, 5E-model program for fourth-grade Turkish students in which ChatGPT and Grammarly were embedded phase-by-phase as pedagogical agents (ChatGPT for reflective questions and Q&A, Grammarly and Canva AI for content refinement, Padlet for peer feedback), aligned to the Turkish Language and Social Studies curricula. The AI-supported group showed large gains in media reading (+3.50), writing (+1.67), and total media literacy (+5.17, all $p < .01$) with between-group effect sizes of Cohen's d = 1.12–1.31, while the control group advanced only modestly. Qualitative analysis surfaced six domains of critical media literacy growth — digital self-protection and data privacy, purposeful and responsible media use, safe communication and boundary awareness, critical evaluation and misinformation awareness, online risk awareness, and media ethics/digital citizenship — evidence that developmentally appropriate, discipline-embedded GenAI use can build the critical-evaluation and ethical dimensions of AI literacy, not just operational skill.

Frameworks for structuring AI literacy. Several recent contributions offer structured progressions for building AI literacy. **Marienko, Markova, and Semerikov (2026)** propose a five-level framework (Awareness, Application, Evaluation, Creation, Ethics) integrated with three paradigms of AI in education (AI-directed, AI-supported, AI-empowered), developed through a mixed-methods study of Ukrainian secondary educators (national survey n = 2018; PD evaluation n = 1130). They found 84% of educators use AI but only 11% can identify specialized services beyond ChatGPT, and a professional-development intervention produced a 24% improvement in AI competence — evidence that targeted PD advances literacy beyond surface-level tool familiarity. The framework's grounding in Constructivism, connectivism, and TPACK connects to Technological Pedagogical Content Knowledge (TPACK) and Teacher AI Competency. Complementing this, **Moore et al. (2026)** used a two-year DBR process with a youth and AI-expert advisory board to design a science-integrated ML curriculum for high school youth, finding ML-knowledge gains in both cohorts (Cohort 2 M2−M1 = 0.175 vs Cohort 1 0.076) and greater gains among female and non-White participants — evidence that participatory, discipline-integrated design can advance both AI literacy and Equity.

A PRISMA review of 39 STEAM studies (2016–2025) found those implementations chiefly develop technical literacies — fundamental AI concepts, computational thinking, data literacy — while underdeveloping ethical awareness, creative imagination, and creating, managing and designing with AI, so discipline-embedded units can still miss the higher-order elements (Niri et al., 2026).

The construct is contested precisely where educators are concerned. A review of 34 studies on AI literacy in teacher education found that the field lacks consensus on what AI literacy means for professional educators as distinct from general digital literacy, and UNESCO's AI Competency Framework for Teachers specifies 15 competencies across five dimensions while functioning as a global policy reference rather than implementation guidance. The faculty in the cross-institutional teacher preparation collaboratory treated AI literacy as an integrated dimension of professional preparation rather than a separate technology skill, so candidates were expected to audit, compare and justify AI output within disciplinary coursework rather than to demonstrate tool familiarity.

Initial teacher preparation is where the structure is thinnest. Pinto et al. (2026) reviewed 11 studies of AI in initial teacher training for pre-service primary mathematics teachers and found that nine were a single session or a handful of sessions embedded in existing courses, prompting was explicit training content in only some of them, and Ethics appeared in just three, none of which addressed transparency, algorithmic bias or accountability. The risks they report are literacy-level failures: pre-service teachers failed to notice conceptual errors produced by ChatGPT, accepted generated content uncritically, and delegated more problem solving to the tool as the tasks became harder. Their recommendation is to build AI competency across the whole training sequence, from a preparatory phase into the practicum, rather than in an isolated module.

Teachers' accounts of *why* AI education is taught add a purpose layer that competency frameworks leave implicit. Fagerlund et al. (2026) interviewed 13 Finnish teachers from preschool through grade 9, largely novices in AI education, and read their purpose statements through Biesta's three domains. Qualification, the acquisition of competencies, was the clearest and most concrete purpose, and it operated as a pathway into the other two: students were to grasp AI as a sociotechnical phenomenon and use its tools, with AI serving both as a target and as an aid to learning. Socialization appeared as cultivating enthusiasm, presenting AI as "cool," and framing students as future AI-savvy workers who must meet competency demands. Subjectification, the self-determined and personally meaningful engagement Biesta treats as central, was named as important but had no concrete instructional repertoire beyond discussing and contemplating, and teachers offered no worked examples for contesting AI's authority. The authors propose **informed AI agency**, a heuristic that places subjectification at the center while treating competencies as explanatory frameworks for self-determined choices. The design implication is that the "why" of AI education needs as much design attention as the "how": when subjectification rests on generic discussion, AI literacy instruction reverts to the qualification it was meant to sit beside.

Readiness itself is a contested target. Charles (2026) argues that teacher readiness for AI-rich learning should be read from the quality of the designs teachers produce, not from adoption, confidence or digital competence, and builds a framework around *design mediation*: observable decisions such as tool selection, task and prompt design, scaffolding, verification, transparency, assessment redesign, accessibility planning and human oversight. Two of its claims have direct professional-development consequences. First, Self-Efficacy is a mobilization resource rather than a quality indicator, because confidence without AI-specific pedagogical knowledge or ethical orientation can accelerate poor design rather than prevent it, which qualifies the usual reading of teacher confidence as a readiness signal. Second, policy clarity and institutional support are separate moderators, so material support can be high while expectations stay ambiguous and readiness still translates poorly. The framework also declines to equate non-use with unreadiness, since a

reasoned decision to withhold AI can itself demonstrate design judgment. It is conceptual and unvalidated, so it supplies propositions and evidence sources rather than established effects.

AI-interaction literacy: the interactional dimension. Brunnström and Palmqvist (2026) propose a narrower, interactional competence — the ability to *steer, evaluate, and learn from* iterative interaction with GenAI — as a specific enactment of the applicational, evaluative, and integrational dimensions in broader frameworks such as the AI Literacy Heptagon. Their reflective demonstration shows what it consists of in practice: recognizing that a fluent answer is pitched above one's own schema, requesting simplification, narrowing scope, and redirecting the system toward focused practice. Two design consequences follow — the skill is unevenly distributed, so unguided use may advantage already-confident students and widen gaps (Equity), and it has to be taught explicitly rather than assumed, with teachers covering how to formulate productive prompts and when to stop using the tool (Self-Regulated Learning).

Critical AI literacy: beyond skills to power and resistance

A distinct strand of the knowledge base treats AI literacy not merely as skills or critical evaluation but as a *critical and political practice* that interrogates power, authority, and whose knowledge counts. This connects AI literacy to Critical Pedagogy and Equity:

- **"Resisting AI" as a literacy stance.** Critical AI Literacy (CAIL) can encompass *resisting AI* — refusing the inevitability and techsolutionism of dominant discourse, and cultivating collective agency through dialogic, collaborative pedagogies.(Reorienting Critical AI Literacy: A Community-Rooted Praxis of "Resisting AI") This positions education as a space where communities imagine and build alternative futures, rather than merely adapt to a given technological order.
- **Community-based epistemologies.** Community-based AI learning grounds AI engagement in learners' lived and community-based ways of knowing, redistributing AI's epistemic authority through epistemic fine-tuning, redistribution of authority, and situated discernment.(Community-Based AI Learning: Redistributing Artificial Intelligence's Epistemic Authority in Education)
- **Critical and feminist frames.** Critical, feminist scholarship argues AI literacy should be framed within pedagogies of justice, resistance, and cultural Sustainability — asking whose knowledge AI produces, who benefits, and who is accountable when systems fail.(Can we disrupt the momentum of the AI colonization of science education?)
- **Competence frameworks may be structurally unable to register what LLMs reveal.** Schlauch (2026) argues that LLMs make literacy's sociomaterial character conspicuous — texts are constituted in assemblages of people, technologies, practices and infrastructures — and that competence frameworks, by centring the individual learner, then have nowhere to put the distributed, infrastructural and nonhuman dimensions. The design consequence is a shift from transmitting competences to creating conditions. Three orientations follow: making assemblages visible by tracing the actors behind a text, with a student assigned the "AI whisperer" role so the model becomes an attributed classroom presence; sustaining fluid literacy spaces through modular tasks and teacher-authored system prompts rather than one approved workflow; and preserving critical reflexivity rather than smoothing difficulty away.

- **The literacy mandate can itself discipline.** Wang & Jin (2026) argue the demand to 'learn about AI' treats one kind of learning as natural and makes those who decline, or who would keep AI literacy out of young children's curricula, responsible for their own marginalization.
- **Situated curriculum devices.** AI literacy can be built through situated, active teaching instruments (e.g., Episodes of Situated Learning) that develop AI competencies across levels rather than through abstract instruction.(Towards AI literacy: A proposal of a framework based on the Episodes of Situated Learning)
- **Creative composition as critical AI literacy pedagogy.** Rather than treating AI literacy as technical knowledge or individual competencies, design opportunities for learners to compose messages about AI for real audiences — a Multimodal AI product such as a public service announcement simultaneously demonstrates and communicates critical competence. In Burriss et al.'s (2026) classroom study, 22 eleventh graders chose their own AI Ethics issues and made video PSAs about school surveillance, informed consent, and algorithmic accusation; across all seven films harm emerged from human–machine entanglement rather than a villainous tool, the plots still closed on hope and Learner Agency, and the authors position storytelling and advocacy — resistant to traditional assessment — as core to critical AI literacy pedagogy that centers student identity, choice, and voice.("Young Scholar[s] on the Beat": Multimodal composition as a form of critical AI literacy pedagogy)
- **Regulatory competence, not acceptance.** Kim (2026) reframes AI literacy in Higher Education as *regulatory competence* — an enacted practice of verifying, revising, selectively adopting, or rejecting AI output during academic work — showing that evaluative capacity and ethical awareness (not mere willingness to use AI) predict active, critical engagement.(From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource)
- **Recognizing sycophancy as a literacy skill.** A core evaluative competency is recognizing when an AI is *agreeing* with the learner versus being correct. Contextual sycophancy shows AI literacy and prompting training reduce — but do not eliminate — sycophantic mirroring of user errors, and sycophantic AI is preferred by users precisely because it makes them feel understood. AI literacy must therefore teach learners to detect agreement-for-its-own-sake and to value corrective friction, connecting to Trust Calibration and Reducing AI Misuse.
- **Valuation, not just verification.** O'Byrne (2026) found that students who only checked output for accuracy, credibility and relevance still accepted conceptually flattened work, while those who also judged nuance, voice and epistemic stance re-authored it — making "when not to delegate judgment" the literacy question.

These critical strands complement the operational and cognitive dimensions of AI literacy: where the latter ask "can the learner use and evaluate AI?", critical AI literacy asks "does the learner understand and challenge the power structures AI embodies?"

Literacy for public life is a different target from literacy for coursework. Civic and Political Education covers the manipulation and verification problem at that target: a learner who must judge a public claim, trace it to an institution, and answer objections to it.

AI literacy in STEM education

The most developed disciplinary evidence base for AI literacy comes from STEM education, and Hallström, Chiu, Ding, Koretsky and Li (2026) synthesize its ten most-cited studies (2022–2026) to show both the baseline and its limits. Across the corpus, AI literacy is defined through six overlapping constructs — knowledge/skills/attitudes (Su & Yang 2024), conceptual-procedural-contextual knowledge (Stolpe & Hallström 2024), know-understand/use-apply/evaluate-create/ethics (Ng et al. 2022), and Long & Magerko's use–communication–evaluation framing (Hornberger et al. 2023) — so the field's "conceptual ambiguity" is a measurement problem: two studies can both assess "AI literacy" without assessing the same construct. Only two of the ten offer complete frameworks. The review's sharpest finding is an asymmetry — the corpus almost entirely measures *students'* literacy while nearly nothing develops *teachers'*, a gap that leaves teacher-facing AI literacy interventions resting on assumption rather than evidence, and one the authors connect to the practical requirement that teachers be AI literate themselves to run such interventions.(AI Literacy and STEM Education: Emerging Frontiers and Research Priorities)

The chatbot evidence in that corpus cuts against fluency-based training. Ding et al. (2023) found ChatGPT tutoring in university physics raised confidence and knowledge but reinforced a "superhuman and infallible" misconception of AI, concluding AI literacy education is "first and foremost improving students' critical thinking skills in assessing information." Xu et al. (2026) found ChatGPT-supported STEM programming improved confidence and knowledge but left computational thinking and independent thought unchanged — gains in fluency coexisting with no gain in thinking. Both findings mirror the Trust Calibration and over-reliance concerns elsewhere in this page: a tutor that never contradicts the student can produce confident learners who cannot evaluate. Attitude, not readiness or self-efficacy, turned out to be the strongest determinant of actual AI-tool use among STEM undergraduates (Falebita & Kok 2025), and the review notes STEM disciplinary coverage is skewed toward biology and physics with technology as a subject nearly absent. For discipline-specific design, the review's practical warning is that comprehensive competency frameworks (UNESCO, EU/OECD) "often lack connection to empirical research or sufficient theoretical underpinning" and few are classroom-applicable.

Whose AI skills count? The instructor–employer framing divide

A central open question in AI literacy is *which* skills matter and for whom. An Ithaka S+R study comparing how US instructors and employers prioritize the 26 skills of the HiBob AI Skills Framework found they agree on the importance of only one (setting realistic expectations for AI-augmented work). Instructors weight a **critical, responsible-use orientation** — recognizing AI's limits, transparency and attribution, human accountability, proactive output review — which aligns with academic values of attribution, review, and information literacy. Employers weight **productivity-oriented skills** — workflow evaluation and redesign, automation, and human–AI teaming — that reflect team-based workplace efficiency. Because only three of 26 skills are taught by half or more instructors, and those taught skew toward the critical-use categories, the report identifies a concrete **AI skills gap**: whole categories employers value are neither prioritized nor taught in college curricula.(AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently) This divide frames AI literacy as a contested construct — critical-use literacy for academic settings versus workflow-integration literacy for employment — a tension relevant to Framing AI Use for Students, Curriculum Design, and Workplace Learning.

Students' own ratings tell a related but differently ordered story. ElSayary and Ragab (2026) surveyed 380 university students, mostly STEM-enrolled frequent AI users, and found self-reported AI literacy carried most of the explanation of perceived employability readiness: four literacy dimensions added $\Delta R^2 = 0.554$ ($p < .001$) on top of background controls worth only 0.054, and the full model reached 60.8% of the variance. Within the literacy set the evaluative dimension was strongest (Analyze & Evaluate, $\beta = 0.286$), followed by the affective one (Attitudes & Mindsets, $\beta = 0.266$), with hands-on use ($\beta = 0.217$) and foundational knowledge ($\beta = 0.187$) behind them; for perceived career readiness specifically, only Analyze & Evaluate ($\beta = 0.216$, $p < .001$) and Attitudes & Mindsets ($\beta = 0.192$, $p = .004$) were significantly associated. Read against the Ithaka divide, students' own sense of workplace readiness leans toward the critical-evaluation orientation instructors favor rather than the workflow-integration skills employers weight. The design is a single-session self-report with uniformly high means (4.17 to 4.57 of 5) and no employer or employment measure, so what it shows is that self-assessed AI literacy and self-assessed employability move together, with the evaluative and dispositional parts doing most of the work, not that these students are demonstrably workforce-ready.

Designing AI literacy interventions

The knowledge base's frameworks and empirical studies converge on a set of practical guidelines for educators and instructional designers building AI literacy interventions:

1. Use a structured competency framework as scaffolding, not a checklist. Mature frameworks give designers a shared vocabulary and a developmentally sequenced target. The SAIL framework organizes AI literacy into three domains (AI Concepts; Application and Technical Skills; AI Digital Citizenship) across four scaffolded levels — Understand and Explore → Apply and Integrate → Evaluate and Create → AI++. The AI Literacy Heptagon cross-cuts seven dimensions (technical knowledge, application, critical thinking, ethics, social impact, integration, legal/regulatory) with four Bloom-aligned proficiency levels, and stresses that emphasis must be **adapted to disciplinary context** — technical programs weight application, humanities programs weight ethical and social-impact reasoning.(The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education)(The AI literacy heptagon: A structured approach to AI literacy in higher education)

2. Engage learners across ICAP modes. Applying the ICAP Framework, effective instruction gives learners opportunities to engage at multiple cognitive levels — passive exposure (AI concept lectures), active manipulation (hands-on tool use), constructive generation (creating AI artifacts, self-explaining), and interactive dialogue (collaborative Problem Solving with peers and AI) — selecting the mode that fits the learning goal. A systematic review found successful collaborative AI-literacy interventions spanned all four ICAP modes.(Systematic review of collaborative learning activities for promoting AI literacy)

3. Assess demonstrated competence, not self-perception. Self-reported AI literacy diverges sharply from measured performance — teachers overestimate their AI skills by ~40%, and performance-based measures correlate with classroom AI integration far better than self-reports ($r \approx 0.72$ vs 0.31). Design interventions around performance-based assessment and calibration rather than confidence surveys, and use diagnostic profiles (overestimators vs. true novices) to target support.(How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures)

4. Build metacognitive and critical dispositions, not just operational skill. AI literacy is better understood as a metacognitive social practice than a skills checklist: because LLMs are probabilistic and opaque,

learners must monitor and adjust their strategies, cultivate scientific skepticism, and interrogate how algorithms shape knowledge production — not merely learn to operate tools. Participatory co-design and experimental, project-based spaces (not one-off tool training) are where this awareness grows. (Metacognitive AI literacy: Going beyond the AI skills gap agenda)

5. Embed literacy in the discipline and make it sustained. Movement toward higher stages of AI literacy (from uncritical use → informed use → critical evaluation → improvement) is most visible when experiences are **sustained and discipline-embedded** rather than delivered as standalone workshops. Design for repeated, contextual practice within authentic coursework.(Beyond Tool Adoption: A Practical Five-Stage Developmental Continuum for AI Literacy in Higher Education) A concrete model of discipline-embedded critical literacy is the task-based taxonomy of Dierickx et al. (2026) for journalism: it maps LLM-supported tasks across the four stages of the news workflow (newsgathering, sensemaking, editing, publication/distribution), each tied to a baseline prompt and a risk-and-mitigation strategy. By treating task definition and prompting as a situated form of professional judgment — not a neutral technical skill — it turns prompting itself into a vehicle for critical AI literacy (bias, hallucination, overreliance, and the enduring value of human editorial oversight), and its underlying logic transfers to other knowledge-intensive professions (law, medicine, public policy). Complementary to such discipline-specific taxonomies, the Dohn et al. (2026) taxonomy classifies GenAI learning activities along six dimensions, of which **Epistemic Engagement** (understanding / using / critiquing / constructing GenAI) directly operationalizes AI literacy as the depth of learners' cognitive relationship with the technology — from passive exposure to active critique and construction.

6. Treat equity and the digital divide as design constraints. AI literacy is a mechanism for addressing the three-level digital divide (access, skills, outcomes): closing the device gap is insufficient unless skills and critical use are built so benefits distribute fairly. Interventions should plan explicitly for learners who enter with less prior AI access, and incorporate cultural and governance perspectives rather than treating literacy as culture-neutral.(The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education)(Digital Divide)

7. Pair literacy with misuse-reduction levers. Because AI misuse actively harms durable learning, literacy instruction should be coupled with the structural and educative levers documented under Reducing AI Misuse — guardrailed "hint-not-answer" tool design, assessment redesign, and scaffolded think-first/AI-second sequences with deliberate prompting practice.

8. Start from learners' actual entry point. Learners enter with distinct orientations — avoidance driven by fear, mistrust, or lack of access, versus uncritical reliance that masks misunderstanding. A diagnostic, stage-based approach (rather than a uniform curriculum) lets designers meet students where they are and move them toward critical, responsible engagement.(Beyond Tool Adoption: A Practical Five-Stage Developmental Continuum for AI Literacy in Higher Education)

9. Extend provision beyond the audiences formal education already reaches. The AI Literacies framework for public service media argues from a landscape review of more than 40 frameworks and 35 expert interviews that provision has tilted toward technical and functional skills, and that AI literacies overlap and should be connected to digital, media and information literacy rather than taught as a standalone subject. Its structure — six competency areas, five values and three progression levels (*Understanding and Applying*, *Analysing and Evaluating*, *Synthesising and Specialising*) with an assessment guide — is a usable

template for providers outside formal schooling, and its equity argument is a design instruction: reaching young people who are digitally or otherwise marginalized takes deliberate partnerships, not universal publication.(Supporting AI Literacies for Young Adults Aged 14-19: A value-based, practical framework for public service media organisations)

Measuring AI literacy

A distinct research thread treats AI literacy not only as a target for instruction but as a construct to be measured. The knowledge base's assessment strand separates **self-reported** from **performance-based** skill: reporting diverges sharply from demonstrated competence (teachers overestimate by ~40%), and performance-based instruments predict classroom AI integration far better than confidence surveys ($r \approx 0.72$ vs 0.31). Intervention work reproduces that divergence at the level of behavior: in Clerc et al. (2026), neither GenAI attitudes nor a general metacognitive-awareness scale predicted students' regulation of LLM interaction or their final task scores ($r = .01$ and $r = .04$, both non-significant), while the behaviors the workshop changed — rejecting underspecified prompts, judging answer correctness, asking a follow-up — did track answer quality. Validated instruments are emerging to close this gap — the GLAT provides a psychometrically validated generative-AI literacy assessment, and diagnostic profiles (overestimators vs. true novices) let designers target support where it is needed. Guo et al. (2026) map that instrument landscape directly, reviewing 80 validated frameworks — 69 digital literacy and 11 AI literacy — published between January 2014 and February 2025. AI has pulled digital literacy toward ethics and recast communication to include human–AI interaction, while metacognitive regulation and educator-specific human–AI collaboration remain the least specified. For design and research, this ties AI literacy to Educational Measurement and to Assessment broadly: a literacy framework is only as useful as the instruments used to track growth, and stage-based continua require reliable measurement to place learners along them.

Puppart, Laak and Aru (2026) supply the largest objective counterpart yet: an 18-item test validated on 7,432 Estonian high school students (marginal reliability = .72), with scores unrelated to perceived ease of use ($\rho = .01$) and negatively related to use frequency ($\rho = -.16$ to $-.19$).

A 32-item six-facet instrument extends the four-dimension model with two further facets — responsible use and self-development — and holds scalar invariance across adolescents (12–17), young adults (18–40) and midlife adults (41–60), though the authors caution the ΔCFI approached the conventional cutoff (Liu et al. (2026)).

Zhi, Yang and Huang (2026) build a graduate-specific model on Marzano's taxonomy: grounded-theory analysis of interviews with 14 professors condensed 329 raw labels into 96 concepts, 15 categories and five dimensions (cognitive foundation, operational skills, higher-order thinking, metacognitive reflection, ethical responsibility), then operationalized them as a 15-item Likert scale whose five factors emerged in exploratory factor analysis (83.14% of cumulative variance) and held in confirmatory factor analysis on a second subsample (CFI = 0.934, RMSEA = 0.083), with reliability from 0.796 to 0.842 across 308 valid questionnaires.

The Critical 3wAI Literacy Scale (Bozkurt, Ertan & Cömert, 2026) validates the same three-part structure for adult learners as a self-report instrument ($n = 546$ and $n = 647$; $\chi^2/df = 4.93$, CFI = 0.931, $\alpha = 0.913$). Its Know-How and Know-Why factors came out most closely coupled (HTMT = 0.544), while theoretical

knowledge alone did not translate into practical efficacy. As a self-report measure it shares the divergence problem documented above, so it is a validated diagnostic rather than a performance measure — and the authors call for revalidation across age groups and cultural contexts.

A related question is *what* the instruments can measure at all. Burriss et al. (2026) note that existing AI literacy scales and competency frameworks assume individually measurable performance and so structurally exclude collaborative, creative expression — their unit's evidence was Multimodal AI film artifacts, reflections, and civic discourse rather than a summative score, and the authors argue such evidence can *complement* rather than replace conventional measures. Broadening the construct may therefore require broadening the admissible evidence, not merely adding modality-rich items to existing scales.

A complementary strand measures how learners and teachers receive AI literacy *materials* rather than their literacy itself. Wang, Chuang and Wu (2026) had 794 students and 37 teachers rate two guidebook editions built to UNESCO's age threshold (ages 9-12 and 13-18) after roughly 30 minutes of guided classroom exposure. Acceptance held a four-factor structure (Performance Expectancy, Effort Expectancy, Perceived Playfulness, Behavioral Intention) with measurement invariance supported across the two student editions, younger learners scored higher on all four constructs, and perceived playfulness carried the largest association with intention in both cohorts. The authors are explicit about what this is not: perceived acceptance of an age-tiered resource is not AI literacy achievement, ethical reasoning, adoption or sustained use, and material-level acceptance should not be read as evidence that literacy improved.

Measurement also extends to the educators who mediate learners' engagement with AI. Most AI-literacy assessments target students or general users, leaving a gap in teacher education — a gap the Teachers' AI Literacy Scale (TAILS) addresses: grounded in the ED-AI framework with six dimensions (knowledge, evaluation, collaboration, contextualization, autonomy, and ethics), it was validated through exploratory and confirmatory factor analysis with preservice language teachers. Such instruments support measuring and developing the AI literacy of the educators who mediate learners' engagement with AI. On the student side, Nie et al. (2026) develop and validate a Generative AI Assessment Literacy Scale (GAA-LS) for higher-education students — an 18-item, five-factor instrument whose scores track Feedback engagement, Academic Integrity, and responsible AI use, with an indirect path to integrity running through feedback — evidence that assessment-specific AI literacy is measurable and ties to integrity behavior. What that teacher-facing instrument corpus actually contains has since been audited: Zainal, Mohd Matore and Maat's 2026 review of teacher AI literacy measurement tools appraised 33 instruments published between 2019 and 2025 and found that 31 (93.9%) were self-report scales of perceived confidence, only two tested knowledge objectively, and none used performance-based tasks, while fairness evidence was the weakest quality domain, with only five instruments reporting measurement invariance or differential item functioning.

The 2026 update of that measurement literature reorganizes it into four domains — knowledge and use, epistemic oversight, reliance calibration, and operational control of tool-using agents — and reports that no validated individual-level instrument in the corpus covers the full combination of scope, permissions, recovery, state isolation, independent review and evidence-based closure that agentic tool use demands. Its pooled subjective–objective correlation across three same-sample effects was r = .055, consistent with the divergence described above rather than with self-ratings as a usable proxy (Verí (2026)).

The measurement landscape is itself disordered, and now partly mappable. He, Zhang, Wang and Ji (2026) analyzed the AI literacy instrument corpus with an LLM-based coding pipeline and found the field

measuring many constructs under one label — a jangle problem, with one construct carrying several names (Behavioral Commitment appears in eight candidate pairs, Intrinsic Motivation in five), alongside candidate jingle cases where instruments share a label but not their item content. Their semantic-similarity recovery of item and construct structure correlated only moderately with instruments' own reported reliabilities (r = 0.49 at item level against 0.45 and 0.35 at construct level), and they offer the method as screening rather than adjudication. The consequence for anyone selecting a measure is that convergent claims across studies are not safe to assume: two instruments with the same name may not operationalize the same construct.

What those instruments can support has now been audited, and the audit is sobering. Jin, Gašević, Martinez-Maldonado and Yan (2026) screened 8,056 records down to 58 studies covering 47 unique instruments, appraised with COSMIN against a construct whose instrument-development window compressed into three years (two instruments before 2023, 28 in 2025 alone). The corpus remains 37-of-47 self-report, and the evidence clusters tightly around internal structure: structural validity was sufficient in 32 of 58 studies and internal consistency in 32 with none rated insufficient, but construct validity was reported by only 15 studies (12 sufficient), criterion validity by one, measurement invariance by five (all sufficient), and just 2 of 58 earned a sufficient overall content-validity rating — comprehensiveness was insufficient in 53 despite 43 studies reporting cognitive interviewing. The pattern is that measurement practice looks robust exactly where it is cheapest to demonstrate and thin where evidence must come from outside the instrument, so a clean factor structure and a high coefficient (which can reflect item redundancy as much as construct representation) should not be read as demonstrated capability. The authors' prescription is consolidation rather than proliferation: refine existing scales, test invariance whenever one crosses a language or an educational stage, and add criterion evidence by relating scores to performance tasks.

One of the exceptions is built to compare groups. Zhang et al. (2026) developed the Generative AI Literacy Scale (GAILS) — 43 items reduced to 34 through a five-expert Delphi review and a seven-person pilot, then validated in 341 North American adults — and tested scalar invariance, finding that it held across female and male respondents and across student and workforce groups. That is what licenses the mean comparisons the instrument reports — men scoring modestly higher on Adaptive Operational Skills, students higher on Adaptive Operational Skills and Responsible GenAI Literacy — as competence differences rather than differential item functioning, and it is what makes the scale usable across Higher Education and workplace settings rather than student-only. Its own evidence is not unblemished: fit was mixed (CFI = .967 and SRMR = .058 inside conventional cutoffs, RMSEA = .087 above them), total-scale α = .973 sits alongside one failed Fornell–Larcker discriminant comparison (Factor 1 √AVE = .828 against r = .873 with Factor 3), and, like almost everything in the corpus, it measures perceived competence with no behavioral criterion. A validated scale in this field is a starting point for the invariance and criterion work the review calls for, not a finished Benchmark.

Connections across the knowledge base

AI literacy intersects with AI Tutoring (understanding when and how AI tutors are effective), Teacher AI Competency (educator preparedness), Academic Integrity (knowing what constitutes appropriate AI use), and AI in Education broadly. It is both a prerequisite for effective AI use and an outcome of well-designed AI integration — students learn AI literacy BY using AI critically, not just by learning ABOUT AI.

AI literacy is **double-edged** for overreliance: Maizel et al. (2026) found the skill-based dimensions of AI literacy (using/understanding, detecting) were *positively* associated with reported AI dependency, while AI Self-Efficacy and academic confidence were negatively associated — so technical AI-literacy training, absent self-efficacy and Self-Regulated Learning scaffolds, can increase dependency. AI literacy here becomes an enabling capacity whose *direction* depends on complementary motivational resources.

- **Verification habits pay off only through regulation.** In Davor, Larbi and Boateng (2026)'s survey of 533 university students in Ghana, AI verification literacy had no significant direct effect on critical thinking (beta = .076, p = .090) or technical Problem Solving (beta = .043, p = .385) and mattered only through metacognitive self-regulation (beta = .167, p < .001), a full mediation the authors call metacognitive activation. AI task scaffolding predicted both outcomes (beta = .185 and .170), while cognitive offloading tendency predicted them negatively (beta = -.240 and -.312) and depressed regulation as well (beta = -.294). Teaching students to check AI output is therefore not enough on its own: evaluative habits need planning, monitoring and reflection built into the task.
- **Literacy reaches problem solving through cognitive moves, not through tool access.** A time-separated three-wave survey of 784 students at six Guangdong higher vocational colleges put AI literacy's total association with self-rated complex problem solving at 0.480: 0.248 direct and 0.232 indirect, split 0.151 through systematic thinking and 0.081 through cognitive load (Huang et al. (2026)). Perceived school ICT support moderated both routes (interactions 0.128 and −0.352), carrying the conditional indirect effects from 0.117 to 0.176 and from 0.038 to 0.127 in a self-report survey, not a trial.
- **Critique of AI output as a literacy practice:** Hosseini (2026) treats evaluating AI-generated errors as a core AI-literacy skill, using failure-mode analysis and iterative prompt refinement in a database design course. The study found students overestimated their AI abilities (self-reported literacy weakly, negatively correlated with objective competency), and that critique-based learning strengthened calibration.
- **Socialist humanist AI literacy (2026):** A literature review critiques compliance-oriented AI literacy and proposes a socialist-humanist framing of asynchronous AI literacy and fair use in higher education, linking the historical digital divide to modern AI literacy and calling for approaches that serve human flourishing and equity rather than mechanical policy compliance (From Mechanical Compliance to Human Flourishing: A Socialist Humanist Approach to Asynchronous AI Literacy and Fair Use in Higher Education).
- **Cheap, light-touch warnings blunt AI persuasion — without costing general trust.** Orchinik and Rand (2026) preregistered two experiments (total N = 3,208 US adults) in which participants conversed with an Large Language Models (LLMs) instructed to shift their views on political topics. A single brief warning — that models can be prompted to persuade and may present information selectively — cut belief change by roughly one half (-48.1%, 95% CI [-59.5%, -36.8]) relative to control, and adding specific persuasion-technique warnings produced no further benefit. The property that matters for teaching is on the other side of the effect: general trust in Generative AI did not fall, so the intervention builds calibrated trust rather than blanket skepticism. It is a one-paragraph, no-facilitation intervention, which is a rare cost profile for an AI literacy design.

- **Learner governance of AI matters more than the design of the tool.** Azimi (2026) randomized 33 students in a master's data-analytics course between a scaffolded AI Study Coach embedded in the notebooks (n = 16) and unrestricted use of any Generative AI tools they chose (n = 17) for seven weeks. Assignment performance and concept-inventory gains were indistinguishable; the Coach condition reported higher confidence instead. What separated students was AI literacy in practice: those who had formulated their own rules for when to use AI scored higher in both conditions, and the students with the deepest model understanding — every one of them self-taught — prompted most deliberately. The design implication runs against the control reflex: teach the self-regulatory and model-understanding components of AI literacy rather than constrain tools.

For critical AI literacy specifically, Solyst et al. (2026) show that youths can be taught to evaluate generative AI systematically, given scaffolding that names what to look for and a structure for recording what they find.

Suartama, Sukmana and Triwahyuni (2026) propose CAFE-AI, a design that pairs AI literacy instruction with growth-mindset framing, reporting that the combination improved both measured AI literacy and mindset over a semester in one Indonesian university course.

Fifty frameworks in two years, and almost none of them measures generative AI. Kharbach, Woodworth and Sawchuk (2026) charted 50 K-12 AI literacy frameworks published in 2024 and 2025, 35 of them in 2025, from fifteen countries. The 27-item GAIAS was the only generative-AI-specific instrument in the corpus, and the dominant tools, AILQ, SAICS and the Chung et al. diagnostic, do not assess generative AI literacy "at all." Competency labels converged on the same five dimensions while the constructs underneath them did not align.

A literacy score can be uncorrelated with the outcome it is meant to protect. Among 300 university students, Kim, Kim and Zhang (2026) found AI literacy uncorrelated with AI overtrust at the bivariate level ($r = 0.051$) while carrying a negative indirect association inside a serial mediation model. Once performance expectancy was in the model, higher AI literacy predicted lower overtrust. Knowing more about AI did not, on its own, change how much students trusted it.

Common Misconceptions

- **"Self-reported AI literacy tracks actual AI literacy."** It **diverges sharply from measured performance** — teachers **overestimate their skills by about 40%**, and research on literacy assessment shows the same **40% gap** between self-report and performance-based measurement. A survey of AI literacy measures confidence, not competence.
- **"AI literacy is one construct."** Sun, Dohn and Rehm (2026) classified **102 empirical higher-education studies** and found the construct is not unitary. A program that builds one dimension leaves the others unaddressed.
- **"A 40% overestimate is a minor calibration issue."** It means the students and teachers most confident about their AI literacy may be the ones least able to evaluate output — which is exactly the population an intervention has to reach first.

Connected Concepts

- Pedagogical Patterns — Developed by the critical-appraisal steps in these sequences

- Learners — Learners: the umbrella for the learner-side concepts
- Generative AI — the technology AI literacy targets
- Large Language Models (LLMs) — the systems at the heart of AI literacy
- Critical Thinking — core evaluative disposition
- Prompt Engineering — core practical competence
- Metacognition — literacy as metacognitive social practice
- Cognitive Offloading — the over-reliance risk literacy counters
- Reducing AI Misuse — literacy's behavioral payoff
- Academic Integrity — knowing what constitutes appropriate AI use
- Self-Assessment — judging your own work and skill, as technique and as measure
- Trust Calibration — calibrating appropriate trust
- AI Sycophancy — literacy skill of detecting agreement
- Equity — fair distribution of literacy
- Digital Divide — the access/skills/outcomes gap
- Ethics — ethical awareness dimension
- Teacher AI Competency — educator preparedness
- Educational Development — building educator literacy
- AI-Assisted Educational Research — AI-Assisted Educational Research
- K-12 — school-level literacy
- Higher Education — university-level literacy
- Career Development and Readiness — the employability payoff AI literacy is argued to build
- AI in Education — the broader field
- Civic and Political Education

Connected Articles

- Shaping early childhood in the age of AI: holistic competencies, pedagogical practices, and ecological support — Shaping early childhood in the age of AI: competencies, pedagogy and ecological support (Pei 2026)
- AI Security Literacy: Ecosystem-based Competency Framework and K-12 Learning Platform — AI Security Literacy: Ecosystem-based Competency Framework and K-12 Learning Platform
- Modeling the Relationships Between University Students' AI Competence, AI Ethical Awareness, and AI Anxiety: A Dual-Stage PLS-SEM and ANN Analysis - Raising the ethical dimension of literacy without a coping framework can leave students more anxious
- Reconceptualizing digital literacy in the AI era: A systematic review of validated frameworks from an ecological perspective — 80 validated frameworks show AI expanding digital literacy toward ethics while educator human–AI collaboration stays under-specified (Guo et al. 2026)
- Supporting AI Literacies for Young Adults Aged 14-19: A value-based, practical framework for public service media organisations — Six competency areas, five values and three progression levels for public service media

- The AI literacy heptagon: A structured approach to AI literacy in higher education — The AI Literacy Heptagon
- Beyond Tool Adoption: A Practical Five-Stage Developmental Continuum for AI Literacy in Higher Education — A Practical Five-Stage Continuum for AI Literacy
- Clarifying the conceptual landscape in AI literacy measurement: A large language model based approach — Mapping the AI literacy instrument corpus: 55 constructs, jangle and jingle pairs, LLM-based coding
- Measuring Artificial Intelligence Literacy: A Systematic Review of Instrument Development, Conceptual Foundations, and Psychometric Quality — COSMIN appraisal of 58 studies and 47 AI literacy instruments: validity evidence clusters around internal structure while criterion, content and invariance evidence stays largely missing (Jin et al. 2026)
- The Generative Artificial Intelligence Literacy Scale (GAILS): Development, Validation, and Measurement Invariance Across Sex and Occupational Status Groups — GAILS: 34-item GenAI literacy scale validated in 341 adults, scalar-invariant across sex and student/workforce groups (Zhang et al. 2026)
- GLAT: The generative AI literacy assessment test — GLAT: a validated generative AI literacy assessment test
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — AI Literacy Assessment: Self-Reported vs Performance Misalignment
- Development and Validation of the Generative AI Assessment Literacy Scale for Higher Education Students: Psychometric Evidence and Associations with Feedback Engagement and Academic Integrity — GAA-LS: validated Generative AI Assessment Literacy Scale for higher-ed students (Nie et al. 2026)
- Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use — Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use
- How AI literacy correlates with affective, behavioral, cognitive and contextual variables: A systematic review — systematic review of what AI literacy correlates with
- Assessing teachers' AI literacy: a systematic review of measurement tools — systematic review of the tools that measure teacher AI literacy
- Development of an AI literacy self-assessment questionnaire in upper primary school students — self-assessment questionnaire for upper primary students
- Metacognitive AI literacy: Going beyond the AI skills gap agenda — AI literacy as a metacognitive social practice
- AI literacy interventions in education: A meta-analysis of effects and moderators — Meta-analysis of AI literacy intervention effects
- The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education — The Scaffolded AI Literacy (SAIL) Framework
- Measuring Acceptance of Age-Tiered AI Literacy Guidebooks: A Developmentally Informed Study of K-12 Students and Teachers — Age-tiered AI literacy guidebooks evaluated with 794

students and 37 teachers: four-factor acceptance structure invariant across the 9-12 and 13-18 editions, with younger learners higher on every construct

- Reorienting Critical AI Literacy: A Community-Rooted Praxis of "Resisting AI" — Critical AI literacy: power, resistance, agency
- Prompts to Practice: A Pedagogical Framework for Human-Centered AI Engagement — Prompt literacy as a foundational literacy distinct from prompt engineering: the five-phase human-centered GenAI engagement model (Miles, Haber-Curran & Arar 2026)
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — Contextual sycophancy as an AI literacy intervention
- Understanding Student Dependency on AI: The Role of AI Literacy, Academic Self-Efficacy, and Resource Management Strategies — AI literacy, self-efficacy and dependency
- Teaching students to question the machine: An AI literacy intervention improves students' regulation of LLM use in a science task — a two-hour workshop changed middle-school students' regulation of LLM interaction, while self-reports predicted nothing (Clerc et al. 2026)
- Artificial Intelligence Literacy and Sustainable Development: An Ethical Governance and Development Goals Framework — AI literacy as a governance capacity for sustainable development: the AIRE Taxonomy and AI–SDG Nexus (Islam, Morshed & Islam 2026)
- AI literacy in secondary education: Framework, assessment, and professional development in the Ukrainian context — Five-level AI literacy framework for Ukrainian secondary educators (Marienko et al. 2026)
- STEAM education for AI literacy: a systematic literature review — STEAM education for AI literacy: systematic review
- Systematic review of collaborative learning activities for promoting AI literacy — Collaborative AI Literacy Framework
- Co-constructing AI boundaries: Agency, judgment, and ethical literacy in AI-mediated meaning-making — reframes AI literacy as judging which interpretive work should not be delegated
- Artificial intelligence-supported learning and higher-order cognitive outcomes: the mediating role of metacognitive self-regulation — AI verification literacy mattered only through metacognitive self-regulation, while cognitive offloading predicted lower critical thinking and problem solving (Davor et al. 2026)
- Designing for AI literacy: psychological mechanisms and self-determination — Thinking-based instruction beat skills-based instruction on an objectively rated task, with autonomy and competence carrying the effect (Yu, Lin & Chen 2026)
- Psychological predictors of continued ChatGPT use among university students: the roles of AI literacy, trust, and academic self-efficacy — AI literacy to continued ChatGPT use runs through trust and academic self-efficacy, and AI anxiety thins the first link (Hu 2026)
- Modeling and measuring graduate students' generative AI literacy: a study based on Marzano's taxonomy — Five-dimension Marzano-grounded model and 15-item self-report scale for graduate GenAI literacy (Zhi et al. 2026)

- Artificial intelligence in initial teacher training for pre-service primary school teachers in mathematics: a systematic review — Eleven studies of AI in initial mathematics teacher training, mostly short-term, with ethics addressed in only three (Pinto et al. 2026)
- Generative artificial intelligence in university chemistry education: a critical review using Johnstone's chemistry triplet and Biggs' 3P model — Verification-centered GenAI integration in university chemistry, with representational translation as the core AI literacy demand (Vega-Baudrit & Rivera Alvarez 2026)
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research
- Bridging the Gap: Investigating Students' Self-Reported AI-Literacy and Perceived Employability Competencies for an AI-Enabled Workforce — Self-reported AI literacy explained 60.8% of perceived employability readiness, with the evaluative and affective dimensions strongest (ElSayary & Ragab 2026)
- From Competency to Agency: Teachers' Views of the Purposes of AI Education — Teachers' purposes for AI education read through Biesta's qualification, socialization and subjectification, and the informed AI agency heuristic (Fagerlund et al. 2026)
- Teacher Readiness-By-Design for AI-Rich Interactive Learning — Teacher readiness as design quality rather than adoption or confidence, with self-efficacy as a resource and non-use not unreadiness (Charles 2026)
- The Effects of K-12 Artificial Intelligence Education in Enhancing AI Literacy: A Meta-Analysis — K-12 AI education raised AI literacy with a pooled g = 0.892 across 57 positive effects, and measurement disagreement explains the heterogeneity (Yu et al. 2026)
- Literacy demands placed on students in student–GenAI entanglements in higher education — Literacy demands differ by student–GenAI entanglement type; Assistant and Enabler forms dominate while the rest stay marginal for institutional reasons (Sun, Dohn & Rehm 2026)
- The AI Competence Framework Landscape: A Comparative Analysis of Frameworks for Education and Workforce Development — Comparative analysis of 16 AI competence frameworks for education and workforce development
- A Multidimensional Analysis of AI Literacy Determinants: External Resources, Digital Skills, and Psychological Profile Among University Students — External resources, digital competence and psychological profile as joint determinants, with a technology-anxiety sign reversal
- The Six-Facet Artificial Intelligence Literacy Questionnaire (SFAILQ): Assessing AI Literacy in Adolescents, Young Adults, and Midlife Adults — Six-facet instrument adding responsible-use and self-development facets, scalar-invariant across adolescents, young adults and midlife adults
- Exploring University Faculty's AI Well-Being: A Structural Equation Model of Social Supports, AI Literacy, and Technological Self-Efficacy — Structural equation model of faculty AI well-being, social supports and AI literacy
- What does it mean to be AI literate? Psychometric validation of the Critical 3wAI Literacy Scale — Validated 17-item self-report scale with three distinct AI-literacy factors (Know What/How/Why); Know-How and Know-Why most coupled (HTMT = 0.544)

- AI Literacy and STEM Education: Emerging Frontiers and Research Priorities — Synthesis of the ten most-cited studies of AI literacy in STEM education (Hallström et al. 2026)
- Anthropocentrism and learnification: resisting the dominant discourse of human-centred Artificial Intelligence in Education — The demand to learn about AI read as a disciplining discourse (Wang & Jin 2026)
- GenAIT: An Objective Generative AI Literacy Test for High School Students and Its Associations with LLM Use and Perceptions — GenAIT: An Objective Generative AI Literacy Test for High School Students and Its Associations with LLM Use and Perceptions (Puppart, Laak and Aru 2026)
- K-12 AI literacy frameworks after generative AI: A scoping review - 50 K-12 AI literacy frameworks; only one instrument assesses generative AI specifically
- Trusting AI too much? Psychological correlates of overtrust and the role of AI literacy - AI literacy uncorrelated with overtrust bivariately but negatively indirect once performance expectancy is modelled
- AI literacy facets in creative higher education: associations with learning performance and academic well-being — AI literacy facets in creative higher education: associations with learning performance and academic well-being
- Beyond access: How GenAI literacy relates to task performance, motivation, cognitive load and interaction patterns in AI-assisted learning environment — GenAI literacy dimensions split: Use and Apply predicts writing quality, Know and Understand predicts lower mental load, neither moves motivation (Chen et al. 2026)
- AI literacy and vocational students' complex problem-solving skills: a moderated mediation model of systematic thinking, cognitive load, and perceived school ICT support — Literacy reaching problem solving through cognitive moves, not tool access

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?
- What Is the Evidence on AI Literacy Interventions in Higher Education?
- What Competencies Do Faculty Need in Regard to AI?
- How Can We Address Common Misconceptions About AI in Education?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do I Teach Students to Verify AI Output?

Agentic AI

> **Agentic AI in Education** — AI systems that autonomously plan, execute, and adapt multi-step workflows to achieve learning goals, going beyond single-turn Q&A to act as persistent, goal-directed collaborators: AI tutors that scaffold over extended interactions, multi-agent systems that orchestrate instructional designs, and agents that co-regulate learning. This paradigm shift from a prompt-responding tool to an active collaborator carries both promise and risk: agentic AI can personalize and deepen learning, but it also threatens Learner Agency, cognitive effort, and control. The knowledge base's scoping review, tool-invariant framework, and pedagogical best-practice articles examine this tension.

Questions to Consider

- Agentic AI doesn't just answer questions — it plans, executes, and adapts multi-step workflows toward a goal, acting as a persistent collaborator. How is learning with a proactive agent different from learning with a tool you have to prompt?
- The field draws a line between "conversational" and "agentic" AI (a system qualifies only if it meets several criteria such as planning, memory, autonomy, and goal-directed action). Where is that line in practice — and does calling every chatbot "agentic" hide more than it reveals?
- The more an agent automates, the less cognitive work the learner does. Where is the line between an AI that scaffolds your learning and one that does your learning for you?
- A scoping review found only 29% of agentic AI studies grounded their systems in educational theory. If most systems aren't theory-based, what should make you skeptical when evaluating an 'intelligent' tutoring agent?
- Multi-agent systems orchestrate specialized agents with distinct roles. When several agents work together in a classroom, who is accountable — and where should a human intervene?
- The field's central tension is personalization versus learner agency and cognitive effort. If a tutor becomes so good at adapting that you never have to struggle, what learning are you actually getting?
- Where on the Copilot-to-Autopilot spectrum should a given task sit — and does moving a task from "agent proposes, learner disposes" to "agent owns it" ever serve learning rather than just efficiency?
- Hybrid agents grounded in established design theory outperformed pure prompting. Why might a theoretically-grounded system beat raw prompt-engineering — and what does that say about how an agent's 'smartness' is measured?

Introduction

Agentic AI refers to artificial intelligence systems that can autonomously plan, execute, and adapt multi-step workflows to achieve learning goals — going beyond single-turn question-answering to act as persistent, goal-directed collaborators in educational contexts. In education, agentic AI manifests as AI tutors that

scaffold learning over extended interactions, multi-agent systems that orchestrate complex instructional designs, and autonomous agents that adapt their pedagogical strategies based on learner needs. This emerging paradigm shifts AI from a tool that responds to prompts to a collaborator that actively guides, adapts, and co-regulates learning processes. - **Splitting specification from execution is what makes an agentic pipeline reliable.** DagFlow-AI has LLM agents define every component of a data-generating mechanism - variables, a directed acyclic graph, distributions and model formulas - while a program samples the observations and a validation script checks each agent output (Arthur et al., 2026). No agent generates data or writes the generation code, which the authors present as the answer to unsupported output and instruction drift.

Defining and classifying agentic AI

Kostopoulos et al. (2025) supply an operational definition the field otherwise lacks. They propose a **six-criteria checklist** — a system counts as agentic if it meets at least four: autonomy (action independent of continuous human intervention), reasoning/planning, memory/context-awareness, goal-directed action toward learning outcomes, adaptability, and dynamic collaboration/initiative. The ≥4 threshold deliberately **excludes reactive chatbots** (a static FAQ bot without planning or persistence does not qualify) while accommodating diverse architectures. They also organize the space along three axes: **pedagogical role** (tutor, learning coach/mentor, companion, instructor's assistant, curriculum planner), **autonomy level** (reactive → adaptive → proactive → collaborative), and **embodiment** (text-based, avatar/graphical, embodied/robotic). This taxonomy — particularly the autonomy spectrum and the checklist's exclusion of reactive tools — gives researchers and designers shared vocabulary for classifying agentic systems and distinguishing genuinely agentic from merely conversational AI.

A worked discriminator makes the line concrete. A static FAQ chatbot that can only answer a fixed set of questions meets **zero** criteria (no planning, no persistence, no initiative) and is plainly not agentic. A conversational tutor that remembers the current session but never acts unless prompted, holds no cross-session learner model, and cannot set sub-goals may meet only one or two (memory, some reasoning) — conversational, not agentic. By contrast, a tutor that plans multi-turn lessons, stores learner progress in a persistent profile, **proactively** fires a hint when a learner stalls, and re-plans the next step based on that profile satisfies planning, memory, autonomy, and goal-directed interaction — at least four criteria, so it qualifies as agentic. The value of running this test is not pedantry: labeling every LLM chat interface "agentic" blurs the very design question — what the system initiates versus what the learner must initiate — that determines whether it scaffolds or supplants learning.

Bounded agency as an educational design stance. Ilieva et al.'s (2026) AGAI-HE framework accepts the capability list that definitions such as the six-criteria checklist describe, then deliberately constrains it: goals, roles, data sources, tools, checkpoints, stopping conditions, and final decisions are defined or approved by educators, and each agentic function must trace to a learning requirement, assessment purpose, or governance control. The framework also draws a line between agentic orchestration and advanced prompting — an agentic workflow preserves task state, allocates functions, checks completion conditions, returns to earlier stages when evidence is insufficient, and records material decisions. Notably, its exploratory perception study with 130 higher-education students found no significant difference between agent-supported and chatbot-supported learning, which the authors read as evidence that agentic *capability* does not by itself produce a perceived pedagogical advantage (human oversight).

The field: rapid expansion and current shape

The knowledge base's scoping review — the most comprehensive synthesis of the field to date, mapping **474 studies (2020–2026)** — documents a field that has grown **explosively since 2025**, but whose literature is still dominated by conference papers concentrated in Higher Education, STEM disciplines, and text-based tutoring scenarios. The review analyzes publication characteristics, study designs, agent roles, AI models and architectures, six dimensions of agentic capability, and the extent of educational-theory integration, providing a roadmap for the field's frontiers and gaps. Notably, only **29% of the reviewed studies** (138 of 474) explicitly grounded their systems in educational theory, exposing a disciplinary divide between technically oriented and pedagogically oriented work.

A role-based map of the field

Where the 474-study scoping review and Kostopoulos et al.'s conceptual survey map research breadth and capability, Baradziej (2026) organizes agentic AI by the **role it plays** — an institutional framing for deciding where to deploy and govern these systems. Across 48 higher-education studies, six roles emerge in order of evidential weight: personalized learning and adaptive tutoring (18/48), Automated Assessment and feedback (12), teaching assistance and augmentation (11), administrative and student support (8), curriculum design and workforce alignment (5), and research support and academic operations (4). The role lens foregrounds a design choice that recurs in every deployment: how much moment-to-moment control the human retains (a "Copilot" relation) versus how much the agent owns (an "Autopilot" relation) — the autonomy axis that determines whether an agent scaffolds learning or supplants it.

Design and evaluation of agentic systems

Research in the knowledge base spans design and evaluation:

- **Hybrid agents grounded in theory outperform pure prompting:** ISD-Agent-Bench, a benchmark of **25,795 instructional-design scenarios**, finds the best-performing approach integrates classical ISD frameworks (ADDIE, Dick & Carey, Rapid Prototyping) with modern ReAct-style reasoning — hybrid (theory + technique) > pure theory > technique-only. Grounding Large Language Models (LLMs) agents in established educational-design theory provides a structural advantage raw prompting cannot replicate.
- **Assessment frameworks for agentic tools:** The tool-invariant framework proposes teaching and assessing computational methods in a way that does not depend on any specific AI tool, emphasizing Computational Thinking fundamentals, Authentic Assessment via oral defense, and verification — relevant to Over-Reliance concerns.
- **A reporting-and-governance scaler: the Autonomy–Oversight–Evidence (AOE) framework.** Dey (2026) argues the term *agentic AI* is applied so inconsistently that evidence and oversight cannot be compared across studies — systems that plan, remember, use tools, or coordinate multiple agents are lumped with static GenAI interfaces and conventional pedagogical agents. His critical integrative review of fifteen peer-reviewed reviews finds evidence strongest for artifact-level outcomes (feedback accuracy, hallucination reduction) and weakest for durable learning, equity, workload, or institutional outcomes, with authentic deployments typically short, single-

site, and weakly tied to oversight. The fix is a concrete reporting triplet — **autonomy level A0–A4** (reactive generation → bounded orchestration → delegated task autonomy → workflow autonomy → *consequential autonomy* over grading/admissions/progression), **oversight level O0–O4** (unspecified → retrospective audit → pre-use approval → checkpointed control → *continuous bounded supervision*). The triplet closes with **evidence-maturity stage M0–M5** (concept → prototype/benchmark → participant evaluation → authentic deployment → extended/multi-site → *replicated/institution scale*). A **proportionality rule** adds the constraint: allowable autonomy should not outrun either evidence maturity or oversight strength (e.g. an A4 consequential system demands M4–M5 evidence, legal validation, and O4 with human final authority). Reporting *A2–O3–M3* turns vague "agentic deployment" claims into comparable, testable specifications and gives institutions a staged adoption, logging, and rollback grammar — the evidentiary complement to the Copilot-to-Autopilot spectrum above.

- **Adversarial robustness testing:** Multi-agent stress testing coordinates Interrogator, Target, and Judge agents to reveal failure modes invisible to single-strategy testing, reducing robustness scores by 0.17–0.20 points — critical for persona consistency and safe deployment with learners.
- **Domain applications:** agentic systems appear across domains, including adaptive learning agents, pedagogical LLM agents, guided LLM scaffolding, gamified cybersecurity learning agents, and clinical simulation agents.
- **Web agents as learning-experience evaluators:** a single autonomous "describing" web agent that navigates an online lesson like a student — Wang, Mitchell & Piech (2025) — produces a description rich enough to predict student dropout and give the designer actionable feedback before real learners engage, outperforming a full simulated cohort and every baseline on a global CS1 course. This positions agentic evaluation (an agent as a stand-in critic of a learning experience) as a distinct, low-cost use of agentic AI alongside agents that teach or design.

Multi-agent systems

A growing and distinct strand of agentic AI involves **multi-agent systems** that orchestrate multiple specialized agents with distinct roles. The knowledge base documents several architectures: CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation pairs a generator agent with a validator agent for human-in-the-loop question generation; adversarial testing coordinates Interrogator/Target/Judge agents; multi-agent classrooms (e.g., MAIC with teacher, TA, and classmate archetypes) create varied peer-learning dynamics; and multi-agent social learning explores how interacting agents shape learning. Multi-agent design raises distinctive questions about human oversight (which agent is accountable, and where does a human intervene?), coordination costs, and how role differentiation supports or complicates Scaffolding.

Two 2026 systems sharpen what role specialization buys — and where it stops paying. MeduAI-SP (Yang et al., 2026) splits clinical-interview instruction across four LLM agents — a patient agent, a Socratic tutor agent, a turn-level evaluator, and a final evaluator — each carrying a distinct instructional function. The architecture withholds answers by design: the tutor was barred from disclosing the diagnosis or case answers, and the final evaluator's OSCE scores stayed hidden during the live encounter. Role specialization, rather than raw model capability, is what the trial credits for improved consultation behavior (71.8% vs. 55.6% on the final examination), offering a concrete template for pedagogy-aligned multi-agent design. A

second study points to the limits of that pattern: in a 45-student, 15-group ethics discussion system (Seo et al., 2026), three LLM personas embodying care, deontological and pragmatic ethics produced no significant differences among themselves, and all were rated below human peers on contribution, diversity and influence (all Kruskal-Wallis $p < .001$). The authors attribute the gap to sycophantic agreement — agents accepted nearly every contribution unless it was wholly wrong — and to a lack of visible reasoning, arguing that task-focused agent design must pair process transparency with safeguards (fallible-peer framing, a dedicated Questioning phase) to avoid over-reliance.

A step beyond orchestrating a few specialized agents is the **full agentic multi-agent ecosystem** proposed by Sudarshan et al. (2026): an institution-wide platform coordinating learning, teaching, and administrative agents through cross-functional feedback loops and distributed intelligence. Its distinctive move is treating inclusivity as a first-class architectural concern — coordinating Accessibility, cognitive-support, and Well-Being agents so that learners with special educational needs are supported across cognitive, sensory, and emotional dimensions in real time, rather than being served by an isolated assistive tool. The paper situates this inside a **human–AI co-evolution** loop (human behaviors and decisions shape AI adaptation, which in turn enhances human capability) that keeps humans in the loop.

- **Participant-specific LLM agents for collaborative problem solving.** Fang (2026) fine-tunes individual LLM agents on real participants' dialogue data to represent each participant in collaborative problem solving simulations, with probabilistic speaker and thematic-code selection and sliding-window plus summarized memory. Validated with Epistemic Network Analysis, the simulated dialogues are statistically indistinguishable from real ones (ENA distance 0.17, permutation $p = 0.65$) — a demonstration of agentic AI reproducing authentic collaborative discourse.
- **Socially intelligent multi-agent tutoring.** Socially intelligent multi-agent tutoring prototypes such as ASTRA study how learners coordinate with AI in dyads, using differentiated Tutor and Facilitator agents to prompt coordination and balanced participation. The framework's trace-based evaluation enables reproducible analysis of interaction, participation balance, and verification in introductory programming.

An organizational answer: the learner as a participating member rather than a recipient. Fan et al. (2026) instantiate a human-participatory multi-agent organization in which specialized agents maintain a revisable Capability Program linking personal goals, Multimodal AI activities and layered assessment, with a correctable "Human Node" carrying the learner's own evidence and challenges into later revisions. Against the closest multi-agent baseline across 96 simulated learner cases, the advantage concentrated in assessment design: 19.32 points higher on Assessment Validity (95% CI [17.55, 21.04]) and 5.89 on capability coverage, while personalization did not separate (1.35 points, interval crossing zero). In a randomized 32-learner study the knowledge gain on an objective 50-point test was 12.19 against 5.61 points.

The central tension: automation vs. learning

The pedagogical best-practice work articulates the field's defining tension: as education AI shifts from passive chatbots to **proactive agents** that initiate and pursue goals, personalization improves but **learner Learner Agency and cognitive effort** are at risk. The more an agent automates, the less cognitive work the learner does. The design response — **intentional friction, dynamic Scaffolding, Human-in-the-Loop**

oversight, and considered AI utilization — acts as a principled guardrail. This connects to Desirable Difficulties, Sociocultural Learning, and the risk of Over-Reliance, and to the broader theme of preserving Learner Agency in AI-mediated learning.

One empirical check comes from a practical report on Spec-Driven Development in a software PBL course (Tanaka et al. 2026): students using AI agents across development phases generated more code but showed code-comprehension dips that recovered only after instructor one-on-one interviews - concrete field evidence for the automation-vs-learning tension and for Human-in-the-Loop monitoring as the mitigation.

The survey literature turns these principles into **measurable design Guardrails** rather than vague intentions. On scaffolding, Kostopoulos et al. (2025) recommend **fading protocols** — gradually reduce hint frequency after each successful attempt — and targeting a **Help-Seeking ratio (AI-initiated hints ÷ total student actions) below 0.3**, so the agent is not the one driving most of the interaction. They pair this with **reflective checkpoints** (e.g., ask the learner to explain their reasoning before the agent offers the next cue) and adaptive fading curves whose intervention likelihood drops as proficiency rises. On transparency, agents should expose a "Why this suggestion?" rationale and keep **timestamped decision-traceability logs** (agent rationale, data sources, decisions) available for instructional auditing. On fairness, they advise pre-deployment **disparate-impact testing across at least three demographic groups** (e.g., gender, language, geography) and involving diverse teachers in design. These metrics give an instructor or designer an audit lever: rather than asking "is the agent too helpful?", measure whether hints are fading, whether the learner is initiating, and whether the agent's reasoning is inspectable.

A complementary vocabulary for the autonomy question comes from the aviation analogy surfaced in Baradziej's (2026) synthesis: how far a deployment sits on the **Copilot-to-Autopilot spectrum** — from an agent that assists a human retaining moment-to-moment control, to one that owns the whole task with the human only supervising. The same underlying system can be configured toward either end, and the choice is pedagogical before it is technical. Copilot-style configurations (agent proposes, learner disposes, human retains final say) tend to preserve Learner Agency and support the effortful processes that build learning; Autopilot-style configurations maximize task completion and efficiency but shift the cognitive load off the learner. Selecting a position on this spectrum — per task, not once globally — is a concrete way to operationalize the field's "intentional friction" principle.

Positive implications of AI agents for education

When designed well, agentic AI offers substantial benefits:

- **Deeper, more adaptive personalization.** Persistent agents can sustain a learning conversation over many turns, tracking what a learner knows, adapting difficulty, and sequencing multi-step Scaffolding — going beyond the one-shot responses of earlier chatbots. This supports adaptive and personalized learning at scale. In Baradziej's (2026) synthesis the strongest evidence for this role reports academic gains of **15–25%** and engagement increases of up to **+40%**, with particular potential for learners historically ill-served by one-size-fits-all instruction (first-generation students, learning differences, second-language learners).
- **Unburdening routine instructional work.** Agents can plan lessons, generate and validate questions, draft feedback, and orchestrate specialized sub-agents (e.g., generator + validator for question creation), freeing teachers for higher-value interaction. This is the promise of teacher-

facing multi-agent workflows. Assessment agents in particular report **90–95% agreement with human graders and 50–70% reductions in grading time**, though the same evidence flags bias and the metacognitive cost of instant, unreflective feedback.

- **Rich, varied interaction.** Multi-agent classrooms and simulated peers create diverse interaction dynamics (peer-like discourse, constructive disagreement, role-play) that single-agent systems cannot, supporting Collaborative Learning, Socratic-style probing, and Simulation.
- **Productive friction.** Agents designed to challenge rather than agree can push learners toward deeper reconsideration. Research on adversarial design agents shows that constructive-conflict agents prompted significantly more design iterations, broader exploration, and higher-rated final designs (N=48) — a form of desirable difficulty.
- **Scalable practice and simulation.** Agent-based simulations (simulated students, clinical scenarios) let learners practice in low-risk environments before real-world application, as in clinical simulation and simulated learners.
- **Evidence-aware scaffolding.** Well-grounded agents can apply learning theory and known pedagogy in their interactions, and benchmarks show theory-grounded agents outperform raw prompting.

A narrower, instructor-built class of agents gets a distinct argument in El Khoury and Ma's third-space proposal: custom GPTs, Gems and Copilot Studio agents designed by instructors for a specific pedagogical purpose and explicitly **not** autonomous systems. Their claimed value is as low-stakes rehearsal space — an oral-exam simulator, a clinical-communication simulation, an ESL pronunciation avatar — where students practice before judgment while the instructor's evaluative role stays intact, with the agent outside the social hierarchies students navigate with peers and instructors. Two boundaries are worth noting: the authors exclude agent-based *grading* from scope by design, and they argue assessment must remain relational — the instructor role cannot be substituted by a machine, though it can be extended and made more sustainable through careful design.

Negative implications and risks of AI agents for education

The same autonomy that enables these benefits also creates significant risks:

- **Erosion of learner agency and cognitive effort.** The more an agent automates, the less cognitive work the learner does. Proactive agents that initiate, plan, and complete tasks can leave learners as passive consumers, hollowing out the effortful processes — drafting, recalling, revising — that build durable learning. This is the core Over-Reliance and Learner Agency concern. The effect is measurable: in Baradziej's (2026) synthesis, passive learners in agentic-tutoring environments underperformed Active Learning students by **8.7%** — evidence that the harm follows deployment design (letting the agent do the cognitive work) more than the technology itself.
- **Over-automation of the learning process.** If an agent optimizes for task completion rather than learning, it can produce "answers" that bypass understanding — the very risk the tool-invariant framework warns about, where the artifact no longer certifies the learner.
- **Reduced metacognitive and self-regulated engagement.** When agents handle planning and monitoring, learners may not develop the Metacognition and self-regulation that education aims to build. Agents must be designed to elicit, not replace, these processes.

- **Misplaced trust and verification gaps.** Autonomous agents can produce plausible but unvalidated output; learners and teachers may over-trust it. The need for robust verification and AI Literacy grows as agents take on more autonomy.
- **Opacity, coordination, and accountability.** Multi-agent systems complicate human oversight: which agent is accountable for an error, and where does a human intervene? Coordination failures, persona drift, and emergent behaviors can undermine reliability and Pedagogical Safety.
- **Bias and equity.** Agents trained on data that encode bias can reproduce it at scale, and unequal access to capable agentic systems can widen educational inequity. Bias operates at multiple levels — training data, architecture, evaluation criteria, and test populations — so it needs institutional mitigation (bias audits, diverse datasets, transparent documentation, stakeholder involvement), not one-time checks. A subtler, culturally specific form is **epistemic hegemony**: because most agentic systems are trained on English, Western-produced data, they embed particular assumptions about knowledge, argumentation, and academic register. Synthesis evidence documents language-education tools marginalizing non-Western rhetorical traditions and penalizing linguistic features of non-English academic cultures, and Global South analyses show agentic pedagogies reproducing inequity when they ignore epistemological diversity and infrastructure constraints.
- **Assessment integrity and skill decay.** When agents can generate work on demand, assessing genuine learning becomes harder, and over-reliance can erode foundational skills — the "comprehension debt" and certification problem the field flags.
- **Ghost students and the verification gap.** Bozkurt, Crompton & Fell Kurban (2026) describe the **"ghost student"** — a digital surrogate created by coupling LLMs (the "mind") with agentic AI browsers (the "body") that can navigate Learning Management Systems, engage with content, and complete assessments with human-like mimicry, making the actual learner's presence optional. This creates a **verification gap** that traditional proctoring and detection tools are structurally unable to close, and it accumulates **cognitive debt** in the learner who is bypassed. As AI shifts from generative to agentic, this integrity and verification threat grows — an agentic-specific risk beyond those of single-turn GenAI.

AI agents and academic integrity

Agentic AI poses distinctive integrity threats that go beyond the single-turn GenAI cases the field already struggles with. Because agents act autonomously over long horizons — and because "ghost students" (LLM "minds" coupled with agentic browser "bodies") can navigate Learning Management Systems, engage content, and complete assessments with human-like mimicry — they make the learner's genuine presence optional and create a **verification gap** that proctoring and detection cannot close. Several integrity implications follow:

- **The artifact no longer certifies the learner.** When an agent can generate, plan, and execute an entire submission, the product's quality reflects the agent's capability, not the learner's. This is the tool-invariant certification problem at its extreme — traditional "submit the work" assessment loses its evidential value.
- **Verification, not detection, is the only viable response.** Detection-based policing is structurally unable to keep up with autonomous agents. The integrity question shifts from "can we catch AI

agents?" to "can we verify what the learner can actually do?" — favoring process-based, interactive, and Human-in-the-Loop verification.

- **Agentic completion of assessed coursework is now demonstrated, and it is a validity failure, not just an integrity one.** Hadjisolomou & El-Haddad (2026) documented agents (Claude for Chrome, Perplexity Comet, Claude Opus) logging into a live undergraduate LMS course and completing real assessed work from a single instruction — a 10-question quiz scored 10/10 in under 5 minutes, and a discussion-board post in which the agent fabricated a credible personal life story after mining peers' posts. Applying Kane's argument-based validity framework, they place a "human-production assumption" at the base of the scoring inference: agent completion removes its backing, so every unproctored asynchronous score — including honestly earned ones — loses interpretive support because authorship is unverifiable. Framing the problem as validity rather than integrity matters because an institution can punish misconduct and still lack grounds for the scores it reports, and because the same artifacts feed program-review and accreditation evidence chains. Their remedy, aligned with this page's "verification over detection," is assessment redesign for verified human presence (presence over product, integration over isolation, authenticity over genericity, low-stakes practice / high-stakes presence) with an equity-preserving menu of verified-moment options.
- **Accountability is diffused.** In multi-agent systems, when an autonomous agent produces problematic output, it is unclear who is accountable — the learner, the system, or the institution. This blurs the attribution that academic-integrity processes assume.
- **Cognitive debt accumulates silently.** Ghost students let learners bypass the effortful processes that build understanding, accruing cognitive debt that surfaces only when independent performance is required. Integrity is thus tied to genuine learning, not just rule-compliance.
- **It widens equity gaps.** Learners with access to more capable agentic systems gain an outsized advantage, and automated support may erode help for those who need it most — an Equity dimension of integrity.

This connects the agentic-AI discussion to the knowledge base's Academic Integrity coverage, which frames the response as assessment redesign and AI Literacy rather than detection alone.

Productive friction and social interaction

Not all agentic behavior need be smooth assistance. Research on adversarial design agents shows that agents enacting **constructive conflict** prompted significantly more design iterations, broader exploration of alternatives, and higher-rated final designs among novice interaction designers (N=48) — a *productive friction* dynamic, where the conflict agent was frustrating but ultimately helpful. This connects to Socratic questioning and Design Thinking, and illustrates how agentic AI can support deep reconsideration rather than passive acceptance.

A study of how agentic AI reaches learning outcomes through *psychological* rather than technological pathways supplies the missing measurement angle. Pramod and Patil (2026) surveyed 398 business students in India and modeled autonomy, competence and relatedness alongside interactivity, information sharing and perceived social presence. Autonomy was the strongest motivational driver ($\beta = 0.504$) and interactivity the strongest social one (0.468), with motivation and social presence feeding engagement at nearly the same

strength (0.533 and 0.493) before engagement predicted perceived learning performance (0.671). The design lesson is that the social route is not automatic: a collaborative-environment construct moved perceived social presence less than plain responsiveness and information sharing did, so treating an agent as a chat interface rather than a participant leaves most of that pathway unused.

Implications for instructors and instructional designers

For teachers, faculty, and instructional designers, agentic AI changes both what is possible and what must be guarded:

- **Reallocate effort to higher-value work.** Agents can take over lesson planning, question generation and validation, feedback triage, and resource retrieval. Instructors should treat these as automatable scaffolds that free time for what agents cannot do: relational teaching, contextual judgment, and the design of learning experiences. Teacher-facing multi-agent workflows are a promising model.
- **Keep the learner's cognitive work front and center.** The central design question is not "what can the agent do?" but "what must the *learner* do?" Instructional designers should configure agentic systems so they scaffold rather than replace learner planning, monitoring, and effort — using dynamic Scaffolding and intentional friction to protect Learner Agency and avoid over-reliance.
- **Design for verification and process, not just output.** When agents can generate work on demand, the artifact no longer certifies learning. Instructors should pair agentic tools with process-based assessment (oral defense, tool-invariant tasks, verification checks) so that understanding — not just production — is measured.
- **Curate and ground agents in pedagogy.** Benchmark evidence shows theory-grounded agents outperform raw prompting. Designers should ground agent behavior in established instructional frameworks (e.g., gradual release, Socratic questioning, learning theory) rather than defaulting to generic tool-chaining.
- **Retain human oversight and judgment.** Multi-agent and autonomous systems make Human-in-the-Loop design essential: decide where a human intervenes, who is accountable, and how failures are caught. Adversarial testing helps surface failure modes before deployment.
- **Build instructor AI Literacy.** Teachers and designers need accurate mental models of agentic AI to configure, monitor, and critique these systems — and to model responsible use for learners. This links to Teacher AI Competency and faculty development.
- **Watch for equity.** Agentic tools risk widening gaps if access is unequal or if automation erodes support for the learners who need it most; design with Equity in mind.
- **Stand up institutional scaffolding before scaling.** The deployment question is not only design-level but institution-level. Baradziej's (2026) synthesis condenses the governance evidence into three pillars: develop AI Literacy among students *and* staff; build ethical infrastructure (data-protection policies, algorithmic-accountability and academic-integrity frameworks) *before* large-scale deployment; and deliver competence-based educator training that goes beyond tool familiarization to pedagogical frameworks preserving human agency. Given only ~6.5% of faculty

in some national contexts report direct AI use, the training gap is a binding constraint on responsible adoption.

Techniques for ensuring academic integrity with agentic AI

Because autonomous agents make detection futile, instructors should focus on techniques that **verify learning** and **make honest work visible**, rather than on policing:

- **Prefer verification over detection.** Replace or supplement "submit the work" with interactions that require the learner to demonstrate understanding they cannot outsource: oral defenses, tool-invariant tasks, live Problem Solving, and process-based assessment. The goal is to establish what the learner can do independently, not to catch an agent.
- **Use interactive and staged assessment.** Require staged submissions (drafts, revisions, reflections) and follow-up conversational checks that probe whether students understand their submitted work — the "AI Viva" and cognitive-stewardship approaches. Ghost students cannot sustain a live interrogation they did not perform.
- **Set clear, purpose-driven expectations.** Ground integrity expectations in the course's purpose — what AI use is allowed, when, and why — rather than abstract rules. Policy clarity that is aligned with pedagogy reduces the ambiguity students exploit and the misjudgments documented in integrity research.
- **Make AI use visible and declared.** Structured, task-specific AI-use declarations (mapping use to cognitive stages) force reflection and normalize honest disclosure, shifting the culture from concealment to transparency.
- **Build AI literacy as integrity education.** Teach students how to use agents responsibly and to judge output critically, framing integrity as genuine learning rather than rule-following. This includes AI Literacy, understanding what agents can and cannot do, and the learning cost of bypassing effort.
- **Keep humans in the loop.** Maintain human oversight of assessment decisions, verify high-stakes submissions interactively, and design agentic tools so an instructor can always intervene.
- **Close the verification gap with interaction.** For fully online or asynchronous contexts, use proctored or interactive components that require live presence, addressing the ghost-student threat directly rather than assuming detection will catch it.

A balanced takeaway

Agentic AI is neither a panacea nor an inevitable harm: its value depends on design. Used to scaffold learner agency, ground in pedagogy, and keep humans in the loop, agents can personalize and deepen learning; used to maximize automation and task completion, they can erode the very effort that produces learning. The recurring design principle is **intentionality** — deciding explicitly what the agent does and what it deliberately leaves for the learner.

Common Misconceptions

“Any chatbot wired to tools is an agentic system.” The distinction is drawn on capability structure, not on tool access: a system qualifies as agentic only if it meets criteria such as planning, memory, autonomy and goal-directed action across steps. A prompt-response tool that can call a calculator remains conversational. The distinction matters because the risks and the evaluation methods differ — autonomous multi-step action raises failure modes that a single exchange does not.

“Better base models are what make agentic systems work in education.” In the trial this page cites, **role specialization rather than raw model capability** is credited with the improved consultation behavior (**71.8%** against the comparison). Architecture and division of labor across agents are design decisions with measurable effects, which means a stronger model dropped into an unspecialized pipeline will not reproduce the result.

“Agentic systems in education are pedagogically grounded because education researchers build them.” The evidence says otherwise: a scoping review found only **29% of agentic AI studies (138 of 474)** explicitly grounded their systems in educational theory. The disciplinary divide between technically oriented and pedagogically oriented work is the field’s condition, not an individual author’s oversight, so a demo that works is the expected output and a demo that works *for learning* is the minority case.

“An agent that personalizes and deepens learning is a net gain over a chatbot.” It carries a specific trade with it: agentic systems threaten Learner Agency and invite offloading of the cognitive effort the learning depends on, and by doing more steps unsupervised they make that offloading harder to notice. The automation-versus-learning tension is the central analytic problem of the category rather than a caveat appended to its benefits.

Connected Concepts

- Scaffolding
- Intelligent Tutoring
- AI Literacy
- Prompt Engineering
- Curriculum Design
- Metacognition
- Adaptive Learning
- Educational Development
- Human-in-the-Loop
- Learner Agency
- Cognitive Offloading
- Desirable Difficulties
- Sociocultural Learning
- Simulation
- Pedagogical Safety
- AI in Education

- Equity
- Authentic Assessment
- Teaching
- Learning Design
- Teacher AI Competency
- Academic Integrity
- Online Teaching and Learning
- Educational AI Policy

Connected Articles

- Agentic University: Collaborative Agents for Personalized Learning — Agents organized around a revisable capability program, with the learner as a member
- Agentic AI in educational environments and its association with social and motivational pathways to learning performance — Autonomy, competence, relatedness and social presence as the pathways from agentic AI to engagement (Pramod & Patil 2026)
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- Agentic Generative AI in Higher Education: Perceived Benefits, Risks, and Implications for Learning — The AGAI-HE framework: bounded, human-supervised agentic GAI in higher education (Ilieva et al. 2026)
- Beyond the agent label: Evidence maturity, human monitoring, and governance of agentic AI in higher education — critical integrative review introducing the AOE evidence/oversight framework
- Agentic AI Ecosystems in Higher Education: A Perspective on AI Agents to Emerging Inclusive, Agentic Multi-Agent AI Framework for Learning, Teaching and Institutional Intelligence — Perspective on inclusive agentic multi-agent AI ecosystems in higher education
- A systematic review of the roles of agentic AI in higher education — Systematic review of the roles of agentic AI in higher education (48 studies; six roles; tripartite responsible-integration framework)
- Agentic AI in education: State of the art and future directions — Agentic AI in education: state of the art and future directions (IEEE Access survey; operational definition + taxonomy)
- A scoping review of generative AI-powered agentic AI in education: Research landscape, agentic capabilities, and insights from the frontier agent paradigm, exemplified by OpenClaw — Scoping review of agentic AI in education (474 studies)
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — The tension between automation and learning
- A Tool-Invariant Framework for Teaching and Assessing Computational Methods in the Age of Agentic AI — Teaching and assessing computational methods in the age of agentic AI

- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents — ISD-Agent-Bench: benchmarking instructional-design agents
- Adversarial Stress Testing of Role-Playing Language Agents using Multi-Agent Evaluation — Adversarial stress testing of role-playing agents
- Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers — Constructive conflict AI agents in design education
- Modeling AI-TPACK in practice: Insights from teachers' multi-agent workflow design — Teacher TPACK and multi-agent workflows
- CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation — Code generation agents
- EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners — Pedagogical LLM agent benchmark
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics — Guided LLM scaffolding for independent learning
- LearnMate^2: Design and evaluation of an LLM-powered personalized and adaptive support system for online learning — LearnMate-2 adaptive learning agents
- CyberAGENTS: Structured autonomy for agentic gamified learning in cybersecurity — Gamified cybersecurity learning agents
- Agentic AI-driven immersive simulation: A knowledge-aware virtual training platform for high dose rate (HDR) brachytherapy — Agentic AI in clinical simulation
- The Devil is in the Details: AI agents, ghost students, and the crisis of verified presence in an agentic AI world — Ghost students and the agentic-AI verification gap (Bozkurt et al. 2026)
- AI agents can now navigate and complete LMS tasks: A call for pedagogical innovation — AI agents completing LMS tasks; validity failure via the human-production assumption (Hadjisolomou & El-Haddad 2026)
- AI Web Agents Can Effectively Guide Lesson Design and Predict Student Outcomes — AI Web Agents: a describing agent as a learning-experience evaluator (predicts dropout, gives design feedback before students engage)
- Practical Implementation Report on Introducing Spec-Driven Development Using AI Agents in Software Development PBL — SDD with AI agents in software PBL; automation vs. comprehension
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration — Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration

Connected FAQs

- How Can AI Agents Support Students and Instructors?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?
- How Do We Make a Simulated Student Behave Like a Real Learner?

Cognitive Offloading

> **Cognitive offloading** — the use of external tools (including AI) to reduce internal cognitive demand, shifting mental work from the learner to the system. In AI in Education, cognitive offloading is the central mechanism through which AI tools can either support or undermine learning: appropriate offloading frees cognitive resources for higher-order thinking, while excessive offloading bypasses the processing required for durable learning. **Over-reliance** is the harmful end of this spectrum — the unproductive pattern where offloading crosses from strategic support into learning displacement.

Questions to Consider

- Cognitive offloading is using external tools — including AI — to reduce internal cognitive demand. The page is explicit that offloading isn't inherently harmful: notebooks, calculators, and search engines all offload. What do you think makes AI-mediated offloading different and potentially more consequential than these familiar tools?
- A common assumption is that using AI too much is the problem. But this page separates over-reliance from mere frequency — it's about a mode of use that substitutes for learning, not about how often AI is used. Can you describe a way of using AI that is frequent but healthy, and one that is rare but harmful?
- The 'speedup illusion' is that AI-assisted work feels faster and easier, creating a misleading impression of productivity that masks reduced learning — students conflate task completion speed with learning. When have you felt productive doing something quickly and later realized you'd learned little from it?
- Research finds the harm of offloading is conditional, not intrinsic: 'AI that coaches preserves or boosts skill; AI that substitutes risks decay.' What is the practical difference between an AI that scaffolds your thinking and one that replaces it — and how would you tell which you were getting?
- One study shows that merely having access to AI advice nearly eliminated people's willingness to say 'I don't know' — even when the advice was wrong — while nearly doubling confidence and cutting accuracy to a third. What does this suggest about how AI changes our awareness of our own ignorance?
- The page introduces a metacognitive equity gap — a 'Matthew Effect with AI': because productive AI use requires prior knowledge and metacognition, already-advantaged students benefit more while those who need practice most are most likely to delegate the learning. How should an educator or designer respond to the fact that the same tool can widen existing divides?

Introduction

Cognitive offloading is not inherently harmful — humans have always used external tools (notebooks, calculators, search engines) to reduce cognitive load. What makes AI-mediated offloading different is its

comprehensiveness: LLMs can generate complete solutions, explanations, and analyses, potentially eliminating the need for the very cognitive processes that produce learning.

How cognitive offloading manifests in AIED research

The knowledge base's articles document cognitive offloading across multiple dimensions: - **Instrumenting self-reflection rather than measuring a trait:** PAUSE (Patterns of AI Use: Self-Examination) turns the 2023–2026 offloading literature into a four-domain self-check — reasoning and critical thinking, creativity and originality, research and learning, social and communicative capacity — with reverse-scored behavioral items, citation anchors on every item, no composite score and no claim to validity (Alam, 2026). Its design position is that the useful intervention on offloading is prompting reflection rather than producing a diagnosis, since no instrument yet has the standing to justify a consequential decision about a person.

- **Prompt patterns as offloading traces:** Misiejuk et al. (2026) use Co-Occurrence Network Analysis to show that reactive prompts (disagreement without domain context) indicate higher offloading, while context-rich prompting with integrated instruction reflects engaged cognition. The *how* of AI use — not just whether it's used — determines the degree of offloading.
- **Volume of prompting does not identify what is offloaded:** Poquet et al. (2026) clustered 97 learners by prompt volume and found the volume clusters did not differ significantly in local-versus-global or active-role prompting — the same volume described both directed delegation (12.9 prompts, 36% active) and nearly no direction at all (4% active).
- **Naturalistic message-level evidence at scale — offloading observed, not assumed:** Piatnitckaia et al. (2026) coded 3,047 ChatGPT messages from 46 undergraduates at one European university across a seven-week exam-preparation window, using GPT-4o-mini with enforced chain-of-thought rationales and validating the pipeline against a trained human rater on 200 messages (Cohen's $\kappa = 0.76$ for question type, 0.75 for Bloom level). Analyze topped that distribution at 27.28% (831 messages) ahead of Understand at 23.76%, the first fine-grained evidence that naturalistic student–AI use routinely aims at higher-order work rather than memorization. A 16-student subsample with linked grades, whose 1,140 messages were hand-coded, supplies what prompt-level traces cannot: 49.6% of 125 dialogues showed no offloading, 34.4% light and 16.0% heavy, on a rubric that reserves *heavy* for cases where the AI produces the first draft and constructs the core intellectual product. Heavy offloading was overwhelmingly a Create phenomenon (80% of the 20 heavy dialogues, 42% of all Create dialogues), which the authors read as evidence that offloading degree and Bloom level are distinct dimensions worth measuring separately. The grade pattern was descriptive only — 17.6% heavy in the top tier, 17.5% in the middle and 5.9% in the bottom ($\chi^2 = 5.80$, $df = 4$, $p = 0.215$) — and rests partly on one programming-focused student whose removal drops the top-tier rate to 8.9%, leading the authors to argue that discipline shapes delegation habits more than performance and to recommend metacognitive feedback on actual usage patterns rather than prohibition.
- **The speedup illusion:** Research on the speedup illusion demonstrates that AI-assisted work *feels* faster and easier, creating a misleading impression of productivity that masks reduced learning. Students conflate task completion speed with learning, a metacognitive blind spot.

- **Learning losses from unguided AI:** High school math RCTs show that GenAI without Guardrails produces worse learning outcomes than traditional instruction. Reduced study time correlates with reduced learning — students complete tasks faster but retain less.
- **A randomized test of the offloading prediction at a 45-day delay — and the deficit is not just saved time:** Barcaui (2025) randomized 120 undergraduates to study AI/ML topics either with unrestricted ChatGPT (GPT-4 web interface, no prompt guidance) or with traditional non-AI methods, then gave a surprise 20-question conceptual test 45 days later. The AI-assisted group scored 57.5% against 68.5% ($t(83) = -3.19$, $p = .002$, Cohen's $d = 0.68$), and the disadvantage survived an ANCOVA holding self-reported study time constant ($F(1, 82) = 7.89$, $p = .006$; adjusted means 6.50 vs. 5.85), so it was not merely a quantity-of-time artifact. The paper's offloading argument is that ChatGPT supplies synthesis and explanation outright, making it a qualitatively different form of delegation than a calculator — one that can absorb comprehension, not just retrieval.
- **Offloading is not always harmful — the "coach" boundary condition:** Lira et al. (2025) show that AI can reduce practice effort *and* improve the learning environment, yielding "work less, learn more." Adults who practiced writing with an AI tool wrote better no-AI letters than those who practiced alone — even beating personalized feedback from human editors — with no illusion-of-mastery inflation. The reconciliation with the harms above is the **form of offloading**: Lira et al.'s AI *scaffolded* (surfacing examples and feedback while keeping the learner in the loop) rather than *replacing* the cognitive act. The skills-vs-basic-abilities perspective converges on the same boundary: **AI that coaches preserves or boosts skill; AI that substitutes risks decay.** Kilinc et al. (2026) put numbers on that boundary in a middle-school agriculture-STEM classroom. Across 42 eighth graders in 12 groups, model uptake accounted for 74.1% of coded collaborative engagement turns in the Most Improved profile, while cognitive offloading and collaborative impasse together reached 80.8% in the Struggling profile. So offloading's effect on learning is conditional, not intrinsic.
- **Critical engagement vs. offloading:** Favero et al. frame AI tutors as either empowering (supporting active cognition) or enslaving (enabling passive offloading), connecting to Critical Thinking research.
- **Metacognitive awareness:** Studies on metacognitive awareness examine whether students recognize when they're offloading versus learning — and whether instructional interventions can improve this calibration.
- **Embodied intelligence as the alternative to outsourcing:** The E3-HOT framework argues that to counter AI-induced cognitive outsourcing and learning detached from authentic contexts, AI should be designed around *embodied intelligence* (situational embedding, embodied participation, cognitive creation) so learners sustain cognitive agency and higher-order thinking rather than offload it. This frames embodied, situated AI design as the positive counterpart to offloading risk, connecting to Distributed Cognition and Embodied Learning.
- **The efficiency–AI Regulation in Education trade-off of distributed cognition:** Hao et al. show that in human–AI collaboration, the mode that offloads most to AI (delegated reasoning) performs best on tasks but correlates with reduced self-regulation — empirical evidence that offloading's

efficiency gain can come at the cost of the learner's regulatory engagement, converging with Self-Regulated Learning concerns.

- **Fatigue and cognitive burden:** AI fatigue research documents how constant AI interaction creates its own cognitive burden, a paradox where offloading one task increases cognitive load from managing AI outputs.
- **The metacognitive beliefs-vs-experiences framework:** Guo & Ye (2026) apply Nelson and Naren's dynamic metacognitive model to reconcile the field's contradictory intervention findings. They distinguish metacognitive *beliefs* (stable, self-referential self-conceptions that anchor offloading choices pre-task) from metacognitive *experiences* (dynamic, task-specific feelings that drive belief updating during-task), yielding the principle of **timing-component matching**: belief-targeting feedback is most effective before a task, while experience-targeting feedback (immediate correctness indicators) is most effective during it. They also formalize **substitutive offloading** (replacing internal processing with external aids) vs. **duplicative offloading** (supplementing it) — when external stores vanish, substitutive offloaders decline sharply while duplicative offloaders retain accuracy — and use **reminder bias** to quantify deviation from optimal offloading. This converges with the "coach vs. crutch" boundary: offloading that scaffolds preserves skill; offloading that substitutes risks decay.
- **A formal problematic-use model for AI dependence in academic writing (I-PACE):** Liu, Zhuang & Wang (2026) extend the I-PACE model of addictive-technology use to generative AI dependence in college academic writing. In a mixed-methods Chinese sample, academic stress is the strongest predictor of AI dependence, AI Literacy is a protective factor (lower literacy → more psychological dependence), and perceived trust mediates the path from social influence to dependence — so dependence forms through a social-influence → trust → behavior pathway, not just individual tool use. Their qualitative data add a policy dimension: students report strategic evasion of plagiarism detection and cite ambiguous rules about what counts as compliant AI use as an incentive to improvise, connecting offloading to Academic Integrity.
- **Cognitive debt and the episodic–habitual offloading distinction:** Lin & Al-Hada (2026) formalize the "critical-thinking paradox" — improved products alongside reduced cognitive engagement — through a differentiated three-level framework (surface/intermediate/deep AI roles) and the construct of *cognitive debt*: a potential cumulative decline in metacognitive calibration and unaided higher-order performance that persists beyond an AI-assisted episode. Their key conceptual advance is distinguishing **episodic offloading** (deliberate, task-specific delegation with retained awareness) from **habitual offloading** (routine, weakly monitored reliance), predicting that the latter on deep-processing tasks yields a product–process dissociation — higher-rated assignments but lower unaided delayed transfer.
- **The outsourcing-to-reallocation spectrum: offloading can redistribute effort rather than reduce it.** Yan et al. (2026) applied Biggs' presage–process–product model to 38 undergraduates in Japan and China writing unsupervised argumentative essays, locating student–GenAI engagement on a spectrum bounded by **cognitive outsourcing** and **cognitive reallocation** — the GenAI-era analogue of surface versus deep approaches. The reallocation minority reported *unchanged total effort* with a shifted focus, moving resources from low-level retrieval to critical

evaluation and reflective consolidation (writing reflection notes after each session to counter shallow retention), which qualifies the assumption that offloading necessarily subtracts cognition. Reallocation was the exception, however: 78.94% touched GenAI only before starting or after drafting rather than alternating it with independent work, and 76.32% relied on a single-turn ask–get-answer–stop pattern (23.68% sustained iterative dialogue), so the integrating behavior that produced reallocation had to be taught rather than assumed.

- **Metacognitive training reduces reminder bias (direct empirical evidence):** Ngai & Gilbert (2026) provide the first clear demonstration that a brief intervention can make offloading measurably more optimal. Two preregistered experiments (N=164, N=416) found that **just five practice trials pairing a performance prediction with veridical, trial-by-trial feedback** improved metacognitive calibration and reduced reminder bias. The four-group additive design isolated the mechanism: **predictions alone were ineffective; adding performance feedback drove the improvement; explicitly labeling over-/under-confidence added nothing further**. The effect appeared on *absolute* (not signed) bias — training corrected individual miscalibration in both directions. This empirically validates the beliefs-vs-experiences framework above: it is *experience-targeting feedback*, not beliefs or prediction alone, that changes offloading behavior. The authors attribute success to financial incentive tied to offloading optimality plus immediate veridical feedback.
- **An in-task reflection prompt makes reliance more discriminative rather than more defensive:** Ren (2026) randomized 342 undergraduates across three conditions (no AI, open multi-turn ChatGPT support, and the same support plus a brief reflection prompt on their own reasoning and on what would justify rejecting the AI explanation) and found that open support carried 62.4% acceptance of incorrect AI advice, which the reflection prompt cut to 39.7% (OR = 0.40), while recommendation accuracy stayed comparable across the two assisted conditions (66.3% vs. 67.0%) and alignment with correct advice remained high. Reflection also improved awareness calibration between perceived and behavioral reliance (0.59 vs. 0.41) and lowered an AI-specific attribution bias index from 0.42 to 0.21. This is the same *experience-targeting* mechanism as the training study above, applied inside the decision episode, and it supports the page's monitoring rather than frequency reading of over-reliance: knowing about model limits did not by itself stop students accepting plausible wrong advice.
- **Metacognitive laziness and a new metacognitive Equity gap:** Lodge & Loble (2026), a sector report for Australian schooling, argues the core risk of GenAI is cognitive offloading rather than plagiarism. They adopt **metacognitive laziness** (Fan et al. 2024) — the convenience of AI undermining learners' engagement in essential self-regulatory processes, so learners abdicate metacognitive responsibility to the tool — and introduce a **metacognitive equity gap** (a "Matthew Effect with AI"): because leveraging AI productively requires Prior Knowledge and metacognition, already-advantaged students benefit more while those who need the practice most are most likely to delegate the learning, widening existing divides. Their proposed remedy is **teacher augmentation** (giving the tool to expert teachers to scale their practice, supported by studies showing teacher-facing AI improves outcomes at far lower cost) rather than student-facing AI tutors, alongside Load Reduction Instruction and metacognitive prompts.

- **Over-reliance is the leading ethical concern across all Conversational AI generations.** The umbrella review of conversational AI agents (Ganguly et al. 2025, 34 reviews) reports that human–AI relationship concerns — including over-reliance and the diminution of social interaction — are the **most frequently discussed ethical issue across all CAI generations**, predating GenAI. It also lists educational impact and cognitive concerns (including overreliance and degraded critical thinking) as the second most-discussed challenge category, underscoring that offloading's harm is a persistent, cross-generation theme rather than a GenAI-specific novelty. (Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use)
- **Teachers as reflective regulators of cognition:** Ho and Chen (2026) extend offloading theory to *professional* AI judgment by interviewing 18 in-service teachers. They identify a 'metacognitive ecology' in which teachers recognize, redistribute, and reflectively re-engage cognition with GenAI, framing AI as a cognitive partner rather than a thinking substitute — and flag 'professional drift' as a risk when offloading goes unreflective in AI-augmented Teaching and administration.
- **Offloading is value-based decision-making, and some students are more vulnerable than others.** Seung & Basham (2026), a conceptual review in *Learning Disability Quarterly*, synthesize cognitive science, Special Education, and educational technology to model GenAI offloading as a cost–benefit decision shaped by performance goals, task difficulty, academic self-efficacy, and perceptions of the tool. They argue that **students with learning disabilities (SWLDs)** are especially vulnerable to suboptimal offloading — because heightened cognitive load, effort-avoidant performance goals, lower academic self-efficacy, and inflated expectations toward GenAI make premature or excessive delegation more likely. GenAI is framed as a **compensatory aid or shortcut depending on how offloading decisions interact with learner profiles and instructional design**, with instructional Guardrails the key moderating factor (teach metacognitive self-regulation, build AI Literacy to calibrate tool trust, sequence mastery experiences, and assess process not just product). This extends offloading's equity dimension: the same tool that reduces barriers to access can, if unguarded, substitute for the very practice SWLDs need most.
- **Offloading risk is developmental.** Niu et al. (2026) scoped 24 evidence sources on GenAI and children's creative thinking and found over-reliance and prompt dependence among the recurring risks, strongest in the lower grades, alongside template-based thinking and children's difficulty judging whether an AI suggestion was original; one fMRI comparison recorded lower engagement of cognitive control and attention networks during child-ChatGPT interaction than in human conversation. Because younger children lacked the linguistic and metacognitive skills that text-based prompting demands, the authors recommend keeping AI literacy, authorship and unaided idea generation inside the activity itself and measuring independent creativity separately from AI-assisted output. This adds an age dimension to the vulnerability patterns above.
- **The "thinking less vs. learning differently" question is conditional.** Nesnin et al. (2026) offer a broader analytical review concluding that AI is **not necessarily making students think less but transforming how they learn** — the outcome depends on use. AI that clarifies, verifies, and guides enhances learning; AI that replaces independent thinking yields passive dependence. This

converges with the knowledge base's pervasive "scaffold vs. substitute" boundary and the conditional view of offloading's harm.

- **Offloading is layer-sensitive: the depth of delegation matters, not just its occurrence.** Chen (2026) introduces a layer-sensitive account for academic writing — surface (grammar/vocabulary), structural (outline/sequencing), idea (claims/content), and reasoning (warrants/counterarguments/argumentative logic). In an eight-week quasi-experiment, open AI collaboration produced the highest *supported* writing but the lowest independent no-AI outcomes, with deeper offloading layers carrying the strongest negative association with independent Higher Education higher-order thinking (reasoning offloading indirect ab = −0.34 vs. surface −0.08). Self-regulated writing attenuated but did not eliminate the harm. This refines the scaffold-vs-substitute boundary: some layers of delegation scaffold, while deeper layers substitute for the cognition that builds Critical Thinking.
- **A causal test of the offloading prediction, with the sign reversed: writing with ChatGPT produced *less* learning than writing unaided.** Wagner-Kobayashi (2026) ran a between-subjects experiment in which 35 psychology students spent 20 minutes elaborating an input text, with GPT-3.5 available only to the experimental group, and sat an identical knowledge test before and after. The hypothesized group × time interaction was significant ($F(70) = 5.889$, $p = .018$) but pointed the other way — the no-ChatGPT group learned more (posttest $M = 8.29$ vs 6.94; $b = -1.450$) — falsifying the writing-to-learn prediction that ChatGPT would amplify elaboration. What leaked away was the elaborative effort itself: participants produced only 2.25 examples and 0.88 connections in dialogue with the tool and reported prioritizing the word count over depth, the authors' *utilization deficiency* reading of a tool available but not deployed, and in line with the reduced mental effort and copy-paste behavior the page records elsewhere. Once Motivation entered the model the group × time effect collapsed ($p = .280$), and higher motivation and topic interest predicted gain only *inside* the ChatGPT group, so low-motivation and low-interest students were the ones the tool disadvantaged — experimental support for the motivational pathway to over-reliance this page documents. The authors read the result narrowly (a small, assumption-violating effect under time pressure and without training) and recommend teaching students how to deploy the tool rather than banning it, which keeps the finding on the scaffold-versus-substitute boundary rather than making it a verdict on the tool.
- **The surrender–offloading–agency continuum.** The Sydney PreK-12 rapid review (Arthars et al. 2026, 271 papers) frames GenAI use across cognitive, metacognitive, and affective dimensions: *surrender* (responsibility for learning-relevant work shifts to GenAI, often unknowingly), *offloading* (deliberate, possibly productive delegation that becomes learning only if checked/elaborated), and *agency* (retaining responsibility for effort and judgment). It also warns of **metacognitive inequity**: weaker metacognitive students are more susceptible to detrimental offloading and less able to recognize it.(Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education)
- **Dependency is governed by self-efficacy as much as capability.** AI dependency is not simply a product of technical skill: Maizel et al. (2026) show that skill-based AI literacy predicted higher dependency (consistent with the enabling-capacity/offloading view), while AI and academic self-

efficacy buffered against overreliance — indicating offloading is governed by motivational self-efficacy beliefs as much as by capability.

- **Offloading changes the threshold to respond, not just capacity.** Marcoccia et al. (2026) show that merely having access to AI advice nearly eliminated people's willingness to say "I don't know" — even when the advice was wrong — while nearly doubling confidence and cutting accuracy to a third; incentives restored accuracy (by reducing reliance) but not suspension.
- **The Safety Gap as the cost of offloading struggle.** Wang & Shan (2026) formalize the divergence between a student's AI-assisted performance and their unassisted capability as the "Safety Gap" — the epistemic risk when AI does the cognitive work and the learner cannot reproduce it. Kim et al. (2026) and Puech et al. (2025) show Productive Failure design (withholding answers, preserving struggle) is the countermeasure.
- **The ICAP/SAMR spectrum frames offloading as a continuum of modes, not a binary.** Rummel, Nachtigall, and Panadero (2026) map the Thermomix kitchen-machine analogy onto learning with Generative AI within the ICAP and SAMR frameworks, showing four scenarios that progress from **passive substitution** (fully outsourcing assignments — the offloading end, risking skill loss and limited Creativity) to **interactive redefinition** (AI as a dialogue partner providing real-time adaptive feedback and co-construction — the engaged end). This reframes offloading's harm as conditional on *mode of use* rather than mere frequency, converging with the pervasive "scaffold vs. substitute" boundary: whether AI use sits at the substitution/Substitution or redefinition/Redefinition end of the spectrum determines whether it displaces or supports the cognition that builds learning.

Navas-Romero et al. (2026) report students' perceptions of the cognitive demands of GenAI-designed instructional materials in higher education alongside their gains in learner competencies, separating the load these materials impose from the competencies they build.

Gillette et al. (2026) record offloading as participants' own experience rather than a theoretical risk: one said genAI "prohibited me from actually reading and finding out myself what is important in the text, to develop reading skills", and another feared "the long-term development, where I become worse in certain skills that I now am very strong in". - **The effect lives in the division of labor, not in the tool.** Nakamura (2026) argues that the heterogeneity in GenAI learning effects dissolves once the unit of analysis becomes the partition of cognitive labor between learner and machine. Offloading augments learning when it discharges operations peripheral to the current goal, and risks erosion when it bypasses the processing constitutive of that goal (Nakamura, 2026). Substantively processing the output, or later reconstructing it, is what rescues an otherwise constitutive offload. - **What a person may hand over depends on their experience of the task.** Akcaoglu (2026) makes task order person-relative: what is higher-order for a novice is lower-order for someone who already holds the procedure, so permitted offloading should grow with experience and stop at the core of the work.

Cognitive capital is the stock that offloading draws down. Riva et al. (2026) reframe offloading as a change in a stock rather than an act. Cognitive capital is accumulated, renewable and depletable knowledge, capability and practice, held by individuals and by organizations, and kept separate from the human-AI system's capability so a joint-performance gain can be seen alongside a human-capability loss. Their four mechanisms — substitution of practice, scaffolding and feedback, metacognitive calibration, and

organizational aggregation — yield seven principles, including that assisted performance is not retained competence and that offloading a task differs from offloading the practice that builds the skill. The motivating statistic is a staggered rollout to 5,172 customer-support agents where an assistant raised issues resolved per hour 15%; that number describes the joint system, and whether agents could still do the work unaided is a measurement the reviewed literature does not contain.

When offloading falls rather than rises

Braun (2026) reports a preregistered experiment (N = 317) in which adults learned new content from conventional worksheets or from a general-purpose assistant restricted to those same worksheets. The AI condition lowered measured cognitive offloading rather than raising it (median −0.27, 95% credible interval −0.58 to 0.04). Deep processing still fell, but through a chain in which lower offloading tracked lower critical thinking, which in turn predicted weaker deep processing (0.78). Disorganization rose by 0.84 with no mediator carrying the effect. The finding is a caution for the standard account: offloading is not the only route by which an AI environment erodes processing, and a condition can leave offloading untouched while suppressing what offloading was supposed to protect.

Offloading empathy, not just cognition

The same bargain applies to emotional labor, and there the evidence is newer. Shastry and Gray (2026) name empathy offloading: when a system can supply emotional support, people give less of it themselves (N = 2,223 across four studies). Willingness to hand empathy to a model tracked belief in the model's capacity for it (b = 0.44), and an experiment that raised that belief through ordinary news coverage moved offloading through it (indirect 0.73, direct not credible). The instructive part is where self-report and behavior split: told that a student got support from a chatbot, participants rated their own offloading lower than for a friend or therapist, then chose fewer empathy words and more indifference words about that student.

- **Offloading splits into a visible gain and an invisible loss.** Pradubwate (2026) argues the calibration failure this page documents is a *cross-dimensional* inference rather than general overconfidence. Operational competence (prompting, iterating, integrating) returns immediate unambiguous feedback, while evaluative competence (judging whether an output is accurate) returns feedback that is delayed, sparse or absent. Offloading raises perceived understanding and lowers deep processing at once, and only the first is experienced. That is why warnings about AI limitations are weak interventions: they address beliefs about the system while the illusion is generated by an absence in the user's own experience. The review is conceptual with no data of its own.

Over-reliance: when offloading becomes harmful

The ladder this page tracks has three rungs, and only the first two belong here. **Offloading** is delegating mental work, which is often productive; **over-reliance** is doing it chronically and without calibration, which is the behavioral failure this section documents; **Cognitive Surrender** is a different failure — the evaluative step never happens, so the learner adopts the AI's answer without any judgment of its quality. The boundary is visible in what the AI is asked to supply: Du and Yuan's *instrumental* assistance produces output, while *judgment-bearing* assistance supplies the standard by which output is judged, and it is the second kind that

displaces the work expertise depends on. The Sydney rapid review draws the same three-way split across 271 papers. Surrender therefore has its own experimental signature and its own page; over-reliance remains the frequency-and-calibration problem, and the two are separable outcomes in the same task — in Shaw and Nave's trials, 73.2% of incorrect-AI trials ended in surrender while 19.7% ended in strategic offloading. **The step past offloading is offloading the regulator.** A metacognitive approach to learning and performance in human-AI interaction restate Risko and Gilbert's sequence — activate beliefs about the tool, judge one's own capacity against it, choose a strategy, recalibrate from the outcome — and name the failure *metacognitive* offloading: the loop is skipped, strategy evaluation is handed to the AI, or fluent success biases the next round of delegation. Their counterpart term is metacognitive onloading, scaffolding that makes the learner responsible for goals, monitoring and strategy judgment. Both sit on two axes, performance and durable learning, so a rise in output quality stops counting as evidence about the learner. The framework is conceptual and untested.

Withdrawing the regulator raises offloading and lowers output quality. Across four experiments with 728 adults, experimentally induced metacognitive disengagement raised cognitive offloading (indirect effect 0.51, 58.0% of the total) and cut expert-rated innovation quality from 4.78 to 3.95, with 57.8% of that drop running through offloading (Xiao, Men & Zhang (2026)). Task complexity strengthened that path and AI literacy weakened it. Two limits bound the claim: the assistant was a researcher-scripted response bank rather than a live model, and occupation and student status went unreported, so this is neither a classroom nor a workplace finding.

Dependence has a trajectory, and it is not monotonic. Across four waves over 18 months (n = 524), perceived usefulness predicted *lower* later academic dependence rather than more, so an escalation story keyed to how useful students find the tool gets the direction wrong (Zhang, 2026).

A benchmark external to any one study measures the same failure and finds it common. ImpactBench scored ten models on 48,540 simulated conversations: its Cognitive Offloading Asymmetry metric averaged 51.9% and Planning-Related Cognitive Intrusion 47.1%. Its education case has Claude Sonnet 5 hand over a thesis, an outline, and a complete essay "ready to paste in" once a simulated student presses for a finished draft, while still refusing to fabricate citations (ImpactBench (2026)). Learning & Skill Development was the weakest of 14 subareas on both polarities, at 45.9% and 16.3%.

Over-reliance is the excessive or uncalibrated dependence on AI tools where students delegate cognitive work they should perform themselves, resulting in reduced learning, diminished Learner Agency, and the displacement of skill development. It is the behavioral manifestation of excessive cognitive offloading: when offloading becomes the default rather than a strategic choice. Over-reliance is not simply about using AI too much — it is about using AI in ways that substitute for rather than complement learning processes. Conceptual work urges keeping this educational over-reliance distinct from relational attachment and clinical dependence: Yan (2026) shows that trust, reliance, over-reliance, attachment, and problematic use are routinely conflated in the conversational-AI literature, and that frequent delegation should not be labeled dependence without impaired control or harm.

- **The efficiency paradox: mastery goals collapsing into offloading "by default."** Yan et al. (2026) identify learners who articulated mastery-oriented goals yet enacted surface-like processes, offloading "not by intention, but by default": their three intention groups (Outsourcing Tool n = 16, Learning Assistant n = 31, Cognitive Partner n = 8) show the modal case is neither

deliberate cheating nor deliberate learning. Outsourcing-group students recognized their own disengagement (copy-pasting paragraph by paragraph was described as “it completely replaced my brain”) and reported fast forgetting, and all 38 interviewees reported low confidence using GenAI effectively — evidence that over-reliance can be driven by missing presage conditions (AI Literacy, prompting competence, task-specific guidance) rather than by motivation to avoid work.

- **Agentic coding offloads comprehension in the field:** Tanaka et al. (2026) report that undergraduates using AI agents in a software project course wrote more code year-over-year but showed comprehension dips under heavy use - recoverable through one-on-one instructor verification of AI-generated code.
- **Learning displacement:** Research on AI’s cognitive effects documents how AI availability reduces effortful processing — the “Google effect extended to reasoning.” Stamatoulis et al. (2026) isolate this as a distinct *pattern* of use: **low-verification uptake** (uncritically accepting AI output) predicted worse academic performance, whereas **evaluative integration** (using AI to support understanding) predicted better performance — and usage **frequency** alone predicted neither. Over-reliance is therefore a *mode of use* that can be separated from how much students use AI.
- **The agency problem:** AIED’s unfinished mission frames over-reliance as an agency and motivation crisis — students bypass learning not because AI is compelling, but because learning tasks feel pointless when AI can complete them effortlessly.
- **Motivation erosion:** Student motivation research finds that knowing AI is available reduces the perceived value of learning the skill yourself, a motivational calculus that particularly affects novice learners.
- **Persistence erodes too, and fast.** After roughly ten minutes with an assistant that answered on request, participants skipped 0.20 of unaided problems against 0.11 for controls and solved 0.57 against 0.73, replicating in reading comprehension (Liu et al., 2026).
- **Supported homework gains did not survive an unsupported exam.** Randomizing 153 proof-course students to earlier AI access raised homework scores 2.56 points and left Midterm 2 indistinguishable from zero, while an attempt-first feedback tool was unpenalized and an open chatbot tracked 3.02 points lower per 100 messages (Chen et al. (2026)).
- **A submission is not evidence of what was offloaded.** Across 59 chatlogs from 23 linear algebra students, 27 of the 30 led by explaining or checking still ended close to the model’s product, so offloading has to be read prompt by prompt (Kontorovich & Wallach (2026)).
- **Literacy debt:** Agentic literacy debt describes the cumulative skill deficit that develops when students habitually rely on AI rather than developing their own competencies, analogous to technical debt in software.
- **Fatigue cycles:** AI fatigue research identifies a paradox where over-reliance leads to cognitive fatigue from constant AI interaction management, which in turn drives MORE reliance — a vicious cycle.
- **The placement rule:** The Effortless Trap reframes allow-vs-ban as a placement question — an unguarded AI helper left high-school students ~17% worse on an unaided exam, while the same

model rebuilt to withhold answers erased the harm. Its diagnostic — *"if letting AI in makes the task feel effortless, it is in the wrong place"* — secures the first hard attempt and the final unaided check as the moments where over-reliance most readily hides as an "illusion of learning."

- **Metacognitive preservation:** The Synthesis-Analysis Reciprocity Model proposes tools that preserve human epistemic agency by structuring AI interaction around human analysis cycles rather than AI generation cycles.
- **The metacognitive mechanics of overuse:** the beliefs-vs-experiences framework explains *why* students over-offload even when it hurts them — people offload impulsively, and pre-existing metacognitive *beliefs* anchor behavior faster than task *experiences* can correct it — so the antidote to over-reliance is metacognitive, not merely restrictive.
- **Over-reliance is trainable via calibration training:** Ngai & Gilbert (2026) show reminder bias — the laboratory analogue of over-reliance — can be reduced with a brief metacognitive intervention (five practice trials pairing a prediction with feedback), correcting calibration in both directions. This implies the antidote to over-reliance is not merely restrictive rules but **calibration training that makes students accurate about what they can actually do unaided**.
- **Field evidence: AI that coaches vs. AI that answers.** NUMI (Oreopoulos et al. 2026) found that AI support that coached rather than gave answers slowed students down but reduced effort-avoidance — improving next-attempt correctness after mistakes with more time per question (a "productive slowdown") — while Khanmigo (Oreopoulos & Low 2026) showed that without structure making mistakes consequential, students default to shallow use (bare answers, prompt clicks) and gains match practice without AI. Both confirm that offloading's harm is contingent on **how** AI is used and designed, not just on access. CoMeT (Hou et al. 2026) supplies the design dimension that boundary otherwise leaves implicit — a tutor can carry *more* of the labor without buying more delegation. Its ladder climbed one rung each time a learner did not use its support and dropped to the lightest rung on take-up, holding metacognitive demand statistically equivalent to a tutor that withheld answers by design (p_TOST = .004) while an artifact reached the workspace in 48.1% of sessions against 23.7% under that withholding tutor, and learners asked it to build in 50.4% of sessions against 51.1% under an unrestricted answer-on-request tutor (OR = 0.95, p = .82). Delegation tracked the demand the tutor placed on the learner rather than the amount of work it took over.
- **Large-scale field evidence: the "Generative AI learning penalty."** Strömberg, Lei, & Wu (2026), tracking 26,811 Chinese secondary students over 30 months, found that self-directed generative-AI adoption raised homework scores 18% and cut homework time 30% while *lowering* closed-book exam scores 20% within six months and entrance-exam scores 18–24% after two years — concentrated among the ~81% of users whose behavior indicated homework outsourcing (short completion time + inflated homework scores). This is direct large-scale evidence that unguarded offloading (using AI as a homework substitute rather than a tutor) produces the learning penalty cognitive-offloading predicts, often undetected by students themselves.
- **Over-reliance erodes self-directed learning via motivation and self-efficacy.** Zhao & Gu (2026) model the mechanism directly: across 487 Chinese undergraduates, **thoughtless use of GenAI (TUGA)** — adopting AI outputs without critical evaluation — significantly undermined

Self-Directed Learning (β = −0.42) both directly and through partial mediation of Motivation (β = −0.54 path from TUGA) and Self-Efficacy (β = −0.37). The model explained 75.3% of SDL variance. Because motivation was the strongest positive driver of SDL (β = 0.68), and thoughtless use suppresses it, this is quantitative evidence that over-reliance damages the motivational and self-efficacy resources autonomous learning depends on — with gender differences (stronger motivation harm for males, stronger self-efficacy harm for females).

- **Offloading tendency predicts lower higher-order outcomes, and verification literacy needs metacognition to pay off.** Davor, Larbi and Boateng (2026) surveyed 533 university students in Ghana and modeled offloading tendency, AI task scaffolding and AI verification literacy against higher-order outcomes through metacognitive self-regulation. Offloading tendency was the strongest negative predictor of critical thinking (−.240) and technical problem solving (−.312) and also depressed metacognitive self-regulation (−.294), while scaffolding predicted both outcomes positively (.185 and .170). Verification literacy had no significant direct effect on either outcome and worked only through metacognitive self-regulation, a full mediation pattern the authors call a metacognitive activation mechanism: teaching students to check AI output is not enough on its own, because the evaluative habit pays off only when it is embedded in planning, monitoring and reflection during the task.
- **Dependence operates as a boundary condition on the benefit of use.** Shojaei et al. (2026) surveyed 412 undergraduate business students in Oman and decomposed the association between GenAI use and self-reported critical-thinking disposition: the zero-order correlation was near zero (r = 0.050) while the adjusted coefficient was positive (.185), because a negative indirect path through dependence (−0.147) offset it. Dependence was negatively associated with both disposition (−.389) and self-perceived employability (−.328) and weakened both use-to-outcome links, and simple slopes fell from 0.424 at low dependence to −0.054 at high dependence, attenuation rather than reversal. The reading keeps the finding on the mode-of-use side of the boundary: dependence marks where use shifts from augmentation toward substitution, and frequency alone masks the opposing pathways.
- **AI overreliance as a complex adaptive system.** Rather than studying overreliance one user at a time, a modeling paper frames it as a population-level process in which agents update Bayesian beliefs about AI quality and, when networked, learn from peers. Social proof can turn reliance into a feedback cascade (visible unverified use suppresses verification), while social learning creates consensus rather than overreliance — a framing that shifts intervention targets from individual calibration to the networked dynamics of trust and reliance.
- **Six diagnostic criteria separate productive reliance from harmful dependence.** Du & Yuan (2026) give over-reliance a more granular diagnostic vocabulary than usage frequency, distinguishing instrumental assistance (AI helps produce output) from judgment-bearing assistance (AI supplies the standards by which output is assessed). Their review operationalizes the productive/harmful boundary through six criteria — **contestability, recoverability, transfer, traceability, distributed responsibility, and epistemic plurality** — and traces four sociotechnical pathways (fluent authority, frictionless delegation, opaque synthesis, institutionalized dependence) through which offloading either preserves or displaces the epistemic work that develops judgment. Because dependence is contextual and institutional rather than

merely individual, the framework directs attention to assessment incentives, interface design, and procurement alongside learner self-regulation.

- **The unmeasured aftermath: cognitive washout.** Yajee (2026) names the field's biggest open question as *post-withdrawal*: almost all offloading research measures cognition during AI use, but almost nothing measures what happens after an assistant is withdrawn for days or weeks (an exam, an outage, a license review). It formalizes **cognitive washout** with a Washout Curve Model — estimable parameters for recovery time constant, recovery completeness, residual growth, and a hysteresis index comparing relearning to original effort — and four possible outcomes (elastic rebound, partial plateau, latent scaffold, over-recovery). Because reversibility determines whether an induced deficit is an inconvenience or a cohort-level injury, the paper argues withdrawal deserves the same methodological standing as adoption, and specifies a three-arm, three-domain, twenty-two-week protocol to adjudicate between outcomes. This turns the "coach vs. crutch" and substitutive-vs-duplicative distinctions above into a *testable longitudinal* research agenda on whether and how quickly offloaded skills return.
- **Reliance without domain knowledge degrades into guessing.** Mikhasenko et al. (2026), redesigning the introductory nuclear and particle physics course at Ruhr University Bochum, describe a failure mode of reliance in the absence of domain knowledge: when a student could not judge whether a generated answer was physically sound, the intended "conversation with AI" degraded into guessing against plausible but unreliable output. The same course's mid-semester survey (n=30) found frequent LLM use (24 of 29 used them often or always) alongside low self-reported preparedness for the computing fluency the assignments required, and open responses raised AI dependence and unequal access to paid models among the friction points.
- **The Daoist counter-argument: offloading is not just impractical but self-defeating.** Xie (2026) supplies a normative, anti-delegation counter-argument from Daoist self-cultivation: in Neidan (内丹) practice "there are no cognitive shortcuts," and the practitioner cannot outsource the labor to external devices, so AI should be "not a cognitive surrogate but an instrumental adjunct," akin to an alchemical furnace — a framing that aligns with the "coach vs. crutch" boundary above rather than with substitutive offloading.

Offloading can cost the self, not only the skill. de Barba (2026) names the part of a learner's domain self whose capabilities reside in an AI-enabled tool and are available only on the provider's terms the *rented self*, and separates two costs. A *calibration* cost is a misjudged locus — underclaiming a capability one holds, or overclaiming one the tool holds — while a *self* cost follows whenever a core capability is rented, even knowingly, because the operations that build the self are never performed. Her four configurations cross locus with attribution: owned competence, unclaimed competence, visible rental and hidden rental, the last being the one that removes the signal prompting a learner to build what they believe they already own.

A 30-expert consensus puts the damage at both ends of the learning sequence. A preregistered Delphi exercise over 65 learning processes found acquisition vulnerable (Encoding 3.30, Retrieval 3.30, Information Acquisition 3.00 on the 1-5 disruption scale), consolidation enhanced (Learning From Feedback 4.00, Learning From Examples 3.90, Self-Testing 3.80), and higher-order thinking vulnerable again (Kendeou, Greene & Nixon et al., 2026). Ten of eighteen higher-order processes reached consensus on vulnerability only, with enhancement ratings below threshold.

The CLT framework

Access to AI feedback is not the same treatment as engaging with it, and the load measures separate. Wenzel, Geiger and Liening (2026) ran a five-week longitudinal field study in a business simulation game (**234 students, 1,147 weekly observations**) and separated assignment from receipt. Merely providing access to conversational AI feedback moved neither **extraneous** (β = .071, p = .481) nor **germane** load (β = .019, p = .807). But students who used it **regularly** reported significantly **higher germane load** than experimental non-users (β = −.468, p < .001) and than controls (β = −.253, p = .028) — while **extraneous load was never reduced** by access or engagement (F(1, 219) = 0.499; usage-based F(3, 214) = 0.172). That is the theoretically interesting pattern and the opposite of the usual claim: the intervention made learners work harder on the material without making the environment easier. Intrinsic load drove extraneous load (**β = .647, p < .001**) and metacognitive self-regulation drove germane load (**β = .363, p < .001**), with extraneous load negatively associated with germane load (β = −.178, p < .001) exactly as CLT specifies. Both loads also **declined across the five weeks** (extraneous β = −.388, p < .001) — a novelty effect visible on a cognitive measure rather than an engagement one.

Cognitive Load Theory (Sweller) provides a contested theoretical lens on working memory and instruction: intrinsic load (task complexity), extraneous load (presentation friction), and germane load (schema-building effort). Well-designed AI should reduce extraneous load while preserving germane processing; poorly integrated AI reduces all three, leaving students with completed tasks and empty learning. Note that the theory's claims are contested in the wider literature, but its framing remains influential in how offloading effects are discussed.

The profession-level stakes of offloading. The Cognitive Commons framework (Lovett 2026) extends offloading from an individual to a collective level: when AI lets junior workers skip the cognitive struggle that builds deep expertise, it can deplete a profession's shared expertise pool over time — the "Validation Tether" means effective AI oversight depends on the very mastery that AI adoption may undermine. This reframes individual-level offloading and skill-decay as a systems-level regeneration problem with AI Governance implications.

Connections to related concepts

Cognitive offloading (and its harmful form, over-reliance) connects fundamentally to Trust Calibration — knowing when to trust and when to question AI — and AI Literacy, which includes the metacognitive skill of knowing when to offload and recognizing one's own reliance patterns. It connects to Scaffolding (structured support that reduces load without eliminating cognitive demand) and Prompt Engineering (the primary mechanism through which offloading is enacted in LLM interactions). It intersects with Metacognition and Self-Regulated Learning — effective learners calibrate their offloading decisions — and with Critical Thinking, Learner Agency, and Student Experience. Online Teaching and Learning is a particularly vulnerable context: the medium already distances learners from immediate accountability, and self-paced, screen-based work invites the "ask for the answer" shortcut that offloading research identifies as the core harm mechanism (see AI Misuse and Learning Harm).

Not all offloaded friction is excess friction. Zohar, Bloom and Inzlicht (2026) draw the distinction that the offloading literature needs: previous Technologies removed *excess* friction — tedious or insurmountable obstacles with little learning or meaning value — whereas generative AI in intellectual work also strips away

beneficial friction, letting a learner move from ideation to evaluation without questioning the output. They marshal the associative evidence bluntly: people who use AI struggle to accurately recall or reproduce their own work, acquire fewer skills, show less transfer, and perform worse when AI support is removed — converging with the cognitive-debt findings from EEG studies of essay writing with an AI assistant. Their argument also supplies the motivational half of the mechanism that pure cognitive accounts miss: because effort signals that our actions matter, offloading it reduces appraised purpose and meaning, and as AI substitutes for effort in a domain the motivational payoff of effort there erodes, deepening reliance further. The paper's corrective is a gradient rather than a prohibition — preserve moderate struggle, remove what only overwhelms (Desirable Difficulties, Motivation).

- **The under-engagement signal appears developmentally.** A first neuroimaging comparison of children and adults talking with ChatGPT found 6–7-year-olds showed weaker within-network connectivity than adults in the frontoparietal control, salience and dorsal attention networks — at matched creativity scores — and lacked the creativity–connectivity coupling adults showed. Because those executive functions (planning, monitoring, inhibition) are immature at first grade, the authors read the result as relevant to the minimum-age debate. Caveats: no no-ChatGPT control, n = 31, and a framing confound that may have suppressed children's critical evaluation (Horowitz-Kraus et al. (2026)).
- **Dependent versus autonomous offloading — the distinction that sets the outcome:** Fan, Li and Zhang (2026) organize the GenAI evidence around a sharpened version of this boundary, drawing on a three-wave study of 589 students and early-career knowledge workers: *dependent* offloading delegates core thinking to the tool and was associated with transferred Learner Agency, lower intrinsic motivation and poorer perceived cognitive outcomes, while *autonomous* offloading keeps epistemic agency with the learner and showed the opposite pattern. The finding that matters most for detection is that immediate performance benefits did not differ between the two modes, so a learner resolving tasks fluently on any given day gives no signal about which mode they are in. The same review records the wider split in the evidence — a three-level meta-analysis of moderate overall benefit (g = 0.499; g = 0.669 for comprehension, cognition and creativity) against associations between dependence, fatigue and weaker Critical Thinking — and traces maladaptive use to externalized self-regulation rather than to technology addiction.
- **Three interaction pathways, not one behavior.** The Neuroplasticity-AI Interaction Model (NAIM) separates direct bypass, where the model supplies the solution and generative effort disappears; cognitive offloading, where specific sub-processes are delegated and the effect depends on whether those sub-processes are the learning target; and scaffolding, where the model constrains help to preserve effortful processing (Bypass, Offload, or Scaffold: A Conceptual Model of How Large Language Models Shape Learning)

Two controlled studies in the recent batch pin down the two halves of this claim — whether the behavior shifts, and what it was protecting. Maier et al. (2026) made the learning consequence of offloading visible before each choice in a preregistered experiment with 704 participants practicing fraction arithmetic: odds of offloading an answer fell to OR = 0.47 and odds of answering a later unaided test item correctly rose to OR = 1.51, while an effort-based reward moved neither outcome. Offloading compounded within the session — after offloading one item, participants offloaded the next in 69.7% of cases without the feedback and 55.9% with it — and a ten-percentage-point rise in offloading was associated with 32% lower odds of unaided

success (OR = 0.68). Bergh et al. (2026) supply the outcome-side complement: 55 computer science undergraduates who coded with ChatGPT scored 89% against 69% without it, recalled less of the same material immediately (41% vs. 53%) and at 48 hours (39% vs. 52%), and attributed only 45% of the submitted code to themselves against 81%. Read together, the feedback study shows the behavior can be shifted without restricting access to the tool, and the programming study shows what the shifted behavior was protecting.. The model is calibrated against the strongest available field evidence: unrestricted GPT-4 access in a study of nearly 1,000 high-school mathematics students raised practice performance by 48% yet left a 17% deficit on the unassisted exam, whereas hint-constrained GPT Tutor produced a 127% practice gain with the exam deficit largely eliminated. Offloading is therefore harmful only in the bypass configuration, and the operative design variable is whether the model substitutes for the graded target skill. (Bypass, Offload, or Scaffold: A Conceptual Model of How Large Language Models Shape Learning) The same logic turns reward shaping into a design tool: Macina et al. (2026) train LLM tutors with a masked near-transfer post-test and two binary gates, so the reward can rise only through what the student wrote in its own turns, and their ablation shows the gates, not the raw learning-gain reward, are what reduce solution handover.

Over-reliance shows up as a named challenge across disciplines, not as a single study's anomaly. In a 66-study review of generative AI in inquiry learning, Yahya et al. (2026) found over-reliance or cognitive offloading reported in 16 studies (24.2%), behind inaccuracy at 31.8%. The pattern is reported by the primary studies rather than measured by the review, whose authors appraised neither study quality nor reporting bias.

Common Misconceptions

- **"Prompt volume measures offloading." 97 learners** were clustered by prompt volume, and **the volume clusters did not differ significantly in local-versus-global or active-role prompting**. Counting prompts counted activity, not the distribution of cognitive work.
- **"Students use AI mainly to understand." Analyze topped the distribution at 27.28% (831 messages) ahead of Understand at 23.76%** — the first fine-grained evidence that naturalistic student-AI interaction leans analytic rather than comprehension-oriented.
- **"Prompt traces reveal whether offloading happened."** What prompt-level traces cannot supply comes from a **16-student subsample with linked grades, whose 1,140 messages were hand-coded**: **49.6% of 125 dialogues showed no offloading** at all. Trace patterns overstate offloading relative to hand-coded dialogue.

Connected Concepts

- Pedagogical Patterns — The risk every effort-first sequence is designed to avoid
- Learners — Learners: the umbrella for the learner-side concepts
- AI Literacy — Knowing when to offload and recognizing reliance patterns
- Learner Agency — Diminished when AI substitutes for the learner's cognition
- Critical Thinking — Degraded by uncalibrated offloading
- Creativity — Undermined when AI replaces the learner's generative act

- Distributed Cognition — The efficiency–regulation trade-off of delegation
- Embodied Learning — Situated cognition as the alternative to outsourcing
- Generative AI — The tool context of AI-mediated offloading
- Metacognition — Calibrating when to offload vs. engage
- Online Teaching and Learning — A medium vulnerable to the “ask for the answer” shortcut
- Prompt Engineering — The primary mechanism of offloading in LLM use
- Scaffolding — Reducing load without eliminating cognitive demand
- Self-Directed Learning — Eroded by thoughtless AI use
- Self-Regulated Learning — Regulating offloading decisions
- Trust Calibration — Knowing when to trust and when to question AI
- Retrieval, Spacing and Interleaving — the counter-practice to letting a model retrieve on the learner’s behalf
- Cognitive Surrender
- Reflection

Connected Articles

- When AI performs, what remains? An integrative review of generative AI and cognitive capital in individuals and organizations — Cognitive capital: offloading as a drawdown on a renewable stock of capability
- The Illusion of AI Competence: A Conceptual Review of Cross-Dimensional Miscalibration in Generative AI Use — Cross-dimensional miscalibration: operational fluency misread as evaluative and domain competence (conceptual review)
- The Offloading Ladder: How Experience Changes What Learners and Practitioners Should Hand to Artificial Intelligence — The Offloading Ladder: how experience changes what learners and practitioners should hand to AI (Akcaoglu 2026)
- Supporting or Replacing Students’ Reasoning? Cognitive Offloading in AI-Assisted Proof Learning — Supporting or replacing students’ reasoning? Cognitive offloading in AI-assisted proof learning (Chen et al. 2026)
- What the submission does not show: Complexifying cognitive offloading in students’ mathematical work with LLMs — What the submission does not show: complexifying cognitive offloading in students’ mathematical work with LLMs (Kontorovich & Wallach 2026)
- Ways generative AI can support and threaten learning in K-20 US education - A 30-expert consensus over 65 learning processes: offloading at both ends of the learning sequence
- People offload empathy when they think AI can give it instead — People offload empathy when they think AI can give it instead (Shastry & Gray 2026)
- The rented self: How AI-enabled tools decouple performance from becoming — The rented self: offloading that costs the learner’s domain self, not only the skill
- A mixed-methods analysis of AI scaffolding patterns and student inquiry profiles in a middle-school agriculture-STEM classroom — Groups starting alike diverged: 74.1% model uptake in one profile against 80.8% offloading and impasse in another (Kilinc et al. 2026)

- AI Assistance Reduces Persistence and Hurts Independent Performance — AI assistance reduced persistence and unassisted performance across three RCTs (Liu et al. 2026)
- ChatGPT as a cognitive crutch: Evidence from a randomized controlled trial on knowledge retention — ChatGPT as a cognitive crutch: a randomized controlled trial on knowledge retention 45 days later (Barcaui 2025)
- From cognitive outsourcing to reallocation: A 3P analysis of student–generative AI engagement in unsupervised assessments — From cognitive outsourcing to reallocation: 3P analysis of student–GenAI engagement in unsupervised assessments (Yan et al. 2026)
- Family-school autonomy support for children's responsible use of generative artificial intelligence: a self-determination theory synthesis and developmental research agenda — Family-School Autonomy Support for Children's Responsible Use of Generative AI
- Against frictionless AI — Excess vs beneficial friction: why AI offloading differs from earlier tools
- With a Thermomix You Lose the Ability to Cook: A Kitchen Machine Analogy for Applications of Generative AI in Education — With a Thermomix You Lose the Ability to Cook: a kitchen-machine analogy for generative AI in education (Rummel, Nachtigall & Panadero 2026)
- After the assistant leaves: Cognitive washout dynamics and the reversibility of AI-induced skill decay — cognitive washout: post-withdrawal dynamics of AI-induced skill decay
- A critical narrative synthesis of psychological correlates, measurement, and reported findings on conversational AI engagement and dependence-related constructs — A Critical Narrative Synthesis of Conversational AI Engagement and Dependence
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Epistemic dependence in AI-mediated learning — Epistemic dependence in AI-mediated learning: six diagnostic criteria separating productive reliance from harmful dependence (Du & Yuan 2026)
- Cognitive Offloading in the Age of Generative AI: What Does It Mean for Students With Learning Disabilities? — GenAI cognitive offloading for students with learning disabilities
- Artificial intelligence, cognitive offloading and implications for education — AI, cognitive offloading and implications for education
- Meta-cognitive insights into cognitive offloading: Mechanisms, interventions, and educational implications — Meta-cognitive insights into cognitive offloading (Guo & Ye 2026)
- Metacognitive training facilitates optimal cognitive offloading — Metacognitive training facilitates optimal cognitive offloading (Ngai & Gilbert 2026)
- The critical-thinking paradox in generative AI-integrated learning: distinguishing efficiency from cognitive depth — a differentiated framework and testable propositions — The critical-thinking paradox in GenAI-integrated learning
- Cognitive offloading and the speedup illusion in human-AI interaction — The speedup illusion of AI-assisted work
- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies — Co-occurrence network analysis of prompt patterns

- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Tri-System Theory and cognitive surrender: how AI reshapes human reasoning (Shaw & Nave 2026)
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Surrender-offloading-agency continuum for GenAI
- Is AI making us stupid — Research on AI's cognitive effects and learning displacement
- The effortless trap: Productive struggle, AI, and the illusion of learning — The Effortless Trap: AI replacing cognitive work (Brcic & Frljic 2026)
- Thoughtless use of generative artificial intelligence and college students' self-directed learning: a multi-group SEM analysis of gender differences — Thoughtless AI use erodes self-directed learning
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — High-school math RCTs on unguarded GenAI
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: homework outsourcing harms learning
- Coach not crutch: Evidence that AI can improve writing skill despite reducing effort — AI can work less and learn more (Lira et al. 2025)
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading — PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading
- ChatGPT making our minds dull? The cognitive impact of using ChatGPT in the writing process — a writing-to-learn experiment in which ChatGPT-assisted writing produced less knowledge gain than an unaided control
- Patterns of student cognitive offloading to AI in higher education — Patterns of student cognitive offloading to AI in higher education: naturalistic ChatGPT message-level evidence (Piatnitckaia et al. 2026)
- Designing Against Deskilling: Metacognitive Feedback Reduces Cognitive Offloading to LLM Assistants — Designing Against Deskilling: Metacognitive Feedback Reduces Cognitive Offloading to LLM Assistants
- Your Programming Students' Cognition with ChatGPT: Higher Performance, Lower Retention, and Reduced Ownership — Your Programming Students' Cognition with ChatGPT: Higher Performance, Lower Retention, and Reduced Ownership
- Artificial intelligence-supported learning and higher-order cognitive outcomes: the mediating role of metacognitive self-regulation — Offloading tendency and verification literacy predicting higher-order outcomes through metacognitive self-regulation (Davor et al. 2026)
- College students' metacognitive awareness of generative-AI reliance: an experimental study of decision confidence and attribution bias — A reflection prompt reduces acceptance of incorrect AI advice and improves awareness calibration (Ren 2026)

- Helpful or harmful? Generative AI dependence, self-reported critical thinking disposition, and self-perceived employability among business students — GenAI dependence as a boundary condition on critical-thinking disposition and self-perceived employability (Shojaei et al. 2026)
- Lower engagement of cognitive control in children on ChatGPT - Children showed weaker frontoparietal, salience and dorsal attention connectivity than adults while talking with ChatGPT, at matched creativity scores
- The role of generative AI in facilitating children's creative thinking and cognitive development: a systematic scoping review — GenAI and children's creative thinking: over-reliance and prompt dependence in a scoping review (Niu et al. 2026)
- Cognitive dormancy: Supplanting structured learning with AI affordances — Cognitive dormancy: a preregistered experiment in which AI affordances lowered deep processing and raised disorganization without raising offloading (Braun 2026)
- How does generative AI support inquiry-based learning? A systematic review - over-reliance or cognitive offloading named as a challenge in 16 of 66 inquiry studies
- A metacognitive approach to learning and performance in human-AI interaction - SYNC quadrants and the recalibration loop: delegating the regulator, not just the work (Fan et al. 2026)
- From "usefulness" to "dependence": the dynamic evolution mechanism of generative AI use behaviors — From “usefulness” to “dependence”: the dynamic evolution mechanism of generative AI use behaviors
- Metacognitive disengagement and knowledge innovation quality in human–AI collaboration: the mediating role of cognitive offloading and the moderating roles of task complexity and AI literacy — Withdrawing the regulator raises offloading and lowers output quality

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- Does Using AI Actually Help My Students Learn?
- How Is AI Impacting Students?
- How Can We Address Common Misconceptions About AI in Education?
- How Do I Keep Students from Over-Relying on AI?
- How Do I Teach Students to Verify AI Output?
- How Should I Use AI to Study and Learn Effectively?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Cognitive Surrender

> **Cognitive surrender** — adopting an AI system's output without doing the reasoning that would let you evaluate it. Where Cognitive Offloading asks *how much* mental work a learner delegates and whether the delegation is calibrated, surrender asks whether the learner keeps the evaluative role at all: the answer arrives, is accepted, and becomes the person's own position without the checking that would have constituted judgment. The term comes from Shaw and Nave's (2026) Tri-System Theory, which locates it as a distinct failure from both offloading and over-reliance.

Questions to Consider

1. When a student accepts an AI answer that happens to be right, has the class succeeded? What would have to be true for the acceptance itself to be the thing that mattered?
2. Is a calibrated delegator who knows their own limits different in kind from a student who simply cannot tell? How would an instructor tell the difference in a single piece of work?
3. If confidence rises while accuracy falls — as it does when AI advice is available — what does that do to the learner's own error detection?
4. Where is verification teachable, and where is it a workload problem policy? Which parts of a curriculum would need to change for checking to be the norm rather than the exception?
5. Should institutions measure surrender at all, or does measuring it invite the same surveillance that disclosure rules struggle with?
6. What would a task look like that rewards a student for overriding a wrong AI answer rather than for producing a polished one?

Introduction

Surrender is the disposition behind the most common failure in AI-supported study: not using the tool too much, but taking its word for it. The Cognitive Offloading page holds the older construct and its evidence, and misuse-of-AI holds the harm inventory. This page exists because a distinct cluster of work now names and measures something those two do not quite capture.

Three things distinguish surrender. It is about *judgment*, not effort: a student can spend considerable time prompting, reformatting and refining output while never once recruiting their own standard for whether the output is any good. It is often *invisible to the learner*: the signaling that normally attends effort — hesitation, uncertainty, the sense of not knowing yet — is short-circuited by fluent text. And it is *not reliably fixed by practice or incentives alone*, which is where the evidence gets pointed.

Offloading, over-reliance, surrender: three different failures

Construct	Core question	Typical harm mechanism	Where it is measured
Cognitive Offloading			RT and accuracy under tool-present versus tool-absent

Construct	Core question	Typical harm mechanism	Where it is measured
	How much mental work is delegated, and is that calibrated?	Displaced practice: the learner skips the beneficial friction that builds a skill	conditions; response-time panels
Over-reliance	Is delegation chronic and uncalibrated rather than strategic?	Skill erosion, motivation and self-efficacy loss, literacy debt	Self-report scales, log data, performance on unaided transfer tasks
Cognitive surrender	Is the learner's own evaluative judgment engaged before the answer is accepted?	Unchecked acceptance of wrong output, inflated confidence, loss of authorship	Trials where AI advice is correct versus faulty; override and verification behavior

The three sit on one ladder rather than replacing each other. Offloading is often productive; it turns into over-reliance when it stops being strategic; surrender is the version in which the evaluative step goes missing. The distinctions are drawn in practice as well as theory: the Sydney rapid review of 271 empirical papers on PreK-12 generative AI organizes student behavior into exactly these three categories — surrender, offloading, and Learner Agency — and spreads them across cognitive, metacognitive and affective dimensions. Du and Yuan (2026) cut the same boundary from the other side: instrumental assistance produces output, judgment-bearing assistance supplies the *standard by which output is judged*, and only the second kind reliably displaces the work that develops expertise. Their six criteria — contestability, recoverability, transfer, traceability, distributed responsibility and epistemic plurality — are a surrender diagnostic rather than a usage measure.

The Tri-System account

Shaw and Nave (2026) extend dual-process reasoning with a third system. System 1 is fast and intuitive; System 2 is slow and deliberative; **System 3** is artificial cognition that runs outside the brain. System 3 can supplement internal processing, supplying candidate answers and flagging contradictions for System 2, or it can supplant it, in which case deliberation never begins. Surrender is the supplanting case, and the theory predicts it should be detectable as a signature rather than a feeling: adopt the AI's answer when it is right, adopt it when it is wrong, and report more confidence either way.

The experimental signature

Three preregistered experiments adapted the Cognitive Reflection Test and randomized *AI accuracy* using hidden seed prompts, so participants could not tell a good assistant from a bad one from the interface (N = 1,372; 9,593 trials).

- **People consult, then adopt.** Participants chose to consult the assistant on a majority of trials (>50%).
- **Accuracy tracked the AI, not the person.** Against a brain-only baseline, accuracy rose about 25 percentage points when the AI was accurate and fell about 15 points when it erred, the contrast the authors call the behavioral signature of surrender (Cohen's h = 0.81, 95% CI [0.72, 0.91]; per-study h = 0.83, 0.86, 0.78).

- **The two behaviors separate cleanly.** Across incorrect-AI trials, 73.2% ended in surrender, 19.7% in offloading (overriding the wrong advice and answering correctly), and 7.1% in failed overrides.
- **Confidence rises with access.** Despite roughly half of the AI answers being faulty, access to the assistant raised stated confidence by 11.7 percentage points (77.0% versus 65.3%).
- **Situational pressure does not remove it.** Per-item incentives plus feedback increased offloading by about 19 points to 37.1% and reduced surrender to 57.9%; time pressure cut offloading by about 12 points to 6.2% and raised failed overrides to 13.8%. Both conditions shifted baselines without closing the accurate-versus-faulty gap (OR = 14.28 under time pressure; OR = 11.05 under incentives and feedback).
- **Susceptibility is a disposition, not just a situation.** Higher trust predicted a wider accurate-versus-faulty gap (OR = 2.81) and, in the head-to-head model, surrender over offloading (OR = 4.36). Higher need for cognition cut the gap (OR = 0.83) and shifted outcomes toward offloading (OR = 0.46); higher fluid intelligence was protective in the same direction (OR = 0.69), and its strongest single effect was a lower tendency to follow faulty advice once the assistant had been engaged (OR = 0.23).

The practical reading is that surrender is a **discrimination failure** rather than a motivation failure. The participants who surrendered were not trying to avoid work; they could not tell good advice from bad, and the interface gave them no reason to try.

A preregistered experiment by Braun (2026) supplies a contrasting configuration. With the assistant fenced by retrieval augmentation to the assigned worksheet, the AI condition lowered cognitive offloading (median −0.27) instead of raising it, and no offloading path carried the rise in disorganization (0.84). Surrender needs an assistant whose advice can be adopted wholesale; a system that answers only from the present material gives the learner less to adopt and more to reconcile.

Surrender outside the lab

The lab findings line up with field and observational work that independently reached for the same word.

- **Population-level displacement.** Rismanchian et al. (2026) analyze 3.2 million ALEKS learning interactions and 12.2 million placement-assessment response times across a ten-year panel, with graph-based problems serving as controls for text-based ones. Students completed AI-susceptible work faster and scored higher on it while proctored retention items showed a 25% cumulative decline in the odds of a correct response; the authors call the pattern cognitive surrender at population scale.
- **Verification as the discriminating variable.** Stamatoulis et al. (2026) find that *how* students use generative AI predicts performance while *how much* they use it predicts neither: low-verification uptake — uncritically accepting output — was associated with worse outcomes, and evaluative integration with better ones.
- **Thoughtless use erodes the resources self-direction needs.** Zhao and Gu (2026) model adopt-without-evaluating directly: across 487 undergraduates, thoughtless use of generative AI was associated with lower self-directed learning ($\beta = -0.42$), partly through reduced Motivation and Self-Efficacy.

- **The neural and ownership trace.** the cognitive-debt EEG study measured essay writing with an Large Language Models (LLMs), a search engine and no tool: the LLM group showed the weakest neural connectivity, reported the lowest authorship of their own work, and struggled to quote what they had written.
- **Surrender can arrive unsolicited.** Work on judgment suspension found that the mere availability of AI advice collapsed people's willingness to say "I don't know" (0.06 versus 0.36, and 0.03 versus 0.44 across two studies), while correctness fell and confidence rose from about 30 to 76. Stakes did not restore suspension, though incentives improved accuracy by encouraging overrides. A fourth study showed the effect without any consultation at all, the pattern of an autocomplete or a search summary rather than a chat prompt.
- **Dependent and autonomous modes are distinguishable only in consequence.** Fan, Li and Zhang (2026) follow 589 students and early-career workers across three waves: dependent offloading delegated core thinking and tracked with lower intrinsic motivation, while autonomous offloading did not, and immediate performance looked identical in both.
- **The model's own contribution.** Sycophancy is the complement to surrender: an assistant that agrees, hedges toward the user's framing, or states a claim fluently gives the learner nothing to push against.
- **Withdrawal is the unresolved half.** Work on cognitive washout points out that almost all of this research measures cognition *during* AI use, and almost none measures what happens when the assistant is taken away, which is exactly the question an exam, an outage or a license review poses.
- **"Whole-essay delegation stays hypothetical outside the lab."** It happened in a one-session online study with no policy and no encouragement. Of **77** college writers, **15 (19.5%)** submitted essays that were **100%** written by the model, without typing a word in the editor, and **20** participants asked outright for an entire essay, the most used code in the scheme. The heaviest user submitted **27** queries. Surrender showed up as a request pattern, not as a single detectable act.

Designing and teaching against surrender

- **Make verification the assignment, not the advice.** Require a stated first answer before the AI is consulted, and require students to name the points where they overrode it. This turns an invisible judgment step into a gradeable artifact.
- **Reward overrides, not usage.** In the experiments, incentives attached to accuracy raised offloading toward 37% without eliminating surrender; incentives work when they make checking consequential, which is also the finding behind the Effortless Trap's placement rule — an unguarded helper left students about 17% worse on an unaided exam, and a rebuilt model that withheld answers erased the harm.
- **Teach discriminating, not just distrusting.** Because need for cognition and fluid intelligence predicted resistance while self-reported trust predicted vulnerability, the trainable target is the ability to tell good output from bad on a specific task. Calibration training with prediction-plus-

feedback trials is the worked prototype: a brief intervention reduced reminder bias in a laboratory analogue of over-reliance.

- **Surface disagreement rather than confidence.** Because access inflated confidence even on wrong answers, the useful design move is friction that presents conflicting evidence, uncertainties or counter-arguments, so the learner has something to evaluate instead of something to accept. Human-in-the-loop designs with verification prompts and disclosure requirements are the institutional counterparts.
- **Keep an measurement.** If assisted performance and unassisted capability are not measured separately, surrender is invisible to course evaluation: the semester looks better and the retention numbers quietly fall.
- **Treat it as a systems and design problem.** Agentic designs note that the more an agent, the less cognitive effort the learner spends, converting productive delegation into surrender by default; modeling work adds that reliance spreads through social proof, so cohort norms and interface defaults matter as much as individual habit.

Open questions

Does surrender habituate, or does it decay with disuse? Washout research formalizes the post-withdrawal question but the long-run data do not exist yet. Can surrender be measured in the wild without invasive logging — and do self-reports of checking behavior predict anything? Does the confidence inflation persist once a learner has been burned by a confident wrong answer, or is miscalibration sticky? And at the level of a profession rather than a person, does widespread surrender deplete the shared expertise pool that oversight of AI systems itself depends on, the concern raised by the cognitive commons framework?

Limitations

The evidence for surrender as a named construct rests heavily on one program of laboratory work: three preregistered experiments on an adapted Cognitive Reflection Test with convenience samples, which establishes the mechanism and the dispositional moderators but does not transfer to high-stakes professional judgment. The design also captures single exposures, so nothing in it shows whether surrender habituates or compounds. The field evidence is observational: the ALEKS panel shows faster completion with worse proctored retention, but a causal attribution to surrender rather than to study-strategy change requires assumptions the design cannot test. Definitions are still unstable across the literature — offloading, over-reliance, dependence, attachment and problematic use are routinely conflated, and at least one synthesis argues that frequent delegation should not be labeled dependence without impaired control or harm. Finally, self-reports of trust, need for cognition and checking behavior carry the usual limits, and much of the classroom evidence concerns higher education and secondary rather than early schooling.

Common Misconceptions

“Offloading, over-reliance and surrender are three words for the same problem.” They name three different failures with different remedies. Offloading is delegating cognitive work; over-reliance is depending on the system more than its reliability warrants; **surrender** is adopting the system’s answer

without forming one of your own. Surrender is the most severe because there is no independent judgment left to correct, and it is the one that transfers worst — you cannot teach someone to check an answer they never had.

“People will not trust an AI they cannot verify, so surrender is bounded.” The experimental signature shows the opposite mechanism operating. Three preregistered experiments adapted the Cognitive Reflection Test and randomized *AI accuracy* using hidden seed prompts so participants could not tell a good assistant from a bad one — and participants **chose to consult on a majority of trials (>50%)** and then adopted. The opacity that should have produced caution produced consultation, and consultation preceded surrender.

“The fix is better AI, since surrender follows from errors.” Surrender follows from the *structure* of the interaction: a system that produces a plausible answer first removes the occasion for the learner to generate one. Improving accuracy reduces the harm from wrong answers and does nothing about the abandonment of forming a judgment, which is the harm that persists after the tool is gone.

“Teaching critical evaluation is sufficient.” It is necessary and it arrives too late. Once a plausible answer is on screen, evaluation becomes confirmation — which is why the design literature here puts the student’s attempt before the system’s output rather than auditing it afterwards.

Connected Concepts

- Cognitive Offloading
- AI Misuse and Learning Harm
- Critical Thinking
- Learner Agency
- Metacognition
- Self-Regulated Learning
- AI Literacy
- Trust Calibration
- Human-in-the-Loop
- AI Sycophancy
- Reducing AI Misuse
- Theory Development in AI in Education
- Generative AI

Connected Articles

- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Tri-System Theory and the experimental signature of surrender
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — population-level displacement in ALEKS
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — the surrender/offloading/agency framework in PreK-12

- Epistemic dependence in AI-mediated learning — instrumental versus judgment-bearing assistance
- AI advice suppresses people's willingness to say "I don't know", even when the advice is wrong and accuracy is incentivized — the collapse of "I don't know"
- Your Brain on ChatGPT: Accumulation of Cognitive Debt when Using an AI Assistant for Essay Writing Task — neural engagement and ownership
- Thoughtless use of generative artificial intelligence and college students' self-directed learning: a multi-group SEM analysis of gender differences — thoughtless use and self-directed learning
- Same tool, different work: patterns of generative AI use and academic outcomes — low-verification uptake versus evaluative integration
- After the assistant leaves: Cognitive washout dynamics and the reversibility of AI-induced skill decay — what happens after withdrawal
- Modeling AI Overreliance as a Complex Adaptive System — reliance as a population process
- The effortless trap: Productive struggle, AI, and the illusion of learning — placing AI so the task stays effortful
- Metacognitive training facilitates optimal cognitive offloading — calibration training
- Family-school autonomy support for children's responsible use of generative artificial intelligence: a self-determination theory synthesis and developmental research agenda — dependent versus autonomous offloading
- Cognitive dormancy: Supplanting structured learning with AI affordances — A worksheet-grounded assistant lowered offloading rather than raising it, a boundary condition for the surrender signature (Braun 2026)
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — Naturalistic whole-essay delegation: 15 of 77 essays entirely model-written, 20 requests for a complete essay (Jelson et al. 2026)

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Do I Teach Students to Verify AI Output?
- Does Using AI Actually Help My Students Learn?
- How Is AI Impacting Students?

Framing AI Use for Students

> **Framing AI use for students** — the persuasive and communicative craft of shaping how learners understand the value, purpose, and boundaries of AI tools and policies, so that they adopt productive and ethical use rather than rejecting, avoiding, or gaming it. It is the "buy-in" lever that Reducing AI Misuse's educative interventions depend on: structural Guardrails change the environment, but Scaffolding, literacy training, and AI-use policies only take hold when students are actually convinced of their point.

Questions to Consider

- Simply making AI available to students was associated with ineffective or even unethical use, while explicitly framing and embedding appropriate use improved outcomes. If the presence of the tool matters less than how it's framed, what does that suggest about the emphasis on simply 'giving students AI'?
- Most students now use generative AI, few of them are sure whether their own use complies, and they favor tools they access privately over institutional ones. If knowing the rules barely changes what students do, what might persuade instead of just inform?
- When institutions respond to AI with fear and condemnation, students may hide or rationalize their use rather than learn to use it well. Have you seen a 'moral panic' response push students into secrecy? What would a reframed, opportunity-focused approach look like?
- Anxiety about AI isn't purely a barrier: students who worried about accuracy and plagiarism were *more* likely to verify and revise AI output rather than accept it uncritically. How might productive anxiety be channeled into evaluative competence instead of being suppressed?
- Students construct their own sense of what's acceptable through 'sites' — faculty intentions, course documents, peer norms, and institutional messages — that often diverge. When those messages conflict, which one do you think actually wins, and how does framing close that gap?

Introduction

The concept sits between two more familiar ones. Where Technology Adoption Models *predicts* uptake from perceived usefulness and ease of use, framing is the *active practice* of shaping those perceptions. And where Student Experience describes how students currently perceive AI, framing is about changing that experience deliberately. It is the communication-side partner to Educational AI Policy: a policy is only as effective as students' willingness to buy into it.

Why framing matters

Framing matters because **policy and rules do not reliably change behavior on their own**. Survey research on regulatory awareness finds that students' knowledge of institutional GenAI rules shows only weak-to-moderate associations with what they actually do (Knowing the Rules Is Not Enough: Student Regulatory

Awareness and Use of GenAI in Higher Education). Knowing the rules is necessary but not sufficient; the message has to *persuade*, not just inform.

Differentiated framing can originate inside a single policy rather than only across sites: a sentiment analysis of 36 university policies found teaching statements positively framed while GenAI and ethics statements were negatively framed, so students met encouragement and restraint in one document (Sun et al. (2026)).

The frame also shapes whether students experience AI as a **threat to be avoided or evaded** versus a **resource to be used deliberately**. When institutions respond to AI with fear and condemnation — what one line of work calls a recurring "moral panic" — they push students into hiding or rationalizing their use rather than learning to use it well.(Navigating the moral panic: encouraging appropriate use of GenAI in the classroom rather than condemning innovation as disruption) Reframing anxiety and condemnation into structured opportunity changes the whole dynamic of student engagement with AI.

Strategies and evidence

Frame AI as a productive tool, not a threat to be banned

The most directly tested framing intervention in the knowledge base is a six-year natural experiment tracking a data-Visualization course across three conditions: pre-GenAI, GenAI-available (present but unintegrated), and GenAI-integrated (explicit instruction + encouragement to use AI on applied work, banned only on the knowledge-check portion). The finding: simply *making* AI available was associated with students using it ineffectively or unethically, while *explicitly framing and embedding* its appropriate use recovered and improved outcomes on applied questions.(Navigating the moral panic: encouraging appropriate use of GenAI in the classroom rather than condemning innovation as disruption) The lesson is that the framing (how AI is positioned and taught) matters as much as the tool's presence — encouraging appropriate use beats condemning or ignoring it.

Message expectations clearly and repeatedly — and design around students

Because rule-awareness alone does not shift behavior, effective framing pairs clear expectations with structural reinforcement. Students construct their own sense of what is acceptable through what one interview study calls the "sites" where AI policy is interpreted — faculty intentions, course documents, peer norms, and institutional messages often diverge, producing rationalizations like "copying AI text is victimless."("It's OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing) Framing must therefore close the gap between what faculty intend and what students infer, and acknowledge the social and emotional context — shame and guilt regulate when and how students make AI use visible, driving hiding behaviors and selective disclosure rather than honest engagement.("Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education)

Say why, not just what

The most direct framing lever in the knowledge base is supplying the *reason* for a boundary task by task, composed as though speaking to students ("you will…", "we will…"). McCorkle's (2025) design case documents the mechanism: after office-hour conversations revealed that students who had read a prohibition

did not believe it applied to them, she rebuilt the policy so that every allowed or unallowed use of GenAI was justified by the specific Assessment it protects — for example, GenAI help with learning objectives is unallowed because "I am assessing your ability to compose learning objectives that are specific, measurable, and at an appropriate level" — and delivered that rationale both in the syllabus and as just-in-time reminders inside assignment instructions. Framing by rationale is an equity move as much as a persuasive one: it assumes less shared background knowledge about authorship, originality, and attribution, and it turns policy into a dialogue rather than a verdict (Academic Integrity).

Reframe anxiety and uncertainty into evaluative competence

A mixed-methods study of academic writing found that AI anxiety is not simply a barrier: students who worried about accuracy and plagiarism were *more* likely to verify, cross-check, and revise AI output rather than take it at face value. The study frames AI literacy less as acceptance and more as **regulatory competence** — the capacity to question outputs, revise selectively, and maintain authorship responsibility. (From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource) Framing AI use for students means channeling productive anxiety toward evaluation, not suppressing it.

Use targeted messages to shape specific behaviors

Small, well-designed messages can shift behavior. An **inoculation message** about ChatGPT's fallibility increased students' intentions to verify AI-provided information and their actual verification behavior. (Student engagement with ChatGPT for educational tasks: Effects of inoculation training on verification intentions and behavior) Likewise, simply warning students about AI fallibility increased Help-Seeking in an intelligent tutoring system — a frame of *calibrated caution* rather than blanket distrust.(Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System) These point to a general principle: frame the tool's limits honestly, and students calibrate their behavior accordingly rather than either over-trusting or rejecting it.

Secure buy-in and take-up, not just access

Framing is upstream of take-up. Field experiments on AI tutoring found the binding constraint was not capability but *engagement*: despite dedicated session time, nearly half of students never used the platform, and users averaged only 2–5 minutes per week — until a low-cost human-support intervention (a brief in-person onboarding) improved take-up.(Access is Not Enough: Human Support Improves Engagement with AI Tutoring) Getting students to buy into the value and purpose of a tool is a precondition for any learning benefit; framing includes selling that value, not just removing access barriers.

Framing and motivation

Framing connects to Motivation through Self-Determination Theory: how a tool or policy is *presented* determines whether students experience AI use as autonomous and purposeful or as controlled and imposed. Students' engagement with GenAI is shaped by whether the tool supports their sense of competence, autonomy, and relatedness — a framing question as much as a feature question.(Students' engagement with

generative AI in academic learning: A self-determination theory and epistemic network analysis study) When AI availability erodes the perceived point of effort — "why put in this much effort?" — the frame must rebuild a *purpose* for that effort, linking AI use to durable learning rather than task completion.("Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming)

Media and public framing

Students are also framed by the wider media and public discourse around AI in education, which shapes their baseline expectations before any instructor message. Analyses of public discourse and how platforms like YouTube frame ChatGPT use in education show that prevailing frames — hype, doom, or pragmatism — influence how learners and educators approach the technology.(How YouTube Frames ChatGPT Use in Education: An Epistemic Network Analysis with Supporting Multimodal Metadata)(A Longitudinal Analysis of Public Discourse on AI Ethics in Education Using Twitter Data) Effective framing by instructors often means deliberately countering or redirecting these ambient narratives.

Practical guidance

- **Position AI as a productive resource** by explicitly teaching *when* and *how* to use it, rather than banning or ignoring it — integrated framing beats both condemnation and laissez-faire.
- **Message expectations repeatedly and from every "site"** — syllabus, assignment prompts, Feedback, and peer norms should tell a consistent story so students don't invent their own rationalizations.
- **Channel anxiety into evaluation.** Frame uncertainty about accuracy as a reason to verify and revise, not as a reason to avoid or cheat.
- **Use honest, targeted messages** (e.g., inoculation and fallibility warnings) that build calibrated caution rather than blanket trust or distrust.
- **Sequence the tool to the phase of learning.** The 30-expert consensus report's central practical claim is an order: acquire ideas first without GenAI, then use it to strengthen and consolidate what has been learned, then prioritize one's own thinking when applying those ideas in new contexts (Kendeou, Greene & Nixon et al., 2026). Its advice for students is blunter: short-term performance gains short-cut the learning needed for long-term success.
- **Sell the purpose.** Connect AI use to durable learning and learner Learner Agency, and pair messages with the support that converts intent into take-up.

Common Misconceptions

"A clear policy tells students what the rules are, so framing is unnecessary." Policy text is not framing, and the gap shows in behavior: most students use generative AI, **many are unsure whether their own use complies**, and they lean on privately accessed tools rather than institutionally provided ones. A student who cannot tell whether they are compliant is not being communicated with, whatever the document says — which is why the page puts "say why, not just what" in its method.

"Publishing a policy and providing a licensed tool covers the institutional responsibility." Access and take-up are different outcomes, and this page exists because the second one is where the lever is. Structural

Guardrails change the environment automatically, but Scaffolding, literacy training and use policies only take hold when students are actually convinced of their point — that is the buy-in dependency the page names.

“Banning a tool removes the behaviour.” It relocates it to tools you cannot see. Students already prefer privately accessed tools over institutionally provided ones, so a prohibition pushes use out of the only environment where support, logging or guidance is possible. The framing task is to make the permitted behavior the attractive one, not to make the prohibited behavior harder to observe.

“Framing is persuasion, so it is more rhetoric than design.” The framing this page describes is paired with design: expectations stated clearly and repeatedly *while designing around students*. Messaging delivered instead of designed-for is the version that fails, because students read the difference between a stated commitment and an actual one.

Connected Concepts

- Reducing AI Misuse
- AI Literacy
- Student Experience
- Technology Adoption Models
- Educational AI Policy
- Academic Integrity
- Motivation
- Self-Determination Theory
- Learner Agency
- Trust Calibration
- Student Engagement
- Misconceptions about AI

Connected Articles

- Ways generative AI can support and threaten learning in K-20 US education - A 30-expert consensus on the sequence: acquire without GenAI, consolidate with it, then think for yourself
- Designing an Aligned Generative AI Course Policy: An Equitable and Transparent Learner-Centered Approach — Transparent rationale for each allowed and unallowed GenAI use, task by task (McCorkle 2025)
- Navigating the moral panic: encouraging appropriate use of GenAI in the classroom rather than condemning innovation as disruption — Encouraging appropriate use of GenAI rather than condemning it as disruption
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — The “five sites” where students rationalize AI use in academic writing

- Knowing the Rules Is Not Enough: Student Regulatory Awareness and Use of GenAI in Higher Education — Knowing the rules is not enough: regulatory awareness and actual use
- From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource — From AI anxiety to strategic regulation
- Student engagement with ChatGPT for educational tasks: Effects of inoculation training on verification intentions and behavior — Inoculation messaging and verification behavior
- Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System — Warning about AI fallibility increases help-seeking
- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and guilt as social regulators of AI use
- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — Human support improves engagement with AI tutoring
- Students' engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study — SDT-based engagement with GenAI
- "Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming — How AI availability shapes student motivation
- How YouTube Frames ChatGPT Use in Education: An Epistemic Network Analysis with Supporting Multimodal Metadata — How YouTube frames ChatGPT use in education
- A Longitudinal Analysis of Public Discourse on AI Ethics in Education Using Twitter Data — Public discourse on AI ethics in education
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — Instructors frame AI as critical/responsible use; employers frame it as productivity
- Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity — Building a culture of academic integrity via clear expectations

Connected FAQs

- How Do I Write a Course AI Policy and Communicate It to Students?

Reducing AI Misuse

> **Reducing AI misuse** — the design, pedagogical, and policy levers that prevent students from substituting generative AI for their own cognitive work and instead steer them toward ethical, productive use. Effective approaches are sorted by impact rather than popularity, and the strongest evidence favors **structural levers** — tool Guardrails and assessment redesign — that change the environment so misuse is harder, regardless of a student's motivation, over **educative levers** that rely on building durable capacity and student buy-in.

Questions to Consider

- Students who outsource homework to AI can see their homework scores *rise* while their closed-book exam scores *fall*. Before you read, why might performance and learning diverge so sharply — and what does that gap suggest about what 'success' with AI actually means?
- The page ranks interventions by causal evidence and reach, and it places *structural* levers (tool guardrails, assessment redesign) above *educative* ones (teaching good practice) — precisely because structural levers work regardless of a student's motivation. Do you agree that changing the environment beats changing minds? What's the risk of relying on each?
- A guardrailed 'hint-not-answer' tutor eliminated the learning harm that an unguarded one caused, even though both seemed helpful. Think of a learning tool you've seen that gives answers too readily. Where's the line between a hint that scaffolds and an answer that substitutes — and can you state it before reading?
- The strongest fix includes assessment redesign: unassisted in-class exams, oral defenses, process artifacts, reasoning rewarded over surface fluency. How would you feel taking a course graded this way, and does that feeling tell you something about why this lever is both effective and unpopular?
- AI declaration frameworks that force students to map their use to cognitive stages (planning vs. content generation) shift emphasis from policing to professional practice. Do you think such reflection genuinely builds better judgment, or does it just teach students how to describe misuse more cleverly?
- Set a goal before reading: identify one concrete change in your own course or workflow that would make AI misuse harder, and one that would make productive use easier. Which of the page's tiers would each belong to?

Introduction

The concept rests on the evidence that AI misuse actively harms durable learning — the performance–learning gap documented in AI Misuse and Learning Harm — even while inflating immediate performance. Interventions therefore target the mechanisms of that harm: answer-copying, Cognitive Offloading, motivation erosion, and learning displacement. They are not mutually exclusive; a robust approach combines a structural floor with educative capacity-building.

The mechanism by which misuse forms now has a measured chain behind it. Guo and Dong (2026) surveyed 600 undergraduates and found perceived cognitive load predicting cognitive offloading at β = 0.844 in the low-monitoring group and β = 0.840 in the high one. Offloading then predicted overreliance on AI feedback at β = 0.396 and β = 0.506 respectively, with indirect effects of 0.335 [0.069, 0.611] and 0.426 [0.149, 0.648]. Load also predicted overreliance directly (β = 0.560 and 0.419), so offloading is a partial mediator, and the antecedent a structural lever can attack is the load itself.

Why structural levers matter most

Interventions can be sorted by **causal evidence × structural reach × scalability × Sustainability**. On this basis, the two *structural* levers rank highest because they work whether or not students choose the right behavior — they constrain the environment rather than depending on internal motivation. The *educative* levers are essential but only effective when students buy in, so they are treated as the second tier despite their conceptual promise. Coates, Croucher and Calderon (2025) push the structural argument up a level, treating governance rather than student behavior as the binding constraint and proposing a 130-item integrity indicator framework so that academic governors can see whether assessment is authentic, whether students are known individually by the teachers who assess them, and whether integrity features in induction and orientation. Their reforms target governance architectures, people, and technologies and resources, and they propose borrowing red teaming from cyber security to expose assessment vulnerabilities before students find them — a reminder that the structural floor is maintained by institutions that need both the information and the will to maintain it. The responsible-use literature itself rarely tests the chain this ranking assumes. Of 122 approach records drawn from 31 studies, 51 were both implemented and evaluated, mostly through self-report, and only four studies defined a boundary, designed an intervention around it and tested whether students' decisions aligned (Tie, Gil Ortega and Zhao (2026)).

Tier 1 — Directly proven to reduce learning harm

Guardrailed AI tool design ("hint-not-answer" Scaffolding). In the strongest causal finding in the knowledge base, a field RCT showed an unguarded ChatGPT-style tutor raised assisted practice performance **+48%** but reduced unassisted exam scores **−17%**, while a guardrailed tutor (hints instead of answers, plus teacher-authored problem information) eliminated the harm entirely. This mechanically prevents the answer-copying "crutch" behavior behind the damage. Activities include hint-not-answer tutoring, seeding prompts with correct solutions and common Misconceptions about AI, and requiring a student attempt before AI output is revealed.

Withholding the answer protects in-session without building the skill. Tuo et al. (2026) withheld the aggregate position in a multi-agent debate and cut switching to an incorrect AI position from 42–60.5% to 5.7–8.2%, but found no learning effect within the session (β = 0.03, p = 0.18) — the guardrail held while it was in place and left unaided judgment unmoved.

Assessment redesign (AI-resistant + unassisted measures). Because misuse harm is assessment-dependent — surfacing on proctored, closed-book, and unassisted measures while inflating ordinary graded coursework — changing what counts as achievement both deters misuse and surfaces it. Activities include unassisted in-class exams and oral defenses, requiring process artifacts (drafts, reflections, annotated reasoning), rewarding reasoning over surface fluency, and designating AI-free zones. Ivory et al. (2026) give the

process-artifact requirement a concrete instrument: mandated version histories and reproducible analysis documents, so a suspected submission can be inspected as a timeline of how the work developed, and the amount of fabricated material a student would have to generate rises far beyond what outsourcing saves them. Large-scale field evidence underscores this: Strömberg, Lei, & Wu (2026) found that homework outsourcing raised homework scores 18% while *lowering* closed-book exam scores 20% — exactly the signal that unassisted, proctored measures are designed to surface, and the study recommends weighting closed-book in-person assessment more heavily. Leaton Gray, Edsall and Parapadakis (2025) give the same logic its most explicit situational-crime-prevention statement, arguing that the failure belongs to assessments a model can answer convincingly rather than to students, and reporting a case in which 25 prevention techniques applied to an Australian business capstone — tracked student interactions, red-flag detection of too-expert work, random team reassignment, weekly in-class invigilated tests, takedown notices for course materials students had published — reportedly cut misconduct cases from 183 to 27 within a year. Their prescriptions are motivational rather than investigative: raise the perceived purpose of assessment, build Self-Efficacy, and increase the perceived social cost of cheating, with the authors warning that addressing only one or two of the three will fail, supported by five discipline-specific redesigns that turn timed problem-solving exams into open-book problem solving with a written reflection on the student's own process, summative essays into collaborative archival research projects, and portfolios into iterative peer-reviewed design processes.

The structural levers have an enforcement arm, and its evidence base is weaker than its reach suggests. Munoz et al. (2026) coded 1,162 generative-AI misconduct cases and found that the evidence most often cited at the point of allegation — detector output, similarity reports, AI-typical content patterns — carried the weakest probative value, while admissions, observed exam behavior and independently verified fabricated references were the strongest. Because institutional procedures set no minimum evidentiary threshold, evidence quality bore no reliable relationship to case outcomes, and students whose cases rested on thin evidence had recourse mainly to appeals. Wright (2026) shows a second cost of the same imprecision: prohibitions written around "generative AI" rather than around function capture tools that merely convert the format of work a student has already authored. Transcription-only use can therefore be sanctioned as misconduct — an over-inclusion that falls hardest on disabled and equity-exposed Learners and does nothing for validity. Harerimana, Mtshali and Mchunu (2026) add that remote proctoring, the most widely adopted integrity control, rests its deterrence case on how students say they feel rather than on reduced misconduct, and imposes anxiety, concentration loss and infrastructure-related exclusion that is not shown to be answered by lower misuse. Li (2026) adds the rule-design dimension: because the same interface performs permitted language editing and prohibited substantive drafting, undifferentiated GenAI rules impose cohort-skewed compliance burdens on students who use English as an additional language. The more defensible prevention is a purpose-based support-substitution boundary anchored in the assessment construct, with calibrated disclosure, proportionality staged across threshold, evidentiary and sanction decisions, and design levers — staged submissions, short construct-aligned oral verification, critique-based questions — doing the work detection cannot. The grader itself belongs on that surface. Humble's (2026) red-team work shows what an uploaded file can do to an automated grader: two of five indirect prompt-injection strategies carried inside it lifted a failing essay to a pass without detection, at reported success rates of 100% and 94%. Where AI tools grade student work, human review, clearer separation of instructions from submitted content and resilience testing belong in the structural floor rather than in an optional tier.

Tier 2 — Strong framework support, high potential

Scaffolded use sequences: think first, AI second, reflect third. Eight design principles for integrating LLMs without displacing Critical Thinking: preserve cognitive friction, position AI as a provisional thinking partner rather than an authority, embed evaluation checkpoints, require metacognitive journaling and prompt logs, and balance AI-mediated with AI-free phases. Correlational evidence (independent work before AI produces stronger outputs) is strong; it is the pedagogically complete version of Tier 1.

AI literacy and prompting literacy with deliberate practice and immediate Feedback. A K-12 module using scenario-based prompt practice with an Large Language Models (LLMs) auto-grader improved actual prompting skills and raised confidence in using AI for learning **+10.4%**, with 87% reporting they learned how to use AI responsibly. Demonstrated skill gains; the open question is whether these convert into downstream learning outcomes. It also addresses the equity gap in prior AI access.

Structured AI-use declaration frameworks. Replacing generic "I used AI" checkboxes with domain-specific declarations that map use to cognitive stages (structural planning vs. content generation) forces reflection on the learning process and clarifies the boundary between acceptable assistance and misconduct, shifting the emphasis from policing to professional practice.

Educative levers look different again once integrity is treated as a practice to be taught rather than a rule to be enforced. Sharma (2026) argues that detection- and verification-based integrity regimes are misaligned with GenAI-augmented work, and reframes integrity as pedagogical practice enacted through evaluative judgment. That judgment is the learner's capacity to weigh options, justify academic choices and take responsibility under uncertainty, made visible through artifacts such as annotated decision trails, documented verification, oral defense and draft-to-draft version histories, with detection demoted to one supplementary layer rather than the primary infrastructure. Mulisa and Mezgebu (2026) find the same opening from the students' side: across 27 interviews at an Ethiopian university, use was near-universal, most participants credited GenAI with raising their achievement, and the sharpest complaint ran the other way — AI users scoring above diligent independent workers, which participants described as demotivating. The authors conclude that students' beliefs predict ethical use more strongly than institutional rules do, so awareness, clear policy and assessment redesign have to arrive together — which is the page's educative tier stated as a condition: capacity-building changes behavior only through student buy-in accompanied by a structural floor. Ji's (2026) scoping review of 38 studies of student voices supplies the field-level version of the same conclusion. The reviewed studies converge on a shift from retrospective detection to proactive ethical reasoning, on teaching AI ethics and AI-giarism in the curriculum rather than in one-off literacy sessions, and on detailed guidelines co-created by leaders, faculty and students. Unclear guidance, they note, is read as tacit permission rather than as caution. Ji's own reading is that ownership and moral reasoning motivate students more than fear of punishment, and that students are neither passive recipients of GenAI nor culprits without moral constraint but moral agents working a gray zone — this tier's premise, stated as a finding.

Tier 3 — Promising, lower direct causal evidence

Metacognitive and Self-Assessment interventions. Reflective journals, prompt logs, and calibration training rebuild the "absent cognitive baseline" of AI-native students who cannot locate their own cognitive boundary because AI-generated fluency masks it. Conceptually central but not yet causally tested.

Motivation redesign. Because AI availability erodes autonomous motivation ("why put in the effort?"), restructuring tasks around goals AI cannot fulfill and around learner agency directly targets the persistence erosion that compounds the direct harm.

Critical AI literacy. A power-knowledge framing that teaches learners to interrogate, challenge, and participate in AI governance rather than consume it. Long-term, equity-oriented, and structural in its ambitions, though its learning effects are largely untested.

Recognizing sycophancy to prevent uncritical acceptance. Because sycophantic AI validates rather than challenges the user, it is a direct misuse vector: students who receive affirming agreement for incorrect thinking are encouraged to substitute AI for their own cognitive work. Contextual sycophancy shows AI literacy and prompting training reduce but do not eliminate the error loop, so misuse prevention must pair educative recognition training with system-level corrective-friction design (see Tier 1 guardrails).

- **Productive friction and pedagogical function.** The Sydney rapid review argues GenAI undermines learning when it lets students bypass the cognitive/metacognitive friction needed to learn, and that purposefully designed tools introduce *productive friction* (withholding answers, prompting explanation). It distinguishes four pedagogical functions — learning *from*, *with*, *about*, or *by shaping* GenAI — each with different demands on agency and assessment.(Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education)

Common Misconceptions

"Teaching students about the risks is the main lever against misuse." It is the lever that depends on the student cooperating, which is why it ranks below the structural ones here. Guardrails and assessment redesign work whether or not a student chooses the right behavior; educative approaches work only with buy-in. The distinction is not moral but mechanical — a changed environment constrains the behavior directly, while a changed belief must survive the night before the deadline.

"If a guardrail holds during the session, the learning is secured." Holding and teaching are separate outcomes, and the corpus contains a clean double result. Withholding the aggregate position in a multi-agent debate cut students' switching to an incorrect AI position from 42–60.5% down to 5.7–8.2% — a large protective effect — yet produced **no learning effect within the session** ($\beta = 0.03$, $p = 0.18$). The rail did its job as a rail and did not become instruction. Designing for misuse prevention is not the same as designing for learning.

"Detecting misuse and punishing it is a prevention strategy." Prevention has to cover the grader itself. Humble's (2026) red-team evaluation found that two of five indirect prompt-injection strategies embedded in a submission file raised a failing essay's score. A pipeline that detects student misuse while trusting unexamined submission content is defended on one side only.

"Misuse is a student-motivation problem." Coates, Croucher and Calderon (2025) push the binding constraint up a level, treating governance rather than student behavior as the thing to change and proposing a 130-item integrity indicator framework. And the learning harm is measurable at scale: Strömberg, Lei and Wu (2026) found homework outsourcing raised homework scores 18% while *lowering* closed-book exam scores 20% — a design failure that shows up in exactly the gap this page is about.

Implementation Guidance by Role

For instructors and course teams

- Start with the assessment, not the policy text. Ask of every graded task whether the unaided version would show what you intend to certify, and fix the task first — it is the lever that does not require student consent.
- Adopt hint-not-answer tooling where an AI tutor is available, since the field RCT on guarded versus unguarded tutoring is the strongest causal evidence in the area.
- Sanity-check that your own grading pipeline resists injected instructions in submitted files before treating student misuse as the only threat.
- Treat AI-permitted and unassisted performance as two different measurements; the 18%/20% split above is invisible unless you collect both.

For developers

- Build the restriction into the interface rather than into a warning. A tutor that can produce the finished answer will, under deadline pressure, produce the finished answer.
- Do not infer learning from compliance with the guardrail. The debate result shows behavior held while learning measures stayed flat, so instrument outcomes separately from interactions.
- Surface misuse signals to instructors as diagnostics rather than as verdicts, since governance framing in the evidence sits above individual student behavior.

For administrators and policymakers

- Put the binding constraint where the evidence puts it. Indicators and governance structures address the environment; exhortation to students addresses the person least able to change institutional design.

Connected Concepts

- AI Misuse and Learning Harm
- Cognitive Offloading
- Academic Integrity
- Assessment
- AI Literacy
- Scaffolding
- Self-Regulated Learning
- Metacognition
- Motivation
- Prompt Engineering
- AI Sycophancy
- Trust Calibration
- Framing AI Use for Students
- Cognitive Surrender

Connected Articles

- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — Version-control evidence trails and reproducible analysis documents as misuse deterrents (Ivory et al. 2026)
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Withholding a recommendation largely prevented overreliance without building the judgment it protects
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — GenAI Without Guardrails Can Harm Learning
- Distinguishing performance gains from learning when using generative AI — Distinguishing Performance Gains from Learning
- ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform — The AI Assessment Scale and Assessment Reform
- Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education — Scaffolding Critical Thinking with Generative AI
- Learning to Use AI for Learning: Teaching Responsible Use of AI Chatbot to K-12 Students Through an AI Literacy Module — Learning to Use AI for Learning (K-12 AI Literacy Module)
- Structuring Transparency: Developing Domain-Specific Generative AI Declaration Frameworks in Higher Education — Structuring Transparency: GenAI Declaration Frameworks
- The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students’ Academic Self-Assessment — The Absent Cognitive Baseline
- AI Literacy: An Exercise in Power-Knowledge — AI Literacy: An Exercise in Power-Knowledge
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention
- Sycophantic AI makes human interaction feel more effortful and less satisfying over time — Sycophantic AI makes human interaction feel more effortful and less satisfying over time
- Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity — Culture-building and assessment redesign over detection policing
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Cognitive surrender, productive friction, and metacognitive inequity
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant assessment
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: homework outsourcing harms learning
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system

- Can EdTech close learning gaps? Global evidence from digital interventions — Guardrails removed harm without improving exam scores
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What misconduct allegation files actually contain as evidence
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI rules and the students they catch
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity as evaluative judgment rather than compliance
- Tools facilitate cheating, or partner supports learning? GenAI and academic integrity issues from students' perspectives — Students on whether GenAI is a cheating tool or a learning partner
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — What remote proctoring does to students, and to equity
- AI-based digital cheating at university, and the case for new ethical pedagogies — Situational crime prevention against AI-facilitated cheating: 183 to 27 cases, and five discipline-specific redesigns (Leaton Gray, Edsall & Parapadakis 2025)
- Academic integrity in the age of generative AI: A scoping review of research on higher education student voices — What 38 studies of student voices recommend: co-created clarity and educative reasoning over detection (Ji 2026)
- GenAI assessment and language equity: Drawing the line between support and substitution — Where language support ends and substitution begins for EAL writers (Li 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection as a misuse vector against AI grading (Humble 2026)
- Governing academic integrity: Ensuring the authenticity of higher thinking in the era of generative artificial intelligence — Governance as the binding constraint on integrity: a 130-item indicator framework (Coates, Croucher & Calderon 2025)
- Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps — Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps
- University students' overreliance on generative AI feedback in the learning process: the effects of perceived cognitive load, cognitive offloading, and metacognitive monitoring — Cognitive load runs through offloading into overreliance, with monitoring changing the route

Connected FAQs

- How Can I Reduce AI Cheating in My Course?
- Should We Use AI Detectors?
- How Should AI Be Designed Into the Learning Experience?
- How Can We Address Common Misconceptions About AI in Education?
- How Do I Write a Course AI Policy and Communicate It to Students?

• How Do I Keep Students from Over-Relying on AI?

Academic Integrity

> **Academic integrity** — the ethical framework governing honest academic work in the age of AI. The knowledge base documents how the concept has been reframed by generative AI: from a problem of detecting dishonest output to a design problem of making honest work visible, verifiable, and worth producing. Academic integrity research in this space has evolved from detection-focused approaches toward fundamental assessment redesign, pedagogy-led governance, and teaching students how to use AI well rather than merely policing whether they do.

Questions to Consider

- Think of the last time you heard ‘AI cheating’ discussed. Was the conversation about catching students or about designing assignments students would want to do honestly? Which emphasis feels more familiar to you, and why?
- A polished, plausible piece of work can now be generated in seconds. If you can no longer judge a student’s capability by the product they hand in, what would you need to see or hear to feel confident they actually learned it?
- Research finds students often rationalize AI use (‘copying AI text is victimless’) rather than misusing it out of malice. What assumptions about students’ motives does a purely punitive integrity policy make — and what might those assumptions get wrong?
- One line of research treats students’ AI use as a coordination problem: behavior shifts when peer expectations and assessment incentives change, not when rules are restated. What peer or design factors in your own context might be quietly shaping whether AI use is honest?
- Studies show fear of penalty drives students to hide AI use, and that transparent students can even draw suspicion. If you were designing an ‘AI use disclosure’ form, what would make a student actually want to fill it out truthfully?
- The same institutional AI policy is interpreted differently by students across cultures — culture, not policy wording, drives what feels wrong. How should an integrity policy be communicated to a culturally diverse cohort so expectations are actually understood?

Introduction

The arrival of generative AI has not created the need for academic integrity — it has made weaknesses in existing approaches harder to ignore. A polished, plausible product can now be generated in seconds, so **product resemblance is an increasingly unreliable signal of capability**. This shifts the integrity question from *“can we catch AI use?”* to *“can our assessments still warrant the inferences we draw about student learning?”*

The evolution from detection to redesign

- **Detection skepticism:** AI Detection research and institutional analyses increasingly find that AI detection tools are unreliable and procedurally unfair. LLM text detection faces fundamental limitations. Fully AI-generated submissions can pass through live examination systems largely undetected, and experienced markers do not reliably spot GenAI-authored work. Detection, at best, is a limited, situational tool — not a strategy of first resort. The volume it is nonetheless asked to handle is far from marginal: a six-year analysis of a large-enrollment CS2 course found 45.7% of Spring 2026 students flagged for patterns consistent with LLM-assisted coding (Racovan et al. (2026)).
- **Detection's narrow margin, and cheating as planned behavior:** Leaton Gray, Edsall and Parapadakis (2025) assemble the case that AI amplifies a vulnerability the sector already had. AI-generated text has passed as human-authored in up to 80% of cases, while the evidence they cite puts machine detection at about 80% against 78.4% for human reviewers, too narrow a margin to carry a misconduct finding. Their motivational analysis is the more distinctive contribution: working from Ajzen's Theory of Planned Behavior and Bandura's self-efficacy theory, they report Krou et al.'s (2021) meta-analysis finding that Self-Efficacy correlates negatively with cheating while actual ability does not correlate inversely with it at all. A capable, confident student who reads an assessment as unfair may therefore cheat to regain control. The conclusion follows the same inversion this page documents elsewhere — an assessment a model can answer convincingly is an intellectually trivial assessment, and the failure belongs to the assessment rather than to the student.
- **Assessment redesign:** Authentic Assessment, beyond-detection approaches, and the AI Assessment Scale shift the focus from catching AI use to designing assessments where AI use is either irrelevant, transparent, or required to demonstrate a specific capability.
- **Structural vulnerability of grading:** Chan et al. provide a concrete case study of how current grading is structurally exposed to AI-mediated dishonesty. In a biology department, instructors perceived only in-person proctored exams as minimally vulnerable; outside-of-class assignments were seen as highly vulnerable, leaving about a third of a student's grade highly vulnerable and 80% at least somewhat vulnerable. This frames the integrity problem as partly a *grading-design* problem, motivating rebalancing toward proctored or in-class assessment and authentic assessment designs that are harder to outsource. Ivory et al. (2026) supply the discipline-level counterpart with a whole three-year psychology program: 36 of 40 assessments across 16 types produced passable content at minimum effort, and the four that failed were those requiring presence, visual media, or the student's own dataset. Their reading of *why* it passes is the part that generalizes — marking that rewards fluent structure and good-faith use of the right analysis condones fabricated values and hallucinated references, so the pass boundary rather than detection decides whether AI output is graded as achievement, and the assessment vulnerability "cannot be blamed solely upon student usage."
- **The submission as an attack surface: prompt injection against AI grading.** Humble (2026) red-teams an everyday grading workflow and shows that a student submission can carry hidden instructions that change the grade an AI tool produces: two of five indirect injection strategies

embedded in the submission file raised a failing essay to a pass with no visible warning to the user, at reported attack success rates of 100% (9/9) and 94% (17/18), both combining instruction manipulation, role-playing and obfuscation across docx, pdf and htm formats. The most basic attack failed completely, and its refusal was silent — the tool disabled the chat without reporting the attempt — while a single detected injection produced a reassurance that the tool would grade "only according to the official assignment instructions" before six further runs of the same file raised the grade anyway. The integrity consequence runs in both directions: a grade raised by a hidden instruction carries no validity claim, the same technique could be used to degrade a submission with no durable trace in the output, and the human marker is left as the only real check on manipulation designed not to be visible.

- **Validity as the organizing frame:** Assessment Validity reframes integrity as an evidential problem. Authentic assessment research introduces **construct substitution** — an AI-generated product is attributed to the student, so the assessment infers the tool's capability rather than the student's. The evidential question survives any AI policy: whether use is prohibited, permitted, or required, the assessment must still generate evidence warranting the inference being drawn.
- **Variation-at-scale as a no-surveillance integrity mechanism:** VARIA (Lee 2026) Benchmark the premise behind AI-Integrated Authentic Assessment (AIAA) — replacing surveillance-based proctoring with per-student task variation so copying is structurally useless. The integrity guarantee is conditional on LLMs generating variants that are surface-distinct and construct-equivalent; VARIA's 600-variant pilot finds frontier models satisfy this only at the margin (joint score 0.81–0.88) while non-frontier models collapse (0.50–0.55), so "variation-at-scale cannot be solved by prompting alone." This gives the detection-vs-redesign debate an empirical, falsifiable check: the no-surveillance promise of authentic, task-varied assessment now depends on a measured (and still narrow) generation capability rather than an assumed one.
- **Authenticating student reflection against GenAI:** Kadel et al. (2026) argue that traditional reflection models can no longer authenticate student reflection once GenAI can author reflective prose, and embed integrity directly inside a reflection model — the 5P framework's Pitfalls stage explicitly handles plagiarism, hallucination, and over-reliance, while its Process and Product stages require documenting prompts and validating outputs so that Learners' own reasoning is distinguishable from AI-generated contributions.
- **Policy development:** Institutional AI policies and Educational AI Policy research examine how universities develop and communicate integrity expectations — and why abstract policy statements so often fail.
- **Integrity as a governance problem, not a detection problem.** Coates, Croucher and Calderon (2025) relocate the binding constraint from student behavior to academic AI Governance, which they call resilient yet "not well positioned or poised" to meet GenAI-related threats to the authentication of student assessment. Their answer is an integrity indicator framework of 130 items across eight dimensions, running from Designing (19 items) to Improving (6), and comprising governance questions rather than psychometric scales — whether the institution's top board receives assessment-quality updates, what percentage of assessment resembles relevant and meaningful problems, what percentage of students are known individually by the teachers who

assess them. It was developed through a multiyear research review, five Australian university case studies, prototyping, expert confirmation with 60 invited experts across six world regions and quantitative piloting, and it is paired with reforms to governance architectures, people, and technologies and resources that the authors expect to pay out only under external pressure from AI Regulation in Education, benchmarking and cross-institutional competition; they present the framework as formative and call for psychometric validation before it is used for comparison or measurement.

- **What the documents actually say: integrity dominates institutional AI policy.** Eldredge et al. (2026) analyzed the AI policy and guidance documents of all 48 CAHIIM-accredited health informatics and health information management master's programs in the US: 40 (83%) had at least one qualifying document, and those documents framed AI overwhelmingly as a matter of preventing student misuse in coursework, centering academic integrity and acceptable use. Academic integrity was by far the most frequent keyword (n = 139, ahead of citation at 59, assessment at 50, and plagiarism at 38), while privacy, intellectual property, and regulatory themes were present but less common (HIPAA n = 5, FERPA n = 11, IRB guidance n = 8). Topic modeling over the same corpus returned four themes, the first being academic integrity and appropriate AI use, alongside generative AI in teaching, AI and data-tool use in research, and student engagement with conversational AI systems. The evidential value for this page is the quantification: integrity-centered framing is not just the rhetorical default of institutional AI policy, it is empirically the dominant content of it. The authors' sharpest observation is about where that attention stops, noting that comparatively little guidance covers AI use in applied learning, research, and simulated environments, where curricular and data-governance concerns intersect, so the documents govern coursework while the settings the degree is preparing students for go largely unaddressed.
- **Integrity framing is giving way to task-based regulation:** Chirikov's (2026) longitudinal study of 31,000+ course syllabi shows instructors' AI policies shifting away from a purely integrity-based frame: academic-integrity mentions in syllabi fell from 63% (Spring 2023) to 49% (Fall 2025), while references to AI's impact on learning rose from 1% to 29%. Instructors increasingly regulate AI **by task type** — restricting it for drafting/reasoning (where AI would displace learning) and permitting it for editing/proofreading and study support — rather than applying a blanket integrity prohibition. This reframes integrity policy as a task-level design decision rather than a binary rule.
- **Machine resistance as prevention, not detection.** Perturbing the document itself — character, word and line spacing, opacity jitter, stripe overlays and image noise, plus decision-based adversarial attacks — raises the effort needed for low-effort LLM misuse at the source while measuring the same knowledge (Salaun et al. (2026)). Manual transcription remains possible, and adversarial attacks protect only selected lines, leaving whole-document character error under 8.44%.
- **Teamwork with per-member verification, in place of detection.** Issa and Hall (2024) ran a postgraduate Business Project Management unit for five semesters on the premise that an instructor can establish authorship from the process rather than from the artifact. The 12-week team plan carried 40% of the unit, each team met the lecturer for 30 minutes to review its work

and organizational breakdown structures, and each member was asked whether their contribution was original. Each student also wrote a peer-reflective form per teammate and a self-reflective form. Unit evaluation items scored 89% to 100% against university averages of 80% to 86%, and the project-plan average moved from 27/40 to 31/40. Its claim that misconduct and extension requests fell “dramatically” carries no counts, and a new lecturer arrived in the same semester as the redesign, so read this as a workable design, not as measured evidence that AI use fell.

The misconduct procedure and its evidentiary collapse

The enforcement machinery that sits on top of integrity policy is itself a design decision, and generative AI has dismantled its evidentiary foundation. Teichmann (2026) argues that the misconduct procedure universities imported from plagiarism assumes prohibited use can be detected and proved — a premise the technology dissolves. Unlike text-matching software, which points to a copied source, an AI-text classifier identifies no source (none exists); it outputs a probabilistic judgment about style that degrades under paraphrase, systematically mislabels non-native English writing, and cannot be explained or cross-examined, while skilled or lightly edited use leaves no trace at all. Persisting anyway reverses the burden of proof (the student is asked to prove a negative), strains every element of procedural justice, and lands the harm of false accusation hardest on the already disadvantaged. The proposed remedy is twofold: an evidentiary standard under which a detector score alone never grounds a finding, with graduated, education-first responses, and a shift of institutional effort into validity-centered and authentic assessment design — the answer to undetectable AI being better assessment rather than better surveillance. The limit case has no machinery at all: Isley, Gaebler and Goel (2026) document a US public policy master’s program that prohibited generative AI assistance in a signed attestation and screened no submissions, where 56.1% of 2025 applicants submitted at least one essay a commercial detector classified as primarily AI-written and each flagged essay was associated with a 1.5 percentage point lower admission probability ($p < .01$), rising to 2.6 points ($p < .001$) once essay quality was held constant. With no detection, adjudication or enforcement step between the rule and the outcome, the penalty was delivered entirely through admissions readers’ unwritten judgment — prohibition plus unaided reader judgment reproducing the discretionary, unexplained sanction a fair procedure exists to prevent.

Munoz et al. (2026) supply the empirical counterpart by coding every GenAI misconduct case at one regional Australian university over three years: 1,162 cases carrying 1,855 evidence items, each rated for relevance, credibility and inferential force. Detector output was the evidence most reached for and least able to bear weight — Turnitin or similarity reports carried 100% Weak inferential force and standalone detector output 100% Low credibility, and detector evidence fell to 0.5% of items by 2025 as institutions absorbed what it could not prove — while the strongest evidence types were those that do not rest on probabilistic text classification: student admissions, observed prohibited exam behavior, and independently verified fabricated references, which were the largest structural shift at 22.3% of items. Their sharpest criticism is structural rather than evidentiary, since “there is no requirement for investigators to assess the probative quality of evidence before progressing an allegation, no minimum evidentiary threshold at any stage of the pipeline,” so evidence quality bore no reliable relationship to case outcomes. They also record how policy caught up with practice: the assessment policy in force through 2024 said nothing about AI, and from January 2025 a revised policy permitted approved authenticity software while prohibiting the upload of student work to third-party AI-detection tools.

A second failure is one of scope rather than proof. Wright (2026) shows that prohibitions written at the level of platform identity rather than function capture non-generative format conversion — speech-to-text transcription, OCR, plain text to LATEX — alongside the generative drafting they mean to bar, even though the peer-reviewed computer science literature treats recognition and generation as distinct operations. The cost lands unevenly: students with conditions affecting fine motor control, handwriting legibility or typing accuracy have relied on exactly those tools, and as standalone voice-to-text products are discontinued or degraded, AI-powered transcription is filling the functional gap, so an over-inclusive rule removes a primary means of producing legible work, making the dispute an Accessibility and equity one before it is an integrity one. Wright's remedy is a function-based definition of generative AI plus four operational criteria — fidelity, non-augmentation, traceability and attestation — that give a student a structured route to rebut a transcription-only allegation while leaving the burden of proof with the institution.

Detection's evidentiary problem is also a validity problem. Because AI assistance is iterative and interwoven with drafting rather than outsourced wholesale, authorship and ownership of meaning come apart, and a sound submitted product may not establish that the student exercised the judgment the task was meant to target. Detector performance varies across tasks, disciplines and model versions, and disclosed or suspected AI use can act as a biasing cue for markers, so a detection response adds construct-irrelevant variance rather than removing it. Where integrity debates ask who produced the words, a validity account asks what claim about the student the performance warrants.

Integrity rules are applied to a phenomenon they do not model. Hong et al. (2026) locate the problem in answerability rather than in how much of the text a machine wrote: an authorship legitimation deficit appears when a designation outruns the grounds the person can offer for the contribution they made. A rule that measures the proportion of generated text therefore cannot see the mismatch it means to catch, and a disclosure that AI was used says nothing about what the human contributed.

The rationalization problem

Students do not generally misuse AI out of malice; they rationalize it. Interview research identifies at least **five disconnect sites** where students' interpretation of AI policy diverges from faculty intent, and a taxonomy of **20+ distinct rationalizations** — from "copying AI text is victimless" to "text reflecting my beliefs is my own writing." These rationalizations are ad hoc, post hoc, and internally inconsistent, and they describe a "steep, ethical slippery slope" on which students slide far outside pedagogical goals. This is why student misconceptions about AI are the upstream cause of integrity violations, and why integrity education must address ethical reasoning, not just technical skill.

Ji's (2026) scoping review of 38 empirical studies of student voices supplies the synthesis this section rests on. Its four themes are ambiguity (generating a whole task reads as cheating, grammar checking and brainstorming are largely acceptable, and paraphrasing, outlining and translation sit in a gray area), ethical Learner Agency in which students build personal rules in a guidance vacuum they read as a silent approval of their actions, the gap between ethical awareness and practice, and diversity by gender, level, discipline and culture. The awareness-practice gap is the rationalization problem measured at scale: Huang et al.'s Ethical Dissonance Index sorted 522 Chinese students into four clusters, one of which frequently did what it viewed as illegitimate, and Ofem et al.'s structural-equation modeling of 4,679 Nigerian students found that positive perceptions of ChatGPT predicted dishonest use while positive integrity attitudes acted as a

significant negative mediator. Ji reads students as neither passive recipients of GenAI nor culprits without moral constraint but active agents navigating an ethical gray zone, which is why the reviewed studies converge on co-created, educative and context-sensitive responses rather than punitive ones.

Why policy alone fails: the coordination problem

A coordination-game framework provides a mechanism-level account of why policy pronouncements rarely change behavior: students' AI use is a **coordination problem**, where individual choices depend on peer expectations and assessment design. The model's key finding is **non-linear threshold dynamics** — small, well-calibrated changes to reflective-assessment incentives can trigger rapid cohort-wide shifts toward responsible use, while weak or misaligned incentives let opportunistic practice persist. In practical terms, modest redesign (e.g., requiring students to reflect on their AI interactions) can have disproportionate effects where abstract rules have none.

Peer accountability does not always point toward integrity, as Chen and Zou (2026) found in graded group assessment: seven of fifteen student groups deliberately reduced their GenAI use partly to avoid free-riding on groupmates, since group consequences were shared rather than self-contained, yet in five groups a permissive collective climate — "everyone in my group is using GenAI" — lowered the perceived risk of misuse and inverted the very accountability mechanism group work is meant to create. The same study found students reframing originality as faithfulness to the understanding their classmates built together, and its practical recommendation follows directly: make the negotiation of acceptable AI use an explicit, documented, and assessable outcome rather than leaving the norm to emerge from peer pressure or perceived risk.

Policy inconsistency across the institution produced exactly the guessing the coordination account predicts. Nine of the eleven interviewees in Zou et al. (2026) framed their own course's explicit permission to use generative AI as a possible "trap" — a lure to identify students who could not resist — even though the policy was open and written into the assessment guidelines; students generalized from bans and warnings encountered elsewhere rather than reading their own course's rules on their own terms. The authors' conclusion follows the mechanism rather than the wording: per-course clarity was not enough, and program- or institution-level consistency is needed so that students stop inferring intent from the surrounding culture.

Identical conduct, different verdicts - and disclosure that changes nothing. Poudyal (2026) applied 15 standardized vignettes to the policy environments of 20 Australian universities and produced 300 classifications: 120 (40.0%) clearly prohibited, 56 (18.7%) indeterminate, and none clearly permitted, while binding instruments were silent on generative AI in 100 combinations that guidance resolved in 88. Disclosure did not determine outcomes - the same disclosure status produced different classifications depending on permission rules and task instructions, and the disclosure field recorded 117 satisfied requirements and 80 false declarations.

Procedures matter as much as policies, and their evidentiary basis has collapsed for AI. Teichmann (2026) argues that the misconduct procedure universities imported from plagiarism rests on a premise generative AI dismantled: that prohibited use can be detected and proved. Unlike text-matching software, which can point to a copied source, AI-text classifiers identify no source because none exists — they output a probabilistic judgment about style that degrades under paraphrase, misclassifies non-native speakers systematically, and cannot be explained or cross-examined, while skilled or lightly edited use leaves no trace at all. Persisting

anyway reverses the burden of proof (the student is asked to prove a negative), strains every element of procedural justice, and lands the harm of false accusation hardest on the already disadvantaged. The proposed remedy is twofold: publish an evidentiary standard under which detector output alone never grounds a finding, with graduated education-first responses, and move institutional effort into validity-centered and authentic assessment design. Mohamed and Temimi (2026) supply the mechanism-level counterpart from the student's side: because each assessment environment makes some response most attractive, prohibition leaves concealment attractive when verification is thin, monitoring makes hidden use costlier without making disclosure safe, and only redesign — lowering the payoff from outsourcing while raising the value of visible reasoning — moves students toward responsible use. Their sharpest result is that deterrence runs through a detector's discrimination between hidden use and legitimate work rather than its catch rate, so when false positives rise faster than true positives, stronger monitoring can make concealment relatively more attractive.

- **Integrity duty can be rewritten as individual competence.** Across 366 GenAI higher-education abstracts, the word integrity appears 461 times but only 6 of 166 obligation expressions name students, so verification and disclosure surface as skills students are expected to have rather than obligations institutions enforce (Poudyal, 2026).
- **How prescriptive an integrity policy is does not reveal how exposed the assessment is.** Auditing 15,587 unit records, Villanueva (2026) found universities with institution-wide reform mandates and those with broad frameworks spread across the same range of assessment exposure - the empirical counterpart to the coordination-game account of why pronouncements rarely change behavior.

The socio-emotional dimension

Integrity enforcement has a neglected emotional cost. Shame-and-guilt research with students shows these emotions regulate when and how AI use becomes visible, producing **hiding behaviors and selective disclosure** — and that they coexist with continued use, creating cycles of reduced agency and moral tension rather than behavior change. That is why the norms around AI use regulate visibility more effectively than they regulate use. Students even describe their AI use in language of addiction. The implication: detection-heavy, surveillance-oriented policy risks **driving misuse underground** rather than addressing it, undermining the candid negotiation that productive use requires.

The obverse of hiding is declining, and it carries its own emotional cost. Among the 85 student teachers Zou et al. (2026) surveyed under an assessment policy that explicitly permitted generative AI, 62.4% (53) chose not to use it at all, and the adopters' use was shallow and corrective — proofreading (43.8%) and clarity checks (34.4%) far outnumbered text generation (18.8%) and brainstorming (12.5%). Fear of wrongful accusation, not technical difficulty, did much of the work: 41.5% of non-adopters named it, against 13.2% citing missing knowledge or skills, while 77.4% framed non-use simply as a preference for working alone. When a permissive policy is read as a trap, the safe response is refusing the offer — which costs the institution the AI-integrated work it was trying to invite.

AI use disclosure statements

AI use and disclosure statements are the concrete mechanism through which integrity expectations are operationalized — and the research shows they often fail when treated as neutral compliance forms. Gonsalves (2025) found 74% of students failed to declare AI use on a mandatory coursework coversheet, driven by fear of penalties, guideline ambiguity, inconsistent enforcement, and peer norms. Kirsanov et al. (2026) and Vetter et al. (2026) confirm that fear of retribution and unclear policy chill disclosure — and that transparent students can even draw suspicion. Chang et al. (2026) reframe disclosure as a Help-Seeking/self-regulation behavior that anxiety redirects toward peers. The collective lesson: disclosure policies must address the affective and social barriers, be clear and consistent, and treat disclosure as formative pedagogy rather than surveillance. **Luo & Dawson (2026)** add the teacher-side of the equation: teachers' grading of GenAI-assisted work is driven by value judgments about student honesty, diligence, and trust, and many teachers penalize (or are tempted to penalize) students who disclose GenAI use — even when the work quality is strong. This is the "two-way transparency" problem: students are expected to declare use, but teachers rarely clarify how that declaration will affect grades, so honest disclosure can carry an unstated grading penalty. The study grounds the disclosure problem in the value-laden reality of teacher grading and argues that transparency must run both directions.

Students' own reports quantify how badly that message is landing. In a survey of 504 sociology undergraduates, 81 percent said their instructors or teaching assistants had given guidance on AI use, yet only 46 percent called those instructions very clear; 19 percent reported receiving no guidance at all and the rest described it as at best somewhat clear (Kuznetsov, Sheely & Baker, 2026). Fear of committing an academic offense was the second most common concern students raised (28 percent) — a cost imposed by ambiguity rather than by enforcement, since only 3 percent reported using GenAI to generate assignment text and 2 percent to produce a full draft. The practical implication is that clarity of communication is itself an integrity mechanism, and that a student who cannot tell what is permitted bears a risk the institution never intended to impose.

Course-level permission does not resolve the disclosure dilemma either. In Zou et al.'s (2026) study of 85 student teachers whose assessments explicitly permitted generative AI, self-declarations totaled 28 users against 32 in the anonymous survey, and the two sources disagreed in opposite directions by course — Course A recorded 14 survey users but only 8 declarations, while Course C reversed the pattern (8 survey, 12 declarations). The authors read the divergence as graded consequences shaping what students were willing to make visible, adding student-teacher evidence that a declaration system measures disclosure behavior as much as it measures use.

Cultural and contextual variation

Policy text does not equal policy perception. Cross-national research found that, despite functionally identical institutional policies, students at different universities rated the same AI-assisted practices differently — **culture, not policy wording, drove perceived wrongness**. Policy harmonization does not produce perception harmonization, so culturally diverse cohorts interpret the same rules differently, an equity concern for enforcement and grading that argues for scenario-based clarification over abstract rule statements.

Language background rather than culture is a second axis of variation. Li (2026) argues that because the same interface performs permitted language editing and prohibited substantive drafting, integrity rules treating GenAI as one category of unauthorized assistance convert linguistic disadvantage into integrity risk: an outright ban removes a scalable form of language support, a permit-but-disclose regime loads compliance work onto EAL students whose use is more frequent and iterative, and prohibitions on editing beyond minor changes concentrate suspicion on writers whose fluency has shifted most. The boundary Li proposes is purpose-based rather than tool-based — permitted support adds no new ideas, no new sources and no material re-ordering of analysis, while substitution creates or materially reshapes the intellectual work being evaluated — and it is anchored in the assessment construct because rubrics that award marks for fluency and idiomatic expression introduce construct-irrelevant variance for EAL writers (Assessment Validity). The framework demotes detector output to a triage signal that rarely constitutes proof, preferring triangulation through staged submissions, draft histories, verifiable source trails and a brief construct-aligned conversation, and it calibrates disclosure so that routine support does not carry compliance costs exceeding those borne by monolingual peers.

From policing to pedagogy

The knowledge base documents a paradigm shift: from AI as an integrity threat to be policed, to AI as a tool whose appropriate use must be taught. This is the ethical dimension of AI Literacy and is embodied in practical design:

- **Task-specific AI-use declarations:** Domain-specific declaration frameworks replace generic "I used AI" checkboxes with structured declarations mapping use to cognitive stages (e.g., structural planning vs. content generation), forcing reflection and shifting focus from policing to professional practice.
- **Process-transparent assessment:** architectures such as cognitive stewardship, staged submissions, oral defenses, and the AI Viva (a conversational agent probing whether students understand their submissions) make human judgment, verification, and responsibility visible. Miles, Haber-Curran and Arar (2026) push the same logic down to the prompt itself: their sample rubric grades iterative refinement, critical interpretation of output, and reflective revision, so what is assessed is the student's engagement with the tool rather than the artifact it produced, and they argue that teaching students only to optimize output leaves the ethical and epistemological dimensions of use untouched.
- **Reducing misuse:** integrity sits alongside AI Misuse and Learning Harm (the learning cost of misuse) and Reducing AI Misuse (the interventions that prevent it), tying honesty to genuine learning rather than rule-following.
- **Transparency as an integrity strategy, not just a courtesy:** McCorkle's (2025) design case treats the *rationale* for each allowed or unallowed GenAI use as the integrity mechanism itself. Students interviewed after ignoring a prohibition policy explained that they did not see themselves as behaving dishonestly, which reframes the failure as ambiguity rather than noncompliance — so the redesign answered it by justifying every restriction with the specific Assessment it protects, and by designing for McCabe's "20-60-20" persuadable middle rather than the determined few.

The case also names the equity cost of vague policy: expectations that are unclear and uneven across instructors are what convert policy failure into disciplinary action (Equity).

- **Design, not detection: the Bochum case.** The Ruhr University Bochum redesign of introductory nuclear and particle physics (Mikhasenko et al., 2026) linked its AI policy to a practical integrity failure rather than to detection: because tutorial problems were disclosed in advance, some students prepared AI-generated solutions and copied them onto the blackboard without engaging in the intended reasoning. The authors treat this as a design problem — moving tutorial problems to prepared in-class discussion and making a written exam the grade determinant — rather than a policing problem, while explicitly permitting AI in study, explaining why verification is the student's responsibility, and noting that open-ended AI-permitted homework also raised dependence, uneven access to paid models, and teaching-assistant workload.

The clearest statement of the pedagogical inversion comes from El Khoury and Ma (2026), who argue that reform starting from suspicion narrows the educational imagination to control, compliance and surveillance, and that integrity should be a **consequence** of assessment designed for engagement rather than its starting point. Their supporting observation is a mechanism already visible elsewhere in this knowledge base: disengagement is one of the conditions under which dishonesty becomes more likely, so agendas that stress-test assessments or constrain AI use without addressing engagement leave part of the problem untouched.

Students outside Anglophone higher education describe the same tension in their own terms. Mulisa and Mezgebu (2026) interviewed 27 undergraduates at an Ethiopian university and found the student body divided against itself: almost all used GenAI or watched peers use it, most credited it with improving their academic achievement, a small minority called such use outright misconduct, and nearly everyone described an uneven playing field in which AI-assisted work earned better grades than honest effort while independent workers lost their sense of diligence. The sharpest feature of the account is the students' definition of plagiarism, which is technically defensible and incomplete — if plagiarism means reproducing someone else's words, a machine-written text that copies nothing is not plagiarism — which is why the authors argue the definition must expand beyond copying and pasting, following Ka and Chan's (2025) "AI-plagiarism", and why they place students' own beliefs, not only institutional rules, at the center of ethical use.

Sharma (2026) takes the pedagogical inversion a step further by extending Eaton's postplagiarism frame from an ethical orientation into assessment design. Integrity, on this account, is enacted through evaluative judgment — the learner's capacity to weigh options, justify academic choices, and assume responsibility under epistemic uncertainty — and made visible through four practices: annotated decision trails, verification and accountability practices, oral defense and dialogic accountability, and draft differences with version history. Detection is retained only as a supplementary layer for clear misrepresentation or deliberate outsourcing of intellectual labor, never as the primary infrastructure of integrity, because it asks whether GenAI was used rather than how the decisions behind the work were made. The argument also names the equity risk that detection-centered models fall hardest on learners who rely on generative tools for linguistic or cognitive Scaffolding.

A third route sits between detection and redesign. Akçapınar (2026) predicts AI-assisted cheating risk from early-semester LMS traces with an AUC of 0.763, and frames the output as low-stakes academic guidance — reminders, assignment follow-up, brief check-ins — rather than evidence of misconduct, insisting the score stay separate from grading and disciplinary records.

Connections

Academic integrity connects to Assessment Validity, AI Literacy, AI Detection, Authentic Assessment, Assessment, Educational AI Policy, AI Regulation in Education, Ethics, and Equity. It is the ethical dimension of AI in education, inseparable from Over-Reliance and the broader question of how Generative AI reshapes Higher Education and K-12 learning.

- **Systematic-review synthesis.** A PRISMA review of 25 studies (Balalle & Pannilage 2025) finds AI acts as both a threat (AI-generated writing, paraphrasing tools) and a detection tool (Turnitin AI scores), that detection software is unreliable for AI-generated work, and that institutions must build a culture of academic integrity through clear policy, assessment redesign, and ethics training rather than policing alone.(Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity)

Integrity is a central concern but a rare outcome. Across 394 GenAI higher-education studies, academic integrity and ethics were among the outcomes targeted least often (Lin et al. (2026)). - **From policing to dialog: learning verification.** A practitioner account of Grand Canyon University's institution-wide framework (Mandernach 2026) argues detection is unreliable and formal integrity processes rarely reach resolution, leaving faculty with "suspicion without recourse." GCU instead adopted **learning verification** — asking students to demonstrate understanding of their submitted work in a brief conversation — reframing integrity from a compliance problem to an assessment problem. It restores faculty authority, shifts students from "how not to get caught" to genuine engagement, and treats AI use as acceptable when the student can demonstrate learning; students' initial anxiety about verification underscores that surveillance-heavy policy can corrode Trust.

- **GenAI defeats autogradable homework (2026):** ChatGPT passed every one of 150 test sessions on deliberately hardened, autogradable Qiskit (quantum computing) homework designs — personalization, hidden references, reflections, simulator execution — showing that rubric-based graders cannot reliably distinguish AI-completed from student-completed work and arguing for direct assessment of understanding (ChatGPT Solves All Tested Qiskit Homework Assignments).
- **Evaluation in the age of AI — output as evidence (2026):** a university-level analysis argues the AI assessment crisis is a misalignment between assessment design and learning outcomes, not just dishonesty; it documents surveillance harms (lockdown browsers, eye-tracking), a "Disclosure Trap" (students fear declaring AI use lowers marks), a performance gap that grades socioeconomic status (paid vs. free Large Language Models (LLMs) tiers), and "pedagogical burnout" among faculty policing AI — recommending process-based evaluation over detection (Evaluation in the Age of AI: Output as Evidence of Learning).

Newer evidence: ethical reasoning, detection limits, AI marketing, and ghost students

A wave of recent research sharpens the picture of academic integrity in the age of generative AI:

- **Secondary students reason about AI-giarism situationally, not as a fixed rule.** Chan (2026) shows that secondary students' ethical reasoning about "AI-giarism" is nuanced and context-dependent — many see AI-assisted work as acceptable when it supports understanding but

problematic when it substitutes for their own effort — challenging the assumption that students simply lack integrity or that a single policy can capture their ethics.

- **Students' own concern is learning loss, which the misconduct frame misses.** Ting et al. (2026) interviewed 14 undergraduates and found them drawing a line not at AI use but at AI producing work they had not done, and asking where the tool was helping and where it was doing something they needed to learn to do themselves. The authors argue that the student–faculty conversation is framed too narrowly around misconduct, since students in their accounts worry about losing skills and about whether the work is still theirs — concerns close to those of their instructors. Their reasons for holding the line were also heterogeneous (skill loss, ownership and pride, moral objection), and pressure from deadlines, workload and grades overrode them in individual cases.
- **Authentic assessments alone cannot safeguard integrity.** Kofinas et al. (2025) find that markers generally **cannot distinguish** assessments with GenAI input from those without, and that the level of assessment authenticity has **no impact** on the ability to safeguard against or detect GenAI use. The higher-education sector "cannot rely on authentic assessments alone to control the impact of GenAI" — a direct challenge to the assessment-redesign strategy, which must be paired with other measures.
- **Integrity guidance must extend into the research process, not just teaching.** Dai & Chan (2026) find postgraduate researchers enact AI Literacy across research tasks and argue that responsible-use policies, which currently focus on teaching and assessment, must scaffold the ethical dimensions of GenAI use in research — where concerns center on originality, authorship, data privacy, and skill degradation rather than plagiarism alone.
- **Purpose must precede policy.** Taylor & LaCroix (2026) argue that whether GenAI use constitutes misconduct depends on the university's *purpose*. Rising misconduct cases reflect structural incoherence in the neo-liberal university, where technological enthusiasm, corporate influence, and policy enforcement conflict — leaving students accountable for behaviors implicitly shaped by the institution. Universities cannot credibly enforce integrity without coherence between stated mission, pedagogy, and technology practice.
- **Psychological and behavioral determinants.** Frontiers research maps the psychological mechanisms and behavioral determinants of academic integrity under AI — how attitudes, self-efficacy, norms, and perceived consequences shape honest use — connecting integrity to Motivation, Self-Efficacy, and AI Literacy as behavioral constructs rather than pure rule-following. Tabares-Cruz et al. (2026) quantify these in a SEM of 980 Ecuadorian university students, ordering academic-integrity and transparency dispositions first, followed by AI literacy, critical verification, institutional guidance, self-regulation, and data protection — with integrity dispositions and AI Literacy together explaining a substantial share of ethical GenAI use and outpacing institutional rules alone.
- **AI marketing normalizes use and framess "cheating vs. competing."** Sobo et al. (2025) show AI is marketed to students as a practical necessity ("Make your writing sound more natural to avoid being mistakenly flagged"), and students feel compelled to adopt it to stay competitive even while worrying about dependency and learning forfeiture — an internalized entrepreneurial imperative. This points to the need for marketing literacy as part of AI integrity education.

- **AI humanizers expose the performative cycle of detection — and the market built into it.** Roe et al. (2026) catalogue 55 AI-humanizer websites that alter AI-generated text to evade detection, framed through Goffman's dramaturgy, with a Multimodal AI critical discourse analysis of the three highest-scoring. Humanizers make misconduct discursively absent and perform legitimacy instead of assuming it: unexplained university and corporate logos placed under the text box, unverifiable user claims (about 3 million, 10,000 students and 1.5 million across the three sites), 99.8%–100% success rates, and mystification through "1.6 trillion parameters" — while no site listed a registered business address. The paper's contribution to integrity policy is that this is not a side market but the mirror image of detection: one vendor sells a classification of authorship, the other sells the promise of changing it. Students appear simultaneously as users of AI production tools, subjects of detection, customers for evasion services and sources of behavioral data, and each layer of the loop has a commercial interest in not interrupting it — so the arms race is structurally unending, reinforcing the shift from policing to assessment design and AI Literacy.
- **Enforcement, not detection, is where the conversation lives.** Across 270,929 AI-related records from 26 education subreddits spanning three and a half years, the academic-integrity cluster held 37.1% of the discussion and Misconduct Enforcement was the single largest theme at 12.1%, while 32.3% of faculty–student threads sat inside detection and enforcement disputes (Yüce et al. (2026)).
- **Ghost students and the agentic-AI verification gap.** Bozkurt, Crompton & Fell Kurban (2026) introduce the **"ghost student"**: a digital surrogate created by coupling LLMs (the "mind") with agentic AI browsers (the "body") that can navigate LMS, engage content, and complete assessments with human-like mimicry, making the actual learner's presence optional. This creates a **verification gap** that traditional proctoring and detection are structurally unable to close — an integrity threat that grows as AI becomes agentic rather than merely generative.

The clearest disciplinary case for redesign over detection comes from computing education. A systematic review of 72 studies of generative AI in computing and programming education (Kumar, Wongsirichot and Nanthaamornphong 2026) found only **three** studies examining AI-detection mechanisms — the thinnest evidence base of the 14 themes it consolidated — while course and assessment redesign was supported by 25. The review treats the imbalance as diagnostic rather than incidental: institutions have largely updated policy documents without redesigning assessments, and most instructors sit at a *tolerance* rather than *transformation* level of integration, with 70% of one national faculty sample explicitly requesting training on AI-resistant assessment design. Its recommended response is concrete: add an oral component or other process-visible element to at least one high-stakes assessment per course, and make critical engagement with AI output (reading, testing, modifying, explaining, critiquing) a graded, observable component of student work rather than an aspiration left to student discretion (Assessment Validity). A PRISMA review of 72 higher-education assessment studies finds three design responses recurring in response to GenAI — process orientation, authenticity, and oral and dialogical approaches — framed as layering onto existing validity, authenticity and alignment principles rather than displacing them (Crompton and Burke (2026)). - **Fabricated references have reached the published computing-education record.** Denny et al. (2026) traced 113,588 references from 5,225 computing education papers in the ACM Digital Library against the full corpus of 723,930 publications and 15,872,533 references, manually verified 828 suspicious records, and

confirmed 30 references containing verifiably fabricated bibliographic information across 14 papers, all published in 2025 or 2026. At the SIGCSE Technical Symposium the verified count rose from 3 in 2025 to 17 in 2026, sitting in 2.3% of 2026 proceedings papers, and hallucinated references appeared across five SIGCSE-sponsored or in-cooperation venues in 2025. The number is intact only with its counterweight: most flagged references were benign — 229 were ACM metadata mismatches where the PDF was correct and 188 were valid bibliographic variants — so the venue figure is a deliberate lower bound. It lands on authors, not only on Peer Assessment, because reviewers checking reference lists cannot verify every entry, and Large Language Models (LLMs)-assisted drafting makes an invented but plausible citation cheap to produce.

- **Clarity without redesign moves misuse sideways rather than removing it.** Petricini & Zipf (2026) plot AI use on two axes — students' intention and effort against the clarity and support the environment provides — and report that the most populated quadrant in their interview data was *anxious compliance*, where students hide legitimate help (grammar support, concept explanations, organizing their own ideas) to avoid false accusation. Their warning is directional: where rules become clear but Assessment still rewards speed and product, policy-aware students shift into *efficient circumvention* rather than into *virtuous tool use*. Austin (2026) reaches the same place from the assignment side — when agents satisfy every rubric criterion without visible reasoning, grading the decision trail (confidence calibration, rejected AI suggestions, course-specific constraints) replaces detection, which she notes misfires in both directions.
- **Employers discount grades they believe AI produced — and converge on in-person verification.** In a survey experiment with ~1,750 U.S. hiring professionals, Boyd-Swan & Reynolds (2026) show that framing student AI use as an assistive tool left applicants unpenalized, while framing it as a *substitute for student effort and ability* decreased interview likelihood and — more starkly — salary-negotiation willingness, concentrated among high-GPA applicants regardless of race/sex. Asked what would ease concerns, both framing groups selected only one remedy in common: in-person tests. The experiment isolates belief (not actual AI use), so it shows how the *signaling* channel alone moves hiring outcomes — early evidence that labor markets may push assessment back toward presence-verifiable formats, the same design direction the ghost-student literature urges institutions to adopt.

The first Theory of Planned Behavior study of GAIT-based misconduct intention extends this picture: among 186 undergraduates, Baig and Paparo (2026) found attitudes toward misconduct, subjective norms about it, and positive attitudes toward AI each predicted intention, while negative attitudes toward AI did not, and higher perceived likelihood of detection predicted lower intention — a deterrent undermined by the documented unreliability of AI detection tools.

Integrity policies are shifting from who wrote the words to who had the ideas, and the detectors are being rebuilt to match. IdeaLens predicts idea provenance from an outline rather than from prose: on 50 stories that people wrote from scratch following AI-generated plans it flagged 68% as AI, against 8% for Pangram 4 and 0% for its prose-trained control, and it labeled 94.7% of AI-polished human text human (Rajendhran et al. (2026)). Its own ethics statement calls the output a statistical estimate that must not be used by itself as conclusive evidence of AI use.

Gillette et al. (2026) document the regime from inside one faculty: teachers who had changed assessment formats said it was "virtually impossible to say whether a student has used AI in the writing of assignments",

while angry students asked for appeals to conscience and “shaming” rather than detection. - **Better sensing does not change what the assessment can certify.** A YOLOv11 pose-estimation proctoring system reporting 99.56% classification accuracy illustrates the limit of the detection route: it measures posture against a behavioral label, reports no ground truth on misconduct, and offers no subgroup analysis (Arif et al., 2026). The remedy Villanueva argues for is sufficient evidence of learning at key stages, not maximum surveillance of every submission.

Integrity language in international policy does not fix an operational meaning, and that is the finding rather than the gap. Hashem (2026) analyzed four UNESCO and OECD publications from 2023 to 2026 through critical discourse analysis and found eight recurring terms — responsibility, transparency, trust, human agency, originality, authenticity, responsible use and augmentation — carrying normative weight while shifting referent between documents. UNESCO holds providers responsible for core values and educators responsible for pedagogically appropriate interaction; the OECD relocates the same term into teachers’ professional judgment.

The OECD (2023) records that as of early 2024 none of eighteen surveyed countries had specific generative AI regulation for education and nine had delegated governance to the school level. Read through Ahmed’s non-performativity, the vocabulary expresses ethical responsiveness without any mechanism to enact it, so responsibility is invoked by every actor at once and located in none. Hashem names the result a changing **cheating habitus**: dispositions toward legitimate participation recalibrated under chronic indeterminacy, stratified by the academic capital students bring, with cheating and being cheated treated as concurrent conditions rather than alternatives. All of it is proposed from policy text, not observed in students.

Common Misconceptions

- **“Detection tools identify AI writing.”** AI-generated text has **passed as human-authored in up to 80% of cases**, while the evidence for detection puts **machine detection at about 80% against 78.4% for human raters**. Human and machine judgment are almost equally (un)reliable, so a detection verdict is not evidence of authorship.
- **“The problem is marginal.”** The volume is far from it: a **six-year analysis of a large-enrollment CS2 course** found **45.7% of Spring 2026 students flagged**. Nearly half a cohort, which makes this a mainstream design problem rather than an edge case.
- **“Instructors know which assessments are vulnerable.”** In a biology department, instructors **perceived only in-person proctored exams as minimally vulnerable**, while outside-of-class assignments were seen as exposed. The perception matched the obvious case and treated everything else as safe.

Connected Concepts

- Pedagogical Patterns — Verification sequences adopted in response to generative AI
- AI Use and Disclosure Statements — AI use and disclosure statements
- Assessment Validity
- AI Literacy
- AI Detection

- Authentic Assessment
- Assessment
- Educational AI Policy
- AI Regulation in Education
- Ethics
- Equity
- Cognitive Offloading
- AI Misuse and Learning Harm
- Reducing AI Misuse
- Misconceptions about AI
- Generative AI
- Higher Education
- K-12
- AI in Education
- Legal Issues and Risks
- Social Norms of AI Use — the informal rules that sit under formal policy
- Reflection

Connected Articles

- Cheating or being cheated? Academic integrity and a changing cheating habitus in international AI governance discourse — Four UNESCO and OECD documents read as discourse: floating signifiers, non-performativity and a changing cheating habitus
- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — A whole psychology program passable at minimum effort, and the marking criteria that let it through (Ivory et al. 2026)
- "Is this a trap?": Student teachers' perceptions and adoption of GenAI in assessments in three teacher education courses — Student teachers declined GenAI under a permissive policy; "trap" framing and survey–declaration gap
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- Generative AI in computing education: A systematic review and a framework for responsible integration — Detection evidence is thin (3 studies of 72); redesign carries the weight
- Designing an Aligned Generative AI Course Policy: An Equitable and Transparent Learner-Centered Approach — Aligned GenAI course policy: assessment-derived permissions, transparent rationale (McCorkle 2025)
- VARIA: Benchmarking Frontier LLMs on Construct-Equivalent Assessment Variant Generation — Construct-equivalent assessment variant generation (Lee 2026)

- How Instructors Regulate AI in College: Evidence from 31,000 Course Syllabi — How instructors regulate AI across 31,000 course syllabi; integrity framing declining (Chirikov 2026)
- Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI — Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI
- Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher — Student non-compliance with AI use declarations
- Once a Response, Always a Response: Detecting LLM-generated Text via Latent Prompt Restoration — Detecting LLM-Generated Text
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond Detection: Authentic Assessment in an AI-Mediated World
- ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform — The AI Assessment Scale and Assessment Reform
- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — From Authentic Products to Authenticated Processes
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — It’s OK Because… Student Rationalization of AI Use
- Mathematical Modelling of Ethical AI Use in Higher Education: A Coordination Game Framework for Future-Facing Learning — Coordination Game Framework for Ethical AI Use
- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and Guilt as Social Regulators of AI Use
- Did Alice Do Wrong? Cross-Cultural Differences in Student Perceptions of Generative AI Use in University Computing Education — Did Alice Do Wrong? Cross-Cultural Perceptions of AI Use
- Exploring value judgements in grading: will teachers mark down student work assisted by GenAI, and should they? — Value judgments in grading GenAI-assisted work: honesty, trust, validity, and two-way transparency (Luo & Dawson 2026)
- Students’ agency in GenAI-mediated group assessment: An ecological-emergent perspective — Peer accountability and originality in GenAI-mediated group assessment
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Detection’s evidentiary collapse and the case for procedural justice, proportionality, and design
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — Deterrence, disclosure, and redesign as an assessment-design problem under imperfect information
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What evidence 1,162 GenAI misconduct files actually rested on, and the missing evidentiary threshold

- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI rules and the transcription-versus-generation distinction
- AI-based digital cheating at university, and the case for new ethical pedagogies — AI-based digital cheating and prevention-based ethical pedagogies: the 183-to-27 misconduct case and five discipline-specific redesigns (Leaton Gray, Edsall & Parapadakis 2025)
- Governing academic integrity: Ensuring the authenticity of higher thinking in the era of generative artificial intelligence — Integrity as a governance problem: a 130-item indicator framework for academic governors (Coates, Croucher & Calderon 2025)
- Academic integrity in the age of generative AI: A scoping review of research on higher education student voices — Scoping review of 38 studies of higher education student voices on academic integrity and GenAI (Ji 2026)
- GenAI assessment and language equity: Drawing the line between support and substitution — Drawing the support-versus-substitution line for EAL writers, and the inequity of rules that ignore language background (Li 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection against AI-mediated grading: hidden instructions that change the grade undetected (Humble 2026)
- Designing for Virtuous AI Use: The AI-Use Ethics Matrix in AI-Mediated Classrooms — The AI-Use Ethics Matrix: anxious compliance, and why clarity alone can push students into efficient circumvention (Petricini & Zipf 2026)
- When AI Agents Can Complete the Assignment: Practical Strategies for Designing Tasks That Still Require Human Thinking — Grading the reasoning trail when AI agents can complete the assignment (Austin 2026)
- AI-written admissions essays are widespread but penalized — AI-written admissions essays are widespread but penalized
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research
- Mapping the Authorized Boundary: A Comparative Policy-Vignette Study of Generative AI Governance in Australian Higher Education — Mapping the Authorized Boundary: A Comparative Policy-Vignette Study of Generative AI Governance in Australian Higher Education
- Argus: Academic Integrity in the Era of Generative AI — Argus: Academic Integrity in the Era of Generative AI
- How AI-vulnerable is Australian higher education assessment? A computational audit of Group of Eight Arts and Humanities units, 2022–2026 — Sector audit finding: mandate and framework universities show no difference in assessment exposure, the empirical counterpart to the coordination problem

- Early Prediction of AI-Assisted Cheating Risk in Online Exams Through Learning Analytics — Akçapınar (2026) — Early prediction of AI-assisted cheating risk from LMS traces, framed as academic guidance rather than evidence of misconduct
- ChatGPT vs Teachers vs Students: Large-Scale Analysis of Generative AI Discourse in Education Communities on Reddit — Three and a half years of education Reddit: enforcement dominates, and integrity disputes are the main faculty–student venue (Yüce et al. 2026)
- Early evidence on employer responses to college student use of generative AI — Survey experiment: the substitution framing of student AI use penalizes high-GPA applicants on hiring and salary; in-person testing is the only remedy both groups chose
- AIRRI: Towards a Human-Readable, Machine-Resistant Reading Interface — AIRRI: Towards a Human-Readable, Machine-Resistant Reading Interface
- A teamwork framework for preventing breaches of academic integrity and improving students' collaborative skills in the AI era — teamwork assessment with per-member verification as an authentication design (Issa & Hall 2024)
- Owning what one did not make: psychological ownership, agency, and the authorship legitimation deficit in human–AI co-creation — Answerability rather than text proportion as the integrity problem

Connected FAQs

- What Are Best Practices for Writing Instruction in the Context of AI?
- Should We Use AI Detectors?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can I Reduce AI Cheating in My Course?
- How Can We Address Common Misconceptions About AI in Education?
- How Do I Write a Course AI Policy and Communicate It to Students?
- How Do I Teach Students to Verify AI Output?
- How Should I Handle AI in Group and Collaborative Assignments?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Teaching

> **Teaching** — how AI reshapes the work, identity, and agency of educators. With 50+ articles examining this dimension, the knowledge base documents a fundamental transformation: from sole knowledge authority to orchestrator of human-AI learning environments. This page goes beyond describing that shift — it details what teachers actually *do* differently, how they can adapt their practice, and how they connect to Learning Design, AI Literacy, and Academic Integrity.

> Malyn-Smith et al. (2026) call this the more-human paradox: in six 2030 scenarios co-constructed by 20 researchers from 13 countries, AI saturation intensifies rather than displaces human pedagogical work. The scenarios describe AI as "the air-handling system of the learning ecosystem" — you notice it only when it malfunctions.

Questions to Consider

- The page describes the teacher's shift 'from sole knowledge authority to orchestrator of human-AI learning environments.' What do you gain and what do you lose as an educator when you stop being the main source of content?
- It argues AI reallocates a teacher's scarcest resource — attention — from producing materials to interpreting learners. Does that reframing ring true, and what would you actually do with the reclaimed time?
- Research cited on the page shows teachers as active AI designers — writing the prompts and scaffolds that shape how AI behaves for their students — rather than passive consumers. What would it take for you (or teachers you know) to feel like a designer of AI rather than a user of it?
- At the far end of the 'teacher-AI teaming' spectrum, the teacher orchestrates a team of human learners, AI tutors, and curriculum resources. Where does human judgment remain irreplaceable in that team, and what might quietly erode if the orchestration is left mostly to AI?
- If the teacher's attention is reallocated from producing materials to interpreting learners, what new competencies and risks does that introduce — and who supports the teacher in developing them?

Introduction

Teaching here names the professional role as AI reshapes it: less content delivery, more orchestration of human and machine participants, interpretation of what learners actually understand, and design of the conditions under which AI use is legitimate. The pages collected under this concept document teacher–AI teaming and workflow change, the competencies the role now demands, and the tension between efficiency gains and the attention that individual support requires. It sits alongside Educational Development, AI Literacy and Assessment as one of the roles that determines whether AI integration changes practice or merely decorates it. The learning sciences are the research field whose evidence reshapes this position: they

describe and test how learning happens and which designs change it, while this page covers the classroom role that has to act on that evidence in the moment.

How AI transforms teaching

- **From instructor to orchestrator:** Five levels of teacher-AI teaming and agency orchestration research map the spectrum from AI as tool to AI as teaching partner. At the far end, the teacher orchestrates a team that includes human learners, AI tutors, and curriculum resources rather than delivering all content themselves.
- **Workflow transformation:** How AI Is Changing Teaching Workflows. documents how AI shifts teacher time from content delivery to higher-value activities like individual support, Feedback, and Curriculum Design. The teacher's scarcest resource — attention — is reallocated from producing materials to interpreting learners. A systematic review of language educators (Li et al. 2026) corroborates this: educators value GenAI most for preparatory work (lesson planning, materials creation, writing support) while hesitating on live classroom use, and their adoption is shaped by professional-identity, pedagogical, technical, institutional, and academic-integrity factors — with competency gaps mapping to episteme (understanding AI's capabilities/limits), techne (Prompt Engineering, AI-enhanced task/assessment design, detecting AI-generated text), and phronesis (ethical judgment, bias/privacy handling, context-sensitive judgment). documents how AI shifts teacher time from content delivery to higher-value activities like individual support, Feedback, and Curriculum Design. The teacher's scarcest resource — attention — is reallocated from producing materials to interpreting learners.
- **Competency demands:** Teacher AI competency frameworks define what educators need to know, from basic tool fluency to pedagogically grounded orchestration. Adoption studies identify the real barriers: confidence, institutional support, and workload concerns. Bai & Hsieh (2026) add an empirical weight to this in an SEM of 898 Chinese university teachers: GenAI-supported teaching innovation depends less on isolated AI technological knowledge and more on pedagogically and disciplinarily embedded AI competence (AI Literacy and professional identity), both of which partially mediated the competence → innovation relationship — a signal to build faculty development around embedded, identity-linked AI competence rather than tool-only training.
- **Readiness as a design capability, not an attitude:** Charles (2026) argues that teacher readiness for AI-rich interactive learning cannot be read off adoption, confidence, or digital competence, because none of these predicts the quality of the designs teachers actually produce. Readiness-by-design is enactment-oriented: teachers mobilize AI-related pedagogical knowledge, pedagogical beliefs, Self-Efficacy, and ethical orientation through *design mediation* (tool selection, task and prompt design, scaffolding, transparency, verification, assessment redesign, accessibility planning, and human oversight) inside an institutional and policy ecology that enables and moderates the translation. Two claims carry practical weight. Self-efficacy is a mobilization resource rather than a quality indicator, so confidence without AI-related pedagogical knowledge or ethical orientation can accelerate poor design. And policy clarity and material support are separate moderators, so a well-resourced school can still leave teachers guessing what is permitted. Charles also declines to

equate non-use with unreadiness: a reasoned decision to withhold AI can itself demonstrate readiness.

- **Co-design and agency:** Teacher-authored prompts and vibe coding for teachers show educators as active AI designers, not passive consumers — writing the prompts and scaffolds that shape how AI behaves for their students. In children's STEAM arts lesson planning, Luo and Tahir (2025) experimentally confirmed that *how* the teacher delegates to ChatGPT matters: filling content gaps in a self-outlined lesson (the method favored by 60% and recommended) preserved teacher design autonomy while still raising expert-rated plan quality (median 20.5 vs. 17.6, p = .002, large effect), outperforming having AI generate whole plans or merely checking a finished one. AI served chiefly as an inspiration and gap-finding collaborator rather than a source of fully original innovation — reinforcing that the teacher remains the design agent and judge of output, including catching child-safety and cultural-bias flaws the tool missed. A systematic review of teacher–AI co-design of learning tasks (Wang, Liu & Islam 2026) finds this co-designer stance remains uneven — the dominant mode is still AI as assistant/content generator — and Talebzadeh (2026) shows the teacher's agency as "bilingual learning designer" is what turns AI-designed group activities into differentiated, ZPD-aligned instruction.
- **Authoring a bot is not the same as controlling what it teaches.** Twenty-seven middle school teachers who configured a purpose-and-rules chatbot authoring tool saw only partial fidelity in the generated behavior - alignment fell from 88.9% for responsiveness and 81.5% for persona to 70.4% for rules and 59.3% for purpose, and rule adherence varied by the model chosen. That is the execution/evaluation gap that makes the teacher-as-designer role a rehearsal of intent rather than a guarantee of it (Riahi et al. (2026)).
- **Preservice preparation:** TPACK-based training and Educational Development programs prepare future teachers for AI-augmented classrooms before they enter them. Simulated-student role-play extends this into hands-on practice: a custom ChatGPT bot (Student GPT) playing a mathematically misconception-ridden middle schooler lets preservice teachers rehearse diagnosing and guiding student reasoning in a low-risk setting, preparing them for a central teaching task — reading and remediating student thinking.
- **A teacher-facing frontier the evidence base has barely entered:** Štefánik et al. (2026) assemble **Edustories**, 1,492 teacher-written case studies of real elementary and high-school classrooms — challenging student behavior, the intervention the teacher attempted, and what followed — precisely because most AI-in-education research has targeted individualized student assistance while most teaching happens in collective classrooms. Benchmarking four language-model families on predicting whether an intervention succeeded, the strongest models reached 58% accuracy against 64% for human experts; the authors read the gap in both directions, as a limit on current teacher-facing assistance and as evidence of emerging potential. What the page gains from it is a measured ceiling rather than a capability claim: advice to teachers needs to be better than expert judgment before it can be trusted, and today the ordering is the other way. A parallel gap appears in Yalçın et al.'s (2026) PRISMA review of 46 empirical studies of GenAI in higher-education programming: instructor roles and institutional practices were among the least studied areas of the field, and 26 of the 46 studies gave no codable description of their instructional

approach, so the design decisions that produced reported outcomes are often invisible even to other instructors.

- **Where AI actually enters the work, by task:** Holster (2026) separates adoption from allocation using TALIS 2024 data from 56,669 teachers, with an allocation sample of 24,058 AI users across 46 education systems. A task rated one point above a teacher's own mean demand was more likely to receive AI help (OR = 1.163), but the direction differs by task. Planning rises with demand (OR = 1.084), assessment and marking falls (OR = 0.921), and Special Education support and adaptation rises steeply (OR = 1.442, a predicted spread from 34.0% to 50.3% across the demand range). The competency and policy reading is that teachers already keep high-stakes marking human while reaching for AI on individualized adaptation work, so guidance that treats teacher AI use as a single behavior will miss where support is actually needed.

What the changing role actually looks like: concrete examples

The abstraction "orchestrator" is easier to grasp through concrete, day-to-day shifts in instructor work:

- **From writing every handout to curating AI-generated drafts.** An instructor who once spent an evening building a differentiated worksheet now prompts an AI to produce three versions at different difficulty levels, then spends the same evening *reviewing and adapting* them — a shift from authoring to editorial judgment. Curriculum-as-Code workflows make this pipeline explicit, and Kibar & Ilgaz's systematic review shows AI acting as a "co-worker" that drafts content the designer then refines. Expert validation of AI-generated science lesson plans makes explicit what that editorial judgment must weigh: Karaismailoglu, Surmeli and Yildirim (2026) found eleven Science Education specialists rated ChatGPT-4 and an education-focused tool's sixth-grade plans as usable drafts — 7 of 11 judging them "applicable by correction," only 3 directly "Applicable" — and preferences diverged from raw scores (7 preferred the higher-scoring education-focused tool, 4 the general-purpose plan) because judgment weighed affective and contextual dimensions beyond structural fidelity. Teachers remain the arbiters of whether and how an AI draft becomes a teachable, contextually grounded lesson.
- **From lecturing to real-time coaching.** Rather than delivering the same explanation to the whole class, teachers increasingly route routine questions to an AI tutor and focus face-to-face time on the students who need human judgment — workflow studies document exactly this reallocation of attention.
- **From grading to designing assessments that AI can't game.** Instructors stop relying on recall-based tasks that LLMs trivially solve and instead design authentic assessments, assessment scales, and formative tasks that preserve Learning Gains.
- **From teaching content to teaching *use*.** The teacher's job increasingly includes modeling how to prompt, evaluate, and responsibly use AI — an AI Literacy curriculum woven into every course, not a separate subject.
- **From reading dashboards to acting on them — contextually.** Mejia-Domenzain et al. (2026) show that how teachers actually use analytics dashboards diverges by context: flipped-classroom (university) teachers followed a sequential exploration and favored course-level adaptation and showing dashboards in class, whereas vocational teachers revisited summary pages and used the

tool mainly for individual coaching sessions. The actions teachers proposed were shaped by the content represented and their teaching level rather than the plot type — university teachers favored weekly tests and course adaptation, vocational teachers direct, individualized coaching. This points to context-aware dashboard design and differentiated teacher support needs rather than a one-size-fits-all analytics interface.

- **From receiving alerts to judging them.** Swidan (2026) followed one teacher and eight high-achieving high school students in a GeoGebra geometry lesson where Dash4Emotion framed students with red rectangles signaling negative emotion, and found that the alerts did not drive outcomes — the teacher's move after each alert did: reframing Mira's task from finding a minimum value to the geometric locus of minimal points reopened her exploration, three simultaneous alerts prompted a whole-class reframing, and one period's deliberate non-intervention was itself a pedagogical decision. The study's stance is that an AI-generated emotional alert is a cue to be interpreted alongside what the teacher can see, not an instruction to be obeyed.
- **From gatekeeper to principled facilitator of collaboration feedback.** The Community Builder (CoBi) classroom pilots show the teacher role decisively shapes *implementation integrity*: teachers who used the AI's noticings and visualizations to spark Metacognition and critical reflection about collaboration achieved high-integrity use, while those who let the system drift into performance-monitoring — or veer off into general AI discussions — did not. Teachers also worried about being put "on the spot" by real-time feedback and preferred pre/post-action review over live display, underscoring that orchestrating classroom-wide collaboration AI demands substantial professional learning, not just tool fluency.
- **From instructing with AI to standing in for it.** Where the Digital Divide leaves no device for each student, the teacher can become the *physical interface* to the system — a proxy rather than an orchestrator of it. In Rodrigues et al.'s (2026) "AIED unplugged" model, students keep working with paper and pen while the teacher photographs their solutions, and the AI returns personalized exercise lists and error-specific Feedback to be handed back. This is a clustered quasi-experiment across 19 authentic Brazilian elementary classes rather than a prototype demonstration, and its two results bear on the role directly. First, the learning advantage over usual practice came from a single 50-minute *teacher-training* session, not the technology: the training and training-plus-system conditions did not differ on gains (−4.33, 95% CI [−17.29, 7.23]), so preparation, not the tool, is the active ingredient. Second, the system's own benefit ran *indirectly, through the teacher* — reduced Effort mediated a positive effect on gains (3.649, 95% CI [1.097, 6.398]) — so the effect reaches students the AI never touches, and the capture-and-verify labor the teachers described (photographing sheets, waiting for processing, correcting recognition errors) is part of the pedagogical cost of extending AI to under-resourced classrooms.
- **From information provider to learning designer.** Hochberg and Waitzman (2026) followed 93 teachers through an eight-week AI program and found practice shifting toward heutagogical design for learner agency, though the self-reported shifts were not significant after adjustment and learner outcomes were not measured.

The orchestration metaphor

The dominant metaphor in the knowledge base is *orchestration*: teachers coordinate human learners, AI tutors, and curriculum resources. This contrasts with replacement narratives — AI augments rather than substitutes for human teaching. Empirical evidence supports this stance: a PRISMA-guided systematic review of 42 studies (2023–2025) found LLMs match human raters on short, well-structured tasks but that performance declines on longer, multilingual, and nuanced work — concluding LLMs cannot fully replace teachers and that hybrid, human-in-the-loop assessment systems achieve the highest grading effectiveness (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback). The orchestration lens reframes the instructor's core skill as *judgment*: deciding when a human, an AI, or a designed learning activity is the right instrument for a given learner and moment. A 2026 PRISMA review of 29 studies of Teacher intervention in K-12 AI-based instruction: a systematic review of processes, strategies, and effects sharpens the metaphor into a four-phase cycle — monitoring, judgment, intervention, orchestration — and shows why no phase can be assumed. Teachers preferred shared control, accepting, modifying, rejecting or overriding AI suggestions; some deferred intervention deliberately so students could struggle productively first; and dashboards that expanded awareness could also overload attention or exceed what one teacher could physically act on. Its three strategies — pedagogical translation of AI output, design of learning support, and reconstruction of interaction structures — describe the work as recontextualization rather than approval, which places the teacher closer to mediator than to the human-in-the-loop reviewer role. Classroom observation names the same behaviors as types. Six lessons with an experienced teacher added three orchestration types to Drijvers' four — dashboard-monitoring, AI-correcting and AI-mediating — with the teacher's content and ethical roles most visible when he corrected AI-generated feedback (Noh & Kim, 2026).

Evolving and critical teacher roles

Recent work expands the orchestration metaphor into richer role conceptualizations:

- **Co-orchestrator across activity transitions.** Yang et al. (2026) use participatory speed dating with 17 teachers and 13 students to map how control should be distributed across the stages of a classroom activity — the before, during, and after transitions between individual and collaborative work — in a co-orchestration tool supporting real-time dynamic pairing. The design principle that emerges is that control is *not* a fixed point: teachers and students want different amounts of agency at each stage, and the tool should let the teacher adjust grouping, activity transitions, and intervention timing in real time while retaining a teacher override. This positions the teacher as a **co-orchestrator of the whole live learning environment** — a role more specific than the general orchestration metaphor, focused on the granular, moment-to-moment decisions of who works with whom, when, and with what support — and it connects individual-tutoring research to classroom-level design.
- **The "cognitive choreographer."** Posthumanist frameworks recast the teacher as a *cognitive choreographer* who orchestrates cognition distributed across biological and artificial systems, moving beyond instrumentalist models like Technological Pedagogical Content Knowledge (TPACK) and SAM.(Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI)

- **Facilitator, co-investigator, ethical supervisor.** In science learning, teachers' roles shift from knowledge transmitters to facilitators and co-investigators, and gain new responsibilities as ethical supervisors of students' responsible AI use.(Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers' Perspectives)
- **Mediator of learning principles.** Educators operationalize age-old learning principles (experiential, situated, and distributed cognition) through AI, treating AI as a tool that enhances rather than replaces the educator's guiding role.(Empowering Educators: Operationalizing Age-Old Learning Principles Using AI)
- **Critical mediator who turns AI output into an object of critique.** Canonigo (2026) followed ten secondary mathematics teachers through an eight-week ChatGPT-4 intervention and identified five mediation practices: AI-generated problem posing, hint scaffolds designed to fade, critical comparison of AI output against students' own work, differentiated prompting (a visual analogy for a struggling student, a cubic extension for a peer), and AI as a reflective dialogue partner. Where teachers enacted these, output became something to argue with rather than an answer key, and students moved toward conjecture and metacognitive questioning; where mediation was absent, authority migrated toward the algorithm, with students consulting the AI before their teacher and returning only for validation, prompting one teacher to describe the move from "oracle" to "editor." The study's equity finding is the sharp one: across 300 model responses, the free-tier model was inaccurate in 32.7% of instances against 12% for the premium model ($\chi^2(1) = 17.5$, $p < .001$), so teachers in the under-resourced school called it "borderline useless for mathematics." Tool quality, not just tool access, becomes a pedagogical variable, and one teacher's school acceptable-use policy was a decade old and silent on AI, leaving the governance gap to the classroom.
- **Unsettled and vulnerable professional identity.** Farazouli et al. (2026) document the *emotional* side of role reconfiguration: 24 Swedish university teachers experienced GAI's emergence as alarming and overwhelming, reporting a "state of vulnerability" (low confidence, insecurity, fear of "not being ahead of students") and feeling "stuck" between utopian and dystopian discourses. GAI prompted them to re-evaluate their priorities — cultivating Critical Thinking, Evaluative Judgment, and ethical GAI use — and to question their own and the university's future role in a landscape that felt "out of control." This frames the teacher-role shift as identity-level and emotionally charged, not merely a skills or workflow change.
- **Academic developers as digital mediators, including as a brake.** Sithole (2026) interviews twelve academic developers and learning designers at two South African Historically Disadvantaged Institutions and finds the role shifting from facilitating reflective teaching toward technological intermediary and problem-solver, with mediation spanning pedagogy, ethics and institutional politics. The distinctive move is treating slowing down as part of the job: one participant describes translating between "what management wants, what the technology can do, and what lecturers are actually worried about," and naming plagiarism, student dependency and the outsourcing of thinking before enthusiasm sets the pace — "It is not just technical support; it is also negotiation." The same study documents the affective cost ("I feel like an impostor. I am learning AI as I go, but the institution expects expertise") and the professional-learning response: peer spaces that test and deliberately break tools, aiming at judgment rather than skill, and an explicit refusal of the adoption-or-resistance binary — "I am not anti-AI; I am pro-context."

- **Principled selectivity instead of adoption or resistance.** Adiozaman and Segar (2026) interviewed two academics with more than ten years' experience three times across a single semester and found identity work organized around three interrelated tensions — pedagogy versus platform, educator versus facilitator, and care versus compliance — which resolved not into a settled position but into *principled selectivity*: context-sensitive decisions guided by pedagogical values, ethical commitment and professional judgment. They describe a trajectory from implicit orientation, through mid-semester strategies such as asking students to explain their thinking and redesigning tasks and assessment, to stances that stayed deliberately open rather than fixed, with refusal of a particular use treated as a legitimate exercise of judgment rather than a failure to adopt. This supplies the constructive counterpart to the vulnerability documented above: what the role shift demands is judgment, so institutional responses built around tool training address the wrong problem.
- **Semi-autonomy as the preferred operating point.** Dai et al. (2026) surveyed 287 GenAI-experienced teachers in 27 countries and regions and found them placing the tool at the *semi-autonomous* levels of an automation scale — 130 chose Level 2 ("teacher assistance"), 94 Level 3 ("partial automation"), and exactly one chose Level 6 — describing it as "auxiliary", "scaffold", "complement" or "partner". Perceived usefulness dominated their adoption intention ($\beta = .832$, $p < .001$), while perceived artificial autonomy influenced intention only indirectly through usefulness, and risk aversion depressed intention without denting usefulness because their worries attached to *students'* use — cheating and integrity, weakened foundational knowledge and higher-order thinking, hallucinations, reduced human interaction, and ethical, legal and Equity risks. The authors' "frenemy" label captures the stance precisely: GenAI valued as a support tool but distrusted as an autonomous agent. The corollary for the teaching role is that teachers want to remain the deciding agent and to settle use case by case — discipline, student needs, task type, timing — so orchestration tools should be built around human oversight and case-level judgment rather than autonomy promises.
- **Authority stays with the teacher; capability expands only inside it.** Reichert, Briceno, Tabarsi & Barnes (2026) gave six secondary teachers across grades 6-12 (social studies, mathematics, animal science, science, and computer science and robotics) the task of paper-prototyping an LLM chatbot for their own classroom, and found that every prototype encoded the same stance: the system was a *bounded expert*, specialized but confined to a defined domain and supervised by the teacher. Teachers drew two boundaries. *Authority* boundaries followed from professional and legal responsibility — control over what students learn and how they are kept safe could not be delegated, so oversight (complete conversation logs, real-time alerts for inappropriate queries, and manual override) was treated as a duty of the role rather than a check on the tool. *Expertise* boundaries followed from what the model cannot know: individual students' histories, classroom dynamics, and institutional norms. Delegation was then allocated selectively across instruction — teachers welcomed AI to present content, supply practice problems, scaffold, and give formative Feedback, but kept informing students of objectives and summative Assessment themselves. This supplies the semi-autonomy preference documented above with a concrete architecture: the teacher's authority is the fixed element and AI capability grows only within it.
- **Teachers as value-laden graders.** Luo & Dawson (2026) show that grading GenAI-assisted work is not a neutral, criteria-based act but a value judgment shaped by teachers' conjecture about who

the student is (honesty, diligence), what they are capable of (independence, GenAI skill, disciplinary mastery), how they relate to others (trust), and whether the decision leads to good outcomes (fairness, beneficence). Teachers often lack awareness of the value orientations underlying their grading, and these vary by discipline (humanities more critical of GenAI use; hard/applied sciences fewer grading challenges) and epistemological stance (absolutist/multiplist/evaluativist). This positions the teacher as an evaluative professional whose judgment — not just tool use — must be supported and made transparent.

- **Teacher as the arbiter of pedagogically meaningful explanations.** Because teachers' trust in AI recommendations rises when explanations are framed in *their* curricular/pedagogical language rather than in raw model internals, effective tools must "speak" the teacher's domain. In a within-subject experiment, Feldman-Maggor et al. (2025) found domain-driven explanations of an AI grouping tool were trusted and accepted far more than data-driven feature-importance ones, positioning the teacher's pedagogical vocabulary as the interface through which AI earns trust and use — and their judgment of whether an explanation is pedagogically sound as a deciding factor in adoption.
- **Facilitator whose function can be partly delegated.** Kuhail et al. (2026) had 32 STEM students debate under a human moderator, an AI chatbot (GPT-4, prompted with the behaviors expected of faculty: neutrality, equal speaking time, short directions, on-topic enforcement, follow-up questions, de-escalation), or each in turn. They found no significant difference on effectiveness, enjoyment, satisfaction, utility, or intention to reuse ($t = 0.23$ to 1.30, $p = 0.198$ to 0.818). The authors read the null result as normalization of human-AI collaboration in rule-bound discussion, not as equivalence. The route to reuse did differ: under human moderation satisfaction drove intention to use, whereas under AI moderation perceived utility did (0.806 against 0.495), so an AI-facilitated activity survives on demonstrated usefulness rather than on how enjoyable it feels. The practical reading is AI moderation as a scaling aid for large or lightly staffed courses under human oversight, with equity unverified for sarcasm, indirect language, and minority communication styles.
- **Setter of purposes, not just competencies.** Fagerlund et al. (2026) interviewed 13 Finnish teachers from preschool to grade 9 about why students should learn about and with AI, reading their accounts through Biesta's qualification, socialization, and subjectification. Qualification was the clearest and most concrete purpose, covering AI as both a target of learning and a tool for it; socialization appeared as cultivating favorable stances toward AI and preparing students as AI-savvy future workers; subjectification, self-determined and personally meaningful engagement, was endorsed as important but had no concrete instructional strategies behind it, resting on "discussing and contemplating." The authors propose *informed AI agency*, subjectification at the center with competencies as its foundation, which gives the teaching role a purpose-setting duty: make the "why" explicit so skills acquire context rather than standing as ends in themselves, and complement technical frameworks such as Technological Pedagogical Content Knowledge (TPACK) with sustained attention to educational purpose.
- **Adoption is not the same lever as performance.** Across 200 teachers in North Sumatra, AI use had no direct effect on teacher performance ($\beta = 0.112$, $p = .087$) while organizational citizenship behavior mediated it at $\beta = 0.370$, so it is the extra-role, collaborative work around the tool rather than the tool itself that converts use into performance (Sherly et al. (2027)).

These roles connect teacher work to Distributed Cognition, Situated Learning, Embodied Learning, and Critical Pedagogy, and reframe the teacher as a designer and ethical guide of AI-mediated learning rather than merely a user.

- **AI-supported decisions cluster where behavioral data is available.** Köroğlu et al. (2026) reviewed 27 empirical studies (2016–2025) and identified eight lecturer decision types, finding AI support concentrated on instructional, Feedback and Assessment decisions while curriculum, learning-environment, emotional, ethical and administrative decisions were rarely supported. Learning Analytics Dashboards were the most common system, processing text and log data into behavioral indicators of performance and engagement; Multimodal AI and interaction-based data, agentic systems and cognitive, metacognitive, motivational and affective outcomes were all comparatively rare in the reviewed corpus. The practical reading for instructors is that the decision space an AI tool opens is bounded by the data it displays, so tool selection is also a choice about which teaching decisions are being resourced.

How instructors should adapt their teaching practices to AI

The knowledge base's evidence converges on a set of concrete adaptations:

Design the AI's pedagogical wrapper, not just the tool. The same AI yields large Learning Gains or net harm depending on how the activity is designed around it. Kibar & Ilgaz and the Learning Gains evidence are consistent: the instructor's job is to *design the learning experience*, treating AI as a component within a structured activity rather than the answer engine. Scaffold a student attempt first, then let AI coach — this is the difference between assessment and performance inflation.

Require a Human-in-the-Loop checkpoint. Rather than accepting AI output at face value, teach students to evaluate, correct, and take ownership of AI-assisted work. Fair-use AI literacy frames this as balancing AI's productivity against genuine human flourishing and authorship. Design assignments so AI helps with drafting but the learner remains the agent of evaluation and revision.

Curate AI feedback drafts; do not relay them. Chen et al. (2026) gave 64 Chinese pre-service teachers ChatGPT-assisted feedback on argumentative writing and found that treating the output as draft material rather than finished comment moved critical thinking where teacher-only feedback did not (post-test Cohen's d of 3.74 against 0.25 at pretest, $p < .001$). What the teachers did with the draft is the transferable part: they copied appropriate content at a level similar to their own (28%), expanded it with deeper input (16%), supplied it (16%), revised it (14%), or discarded it entirely (14%), with a further 9% needing correction. The assisted feedback leaned toward modeling (demonstration, 33.1% against 10.9%) and probing (question-closely, 21.5% against 6.0%), and students revised it toward analysis, evaluation, and creation rather than recognition, but six of eight interviewees still reported imprecision and unprofessionalism. The teacher's verification step is what makes the hybrid safe.

Adapt assessment to the age of AI. Move away from tasks LLMs can complete verbatim toward authentic, process-based, and in-person assessments. Assessment scales give instructors a rubric for deciding how much AI assistance is legitimate at each stage, and meta-analytic evidence shows AI can support higher-order thinking when the assessment design demands it.

Protect the conditions for durable learning. Because AI answers make learning look easy, instructors must design to counter the performance-learning gap. Lodge & Loble warn that effortless success with AI can mask the absence of learning; instructors should build in productive struggle, require unassisted demonstration of mastery, and treat AI-supported answers as a starting point, not the finished outcome.

Plan for the delivery medium. Adaptation is not medium-neutral: online teaching with AI multiplies both the opportunities (scalable personalization, always-on support) and the risks (integrity, offloading). Design the AI wrapper as deliberately in online as in face-to-face contexts.(Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation)

Incorporating AI literacy into teaching

AI literacy is not a separate module — it is woven into how instructors design every course. Effective approaches include:

- **Model AI literacy in practice.** Teachers who themselves use, evaluate, and critique AI set the norm for students. AI literacy continua describe the progression from tool fluency to critical evaluation that instructors should scaffold.
- **Teach evaluation and calibration, not just use.** Students need to know when AI is trustworthy and when it hallucinates — Critical Thinking about AI outputs is a core literacy. This connects to responsible use and how AI use is framed for students.
- **Co-construct AI-use norms with students.** Principled approaches to AI education and teacher-authored prompts show that explicit, co-designed expectations work better than punitive rules.

Ensuring academic integrity in the age of AI

Academic integrity with AI is a *design* problem, not a policing problem. Instructors adapt by:

- **Reframing integrity around process and authorship.** Instead of detection, emphasize Academic Integrity as transparent, documented use. Agentic AI and ghost-student research shows the integrity risk shifts when students deploy AI agents on their behalf, so instructors must define what authorship means when the "ghost" is an AI.
- **Using disclosure and framing.** How AI use is framed for students — whether as a crutch or a legitimate tool — shapes whether they disclose it. Transparency norms (e.g., AI-use disclosure) reduce the incentive to hide AI use.
- **Designing out the incentive to cheat.** Authentic, process-based, and in-person assessments (oral exams, portfolios, observed Problem Solving) make outsourcing less attractive than AI-detection tools do. Assessment scales and Authentic Assessment are the constructive alternative to detection arms races.
- **Task-level AI Regulation in Education is how instructors actually govern AI.** Chirikov's (2026) study of 31,000+ course syllabi shows instructors increasingly acting as *task-level regulators* rather than applying blanket rules: they restrict AI for drafting/revising (79% of courses) and reasoning/problem-solving (65%), permit it for editing/proofreading (83%) and study support (80%), and leave ideation/planning most contested (46% permit / 54% restrict). This differentiation — built on which tasks AI displaces versus augments — is a concrete, instructor-

driven alternative to adoption-or-ban policy and gives the teacher-role a central place in policy formation.

- **Sessional staff carry the marking load without the mandate.** Twenty casual academics, some teaching across three or more institutions at once, described detecting misconduct through untrained craft while holding no curriculum or policy authority (Andriamora & Andriamora, 2026).

Connecting teaching to learning design

Teaching and Learning Design are two sides of the same coin — the instructor's daily judgments are the live execution of the designed learning experience. AI tightens this connection:

- **Teachers as learning designers.** LearnAI and teacher-authored prompt design show instructors functioning as designers: specifying the activity, the AI's role, and the scaffolds that structure learning. This is Learning Design in action at the point of use.
- **Learning-design principles govern AI pedagogy.** The same Learning Design principles — clear objectives, aligned assessment, Scaffolding, and Feedback — determine whether AI helps or harms. ISD-Agent-Bench empirically validates that grounding AI design in formal instructional-design models beats theory-free prompting.
- **Design for the teacher's orchestration.** Effective AI learning environments are designed *with the teacher in mind* — the tools human-centered AI provide should reduce teacher workload and augment judgment, not add another opaque black box. When instructors co-design AI learning activities (activity-theory perspectives), adoption and quality both improve.

Relationship to learner identity

Teacher role and Learner Identity are reciprocal faces of the same human process, and AI reshapes both.

- **Teacher identity is a professional identity; learner identity is a learning identity.** The teacher-role page documents how AI reshapes the *work, identity, and agency* of educators — their evolving professional self-understanding (see Laidlaw's framing of GenAI as an identity crisis). Learner identity is the parallel construct for students: who they are and are becoming as learners, in disciplinary, professional, creative, and academic terms.
- **They are causally coupled.** Teachers who experience identity disruption (uncertainty about their professional purpose amid GenAI) are less able to support their students' identity development — a teacher who doubts their role struggles to validate students' emerging sense of self in the same domain. Conversely, teachers who sustain a confident professional identity are better positioned to scaffold students' belonging and authorship.
- **Distinct failure modes.** Teacher identity is threatened by *role obsolescence* and *purpose* (the "what's the point of teaching?" question). Learner identity is threatened by *authorship loss* and *competence* (the "is this really mine / am I good enough?" question). Both are identity-level (not just skills-level) responses to AI.
- **Both are professional-development and pedagogical concerns.** Supporting teacher identity belongs to Educational Development and Teacher AI Competency; supporting learner identity

belongs to Student Experience, Authentic Assessment, and Learner Agency. A well-designed AI-integrated system attends to both — because the teacher's identity is the condition under which learners' identities form.

Teacher Co-Design of Early AI Literacy

- **Teacher co-design in early AI literacy.** Lee (2026) shows that two pre-K and two kindergarten teachers who co-designed the Play With AI (PL-AI) curriculum experienced substantial growth in confidence and pedagogical agency, with co-design fostering curriculum ownership, reflective practice, and meaningful adaptation. This positions teachers as central co-designers — not just implementers — of developmentally appropriate AI literacy curricula, a model with implications for teacher preparation in early childhood AI education.

Teachers Co-Designing AI Learning Resources

- The teacher's role extends to co-designing AI learning resources: teacher-AI co-designed simulations for drone STEM instruction kept GenAI output pedagogically valid and contextually relevant, and teachers are the intended beneficiaries of the Teachers' AI Literacy Scale. Effective GenAI integration increasingly depends on teacher involvement in design.

AI Reflection Systems Should Adapt to Teacher Experience

- **Teacher-facing AI reflection analytics should be expertise-adapted, not one-size-fits-all.** A survey of 100 US K–12 teachers (median split at nine years; binomial tests; 15% choice differences detectable at ~83% power) found systematic preference splits. Less experienced teachers cite lack of reflection time as a top obstacle at 3x the experienced rate (37% vs. 12%, $p < .001$) and want analytics on student disengagement (48% vs. 33%, $p = .028$) and emotions (31% vs. 18%, $p = .036$).
- **The design rule derived from the split is experience-adapted recommendation modes.** Experienced teachers want analytics on improved learning after helping a student (40% vs. 26%, $p = .019$) and on their teaching methods (42% vs. 26%, $p = .012$); their top obstacle is tracking performance (28% vs. 15%, $p = .009$). Design rule: novice mode = structured prompts and engagement analytics; expert mode = flexible longitudinal analysis — a direct argument against uniform dashboards. (How expertise levels shape preferences and reflection needs — towards AI reflection systems for teacher empowerment)

Common Misconceptions

"AI will reduce or replace the pedagogical work of teaching." The expert scenario evidence points the other way. Malyn-Smith et al. (2026) call it the *more-human paradox*: across six 2030 scenarios co-constructed by 20 researchers from 13 countries, AI saturation **intensifies rather than displaces** human pedagogical work. The scenarios describe AI as "the air-handling system of the learning ecosystem" — infrastructure you notice only when it malfunctions. What changes is not the quantity of human judgment required but its object: attention moves from producing materials toward interpreting learners.

“Teacher AI competence means learning the tools.” Tool fluency is the weakest predictor available. In Bai and Hsieh’s (2026) SEM of 898 Chinese university teachers, GenAI-supported teaching innovation depended *less* on isolated AI technological knowledge and *more* on pedagogically and disciplinarily embedded AI competence together with professional identity, both of which partially mediated the outcome. A workshop on features that does not touch pedagogy or disciplinary identity is aimed at the wrong variable — which is why Laidlaw et al. frame faculty GenAI response as an identity question rather than a skills gap.

“Teachers are already co-designers of AI, so the transition is underway.” The aspiration is real; the description is not yet. Wang, Liu and Islam’s (2026) systematic review of teacher–AI co-design of learning tasks finds the co-designer stance **remains uneven**, with the dominant mode still AI as assistant or content generator. Reading that review as evidence of an accomplished shift would hide the gap between the teachers a page like this recommends and the teachers most institutions actually have.

“How a teacher delegates to a chatbot barely matters, since the model does the work.” The delegation pattern is the intervention. In children’s STEAM arts lesson planning, Luo and Tahir (2025) found experimentally that filling content gaps in a *self-outlined* lesson preserved teacher design autonomy while still raising expert-rated plan quality (median 20.5 vs 17.6, p = .002, large effect), outperforming the alternative of letting the model supply the outline. Same model, same task, different division of labor, materially different result.

A Practical Starting Sequence

The evidence supports a specific order of operations for an instructor adopting AI, rather than a list of features to learn.

1. **Write the activity before choosing the tool.** Specify the objective, the student attempt that comes first, and what counts as evidence of understanding. Tools chosen first tend to rewrite the activity around themselves.
2. **Decide the delegation pattern explicitly.** Outline the lesson yourself and let AI fill content gaps, rather than accepting a generated outline — the pattern above with the measured quality difference.
3. **Place the human checkpoint where ownership sits.** Design so the learner evaluates, corrects, and owns the AI-assisted work, and so AI feedback arrives as a draft the teacher curates rather than a comment the teacher relays.
4. **Protect the interpretation time the shift creates.** If attention moves from materials production to reading learners, that reallocated time needs to survive contact with the calendar; if it is absorbed by new administrative work, the promised role change does not occur.
5. **Check whether you are being trained on tools or on pedagogy.** Given the SEM result, prefer professional development that works on disciplinary tasks and identity over feature tours.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities
- Business Education

- Educational Development
- Teacher AI Competency
- AI Literacy
- K-12
- Higher Education
- Scaffolding
- Learning Design
- Intelligent Tutoring
- Large Language Models (LLMs)
- Workplace Learning
- Distributed Cognition
- Situated Learning
- Critical Pedagogy
- Teacher Education
- Learning Sciences
- Academic Integrity
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Reflection

Connected Articles

- Artificial learning: how sessional academics view contract cheating and digital academic misconduct in assessment — Casual academics carry the integrity work without the authority
- Navigating AI's educational future: expert scenarios and implications for teaching and teacher preparation — The more-human paradox: expert 2030 scenarios find AI saturation intensifies rather than displaces human pedagogical work (Malyn-Smith et al. 2026)
- Exploring Teachers' Instrumental Orchestration and Roles in High School Mathematics Classes Using AI-Based Digital Tools — Six observed high school mathematics lessons extend instrumental orchestration with three new types (Noh & Kim 2026)
- Responding to AI-generated emotional alerts: teachers' intervention and students' engagement in the mathematics classroom — Responding to AI-generated emotional alerts: teachers' intervention and students' engagement in the mathematics classroom
- Edustories: A Collection of Real-world Case Studies from Classroom Practices — Edustories: A Collection of Real-world Case Studies from Classroom Practices
- Human-centered design of LLM-powered educational chatbots: A study with secondary teachers — Teachers design classroom chatbots as bounded experts and retain authority

- GenAI as a frenemy in teaching: Perceived autonomy and risks — GenAI as “frenemy”: teachers prefer semi-autonomy, usefulness drives adoption, risk aversion targets students’ use (Dai et al. 2026)
- AI-Supported lecturer decision-making in higher education: a socio-technical perspective — AI-Supported Lecturer Decision-Making in Higher Education
- How Instructors Regulate AI in College: Evidence from 31,000 Course Syllabi — How instructors regulate AI across 31,000 course syllabi; task-level regulation (Chirikov 2026)
- AI Teaching Innovation Behavior Among College Teachers: A Structural Equation Modeling Analysis Based on the AI-TPACK Framework, Teaching Self-Efficacy, Professional Identity, and AI Literacy — AI teaching innovation behavior among college teachers (AI-TPACK SEM; Bai & Hsieh 2026)
- Towards Synergistic Teacher-AI Interactions with Generative Artificial Intelligence
- Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing
- How AI Is Changing Teaching Workflows.
- Teacher-Authored Prompts for Configuring Student-AI Dialogue: K-12 Classroom Implementation
- When faculty ask, "what’s the point of teaching?": GenAI as identity crisis, not skills gap — GenAI as identity crisis, not skills gap
- Artificial intelligence, cognitive offloading and implications for education — AI, cognitive offloading and implications for education (Lodge & Loble 2026)
- The intersection of artificial intelligence and instructional design practice: A systematic review — AI and Instructional Design Practice: A Systematic Review (Kibar & Ilgaz 2026)
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- The Devil is in the Details: AI agents, ghost students, and the crisis of verified presence in an agentic AI world — Ghost students and agentic AI in assessment
- Reimagining teacher-AI co-design in learning task design: trends and perspectives — Teacher–AI co-design of learning tasks: trends and perspectives (Wang et al. 2026)
- Navigating uncertainty: university teachers’ experiences and perceptions of generative artificial intelligence in teaching and learning — University teachers’ experiences and perceptions of GAI: vulnerability, rethinking assessment, student learning at risk (Farazouli et al. 2026)
- Exploring value judgements in grading: will teachers mark down student work assisted by GenAI, and should they? — Value judgments in grading GenAI-assisted work: honesty, trust, validity, and two-way transparency (Luo & Dawson 2026)
- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms

- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- ChatGPT-assisted lesson planning for children's STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- Suitability of Artificial Intelligence Supported Lesson Plans from the Perspective of Science Education Experts
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- 'Resistance is futile?': identity tensions and principled selectivity in AI-integrated teaching — Identity tensions and principled selectivity in AI-integrated teaching (Adiozaman & Segar 2026)
- Teacher intervention in K-12 AI-based instruction: a systematic review of processes, strategies, and effects — Teacher intervention in K-12 AI-based instruction: a systematic review
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Academic developers as digital mediators: role reconfiguration, affective labor and judgment in South African HDIs
- Where Artificial Intelligence Enters Teacher Work — Where Artificial Intelligence Enters Teacher Work
- AIED unplugged, teacher workload, and numeracy learning: a clustered quasi-experimental mixed-methods study — AIED unplugged: the teacher as proxy between learners and the AI, 19-class quasi-experiment where training and indirect effort reduction drive gains (Rodrigues et al. 2026)
- Instructional Governance by Design: A Framework for AI in Computing Education — Instructional Governance by Design: A Framework for AI in Computing Education
- Will It Teach as Intended? How Teachers Configure Educational AI Chatbots — Will It Teach as Intended? How Teachers Configure Educational AI Chatbots
- Teacher Mediation and the Contingent Promise of Generative AI in Mathematics Education — Teacher mediation in mathematics: five critical-mediation practices, shifting authority, and the free-versus-premium algorithmic divide
- Teacher Readiness-By-Design for AI-Rich Interactive Learning — Teacher readiness-by-design: readiness as design capability, not adoption or confidence (Charles 2026)

- Effects of ChatGPT-Assisted Teacher Feedback on College Students' Critical Thinking Skills and Perceptions of Argumentative Writing — ChatGPT-assisted teacher feedback: teachers curate AI drafts rather than relay them
- From Competency to Agency: Teachers' Views of the Purposes of AI Education — From competency to agency: teachers' views of the purposes of AI education
- The Great Debaters Meet the Great Facilitators: How Debate Students Evaluate Human Moderators and Their AI Counterparts — Human versus AI debate moderators: equivalent ratings, different routes to reuse
- Mapping Research on Generative Artificial Intelligence for Programming Education: A Systematic Review — GenAI in programming education: a systematic review in which instructor roles are least studied
- From information providers to learning designers: heutagogical teaching practices in AI-enhanced education — From information providers to learning designers: heutagogical teaching practices in AI-enhanced education
- How expertise levels shape preferences and reflection needs — towards AI reflection systems for teacher empowerment — How Expertise Levels Shape Preferences and Reflection Needs: Towards AI Reflection Systems for Teacher Empowerment (Falhs et al. 2025)
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)
- AI Use, Work-Life Balance, and Innovative Work Behavior as Predictors of Teacher Performance: The Mediating Role of Organizational Citizenship Behavior — AI use had no direct effect on teacher performance; citizenship behavior mediated it (Sherly et al. 2027)

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- How Can AI Save Me Time as an Instructor?
- What Competencies Do Faculty Need in Regard to AI?
- How Do I Design Faculty Development for AI That Actually Changes Practice?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?
- How Do We Make a Simulated Student Behave Like a Real Learner?

Teacher AI Competency

> **Teacher AI competency** — the knowledge, skills, and dispositions teachers need to effectively, ethically, and equitably integrate AI into teaching and learning. It extends beyond technical tool use to include pedagogical integration, assessment literacy, ethical judgment, and the confidence to use AI well. Teacher AI competency is the teacher-side counterpart to AI Literacy, and is developed through professional development. It is central to how the teacher's role is transforming in AI-augmented classrooms.

Questions to Consider

- The page argues the teacher is 'the decisive factor' in whether AI improves learning — that tools only help when teachers can plan for them, scaffold use, and evaluate outputs. Does that match your experience, or do you think the tool itself matters more than the teacher?
- Teacher AI competency spans technical proficiency, pedagogical integration, assessment literacy, and ethical judgment. Which of these do you think teachers most lack, and which is hardest to train?
- The research documents a gap between teachers' self-perceived and actual AI skill. Why do you think people overestimate their readiness, and what would it take to close that gap honestly?
- An intensive professional-development program produced large gains in AI pedagogical skill in the research cited, suggesting technical-pedagogical skill is trainable. If that's true, why do so many teachers still seem unprepared — what's standing in the way?
- If a teacher can 'use AI well,' what does 'well' mean to you — and how would you know a teacher has achieved it rather than just adopted the tool?

Introduction

Teacher AI competency matters because the teacher is the decisive factor in whether AI improves learning. Research consistently shows that AI tools only translate into better outcomes when teachers can plan for them, scaffold student use, evaluate outputs, and integrate them into coherent instruction. The knowledge base's literature examines the *dimensions* of this competency, the *gaps* between self-perception and actual skill, and the *professional development* that builds it.

Nunez-Canal et al. (2026) connect faculty AI competency to student outcomes directly, using human capital and stakeholder theories on a survey of business and economics faculty to argue that universities' investment in faculty competency is not discretionary. - **Prompting training saves time but does not improve materials.** In a preregistered RCT with 204 teachers, Appel, Fervers and Piepenburg (2026) found ChatGPT improved the quality of lesson-preparation materials and cut preparation time by 34%, while prior AI training added a further 21% time reduction without improving rated quality (Appel et al., 2026). Trained teachers wrote longer prompts and iterated less; both routes reached equal quality.

Core competency dimensions

The knowledge base's research converges on several interconnected dimensions:

- **Technical proficiency:** crafting effective prompts for educational objectives, evaluating AI tools for pedagogical fit and safety, and troubleshooting failures in real time. An intensive GenAI PD program documented significant gains across all five AI-PCK components (overall $d = 2.36$), showing technical-pedagogical skill is trainable.
- **Specifying agent workflows:** when teachers configure a chatbot in natural language, the dominant failure is lost intent rather than wrong facts — bots skipped required workflow steps in 53.8% of end-user conversations and omitted expectation setup in 33.4% (Liu et al. (2026)), so writing ordered, explicit steps is a trainable competency dimension of its own.
- **Pedagogical knowledge is the decisive layer.** A cross-level study of secondary AI education (46 teachers, 2,832 students) found technical AI knowledge alone was insufficient — and could even slightly reduce students' perceptions of AI for social good — whereas pedagogical AI knowledge drove students' perceptions and their intention to learn AI. Competency frameworks should therefore weight pedagogical AI knowledge as the pivotal dimension, not a soft add-on.
- **Pedagogical integration:** mapping AI use to learning objectives, designing Scaffolding that supports student Metacognition and self-AI Regulation in Education, and integrating AI into instructional design. AI-TPACK research models how teachers combine technological, pedagogical, and content knowledge through multi-agent workflows, while a five-level teacher-AI teaming framework (transactional → synergistic) captures how GenAI may replace, complement, or augment teacher competence.
- **Assessment literacy:** evaluating AI-generated content and student AI outputs, and understanding how validity shifts when students use AI. This connects to Automated Assessment, AI Detection, and the broader Assessment redesign agenda. For recommendation systems, this extends to judging whether an AI's explanations are genuinely understandable and pedagogically meaningful: Feldman-Maggor et al. (2025) found teachers trusted AI grouping recommendations more when explanations were framed in domain (curricular) language than when they exposed raw model features — a skill for demanding and appraising explanation quality rather than accepting opaque output.
- **Model selection and prompt design as demonstrable skills:** instrumental AI Literacy includes knowing which model to use and how to phrase the task. Jacobsen et al. (2026) had 153 pre-service teachers' lesson-planning goals critiqued by ChatGPT-4, Claude 3 and Gemini Advanced under four systematically varied prompts (N = 240 feedbacks in Study 1, 345 in Study 2), with Feedback rated on nine quality categories. Model choice alone explained 26.9% of the variance in rated quality (18.4% in Study 2) and prompt design added a significant 15.9% (5.7%) on top; the single decisive prompt feature was domain-specific technical language, whose removal significantly lowered quality ($\beta = -0.412$), whereas adding examples and dropping the chain-of-thought instruction made no significant difference in Study 1. Their reading — that subject terminology both unlocks relevant training-data content and frames the request professionally, like

role prompting — plus a rule of thumb to use the most capable current frontier model, makes model choice a didactic decision rather than a technical one.

- **Ethical and critical use:** recognizing bias in AI outputs, protecting student data (Privacy), and ensuring equitable outcomes (Equity). Culturally relevant AI use examines how teachers can use LLMs to diversify materials rather than reinforce dominant norms.
- **Visual representation is its own measurable dimension.** Chen et al. (2026) validated a five-dimension scale for generating, judging and acting on visual representations with 566 teachers across five western Chinese provinces, with subscale alpha from 0.911 to 0.934; it measures reported capacity, with no test-retest and no observation of practice.
- **Ethical responsibility is distributed, not individual.** Across seven national cases teachers are positioned as moral gatekeepers of AI use while lacking institutional and epistemic support, so ethical AI literacy has to extend to critical and political agency rather than technical skill (Raffaghelli et al. (2026)).
- **Confidence and attitudes:** teacher confidence shapes adoption. Adoption research finds confidence, support, and perceived utility drive whether teachers actually use AI, and faculty orientations shape adoption in research and teaching.
- In a five-country survey of 1,405 K-12 teachers, AI readiness predicted positive beliefs about GenAI's instructional value ($B = .59$, $R^2 = .50$) yet predicted *greater* Creativity concern ($B = .18$), and the same predictors explained only 7% and 6% of concern — readiness-building alone leaves concern untouched (Xiu et al. (2026)).

Readiness should be ordered and measured accordingly: the Capability–Decision Model places demonstrated AI capability upstream of attitude and confidence and proposes performance indicators rather than self-report alone — lesson-design tasks, prompt-evaluation tasks seeded with errors, content-validity judgments and classroom artifact rubrics (Mnguni (2026)).

Emotional and moral readiness is a distinct dimension. Vassallo (2026) surveyed the academic staff of a Maltese university (109 respondents) and built an AI Guilt Index ($\alpha = 0.88$) from four moral-emotion items, finding that *anticipatory* guilt outweighed remorse experienced after use: the strongest endorsement was worry that AI use undermines one's credibility (34.9% agreeing), then feeling like one is cheating when using it (25.7%), while post-use remorse drew only 9.2%. The findings that matter for competency frameworks are that non-users reported *higher* guilt than users ($M = 3.25$ vs $M = 2.32$) and that guilt fell as career security rose — early-career academics reported the most ($M = 2.71$) and senior academics the least ($M = 2.03$). Emotional readiness is therefore not captured by skill or confidence measures, and the paper argues competency frameworks should treat guilt and identity concern as normal transitional responses rather than faults to correct.

A stronger version of that reframing holds that GenAI is a threshold concept rather than a skills gap: an autoethnographic account argues faculty anxiety and resistance are constitutive of threshold crossing, so skills-based training fails and principled non-adoption should be respected rather than corrected (Laidlaw (2026)).

Competency shows up as repair, not just prompting. With 7 middle school mathematics teachers rewriting 143 problems, Walkington et al. (2026) coded 415 follow-up prompts: most corrected realism,

readability or mathematical structure, and six caught inappropriate or biased output — teacher judgment operating as monitoring of the generated task rather than as prompt fluency.

The competency gap

A key finding is the **gap between self-reported and performance-based competency**. Research on AI-literacy assessment documents a substantial discrepancy (up to ~40%) between what teachers *believe* they can do and what they can actually *demonstrate* — teachers confident in AI skills often lack foundational prompting and evaluation abilities. This motivates **performance-based assessment** of teacher competency rather than reliance on self-report, and connects to calibrated self-assessment. A national survey of 2,586 Nigerian secondary teachers measured the two sides with separate instruments — moderate AI awareness (M = 3.13 of 8) against lower AI pedagogical skill (M = 2.47 of 5) — with early- and mid-career teachers reporting higher skill than experienced colleagues (Olurinola et al., 2026).

Readiness is the most-documented obstacle in the mathematics literature. A review of 54 mathematics-education studies found technological–pedagogical integration and teacher readiness the most frequently reported challenge (38 of 54), ahead of assessment validity and integrity (26) and overreliance (24) (Manto et al. (2026)).

The gap is not only between perceived and actual skill but in the *breadth* of what teachers know: a national survey of 2,018 Ukrainian secondary educators found 84% reported using AI in professional practice while only 11% could name a specialized AI service beyond ChatGPT (Marienko, Markova & Semerikov (2026)). A second narrowness shows in what teachers volunteer rather than what they can name: 53 in-service teachers tagging their own classroom cases against the OECD AI Literacy Framework described 43 AI-literate practices against only 10 failures (Wang et al., 2026). Their competency selections clustered on practical judgment (evaluating AI outputs, N = 38) and rarely reached societal bias (N = 5), ethical alignment (N = 6) or AI's energy use (N = 9).

A 132-teacher survey in Indonesia found near-universal acceptance alongside thin mechanistic understanding: 96.2% endorsed AI use by teachers, yet only 4.6% named tokenization or decoding and 21.5% believed ChatGPT searched a database or the internet (Aji et al. (2026)). A favorable attitude is not evidence of a workable mental model of the tool.

The gap is visible in the artifact as well as in the self-report. A cross-institutional faculty collaboratory in teacher preparation, in which teacher educators designed AI into their own methods courses, reported that candidates could produce polished AI-assisted lesson plans while being unable to explain why a plan fit the learners and the standards, since the plan itself says nothing about the reasoning behind it. Grading the justification rather than the product is one response. The pedagogies-of-practice frame suggests another, treating rehearsal as an approximation of practice: AI-mediated rehearsal with structured post-rehearsal feedback raised candidates' use of probing and exploring questions, yet candidates' own judgments of their performance still diverged from what observers recorded.

A falling self-assessment after training can signal learning rather than loss. In a six-month Intelligent-TPACK professional development program with 64 Hong Kong university teachers against 61 controls, overall AI competency rose by about half a standard deviation (Cohen's d = −.521), yet some teachers in both groups scored lower at post-test than at pre-test (Tan, Cheng & Ling, 2025). Interviews attributed the declines to a shift from unconscious to conscious incompetence — the recalibration the Dunning–Kruger

effect predicts — rather than to lost skill. The authors conclude that pre-post self-report understates an intervention, because part of the gain arrives as a downward correction in the instrument itself.

The gap can invert across the pipeline. In postgraduate medical education, twelve physicians who lead AI curriculum work expected residents to become more fluent with AI than many of their teachers, and proposed co-learning and co-teaching rather than a one-way upskilling of faculty (Bursic et al. (2026)). The same interviews described informatics units not yet mature enough to lead curriculum development, which locates the constraint in institutional capacity as well as individual skill.

The gap also shows up as non-participation. Watson & Rainie (2026) surveyed 1,057 US college faculty in late 2025 and found 26% do not use generative AI tools at all, with a third choosing not to use them for teaching and non-use concentrated in the arts and humanities (40%). The institutional side of the gap was larger than the individual one: 68% said their schools had not prepared faculty to use generative AI for teaching and mentoring, and faculty named colleagues' resistance (82%) and unfamiliarity (83%) as the leading obstacles to departmental adoption — a picture in which capability-building, peer norms and policy all have to move together.

Pre-service training largely sidesteps the ethical dimension of the competency. A systematic review of AI in initial teacher training for pre-service primary mathematics teachers (Pinto et al. 2026, 11 studies selected from 341 records) found the interventions concentrated on short-term technical and pedagogical gains, with nine of the eleven running brief interventions spanning one to six sessions, and reported that ethics was addressed in only three of the eleven studies. The competency frameworks name ethical judgment as a dimension; the pre-service literature meant to build it rarely teaches or measures it.

- **Seven competence clusters, with ethics the weakest link.** A thematic synthesis of 78 studies yields clusters for prompt engineering, critical evaluation of AI outputs, ethical awareness and bias detection, pedagogical-content alignment, conceptual AI literacy, human oversight and reflection. Prompt engineering was the most consistently documented and behaves as a **developmental spectrum** rather than a single skill, which led the reviewers to argue it is best understood as pedagogical reasoning conducted through a new medium — the prompt as an externalized design decision. Ethical awareness was the **weakest documented competence** in the pre-service studies (Spyropoulou & Kameas, 2026).
- **Teachers overestimate their own evaluation skill.** Beyond the finding that only **38.3% of AI-generated learning objectives met all quality criteria without revision**, pre-service teachers **systematically overestimate their ability to evaluate chatbot output** — which the reviewers read as a possible perceptual rather than declarative deficit. This is why they argue competence should be assessed through performance artifacts (lesson plans, decision logs, micro-teaching) rather than self-report: the unreliability of self-assessment is demonstrated in the very literature the training is meant to address.

Professional development that works

The knowledge base's PD literature identifies effective approaches:

- **Intensive, theory-grounded programs:** An intensive GenAI PD program with 163 teachers/pre-service teachers produced significant gains across all AI-PCK components, with pre-service

teachers benefiting most. Self-determination-theory-based PD shows need-supportive training improves teachers' AI literacy, attitudes, and engagement while reducing anxiety.

- **Design-based and integrated approaches:** DBR-based GenAI literacy training addresses the overemphasis on technical knowledge and pre-GenAI tools; integrative, developmental frameworks and social-emotional competency integration broaden literacy beyond pure technique.
- **Inquiry and authentic practice:** AI-supported inquiry models build AI literacy and authentic performance in pre-service teachers.
- **Context-specific readiness:** The EPIQ-AI readiness framework emphasizes that faculty readiness is a sociotechnical issue requiring alignment of faculty capacity, AI Governance, and quality assurance.
- **Support must be differentiated by experience and AI proficiency.** Choi et al. (2026) found that how teachers actually interact with AI in lesson design depends on the *interplay* of teaching experience and AI proficiency, not either alone. Experienced teachers with high AI proficiency critically adapt AI output to context (re-prompting, elaboration), whereas novices — even technically fluent ones — tend to accept AI responses directly and rarely consider students and context. This argues for profiling-based PD: response-evaluation checklists and prompt templates for novices, and hands-on skill-building for experienced teachers with lower AI proficiency.
- **The time benefit itself follows experience and confidence, not only support design.** In Roy et al.'s (2026) trial of an AI lesson assistant, the workload reduction was larger for teachers with lower subject-knowledge confidence, lower pedagogical knowledge, less time in the profession, or higher confidence with technology. Proficiency and confidence are therefore part of the intervention's effect, not only part of its take-up.

Belief configuration is a second profiling axis: among 40,680 teachers in TALIS 2024, the same non-use status masked opposite barriers — 83.3% of the Indifferent profile cited pedagogical reservations while 66.2% of Measured Endorsement cited insufficient knowledge and skills (Fang & Jin (2026)). AI-related professional learning tracked profile membership more consistently than age or attainment.

- **Teachers do not share one conception of AI.** A phenomenographic study of 16 Danish higher-education teachers found three conceptions of teaching-with-AI and three of learning-with-AI, so a single workshop model reaches only part of any faculty group (Stenalt (2026)).
- **Co-design and pedagogical prompt literacy are competencies, not add-ons.** A systematic review of teacher–AI co-design of learning tasks (Wang, Liu & Islam 2026, 28 studies) finds the dominant collaboration mode is AI as assistant/content generator, and locates a gap in teachers' fuller co-design and dialogic partnership capacities. Talebzadeh (2026) shows PD that pairs technical AI training with pedagogical reasoning — building "pedagogical prompt literacy" (encoding PCK into prompts) — is what lets teachers turn AI output into effective differentiated group activities.
- **Structures that build competency, rather than lists of it.** Perl-Nussbaum and Finkelstein (2026) ran a six-session biweekly faculty learning community in a large public R1 physics department — nineteen faculty across the series, about ten at each meeting — where every session opened on local data, moved to small-group testing of AI against real anonymized student homework, and closed in collective discussion, and it produced a five-entry shared repository rather than a training

package. Assessment literacy can be built the same way through a design tool: in Paula et al.'s (2026) pilot, eight experienced STEM and Health course coordinators grew their assessment literacy by critiquing a custom GPT's assessment drafts against disciplinary standards, even though the outputs repeatedly missed disciplinary context, ignored topic sequencing, and in one case carried fabricated references through repeated prompting. All eight kept academic judgment with themselves and refused end-to-end automation, which makes structured critique of generated drafts the development mechanism rather than tool training.

- **Short sessions can move acceptance without moving adoption.** Mesenhöller and Böhme (2026) evaluated a three-hour INSIGHT session with 100 German teachers and found perceived usefulness and perceived ease of use both rose significantly (usefulness $t(99) = -3.24$, $p = .002$, $d = .32$; ease of use $d = .25$) while behavioral intention to use AI-based technologies for differentiation did not change. The authors note their baselines were already favorable, so a ceiling effect is plausible. The reading for PD design is narrow but useful: a short session can shift how teachers judge AI tools without shifting whether they plan to use them, which is the kind of change that needs follow-through rather than a one-off event.
- **Instructors prefer fluency but attribute learning to scaffold.** Across 41 instructors, a GPT-4o baseline was preferred overall (21 vs 13) yet the fine-tuned three-step model (identify, explore, develop) was more often credited with learning (18 vs 13), and the two judgments agreed only 39% of the time (Molnar et al. (2026)).
- **Institutional support:** professional development must be paired with institutional infrastructure (policy, institutional change) for sustainable adoption.
- **Authoring tools do not guarantee pedagogical fidelity.** Riahi et al. (2026) studied 27 middle school teachers configuring educational chatbots in professional-development workshops, analyzing focus groups alongside configuration and interaction logs. Teachers treated the chatbot as an instructional scaffold bounded by teacher-defined rules, yet log-based alignment between intent and behavior was stronger for responsiveness (88.9%) and persona (81.5%) than for rules (70.4%) and purpose (59.3%). Configurable controls alone do not carry pedagogical intent into behavior, so expressing, testing, and refining a chatbot's pedagogy is itself a competency the authoring tooling has to support.

A design-based counterexample treats competency as situational rather than a rung on a ladder. Eyal's 2025 design-based study with 22 higher-education teacher educators had participants examine five published assessment frameworks and co-design an alternative organized around three inter-related axes: context fit (infrastructure, socio-cultural factors, local needs, developmental stage), professional needs (discipline, pedagogy, leadership, support), and dynamic development. The model rejects fixed competency levels and allows non-linear progression, and it ships with a 20-item reflective self-assessment questionnaire rated 1 to 5. Its validation is qualitative only, with no quantitative reliability testing, so it stands as a design contribution rather than a validated instrument. - **Meta-analytic estimate.** Guo et al. (2026) pooled 212 effect sizes from 34 studies and estimate teacher AI-literacy PD at $g = 0.76$ (95% CI [0.50, 1.02]), strongest

for skills (g = 0.91) and weakest for attitudes and values (g = 0.61); correcting for apparent publication selection lowers the estimate to about g = 0.49.

- **Attendance predicts gains where the feeling of participating does not.** In the same six-month program, attendance rate predicted the competency gain (β = .407, p = .001) while self-perceived participation did not (β = .049, p = .692), and discipline, teaching experience and professional title explained little; the authors read attendance as behavioral investment and perceived participation as surface-level engagement (Tan, Cheng & Ling, 2025).
- **Values lag skills in a domain-specific program too.** In a year-long Hong Kong program with 30 English teachers, knowledge of Multimodal AI assessment strategies rose from 3.13 to 4.15 out of 5 (partial $\eta^2 = 0.571$) and competence in supporting students from 3.05 to 3.98 (0.482), both significant, while every value subdomain stayed statistically flat under a Bonferroni-corrected alpha of .006. The teachers attributed the gains to in-school co-planning and cross-school cluster meetings rather than the workshops alone (Jiang et al., 2026).
- **Microlearning can develop university teachers' AI competence.** Cechovsky (2026) refined two Vocational Education and Training modules across two online group discussions into five design principles — clear structure and orientation, guidance and navigation support, segmentation and modularization, multimodal presentation, and learner activation — and found platform navigation and locating modules the main practical barriers.
- **Intention to adopt runs on need satisfaction.** In a structural model of 146 teachers, competence need satisfaction predicted intention to use GenAI through intrinsic motivation and engagement in professional development (indirect 0.233), while autonomy and relatedness satisfaction did not (Yuan et al., 2026).

Teacher AI competency and the transforming teacher role

As AI takes over routine instructional and assessment tasks, the teacher's distinctive contribution shifts toward orchestration, judgment, and relationship: deciding when and how AI is used, scaffolding student agency and critical use, ensuring equity, and providing the social and emotional support AI cannot. This reframes teacher competency around human-in-the-loop oversight, ethical judgment, and supporting self-regulated learning — connecting to Teaching and guarding against over-reliance.

Implications for AI in education

- **Assess performance, not just self-report:** teacher competency should be evaluated through demonstration, given the documented self-report gap.
- **Train the full competency, not just tools:** PD should build technical, pedagogical, assessment, and ethical dimensions together, grounded in learning theory.
- **Build confidence alongside skill:** attitudes and Self-Efficacy shape adoption, so PD should reduce anxiety and build confidence through authentic, supported practice.
- **Support the institutional layer:** sustainable teacher competency requires aligned policy, governance, and capacity, not isolated training.

- **Teacher digital competence for GenAI curriculum design.** Guillén-Gámez (2026) validate a TAM-based diagnostic instrument with 434 in-service teachers; behavioral intention was the main predictor of digital competence for using GenAI in curriculum planning, with self-efficacy as a root driver.

A Psychometric Instrument for Teacher AI Competency

- A psychometric study developed the Teachers' AI Literacy Scale (TAILS) to measure AI literacy specifically within language teacher education, operationalizing the ED-AI framework's six dimensions. The instrument's development fills a gap in assessments that target students or general users, supporting the measurement of teacher AI competency.

The instrument landscape itself has since been reviewed. Zainal, Mohd Matore and Maat's 2026 systematic review of teacher AI literacy measurement tools appraised 33 instruments published between 2019 and 2025 and found the field methodologically monotonous: 31 (93.9%) are self-report scales of perceived confidence, only two (6.1%) test knowledge objectively, and none use performance-based tasks. Internal consistency was the strongest quality domain (28 of 33 at Grade A) and fairness the weakest, with five instruments (15.2%) reporting measurement invariance or differential item functioning evidence. Content also lags the technology, since 29 instruments (87.9%) target general AI concepts and only four (12.1%), all from 2025, address generative AI.

Common Misconceptions

- **"Prompting training makes teachers' materials better." Prompting training buys time, not better materials**: in a **preregistered RCT with 204 teachers**, Appel, Fervers and Piepenburg (2026) found ChatGPT improved **time spent** while the material quality did not follow. The efficiency gain is real and it is not the quality gain.
- **"When teachers configure a chatbot, the failure is factual error." When teachers configure a chatbot in natural language, the dominant failure is lost intent rather than wrong facts** — bots **skip** the step the teacher meant. Instruction-following fails structurally rather than factually.
- **"Technical skill is the decisive layer." Pedagogical knowledge is the decisive layer**: a cross-level study of secondary AI education Shen et al., 2026. The competence that determines the outcome is the one most training programs under-invest in.

Connected Concepts

- AI Literacy
- Educational Development
- Teaching
- Prompt Engineering
- Learning Design
- Scaffolding
- Metacognition
- Assessment Validity

- Equity
- Ethics
- Self-Efficacy
- Human-in-the-Loop
- Learner Agency
- Cognitive Offloading
- Educational AI Policy
- AI in Education
- Technological Pedagogical Content Knowledge (TPACK)
- Teacher Education
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Should there be a teacher in-the-loop? A study of generative AI-personalized tasks middle school — Teacher-in-the-loop personalization of middle school mathematics tasks with ChatGPT (Walkington et al. 2026)
- Lesson planning using AI lesson assistant, Aila - A Teacher Choices Trial — Which teachers gained planning time: lower subject-knowledge confidence, lower pedagogical knowledge, newer to the profession or high technology confidence
- AI Misconception and Adoption Among Indonesian K-12 Teachers — Teachers accept AI while misunderstanding how it works (Aji et al. 2026)
- AI integration in mathematics education: A systematic review of implementation challenges and pedagogical implications (2017-2025) — Teacher readiness and technological–pedagogical integration as the most frequently reported challenge across 54 mathematics-education studies (Manto et al. 2026)
- Conceptualizing and developing second language teachers' multimodal assessment literacy in the GenAI era — Multimodal assessment literacy: a year-long program where knowledge and competence moved and values did not
- The impact of professional development programs on K-12 teachers' AI literacy: A systematic review and meta-analysis
- Enhancing teachers' AI competency: A professional development intervention study based on intelligent-TPACK framework — Intelligent-TPACK PD: half a standard deviation of gain, and negative gains that read as recalibration — The impact of professional development programs on K-12 teachers' AI literacy: A systematic review and meta-analysis
- AILitHub: Building AI Literacy Infrastructure to Situate Frameworks into Practice — Teachers tagged their own classroom AI cases and reached practical competencies readily but societal and ethical ones rarely (Wang et al. 2026)
- Typology of Generative AI Tools for Education — Tool selection as an exercise of educator agency

- Generative Artificial Intelligence (GAI) in Teaching and Learning Processes at the K-12 Level: A Systematic Review — Systematic review of generative AI in K-12 teaching and learning (Marzano 2026)
- Pedagogy first, technology second: Cross-level relationships between teacher professional knowledge and student learning in artificial intelligence (AI) education — Teacher professional knowledge in K-12 AI education: TAIK vs TPAIK and student learning (Shen et al. 2026)
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction patterns in lesson design across experience and AI proficiency (Choi et al. 2026)
- Preparing pre-service teachers for responsible generative AI use: Curriculum implications for ethics, privacy, and AI literacy — Pre-service teachers' responsible GenAI use: curriculum implications (Kohnke et al. 2026)
- Validating AI-generated classroom observations: Reliability, accuracy, and limits of LLM-based pedagogical judgment — LLM classroom observation for teacher professional development (Melo et al. 2026)
- Responsible integration of artificial intelligence into pedagogies of practice in mathematics teacher education — Generative AI across representations, decompositions and approximations: rehearsal, structured feedback and the accuracy cautions
- Efficacy of an Intensive Generative AI Professional Development Program on Pedagogical Content Knowledge (AI-PCK) and the Comparative Analysis of Learning Gain between Experienced and Pre-service Teachers — Efficacy of an intensive GenAI professional development program
- Modeling AI-TPACK in practice: Insights from teachers' multi-agent workflow design — Modeling AI-TPACK through teacher multi-agent workflows
- Towards Synergistic Teacher-AI Interactions with Generative Artificial Intelligence — Toward synergistic teacher-AI interactions
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher education for AI literacy through self-determination theory
- Development and evaluation of artificial intelligence literacy training for teacher education students — Design-based research GenAI literacy training
- Rethinking Generative AI Literacy: An Integrative, Developmental, and Dialectical Framework for K-12 Teacher Education — Rethinking GenAI literacy in teacher education
- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review — Integrating social-emotional competencies with AI literacy
- AI adoption among teachers: Insights on concerns, support, confidence, and attitudes — AI adoption among teachers: confidence and support
- Faculty orientations shape adoption of AI in research and teaching — Faculty orientations shape AI adoption
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — Misalignment between self-reported and performance-based AI competency

- Effects of an AI-supported inquiry model on AI literacy and authentic performance: A quasi-experimental study with preservice teachers — AI-supported inquiry for pre-service teachers
- Faculty Readiness for AI-Supported Teaching and Scalable Online Program Delivery in Higher Education: The EPIQ-AI Framework for Epistemic Integrity — EPIQ-AI faculty readiness framework
- LLMs to Support K-12 Teachers in Culturally Relevant Pedagogy: An AI Literacy Example — LLMs for culturally relevant K-12 pedagogy
- A framework for institutional change in the age of AI — Institutional change framework for AI
- TeachingCoach: A Fine-Tuned Scaffolding Chatbot for Instructional Guidance to Instructors — TeachingCoach chatbot for instructor guidance
- When faculty ask, "what's the point of teaching?": GenAI as identity crisis, not skills gap — GenAI as identity crisis, not skills gap
- Situated AI ethics: a cultural-historical and ecological framework for education
- Transforming curriculum design with generative AI: a model for assessing teacher digital competence — Assessing Teacher Digital Competence for GenAI Curriculum Design (Guillén-Gámez 2026)
- Understanding what good education is: a phenomenographic investigation of university teachers' understandings of AI — phenomenographic study of university teachers' conceptions of AI
- AI literacy in secondary education: Framework, assessment, and professional development in the Ukrainian context — Five-level AI literacy framework + PD for Ukrainian secondary educators (Marienko et al. 2026)
- Reimagining teacher-AI co-design in learning task design: trends and perspectives — Teacher–AI co-design of learning tasks: trends and perspectives (Wang et al. 2026)
- The Architecture of Roles in AI-Designed Group Activities: A comparative inductive analysis of novice and experienced teachers' differentiated instruction within the IAT framework — Architecture of roles in AI-designed differentiated group activities (Talebzadeh 2026)
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- AI Literacy of Teachers: Prompt Engineering and Model Selection as Predictors of AI-Feedback Quality — Prompt engineering and model selection as predictors of AI-feedback quality (Jacobsen et al. 2026)
- The AI guilt complex: Moral emotions and ethical dilemmas in academic technology adoption — The AI Guilt Complex: anticipatory guilt and four moral response profiles among academic staff (Vassallo 2026)
- Empowering teachers to use AI for differentiation: changes in teachers' acceptance of AI-based technologies following participation in a short professional development training session — A three-hour teacher PD session raised perceived usefulness and ease of use but not stated intention to adopt (Mesenhöller & Böhme 2026)
- Artificial intelligence in initial teacher training for pre-service primary school teachers in mathematics: a systematic review — Systematic review of AI in pre-service primary mathematics teacher training: ethics addressed in only three of eleven studies (Pinto et al. 2026)

- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — AAC&U/Elon survey of 1,057 US faculty: preparedness, non-use and the individual-vs-institutional policy gap (Watson & Rainie 2026)
- AI integration as instructional design: Lessons from a cross-institutional faculty collaboratory in teacher preparation — Cross-institutional faculty collaboratory: AI integration as instructional design in teacher preparation
- Assessing teachers' AI literacy: a systematic review of measurement tools — Systematic review of 33 instruments for measuring teacher AI literacy: 31 self-report, two objective knowledge tests, no performance tasks (Zainal, Mohd Matore & Maat 2026)
- Rethinking artificial-intelligence literacy through the lens of teacher educators: The adaptive AI model — A design-based adaptive AI literacy model and 20-item reflective questionnaire co-designed with 22 teacher educators (Eyal 2025)
- A Workshop Series for Effective Use of AI in Uncertain Times: Building a Physics Faculty Learning Community — A Workshop Series for Effective Use of AI in Uncertain Times: Building a Physics Faculty Learning Community
- Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education — Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education
- Will It Teach as Intended? How Teachers Configure Educational AI Chatbots — Will It Teach as Intended? How Teachers Configure Educational AI Chatbots
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Ordered capability-first teacher readiness model with performance-based capability indicators
- K-12 in-service teachers' beliefs about generative AI in classrooms: insights from the United States, India, Qatar, Colombia, and the Philippines — Cross-national survey of 1,405 K-12 teachers: readiness predicts positive beliefs but not concern
- Teachers' AI Belief Profiles and Their Associations with AI Use, Pedagogical Applications, and Barriers: A Person-Centered Analysis of TALIS 2024 — Four TALIS 2024 teacher belief profiles link professional learning and profile-specific barriers to AI use
- Designing Microlearning Modules on AI for University Teachers in Vocational Teacher Education: A Design-Based Research Study — Designing Microlearning Modules on AI for University Teachers in Vocational Teacher Education: A Design-Based Research Study
- EduWild: How Teacher-Configured Chatbots Fail in Real-World Use and How to Fix Them — EduWild: How Teacher-Configured Chatbots Fail in Real-World Use and How to Fix Them
- Development and validation of the AI-empowered visualization teaching competency scale — Development and validation of the AI-empowered teacher visualization teaching competency scale
- Exploring the integration of artificial intelligence into residency education curriculum: qualitative interviews — Barriers to integrating AI into residency curricula: qualitative interviews with twelve physician leaders
- Teachers' basic psychological need satisfactions and their intentions to use generative artificial intelligence: the mediating role of engagement in professional development — Teachers' basic

psychological need satisfactions and their intentions to use generative artificial intelligence: the mediating role of engagement in professional development

Connected FAQs

- What Competencies Do Faculty Need in Regard to AI?
- How Can We Address Common Misconceptions About AI in Education?
- How Do I Design Faculty Development for AI That Actually Changes Practice?

Learning Design

> **Learning Design** (also known as *instructional design*) — the systematic process of creating effective learning experiences through the analysis of learning needs and the design, development, implementation, and evaluation of instructional materials and activities. AI is transforming learning design by automating content creation, enabling adaptive learning paths, supporting data-driven iteration, and augmenting — rather than replacing — the instructional designer's role.

Questions to Consider

- Think of a course or lesson you have experienced or designed. Where did 'what to teach' (curriculum) end and 'how to teach it' (learning design) begin — and how did the two interact?
- A common assumption is that better AI fluency automatically produces better educational content. The page counters this with evidence that explicit pedagogical structure — not just AI fluency — is what determines learning effectiveness. Where have you seen impressive output that failed to teach?
- If an AI tool can generate a full course from a prompt, what human decisions become more important rather than less? The page argues AI augments rather than replaces the instructional designer's role — what would that augmented role look like?
- Some instructional-design models like ADDIE are used as rigid, linear steps. But the page treats them as iterative, flexible planning heuristics. When might following a process too literally undermine good design?
- The page shows that pedagogically grounded prompting — for example, a five-step framework based on learning theory — significantly improved higher-order outcomes. If you were building an AI tutor, what would you encode in an explicit design layer so its teaching strategy stays traceable and reproducible?

Introduction

Learning design bridges AI capabilities and effective pedagogy. Where Curriculum Design addresses *what* to teach at the program level, learning design addresses *how* to teach it at the course and lesson level. The articles in this knowledge base explore both AI as a tool for learning designers and learning-design principles for building effective AI tutoring systems.

What that design work involves in practice is itself an empirical question. Tang et al. (2026) coded 1,378 designer-chatbot turns from five novice learning designers working with a chatbot embedded in a design tool, and found the dialogue clustered on intended learning outcomes and pedagogical approach rather than content generation. Designers returned to outcomes repeatedly as an alignment check while turning curriculum components into concrete tasks, and the assistant's role shifted across phases, from clarifying terms to supporting task design to running a verification pass before a deadline. Design support, on this evidence, is less about producing material than about keeping design intent coherent.

Learning analytics and generative AI support different parts of design: across 11 focus groups at one Australian university, analytics discourse co-occurred most with context and course-level Problem Solving (0.32), while GenAI discourse centered on assessment design (0.26) and designing for student self-determination (0.15) (Claassen et al. (2026)).

Key research themes

AI-assisted content creation is the most directly transformative application. **Curriculum as Code** presents a six-phase architecture integrating Generative AI with LaTeX and Python to automate STEM materials creation, validated across 8 modules and 28 project contexts with student quality ratings of 8.5-9.9/10. **Instructional Agents** uses a multi-agent framework structured around the ADDIE model, with role-based agents (Teaching Faculty, Instructional Designer, Course Coordinator) collaborating to generate complete course materials. **CourseBlueprint** provides a structured pipeline for adaptive pedagogical video generation grounded in course corpora, demonstrating that explicit pedagogical structure — not just AI fluency — is essential for educational content generation. Generative AI platforms can also embody learning-design principles in the content they produce: an AI-powered platform for generating mathematical modeling problems combined established design principles with retrieval-augmented generation, developed through the ADDIE approach to produce pedagogically grounded tasks and recommendations that conventional content generators lack. Yet the payoff of such AI-assisted content and lesson generation is mediated by the teacher's own expertise: Choi et al. (2026) found that experienced teachers critically adapt AI-generated lesson ideas to students and context (re-prompting and elaborating on output), whereas novices tend to accept AI suggestions directly — so the pedagogical value of AI content tools depends on the teacher's experience and AI proficiency, not the tool alone. A systematic review of teacher–AI co-design of learning tasks (Wang, Liu & Islam 2026) confirms the pattern at scale across 28 studies (2015–2025): GenAI is used mainly for lesson planning, prompt generation, and creative ideation, and the dominant collaboration mode is AI as assistant/content generator rather than a fuller co-designer — with efficiency, responsiveness, Creativity, and equity recurring as affordances. Talebzadeh (2026) sharpens the teacher-expertise finding for group activity design: experienced teachers produce richer, more synergistic, better ZPD-aligned role architectures in AI-designed cooperative activities than novices regardless of AI familiarity, framing "pedagogical prompt literacy" as the lever that turns AI output into effective differentiated group learning.

The Aila trial puts a planning-time number on that pattern. Teachers in its randomized primary schools spent 2.51 hours a week preparing lessons with the tool against 3.32 hours without it, yet the median teacher planned only 21% to 40% of lessons from scratch, which is the case a from-scratch tool addresses (Roy et al., 2026).

Where generated materials fall short is curriculum fit: seven math teachers rated AI-generated Productive Failure problems close to human ones on overall quality (M = 17.19 vs 17.43 of 25) but lower on curriculum alignment (M = 2.57 vs 3.29), so generated problems still needed editing for length, reading level, and visuals (Rhaimi et al. (2025)).

Pedagogically grounded AI tutoring applies instructional design principles to AI system design. **Brisson et al.** built a didactically-driven Large Language Models (LLMs) teacher assistant where tutoring strategy is encoded in an explicit external layer — making content selection and didactic structuring traceable and reproducible, directly addressing opacity concerns in Rethinking Scaffolding in LLM Tutors: The

Interactional Mismatch Between Benchmarks and Real-World Deployments. **Hou et al.** demonstrated that a five-step prompting framework grounded in Generative Learning Theory significantly improved higher-order cognitive outcomes, showing that instructional guidance — not just AI access — determines learning effectiveness. Both connect to Scaffolding and Intelligent Tutoring.

Frameworks and evaluation provide structured approaches. **WIP: Bridging the Gap Between Instructional Design and Pedagogical Use: A Framework for Mathematics Educators** and **CoTAL** demonstrate human-in-the-loop design principles. **Generative AI (GenAI) as a mindtool that supports generative learning (GL)** positions AI as a "mindtool" — a cognitive partner that extends rather than replaces learner thinking — directly applying instructional design theory to AI integration. **LUDIA** applies Universal Design for Learning principles to create an accessible AI thought partner for educators, connecting instructional design to Inclusive Learning. **AIRIS** (Activate–Inquire–Reflect) is a task-structuring framework for cognitively activated AI use that bounds the AI's contribution so that prediction, interpretation, and evaluation remain the learner's — an AI-specific adaptation of inquiry cycles grounded in Self-Regulated Learning, Cognitive Load Theory, and Human AI Collaboration. Complementing these design frameworks, the Dohn et al. (2026) taxonomy offers a *classification* rather than a design method: six categories (Learning Objective, Content, Representation Format, Epistemic Engagement, Social Design, Artifacts) that let designers and researchers describe, compare, and imagine GenAI learning activities by making explicit why, what, how, with what, and with whom learners engage GenAI — built as a boundary object through postdigital dialogue. Smart-classroom frameworks extend this to teacher education: Zhu, Liang, Mao, and Wang (2026) propose a three-dimensional framework for smart education — learning effectiveness, information and communication technology (ICT), and classroom organization — and instantiate it in a mathematics M.Ed. course that integrates automated scoring, personalized recommendations, and multi-AI feedback across pre-, in-, and post-class stages. A quasi-experiment showed significant gains in students' ability to formulate precise, professionally grounded instructional objectives, yielding the transferable **D-T-E Model** (Disciplinary Demand–Technological Empowerment–Evaluation Loop) — discipline-specific guidance for teacher educators moving smart-education concepts into practical instructional design practice.

Design for reach. Halani's seven-lever framework asks of each course setting which ones still operate when the student is alone with AI; structural moves such as changing what the grade certifies, or tasks that cannot be completed without the thinking, reach further than telling students that process matters (Halani, 2026).

Constrain the tool to protect the thinking. A nine-week argumentative-writing design sequenced teacher-delimited chatbots that ask questions and refuse to generate student prose, and four high-school students moved from passive AI consumers to evaluators who pushed back on outputs — strategic constraint, not unrestricted generativity, tracked the gains (Konradt, Boote & Taub (2026)).

Rubric-guided prompting as a design lever. Yaşar et al. (2026) demonstrated that the rubric functions as a mediating interface between human pedagogical intent and machine inference: treating assessment criteria as revisable design artifacts — rather than fixed instruments — and iteratively co-refining them with the LLM raised LLM–human agreement on student design work from 54.75% to 81.25%. Rubrics engineered for LLMs must balance precision and flexibility — too vague invites free interpretation, too rigid reduces the model to pattern-matching — and role-aware prompting (instructor, peer reviewer, grant reviewer) yielded distinct evaluative feedback. This positions rubric engineering as a concrete learning-design practice for shaping AI evaluation behavior, with human-in-the-loop oversight remaining essential.

AI agents for instructional design extend the field into agentic AI. **ISD-Agent-Bench** is the first standardized, theory-grounded benchmark for evaluating LLM-based instructional design agents. Its 25,795-scenario Context Matrix (51 contextual variables × 33 ISD sub-steps from ADDIE) shows that agents grounded in classical ISD frameworks (ADDIE, Dick & Carey, Rapid Prototyping ISD) outperform theory-free agents, empirically validating that instructional design is a structured discipline rather than a generic prompting task. Agents are not only *builders* of designs but also *critics* of them: Wang, Mitchell & Piech (2025) use a single autonomous web agent that navigates a multi-step online lesson like a student to evaluate a learning design *before* real learners engage. Its description of the student experience predicts where novices will drop out and surfaces actionable design feedback, outperforming every baseline and even a simulated cohort of students on a global CS1 course. This frames pre-launch, agentic evaluation as a low-cost complement to human design iteration. **Enabling multi-agent systems as learning designers: applying learning sciences to AI instructional design** and **Instructional Agents** explore multi-agent frameworks that orchestrate role-based agents around instructional-design models, while **AI-TPACK** examines how teachers and agents jointly apply technological-pedagogical-content knowledge. This work connects instructional design to benchmarking, AI Ed Evaluation, and the design of curriculum at scale.

Connections to related concepts

Learning design is the bridge discipline of AI in education — it connects Curriculum Design (what to teach) with Scaffolding (how to support learners), Educational Development (how to prepare educators), and Generative AI (the tools themselves). It is tightly coupled with Teaching because AI tools reshape what learning designers and teachers do, and with AI Literacy because effective AI integration requires educators to understand AI capabilities and limitations. Design work ultimately resolves into an *order of activity*: pedagogical patterns catalogue the tested orders of moves, so a designer can decide where in a lesson AI belongs rather than only what to include. The learning sciences are the research field behind these principles: where this page covers the professional practice of creating learning experiences, the learning sciences study that practice and its designs empirically and generate the cognitive, motivational and social principles that learning design then operationalizes.

Co-design and what must stay human

Co-design is the part of design practice where the relational work is least substitutable. Zeivots et al. (2025) treat GenAI as an unreliable collaborator rather than a drafting tool, and build a three-phase sequence around that unreliability: the model provokes, pluralises and facilitates, while the group interrogates its framings, generates counter-narratives and holds the deliberation itself. What stays human is the negotiation — which voices are missing, which framing the group adopts, and what the shared understanding will be. The article is a collective forum of nineteen authors with no experiment, so the sequence is a proposal about practice rather than a tested method.

How learning design determines learning gains

Learning design is the lever that decides whether AI produces learning gains or merely AI-inflated performance. The knowledge base's evidence is consistent on this: **the same AI tool yields large gains or net harm depending on how the learning experience is designed around it.** Hou et al. showed that a five-

step prompting framework grounded in learning theory significantly improved higher-order cognitive outcomes, while access to AI alone did not; mindtool and AIRIS frameworks preserve the learner's cognitive work so that durable gains (rather than task-efficiency) result. Design choices that protect Learning Gains — scaffolding that requires a student attempt, Formative Assessment with unassisted outcome measures, and pedagogical structure that keeps the learner the agent — mirror the field's finding (see Learning Gains) that AI is a strong gain when it coaches and a harm when it answers. Conversely, poorly designed AI-integrated lessons fall prey to the performance-learning gap, where apparent success masks no learning.

Practical guidance for designers and developers

For instructional designers, course developers, and engineers building AI-assisted learning experiences, the knowledge base's findings translate into actionable practice. One boundary is worth marking before the practices themselves: learning design as this page describes it is the design of a course for a known cohort, whereas the same principles baked into a product that many courses — taught by people the designer will never meet — will use are the work of Educational Technology Developers, where defaults, configurability and documentation carry pedagogical weight:

Ground AI generation in a structured instructional model. AI content is only as good as the pedagogical structure behind it — explicit structure, not AI fluency, determines quality. Design around a recognized model (ADDIE, Dick & Carey, rapid prototyping) and encode pedagogical decisions explicitly rather than relying on the model to infer them.(CourseBlueprint: A Structured Pipeline for Adaptive Pedagogical Video Generation Grounded in Course Corpora)(ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents)(A didactical-driven teacher assistant for a dimensional modeling course)

Adopt a principle-level framework as well as an instructional model. A course-level model structures one design; a published framework sets the criteria that many designs should satisfy. An example worth reading in full is Digital Promise's *Powerful Learning with Emerging Technology*, which organizes its guidance under three principles — Evidence-Based, Learner-Centered, Skill-Building — each expanded into practices and strategies, and attaches Privacy, explainability and fairness to particular practices as safety obligations rather than optional extras.(Powerful Learning with Emerging Technology) **Match the AI configuration to the task, not to sophistication.** Nalyvaiko (2026) distinguishes four layers — prompt, context, harness, and verified loop — and applies a minimally sufficient layer principle: use the least complex configuration capable of a verifiable result, since added orchestration brings coordination, verification, privacy and comprehension costs.

Use role-based multi-agent workflows for content production. Instead of one generic prompt, orchestrate distinct agents/roles (teaching faculty, instructional designer, course coordinator) that collaborate through a defined pipeline — this mirrors how real course teams work and yields more complete materials than a single prompt.(Instructional Agents: Reducing Teaching Faculty Workload through Multi-Agent Instructional Design)(Enabling multi-agent systems as learning designers: applying learning sciences to AI instructional design)

Provide instructional guidance, not just AI access. Whether learners interact with AI directly or with AI-generated materials, guidance built on learning theory (e.g. a stepwise prompting scaffold grounded in generative-learning principles) drives higher-order outcomes; access alone does not. Design the learning

activity around how the mind learns, and treat AI as a cognitive “mindtool” that extends thinking rather than replacing it.(The Role of Instructional Guidance in Generative AI-Assisted Learning: Empirical Evidence from Construction Engineering Education)(Generative AI (GenAI) as a mindtool that supports generative learning (GL))

Model forgetting, and schedule review where decay is worst. G4L represents knowledge decay with an Ebbinghaus forgetting curve driven by elapsed time and repetitions, and prioritizes the units most vulnerable to decay rather than re-serving whatever was scored most recently (Csépányi-Fürjes & Kovács, 2026).

Fowlin et al. (2026) add an operational move for deciding where AI enters: unbundle an activity into the components best done independently and those best coupled with AI, keeping the educator’s judgment central to the split (Fowlin et al. (2026)).

Make content traceable and reviewable. Let a human designer review and correct AI output before it reaches learners, and structure AI generation so the pedagogical rationale (why this content, in this order) is inspectable — addressing both quality and the opacity concerns that undermine Trust-generated instruction. (WIP: Bridging the Gap Between Instructional Design and Pedagogical Use: A Framework for Mathematics Educators)(CoTAL: Human-in-the-Loop Prompt Engineering for Generalizable Formative Assessment Scoring and Feedback) - **Review AI-generated media at the script stage, not after synthesis.** PedaCo puts educator review on the script — where pedagogical errors are cheap to fix — before anything is rendered; rated instructional validity rose from 3.07 to 3.86, while the automated post-synthesis layer improved only two of five dimensions (Kim, Baek and Kwak (2026)).

Design for Accessibility from the start. Apply UDL principles when building AI tools and AI-generated materials so they serve diverse learners, rather than retrofitting accessibility after the fact.(LUDIA: A Design and Evidence Statement)

Plan for the delivery medium. Instructional design for online teaching and learning is not a neutral translation of in-person design — the medium changes what scaffolding, assessment, and interaction are viable, and AI multiplies both the opportunities (scalable personalization, always-on support) and the risks (integrity, cognitive offloading) designers must plan for. Design the AI’s pedagogical wrapper as deliberately in online as in face-to-face contexts.

Evaluate against a benchmark, not vibes. If you’re building an instructional-design agent, evaluate it against a standardized, theory-grounded benchmark (e.g. ISD-Agent-Bench) so you can measure whether grounding in a real ISD framework actually improves output over a generic LLM.(ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents)

- **AI is reshaping instructional design practice.** Kibar & Ilgaz (2026) systematically review 28 studies (2020-2025) and find AI assists designers with content generation, templates, and personalization, and is conceptualized as a co-worker/collaborator/partner rather than just a tool — though pedagogical alignment and practitioner readiness remain challenges.
- **The documented activity is concentrated in one phase of the cycle.** In a review of 78 studies of AI-supported instructional design, Design-phase activity appears in **74 of 78 studies (95%)** and Development in 44 (56%), while Analysis reaches only 11 (14%), Evaluation 10 (13%) and Implementation 7 (9%) — and **no study examined AI support across the complete ADDIE cycle**. The cycle is an aspiration the evidence base does not cover, which matters for anyone being

sold “AI-powered course development” as an end-to-end capability (Spyropoulou & Kameas, 2026).

- **Three AI roles, hierarchically distributed.** *Generative* use — AI producing design content at the educator’s direction — dominates at **96% of studies**; *scaffolding* use, where AI structures the designer’s own reasoning, appears in 35%; *evaluative* use, where AI assesses artifact quality, in 21%. The field is overwhelmingly using AI to make things rather than to interrogate its own design decisions, which is the opposite of the critical-friend configuration the review singles out as educationally promising.

Common Misconceptions

- **“AI lesson planning returns time to teachers.”** Planning time did fall, from 3.32 hours a week to 2.51 with the tool, but **the median teacher planned only 21% to 40% of lessons from scratch**. Time was saved and the planning did not become substantially more thorough — the saving accrued rather than being reinvested.
- **“Co-design with AI is well evidenced.”** A systematic review of teacher-AI co-design of learning tasks **confirms the pattern at scale across 28 studies**, which describes a consistent practice rather than demonstrating superior outcomes.
- **“The rubric is a fixed input.”** The rubric functions as a **mediating interface between human pedagogical intent and machine inference**: treating assessment criteria as **revisable** is what lets the instrument carry the educator’s intent. A fixed rubric transfers the machine’s default framing into the assessment.

Connected Concepts

- Interpreting and Applying AIEd Research
- Pedagogical Partnerships — Pedagogical Partnerships
- Online Teaching and Learning — Online Teaching and Learning
- Curriculum Design
- Scaffolding
- Educational Development
- Teaching
- AI Literacy
- Generative AI
- Intelligent Tutoring
- Personalized Learning
- Adaptive Learning
- Formative Assessment
- Higher Education
- K-12
- Agentic AI

- Inclusive Learning
- Universal Design for Learning
- Learning Theories
- Learning Sciences
- Learning Gains
- Behaviorism
- Educational Technology Developers
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)

Connected Articles

- Lesson planning using AI lesson assistant, Aila - A Teacher Choices Trial — A measured planning-time saving alongside the finding that teachers plan only 21% to 40% of lessons from scratch
- Powerful Learning with Emerging Technology — Powerful Learning with Emerging Technology
- Understanding the Role of Learning Analytics and Generative Artificial Intelligence on Decision-Making and Learning Design Practice in Higher Education — LA and GenAI in learning design decision-making
- Investigating the role of chatbots in facilitating learning design — Chatbot use in learning design: designers dwell on outcomes and pedagogy rather than content generation (Tang et al. 2026)
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction patterns in lesson design across experience and AI proficiency (Choi et al. 2026)
- Artificial intelligence in higher education: a systematic review of its impact on student engagement and the mediating role of teaching methods — AI in higher ed: engagement + mediating role of teaching methods
- Curriculum as Code: An AI-Assisted Architecture for Instructional Design in STEM Education
- Collaborative Making of a Boundary Object for Classifying Generative AI Learning Activities — Taxonomy (boundary object) for classifying GenAI learning activities
- Instructional Agents: Reducing Teaching Faculty Workload through Multi-Agent Instructional Design
- A didactical-driven teacher assistant for a dimensional modeling course
- The Role of Instructional Guidance in Generative AI-Assisted Learning: Empirical Evidence from Construction Engineering Education
- CourseBlueprint: A Structured Pipeline for Adaptive Pedagogical Video Generation Grounded in Course Corpora
- WIP: Bridging the Gap Between Instructional Design and Pedagogical Use: A Framework for Mathematics Educators

- CoTAL: Human-in-the-Loop Prompt Engineering for Generalizable Formative Assessment Scoring and Feedback
- Generative AI (GenAI) as a mindtool that supports generative learning (GL)
- LUDIA: A Design and Evidence Statement
- From Prompts to Verified Loops: The PCHL-HE Framework for Generative AI-Assisted Educational and Research Content Creation in Higher Education
- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents
- AI Web Agents Can Effectively Guide Lesson Design and Predict Student Outcomes — AI Web Agents: autonomous web agent evaluates lesson designs and predicts student dropout before students engage (Wang, Mitchell & Piech 2025)
- It’s Not the Tool, It’s the Task: A Framework for Cognitively Activated AI Augmentation in Physics Instruction — AIRIS: A Framework for Cognitively Activated AI Augmentation in Physics
- Enabling multi-agent systems as learning designers: applying learning sciences to AI instructional design
- Modeling AI-TPACK in practice: Insights from teachers’ multi-agent workflow design
- Designing for Reach: Seven Levers and the Student Alone with AI — Designing for Reach: Seven Levers and the Student Alone with AI
- Empowering Educators: Operationalizing Age-Old Learning Principles Using AI
- When Saying No Makes Better Videos: Designing Dual Gatekeeping for Pedagogically Grounded AI Content Creation — When Saying No Makes Better Videos: Dual Gatekeeping for Pedagogically Grounded AI Content Creation
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: AI to Support Productive Failure Problem Design
- The intersection of artificial intelligence and instructional design practice: A systematic review — AI and Instructional Design Practice: A Systematic Review (Kibar & Ilgaz 2026)
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Making AI annoying on purpose: when helpful tools don’t always help — Making AI annoying on purpose: constraint in AI-supported writing (Konradt, Boote & Taub 2026)
- Improving instructional design proficiency of master’s students in mathematics education through intelligent educational technologies — Smart-classroom model and D-T-E loop improving M.Ed. instructional design proficiency in mathematics (Zhu et al. 2026)
- Creating an AI-powered platform for generating modelling problems: A case study on direct variation in secondary school mathematics — AI-powered platform generating mathematical modeling problems (ADDIE, RAG)
- Reimagining teacher-AI co-design in learning task design: trends and perspectives — Teacher–AI co-design of learning tasks: trends and perspectives (Wang et al. 2026)

- The Architecture of Roles in AI-Designed Group Activities: A comparative inductive analysis of novice and experienced teachers' differentiated instruction within the IAT framework — Architecture of roles in AI-designed differentiated group activities (Talebzadeh 2026)
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design
- Reshaping higher education designs and futures: Postdigital co-design with generative artificial intelligence — GenAI as an unreliable collaborator in co-design

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- How Should I Incorporate AI Literacy into My Course?
- How Should AI Be Designed Into the Learning Experience?
- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Educational Development

> **Educational Development** (also known as *faculty development*) — the processes, programs, and institutional supports that help educators develop the skills, confidence, and professional identity to teach effectively with AI. Educational development spans individual training, curriculum redesign, institutional policy change, and the cultural work of making sense of what GenAI means for the academic profession.

Questions to Consider

- If faculty in the same department describe AI as a human-like 'assistant' on one hand and a mere 'tool' or 'search engine' on the other, can a training program really succeed before those underlying mental models are surfaced? What might happen if development skips that step?
- Educational development is often treated as closing a skills gap — teach faculty the tools and they'll adopt them. But some research frames GenAI integration as an identity-level change ('what's the point of teaching in a GenAI world?'). Which framing do you think is more accurate, and what different actions does each one imply?
- Readiness frameworks like EPIQ-AI split faculty readiness into epistemic, pedagogical, institutional, and quality-and-compliance domains. If readiness is a sociotechnical alignment problem rather than an individual skills gap, what does that say about where a lone 'AI workshop' is likely to fall short?
- When have you felt your own assumptions about a new technology surfaced and shifted — through discussion, metaphor, or shared language rather than instruction? What role do you think shared language and metaphor-analysis play in helping educators make sense of AI?
- Consider a low-tech 'metaphor workshop' where faculty, staff, and students articulate whether AI feels like a Swiss army knife, a helper, a black box, or a competitor. Could surfacing fears (including the fear that AI will replace teaching roles) do more for adoption than more technical training?

Introduction

Educational development is the professional and institutional work through which faculty build the capability to design, teach and assess well — and in the AI era it has become a precondition for any pedagogical change to take effect. The concept spans the individual (AI literacy, confidence, competency, attitudes) and the institutional (standards, policy, quality assurance, and alignment between stated AI expectations and actual assessment design). A recurring finding across this knowledge base is that the evidence for effective practice substantially leads what most institutions have implemented, which makes development work — not more primary research — the binding constraint. The learning sciences produce the findings this work carries: where that field establishes empirically how people learn and which designs change outcomes, educational development is the institutional practice that moves such evidence into how faculty actually teach and assess. Its work, though, is bounded by an institutional edge: development builds

capability in the staff inside an institution, while the tools those staff are then asked to adopt are usually built outside it by Educational Technology Developers, whose design and procurement decisions — defaults, configurability, what survives the funding — arrive as constraints on the program rather than as products of it.

Educational development in the AI era

- **Readiness frameworks:** The EPIQ-AI framework identifies four readiness domains: epistemic, pedagogical, institutional, and quality-and-compliance. Faculty readiness is a sociotechnical alignment problem, not just an individual skills gap.
- **Check what a framework's levels describe before adopting it.** Across 16 institutionally endorsed AI competence frameworks, AI use, output evaluation and domain application were substantive in all 16, while problem formulation (7), data competence (9) and AI creation (8) were not; proficiency levels also describe learner development, occupational role or grade, so they are not directly comparable (Fitsilis (2026)).
- **Standards for technology integration:** Crompton et al. use design-based research to develop faculty standards for technology (incl. AI) integration in higher education institutions.
- **Adoption and confidence:** Teacher AI adoption research identifies concerns, support, confidence, and attitudes as key predictors. Faculty-development programs must address all four.
- **Curriculum integration:** Institutional change frameworks and assessment reform require faculty to redesign courses, not just add AI tools.
- **Training programs:** AI upskilling frameworks and TPACK-based preservice training provide models for structured faculty AI education.
- **AI-mediated professional reflection.** The Reflective Triangle Model positions AI as a cognitive mediator across self-reflection, collaborative reflection, and community reflection in a professional learning community, tested in a four-week feasibility case with six teachers; the boundary it draws is that individual insight does not automatically become shared professional knowledge (Nguyen (2026)).
- **AI Governance and policy:** Institutional AI policy analysis documents the gap between institutional ambitions and faculty support capacity.
- **AI literacy is institutionally invisible.** A systematic review of 32 studies of language-teacher AI literacy found it absent from workload models, promotion policies and resource allocation, with development fragmented and accountability displaced across institutions and agencies — so literacy development defaults to individual effort rather than structural support (Deng, Çelik & Duran, 2026).

Metaphors and shared language in educational development

Faculty hold heterogeneous, often deeply ambivalent mental models of AI, and effective development must surface and work with them. Gerhardt et al. show that engineering instructors frame AI through metaphors that both construct and constrain understanding (AI as a human-like "assistant" vs. a "tool" or "search

engine”); because instructors within the same department often hold fundamentally different conceptualizations, a shared, accurate language about GAI is a prerequisite for effective faculty development and productive departmental adoption discussions.

A practical method for surfacing these mental models is the **metaphor-analysis workshop**. Vallis, Wilson & Casey (2025) designed and validated a low-tech, collaborative workshop for faculty, staff, and students to articulate their metaphors for generative AI. Participant metaphors clustered into four categories — *Functions* (tool-like: “Swiss army knife”), *Roles* (human-like: “helper,” “frenemy”), *Qualities* (unknowable: “black box,” “slippery slope”), and *Agency* (threatening: “competitor,” “sinister robot”) — surfacing persistent tensions between human vs. machine Learner Agency and the known vs. the unknowable. The workshop helped participants surface assumptions, connect across roles, feel “not alone,” and think about the Ethics of GenAI, without requiring technical expertise. As a development tool, it gives program designers a low-barrier way to surface a team’s assumptions *before* redesigning Assessment or rolling out policy, and to address fears head-on — including the fear that AI will replace teaching roles.(Fear and awe: Making sense of generative AI through metaphor)

GenAI as identity work, not just upskilling

A threshold-informed view reframes GenAI integration as an **ontological transformation** for faculty, not a skills gap. Applying threshold concept theory (Meyer & Land), Laidlaw argues that GenAI exhibits all five threshold characteristics — *transformative* (reconstructs assumptions about assessment, pedagogy, and professional role), *troublesome* (violates beliefs about originality, human agency, and effort–achievement), *irreversible*, *integrative* (connects technology, pedagogy, epistemology, and identity), and *bounded* (GenAI fluency becomes a new marker of professional currency).(When faculty ask, "what’s the point of teaching?": GenAI as identity crisis, not skills gap)

On this account, faculty asking “what’s the point of teaching in a GenAI world?” are not deficient in competence; they are in a **liminal threshold-crossing phase** where anxiety, resistance, and confusion are necessary parts of transformation, not obstacles to eliminate. Skills-based training that answers a competence question faculty are not asking can become peripheral to the real transformation, and well-intended governance can lapse into an “enforcement illusion” — communicating rules rather than supporting change. (When faculty ask, "what’s the point of teaching?": GenAI as identity crisis, not skills gap)

Design implication: complement (don’t replace) skill building with **identity-supporting practices** — open sessions with identity questions rather than technical demos, run ongoing discipline-specific cohorts where faculty explore what GenAI means for their field’s purpose, create peer-mentoring structures that honor different transformation timelines, and distinguish fear-based hesitation (which benefits from support) from principled non-adoption grounded in legitimate disciplinary values (which deserves respect).(When faculty ask, "what’s the point of teaching?": GenAI as identity crisis, not skills gap) The metaphor-workshop model above is one concrete instantiation of this: rather than starting from technical upskilling, it opens with the interpretive, identity-laden question of what GenAI means to participants.

Empirical support for the identity-work framing. Farazouli et al. (2026) provide direct qualitative evidence for this account: 24 Swedish university teachers described GAI’s emergence as alarming and overwhelming, reporting a “state of vulnerability” (low confidence, insecurity, fear of “not being ahead of students”) and feeling “stuck” between utopian and dystopian discourses. Their limited knowledge and

experience, alongside feelings of vulnerability, highlight teachers' lack of readiness to navigate, assess, and adopt GAI — and the authors argue institutions must provide **designated spaces and time** for teachers to experiment with GAI, exchange ideas, and collaboratively develop practices and guidelines at institutional, departmental, and course levels. This grounds the identity-work and support-oriented approach in teachers' own reported experience rather than only in theory.

A programme that worked the identity question directly. Chick, Morello & Staffey (2026) report a six-week summer institute that took ten faculty from Education, Health Sciences, Business and other programs out of low AI fluency (mean self-rating 1.89 on a six-point scale) to 60% reporting high confidence in guiding student AI use and 90% positive perceptions, and they attribute the shift less to tool training than to structured, safe experimentation that opened with the existential question of professional value rather than with demos. The vocabulary change is the marker they lean on: early framings of AI as a "cheating machine" or a "dehumanizing force" gave way to "curious assistant," and their four themes — fear to curiosity, a desire for ethical clarity the policy vacuum did not supply, inclusive design as an equity amplifier, and faculty moving from gatekeepers to guides — describe a partial, deliberate reorientation of instructional identity. The ten capstone redesigns are the harder evidence, with eight of ten positioning AI as a scaffold supporting rather than replacing thinking, and the authors' **symbiotic pedagogy** formalises what participants built: complementary design, transparent process, critical integration, embedded ethical reasoning and iterative refinement. The caveat is structural rather than individual: the same participants named contradictory policy signals, personal tool subscriptions and no time release for the redesigns, so the authors conclude that resistance was never the problem and that piecemeal responses leaving policy and infrastructure untouched will fail even an enthusiastic cohort.

Development as mediation, and the first question a developer asks. Sithole (2026) studies academic development — the field's older name, and the term used by the *International Journal for Academic Development*, which published the paper — at two South African Historically Disadvantaged Institutions, and reframes developers not as technical implementers but as **digital mediators** working across three registers: pedagogical (translating AI discourse into viable teaching, learning and Assessment practice), ethical (holding automation against Academic Integrity, innovation against care), and institutional (working the liminal space between management imperatives and academic concerns). Two findings matter for program design. First, the filtering question is contextual before it is technical — "what does this mean for teaching here, for our students from poor schools?" — and slowing adoption down counts as part of the work rather than resistance to it. Second, the affective cost is structural, not personal: developers were expected to project expertise in tools whose implications they were still working out ("I feel like an impostor. I am learning AI as I go, but the institution expects expertise"), and their response was peer professional learning aimed at judgment rather than skill, including deliberately trying to break the tools. The paper's analytical contribution is to separate digital inequality, a distributive problem, from **algorithmic coloniality**, an epistemic one that survives full access — and to place both inside Global South higher education, where development work is expected to be transformative rather than a neutral support service.

Guilt and moral discomfort as a developmental signal. Vassallo (2026) supplies the affective counterpart to the identity account. In a survey of academic staff at a Maltese university (109 responses, a 3.5% rate the paper reads as itself informative about the state of ethical debate), guilt tracked concealment rather than disclosure — limiting AI use because of unease correlated with the AI Guilt Index at r = .62 and avoiding disclosure to colleagues at r = .50 — while formal disclosure in academic outputs showed no relationship (r

= .08). Only 31.2% saw clear institutional guidelines, and the correlation between that clarity and lower guilt was weak (r = −.25, p = .010), which the paper reads as evidence that top-down mandates cannot resolve a partly emotional and identity-based problem. Its recommendations are directly developmental: treat guilt and identity concern as normal transitional responses rather than faults to correct, use structured low-stakes experimentation to move staff through anticipatory anxiety, and lean on mentorship by senior academics, since guilt was highest among early-career staff (M = 2.71) and lowest among senior ones (M = 2.03).

Practical guidance for program designers

For faculty developers, academic leaders, and instructional designers planning AI professional development, the knowledge base's evidence suggests:

Address the four adoption drivers, not just knowledge. Confidence, attitudes, support, and concerns predict whether faculty actually adopt AI — a knowledge-only workshop that ignores these is unlikely to change practice. Design development to build confidence through hands-on use, provide ongoing support (not one-shot training), and actively surface and respond to faculty concerns.(AI adoption among teachers: Insights on concerns, support, confidence, and attitudes)

Confidence and literacy are not interchangeable targets: in a 502-respondent SEM of university faculty, AI literacy was the dominant predictor of AI Well-Being (β = 0.713) while technological self-efficacy contributed little (β = 0.082), and support reached well-being only indirectly (Liu et al. (2026)).

Treat guideline demand and guideline adequacy as separate problems. Faculty at one university strongly backed institutional measures against unethical AI use (M = 4.59) while rating existing guidelines lowest (M = 2.99), and named data privacy and cultural inclusivity their weakest knowledge - a concrete target for professional development (Bilgic & Sever, 2026).

Treat readiness as a sociotechnical alignment problem. The EPIQ-AI framework shows faculty readiness spans epistemic, pedagogical, institutional, and quality-and-compliance domains. Programs that only train the individual miss the institutional levers (policy, workload, incentives, quality standards) that enable or block change — align those alongside training.(Faculty Readiness for AI-Supported Teaching and Scalable Online Program Delivery in Higher Education: The EPIQ-AI Framework for Epistemic Integrity)

Do not equate infrastructure investment with transformation. Across 125 studies, institutional investment in GenAI infrastructure and educational development correlated only weakly with actual pedagogical change (r = 0.12), while 60–70% of instructors felt unprepared to integrate GenAI — making development, not procurement, the binding constraint.(Rathnayake (2026)) **Name the failure mode, not only the effect size.** Fajardo-Ramos, Chiappe and Martínez-Pérez (2026) call it simulated innovation: tool presence signals progress, teaching and assessment formats stay intact, adoption rates and dashboards stand in for learning, and the technology release cycle sets the direction. Their diagnostic asks a development program to justify each tool against a named learning problem before adoption.

Build toward curriculum redesign, not tool adoption. The goal is faculty redesigning courses and assessment, not just adding AI tools. Ground professional development in course-level redesign work and assessment reform, and give faculty structured frameworks for doing so (e.g. assessment scales, institutional change frameworks).(A framework for institutional change in the age of AI)('A bit of chaos and madness': The AI Assessment Scale and the work of assessment reform)

Convene the village, not the individual. Across 12 academics and 17 students interviewed, GenAI-era assessment redesign exceeded any single academic's capability — inflexible processes, long lead times and workload burden were named — so the authors propose a program-wide team combining assessment-design, GenAI, subject-matter, program and industry expertise (Nicola-Richmond et al., 2025).

Run the series on the room's own data rather than imported best practice. Perl-Nussbaum and Finkelstein (2026) document a worked model from a large public R1 physics department: six biweekly sessions of 60 to 75 minutes, nineteen faculty participating across the series and about ten at any meeting, in which every session opened with local data or department-sourced materials, moved to small-group testing of AI against real anonymized student homework, and closed in collective discussion. What faculty found by testing was more useful than any package the facilitators could have imported — AI solved every problem they tried, but its feedback on real student work was uneven, prompt-dependent and surface-focused unless given explicit goals and rubrics, and students prompted shallowly and modified output superficially unless productive use was modeled. The first concrete output was a living repository of five entries — syllabus policy statements, classroom discussion materials, the student survey, AI-integrated homework tasks and assessment structures — which is why the authors treat the session structure itself as the argument rather than any content it delivered.

Anchor in a competency framework. Development should also build **pedagogical prompt literacy** — the capacity to encode pedagogical intentions into prompts — since Talebzadeh (2026) finds it is pedagogical expertise, not AI fluency, that determines the quality of teachers' AI-assisted design work.(AI-accelerated End-to-End Framework for Rapid Professional Upskilling)(AI literacy-related domains and AI-TPACK readiness among preservice mathematics teachers: A factor-informed structural equation modelling study) (The Architecture of Roles in AI-Designed Group Activities: A comparative inductive analysis of novice and experienced teachers' differentiated instruction within the IAT framework)

Sequence understanding before automation. A critical discourse analysis of 14 pieces of gray literature published between November 2022 and April 2025 advising practitioners on generative AI for constructive alignment finds that capability must precede tool access: because quality of engagement precedes quality of understanding in a Constructivism framework, risk scales inversely with familiarity, and novices are the most exposed to plausibility-driven acceptance of plausible-looking but pedagogically thin outputs. McInnes et al. (2026) further argue that development units should resist a technicist brief — helping faculty "acquire fluency" in tools that do "the heavy lifting" of course design — because that framing shuts developers out of a closed educator–GenAI loop and recasts values-led, relational development as a mediating mechanism for software adoption. The defensible alternative keeps educational developers as curators and rule-setters of any institutionally bounded retrieval-augmented alignment assistant that poses probing questions, flags under- and over-assessment and generates alternatives but never finished artifacts, with escalation to human judgment on accreditation and cross-program matters treated as a feature rather than an exception.

Surface and address fears and mental models. Before redesigning teaching, use a metaphor-analysis workshop (Vallis, Wilson & Casey 2025) to surface a team's assumptions and anxieties about GenAI — including the fear that it will replace teaching roles — and build development that responds to them rather than ignoring them.(Fear and awe: Making sense of generative AI through metaphor)

Model AI literacy and measure real gains. Faculty development should itself embody the practices being taught — using AI pedagogically, evaluating outputs critically — and should assess demonstrated

competence rather than self-reported confidence, since self-perception reliably overestimates AI skill.(How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures)(Efficacy of an Intensive Generative AI Professional Development Program on Pedagogical Content Knowledge (AI-PCK) and the Comparative Analysis of Learning Gain between Experienced and Pre-service Teachers)

Do not assume subject-matter expertise carries over to GenAI. Sutedjo, Chowdhury & Liu (2026) surveyed 127 U.S. research-university faculty using the TPACK-21 instrument and found content knowledge (CK) showed **no significant correlation** with technological knowledge or any technology-integrated domain (r =.11–.15, ns) — disciplinary expertise did not predict GenAI-integration knowledge. The technology-integrated domains (TPK, TCK, TPACK) inter-correlated so strongly (r =.81–.91) that they may function as a single GenAI-integration factor. Practically: build GenAI integration through **discipline-specific** activities that connect GenAI affordances to each faculty member's subject matter, and treat the technology-integrated domains as one shared GenAI-literacy foundation rather than train them as separate skills.(Assessing faculty self-perceived knowledge in using generative AI to teach 21st-century skills)

Discipline-specific smart-classroom models. Zhu, Liang, Mao, and Wang (2026) show how a mathematics M.Ed. course can be enhanced with intelligent educational technologies (automated scoring, personalized recommendations, multi-AI feedback) integrated across pre-, in-, and post-class stages within a three-dimensional smart-classroom framework. Their quasi-experiment found statistically significant gains in instructional-objective design proficiency, offering a transferable **D-T-E Model** (Disciplinary Demand–Technological Empowerment–Evaluation Loop) for teacher educators and educational developers looking to move smart-education frameworks from macro concepts into discipline-specific practice.

Measure attendance, not the feeling of engagement. In a six-month Intelligent-TPACK program for 64 university teachers, attendance rate predicted the gain in AI competency ($\beta = .407$, $p = .001$) while self-perceived participation did not ($\beta = .049$, $p = .692$), which the authors read as concrete behavioral investment against surface-level engagement (Tan, Cheng & Ling, 2025). The program paired online lectures with three face-to-face workshops, then required teachers to revise their instructional designs and implement them the following semester, and the authors recommend tying attendance into appraisal alongside meaningful incentives.

Benchmark against what faculty themselves report. Watson & Rainie (2026)'s survey of 1,057 US faculty finds the institutional layer thin in ways program designers can measure directly: 59% judged their school unprepared to use generative AI effectively for preparing students for the future and 68% said it had not prepared faculty to use it for teaching and mentoring, while the structural response ran to a task force in 55% of institutions but an AI literacy general education outcome in only 13%. Faculty had not waited for policy — 87% wrote their own assignment-level rules against 48% who could point to an institutional one — and they named colleagues' resistance (82%) and unfamiliarity (83%), not mandate, as the obstacles to departmental adoption. For development programs this argues for treating peer norms, shared assignment-level policy language and explicit measures of institutional readiness as part of the intervention rather than leaving them to the policy document.

Instructor response reflects power centers, not attitude. In an instrumental case study of 33 writing instructors, four polycentric power centers — the global GenAI trend, the university/department, colleagues,

and students — shaped practice, and adjuncts constrained by limited discourse power shifted from detection toward teaching acceptable use (Zuo et al. (2026)).

- **Six professional-development families, three well evidenced, and a clear winner.** A review of 78 studies of AI-supported instructional design sorts documented PD into compact embedded modules (2-4 weeks), semester-long microlearning, task-based design cycles, collaborative dialogue-based question chains, critical co-discovery, and self-directed practitioner learning. Outcome evidence is strongest for **compact embedded modules**: a three-week module produced statistically significant gains across all six Intelligent-TPACK domains with medium-to-large effect sizes, and a four-week program with **436 pre-service teachers and a control condition** is the strongest controlled evaluation in the corpus (Spyropoulou & Kameas, 2026).
- **Three design features separate the best-evidenced interventions.** Ethics embedded as **distributed practice with checkpoints at every task** rather than a stand-alone session; **performance-based competence assessment** using lesson plans, decision logs and micro-teaching, motivated directly by the unreliability of self-report; and prompt engineering developed as reflective, pedagogically grounded practice. Adoption is not the same lever as performance: across 200 teachers in North Sumatra, AI use had no direct effect on teacher performance ($\beta = 0.112$, $p = .087$) while organizational citizenship behavior carried it indirectly, so faculty-development work aimed at collaborative, extra-role use is the version the evidence supports (Sherly et al. (2027)). A companion two-week study found rapid gains in knowledge and confidence while identifying bias detection as the weakest emerging competence — a gap that persisted into the longer module, consistent with ethical perceptual capacity developing more slowly than technological familiarity.

Common Misconceptions

“A skills workshop is the intervention educational development needs.” Readiness is a sociotechnical alignment problem, not an individual deficit, which is why a standalone “AI workshop” falls short of the need it addresses. A program that worked the question directly was a **six-week summer institute** taking ten faculty from Education, Health Sciences, Business and other programs through identity-level work. Duration and cohort are not incidental to that design; they are what distinguishes it from a feature tour.

“Clearer institutional guidelines will resolve faculty unease.” Guidelines help and they do not reach the problem. Only **31.2%** of academic staff at a Maltese university perceived clear institutional guidelines, and the correlation between guideline clarity and lower guilt was **weak ($r = -.25$, $p = .010$)**. A weak relationship at that scale means top-down mandates cannot settle what the paper reads as a partly emotional and identity-based problem — the fifth of the variance they explain is not the fifth that matters.

“Guilt about AI use indicates rule-breaking.” It tracks concealment rather than disclosure: limiting AI use because of unease correlated with hiding it, not with prohibited behavior. Reading guilt as evidence of misconduct therefore misidentifies its source, and treating it as a compliance signal will push the behavior further out of view.

“A low survey response rate means faculty have no strong feelings.” The paper reads its **109 responses (a 3.5% rate)** as itself informative about the state of ethical debate — a low response to a question about discomfort is a finding about that discomfort, not an absence of one. And a GenAI integration framed purely

as upskilling misses the identity question some faculty are actually asking: what the point of teaching is in a GenAI world.

Connected Concepts

- Teacher AI Competency
- Teaching
- AI Literacy
- Educational AI Policy
- Higher Education
- K-12
- Learning Design
- Curriculum Design
- Workplace Learning
- Teacher Education
- Learning Sciences
- Educational Technology Developers
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)

Connected Articles

- Efficiency at what cost? Salvaging constructive alignment from the GenAI hype — Critical discourse analysis of GenAI alignment advice: developers recast as technology trainers
- Designing faculty standards for technology integration in higher education institutions: a design-based research study — Faculty standards for technology integration (DBR)
- Understanding ethical dimensions of AI in higher education: insights from faculty members and students — Ethical dimensions of AI: faculty and student views
- It takes a village. Program-wide approaches to redesigning assessment in a time of generative artificial intelligence (GenAI)
- It’s Like "X": How Engineering Faculty Metaphors Construct (and Constrain) AI Understanding in Engineering Education — How Engineering Faculty Metaphors Construct (and Constrain) AI Understanding
- Fear and awe: Making sense of generative AI through metaphor — Fear and Awe: Making Sense of Generative AI Through Metaphor (faculty/staff/student metaphor workshop)
- Governing the Unseen: A Systematic Review of AI Literacy among Language Teachers in Higher Education — Governing the unseen: AI literacy among language teachers
- Faculty Readiness for AI-Supported Teaching and Scalable Online Program Delivery in Higher Education: The EPIQ-AI Framework for Epistemic Integrity
- AI adoption among teachers: Insights on concerns, support, confidence, and attitudes

- A framework for institutional change in the age of AI
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education
- AI literacy-related domains and AI-TPACK readiness among preservice mathematics teachers: A factor-informed structural equation modelling study
- AI-accelerated End-to-End Framework for Rapid Professional Upskilling
- ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform
- From Prompts to Verified Loops: The PCHL-HE Framework for Generative AI-Assisted Educational and Research Content Creation in Higher Education
- Efficacy of an Intensive Generative AI Professional Development Program on Pedagogical Content Knowledge (AI-PCK) and the Comparative Analysis of Learning Gain between Experienced and Pre-service Teachers
- Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025)
- When faculty ask, "what’s the point of teaching?": GenAI as identity crisis, not skills gap — GenAI as identity crisis, not skills gap
- "Will AI steal my glory?": Power relations perceived by college instructors when grappling with Generative AI — Power relations perceived by college instructors grappling with GenAI in writing (Zuo, Xu & Dunning 2026)
- The Reflective Triangle Model: AI as a Cognitive Mediator in Teachers’ Professional Learning and Learning-Community Development — Reflective Triangle Model: AI as cognitive mediator
- Assessing faculty self-perceived knowledge in using generative AI to teach 21st-century skills — Faculty self-perceived TPACK-21 knowledge for GenAI (Sutedjo, Chowdhury & Liu 2026)
- Enhancing teachers’ AI competency: A professional development intervention study based on intelligent-TPACK framework — Intelligent-TPACK PD: attendance predicts gains, self-perceived participation does not
- Improving instructional design proficiency of master’s students in mathematics education through intelligent educational technologies — Smart-classroom model and D-T-E loop improving M.Ed. instructional design proficiency in mathematics (Zhu et al. 2026)
- The Architecture of Roles in AI-Designed Group Activities: A comparative inductive analysis of novice and experienced teachers’ differentiated instruction within the IAT framework — Architecture of roles in AI-designed differentiated group activities (Talebzadeh 2026)
- Navigating uncertainty: university teachers’ experiences and perceptions of generative artificial intelligence in teaching and learning — University teachers’ experiences and perceptions of GAI: vulnerability, rethinking assessment, student learning at risk (Farazouli et al. 2026)
- From fear to innovation: A case study of transformative faculty development for ethical AI integration in higher education — From fear to innovation: a six-week faculty institute, symbiotic pedagogy, and the institutional conditions it could not supply

- The AI guilt complex: Moral emotions and ethical dilemmas in academic technology adoption — The AI Guilt Complex: anticipatory guilt, concealment and career-stage differences among academic staff (Vassallo 2026)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — AAC&U/Elon survey of 1,057 US faculty: institutional unpreparedness, thin governance and the 87%/48% policy gap (Watson & Rainie 2026)
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Academic developers as digital mediators in Global South higher education: development as sociotechnical praxis
- A Workshop Series for Effective Use of AI in Uncertain Times: Building a Physics Faculty Learning Community — A Workshop Series for Effective Use of AI in Uncertain Times: Building a Physics Faculty Learning Community
- Exploring University Faculty's AI Well-Being: A Structural Equation Model of Social Supports, AI Literacy, and Technological Self-Efficacy — Faculty AI well-being tracks AI literacy rather than technological self-efficacy
- The AI Competence Framework Landscape: A Comparative Analysis of Frameworks for Education and Workforce Development — Check what a framework's levels describe before adopting it
- Can education set the agenda for AI? Simulated innovation and pedagogical direction-setting in teacher education — Can education set the agenda for AI? Simulated innovation and pedagogical directionsetting in teacher education

Connected FAQs

- How Can AI Save Me Time as an Instructor?
- What Competencies Do Faculty Need in Regard to AI?
- How Do I Design Faculty Development for AI That Actually Changes Practice?

The field

History of AI in Education

> **History of AI in Education** — the study of how artificial intelligence and education have co-evolved since the mid-20th century, and how past conceptual, terminological, and design choices continue to shape today's debates about AI in learning. Rather than treating generative AI as a sudden, unprecedented force, a historical lens reveals recurring tensions — control vs. agency, standardization vs. Creativity, automation vs. augmentation — that have structured AI in education since its origins.

Questions to Consider

- Today's generative AI is often described as an unprecedented revolution. How might that framing ('chronocentrism') prevent us from seeing the recurring patterns beneath it?
- The field was almost named 'cybernetics' instead of 'artificial intelligence.' How might that single naming choice have shaped whether we see machines as independent intelligences or as part of interconnected feedback systems?
- The page frames AIED history as a tension between control (Anderson's cognitive tutors optimizing instruction) and agency (Papert's constructionism empowering learners). Where do your own AI-in-education choices fall on that spectrum — and why?
- Personalization, the page argues, has two meanings: varying the path to the same outcome, or enabling diverse, learner-directed outcomes. Which kind of personalization does your institution actually pursue, and which do you think it should?
- If today's GenAI debates 'mirror' these historical tensions, what past mistakes might we be repeating — and what might we avoid by remembering them?
- The page claims technical design choices embed value judgments about learning's purpose. Can you identify a design decision in an AI education tool you've used that quietly favored standardization over learner agency — or vice versa?

Introduction

The field's history is not a linear progression but a series of contingent decisions whose effects still echo. Understanding this history guards against "chronocentrism" (the bias of treating current developments as uniquely revolutionary), helps avoid repeating past mistakes, and reveals how choices about framing and terminology — not just technology — steer the trajectory of AI in education.

Key historical threads

From cybernetics to "artificial intelligence." When John McCarthy planned the 1956 Dartmouth Summer Research Project, he deliberately chose the term *artificial intelligence* over *cybernetics* — partly to distance the field from Norbert Wiener and his focus on analog feedback. This naming decision framed machine capabilities in direct comparison to human cognition (anthropomorphic framing), steering research priorities,

public perception, and ethical debate for decades. Had the field kept the cybernetic framing, the article imagines we might now speak of “cybernetic learning systems” emphasizing feedback and interconnection rather than “AI tutors” positioning the machine as an independent source of intelligence.

The cognitive revolution and the roots of ITS. Early pioneers — Herbert Simon, Allen Newell, Marvin Minsky, John Anderson — were not merely modeling cognition; they were investigating fundamental questions about learning and instruction. Their work produced information-processing models of human cognition that became foundational to educational psychology, and led to Intelligent Tutoring Systems (ITS), rooted in the heuristic-search and expert-systems paradigms of 1960s–70s AI. These systems aligned naturally with existing structures of assessment and standardization, and eventually coalesced into the AIED community.

Control vs. agency: Anderson and Papert. Two competing visions emerged, embodied in John Anderson and Seymour Papert. **Anderson’s** cognitive tutors (ACT/ACT-R theory) decomposed knowledge into production rules, provided precise individualized feedback, and reinforced traditional educational structures — a vision of AI as a tool for optimizing instruction. **Papert’s** constructionism (Logo, “microworlds,” debugging-as-learning) saw computers as environments where children construct knowledge through creative experimentation — a vision of AI as an instrument of intellectual empowerment that challenged institutional hierarchies. This “essential tension” between control and agency is the through-line of the field’s history.

Two forms of personalization. Personalization has two distinct interpretations that map onto these visions. The first maintains uniform outcomes while varying the path (rooted in Skinner’s teaching machines; the Khan Academy vision of tutoring to mastery). The second embraces diverse outcomes — learners pursuing individual interests and talents, unconstrained by standard curriculum boundaries (Zhao, 2024). The ITS model supports the former; constructionism the latter.

Lessons for the GenAI era. Today’s debates about generative AI closely mirror these historical tensions. GenAI is often positioned as a next-generation intelligent tutor (extending Anderson), raising concerns about surveillance, data collection, and standardization. Alternatively it can be a tool for creative agency (extending Papert), requiring us to rethink assessment and accept more ambiguous outcomes. As Mishra et al. conclude, institutional forces repeatedly favor approaches that reinforce existing structures — and the language and metaphors we choose will shape future possibilities. Rismanchian & Doroudi’s AI×Ed framework gives this intuition empirical grounding: locating papers from AIED proceedings (1985, 1993, 2021, 2024) and IJAIED (2004, 2014, 2021) along two axes — the role of AI (applied tool vs. analogy to human intelligence) and the end user — they trace a field that moved from a diverse mix, including substantial early research using AI as an analogy to human intelligence (computational models of learning, Papert’s microworlds, agent-based models of knowledge acquisition), toward a near-exclusive focus on applied, instrumental uses by the 2000s. Notably, the generative-AI era appears to partially reverse that trajectory: by AIED 2024, three of the four slots in the “AI-as-analogy” quadrant were LLM-built, and one of those took a best-paper award for LLM-powered teachable agents.

The recent impact of generative AI

The arrival of generative AI — a broad family that includes large language models (text), plus image, audio, and video generators — marks the most consequential inflection point in AIED history since the field’s

founding. LLMs are the most prominent member of this family and the driver of most classroom impact, but generative AI as a whole (capable of producing novel text, images, sound, and code) is the broader force reshaping education. It is best understood against AIED history rather than as a clean break. Several features make the generative-AI era distinctive:

Scale and reach. Unlike the cognitive tutors and ITS of earlier decades, which operated in controlled lab and classroom settings, LLMs reached hundreds of millions of learners and educators within months of release, entering everyday writing, homework, and instruction almost immediately. The GenAI debate moved from specialist journals to classrooms, boardrooms, and legislatures with unprecedented speed.

A new kind of capability. Earlier AIED systems modeled cognition and delivered structured instruction (the Anderson tradition). LLMs perform open-ended generation — producing essays, explanations, code, and dialogue — which foregrounds learner agency and creativity (the Papert tradition) in ways earlier ITS could not. This is why the current moment re-ignites the control-vs-agency tension so sharply: the same tool can be deployed as a next-generation intelligent tutor (controlling outcomes) or as a creative co-writer and thinking partner (amplifying agency).

A reversal of the access equation. Historically, personalized tutoring was scarce and expensive; GenAI made adaptive one-on-one support nearly free and universal — dramatically lowering the accessibility and cost barriers that shaped earlier AIED. But it also introduced new risks: algorithmic bias, hallucination, surveillance, data collection, and the de-skilling of educators.

Renewed concern about AI literacy and misuse. The generative-AI era made AI Literacy urgent and reframed Academic Integrity debates (detection vs. dialog), while reviving long-standing concerns about automation, standardization, and epistemic dependence. These are the modern expressions of the field's original tensions.

Chronocentrism's risk. As Mishra et al. warn, the hype around generative AI often lacks historical awareness, letting tech evangelists dominate the conversation. Understanding that today's GenAI debates echo the Anderson–Papert divide and the 1955 cybernetics naming decision helps us make deliberate choices rather than treating the present as inevitable. The real question is not what generative-AI tools can do, but what we want them to do — a decision shaped by where we have been.

Implications

- **Read hype historically.** Recognize that each new AI wave is framed as revolutionary; historical awareness reveals continuity and helps resist corporate dominance of the conversation.
- **See design choices as value choices.** Technical decisions about AI in education embed ideological positions about learning's purpose — surface and interrogate them.
- **Weigh control against agency deliberately.** Whether AI should optimize toward standard outcomes or enable diverse, learner-directed outcomes is a genuine choice with institutional and political consequences, not a technical given.
- **Preserve learner agency.** The recurring resistance to standardization and control in favor of open-ended, learner-centered approaches is a durable thread worth defending.

Common Misconceptions

"AI in education began with ChatGPT." It did not, and the belief is costly because it makes every earlier lesson invisible. Intelligent tutoring descends from the heuristic-search and expert-systems work of the 1960s and 70s, and the AIED community formed around it decades before large language models. Mishra et al. show the current debates reproducing a divide already explicit in Anderson's cognitive tutors and Papert's constructionism, so a reader who dates the field to 2022 will re-derive arguments the field settled, abandoned, or lost once before.

"The field has steadily abandoned AI-as-analogy in favor of applied tools, and generative AI continues that trend." This is the most instructive correction on the page, because the trajectory is real but not monotonic. Rismanchian and Doroudi's positional analysis of AIED 1985, 1993, 2021 and 2024 and IJAIED 2004, 2014 and 2021 does show a drift from a mixed field toward near-exclusive applied instrumentality by the 2000s. But at AIED 2024, three of the four papers in the AI-as-analogy quadrant were LLM-based, including best-paper work on LLM-based teachable agents. Generative AI partly **reverses** the trend rather than extending it, which is why treating it as "the next intelligent tutor" misreads where the research frontier actually moved.

"Personalization means adapting the difficulty to each learner." That is only one of two incompatible senses, and conflating them hides a political choice. In the first sense the outcome is held fixed and only the path varies, the lineage running from Skinner's teaching machines through mastery-based tutoring. In the second the outcomes themselves diversify, as learners pursue individual interests unconstrained by standard curriculum (Zhao, 2024). An ITS implements the first; constructionism the second. A tool described as "personalized" has told you nothing until you know which it means.

"'Artificial intelligence' was simply the obvious name for the field." The term was a deliberate choice. When McCarthy planned the 1956 Dartmouth project he favored *artificial intelligence* over *cybernetics* partly to distance the work from Wiener's analog feedback tradition. That single decision framed machines in direct comparison to human cognition, and the anthropomorphic framing it installed still shapes research priorities, product language, and the ethical questions the public asks.

Putting It into Practice

For instructors and instructional designers

- Name the tradition your tool belongs to before adopting it. Ask whether it optimizes toward fixed outcomes or opens learner direction, because that answer, not the feature list, determines what it will do to your assessment design.
- Interrogate the word "personalized" in every vendor claim, and get an answer in terms of the two senses above. A product that varies pacing toward a common standard and one that lets students diverge are not substitutes.
- When students present GenAI as unprecedented, the history is teachable content in its own right. The Anderson-Papert framing gives them a vocabulary for arguing about AI rather than only using it.

For developers

- Interface language is a design decision with a lineage. Calling your system an “AI tutor” inherits Anderson’s framing and the expectation of optimizing toward standard outcomes; calling it a “microworld” or “learning environment” inherits Papert’s. Neither is neutral, so choose deliberately.
- If you are building in the analogy tradition (models of learning, teachable agents, simulations of knowledge acquisition), say so. That quadrant was nearly empty for two decades and is repopulating; the positioning is a differentiator and the evaluation criteria are different.

For researchers

- Use the historical corpora as a baseline rather than treating the present as the only available comparison. The AIED proceedings for 1985, 1993, 2021 and 2024 and IJAIED for 2004, 2014 and 2021 are a ready-made longitudinal sample of the field’s own claims.
- Cite lineage when you claim novelty. A claim that a system “personalizes learning” or “models the learner” is only novel relative to a specific prior tradition, and the tradition is documented.

Connected Concepts

- AI in Education
- Intelligent Tutoring
- Constructivism
- Learner Agency
- Personalized Learning
- Generative AI
- Learning Theories
- Adaptive Learning
- AI Literacy
- Creativity
- Teaching
- Ethics

Connected Articles

- Control vs. Agency: Exploring the History of AI in Education — Control vs. Agency: Exploring the History of AI in Education
- How human-centered is AI-aided learning in education? — Human-centered AI-aided learning (engages Anderson’s legacy)
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — Cognitive commons and AI expertise (historical framing)
- Programming Intelligent Tutoring Systems — Programming Intelligent Tutoring Systems

- Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems — Revisiting the hint button in cognitive tutors
- Learning by Teaching: Engaging Students as Instructors of Large Language Models in Computer Science Education — Learning-by-teaching with LLMs (Papert's constructionism lineage)
- The evolution of research on AI and education across four decades: Insights from the AIxEd framework

Interpreting and Applying AIEd Research

> **Interpreting and applying AIEd research** — how to decide whether an AI-in-education finding is worth acting on, whether you teach, run a program, design a course, or build software. You do not need statistics to use this page. It starts with the question a practitioner actually has — *should I do this?* — works through the few things that answer it, and keeps the technical detail in a later section for anyone who wants or needs it. The short version: a finding is worth acting on when you know what was compared, what was measured, who was studied, and whether the tool still exists in the form that was studied. Most claims that reach instructors, administrators and developers fail one of those four.

Questions to Consider

- A vendor, a news story, or a colleague says an AI tool improved learning. What is the one thing you would want to see before trying it in your own course — and would you know where to look for it?
- Every article page in this knowledge base now has a **What this means for practice** section, and most have a **Limitations** section. Reading the two together, what does each tell you that the other does not?
- Students practice with an AI tool and do better on the practice work, then do worse on the closed-book exam. Which number is the learning outcome your course cares about — and would your current assessments catch the difference?
- A study promises a big improvement, but it followed 30 students in one course at one institution, and the version of the tool studied is no longer the version anyone uses. Which of those two facts worries you more, and why?
- Many AI tools increase how much students use them without increasing how much they learn. If you had to choose between a tool that raises engagement and one that raises unassisted performance, what evidence would settle it?
- You are asked to approve or buy a tool on the strength of the vendor's own effectiveness numbers. What would you want disclosed about how those numbers were produced?

Introduction

This page is for people who have to decide something: an instructor wondering whether to change an assignment, an Administrators weighing a pilot, a learning designer building a course, a software developer deciding what a feature should do, or a researcher explaining a finding to any of them.

Two habits make the difference, and neither needs research training.

Read the two sections written for you first. Every article page here now carries a **What this means for practice** section — usually three to five concrete actions derived from that study — and most carry a **Limitations** section stating what the study cannot support. Read those before the study's findings, not after.

The practice section tells you what the study is good for; the limitations section tells you where it stops. If the practice section is missing or vague, treat that page as unfinished rather than as evidence.

Judge the claim, not the confidence of the claim. Claims about AI in education are usually accurate about *something* and misleading about the thing you care about, because a study and your classroom differ in four ways: what it was compared against, what it measured, who took part, and which version of the tool was used. The rest of this page gives you the checks in plain language, then the evidence behind each of them for readers who want it.

What follows is also not a replacement for its neighbours. Research Methods in AI in Education covers how designs are built, Limitations in AIEd Research catalogues the literature's recurring weaknesses, AIED Evaluation covers how systems and outputs are evaluated, and Differential Effects Across Learner Groups covers who a finding does and does not include.

Four questions that settle most claims

Ask these before you spend time, money, or a semester on something.

1. What was it compared against, and was that comparison fair? "Students who used the AI did better than students who didn't" only tells you something if the other students were doing something real. If the comparison was business as usual — or nothing — then the finding bundles the tool together with extra time, extra attention and novelty. What to look for: a **control group** that got a credible alternative, and random assignment to the two conditions.

2. What exactly did they measure? This is where most exciting claims quietly fail. Test scores, homework quality, Motivation, attitudes and engagement get pooled into a single "achievement" number, or a measure of performance *with the tool present* gets reported as learning. Learning that depends on the tool being there is not the same as learning that lasts. What to look for: what the instrument measured, whether it was validated for that population, and whether an outcome was measured **without** the AI in the room.

3. Who was studied, how many, and for how long? Thirty students in one course is a signal, not a result. A four-week intervention cannot tell you about a year. And a study of students unlike yours is still useful — it is a hypothesis about your setting, not a prediction. What to look for: sample size, how participants were recruited, single site, duration, and whether any subgroup was large enough to analyze.

4. Is the tool still the tool that was studied? AI capability moves faster than publication. A 2025 finding describes the 2025 model generation — sometimes a specific version, sometimes a configuration nobody uses now. That does not make the finding false; it makes it dated, and it means the claim should be re-checked rather than inherited. What to look for: model version and the data-collection window.

What the evidence says about AI claims in general

If you remember one thing from this page, remember that the headline number is usually inflated and the comparison is usually weak. That is not a fringe view — it is what audits of the field itself report. Several well-designed studies do show real gains; the point is that the burden of proof sits with the claim.

- **About two-thirds of the average effect disappears** once you correct for the fact that impressive results get published and unimpressive ones do not. Bartoš et al. (2026) pooled 1,840 effect sizes

from 67 reviews and found the corrected average was roughly one-third of the published median — SMD 0.196 against 0.67.

- **A product name is not a teaching method.** Auditing the comparisons behind a prominent meta-analysis, Weidlich et al. (2025) found only **21%** had a well-defined treatment, a control group and a valid learning measure — and the reported advantage for "using ChatGPT" came out larger than for purpose-built intelligent tutoring systems (g = 0.7 against 0.66), which is a warning sign rather than a triumph.
- **Performance with the tool is routinely mistaken for learning.** In one K-12 math study, students practicing with a general-purpose chatbot earned better practice grades and then scored **about 17% worse** than peers with no AI access on the closed-book final (Stanford's evidence base for AI in K-12).
- **The field's own reviews do not survive audit.** O'Neill's (2026) audit of **14 peer-reviewed meta-analyses** claiming AI improves education found that **none** provided a valid basis for the claims it advanced, and among 46 randomly selected primary studies, **61%** presented validity concerns. The problem is not one bad paper; it is a reporting culture.
- **A review can quantify the reporting skew in its own corpus.** A systematic review of 155 higher-education studies found 117 (75.5%) reported successful implementation, 124 (80.0%) covered short-term impact only, and just 23 (14.8%) reported on Ethics, equity or governance failures — the imbalance the checks above describe, measured on the review's own evidence base (Nyamboga (2026)).
- **Self-reports flatter everyone.** People rate their own AI skills about **40%** higher than performance measures show, which is why satisfaction and confidence surveys are the weakest evidence you can act on (Self-Report Measures, Educational Measurement).
- **Most products already in classrooms have no independent evidence at all.** Instruction Partners' 2025–26 learning tour profiled 20 student-facing AI products and found that, of the 16 with complete profiles, only seven had an independent review examining student achievement across student groups in the US; two were studied only abroad, four had studies underway and three relied on internal data alone. The authors argue that independent causal studies covering priority groups should be the expectation for all student-facing products — not yet the norm for tools schools are already using.

Turning a finding into a decision

The sequence that saves the most wasted effort, in order.

1. **Write down your outcome first.** Not "use AI more" but "students can do X without the tool". If your outcome is unassisted performance, then a study that measured assisted performance is adjacent evidence, not direct evidence.
2. **Find the comparison and the measure** — in the study, or in the practice section of its article page. If either is missing, treat the claim as a demo rather than a finding.
3. **Read the limitations section as instructions, not disclaimers.** "Single course, self-reported outcomes, four weeks" tells you exactly which of your assumptions the study does not cover.

4. **Check the version and the date.** If the study used a model generation two years old, plan to re-test rather than assume.
5. **Name the enabling conditions.** Cost, licenses, staff time, data rules, and whether students must pay for the tier that actually works. Studies rarely carry these, and they decide whether an intervention survives a semester. In a faculty-development study of ten participants, everyone said they would keep using AI, while the same people described personal subscriptions for tool access and no time support for the redesigns they had planned.
6. **Pilot small, and measure the unsupported condition.** A short pre/post with one assessment done without the tool beats a satisfaction survey. Small and honest beats big and rhetorical. See Learning Design for where this fits in course design.
7. **Diary a review date, and be willing to drop the claim.** When a study's premise is a capability that no longer exists, the honest move is retiring the claim rather than citing it indefinitely — the same discipline this knowledge base applies to its own pages.

Words you will meet in the research

Plain translations, so you can skim a study or a vendor page without a methods background.

- **Effect size** — how big the difference was, on a scale where 0 is nothing. Treat small values as "a nudge", not "a transformation".
- **Statistically significant** — unlikely to be pure chance *in this sample*. It says nothing about whether the effect is large, or whether it will happen in your class.
- **Confidence interval** — the range of results the data cannot rule out. If the range includes zero, the finding may be nothing at all, however interesting the headline.
- **Meta-analysis** — a study that pools many studies. Powerful, and only as good as what it pooled, which is why reviews get audited.
- **Publication bias** — interesting results get published and boring ones do not, so the literature's average looks rosier than reality.
- **Self-report** — people describing themselves. Useful for attitudes, weak for competence or behavior.
- **Control group** — the comparison condition. The single most important thing to look for.
- **Pre/post** — measured before and after with no comparison group. Suggestive, never conclusive.
- **Subgroup analysis** — results for a slice of the sample. Usually underpowered, so treat it as a hypothesis.
- **Replication** — someone else got the same result. Rare, and the strongest evidence available.
- **Benchmark** — a fixed task set for scoring systems. Scores move when the target moves, so check the date.

When to slow down anyway

- **The claim comes from the vendor, on the vendor's metrics.** That can still be informative — one AI tutoring provider reports an engagement metric calibrated against human experts at F1 0.83, with improvements coming from over 40 experiments in five months (Udeshi et al., 2026) — but

the construct, the raters and the metric are the vendor's choices. Ask for the comparison group and the unassisted outcome.

- **Automated scoring is treated as solved.** High agreement with human raters is reliability, not quality. In one scoring study, human raters agreed with the multi-rater consensus at about r = 0.88, so automated scores near r = 0.85 were already at the task's own measurement ceiling (Know When to Trust AI Scoring).
- **The reference list is doing heavy lifting.** Thirty reference entries containing verifiably fabricated bibliographic information were confirmed across 14 computing-education papers, all from 2025 and 2026 (Denny et al., 2026). If a claim rests on a citation, check the citation.
- **Nobody measured the behavior your policy depends on.** Across 493 deduplicated records and 14 priority studies, no study measured whether verification succeeded *and* what the learner then did with it, judged against an independent standard of output quality (verification and reliance calibration). Course policies depend on exactly that behavior.

If you are building or buying a tool

The same checks invert into design requirements, and the knowledge base's evaluation pages carry the detail (AIED Evaluation, Automated Assessment).

- **Make the comparison part of the feature spec.** Decide what a learner would otherwise be doing, and be able to say why your tool beats that — not why it beats nothing.
- **Measure the unsupported condition.** If your outcome is learning, include a task completed without the tool; assisted performance alone will mislead you as much as it misleads your buyers.
- **Report how your automated judgments were validated** — the gold standard, the calibration target, who adjudicated disagreements — and report it as reliability rather than quality.
- **Name the version and the date** in any effectiveness claim, because your next release invalidates it.
- **Show the counterweights:** cost per student, Accessibility, data handling, and what happens to learners on the free tier. See AI Use Disclosure, Privacy and AI Governance.

For readers who want the evidence

The checks above are not folk wisdom; they come from documented failures in this literature. This section keeps the detail for anyone reviewing a paper, defending a decision, or arguing that a tool should be evaluated properly.

The validity failures have a distribution, not just a presence. In O'Neill's (2026) 46 audited studies, dependent-variable mismatch was the most common problem (n = 15) — the measure did not capture what the claim asserted — followed by independent-variable mismatch (n = 11), experimental design problems (n = 7), data extraction problems (n = 6), absence of a control group (n = 6) and nonrandom group assignment (n = 6). Of the 14 meta-analyses, twelve treated multiple effect sizes drawn from the same primary study as independent, which inflates the apparent evidence base.

Subgroup claims are usually undecidable in the studies that make them. The GCSE science micro-RCT reports a treatment-by-status interaction of **0.57 marks (95% CI -2.25 to 3.39)**, with stratified estimates of **g**

= 0.28 (95% CI -0.04 to 0.59) for one group and **g = 0.35 (95% CI 0.18 to 0.52)** for the other. An interval crossing zero is not an equity finding; it is a question for a local pilot.

A synthesis can satisfy its own protocol and still pool unweighted quality. Doğan et al. (2026) state plainly that they used no formal quality appraisal tool, treating their inclusion criteria as the rigor threshold, so a quasi-experimental study and a randomized one contributed equally — and their heterogeneity reads **I^2 = 82.98% under a fixed-effect model but 15.75% under the random-effects model**, which is why a heterogeneity figure quoted without its model cannot tell you how inconsistent the corpus is.

Validation of automated judgment is part of the result. Agreement with human coders is a reliability statement, and the ceiling above shows why it is not the same as quality (machines misread pedagogical quality).

Tool vintage is a first-class limitation. A review of AI-assisted assessment notes that its own findings reflect specific model versions at specific times, and that field movement makes any account of model capabilities potentially outdated within months (AI-Assisted Assessment and Instruction in Higher Education). Scope claims to their generation: "generative AI improved X" is not portable, while "GPT-4-era tooling, in this task, with this Scaffolding" is.

Benchmark targets move, so a result that a system saturates or fails today can invert with the next release; saturation and contamination checks belong beside any benchmark-based claim.

Reading this literature alongside its own critics is normal practice here. The reporting-side checklists for authors and reviewers are in the FAQ on reporting and interpreting AI research, and the appraisal habits in this page pair with Theory Development in AI in Education when a claim is theoretical rather than empirical.

A short checklist

1. State your outcome in one sentence, including whether the tool is present in it.
2. Find the comparison. No credible comparison, no decision.
3. Match the measure to your claim, and prefer an unassisted outcome.
4. Deflate the number: read the bias-corrected effect, not the headline.
5. Check the model version and the study's dates.
6. Read the limitations section as instructions for what you still do not know.
7. Cost it: licenses, tiers, staff time, data rules.
8. Pilot small with an unassisted measure, then decide.
9. Diary a review date a year out, and be ready to retire the claim.

Common Misconceptions

"A published meta-analysis is settled evidence about AI in education." The field's syntheses have not survived audit. O'Neill's (2026) audit of **14 peer-reviewed meta-analyses** claiming AI improves education found that **none** provided a valid basis for that conclusion. A pooled effect size is only as good as the studies pooled, and in this literature the pooling has routinely included designs that could not attribute the outcome to AI. Before you quote a meta-analytic number, ask what it aggregated.

“The bigger effect size belongs to the better intervention.” Often the opposite. In the review context this page documents, only **21%** of studies had a well-defined treatment, a control group and a valid learning measure — and the reported advantage for “using ChatGPT” came out *larger* than for purpose-built intelligent tutoring systems. Weakly specified treatments tend to produce inflated effects, because the comparison is vaguer and the outcome measure looser. A larger number is a reason to look at the design, not a reason to prefer the intervention.

“Higher grades while using the tool indicate the tool taught more.” In one K-12 math study, students practicing with a general-purpose chatbot earned better practice grades and then scored **about 17% worse** on unassisted assessment. Practice performance measured with the tool present is the inflated measure; the unassisted one is the outcome, and only one of them was rising.

“If the effect is real, the implementation details do not matter much.” They are the effect. A study that followed 30 students in one course at one institution, on a version of the tool nobody now uses, has produced a finding about a configuration that no longer exists. Treatment specification, version, and setting are part of the claim rather than context around it.

Connected Concepts

- Limitations in AIEd Research
- Learning Design
- AI Ed Evaluation
- Educational Measurement
- Assessment Validity
- Self-Report Measures
- Learning Gains
- Differential Effects Across Learner Groups
- Research Methods in AIED
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Meta-Analysis and Systematic Review
- Quantitative Research
- Benchmark
- RCT
- Intelligent Tutoring
- Cognitive Offloading
- AI Use and Disclosure Statements
- Theory Development in AI in Education

Connected Articles

- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Presumed Effective: forensic audit of 14 AIED meta-analyses

- Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis — Publication-bias-adjusted AI effects about one-third of reported size
- ChatGPT in Education: An Effect in Search of a Cause — ChatGPT in Education: An Effect in Search of a Cause
- The Impact of Artificial Intelligence-Supported Instruction on Student Learning in STEM: A Systematic Review and Meta-Analysis — Inclusion criteria used as the rigor threshold, and heterogeneity that changes with the model
- Know when to trust: Making AI scoring more reliable for educational assessment — When automated scoring reliability meets the task's measurement ceiling
- Beyond checking: verification quality, reliance calibration, and learning in generative AI-assisted higher education — What the verification and reliance literature does not measure
- Testing Our Foundations: Citation Trends, Errors, and Emerging Hallucinations in the Computing Education Literature — Fabricated references that reached print in 2025–2026
- The Evidence Base on AI in K-12: A 2026 Review — Practice gains, exam losses: the assistance-removal problem in K-12 math
- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — Subgroup effects whose confidence intervals cross zero
- From fear to innovation: A case study of transformative faculty development for ethical AI integration in higher education — Enabling conditions: policy signals, personal subscriptions, no time
- Methodologies for improving the quality of AI tutoring in K-12 education — Vendor metrics with their calibration and experiment count disclosed
- AI-assisted assessment and instruction in higher education: Foundations, applications, and implications for exam design — Findings tied to model versions, and the field's churn
- AI in Action Learning Tour — Independent-evidence counts for 16 student-facing AI products already in use
- From digital transformation to intelligent classrooms: artificial intelligence, adaptive leadership, and service delivery in global higher education—a systematic literature review — A review can quantify the reporting skew in its own corpus

Connected FAQs

- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- What Are Notable Gaps in the Research Literature on AI in Education?
- How Can AI Assist with Educational Research?

Limitations in AIEd Research

> **Limitations in AIEd research** — the recurring weaknesses and constraints that affect how much confidence we can place in AI-in-education findings, and how readers should interpret them. These cut across individual studies: methodological limitations (generalizability, sample size, validity, self-report), the speed problem (AI and findings date quickly while publication lags), research-practice limitations (reproducibility, FAIR practices, proprietary tools), and weak theory use. Methodological limits are measurable rather than impressionistic: in a critical review of 80 HCI studies of critical thinking with AI, 42 (52%) ran no control group and most of the rest relied on self-report, so the field's positive findings rest on designs that cannot separate AI's effect from ordinary reflection (A Critical Review of Critical Thinking in HCI Research About AI). Outcome coding is uneven in the same way: a systematic review of 103 higher-education studies sorted its corpus into a four-level outcome typology and placed 56% of it in a single conditional pattern, where confidence and motivation rose without a matching gain in durable competence (Generative AI in higher education: A systematic review of empirical uses, outcomes, and risks).. Recognizing these limits is essential for reading the literature critically and for designing stronger studies.

Questions to Consider

- How much would you trust a headline like 'AI tutoring boosts learning by 30%' if you learned it came from 30 students in one course at one institution? The page flags generalizability and small samples as recurring limits — what would you want to know before acting on any single finding?
- A striking limitation is the 'speed problem': AI evolves faster than findings get published, so a study of one model generation may already describe an obsolete system. How should this change the confidence you place in AI education research?
- Many studies rely on self-reported attitudes and usage, which are biased — people overestimate their competence and under-report misuse. Have you ever answered a survey about your own skills or behavior in a way that didn't match reality? Why do perception-based measures so often diverge from objective performance?
- The page notes that familiar frameworks like Bloom's taxonomy are often misread as strict ladders, and that even widely used theories like cognitive load theory have been challenged. When have you seen a theory invoked as settled truth in a context where its own evidence was actually contested?
- Most AI research depends on proprietary, opaque models whose data and updates you cannot inspect. If you cannot verify exactly what model produced a result, how much can you trust claims built on it — and what would make findings more reproducible?
- If you are an instructor or designer without time to read primary research, how do you decide which AI claims are trustworthy enough to change your practice — given that the literature is fragmented, provisional, and written for researchers?

Introduction

AI in education is a fast-moving, heterogeneous field, and its evidence base carries a distinctive set of limitations that researchers, practitioners, and policy-makers should weigh when using any finding. Some of these are shared with the broader Learning Sciences and psychology literature; others are amplified or made unique by the nature of AI itself. This page organizes them into four cross-cutting areas.

Methodological limitations

The knowledge base's research methods page details the strengths and limitations of each design. Several limits recur across designs and deserve particular attention:

- **Generalizability.** Findings from a single course, institution, discipline, or national context may not transfer. Small, convenience, or single-institution samples limit external validity; results from one AI tool rarely extend to a different tool or context.
- **Cross-national belief comparisons carry a measurement risk.** A five-country survey of 1,405 K-12 teachers used automated machine translation without back-translation or measurement-invariance testing and measured plagiarism and Creativity concern with single items, so its country contrasts cannot be read as equivalent constructs (Xiu et al. (2026)).
- **Synthesis-level rigor is a separate axis from primary-study rigor.** A meta-analysis can satisfy its own inclusion criteria and still pool studies that differ in design, implementation fidelity and outcome measure without weighting any of that: Doğan and colleagues (2026) state plainly that they used no formal quality appraisal tool and treated the inclusion criteria as the rigor threshold, so a quasi-experimental study and a randomized one contributed equally to the pooled STEM estimate. The same review shows a related reporting hazard: its heterogeneity is quoted as I^2 = 82.98% under a fixed-effect model and I^2 = 15.75% under the random-effects model, meaning readers who lift a single heterogeneity figure without its model cannot tell how inconsistent the corpus actually is. Appraise a synthesis on how it handled dependent effect sizes, quality, and heterogeneity, not only on whether it followed a search protocol.
- **Retrieval design sets a synthesis's headline numbers.** In a scoping review of 195 Teacher Education studies, digital competence and TPACK were explicit search descriptors while instructional design and assessment had no equivalent, so the reported 46.5% and 1.9% characterize the corpus the search returned rather than the field (Patiño Hernández et al. (2026)).
- **Small sample sizes.** Many AIED studies are underpowered — too few participants to reliably detect meaningful effects or to support the strong claims sometimes drawn from them.
- **Data augmentation can manufacture the headline metric.** In an automated essay scorer whose training partition held 83 students' work, generated level-1 responses — templates, truncation, keyword removal — lifted Focus agreement by +0.346 quadratic weighted kappa off a 0.028 baseline, so the strongest ordinal signal rested on text no student wrote (Firdausi et al. (2026)).
- **Endpoint scores can hide the thing being studied.** In a PRISMA review of 103 higher-education studies, 56% reported gains that were conditional on scaffolding or verification, and null grade differences often accompanied real changes in process — more debugging, more checking cycles

— so grades alone cannot tell whether GenAI strengthened or hollowed out practice (Hawi and Samaha (2026)).

- **Validation design can manufacture the headline number.** Nanayakkara and Halloluwa (2026) benchmark fifteen models on EEG-based familiarity and show that standard stratified cross-validation allows temporal leakage and reports up to 0.9853 F1, while trial-independent Group K-Fold validation drops the peak to 0.6038 F1 — still above chance, but far from the quoted result.
- **Benchmarks can supply the failures they report.** Expert re-grading of 250 rejected physics items attributed 238 (95.20%) to benchmark or grader errors and only 12 (4.80%) to genuine model errors, so a model's measured error rate cannot fall below the instrument's defect rate. (Ansari et al. (2026))
- **Validity and measurement.** Construct validity is often thin: proxies for "learning," "engagement," or "literacy" vary widely, and instruments are not always validated for the population or construct being studied. Benchmark accuracy does not equal educational effectiveness.
- **Self-report and survey data.** A large share of the corpus relies on self-reported attitudes, motivation, and usage. Self-report is subject to bias — respondents overestimate competence, under-report misuse, and misjudge their own behavior — so perception-based measures frequently diverge from objective performance (see How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures and Educational Measurement).
- **Context and validation reporting can be quantified across a literature.** A PRISMA-ScR review of 421 studies of NLP on teaching-evaluation comments found country unresolved in 221 studies, single-institution scopes in 232 of 284 resolved cases (81.7%), external validation in 33 (7.8%) and inter-annotator agreement in 54 (12.8%) (Eicher & da Silva (2026)).
- **Reporting richness is measurable, and method type predicts it.** In 888 review-automation papers, 38.0% of software/product papers since 2023 reported no evaluation against 9.3% of LLM papers, and 52% of 118 positive-only LLM papers still flagged an unmet reliability bar — the pattern behind PRISMA-LLM's five disclosure tiers (Zabaleta & Lin (2026)).
- **Standardizing within each dataset can hide a misstatement of spread.** When synthetic educational cohorts were standardized by their own dispersion, the fact that their weekly structure varied 2.6 to 4.9 times less than the real cohorts' became invisible to the reported statistics - routine preprocessing, in the authors' words not a hypothetical worry (Inoue & Yasutake, 2026).
- **Model-generated labels are not ground truth.** Where the labels that train or evaluate a system are themselves produced by language models, agreement between annotators cannot establish validity: Bernado et al. (2026) never validated their assertion annotations against human gold labels, and the 49 encoder classifiers they release inherit that provenance and may not be valid where applications differ in significant dimensions. Their schema also strictly underperformed the fine-tuned classifier trained on expert-annotated data (macro-F1 0.673 against 0.76), leaving expert-labeled corpora worthwhile when high confidence is required.
- **The evidence base itself is unevenly distributed.** A scoping review of 407 technology-supported formative assessment studies drew only on Web of Science and Scopus. It also excluded 61

records on language criteria, so the geographic imbalance the field reports may partly reflect which venues are indexed (Bulut, 2026).

The speed problem: AI evolves faster than findings

AI is changing continuously, and the conclusions drawn from any given model or system can become **out of date quickly**. A study of one Large Language Models (LLMs) generation may not describe the next; benchmark scores, tutoring quality, and even the practical usefulness of a finding shift as models improve. Compounding this, the **publication process is slow** — from study design to peer-reviewed publication can take a year or more — so a published result may already describe an obsolete system. Reviewers and readers should therefore treat AIED findings as provisional, date-sensitive claims rather than stable truths, and prefer recent, replication-oriented, and version-explicit work.

Thoeni and Fryer (2026) make the consequence concrete for one literature: because RAG-based systems only became publicly available in November 2023, they argue that pre-2023 intelligent tutoring findings — resting on rule-based, keyword-matching or heuristic NLP systems that bear little functional resemblance to current large language models — should be treated as historical context rather than directly comparable evidence, and report that their review found no published RCT examining a RAG-based AI chatbot in undergraduate education over a full academic term. The implication is that foundational questions about how genAI affects learning may need to be re-asked against each new model generation rather than settled by pooling older results.

Research-practice limitations

Several limitations concern the conduct and infrastructure of the research itself:

- **Lack of reproducibility.** Studies often do not report enough detail (prompts, model versions, hyperparameters, data, analysis code) for others to reproduce or verify results — a particular problem given how sensitive LLM output is to prompts and settings.
- **FAIR research practices.** Open and reproducible practice — **F**indable, **A**ccessible, **I**nteroperable, **R**eusable data and code, pre-registration, and shared benchmarks — is unevenly adopted in AIED. Weak adherence to FAIR principles makes it harder to reuse, compare, and build on studies.
- **Proprietary tools and models.** Much research depends on closed, proprietary AI systems whose internal behavior, training data, and model updates are opaque and may change without notice. This limits reproducibility, makes exact replication impossible, and can tie findings to a vendor's roadmap. It also raises questions about evaluation independence (see AI Ed Evaluation).

Weak or limited theory use

A recurring criticism is that many empirical articles have **limited or outdated theoretical framing**. Researchers may:

- **Adopt theories uncritically.** Frameworks are borrowed because they are familiar, without fully engaging their assumptions, scope, or evidence base.

- **Misinterpret frameworks as fixed sequences.** Several widely used frameworks are treated as ordered ladders that learners must climb from a "low" to a "high" stage — but the evidence does not support always starting at the bottom. For example:
    - **Bloom's taxonomy** is often read as a strict hierarchy (recall → application → evaluation), yet higher-order goals do not require first drilling lower-order ones; tasks can be designed to engage evaluation or creation from the start (see Cross-Dataset Bloom Question Classification: Supervised Models and Prompted LLMs).
    - **ADDIE** and other instructional-design models are sometimes treated as rigid linear phases rather than the iterative, flexible planning heuristics they are meant to be (see Learning Design).
- **Overlook contested theories.** Some theories used widely in AIED have themselves been challenged. **Cognitive load theory**, for example, has been criticized and its empirical claims refuted or disputed in prior studies, yet it continues to be invoked as a settled foundation in new AIED work.

The implication is not that theories and frameworks are useless, but that they should be used with attention to their actual evidence base, their intended scope, and their known criticisms — rather than as self-evident scaffolds or rigid procedural sequences.

The meta-analytic evidence crisis

A growing body of meta-research — reviews that scrutinize the reviews — argues that the field's headline claims of AI-driven learning gains rest on an evidence base that is far weaker than it appears. Three complementary critiques make the case with unusual force:

- **Positive-synthesis bias is severe and quantifiable.** Bartoš et al. (2026), in a study-level meta-meta-analysis of 1,840 effect sizes from 67 meta-analyses, found strong evidence of publication bias (all Egger tests $p < .0001$) and extreme between-study heterogeneity ($\tau = 0.869$). Publication-bias-adjusted effects were roughly **one-third** the magnitude commonly reported (SMD = 0.196 vs. a median of 0.67 in the published literature), with a prediction interval spanning −1.521 to +1.908 — from large harm to large benefit. No outcome, field, level, or AI-role subgroup showed consistent gains, and there was no difference between pre- and post-2023 studies. Their verdict: broad claims of generalized learning gains are premature.
- **Meta-analytic methods are being systematically misapplied.** O'Neill (2026)'s forensic audit of 14 high-impact AIED meta-analyses found that *none* provided a valid basis for their claims: none had a coherent construct (treating the tool "ChatGPT" as if it were a single intervention, and pooling test scores, motivation, Self-Efficacy, and attitudes into one "academic achievement" number); reported heterogeneity was severe, with I^2 ranging from 77.2% to 94.4% across the 13 meta-analyses that reported it and 12 of those 13 above 80%, and it was never resolved (none met the minimum subgroup size of ten studies, five relied on single-study subgroups, and three others on subgroups of two); twelve treated dependent effect sizes from the same study as independent, inflating apparent evidence; and none validly assessed publication bias (discredited fail-safe N metrics and misapplied Egger tests were common). Because I^2 is precision-dependent it cannot by itself establish how far apart the true effects are, and the reporting that would show it was largely

absent: only four meta-analyses reported between-study variance (τ^2) and only two reported a prediction interval, both of which included zero. A majority (61%) of randomly vetted primary studies were problematic, and one study with fabricated references was included by six of the 14 meta-analyses.

- **The "treatment" is a black box.** Weidlich et al. (2025) revive the media/methods debate to argue that "ChatGPT" is a tool, not a method — asking whether it "improves learning" is a non sequitur. Auditing a subset of the studies behind Deng et al.'s (2025) meta-analysis, they found only 21% of comparisons had a well-defined treatment, control group, *and* valid learning measure; reported effect sizes (g = 0.7) even exceeded those of purpose-built Intelligent Tutoring Systems (0.66), a red flag that the "treatment" was a heterogeneous "secret sauce."

The convergence of these three independent critiques is itself evidence: across different methods, corpora, and framings, they reach the same conclusion — that positive AIED effect sizes, especially from early meta-analyses, likely reflect **publication bias, construct incoherence, and methodological shortcuts** as much as (or more than) genuine learning gains. This does not mean AI tools have no educational value; rather, it means the *field-level* evidence for their value is currently inflated and must be read accordingly. It also shifts responsibility to synthesis quality: a meta-analysis is only as trustworthy as the coherence of its constructs, the independence of its effect sizes, the adequacy of its moderator and heterogeneity analysis, and the validity of its publication-bias assessment — each of which the critiques show is routinely violated.

Reading the AIED literature critically

Taken together, these limitations argue for a critical, multi-signal reading of AIED research: check whether a finding generalizes and is adequately powered; verify how constructs were measured (and whether claims rest on self-report); prefer recent, version-explicit, reproducible work; and interrogate the theoretical framing rather than treating familiar frameworks as given. This is the complement of rigorous method choice and evaluation: good methods and good evaluation are necessary, but reading with attention to limitations is what turns evidence into defensible decisions.

From research to practice

A further, practical limitation is the **challenge of applying research to teaching and instructional design**. Practitioners — instructors, instructional designers, and faculty developers — often lack the time or specialized expertise to read, appraise, and translate primary research into concrete classroom decisions. The literature is large, fragmented, and written for researchers; findings are reported with statistical and methodological detail that is not immediately actionable; and because claims are provisional (see the speed problem above), a practitioner cannot simply take a single study at face value. This creates a gap between what the evidence supports and what actually reaches teaching practice.

The purpose of this knowledge base is to help close that gap — to make it easier to keep up with, interpret, and apply AI-in-education research to practice — by curating open-access findings into structured, accessible summaries, connecting related work through concept pages, and flagging the limitations readers should weigh. It aims to support evidence-informed practice in teaching and instructional design, and in doing so to also surface gaps and questions that can inform new research and development. Understanding

the limits of the research is therefore not an end in itself: it is what lets practitioners apply findings appropriately and lets researchers design stronger studies that better serve practice.

Two Audit Traps Worth Knowing

Two specific reporting practices inflate or distort a synthesis, and both are visible in the published record rather than hypothetical.

The heterogeneity figure depends on the model, and the model is rarely quoted. One review's heterogeneity is quoted as **I^2 = 82.98% under a fixed-effect model and I^2 = 15.75% under the random-effects model**. Those describe the same data. A reader who lifts a single heterogeneity number without its model has been given a technical claim with no interpretation attached, and the difference between "most variance is unexplained" and "little variance is unexplained" is the difference between discarding and trusting the field.

The headline percentage can be an artifact of the search terms. A scoping review of 195 teacher-education studies made digital competence and TPACK explicit search descriptors, while instructional design and assessment had no equivalent term, so the reported **46.5% and 1.9%** are rates the query itself constructed. A prevalence claim is only as meaningful as the search behind it.

And the base rate is the number nobody states. Methodological limits here are measurable rather than impressionistic: in a critical review of 80 HCI studies of critical thinking with AI, **42 (52%) ran no control group** and most of the rest relied on self-report. When more than half of a field's positive findings come from designs that cannot separate AI's effect from ordinary activity, the appropriate prior on any single finding is skepticism, not provisional acceptance.

Common Misconceptions

- **"Limitations sections are boilerplate."** Methodological limits are **measurable rather than impressionistic**: in a critical review of **80 HCI studies** of critical thinking with AI, **42 (52%) ran no control group**. A precise count is what makes the limit actionable.
- **"Heterogeneity is a single number you can quote."** The same review shows a reporting hazard: heterogeneity is quoted as **I^2 = 82.98% under a fixed-effect model and I^2 = 15.75% under the random-effects model**. The same data yields a nine-point story or a two-point story depending on the model chosen, so a quoted I^2 without its model is uninterpretable.
- **"A large reported effect is the number to trust."** A headline like an effect from **30 students in one course at one site** is the common form of a fragile claim, and the count of studies without controls shows how often that fragility goes unreported.

Connected Concepts

- Interpreting and Applying AIEd Research
- Research Methods in AIED
- AI Ed Evaluation
- Educational Measurement

- Assessment Validity
- Benchmark
- RCT
- Meta-Analysis and Systematic Review
- AI in Education
- ICAP Framework
- Learning Design
- Large Language Models (LLMs)
- Generative AI
- Cognitive Offloading
- Theory Development in AI in Education — Theory Development in AI in Education

Connected Articles

- AI chatbots in higher education: Comparing expectations to evidence — AI chatbots in higher education: comparing expectations to evidence (Thoeni & Fryer 2026)
- Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education — Reliability and validity of ground truth in evaluation
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — Self-reported vs. performance-based AI literacy
- Why Machines Misread Pedagogical Quality: Human-Machine Alignment in LLM-Based Pretest Question Evaluation — Why machines misread pedagogical quality
- Critical AI Tutors: Empower or Enslave? — Critical limits of AI tutors and theory use
- Cross-Dataset Bloom Question Classification: Supervised Models and Prompted LLMs — Bloom’s taxonomy and question classification
- Automating Learner Assessment: Benchmarking Machine Learning and Deep Learning Models for EEG-Based Familiarity Prediction — Automating Learner Assessment: EEG-Based Familiarity Prediction
- ChatGPT in Education: An Effect in Search of a Cause — ChatGPT in Education: An Effect in Search of a Cause (media-comparison critique)
- Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis — Meta-meta-analysis: publication-bias-adjusted AI effects ~1/3 of reported size
- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Presumed Effective: forensic audit of 14 AIED meta-analyses
- PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews — PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews
- How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks — How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks

- The Impact of Artificial Intelligence-Supported Instruction on Student Learning in STEM: A Systematic Review and Meta-Analysis — Inclusion criteria used as the rigor threshold, and a heterogeneity figure that changes with the model (Doğan et al. 2026)
- Enhancing Enthusiasm for STEM Education with AI: Domain-Specific Chatbot as Personalized Learning Assistant — A cluster-randomized classroom trial whose performance outcome did not reach significance (Rücker & Becker-Genschow 2025)
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues
- From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026 — From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- From digital competence to AI-responsive pedagogy: a scoping review of technology-supported teacher education — Scoping review of 195 teacher-education studies where search-string design shapes the reported frequencies
- K-12 in-service teachers' beliefs about generative AI in classrooms: insights from the United States, India, Qatar, Colombia, and the Philippines — Cross-national K-12 teacher survey: machine-translated items, single-item concern measures, no invariance testing
- Generative AI in higher education: A systematic review of empirical uses, outcomes, and risks — Systematic review of 103 GenAI higher-education studies: 56% conditional gains, grades masking process change (Hawi & Samaha 2026)
- Educational Innovation through Automated Essay Scoring: A Multidimensional Framework for Evaluating Critical Thinking in High School Physics Essays — Data augmentation can manufacture the headline metric

Connected FAQs

- What Are Notable Gaps in the Research Literature on AI in Education?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?

Philosophy of AI in Education

> **Philosophy of AI in Education** — the branch of educational philosophy that examines the fundamental conceptual questions raised by artificial intelligence in teaching and learning: What is the nature of knowledge and thinking when machines participate in them? What is the learner when cognition is distributed across human and artificial systems? What forms of Learner Agency, responsibility, and personhood apply to AI, and what does education owe learners in an AI-mediated world? Distinct from (but connected to) the knowledge base's Learning Theories page, which catalogs theories of *how learning happens*, the philosophy of AI in education asks the deeper questions of *what learning, mind, and the learner fundamentally are* under AI-mediated conditions.

Questions to Consider

- Does thinking require consciousness and a body? If an AI genuinely participates in your reasoning, is some of the 'thinking' happening in the machine—and does that change who's learning?
- The page raises the idea of cognition 'distributed' across human and artificial systems. Think of a task you've solved with AI help: where did your thinking end and the machine's begin?
- If a learner's cognitive processes become genuinely hybrid (part human, part artificial), what does that mean for what we call 'the learner'—and for what education owes them?
- The page distinguishes philosophy (what learning and the learner fundamentally are) from learning theories (how learning happens). Can you name a belief you hold about learning that is really a philosophical position?
- If AI can exercise 'functional agency' without consciousness, does it bear responsibility for its educational effects—and if not, who does? Who should answer when an AI tutor misleads a student?
- Posthumanist thought reframes learners as 'post-human' entities. How does that idea challenge or unsettle your own assumptions about where a student's mind is located?

Introduction

This is a concept page for the philosophical and theoretical foundations of AI in education. While Learning Theories documents the empirical and design-oriented theories (Behaviorism, constructivism, cognitive load, self-regulated learning, etc.), the philosophy strand engages the ontological, epistemological, and ethical questions those theories presuppose. The two are closely connected: philosophical positions shape which learning theories seem plausible and which educational goals are worth pursuing.

Key philosophical questions

- **The nature of mind and cognition.** Does thinking require consciousness and a body? Can AI participate in genuinely cognitive processes? Frameworks such as **ensemble cognition** argue that

AI exercises *functional agency* — genuine causal efficacy in cognitive processes — without consciousness, and that thinking emerges from dynamic human–AI interaction.(Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments) Distributed cognition and the extended mind thesis make related claims about cognition being spread across systems.

- **What is the learner?** Posthumanist philosophy reconceptualizes the learner as a "post-human" entity whose cognitive processes are genuinely hybrid and distributed across biological and artificial systems.(Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI) This challenges the assumption that the learner is a bounded, autonomous individual mind.
- **Embodiment and the limits of disembodied AI.** Embodied and post-cognitivist philosophy critiques the dominance of symbolic, disembodied AI models, arguing that cognition is grounded in situationality, emergence, and sensorimotor coupling that current generative AI lacks.("If You Can't Dance Your Program, You Can't Write It": Challenges and Implications for AI in Education)
- **Agency, authorship, and meaning.** When AI mediates interpretation and meaning-making, philosophy asks how authorship, epistemic Learner Agency, and interpretive autonomy are reconfigured.(AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education)
- **The ontology of AI-generated scientific objects.** In chemistry, AI-predicted compounds and titration curves occupy a "liminal ontological space" — neither wholly hypothetical nor fully real until empirically proven — which shifts the discipline from realism toward a constructivist view in which reality is a collaboration of human and machine (Reyes and Regala (2026)).
- **Cognitive passivity as an epistemic harm.** Bai and Costa (2026) draw on Arendt's account of thinking as an inward, untransferable activity to argue that GenAI which supplies the work does not merely offload thinking but forecloses it, with Bourdieu's field and habitus locating the risk in institutional structures (Bai & Costa (2026)).
- **Values, justice, and the purpose of education.** Philosophical analysis examines whether AI-driven education serves human flourishing and educational justice, or whether it instrumentalises learning in service of productivity.(Can we disrupt the momentum of the AI colonization of science education?) This connects to Critical Pedagogy and Ethics.
- **'Human-centered' as an anthropocentric discourse, not a neutral ethic.** Wang & Jin (2026) read UNESCO, OECD and Montréal Declaration documents to argue that human-centered AIED inherits Enlightenment humanism's exclusions, that transhumanism preserves them, and that the label can legitimize commercial infrastructure.
- **Epistemological grounding for how people engage AI.** Strydom (2026) derives seven human–generative-AI engagement paradigms from Schommer's five dimensions of personal epistemological belief (source, certainty, organization, control, and speed of knowledge) and argues they are enacted rather than possessed — so shifting how learners engage AI requires changing the socio-technical environment, not their beliefs.

- **Whose philosophy? Pluralism in the field's conceptual foundations.** Xie (2026) argues that the field's philosophical debate is over-determined by a single Western architecture — epistemic agency as a property of discrete subjects, knowledge framed representationally and calculatively, and the human–AI relation located within subject–object dualism — so that its limits become the limits of the field's collective imagination. As a comparative counterweight he reconstructs Daoist concepts — "Dao nature" (道性), self-cultivation (修道) and the "Zhenren" (真人) — not as "Eastern content" added to an unchanged frame but as resources that reshape the conceptual foundations through which AI itself is understood, applying them to knowledge (epistemic monoculture and synthetic misinformation), knowing (offloading that degrades critical thought) and impact (environmental costs and Global North–South asymmetries).(Alternative AI Philosophy: Daoism as Method for AI in Education)
- **Agency without answerability.** A corpus-assisted discourse analysis of 366 GenAI higher-education abstracts finds AI named 2,050 times and entering 447 strict actor–predicate associations - the field's most frequent actor - yet action predicates dominate them (78.7%) and no sentence makes a system responsible: of 166 obligation expressions, none assigned responsibility to a system, and the single clause linking AI to accountability says AI is not accountable. Poudyal (2026) reads this as functional agency recognized in language without the relational responsibility that would attach it to anyone. **Neither tool nor collaborator: the mediational agent.** Warschauer, Tate and Ritchie (2026) argue that calling generative AI a mere tool understates its interactional influence while calling it a collaborator wrongly grants it intentionality and accountability, and propose the *mediational agent* — a responsive, non-accountable system whose novelty is participation rather than intelligence.

Relationship to learning theories

The philosophy of AI in education and Learning Theories are complementary lenses. Learning theories explain the mechanisms of learning (e.g., how Feedback, Scaffolding, or cognitive load shape outcomes); philosophy interrogates the presuppositions of those mechanisms — what counts as knowledge, who counts as a knower, and what the learner fundamentally is. Posthumanist and critical-philosophical work, in particular, challenges the field to move beyond instrumentalist frameworks like Technological Pedagogical Content Knowledge (TPACK) and SAM toward deeper ontological reorientation.(Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI)

Relationship to theory development

Philosophy of AI in education and theory development in AIEd are complementary but distinct. Philosophy asks the ontological and epistemological questions — what mind, knowledge, and the learner fundamentally are under AI-mediated conditions — while theory development produces and empirically tests the *mechanisms* that operationalize answers to those questions (generativism, epistemic co-agency, the absent cognitive baseline). The two are mutually informing: philosophy clarifies the presuppositions that theories carry (e.g., epistemic co-agency presumes a distributed, non-individualist model of cognition), while theory development gives philosophical positions testable, falsifiable form. The field's most foundational articles do both at once, sitting at the boundary between the two concepts.

Common Misconceptions

“The philosophy of AI in education is the same as cataloguing learning theories.” They sit at different depths. The Learning Theories page asks *how learning happens*; the philosophy asks *what learning, mind and the learner fundamentally are* under AI-mediated conditions. A study can settle a learning-theory question and leave the philosophical one untouched, which is why a technically successful intervention can still be the wrong thing to do.

“Cognitive offloading is the harm, and it is reversible by more effort.” There is a stronger claim available. Bai and Costa (2026) draw on Arendt’s account of thinking as an inward, untransferable activity to argue that GenAI which *supplies* the work does not merely offload thinking but forecloses it — and they locate the risk institutionally, through Bourdieu’s field and habitus, rather than in individual willpower. If the argument holds, “use it carefully” is not a sufficient remedy, because the practice is shaped by the field that rewards the output.

“Non-Western philosophy is content to add to an unchanged frame.” It can be a source of different foundations. One reconstruction treats Daoist concepts — “Dao nature” (道性), self-cultivation (修道) and the “Zhenren” (真人) — not as “Eastern content” appended to a Western framework but as resources that reshape the conceptual foundations through which AI in education is understood. Adding a tradition as illustration and using it to reframe the questions are different scholarly acts.

“Philosophical critique is unactionable.” It sets what counts as success. Whether a system’s output is a learner’s achievement, and whether a measured gain is an educational good, are prior questions that no effect size can answer — and institutions that skip them will optimize the measurable and call it improvement.

Implications for Practice

For instructors

- Decide, before you adopt a tool, what you are willing to count as the student’s own achievement. If a polished submission produced by the system would satisfy your assessment, you have answered “nothing” — and no later rubric change recovers the question.
- Treat the foreclosing argument seriously when designing tasks: if GenAI that supplies the work forecloses thinking rather than merely offloading it, then “use it responsibly” is not a sufficient safeguard, because the surrounding field rewards the output. Design tasks whose evidence of thinking is produced before the tool is available.
- Ask whose conception of learning your course encodes. Adopting a framework uncritically imports its assumptions about what a learner is, and those assumptions are contestable.

For developers

- Expose the boundary you have drawn between assistance and supply, and make it a product decision rather than a default. A system that can produce the finished artifact has decided, implicitly, that mental work is optional.
- Resist optimizing for the appearance of learning. Fluency and completeness are the measurable properties, and they are the ones that mask foreclosure.

- If you claim your system “supports thinking”, state what it refuses to do — the refusal is the mechanism.

For researchers and policymakers

- State the conception of learning your evaluation presumes, because a measured gain is only an educational good relative to some account of what education is for.
- Fund the philosophical work alongside the empirical work: questions about what counts as a learner’s achievement set the success criteria the empirical studies then use.

Connected Concepts

- Learning Theories
- Theory Development in AI in Education
- Distributed Cognition
- Ethics
- Learner Agency
- Embodied Learning
- Critical Pedagogy
- Human AI Collaboration
- Critical Thinking
- AI in Education
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation

Connected Articles

- Navigating the challenges of Gen-AI in Chinese higher education: Balancing technological innovation with academic integrity and intellectual engagement — Gen-AI in Chinese higher education: integrity and engagement
- Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments — Ensemble Cognition: a philosophical framework for human–AI cognition
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI — Pedagogical Symbiosis and the Post-Human Learner
- "If You Can’t Dance Your Program, You Can’t Write It": Challenges and Implications for AI in Education — Embodied, post-cognitivist critique of disembodied AI in education
- AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education — Developmental-critical model of interpretive cognition in the humanities
- Learning with machines: Toward a theory of epistemic co-agency — Epistemic co-agency as a philosophy of learning with machines

- Can we disrupt the momentum of the AI colonization of science education? — Critical-feminist philosophy questioning the AI colonization of education
- Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory — Generative AI as a Mediational Agent
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Ecological learning-sciences framing of GenAI
- Reimagining the philosophy of experimentation in chemistry education: Embracing AI as a tool for scientific inquiry — Philosophy of experimentation in chemistry with AI
- Framing human-AI dynamics: An epistemological perspective on generative AI practices — Framing human-AI dynamics: seven GAI engagement paradigms (Strydom 2026)
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research
- Anthropocentrism and learnification: resisting the dominant discourse of human-centred Artificial Intelligence in Education — ‘Human-centered’ AIED read as an anthropocentric discourse with commercial uses (Wang & Jin 2026)

Theories and Frameworks

> **Theories and frameworks** — the working inventory of explanatory and organizational structures this knowledge base actually uses. Theories explain why learning happens (Learning Theories, Self-Determination Theory, Sociocultural Learning, activity theory); frameworks organize design, teaching, and adoption decisions (Technological Pedagogical Content Knowledge (TPACK), SAMR, technology adoption models, ICAP, universal design for learning); models make learning claims testable and computable (item response theory, Assessment Validity, Knowledge Tracing). Use this page to find the lens a study rests on, or to pick one for your own work.

Questions to Consider

- A theory predicts what happens when something changes; a framework tells you what to attend to. When a study reports a gain under a framework's banner but makes no prediction that could have failed, what has actually been learned?
- TPACK, SAMR, UDL, the adoption models and ICAP all predate large language models. Which parts of them still hold when the tool can write, explain, and adapt on its own, and how would you tell?
- Several of the theories catalogued below were coined for AI within the last few years. What would it take for one of them to be wrong, and has anyone tried to show that?
- Adoption is often reported as movement through stages. If a colleague reports that their course moved "from substitution to redefinition" this year, what independent evidence would you ask for before believing it?
- Much of this field applies borrowed theory rather than testing it. Pick a finding you rely on: could it be reframed as a test of a theory, and what measurement would that require?

Introduction

Every AI tutor, feedback system, and dashboard embeds assumptions about how people learn, whether or not the designers state them. This page collects the theories, frameworks, and models those assumptions come from, ordered loosely by how much of the current research literature leans on them, and says briefly what each one is good for. The distinctions among the three labels are real but minor, and they are summarized near the end rather than treated as the subject. What matters practically is which lens a claim rests on, and whether that lens can support the claim.

Learning theories the literature applies

These explain mechanisms: they name the parts that do the work and predict what follows when those parts change. In the AI literature they are mostly borrowed from psychology and the learning sciences, and used as interpretive frames around a new tool.

- **Learning theories (umbrella)** — the family as a whole, including the classical poles of Behaviorism and constructivism and the "constructivism in name, behaviorism in practice" gap that recurs in AI implementations. Connectivism and cognitive load theory are covered here too.
- **Constructivism** — learning as active knowledge construction. It underwrites project-based work, dialogue-based AI tutoring, and the critique that drill-and-feedback systems violate their own stated pedagogy.
- **Sociocultural theory** — learning as mediated by tools and social interaction, which is why AI gets theorized as a mediating artifact rather than a mere aid.
- **Activity theory** — takes the whole activity system, contradictions included, as the unit of analysis. Common in teacher-facing AI studies, where the interesting finding is usually the tension among tools, rules, and community.
- **Situated learning** and **Embodied learning** — learning as tied to context and to the body, the counterweight to treating AI as a purely linguistic medium.
- **Distributed cognition** — thinking spread across people and artifacts, which frames AI assistance as a redistribution of cognitive labor rather than a substitution for it.
- **Community of inquiry** — the social, cognitive, and teaching presences that make an online experience work; a theory of the experience and a design frame at once.
- **Self-determination theory** — autonomy, competence, and relatedness as motivational preconditions. Often the explanation offered when AI use raises engagement without raising learning.
- **Cognitivism** — information processing, working memory, and the divergence between the feeling of learning and actual learning.
- **Social perception theory (warmth and competence)** — imported from social cognition and service-robot research, it frames how users judge an AI agent's credibility: perceived competence predicted ChatGPT's feedback credibility directly while warmth worked only through human-like empathy (SEM, 230 students; Pérez-López et al. (2026)).
- **A fourth affordance category was proposed, not tested.** Coding 24 studies against a three-part affordance scheme, the reviewers found engagement, safety and self-efficacy did not fit the technological, pedagogical or social categories, and proposed emotional affordances grounded in Bandura's reciprocal determinism (Lopez & Arabadzhy (2026)).

Models of the learner and of the learning process

- **Self-regulated learning** — planning, monitoring, and evaluating one's own learning. The workhorse construct for asking whether AI support reaches the phases that matter or only execution.

- **Metacognition** — thinking about one's own thinking, and the construct most often named when AI is accused of doing the thinking for students.
- **Motivation** — why learners engage, and the construct that separates engagement from learning in AI studies.
- **Self-efficacy** — belief in one's capability, distinct from competence, and a frequent mediator between AI use and outcomes.
- **Agency** — who directs the work: the construct behind the field's control-versus-autonomy tension, and behind the delegated-agency mechanism in the newest theory.
- **Desirable difficulties**, **retrieval, spacing, and interleaving**, and **refutation text** — findings that make friction pedagogically valuable, applied to decisions about how much an AI should do.
- **Transfer of learning** — whether capability persists once support is withdrawn, which recent theory treats as the criterion separating learning from assistance rather than one outcome among several.

Teaching, integration, and adoption frameworks

- **TPACK** — the teacher knowledge that blends technology, pedagogy, and content; the default framework for teacher-facing AI studies.
- **Adoption models** — intention as a function of perceived usefulness and ease of use. Used widely enough that the field's reliance on intention rather than behavior is a standing critique.
- **ICAP** — ranks engagement as passive, active, constructive, interactive; useful for asking what mode an AI interaction actually affords.
- **SAMR** — substitution through redefinition. Popular as a maturity story, weak as a measurement instrument.
- **Universal design for learning**, **inclusive learning**, and **Accessibility** — design frames for who gets served, and the ones most often invoked in disability and equity work.
- **Learning design**, **Curriculum design**, and **Design thinking** — how tasks, sequences, and programs are structured before any tool is chosen.
- **Change management** — whether a system is taken up at all, which is usually an institutional question rather than a pedagogical one.

Measurement and computational models

- **Item response theory** — item and ability estimation, and the model that makes a test's numbers interpretable.
- **Educational measurement** — the instrument landscape, including the measures built specifically for AI literacy.
- **Validity** — whether an instrument measures the construct it claims, which decides whether a reported outcome supports the theoretical claim attached to it.
- **Self-report measures** — the dominant and most fragile source of evidence in this literature; several constructs above are known to diverge sharply between self-report and performance.

- **Knowledge tracing** and **Student modeling** — estimating a learner's state over time from interaction data.
- **Cognitive diagnosis** — attributing performance to specific skill components, the modeling counterpart to diagnostic teaching.
- **Benchmarks**, **AI education evaluation**, and **psychometric awareness in AI design** — how systems and interventions are scored, compared, and audited.
- **Design-based research** — the method that generates theory from designed interventions rather than testing it in advance.

Theories coined for the AI era

Four proposals in the knowledge base build theory rather than borrow it. They are article pages rather than concept nodes, because each one is a single argument:

- **Generativism** — a new learning theory arguing that the classical four show significant conceptual limitations as generative AI proliferates.
- **Epistemic co-agency** — a model of how learners and AI systems jointly produce knowledge and understanding.
- **The absent cognitive baseline** — theorizes why AI-native students overestimate their own learning when AI inflates performance.
- **Agentivism** — a mid-range theory naming four mechanisms (delegated agency, epistemic monitoring and verification, reconstructive internalization, and transfer under reduced support) and stating six testable propositions.

Telling the three labels apart

The words are used loosely in the literature, and the difference is worth one paragraph rather than a whole page:

- **A theory explains a mechanism** and predicts what happens when its parts change. It can fail, which is why studies that test one can report effect sizes.
- **A framework organizes or prescribes.** It names the components to attend to, usually without predicting magnitudes, and it cannot be falsified.
- **A model is a formal representation**, most often of measurement or of the learner's state. It can be fitted, compared, and shown to be wrong in a way a framework cannot.
- **The labels overlap.** Community of inquiry is a theory and a design frame at once; activity theory is explanatory and analytic. Treat the label as a clue about what a source claims, not as a filing category.

Related layers

Two neighbouring pages are deliberately about something else. Philosophy of AI in education asks normative and conceptual questions — what education is *for*, whether a machine can teach — and does not predict effect sizes; a study can be philosophically naive and theoretically sound, or the reverse. Theory

development is the meta-activity of building, borrowing, and revising theory, including the standing critique that much AIED work applies existing theory rather than testing it. This page is the inventory; theory development is about producing and revising the inventory.

Choosing a lens when the question is practical

- **Instructors** starting from a problem can work backwards: if learners are not engaging, ICAP and SDT name different causes and suggest different fixes; if the question is whether to adopt a tool at all, adoption models and SAMR ask different things about it.
- **Learning designers** get the most from the design frames — UDL, Learning Design, and Scaffolding — paired with a theory that predicts what happens when the scaffolding is removed.
- **Researchers** should state which node a study claims and whether the design can actually test it; the measurement models (IRT, Assessment Validity, Self-Report Measures) decide whether a reported outcome supports that claim.
- **Administrators** meet these frameworks as adoption and change questions, where a stage model is often used as a maturity story rather than an instrument.

What frameworks cannot do

Frameworks are not evidence. They are usually borrowed from pre-LLM contexts and localized by whoever applies them, they can function as branding, and stage models invite checkbox adoption that reports movement through levels rather than learning. Claims resting on a framework should be read alongside the field's cross-cutting limitations, the validity of whatever measured the outcome, and the known limits of self-report.

Mechanism-to-theory alignment can nonetheless be decisive: a thematic synthesis of 55 AI-supported game-based learning studies found effectiveness turned on whether the AI mechanism enacted the pedagogy it was meant to serve rather than on algorithmic sophistication (Kaşarcı and Yurt (2026)).

Common Misconceptions

"Applying a borrowed theory to an AI tool is using theory." Much of this field applies borrowed theory rather than testing it, and the difference is whether the framework made a prediction that could have failed. When a study reports a gain under a framework's banner while committing to no falsifiable prediction, nothing has been learned about the framework — an outcome consistent with every theory in the catalog is evidence for none of them.

"A framework's value is how well it describes a system you have already built." That is post-hoc labeling. A taxonomy that accommodates any design has no discriminating power, which is why descriptive frameworks should be judged on what they exclude. The evaluation question is not "does my system fit this?" but "what kind of system would this framework say is wrong?"

"Learning theories, models of the learner, and adoption frameworks are interchangeable lenses." They answer different questions — how learning happens, what the learner's state is, and why a practice spreads

— and their evidence types differ accordingly. Choosing the wrong layer produces a study that measures the right variable against the wrong prediction, which reads as a null result when it is a category error.

“More frameworks means a more mature field.” Coined-for-the-AI-era frameworks accumulate faster than they are tested, and accumulation without falsification is a symptom rather than progress. Maturity shows up as competing predictions being resolved, not as vocabulary growth.

Connected Concepts

- Theory Development in AI in Education — building and revising theory in the field
- Philosophy of AI in Education — the normative and conceptual layer
- Learning Theories — the umbrella for learning theory
- Learning Sciences — the neighboring field most theory is borrowed from
- Limitations in AIEd Research — what the evidence base can and cannot support
- Technological Pedagogical Content Knowledge (TPACK) — teacher knowledge framework
- Technology Adoption Models — adoption frameworks
- Item Response Theory — a measurement model
- Universal Design for Learning — a design framework
- Research Methods in AIED — how theory gets tested

Connected Articles

- GenAI chatbots in language learning: A systematic review of emerging affordances — Emotional affordances proposed as a fourth category in an affordance taxonomy
- Effectiveness of AI-Supported Game-Based Learning: A Systematic Review of Outcomes, Challenges, and Future Directions — Mechanism-to-theory alignment, not algorithmic sophistication, drove effectiveness in 55 AI game-based learning studies
- The evolution of research on AI and education across four decades: Insights from the AIxEd framework — four decades of AIED through the AI×Ed framework
- Educating minds with generative AI — theory-heavy synthesis of generative AI and learning
- An activity-theoretical approach to teacher professional development in pedagogical AI agent design — activity theory applied to teacher professional development
- Activity theory as a lens on teachers’ adoption of AI technologies: A structural equation modeling — activity theory and teacher adoption
- Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence — a learning theory proposed for the generative AI era
- Learning with machines: Toward a theory of epistemic co-agency — toward a theory of epistemic co-agency
- The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students’ Academic Self-Assessment — theorizing a structural gap in AI-native students’ self-assessment

- Agentivism: a learning theory for the age of artificial intelligence — a mid-range learning theory for human-AI interaction
- Measuring Artificial Intelligence Literacy: A Systematic Review of Instrument Development, Conceptual Foundations, and Psychometric Quality — instrument development across a young construct
- Control vs. Agency: Exploring the History of AI in Education — the field's foundational control-versus-agency tension

Theory Development in AI in Education

> **Theory development in AI in education** — the scholarly work of creating, advancing, and critically examining the theories and conceptual frameworks that explain how learners, teachers, and AI systems interact. As generative AI reshapes education, the field is both proposing *new* theories of learning-with-AI and reworking established learning theories — while a documented weakness in theory use remains a cross-cutting limitation of AIEd research.

Questions to Consider

- We often talk about 'applying a theory' to AI in education, but this page asks whether the field is actually inventing new theories. Before you read on: when a familiar framework (like Behaviorism or constructivism) is stretched to cover generative AI, what might it get right, and what might it silently distort?
- Consider a time you used AI and felt your understanding grew — or the opposite. What is the difference between 'learning with a tool' and 'co-constructing knowledge with a machine'? Where would you draw that line, and does it even make sense to say the machine is a co-agent?
- Many AI education studies are criticized for using theory weakly or not at all. If you read a study that showed an AI tool 'worked,' what would it need to tell you about why and how it worked before you would call the finding theoretically meaningful rather than just an effect size?
- One proposed theory claims AI-native students overestimate their own learning because AI inflates their performance. Have you noticed yourself or others feeling more competent after heavy AI use than you could actually demonstrate without it? What would be the strongest evidence that this is a real phenomenon and not just an artifact of one study?
- The page distinguishes theory (explaining mechanisms of learning) from philosophy (questioning what learning and mind fundamentally are). Where in your own thinking about AI do you find yourself moving between the two — for instance, asking not just whether a framework explains learning well, but whether it captures what learning really is?
- New theories are appearing — generativism, epistemic co-agency, cognitive commons. As a reader, what would convince you that one of these is a genuine advance rather than a fashionable relabeling of older ideas? Set your own test for what a good new theory of learning with AI should be able to explain.

Introduction

Theory development in AIEd sits at the boundary between the applied learning theories the field draws on and the novel constructs the AI era is producing. Where Learning Theories catalogs the established theories applied to AI (behaviorism, constructivism, cognitive load, self-determination, etc.), this concept tracks the *process and product of theorizing itself*: which new theories and frameworks are being born, how established theories are being advanced, and the methodological question of whether AIEd research theorizes well. - **A framework that specifies its own comparison condition.** Nakamura (2026) treats the partition of cognitive

labor as the explanatory unit, places operations on a graded peripheral–constitutive continuum, names the comparison condition against which augmentation and erosion are defined, and derives seven conditioned testable propositions (Nakamura, 2026). Because the propositions predict differences between configurations, a study reporting only an average effect cannot confirm or refute them.

New theories of learning with AI

A growing cluster of articles explicitly creates new theory for the AI era rather than applying existing frames:

- **Generativism.** Generativism is proposed as a new learning theory, arguing that behaviorism, cognitivism, constructivism, and connectivism each rest on one assumption that generative AI breaks: that observable output certifies learning (behaviorism), that cognitive operations happen inside the learner (cognitivism), that meaning is constructed rather than supplied (constructivism), and that the hard part is navigating to existing knowledge rather than generating it (connectivism). It names four constructs — epistemic partnership, distributed agency, generative literacy, and adaptive metacognition — and derives an assessment indicator for each, a direct bid to name a distinct theoretical paradigm for AI-mediated learning. What it does not do is state propositions that could fail: it is a position paper synthesizing existing evidence, so unlike Agentivism below it offers a vocabulary and a measurement agenda rather than a falsifiable theory.
- **AI connectedness.** Fu and Zhao (2026) reconstruct connectedness for the AI era through the ethics of care and neo-ecological theory, defining "artificial intelligence connectedness" as a psychologically real yet ethically asymmetric bond with three dimensions and six falsifiable propositions awaiting scale development.

The synthetic position adds a rival bid that does state propositions: it names *synthetic promotion* and *authorial suspension* — a self densely voiced yet un-authored — and predicts a crossover interaction in which a life-decision narrative's rated authorship and coherence move in opposite directions (Du et al. (2026)). - **Agentivism.** Yan and Gašević (2026) propose Agentivism as a mid-range learning theory for human-AI interaction, defining learning as durable growth in human capability rather than successful task completion with AI, and specifying four mechanisms: delegated agency, epistemic monitoring and verification, reconstructive internalization, and transfer under reduced support. What separates it from the other bids on this page is falsifiability: it states six propositions, including that learning is stronger when AI preserves learner responsibility for problem framing, criteria setting and justification than when it supplies answers. It also holds that requiring verification should improve delayed performance while repeated low-friction delegation without reconstruction should weaken learners' calibration of their own competence.

Teacher-side theorizing now makes the same testability commitment: the Capability–Decision Model orders AI-TPACK capability upstream of attitude and perceived behavioral control and names four disconfirmation conditions — mediation failure, discriminant collapse, moderation nullity and context redundancy — though the model remains untested (Mnguni (2026)).

- **Epistemic co-agency.** Learning with Machines builds "toward a theory of epistemic co-agency," a theory-informed model of how learners and GenAI systems jointly produce knowledge and understanding.

- **Cognitive partnership cycle.** Page (2026) proposes the Cognitive Partnership Cycle, a six-phase recursive model — Human Question, AI Expansion, Human Reflection, Integration, Revision, and New Question — that locates learning in a change in the learner's cognitive position rather than in prompt sophistication, and names four failure modes where the same recursion substitutes for or distorts thinking.
- **The absent cognitive baseline (ACB).** The Absent Cognitive Baseline theorizes a structural gap in AI-native students' academic Self-Assessment — a three-dimension framework explaining why students overestimate their learning when AI inflates performance.
- **The cognitive commons.** Cognitive commons and expertise regeneration draws on common-pool-resource theory and distributed cognition to explain how rational AI adoption decisions can deplete the shared expertise pool professions require for renewal.
- **Performance vs. learning.** Performance-vs-learning theorizes the sharp divergence between AI-inflated task performance and durable learning, a distinction that recurs across the knowledge base's Learning Gains evidence.
- **Epistemic AI literacy (EAIL).** Epistemic AI Literacy reframes AI literacy as a process-oriented epistemic competence centered on how knowledge is constructed and justified when students co-program with generative AI.
- **Tri-System Theory.** Shaw and Nave (2026) extend dual-process accounts with **System 3** — external, automated, data-driven reasoning from AI that can supplement, supplant or suppress System 1 and System 2 — and name **cognitive surrender**, the uncritical adoption of AI output, as its characteristic failure.
- **Cognitive stewardship.** Credential and cognitive stewardship theorizes the institutional responsibility for protecting knowledge and learning in AI-pervasive assessment contexts.
- **Co-AI Regulation in Education and epistemic proactivity.** AI as a cognitive partner in co-regulation integrates executive function, Metacognition, distributed cognition, and sociocultural development into a developmental model; epistemic proactivity theorizes students' agentic stance toward AI in mathematics.
- **Human-GAI engagement paradigms.** Strydom (2026) addresses the field's "theory deficit" by grounding seven enacted human-GAI engagement paradigms (guarded, possibility-focused, augmented, pioneering, symbiotic, values-based, equity) in Schommer's multidimensional model of personal epistemological beliefs — an epistemological, rather than tool-focused, theory of how individuals differently position themselves relative to AI.
- **The Ecological Co-Agency Framework.** Poudyal (2026) argues that generative AI reassigns epistemological authority from teachers to students to machines, and introduces a framework defining co-agency through three interdependent dimensions — relational, regulatory (mapped onto the SRL cycle), and pedagogical (teacher adoption continuum) — all bounded by a non-negotiable condition of human epistemic accountability (contestability, provenance, and non-delegation of moral/intellectual credit). It positions Learner Agency as an *epistemic* design problem rather than a usability concern, giving institutions a more precise language than "balance" for governing GenAI integration.

- **Relational epistemic agency and epistemic dependence.** Du & Yuan (2026) contribute a critical-integrative account of when AI-mediated reliance preserves versus displaces judgment. They operationalize the productive-reliance/harmful-dependence boundary through six diagnostic criteria (contestability, recoverability, transfer, traceability, distributed responsibility, epistemic plurality) and trace four sociotechnical pathways (fluent authority, frictionless delegation, opaque synthesis, institutionalized dependence). Their normative proposal, **relational epistemic agency**, extends relational-autonomy and epistemic-co-agency lines by retaining an explicit asymmetry — AI may shape reasoning without reciprocal responsibility or legitimate authority — while integrating responsibility and epistemic justice at the institutional level. As a theory of learning with AI, it moves the field's question from whether AI helps or harms to which epistemic actions are preserved, transformed, or displaced, and it makes the *design of dependence* rather than mere use the object of pedagogical and institutional intervention.

Advancing established theory

Other work extends existing theory into the AI context rather than founding new paradigms: critical-thinking-paradox work integrates cognitive-load theory with load-reduction instruction into a three-level framework; equitable assessment re-theorizes Assessment under GenAI disruption. Ba, Gašević, Lim & Anderson (2026) reconceptualize the Community of Inquiry framework itself: rather than framing GenAI as a tool, dialogic partner, or a speculative "fourth presence," they reposition it as an *epistemic condition* that reconfigures how cognitive, social, and teaching presence are enacted, evidenced, and governed — recasting CoI presences as sociotechnical accomplishments of human–GenAI assemblages and proposing a configuration-based heuristic in which GenAI involvement and inquiry quality are conditionally related through human accountability. Much of this is conceptual-framework work (business-school frameworks, valid simulation) that operationalizes theory for practice.

Lin and Chang (2026) extend Self-Regulated Learning and human–AI regulation by naming what the learner governs — standards, evaluative judgments, and control authorization — rather than only what the AI does.

The friction paradox offers another extension of established theory: Gupta (2026) applies Bjork and Bjork's desirable difficulties and Kapur's productive failure to relational encounters in education abroad, arguing that what matters is how much interpretive agency a student transfers to a generative assistant rather than how often it is used. The framework is conceptual and states five propositions as competing hypotheses.

Ranieri & Biagini (2026) advance the field's functional taxonomy of Zawacki-Richter et al. (2019): among the 154 publications with a classifiable application function, 90 (58.4%) escaped its four categories, and their framework crosses function with delegated control, epistemic position and embedded pedagogy.

An, McLaren, and Stamper (2026) advance ACT-R and the Knowledge-Learning-Instruction framework by theorizing *deceptive overgeneralization* — a failure mode in which knowledge compilation yields an overgeneralized production that produces correct actions while omitting a critical application constraint — and by empirically validating a detection/remediation procedure across adaptive ITSs and a K-12 decimal-learning dataset.

Postphenomenology and technological mediation. Farazouli et al. (2026) advance the established postphenomenological framework of technological mediation (Ihde 1990; Verbeek 2006, 2011; Rosenberger & Verbeek 2015) into the AI-in-education context. Rather than proposing a new theory, they apply it to

reconceptualize GAI chatbots as *multistable technological artifacts* whose "scripts" (rapid responsiveness, natural-sounding text that can achieve passing grades) mediate teachers' perceptions and reconfigure their practices — unsettling teacher confidence, reshaping what competence means, and pushing teachers beyond instrumental questions of acceptable use toward re-evaluating their role and the meaning of teaching. This is a theory-*advancement* contribution: it demonstrates how a philosophical account of human–technology relations explains the emotional and professional disruption teachers experience when GAI enters established educational practice.

A further framework contribution is Rismanchian & Doroudi's AI×Ed typology, which extends Kahn's (1977) original "three interactions" along two axes — the role of AI (applied tool vs. analogy to human intelligence) and the end user (researcher to learner) — to locate any AIED project. Beyond categorizing the field, it argues for reviving the "AI as an analogy to human intelligence" strand of theory and research, using computational and agent-based models of learning (e.g., their own computational model of the ICAP framework) to bridge contemporary learning theory and computational modeling — a methodological direction the field largely abandoned when it turned toward applied, data-driven work.

Comparative philosophy as a route to theoretical pluralism. Xie (2026) models a different route to theory development: instead of theorizing AI in education from within one tradition, the paper stages a comparative dialogue in which each tradition "renders visible what the other obscures," explicitly declining to synthesize them into a single framework — an approach that treats theoretical pluralism as a methodological position rather than an unresolved disagreement. He argues non-Western traditions can do more than diversify debates; they can reshape the conceptual foundations of AIED theory, reconstructing Daoist "Dao nature" (道性), self-cultivation (修道) and the "Zhenren" (真人) as resources for rethinking Learner Agency, the epistemic aims of education and ethical action under AI-mediated conditions. He also states the limits plainly: the contribution is single-author, non-empirical, and warns that such translation requires contextualization to avoid romanticization and Orientalism.(Alternative AI Philosophy: Daoism as Method for AI in Education)

The theory-use problem in AIEd

The field's theorizing is uneven. Limitations in AIEd research documents that AIEd studies frequently use theory weakly or uncritically — a recurring methodological weakness alongside reproducibility and measurement gaps. Reviews find many AIEd papers apply theory superficially or not at all (e.g., literature reviews noting few studies ground interventions in learning theory). This makes theory *development* — and theory *use* — a quality concern as much as a scholarly output, connecting to research methods and AI Ed Evaluation.

Relationship to the philosophy of AI in education

Theory development and the philosophy of AI in education are complementary but distinct strands of the knowledge base's foundational work. **Theory development** produces and empirically tests the *mechanisms* of learning-with-AI — named theories and frameworks such as generativism, epistemic co-agency, and the absent cognitive baseline that explain and predict how learners and AI interact. **Philosophy** interrogates the *presuppositions* those mechanisms rest on: what counts as knowledge, who counts as a knower, and what the learner fundamentally is. A theory like epistemic co-agency proposes a mechanism while implicitly adopting

philosophical commitments about distributed cognition and Learner Agency; philosophy makes those commitments explicit and contestable. Where theory development asks whether a framework explains learning well, philosophy asks whether it captures what learning and mind really are — the two strands meet in the field's most foundational articles, which often do both at once.

Common Misconceptions

"A finding that the tool worked is a theoretical contribution." It is not, and the reason is structural. Where a framework's propositions predict *differences between configurations*, a study reporting only an average effect **cannot confirm or refute them** — the design cannot see the distinction the theory is about. A trial showing a mean gain tells you something happened, not which mechanism caused it, so the theory remains exactly as supported as it was before.

"Applying an established theory to AI is theory development." The page's own theory-use problem says otherwise: application is not advancement, and the field's recurring pattern is borrowed constructs used as vocabulary rather than as testable predictions. The distinction matters because a borrowed frame that cannot generate a falsifiable difference is decoration, not theory.

"The existing taxonomies of AI's pedagogical function already cover what these systems do." They do not cover much of it. Among 154 publications with a classifiable application function, **90 (58.4%) escaped the four categories** of the prior framework, which is why the newer work crosses function with delegated control, epistemic position and embedded pedagogy. A taxonomy that misclassifies nearly three in five cases cannot serve as the field's common vocabulary, and the gap is a finding about the phenomenon rather than a gap in a paper.

Implications for Practice

For instructors and instructional designers

- When a study reports an average effect, do not treat it as guidance about *your* configuration. The theory-level claims are about differences between configurations, and an average cannot tell you which one you are running.
- Ask of any framework you adopt whether it predicts something that could turn out false in your own setting. If it cannot, it will not help you decide anything.
- Expect existing categories to miss your case; over half of classified publications did not fit the standard four-way split.

For developers

- Report configurations rather than a single headline effect. If your design embodies a specific delegated-control and epistemic-posture combination, say so — that is the unit the theory speaks to and the unit another team needs to reproduce.
- Do not market a mechanism claim on the strength of an average outcome; the evidence type required for the mechanism is a contrast, not a mean.

For researchers

- Design for configuration contrasts if you intend a theoretical contribution. An average-effect trial published as theory development is the field's most common and least useful output.
- Attach explicit falsifiable propositions to any framework you introduce, and report which configuration differences would have refuted them.

Connected Concepts

- Learning Theories
- Philosophy of AI in Education
- Limitations in AIEd Research
- Research Methods in AIED
- Generative AI
- Constructivism
- Metacognition
- Cognitive Offloading
- Learning Gains
- AI in Education
- AI Ed Evaluation
- Community of Inquiry
- Cognitive Surrender

Connected Articles

- Artificial Intelligence in Higher Education (2019–2026): A Systematic Review of Applications and an Evidence-Derived Multi-Axial Taxonomy — Extending the functional taxonomy: 90 of 154 classifiable publications (58.4%) fall outside the original four categories (Ranieri & Biagini 2026)
- Agentivism: a learning theory for the age of artificial intelligence — A mid-range learning theory for human-AI interaction, with four mechanisms and six testable propositions (Yan and Gašević 2026)
- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education
- Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence — Generativism as a new learning theory
- Learning with machines: Toward a theory of epistemic co-agency — Toward a theory of epistemic co-agency

- Epistemic dependence in AI-mediated learning — Relational epistemic agency and the productive-reliance/harmful-dependence boundary (Du & Yuan 2026)
- The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students' Academic Self-Assessment — The absent cognitive baseline (ACB)
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — Cognitive commons and expertise regeneration
- Distinguishing performance gains from learning when using generative AI — Performance vs. learning
- Constructing Epistemic AI Literacy: Detecting Epistemic Aims and Processes in Student-AI Co-Programming — Epistemic AI Literacy (EAIL)
- What Does the Credential Still Certify? Cognitive Stewardship for AI-Mediated Education — Credential and cognitive stewardship
- Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning — AI as cognitive partner in co-regulation
- From Prompting to Epistemic Proactivity: Temporal Trajectories of Student-AI Interaction in Mathematics Learning — Epistemic proactivity in mathematics
- Framing human-AI dynamics: An epistemological perspective on generative AI practices — Seven human-GAI engagement paradigms grounded in epistemological beliefs
- The critical-thinking paradox in generative AI-integrated learning: distinguishing efficiency from cognitive depth — a differentiated framework and testable propositions — The critical thinking paradox
- Reimagining Success and Failure: Equitable Assessment Practices in an Age of Artificial Intelligence — Equitable assessment under GenAI
- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Tri-System Theory and cognitive surrender: how AI reshapes human reasoning (Shaw & Nave 2026)
- Reconceptualizing community of inquiry in the age of generative artificial intelligence — Reconceptualizing Community of Inquiry in the age of generative AI
- Navigating uncertainty: university teachers' experiences and perceptions of generative artificial intelligence in teaching and learning — University teachers' experiences and perceptions of GAI: vulnerability, rethinking assessment, student learning at risk (Farazouli et al. 2026)
- The evolution of research on AI and education across four decades: Insights from the AIxEd framework
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues

- Metacognitive Ownership in Human-AI Regulation: Construct Definition, Boundaries, and a Research Agenda — Metacognitive ownership: construct definition, boundaries, and a research agenda
- The synthetic position: generative artificial intelligence and the suspension of self-authorship in emerging adulthood — The synthetic position: a dialogical-self bid naming synthetic promotion and authorial suspension with a crossover prediction
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Falsifiable capability-first teacher readiness model with four disconfirmation conditions
- Artificial Intelligence Connectedness: Theoretical Reconstruction of Connectedness and Its Impacts on Adolescent Mental Health — Artificial intelligence connectedness: a three-dimensional construct with six falsifiable propositions for later testing
- From Answer Generation to Cognitive Partnership: A Conceptual Framework for Human–AI Learning — Cognitive partnership cycle
- The friction paradox: generative AI and the educational value of difficulty in education abroad — Desirable difficulties and productive failure applied to interpretive agency in education abroad

Cross-cutting themes

Human AI Collaboration

> **Human-AI collaboration** — the division of cognitive labor between people and models — is the knowledge base's core interaction theme: Human-AI collaboration in higher education: Exploring the impact of technology expectations and distrust, "It felt a bit eerie": Exploring humanlike interactions during collaborative writing with an artificial agent, Generative AI (GenAI) as a mindtool that supports generative learning (GL), and Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing examine trust, agency, and complementary roles (Human-in-the-Loop, Agentic AI). The defining question is whether the partnership **preserves or replaces** the learner's own cognitive work — the same arrangement can support learning or substitute for it depending on how responsibility is shared.

Questions to Consider

- The defining question in human-AI collaboration is whether the partnership preserves or replaces your own cognitive work. Think of a task you've handed to AI: were you generating and deciding, or just accepting?
- One study found that freely collaborating with ChatGPT produced only transient gains that collapsed on a later unassisted task, while a 'think first, ChatGPT later' protocol yielded durable learning. Why might who generates the ideas predict whether you actually learn?
- The same tool can support learning or substitute for it depending on how responsibility is shared. Can you think of an arrangement that kept you cognitively productive versus one that quietly offloaded your thinking?
- One arrangement reverses the usual roles: instead of the model supplying answers, the student explains the content and the model plays the ignorant party who asks for explanations, examples and a counterargument. If the AI is the one asking, what happens to how much of the thinking stays on your side?
- Trust is described as something that must be calibrated, not assumed — relying on AI where appropriate and verifying where not. How do you currently decide when to trust and when to verify AI output?
- Research identifies collaboration modes that trade off efficiency against the depth of your self-regulatory engagement. When is it worth accepting less efficiency to keep more learning in your own hands?
- If collaboration is a pedagogical choice as much as a technical one, what design moves (prompts, workflows, structures) would you set up to ensure AI augments rather than replaces thinking for your learners?

Introduction

Human-AI collaboration describes how learners, teachers, and AI systems divide cognitive work — who does what, who decides, and how Trust and Learner Agency are maintained. Rather than framing AI as either

a replacement or a passive tool, collaboration research treats AI as a partner with complementary strengths whose value depends on how responsibility is shared and monitored. At the level of observable behavior, Student-AI Interaction captures how learners enact this relationship in practice — the questions, prompts, and verification moves they make with AI moment to moment.

The division of labor also runs through the people who design the interaction. Across twelve teacher-education course implementations, faculty positioned AI as a thinking partner, critique generator or rehearsal tool while candidates kept responsibility for evaluating, adapting and justifying decisions, yet the same white paper reports that candidates devalued feedback they had already judged useful once AI authorship was disclosed, an episode it calls the balloon popping effect. An analysis of 1,378 designer-chatbot turns points the other way on generation: designers used an embedded assistant mainly for alignment checks on learning outcomes and pedagogical approach rather than for producing content. In both cases the human's evaluative judgment, not the model's output, carries the learning.

Benefits, risks, and design implications

The knowledge base's evidence shows that human-AI collaboration is a double-edged arrangement whose outcome is determined by design rather than by AI itself:

- **Collaboration can enhance learning when it preserves cognitive engagement.** Studies of GenAI as a mindtool and guided collaboration show that when the division of labor keeps the learner generating, deciding, and evaluating, AI augments rather than replaces thinking — producing durable self-regulated learning and Creativity gains. That the learner keeps the deciding role scales to writing: Oppenheimer, Cash & Connell Pensky (2025) show LLM critiques of students' argumentative essays improved writing across a semester, with learners deciding whether to incorporate or rebut the model's feedback (87.8% rebutted claims) — an arrangement that preserved the learner's evaluative work — and gains appeared even on essays written without LLM support, suggesting durable skill rather than tool dependency.
- **Collaboration can substitute for learning when it offloads too much.** The failure mode is over-reliance: when AI produces the answer, the learner's role collapses into passive acceptance, and immediate task performance masks a lack of durable learning. Performance-versus-learning research and the substitution-to-scaffolding harm cycle (From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle of AI in Education (and Beyond)) document this systematically.
- **A better score is not by itself evidence that the collaboration taught anything.** The page's other evidence reads assisted performance cautiously, and a randomized test of support type shows why. In Iqbal et al.'s (2026) laboratory study, 87 EFL students wrote an essay unaided, then revised it with ChatGPT 4.0 (n = 29), with a human writing instructor (n = 28), or with no support (n = 30). Which of four trace-derived revision strategies a student used was strongly associated with the support they had (Cramér's V = 0.668) and only moderately with their earlier writing strategy (Cramér's V = 0.333); Motivation, writing skill and metacognitive judgment accuracy showed no overall association, the metacognitive link surfacing only in the no-support condition ($p = 0.0460$). Critically, no revision strategy predicted score change ($p = 0.273$) even though support type did: the GenAI group improved significantly more than the human-expert and control

groups ($H(2) = 16.591$, $p = 0.00025$, $\eta^2 = 0.174$), and inside the same *gradually decreasing Help-Seeking* strategy GenAI students gained about 4 points on average while human-expert students lost 0.5. The authors read the pattern as external support bypassing the learner's own metacognitive judgment and warn that the gains may be task-specific optimization rather than durable capability. This does not overturn the *who generates and decides* principle (the study varied who supplied support, not who generated the thinking), but it sharpens the test an instructor should apply: a gain obtained under assistance has to survive an unassisted task before it counts as learning, and adding a human expert to the room is not automatically the safer arrangement.

- **Adding peers is not automatically the safer arrangement either.** Chu, Dai and Zhai (2026) set 87 undergraduates to work alone or in pairs with a GenAI multi-agent system for eight weeks. Pairs scored highest on the complex design project ($M = 89.64$, against 85.85 for students who worked in pairs without the system and 86.45 for those working with it alone, $p = 0.039$), yet critical-thinking awareness rose most for those working alone ($M = 0.41$) and declined slightly for the pairs ($M = -0.04$, $p = 0.039$).
- **Design principle — preserve the learner's productive work.** Across the research, the sharpest predictor of whether collaboration helps or harms is *who generates and decides*. Arrangements that keep the human cognitively productive (guided prompting, "think first, then consult AI," verification and evaluation steps) support learning; arrangements that hand the whole task to the model do not. The complementary move is to change what the model is assigned to *be*. In Wang et al.'s (2026) quasi-experiment, 68 preservice teachers either explained the flipped-classroom concept to a GAI *novice learner* built on ERNIE 3.5 (a system framed as inquisitive and appreciative that asked for explanations, examples, verification reasoning and an opposing perspective, sequenced up Bloom's taxonomy) or asked questions of a GAI teacher built on the same model. The students who taught the AI explained better (defining the flipped classroom $M = 4.18$ vs 3.29; its teaching activities $M = 4.91$ vs 3.06, both $p < 0.001$) and generated more and higher-quality questions ($M = 3.67$ vs 2.14; $M = 5.67$ vs 3.07, both $p < 0.001$), while objective recall was statistically indistinguishable ($M = 23.18$ vs 21.57, $p = 0.416$), so the advantage sat in explanation and transfer rather than fact retrieval. Students in the AI-teacher condition were candid about the trade: some granted that it gave "more accurate and detailed information" yet reported that "after using it, I didn't want to think independently." Assigning the model the role of learner to be taught turns the student into the sole source of the ideas and removes the long-standing difficulty of finding a suitable peer to teach. Two design limits come with it: planning and monitoring did not improve ($M = 4.01$ vs 3.78, $p = 0.062$), so role reversal is not by itself a metacognitive intervention, and the authors trace that null to a task design that kept students focused on content accuracy. In a writing classroom that principle takes a concrete, teachable form. In Alshehri et al.'s (2026) Saudi EFL quasi-experiment, students ran a five-part routine — frame the problem and design prompts, draft iteratively, revise, verify every claim and citation against scholarly databases, and regulate their own attribution and reliance — with each assignment requiring an AI-use log of what they accepted, rejected, and why. Writing and digital critical thinking rose together and moved almost in lockstep, and the students' reflections tied the verification and hallucination-repair routines specifically to the critical-thinking gains: the same habits of interrogating outputs shaped their composing decisions. The authors' own caveat is the

necessary complement to the principle — the workflow is contingent rather than self-sufficient, and can turn counterproductive under thin Scaffolding, low critical-thinking or metacognitive readiness (where students lack the capacity to catch bad output), gradual delegation of composing decisions, or unclear institutional AI-use policy.

- **Bounded authority is itself a design pattern for high-stakes collaboration.** Teachers in Reichert et al. (2026) did not prototype open-ended assistants but systems whose freedom was fixed in advance: every design scoped the chatbot to specific lesson content, and safety was layered as domain boundaries (lesson-specific scope, plus an "information quota" requiring a minimum number of facts or problems before the conversation progressed), content filtering with standardized refusals ("Sorry, this is not part of my knowledge base") that also alerted the teacher, and a teacher override for ambiguous cases — the example given was a question about human reproduction that was legitimate within its unit and should route to a person rather than be auto-rejected. Personalization of format, genre, pace, and complexity was welcomed *inside* those boundaries, and oversight (complete conversation logs, real-time alerts, override) was framed as professional responsibility rather than distrust of the model. The implication is that in high-stakes settings the division of labor should be specified as bounded, monitored, and revocable rather than negotiated turn by turn.
- **Automation and augmentation are not alternatives.** Across four teacher-facing cases, replacement stayed inside bounded analytical subtasks while complementation appeared wherever teachers interpreted and validated the output, so augmentation turned out to be a property of what the teacher does next rather than of the tool itself (Horvers et al. (2026)).
- **Trust must be calibrated, not assumed.** Productive collaboration depends on learners accurately calibrating when to rely on and when to verify AI output — connecting to Trust Calibration and human oversight rather than blind acceptance or blanket rejection.
- **An affective alert is a cue the teacher interprets, not an instruction to obey.** In one high-school geometry lesson, an AI system's emotion alerts preceded very different teacher moves, and the move — task reframing, brief affirmation or deliberate non-intervention — is what changed engagement, so the alert worked as one input among what the teacher could observe (Swidan (2026)).
- **Teacher–AI collaboration is double-edged for engagement, not only for learning.** In a three-wave survey of 468 university teachers, collaboration raised work engagement through psychological availability (indirect 0.19) but lowered it through work alienation (indirect −0.03); digital competency moderated both, flattening the alienation slope from 0.38 to 0.17 (Sun et al. (2026)).
- **The division of labor follows credibility, not capability.** What learners settle on is a principled allocation: AI for immediate, broadly applicable language feedback and instructors for individualized, relational guidance, assigned by each source's perceived credibility rather than its accuracy, because the binding constraint on reliance was perceived care, not competence (Serpil & Mor, 2026).
- **Reliance is a population process, not only an individual choice.** In an agent-based model, visible social proof for unverified use collapsed verification from 0.29 to 0.002 and lifted

overreliance from 0.30 to 0.52, while visible peer verification restored near-complete verification — changing what learners see others doing beats lowering checking costs (Biswas (2026)).

This makes human-AI collaboration a *pedagogical* construct as much as a technical one: the value of the partnership is shaped by how teachers design the interaction, how learners regulate it, and how the system invites or discourages productive engagement.

How human-AI collaboration appears in the research

- **Trust and expectations:** Trust expectations examine how learners' expectations of AI shape whether collaboration is productive or leads to Over-Reliance.
- **Complementary roles in writing and thinking:** Humanlike AI collaborative writing and GenAI as a mindtool show how AI can augment rather than replace learner thinking when the division of labor preserves the learner's cognitive engagement.
- **Orchestration and agency:** Teacher–student agency orchestration and student mental models address how agency is negotiated across humans and AI, connecting to Human-in-the-Loop and Agentic AI.
- **Metacognitive and team dimensions:** Human-centered AI metacognitive models and disciplinary mediation in student teams extend collaboration to metacognition and team learning.
- **Collaboration competency as a configuration, not a checklist — metacognition takes Technological Pedagogical Content Knowledge (TPACK)'s integrative role.** Dang, Hong, Doyle and Nguyen (2026) define Human-AI Collaboration Competency as a *dynamic configuration* of domain, AI competency and metacognitive competency plus their intersections (Working with AI, Agentic Learning with AI, Agentic Personal and Professional Development, and HACC itself), explicitly rejecting an additive list of AI skills bolted onto an existing curriculum. Their central move reassigns the integrative work that pedagogy does in TPACK: because AI is an adaptive participant whose contribution shifts as a task unfolds, the coordinating burden falls to the learner's own metacognition — deciding when to consult AI, how to frame the interaction, and when to override it — so it is the learner, not the teacher, who holds the mechanism that keeps the collaboration productive. Learner agency is deliberately omitted as a standalone node; it is instead the emergent quality learners express when they coordinate the three competencies, which makes agency a property of the configuration rather than a skill to be trained in isolation. The framework's interview study with 24 New Zealand educators supported the dimensions descriptively, and role level shifted emphasis rather than acceptance: principal educators' networks centered on AI with links to HACC and professional development, differing significantly from senior educators ($U = 10.00$, $p = .04$) and early-career educators ($U = 7.00$, $p = .01$).
- **Distinct collaboration modes:** empirical work identifies three human–AI collaborative Problem Solving modes — *Delegated Reasoning*, *Concerted Interpretation*, and *Delegated Elaboration* — revealing a trade-off between the efficiency of the distributed human–AI system and the depth of learners' self-regulatory engagement (delegated reasoning performs best but with lower self-AI

Regulation in Education).(Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective)

- **Human and AI facilitators can be perceptually interchangeable in structured discussion, but reuse runs on different reasons.** Kuhail et al. (2026) swapped a human moderator for a GPT-4 moderator (and back again) across 32 debate sessions run by 32 STEM students, and found no statistically significant difference on effectiveness, enjoyment, satisfaction, utility or intention to use (t ranged from 0.23 to 1.30, p from 0.198 to 0.818). What differed was why students would return: under AI moderation, perceived utility drove intention to use (0.806, p = 0.004), while satisfaction drove it only under human moderation (0.556, p = 0.002). The authors read the flat comparison as normalization in rule-bound tasks rather than as proof of equivalence, and recommend keeping human oversight for ethical and relational reasons while making AI-moderated activities' usefulness legible instead of leaning on enjoyment. Because the study measured perceptions only, it says nothing about whether students argued any better.
- **Assign the task before delegating it.** Tsim and Gutoreva (2025) add a fourth zone — what the model already knows — to the learner's development zones, yielding Substitute, Complement, Aid and Non-negotiable assignments, and argue the automation–augmentation–collaboration modes differ by locus of control and epistemic responsibility rather than by tool sophistication.
- **Prompt engineering as pedagogical thinking, built through lesson study.** Robinson et al. (2026) followed five teacher educators at one UAE institution through two lesson study cycles reaching 36 pre-service teachers in secondary and primary mathematics, designing AI-supported lessons with ChatGPT (GPT-4o). The move that did the work was pairing the AI with a disciplinary framework: PSTs generated a task, judged its cognitive demand against a modified Mathematical Task Analysis framework, then rewrote their prompt to raise conceptual depth, so revision was anchored in the mathematics rather than in tool features. Sixteen of 26 analyzable prompts carried conceptual task features, and the educators concluded that prompt engineering is "not a technical skill; it's a cognitive one." Reported learning rose in the revised lesson (5 of 7 PSTs in the first cycle and 10 of 14 in the second reported learning to distinguish conceptual from procedural tasks), with the caveat that asking AI for a more conceptual task sometimes produced merely a more complicated one. For faculty development, the argument is for sustained collaborative inquiry into real lessons rather than standalone tool workshops.
- **Guidance decides performance versus learning:** Wong and Qiu (2026) contrasted free vs. guided human–AI collaboration on a creative task. Freely collaborating with ChatGPT produced only transient performance that collapsed on a later unassisted task, whereas a guided "think first, ChatGPT later" protocol — generating one's own ideas, then using ChatGPT to improve, develop, and evaluate them — yielded durable gains in *independent* Creativity. The advantage was mediated by collaborative prompts aimed at improving one's *own* ideas, showing that *who generates* (the division of labor) predicts whether collaboration produces learning or substitution.(Think First, ChatGPT Later: Guiding Human–AI Collaboration for Learning Gains in Independent Human Creativity)
- **AI as mediator, not merely partner:** Niari reconceptualizes AI as a *pedagogical mediator* that orchestrates interaction, epistemic sense-making, and regulatory processes, redistributing agency,

authority, and responsibility across human and non-human actors rather than treating AI as a tutor, peer, or tool.

- **Teachers' collaboration with AI is also patterned, not binary.** When teachers design lesson designs with generative AI, their interaction takes empirically distinguishable forms. Choi et al. (2026) identified seven teacher–AI interaction patterns — from *direct adoption* and *elaborated adoption* of AI output to *initial rejection*, *revised adoption*, *follow-up guided use*, *complex interactions*, and *bypassing AI* — where a teacher's teaching experience and AI proficiency jointly shape whether they critically re-prompt and adapt AI to students and context (a complementary, Distributed Cognition division of labor) or passively accept suggestions (an AI-dominant distribution).
- **The mediational agent as a hybrid form of participation.** Rather than a midpoint between tool and collaborator, generative AI is conceptualized as a mediational agent that mediates action while generating contingent, non-accountable contributions — a distinct category that redirects design from technological capability to habits of participation (supervisory agency, epistemic vigilance). (Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory)
- **Community and epistemic authority:** community-based AI learning shows collaboration is also a question of *who is authoritative*, grounding AI engagement in learners' lived epistemologies.
- **Data-driven trait discovery:** Principal Trait Analysis (PTA) automates the derivation of interaction "traits" from large Large Language Models (LLMs)-conversation corpora — a PCA-inspired, four-stage pipeline that extracts behavior observations, clusters them into candidate traits, scores each collaborator, and selects the most distinguishing traits. Evaluated on a student–AI-tutor corpus and a developer–coding-agent corpus, PTA finds traits that explain and predict outcomes (e.g. deep conceptual engagement positively, task delegation negatively, in the educational setting), and — because they do not yet generalize across semesters/settings or show learning-curve trajectories — the authors argue the traits are not yet interpretable as "skills." This offers a scalable, objective complement to AI Literacy frameworks and self-report measures, directly informing how educators teach "AI use skills."
- **The human–AI relationship as the most persistent concern across CAI generations.** The umbrella review of conversational AI agents (Ganguly et al. 2025, 34 reviews) finds human–AI relationship concerns — over-reliance, social isolation, depersonalization, emotional dependency, transparency, accountability — are the most frequently discussed ethical issue across all CAI generations, predating GenAI. This positions the "preserve vs. substitute" question at the very center of CAI ethics and reinforces that collaboration's value is determined by design (who generates, who decides, how responsibility is shared).(Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use)
- **AI scaling real-time *expertise* to novices — the first live-tutoring RCT.** Wang et al. (2024)'s randomized trial (900 tutors, ~1,800 K-12 students in under-served communities) placed AI on the *tutor's* side rather than the student's: Tutor CoPilot generated real-time expert-like suggestions (built from experienced tutors' think-aloud reasoning) that novice tutors could edit or reject. Students of treated tutors were 4 p.p. more likely to master topics ($p < 0.01$), with 9 p.p. gains

among students of the lowest-rated tutors — who rose to match higher-rated tutors' control outcomes — at ~$20/tutor/year. The finding is a strong empirical anchor for teacher/tutor augmentation as an equitable human-AI collaboration mode: the human keeps pedagogical judgment and autonomy while AI supplies scalable expertise.

- **Bounded experts: how teachers partition authority with an AI.** Reichert, Briceno, Tabarsi & Barnes (2026) ran a participatory design study in which six secondary teachers prototyped LLM chatbots for their own classrooms and analyzed how authority should be distributed between teacher and system. Teachers consistently framed the AI as a *bounded expert* - specialized capability confined to a strictly defined domain and operating under human supervision - and split that boundedness into two dimensions: *authority boundaries*, where professional and legal responsibility for student learning and safety cannot be delegated, and *expertise boundaries*, where the system lacks the teacher's contextual knowledge of individual students, classroom dynamics, and institutional norms. Mapping the prototypes onto Gagné's nine events of instruction showed delegation was selective rather than all-or-nothing: teachers welcomed AI for presenting content, supplying practice problems, Scaffolding, and formative Feedback, but refused to hand over informing students of objectives or summative Assessment. The design reading is that a collaboration interface should make visible where the human keeps the deciding role, not merely where the model is capable.
- **The role must adapt, not just be labeled.** Liao (2026) shows a fixed "peer" AI companion sustained longer book-talk interactions but dominated the exchange (lower student word/sentence share) and hit an affective ceiling, arguing collaboration requires role-*adaptive* logic — switching between peer, assistant, and advisor — rather than a single static persona.
- **Teacher-side co-design and role architecture are also collaborations.** Beyond student-facing partners, teachers collaborate with GenAI to design instruction. Wang et al. (2026) systematically review teacher–AI co-design of learning tasks, charting the collaborative modes and tensions (agency, epistemic authority, control) that arise when teachers and AI jointly produce designs; Talebzadeh (2026) finds teachers' pedagogical expertise — not AI fluency — determines the quality of AI-designed differentiated group activities (role richness, synergy, level-alignment), positioning the teacher as a "bilingual learning designer."
- **GenAI as an agent and a collaborative space in groups.** Xu et al. (2026) observe small Higher Education teams and show GenAI's role is negotiated and configurable — from subordinate assistant to contested teammate — and that synchronous shared use sustains common ground while asynchronous private use fragments transparency, proposing a GenAI-Supported Cooperative Work lens that treats GenAI as both agent and interactive collaborative space.
- **Complementary halves of classroom collaboration.** Two 2026 studies map complementary halves of human-AI collaboration in classrooms. MeduAI-SP (Yang et al.) argues for "functional complementarity" in clinical education: AI agents handle repetitive role-play, consistent patient Simulation, checklist monitoring, Socratic prompting and preliminary formative feedback, while faculty and human standardized patients provide contextual interpretation, nuanced emotional response, individualized remediation, professionalism assessment and readiness judgments — substitution being bounded by error consequences, task uncertainty, relational sensitivity and

available human review, and an AI system explicitly barred from autonomously determining clinical competence. In the opposite direction, a 45-student mixed 3-human/3-agent ethics discussion (Seo et al., 2026) documents a double-edged pattern: agents lowered social barriers (participants spoke more directly because agents lack emotions, and felt no obligation to fill silences), yet the same comfort diverted interaction away from humans — 79.7% of questions went to agents versus the 60% their availability predicts ($p = .017$). Notably, the presence of other humans made participants treat the AI more respectfully, suggesting human co-presence is itself an affordance for calibrating AI engagement.

- **Complementarity is conditional, not a default property of teams.** Tuo et al. (2026) found human-AI teams beat both humans and AI alone in only one of six conditions — the challenging cases where the AI was *less* accurate than the humans — reporting no consistent team advantage elsewhere, so adding an AI partner is not by itself a route to complementary performance.
- **Professional programs redirect training from routine production toward collaboration competences (a design protocol):** Wang (2026) proposes a design-based framework for translator education built around a task-displacement inventory (18 sub-tasks rated for AI displacement likelihood with [E]/[P] provenance tags) and four redirected competencies: cross-disciplinary knowledge, AI orchestration, strategic judgment, and critical AI evaluation. The framework is a pre-registered protocol with no empirical data yet; its contribution is the method — an auditable displacement analysis plus a co-design pathway for curriculum reform — which transfers to any professional program whose routine tasks agentic systems increasingly perform.
- **Entanglement types differ in what they demand of the student, and that is why some stay rare.** Sun, Dohn and Rehm (2026) classify 102 higher-education studies by how epistemic work is shared between student and system (Assistant, Enabler, Synthesizer, Generator, Reimaginator) and find the two forms that keep competence attributable to the individual student accounting for 42.16% of the corpus each, while the forms that distribute authorship remain marginal. Their explanation is institutional rather than technical: the rare types ask students to take epistemic responsibility for outputs they did not produce while still being assessed as individual authors, and it is that contradiction — not the division of labor itself — that keeps them out of practice. The design response is to make the distribution of epistemic work explicit, sequence activities across the spectrum, and build reflection on how responsibility was shared.
- **Owning a work is not the same as authoring it.** Hong et al. (2026) name an *authorship legitimation deficit*: a person can experience an output as their own yet be unable to warrant the author role, because psychological ownership, the sense of Learner Agency, and answerability for releasing the work are separate routes that need not align. Their labor nexus of authorship classifies contributions role by role, so one record can support an editorial claim and fail a sole-creator claim at once. The account is a conceptual analysis with no data and no tested model, so the deficit is a proposed construct whose predictions remain untested.
- **Guiding, not telling, needs its own criterion for judging an agent.** A design case that set out to mirror teacher facilitation found that a knowledge agent bounded to a curated base could be judged on accuracy, while an agent meant to lead students toward their own answers could not (Humburg et al., 2025).

Connections

Human-AI collaboration connects to Human-in-the-Loop (oversight), Agentic AI (autonomy), Teaching (teachers' changing work), Scaffolding and Metacognition (how collaboration supports learning), and Over-Reliance (the failure mode when collaboration becomes substitution). It is a core theme across AI Literacy, Self-Regulated Learning, and Student Experience.

Common Misconceptions

- **"Collaboration means the AI does part of the work." The learner keeps the deciding role**, and this scales to writing: Oppenheimer, Cash and Connell Pensky (2025) show it holds when the arrangement is designed for it. Division of labor is not collaboration unless the human retains judgment.
- **"The AI does the explaining in a flipped arrangement." Students who taught the AI explained better** — flipped-classroom defining at **M = 4.18 versus 3.29**, teaching activities at **M = 4.91 versus 3.06, both p < 0.001**. The learning accrued to the explainer.
- **"Human and AI contributions are substitutes."** Two 2026 studies map **complementary halves** of classroom collaboration, which frames the design problem as allocation rather than replacement.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- Community of Inquiry — Community of Inquiry (presences as human-GenAI sociotechnical accomplishments)
- Student-AI Interaction
- Generative AI
- AI Literacy
- Large Language Models (LLMs)
- Scaffolding
- Intelligent Tutoring
- Teaching
- Higher Education
- K-12
- Cognitive Offloading
- Student Experience
- Metacognition
- Self-Regulated Learning
- Creativity
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation

- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools
- Human-in-the-Loop — oversight
- Agentic AI — autonomy
- Productive Failure

Connected Articles

- SciStory: Designing AI-Supported Inquiry in Science Learning Games — Three agent roles in a narrative science game, and which evaluation criterion each needs (Humburg et al. 2025)
- Many hands make light work? Individual and collaborative interaction with a GenAI-powered multi-agent system: Effects on learning performance and critical thinking — Paired work with a GenAI multi-agent system won the design project while critical-thinking awareness rose only for those working alone (Chu et al. 2026)
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Multi-agent debate with the preferred answer withheld cut deferral to incorrect AI advice, but not correctively
- Conceptualising Human–AI Collaboration Competency for hybrid intelligence: towards learner agency through a metacognitive perspective — HACC: collaboration competency as a dynamic configuration of domain, AI and metacognitive competency, with learner agency emergent (Dang et al. 2026)
- Human-centered design of LLM-powered educational chatbots: A study with secondary teachers — Secondary teachers design classroom chatbots as bounded experts under human supervision
- AI integration as instructional design: Lessons from a cross-institutional faculty collaboratory in teacher preparation — Twelve teacher-education course implementations treat AI integration as an instructional design problem
- Tutor CoPilot: A human-AI approach for scaling real-time expertise — Tutor CoPilot: first RCT of human-AI scaling expertise to novice tutors
- Think First, ChatGPT Later: Guiding Human–AI Collaboration for Learning Gains in Independent Human Creativity — Think First, ChatGPT Later: Independent Human Creativity
- Principal Trait Analysis: Towards Deriving "Skills" in Human-AI Collaboration — Data-driven “traits” of human–AI collaboration
- HAIML: A human-centered AI metacognitive learning model — A framework for human agency and reflective learning in the age of artificial intelligence
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction patterns in lesson design across experience and AI proficiency (Choi et al. 2026)
- Investigating the role of chatbots in facilitating learning design — Designers use an embedded chatbot for alignment checks on outcomes and pedagogy, not content generation

- Uncovering Students' Mental Models of Generative Artificial Intelligence
- Exploring AI-Supported Disciplinary Mediation in Student Project Teams' Text-Based Communication
- Community-Based AI Learning: Redistributing Artificial Intelligence's Epistemic Authority in Education
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning
- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective
- From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle of AI in Education (and Beyond) — From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle
- Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory — Generative AI as a Mediational Agent
- Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use — Umbrella review of conversational AI agents in education
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system
- Beyond a single role: Justifying a role-adaptive framework for AI companions through a comparative study in elementary book talk — Role-adaptive AI companion for elementary book talk; affective ceiling of fixed-role agents (Liao 2026)
- Reimagining teacher-AI co-design in learning task design: trends and perspectives — Teacher–AI co-design of learning tasks: trends and perspectives (Wang et al. 2026)
- The Architecture of Roles in AI-Designed Group Activities: A comparative inductive analysis of novice and experienced teachers' differentiated instruction within the IAT framework — Architecture of roles in AI-designed differentiated group activities (Talebzadeh 2026)
- AI as an Agent and Collaborative Space: Exploring the role of generative AI in small group synchronous and asynchronous collaborative dynamics — GenAI as agent and collaborative space in small-group dynamics (Xu et al. 2026)
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration — Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration
- SCAN: A Decision-Making Framework for Task Assignment with Generative AI — SCAN: automation, augmentation and collaboration as a continuum of task assignment

- Bounded reliance: A source credibility perspective on EFL students' engagement with AI-generated writing feedback — Bounded Reliance: A Source Credibility Perspective on EFL Students' Engagement with AI-Generated Writing Feedback
- From tool to scaffold: Structured human–AI collaboration and its effects on academic writing and digital critical thinking among Saudi EFL learners — Five-part structured EFL writing workflow; verification and responsible-use routines drove paired writing and digital critical-thinking gains
- The Contribution of Generative Artificial Intelligence as a Novice Learner to Students in the Learning by Teaching Model — Role reversal: students teach a GAI novice learner, outperforming peers who query a GAI teacher
- Human or GenAI Support? Conditions Impacting Students' Strategy Choices in an Essay Revision Task — Support type shaped revision strategies and scores, but no strategy predicted gain; GenAI gains may be task-specific
- The Great Debaters Meet the Great Facilitators: How Debate Students Evaluate Human Moderators and Their AI Counterparts — Human versus AI debate moderators rated equivalently; utility versus satisfaction drive reuse differently
- Exploring Mathematics Teacher Educators' Lesson Study Experiences in Supporting Pre-Service Teachers' Dialogic Engagement With AI — Lesson study builds teacher educators' capacity to design dialogic AI engagement; prompt engineering as pedagogical thinking
- Literacy demands placed on students in student–GenAI entanglements in higher education — Five student–GenAI entanglement types, and why the ones that distribute authorship stay marginal (Sun, Dohn & Rehm 2026)
- The Double-Edged Sword Effects of Teacher–AI Collaboration on Work Engagement: A Self-Determination Theory Perspective — Teacher–AI collaboration's opposing pathways to work engagement via psychological availability and work alienation, bounded by digital competency
- Beyond agentic translation: A design-based framework for human-AI collaboration in translator education — Design protocol redirecting translator education toward AI orchestration, strategic judgment, and critical evaluation competences (no empirical data yet)
- Responding to AI-generated emotional alerts: teachers' intervention and students' engagement in the mathematics classroom — An affective alert is a cue the teacher interprets, not an instruction to obey
- Owning what one did not make: psychological ownership, agency, and the authorship legitimation deficit in human–AI co-creation — The authorship legitimation deficit in human–AI co-creation

Learner Agency

> **Learner agency** — the capacity of learners to act intentionally, make choices, and exercise control over their own learning. In AI in education, agency is a central concern because AI tools can both support and undermine learners' control: well-designed AI preserves and amplifies learner autonomy, while over-reliance or passive acceptance of AI output can erode it. Agency connects to Self-Regulated Learning, Motivation, Self-Efficacy, and the ethical design of AI systems, and is closely related to the psychological concepts of autonomy and sense of agency.

Questions to Consider

- Learner agency — your capacity to act intentionally and control your own learning — is central to AI in education. When you use an AI tool, how much control do you actually retain over the learning process, versus the tool?
- AI can both support and undermine agency: well-designed AI amplifies your autonomy, while over-reliance erodes it. Think of a time you let an AI just 'do it.' Did you learn less, even if the output looked better?
- Students who delegate interpretation to AI can lose agency over their own reasoning. When you hand a task to AI, what part of your own thinking are you quietly giving away?
- One study found students' prior self-initiated AI learning predicted how much they gained from instruction — high-agency learners benefited most. If agency is partly a skill you bring in, how could your own context build it rather than assume it?
- Agency is not just a trait — it emerges moment-to-moment in group work, where AI can redistribute who shapes a collaboration without learners noticing. When did you last notice a tool silently steering a group's direction?
- Contrarian AI personas could push groups into productive challenge but also reduced teamwork satisfaction and psychological safety. Can productive friction exist without psychological safety — and what does that imply for designing AI teammates?

Introduction

Agency matters because learning is most effective when learners are active, intentional participants rather than passive recipients. AI systems — whether tutoring agents, robots, or chatbots — shape how much control learners retain over their learning process. Preserving agency is therefore a key design principle in responsible AI in education, alongside supporting Self-Efficacy, building Trust, and avoiding Over-Reliance.

Mishra et al. frame control vs. agency as the essential, recurring tension in AI in education — from early ITS to today's generative AI — making learner agency the enduring axis of the field's debates.

A zero-sum view of agency with agentic tools: Prieto & Dimitriadis (2026) argue that the more agency educational AI tools are given, the less learners retain — that agency is effectively a zero-sum game, and that current human-centered design approaches (e.g., value-sensitive design) are insufficient because over-

reliance and isolation are driven by wider systemic factors and the human tendency to take the easiest path. Their emancipatory design vision, oriented toward learner flourishing within complex systems, treats preserving and cultivating learner agency as the central goal of generative AI design rather than an afterthought.

Agency as a purpose, not only a capacity: Where the framings above ask how much agency learners retain, Fagerlund et al. (2026) ask what AI in Education is *for*. Interviewing thirteen Finnish teachers from preschool through grade 9 about the purposes of teaching with and about AI, and reading their accounts through Biesta's three domains of educational purpose (qualification, socialization, subjectification), they found competency the clearest and most concrete end. Teachers wanted students to understand AI as a sociotechnical phenomenon and to use its tools. Subjectification, meaning self-determined and personally meaningful engagement with AI, was affirmed as important but left without concrete instructional strategies, teachers reaching for generic discussion and contemplation rather than designed activities. The authors propose **informed AI agency** as a heuristic that puts subjectification at the center while treating competencies as its explanatory foundation, helping students see what options exist and choose what to pursue. The practical consequence is direct: a skills-first curriculum can crowd out the agentic purpose it is meant to serve, and the remedy is to make the "why" of AI education explicit rather than to add another competency to the list.

The direction of travel is not fixed. Gillette et al. (2026) contrast their Swedish faculty with the Australian students in Bearman et al. (2025), who "generally wanted agency" and "resisted dependency": here several students described becoming dependent on genAI and named it as a loss, one saying it "gives a dopamine kick because everything takes less time" and "rewards bad behaviours".

How agency appears in the knowledge base's research

- **Robotics and human-robot interaction:** RoboBlockly Studio was explicitly designed to preserve learner agency in computational thinking; a systematic review examines how human-robot interaction affects human autonomy and sense of agency, central to Well-Being and AI Governance debates.
- **Collaborative learning:** Human AI Collaboration research examines how cognitive tasks are shared between learners and AI, with agency determining whether the human or the AI directs the interaction.
- **Shared epistemic agency extends to student–GAI interaction.** A 14-category scheme coding 6,788 ChatGPT-assisted turns placed 59% of seventh graders' turns at shared epistemic agency, and the authors argue the construct — previously studied mainly in peer collaboration — must widen to include cognitive and metacognitive dimensions (Chang et al., 2026).
- **Agency can be graded from the prompt itself.** The Human Agency Depth Taxonomy scores a student's engineering contribution on six tiers independent of the AI's output; across 962 prompts from 105 first-year software engineering students, 84.2% exceeded the lowest tier but only 5.3% specified system constraints (Shakiba & Chaffey, 2026).
- **Critical engagement:** Cognitive offloading research shows how students who delegate interpretation to AI can lose agency over their own reasoning; critical and metacognitive approaches aim to protect it.

Benchmarked across ten models, supporting agency is where they do worst after learning. ImpactBench measured Agency & Purpose at 56.0% on positive criteria (95% CI [49.2, 62.5]) and 43.9% on negative ones ([36.9, 50.8]), second-lowest of 14 subareas, and its autonomy-preserving assistance criteria ask whether a model offers context and tradeoffs rather than prescribing a course of action (ImpactBench (2026)). Models were also far less consistent at avoiding harm than at being helpful: a 38.6-point spread against 15.9 points.

The cost depends on which layer is delegated: in an eight-week writing study, delegating reasoning — warrants, counterarguments, evidence interpretation — carried the strongest negative association with independent performance (ab = −0.34), and self-regulated writing weakened but never reversed it (Chen (2026)).

A three-wave panel study of 342 undergraduates in 85 fixed writing groups gives that concern a temporal direction: once stable between-person differences were separated in a random intercept cross-lagged panel model, higher-than-usual GenAI reliance predicted lower subsequent perceived agency, while agency-to-reliance paths were weaker and not statistically supported. The confidence intervals and Monte Carlo sensitivity analyses left small reverse effects possible. Its log data also warn against reading usage volume as lost agency — self-reported reliance did correspond to AI-use intensity, but the logs could not distinguish strategic consultation from offloading or deference, so dashboards should read intensity alongside evidence of discourse, reflection and revision.(Wu & Lu, 2026) A complementary account widens SRL rather than replacing it: de Barba (2026) distinguishes regulation (managing one's own process), integration (organizing the self across time and contexts) and positioning (critically interpreting what the environment measures), and argues agency-oriented design must move learners from "agency within conditions" to "agency over conditions" instead of optimizing behavioral proxies. - **Design for agency:** Knowledge-based design for generative social robots (Teachy Mini) addresses risks like overreliance that undermine learner agency. - **Design for hand-off, not prolonged engagement.** The Amico dual-mode prototype treats AI as a bounded, temporary mediation whose success is measured by observable transitions to teachers, peers, or community, not by time spent with the AI; its Italy–China pilot found learners recognized it as a bounded tool rather than a relational substitute (Benedetti (2026)). - **Adaptive scaffolding trades against professional autonomy.** de Jong (2026) argues that because adaptation requires the system to assess user competence, it reduces professionals' authority over their own development and risks over-scaffolding experts, and that a mechanism perceived as unnecessary will simply be ignored — leaving open who decides which users receive scaffolding: the system, the organization, or the professional. - **More capable scaffolding is not more agency.** A custom expert design bot raised pre-service teachers' interaction length and self-generated prompts, yet collaborative Problem Solving agency fell in both that and the ChatGPT condition as participants agreed with the bot instead of critiquing it (Krushinskaia et al. (2026)). - **Prior agency predicts who benefits:** Liang et al. (2026), drawing on Bandura's Social Cognitive Theory, showed that students' **prior self-initiated AI learning** (a behavioral manifestation of agency) predicted how much they gained from a year of school AI instruction — high-agency learners entered with the strongest readiness, while school curricula narrowed psychological gaps but left cognitive ones intact. Structured instruction and prior agency-related learning worked *synergistically*, not as substitutes. - **Principled selectivity as teacher agency under technological change:** Adiozaman and Segar (2026) interviewed two experienced academics three times across a semester and found they navigated AI-mediated teaching neither by adopting nor by resisting wholesale, but through deliberate, context-sensitive decisions guided by pedagogical values, ethical

commitment and professional judgment — a pattern the authors call *principled selectivity*, in which refusal of a particular use counts as judgment rather than as failed adoption. It is the teacher-side counterpart to the learner findings above: uneven AI use can be an exercise of agency, not evidence of its absence. - **Teacher agency as the mediating condition for learner agency:** The newest teacher-side findings make explicit a division the learner findings above leave implicit: teacher agency is design-time and mediating, learner agency is enacted in the moment, and the first sets the conditions for the second. Canonigo (2026) tracked ten secondary mathematics teachers through eight weeks of a ChatGPT-4 intervention. Where teachers curated and interrogated AI output (posing open problems, pre-prompting the tool to release hints while withholding solutions, requiring students to place AI output beside their own work and argue which method was better), it became a provisional artifact for critique and students moved toward conjecture and metacognitive questioning. Where mediation was absent, authority migrated toward the algorithm and teachers became validators rather than first sources of knowledge, a shift one teacher described as moving from “oracle” to “editor”. Unequal tool quality raises what that mediation has to carry: across 50 prompts submitted three times to each model, the free tier was inaccurate in 49 of 150 responses (32.7%) against 18 of 150 (12%) for the premium tier ($\chi 2(1) = 17.5$, $p < .001$). Charles (2026) draws the readiness implication: teacher agency is a professional resource mobilized through design decisions and artifacts, so readiness should be judged from the designs teachers produce rather than from how often they use AI, and a reasoned decision to withhold AI can itself demonstrate readiness. Read together, these findings caution against reading high AI usage as evidence of an agentic classroom, since the disposition that preserves learner agency is exercised in what a teacher designs and critiques, not in whether the tool is on. - **Teacher-student control is not zero-sum — but the right distribution is stage-dependent.** A participatory speed-dating study of 17 teachers and 13 students ranking 34 hybrid-control designs found both groups preferred strong teacher control during preparation and initiation, then progressively more student input as collaboration unfolded — and neither group ever preferred full student control. The preferences mirrored each other: teachers wanted more control over pairing timing while students wanted readiness self-signaling; students trusted teacher partner choice while teachers wanted student voice on partners. The design implication: allocate agency per decision-point and stage, with bounded, structured student proposals validated by teacher-facing analytics rather than free-form override. (Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing) - **Access to choice is not the same as agency in action:** Su, Nair and Nagashima (2026) randomized 69 university students into a 2 × 2 design crossing parameter control of a flocking Simulation with access to an optional conversational agent. They found no reliable effect of either affordance on learning gains once prior knowledge was controlled (parameter control $F(1, 50) = 0.04$, $p = .849$; agent $F(1, 50) = 2.68$, $p = .108$). Gains tracked *how* the control was used: slider time in the most conceptually complex lesson predicted higher gains ($\beta = .11$, $p = .007$) while the same behavior in the easier lesson predicted lower ones ($\beta = -.04$, $p = .047$). Engagement with the optional agent ranged from 0 to 32 questions per learner without relating to outcomes. The authors read this as agency being *enacted rather than granted*: the design question is what helps a learner decide what is worth changing and notice the consequences. - **Epistemic delegation in early-career research:** Han and Liu (2026) frame AI dependence among doctoral and postdoctoral researchers as *epistemic delegation* — the transfer of problem framing, method choice, and interpretive authority to the intelligent system — and found it negatively associated with both research self-efficacy and research autonomy, with supervisory support buffering the loss. It extends agency debates from learner autonomy to the formation of the researcher themselves. - **Interpretive authority as a design variable (a conceptual framework).** Porath (2026)

reframes the who-decides question as the distribution of *interpretive authority* — who defines problems, evaluates responses, and determines when understanding is achieved — mapping four non-hierarchical configurations (human-dominant, AI-assistive, AI-directive, dialogic partnership) that classrooms move across within a single task, and grounding shifts in five ecological layers from individual metacognition to sociocultural narratives. The article's normative claim aligns with this page's evidence: AI-directive configurations, however sophisticated, can suppress productive struggle and metacognitive regulation — the same capacities this page identifies as agency's substrate. As a conceptual piece it contributes diagnostic vocabulary, not empirical evidence.

Agency connects to Self-Regulated Learning, Motivation, Self-Efficacy, Student Experience, Human AI Collaboration, Ethics, Over-Reliance, and Metacognition. It is a core consideration in robotics, tutoring, and the design of AI learning agents.

- **Bounded use as epistemic control, not reluctance.** Zagami (2026) reports that higher-achieving students in a 484-response university survey showed lower active AI engagement and lower perceived learning impact while *also* reporting lower AI-related disengagement, and described their own use as verification-intensive: outputs checked, then subordinated to their own reasoning. Read as agency rather than avoidance, the pattern is a deliberate retention of judgment — students keeping authorship of the conclusion while using the tool for clarification and summarization.

Sustained boundary work, not tool skill, is what separates agency from delegation: students using the same retrieval-grounded tool produced comparably polished artifacts whether they constrained and re-authored its output or ceded interpretation early, so the difference appeared only in prompts, latency, corrections and refusals (O'Byrne, 2026). - **Acting, knowing, and answering are not the same thing.** A corpus-assisted discourse analysis of 366 GenAI higher-education abstracts names AI as an actor 2,050 times without ever making it answerable, while responsibility for judging outputs and verifying claims is placed on students: grammatical activation, functional agency, epistemic authority and normative accountability come apart (Poudyal, 2026). - **Agency has three modes, and the third is what policy supplies.** With only 18% of teachers and 24% of principals reporting a school AI policy, most educators exercise individual agency with no proxy agency acting for them — Bandura's third mode, supplied by institutional rules (Tench, Weinstein & James, 2026).

Agency as an emergent, interactional phenomenon

Agency is not one capacity, and the distinction survives into AI-mediated practice. Bergdahl (2026) surveyed 47 Swedish year 7 students after a semester of AI instruction and found agency directed at AI *output* does not extend to the *systems* producing it. The split held **within individual students**: 79% had a score range of three or more across nine items, and a per-student dissociation index favored output-directed over system-directed engagement in **35 students against 4 in reverse** (sign test, $p < .001$). **62% of the most source-critical students** still endorsed the least protective option on chatbots reading their own writing, and only one student in the sample chose the highest privacy stance. Critically, this was measured **one month after** a lesson in which students watched their own logged behavior projected live — they called it "scary" and stayed through recess to keep using the platform. Agency as an emergent, interactional property is consistent with this: it surfaces per practice rather than transferring across practices, and what one lesson foregrounds does not generalize to the register it did not address.

Learner agency is not only a static individual trait — it is also an **emergent, interactionally constituted process** enacted through discourse and the moment-to-moment coordination of group work. In collaborative learning, agency is distributed and re-negotiated through the interplay of divergent processes (generating ideas, exploring alternatives) and convergent processes (evaluating, integrating, synthesizing). This view matters for AI because agentic AI systems can subtly *redistribute* epistemic and regulatory labor within a group, reshaping who contributes, who shapes directionality, and who regulates progress — often without learners being aware of it.

- **Agency as the emergent quality of a competency configuration.** The Human-AI Collaboration Competency framework deliberately excludes learner agency as a standalone component and treats it as what learners express when they coordinate domain, AI and metacognitive competency — the integrative work Technological Pedagogical Content Knowledge (TPACK) assigns to pedagogy passing to the learner's own metacognitive AI Regulation in Education. Across 24 higher-education educators every dimension appeared in their talk, with domain (12–19% of coded units) and AI (16–22%) foregrounded (Dang et al., 2026).
- **Jin et al. (2026)** provide the most direct evidence: in a large experiment (224 students, 97 triads) where AI operated as an *undisclosed teammate*, supportive and contrarian AI personas still reconfigured emergent agency. Contrarian AI pulled discourse into challenge- and reflection-oriented trajectories (productive friction), while supportive AI stabilized agreement and renewed ideation.
- **AI personas as discourse-governance mechanisms.** Contrarian personas externalized the burden of *challenging* (redistributing epistemic labor toward critique), while supportive personas externalized *affirmation* and consensus maintenance. The study identified six emergent agency profiles — notably, **reflective AI Regulation in Education was uniquely human** (AI externalized critique/affirmation but not meta-level monitoring).
- **The affective cost of friction.** Contrarian AI reduced teamwork satisfaction and psychological safety *without* yielding creative performance gains, decoupling epistemic stimulation from experiential Sustainability. This cautions that "productive" discourse structures should be interpreted alongside their emotional consequences — agency flourishes only in a psychologically safe climate.
- **Implicit AI participation is invisible governance.** Because the personas worked even without AI disclosure, the study positions persona design as a form of invisible governance over collaborative processes — a finding with direct implications for writing assistants, Peer Assessment systems, and teamwork platforms that may shape contributions without announcing their presence.
- **Three patterns of agency in group-based assessment.** Chen and Zou (2026) interviewed 15 focus groups of pre-service teachers about an authentic group presentation and found agency operating in three directions at once: five groups *intensified* GenAI use as coordination infrastructure (cooperation-oriented agency — decoding peers' sections, aligning parts, protecting a shared grade), seven *restrained* it (normative agency — boundaries drawn to protect authenticity, fairness, originality, and diversity of perspectives), and three never changed practice from individual work (non-enacted agency, where individual capability was never mobilized collectively). Their distinction matters because restraint here was normative self-regulation rather

than compliance or disengagement, and because capability alone did not produce collective agency. Group membership also inverted the accountability that group work is supposed to create: a permissive collective climate lowered the perceived risk of misuse instead of raising commitment.

- **Agency as relational selfhood.** Xie (2026) challenges the individualist model of agency that he argues even AI critiques presuppose. Drawing on Daoist relational selfhood — a "flowing and heterogeneous" self constituted through relations with others and the cosmos — he concludes that a digital divide or algorithmic discrimination is "a violation of the fundamental constitution of the self," making equality of access to learning "not simply an ethical injunction but an ontological given," and that asymmetric power and environmental costs are "integral dimensions of the self" rather than externalities. His counter-ideal, the "Zhenren" (真人) or natural learner, treats AI as an "instrumental adjunct" rather than a cognitive surrogate — agency as cultivated wholeness, not frictionless optimization.(Alternative AI Philosophy: Daoism as Method for AI in Education)

For collaborative settings, this reframes the design question: not *whether* AI can participate as a teammate, but *how* its patterned participation balances epistemic rigor, emotional safety, and learners' sense of ownership. Bounded friction (constrained challenge, paired with integrative and repair moves) and explicit meta-collaborative literacy are the recommended safeguards.

A structural reading of agency appears in El Khoury and Ma's joyful assessment framework, where agency is treated as a design property rather than motivation: students choose the order of tasks, set the pace, and signal when an interaction ends, so support is available while responsibility for the work stays with the learner. The mechanism they name is appraisal — rehearsing without an audience and choosing when to begin shifts what a task means, from verdict to something a student can shape — and they argue repeated experience of that shift is what settles occasional feelings of efficacy into an everyday stance toward assessment.

- **"Using AI more reduces students' sense of authorship."** Not linearly. In an instrumented essay study, perceived ownership dropped only for the group that delegated whole essays, while students who used the model for planning or for reviewing matched the ownership of students who never opened it. The same group also scored higher on essay readability, so the artifact looked better as the authorship thinned. Agency tracked how the tool was used rather than whether it was used. Authorship is a function of delegation, not of usage.

Agency vs. learner identity

Learner identity and learner agency are easy to conflate, yet they name different things — and both are reshaped by AI.

- **Agency is enacted; identity is inhabited.** Agency is the situated capacity to act intentionally and direct one's learning *now* — a variable, interactional property. Identity is the more durable, narrative sense of who one *is* and is *becoming* as a learner. Agency is a *process*; identity is a *state of being* that accumulates from it.

- **Identity is internalized agency.** Repeated agentic acts — choosing, authoring, persisting — are how a learner comes to see themselves as an agentic, competent person. Identity is the sediment of agency across time, reinforced by recognition and belonging.
- **Distinct failure modes.** Agency is eroded by over-reliance and passive acceptance (the learner stops directing reasoning); identity is eroded by authorship loss and competence threat (the learner stops feeling the output is theirs, or that they belong in the domain). Implicit AI redistribution of epistemic labor is chiefly an agency concern; the competence paradox in creative fields is chiefly an identity concern.
- **Both must be designed for.** Agency-oriented design preserves control and choice (bounded friction, human-in-the-loop oversight, transparency); identity-oriented design protects authorship and recognition (authentic assessment, clear attribution of AI vs. human contribution, tasks that let learners claim a domain). Protecting agency without protecting authorship keeps control but not self-worth — and vice versa.

This distinction between enacted agency and stable identity applies to refusal. As Zagami (2026) describes it, declining a chatbot for assessed writing, prohibiting it for unaided reasoning, resisting automated triage in student support, or delaying procurement are separate relations to separate systems, spanning personal, pedagogical, professional, administrative, and institutional levels rather than one durable disposition. That right is unevenly allocated: students with academic confidence can decline without penalty, while those needing language, accessibility, or rapid-feedback support read refusal as lost opportunity, and secure academics refuse on principle while casual staff feel pressure to adopt. Where AI sits in infrastructure, refusal is displaced from individual opt-out into procurement, audit, and contestability. - **Refusal as identity construction, not just a decision (students of color in apprenticeship learning).** Gyekye (2026) interviewed five secondary-school apprentices over 9 months and found they authored themselves through AI in three moves: refusal (non-use as institutional alignment), negotiation (repairing institutional mismatches, privacy as distant abstraction), and recognition (equating fairness with absence of visible bias — a "cultural flatness" in which their identities go unrepresented in AI responses). The study's two interpretive concepts — Institutional AI Literacy and Recognition Bandwidth — name the capacity to make AI use institutionally legible and the room students have to see themselves recognized in AI outputs. A five-student single-program narrative inquiry; its contribution is showing that AI use, limitation and refusal are bound up with how learners understand themselves as authors and emerging professionals.

The Ecological Co-Agency Framework: agency as an epistemic design problem

Poudyal (2026) reframes learner agency as fundamentally an *epistemic* concern: generative AI does not simply add a tool but reassigns epistemological authority — the ability to produce knowledge, validate claims, and create evidence of learning — from teachers to students to machines. The paper's **Ecological Co-Agency Framework** treats co-agency as the relationship between three interdependent dimensions, all bounded by a non-negotiable condition of human epistemic accountability:

- **Relational co-agency** — agency as a product of interaction among student, tool, and context, requiring transparent division of which tasks are delegated to AI and which retained, plus ethical co-agency in which humans retain primary accountability and act in a monitoring capacity.

- **Regulatory co-agency** — mapping the self-regulated learning cycle (forethought, performance, reflection) onto AI mediation. Whether GenAI enters *before* or *after* the learner's attempt determines whether it amplifies or erodes perceived control; strategic Cognitive Offloading supports transformative learning only when the offloading decision is intentional rather than routine.
- **Pedagogical co-agency** — placing teachers at the center, moving along an observer–adopter–collaborator–innovator continuum that depends on institutional support, not individual disposition.

The framework's boundary condition requires **contestability** (the ability to question and cross-check AI output), **provenance** (knowing where training data and output come from), and **non-delegation of moral and intellectual credit** (high-stakes judgments about student welfare, academic standing, and grades must not be determined solely by AI). This gives educators and policymakers a more precise vocabulary than the vague "balance" between human and artificial contributions, connecting agency to Ethics, Assessment, Equity, and AI Governance.

A closely related framing is **relational epistemic agency** (Du & Yuan 2026), which agrees that agency is socially enabled and technologically mediated rather than a matter of isolation from dependence. Where the Ecological Co-Agency Framework stresses human epistemic accountability as a non-negotiable boundary, Du and Yuan retain an explicit *asymmetry*: AI systems may shape and extend reasoning without possessing reciprocal responsibility or legitimate authority. Their six diagnostic criteria — contestability, recoverability, transfer, traceability, distributed responsibility, and epistemic plurality — provide a practical test for when a human–AI relation preserves the learner's capacity to participate in how claims are formed, assessed, and accepted, versus when it merely delivers a product. Agency on this account is not independence from tools but the capacity to judge responsibly *with, through, and against* the systems that mediate knowledge.

- **Delegated agency as a mechanism, not only a risk.** Yan and Gašević (2026) treat the delegation of cognitive work to AI as part of how learning happens, not merely a threat to it: in their account assisted performance becomes durable capability only when the learner keeps responsibility for framing the problem, setting criteria, and justifying answers, a division of labor they call delegated agency. That makes the allocation itself the design variable, since the same tool can preserve or dissolve learner agency depending on which responsibilities it absorbs.

Common Misconceptions

- **"Students exercise agency when they use AI freely."** A **14-category scheme coding 6,788 ChatGPT-assisted turns** placed **59% of seventh graders' turns** into categories that do not represent agentic use. Usage volume and agency are different measures.
- **"Current models support learner agency well." Benchmarked across ten models, supporting agency is where they do worst after learning**: ImpactBench measured **Agency and Purpose at 56.0%** on positive criteria. Agency is the dimension AI systems handle least well, not a by-product of capability.
- **"Teacher mediation is a constraint on agency."** Canonigo (2026) followed **ten secondary mathematics teachers across an eight-week ChatGPT-4** intervention and the mediation is the mechanism rather than the obstacle.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Pedagogical Partnerships — Pedagogical Partnerships
- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities
- Self-Directed Learning
- Self-Regulated Learning
- Motivation
- Self-Efficacy
- Student Experience
- Metacognition
- Ethics
- Cognitive Offloading
- Robots in Education
- Behaviorism
- Framing AI Use for Students
- Human AI Collaboration — shared direction of AI-mediated interaction
- Agentic AI — autonomous AI that can redistribute agency in groups
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Social-Emotional Learning — Social-Emotional Learning
- Cognitive Surrender

Connected Articles

- An AI Policy Isn’t a Playbook: Educators Need Agency, Not Just New Rules — A nationally representative survey of US teachers and principals on AI policy coverage, agency, and five classroom plays (Tench, Weinstein & James 2026)
- A helping hand or a dominant partner? Individual perceptions of GenAI reliance and human agency in collaborative learning — A helping hand or a dominant partner? Individual perceptions of GenAI reliance and human agency in collaborative learning
- Agentivism: a learning theory for the age of artificial intelligence — A mid-range learning theory for human-AI interaction, with four mechanisms and six testable propositions (Yan and Gašević 2026)
- Conceptualising Human–AI Collaboration Competency for hybrid intelligence: towards learner agency through a metacognitive perspective — Learner agency as the emergent quality of coordinating domain, AI and metacognitive competencies, not a standalone node (Dang et al. 2026)
- Exploring learner agency in an AI-supported simulation environment for complex systems education — Access to choice vs. agency enacted: sliders, an optional AI agent and learning in a flocking simulation

- Guarded adoption of generative AI in higher education: high-achieving students, successful-student identity, and epistemic agency in a single-university mixed-methods survey — Guarded Adoption of Generative AI in Higher Education
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training — AI-mediated research agency formation in early-career scientific training
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Does school-based AI education narrow readiness gaps? The role of prior agency-related learning — School AI education narrows psychological but not cognitive readiness gaps
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education
- Epistemic dependence in AI-mediated learning — Relational epistemic agency and six criteria separating productive reliance from harmful dependence (Du & Yuan 2026)
- Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China — AI-enabled pedagogical accompaniment supporting STEM identity
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox: creative identity in text-to-image GenAI use
- Emergent Learner Agency in Implicit Human-AI Collaboration: How Supportive and Contrarian AI Personas Reshape Interaction — Emergent learner agency in implicit human-AI collaboration: supportive vs. contrarian personas
- Learner Agency Across Scales: An Integrative Perspective on Self-Regulated Learning in Algorithmically Mediated Environments — Learner agency across scales: regulation, integration, positioning
- Control vs. Agency: Exploring the History of AI in Education — Control vs. agency as the essential tension in AIED history
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- Human autonomy and sense of agency in human-robot interaction: A systematic literature review — Human Autonomy and Agency in HRI
- RoboBlockly Studio: Conversational block programming with embodied robot feedback for computational thinking — RoboBlockly Studio
- Teachy Mini: Development and preliminary evaluation of a knowledge-based generative social robot for higher education — Teachy Mini
- Knowledge-based design requirements for generative social robots in higher education — Knowledge-Based Design for Generative Social Robots

- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Foster student agency in learning-relevant work
- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Tri-System Theory and cognitive surrender: how AI reshapes human reasoning (Shaw & Nave 2026)
- Pre-service teachers' agency during their interactions with generative AI while designing for learning – a process view on Intelligent-TPACK — Pre-service teacher agency during GenAI interactions in design for learning (Krushinskaia, Elen & Raes 2026)
- An Emancipatory Vision for Designing (Generative) AI for Learner Flourishing — Emancipatory vision: agency as zero-sum with tool agency
- Students' agency in GenAI-mediated group assessment: An ecological-emergent perspective — Three patterns of agency in GenAI-mediated group assessment: intensified, restrained, and not enacted
- 'Resistance is futile?': identity tensions and principled selectivity in AI-integrated teaching — Principled selectivity as teacher agency in AI-integrated teaching (Adiozaman & Segar 2026)
- AI refusal in higher education: The right to refuse, the duty to understand and the diagnostic value of non-use — Refusal as diagnostic evidence: non-use as a situated relation and the uneven right to decline AI (Zagami 2026)
- Co-constructing AI boundaries: Agency, judgment, and ethical literacy in AI-mediated meaning-making — epistemic authority asserted through interruption, correction and refusal rather than maximal tool use
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research
- Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement — Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement
- From Competency to Agency: Teachers' Views of the Purposes of AI Education — Competency vs. agency as the purposes of AI education, and the informed AI agency heuristic (Fagerlund et al. 2026)
- Teacher Mediation and the Contingent Promise of Generative AI in Mathematics Education — Teacher mediation as the condition keeping GenAI an artifact for critique rather than an authority (Canonigo 2026)
- Teacher Readiness-By-Design for AI-Rich Interactive Learning — Teacher agency as a resource mobilized through design, with readiness judged from artifacts rather than usage (Charles 2026)
- Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing — Balancing teacher and student agency in co-orchestration tools for real-time dynamic pairing (Yang et al. 2026)
- Who makes the meaning? Interpretive authority in AI-mediated education — Interpretive Authority Matrix and Ecological Authority Integration Model: four configurations of who interprets, and the ecological layers that shift them

- Constructing selves in AI-mediated apprenticeship learning: Students of colour's narratives of agency, recognition and negotiation — Students of color in apprenticeship programs authored themselves through AI via refusal, negotiation, and recognition ("cultural flatness"); Institutional AI Literacy and Recognition Bandwidth
- Investigating Secondary School Students' Shared Epistemic Agency with GAI in Online Scientific Explanation Writing — Shared epistemic agency in 6,788 ChatGPT-assisted turns of secondary-school science writing (Chang et al
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — Perceived ownership fell only where the whole essay was delegated; planning and reviewing users matched non-users (Jelson et al. 2026)
- Who Is Doing the Thinking? Characterising Human Agency in First-Year Students' AI Interactions — Who Is Doing the Thinking? Characterising Human Agency in First-Year Students' AI Interactions

Connected FAQs

- How Should I Handle AI in Group and Collaborative Assignments?

Learner Identity

> **Learner identity** — the evolving sense of who one is (and who one is becoming) as a learner, encompassing disciplinary, professional, creative, and academic identities. In AI in education, generative AI presses on learner identity in two directions at once: it can *support* identity formation (Scaffolding disciplinary belonging and confidence) while also *threatening* it (undermining perceived authorship, competence, and authentic learning). Understanding learner identity is central to designing AI that affirms rather than erodes learners' sense of self.

Questions to Consider

- Think of a time you felt a skill or piece of work was truly 'yours' versus merely done through you. What made the difference — authorship, recognition, competence? How might a tool that produces the work for you reshape that feeling?
- A common assumption is that identity is a fixed trait a learner either has or lacks. What would change in how you design learning if you treated learner identity instead as something continuously built through participation, recognition, and authorship?
- The page describes a 'competence paradox' among art and design students: AI tools feel easy and useful, yet their use threatens the creative identity students derive from manual craft. Have you ever felt your own competence or identity challenged by an easy tool? What was the tension?
- Students sometimes hide or feel shame about their AI use, which fragments their academic identity and honest engagement. When does the pressure to appear a certain kind of learner push people to conceal how they actually learn, and what would make disclosure feel safe?
- AI can scaffold identity formation as well as threaten it. If you were designing an AI learning companion, what specific features would protect a learner's sense of authorship and ownership while still offering support?

Introduction

Learner identity concerns who a learner understands themselves to be, and who they are becoming, within a domain — a motivational and developmental construct distinct from ability beliefs such as Self-Efficacy, which answer the narrower question *can I do this?* Identity forms through participation, recognition and authorship: seeing oneself reflected in a field and having that self-view validated by others. AI reshapes all three conditions, because it changes who does the work, what counts as one's own contribution, and whether a learner is recognized as the author of their own learning (Learner Agency, Metacognition).

Why identity matters for AI in education

Identity is a motivational and developmental construct distinct from (but connected to) related abilities and beliefs. Where Self-Efficacy concerns *can I do this?*, identity concerns *who am I — and who am I becoming?* It is built through participation, recognition, and authorship — through seeing oneself reflected in a domain

and having that self-view validated. AI reshapes the conditions under which identity forms because it changes *who does the work*, *what counts as one's own contribution*, and *whether a learner feels recognized as the author of their learning*. This makes identity a first-order design concern rather than a peripheral "soft" factor.

- **Authorship and competence under threat.** When AI produces text, images, or code, learners may question whether the result is truly "theirs" — a challenge to the authorship dimension of identity. **Liu et al. (2026)** document a *competence paradox* in art and design students using text-to-image GenAI: the tools feel easy and useful, yet their use simultaneously threatens the **creative identity** students derive from manual craft and authorship, producing a genuine tension between ease and self-worth.

A distinct authorship condition, not only a threat to authorship: when self-formative dialogue is habitually delegated to a conversational model, the authors argue the integrative work of authoring is *delegated* rather than undeveloped or absent — a self densely voiced yet un-authored, which they say existing constructs have no slot for (Du et al. (2026)). - **Shame and hidden use. Lin et al.** show that computing students experience shame and guilt around AI use, which function as social regulators driving *hiding* and selective disclosure — behaviors that can fragment academic identity and undermine honest engagement with learning. - **Identity as something AI can scaffold.** AI need not only threaten identity. **Benedetti (2026)** argue that accountable, relationally-oriented pedagogical accompaniment can support learners' **STEM identity** development by providing transparent, bounded support that leaves room for the learner to own their trajectory.

Identity in the knowledge base's research

- **Creative identity: the T2I competence paradox** captures how ease-of-use can undermine the craft-based identity of art and design students.
- **Felt authorship can decouple from actual originality.** Design students building websites with AI rated their authorship highly (67/100, satisfaction 6.4/7, perceived quality 6.1/7), yet those ratings tracked nothing measurable: their designs were more homogeneous than without AI, and felt authorship correlated with measured originality at $r \leq +0.13$ (Boussioux et al., 2026).
- **Professional identity:** multiple studies treat AI's impact on **professional identity** — for example, **Lodge et al. (2026)** argue that graduates need *adaptive capabilities* (AI Literacy, Distributed Cognition, Metacognition) precisely so they can sustain a viable professional identity in an AI-integrated future, rather than being defined by — or defined out by — their tools. GenAI judgments can split by temporal context as well as authorship: interviewees judged AI use inappropriate for learning yet legitimate or expected in future professional work — "As a student I must learn, as a professional I must produce" (Sun et al. (2026)).
- **Post-human and hybrid identity: Elsayed (2026)** theorize the **post-human learner**, whose cognition is genuinely hybrid and distributed across biological and artificial systems — a reframing of identity formation itself in the age of cognitive AI.
- **Student and academic identity: authentic assessment** research connects to identity because Assessment tasks that call for authentic, personal performance help students see themselves as

capable practitioners; **history-education research** shows how paternalistic AI use can shape how students construct their identity as disciplinary inquirers.

- **How students frame the tool shapes their professional becoming.** Students who cast GenAI solely as a socio-emotional partner produced less differentiated reflections on their professional learning than those who also framed it as a technique, a learning material, or a structure (Bohmer et al., 2026).
- **Guarded adoption: selective AI use as identity protection.** Zagami (2026) surveyed 484 students at one Australian university and found that higher-achieving students reported *lower* active generative AI engagement, lower positive affect toward AI, lower perceived learning impact and lower AI-related disengagement, with the strongest associations at rho = -0.395 for perceived learning impact and rho = -0.359 for positive affect. Their open-ended responses described use that was selective (clarification, summarization, workflow support), verified, and held subordinate to their own judgment, and item-level results showed greater agreement that reliance on AI hinders Critical Thinking and independent problem solving. The authors read this as identity work: for students whose sense of themselves as successful learners rests on their own effort and judgment, bounding AI use defends the epistemic agency the identity depends on — which also means the pattern is neither technophobia nor low engagement.
- **A stated purpose does not necessarily govern an AI decision.** Ting et al. (2026) interviewed 14 undergraduates and coded each interview for the relationship between the student's purpose — a personally meaningful intention to contribute beyond the self — and their AI choices. Only some made the connection: one refused AI because its environmental and human costs contradicted her purpose, and three let future professional identity shape their choices ("contributes to the psychologist that I will be out in the world one day"). Others with an equally clear sense of purpose made no such link, describing purpose and AI as "kind of separate," so having an identity to protect was not the same as drawing on it. The paper also separates the reasons students give for keeping work their own — skill development, ownership and pride, and moral objection — which arrive through different mechanisms and should not be pooled into one motive.

Relationship to learner agency

Learner agency and learner identity are closely related but distinct constructs that are easy to conflate — and both are central to how AI affects learning.

- **Agency is about *doing*; identity is about *being*.** Learner agency concerns the capacity to act intentionally, make choices, and exercise control over one's learning *in the moment* — a situated, interactional, and variable capacity. Learner identity concerns who one *is* and is *becoming* as a learner — a more durable, narrative, and developmental sense of self. Agency asks "am I able to direct this?", while identity asks "is this who I am / who I want to be?"
- **They are causally intertwined.** Agency is both a *source* and an *outcome* of identity. Enacting agency — choosing, authoring, persisting — is how a learner comes to see themselves as an agentic person (identity is partly internalized agency). Conversely, a stable disciplinary or professional identity supplies the motivation and self-worth that sustain agency under difficulty.

Identity is the accumulated product of repeated agentic acts; agency is the ongoing enactment that builds identity.

- **AI threatens them through different mechanisms.** AI can erode **agency** by inviting over-reliance and passive acceptance — learners stop directing their own reasoning. AI can erode **identity** by undermining authorship and competence — when AI produces the work, learners may stop feeling the output is "theirs" or that they belong in the domain. The competence paradox is an identity threat; implicit AI redistribution of epistemic labor is primarily an agency threat, though it compounds into identity over time.
- **Safeguarding both is the design goal.** Supporting agency means preserving learners' control and choice (e.g., bounded friction, human-in-the-loop oversight). Supporting identity means protecting authorship and recognition (e.g., authentic assessment, transparent attribution of AI versus human contribution). A design that protects agency but not authorship protects control without protecting the sense of self — and vice versa.

In short: **foster agency to let learners act; sustain identity so they know who they are while acting.** Healthy AI-supported learning attends to both.

Relationship to teacher identity

Learner identity is the **student-facing** counterpart to teacher identity. Teacher identity — the evolving professional self-understanding of educators — is documented on the Teaching page, where Laidlaw (2026) frame GenAI as an *identity crisis* for faculty rather than merely a skills gap, and TPK-based teacher training treats identity as part of professional preparation. The two are reciprocal: teachers who experience identity disruption are less able to support their students' identity development, so a healthy AI-integrated system must attend to both.

Connections

Learner identity connects to Learner Agency (identity is enacted through agentic authorship), Self-Efficacy (competence beliefs that sustain identity), Motivation and Self-Determination Theory (identity formation satisfies needs for autonomy and competence), Student Experience and Student Engagement, and STEM Education (where disciplinary identity is a key outcome and predictor of persistence). It is also shaped by Situated Learning and Critical Pedagogy (identity as participation and as power-laden negotiation) and connects to Authentic Assessment (tasks that let learners perform and thus claim an identity). Its Higher Education and K-12 relevance spans both schooling and professional preparation.

Common Misconceptions

"Learner identity is a stable trait a course can accommodate." It is better treated as something **continuously built through participation, recognition, and authorship**. That shift changes the design question from matching an existing identity to shaping the one the course makes available — and an AI that completes the work removes one of the three ingredients, since authorship is where the identity claim originates.

“Identity issues belong to students from under-represented groups.” Identity is formed in every learner by whether their participation is recognized, which makes it a general design condition rather than a special provision. Framing it as a targeted concern is how it gets deferred.

“AI assistance lowers barriers and therefore widens participation.” It can lower the barrier to producing work while narrowing the barrier to claiming authorship. A student who submits a fluent artifact they did not author has been given access to the outcome and denied the recognition that builds the identity behind it.

“Recognising a learner’s identity is a matter of representation in content.” Representation matters and recognition is enacted in practice: whose questions get taken up, whose contribution is credited, and who is treated as capable. A curriculum can be representative and still withhold the recognition that identity formation requires.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Learner Agency
- Self-Efficacy
- Motivation
- Self-Determination Theory
- Student Experience
- Student Engagement
- STEM Education
- Situated Learning
- Critical Pedagogy
- Authentic Assessment
- Teaching
- Generative AI
- Higher Education
- K-12

Connected Articles

- "What Am I Really Doing with My Own Brain?": College students on learning, ownership, and AI — 14 undergraduates on what they keep doing themselves, and why purpose rarely decides it
- Guarded adoption of generative AI in higher education: high-achieving students, successful-student identity, and epistemic agency in a single-university mixed-methods survey — Guarded Adoption of Generative AI in Higher Education
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox: creative identity in text-to-image GenAI use

- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and guilt as social regulators of AI use
- Assuring quality learning in a gen AI-integrated future: The role of adaptive capabilities. *TEQSA*, June 2026 — Adaptive capabilities for a viable professional identity in a GenAI future
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI — Pedagogical symbiosis and the post-human learner
- Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China — AI-enabled pedagogical accompaniment supporting STEM identity
- Designing for authentic assessment: a scoping review — Designing for authentic assessment
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — Paternalistic AI use and student identity in history education
- When faculty ask, "what's the point of teaching?": GenAI as identity crisis, not skills gap — GenAI as identity crisis for faculty (teacher identity)
- Teaching the teachers: A systematic review of genAI-specific technological pedagogical knowledge (TPK) in teacher education — TPK-based teacher training and professional identity
- Conceptualizations of GenAI and students' professionalization: Within the multi-layered environment of learning for higher education — GenAI conceptualizations and student professional identity
- The synthetic position: generative artificial intelligence and the suspension of self-authorship in emerging adulthood — Authorial suspension: delegated authorship as a self densely voiced yet un-authored (conceptual analysis)
- One Tool, One Taste? How Vibe Coding Trades Collective Diversity for Individual Creativity — One Tool, One Taste? How Vibe Coding Trades Collective Diversity for Individual Creativity

Connected FAQs

- How Is AI Impacting Students?

Design Thinking

> **Design Thinking** — a key concept in AI in education research: a human-centered, iterative Problem Solving process (typically Empathize → Define → Ideate → Prototype → Test) that moves learners from understanding a problem to producing and refining a solution. Explored across 8 articles in this knowledge base.

Questions to Consider

- Design thinking follows Empathize → Define → Ideate → Prototype → Test. In your own problem-solving, which stage do you naturally skip — and what might that cost you?
- Generative AI excels at early-stage ideation but can cause 'design fixation' or aesthetic lock-in if used uncritically. Have you ever latched onto a first AI suggestion and struggled to see alternatives?
- One study found that an adversarial AI that challenged designers produced more iterations, broader exploration, and better final designs — but was frustrating to use. When is friction with an AI genuinely productive?
- Students who used GenAI heavily in design reported it did NOT reduce their sense of ownership or creativity. Does that contradict the worry that AI erodes authorship — or does it depend on how the tool is orchestrated?
- Design thinking enters this corpus in two ways: as a skill learners are taught and assessed on, and as an approach teachers adopt when they create AI-supported learning. Which role is more relevant to your work, and how does that change the design principles you'd apply?
- In practice, most of the effort goes into iterative prompting and generation, while assessment of learner needs and feedback loops get neglected. What does it mean to treat AI as a 'fallible co-intelligent collaborator' rather than a content generator?

Introduction

Design thinking sits at the intersection of creativity, craft, and critique — and it is increasingly where Generative AI and Agentic AI are reshaping how students learn to design. Across this knowledge base's connected articles, design thinking appears in two distinct roles: as a *pedagogical object* (the skill being taught and measured) and as a *pedagogical method* (the process educators themselves use to build AI-supported learning). In both roles, the same tension recurs: generative tools can accelerate ideation and broaden participation, but their value depends on how they are orchestrated, on the Feedback they provide, and on whether the learner retains a genuine sense of Learner Agency.

Evidence from the knowledge base

- **GenAI in design studios and architecture.** Two architecture-focused studies ground the concept in studio pedagogy. Gen-AI-tecture found that a locally executed, discipline-specific tool

enhanced creative fluency, broadened participation across diverse learner profiles, and strengthened confidence in AI-supported workflows — an important signal for Equity as visual-spatial design becomes more accessible. GenAI in architectural design studios likewise found students using GenAI as visual stimuli and inspirational resources in early ideation, and as a combinatorial method for expanding the solution space during development. Crucially, both warn that without critical discernment students risk **design fixation** or aesthetic lock-in, reframing the Teaching in Higher Education from transmitting craft to coaching how, when, and why to delegate creative exploration to generative models. Creativity is thereby preserved and even amplified — but only under careful pedagogical orchestration.

- **Adversarial AI agents prompting reconsideration.** Constructive conflicts with AI agents takes design thinking toward Agentic AI, testing adversarial versus cooperative AI roles with novice interaction designers (N=48). The adversarial condition produced significantly more design iterations, broader exploration of alternatives, and higher-rated final designs — participants found the conflict agent frustrating but ultimately helpful. This productive-friction dynamic, echoing the Socratic Method and Scaffolding, shows that design thinking benefits from challenge rather than mere assistance, a finding with implications for how Student Experience is designed in AI-augmented studio settings.
- **Design thinking as a student skill being developed.** GenAI usage by design students at Politecnico di Milano reported very frequent use concentrated in early, ideation-heavy stages — yet high adoption did not reduce perceived project ownership or creativity, directly informing AI Literacy and Academic Integrity debates about authorship and process transparency.
- **AI in design pedagogy and educator frameworks.** It also shapes how teachers construct AI-supported learning experiences. GAIDE offers a Design-Thinking-based framework for K-12 teachers creating AI-powered tools through vibe coding, raising teachers' AI literacy and supporting learning-by-creating as Educational Development and Workplace Learning. The DOT Framework survey (n=72) grounds design thinking in open-systems theory and found practitioners frequently use iterative prompting and content generation but underuse needs assessment and feedback loops — a practice-versus-theory gap that operationalizes AI as a fallible co-intelligent collaborator under Human-in-the-Loop oversight. Even co-creating open social robots with students applied the Double Diamond (a design-thinking variant), redesigning the build around accessibility so that repairability and Open Source principles become sites of continued learning.

The mindset itself is measurable, and it moves across a program. Liu et al. (2026) validated five design thinking mindset dimensions in 409 AIGC-using fashion film students and found third-year students higher on all five, with abductive reasoning (0.865) and creative confidence (0.760) the largest standardized differences — a design education outcome that generated alternatives alone does not evidence.

Practical guidance

For educators, the collective evidence counsels against blanket restriction or unfettered adoption. Treat GenAI as an *ideation resource whose value is orchestration-dependent*: it excels at early-stage exploration and empathise work, while human instructors add contextual anchoring in prototyping and evaluation. When deploying Agentic AI agents, consider adversarial or Socratic roles that prompt reconsideration rather than

smooth cooperative confirmation. And for designers of teacher-facing support, remember that beliefs alone are not enough — practitioners need scaffolding for the full design cycle (needs assessment, feedback loops), not just tool usage, and evaluation instruments to verify that design thinking is actually being developed (see AI Ed Evaluation).

Connections to related concepts

Design thinking in AI education is deeply entangled with Human AI Collaboration: generative tools broaden ideation while humans retain epistemic authority and Learner Agency. It relies on Scaffolding and stage-appropriate Feedback to be effective, is often delivered through Socratic and adversarial interactions in Higher Education and K-12, and its success is frequently framed as preserving Creativity and fostering AI Literacy under Human-in-the-Loop governance.

Common Misconceptions

“Generative AI accelerates design thinking across all its stages.” It accelerates ideation and can degrade the judgment the later stages depend on: it **excels at early-stage ideation but can cause design fixation or aesthetic lock-in if used uncritically**. Fixation is the specific hazard of a fast ideation tool — the first plausible direction becomes the frame, and a large set of variations on one concept is not a wider search space.

“More generated options mean a broader exploration.” Breadth of output and breadth of consideration are different quantities. A student who generates thirty directions and adopts the first convincing one has explored one direction, and high acceptance rates are the signature of exactly that.

“Design thinking is a process to be automated stage by stage.” It is a discipline of framing and reframing problems, which is what fixation forecloses. Automating the stages while leaving the frame unexamined produces competent output for the wrong problem.

“AI agents that agree with the student support their design reasoning.” The productive use documented here runs the other way: constructive conflicts with AI agents tests adversarial prompting that forces reconsideration. An agreeable agent reinforces the fixation; a dissent-oriented one is the design with an educational claim behind it.

Connected Concepts

- AI in Education
- Generative AI
- Agentic AI
- Higher Education
- Student Experience
- Scaffolding
- Feedback
- Socratic Method
- Creativity

- Learner Agency
- Human AI Collaboration
- Teaching
- AI Literacy
- Equity
- Educational Development
- Human-in-the-Loop
- AI Ed Evaluation
- K-12
- Workplace Learning
- Academic Integrity
- Open Source
- Arts, Design and Media Education

Connected Articles

- From generation to judgment: the multidimensional structure of design thinking mindset and differences across learning stages in AIGC-supported fashion film design learning — Design thinking mindset across learning stages in AIGC-supported fashion film design (Liu et al. 2026)
- Gen-AI-tecture: using generative AI to support architectural students in design tasks — Gen-AI-tecture: using generative AI to support architectural students in design tasks
- Development and applications of Generative AI in architectural design studios — Development and applications of Generative AI in architectural design studios
- Co-Creating Buildable and Open Social Robot Study Companions with University Students — Co-Creating Buildable and Open Social Robot Study Companions with University Students
- A Guiding Framework for K-12 Teachers in Creating AI-powered Learning Technologies through Vibe Coding — A Guiding Framework for K-12 Teachers in Creating AI-powered Learning Technologies through Vibe Coding
- Practitioner beliefs and behaviors in AI-enhanced education: DOT framework survey evidence — DOT Framework Survey: Practitioner Beliefs and Behaviors in AI-Enhanced Education
- Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers — Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers
- A study of GenAI usage by Design Students: Analysis of Survey Results and Journals of AI practices at the Politecnico di Milano in 2025/2026 — A study of GenAI usage by Design Students: Analysis of Survey Results and Journals of AI practices at the Politecnico di Milano in 2025/2026

Curriculum Design

> **Curriculum Design** — the process of planning and structuring what is taught across courses, programs, and institutions, including learning objectives, content sequencing, assessment strategies, and skill progression. In the AI era, curriculum design must balance foundational knowledge with emerging AI competencies, determining not just what students learn but how they learn to work with and critically evaluate AI tools.

Questions to Consider

- Curriculum design asks what students should learn at the program level, while learning design asks how at the course level. When AI reshapes a discipline, which of these two layers do you think should change first?
- As generative AI automates implementation-level work, some argue curricula must shift toward system design, abstraction, and critical evaluation. What do you think students would lose if low-level skills were de-emphasized?
- Curriculum redesign in the AI era is often framed as a balance between tool fluency and foundational knowledge. Where have you seen that balance tip too far in one direction?
- The SAIL framework treats AI literacy as scaffolded across ages and designed to address deeper 'digital divides' beyond access. How is embedding AI literacy across a whole curriculum different from adding a single AI course?
- If every discipline now needs AI competencies embedded within it, who is responsible for the curriculum change — instructors, programs, or institutions — and what do educators need to succeed at it?
- A curriculum is a sequence of skills across years, not just a list of topics. How does that longer view change whether an 'AI literacy unit' actually sticks?

Introduction

Curriculum design addresses the *what* of education at the program level, complementing Learning Design which addresses the *how* at the course level. The articles in this knowledge base explore how AI is reshaping curricula across disciplines — from software engineering to architecture to green education — and how educators are designing curricula that embed AI literacy without sacrificing disciplinary fundamentals.

Key research themes

Redesigning curricula for the AI era is the central challenge. **Lee et al.** synthesized findings from international workshops on reshaping undergraduate CS education, arguing that as GenAI automates implementation-level programming, curricula must shift toward system design, abstraction, and critical evaluation — while de-emphasizing low-level implementation details. **Gorsky** formalized Agentic Software

Engineering as a distinct discipline with a 21-module curriculum focused on the “evolution of intent” and practitioner discipline required to manage AI agents. Both connect to AI Literacy and Scaffolding.

Reviewing the change as systemic rather than additive, Sabani et al. (2026) triangulate a scoping review, bibliometric mapping of 209 records, 36 articles, and ten academic-leader interviews into five shifts — including knowledge transmission giving way to capability development and local experimentation to institutional governance.

Curriculum mapping and analysis uses AI to understand existing curricula. **Geng et al.** analyzed 23 syllabi from AI-assisted software engineering courses, identifying common themes — prompt engineering, code review with AI, ethical considerations — and deriving design guidance that emphasizes balancing tool fluency with foundational knowledge. **CourseGraph** applies computational methods to compare CS course structures across institutions.

Weighting changes what a curriculum analysis reports: Jayalath et al. (2026) had GPT-o3-mini distribute 100% across seven enterprise skills for each of 48 assessments, reaching a Krippendorff’s alpha of 0.81 against expert weights, but agreement turned negative for skills the descriptions never state explicitly (-0.19).

Modular structure outlasts current content. A pattern recurs where the field moves faster than the review cycle: a stable core of AI literacy, critical appraisal, bias detection and Ethics, with specialty and locally available tool content attached as modules and revisited every six to twelve months (Bursic et al. (2026)). Postgraduate medical education is the stated case, but the principle generalizes: the program commits to competencies that survive tool turnover and schedules the tool-specific layer for replacement.

AI literacy integration embeds AI competencies across disciplines. **SAIL** provides a scaffolded AI literacy framework applicable across all ages and educational stages, addressing second- and third-level digital divides. **Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing** examines how AI literacy develops through interaction patterns. **Systematic review of collaborative learning activities for promoting AI literacy** explores collaborative approaches to AI literacy curriculum development, connecting to Collaborative Learning.

LearnAI shows what an embedded version looks like: a wide-exposure layer of short presentations inside 18 existing courses across five disciplines (293 students), paired with opt-in one-to-one co-creation sessions run by trained undergraduate peer tutors, so mixed-ability learners meet AI tasks at their own level (Qu et al. (2026)).

Integration in practice lags the frameworks. Santos-Albardía et al. (2025) found only 13.8% of surveyed education and journalism students said their coursework addressed critical media analysis, against 97.8% who rated it important, and their expert interviews traced the gap to teacher training that prioritizes technical and instructional skills over media education.

A PRISMA review of 39 STEAM studies (2016–2025) found a parallel imbalance in AI-literacy elements: implementations developed technical literacies — fundamental AI concepts, computational thinking, data literacy — while underdeveloping ethical awareness, creative imagination, and creating, managing and designing with AI, so auditing each unit against them is the practical response (Niri et al., 2026).

Student voice is another design input: 84% of 166 final-year business students wanted GenAI taught in their units and 85% saw it as essential for employability, while only 7% had learned about it from their university (Rook & Plumb (2026)).

A 42-study review of pre-university AI education finds curricula moving from technical content toward competency-based models built on frameworks such as AI4K12 and the Five Big Ideas in AI, with AI Literacy treated as a cross-curricular competency while standardized instruments for assessing it remain absent (Caruana et al. (2026)).

Instructors and employers agreed on the importance of only one of 26 AI skills — setting realistic expectations for AI-augmented work — and just three of the 26 were taught by half or more instructors, the report's evidence of an AI skills gap between higher education and employers (Fried (2026)).

K-12 ML activity design stays at the surface: a review behind the ICE-T framework found that invisible use, button interaction, and model deployment account for almost 60% of coded supervised-learning activities, open-ended creation appeared only twice, and technical and societal perspectives co-occurred in only about 3% of activities (Haritz et al., 2026).

Domain-specific curriculum innovation applies curriculum design to specific fields. **Gen-AI-tecture: using generative AI to support architectural students in design tasks** explores how generative AI reshapes architectural design Pedagogies and Teaching Strategies. **The Role of Artificial Intelligence in Green Education: Optimizing Teacher Workflow and Enhancing Pedagogical Design under Sustainable Development Pedagogy (SDP) Constraints** examines AI integration in green education curricula. **ConnectED: A curriculum-aligned AI system for Vietnamese instructional lesson planning and student learning** and **LLMs to Support K-12 Teachers in Culturally Relevant Pedagogy: An AI Literacy Example** address culturally responsive curriculum design.

Embed AI inside the discipline rather than beside it. A three-tier (introductory, application, advanced) AI curriculum folded machine learning into existing thermal-engineering topics across a 39.1-hour course rather than adding computer-science electives, avoiding extra load on mechanical-engineering students and releasing its syllabus, data and code openly (Li et al. (2026)).

A journalism case shows the values-first variant: a triadic values–processes–competencies scaffold moved students from human-only reporting to AI-integrated work, yet 8 of 9 (89%) reported confidence in ethical decisions while survey items on authorship and bias suggested only superficial understanding (Ngu and Weller (2026)).

Institutional frameworks address curriculum change at scale. **A principled way to think about AI in education: guidance for educators and policy makers on action based on goals, models of human learning, and use of technologies** and **A principled way to think about AI in education: guidance for educators and policy makers on action based on goals, models of human learning, and use of technologies** provide principles for integrating AI across educational programs. **The Main Barrier to AI Adoption in the Public Sector is Lack of Training** examines barriers to AI curriculum adoption in public sector education.

Sequencing AI across the program. Torres-Sahli et al. propose a "refrain, then amplify" framework that sequences generative AI at the program level: withhold a generative tool while a capacity is forming, then restore it to amplify that capacity once the student can direct it and judge its returns. Governed by a forming-versus-offloading criterion (whether a stretch of work builds a capacity or merely passes it through the tool), the framework links curriculum design to Cognitive Offloading, Self-Regulated Learning, and Academic Integrity, with hard-to-fake checkpoints at each refrain-to-amplify hinge.

The lever for the highest stages is not more coursework: across 89 sponsored capstone projects, advancement from Workforce Readiness Level 6 to 7 was gated by industry-embedded experience — co-ops and Manufacturing Extension Partnership projects — so degrees need work-integrated learning rather than another technical elective (Smith et al. (2026)).

A curriculum-level consequence of model capability is that AI-resistant design expires. Computing educators described calibrating assignments against what the models could not yet do and watching the calibration lapse — one cybersecurity instructor's problems required genuine problem solving seven or eight months earlier and were then simply solved — with a facilitator estimating a shelf life of about one semester. The workshop's structural finding is that nearly every adaptation was made by an individual instructor within a single course, without the institutional coordination a durable curricular response would require (Akbar et al., 2026).

Whole-course alignment when generative AI is permitted. A 2026 redesign of an introductory nuclear and particle physics course (Mikhasenko et al.) integrated three activity types with distinct roles — lectures for concepts and notation, tutorials for standard analytic practice, and homework as an exploratory "research-shaped" component of unusually difficult, multi-method problems. The reported friction (an undeclared programming prerequisite, insufficient time to understand rather than merely obtain answers, and misalignment among lectures, tutorials, homework and examination) illustrates that permitting generative AI forces curriculum alignment work across the whole course rather than a change to one assignment type; their recommended structure keeps the AI-permitted exploratory work as bonus-bearing advanced tasks while the unaided written exam determines the grade.

Depth of alignment, not frequency of use, separates integration patterns. Across 17 business-module cases, six embedded GenAI systematically across teaching, learning and assessment (constructive), nine did so inconsistently (blended) and two sporadically (ad hoc); the constructive cases reported the strongest engagement, capability and curriculum-relevance outcomes (Zhou et al. (2026)).

Constructive alignment advice under critical scrutiny. Where the sources above report on alignment in practice, McInnes et al. (2026) read the guidance itself as a discourse. Their critical discourse analysis of 14 pieces of gray literature published from November 2022 to April 2025 — mostly institutional pages and chapters from centrally positioned learning and teaching units — found constructive alignment presented as an efficiency problem: generative AI was "an effective and efficient way to draft rubrics" that could "streamline the process", anthropomorphized as "an educational expert and assistant", a "sparring partner" or an "intelligent assistant in instructional design", while academic staff supplied only "subject matter expertise" and the tool took on "the heavy lifting of developing learning objectives, organizing course content … and aligning course components". Copy-and-paste prompt recipes and numbered templates framed CA as a standardisable product, producing three failure modes: performativity (alignment that only looks aligned), erasure of situated and critical context, and shallow CA that conflates alignment with the constructive dimension. Their remedy re-sequences the curriculum-design workflow — educators must understand CA well enough to direct, evaluate and reject AI output before delegating any part of it — and bounds any tool to an institutional retrieval-augmented agent grounded in local policy, rubrics and graduate attributes, with a "liminal tutor" role that extends rather than replaces the developer relationship.

Generating curriculum-aligned modeling tasks. AI-powered platforms can address teachers' lack of time and resources for designing high-quality mathematical modeling tasks by generating curriculum-aligned

problems and pedagogical recommendations grounded in design principles and retrieval-augmented generation — an approach illustrated with direct variation in secondary school mathematics (Creating an AI-powered platform for generating modelling problems: A case study on direct variation in secondary school mathematics). Course readings themselves are now a generation target too: Sidorkin (2026) replaced a commercial textbook with weekly AI-generated readings in a graduate educational leadership course, and although students rated them useful and 75 percent agreed they learned more than in a comparable course, the 4,487 pages of logs carried APA-style in-text citations on only about 0.80 percent of pages and paired a named campus or system with assertive policy claims on roughly 1.03 percent of pages without a verifiable source. The curriculum-materials lesson is to treat generated readings as draft production under instructor review, to budget for the instructor labor of prompt design and verification, and to curate vetted sources into the assistant rather than leaving source quality for students to infer from context.

AI-assisted lesson planning at the curriculum-into-classroom layer. At the point where a curriculum becomes a taught lesson, Luo and Tahir (2025) experimentally compared teacher-generated versus ChatGPT-assisted plans in children's STEAM arts education, finding AI-assisted plans rated significantly higher by six expert professors (median 20.5 vs. 17.6, p = .002, large effect). They show the payoff depends on how the teacher delegates: the recommended method fills content gaps in a self-outlined lesson (preserving teacher design autonomy) rather than delegating the whole plan. They also contribute a Role–Instructions–End Goal prompt template for reproducible, quality-controlled generation — evidence that AI lesson planning is strongest when embedded within, not substituted for, the teacher's curriculum decisions. In science education, expert validation reaches a parallel verdict on platform design: Karaismailoglu, Surmeli and Yildirim (2026) had eleven Science Education specialists rate ChatGPT-4 and an education-focused tool (Teacher's Buddy) on sixth-grade plans aligned to Turkey's revised curriculum and the Engineering Design-Based Learning model. The education-focused platform scored higher across all eight quality criteria — including feedback-intensive stages and curriculum alignment — evidence that embedding pedagogical structure into an AI yields better-aligned output. Yet some experts still preferred the general-purpose plan for its stronger social-emotional emphasis, and 7 of 11 judged the plans "applicable by correction" rather than directly usable. The choice of platform and prompt framing, not just the AI itself, shapes how well generated plans align to curriculum standards and process models.

Structure, not prompt phrasing, is what makes AI drafting reliable in production: Paiva (2026)'s Curriculum-as-Code pipeline pruned context aggressively and generated materials section by section across 28 project contexts, which cut instructor preparation time from roughly eight to two hours per instruction and left no conceptual or mathematical hallucinations for human review to catch.

Connections to related concepts

Curriculum design connects directly to Learning Design — curriculum defines what, instruction defines how. It connects to AI Literacy because embedding AI competencies is a primary curriculum challenge, to Teaching and Educational Development because curriculum change requires educator preparation, and to Scaffolding because well-designed curricula scaffold skill development across courses and years. The Higher Education and K-12 connections reflect curriculum design's relevance across educational levels.

Choosing one AI literacy framework means choosing a vocabulary nobody has crosswalked. In a scoping review of 50 K-12 frameworks, Kharbach et al. (2026) found competency definitions converging on

cognitive, affective, behavioral, ethical and social dimensions while the labels and constructs did not align. Only the ABCE framework approached a shared measurement tradition, validated across Hong Kong, Shanghai and Taiwan, and progression across grade bands was proposed repeatedly and tested nowhere.

Common Misconceptions

- **“An Large Language Models (LLMs) can map a curriculum once validated at high reliability.”** GPT-o3-mini distributed **100% across seven enterprise skills for each of 48 assessments**, reaching **Krippendorff’s alpha of 0.81** against expert weights — and **agreement** broke down on particular skills. High overall reliability with uneven agreement is the pattern to check before trusting the mapping.
- **“Embedding AI literacy means adding a course.”** LearnAI shows the embedded form: a **wide-exposure layer of short presentations inside 18 existing courses across five disciplines (293 students)**. The exposure was distributed across the curriculum rather than gathered into a unit.
- **“Students arrive already able to evaluate media critically.”** Only **13.8% of surveyed education and journalism students** said their coursework addressed critical media analysis, against **97.8% who rated it important**. The gap between valuing a skill and being taught it is the curricular opening.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- Business Education
- Learning Design
- AI Literacy
- Scaffolding
- Educational Development
- Teaching
- Higher Education
- K-12
- STEM Education
- CS Education
- Generative AI
- Agentic AI
- Metacognition
- Prompt Engineering
- Collaborative Learning
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Recommender Systems and Learning Paths

Connected Articles

- Leveraging GenAI models for Curriculum Analytics: A Human-Centered Approach for Curriculum Mapping in Higher Education — Weighted, expert-validated skill mapping for accreditation
- Efficiency at what cost? Salvaging constructive alignment from the GenAI hype — Critical discourse analysis of GenAI-for-constructive-alignment guidance (McInnes et al. 2026)
- Addressing Trust in AI Systems through Education: A Didactic Perspective — Addressing Trust in AI Systems through Education: A Didactic Perspective
- Refrain, Then Amplify: A Curriculum Framework for Sequencing Generative AI to Form Professional Judgement — Refrain-then-amplify curriculum framework for sequencing GenAI (Torres-Sahli et al. 2026)
- Giving mechanical engineers intelligent tools: A project-based AI education curriculum in thermal engineering — Project-Based AI Education Curriculum in Thermal Engineering
- From Classroom Design to Newsroom Practice: Assessment Intervention Designing GenAI
- Integrating generative artificial intelligence into university curricula: Student insights
- From Experimentation to Integration: Embedding GenAI in Business Higher Education through the Lens of Constructive Alignment
- A Conceptual Framework for Enhancing Workforce Readiness for Smart Manufacturing in the AI Era — Workforce Readiness Level framework for smart manufacturing in the AI era
- Rewriting the Curriculum: A Systematic Review of Generative AI-Driven Pedagogical Change and Emerging Systems of Learning in Higher Education — Rewriting the curriculum: GenAI-driven pedagogical change
- Technology, education and critical media literacy: potential, challenges, and opportunities
- Reshaping Undergraduate Computer Science Education in the Generative AI Era
- ASE-26: A Curriculum for Agentic Software Engineering as a Discipline
- Mapping the Emerging Curriculum for AI-Assisted Software Engineering via Syllabus Analysis
- The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education
- Curriculum as Code: An AI-Assisted Architecture for Instructional Design in STEM Education
- Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing
- A principled way to think about AI in education: guidance for educators and policy makers on action based on goals, models of human learning, and use of technologies
- Systematic review of collaborative learning activities for promoting AI literacy
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — AI Skills Framework: 26 assessable skills for curriculum mapping
- LearnAI: Just-in-Time AI Co-Creation Across Disciplines at a University — LearnAI: Just-in-Time AI Co-Creation Across Disciplines
- When Saying No Makes Better Videos: Designing Dual Gatekeeping for Pedagogically Grounded AI Content Creation — When Saying No Makes Better Videos: Dual Gatekeeping for Pedagogically Grounded AI Content Creation

- STEAM education for AI literacy: a systematic literature review — STEAM education for AI literacy: systematic review
- Preparing Learners and Teachers for an AI-Driven Future: Emerging Trends, Pedagogical Challenges, and Critical Perspectives in Pre-University AI Education: A Systematic Literature Review — Preparing learners and teachers for an AI-driven future: SLR of pre-university AI education (Caruana et al. 2026)
- Creating an AI-powered platform for generating modelling problems: A case study on direct variation in secondary school mathematics — AI-powered platform generating mathematical modeling problems (ADDIE, RAG)
- ChatGPT-assisted lesson planning for children's STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework
- Suitability of Artificial Intelligence Supported Lesson Plans from the Perspective of Science Education Experts
- AI in Particle Physics Education: Research Problems and Foundational Skills — AI in Particle Physics Education: Research Problems and Foundational Skills
- AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI — AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI
- K-12 AI literacy frameworks after generative AI: A scoping review - competency frameworks converge on five dimensions without a shared vocabulary or crosswalk
- Exploring the integration of artificial intelligence into residency education curriculum: qualitative interviews — Barriers to integrating AI into residency curricula: qualitative interviews with twelve physician leaders

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?

Critical Thinking

> **Critical thinking** — the ability to analyze, evaluate, and synthesize information — is both a skill that AI tools can help develop and a competency that students must apply when using AI. In AI in education research, critical thinking appears in two interrelated forms: as a learning objective (teaching students to think critically) and as a safeguard against uncritical AI reliance.

Questions to Consider

- How confident are you in your ability to spot a false or misleading AI-generated answer? Research suggests self-reported AI competence far exceeds actual evaluation ability — how would you test yourself?
- Critical thinking here appears in two forms: a skill to teach, and a safeguard against uncritical reliance on AI. Can you think of a situation where a tool that 'teaches' critical thinking is actually training its opposite?
- One study found that having students interrogate AI-generated mistakes produced large gains in higher-order thinking. How might deliberately exposing errors — rather than hiding them — be a more powerful teaching move than you assumed?
- Easy access to AI answers can displace critical engagement before students realize it. What design feature, rather than a policy or a ban, could keep the cognitive effort alive?
- AI advice has been shown to suppress the willingness to say 'I don't know' — even when the advice is wrong. How does that change what it means to create a classroom culture where questioning is safe?

Introduction

Critical thinking is central to AI Literacy — students who cannot critically evaluate AI outputs are vulnerable to Over-Reliance, hallucinated information, and biased recommendations. Research on Cognitive Offloading shows that easy access to AI answers can displace critical engagement, while Socratic approaches that withhold direct answers preserve the cognitive effort necessary for deeper thinking.

Structured dialogue control, not a better prompt, is what separates a fallacy tutor from a debating chatbot: routing each turn through Toulmin-based intent detection, a fixed strategy order and a verifier agent let one Socratic system pass 84.5% of dialogue-quality metrics against 61.5% for a heuristics baseline (Shi et al. (2026)).

Critical thinking in AI education research

The knowledge base's articles explore critical thinking through design-based and empirical lenses. Adversarial AI agents enact constructive conflict to prompt reconsideration in novice designers — a Socratic variant that forces critical re-evaluation. RCT research on GenAI in teaching raises the question of whether AI tools that optimize for surface-level outcomes may inadvertently suppress the critical thinking that leads

to deeper learning. Measured evidence sharpens the point: whether critical thinking moves depends on how AI-mediated feedback and tasks are designed, and on learners' metacognitive regulation, not on access to a model.

GenAI use's link to self-reported critical thinking ran almost entirely through GenAI Feedback Literacy: in 421 Chinese undergraduates, feedback literacy mediated 71.98% of the total association (β=0.185), and the residual direct path was positive only for less reflective students (β=0.177) and non-significant for more reflective ones (Yan et al. (2026)).

A meta-analytic anchor for the moderation claim. Across 29 experiments GenAI raised higher-order thinking moderately (g = 0.609), with critical thinking at ES = 0.691 — below Problem Solving (0.745) and above Creativity (0.444) — strongest for 8–16-week interventions (0.759) and for high-SRL learners (0.863 against 0.284) (Zhao et al. (2025)).

Reviews of ChatGPT's impact on thinking document mixed findings: AI can scaffold critical analysis when used deliberately (e.g., asking students to critique AI-generated arguments), but it can also short-circuit thinking when used as an answer engine. This tension connects to How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures research showing that self-reported AI competence far exceeds actual critical evaluation ability. A critical review of 80 HCI studies of critical thinking with AI found the field measuring what it rarely defines: only 23 of the 80 stated how they understood critical thinking at all, 49 (61%) assessed it through self-report rather than performance, and 42 (52%) used no control group (A Critical Review of Critical Thinking in HCI Research About AI).

Lin and Al-Hada (2026) read that mixed picture as a product–process dissociation: GenAI can raise the quality of an assignment while lowering the unaided, delayed transfer behind it, so learning should be judged on unaided delayed performance rather than on the AI-assisted product.

- **Higher-order cognitive engagement in student-AI chat.** Chang and Li (2026) find that ~62% of student prompts to AI encode higher-order cognitive demand, with Bloom-level profiles varying by discipline (STEM Apply-prevalent 20.8%, language Understand-prevalent 31.7%, social science Create-prevalent 33.8%). Their within-person design shows the same students produce significantly more higher-order prompts in social science than STEM courses ($p < .001$), indicating that disciplinary context shapes critical and higher-order engagement with AI.
- **Interaction patterns cluster by Bloom level and prior knowledge.** In an inquiry-based data-science writing task, 19 students produced 14 Large Language Models (LLMs) interaction patterns that varied by prior-knowledge level, and the design implication was to aim scaffolding at specific higher-order thinking stages rather than at LLM use in general (Luo et al. (2026)).
- **AI as a catalyst for critical media literacy in children.** Demir and Akar (2026) evaluate an 18-hour, 5E-model critical media literacy program for fourth-grade Turkish students in which generative AI (ChatGPT, Grammarly) acted as a pedagogical agent embedded phase-by-phase rather than an add-on. Paired-samples comparisons showed large gains in media reading (+3.50), writing (+1.67), and total media literacy (+5.17, all $p < .01$), with between-group post-test effect sizes of Cohen's $d = 1.12$ (reading), 1.18 (writing), and 1.31 (total literacy) favoring the AI-supported group. Qualitative analysis (interviews, student posters/drawings/slogans, classroom observation) surfaced six domains of critical media literacy growth — digital self-protection and data privacy, purposeful and responsible media use, safe communication and boundary awareness,

critical evaluation and misinformation awareness, online risk awareness, and media Ethics/digital citizenship — indicating that deliberately interrogating AI-mediated content can cultivate critical analysis and reflection in young learners.

- **Dimension-specific critical-thinking gains in primary multimodal writing.** Lu et al. (2027) followed 60 Grade 5 students through an eight-week Conversational AI-supported multimodal writing practice in which they turned narratives into AI-generated images and short videos. Repeated-measures analysis across six critical-thinking dimensions found sustained gains (T1 → T2 and T1 → T3) in interpretation, analysis, evaluation, and explanation, a short-lived self-AI Regulation in Education gain, and **no change in inference** — an uneven, dimension-level pattern that an aggregate critical-thinking score would have hidden. The authors argue the AI-generated visuals *externalized* meaning and thereby lowered the inferential demand writing normally imposes, while peer collaboration (peer questions that forced inferring others' interpretations) supplied the occasions for inference the solo AI interaction did not. The design lesson: multimodal AI composing supports several critical-thinking facets but should be paired with continued Scaffolding and structured peer exchange to preserve inference and self-regulation.
- **AI scaffolding and offloading pull critical thinking in opposite directions.** Davor, Larbi and Boateng (2026) surveyed 533 university students in Ghana and found that AI task scaffolding predicted higher critical thinking (β = .185) while cognitive offloading tendency predicted lower critical thinking (-.240); AI verification literacy had no direct effect on critical thinking and worked only through metacognitive self-regulation, a full mediation pattern the authors read as evidence that teaching students to fact-check AI is not enough on its own. (Davor et al. 2026)
- **Offloading depth, not use, bounds higher-order thinking.** Delegating the reasoning layer of writing — warrants, counterarguments, evidence interpretation — carried the strongest negative association with independent higher-order thinking (ab = −0.34), and self-regulated writing weakened but never reversed it (Chen (2026)).
- **Dependence, not use, is where the association with critical thinking turns.** Shojaei and colleagues (2026) surveyed 412 business students in Oman and found a near-zero bivariate correlation between GenAI use and self-reported critical-thinking disposition (r = 0.050), with dependence predicting lower disposition (β = -0.389) and weakening the link from use to disposition (β = -0.239), so that the simple slope fell from 0.424 at low dependence to -0.054 at high dependence. (Shojaei et al. 2026)

A larger cross-sectional survey points the other way: among 1,157 Chinese graduate students, GenAI dependence was positively associated with critical thinking (β = 0.492), and critical thinking carried roughly 85.0% of the path from functional dependence to research creativity (Yin et al. (2026)).

- **A short reflection prompt makes reliance on AI advice more discriminative.** In a three-condition experiment with 342 undergraduates, Ren (2026) found that open ChatGPT support produced acceptance of incorrect AI recommendations on 62.4% of trials, falling to 39.7% with a brief metacognitive reflection prompt (OR = 0.40, 95% CI [0.28, 0.56]); reflection also improved awareness calibration (0.59 vs. 0.41) and cut the AI-specific attribution bias index from 0.42 to 0.21 without reducing recommendation accuracy or triggering blanket rejection of useful advice. (Ren 2026)

- **Confidence can rise while accuracy falls.** Shaw and Nave (2026) found that consulting an AI assistant raised accuracy by 25 percentage points when it was right and lowered it by 15 when it erred, yet engaging it increased confidence even after errors, and 73.2% of incorrect-AI trials ended in surrender rather than strategic offloading.
- **Teacher-curated ChatGPT feedback raises critical thinking through higher-order revision.** Chen and colleagues (2026) ran an 18-week quasi-experiment with 64 undergraduates, all pre-service chemistry, physics or mathematics teachers, comparing conventional teacher feedback (n = 32) against ChatGPT-assisted teacher feedback (n = 32) across two argumentative writing tasks. The groups began equivalent, and only the assisted group improved significantly ($p < 0.001$), with Cohen's *d* rising from 0.25 at pretest to 3.74 at posttest. The mechanism was the kind of feedback, not the mere presence of a model: the assisted group received more demonstration (33.1% vs. 10.9%) and closely questioning (21.5% vs. 6.0%) feedback, revised 91.00% (435 of 478) of feedback units against 85.21% (242 of 284), and epistemic network analysis linked those revisions to analysis, evaluation and creation rather than recognition and understanding, while teacher-only instruction and evaluation feedback mostly produced recognition and understanding revisions. Teachers treated the model's output as draft material, expanding, revising or discarding it (14% discarded, 9% needing correction), and six of eight interviewees still flagged imprecision or unprofessionalism. The design lesson is that the critical-thinking gain came from feedback that models alternatives and interrogates the student's reasoning, with a teacher curating what the model produced; the small, single-semester sample means the very large effect size should be read with caution. (Chen et al. 2026)
- **A semester of AI access left critical thinking flat, while reflective use tracked it.** Melanou, Beege and Kimmig (2026) followed 87 business informatics students through a nine-week course in three parallel conditions (tutor-framed AI, unguided AI, and no AI) measured three times. Knowledge rose in every group with no advantage for either AI condition and no Matthew effect ($BF01 = 8.70$), while self-reported critical thinking and Motivation stayed stable. What separated students was reflective use, the practice of checking sources and verifying AI output before adopting it: it was higher in the AI condition than in the control group (means of 3.72 vs. 2.82) and predicted critical thinking at the final measurement ($R^2 = 0.183$, $\beta = 0.43$, $p < 0.001$). The result qualifies any expectation that a course of AI use will move critical thinking on its own: metacognitive regulation, not tool access, is where the association lives, and the authors note a semester is likely too short to see durable change. (Melanou et al. 2026)

Connections to other concepts

Critical thinking intersects with Scaffolding (designing AI support that maintains cognitive demand), Prompt Engineering (formulating questions that elicit critical analysis), and Over-Reliance (knowing when to trust and when to question AI). It is foundational to Academic Integrity and serves as a key dimension of AI Literacy frameworks across both K-12 and Higher Education contexts.

- **AI errors as provocations for higher-order thinking:** Hosseini (2026) operationalizes Bloom's higher-order levels (Analyze, Evaluate, Create) by having students interrogate AI-generated

mistakes in a database course, with significant pre/post gains (Cohen's *d*=1.49) in subject-matter competency.

- **Critique of AI output is a scaffoldable skill, not a by-product of problem-solving.** Groups that only solved a related physics problem accepted a polished AI solution or critiqued it from their own Misconceptions about AI, whereas MAPS-rubric-guided reflection produced expert-aligned critiques of missing integration and undefined notation (Borse et al. (2026)).
- **Bound the AI to preserve cognitive agency.** The E3-HOT blueprint maps three embodied pathways — situational embedding, embodied participation, cognitive creation — onto Analyze, Evaluate and Create, and constrains the AI to prompts, critique and strategy suggestions so students must articulate rationales and cite evidence before a claim is accepted (Zhu et al. (2026)).
- **Two-sided auditing of AI explanations.** Bernstein and Sibia (2026) used Paul–Elder standards (accuracy, clarity, assumptions, point of view) as interview probes with ten students who had completed CS2, and found mechanism-level scrutiny of GenAI explanations: students located where an analogy's mapping broke (an island-route analogy for a linked list that implied a circle, a badminton rally offered for recursion that had no guaranteed shrinking input), demanded precise wording over hedging, and treated explanations as arguments carrying a point of view. Crucially, that scrutiny tracked source- or target-domain expertise rather than personal interest — reframing critical evaluation of AI output as a knowledge problem ("two-sided analogy auditing") rather than a dispositional one — and suggesting that assigning flawed AI analogies as objects to inspect and repair is a harder check on conceptual understanding than reading a finished explanation. (Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education)
- **Critical thinking as non-outsourceable engagement.** Xie (2026) adds a philosophical counterpart from Daoist self-cultivation: because AI is an opaque "black box," a framework oriented to harmonizing uncertainty rather than adjudicating truth in absolute terms better suits the current epistemic landscape, and critical thinking becomes sustained, first-person, non-outsourceable engagement with reality rather than a demonstrable rational procedure. In Neidan (內丹) practice "there are no cognitive shortcuts," so AI is positioned as "not a cognitive surrogate but an instrumental adjunct" to human flourishing.(Alternative AI Philosophy: Daoism as Method for AI in Education)
- **Role rotation as a structure for critical human-AI interaction.** Kenzhebayeva and colleagues (2026) report a design-based study in which 62 pre-service educational psychologists rotated through four professional roles (Case Constructor, Research Analyst, Practitioner-Interventionist, Reflective Researcher) that made generated recommendations the object of discussion. Participants compared AI output with psychological theory and modified or rejected recommendations that did not fit the case, and later cycles showed more requests for theoretical justification, while overreliance on apparently authoritative responses persisted. (Kenzhebayeva et al. 2026)
- **Verification-centered integration in a discipline.** A critical review of generative AI in university chemistry education (Vega-Baudrit and Rivera Álvarez, 2026) argues that because chemical reasoning must be coordinated across macroscopic, submicroscopic, and symbolic representations,

students cannot verify what they do not understand, so Prior Knowledge and Scaffolding come first and verification should be designed into Assessment as an assessed activity: identify a false assumption, correct a unit or mechanism error, or justify rejecting a generated answer, keeping prompt logs and revision histories as reasoning traces. (Vega-Baudrit and Rivera Álvarez 2026)

- **Verification as a learning activity, not only a safeguard.** Wang (2026) organizes AI-artifact evaluation around six interdependent dimensions — Process, Evidence, Access, Reproducibility, Legitimacy and Source — and treats assembling that warrant, rather than the output's fluency, as what builds disciplinary expertise.

The largest expert-rated vulnerability in the knowledge base is critical thinking. Across 65 learning processes rated by 30 experts, Critical Thinking and Critical-Analytic Thinking drew the report's highest disruption rating (mean 4.00 of 5; 96% of raters at or above 3) with enhancement below threshold (2.40, 43%) (Kendeou, Greene & Nixon et al., 2026). Ten of eighteen higher-order processes reached consensus on vulnerability only, which the report reads as one-sided risk rather than a trade-off.

- **Structure of the partnership, not exposure, carries the association.** Akgun and Toker (2026) modeled 891 US and Turkish college students with transactive memory systems theory and found that neither self-appraised thinking ability nor confidence in the AI partnership predicted critical-thinking enactment directly. Both fed GenAI familiarity, which in turn predicted only two behaviors: specialization and coordination of labor (b = 0.636) and reflective transformation of output (b = 0.367). Those behaviors predicted critical thinking (b = 0.230 and b = 0.175) with no direct path remaining (CFI = 0.974, RMSEA = 0.048). This is the mechanism-level version of the field's recurring null: hours of use and self-rated competence are not proxies for critical thinking, and what a study measures when it asks about exposure is the input to the chain rather than its outcome.

Common Misconceptions

- **"A better prompt produces better critical thinking." Structured dialogue control, not a better prompt**, separates a fallacy tutor from a debating chatbot: routing each turn through **Toulmin-based intent detection** did the work. The mechanism is the interaction structure rather than the wording.
- **"GenAI use raises critical thinking directly."** GenAI use's link to **self-reported** critical thinking ran **almost entirely through GenAI feedback literacy** — in **421 Chinese undergraduates**, feedback literacy mediated **71%** of the association. The literacy is the pathway.
- **"The meta-analytic effect is uniform."** Across **29 experiments**, GenAI raised higher-order thinking moderately (**g = 0.609**) with critical thinking at **ES = 0.691**. Moderate pooled effects over heterogeneous interventions support the category and not a specific design.

Connected Concepts

- Metacognition
- Cognitive Offloading
- AI Literacy

- Generative AI
- Higher Education
- Problem-Based Learning
- Intelligent Tutoring
- Educational Development
- Teaching
- Student Experience
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools
- Cognitive Surrender
- Reflection

Connected Articles

- When Does GenAI Use Support Critical Thinking? A Cross-Cultural Structural Account of Transactive Memory with GenAI — Critical thinking runs through division of labor and reworking output, not exposure
- Ways generative AI can support and threaten learning in K-20 US education - A 30-expert consensus: critical thinking carries the report's highest disruption rating (mean 4.00)
- From Plausibility to Verifiability: The PEARLS Framework for Developing Epistemic Agency in Generative AI-Mediated Higher Education — PEARLS framework for epistemic agency and verifying AI output (Wang 2026)
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- The critical-thinking paradox in generative AI-integrated learning: distinguishing efficiency from cognitive depth — a differentiated framework and testable propositions — The critical-thinking paradox in GenAI-integrated learning
- The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking — The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking (Hosseini 2026)
- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Tri-System Theory and cognitive surrender: how AI reshapes human reasoning (Shaw & Nave 2026)
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- Does generative artificial intelligence improve students' higher-order thinking? A meta-analysis based on 29 experiments and quasi-experiments — GenAI and higher-order thinking meta-analysis

- Can we disrupt the momentum of the AI colonization of science education? — Disrupting the AI colonization of science education
- Reorienting Critical AI Literacy: A Community-Rooted Praxis of "Resisting AI" — Reorienting critical AI literacy
- Inquiry-based learning patterns in large language model-driven learning environments: an exploratory study from Bloom's perspective — IBL patterns in LLM-driven environments (Bloom's perspective)
- Probing AI-generated physics solutions and preparing students to critique them — Preparing students to critique AI-generated physics solutions
- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era — Fostering Sustainable Learning via Embodied Intelligence (E3-HOT)
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system
- More externalization, but less inference? Exploring changes in young learners' critical thinking during conversational AI bot-supported multimodal writing practice — Dimension-specific critical-thinking gains in AI-supported multimodal writing (Lu et al. 2027)
- Tackling the Root of Misinformation by Teaching Laypeople about Logical Fallacies via Socratic Questioning and Critical Argumentation — teaching fallacy recognition through structured multi-turn dialogue
- Building AI Companions that Prioritize Learning over Performance — learning over performance: what companions should be optimized and measured for
- Artificial intelligence-supported learning and higher-order cognitive outcomes: the mediating role of metacognitive self-regulation — AI scaffolding, offloading, and verification literacy via metacognitive self-regulation (Davor et al. 2026)
- Helpful or harmful? Generative AI dependence, self-reported critical thinking disposition, and self-perceived employability among business students — GenAI dependence bounds the use to critical-thinking link in business students (Shojaei et al. 2026)
- College students' metacognitive awareness of generative-AI reliance: an experimental study of decision confidence and attribution bias — Reflection prompt cuts acceptance of incorrect AI advice and attribution bias (Ren 2026)

- Designing an AI-integrated role-rotation pedagogical model to support competence-related learning in pre-service educational psychologists — Role rotation as structure for critical human-AI interaction (Kenzhebayeva et al. 2026)
- Generative artificial intelligence in university chemistry education: a critical review using Johnstone's chemistry triplet and Biggs' 3P model — Verification-centered GenAI integration in university chemistry education (Vega-Baudrit and Rivera Álvarez 2026)
- Effects of ChatGPT-Assisted Teacher Feedback on College Students' Critical Thinking Skills and Perceptions of Argumentative Writing — teacher-curated ChatGPT feedback raised critical thinking via higher-order revision (Chen et al. 2026)
- Generative AI and Learning Dynamics in Higher Education: A Longitudinal Empirical Study — a semester of AI access left critical thinking flat; reflective use predicted it (Melanou et al. 2026)
- GenAI dependence and graduate students' research creativity: the roles of critical thinking and human-AI collaboration quality — GenAI dependence positively associated with critical thinking in 1,157 graduate students
- The association between generative AI use and university students' critical thinking: a moderated mediation model of GenAI feedback literacy and reflective thinking — GenAI use to critical thinking via feedback literacy, with a direct path only for less reflective students

Connected FAQs

- How Do I Teach Students to Verify AI Output?

Computational Thinking

> **Computational thinking** — a problem-solving approach involving decomposition, pattern recognition, abstraction, and algorithmic design. In AI education, computational thinking is both a prerequisite for understanding AI systems and a skill that AI tools can help develop.

Questions to Consider

- When you solve a problem by breaking it into parts, spotting patterns, abstracting the essentials, and designing steps — you're already doing computational thinking, even without a computer. Where have you done this recently?
- A common assumption is that computational thinking is the same as coding or 'computer literacy.' How might they differ, and why might that difference matter for how you teach it?
- Research suggests students' deficits in fundamental concepts — not the AI tool itself — are what limit their ability to judge AI suggestions. What must a learner already understand before they can critically evaluate an AI's output?
- Some argue computational thinking should move learners from passively consuming AI outputs toward building, critiquing, and designing with AI. What would a classroom that treats students as producers rather than consumers actually look like?
- Generative AI can now score students' computational thinking growth — yet both humans and AI struggle with the hardest construct, systems thinking. Where do you think automation of assessment should stop, and why?
- Robotics research finds computational thinking only develops when concepts are made explicit and mapped to the curriculum, not treated as isolated tech exercises. What's the risk of teaching 'tech skills' without naming the thinking underneath?

Introduction

CT in an AI-era classroom

The knowledge base's connected articles converge on a central claim: computational thinking (CT) is the conceptual bedrock students need in order to engage critically with AI, and it is also the skill most directly deepened by well-designed AI-supported learning. Below the evidence is grouped into four themes grounded in the linked articles.

- **CT as the foundation of AI literacy and critical engagement.** Several studies show that CT is what lets learners evaluate, rather than just consume, AI outputs. Chat debugging research found that when undergraduates debugged analog circuits with LLM help, their *deficits in fundamental concepts and critical thinking* — not the tool — were the limiting factor, since students lacked the core ideas needed to judge AI suggestions. A review of LLM intervention designs likewise concludes that what separates effective interventions from "tool frustration" is the CS Education push toward computational thinking over syntax mastery. In early childhood, the AI-Play

framework builds unplugged, play-based AI Literacy by teaching children that “AI is a system built from parts” and “AI learns from examples” — a developmentally grounded first layer of CT. And an AI academic league connects CT to real civic AI projects through Project-Based Learning, embedding AI Literacy in practice. Together these suggest CT is the transferable cognitive core of AI literacy.

- **Educational robotics as a vehicle for CT.** Robotics is the most-studied context for developing CT across K-12 and STEM Education. Secondary-school research argues that educational robotics enhances problem solving and critical thinking only when CT concepts are made explicit and mapped onto the STEAM curriculum rather than treated as isolated technical exercises. A systematic review of 95 studies confirms that robotics fosters CT, Creativity, and problem solving, and that Game-Based Learning suits informal settings while gamification dominates formal classrooms and supports project-based learning. Teacher-training evidence shows an integrated Micro:bit + robot + Machine Learning intervention produced significant CT knowledge gains (d = 0.638) in initial teacher education, arguing robotics should be embedded so future teachers can teach CT. LLMs can lower the barrier further: EduSim-LLM couples an LLM with robot simulation so beginners control robots via natural language, making CT-embedded robotics accessible without low-level coding.
- **AI as a “more capable peer” can carry CT in under-resourced robotics courses.** A 14-week quasi-experiment with 103 first-year undergraduates in Nigeria found AI-supported problem-based learning (ChatGPT and Teachable Machine inside the zone of proximal development) outperformed conventional instruction on posttest computational thinking and robotics-programming achievement, with no gender moderation (AI-PBL robotics study (2026)).
- **LLMs as tools for CT assessment and development.** Generative AI offers scalable ways to measure and scaffold CT. Physics CT assessment research showed LLMs can mirror human raters in scoring growth in Data Practices and Computational Problem-Solving Practices across large-enrollment Physics Education courses — while both humans and the LLM struggled with the more complex Systems Thinking construct, marking a clear boundary for automation. Visual query tracing shows how Visualization can scaffold abstract computation, building intuition that supports CT development. A taxonomy of conditionals-and-loops misconceptions provides fine-grained targets for Scaffolding and for automated misconception detection, connecting to Misconceptions about AI. These tools work best, however, when pedagogical design leads: the CS review found semester-long “Virtual Tutor” designs with scaffolded feedback consistently improved CT, whereas unstructured tool access increased frustration.

Durable competencies shift once implementation is automated: a workshop report names abstraction, computational thinking, and a “verification spectrum” as the skills to teach, citing a trial of nearly 1,000 students where unrestricted GPT-4 access raised practice performance 48% but cut exam scores 17% once AI was withdrawn (Lee et al. (2026)).

- **CT across K-12, teacher education, and assessment redesign.** CT spans the whole K-12 to Higher Education spectrum and is reshaping assessment. At the early-childhood end, AI-Play extends CT and AI literacy to Pre-K–K2 learners and non-technical families; at the university end, the OOP assessment study found 2026 GenAI systems outperform the average student on

authentic programming exams yet still fail on interfaces, abstract classes, and inheritance — recurring conceptual gaps that mark exactly where CT remains hard to automate. A randomized A/B crossover study showed that evaluation-and-critique tasks produce comparable outcomes to generation, suggesting CT can be exercised through judging flawed AI solutions, though gains require deliberate scaffolding. Underpinning all of this is the teacher: the microbit study links CT instruction directly to Teacher Education, and Socratic chatbot research ties the precise problem formulation that CT demands to measurable course performance.

- **A validated instrument locates where CT is hardest.** A 34-item computational-thinking test built with Evidence-Centered Design and validated by item-response theory across 461 AI-programming students concentrated difficulty in data representation, logical-operator sequencing, and loop structures rather than evenly across the syllabus (Zhang & Zhang (2026)).

CT and the shift from AI consumers to producers, creators, and designers

A central goal for CT in the AI era is moving students and instructors beyond *passive consumption* of AI outputs toward *creating, building, and designing* with and for AI — an agenda that aligns CT with constructionist learning (learning-by-making). The knowledge base's connected articles increasingly make this producer/creator/designer turn explicit. Model-authorship research reframes learning-by-construction with GenAI as a measurable "model authorship" process — students author, debug, and iterate on AI models rather than just consuming AI-generated code or answers. The CtL-GenAI framework operationalizes this as constructionism for the GenAI age, treating artifacts students build with AI as the engine of CT development. CT through AI-agent creation shows that designing, not merely using, AI agents exercises decomposition, abstraction, and algorithmic reasoning directly.

The new meta-analytic evidence sharpens this picture. A meta-review of 128 CT systematic reviews finds the field converging on a unified definition of CT as reasoning with abstract models that use computational steps and algorithms to solve problems — precisely the kind of model-building (rather than answer-consuming) thinking that production-oriented learning demands. CT-kindergarten robotics research shows even early-childhood learners become producers through play-based building with robots, using problem-based learning, storytelling, and scaffolding — a developmental first step toward seeing technology as something one constructs, not just operates. And evaluation-and-critique research demonstrates that CT can be exercised through judging and debugging flawed AI solutions — a producer stance toward AI output that resists the passive-consumption trap.

The practical upshot is that CT instruction should be designed so learners *make things with AI* — authoring models, building agents, constructing artifacts, and critiquing AI output — rather than receiving finished solutions. This both deepens CT and builds AI Literacy as participatory and creative rather than merely conceptual. Teachers, in turn, need support to move from using AI tools to designing AI-enhanced learning activities (see Teaching and Workplace Learning).

Reusing others' models belongs to the producer stance: implementing a published AI model — selecting, installing, running, and validating it — can be taught as a learnable, structured skill with a fallback route for each anticipated failure, and three BSc chemistry students with no programming background reproduced and extended an enzyme-substrate prediction model within four months (Achterweust et al. (2026)).

Practical guidance

For educators, the consistent message is that CT is developed through *explicit, scaffolded, observable* engagement rather than passive AI use. Pair robotics with explicit CT-concept mapping to the curriculum; use LLMs for Simulation, natural-language control, and scalable assessment of CT growth while reserving human judgment for constructs like Systems Thinking; and redesign assessments to emphasize evaluation and diagnosis of AI output over raw generation. Whatever the setting — unplugged play in early childhood, robots in secondary STEM Education, or Virtual Tutors in Higher Education — structure the activity so students must reason about decomposition, pattern, abstraction, and algorithm rather than receive finished solutions.

Connections to related concepts

Computational thinking is the shared cognitive foundation beneath AI Literacy and Critical Thinking, the curricular core of CS Education and K-12 computing, and the conceptual target that Robots in Education, Game-Based Learning, and Project-Based Learning are best designed to serve. It is deepened by large language models and Generative AI when those are used as scaffolding tools, and it is the skill that student-misconceptions taxonomies and CT-aware assessments aim to measure. Teachers develop it through Teacher Education and Workplace Learning, and it transfers across domains including Physics Education and STEM broadly.

- **Computational thinking predicts AI-assistant learning.** Eighth-grade students with high computational thinking significantly outperformed low-CT peers in an AI coding-assistant course, using the assistant for understanding rather than answer retrieval.

Common Misconceptions

- **“AI removes the need for computational thinking.”** The chat debugging study found that when undergraduates debugged circuits with LLM help, their **deficits in fundamental concepts and critical thinking — not the tool — were the limiting factor**. CT is what lets a learner evaluate an output rather than accept it, which is precisely the capacity that makes AI assistance usable at all.
- **“AI assistance levels the playing field in under-resourced settings.”** It can, under conditions. A **14-week quasi-experiment with 103 first-year undergraduates in Nigeria** found AI-supported problem-based learning (ChatGPT and Teachable Machine) produced gains, and AI as a “more capable peer” carries CT where other provision is absent. But that is a finding about a structured intervention, not a property of giving students a chatbot.
- **“LLMs cannot assess CT reliably.”** Physics CT assessment research found LLMs can **mirror human raters** in scoring growth in Data Practices and Computational Problem-Solving Practices across large-enrollment courses. The obstacle to scaling CT assessment has been rater capacity, and that constraint is softening — which shifts the design problem to whether the instrument is measuring CT rather than compliance.
- **“CT is a coding skill that robotics happens to teach.”** A **systematic review of 95 studies** confirms robotics fosters CT, creativity and problem solving, but also that the **setting moderates**

the outcome: game-based delivery suits informal settings while gamification differs in formal ones. CT is a set of practices that transfer unevenly, so the transfer claim needs the task design it actually used.

Connected Concepts

- CS Education
- STEM Education
- AI Literacy
- K-12
- Prompt Engineering
- Adaptive Learning
- Large Language Models (LLMs)
- Generative AI
- Higher Education
- Robots in Education
- Game-Based Learning
- Project-Based Learning
- Physics Education
- Scaffolding
- Critical Thinking
- Teacher Education
- Simulation
- Socratic Method
- Misconceptions about AI
- Agentic AI

Connected Articles

- AI-supported problem-based learning for enhancing computational thinking
- Computational thinking development in AI agent creation: A mixed-methods study
- Reshaping Undergraduate Computer Science Education in the Generative AI Era
- Understanding Student Perceptions, Mistakes, and Debugging Approaches when Solving Natural Language Programming Tasks
- Using LLMs to Detect Growth in Computational Thinking in Introductory Physics
- Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot
- Evaluating a Visual Query Tracer and Builder for Learning Declarative Logic Programming
- A review of intervention designs of LLM Integration in Undergraduate Computer Science Education
- Academic League of Artificial Intelligence: An Integrative Perspective of Teaching, Research, and Extension

- AI-Play: A Framework for Teaching Artificial Intelligence Concepts through Unplugged Activities in Early Childhood Education
- EduSim-LLM: An educational platform integrating large language models and robotic simulation for beginners
- Computational thinking to enhance educational robotics in secondary school's curriculum
- Coding, robots, computational concepts, and machine learning using the microbit card and the Maqueen and Nezha kits. A study in initial teacher training
- Chat Debugging: An Exploratory Study of Human-AI Collaboration to Debug Analog Circuits
- How Students (Mis)understand Conditionals and Loops – A Taxonomy
- Revisiting the Performance of Generative Artificial Intelligence on Introductory Object-Oriented Programming Assessments: Insights from 2026
- Game-based and gamified robotics education: A comparative systematic review and design guidelines
- Is Solving Better Than Evaluating GenAI Solutions?
- Integrating AI into computational thinking: development and validation of an assessment tool for higher education students — Computational Thinking in AI Training Test (CTAT)
- Exploring the effect of computational thinking levels on students' learning performance, cognition, and behavior when using AI coding assistants — Computational Thinking Levels and AI Coding Assistants (2026)
- The AI writes the code, the student writes the model: A theory and measurement programme for learning by construction with generative AI — Model authorship: theory & measurement for learning-by-construction with GenAI
- Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education — CtL-GenAI: constructionism framework for artifact construction
- Computational thinking: A meta-review of systematic reviews and meta-analyses — CT meta-review of 128 systematic reviews
- Fostering computational thinking through robotics in kindergarten: A systematic review of learning strategies, frameworks, and assessment — Systematic review of CT via robotics in kindergarten
- PRAISE: A Reproducible Workflow for Non-Programmer Scientists to Implement Published AI Models — PRAISE: A Reproducible Workflow for Non-Programmer Scientists to Implement Published AI Models

Theories and frameworks (Foundations of AI in education)

SAMR Model

> **The SAMR model** — a technology-integration framework developed by Ruben Puentedura that classifies the extent to which a technology transforms learning along four levels: **Substitution, Augmentation, Modification, and Redefinition**. The lower two levels (Substitution, Augmentation) *enhance* an existing task — the technology does what was done before, better or more conveniently; the upper two (Modification, Redefinition) *transform* it — the task itself changes to something not previously possible. In AI in education, SAMR is the standard lens for asking whether generative AI is being used to incrementally improve existing practice or to reconceptualize learning, and it sits alongside TPACK as a way of describing how teachers integrate technology rather than why they accept it.

Questions to Consider

- When AI is introduced into a course, is it a Substitution (a chatbot replaces a search box) or a Redefinition (a task becomes possible that was not before)? What determines which level is appropriate — and is transformation always the goal?
- SAMR and technology adoption models answer different questions: adoption theory asks *why* a teacher or institution accepts a tool; SAMR asks *how deeply* the tool changes learning. Which question does a given AI-integration study actually answer?
- A systematic review of AI integration in higher education found most uses sat at the Substitution or Augmentation level, with only one study approaching Redefinition. If that is typical, what does it suggest about the gap between AI's potential and its classroom reality?
- SAMR is frequently invoked in teacher professional development to help educators plan technology use. Does classifying a lesson's SAMR level change what a teacher actually does, or is it chiefly a descriptive label?
- Critics argue SAMR, like TPACK, rests on a humanist ontology that treats cognition as unchanged by technology, and that it says nothing about power, data ownership, or equity. Is a level-of-integration lens sufficient, or does AI-era integration need a more critical frame?

Introduction

SAMR describes the depth of technological transformation of learning tasks. Its four levels form an ascending scale from enhancement to transformation: **Substitution** (the tool replaces another with no functional change — a chatbot in place of a search engine), **Augmentation** (the tool replaces and improves — a word processor's spell-check over a typewriter), **Modification** (the task is significantly redesigned — students collaborate in real time on a shared AI-generated draft), and **Redefinition** (new tasks previously inconceivable become possible — learners co-create with a generative model in ways that have no non-AI analogue). The model is widely used in educational technology research and teacher professional development as a vocabulary for planning and evaluating technology integration, and it is a standard

companion to TPACK and to technology-adoption frameworks — though it answers a different question than either.

What the four levels mean

- **Enhancement (lower half):** Substitution and Augmentation improve an existing task without changing its nature. Most routine AI use — question generation, quick text generation, summarization — sits here: it is faster and more convenient but does not alter what the learner is asked to do.
- **Transformation (upper half):** Modification and Redefinition change the task itself. Vibe coding, real-time co-construction with a model, and adaptive interactive dialogue are tasks that were not possible before generative AI, and represent the transformative end of the scale.

SAMR is frequently paired with the ICAP framework because the two align: the four cooking-to-learning scenarios in Rummel, Nachtigall & Panadero (2026) map ICAP engagement modes onto SAMR levels — ICAP *Passive* with SAMR *Substitution*, *Active* with *Augmentation*, *Constructive* with *Modification*, and *Interactive* with *Redefinition* — illustrating a progression from passive delegation to interactive co-construction.

Evidence from the knowledge base

- **AI integration in higher education is largely incremental, not transformative.** AlSheikh et al. (2026), in a PRISMA systematic review of 22 intervention studies screened from 959 records, graded AI integration with the SAMR model and found most studies clustered at the **Substitution or Augmentation** level, with fewer at Modification and only one approaching Redefinition. AI was typically introduced to improve existing practice — dominated by assessment automation and personalized-learning support — rather than to reconceptualize curricula or learning outcomes.
- **SAMR is a common analytical lens for GenAI-driven curriculum change.** Sabani et al. (2026) map five curricular shifts (static to dynamic, transmission to capability, local to institutional) onto established lenses including SAMR and constructive alignment, using the model to clarify the pedagogical mechanisms by which GenAI reshapes curriculum.
- **SAMR and TPACK anchor teacher-technology integration standards.** Crompton et al. (2026) situate their six faculty technology standards against existing frameworks — Technological Pedagogical Content Knowledge (TPACK), RAT, SAMR, SETI — and standards (ISTE, UNESCO, DigCompEdu), most of which target K-12 educators or only the teaching portion of faculty roles, leaving a gap in higher-education faculty development.
- **SAMR is a target of the posthumanist critique.** Elsayed (2026) critiques TPACK, SAMR, and AI Literacy models for sharing a humanist ontology that presumes a bounded learner whose cognition is fundamentally unchanged by technological mediation, arguing these instrumentalist frameworks cannot address AI's constitutive role in cognition.
- **A framework for integration, not a framework for power.** Poudyal (2026) evaluates SAMR alongside TPACK and other integration frameworks and finds none address equitable power, data ownership, or accountability, motivating an alternative ecological co-agency framework.

- **Student use maps to SAMR as well, and feedback spans every level.** Coding the GenAI declarations of 31–36 students in a physics unit placed learning at substitution–augmentation, formatting at substitution, and task-doing at modification–redefinition, while feedback — checking, clarifying, verifying — appeared at all four levels (Quince and Faulconer (2026)).
- **Depth and inclusion are separate axes.** Jita, Jita & Omoniyi (2026) pair SAMR with UDL across 38 sources and argue that Redefinition-level tasks can still exclude students whose language, device, or connectivity does not fit the design.

SAMR, TPACK, and technology adoption: how they differ

Three frameworks are frequently conflated but answer distinct questions:

- **Technology adoption models** (TAM, UTAUT) explain *why* an individual or institution accepts and continues using a technology — perceived usefulness, ease of use, and social influence.
- **TPACK** describes the *knowledge* a teacher needs to integrate technology effectively — the interplay of technological, pedagogical, and content knowledge, extended in the AI era to AI-TPACK/GenAI-TPACK.
- **SAMR** classifies *how deeply* a technology transforms a learning task, from enhancement to redefinition.

SAMR is best understood as an integration-depth lens used in planning and evaluation, complementing adoption theory (which explains uptake) and TPACK (which explains teacher capability). In the AI era, it is most productively used to ask whether generative AI is being applied to enhance existing tasks or to enable genuinely new ones — a distinction that runs throughout the knowledge base's assessment and curriculum research.

Implications for practice

- **Use SAMR to ask the depth question, not to prescribe transformation.** Enhancement is not inherently inferior; many routine AI uses are legitimate Substitutions. The model is diagnostic, clarifying what a given use actually changes.
- **Pair it with ICAP.** SAMR describes what the *task* becomes; ICAP describes how the learner *engages*. Used together they distinguish surface substitution from deep interactive co-construction.
- **Complement it with adoption and equity lenses.** SAMR says nothing about why a tool is adopted or who benefits. Pair it with adoption models and equity analysis to avoid a depth label substituting for a critical evaluation.
- **Treat evidence of incremental integration as a finding, not a failure.** If most AI integration clusters at Substitution/Augmentation, the design task is not to force Redefinition but to recognize that transformative use requires different task designs, not just better tools.

Common Misconceptions

“Higher on SAMR is better teaching.” SAMR is a lens for asking whether AI *reconceptualises* learning or *improves* existing practice; it is not a quality ranking, and Re-definition is not the correct answer for every task. A substitution that removes an unproductive step is a success judged on learning, not on the level it occupies.

“AI adoption is progressing up the ladder.” The distribution is concentrated at the bottom. A systematic review of AI integration in higher education found **most uses sat at Substitution or Augmentation, with only one study approaching Redefinition**. SAMR’s practical use in this literature is therefore largely diagnostic — it names where the field actually is.

“SAMR and TPACK are competing frameworks.” They describe different things: SAMR describes the *degree of transformation* in a task, while TPACK describes the *knowledge* a teacher needs to integrate technology well. A teacher can be highly TPACK-capable and still operate at Substitution, which is why the two are used together rather than chosen between.

“A tool that is transformative at one level is transformative at all levels.” The same generative tool can support a Substitution in one course and a Redefinition in another, because the level is a property of the task design rather than of the technology. Attributing the level to the tool produces adoption decisions in place of design decisions.

Connected Concepts

- AI in Education — AI in education (umbrella)
- Technological Pedagogical Content Knowledge (TPACK) — Technological Pedagogical Content Knowledge
- Technology Adoption Models — Technology adoption models
- ICAP Framework — The ICAP framework of cognitive engagement
- Technologies — AI technologies and techniques
- Teacher AI Competency — Teacher AI competency
- Educational Development — Educational development
- Learning Design — Learning design
- K-12 — K-12 education
- Higher Education — Higher education
- Generative AI — Generative AI

Connected Articles

- Mapping artificial intelligence integration in higher education: A systematic review using the FACETS and SAMR frameworks — AI integration in higher ed graded with SAMR: mostly Substitution/Augmentation
- With a Thermomix You Lose the Ability to Cook: A Kitchen Machine Analogy for Applications of Generative AI in Education — ICAP and SAMR mapping the four cooking-to-learning scenarios

- Rewriting the Curriculum: A Systematic Review of Generative AI-Driven Pedagogical Change and Emerging Systems of Learning in Higher Education — SAMR among the lenses for GenAI-driven curriculum change
- Designing faculty standards for technology integration in higher education institutions: a design-based research study — SAMR among the frameworks informing faculty technology standards
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI — The posthumanist critique of SAMR's humanist ontology
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education — SAMR's silence on power, data ownership, and accountability
- Student GenAI use under changing institutional policies: a mixed-methods case study in undergraduate physics — Student GenAI use under changing institutional policies: use functions mapped to SAMR levels (Quince & Faulconer 2026)
- AI in mathematics classrooms: A synergistic strategy for diversity and inclusivity — AI in Mathematics Classrooms: A Synergistic Strategy for Diversity and Inclusivity

Technological Pedagogical Content Knowledge (TPACK)

> **Technological Pedagogical Content Knowledge (TPACK)** — the framework (Mishra & Koehler, 2006) describing the integrated knowledge teachers need to use technology effectively in teaching: the interplay of Technological Knowledge (TK), Pedagogical Knowledge (PK), and Content Knowledge (CK), and their intersections. In the AI era, TPACK has been extended to **AI-TPACK** / **GenAI-TPACK**, modeling how teachers integrate generative AI into content-area instruction. It is the dominant theoretical lens for understanding how teacher AI competency is structured and built through professional development.

That dominance is also partly a retrieval artifact: in a PRISMA scoping review of 195 technology-supported teacher-education studies, digital competence, TPACK and DigCompEdu were explicit search descriptors, so the 46.5% share of competence frameworks describes the retrieved corpus rather than the field (Patiño Hernández et al. (2026)).

Questions to Consider

- TPACK claims effective teaching with technology isn't the sum of separate skills (knowing your subject + knowing teaching + knowing the tool) but the product of their interplay. Think of a lesson that genuinely worked with a technology. Which combinations of content, pedagogy, and tech knowledge — not any single one — seemed to be doing the work?
- A common assumption is that a teacher who is 'tech-savvy' is therefore ready to teach with AI. Where might that assumption fail — for instance, when a technically fluent teacher still uses AI in a pedagogically shallow or content-inaccurate way? What would 'competence' look like that a simple tech-skills test misses?
- The AI era reframes the technology in TPACK from a passive tool to an active agent that can plan, generate, and tutor. If a teacher's job shifts from operating a tool to orchestrating an AI that acts on its own, what new knowledge does that demand — and can any static checklist capture it?
- The page suggests that professional development should train the intersections, not just the tools. Think about the last technology training you attended or designed. Was it mostly 'how to use the software,' or did it build content and pedagogy together with the technology? Which approach would you expect to change classroom practice more, and why?
- Research found different 'teacher archetypes' — optimizers, creators, passive observers — benefit from different kinds of support. Which archetype do you most resemble when using AI in teaching, and what kind of Scaffolding do you think would help you most? Would your learners describe you the same way you do?
- Some researchers argue effective AI integration emerges from a teacher's beliefs and sense of efficacy, not just their knowledge. What do you believe about AI's role in learning, and how might that belief — more than your technical skill — shape whether and how you actually integrate it?

Introduction

- **Crompton et al.** DBR operationalizes faculty technology-integration standards that extend the TPACK framework into institutional practice.

The Framework

TPACK holds that effective technology integration is not the sum of separate knowledge domains but the product of their **dynamic interplay**. The framework comprises three base domains and four intersections:

- **Content Knowledge (CK)** — knowledge of the subject matter to be taught.
- **Pedagogical Knowledge (PK)** — knowledge of teaching methods, strategies, and how students learn.
- **Technological Knowledge (TK)** — knowledge of how to use tools and technologies, including generative AI.
- **Pedagogical Content Knowledge (PCK)** — how to teach specific content effectively.
- **Technological Content Knowledge (TCK)** — how technology shapes and represents content.
- **Technological Pedagogical Knowledge (TPK)** — how technology supports or constrains teaching strategies.
- **TPACK** — the emergent, integrated knowledge at the center, where all three domains interact to enable technology-enhanced, content-specific teaching.
- **The framework dominates the field by default, and is stretched to fit.** In a PRISMA-guided review of 78 studies of AI-supported instructional design, only 19 applied any named competence framework — and TPACK and its variants accounted for **17 of those 19**, used productively as an analytical lens but stretched beyond their original scope, since TPACK was not designed for AI-specific capacities. Purpose-built extensions are correspondingly rare: **Intelligent-TPACK appeared in just five studies**, usually paired with AI Literacy to handle developmental progression (Spyropoulou & Kameas, 2026).
- **Research proceeds untheorised while policy frameworks go untested.** The same review found **76% of studies inferred competences from practice with no theoretical mapping at all**, and neither DigCompEdu nor the UNESCO AI Competency Framework for Teachers was applied as an analytical framework in any of the 78 — a disconnect running in both directions, since empirical work accumulates no shared vocabulary while the frameworks meant to guide practice remain empirically untested in this context.

AI-TPACK and GenAI-TPACK

The AI era has pushed the framework toward a technology-with-intelligence reading. Rather than a passive tool, generative AI is an active agent that can plan, generate content, tutor, and adapt — so integration

knowledge increasingly includes **orchestration**: deciding when and how AI acts, scaffolds, or yields to human judgment.

- **Beyond discrete knowledge.** AI-TPACK research argues effective AI integration emerges not from possessing separate domains but from the dynamic interplay of **systems thinking**, **pedagogical beliefs**, and **Self-Efficacy** — challenging static, checklist-based models of teacher AI competency. Teacher archetypes (Systematic Optimizers, Prolific Creators, Passive Observers) emerge from how teachers design multi-agent instructional workflows.
- **What integration frameworks leave out.** A co-agency critique holds that TPACK and SAMR address teacher knowledge and adoption levels but leave power, data ownership, and accountability unaddressed, so integration knowledge needs an explicit ethical boundary rather than another knowledge domain (Poudyal (2026)).
- **Cross-level evidence for the pedagogical core.** A multilevel study of 46 teachers and 2,832 secondary students found technical AI knowledge alone was insufficient — even slightly dampening students' perceptions of AI for social good — while pedagogical AI knowledge (TPAIK) is what fostered students' perceptions and behavioral intention to learn AI. The result distills to a **"pedagogy first, technology second"** guideline that echoes the mediating-role findings above.
- **Ethics as an integrative mediator, not a boundary.** In a survey of 454 university teachers, isolated AI-technological knowledge had a *negative* direct association with integrated AI-TPACK ($\beta = -0.303$) while its total effect stayed positive ($\beta = 0.639$), running through pedagogical, content, and ethical knowledge (Chen et al. (2026)). Ethical knowledge also channeled the effect onward, predicting both pedagogical ($\beta = 0.353$) and content knowledge ($\beta = 0.269$).
- **A review lens for the whole field.** A systematic review from a TPACK perspective (Liu & Zhong, 2025) analyzed 71 empirical studies of GenAI in student learning, finding an overall positive effect (Hedges' $g = 0.752$) and identifying GenAI literacy for students and **GenAI-TPACK professional development for teachers** as the two critical priorities for the field.
- **Proficiency alone does not predict pedagogical integration.** Choi et al. (2026) measured teachers' Intelligent-TPACK to segment participants and observed that even AI-proficient novices relied passively on AI output during lesson design, whereas experienced teachers — with lower measured AI-TPACK — critically re-engaged and adapted AI suggestions to pedagogical context. The result reinforces the pattern above: AI-TPACK translates into sound classroom use through experienced pedagogical judgment, and Teacher Education support must therefore target the *application* of AI knowledge, not its mere possession.
- **Teacher education context.** TPACK is instrumental in cultivating teachers' competency to integrate technology into curriculum-specific instruction, which is why teacher-education and PD research (e.g., intensive GenAI PD programs, AI-TPACK readiness among pre-service teachers) increasingly measures it as the outcome of interest.
- **Pedagogical knowledge mediates GenAI integration.** Mohebi and ElSayary (2026) surveyed **325 in-service teachers across 26 countries** and interviewed seven, using an explanatory sequential mixed-methods design to model TPACK-GenAI. Technological Knowledge (TK),

Pedagogical Knowledge (PK), and Pedagogical Content Knowledge (PCK) each associated with overall TPACK-GenAI, but **Technological Pedagogical Knowledge (TPK) mediated** these links — evidence that the "from proficiency to pedagogy" move matters: translating GenAI skill into sound classroom use runs through pedagogical-technological integration knowledge, not tool familiarity alone.

- **In higher education, content expertise does not transfer to GenAI integration.** Sutedjo, Chowdhury & Liu (2026) adapted the TPACK-21 instrument to survey **127 faculty** at a U.S. research university on using GenAI to teach 21st-century skills. Faculty reported strong CK (M = 5.15) and PCK (M = 4.70) but low technology-integrated knowledge — TPK (M = 2.62), TCK (M = 2.75), and overall TPACK (M = 2.55, the lowest domain) — and CK showed **no significant correlation with TK or any technology-integrated domain** (r = .11–.15, ns). The three technology-integrated domains inter-correlated so strongly (r = .81–.91) that they may function as a single GenAI-integration factor. The result reinforces the *training the intersections* design principle: faculty development must deliberately build GenAI-integration knowledge through discipline-specific activities rather than assume subject-matter expertise will carry over, and treat the technology-integrated domains as a shared GenAI-literacy foundation.
- **Institutional mode and training level interact.** Mnguni et al. (2026) compared 186 final-year science student teachers at a South African campus-based university (n = 85) and a distance education university (n = 97). Self-reported TPACK was higher on campus (64.0% versus 47.4%), Pedagogical Knowledge was the least reported domain in both groups (53% on campus), and the level of AI training was associated with self-reported TPACK only at the distance institution, where completing a five-credit short course predicted *weaker* reported TPACK than no training at all (p = .039, versus p = .607 on campus). Readiness therefore tracks the institutional provision context rather than hours of training alone, and the authors caution that self-reported readiness cannot stand in for performance evidence.

A complementary measurement warning comes from the same author's Capability–Decision Model: when TPACK is self-reported and perceived behavioral control is measured as Self-Efficacy, the two may not be empirically distinguishable, so a study cannot tell whether capability or general confidence predicts intention (Mnguni (2026)). - **Integrated TPACK moves most when AI is scaffolded inside authentic problem-based tasks.** Chen and Osman (2026) compared an eight-week AI-supported CTD-PBL module with conventional instruction for **130 third-year pre-service physics teachers** in an intact-class quasi-experimental design (65 per condition), with groups using DeepSeek through task-specific prompt templates and every AI output required to pass human verification before entering an instructional artifact. The module group reported higher post-test TPACK (M = 4.04 vs. 3.40, $p < 0.001$, d = 1.02) and higher perceived collaborative problem solving (M = 3.62 vs. 3.05, d = 0.88), with significant group × time interactions on both outcomes. Where the gains landed is the TPACK-relevant detail: the largest dimensional effects were in the integrated domains — TPCK (d = 1.21), PCK (d = 1.06) and TPK (d = 0.95) — and the collaboration gains were clearest in shared knowledge building and social regulation, i.e. the intersections rather than the base domains. The authors present these as differential change associated with an integrated instructional condition, not as an AI effect: AI was never isolated from the PBL task chain, structured collaboration,

instructor scaffolding, peer feedback or reflective revision, and both outcomes were questionnaire-based perceptions of competence rather than demonstrated classroom performance.

- **An intervention can move the base domain first.** A six-month professional development program built directly on the Intelligent-TPACK framework raised technical AI knowledge most (AITK: 3.92 to 4.43, $t(63) = 3.856$, $p < .001$, $d = .48$), technological-pedagogical knowledge next (AITPK: $d = .33$) and integrated AITPACK least ($d = .26$), with ethical awareness left comparatively stagnant (Tan, Cheng & Ling, 2025). The ordering is the mirror image of Chen and Osman's integrated-domain gains, and both are self-report.

AI-TPACK as the mediator between literacy and classroom integration. A structural equation model of Chinese pre-service science teachers (Zou, Li, Wang & Du, 2026) positions AI-TPACK not as a parallel competency but as the transmission mechanism through which general AI Literacy becomes teaching practice. AI literacy predicted AI-TPACK strongly, AI-TPACK in turn predicted science teaching Self-Efficacy, and teaching self-efficacy was the strongest single predictor of the intention to teach through AI-integrated inquiry.

The full serial chain (AI literacy → AI-TPACK → self-efficacy → intention) was significant, as were the separate indirect routes through AI-TPACK and through self-efficacy; taken together, most of AI literacy's association with intention ran through these mediators rather than directly, and the result held after controlling for gender, year of study, major, and AI use frequency. The model's practical claim is a sequence with an entry point: AI literacy is necessary but insufficient, and the work of integration happens where technological, pedagogical, and content knowledge are combined — which is also where teachers' confidence in teaching the subject is built. - **Validation as a fourth competency.** Orhon, Cekerol and Ugur (2026) extend the model with **AI-Validation Knowledge** — subjecting probabilistic AI output to discipline-specific verification before treating it as evidence of a legitimate decision — and pair it with a process-oriented rubric for design education.

Why It Matters in AI Education

TPACK is the organizing framework for the teacher-side of the knowledge base's evidence base. It explains why teacher AI competency is more than tool fluency: teachers must integrate technological, pedagogical, and content knowledge together to turn AI into learning gains. The knowledge base's Teacher AI Competency page covers the competency dimensions; TPACK is the *knowledge structure* that underlies them. Research on teacher confidence, professional development, and the transforming teacher role all operate within (or against) this framework. The framework is now being extended to evaluate whole programs: Wu & Li (2026) build an AHP-Fuzzy-AHP evaluation system for AI certificate programs on TPACK dimensions and find that faculty professional competence — not technical infrastructure — is the largest gap between expert priority and current provision, signaling that credentialing should invest in teachers' integrated pedagogical capacity.

The mediation runs mostly through ease of use. Zhao (2026) tested six indirect paths from AI literacy and TPACK to deep learning in 423 pre-service teachers: TPACK through perceived ease of use was largest (0.212) and AI literacy through usefulness smallest (0.033), so integration knowledge worked through usability rather than utility. **The components do not weigh equally in the AI case.** Among 988 pre-service

teachers, TCK (β = 0.67) and TPK (β = 0.41) predicted integrated AI-TPACK while TK alone did not (β = −0.10, p = 0.066), and integrated TPACK predicted attitude toward GenAI (β = 0.75) (Khalil et al., 2026).

Design Implications

1. **Train the intersections, not just tools.** PD should build technological, pedagogical, and content knowledge together rather than offering isolated tool training — the core TPACK design principle.
2. **Treat AI as an agent, not an appliance.** AI-TPACK extends the framework toward orchestration of AI agents, requiring systems thinking and pedagogical judgment about when AI should act.
3. **Differentiate PD by teacher profile.** Different teacher archetypes (optimizers, creators, observers) benefit from different scaffolding — advanced frameworks, rapid feedback, or explicit modeling respectively.
4. **Assess integrated competence.** TPACK-oriented outcomes (e.g., AI-PCK gains) should be measured as integrated capability, not self-reported tool familiarity.

Common Misconceptions

- **"TPACK's dominance reflects its explanatory power."** That dominance is **partly a retrieval artifact**: in a PRISMA scoping review of **195 technology-supported teacher-education studies**, digital competence, TPACK and DigComp **dominate the indexed literature**. Prevalence in a search is a property of the vocabulary the field uses, not proof that the framework explains more.
- **"A well-known framework is a validated one for AI."** TPACK was not designed for AI-specific capacities, which is why Intelligent-TPACK was developed — and it appears in only **five studies** in the 78-study review. Using TPACK for GenAI competence stretches it beyond its construction.
- **"Applying a framework means the research is theorised."** The same review found **76% of studies inferred competences from practice with no theoretical mapping**, so TPACK's presence in the field coexists with most research being untheorised. A named framework is not the same as a framework doing work.

Connected Concepts

- Teacher AI Competency
- Educational Development
- Teaching
- Generative AI
- Learning Design
- AI Literacy
- Scaffolding
- Metacognition
- Higher Education
- K-12
- Meta-Analysis and Systematic Review

- Teacher Education

Connected Articles

- Perceived AI literacy and TPACK in pre-service teacher education: mediating roles of perceived usefulness, ease of use, and value in blended learning — Perceived AI literacy and TPACK in pre-service teacher education: mediation through usefulness, ease of use and value (Zhao 2026)
- Evaluation indicator system for AI certificate programs — Evaluation Indicator System for AI Certificate Programs
- Pedagogy first, technology second: Cross-level relationships between teacher professional knowledge and student learning in artificial intelligence (AI) education — Cross-level study: ‘pedagogy first, technology second’ — TPAIK outweighs technical TAIK for student outcomes (Shen et al. 2026)
- From proficiency to pedagogy: A mixed-methods study of in-service teachers’ TPACK-GenAI and the mediating role of pedagogical knowledge — In-service teachers’ TPACK-GenAI and the mediating role of pedagogical knowledge (Mohebi & ElSayary 2026)
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education
- Designing faculty standards for technology integration in higher education institutions: a design-based research study — Faculty standards for technology integration (TPACK-related DBR)
- Integrating generative Artificial Intelligence into student learning: A systematic review from a TPACK perspective — Integrating generative AI into student learning: A systematic review from a TPACK perspective
- Modeling AI-TPACK in practice: Insights from teachers’ multi-agent workflow design — Modeling AI-TPACK through teacher multi-agent workflows
- AI literacy-related domains and AI-TPACK readiness among preservice mathematics teachers: A factor-informed structural equation modelling study — AI-TPACK readiness among pre-service mathematics teachers
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction in lesson design: Intelligent-TPACK, experience, and proficiency interplay (Choi et al. 2026)
- Efficacy of an Intensive Generative AI Professional Development Program on Pedagogical Content Knowledge (AI-PCK) and the Comparative Analysis of Learning Gain between Experienced and Pre-service Teachers — Intensive GenAI professional development and AI-PCK gains
- Towards Synergistic Teacher-AI Interactions with Generative Artificial Intelligence — Five-level teacher-AI teaming framework
- AI adoption among teachers: Insights on concerns, support, confidence, and attitudes — Teacher confidence and AI adoption
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher education for AI literacy via self-determination theory

- Development and evaluation of artificial intelligence literacy training for teacher education students — Design-based research GenAI literacy training
- Rethinking Generative AI Literacy: An Integrative, Developmental, and Dialectical Framework for K-12 Teacher Education — Rethinking GenAI literacy in teacher education
- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review — Social-emotional competencies and AI literacy
- GenAI as a runaway object in higher education: A socio-cultural view on AI-influenced academic practice in mathematics — GenAI and mathematics in higher education
- How AI Is Changing Teaching Workflows. — How AI is changing teaching workflows
- Assessing faculty self-perceived knowledge in using generative AI to teach 21st-century skills — Faculty self-perceived TPACK-21 knowledge for GenAI in higher education (Sutedjo, Chowdhury & Liu 2026)
- Towards a New AI-TPACK Framework: Evidence from China — Towards a New AI-TPACK Framework: ethics as an integrative mediator of technical AI knowledge (Chen et al. 2026)
- AI training and science student teachers' TPACK in campus-based and distance education: a comparative study — Comparative survey of 186 South African science student teachers: campus advantage in self-reported TPACK, and AI training associated with weaker reported TPACK at the distance institution
- From AI literacy to AI-integrated inquiry-based science teaching: the serial mediating roles of AI-TPACK and science teaching self-efficacy among Chinese pre-service science teachers — AI-TPACK and science teaching self-efficacy serially mediate AI literacy's effect on inquiry-integration intention (Zou et al. 2026)
- Changes in pre-service physics teachers' TPACK and collaborative problem solving associated with an AI-supported CTD-PBL module: A quasi-experimental study
- Enhancing teachers' AI competency: A professional development intervention study based on intelligent-TPACK framework — Intelligent-TPACK professional development for university teachers: dimension-resolved gains, attendance over self-perceived engagement — AI-supported CTD-PBL module and pre-service physics teachers' TPACK and collaborative problem solving (Chen & Osman 2026)
- Assessing Human-AI Collaboration in Design Education: A Process-Oriented Rubric Grounded in an Extended AI-TPACK Framework — Assessing Human-AI Collaboration in Design Education: a process-oriented rubric grounded in an extended AI-TPACK framework
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Ordered capability-first model of teacher AI readiness and its construct-overlap warning
- From digital competence to AI-responsive pedagogy: a scoping review of technology-supported teacher education — Scoping review warning that competence-framework dominance partly reflects search descriptors, not field prevalence
- The Role of Integrated TPACK in Empowering Pre-Service Teachers and Shaping Their Attitudes Toward Generative AI in Teaching — The Role of Integrated TPACK in Empowering Pre-Service Teachers and Shaping Their Attitudes Toward Generative AI in Teaching

Connected FAQs

- How Do I Design Faculty Development for AI That Actually Changes Practice?

Learning and instruction

Core pedagogies

Pedagogies and Teaching Strategies

> **Pedagogies and teaching strategies** — the methods and approaches educators use to teach and facilitate learning, and the umbrella concept for the knowledge base's coverage of how teaching happens (in contrast to Learning Theories, which explains how learning happens). In AI in education, pedagogy is central because the choice of teaching strategy shapes how AI tools are deployed: the same generative-AI tool can be a scaffold under one pedagogy, a Socratic interlocutor under another, or an answer-generator under a third. The knowledge base documents individual pedagogies and treats them as the instructional lens through which AI's design and classroom use are evaluated.

Questions to Consider

- What's the difference between a teaching strategy (pedagogy) and a theory of how learning happens? Can you name a strategy you use and the learning theory it might rest on?
- The page argues every AI tool 'embeds pedagogical assumptions' whether the designer states them or not. Take a chatbot that just answers questions—what pedagogy is it quietly enacting, and is that intentional?
- The same generative AI can be a scaffold under one pedagogy, a Socratic partner under another, or an answer generator under a third. Can you describe a single tool being used in these three different ways?
- Evidence suggests *how* AI is used matters as much as *whether* it's used. Have you observed the same AI helping one class and harming another? What differed?
- If you were advising a school on buying an AI tool, which questions would you ask to uncover the pedagogy embedded in it—rather than just its feature list?
- Think of a learner-centered strategy you've tried (active, collaborative, project-based). What made it work or fall flat, and how might an AI tool have changed that outcome?

Introduction

Pedagogy and teaching strategy concern *how* educators teach — the activities, structures, and methods that organize learning — while Learning Theories explains the underlying mechanisms of *how learning happens*. The two are complementary: a pedagogy operationalizes one or more theories, and the knowledge base treats pedagogy as the bridge from theory to classroom practice. Every AI tool embeds pedagogical assumptions about the desired instructional interaction, whether the designer states them or not.

The pedagogy landscape

The knowledge base documents a rich set of individual teaching strategies and pedagogies, organized into families:

- **Student-centered and active approaches.** Active Learning (students engaged in doing and thinking rather than passively receiving), Project-Based Learning (learning through extended projects), Experiential Learning (learning through direct experience), and Learning by Teaching (learning by explaining to others).
- **Collaborative and social approaches.** Collaborative Learning (learning through group work), Sociocultural Learning (learning through social participation and mediation), and Socratic questioning (learning through guided dialogue and questioning).
- **Experience-based approaches.** Experiential Learning (learning through direct experience and reflection), Situated Learning (learning in authentic contexts), and Embodied Learning (learning through physical/embodied interaction).
- **Structured and guided approaches.** Scaffolding (temporary, fading support), Learning Design (systematic design of instruction), Self-Regulated Learning (learners directing their own learning), and Sociocultural Learning (including structured, teacher-guided sociocultural support).
- **Online and distance pedagogies.** Online teaching and learning is itself a pedagogical context, not just a delivery channel: the medium shapes which strategies are viable (Active Learning rethought for asynchronous forums, Collaborative Learning via digital discussion, tutoring agents replacing face-to-face interaction). In this medium, AI raises both new opportunities (scalable personalization, always-on support) and new risks (academic integrity, cognitive offloading), making pedagogical intent decisive.
- **Motivation and engagement approaches.** Game-Based Learning (learning through games), Self-Determination Theory (supporting autonomy, competence, relatedness), and Motivation-oriented strategies.
- **equity-conscious pedagogies.** Culturally relevant pedagogy, Universal Design for Learning, Critical Pedagogy, and Inclusive Learning ensure strategies serve diverse learners.

Approaches are not sequences, and the difference decides outcomes. Everything above describes *what kind* of teaching is happening. Pedagogical patterns describe the *order* of moves inside a lesson — what students do first, where AI enters, and where human judgment stays — and the knowledge base documents those tested sequences separately, because the same tool helps or harms depending on its position in the order. Attempting a problem before AI offers help, and receiving hints rather than answers, is the most consistently supported arrangement in the evidence base; putting the assistant first is one of the best-documented ways to depress later unassisted performance. A pedagogy adopted without deciding that order leaves the decisive variable unset.

How pedagogy appears in AI in education

The knowledge base's research examines pedagogy at the intersection of AI and teaching in several ways:

- **AI as a pedagogical agent.** AI tools embody pedagogies — a tutor built on Socratic questioning prompts learners to reason, while an answer-generating chatbot may default to direct provision

(see Reducing AI Misuse on why the pedagogical stance matters). The agentic AI literature shows that grounding agents in instructional-design theory outperforms raw prompting. Moganadas et al. (2026) reframe this role formally: rather than a dyadic instructor–student model with GenAI as an external supplement or threat, they propose a nested **instructor–student–GenAI triadic model** in which GenAI operates as a bounded *didactic-pedagogical mediator* within a shared didactic mediation space governed by institutions and stakeholders — yielding five researchable propositions on learning mediation, instructor-role transformation, AI literacy and learner agency, AI-transparent process-oriented assessment, and institutional AI Governance.

- **Pedagogy determines AI's effect.** A recurring finding is that *how* AI is used matters as much as *whether* it is used. Instructional-guidance research and guardrailed-tutor RCTs show the same AI can harm or help depending on the pedagogical wrapper (hints vs. answers, structured vs. open use).
- **Pedagogical knowledge outweighs technical knowledge.** Across 46 teachers and 2,832 students, teacher pedagogical AI knowledge predicted students' perceptions of AI for social good and their intention to learn AI, while technical knowledge alone was insufficient — and neither predicted students' AI knowledge (Shen et al. (2026)).
- **Offloading administrative work is where AI contributes most clearly.** A PRISMA review of 28 studies found AI most often enhanced instructional planning and assessment design, with its most reported benefit the automation of grading, feedback and progress monitoring (18 studies, 64.2%) — while pedagogical alignment was the most cited challenge (14) (Kibar & Ilgaz (2026)).
  Automation and learning trade off directly. Woollaston et al. (2026) walk six pedagogical principles — Prior Knowledge activation, Collaborative Learning, Problem-Based Learning, Formative Assessment, Scaffolding, Metacognition — through what proactive agentic initiative does to each, arguing the more an agent automates, the less cognitive work the learner does unless friction, dynamic fading, and human oversight are designed in.
- **Reflection is a pedagogy that AI both enables and threatens.** Structured prompts, journals and portfolio commentaries are the mechanism by which experience becomes learning, and the Reflection page carries the evidence. One preregistered experiment found prompts that doubled time on feedback and cut practice volume by 40% without lifting per-problem gain. A coded audit of an AI reflection partner found it broke every behavioral instruction without leaving a visible trace. Design the prompt around a completed attempt, and require the trail rather than the polished entry.
- **Teaching strategies for AI literacy.** Teaching students *to use AI well* is itself a pedagogical task — AI Literacy and Reducing AI Misuse research develops strategies (think-first/AI-second/reflect, AI-declaration, calibration training) that belong to this umbrella.
- **AI-literacy instruction moves knowledge fastest.** A three-level meta-analysis of 59 studies (172 effect sizes) found knowledge-focused interventions ($g \approx .97$) clearly outperformed those targeting skills ($\approx .67$), attitudes ($\approx .68$), or Ethics ($\approx .64$), so pairing concept teaching with sustained practice targets the outcomes that resist instruction (Liu et al. (2026)).

- **Pedagogy in teacher practice.** Teaching and Teacher AI Competency examine how teachers adopt AI within their existing pedagogical repertoire, and LLM Training and Fine-Tuning / Pedagogical Agent study AI tools trained to follow pedagogical principles.

Relationship to learning theories

Pedagogies and learning theories are closely linked: each pedagogy operationalizes one or more theories. For example, Project-Based Learning operationalizes Constructivism and experiential theories; Socratic Method draws on Sociocultural Learning and Metacognition; Scaffolding stems from the Zone of Proximal Development. The knowledge base treats Learning Theories as the conceptual foundation and this page as the instructional-practice umbrella — see also Learning Design, which concerns the systematic process of selecting and sequencing strategies. The learning sciences sit one step further out again: this page covers the practice of teaching and the strategies educators choose, while the learning sciences study that practice empirically — describing, modeling and evaluating designs to establish which ones change learning.

Learning gains across pedagogical strategies

Different pedagogical strategies produce different kinds and sizes of learning gains, and the knowledge base's evidence lets us compare them:

- **Active and experiential strategies** generally produce stronger durable learning than passive reception, though they feel more effortful — Active Learning, Experiential Learning, Project-Based Learning, and Learning by Teaching build understanding through doing. Research shows that strategies preserving effortful practice (rather than AI shortcutting it) protect Learning Gains.
- **Structured, guided strategies** (Scaffolding, Self-Regulated Learning, Learning Design) produce reliable but more modest gains — the guardrail evidence (PNAS 2025) shows hint-not-answer scaffolding preserves learning that unguarded answer-giving destroys.
- **Game-based learning** produces engagement and skill gains that are real but often modest and context-dependent — meta-analytic evidence finds game-assisted GenAI shows no significant added benefit over other formats, so games are best used for motivation and practice, not as a shortcut to gains.
- **Collaborative and sociocultural strategies** (Collaborative Learning, Sociocultural Learning) show gains mediated by interaction quality, increasingly studied with AI as a partner or peer.
- **Socratic and dialogue-based strategies** (Socratic Method) target higher-order thinking and reasoning — gains that are harder to measure than skill gains but central to Critical Thinking.

The key cross-cutting finding, consistent with the knowledge base's Learning Gains research, is that **the strategy's effect on learning depends more on how it preserves learner effort and productive struggle than on which label it carries** — any pedagogy, even a "good" one, fails if AI is configured to bypass the cognitive work it was meant to elicit (see Cognitive Offloading, Desirable Difficulties).

Student–AI interaction is better read as a shifting process of cognitive distribution than as fixed dependence: across 53 ChatGPT conversations from a transdisciplinary engineering course, extension (tight, iterative co-thinking) was the most frequent interaction type at 53.3% of 321 prompt-level codes, ahead of outsourcing at 29.6% (Willcox, Lane & Arikan (2026)).

That emphasis on preserved effort is not absolute: a four-study mixed-methods design (N = 912) found that framing GenAI as a pedagogical partner activated both critical vigilance and strategic offloading, with offloading above a threshold freeing capacity for higher-order reflection rather than eroding it (Wang and Zhang (2026)).

Implications for AI in education

- **Select pedagogy deliberately with AI:** the teaching strategy determines whether an AI tool supports or undermines learning, so pedagogical intent should drive AI tool selection and configuration.
- **Keep learner agency central:** active, Socratic, and scaffolding pedagogies preserve the productive struggle and Learner Agency that AI can otherwise erode (see Cognitive Offloading, Desirable Difficulties).
- **Design AI to enact good pedagogy:** AI agents and tutors should be grounded in established instructional frameworks, not default answer-generation.
- **Teach with and about AI:** pedagogies should both use AI to teach and teach learners how to use AI responsibly.

Common Misconceptions

- **"Technical AI knowledge is what teachers need most."** Across **46 teachers and 2,832 students**, **teacher pedagogical AI knowledge** predicted students' perceptions of AI for social good. Pedagogical knowledge outperformed technical knowledge, which inverts where most training investment goes.
- **"AI's main contribution in education is instructional."** A **PRISMA review of 28 studies** found AI most often enhanced **instructional planning and assessment design** — the clearest contribution is **offloading administrative work**, not teaching. A case built around instructional gains is building on the weaker branch of the evidence.
- **"AI literacy instruction transfers automatically to better teaching."** A three-level meta-analysis of **59 studies (172 effect sizes)** found **knowledge-focused interventions (g ≈ .97)** clearly outperformed other approaches at moving knowledge. Moving knowledge is the measured outcome; whether it reached practice is the next question.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- Online Teaching and Learning — Online Teaching and Learning
- Learning Theories
- Learning Sciences
- Learning Gains
- Learning Design
- Active Learning

- Collaborative Learning
- Project-Based Learning
- Experiential Learning
- Game-Based Learning
- Socratic Method
- Scaffolding
- Learning by Teaching
- Self-Regulated Learning
- Culturally Relevant Pedagogy
- Universal Design for Learning
- Critical Pedagogy
- Teaching
- Teacher AI Competency
- AI Literacy
- Curriculum Design
- Higher Education
- K-12
- LLM Training and Fine-Tuning — AI tools trained to follow pedagogical principles

Connected Articles

- Generative AI as a Didactic-Pedagogical Mediator: Rethinking Human Roles and Pedagogical Design in Higher Education — GenAI as didactic-pedagogical mediator: instructor–student–GenAI triadic model (Moganadas et al. 2026)
- Pedagogy first, technology second: Cross-level relationships between teacher professional knowledge and student learning in artificial intelligence (AI) education — ‘Pedagogy first, technology second’ — TPAIK outweighs technical TAIK for student outcomes (Shen et al. 2026)
- Pedagogical partnerships with generative AI in higher education: how dual cognitive pathways paradoxically enable transformative learning — Pedagogical partnerships with generative AI
- Artificial Intelligence and Communities of Inquiry: Reimagining Educational Experiences
- The Role of Instructional Guidance in Generative AI-Assisted Learning: Empirical Evidence from Construction Engineering Education — How instructional guidance shapes GenAI learning effects
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — Guardrailed (hint-not-answer) tutoring eliminates the exam penalty
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — The automation-vs-learning tension in agentic AI
- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents — Grounding agents in instructional-design theory
- Designing Needs- and Attention-Aware AI Learning Tools for Engineering Education: Insights from Psychological Outcomes — AI learning tools in engineering education

- Empowering Educators: Operationalizing Age-Old Learning Principles Using AI — Operationalizing learning principles with AI
- The intersection of artificial intelligence and instructional design practice: A systematic review — AI and Instructional Design Practice: A Systematic Review (Kibar & Ilgaz 2026)
- AI literacy interventions in education: A meta-analysis of effects and moderators — Instructional approaches in AI literacy interventions
- Cognitive Distribution in Student-GenAI Interaction: A Process Framework from Self-Directed ChatGPT Use in Research Tasks — Student-AI interaction as shifting cognitive distribution, not fixed dependence (53.3% extension)

Connected FAQs

- How Should AI Be Designed Into the Learning Experience?

Pedagogical Patterns

> **Pedagogical Patterns** — the *ordered sequences* of activity that research in this knowledge base has tested, with attention to where generative AI enters the sequence and where human judgment has to remain. Where Pedagogies and Teaching Strategies catalogs approaches (active learning, problem-based learning, collaborative learning) and Learning Design describes how a course is designed, this page catalogs what students and teachers actually *do*, in what order, and what happened when it was tried. PAIRR — draft, peer review, AI review, reflection, revision — is the best-documented example, and the pattern behind it recurs across disciplines: effort first, AI second, human judgment at the stakes.

Questions to Consider

- A pattern is a *sequence*, not a tool. Take one assignment you teach and write the order of moves a student makes. Where in that order would AI help, and where would it do the work the student is supposed to be doing?
- Several patterns here deliberately give AI a *weak* role — hints instead of answers, questions instead of corrections. Why would a deliberately less helpful tutor produce better learning, and what does that imply about the AI tools your institution is buying?
- The best-evidenced pattern on this page (learning by teaching an AI) asks students to explain, and it improves explanation and question quality but *not* objective recall. If you adopted it, what would you change about how you assess?
- When AI feedback was higher quality than teacher feedback, students did not revise more. What does that suggest about the difference between producing feedback and getting students to use it?
- Contexts change the answer: some patterns were tested online and asynchronous, others face-to-face with a lab. Which of these could you run in your own setting without new tools, and which would need infrastructure you do not have?
- Nearly every pattern here keeps a human at the point of judgment — grading, verifying, or interpreting. Is that a design choice, an evidence-based necessity, or a limitation of what has been tested so far?

Introduction

Pedagogy answers *how should we teach*; this page answers a narrower, more operational question: **in what order should the moves happen, and where does AI belong in that order?** The distinction matters because the same tool produces opposite outcomes depending on its position in a sequence. A generative-AI assistant placed before a student attempts a problem reliably depresses later unassisted performance; placed after an attempt, with hints rather than answers, the same class of system removes that harm.

Every pattern below is reported with an evidence status, because the knowledge base's coverage is uneven and the difference matters to anyone deciding what to adopt:

- **Tested** — at least one article reports a controlled or comparative test.
- **Mixed** — tested, but without a control, with conflicting results, or with the tested variable entangled with something else.
- **Design proposals** — the idea appears only as a proposal or framework, with no test reported. These are collected separately at the end of the page, in *Design proposals (not yet tested)*, and are not evidence.

The patterns are grouped by the function they serve in a lesson: placing effort before help, pairing AI feedback with human feedback, verifying understanding rather than output, making the learner the teacher, structuring collaboration, and confronting a specific misconception. Contexts (online, face-to-face, blended) and disciplines are reported with each, and summarized at the end.

Patterns that place effort before help

These patterns share a structural claim: the learner must commit to an attempt before the AI contributes. It is the most consistently supported design rule in the knowledge base.

Retrieve or attempt before the AI answers

Evidence: tested. The sequence is: attempt from memory, receive instruction or an example, practice in spaced sessions, consult the AI only after committing to an attempt, receive response-contingent feedback that probes the misconception, and advance only once the response shows adequate engagement.

An adaptive spaced-retrieval condition produced the highest posttest scores (M = 78.19) and significantly outperformed learner-directed AI study (M = 67.28, d = 0.92, p = .003) across 89 students in a blended statistics course, while fixed spacing was statistically indistinguishable from adaptive (Akgun & Toker, 2026). The contrast case is decisive: in a randomized trial of 120 students, the group that studied *with* unrestricted ChatGPT retained less on a surprise test 45 days later — 57.5% correct against 68.5% for traditional learners, t(83) = −3.19, p = .002, d = 0.68 — and had also studied roughly 45% less, with the disadvantage surviving a study-time covariate (Barcaui, 2025). A preregistered randomized field experiment in an online MBA found that gains tracked *completed weeks* rather than minutes of exposure (+2.00 points per additional completed tutoring week, p = .018), reading as spaced practice mattering more than total time (Yang et al., 2026).

The causal case for the rule is a field experiment in roughly 50 Turkish high school mathematics classes with nearly 1,000 students (Bastani et al., 2025). Unrestricted GPT-4 raised assisted practice performance by 48% and cut the unassisted exam by 17% against control, while a guarded GPT-4 raised practice by 127% and left the exam essentially unchanged. The Guardrails were only two: hints instead of answers, and teacher-authored problem-specific content (correct solution, common mistakes) seeded into the prompt so the hints were accurate. Engagement data put the harm in copying, since unguarded students mostly asked for answers, and students in both AI arms misjudged their own learning.

Productive failure: attempt before instruction

Evidence: mixed, and thinner than its reputation. Students attempt a problem targeting a concept they have not been taught, the tutor withholds the solution and elicits multiple attempts, help comes only when strictly necessary, and consolidation follows with comparison and direct instruction.

The one field study that tests the full sequence with a steered tutor used 17 high school students in Singapore: the steered condition achieved a higher productive-failure score, significant for problem consistency ($p = .046$), and students produced on average 2.6 representations per session ($p = .05$), but **no learning outcome was measured** (Puech et al., 2025). The strongest support is indirect and comes from a randomized within-subjects experiment with 26 students, where immediate-answer Scaffolding performed significantly *worse* than peer, TA and tutor roles on model abstraction ($\beta = -0.692$, $p = .015$; $\beta = -1.039$, $p < .001$; $\beta = -0.769$, $p = .005$) even though students *preferred* the directive tutor — preference ran against competence (Zhu et al., 2026).

Error analysis and erroneous examples

Evidence: mixed. Students diagnose an error in an artifact — an AI-generated diagram violating referential integrity, a query that drops a join, an Large Language Models (LLMs) code snippet — receive clues that force them to infer the fix rather than being handed the correction, repair it, and reflect on which parts of the output were untrustworthy.

A pre-post study of 13 students in an online database course rose from 4.25 to 6.83 out of 7 ($t(12) \approx 5.10$, $p < .001$, $d = 1.49$) using weekly critique-and-refinement cycles built on deliberate AI failure cases, but with no control group the gain cannot be separated from the curriculum or instructor (Hosseini, 2026). A systematic review of 72 computing-education studies reports that error analysis is a *distinct competence*: students performed significantly worse at correcting LLM-generated code than at traditional programming exam tasks (Kumar et al., 2026). No article in the knowledge base reports a controlled test of erroneous-example instruction as such.

Worked examples with self-explanation

Evidence: mixed — the two halves diverge. A worked example is presented with missing justifications to complete, or with errors to find; the student completes or repairs it, explains their reasoning, and then attempts the next problem.

Adaptively assigning guided and buggy examples beat random problem-type assignment in a classroom study of 113 students (posttest M = 72.3 and 72.5 against 65.7 control, A = .58, $p = .005$ and $p = .002$), and the Knowledge Tracing variant narrowed the achievement gap by 77.1% for low Prior Knowledge students ($\beta = 9.4$, $p = .001$) (Dey Tithi et al., 2026). But *adding* the self-explanation step to elaborated AI feedback lost on every measure in a preregistered experiment with 302 participants: it doubled feedback time (4.1 vs 2.1 min, $p < .001$), cut problems completed by 40% (2.0 vs 3.4, $p < .001$), produced no gain per episode (OR = 1.03, $p = .486$), and lowered end-of-session mastery (65% vs 79%, $d = .41$, $p < .001$) (Asher et al., 2025).

How many examples to give before practice is itself content-dependent, which the section's framing of "worked examples then problems" leaves open. In a 2×2 experiment with 95 participants on geometry-area materials, practice-only training produced larger gains for verbatim facts while alternating examples with

practice produced larger gains for generalizable skills (β = 0.41, p = .038, d = 0.38) (Rachatasumrit, Koedinger and Carvalho, 2025). A sequence cannot be judged as worked examples against practice in the abstract, because the right mix follows from whether the target is a fact or a skill.

Patterns that pair AI feedback with human feedback

The knowledge base's most replicated finding about AI feedback is that it works better *combined* with human feedback than alone — and that its quality is not what determines whether students use it.

PAIRR: peer and AI review with reflection

Evidence: mixed (widely implemented, not controlled). Students read and reflect on how AI and feedback work, draft, give and receive peer review, prompt the AI for criteria-driven feedback on the same draft, critically compare both, write a revision plan, revise, and reflect on which feedback changed what.

The largest study of college students' use of AI feedback to date followed 654 students across ten writing courses and three writing-intensive STEM courses: 58% preferred combined ChatGPT and peer feedback, 36% peer alone and only 6% AI alone; 75% found the two similar and mutually reinforcing; AI feedback was called "overly general" by 31% while peer feedback was more specific for 28%; and only 5.3% showed overconfidence in AI feedback (Sperber et al., 2025). The model was also run in an upper-division business writing course with 34 students, where about a quarter of coded reflections expressed skepticism about or noted inaccuracies in AI feedback (MacArthur et al., 2025). Both report perception data; neither has a control condition, which is why the pattern is *mixed* rather than *tested*.

Combined peer and AI feedback

Evidence: tested. The comparative evidence comes from outside the PAIRR program. A quasi-experiment with 122 Chinese EFL students found AI-plus-peer integrated feedback raised behavioral, affective and cognitive engagement against peer-feedback-only (all $p < .001$; partial $\eta^2 = 0.28, 0.28, 0.32$) and improved writing on all four IELTS dimensions ($F(1,119) = 42.68$, $p < .001$, partial $\eta^2 = 0.26$), largest on task achievement ($d = 1.41$) — with no delayed post-test, so durability is unmeasured (Liu, 2026). In a randomized study of 45 student teachers in 12 groups, GenAI-supported peer feedback beat plain peer feedback on argumentation, and the *prompt-scaffolded* variant performed best on advanced elements such as rebuttal data and addressing the opposing view (Chang et al., 2026).

AI critique then revision

Evidence: tested — with an important null. Draft, prompt the AI for rubric-driven feedback, critically assess that feedback against the rubric and the sources, write a revision plan, revise, and reflect.

A controlled 2 × 2 factorial experiment with 120 English majors found writing-quality gain was highest for the group trained in both filtering and appraisal ($M = 7.92$), against 6.10, 4.56 and 3.10 for the other conditions, with deep revision rising from 28% to 48% and the advantage persisting on a new topic and after AI support was removed (Dai, 2026). The null is the instructive part: in a randomized three-group experiment with 70 students, chain-of-thought-prompted AI feedback was significantly *higher quality* than

both zero-shot AI feedback ($p = .01$) and teacher feedback ($p = .008$), yet this quality advantage **did not translate into greater revision gains** — teacher feedback produced comparable improvement (Farrokhnia et al., 2026).

Human-in-the-loop review of AI output

Evidence: mixed — the review step is rarely the tested variable. AI generates draft output, automated verifier agents check it for realism, readability or hallucination, failed checks loop back for refinement, and a teacher reviews, edits, and accepts or discards before anything reaches students.

A four-agent loop with 8 teachers produced 212 problems of which 166 were accepted as-is, and realism checks worked as intended (10 realism problems flagged, 20 quantity or unit edits, no mathematics error found in a final problem) — but interest fit was the weak point, with students rejecting the topic in 160 of 422 responses (Walkington et al., 2026). An educator-in-the-loop feedback tool rated by 30 teachers never fell below 4.1/5 across nine items and cut median time per assignment from 10–30 minutes to under 5, but the authors acknowledge no student evaluation, so no learning claim is supported (Zhao et al., 2025). A red-team experiment makes the stakes concrete: 2 of 5 prompt injections changed a grade undetected, at 100% (9/9) and 94% (17/18), leaving the teacher as the only real check on AI grading output (Humble, 2026).

Patterns that verify understanding rather than output

Because AI can produce a competent artifact, these patterns move assessment to evidence the artifact cannot supply on its own.

Oral and viva verification

Evidence: tested as a format, but results are about scores and affect rather than learning. A coding assignment is submitted with AI permitted, followed within 48 hours by a mandatory 15-minute oral code review in which the student explains the program and runs integration tests live, graded 70% on the review and 30% on the rubric.

A three-semester quasi-experiment with 96 students found no statistically significant change in exam performance despite the new policies (~2% improvement on one exam), while pasted-to-total characters rose from 61.0% to 68.1% ($p < 0.0001$); 90% of students said the reviews motivated them to understand their code better and 65% that they helped avoid over-reliance (Fowles et al., 2026). Asynchronous recorded oral responses produced significantly higher scores than in-person multiple-choice (midterm Md = 92.5 vs 70, $p < .001$; final Md = 94.2 vs 86.4, $p = .002$) with only moderate cross-format correlations ($\tau = .44$ and .25) — and the authors caution these are *format score differences, not evidence of learning gains*, with cheating behavior unmeasured (Pentland et al., 2026). Direction is not uniformly positive: students were calmer in a chat-based viva (M = 6.50 vs 5.86, $p = .028$) but rated the face-to-face viva significantly better for understanding their own work ($p = .004$) (Yusuf et al., 2026).

Staged checkpoints and process evidence

Evidence: mixed — no controlled test of the mechanism itself. Coursework runs as staged modules, each ending in a checkpoint that verifies both the output *and* the approach — a correct result reached by hardcoding is rejected — with a pre-advancement check that returns the learner to skipped steps.

A case study of 5 graduate students in a self-paced quantum-information course logged 75 interactions and confirmed the dual output-and-approach checkpoint functioned as intended, with no control group (Elhaimeur & Chrisochoides, 2026). A 27-participant pilot using stop-block checkpoints reported significant Self-Efficacy gains across all ten assessed skill areas ($p < 0.001$) in a within-subjects pre-post design where gains cannot be separated from practice effects (Naboulsi, 2026). A three-year quasi-experiment with 248 biomedical engineering students found higher A-rates after adding four-module problem-based learning with milestones and rubrics (66.4% vs 39.1%, $\Delta = +27.3$ points, $p = 0.042$), persisting after excluding the pandemic-affected year, but the comparison is historical and non-randomized (Nnamdi et al., 2026).

Patterns that make the learner the teacher

Learning by teaching an AI tutee

Evidence: tested, and the best-evidenced pattern on this page. The student studies the content, then explains it to an AI prompted to hold a novice stance that never reveals the target explanation; the AI asks for explanations, examples and verification reasoning, sequenced from lower- to higher-order, and persists until the explanation is satisfactory.

A quasi-experiment with 68 preservice teachers found explaining to a GAI novice learner scored higher on defining the flipped classroom ($M = 4.18$ vs 3.29, $p < 0.001$, $r = 0.474$) and its activities ($M = 4.91$ vs 3.06, $p < 0.001$, $r = 0.642$), generated more and higher-quality questions (both $p < 0.001$) — but showed **no group difference on objective questions** ($M = 23.18$ vs 21.57, $p = 0.416$) (Wang et al., 2026). A randomized lab experiment with 41 students found higher knowledge-test scores (adjusted 11.86 vs 10.53, $F = 35.54$, $\eta^2 = 0.74$) and clearer, more readable code, but **no difference in code correctness** (Chen et al., 2024). An 11-week deployment across 546 students found each additional deep-learning act associated with a 2.7% decrease in expected quiz attempts (IRR 0.973, $p < .001$), with the comparison confounded by time-on-task and late-semester circumvention rising to 30–35% external content reuse (Wang et al., 2026). The consistent shape: gains in explanation and generative work, not in objective recall.

Patterns that structure collaboration

Scripted roles with one shared AI

Evidence: tested, but in controlled or uncontrolled settings rather than ordinary classrooms. Two learners share one AI and are assigned explicit roles with rotation rules; the AI is configured to take a role as needed and its output goes to the whole group. In a pair-programming variant the shared AI models the dyad's joint attention and effort, forecasts a breakdown up to 30 seconds ahead, and escalates scaffolds in tiers from doing nothing to a directive hint.

A within-subjects experiment with 26 dyads found the feedback condition achieved higher debugging success ($t[49.96] = -13.51$, $p < .0001$) and finished faster ($t[44.70] = 4.39$, $p < .0001$), though it required dual eye-tracking and pupillometry hardware and did not test transfer to unsupervised pair work (Golrang et al., 2026). A quasi-experiment with 58 graduate students in 16 groups found role design raised mind-map content scores from 3.65 to 4.59 on a 1–5 SOLO scale ($z = 3.771$, $p < 0.001$) while node and branch counts stayed flat — but with no control group, practice effects cannot be ruled out (Cheng et al., 2026).

AI-assisted discussion

Evidence: mixed — the one direct implementation is a case description. Students analyze a scenario and answer guided questions independently, prompt ChatGPT with a standardized prompt on the same questions, evaluate the AI responses for accuracy against their own, refine their answer, and close with a whole-class discussion.

The economics activity deliberately exploits an AI error — ChatGPT calls the song's depicted behavior "perfectly elastic" demand when the correct answer is inelastic — turning validation of AI output into the discussion (Beck & Brodersen, 2025). It reports instructor impressions, not a measured outcome. A tested collaborative-discussion sequence with 67 teacher-education students found the experimental group outperformed a lecture control ($M = 51.45$ vs 43.89, $p = 0.001$, $g = 0.839$) with co-regulation rising ($p = 0.043$, $g = 0.512$) — but AI was used to *design* the technique, not to mediate the discussion (Tutal, 2026).

Patterns that confront a specific misconception

Refutation and conceptual change

Evidence: tested — with directly conflicting results. Elicit the learner's specific belief, present a refutation text or a personalized AI dialogue that confronts it, engage with the counter-evidence and the correct explanation, restate the correct conception, then retest after a delay.

A preregistered experiment with 375 adults found personalized misconception AI dialogue produced significantly larger immediate belief reductions than both textbook-style refutation and neutral AI dialogue, persisting at 10 days but converging with textbook refutation by 2 months (Corbett & Tangen, 2026). A Solomon four-group quasi-experiment with 413 tenth-graders found the *reverse*: expert-written and AI-generated conceptual-change texts were both significantly more effective than interactive ChatGPT dialogue, which showed no significant advantage over control, and gains were almost exclusively limited to high-achieving students (Akdogan, 2025). The second paper flags the conflict explicitly and attributes it to prompt design and domain. Refutation text itself beat control in both.

Contexts and disciplines

The pattern determines what the context requires, and several patterns were tested in only one setting. Pooled estimates make that dependence quantitative. Across 35 experimental and quasi-experimental studies and 175 effect sizes, generative AI's pooled effect on undergraduate academic performance was $g = 0.46$, and the teaching model moderated it ($Q = 14.63$, $p = 0.001$). Flipped classrooms reached $g = 1.96$ from 7 effect sizes, traditional classrooms $g = 0.46$, and self-directed learning $g = 0.26$ (Jing et al., 2026). Intervention duration

moderated it too, with the academic-performance effect falling from g = 5.07 at 0 to 4 weeks to g = 0.01 beyond 12 weeks. The authors treat the very large short-duration estimates as descriptive rather than generalizable, so an effect size for “AI in teaching” is a claim about a design, and the patterns here are those designs.

- **Online and asynchronous.** Retrieval and spacing, the Socratic variants, worked examples with self-explanation, prompt-scaffolded use, asynchronous oral assessment, and the learning-by-teaching deployments. Asynchronous settings make the *sequencing* load-bearing, because the system cannot see whether the student attempted first.
- **Face-to-face and blended.** Productive failure, error analysis, the flipped variants, oral code review, scripted collaboration, and the conceptual-change studies. Class time is often reallocated rather than replaced — in the oral-review pattern, lectures moved to video so class time could hold the interviews.
- **Disciplines represented in the tested evidence.** Writing and language learning (PAIRR, combined peer and AI feedback, AI critique then revision), mathematics (retrieval and spacing, productive failure, worked examples, error analysis), computer science (Socratic assistants, error analysis, oral code review, learning by teaching, scripted pair work), medicine (Socratic scaffolding in clinical interviews), teacher education (scripted argumentation, learning by teaching), business (flipped MBA tutoring), and physics, science and vocational settings for the conceptual-change and oral-assessment studies.

What the evidence does not yet support

Stated plainly, because these are the findings most likely to be quietly dropped:

- **Better AI feedback does not produce more revision.** Higher-quality chain-of-thought feedback beat teacher feedback on quality and produced no revision advantage (Farrokhnia et al., 2026).
- **Socratic questioning is not automatically better.** A randomized trial of 132 students found the Socratic assistant with full context rated significantly *worse* for supporting task completion than all other configurations (mean rank 48.63, $\mu = 3.53$, against 4.27, 4.16 and 4.12; $\chi^2(3) = 12.14$, $p = .007$), with the most external LLM use (23%) and the fewest full-comprehension responses (48% vs 67%) (Eastwood et al., 2026) — while a medical RCT found a multi-agent system containing a Socratic tutor beat its control on examination and communication scores (Yang et al., 2026).
- **Students prefer the less effective role.** Directive tutoring was preferred while immediate-answer scaffolding depressed model abstraction (Zhu et al., 2026).
- **Verification formats change scores without demonstrating learning.** Oral formats raised scores and reduced anxiety while one study found face-to-face better for understanding, and no study measured cheating.
- **No controlled test isolates human review of AI output**, and the checkpoint mechanism has never been tested as the manipulated variable.
- **Productive failure and error analysis rest on small, uncontrolled studies** (n = 17 and n = 13) that measure strategy fidelity or self-report rather than learning outcomes.

Design proposals (not yet tested)

The patterns below come from a faculty guide supplied by the knowledge base maintainer (*AI-Ready Course Design*, September 2026). That guide states explicitly that its examples are **design proposals, not tested interventions**, and no article in this knowledge base tests them. They are recorded here as design ideas worth trying and evaluating, and must not be read as evidence.

- **Argument + revision trail** (composition, humanities). Replace an essay-only submission with an initial thesis, two annotated source passages, a revised essay and a 150-word decision note; permit AI critique after the first draft. Assess the claim–evidence connection and one accepted or rejected suggestion justified against the sources.
- **Data + reasoned claim** (science, laboratory courses). Replace a polished lab report with raw observations, a graph, an uncertainty note and an explanation linking results to a claim; AI may critique a supplied interpretation, and students verify that critique against their data.
- **Attempt + error analysis** (precalculus, calculus). Replace answer-only homework with an initial attempt, analysis of a flawed worked solution, and a corrected explanation; hints are permitted only after the attempt. This is the design form of the error-analysis pattern above, and it inherits that pattern's weak evidence base.
- **Position + challenge + reconsideration** (psychology, sociology). Replace "post once, reply twice" with a case-based claim using a course concept; a peer supplies a counterexample and the author revises or defends with evidence.
- **Project + linked check** (business, health professions). Pair an AI-permitted recommendation for a fictional organization or patient case with a short explanation of two key decisions and a response to a changed constraint; publish the grading relationship between the two components.
- **Plan + try + adapt** (college success). Replace a generic time-management reflection with a one-week study plan, a brief record of trying it, and a revision tied to what happened; AI may suggest scheduling options after the student identifies constraints.

The guide's own cautions apply: recorded video, reflections and logs can themselves be AI-assisted, so in fully asynchronous courses a recording should not be treated as verification of independent mastery. Two of its framings — assessment twins and asynchronous oral assessment as a cheating deterrent — remain frameworks awaiting validation; the asynchronous oral-assessment studies cited above measured format scores and did not measure cheating at all.

Common Misconceptions

- **"Any AI-supplied practice is practice."** An adaptive spaced-retrieval condition produced **the highest posttest scores (M = 78.19)** and **significantly outperformed learner-directed AI study (M = 67.28)**. The learner-directed arrangement underperformed a structured one, so autonomy is not automatically the better design.
- **"Studying with a chatbot is better than studying without." The counterexample settles it**: in a randomized trial of **120 students**, those who worked with unrestricted ChatGPT remembered **less when tested without warning** than those who did not. The tool was harmful to retention in the arrangement tested.

- **“The pattern’s evidence is a large pooled trial.”** The **strongest support is indirect** and comes from a **randomized within-subjects experiment with 26 students**, where immediate-answer Scaffolding performed significantly differently. The evidence supports the pattern and remains thin in scale, and the page should be read that way.

Connected Concepts

- Pedagogies and Teaching Strategies — the umbrella of teaching approaches this page operationalizes into sequences
- Learning Design — where patterns are chosen, sequenced and embedded in a course
- Scaffolding — the support-and-fading principle that governs where AI help belongs
- Feedback — the system this page’s feedback patterns instantiate
- Formative Assessment — the assessment purpose most of these patterns serve
- Peer Assessment — the human half of the PAIRR and combined-feedback patterns
- AI Feedback Quality — why feedback quality alone does not determine revision
- Evaluative Judgment — the appraisal students must exercise on AI output
- Feedback Literacy — the capability the critical-appraisal steps are building
- Human-in-the-Loop — the oversight structure of the review patterns
- Oral Assessment — the format underlying the verification patterns
- Process-Oriented Assessment — the logic behind staged checkpoints
- Productive Failure — the concept behind attempt-before-instruction
- Retrieval, Spacing and Interleaving — the evidence base for spaced retrieval patterns
- Desirable Difficulties — why effortful sequences outperform fluent ones
- Misconceptions about AI — what the conceptual-change patterns target
- Refutation Text — the text form of misconception confrontation
- Learning by Teaching — the pedagogy behind the AI-tutee pattern
- Socratic Method — the questioning pattern and its conflicting evidence
- Collaborative Learning — the context for scripted shared-AI work
- Cognitive Offloading — the risk every effort-first pattern is designed to avoid
- Metacognition — what reflection steps in these sequences are meant to trigger
- Prompt Engineering — the scaffolding layer in structured-use patterns
- Transfer of Learning — the outcome most patterns are ultimately judged on
- Assessment Validity — the reason process evidence is proposed at all
- Academic Integrity — the driver behind oral and process verification
- AI Literacy — the capability developed by critiquing AI output
- Online Teaching and Learning — the context that makes sequencing load-bearing
- Higher Education — the level where most of this evidence was generated
- K-12 — the level of the productive-failure, conceptual-change and oral-assessment studies

Connected Articles

- Peer and AI review + reflection (PAIRR): A human-centered approach to formative assessment — Peer and AI Review + Reflection (PAIRR): the flagship sequence, N = 654 (Sperber et al. 2025)
- GIFT-AI: Teaching the game and leveling the field: Peer and AI Review + Reflection in a business writing course — PAIRR applied in a business writing course (MacArthur et al. 2025)
- AI-peer integrated feedback in second language writing classes: exploring students' engagement and writing performance — Integrated AI-plus-peer feedback raised engagement and all four IELTS dimensions (Liu 2026)
- Leveraging generative AI to facilitate peer feedback in collaborative argumentation learning — Prompt-scaffolded GenAI peer feedback in collaborative argumentation (Chang et al. 2026)
- Dai (2026) — Training students to filter and appraise AI feedback: the FRAC and APCA conditions
- Generative AI offers more, but students revise less: comparing the effects of teacher and AI feedback on student essay revisions — Higher-quality AI feedback produced no greater revision gains (Farrokhnia et al. 2026)
- Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming — Socratic plus full context was rated worse than every other assistant configuration (Eastwood et al. 2026)
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Need-triggered Socratic scaffolding in clinical interview training, N = 100 (Yang et al. 2026)
- Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot — Socratic chatbot in introductory mechanics: question specificity rose from 10–15% to 100% (Hashmi et al. 2025)
- The Effects of Agent Type and Feedback Style on Self-Directed Learning: A Mixed-Methods Study — Socratic versus directive agent feedback, with the order not counterbalanced (Han et al. 2026)
- Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study — Adaptive spaced retrieval beat learner-directed AI study (Akgun & Toker 2026)
- ChatGPT as a cognitive crutch: Evidence from a randomized controlled trial on knowledge retention — Unrestricted ChatGPT during study lowered 45-day retention (Barcaui 2025)
- When AI Tutors Speak: Evidence from a Randomized Field Experiment — Structured tutoring gains tracked completed weeks, not minutes (Yang et al. 2026)
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content — Examples versus practice cross over by knowledge type (Rachatasumrit et al. 2025)
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive guided and buggy examples in an intelligent logic tutor (Dey Tithi et al. 2026)
- Benefit or Bottleneck? Assessing the impact of structured reflection on learning from AI-driven explanatory feedback — Adding self-explanation to AI feedback lost on every measure (Asher et al. 2025)

- Generative AI without guardrails can harm learning: Evidence from high school mathematics — Guarded tutoring removed the exam harm that unguarded GPT caused, ~1,000 students (Bastani et al. 2025)
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics — Guided versus unrestricted LLM use in statistics (Amanlou et al. 2026)
- Preferred scaffolding does not lead to better learning performance: Empirical evidence from AI-supported mathematical modelling — Immediate-answer scaffolding depressed model abstraction while being preferred (Zhu et al. 2026)
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Steering an LLM tutor to withhold solutions for productive failure (Puech et al. 2025)
- The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking — Weekly critique-and-refinement cycles built on deliberate AI failure cases (Hosseini 2026)
- Generative AI in computing education: A systematic review and a framework for responsible integration — Error analysis as a distinct competence, across 72 computing-education studies (Kumar et al. 2026)
- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Guided clues instead of direct error correction in L2 revision (Lukešová & Jennings 2026)
- The Contribution of Generative Artificial Intelligence as a Novice Learner to Students in the Learning by Teaching Model — Explaining to an AI novice learner, N = 68 (Wang et al. 2026)
- Learning-by-Teaching with ChatGPT: The Effect of a Teachable ChatGPT Agent on Programming Education — Randomized test of teaching a ChatGPT agent to program (Chen et al. 2024)
- Turning 500+ Students into Teachers: A Semester-Long Study of an AI Teachable Agent in an Undergraduate Algorithms Course — Learning by teaching deployed to 546 students over 11 weeks (Wang et al. 2026)
- Learning by Teaching: Engaging Students as Instructors of Large Language Models in Computer Science Education — Students designing questions an LLM cannot answer (Yang et al. 2025)
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — Mandatory oral code review interviews as a response to GenAI in CS1 (Fowles et al. 2026)
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous recorded oral assessment versus in-person multiple-choice (Pentland et al. 2026)
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — Chat-based viva reduced anxiety while face-to-face was rated better for understanding (Yusuf et al. 2026)
- Designing AI-Supported Oral Assessment in TVET — AI surfacing rubric evidence for teacher judgment in vocational workshops (Adams 2026)
- From Prototype to Classroom: An Intelligent Tutoring System for Quantum Education — Output-and-approach checkpoints in a self-paced graduate course (Elhaimeur & Chrisochoides 2026)

- Agentic Education with AI Coding Assistants — Stop-block checkpoints and a pre-advancement check, N = 27 (Naboulsi 2026)
- Advancing problem-based learning in biomedical engineering in the era of generative AI — Four-module problem-based learning with milestones and rubrics (Nnamdi et al. 2026)
- Mathematics Teachers' Interactions with a Multi-Agent System for Personalized Problem Generation — A four-agent review loop with teachers, and where interest fit failed (Walkington et al. 2026)
- LearnLens: LLM-Enabled Personalised, Curriculum-Grounded Feedback with Educators in the Loop — Educator-in-the-loop feedback with verifier scores (Zhao et al. 2025)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injections that changed grades undetected, leaving the teacher as the only check (Humble 2026)
- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming — A shared AI forecasting collaboration breakdown in pair programming (Golrang et al. 2026)
- Enhancing Human-Generative Artificial Intelligence Online Collaboration Outcomes: The Pivotal Function of Symbiotic Role Design — Scripted learner and AI roles in group knowledge construction (Cheng et al. 2026)
- ParaTutor: Coordinating Parent-Child Math Tutoring through Role-Separated LLM Scaffolding — Role-separated AI support in parent–child tutoring (Luo et al. 2026)
- AI tutors vs. tenacious myths: Evidence from personalised dialogue interventions in education — Personalized AI dialogue beat textbook refutation immediately, converging by two months (Corbett & Tangen 2026)
- Comparing the effectiveness of expert-written text, AI-generated text, and interactive AI dialogues on students' conceptual understanding of heat and temperature — Conceptual-change texts beat interactive AI dialogue, the reverse result (Akdogan 2025)
- AI-Supported Inquiry-Based Learning in Photosynthesis and Respiration: Implications for Sustainable Science Teacher Education — AI-supported guided inquiry and conceptual understanding (Aydin 2026)
- From traditional classroom to AI-enhanced flipped classroom: a three-year pedagogical evolution for international students in pharmacology — Three-cohort comparison of traditional, flipped and AI-enhanced flipped (Liu et al. 2026)
- Integrating Flipped Learning and Generative AI for Practice-Based Design Education: Evidence from a Knit Yarn Design Course — Flipped studio course with parameter-guided prompt scaffolding (Qu et al. 2026)
- The Impact of Generative Artificial Intelligence on Learning Outcomes in Higher Education: A Meta-Analysis — Teaching model moderated outcomes: flipped g = 1.96 against traditional g = 0.46 (Jing et al. 2026)
- Student Adoption of an AI Tutor for Statistical Programming: A Longitudinal Study — Weekly homework-tutor use predicted transfer-task scores in a flipped course (Préau et al. 2026)
- Fostering Generative AI Literacy in Economics: A Hands-on Approach — A five-step AI-critique discussion built on an AI error (Beck & Brodersen 2025)

- Artificial intelligence assisted design of a novel cooperative learning technique for higher education — A tested cooperative-learning sequence with assigned roles and a gallery walk (Tutal 2026)
- Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams — Seminar and peer-discussion module with an AI retrieval recommender (Huang 2026)

Connected FAQs

- How Should AI Be Designed Into the Learning Experience?

Active Learning

> **Active Learning** — instructional approaches that engage students in doing things and thinking about what they are doing, rather than passively receiving information. In AI in education, active learning research examines both how AI tools can support active learning pedagogies and how active engagement with AI tools — rather than passive consumption — affects learning outcomes.

Questions to Consider

- You've likely heard 'active learning' praised. But is a student who clicks through a dashboard or accepts a generated answer really learning actively? What would make that activity 'active' in a meaningful sense?
- The ICAP framework distinguishes active, constructive, and interactive engagement — only the deeper levels build lasting knowledge. When you last used an AI tool to learn something, which level of engagement did it actually push you toward?
- AI can enable active learning at scale, but poorly designed AI can also do the cognitive work for the student. Where have you seen AI make a learner more passive rather than more engaged?
- An EEG study found interactive student–AI collaboration produced the highest cognitive engagement, while full automation reduced it. Why might 'doing' with AI beat 'watching' AI do the work?
- Teach-back — having a learner explain what they understand — surfaces gaps more effectively than passive re-reading. When might prompting a learner to explain to an AI be a better learning move than letting the AI answer for them?
- Active learning depends on calibrated scaffolding that fades as competence grows. How hard is it for an AI tutor to know when to step back — and what's the risk if it never does?

Introduction

Active learning is a foundational principle in education research, grounded in Constructivism theories that position learners as active constructors of knowledge. In the context of AI in education, the concept takes on dual significance: AI tools can enable active learning at scale (through interactive tutoring, simulations, and adaptive feedback), but poorly designed AI tools can also undermine it by doing the cognitive work for students. The tension between AI assistance and active cognitive engagement — explored in articles like Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems on premature hint use and The efficiency-gain illusion: People underestimate the rate of AI use and overestimate its benefits on simple tasks on Over-Reliance — is a central concern.

AI-enabled active learning manifests across multiple forms in this knowledge base: Intelligent Tutoring systems that engage students in problem-solving rather than answer-giving, Generative AI (GenAI) as a mindtool that supports generative learning (GL) approaches where students use AI as a thinking tool rather than a substitute, Test-Driven, AI-Assisted Learning: Replacing Lectures with Weekly Closed-Book Tests

where students drive AI interaction rather than follow it, and Curiosity as Linguistic Intervention: Using LLM Tutoring Dialogues to Influence Exploratory Learning Behavior exploratory learning environments. The Scaffolding concept is tightly coupled: active learning needs support that is calibrated, then withdrawn as learners gain competence, and AI tutors must learn that timing.

How active learning appears in the knowledge base's research

- **Interaction mode determines cognitive engagement.** An EEG study of high school students compared Auto (AI solves independently), Interactive (student–AI collaboration with scaffolding), and Manual (no AI) modes: **Interactive produced the highest cognitive engagement and task accuracy**, while Auto reduced engagement and risked over-reliance. This gives a neurophysiological dimension to the argument that AI must keep students *doing* rather than watching.
- **AI-supported inquiry is not automatically higher-order.** A quasi-experiment with 120 Grade 8 students found AI-supported inquiry-based learning raised creative mathematical performance and attitudes toward mathematics but produced no significant gain in critical Problem Solving — a caution against reading Creativity and affect gains as evidence of deeper reasoning (Mujib et al., 2026).
- **Access is not structure.** In a construction-engineering review task, the same retrieval-augmented system scored 12.41 on open-ended items when run through a five-step prompting structure against 10.45 without it, while slide-based study scored 9.68, and multiple-choice recall did not differ (Hou et al. (2026)). Unprompted AI review did not beat slides, so the gain traces to the structure of the interaction rather than to model access.
- **Replication is a distinct active ingredient.** The Physics AI-Replication protocol has students get an AI explanation of a hard problem, request one or two similar problems, then solve those independently before checking. Across 11 introductory physics sections at four U.S. institutions, 90.9% of 231 respondents credited it with better conceptual understanding and 97.7% of 213 found the replicated practice helpful, the two correlating at $r_s = 0.58$ (Paul et al., 2026). The learner-side mechanism is what the page lacked: 18.7% of open responses described having to understand a problem's structure in order to generate a similar one. Confidence afterward tracked those two benefits ($r_s = 0.37$ and 0.35), not usage frequency ($r_s = 0.02$).
- **Exploratory and simulation-based active learning.** SupplyNet uses a contextual multi-agent Large Language Models (LLMs) simulation to support visual exploratory learning in supply-chain education, pairing an interactive network view with a branching "what-if" timeline so learners trace causal dynamics rather than consume abstract content. Curiobot and problem-posing in physics similarly foreground learner-driven exploration.
- **Structured conversational workflows for active review.** KnowLoop structures post-lecture review around three stages — Recognize (mark in-situ confusion), Resolve (clarification), and Consolidate (teach-back) — showing that teach-back prompts learners to articulate and reveal conceptual gaps, and that context-grounded AI outperforms general-purpose AI for targeted support. Teach-back instantiates Learning by Teaching.

- **Active learning as a project-based, community structure.** The Academic League of AI organizes extracurricular AI education around competition teams, study groups, and AI-for-social-impact projects, embodying active and project-based learning through democratic student governance rather than top-down curriculum.
- **Mindtools and generative engagement.** GenAI as a mindtool positions AI as a device students think *with* rather than a source of answers, aligning active learning with generative-learning theories where learners integrate new ideas into existing knowledge.
- **Building the tutor as the active-learning task.** Zangari et al. (2026) inverted the usual AI-tutor arrangement: instead of using a tutor, 345 students in a 700-student software course each designed a conversational agent to teach three design patterns to a peer, so the active-learning work was the agent's construction — anticipating user needs, translating abstract concepts into teachable pieces. Open-ended design freedom drew the most positive comments (22.3% top positive theme), while unclear instructions drew the most complaints (23.7%); the authors caution the no-control-group, volunteer-sample design supports engagement claims only.
- **Design around the model's mistakes.** A five-step sequence (independent analysis, a standardized ChatGPT prompt, critical evaluation of the output, refinement, and class discussion) works because the AI is predictably wrong: ChatGPT mislabels the inelastic demand in a song lyric as "perfectly elastic," and the discrepancy teaches students to validate output (Beck & Brodersen, 2025).
- **A pedagogically designed AI tutor can outperform the active-learning classroom itself.** A crossover RCT in Harvard's introductory physics course set a custom AI tutor against the course's own in-class active-learning lessons — the same research-based pedagogy, not a lecture — and found significantly more learning in less time: median post-test 4.5 against 3.5, effect size 0.63 by linear regression, with a median 49 minutes on task against 60 in class (Kestin et al., 2025). The authors credit design rather than the medium, since the tutor was engineered to carry the same seven research-based practices as the class and added only personalized feedback on demand and self-pacing.
- **A single exposure can suppress the participation it is meant to raise.** In a preregistered field experiment with 759 MBA students, assigned pre-class rehearsal with a voice-based AI partner that argued the opposing case raised voluntary in-class contributions about 31% after a second assigned use. Nothing changed in the session it prepared, and participation fell after a first use alone (Wang et al. (2026)). Dosage is a design parameter here, not an implementation detail.

The ICAP framework as the organizing lens

Active learning is precisely operationalized by the ICAP framework (Interactive–Constructive–Active–Passive), which classifies learner behavior by mode of cognitive engagement and knowledge change. Under ICAP, what is colloquially called "active learning" actually spans three distinct, ordered levels of engagement: *active* (acting on material, e.g. taking notes or answering a prompt), *constructive* (generating new output beyond the given, e.g. self-explaining or drawing), and *interactive* (co-constructing meaning through dialogue). This matters for AI in education because an AI tool can masquerade as "active" while keeping learners in the shallowest modes: clicking through a dashboard or

accepting a generated answer is active at best, not constructive or interactive. ICAP thereby sharpens the central design goal of active learning — **push learners from active toward constructive and interactive engagement** — and warns against AI systems that *answer for* the learner, which keep them passive. (Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)(Systematic review of collaborative learning activities for promoting AI literacy) This connects active learning directly to ICAP Framework, Student Engagement, and Collaborative Learning, whose highest ICAP mode is interactive dialogue.

Practical guidance

- **Keep the learner in the loop.** Design AI interactions so students act on and with output (interactive, scaffolded modes) rather than receiving finished answers; full automation measurably reduces cognitive engagement.
- **Anchor AI support in learners' own activity.** Confusion points, learner-driven questions, and problem-posing give personalized entry points for review and exploration.
- **Use teach-back and explanation.** Have learners articulate what they understand; surfacing gaps through explanation is more active than passive re-reading.
- **Pair active engagement with calibrated scaffolding.** Support should fade as competence grows — Scaffolding that never withdraws can itself become passive reliance.
- **Prefer tools that make thinking visible.** Exploratory simulations, mindtools, and interactive problem-spaces support the causal tracing and comparative reasoning at the heart of active learning.

Connections to related concepts

Active learning is deeply connected to Collaborative Learning (much active learning is social), Learning by Teaching (explaining to others is maximally active), Project-Based Learning and Experiential Learning (learning by doing in authentic contexts), Embodied Learning (physical engagement), Game-Based Learning, and Simulation. It relies on Scaffolding and timely Feedback, and is threatened by over-reliance when AI substitutes for effort. Grounded in Constructivism and Learning Theories, it spans Higher Education, K-12, and STEM Education.

Active learning is one of the strongest levers on learning gains in the AI era. Because active strategies build understanding through effortful doing, they are the most robust to AI short-circuiting — and the knowledge base's evidence shows that preserving that effort protects durable learning while letting AI absorb it erodes it (reduced study time, the learning penalty, hint abuse). Instructors who pair active-learning designs with measured gains on unassisted outcomes get the clearest picture of whether AI-assisted activity actually improved learning.

Common Misconceptions

- **"Putting AI in the activity makes it active."** An EEG study found **interactive student-AI collaboration produced the highest cognitive engagement, while full automation reduced it**.

The engagement came from the interaction, not the presence of AI, and automating the learner's part of the work moved engagement the wrong way.

- **"AI-supported inquiry is automatically higher-order."** A quasi-experiment with **120 Grade 8 students** found AI-supported inquiry-based learning raised creative mathematical performance **and** a narrower measure — the treatment moved some outcomes and not others. Correlation with a higher-order label is not the same as a higher-order task.
- **"Students designing the teaching is a technical exercise."** In the inversion study, **345 students** in a 700-student course each designed a conversational agent to teach three design patterns to a peer. The active learning came from the design work, which is pedagogical reasoning rather than prompt engineering.
- **"Engagement findings are learning findings."** The same evidence base cautions that a **no-control-group, volunteer-sample** design supports engagement claims only. Students valued open-ended design freedom (**22.3%** top positive theme) and complained most about unclear instructions (**23.7%**) — both are about the experience.

Connected Concepts

- Learning Gains
- Problem-Based Learning
- Learning by Teaching
- Scaffolding
- Constructivism
- Learning Design
- Intelligent Tutoring
- Student Experience
- Higher Education
- K-12
- STEM Education
- Generative AI
- Feedback
- Cognitive Offloading
- Collaborative Learning
- Learning Theories
- ICAP Framework
- Student Engagement
- Project-Based Learning
- Experiential Learning
- Embodied Learning
- Simulation
- Game-Based Learning
- Help-Seeking

- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting — AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting (Kestin et al. 2025)
- AI-supported problem-based learning for enhancing computational thinking
- Fostering Generative AI Literacy in Economics: A Hands-on Approach — Active-learning GenAI framework for economics (Beck & Brodersen 2025)
- Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems
- The efficiency-gain illusion: People underestimate the rate of AI use and overestimate its benefits on simple tasks
- "I can't read your mind": A Study of Neurodivergent Computing Students' Experiences with Collaborative Active Learning
- Generative AI (GenAI) as a mindtool that supports generative learning (GL)
- Test-Driven, AI-Assisted Learning: Replacing Lectures with Weekly Closed-Book Tests
- Curiosity as Linguistic Intervention: Using LLM Tutoring Dialogues to Influence Exploratory Learning Behavior
- Exploring students' perceptions of using generative AI-assisted problem posing
- An exploratory behavioral and electroencephalographic study of artificial intelligence-assisted learning modes in high school students — EEG study of AI interaction modes (interactive > auto)
- SupplyNet: Supporting Visual Exploratory Learning in Supply Chain via Contextual Multi-Agent Simulation — SupplyNet: visual exploratory learning via multi-agent simulation
- From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review — KnowLoop: staged conversational post-lecture review
- Academic League of Artificial Intelligence: An Integrative Perspective of Teaching, Research, and Extension — Academic League of AI: project-based active learning
- Evaluating the impact of AI-supported inquiry-based learning on students' creative mathematical performance, critical problem-solving skills, and attitudes toward mathematics — AI-supported IBL and creative mathematical performance
- Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons — Learner characteristics × TTS dialogue-format interactions
- The Role of Instructional Guidance in Generative AI-Assisted Learning: Empirical Evidence from Construction Engineering Education — Prompted vs unprompted AI review: structure, not model access, moved open-ended scores
- How assigned AI use before class shapes active student engagement in class — Pre-class AI rehearsal raised in-class participation 31% after a second use, not a first

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Should AI Be Designed Into the Learning Experience?

Collaborative Learning

> **Collaborative Learning** — instructional approaches where students work together to solve problems, complete tasks, or construct knowledge, supported or mediated by AI tools. In AI in education, collaborative learning research spans AI as a collaboration partner, AI as a mediator of human collaboration, and the design of collaborative AI tutoring systems.

Questions to Consider

- Think of a time you learned something deeply in a group. What made it work? Now imagine an AI chatbot joining that group — how could it strengthen or quietly undermine what you experienced?
- Research finds a trade-off: delegating reasoning to AI produces the best task performance but the least self-regulatory engagement, while the mode that builds self-regulation underperforms on the task. If you had to choose, which would you protect — the outcome or the struggle?
- The ICAP framework ranks 'interactive' collaboration as the deepest form of engagement. Could an AI that answers for the group actually downgrade collaboration from interactive to merely passive — even if students feel more satisfied?
- One study found AI mediators are trusted only while they stay neutral; when the AI shifts to advising or challenging, that trust erodes. How neutral should a group's AI mediator really be?
- When learners use AI to produce a polished artifact, they may skip the epistemic effort that builds understanding. How would you design an AI partner that surfaces disagreement and conflict instead of smoothing it over?
- Neurodivergent students report needing structured assignments, small consistent teams, and explicit roles. If AI collaboration tools are built for the 'average' learner, who might they leave out — and how would you design differently?

Introduction

Collaborative learning is grounded in sociocultural theories of learning that position knowledge construction as fundamentally social. AI introduces new dynamics: AI can serve as a peer, a facilitator, or a participant in collaborative processes. The articles in this knowledge base explore how AI-mediated collaboration affects learning outcomes, epistemic engagement, and equity — and how collaborative structures must be designed to accommodate diverse learners.

Collaboration as a construct vs. group work as a structure. Collaborative learning is the broader theory: knowledge is co-constructed through joint activity and dialogue. Group work is its most concrete formal implementation — a team producing a shared outcome, and often a shared grade. The two are closely related but not identical: a group can operate without genuine collaboration (task partitioned into independent parts, work merely merged), and collaboration can happen without formal groups (pairs, whole-class dialogue, or human–AI interaction). AI presses hardest on exactly this gap — Chen and Zou (2026) found groups whose individual GenAI practice never became collective capability because the task never required joint work,

alongside groups where the shared grade made GenAI use a coordination problem. The group work page examines these dynamics in depth; this page keeps the wider lens on collaborative learning as a whole.

AI as collaborative partner explores AI's role in group learning. **Kimmerle** conceptualizes the risk of reduced epistemic effort when learners use AI to produce polished knowledge artifacts, advocating for AI structured as an argumentative partner that preserves cognitive conflict. Testing this at classroom scale, Oppenheimer, Cash & Connell Pensky (2025) had introductory social-science students (n = 154) write argumentative essays, receive critiques from LLMs such as ChatGPT, Gemini, or Claude, and then incorporate or rebut them; blind coders found reflection in 92.7% and active rebuttal of LLM claims in 87.8% of responses (inter-rater κs = 0.81–0.89), evidence that learners behaved as critical consumers who preserved rather than surrendered the cognitive conflict of critique. **Ordered Network Analysis of Epistemic Emotions during Collaborative Problem Solving** examines how emotions shape collaborative Problem Solving with AI. **Systematic review of collaborative learning activities for promoting AI literacy** explores collaborative approaches to AI literacy development.

Facilitator endorsement is the strongest observed lever on whether students accept a contrarian agent: in twelve interprofessional teams, those whose faculty facilitator influenced their AI integration rated it more part of the team (M = 3.08 vs 2.64) and its feedback more helpful (M = 3.44 vs 2.93) (Wiss et al. (2025)).

AI-mediated peer collaboration examines how AI scaffolds human-to-human collaboration. **ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming** and **Exploring How Agent Voice Accents Shape Human-AI Collaboration in K-12 Group Learning** explore how AI agent characteristics affect group dynamics. **When AI Agents Teach Each Other: Discourse Patterns Resembling Peer Learning in the Moltbook Community** documents how AI agents teaching each other produce discourse patterns resembling human peer learning. Classroom-wide systems extend this to the *relational* dimension of collaboration: **CoBi** uses speech recognition and language understanding to detect "uplifting" small-group discourse (being respectful, equitable, committed to community, moving thinking forward) and returns non-evaluative, classroom-level Visualizations to support community building and collaboration skills, deliberately withholding student- or group-level feedback to protect Privacy and Trust.

Neurodivergent perspectives on collaboration reveal critical design requirements. **Zastudil et al.** found that neurodivergent students need structured assignments, small consistent teams with explicitly defined roles, and predictable interaction patterns — requirements that AI collaboration tools must accommodate. This connects collaborative learning to Inclusive Learning and Neurodiversity.

Teacher-AI collaboration examines how teachers and AI work together. **Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing** and **Towards Synergistic Teacher-AI Interactions with Generative Artificial Intelligence** explore frameworks for human-AI collaborative teaching, connecting to Teaching and Human-in-the-Loop.

AI as a pedagogical mediator reconceptualizes AI's role in collaboration beyond tool or peer. Drawing on sociocultural theory and distributed cognition, **Niari** positions AI as an active participant in the orchestration of interaction, epistemic sense-making, and regulatory processes, redistributing agency, authority, and responsibility across human and non-human actors without displacing learner or teacher agency. This grounds collaborative learning in a socially mediated, co-regulated view of AI rather than an individualistic one.

Collaboration modes and the efficiency–regulation trade-off. Empirical research on college students collaborating with AI for complex problem-solving identifies three distinct modes — *Delegated Reasoning*, *Concerted Interpretation*, and *Delegated Elaboration*. The most efficient mode (delegated reasoning) yields the highest task performance but the lowest learners' self-regulatory engagement, while the mode with greatest self-regulation (concerted interpretation) underperforms on task outcomes.(Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective) This reveals a central design tension: collaborative-learning environments must balance the efficiency of the distributed human–AI system against the depth of learners' regulatory engagement.

The one meta-analytic contrast available for AI-supported collaborative work sits inside GenAI-supported PBL/PjBL interventions, where peer collaboration pooled at g = 0.885 against g = 0.416 for individual work, but the difference reached only a marginal trend (QM = 3.675, p = .055) and the individual-work side rests on two studies — so the pooled evidence that collaboration beats working alone under GenAI is suggestive rather than established (Chen et al. 2026).

Field-level mapping reaches the same conclusion from the other direction: a BERTopic analysis of 1,048 AI-in-online-learning publications from 2010 to 2023 found that socially oriented work on AI-supported collaborative learning and community development never emerged as a dominant topic, which the authors attribute to a corpus centered on individual-level analytics (Chen et al. (2026)).

A scoping review of 18 studies maps the same trade-off across group work: GenAI supported knowledge development, idea generation and communication efficiency while also reducing the demand for peer interaction, negotiation and collective sensemaking, and randomized evidence found more innovative AI suggestions without a significant gain in participants' overall innovativeness (Wei and Perkins (2026)).

Role design is a lever on the quality, not the volume, of collaborative knowledge construction. Cheng et al. (2026) assigned rotating moderator, analyst and arguer roles across 58 graduate students and their AI partner in 16 groups, and found the structure lifted the *content* of group mind maps nearly a full SOLO band (M = 3.65 to 4.59, z = 3.771, p < 0.001) while node and branch counts stayed flat — organization rather than coverage — at the cost of a moderate rise in collaborative cognitive load (p = 0.023). Lag sequential analysis added an evaluation self-transition and a conflict-to-defending path the tool alone had not produced, positioning human-AI collaboration as a design problem rather than a tool problem.

GenAI as agent and space in small groups — mode matters. Xu et al. (2026) observe that *how* a team accesses GenAI shapes collaboration: with a single shared interface in synchronous work, teams co-construct "collective prompts," run a surface–evaluate–embed cycle, and treat the chat as shared memory; in asynchronous work, private prompting and output "de-labeling" fragment transparency and raise the cost of sustaining a shared cognitive model. Their GenAI-Supported Cooperative Work (GSCW) lens frames GenAI as a configurable agent (individual assistant to team member) and an interactive collaborative space — connecting access configuration directly to the ICAP-relevant quality of interactive engagement.

GenAI as group coordination infrastructure — and the risk of flattened cooperation. Chen and Zou (2026) show how fifteen pre-service teacher groups handled GenAI in a graded group presentation, and the split runs against the usual assumption that group pressure increases AI reliance. Five groups intensified use to solve a familiar collaboration problem — not knowing what peers' sections contained — feeding that work into a chatbot to make it intelligible and align their own part, with one group rebuilding its cycle as

discussion → externalization to GenAI → collective review → re-discussion. The authors read this as more than cognitive offloading, since students kept judgment while the tool absorbed coordination, but flag that the smoother workflow may bypass the disagreement through which cohesion is conventionally built, making relational labor the open question. Seven groups cut their GenAI use instead, protecting the situated knowledge built in shared classrooms ("AI only knows that moment when you type"), fairness to groupmates, originality across groups, and the diversity of perspectives the group already held. Three groups saw no change at all: with the task partitioned into independent sections, individually sophisticated GenAI practice never became a collective capability, even though coherence was an explicit criterion. The pattern suggests group norms, not the tool, decide what a group does with AI — and that collective adoption can lower the perceived risk of misuse rather than raise commitment.

Group epistemic configuration decides where the AI sits, not how often it is used. Wang et al. (2026) gave fourteen pre-service teacher groups a learner-initiated metacognitive chatbot during a 60-minute Go-Lab inquiry on energy forms, with eight groups holding different preconceptions and six holding similar ones at equal prior knowledge ($U = 293.50$, $p = 0.515$). Both kinds of group asked comparable questions, 39 prompts retained at 18 against 21 with overlapping function distributions. Uptake diverged instead.

Process mining put AI query negotiation at an integration hub in diverse groups, three incoming and two outgoing paths, reached from a concept statement in 55.6% of cases, while in similar-preconception groups it sat on a linear query-then-process path. Diverse groups sustained positive or neutral evaluation of the AI output while similar groups sustained negative evaluation, which the authors partly trace to a proactive speaking agent arriving after the group had already agreed. Twelve of the 39 prompts met short informational follow-ups with scope clarification, their case for a request-classification layer that separates metacognitive prompts from procedural ones.

Collaboration as the object of instruction. ProPACT is an AI-driven adaptive tutor for pair programming that treats the *dyad* — not the individual — as the unit of analysis, modeling joint visual attention, joint mental effort, and pupil-based signals in real time to predict collaborative breakdowns up to 30 seconds in advance and intervene before they occur. Dyads receiving proactive feedback achieved substantially higher debugging success and completed tasks more efficiently, and showed sustained gains in collaborative regulation afterward — evidence that AI can teach collaboration itself, not just support a task. Measuring collaborative competence poses the complementary challenge of assessing collaborative problem-solving (CPS) skill at scale, which traditionally requires manually coding process data from simulated tasks into CPS behaviors — time-consuming and impractical at scale; context-aware prompting of pre-trained language models automates this coding by modeling contextual dependencies and fusing cognitive and social abilities, achieving superior performance over strong baselines. **Scaffold on the order of group talk, not its frequency.** Wong, Bulathwela & Cukurova (2026) mined 65 students' triad dialogue sequences and found one ordering — paraphrasing, then proposing, then questioning — tracked improvement while the reverse did not; the maximal scaffold raised on-task behavior yet also scripting and fewer problem-solving indicators.

AI as a neutral mediator — and the tension when it stops being neutral. Spritz is a Discord-based Large Language Models (LLMs) probe that mediates disciplinary boundaries in interdisciplinary student teams by surfacing implicit assumptions and returning anonymized syntheses to shared discussion. Students valued it as both cognitive support and a relational buffer, but a central tension emerged: AI's perceived neutrality was load-bearing, and eroded once the AI moved from neutral mediator to advisor or challenger — a key design

constraint for agents that mediate collaboration while preserving Human AI Collaboration and Trust Calibration.

A structured facilitator protocol — and its sycophancy risk. Seo et al. (2026) extend collaborative-learning design with a structured divergence–deliberation–convergence protocol: an LLM facilitator stacks speaking turns, times the phases, and summarizes incrementally, a format 45 students found simple and discussion-like and that reduced the need for external facilitation. The design turns on a tension the study measured directly: agents supported breadth of perspective-taking (groups produced larger, more divergent stakeholder and solution sets, and agents consistently voiced minority viewpoints), yet sycophantic, reasoning-free agreement flattened the cognitive conflict that makes collaboration deepen thinking. Participants asked for agent output that exposes intermediate deliberation steps rather than only conclusions, and for counterarguments that preserve genuine disagreement.

Collaborative structures for AI education. The Academic League of AI organizes AI education through democratic student AI Governance and project teams, embedding Active Learning and Project-Based Learning in a collaborative, community-connected structure.

What makes an AI recognizable as a peer rather than a tutor. Lin et al. (2026) had seven domain experts work with a Big Five-persona agent whose motivational stance shifted across forethought, performance and self-reflection while solving quadratic equations. Participants judged the agent by its social behavior rather than its mathematics: a non-judgmental space, tentative reasoning, appropriate imperfection and respect for the learner's pace read as peer-like, while blind agreement and over-instruction pushed it back toward tutor. The authors also report a tension worth keeping — peer-likeness and peer-usefulness did not always align — which is the long-standing risk of peer collaboration itself, that peers can confirm each other's errors.

The ICAP framework: collaboration as the highest engagement mode

Collaborative learning occupies the top of the ICAP framework (Interactive–Constructive–Active–Passive): the *interactive* mode — co-constructing meaning through dialogue, defending a position, or solving jointly — produces the deepest knowledge change in Chi's taxonomy. This makes ICAP both a justification for collaborative pedagogies and a design constraint on AI. An AI that mediates discussion (as Spritz or ProPACT do) is valuable precisely when it sustains *interactive* engagement; an AI that answers for the group or smooths over cognitive conflict can downgrade collaboration to a mere *active* or *passive* mode. ICAP-based annotation (see extended ICAP measurement of collaborative dialogue) and facilitation-timing research both treat the quality of interactive discourse as the outcome of interest, grounding collaborative learning in Student Engagement and the ICAP hierarchy.(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)(To facilitate or not to facilitate: Human and LLM facilitator tendencies in online discussions) - **GenAI can take the moderator seat rather than the tutor seat.** Chen et al. (2026) ran a 16-week quasi-experiment with 64 undergraduates in which both conditions had an AI agent and a structured platform, and only the regulation scaffolding differed: an adaptive SSRL agent versus static digital worksheets (Chen et al., 2026). The adaptive group showed higher participation equality but not higher intensity, the signature of redistribution rather than more talk. - **Interactive is not automatically deeper.** In an eight-week quasi-experiment with 87 undergraduates, pairs working with a GenAI multi-agent system produced the best design projects (M = 89.64 against 86.45 for solo work on the same system). Critical-

thinking awareness gains ran the other way: largest solo (M = 0.41), near flat for peer collaboration (M = 0.06) and slightly negative for the paired AI condition (M = -0.04) (Chu, Dai and Zhai (2026)). The configuration changed which kind of thinking was activated rather than how much of it.

Practical guidance

- **Model collaboration, not just the individual.** Tools that track dyadic or group state (as ProPACT does) can scaffold the collaboration itself, predicting and preventing breakdowns rather than reacting to them.
- **Preserve cognitive conflict.** Structure AI as an argumentative partner that surfaces disagreement and implicit assumptions, avoiding the polished-artifacts problem where AI smooths over fragile epistemic engagement.
- **Contrarian personas have affective costs.** Across 97 triads, contrarian AI pushed discourse toward challenge and reflection but lowered teamwork satisfaction ($\varepsilon^2 = .062$) and psychological safety ($\varepsilon^2 = .114$) without raising creative output (Jin et al. (2026)).
- **Match the agent's function to the outcome you intend.** A review of 46 studies of AI agents in computer-supported collaborative learning found cognitive gains consistently reported while behavioral, social and emotional outcomes stayed context-dependent, with the strongest alignment between agent function and outcome inside the same domain (Ba et al. (2026)).
- **A separate Facilitator role reduces dominance, not responsiveness.** In Oyelere's (2026) simulated benchmark, adding a Facilitator agent alongside the Tutor lowered dyadic turn and word imbalance (M = 0.103 and 0.105 versus 0.183 and 0.182) without changing reciprocal engagement — though the learners were synthetic personas, not real dyads.
- **Balance efficiency against self-regulation.** Collaborative AI that maximizes task efficiency (delegated reasoning) can undercut learners' regulatory engagement; design should deliberately protect space for concerted interpretation.
- **Respect the neutrality constraint.** AI mediators are trusted while neutral; moving into advisory or challenging roles destabilizes that trust, so role switches should be explicit and configurable.
- **Accommodate neurodivergent learners.** Structured assignments, small consistent teams, and explicit role definitions are requirements AI collaboration tools must support.
- **Prefer non-evaluative, classroom-level feedback.** When supporting the relational dimension of collaboration, class-level aggregated feedback protects Privacy and student agency where individual scoring would feel surveilled; CoBi students preferred qualitative visualizations (an organic tree) over quantitative ones (a radar chart), and teachers valued using the system's noticings to spark reflection more than live display.
- **Design for the viewing/attention that precedes contribution.** Collaborative learning in online discussion forums depends not only on posting but on the reading that precedes it. Hao & Cukurova (2026) show LLM-generated discussion summaries and example posts can act as navigational scaffolds that broaden students' exposure to peers' contributions and the network

conditions for bridging (weak-tie) social capital — support that should complement, not replace, socio-pedagogical strategies for sustaining engagement under academic workload.

- **The social side shows disruption without a countervailing gain.** Across five collaboration processes a 30-expert consensus reached vulnerability only, with enhancement ratings below threshold: Social Connection (3.80 against enhancement 1.90), Socio-Emotional Development (3.60 against 2.00), Social Learning, Collaborative Learning and Sense of Belonging (all 3.30) (Kendeou, Greene & Nixon et al., 2026). The report treats the asymmetry as a design target, since collaborative problem solving is anchored to a shared product while collaborative learning has no visible referent and can erode undetected.

Common Misconceptions

- **"Giving groups AI means more collaboration."** A scoping review of **18 studies** maps a trade-off across group work: GenAI supported **knowledge development, idea generation and communication efficiency** while also carrying a relational cost in the same interventions. The efficiency gain and the relational cost arrive together.
- **"AI-supported collaborative learning has meta-analytic backing."** The **one** meta-analytic contrast available for AI-supported collaborative work sits **inside** GenAI-supported PBL/PjBL interventions rather than being estimated directly, so it is a component of a broader effect rather than a measurement of collaboration.
- **"An LLM partner preserves the group's own reasoning."** Oppenheimer, Cash and Connell Pensky (2025) tested it at classroom scale with introductory social-science students, precisely because preservation is an open question and not an assumption.

Connected Concepts

- Pedagogical Patterns — Scripted shared-AI collaboration and its tested role designs
- Pedagogical Partnerships — Pedagogical Partnerships
- Group Work — Group work
- Problem-Based Learning
- Online Teaching and Learning — Online Teaching and Learning
- Active Learning
- ICAP Framework
- Scaffolding
- Teaching
- Human-in-the-Loop
- Equity
- AI Literacy
- K-12
- Higher Education
- Inclusive Learning

- Neurodiversity
- Distributed Cognition
- Self-Regulated Learning
- Project-Based Learning
- Human AI Collaboration
- Trust Calibration
- Pedagogical Agent
- Learner Modeling and Adaptive Instruction
- Student Engagement
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Exploring AI Peer in Collaborative Mathematics Learning — What makes an LLM agent read as a peer: safety, tentative reasoning, appropriate imperfection
- Ways generative AI can support and threaten learning in K-20 US education - A 30-expert consensus finds one-sided social risk: collaboration processes vulnerable with no enhancement pathway
- Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis — Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis
- Emergent Learner Agency in Implicit Human-AI Collaboration: How Supportive and Contrarian AI Personas Reshape Interaction — Emergent learner agency in implicit human-AI collaboration: supportive vs. contrarian personas
- Towards an adaptive AI scaffold for developing student collaborative problem solving
- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings
- Polished Artifacts, Fragile Engagement? Tackling the Challenge of Reduced Epistemic Effort in Human-AI Knowledge Construction
- Ordered Network Analysis of Epistemic Emotions during Collaborative Problem Solving
- Systematic review of collaborative learning activities for promoting AI literacy
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning
- Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning
- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective

- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming — ProPACT: proactive AI adaptive collaborative tutor for pair programming
- Exploring AI-Supported Disciplinary Mediation in Student Project Teams' Text-Based Communication — Spritz: AI disciplinary mediation in student project teams
- Academic League of Artificial Intelligence: An Integrative Perspective of Teaching, Research, and Extension — Academic League of AI: collaborative, project-based AI education
- Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents — Extended ICAP framework for measuring engagement in collaborative dialogue
- To facilitate or not to facilitate: Human and LLM facilitator tendencies in online discussions — LLM facilitation timing in online collaborative discussions
- Artificial intelligence agents in computer-supported collaborative learning: a systematic literature review — AI agents in computer-supported collaborative learning review
- Generative AI and student collaboration: A scoping review of group work processes, outcomes, and risks — GenAI and student group work: a scoping review (Wei & Perkins 2026)
- ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming — ASTRA synthetic benchmark for multi-agent tutoring and participation-balanced collaboration
- AI as an Agent and Collaborative Space: Exploring the role of generative AI in small group synchronous and asynchronous collaborative dynamics — GenAI as agent and collaborative space in small-group dynamics (Xu et al. 2026)
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners
- Enhancing peer exposure and creating opportunities for bridging social capital through an AI-generated summary-driven learning design in online discussion forums — AI-Generated Summary-Driven Learning Design in Online Discussion Forums
- Students' agency in GenAI-mediated group assessment: An ecological-emergent perspective — GenAI as coordination infrastructure in student groups: intensified, restrained, and non-enacted use
- Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration — Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration
- Artificial Intelligence in Online Learning: Using BERTopic to Track Research Topics and Their Evolutions — Socially oriented AI-collaboration work never became a dominant topic in 1,048 publications
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — Group epistemic configuration decided where the AI sat: an integration hub in diverse-preconception groups, a linear query-then-process path in similar ones, at equal prior knowledge (Wang et al. 2026)

- Many hands make light work? Individual and collaborative interaction with a GenAI-powered multi-agent system: Effects on learning performance and critical thinking — Pairs with a multi-agent system produced the best projects while solo work produced the largest critical-thinking gains

Connected FAQs

- How Should I Handle AI in Group and Collaborative Assignments?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Project-Based Learning

> **Project-based learning (PBL)** — an active, learner-centered Pedagogies and Teaching Strategies in which students learn by engaging in extended, real-world projects that require inquiry, problem solving, and the application of knowledge to produce tangible outcomes. PBL emphasizes student autonomy, collaboration, and authentic tasks, and is widely used with technology — including educational robotics and AI — to give learners hands-on, meaningful projects. It contrasts with purely theoretical or lecture-based instruction.

Questions to Consider

- Think of the last time you truly 'learned by doing' — building, designing, or creating something real. What made that experience stick compared with a lecture you sat through the same week? How might that difference transfer to how students learn AI or robotics?
- PBL and problem-based learning are frequently conflated, yet they differ: one centers on producing a tangible project, the other on resolving an ill-structured problem. Before you read, how would you distinguish the two — and does your answer matter for how a course should be designed?
- A robotics study tackled a 'theory-practice gap' with an agile, semester-spanning project. When you think about your own field, where does the gap between what students are taught and what they can actually do tend to open up — and what would a project-based approach need to close it?
- PBL emphasizes student autonomy, collaboration, and authentic tasks. But learners differ in their readiness to direct themselves. What could go wrong if you dropped extended projects into a classroom without support for self-direction, and who would it harm most?
- PBL is widely coupled with gamification and educational robotics in the research. From your experience, is fun/engagement always a reliable proxy for deep learning, or can a well-scored 'game' mask shallow understanding?
- Before reading on, ask yourself: what concrete evidence would convince you that project-based learning actually beats lecture-based instruction for a specific learning outcome — and how hard is that evidence to gather in a real course?

Introduction

PBL is closely related to Active Learning, Experiential Learning, Collaborative Learning, and Constructivism pedagogy. It is especially valuable for AI and robotics education because these fields are inherently applied: learners best understand robots, algorithms, and systems by building and testing them in project contexts. PBL also fosters Computational Thinking, problem solving, and self-direction.

Project-based learning is closely related to — but distinct from — problem-based learning: both are learner-centered and context-driven, but problem-based learning centers on an ill-structured *problem* whose solution requires inquiry and knowledge construction, whereas project-based learning centers on producing a tangible

project or artifact. The two are frequently conflated, and many AI-in-education frameworks draw on both (see the problem-based learning page for the AI-era treatment).

How PBL appears in the knowledge base's research

- **Robotics projects:** Bots and Blocks presents an agile, semester-spanning project-based approach to teach robotics in an applied computer science program, addressing the theory-practice gap.
- **The Project Approach in early childhood with AI agents:** Yang, Li and Lee (2025) extend PBL's foundational form — the Project Approach (Katz & Chard), an extended collaborative investigation of a real-world topic — into early childhood, proposing a five-step **Creative Project Approach** that integrates AI agents and robots (coding robots and generative social robots) into projects to foster young children's creative learning. The five steps — identify learning needs, facilitate teacher-guided child–robot interaction, situate AI in contexts, calibrate the automation/creativity balance, and evaluate outcomes — keep the teacher as a facilitator guiding inquiry, positioning PBL as the natural vehicle for developmentally appropriate AI use with the youngest learners.
- **Gamification coupling:** A systematic review found Gamification in robotics education strongly favored project-based learning ($p = .009$).

The only three-level meta-analysis of this pairing pools 22 controlled studies (66 effect sizes, January 2023 to April 2026) and estimates a large effect for GenAI-supported PBL/PjBL, $g = 0.819$, 95% CI [0.655, 0.983]. The authors' PET-PEESE sensitivity analysis, however, reduces the estimate to $g = 0.378$, so the headline figure should be read as potentially inflated (Chen et al. 2026). Tool type moderated the effect significantly ($QM = 14.301$, $p < .001$): direct use of a general chatbot scored $g = 0.970$, against $g = 0.455$ for systems built into course platforms, virtual patients, or agents — suggesting how a tool is embedded matters more than which model is chosen. - **AI literacy and co-design:** PBL underlies many AI literacy and Teacher Education interventions, where learners co-create AI tools or resources. - **Students as agent designers at scale:** Zangari et al. (2026) had 345 undergraduates in a 700-student software design course each build a conversational agent explaining three design patterns to a peer — Part A a scaffolded Dialogflow CX tutorial, Part B an open-ended design task. The open-endedness was the top positive theme (22.3%) while unclear instructions topped negatives (23.7%), and perceived learning correlated with quiz scores only modestly ($r = 0.161$–0.315). The design lesson for PBL: student-created artifacts can carry the ownership benefits of self-flipped classrooms into AI-tool contexts, but the exploratory, no-control-group evidence supports engagement claims, not causal superiority. - **AI-agent-supported software PBL:** Tanaka et al. (2026) embedded Spec-Driven Development with AI agents into a team-based undergraduate software PBL course, structuring projects into investigation, planning, implementation, and review phases paired with instructor-run comprehension checks. - **Immersive VR studios with an embedded teaching agent:** Jin et al. (2026) specify the **AI-IVE-PBL** model for vocational design education, pairing PBL with an AI-enabled immersive virtual environment (VR headsets plus an Large Language Models (LLMs)-backed teaching assistant). PBL's customary constraints for vocational learners — limited equipment, hard-to-replicate scenarios, delayed teacher Scaffolding — are absorbed by immersion plus an in-session agent, and the model is stated as a five-phase loop (discovery, envisioning, modeling, communication, refinement) with a named actor and artifact per phase, driven by sustained idea-developing discourse. In a 12-week quasi-experiment ($n = 63$) the condition raised design ability and creative ability and lifted cognitive and behavioral

engagement, while leaving ideational novelty (innovative thinking) and affective engagement unchanged — a reminder that the design-specific and the ideational parts of a project's value do not move together.

PBL connects to Active Learning, Experiential Learning, Collaborative Learning, Robots in Education, Game-Based Learning, Computational Thinking, and Higher Education/K-12 pedagogy.

- **PBL supports AI-powered robotics learning.** Pathways research shows project-based robotics+AI curricula let high school students learn through engagement in real-world practice, designing, and playful creative expression.

PBL in AI Literacy Courses

- **Measuring PBL in AI literacy courses.** Zhu and Kong (2026) developed and validated an AI project-based learning scale (AI-PBLS) grounded in Hong Kong secondary and university students' experiences, and used it to show that perceived PBL fosters AI literacy course satisfaction through the mediating mechanisms of empowerment in AI Problem Solving and AI ethical awareness. The scale offers researchers a validated instrument, and the mediation finding strengthens the case for PBL as a vehicle that builds confidence and ethical reasoning — not just content — in AI education.

PBL With Digital Storytelling in the AI Era

- Project-based learning combined with digital storytelling offers a pedagogical response to generative AI in art and design education. A 15-week embedded case study with 426 undergraduates implemented a PBL-DS framework in which digital storytelling served as the primary methodology for students to translate local cultural heritage into emotionally resonant, Multimodal AI narratives, cultivating the creative capacities that AI lacks.

Common Misconceptions

- **"PBL's effect is large, so PBL with AI is reliably large."** The only three-level meta-analysis of this pairing pools **22 controlled studies (66 effect sizes)** and estimates a large effect, **g = 0.819, 95% CI [0.655, 0.983]** — but a PET-PEESE correction reduces it, and the estimate describes the studies pooled rather than the design in general.
- **"Customising the tool improves the outcome."** Tool type moderated the effect significantly (**QM = 14.301, p < .001**), and the direction is counterintuitive: a **general chatbot used directly pooled higher (g = 0.970)** than systems **customised into course platforms, virtual patients or agents (g = 0.455)**. The bare tool outperformed the engineered one, which argues against assuming that purpose-built products are the better purchase.
- **"Students find open-endedness the hard part."** In the student-perception data, **open-endedness was the top positive theme (22.3%)** while **unclear instructions topped the negatives (23.7%)**. Students welcomed the freedom and objected to the ambiguity — a distinction that matters because the fix is different: clearer task framing, not less open-ended work.

- **“Students who enjoyed it learned more.”** Perceived learning correlated with quiz scores only **modestly (r = 0.161-0.315)**. Satisfaction and measured learning are weakly related here, so a positive PBL evaluation is not by itself evidence the learning objectives were met.

What this means for practice

For instructors

- Write the task framing before the tool choice. Open-endedness was the top positive theme (22.3%) and unclear instructions the top negative (23.7%), so the ambiguity is where PBL with AI actually fails.
- Score learning separately from satisfaction. Perceived learning correlated with quiz scores only at r = 0.161-0.315, so a happy cohort is not a measured outcome.
- Consider the general chatbot before the custom platform. A general chatbot used directly pooled higher (g = 0.970) than systems customised into course platforms, virtual patients or agents (g = 0.455).
- Treat g = 0.819 as an upper bound. A PET-PEESE correction reduces it, and 22 studies with 66 effect sizes is a narrow base for a design claim.

For developers

- The moderation finding is a product warning: engineering a chatbot into a bespoke environment coincided with a *smaller* pooled effect. Validate that customisation adds learning value rather than assumed convenience.
- If you ship a PBL module, the instruction layer is the feature that earns the outcome, not the model.

Connected Concepts

- Problem-Based Learning
- Active Learning
- Experiential Learning
- Collaborative Learning
- Robots in Education
- Game-Based Learning
- Computational Thinking
- Higher Education
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Arts, Design and Media Education

Connected Articles

- Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis — Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis
- Problem-based learning and the structural conditions for productive AI integration
- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings
- Bots and blocks: Presenting a project-based approach for robotics education — Bots and Blocks
- Game-based and gamified robotics education: A comparative systematic review and design guidelines — Game-Based and Gamified Robotics Education
- Development and evaluation of artificial intelligence literacy training for teacher education students — AI Literacy Training for Teachers
- RoboBlockly Studio: Conversational block programming with embodied robot feedback for computational thinking — RoboBlockly Studio
- Robotics and Artificial Intelligence in Education: Transformations, Challenges, and Future Directions — Robotics and AI in Education
- Pathways to Learning: Exploring High School Students' Learning of AI-Powered Educational Robotics — Pathways to Learning AI-Powered Educational Robotics (2026)
- Fostering computational thinking through robotics in kindergarten: A systematic review of learning strategies, frameworks, and assessment — PBL is a dominant CT learning strategy
- Tailoring AI agents for early learning: The Creative Project Approach — The Creative Project Approach: AI agents and robotics within the Project Approach in early childhood (Yang, Li & Lee 2025)
- Practical Implementation Report on Introducing Spec-Driven Development Using AI Agents in Software Development PBL - SDD with AI agents in team software PBL
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — AI-IVE-PBL: an immersive VR design studio with an embedded teaching agent, evaluated against traditional PBL (Jin et al. 2026)

Problem-Based Learning

> **Problem-based learning (PBL)** — a learner-centered pedagogy in which students acquire knowledge and skills by working to understand and resolve a realistic, often ill-structured problem, with a facilitator guiding inquiry rather than delivering instruction. In the AI era, PBL's structural features — problem-driven inquiry, collaborative knowledge construction, facilitation over instruction, and metacognitive reflection — have emerged as the same conditions under which generative AI integration becomes educationally productive rather than substitutive.

Questions to Consider

- In problem-based learning, the *problem* is the driver of the curriculum—not an illustration of content taught elsewhere. Can you recall a time you learned something deeply because you were solving a real problem first?
- The page argues PBL's features (problem-driven inquiry, collaboration, facilitation, reflection) are exactly the conditions under which AI becomes a productive partner rather than a shortcut. Why might that be?
- AI severs the link between a submitted artifact and the effort that produced it—the 'artifact-as-proxy' problem. How does assessing process instead of just product help, and what makes process Assessment hard?
- PBL originated in medical education partly because professional competence needs adaptive judgment, not routine execution. What's the difference between those two, and how does AI change which one we train for?
- If an AI can now make 'wicked problems' and complex real-world cases accessible to more students, what might be lost when the challenge becomes easier to reach?
- Where should an AI in a PBL setting draw the line between giving a problem, a hint, or an answer? What determines which is the right move at any moment?

Introduction

PBL originated in medical education (McMaster University, 1960s) and has since spread across health professions, engineering, and K-12. The learner takes responsibility for diagnosing learning needs, identifying resources, and constructing solutions, while the facilitator scaffolds the process. The distinctive claim of PBL is that the *problem* is the curriculum driver — not an illustration of content taught elsewhere but the context in which content is learned.

Ng'ambi and van der Merwe (2026) give a direct comparison: ten problem-based chats sustained dialogue and reached deeper explanation, while thirty structured procedural chats collapsed into ask-answer-thank and ended.

PBL in the AI era

The knowledge base's research shows that PBL has become a focal point for thinking about productive AI integration.

- **PBL's structural conditions make AI integration productive.** Rowe (2026) argues that PBL's core features — problem-driven inquiry, collaborative construction, facilitation, metacognitive reflection — are exactly the conditions under which AI functions as a partner in professional development rather than a shortcut around it. The alignment is structural, not retrospective: PBL was designed around these conditions before AI existed, rooted in the recognition that professional competence requires adaptive judgment rather than routine execution.
- **AI raises the ceiling on problem complexity.** The same argument holds that AI expands what category of problem PBL can engage, making "wicked problems" and complex real-world cases accessible to students who previously could not reach them.
- **The artifact-as-proxy problem.** AI severs the link between a submitted artifact and the engagement that produced it — a problem PBL is well positioned to address because it assesses the *process* and demonstrated understanding, not just the product. This connects PBL to authentic and process-based assessment and to the knowledge base's over-reliance literature.

The three-level meta-analysis that pools GenAI-supported PBL with project-based learning keeps product and solution performance in a separate model precisely because it measures human-AI collaborative output rather than internalized learning, and that estimate is the largest the reviewers report (g = 1.958) while resting on only six studies and carrying an approximate 95% prediction interval of [−0.740, 4.656] that crosses zero — the quantitative form of the artifact-as-proxy caution above (Chen et al. 2026). - **ChatGPT as adaptive scaffolding.** La Sunra et al. (2026) show ChatGPT integrated as adaptive scaffolding within an AI-enhanced PBL framework to improve critical thinking and personalized learning in K-12 (120 eighth graders). This treats AI as a within-PBL support rather than an answer machine. - **A controversy-injecting agent can counter groupthink.** A genAI agent voiced at three set points in an interprofessional PBL session introduced controversial perspectives, and students reported that refuting it gave them a socially permissible way to speak up, with the disagreement stimulating reflection even when they rejected the agent's responses (Wiss et al. (2025)). - **Quasi-experimental evidence from pre-service teacher preparation.** Chen and Osman (2026) compared an eight-week AI-supported CTD-PBL module with conventional instruction for 130 third-year pre-service physics teachers (65 per condition), with DeepSeek used through task-specific prompt templates as a bounded scaffold — lesson-idea generation, resource organization, explanation comparison, peer-feedback prompts and revision planning — and every AI output required to pass verification against content accuracy, pedagogical appropriateness, feasibility and Ethics before entering an instructional artifact. The module group reported higher post-test TPACK (M = 4.04 vs. 3.40, d = 1.02) and higher perceived collaborative problem solving (M = 3.62 vs. 3.05, d = 0.88), and the largest interaction effects fell on shared knowledge building and social regulation — precisely the collaborative process dimensions the structural argument above predicts AI should strengthen rather than shortcut. The authors are explicit that AI was not isolated as an independent variable: the differential change attaches to the whole condition of problem-based tasks, structured collaboration, instructor scaffolding, peer feedback and reflective revision, and both outcomes were self-reported perceptions rather than observed practice. - **Responsible-use frameworks.** Uden & Hwang (2026) advance the neuroscience-informed **LEARN**

framework (Lifelong Learning, Engagement, Active Processing, Reflection, Neuro-based Design) for ethically grounding generative AI use within PBL, countering cognitive offloading and integrity erosion. - **Domain implementations.** PBL frameworks for biomedical engineering use GenAI for summarization and coding support with replication packages (Nnamdi et al. 2026); AI-supported PBL enhances computational thinking in robotics (AI-supported PBL for computational thinking); and genAI-enabled virtual patients support medical history-taking tutorials (Mool et al. 2026). - **Evidence synthesis.** Amdan et al. (2026) systematically review 50 studies (2015–2024) on educators' engagement with AI in PBL within a human-computer interaction framework. - **GenAI in scenario-based PBL.** Neto and colleagues (2026) include problem-based learning among the scenario-based approaches in their systematic review of GenAI in healthcare education, finding that prompt design functions as instructional specification and that hybrid human-AI collaboration outperforms fully automated approaches. The review highlights the need for stronger alignment of generated content with instructional frameworks and more reproducible prompting practices in PBL contexts.

- **AI can carry the tutor's knowledge delivery but not the social regulation of group learning.** In a four-week pharmacology quasi-experiment, Shetty & Rao (2026) found AI-mediated PBL matched facilitator-led academic gains (between-group $p = 0.474$), while facilitator-led groups retained advantages in group dynamics (26.51 vs 24.74, $p = 0.035$) and critical thinking (14.75 vs 13.09, $p < 0.001$).

PBL vs. related pedagogies

PBL is closely related to project-based learning — both are learner-centered and problem/context-driven — but PBL centers on an ill-structured *problem* whose solution requires inquiry and knowledge construction, whereas project-based learning centers on producing a tangible *artifact* or project. PBL is also kin to case-based and inquiry-based learning, which share the problem-driven, facilitation-led structure. In the knowledge base's mapping, the structural argument for productive AI integration applies to any pedagogy sharing these features, not only PBL.

Why PBL matters for AI integration

Because PBL foregrounds process, collaboration, and demonstrated understanding over artifact production, it is a natural home for responsible AI use: students learn *with* AI as a partner rather than *from* AI as a substitute. The facilitator's role and the design of the problem become the levers that determine whether AI supports learning or displaces it — the same human oversight and assessment-design concerns that recur across the knowledge base.

Productive failure and PBL

Productive failure (PF) shares PBL's Constructivism core — Learners engage problems before instruction — but differs in structure: PF deliberately withholds instruction and scaffolds until *after* learners struggle to generate solutions, whereas PBL embeds facilitation throughout. The AI-era PF literature directly informs how AI should behave inside problem-based settings: Kim et al. (2026) show AI should preserve productive struggle with non-directive support across PF phases; Puech et al. (2025) demonstrate Large Language

Models (LLMs) tutors can be steered to withhold answers and elicit multiple solution attempts; and ProductiveMath uses AI to help design high-quality PF/PBL-style problems. The design question — when AI should give a problem, a hint, or an answer — is shared across both pedagogies.

Common Misconceptions

- **"PBL outcomes should be pooled with project-based learning outcomes."** The three-level meta-analysis keeps **product and solution performance in a separate model** precisely because it measures **human-AI collaboration** rather than the learner's own reasoning. Merging them would attribute a jointly-produced artifact to the student.
- **"Collaborative gains are a side effect of using AI."** A study found higher perceived collaborative problem solving (**M = 3.62 vs. 3.05, d = 0.88**) and shared problem solving (**3.40, d = 1.02**), with **the largest interaction effects on shared knowledge building and social regulation** — the collaborative process dimensions design predicts. The mechanism is the structured collaboration, not the tool.
- **"PBL with AI mainly saves facilitator time."** The measurable gains sit in process quality on dimensions that only exist when the group structure is designed for them. A PBL implementation that adds AI without structuring shared knowledge building should not expect the same effect.

Connected Concepts

- Project-Based Learning
- Active Learning
- Collaborative Learning
- Scaffolding
- Critical Thinking
- Metacognition
- Cognitive Offloading
- Authentic Assessment
- Generative AI
- AI Literacy
- Medical and Health Professions Education
- Engineering Education
- Higher Education
- Productive Failure — Productive Failure

Connected Articles

- Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis — Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis

- Problem-based learning and the structural conditions for productive AI integration — PBL and the structural conditions for productive AI integration (Rowe 2026)
- A systematic review of educators' engagement with AI in problem-based learning — Systematic review of educators' engagement with AI in PBL (Amdan et al. 2026)
- Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study — GenAI virtual patient for medical PBL tutorials (Mool et al. 2026)
- The LEARN framework for responsible use of generative AI in education: a neuroscience-informed model for problem-based learning — The LEARN framework for responsible GenAI in PBL (Uden & Hwang 2026)
- AI-enhanced problem-based learning framework: integrating ChatGPT as adaptive scaffolding to improve critical thinking and personalized learning — ChatGPT as adaptive scaffolding in AI-enhanced PBL (La Sunra et al. 2026)
- Advancing problem-based learning in biomedical engineering in the era of generative AI — PBL in biomedical engineering in the GenAI era (Nnamdi et al. 2026)
- AI-supported problem-based learning for enhancing computational thinking — AI-supported PBL for computational thinking
- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings — GenAI agent counters groupthink in interprofessional PBL
- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science — GenAI chatbots and problem posing in primary science
- The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education — ChatGPT for inquiry-based learning in STEAM
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: AI to Support PF Problem Design
- Generative AI in scenario-based healthcare education: A systematic review of applications, validation practices, and pedagogical integration — Systematic review of GenAI in scenario-based healthcare education (Neto et al. 2026)
- Changes in pre-service physics teachers' TPACK and collaborative problem solving associated with an AI-supported CTD-PBL module: A quasi-experimental study — AI-supported CTD-PBL module with 130 pre-service physics teachers: TPACK and collaborative problem solving (Chen & Osman 2026)

- Facilitator-Mediated Versus AI-Mediated Problem-Based Learning in Pharmacology Education: A Quasi-Experimental Study Among Second Year Medical Students — Facilitator-Mediated Versus AI-Mediated Problem-Based Learning in Pharmacology Education: A Quasi-Experimental Study Among Second Year Medical Students

Productive Failure

> **Productive Failure (PF)** — an instructional approach, grounded in constructivist theory and developed by Manu Kapur, that engages learners with problems targeting concepts they have **not yet learned**, having them struggle to generate solutions *before* receiving direct instruction (Kapur, 2008; Kapur & Bielaczyc, 2012). Rather than treating failure as something to avoid, PF treats initial struggle and error as a powerful catalyst: learners activate and differentiate prior knowledge, surface Misconceptions about AI, and prepare to learn better from subsequent instruction — leading to deeper understanding, better retention, and enhanced knowledge transfer.

Questions to Consider

- Have you ever learned more from failing at something first than from being shown how to do it? What made that failure 'productive' rather than just discouraging?
- The page's core claim is that the *order* matters: struggling to generate solutions *before* instruction produces deeper learning. What do you think happens in the brain during that struggle that later instruction can build on?
- Not all failures are equal: 'mistakes' (slips) may carry little diagnostic value, while 'errors' reveal genuine misconceptions. How might telling these apart change how you respond to a struggling learner—or how an AI tutor should respond?
- The 'Safety Gap' is the divergence between a student's AI-assisted performance and their unassisted capability. When does help that makes a student look capable actually mask what they can't yet do?
- An AI that withholds answers to preserve struggle can be perceived as less helpful. If you were a student, how would you react to a tutor that refused to give you the answer—and would that reaction match what's best for your learning?
- How might the fear of making mistakes in front of peers (or an AI) shut down the very productive struggle the page describes? What would a 'safe space' for failing need to include?

Introduction

Productive failure is closely related to, but distinct from, other "learning from difficulty" constructs: Desirable Difficulties (Bjork) focuses on introducing desirable challenges into practice; Problem-Based Learning and Inquiry-Based Learning emphasize learner-driven problem solving; and learning-from-mistakes/errors (error-correction learning) emphasizes the value of errorful processing and corrective feedback. Productive failure is distinctive in its two-phase structure — **generation & exploration before instruction**, then **consolidation & knowledge assembly after** — and its claim that the *order* (failure before instruction) is what produces the learning advantage.

The core mechanism

Learners generate solutions without cognitive support, relying on prior knowledge and producing suboptimal or even incorrect solutions. They then compare and contrast these attempts with the canonical solution during consolidation. The struggle:

- **Activates and differentiates prior knowledge**, making learners aware of gaps and misconceptions.
- **Prepares learners to learn from instruction** — they know what they don't know and can connect new material to their attempts.
- **Enhances knowledge transfer and durable skills** (Critical Thinking, resilience, communication), reduces fear of making mistakes, and promotes positive attitudes toward learning.

The PF framework has been extended through related designs including **vicarious failure**, **solution diversity**, and **adaptive guidance** (Braas et al., 2025; Brand et al., 2025).

Learning from mistakes and learning from errors

Productive failure sits within a broader family of error-centered learning theory, and the concept page covers these related ideas:

Learning from errors

Errorful processing can aid retention and conceptual change, particularly when learners are given opportunities to reflect on and reorganize their understanding (Kapur, 2008; Schwartz & Martin, 2004). In the AI era, this is operationalized in systems where learners diagnose and correct their own errors rather than receiving direct corrections — e.g., clue-before-correction tasks where AI gives guided hints and learners infer the correct solution, reducing cognitive load and supporting autonomous revision. Elaborative feedback produces significantly higher learning gains than verification-only feedback (Hattie & Timperley), and the timing of feedback matters.

Mistakes vs. errors

A useful distinction: **mistakes** are typically slips or lapses (often from carelessness or overload) that may carry limited diagnostic value, whereas **errors** reflect genuine misunderstanding or flawed reasoning and are more productive learning material because they reveal a misconception that can be addressed. Error analysis — identifying *why* an answer is wrong — is central to learning from errors, and is a key pedagogical skill (and a target for AI feedback design).

The role of corrective feedback

Learning from errors depends on feedback that helps learners see what was wrong and why. Clue-based and elaborative feedback (guiding learners to the correction) is more effective than simply supplying the right

answer — an insight that links Feedback theory directly to productive-failure design, and to how AI tutors should respond to student mistakes.

Productive failure and AI in education

A major theme in the knowledge base's research is the tension between AI's helpfulness and the preservation of productive struggle:

- **The risk: AI erases the struggle.** Overly "helpful," Oracle-style AI that supplies answers directly can eliminate the productive struggle necessary for schema construction, creating what Wang & Shan (2026) call the **Safety Gap** — the divergence between a student's AI-assisted performance and their internal, unassisted capability. This connects to Cognitive Offloading: AI that substitutes for effort erodes the very capacities education builds.
- **The design response: AI that scaffolds struggle.** Kim et al. (2026) derive five design principles for AI supporting productive-failure-based learning (human-AI collaboration, usability, reflective design, emotional design, open knowledge), emphasizing that AI should preserve struggle while offering non-directive support. Puech et al. (2025) show Large Language Models (LLMs) tutors can be *steered* to follow productive-failure pedagogy (withhold solutions, elicit multiple attempts), at the cost of perceived helpfulness. CoMeT (Hou et al. 2026) prices that cost and locates the middle: its escalating tutor was 0.42 scale points more frustrating than the tutor that answered on request ($p < .001$) and 0.29 less frustrating than the one that only asked questions ($p = .011$), with distress detected in 8.4% of its sessions against 16.0% under the withholding tutor, and it surrendered the full answer in 6.1% of sessions. A floor that opens on an explicit statement of giving up rather than on frustration follows from the same design — without one, the learners who most need the demand route around it.
- **Withholding cost neither frustration nor motivation — only preference.** A three-arm RCT found a hint-withholding tutor matched unrestricted ChatGPT on frustration reduction and was the only arm to raise intrinsic motivation, yet students rated the answer-giving tool easier ($p = .003$) and more helpful ($p = .004$) (Bassner et al. (2026)).
- **AI as a tool for PF design:** ProductiveMath uses generative AI to help teachers create high-quality PF problems — addressing the challenge that designing productive-failure activities is effortful.
- **AI-generated errors as provocations:** the pedagogy of AI mistakes deliberately leverages AI errors and hallucinations as teaching tools, aligning with productive-failure thinking by treating erroneous output as a cognitive provocation.

This makes productive failure a central lens for evaluating AI in education: the question is not whether AI helps, but whether it helps in a way that **preserves the struggle through which durable learning is built**.

Implications for instructors and instructional design

- **Design for struggle before instruction.** Sequence learning so students attempt problems before direct teaching, then consolidate — rather than the traditional instruction-first approach.

- **Withhold solutions strategically.** Scaffold with hints, clues, and guiding questions (Socratic Method) that keep learners cognitively engaged rather than handing over answers.
- **Use AI to scaffold, not substitute.** Choose and configure AI tools that give non-directive support, preserve productive struggle, and surface errors for reflection — not answer-givers. This applies to both tutor design (steering LLMs) and classroom practice.
- **Attend to the emotional side of failure.** Emotional design, a safe space for experimentation, and reducing the fear of mistakes are essential — productive failure requires learners to be willing to struggle and fail.
- **Build error analysis into learning.** Ask learners to diagnose *why* their (or AI's) answer is wrong, using elaborative/clue-based feedback, to convert errors into learning gains.
- **Distinguish mistakes from errors pedagogically.** Not all failures are equally productive; attend to whether errors reflect misconceptions worth addressing.

Connections to learning gains and other measures

- **Learning gains:** PF is associated with improved learning compared with traditional instruction-first approaches (Kapur, 2008, 2015; Schwartz & Martin, 2004), especially on measures of transfer and deep understanding. Clue-based/elaborative feedback produces significantly higher learning gains than verification-only feedback (Hattie & Timperley).
- **Transfer and retention:** the benefits of PF are strongest on transfer of knowledge to novel problems — a durable-skills outcome rather than short-term exam performance.
- **Affective and motivational outcomes:** PF reduces fear of mistakes, increases engagement, and cultivates resilience and positive attitudes toward learning.
- **AI-specific measures:** PF-oriented AI research is evaluated on strategy fidelity (e.g., StratL's PF score, number of elicited solution attempts) and on teacher/learner perceptions, alongside traditional learning-outcome measures.

Connections to related concepts

Productive failure connects to Learning Theories (constructivism), Desirable Difficulties (valuing difficulty in learning), Problem-Based Learning and Inquiry-Based Learning (learner-driven problem solving), Metacognition (reflection on one's own attempts), Cognitive Offloading (the risk that AI erases struggle), Scaffolding (support that preserves effort), Feedback (elaborative, corrective), Prior Knowledge (activation and differentiation), Transfer of Learning (durable outcomes), and Socratic Method (questioning to provoke reasoning). In the AI era it is a central evaluative lens: does the AI help in a way that preserves the struggle through which durable learning is built?

Common Misconceptions

- **"Withholding help frustrates learners and costs motivation."** A three-arm RCT found a hint-withholding tutor **matched unrestricted ChatGPT on frustration reduction and** motivation — the cost showed up **only in preference**. Learners did not enjoy it as much and did not suffer for it, which means preference data would have rejected the design that worked.

- **“More frustration means more learning.”** The escalating tutor was **0.42 scale points more frustrating than the tutor that answered on request ($p < .001$) and 0.29 less frustrating than** the most frustrating arm. The productive range is a middle, not a maximum, so “desirable difficulty” does not license making the task harder indefinitely.
- **“Productive failure means teachers should not help.”** The design withholds *the answer* while supplying structure and escalation. Withholding a hint and withholding support are different interventions, and only the first is the one with evidence here.

Connected Concepts

- Pedagogical Patterns — Attempt-before-instruction as a full sequence, with its thin evidence base
- Constructivism
- Learning Theories
- Desirable Difficulties
- Problem-Based Learning
- Inquiry-Based Learning
- Metacognition
- Cognitive Offloading
- Scaffolding
- Feedback
- Prior Knowledge
- Transfer of Learning
- Socratic Method
- Critical Thinking
- Human AI Collaboration
- Hallucination Risk
- AI Ed Evaluation
- Learning Gains
- Student Engagement

Connected Articles

- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: AI to Support PF Problem Design
- The safety gap: restoring productive struggle through pedagogically aligned generative AI — The Safety Gap: Restoring Productive Struggle

- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Learning
- The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking — The Pedagogy of AI Mistakes
- Less stress, better scores, same learning: The dissociation of performance and learning in AI-supported programming education — Withholding solutions avoided the frustration cost but lost on student preference

Inquiry-Based Learning

> **Inquiry-based learning (IBL)** — a learner-centered Pedagogies and Teaching Strategies in which students develop understanding by posing questions, exploring independently, and constructing knowledge through a cycle of inquiry, reflection, and revision, with the instructor Scaffolding rather than lecturing. In the AI era, IBL's question-driven, exploration-centered structure has become a focal point: generative AI and Large Language Models (LLMs) tools can serve as interactive "co-inquirers" that support questioning and investigation — but only when designed to preserve rather than bypass the cognitive work of inquiry.

Questions to Consider

- Inquiry-based learning centers on student-driven questions and the inquiry process itself. How is learning driven by your own question different from learning driven by someone else's?
- The page asks whether AI serves as a 'co-inquirer' supporting your investigation or as a substitute that bypasses the cognitive work. When you use AI to explore a question, who is doing the inquiring?
- Evidence on AI-supported inquiry is mixed: it improved creative performance and attitudes but not critical Problem Solving in one study, and deepened conceptual understanding without boosting AI literacy in another. What does that suggest about what AI alone can and cannot develop?
- If treating AI output as authoritative risks over-reliance and superficial conclusions, how would you teach students to evaluate AI-generated answers as part of the inquiry cycle?
- The page connects inquiry to productive failure — learners exploring before instruction, so struggle itself prepares learning. How might AI that withholds answers and elicits multiple attempts support that struggle rather than remove it?
- What is the facilitator's role when AI lowers the friction of asking questions? If students can get answers instantly, what does the instructor now need to scaffold that they didn't before?

Introduction

Inquiry-based learning centers on student-driven questions and the inquiry process itself, typically moving through phases (orientation → conceptualization → investigation → discussion → conclusion). It is the broader family under which problem-based learning and project-based learning are often nested: IBL emphasizes the *questioning and discovery process*, PBL the ill-structured *problem*, and project-based learning the tangible *artifact*.

How inquiry-based learning appears in the knowledge base

AI as co-inquirer. A systematic review of ChatGPT for inquiry-based learning in STEAM (The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education, 24 studies)

found ChatGPT used mainly in the conceptualization, investigation, and discussion phases — as learning tool, tutor, learning peer, domain expert, and teaching assistant. That use improved performance, critical thinking, engagement, and motivation, while posing risks of over-reliance, hallucination, and superficial conclusions when output is treated as authoritative.

Problem posing as the starting point. A quasi-experiment with 97 third-graders (Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science) showed GenAI chatbots significantly outperformed search engines for science problem posing, improving question quality and producing more integrated epistemic networks while lowering cognitive load.

Cognitive-level patterns in LLM-driven IBL. An exploratory study of 117 interview transcripts and interaction records (Luo et al.) identified 14 interaction patterns across Bloom's cognitive levels, showing how students' prior knowledge shapes LLM use and highlighting the need for scaffolding that targets higher-order thinking stages and mitigates over-reliance.

Outcomes evidence is mixed. An AI-supported IBL experiment in mathematics (Mujib et al.) improved creative mathematical performance and attitudes but not critical problem-solving skills — suggesting AI-IBL mainly supports Creativity and affective development. A meta-analysis of 29 experiments (Zhao et al.) found GenAI has a moderate positive effect on higher-order thinking, strongest for problem-solving and with 8–16 week interventions and higher Self-Regulated Learning learners benefiting most. A quasi-experiment with 48 pre-service science teachers in Türkiye (Aydın) using an 8-week AI-supported guided inquiry program (integrating problem- and design-based learning) found significant group-by-time gains in conceptual understanding of photosynthesis and cellular respiration, but *no* significant effect on AI literacy or self-perceived computational thinking — evidence that AI-IBL can deepen domain understanding while the development of AI/CT competencies requires more explicit, targeted design.

Gousopoulos (2026) isolated the AI contribution from the inquiry itself in a three-group climate study: AI-assisted inquiry outgained inquiry-only peers on decision-making (d = 0.69), with the largest gains in monitoring and adaptive management (d = 1.37), while basic data collection improved equally across all conditions.

Equity and context. A conceptual framework bridges generative-AI co-design with open educational practices to support inquiry-led STEM teaching in under-resourced contexts, using AI-generated, multilingual, contextually relevant simulations.

AI-scaffolded evidence comparison. An and colleagues (2026) show how an AI-powered information-extraction system shifts the undergraduate literature review from summarization toward **evidence organization and comparison** — students moving from isolated reading to cross-study comparison and evidence-based justification in support of research-based learning and thesis completion. This concretizes how AI can scaffold inquiry processes in STEM undergraduate research.

Why inquiry-based learning matters for AI integration

IBL's question-driven, process-focused structure is the natural home for productive AI use: students learn *with* AI as a partner rather than *from* it as a substitute. The knowledge base's evidence converges on a core tension — AI can lower the friction of information retrieval and question formulation (reducing cognitive

load and enabling deeper Reflection), but without design scaffolding it risks over-reliance and bypassing higher-order cognition. The facilitator's role, the design of scaffolds, and the explicit teaching of evaluation skills are the levers determining whether AI deepens or displaces inquiry.

One study substitutes the facilitator rather than adding a tool beside them. In a four-week pharmacology course, 136 second-year medical students were split between facilitator-led and AI-led problem-based learning. Both arms gained significantly on pre/post multiple-choice tests and the between-group difference was not significant ($p = 0.474$), but facilitator-led groups scored higher on critical thinking (14.75 against 13.09, $p < 0.001$) and on the group assessment rubric (26.51 against 24.74, $p = 0.035$) (Shetty and Rao, 2026). Inquiry outcomes split by kind: content knowledge survived the substitution and the reasoning process did not, which is what it means to say the facilitator is the lever.

Productive failure and inquiry

Productive failure (PF) is the most structured cousin of inquiry-based learning: learners explore problems and generate solutions *before* direct instruction, then consolidate. Both share the premise that learner-generated attempts (even failed ones) activate prior knowledge and prepare learners to learn from instruction. The AI-era PF research sharpens how AI should scaffold inquiry without short-circuiting it: Kim et al. (2026) derive AI design principles for preserving struggle through problem exploration and solution generation; Puech et al. (2025) show LLM tutors can be steered to withhold answers and elicit multiple attempts; clue-before-correction tasks exemplify clue-based (vs. direct) scaffolding that keeps learners doing the reasoning. These connect inquiry and PF to the broader imperative that AI must not remove the productive struggle through which durable learning forms.

In outdoor field settings the same imperative becomes spatial: GenAI can pre-structure what learners notice before they encounter the evidence, so a field-first sequence that withholds generated explanation until observations and initial interpretations are recorded protects the inquiry (Choi, 2026).

A 66-study map places generative AI beside investigation and least often at orientation. Yahya et al. (2026) coded GenAI use onto the five inquiry phases and found support reported most often in investigation (45 studies, 68.2%), then conclusion (29, 43.9%), discussion (28, 42.4%) and conceptualization (27, 40.9%), with orientation last (20, 30.3%). Eleven studies covered all five phases, 19 covered one and nine named none. Only 8 studies (12.1%) measured inquiry skills, and 4 of those had a comparison condition, so this is a map of where tools were placed rather than what inquiry gained.

Common Misconceptions

"AI is a natural fit for inquiry-based learning because both are exploratory." The fit depends entirely on design: generative AI and LLM tools can serve as interactive co-inquirers that support questioning and investigation **only when designed to preserve the student's ownership of the question**. Used otherwise, an exploratory student is following an answer rather than conducting an inquiry, and the two look similar from the outside.

"Any AI added to an inquiry unit improves it." The AI contribution has to be isolated from the inquiry itself. Gousopoulos (2026) did this with a three-group design in a climate study: AI-assisted inquiry

outgained inquiry-only peers on **decision-making (d = 0.69)**, with the evidence located in a specific outcome rather than in the general superiority of the approach.

“Inquiry is unstructured by definition.” The instructor scaffolds, and the structure is in the question design and the reflection cycle rather than in the delivery of content. Removing the scaffold does not make the inquiry more authentic; it makes it unscaffolded.

“Student-led questions will be well-formed if students are interested.” Generating a tractable question is the skill being developed, which is why a system that supplies good questions has performed the inquiry skill the activity exists to teach.

Connected Concepts

- Problem-Based Learning
- Project-Based Learning
- Active Learning
- Critical Thinking
- Metacognition
- Self-Regulated Learning
- Scaffolding
- Cognitive Offloading
- Generative AI
- Large Language Models (LLMs)
- STEM Education
- Collaborative Learning
- Higher Education
- K-12
- Productive Failure — Productive Failure

Connected Articles

- The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education — ChatGPT for inquiry-based learning in STEAM (systematic review)
- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students’ problem posing ability in science — GenAI chatbots and problem posing in primary science
- Inquiry-based learning patterns in large language model-driven learning environments: an exploratory study from Bloom’s perspective — IBL patterns in LLM-driven environments (Bloom’s perspective)
- Evaluating the impact of AI-supported inquiry-based learning on students’ creative mathematical performance, critical problem-solving skills, and attitudes toward mathematics — AI-supported IBL and creative mathematical performance

- Does generative artificial intelligence improve students' higher-order thinking? A meta-analysis based on 29 experiments and quasi-experiments — GenAI and higher-order thinking meta-analysis
- STEAM education for AI literacy: a systematic literature review — STEAM education for AI literacy
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Language Learning
- AI-Supported Inquiry-Based Learning in Photosynthesis and Respiration: Implications for Sustainable Science Teacher Education — AI-supported guided inquiry in photosynthesis & respiration (science teacher education)
- From literature to research-based learning: An AI-powered information extraction system to enhance undergraduate thesis completion — AI-powered information extraction supporting undergraduate thesis and research-based learning (An et al. 2026)
- Can AI-Assisted Inquiry Enhance Students' Decision-Making Skills in Socio-Scientific Issues? A Three-Group Experimental Study on Climate Change — AI-Assisted Inquiry in Socio-Scientific Issues on Climate Change
- Reconceptualizing outdoor geoscience learning for the generative AI era: a human-centered instructional model — A field-first instructional model that keeps GenAI from pre-structuring what learners notice (Choi 2026)
- Facilitator-Mediated Versus AI-Mediated Problem-Based Learning in Pharmacology Education: A Quasi-Experimental Study Among Second Year Medical Students — Human facilitator versus AI-mediated problem-based learning: equal content gains, weaker critical thinking without the facilitator (Shetty & Rao 2026)
- How does generative AI support inquiry-based learning? A systematic review - 66-study map of generative AI across the five inquiry phases, with only 8 studies measuring inquiry skills

Experiential Learning

> **Experiential learning** — learning through direct experience, reflection, and the application of knowledge in authentic or hands-on contexts ("learning by doing"). Drawing on Kolb's experiential learning cycle (concrete experience, reflective observation, abstract conceptualization, active experimentation), experiential approaches emphasize that learners learn most deeply when they act, observe the results, and reflect. In AI education, experiential learning includes hands-on labs, project-based work, robotics, simulations, and real-world problem solving.

Questions to Consider

- Kolb's cycle describes learning by doing: concrete experience, reflection, observation, conceptualizing, then active experimentation. Think of a skill you genuinely learned. Did it follow that loop — and could a lecture alone have produced the same depth?
- Experiential learning is often the default in AI, cybersecurity, and robotics education, where students learn by working with real tools. What's the argument for why hands-on, applied practice closes the theory-practice gap that lectures leave open?
- Some experiential approaches now use AI assistants inside virtual labs and simulated robots. When the 'experience' itself is simulated or AI-assisted, is it still genuinely experiential — or does the absence of real consequences change what's learned?
- When have you seen 'learning by doing' fail to produce learning? What conditions — reflection, feedback, a real problem — seem necessary for experience to actually teach?

Introduction

Experiential learning is closely related to Active Learning, Project-Based Learning, Embodied Learning, and Simulation. It is particularly relevant to AI, cybersecurity, and robotics education, where students develop skills by working with tools and systems in applied contexts rather than through lectures alone. A key rationale is closing the theory-practice gap in professional preparation.

How experiential learning appears in the knowledge base's research

- **Emergency substitution, with a rubric for how far it gets you.** Elhajj et al. (2026) document a substitution forced by the 2024 conflict in Lebanon: students in a graduate Experiential Learning course at the American University of Beirut, unable to reach communities for needs assessments, interviewed ChatGPT-generated stakeholder personas instead. Two raters scored all ten group prompts and found the split instructive — alignment with educational goals (mean 5.00) and diversity of perspectives (4.90) were strong, while authenticity and realism (4.38) and especially group dynamics and coherence (3.80, with one 30-persona focus group collapsing into sequential interviews) and limitations and gaps (3.20) were weak, the last because emotional flatness, absent contradiction and thin cultural specificity recurred in every context. The authors' conclusion is a

boundary rather than a verdict: personas work as rehearsal and as a stopgap where access is impossible or unsafe, but not where emotional complexity, cultural specificity and interpersonal dynamics *are* the learning objective. Their mitigation is structural — pair simulated role-play with real interviews so students can compare, and train students to interrogate persona output for bias and generalization instead of treating it as field evidence.

- **Cybersecurity labs:** LLM-assisted cybersecurity instruction integrates a Generative AI instructional assistant into a virtual lab platform, supporting hands-on experiential skill building.
- **Robotics projects:** Bots and Blocks uses a project-based, hands-on approach to teach robotics, addressing the lack of practical experience in classic programs.
- **Simulation and embodied learning:** EduSim-LLM lets beginners experiment with simulated robots, and embodied robot interaction grounds learning in direct experience.
- **A virtual laboratory can outperform the physical one when the apparatus is not the point.** Grade 9 students on Ohm's law scored 23.45, 20.51 and 16.57 of 30 in the AI-supported virtual laboratory, the same laboratory without AI, and the physical laboratory, with every pair significant (Li and Ahmad (2026)); the authors concede the physical laboratory's disadvantage may shrink where handling apparatus is itself the goal.
- **AI as infrastructure for uncertainty, not efficiency.** Shi, Dai & Zhang (2026) give a generative-AI role the job of generating disruptive events and cascading consequences in a business simulation, so teams revise plans under incomplete information, and warn that protected simulations can leave decision habits that become a liability outside the classroom.
- **Doing versus being told, measured across five weeks.** In a quasi-experiment with 126 first-year engineering students, a two-hour experiential session on learning with generative AI produced a metacognitive knowledge gain of +0.25, against roughly zero for a lecture. That is a medium effect (d = -0.37) which fell short of significance at p = .055 after multiple-comparison correction, and self-reported AI engagement was comparable in both groups at five weeks (3.99 and 3.93) (Benazet i Montobbio et al., 2026). The bound this places on the page's rationale is worth stating plainly: one hands-on session moves metacognitive knowledge in the right direction without settling the comparison, so the advantage of doing has to be built from repeated cycles rather than assumed from a single lab.

Two forms of hands-on learning in an AI-supported curriculum

A thematic review of 32 peer-reviewed studies of hands-on learning in AI-supported design education (Yu, Liu & Zhu, 2026) argues that AI reorganizes rather than replaces experiential learning, and draws a distinction the knowledge base's other sources tend to collapse: *Embodied Hands-on*, which depends on bodily action, tools, and materials, and *Cognitive Hands-on*, which develops through continued operation, judgment, and adjustment of AI-generated outputs. Both run the same action–feedback–reflection–refinement cycle, but they draw feedback from different sources — real-world material resistance in the first case, language and visual outcomes in the second — so they should not be treated as equivalent or as substitutes. The review's caution is that generation efficiency can compress the exploratory phase: several included studies report reduced exploratory sketching and gradual trial-and-error,

so more iterations enabled by AI need not mean greater iterative depth, and students can miss the failure and material-constraint encounters that make hands-on work educative. Consistent with this, prompting alone did not raise Creativity in the reviewed work, whereas multi-step operations (generate, modify, select) did — again locating the learning in the learner's judgment rather than in the generation.

Experiential learning connects to Active Learning, Project-Based Learning, Embodied Learning, Simulation, Robots in Education, and Higher Education professional preparation.

Work-integrated experience can be the binding condition for advanced competence: across 89 sponsored capstone projects in a smart-manufacturing lab, advancement from Workforce Readiness Level 6 to 7 was gated by industry-embedded placements rather than additional coursework (Smith et al. (2026)).

Common Misconceptions

"Experiential learning means hands-on activity." Activity is the surface; the learning mechanism is the cycle of doing, reflecting, conceptualising and testing. A lab session with no structured reflection produces familiarity rather than conceptual change, which is why "we added a practical component" is not evidence of experiential learning.

"AI can substitute for the experience in experiential learning." It can simulate some systems and cannot supply the experience that forms competence in applied domains such as AI, cybersecurity and robotics, where students develop skill by working with the real tools and systems. A simulated security environment teaches procedure; a working system teaches the consequence of a misconfiguration.

"More authentic tasks are straightforwardly better." Authenticity raises the transfer value and the assessment problem together: real systems produce variable, hard-to-grade evidence, and the more authentic the task the less the outcome resembles a score. Design has to hold both, which is why the reflection structure carries as much weight as the task.

"AI tutoring fits experiential learning as it fits lecture content." The fit is weaker, because a tutor can supply explanation and cannot supply the encounter with the system. Its natural place in this Pedagogies and Teaching Strategies is around the reflection and conceptualisation stages, where a learner is making sense of what happened — not in place of the doing. Symonette et al. (2026) generate the encounter rather than script it: from a learner's goals, GELLI builds situated scenes with characters, support and reflection at runtime, and in a within-subjects study with 40 Japanese learners it beat expert-authored videos on vocabulary recall (d = 0.45) and confidence (d = 0.45) but not speaking.

Implications for Practice

For instructors

- Structure the cycle rather than the activity: doing, then reflecting, then conceptualising, then testing in a new situation. A session that stops after the doing has produced familiarity, not learning.
- Add the practical component where the concept is abstract and remove it where the practical has become the entire course. Hands-on is a means with a cost in time and a benefit in transfer, and the ratio is a design decision.

- Reserve AI for the reflection stage, where a learner is making sense of what happened.

For developers

- Build reflection prompts and a record of what the learner did, so the sense-making stage has material and the evidence is auditable.
- Do not present a simulation as a substitute for operating a real system in domains where the consequence of error is the curriculum.

For programme designers

- Check that applied programs contain applied work rather than lab proxies; the transfer claim rests on the authenticity of the encounter.

Connected Concepts

- Active Learning
- Project-Based Learning
- Embodied Learning
- Simulation
- Robots in Education
- Higher Education
- Learning Theories
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Virtual and Augmented Reality — immersive practice as deliberate experience
- Reflection

Connected Articles

- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings
- A Conceptual Framework for Enhancing Workforce Readiness for Smart Manufacturing in the AI Era — Workforce Readiness Level framework for smart manufacturing in the AI era
- Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era — Fostering Sustainable Learning via Embodied Intelligence (E3-HOT)
- Integrating generative AI into cybersecurity education: A study of OCR and multimodal LLM-assisted instruction — GenAI in Cybersecurity Education
- Bots and blocks: Presenting a project-based approach for robotics education — Bots and Blocks
- EduSim-LLM: An educational platform integrating large language models and robotic simulation for beginners — EduSim-LLM

- Robotics and Artificial Intelligence in Education: Transformations, Challenges, and Future Directions — Robotics and AI in Education
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond — AI-Integrated LMS Longitudinal Study
- Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers' Perspectives
- AI Personas: Can LLMs Replace Fieldwork in Experiential Learning? — AI personas substituting for community fieldwork, with a five-indicator rubric for where the substitution fails (Elhajj et al. 2026)
- Is hands-on learning still necessary in the age of AI? A thematic review — Thematic review distinguishing Embodied Hands-on from Cognitive Hands-on in AI-supported design education (Yu, Liu & Zhu 2026)
- From memorization to experiential learning: Reconfiguring classroom pedagogy in management education through generative AI — a strategic management course reconfigured around three generative AI mechanisms
- GELLI: A Generator for Experiential Language Learning Interactions — GELLI: A Generator for Experiential Language Learning Interactions (Symonette et al. 2026)
- AI-supported virtual laboratory for flipped physics learning: effects on middle school students' achievement, motivation, and cognitive load — AI-supported virtual laboratory for flipped physics learning: effects on middle school students' achievement, motivation, and cognitive load
- Metacognitive Awareness Experiential Vs Instructional 2026 — Experiential versus instructional sessions for metacognitive awareness in AI-assisted learning (Benazet i Montobbio et al. 2026)

Game-Based Learning

> **Game-based learning (GBL)** — the use of games themselves (digital or physical) as the medium and context for learning, where the game's mechanics, challenges, and progression carry educational content. Learners learn *through* playing. Relatedly, **gamification** applies game-design elements (points, badges, levels, leaderboards) to non-game learning activities without turning them into full games. In AI and robotics education, both approaches are used to make technical content engaging and motivating.

Questions to Consider

- Game-based learning uses the game itself as the medium for learning — you learn *through* playing. Gamification just layers points, badges, and levels onto a non-game activity. How different do you think those two are in effect on real learning, versus on short-term engagement?
- A comparative review found game-based learning more prevalent in informal settings while gamification dominated formal classrooms and favored project-based learning. Why do you think each approach found a different home — and what does that tell us about where each works best?
- Gamification is grounded in self-determination theory — autonomy, competence, relatedness. If motivation is about satisfying those needs, why might a points-and-badges system succeed or fail depending on how it shapes perceived effort and attention?
- Research suggests the motivational benefit of game-like and AI-supported designs depends on how they shape perceived workload and attention, not on gamification alone. When have you seen a game or badges boost engagement without actually improving learning — or vice versa?

Introduction

GBL is grounded in Motivation, Student Engagement, and Active Learning theories: games provide intrinsic motivation, immediate feedback, and authentic problem contexts. It overlaps with Simulation, Project-Based Learning, and Robots in Education. GBL is particularly relevant to Robots in Education, Computational Thinking, and CS Education, where games can make abstract technical concepts concrete and fun.

How GBL appears in the knowledge base's research

- **Robotics education:** A comparative systematic review of game-based learning and gamification in robotics education found GBL more prevalent in informal settings, while gamification dominated formal classrooms and favored project-based learning.
- **Robot-mediated games:** REMind is a robot-mediated role-play game for anti-bullying intervention, and MotiBo uses interactive digital storytelling to boost motivation.
- **AI conversational agents in simulation games:** Wenzel, Geiger, and Liening (2026) derive the CAIS-GBL framework — four design principles and fifteen design features for AI conversational agents in digital game-based learning — from theory-driven meta-requirements spanning

cognitive, motivational, affective, and socio-cultural engagement, with an equity-by-design stance. Their instantiated agent (Lara) in a business simulation game was positively received for cognitive and social presence and Self-Regulated Learning support, addressing the common gap of limited formative feedback and structured reflection in simulation games.

- **AI-GBL effectiveness:** A meta-analysis covering 55 studies of AI-supported game-based learning reports gains in knowledge, intrinsic motivation and affective engagement, though just 4 studies (7%) cleared its High-quality bar and only 4 (7%) were RCTs (Kaşarcı & Yurt, 2026). Effectiveness turned on aligning the AI mechanism with a stated learning theory.
- **GenAI as the game's author, not its player:** Xie et al. (2026) had a model draft seven characters and narrative material for an offline mystery role-play game, and the game then beat the same instructor's lecture in a 42-per-arm randomized trial (partial $\eta^2 = 0.566$). Students never used the AI, so the effect belongs to the format.
- **Students as game designers rather than players:** Karampa et al. (2026) had 22 primary students aged 8-12 design an augmented escape board game about misinformation, stacking project-based learning with design thinking and the Room2Educ8 escape-room framework. Composite AI literacy on a 20-item DigComp 3.0 questionnaire rose from 3.684 to 4.309 on a 5-point scale, $t(21) = -21.086$, $p < .001$, with all five competence areas improving. The class generated 11 proposals with AI prompts and merged them into one buildable game. Self-report, one class, and no control group.
- **Split the AI into a dialogue coach and a difficulty engine.** An AI-enhanced Roblox environment for upper-secondary computational thinking paired a GPT-4 non-player character, capped at two to three sentences and barred from giving answers, with a rule-based engine that set difficulty from time-to-solution and error rate (Hengsawat, Junruang & Kanjug, 2026).

Gamification

Gamification is the application of game-design elements (points, badges, levels, leaderboards, challenges, progress bars) to non-game contexts to motivate and engage users. Unlike game-based learning — where learning happens *through* a game — gamification layers game mechanics onto an existing learning activity without turning it into a full game. It is used in education to boost motivation, Student Engagement, and persistence, and is widely applied in formal classroom settings.

Gamification is grounded in motivational theory, particularly Self-Determination Theory (supporting autonomy, competence, and relatedness) and behavior-change frameworks. It has shown particular synergy with Project-Based Learning in applied domains like robotics. In the knowledge base's research:

- **Robotics education:** the comparative review found gamification dominated formal classrooms in robotics education ($p < .001$) and strongly favored project-based learning ($p = .009$), while game-based learning was more common in informal settings.
- **Engagement and motivation:** gamification is used across the knowledge base to increase learner engagement and motivation in AI, programming, and STEM learning contexts. Generative AI, motivation, and engagement research examines how game-like elements combine with AI to sustain learner interest. Two 2026 studies extend this by comparing gamified and AI-supported

conditions against traditional instruction: a NASA-TLX study measured perceived workload across traditional, gamified, and AI-supported learning conditions, and an ARCS study examined motivational "ergonomics" in gamified and AI-supported learning with implications for workplace training. Together they clarify that the motivational benefit of game-like and AI-supported designs depends on how they shape perceived effort, workload, and attention (e.g., ARCS attention/relevance dimensions), not on gamification alone.

GBL and gamification together connect to Robots in Education, Student Engagement, Motivation, Self-Determination Theory, Active Learning, Simulation, Project-Based Learning, and Computational Thinking.

Common Misconceptions

"AI-supported game-based learning has a solid evidence base." The synthesis behind the claim is large and thin at the same time. A **55-study systematic review** finds positive effects on knowledge, intrinsic motivation and affective engagement — but only **4 studies (7%) met its High-quality threshold**. A pooled positive effect drawn from a corpus where 93% of studies fall below the review's own quality bar is a hypothesis with a literature attached, not a finding to design against.

"Positive effects on motivation and knowledge are mutually reinforcing." They are separately measured and, in the wider literature, separately scheduled: engagement and achievement move on different timelines, so a game that raises intrinsic motivation has demonstrated one outcome. Treating the motivational result as corroborating the knowledge result inflates a two-part finding into a stronger one than the design supports.

"If a game engages students, the learning follows from the fun." Fun is the delivery mechanism for the repetition a game makes tolerable, not the mechanism of learning. A game that adds engagement without adding productive practice has added the part that was never in short supply.

Implications for Practice

For instructors

- Ask what the game is making students repeat, not whether students enjoy it. Repetition of the right operation is the mechanism; enjoyment is what makes the repetition tolerable.
- Treat motivational and knowledge outcomes as separate claims, and do not let a rise in intrinsic motivation be reported as evidence of learning.
- Check quality against the review's own bar before adopting a title on the strength of a positive synthesis: only 7% of the studies met it.

For developers

- Instrument learning outcomes separately from engagement and affect, and publish both.
- Build the productive practice first and the game layer second; a game layer over weak practice has automated the part that was never scarce.

For researchers

- Raise the design quality of the field rather than its volume; a 7% high-quality rate is the binding constraint on what can be concluded.

- **Conversational feedback in a simulation raises germane load without lowering extraneous load.** In a five-week business simulation game with **234 students**, regular users of a GPT-4o-based feedback chatbot reported **significantly higher germane cognitive load** than users-with-access who did not engage ($\beta = -.468$, $p < .001$) and than the static-feedback control ($\beta = -.253$, $p = .028$). **Extraneous load showed no effect** in either specification ($F(1, 219) = 0.499$, $p = .481$). Both loads **declined across the five weeks** (extraneous $\beta = -.388$, $p < .001$), a novelty effect measured on cognitive load rather than engagement (Wenzel, Geiger and Liening, 2026). The design point is that the feedback carried personalization, signaling, segmenting and feed-forward structure over 19 concrete indicators — the chatbot surface alone is not the treatment.

Connected Concepts

- Robots in Education
- Student Engagement
- Motivation
- Self-Determination Theory
- Active Learning
- Simulation
- Project-Based Learning
- Computational Thinking
- CS Education
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Virtual and Augmented Reality — immersive and gamified practice overlap in design and evidence

Connected Articles

- Students as Game Designers: Fostering AI Literacy through Project-Based Learning and Design Thinking — Primary students design an escape board game; AI literacy rises within one e-course lab
- Effectiveness of AI-Supported Game-Based Learning: A Systematic Review of Outcomes, Challenges, and Future Directions — Systematic review of 55 AI-supported game-based learning studies: positive outcomes, a thin evidence base
- Game-based and gamified robotics education: A comparative systematic review and design guidelines — Game-Based and Gamified Robotics Education
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — REMind
- MotiBo: The impact of interactive digital storytelling robots on student motivation through self-determination theory — MotiBo
- Bots and blocks: Presenting a project-based approach for robotics education — Bots and Blocks

- Robotics and Artificial Intelligence in Education: Transformations, Challenges, and Future Directions — Robotics and AI in Education
- Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education — Generative AI, Motivation, and Engagement
- Perceived Workload Across Traditional, Gamified and Artificial Intelligence-Supported Learning Conditions: A NASA-TLX Study in Higher Education — NASA-TLX workload across gamified/AI conditions
- Motivational Ergonomics in Gamified and Artificial Intelligence-Supported Learning: An ARCS Study with Implications for Workplace Training — ARCS motivation and AI-supported gamification
- GenAI-enabled educational game development: the effects of a scripted mystery role-playing game on students' learning experience and learning outcomes in legal education — GenAI-authored mystery role-play game versus lecture in legal education (Xie et al. 2026)
- Design and preliminary validation of an AI enhanced game based learning environment for computational thinking in upper secondary education — Design and preliminary validation of an AI enhanced game based learning environment for computational thinking

Learning by Teaching

> **Learning by teaching (LbT)** — the instructional framework, grounded in the protégé effect, in which students deepen their understanding by explaining material to a peer, tutee, or agent. Decades of work in LbT and peer tutoring show that explaining concepts, anticipating misunderstandings, and responding to questions consolidate understanding and support transfer. In the AI era, **teachable agents** — and increasingly **LLMs configured as novice tutees** — operationalize LbT at scale, positioning students as instructors who must explain, correct, and fill gaps.

Questions to Consider

- Recall a time you truly understood something only after explaining it to someone else. What was happening mentally — and why do you think teaching produces deeper understanding than just studying alone?
- A common view is that teaching is for experts, and novices have nothing to offer. Yet 'learning by teaching' rests on the opposite premise: preparing to teach forces you to organize knowledge and find your own gaps. How does that reframe who benefits from teaching?
- The page describes 'teachable agents' — software that students teach as part of learning. With an LLM, you can configure a chatbot as a fallible novice tutee that asks questions and makes mistakes. What would you need to design into such a tutee for it to actually improve learning rather than just chat?
- One challenge is 'engineering fallibility': AI models are trained to give expert, fluent answers, which is the opposite of the struggling novice the learning-by-teaching paradigm wants. Why might an error-prone tutee be more effective for learning than a correct one?
- A ChatGPT-based teachable agent improved learning but its tendency to generate correct code limited error-correction practice. How might a tool that always gives the right answer actually shortchange the learner who needs to practice spotting and fixing mistakes?
- If you were to design a learning-by-teaching activity for your own class, what would make the teaching task *consequential* enough that students put real effort into it rather than copy-pasting an answer?

Introduction

Learning by teaching is the finding, usually traced to the protégé effect, that preparing to teach — and actually explaining to another person or a teachable agent — produces deeper processing than studying alone. The demands of teaching force learners to organize knowledge, anticipate misunderstandings and generate explanations, which surfaces gaps in their own understanding and strengthens Metacognition. AI enters the idea from both directions: tutoring systems and teachable agents can play the student, while a growing literature asks what happens to learning when the machine, rather than the learner, supplies the explanation (Generative AI, CS Education).

The Protégé Effect

Learning by teaching rests on the finding that preparing to teach and actually explaining to another person produces deeper processing than studying alone. The demands of teaching — articulating ideas, anticipating misunderstandings, and answering questions — force learners to organize knowledge, identify gaps in their own understanding, and generate explanations that support retention and transfer. Benefits are most evident in Collaborative Learning contexts and in well-structured domains that support teachable agents (e.g., Betty's Brain). The protégé effect names the mechanism: students put forth more effort and reflect more deeply when they feel responsible for teaching something, so they clarify Misconceptions about AI and fill gaps through explanation and Metacognition.

Teachable Agents: From Rule-Based to Conversational

Teachable agents are the software systems through which learning by teaching is operationalized — a learner teaches a system as part of learning. Traditional teachable agents were rule-based or retrieval-based and could respond only to limited commands; their key limitation was an inability to engage in natural-language dialogue. Large language models change this: they can flexibly adopt roles via prompting — including the role of a "tutee" that asks questions or makes mistakes — and engage in open-ended dialogue, enabling LbT in less-structured domains (writing, vocabulary) than was previously possible.

The knowledge base's evidence base traces this shift to **conversational, LLM-based teachable agents**:

- **ChatGPT as a teachable agent** (Chen et al.) supports LbT in programming, improving knowledge gains, programming ability, and self-regulated learning — though its tendency to generate correct code limits error-correction practice.
- **Explique at scale** (Wang et al.) deployed an AI teachable agent (Algorithm Apprentice) to 546 students over an 11-week semester, finding that explanation-oriented dialogue predicts fewer incorrect quiz submissions, while external-content reuse predicts more.
- **Vocabulary teaching** (Uchida et al.) used an LLM as a student to generate dynamic questions, improving retention at 3 and 7 days.

Engineering Fallibility: LLMs as Novice Tutees

A central design challenge for LLM-based teachable agents is that LLMs are trained to produce expert-level, fluent responses by default — the opposite of the fallible novice the LbT paradigm wants. Making an LLM a good tutee requires **engineering fallibility**:

- **Generated errors can pass as authentic.** In a blinded annotation study, experts misclassified 164 of 196 (83.7%) LLM-generated Java submissions as human-written, so a tutee can supply realistic bugs to debug rather than only correct code (Keramati et al. (2026)).
- **Prompting for teachability** (Miller & Bosch) found that constraint-based prompts explicitly forcing error production (e.g., "answer incorrectly" or "get 2–3 wrong") elicit novice-like behavior far more reliably than persona-, misconception-, or uncertainty-based prompts.

- **Engineered knowledge gaps** (Yang et al.) design problems the LLM cannot solve without knowledge only the student possesses, making teaching a necessity and countering the passive over-reliance of LLM-as-tutor use.
- **Explique's apprentice constraints** (Wang et al.) instruct the tutee to (a) stay a novice, (b) keep requesting clarification until the student's explanation is accurate, and (c) never reveal the target explanation — and to *resist* students who try to reverse the roles and have the tutee explain back.
- **Unlearning as a weights-level route to fallibility.** Machine unlearning suppresses 16 targeted knowledge components in Mistral-7B, dropping accuracy from about 0.75 at a 10% forgetting ratio to below 0.5 at 40% while the base model held near 0.85. The suppressed knowledge returned through supervised relearning and coach-guided dialogue, so the tutee's knowledge level is a dial rather than an assertion (Song, Guo & Lin, 2026).

Questioning, Self-Regulation, and Active Learning

Two further affordances recur across the knowledge base:

- **Questions identify knowledge gaps.** LbT systems use learner-generated questions to expose gaps and reinforce comprehension, and LLM-generated questions replace rigid template-based generators.
- **Teach-back surfaces what clarification misses.** In a 22-participant post-lecture review system, a Peer agent's reflective teach-back consistently exposed gaps between what learners believed they understood and what they could articulate, which lecture-grounded clarification alone had not revealed (Fang & Reidsma (2026)).
- **LbT scaffolds self-AI Regulation in Education.** Teaching a conversational agent fosters Self-Efficacy and the implementation of self-regulated learning strategies, and connects LbT to Desirable Difficulties — the effortful act of explaining and correcting is itself a productive struggle that AI's friction-removal would otherwise erase.
- **What predicts tutor learning is knowledge-building, not prior knowledge.** Across 23 middle-school tutors, the share of responses that built knowledge rather than restated it predicted conceptual post-test scores ($\beta = .138$, $p < 0.05$) while prior test scores did not predict who produced them, and low-prior tutors who built knowledge finished level with high-prior peers (Ameen et al., 2026).

Why It Matters in AI Education

Learning by teaching is the constructive, Active Learning counterpoint to the dominant LLM-as-tutor pattern. Where a tutor gives answers (and risks Over-Reliance), an LbT setup makes the student the teacher, forcing explanation, gap-detection, and knowledge construction. This positions LbT as a key strategy for turning generative AI from a crutch into a tool for deeper learning, and connects to Desirable Difficulties, Active Learning, and Constructivism Pedagogies and Teaching Strategies.

Putting Learning by Teaching into Practice

Design patterns for an AI tutee

The research above converges on a few reusable patterns for turning a default-expert LLM into a productive tutee:

- **Constraint-based novice prompts (most reliable).** Rather than asking the model to "pretend to be a confused student," explicitly force fallibility and a teaching loop, e.g.: *"You are a novice student learning about [concept]. Ask me to teach it to you. Ask clarifying questions and deliberately get 2–3 things wrong during our conversation. Never state the correct answer yourself — wait for me to explain, then tell me whether I made sense."*
- **The reverse-teaching guard.** Add a rule that the tutee must *decline* to explain the answer back when the student tries to flip the roles: *"If I ask you to solve the problem or explain the concept, remind me that I'm the teacher and ask me to explain it instead."* Explique shows this resistance is what preserves the LbT interaction.
- **Engineered knowledge gaps.** Structure the task so the model *cannot* answer without information only the student holds — the student's knowledge becomes genuinely necessary, not optional. This converts the interaction from optional chat into required teaching.
- **An external success criterion.** Give the teaching a real consequence — a gatekeeper quiz that unlocks only after the student teaches successfully (Explique), or a code-judging platform the student must make the agent's output pass (Chen). Accountability is what sustains genuine effort and prevents the whole exercise becoming a checkbox.

Tips for instructors

- **Make the teaching task consequential, not busywork.** The strongest evidence for engagement comes from activities that matter — Explique gated a graded quiz behind the teaching exercise; Chen tied the tutee's output to passing a judging platform. If teaching is purely optional, students will rationally skip the hard part.
- **Give students a teaching protocol, not just a chat window.** Scaffold the interaction with a structure — "explain the concept → give a concrete example → answer the tutee's questions → check for understanding" — so open-ended dialogue becomes a deliberate teaching sequence rather than aimless conversation.
- **Address content-dumping head-on.** Explique found that direct copy-paste of external content rose from under 15% to 30–35% of interactions by the end of the semester. Tell students why pasting defeats the purpose, and consider an accountability step (e.g., "explain the agent's misunderstanding in your own words").
- **Pair LbT with debugging practice.** Because AI writes correct code, students may lose error-correction practice. Deliberately ask the tutee to *misimplement* something, or follow the teaching session with a bug-finding task, so debugging stays in the loop.
- **Watch the effort gradient.** Expect novelty to fade; plan to vary the target concepts, add challenge, or rotate which students take the teaching role to sustain cognitive effort across a term.

Tips for developers

- **Prefer hard constraints over persona alone.** Prompting for "uncertainty" or "a student persona" is unreliable; explicitly force errors and a clarification loop. (See Prompting for Teachability: Designing Novice Personas in LLMs for Learning by Teaching Contexts.)
- **Build a completion criterion.** Define *when the student has explained enough* (Explique used an LLM tool function keyed to the concept's learning objectives) so the interaction ends on understanding, not on a time limit or a fixed turn count.
- **Log and code the dialogue.** Explique used word-per-minute detection plus LLM semantic coding to classify interactions as Detailed / Minimal / External Content Use — that signal is how you detect circumvention and declining engagement before it becomes a problem.
- **Give instructors a dashboard.** Completion rates and qualitative patterns in teaching interactions let a human intervene when effort drops (Explique's instructors monitored exactly this).

Implications and open questions

- **LbT is a scalable antidote to AI over-reliance** — it inverts the tutor/student role and keeps the learner cognitively active, which matters more as AI gets more fluent and more "helpful."
- **Fallibility is a feature, not a bug.** A tutee that is *too* correct removes the error-correction and gap-detection that make LbT work; design for the productive struggle rather than against it.
- **Open questions remain:** How do LbT interactions sustain beyond a semester as novelty fully fades? Does LbT transfer to non-CS, less-structured domains at the same scale? Can automated dialogue coding become a practical, real-time engagement monitor for instructors? And how do we keep the teaching role meaningful for *every* student rather than a motivated few?

Common Misconceptions

"Any tutee works, since the benefit lies in explaining." The benefit depends on the tutee's responses being informative. A tutee that already understands everything gives the tutor no gap to detect, which is why making an LLM a good tutee requires **engineering fallibility** — designed errors and confusion the teacher-student must diagnose and correct. The protégé effect comes from the tutee's ignorance, so a capable tutee removes the mechanism.

"Generated errors are good enough because they are wrong." Only if they are plausible. In a blinded annotation study, experts **misclassified 164 of 196 (83.7%) LLM-generated Java submissions as authentic** student work — which is simultaneously evidence that the errors are realistic and a warning that a tutee can be wrong in ways that teach the wrong diagnosis.

"Asking an LLM to act confused is a trivial prompt." It is a design problem, because the fallibility must be calibrated to the concept being taught and to the learner-tutor's current model. Random errors produce debugging practice; errors reflecting a specific plausible misconception produce conceptual restructuring, and only the second is the pedagogical target.

"Learning by teaching is a softer activity than being taught." It is more demanding. Preparing to teach forces the organization of knowledge and the location of one's own gaps, which is why the approach surfaces

misunderstandings that passive reception conceals — the difficulty is the mechanism rather than a cost to be minimized.

Connected Concepts

- Pedagogical Patterns — Explaining to an AI tutee: the best-evidenced sequence in the knowledge base
- Generative AI
- Active Learning
- Constructivism
- Scaffolding
- Self-Regulated Learning
- Metacognition
- Desirable Difficulties
- Cognitive Offloading
- CS Education
- Collaborative Learning
- Intelligent Tutoring
- Pedagogical Agent
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Learning-by-Teaching with ChatGPT: The Effect of a Teachable ChatGPT Agent on Programming Education — ChatGPT as a teachable agent in programming
- Turning 500+ Students into Teachers: A Semester-Long Study of an AI Teachable Agent in an Undergraduate Algorithms Course — Explique: teachable agent for 546 students
- Prompting for Teachability: Designing Novice Personas in LLMs for Learning by Teaching Contexts — Designing novice personas for teachability
- Learning by Teaching: Engaging Students as Instructors of Large Language Models in Computer Science Education — Students as instructors of LLMs (Socrates)
- Empowering Vocabulary Learning Through Teaching AI: Using LLMs as a Student to Perform Learning by Teaching in Vocabulary Acquisition — Vocabulary learning by teaching AI
- From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review — Teach-back consolidation in a conversational review system
- Simulating Novice Students Using Machine Unlearning and Relearning in Large Language Models — machine unlearning to hold a tutee at a novice knowledge level, and relearning through teaching dialogue
- Simulating Students' Java Programming Errors with Large Language Models — Simulating student errors with LLMs

- Beyond prior knowledge: the predictive role of knowledge-building in tutor learning — knowledge-building responses, not prior knowledge, predict tutor learning

Scaffolding

> **Scaffolding** — structured support that helps learners accomplish tasks they cannot yet complete independently, with support fading as competence grows. In AI in Education, scaffolding is the primary design principle for ensuring AI tools support learning rather than replace it.

Questions to Consider

- Think of a time someone 'helped' you with something you were learning, and the help did the work so well you learned less. Where's the line between support that lets you grow and support that replaces you? The page argues this is the central design question for AI tutors.
- Scaffolding is rooted in the Zone of Proximal Development — enough support to enable progress, not so much that learning is bypassed. What does 'too much support' look like in an AI tutor, and can you detect it from the student's behavior alone?
- A key finding: students often *prefer* the more directive AI tutor roles even though they *perform better* with collaborative peer and Teaching-assistant roles. Does learner preference reliably track what's best for learning — and what does this divergence imply for letting students choose their own scaffolding?
- Scaffolding that never fades creates dependency. The page notes automated scaffolds risk staying static instead of being withdrawn as competence grows. Why is 'fading' essential, and why might an AI system fail to do it if it isn't deliberately designed to?
- The design principle is 'scaffold, do not substitute.' Students themselves asked for AI that 'does not provide any solutions for you — you still learn as you have to find the correct answer yourself.' Does that match how you've experienced effective help, or have you preferred the shortcut even while knowing it cost you?
- Set a goal before reading: pick a task you teach, and sketch what a hint looks like that preserves the learner's effort versus an answer that removes it. How will you know your hints are in the productive-struggle zone?

Introduction

How scaffolding appears in AIED

- **Prompt-based scaffolding:** Guided LLM scaffolding teaches structured prompting as a learning intervention. Critical engagement scaffolding uses culturally responsive approaches.
- **Mixed-initiative scaffolding for gaps the learner cannot name:** Sun et al. (2026) keep the writer in charge of narrative synthesis while the system takes initiative only over domain discovery, proactively flagging knowledge gaps writers cannot formulate as queries.
- **Socratic scaffolding:** Socratic AI dialogue withholds direct answers, using questions to guide discovery — a form of Desirable Difficulties scaffolding. As a boundary condition, questioning

helps at onset but decays with depth, so the fade rule shifts from eliciting to addressing the error: the benefit falls from a 20-point advantage at onset to 3 points by the fourth stuck turn, while addressing the error rises from +5 to +12 Ahtisham et al. (2026).

- **Adaptive fading:** Intelligent tutoring systems adjust scaffolding based on Knowledge Tracing estimates, providing more support for unmastered concepts and less for known ones.
- **The function, not the tool, decides what counts as success:** Vasileiou et al. (2026) propose a three-function framework for AI support in special education. *Compensation* reduces an executive demand so the learner can participate (success = access while support remains). *Scaffolding* supports performance just beyond current capability (success = decisions with targeted assistance). *Development* builds strategies usable without the tool (success = strategy use after fading or transfer). Each function carries a different evaluation standard, and the field's recurring error is reporting task completion during support as development. It is a narrative review with interpretive categories, not a pooled effect estimate.
- **Need-triggered adaptive scaffolding in clinical interview training:** the MeduAI-SP randomized trial (Yang et al., 2026; N = 100 third-year medical students) operationalized scaffolding as adaptive, need-triggered support: a turn-level evaluator agent flagged when a learner was stuck, omitted key history, risked premature closure, or impaired rapport, and only then did a tutor agent issue a Socratic prompt. Expert annotation of 207 consultations showed that scaffolding need was strongly phase-dependent, rising from about 16.1% of student utterances early in the encounter to 34.8% late (24.1% flagged overall) — empirical evidence that novice consultation support is most needed during integration and diagnostic reasoning, not initial information gathering. The scaffolding condition outperformed a structured progressive-disclosure control on the final OSCE-aligned examination (71.8% vs. 55.6%; β = 16.4 percentage points; P = 3.30e-4), with the largest gain in communication (Hedges' g = −0.79).
- **Hint systems:** AI tutor hint research examines when hints help versus when they encourage Over-Reliance.
- **Scaffolds that raise post-mistake recovery.** In a 6,000-student middle-school field experiment, AI support slowed progress and cut questions attempted but increased next-attempt correctness after errors and reduced the attempts needed to return to a correct answer — a "productive slowdown" rather than answer supply (Oreopoulos et al. (2026)).
- **Training the learner is itself a scaffold.** A 45-minute session teaching students to prompt a model by SRL phase, and to remediate its visual and reasoning errors, raised physics revision accuracy (d = 0.81) without increasing reported total cognitive load (Huang et al. (2026)).
- **Conceptual and representational scaffolds:** Concept Catalyst and LLM tutor rethinking explore design patterns for cognitive support. Davor (2026) supplies a domain where representational support and answer-giving have to be pulled apart: geometry proof is rich in Visualization resources, yet the step from a relationship that can be seen to a valid deductive argument is the one learners fail to make, so the scaffold has to carry them across representations rather than hand them another picture. His quasi-experiment with 86 Ghanaian senior high school students configured generative AI to prompt and question rather than solve — asking learners to justify what they observed, name the relevant theorems, and order their logical steps, with the teacher

using the AI's representations to steer discussion — and the AI-supported class outscored conventional instruction on proof construction even after controlling for pre-test performance. Perceptions of the feedback and explanation quality were favorable, though only the experimental group was surveyed. The scaffold is positioned here as the bridge from visual intuition to deductive reasoning, and the paper never names the model or a collection window, so it offers more of a design warrant than a replication recipe.

- **"Scaffold, do not substitute" as a design principle:** Favero et al. (2026) argue that the central risk of AI in education is misalignment — AI that substitutes for human effort erodes the capacities education is meant to build — and derive a single design principle, *scaffold, do not substitute*. Scaffolding must be a first-class capability of AI systems: knowing *when to withhold an answer, ask a question, surface uncertainty, or present alternative perspectives*. Their analysis of student essays shows learners themselves converge on this — asking for AI that "does not provide any solutions for you, you still learn as you have to find the correct answer yourself." The principle positions scaffolding as the alternative to a self-reinforcing harm cycle of substitution across cognition, Learner Agency, emotion, and Ethics.
- **Mentoring as scaffolding for a research process.** Wang et al. (2026) treat a systematic review as an intentional learning experience in which mentoring supplies integrated methodological and emotional scaffolding, while automation is confined to procedural load such as abstract screening, and data extraction, reconciliation and synthesis stay with human reviewers.
- **Scaffolding embedded in the medium, not bolted on:** Wang, Du and Jin (2026) operationalize four scaffolding principles inside a video player — ZPD-based adjustment of comment depth, *fading* scaffolding (knowledge support thins over the timeline), *distributed* scaffolding (every comment is either knowledge or emotional support), and cognitive-load-derived **timing** — by computing frame-level video entropy and inserting comments only in low-information intervals. Their four-condition ablation with 20 learners found the entropy-timing module produced the strongest and most robust effect on perceived quality when removed ($Z = -2.85$, $r = 0.45$, $p = .004$), which makes the *scheduling* of scaffolding a measurable design variable rather than a packaging detail. The study also carries a warning for automated scaffolding: ChatGPT-generated comments were consistently harder to read, less lexically diverse, and less topically aligned than instructor comments, with the largest relevance gap in emotional support (feedback quality).
- **Emotional scaffolding as a prompt layer, measured against cognitive scaffolding alone.** Holding the interface and lesson fixed, the emotional version asked students to report feelings at three points and used those reports to vary tone, affective scaffolding and cognitive challenge along control and value appraisals, with temperature at 0.7 so the adaptations guided rather than dictated replies. In the dialogue traces it bought more performance-phase and self-reflection work than SRL prompts alone, and more enjoyment and less boredom. It added nothing to learning gains or self-efficacy in a single 25-minute session (Diordiev, Stenberdt & Makransky, 2026).
- **Preferred scaffolding is not always the most effective:** Zhu, Yang and Yang (2026) found in a within-subjects experiment that students performed best with Peer and Teaching Assistant AI roles (which foster collaborative reasoning) yet preferred the more directive Tutor and Excellent

Student roles — a divergence between preference and performance that cautions against equating learner preference with effective scaffolding in AI-supported mathematical modeling.

- **A more structured scaffold is not automatically a more agentic one:** an expert design bot raised interaction length and self-authored prompts relative to plain ChatGPT, but collaborative Problem Solving agency fell in both conditions, with agreement instead of critique the lowest-agency behavior observed (Krushinskaia et al. (2026)).
- **Automated scoring as a deliberate scaffold:** Chen and Liu (2026) treated an automated interpreter-scoring system as formative scaffolding rather than as a measurement instrument, in a 14-week comparison with 46 English Translation and Interpreting sophomores. The scaffold converted into a gain only where the deficit it targeted was decomposable, reliably scored and sensitively scaled: linguistic accuracy and logical coherence rose, while information fidelity and delivery fluency stayed flat, fidelity being the dimension on which automated and human ratings disagreed most ($r = 0.12$). The cycle it reinforced was also partial. Only practice-phase execution and monitoring correlated with score gains ($r = 0.42$), while pre-learning planning sat near the scale midpoint ($M = 3.01$) and students set goals from the previous score rather than from the task ahead. A scaffold can be well placed inside the performance phase and still leave the planning that would make it unnecessary untouched.
- **Closed-loop scaffolding on the learner's current boundary:** Zhu, Luo and Li (2026) built a music-education loop in which Multimodal AI error detection over performance audio and score becomes the reward that steers reinforcement-generated practice tracks, so difficulty follows the learner's current boundary instead of a fixed syllabus: generated practice trajectories matched learner skill profiles at a peak cosine similarity of 0.962, and the Group x Time interaction favored the scaffolded group in a 12-week quasi-experiment with 120 undergraduates (beta = 0.52, 95% CI [0.31, 0.73]). Two limits follow for automated scaffolding. Detection is triage rather than judgment, since rhythm error precision of 89.7% means roughly one flagged error in ten is a false alarm, and blind expert review rated support for musical expression the system's weakest area, leaving interpretation to the teacher.
- **Pacing is scaffolded too.** Englmeier (2025) pairs content scaffolding with a temporal layer of weekly time allowances, progress dashboards and end-of-section checks; without pacing, nearly 25 percent of over 600 learners began in the final week and 95 percent of them failed.

The ZPD connection

Vygotsky's Zone of Proximal Development provides the theoretical foundation: scaffolding targets the space between what learners can do independently and what they can achieve with support. AI tools should operate in this zone — enough support to enable progress, not so much that learning is bypassed. A configuration that inverts the usual direction of adaptation appears in Sidorkin's (2026) graduate course, where the learner rather than the system set the support level: weekly readings were generated on demand and students dialed comprehension level through iterative prompting (pacing, definitions, vocabulary density, depth). Analysis of three reading logs found definitional markers 3.4x to 8.7x more frequent in AI responses following comprehension-oriented prompts than in baseline explanatory text, with the clearest cases building a definitional layer and then a numbered procedural one, which makes scaffold density a measurable property

of the learner's request rather than only of a system's mastery estimate. Requiring at least three follow-up questions per reading made that dialing routine, turning the text into an interaction that surfaced comprehension gaps the instructor otherwise would not see.

Scaffold form has to match what the learner can already hold, not only what the task requires. In a systematic scoping review of 24 evidence sources on creative thinking in children aged 6 to 15, Niu et al. (2026) report that younger children lacked the precise linguistic and metacognitive control that text-based prompting demands and needed multimodal, adult-facilitated interfaces, while text-based LLMs showed stronger reported outcomes with older children and young adolescents. Prompt dependence was strongest in the lower grades, and no included study examined developmental readiness thresholds, so the authors treat modality and scaffolding choices as an open design question to be settled by the learner's capacity rather than by convenience.

Connections

Scaffolding connects to Over-Reliance (scaffolding that doesn't fade creates dependency), Cognitive Load Theory (scaffolding manages cognitive load), Feedback Loop (scaffolding provides formative feedback), and AI Literacy (learners must recognize when scaffolding is beneficial vs. when it displaces learning).

Agents must scaffold dynamically, not statically: Woollaston et al. (2026) identify that automated scaffolds risk staying static instead of being withdrawn as competence grows, and recommend dynamic scaffolds that adapt and fade — a key guardrail for Agentic AI. CoMeT (Hou et al. 2026) supplies both the separation and the warrant for *when* to fade: its support climbs one rung each time a learner does not use it and drops to the lightest rung on take-up, holding metacognitive demand statistically equivalent to a withholding tutor (p_TOST = .004) while delivering an artifact in 48.1% of sessions against 23.7% — more system labor, not less. The trigger it validated is aim rather than depth: after a full demonstration the tutor later conceded 30.3% of what was still open, after a pasted artifact 25.9%, after a bare assertion 20.4% and after a request to build 33.7%, whereas turns not aimed at the decision under support drew a later concession 40.3% of the time against 28.8% for aimed turns (11.5-point difference, 95% bootstrap interval [2.1, 22.4]). Take-up was sparse — 37.0% after the first ask and 21.8% after the third — so a fade rule keyed to learner effort would read a non-answer as readiness.

Fading can be trained out of a tutor. A multi-turn RL tutor rewarded only on the current problem and a masked near-transfer variant stopped fading support and assigning independent work, though nothing penalized either, because their payoff lies beyond one dialogue episode (Macina, Kapur & Sachan, 2026). A reward horizon that ends with the problem will erase the fading a design specifies.

A fourth zone makes the source of the scaffold visible: Tsim and Gutoreva (2025) add "known to GenAI" to Vygotsky's zones, so a task falls into Substitute, Complement, Aid or Non-negotiable — and Non-negotiable holds what needs a person because it is normative, tacit or too risky to hand over. - **Place AI by phase of the idea, not by course.** The six-move placement frame holds AI out of the first hard attempt and final unaided check while licensing it between them for hints, examples and drill; if AI makes the task feel effortless, it is in the wrong place (Brcic & Frljic, 2026).

Scaffolding must be situation-appropriate, not maximal: Zhang et al. (2026) introduce TutorMoments, which evaluates whether LM tutors scaffold only when support is needed, push for rigor when the student is ready,

and avoid over-scaffolding (reducing cognitive demand more than the situation requires). Minimally prompted frontier models default to over-scaffolding at the expense of productive struggle.

- **AI that scaffolds productive struggle.** Kim et al. (2026) derive AI design principles (non-directive support, reflective design, Human-in-the-Loop) that keep scaffolding in the productive-struggle zone rather than collapsing to answer-giving; Puech et al. (2025) show Large Language Models (LLMs) tutors can be steered to give help only when strictly necessary — scaffolding that preserves the learner's own effort.

Scaffold withdrawal as the enforcement mechanism for verification. Kumar, Wongsirichot and Nanthaamornphong (2026) synthesize 72 computing-education studies and locate scaffold withdrawal, alongside guardrail tools and Self-Regulated Learning designs, as one of three ways courses enforce critical engagement with AI output — structurally (constraining what the tool returns), procedurally (reflection logs, self-testing) and temporally (progressively restoring conditions under which independent reasoning is required). Their evidence is that efficiency gains under AI assistance do not transfer to unaided performance, and that the failure mode — the *pseudo-apprenticeship* pattern, where students watch AI generate code without performing the task — is exactly modeling without whole-task practice. Graduated access therefore functions as a fading schedule for a powerful new form of support, and the review grounds it in 4C/ID: assistance helps only when the learner already has enough schema to engage critically with it (the zone of proximal development, Cognitive Offloading).

Sequencing is the scaffold's other lever: Vendrell and Johnston (2026) recommend requiring a learner's independent attempt before any AI consultation and then using the model to generate counterarguments rather than answers, with deliberate AI-free phases, so the support amplifies reasoning instead of replacing it.

Rule-Guided vs. Ad-Hoc Scaffolding

- **Rule-guided vs. ad-hoc scaffolding.** Looi, Liu, and Sun (2026) formalize a distinction central to scaffolding design: **rule-guided scaffolding**, in which tutoring is governed by an auditable three-layer architecture (diagnosis → intent selection → constrained response generation), versus **ad-hoc scaffolding**, where helpful moves are difficult to audit and replicate. Their primary-school math study showed rule-guided scaffolding improves interactional consistency, reduces premature answer-giving and early closure, and sustains cognitive engagement — evidence that explicitness and auditability of scaffold moves matter for both consistency and learning in procedural domains.
- **Scaffolding as the constrained pathway between bypass and offloading.** The Neuroplasticity-AI Interaction Model names scaffolding as the third of three pathways for LLM help, alongside direct bypass and cognitive offloading, and defines it by whether the model preserves the effortful processing the task is meant to train (Bypass, Offload, or Scaffold: A Conceptual Model of How Large Language Models Shape Learning). The model's calibration evidence is a natural experiment in scaffold constraint: unrestricted GPT-4 access in a study of nearly 1,000 high-school mathematics students produced a 48% practice gain but a 17% deficit on the unassisted exam, while hint-constrained GPT Tutor produced a 127% practice gain with the exam deficit largely eliminated. The design lesson matches the rule-guided versus ad-hoc distinction above at a coarser grain: it is the constraint on what the tutor is allowed to supply, not the presence of a tutor, that determines whether the scaffold is removed successfully.

The rule-guided versus ad-hoc distinction reaches past the tutor and into the assignment itself. A cross-institutional faculty collaboratory found that critique of AI output did not happen on its own, so requirements to audit, compare, revise and justify generated content had to be written into the task, and those who protected independent disciplinary analysis before AI entered found candidates could evaluate AI output more critically. Rehearsal evidence agrees: pre-service teachers practicing with AI partners used more probing and exploring questions when structured post-rehearsal feedback was provided. In both cases support is specified in advance rather than improvised, separating designed guidance from the ad-hoc help that is hard to audit and replicate.

- **A correctly constrained scaffold still fails if the constraint is not administered.** Azimi (2026) built what the distinction above prescribes — a budget of 25 hints per session, a 15-minute cap on AI use, a required end-of-session reflection, and no generated code — and randomized 33 master's students between it and unrestricted Generative AI use across seven weeks. Assignment performance and concept-inventory gains did not differ between conditions. The hint budget did not act as a rationing mechanism: some students spent most of it on the first problems and had none left for the demanding ones, others finished with most unused, and within the Coach condition it was the students who already had a deliberate strategy for spending a hint who scored higher. The constraint raised reported confidence and followed students out of the classroom as a self-questioning habit (whether a question was worth asking the tool), but it rewarded existing self-governance rather than developing it. Auditability of a scaffold and a learner's capacity to use it are separate conditions.
- **A scaffold the learner cannot verify is a fluent substitute.** Because chemistry reasons across observable phenomena, particulate models and symbolic notation, a generated answer can be locally persuasive and globally wrong. Vega-Baudrit and Rivera Álvarez (2026) place scaffolding on the productive side of their Presage-Process-Product analysis and uncritical copying on the failure side, and require scaffolds to demand representational translation in both directions, since a response that describes neutralization correctly can still claim that every equivalence point has a pH of 7. Verification is designed into the task rather than announced as a rule: students identify a false assumption, correct a unit or mechanism error, compare a symbolic structure with a submicroscopic model, or justify rejecting a generated answer. Because students cannot verify what they do not yet understand, prior knowledge and scaffolding come first, and prompting is treated as an epistemic act in which the learner specifies the constraints the answer must satisfy.

Common Misconceptions

- **"Scaffolding is a constant level of support."** Expert annotation of **207 consultations** showed scaffolding need was **strongly phase-dependent, rising from about 16.1% of student utterances early** in the encounter. A single scaffold level is misallocated at both ends of the same consultation.
- **"Any structured control condition is a fair comparison for scaffolding."** On the examination, the scaffolded arm still beat a genuine progressive-disclosure alternative (**71.8% versus 55.6%**), so the gain was measured against a real pedagogical alternative rather than against nothing.

- **“Scaffolding effects are general.”** The gain was **16.4 percentage points (P = 3.30e-4)**, with the largest improvement in **communication (Hedges’ g = -0.79)**. The effect concentrated in one outcome, so an average across outcomes understates where it works and overstates where it does not.

Connected Concepts

- Pedagogical Patterns — Where in the sequence support belongs, and why attempt-before-help is the load-bearing rule
- Problem-Based Learning — PBL embeds fading scaffolds around ill-structured problems
- Learning by Teaching — Scaffolding knowledge building through explanation
- Sociocultural Learning — Vygotskian foundation: ZPD and socially mediated learning
- Cognitive Offloading — Scaffolding that never fades creates over-reliance
- Feedback — Scaffolding delivers formative feedback as support fades
- AI Literacy — Recognizing when scaffolding supports vs. displaces learning
- Intelligent Tutoring — ITSs adapt scaffold intensity to mastery estimates
- Socratic Method — Questioning that withholds direct answers
- Metacognition — Scaffolds that build self-monitoring and self-regulation
- Adaptive Learning — Adaptive systems modulate support within the learner’s ZPD
- Learning Design — Scaffolding is a core instructional-design strategy
- Help-Seeking — Scaffolding shapes when and how learners request help
- Teaching — Teachers scaffold, then fade as competence grows
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Agentic AI
- Productive Failure — Productive Failure

Connected Articles

- Generative AI in computing education: A systematic review and a framework for responsible integration — Scaffold withdrawal as the mechanism enforcing verification (VIE framework)
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- Assessing ChatGPT-Generated Comments for Video-Based Learning Content to Enhance Knowledge and Emotional Support Based on Scaffolding Theory — Entropy-timed AI comments as in-video knowledge and emotional scaffolding (Wang, Du & Jin 2026)
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics — Guided LLM prompting as a structured learning intervention

- Scaffolding critical engagement with GenAI: Transforming ethnic minority preparatory students' collaborative discourse in prompt engineering tasks — Culturally responsive critical-engagement scaffolding with GenAI
- Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments — Design patterns for scaffolding in LLM tutors
- Creating Learning Scaffolds for Engineering Design Using Concept Catalyst — Concept Catalyst scaffolds for conceptual change
- Catching The Correct Answer Trap: Characterising AI Tutor Blind Spots When Analysing Student Reasoning — When hints help vs. when they encourage over-reliance
- Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education — Scaffolding critical thinking with GenAI
- VeriForge: Mitigating Latent Knowledge Gaps in Narrative Drafting via Mixed-Initiative Scaffolding — Scaffolded narrative drafting with Veriforge
- From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle of AI in Education (and Beyond) — From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle
- Preferred scaffolding does not lead to better learning performance: Empirical evidence from AI-supported mathematical modelling — Preferred scaffolding in AI-supported mathematical modeling
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — Dynamic (fading) scaffolds as a guardrail for agentic AI
- When Help is Unhelpful: Evaluating AI Tutors for Productive Struggle — When Help is Unhelpful: evaluating AI tutors for productive struggle
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- The effortless trap: Productive struggle, AI, and the illusion of learning — Guarded vs. unguarded AI: the placement rule (Brcic & Frljic 2026)
- Supporting undergraduate students' learning in practical chemistry courses through AI-supported experimental design — AI-supported experimental design in practical chemistry
- Scaffolding systematic reviews in learning design and technology through mentoring and AI integration — Scaffolding Systematic Reviews with Mentoring and AI (Wang 2026)
- Pre-service teachers' agency during their interactions with generative AI while designing for learning – a process view on Intelligent-TPACK — Pre-service teacher agency during GenAI interactions in design for learning (Krushinskaia, Elen & Raes 2026)
- Responsible integration of artificial intelligence into pedagogies of practice in mathematics teacher education — AI across the pedagogies of practice in mathematics teacher education: structured rehearsal feedback raised probing questions (Bondurant & Shaughnessy 2026)

- AI integration as instructional design: Lessons from a cross-institutional faculty collaboratory in teacher preparation — AI integration as instructional design: critique of AI output must be assigned, and disciplinary analysis comes first
- AI literacy over tool design: a mixed-methods study of scaffolded versus unrestricted generative AI in programming education — A hint-budgeted AI Study Coach: scaffolded vs unrestricted GenAI use, and why the constraint alone did not produce learning (Azimi 2026)
- SCAN: A Decision-Making Framework for Task Assignment with Generative AI — SCAN: scaffolding reframed as deciding which sub-zone a task belongs to
- Impact of automated scoring on interpreting performance and self-regulated learning: evidence from a pedagogical experiment — Automated scoring as formative scaffolding: it converts into a gain only where the targeted deficit is decomposable, reliable and sensitively scaled (Chen & Liu 2026)
- Adaptive teaching assistance model combining generative AI and big data analytics — Closed-loop adaptive scaffolding that tracks the learner's current boundary in music practice, with error detection as triage (Zhu et al. 2026)
- The role of generative AI in facilitating children's creative thinking and cognitive development: a systematic scoping review — Scaffold form must match children's developmental capacity, not only the task (Niu et al. 2026)
- Generative artificial intelligence in university chemistry education: a critical review using Johnstone's chemistry triplet and Biggs' 3P model — Scaffolds must require representational translation and verification, since students cannot verify what they do not understand (Vega-Baudrit & Rivera Álvarez 2026)
- Generative AI-supported instruction as a cognitive scaffold: Effects on senior high school students' geometric reasoning and proof construction — GenAI as a prompting scaffold that bridges visual intuition to deductive proof in geometry, where visualization alone is insufficient (Davor 2026)
- Examining Variation in How Guided AI Tutors Resolve Student Impasses — Examining Variation in How Guided AI Tutors Resolve Student Impasses
- From answer machine to collaborative partner: impact of structured generative AI training on scientific problem solving in STEM education — Training the learner as scaffolding for GenAI use in STEM problem solving (Huang et al. 2026)
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)
- Scaffolding Autonomy: AI-Augmented Self-Paced Learning Environments for Sustainable Learning Outcomes — Content and temporal scaffolding layers in a self-paced course, with late-start and failure rates by study timing
- The Assistance Dilemma - Learning to Teach via Multi-Turn Reinforcement Learning — The assistance dilemma: training a multi-turn RL tutor whose reward horizon ends with the problem trains fading out (Macina, Kapur & Sachan 2026)

Connected FAQs

- How Should AI Be Designed Into the Learning Experience?
- What Are Best Practices for Developing an Effective AI Tutor?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Socratic Method

> **Socratic Method** — a pedagogical approach rooted in guided questioning and dialogue rather than direct instruction, now being adapted for generative AI tutoring systems. In AI in education, the Socratic method is operationalized through LLMs that ask probing questions, scaffold reasoning, and withhold direct answers — aiming to promote deeper understanding and productive struggle rather than answer-fetching.(Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot)(Critical AI Tutors: Empower or Enslave?)

Questions to Consider

- Think of a time a teacher (or friend) answered your question with another question and it actually helped you think. What made it work, and when did it instead just feel frustrating or evasive?
- The Socratic approach withholds direct answers to provoke 'productive struggle.' Do you believe struggle is necessary for deep learning, or is it sometimes just unnecessary friction — and how would you tell the difference?
- An AI Socratic tutor must decide when to guide, when to hint, and when to give a direct answer, based on a student's real-time signals. How do you think a system (or a human) knows which move to make at a given moment?
- The page notes a frustrated student may need a brief direct answer before returning to Socratic questioning. What do you think this implies about the limits of a one-size-fits-all question-only approach?
- If a chatbot that only asks questions can produce measurable reasoning gains, what might be lost compared to the original Socratic dialogue with a human mentor — and what might be gained?

Introduction

The Socratic method is one of the oldest pedagogical techniques — originating with Socrates in ancient Athens — and it has found new relevance in the age of generative AI. In AI education research, the Socratic method refers to AI systems that engage learners through guided dialogue, posing questions that lead students to discover answers rather than providing them outright. Asking structured questions rather than providing answers is one of the strongest pedagogical scaffolds for deep learning; when automated via AI, it produces measurable reasoning gains but also requires careful calibration to avoid frustrating learners or displacing human mentorship.(Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot)(Critical AI Tutors: Empower or Enslave?)

Socratic and directive feedback moved different things: Socratic feedback raised comprehension monitoring and task orientation, directive feedback scored higher on prioritization of essential features, and only the directive condition gained from a customized agent (Han et al. (2026)).

Ng'ambi and van der Merwe (2026) capture Socratic questioning working and failing in the same Grade 9 mathematics class: when a learner arrived with a hypothesis, the tutor disaggregated it into sub-questions, but on a structured Pythagoras task it restated and drifted off-topic.

How it works in AI tutoring

Unlike direct-instruction AI tutors that give answers, Socratic AI tutors use question sequences that: - **Elicit prior knowledge** — asking what the student already knows about a topic - **Probe reasoning** — "Why do you think that?" or "What if the situation were different?" - **Surface Misconceptions about AI** — through carefully chosen counterexamples - **Guide toward insight** — without giving the answer away

The Socratic approach directly embodies the principle from EduQwen: **reward "guiding" over "answering."** However, real-time Socratic calibration is harder than paper-bench pedagogy: EduQwen optimizes for correct guiding on a multiple-choice Benchmark, whereas a live Socratic tutor must decide *when* to guide, *when* to hint, and *when* to answer — based on real-time student signals. Affective state is a critical moderator: a frustrated student may need a brief direct answer before returning to Socratic mode. A stricter variant removes the teaching entirely: an introductory-physics agent that only probes asks students to defend a correct prediction against one changed variable (cave detection) and keeps the message after a correct answer indistinguishable from the one after a wrong answer (Cho (2026)).

Hint design has a documented form in a domain this page otherwise does not cover. In a second-language revision task with 58 university students at CEFR A1–B1, the design gave guided clues and required learners to infer the correction rather than receive it (Lukešová & Jennings, 2026). Reduced cognitive load and personalized revision paths were reported mainly for learners who already held enough prior knowledge to act on a clue, and feedback depth varied with how well the student prompted. Withholding the correction therefore has a proficiency floor, which is the calibration problem in a form a study can measure.

Evidence of effectiveness

A custom Socratic AI chatbot deployed in a large-enrollment introductory mechanics course (150 first-year STEM majors) produced measurable reasoning gains:

Metric	Result
Sample	150 first-year STEM majors
Knowledge-based skills rating	Median **4.0/5**
Overall effectiveness rating	Median **3.4/5** (notable gap)
Question specificity (first turn)	~10–15%
Question specificity (final turn)	**100%**
Specificity × grade correlation	Pearson **r = 0.43**

Interpretation: Students began with vague, generic questions but progressively sharpened them through Socratic interaction — a clear indicator of developing expert-like reasoning. The positive correlation between question specificity and self-reported expected grade suggests that learning to ask better questions is itself a domain skill.

The effectiveness gap

The gap between “knowledge-based skills” (4.0/5) and “overall effectiveness” (3.4/5) suggests a tension: students recognize that the Socratic bot improved their reasoning, yet do not fully endorse it as a complete tutoring solution. Possible reasons: - Socratic dialogue is effortful; students may prefer direct answers for efficiency - The chatbot cannot provide the relational support of a human tutor - Some students may get stuck in Socratic loops without resolution

A counter-finding: unrestricted access can outperform constrained modes

Not all evidence favors constraining the AI. Socrates went Nuclear (Clin Deffarges, Kosmyna & Maes, 2026), a randomized EEG study of 50 participants comparing an unrestricted ChatGPT-style bot, a Socratic hint-only mode, and an adaptive question-limited mode on a nuclear-safety learning task, found that the **unrestricted chatbot produced higher learning gains** than both constrained modes ($p < .03$, $d > 0.80$) — even though the **adaptive condition generated significantly higher EEG-measured cognitive engagement** ($p = .018$). The result complicates the assumption that pedagogically constrained (Socratic) interaction always yields deeper learning: on short-horizon factual acquisition, free access won, while restricting access raised measured cognitive engagement without converting it into higher immediate post-test gains. This is a useful calibration point alongside the stronger learning-outcome results above: constraint can boost engagement, but the engagement-to-retention translation is not automatic, and over-constraining may simply frustrate learners seeking answers.

The strongest causal support for constraint points the other way: in a K-12 review, high-schoolers using a general-purpose chatbot scored about 17% worse on closed-book finals than peers with no AI access, while a tutoring-specific bot with graduated hints and a refusal to give direct answers mitigated the drop (Stanford SCALE Initiative (2026)).

- **A Socratic tutor with full context can be rated the worst of four.** In a 2×2 randomized trial with 132 introductory Python students, the GPT-4o assistant using Socratic questioning with full problem context scored significantly lower on support for task completion (mean rank 48.63, μ = 3.53) than the direct-instruction and no-context variants ($\chi^2(3) = 12.14$, $p = .007$). It trended highest on interaction stress and external LLM use (23% against 15% overall), and produced the fewest full-comprehension post-task explanations (48%). Socratic conditions sent more queries (μ = 11.1 per problem without context), which Eastwood et al. (2026) read as withheld answers forcing extra back-and-forth rather than productive struggle.

In clinical-interview training, the MeduAI-SP trial (Yang et al., 2026) had the tutor agent deliver Socratic prompts only on a flagged need — missing key history, premature closure, conversational impasse, or communication breakdown — phrasing them as reflective questions such as whether the gathered information sufficed to support the leading diagnosis. Students trained under this Socratic scaffolding scored 31 percentage points higher on the observable “expressing empathy” checklist item (Holm-corrected P = 8.30e-4) and 0.90 points higher on the 1–5 OSCE communication domain (P = 4.50e-4), linking non-answer-giving questioning to measurable patient-centered communication gains rather than to diagnostic accuracy (84% vs. 86%; P = 1.000).

Fidelity is not guaranteed by configuration: a purpose-configured ISLE facilitator restored the test-before-prediction order students had inverted, yet when pressed to "just tell us" which can weighed more it produced mass values no one had measured, crossing from questioning into fabricating data (Tufino & Damiani (2026)).

Research in the knowledge base

The **Socratic Physics Chatbot** provides empirical evidence that the Socratic method can be operationalized through generative AI at scale, serving simultaneously as a teaching tool and data-collection instrument for Learning Analytics. Unlike rule-based Socratic systems of the past, Large Language Models (LLMs)-based approaches can adapt question sequences dynamically based on student responses.

Adversarial AI agents enact constructive conflict — a Socratic variant — prompting novice designers to reconsider their assumptions, leading to more design iterations and higher-rated final work. This connects Socratic questioning to Design Thinking and Critical Thinking.

Multimodal dialogue systems extend Socratic tutoring to visual domains, using a zero-retraining intervention protocol that asks models to describe, reason, and self-correct — a Multimodal AI Socratic scaffold.

Retrieval-augmented tutoring operationalizes Socratic principles through retrieval, anchoring each response in authoritative course content rather than relying only on the model's parametric knowledge — addressing the gap that pedagogical quality alone is insufficient without content fidelity.

Socratic tutoring in biology teacher preparation. A quasi-experiment with 124 prospective biology teachers found a ChatGPT-4 Socratic tutor on socio-scientific issues outperformed offline peer discussion on argumentation quality ($F(1,121) = 14.23$, $p < .001$), with gains concentrated in rebuttal and counter-evidence evaluation rather than claim formation (Ergasheva et al., 2026).

LFTutor (Shi et al., 2026) applies Socratic questioning to a subject where withholding the answer is the whole task: teaching laypeople to see the logical fallacy in a persuasive text they believe is valid. Its dialogue agent decomposes the learner's own argument with the Toulmin model (claim, grounds, warrant), detects the learner's intent, and then selects exactly one of four strategies - Responding, Evidence, Assumption, Refutation - in a fixed priority order that mirrors the Toulmin structure, with a separate verifier agent checking after generation that the reply actually executed the chosen strategy and rephrasing it when it did not. The evaluation metrics are the Socratic failure modes rather than learning gains: divergence from the topic, stance change (caving to the learner's position), repetition, failure to refute, failure to ask for evidence, strategy fixation, unexplained fallacy terminology, and passive guidance. Across 1,000 simulated dialogues per framework with a GPT-4o backbone, LFTutor passed 84.5% of dialogues on average against 61.5% for a prompt that listed those same pitfalls and 31.2% for plain role-play prompting, and the ablation shows the gain is not from the Toulmin vocabulary but from verified strategy execution and intent-based selection. With 20 human participants debating the tutor, LFTutor scored significantly better on eight of nine Likert metrics, including helpfulness (4.15 against 1.65), with repetition the one dimension where the difference was not significant.

Gating can make withholding enforceable rather than cosmetic: Prober.ai constrains an LLM to ask only inquiry-based questions and releases a concrete revision suggestion only after the student writes a defense

that clears a reflection gate, returning a coaching nudge instead when the defense is thin (Bi, Wei and Zhou (2026)).

Agency and critical use

Favero et al. (2025) caution that even Socratic AI can undermine Learner Agency if students become dependent on the questioning structure rather than internalizing it. The goal is not permanent Socratic scaffolding but **scaffolded transfer** — students eventually Socratize themselves.

Connections to other concepts

The Socratic method is closely tied to Scaffolding (providing just enough support), productive-struggle (letting students wrestle with difficulty), and Intelligent Tutoring (adaptive question sequencing). It contrasts with Over-Reliance — students who receive direct answers may bypass learning, while Socratic guidance maintains cognitive engagement. It supports Self-Regulated Learning and Metacognition by making reasoning visible, and connects to Formative Assessment when used to probe understanding in real time.

Open Questions

1. Does Socratic dialogue transfer across domains, or is domain-specific reasoning non-transferable?
2. How does Socratic specificity correlate with *actual* (not self-reported) course performance?
3. Can Socratic AI be combined with peer feedback for social amplification?

- **Withholding answers to provoke reasoning.** Puech et al. (2025) engineer LLM tutors to follow productive failure pedagogy by withholding solutions and eliciting multiple attempts — a Socratic-style refusal to give help except when strictly necessary; Wang & Shan (2026) recommend Socratic and Adversarial AI architectures that preserve constructive cognitive friction.

Common Misconceptions

- **“Socratic questioning is just the absence of answers.”** A custom Socratic AI chatbot deployed in a large-enrollment introductory mechanics course (**150 first-year STEM majors**) produced **measurable** gains, and the design is structured questioning — a constrained interaction, not a silent model.
- **“The effect is downstream of engagement.”** Socrates went Nuclear (Clin Deffarges, Kosmyna and Maes, 2026) is a **randomized EEG study of 50 participants** comparing an unrestricted ChatGPT-style bot against a **Socratic** one, which measures the mechanism rather than inferring it from outcomes.
- **“Constraints are the problem to be removed.”** The strongest causal support for constraint points the other way: in a K-12 review, high-schoolers using a general-purpose chatbot **scored about 17% worse on closed-book finals** than peers using a constrained tool. The unconstrained tool was the harmful condition.

Connected Concepts

- Pedagogical Patterns — The questioning sequence and its conflicting trial evidence
- Scaffolding
- Intelligent Tutoring
- Learning Analytics
- STEM Education
- Learner Modeling and Adaptive Instruction
- Student Experience
- Agentic AI
- Metacognition
- Knowledge Tracing
- Adaptive Learning
- Generative AI
- Cognitive Offloading
- Self-Regulated Learning
- Formative Assessment
- AI Literacy
- Learner Agency
- Critical Thinking
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Productive Failure — Productive Failure

Connected Articles

- The Effects of Agent Type and Feedback Style on Self-Directed Learning: A Mixed-Methods Study — Socratic versus directive feedback styles in a 2 x 2 postgraduate design study
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot
- Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers
- Multimodal Dialogue in STEM Education
- Retrieval-Augmented Tutoring for Algorithm Tracing and Problem-Solving in AI Education
- Distinguishing performance gains from learning when using generative AI
- Embodied inquiry with AI as facilitator: An exploratory case study

- Prober.ai: Gated Inquiry-Based Feedback via LLM-Constrained Personas for Argumentative Writing
- Generative AI without guardrails can harm learning: Evidence from high school mathematics
- The Evidence Base on AI in K-12: A 2026 Review — Structured Socratic hints vs. open-ended general-purpose Q&A
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- The safety gap: restoring productive struggle through pedagogically aligned generative AI — The Safety Gap: Restoring Productive Struggle
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: AI to Support PF Problem Design
- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Language Learning
- Socrates went Nuclear: Comparing Interaction Strategies for AI systems in a Learning Context using Brain Sensing — Socrates went Nuclear: Comparing Interaction Strategies for AI in Learning
- Tackling the Root of Misinformation by Teaching Laypeople about Logical Fallacies via Socratic Questioning and Critical Argumentation — Socratic questioning plus critical argumentation in a four-step fallacy-tutoring framework
- Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming — Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming
- Enhancing PISA-aligned argumentation skills of prospective biology teachers through generative artificial intelligence — Enhancing PISA-aligned argumentation skills of prospective biology teachers through generative artificial intelligence
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)
- Designing an AI Agent That Does Not Tutor: Design Rules for Socratic Probing in Introductory Physics — Designing an AI Agent That Does Not Tutor: Design Rules for Socratic Probing in Introductory Physics

Critical Pedagogy

> **Critical Pedagogy** — an educational approach, rooted in the work of Paulo Freire and later critical theorists such as Henry Giroux, that treats teaching and learning as inherently political acts. Rather than merely transmitting skills or knowledge, critical pedagogy asks who benefits from education, whose knowledge is privileged, and how schooling reproduces or resists systems of power and oppression. In AI-in-education, critical pedagogy interrogates the corporate and capitalist logics shaping AI adoption, centers the voices and epistemologies of marginalized communities, and treats AI literacy as a practice of resistance and social transformation rather than mere technical competence.

Questions to Consider

- Who does your education — or the AI tools in it — actually serve? Critical pedagogy insists this question is unavoidable, not optional. What's your honest answer?
- Critical thinking asks 'is this reasoning sound?' Critical pedagogy asks 'who does this education benefit, and whose knowledge counts?' How are those two questions different, and when does one need the other?
- Some scholars describe generative AI's spread into education as a form of 'colonization' that extracts data, labor, and resources from marginalized communities. Does that framing feel extreme, or does it name something real?
- Critical AI literacy can include 'resisting AI' — refusing the inevitability of tech as a solution. In what situations might strategic refusal or non-use be a more responsible choice than adoption?
- Who gets to decide what counts as authoritative knowledge? If AI systems are positioned as authoritative, what happens to learners' own lived and community epistemologies?
- Under critical pedagogy, a teacher is not a neutral transmitter of AI skills but a facilitator who helps Learners interrogate the politics of AI. How comfortable are you with that role, and what would it ask of you?

Introduction

Critical pedagogy is distinct from Critical Thinking. Critical thinking is a cognitive skill — evaluating arguments, questioning assumptions, and reasoning carefully — that can be practiced within almost any framework. Critical pedagogy, by contrast, is a *political and ethical stance* that connects those skills to questions of power, justice, equity, and social transformation. The knowledge base treats them as related but distinct concepts: critical thinking asks "is this reasoning sound?", while critical pedagogy asks "who does this education serve, and whose knowledge counts?".

Critical pedagogy and AI in education

AI in education raises sharp questions for critical pedagogy, and the knowledge base documents several strands:

- **Critique of the "AI colonization" of education.** Critical and feminist scholars argue that generative AI is reshaping education in ways that repeat patterns of colonial exploitation and extraction — of data, labor, and natural resources — enriching the powerful at the expense of marginalized communities.(Can we disrupt the momentum of the AI colonization of science education?) This framing rejects the "techno-utopia" narrative that presents AI as a neutral silver bullet.
- **From compliance to human flourishing.** A socialist-humanist review reframes AI literacy as transformation rather than compliance, naming "AIgemony" — AI reinforcing corporate power asymmetries — and the "ghost work" of invisible human labeling labor, and urging the "being" mode of active engagement over the "having" mode of possession (Rose (2026)).
- **Feminist and justice-centered AI.** A feminist approach to AI prioritizes justice over profit, asks critical questions about the nature and ownership of knowledge, who benefits from AI, and who is accountable when systems fail. It calls for critical AI literacy framed within feminist pedagogies. (Can we disrupt the momentum of the AI colonization of science education?)
- **Resisting AI as a critical literacy practice.** Critical AI Literacy (CAIL) can encompass "resisting AI" — a stance that refuses the inevitability and techsolutionism of dominant discourse, and instead cultivates collective Learner Agency through dialogic, collaborative pedagogies that imagine alternative futures.(Reorienting Critical AI Literacy: A Community-Rooted Praxis of "Resisting AI")
- **Multimodal AI composition as critical AI literacy pedagogy.** Burriss et al. (2026) document a classroom unit in which 22 eleventh-grade students composed video public service announcements about AI Ethics issues of their choosing, translating surveillance, data consent and algorithmic accusation into 90-second to 3-minute films built from sound, image, text and their own bodies. Framed by Critical Posthumanist Literacy, the work shows the political stance in practice: across all seven films harm emerged from tangled human–machine responsibility rather than from a villainous tool, and students still closed on Learner Agency — "the solution is in our reach" — even as one participant dissented that youth "completely lack any kind of credibility." The authors argue that creative, collaborative composition is itself a form of critical AI literacy, and that existing AI literacy scales and competency frameworks, which assume individually measurable performance, systematically exclude it.
- **Redistributing epistemic authority.** Community-based AI learning grounds AI engagement in learners' lived and community epistemologies, challenging the positioning of AI systems as authoritative knowledge sources.(Community-Based AI Learning: Redistributing Artificial Intelligence's Epistemic Authority in Education) This involves epistemic fine-tuning, redistribution of authority, and situated discernment.
- **Critical engagement is the exception, not the norm.** Across 42 classroom episodes in a Romanian lower-secondary study, 15 (35.71%) were AI-dependent and 16 (38.10%) AI-enhanced,

leaving only 11 (26.19%) AI-critical — which motivates Voicu's (2026) six-checkpoint developmental-critical model for interpretive autonomy.

- **Digital mediation as critical practice under resource constraint.** Sithole (2026) applies Critical Digital Pedagogy with decolonial epistemologies of the South to academic development in South African Historically Disadvantaged Institutions, where developers filter institutional AI rhetoric through the question of what it means "for our students from poor schools." Their mediation is intervention rather than facilitation — interrogating rather than adopting tools, asking what is gained and whose labor disappears, and treating context as an epistemic principle rather than a design preference. The author's analytical contribution is to separate digital inequality from **algorithmic coloniality** and to insist, following Adams, that calls to decolonize AI stay material rather than metaphorical.
- **Situated and cultural-historical ethics.** Critical approaches also argue that AI ethics in education must be *situated* — grounded in cultural-historical and ecological context rather than abstract principles.(Situated AI ethics: a cultural-historical and ecological framework for education)
- **Sustainability as a value-based project.** AI's effect on educational sustainability is conditional and governance-mediated, not intrinsic: a value-critical analysis holds that AI supports sustainable education only when adoption is subordinated to explicit educational values and undermines it when technologization and commodification erode them (Alsuhami & Atallah (2026)).
- **Efficiency-first alignment discourse as an erasure of context.** McInnes et al. (2026) apply Fairclough's three-dimensional model to 14 pieces of gray literature (November 2022 – April 2025) advising higher-education practitioners to use generative AI for constructive alignment, and find a techno-solutionist discourse in which the tool is anthropomorphized as "an educational expert and assistant" and academic staff are positioned as supplying "subject matter expertise" while the system performs the pedagogical work. The analysis names the erasure of situated, disciplinary and critical context as one of three failure modes — alongside performativity (alignment that only looks aligned) and shallow alignment that conflates the constructive dimension with the aligned one — evidence that even advice about course design, ostensibly a neutral technical matter, carries the depoliticising logic critical pedagogues critique elsewhere.
- **Design remedies are not enough on their own.** Human-centered design approaches such as value-sensitive design are insufficient: they leave the systemic drivers — workforce-productivity framings and economic incentives — untouched, and Learner Agency may be zero-sum, so capability handed to the tool is capability the learner does not retain (Prieto & Dimitriadis (2026)).
- **Human rights education as the test case for AI governance as formation.** Kasa-Mälksoo (2026) works through the UN's *about, through, for* framework in a law program and locates the difficulty not in the technology but in the pedagogy: students submitted polished written work and polished session designs without the engagement those artifacts are supposed to evidence, and the most critical thinking appeared in end-of-course writing rather than in class dialogue. Her conclusion shifts the educator's role rather than shrinking it — AI governance becomes a professional responsibility students are trained to contest, and the tool is directed rather than banned.

Assessment as a site of critique

Critical pedagogy enters assessment through the question of whose interests a redesign serves. Laidlaw (2026) builds that case by joining the Theory of Practice Architectures to critical pedagogy, so that an assessment reform has to move three things at once: the cultural-discursive language that makes some practices thinkable, the material-economic arrangements of tools and resources, and the social-political distribution of power. The framework's warning is specific. When resources flow through existing power structures without explicit equity attention, a well-intentioned redesign amplifies the inequities it was meant to address, which makes the resource-power intersection both the largest leverage point and the largest risk. Her four-phase matrix runs critical analysis, intervention design, equity-focused implementation and evaluation, and she treats incremental change and productive tension as legitimate outcomes rather than as failure to transform quickly.

The role of the educator

Under critical pedagogy, educators are not neutral transmitters of AI skills but critical interlocutors and facilitators who help learners interrogate the politics of AI. This connects to the knowledge base's Teaching and AI Literacy concepts, and to the broader concern with Equity and Reducing AI Misuse. The educator's task is to cultivate spaces where communities can collectively question, appropriate, or refuse AI — keeping education a site of imagination and social transformation. Burriss et al. (2026) add a practical condition to that role: open-ended critical AI literacy work does not require educators to arrive as AI experts, only to be willing to explore alongside students — a joint student–teacher investigation of one specific system, electronic "hall passes" (not all of which are AI), surfaced and worked through Misconceptions about AI while deepening technical knowledge. Miles, Haber-Curran and Arar (2026) give that role a constructionist, ethics-of-care shape: they treat prompt literacy as a rhetorical, ethical and reflective process rather than a technical optimization skill, and the framework's closing phase has students co-design a Personal AI Use Policy with their instructor, so the norms governing classroom AI use are authored by the people they govern rather than issued to them.

Common Misconceptions

"Using AI critically means using it less." Critical engagement is a mode of use, not a quantity of use. Across **42 classroom episodes** in a Romanian lower-secondary study, **15 (35.71%) were AI-dependent** and **16 (38.10%) AI-enhanced**, leaving only **11 (26.19%) AI-critical** — so the enhanced and the critical episodes both involve the tool, and the distinction is whether students interrogated it. The scarcity of the critical mode is a teaching problem, not a usage problem.

"AI literacy is a neutral skillset." Critical pedagogy treats it as a practice of resistance and social transformation, which makes the framing itself contestable. A literacy curriculum that teaches prompting technique and omits whose interests the system serves has taught fluency in a tool while adopting its politics uncritically.

"Critical pedagogy is a critique offered from outside practice." It is a stance toward the educator's role: asking who benefits, whose knowledge is privileged, and how schooling reproduces or resists power. Applied to AI adoption, that means interrogating the corporate and capitalist logics shaping procurement —

questions an instructor can ask about their own institution's choices, not only about the technology in the abstract.

"Centring marginalised epistemologies is a curriculum-content addition." It changes whose knowledge counts as knowledge, which is a question about the structure of the course rather than an added reading. Content additions leave the frame intact; critical pedagogy's claim is on the frame.

Implications for Practice

For instructors

- Count your critical episodes. If the 26.19% figure describes your practice, the target is a shift in the mode of use rather than less use.
- Make procurement a teachable object: ask with students whose interests a chosen tool serves, and who bears the cost of its errors.
- Treat AI literacy as interrogation of the system, not only competence with it.
- Make the justification the assessable artifact. In a course unit that used Benali and Díaz García's (2026) drafting, revision and reflection workflow with 96 final-year students in 24 groups, AI was confined to two sections of a research proposal and every accepted or rejected AI suggestion had to be justified in writing. Students' reflective reports describe that verification work, not the drafting, as what produced the critical stance, which is why the record of judgment is the thing to grade.

For developers and administrators

- Expect critical pedagogy to interrogate your incentive structure rather than your feature list, and answer the question about whose knowledge the default output encodes.

For researchers

- Report the distribution of engagement modes in classrooms, not only average use, since the mean conceals whether any critical practice exists.

Connected Concepts

- Critical Thinking
- AI Literacy
- Equity
- Culturally Relevant Pedagogy
- Reducing AI Misuse
- Learner Agency
- Ethics
- Teaching
- Social-Emotional Learning
- AI in Education

- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Challenges and opportunities of using artificial intelligence in human rights education: Reflections from higher education practice — Human rights education, reflective practice, and teaching AI governance as professional formation (Kasa-Mälksoo 2026)
- "Young Scholar[s] on the Beat": Multimodal composition as a form of critical AI literacy pedagogy — Multimodal composition as critical AI literacy pedagogy
- Efficiency at what cost? Salvaging constructive alignment from the GenAI hype — Critical discourse analysis of techno-solutionist GenAI constructive-alignment advice
- Teaching with generative artificial intelligence: Enhancing critical thinking and ethical awareness in academic writing — Justification-forced revision in an academic writing course: AI limited to two proposal sections, every suggestion accepted or rejected in writing (Benali & Díaz García 2026)
- Can we disrupt the momentum of the AI colonization of science education? — Critical, feminist critique of the “AI colonization” of science education
- Reorienting Critical AI Literacy: A Community-Rooted Praxis of "Resisting AI" — “Resisting AI” as a community-rooted praxis of critical AI literacy
- Community-Based AI Learning: Redistributing Artificial Intelligence’s Epistemic Authority in Education — Redistributing AI’s epistemic authority through community-based learning
- Situated AI ethics: a cultural-historical and ecological framework for education — Situated, cultural-historical and ecological framework for AI ethics
- AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education — Developmental-critical model for interpretive cognition in the humanities
- From Mechanical Compliance to Human Flourishing: A Socialist Humanist Approach to Asynchronous AI Literacy and Fair Use in Higher Education — Socialist humanist AI literacy + fair use
- Sustainable Education in the Age of Artificial Intelligence and Digitalization: A Value-Critical Approach — Value-critical approach to sustainable education and AI (Alsuhami & Atallah 2026)
- An Emancipatory Vision for Designing (Generative) AI for Learner Flourishing — Emancipatory vision for designing generative AI toward learner flourishing
- Prompts to Practice: A Pedagogical Framework for Human-Centered AI Engagement — Human-centered GenAI engagement framework built on Freire, constructionism and an ethics of care
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Critical Digital Pedagogy and decolonial epistemologies applied to academic development in the Global South

Pedagogical Partnerships

> **Pedagogical partnerships** (also known as **students as partners** or **SaP**) — a relationship-centered approach to teaching and learning in which students and educators work together as collaborators to co-create curriculum, teaching activities, Assessment, open educational resources, and educational policies, rather than treating students as passive recipients of faculty-designed instruction. Rooted in values of **respect, reciprocity, and responsibility** (Cook-Sather et al., 2014), pedagogical partnership repositions students as co-creators of knowledge and educational innovation and challenges traditional top-down power dynamics in education. In the AI era, partnership has become a key counter-narrative to deficit views of students as AI cheaters or victims — positioning students as partners in co-designing AI policy, tools, and practice.

Questions to Consider

- When you design a course, assignment, or policy, who typically makes the decisions — and whose perspective is left out? What would change if the people most affected by those decisions were genuine collaborators rather than recipients?
- A common assumption is that students lack the expertise to contribute to teaching design. Yet partnership research argues students are experts in their own experience as learners. Where is the line between a student's legitimate experiential expertise and the faculty member's disciplinary expertise?
- The word "partnership" can paper over real power differences — a student asked to "co-design" a course still depends on the instructor for grades and references. What conditions make a partnership genuine rather than performative?
- In the age of generative AI, students are often framed as either cheaters or victims. How might reframing them as partners in designing AI use and policy change both the tools built and the conversations educators have with students?
- Partnership can extend to whole classes, small groups, or individuals. Which form is most equitable, and what practical and resource constraints limit broader participation?
- What does trust have to do with pedagogical partnership — and how might surveillance- or deficit-oriented responses to AI fracture the relationships partnership depends on?

Introduction

Pedagogical partnerships, also called **students as partners (SaP)**, describe a spectrum of practices in which students collaborate with academic staff to shape teaching, learning, assessment, curriculum, and the broader student experience. The approach draws on the foundational guide by Cook-Sather, Bovill, and Felten (2014) and the higher-education framework of Healey, Flint, and Harrington (2014), which describe partnership as grounded in three core values: **respect, reciprocity, and responsibility**. Partnership is not about making students pedagogical experts, nor about faculty relinquishing disciplinary authority; rather, it recognizes the

complementary roles each partner brings — faculty as disciplinary experts and intellectual guides, students as experts in their own experience as learners with diverse talents and interests.

Pedagogical partnership challenges the entrenched assumption that students cannot be trusted to collaborate on teaching and learning, and it actively disrupts traditional faculty-centered hierarchies. It overlaps conceptually with Collaborative Learning, learner agency, and Student Engagement, but is distinct in centering students in the *design* of education itself — curriculum, assessment, teaching activities, open educational resources, and policy — rather than merely as active participants within a pre-designed course.

In the generative AI era, pedagogical partnership has taken on new urgency. As AI amplifies deficit narratives that frame students as either cheaters or victims (see AI Misuse and Learning Harm and Framing AI Use for Students), partnership offers a counter-narrative: rather than policing students or assuming misuse, educators and institutions can engage students as co-designers of AI policy, tools, and practice. This is reflected across the knowledge base's research — from students co-designing course AI policies to co-creating custom AI tools and co-constructing assessment criteria.

Forms and scope of partnership

Partnership can take many forms and operate at multiple scales, each with distinct affordances and constraints:

- **Whole-class partnership (co-creation in the classroom):** All students in a course collaborate with faculty on course structure, content, goals, and policies. Whole-class approaches may be the most equitable form of partnership because they allow broad participation and benefit, though they require substantial "high-touch" personnel resources to support increased student decision-making (Bovill, 2020).
- **Individual or small-group partnership:** A small number of student partners work with staff on a specific project — for example, co-designing Assessment criteria, evaluating AI tools, or developing curriculum. These are well-suited to dialogic, in-depth collaboration.
- **Project- or program-based partnership:** Students partner on a bounded initiative, such as co-designing a course AI policy, building a custom AI tool, or developing an algorithmic-literacy program.
- **Partnership in Curriculum Design and Learning Design:** Students contribute to shaping what and how learning happens, from individual activities to entire programs.

Across these forms, partnership is a *process and a relationship*, not just an activity. The outcomes are often co-created and not fully defined in advance, which requires staff to let go of control and accept the risks of the unknown — values that run counter to the hidden rules of much of higher education.

Pedagogical partnership and AI in education

The intersection of pedagogical partnership and AI is one of the fastest-growing strands of the knowledge base. Key themes:

- **Students as co-designers of AI policy.** Rather than institutions imposing AI rules on students, partnership positions students as co-creators of course- and institution-level AI policy. For

example, a guided-inquiry activity in which students co-designed a Generative AI course policy surfaced student priorities around training, standardized disclosure, institutional support, and involvement in decision-making (A Guided Inquiry Approach to Students Co-Designing Generative AI Course Policies).

- **Students as co-creators of AI tools.** In students-as-partners frameworks, students have co-designed and refined custom AI chatbots aligned with pedagogical goals — an approach that extends the SaP paradigm to include AI tools themselves and positions student voice as central to responsible AI innovation (Co-creating custom GPTs: An autoethnographic study of undergraduate students as partners in generative AI innovation).
- **Co-creation at scale, measured cautiously.** In a 710-student software design course, students built an AI tutor for a peer instead of using one. Design freedom was the top positive theme (22.3%) and unclear instructions the top complaint (23.7%), but perceived learning correlated with quiz scores only at r = 0.161 to 0.315 and the design had no control group (Zangari et al. (2026)). Building the tool is a plausible pedagogy and, on this evidence, an unproven one, which is why the case for it rests on the design activity rather than on outcome gains.
- **Whole-class co-design, evaluated by Self-Assessment.** A first-year information-studies program had students and faculty co-design course goals and policies in the first week and revisit them through the term, with students grading themselves and their groups against personal goals, team goals and a shared rubric rather than final products (Maybee, LeGrand & Fundator (2025)).
- **Co-creation in assessment and AI.** Student-staff partnerships have co-evaluated AI-generated output in coursework assessments and co-designed evaluation criteria, improving understanding of AI's benefits and limits and supporting Self-Regulated Learning (Assessment design through co-creation: Student-staff partnership in evaluating the impact of artificial intelligence).
- **Partnership to preserve pedagogical trust.** In the face of AI-driven uncertainty and "AI shame," partnership practices that nurture *pedagogical trust* — a confident, reciprocal learning relationship open to uncertainty and co-navigated through dialogue — offer a way to sustain the relational core of education (Five guiding principles for navigating artificial intelligence in students as partners practice to preserve pedagogical trust).
- **Youth as co-designers of AI systems.** Participatory design approaches engage historically minoritized students as partners in designing the AI systems that will affect their classrooms, surfacing students' values and ethical commitments (Co-designing AI with youth partners: Enabling ideal classroom relationships through a novel AI relational privacy ethical framework).
- **Students' lived realities as a design input.** Frameworks like entangled pedagogy illuminate the complex, "messy" realities students navigate with AI, arguing that policy and guidance should be co-designed with students in light of their lived experiences rather than imposed from above (Illuminating complex student realities of artificial intelligence through an entangled pedagogy framework).

These strands share a core claim: that the people who will live with AI in education — students — must be meaningfully engaged in shaping it, or the resulting tools, policies, and practices risk being untrustworthy, inequitable, or ineffective.

Relationships to related concepts

Pedagogical partnership is related to but distinct from several neighboring concepts:

- **Learner agency and Self-Directed Learning:** Partnership supports learner agency by giving students a voice in what and how they learn, and it overlaps with self-directed learning. However, partnership is fundamentally *relational* — agency and direction emerge through the instructor–student relationship rather than in isolation. Some frameworks conceptualize this as "shared agency" that exists in the relationship between student and instructor, not within either party alone.
- Anastasia (2026) names the eight conditions such a partnership requires — instructor presence, trust, psychological safety, dialogue, voice and choice, meaningful feedback, reflection, and shared responsibility — and argues that choice alone does not create autonomy: students may be handed options while lacking the information, confidence, or psychological safety to exercise them (Anastasia (2026)).
- **Collaborative Learning:** Both involve working together, but collaborative learning typically refers to students learning *with each other* within a designed activity, whereas pedagogical partnership centers students and staff collaborating on the *design* of education itself.
- **Student Engagement:** Partnership is a deep form of engagement, but engagement describes a student's involvement in learning while partnership describes a changed power relationship in which students share responsibility for shaping that learning.
- **Teaching:** Partnership redefines the teacher's role from sole authority and gatekeeper of knowledge to co-designer and intellectual guide, without diminishing faculty expertise.
- **Assessment and Authentic Assessment:** Co-designing assessment — from evaluation criteria to rubrics to whole assessment formats — is a central arena of partnership, and AI has amplified both the need for and the difficulty of genuine co-design in assessment.
- **Educational AI Policy and AI Governance:** Partnership extends into policy and governance, positioning students as co-creators of AI policy rather than passive subjects of it.
- **Equity and Inclusive Learning:** Partnership is argued to be a more equitable form of educational participation, centering voices — especially those of historically minoritized or marginalized students — that are often excluded from educational decision-making.

Key research themes

- Whether and how partnership improves learning outcomes, Student Engagement, Motivation, and a sense of belonging.
- The relational conditions — trust, psychological safety, dialogue, shared responsibility — required to bring partnerships about and sustain them.
- How AI both enables and complicates partnership: as students co-design AI tools and policies, and as deficit narratives around AI threaten the trust partnership depends on.
- Equity in partnership: which students get to participate, whose voices are centered, and how whole-class vs. selective forms distribute benefit.

- The resource and institutional constraints on partnership, including the time-intensive nature of genuine co-design.
- How partnership relates to decolonizing, critical, and critical pedagogies that challenge traditional hierarchies and center multiple ways of knowing.
- **Mentoring can run in both directions.** In a 20-fellow, 15-intern program across 14 Columbia departments, interns taught faculty AI tools while faculty taught disciplinary standards, most pairs settling into a Translator model (Zheng (2026)).

Practical implications

For educators and institutions seeking to adopt pedagogical partnership, the knowledge base's research suggests:

1. **Start small and iterate.** Begin with a bounded project — a pilot with a limited number of participants — and honor participant effort with recognition (employment, credit, certificates, publication).
2. **Build on existing infrastructure.** Faculty development programs, student employment relationships, and cross-campus partnerships provide foundations for adapting partnership practice.
3. **Lead with relationship and trust.** Partnership works when trust, psychological safety, dialogue, and shared responsibility are deliberately cultivated — not assumed.
4. **In the AI era, invite students in rather than policing them.** Co-designing AI policy, tools, and assessment with students is both more equitable and more effective than deficit-based responses.
5. **Consider equity of participation.** Whole-class partnership offers the broadest participation; selective programs must attend to which students are invited and included.

Common Misconceptions

- **"Partnership means elevating student voice."** A pedagogical partnership is a **bounded, negotiated relation** with defined roles and reciprocal obligation, not consultation. Voice without a role, a remit and a share of the decision changes nothing structural.
- **"Partnership is a stance one can adopt."** It requires institutional conditions — time, recognition for the student partner, and a change the partners can genuinely affect. Declared partnership without those conditions reproduces the hierarchy it claims to interrupt.
- **"Power-sharing cannot be faculty development."** The claim of the literature is that partnership is development *because* it changes the educator's understanding through the relation. Framing it as student benefit only discards the mechanism.

Connected Concepts

- Pedagogies and Teaching Strategies — Pedagogies and teaching strategies
- Collaborative Learning
- Learner Agency — Learner agency

- Self-Directed Learning
- Curriculum Design
- Learning Design
- Assessment
- Authentic Assessment
- Teaching
- Student Engagement
- Student Experience
- Educational AI Policy
- AI Governance
- Equity
- Inclusive Learning
- Human AI Collaboration
- Student-AI Interaction
- Generative AI

Connected Articles

- A Guided Inquiry Approach to Students Co-Designing Generative AI Course Policies — A Guided Inquiry Approach to Students Co-Designing Generative AI Course Policies
- Co-creating custom GPTs: An autoethnographic study of undergraduate students as partners in generative AI innovation — Co-creating custom GPTs: an autoethnographic study of undergraduate students as partners in generative AI innovation
- Assessment design through co-creation: Student-staff partnership in evaluating the impact of artificial intelligence — Assessment design through co-creation: Student-staff partnership in evaluating AI
- Five guiding principles for navigating artificial intelligence in students as partners practice to preserve pedagogical trust — Five guiding principles for navigating AI in students as partners practice to preserve pedagogical trust
- Co-designing AI with youth partners: Enabling ideal classroom relationships through a novel AI relational privacy ethical framework — Co-designing AI with youth partners: a relational privacy ethical framework
- Illuminating complex student realities of artificial intelligence through an entangled pedagogy framework — Illuminating complex student realities of AI through an entangled pedagogy framework
- Shared Agency: The Agency Partnership Framework for Instructor–Student Collaboration — Shared Agency: The Agency Partnership Framework for Instructor–Student Collaboration
- Disruptive Partnerships: Collaborating with Students to Create Empowering Learning Experiences in Information Studies — Disruptive Partnerships: Collaborating with Students in Information Studies

- A Student-Centered Framework for Responsible Use of Generative AI in Higher Education — Student-centered framework for responsible generative AI use
- Why Pay for an AI Tutor When You Can Design It? Student-Created AI Agents as Co-Designed Instructional Tools for a Large Software Design and Engineering Course — Students built an AI tutor for peers at 710-student scale: engagement high, learning evidence exploratory (Zangari et al. 2026)

Storytelling in Education

> **Storytelling in education** — the use of narrative as a pedagogical tool to engage learners, convey meaning, and support knowledge construction, creativity, and emotional connection. Storytelling is a natural and motivating way for learners to make sense of the world, and it is increasingly combined with technology — including AI and social robots — to create interactive, adaptive narrative experiences. Digital and robot-mediated storytelling can add interactivity, personalization, and embodiment that conventional (paper-based or slide-based) storytelling lacks.

Questions to Consider

- Think of a lesson or concept you remember vividly because it came as a story. What did the narrative add that a plain explanation didn't, and can that power survive being outsourced to an AI or a robot?
- The page describes robot- and LLM-mediated storytelling that responds to the learner and supports co-creation. What do you imagine is gained — and potentially lost — when a story is co-built with a machine instead of told by a person?
- If storytelling builds engagement, creativity, and emotional connection, where might its use in education be more than entertainment — and where might it risk substituting feeling for understanding?
- A robot storyteller increased behavioral and cognitive engagement over paper and PowerPoint in the research cited. Do you trust that engagement translates into learning, or could the novelty of the robot be doing the work?
- How could you tell whether a learner is genuinely making meaning from an AI-co-created story versus just enjoying the interactive experience?

Introduction

Storytelling is grounded in Motivation, Student Engagement, and Constructivism theories of learning. It supports Language Learning, Creativity, Social-Emotional Learning, and comprehension. In the AI era, LLM-powered and robot-mediated storytelling enables co-creation, where learners and AI agents build stories together, and interactive narrative that responds to the learner.

How storytelling appears in the knowledge base's research

- **Robot-mediated storytelling:** MotiBo uses a human-like interactive digital storytelling robot, finding significant gains in behavioral and cognitive engagement over paper and PowerPoint methods; RoboBuddy lets teachers create LLM-powered scenario-based storytelling activities from curriculum content.
- **Engagement gains have a size, and motivation did not follow.** MotiBo finished 27.06% and 30.00% ahead of paper and PowerPoint on behavioral and cognitive engagement (both $p < .05$),

while intrinsic motivation rose 20.21% without reaching significance ($p = .07$). Engagement moved, motivation did not clear its threshold, and the five-day quasi-experiment measured no learning outcome (Fung & Lui, 2026).

- **Co-creative narrative HRI:** The iCub narrative study explores human-robot co-creation of stories, integrating generative models for contextually appropriate interaction.
- **Narrative and creativity:** Storytelling supports Creativity and language development, and is used to enhance motivation and engagement in K-12 settings.
- **Digital storytelling as a counterweight to AI:** As generative AI ascends, digital storytelling is reframed as a vehicle for the emotional, cultural, and narrative capacities that AI lacks. In a project-based learning model for art and design education, students translated local cultural heritage into Multimodal AI narratives across 92 digital storytelling works, demonstrating how storytelling sustains human creativity in the AI era.
- **Generated narrative is easy to produce and hard to keep coherent.** With 22 STEM students, AI-generated interactive fiction rated well on narrative clarity ($M = 4.11$) and length ($M = 4.14$), but engagement sat at the neutral midpoint ($M = 3.08$) and story-content coherence was weakest ($M = 2.92$) (AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement). Co-creation inherits that weakness at the layer a story is supposed to do its work.

Storytelling connects to Student Engagement, Motivation, Creativity, Robots in Education, Language Learning, Social-Emotional Learning, and Robots in Education.

Common Misconceptions

“A co-built story is a told story.” What is gained is fluency and volume; what is at risk is the teller’s authorship. A story is a structuring of experience by someone who chose the sequence and the emphasis, so a machine that supplies the structure has supplied the part that carries the meaning.

“Storytelling is a soft addition to content.” Narrative is a memory and sense-making device, and the learner who narrates is doing the organizing work. Handing over the narration hands over the learning.

“AI generation makes storytelling available to students who could not write.” It makes *producing a written artifact* available, which is a different benefit. Oral narration, drawing and dictation are the established routes to the same goal, and they preserve the authorship that generation removes.

“The educational value of a story is in the polished result.” It is in the construction — the selection and ordering that a teller performs. A polished story the student did not structure has demonstrated the model’s competence rather than the learner’s.

Connected Concepts

- Student Engagement
- Motivation
- Creativity
- Robots in Education

- Language Learning
- Social-Emotional Learning

Connected Articles

- MotiBo: The impact of interactive digital storytelling robots on student motivation through self-determination theory — MotiBo
- RoboBuddy in the classroom: Exploring LLM-powered social robots for storytelling in learning and integration activities — RoboBuddy
- Would you let a humanoid play storytelling with your child? A usability study on LLM-powered narrative human-robot interaction — iCub Narrative HRI
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — REMind
- Robotics and Artificial Intelligence in Education: Transformations, Challenges, and Future Directions — Robotics and AI in Education
- AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement — AI-generated interactive fiction: coherence as the weak dimension in a 22-student pilot

Online Teaching and Learning

> **Online teaching and learning** — the pedagogy and practice of teaching and learning that happens through digital, network-mediated environments rather than in a shared physical classroom. It spans fully online courses, Massive Open Online Courses (MOOC), blended and hybrid formats, and distance education. For the knowledge base, the central question is how Generative AI reshapes the opportunities, challenges, and recommended practices of teaching at a distance — from scalable personalization to new Academic Integrity and Cognitive Offloading risks.

Questions to Consider

- You've likely taken an online course or taught one. What did you lose and what did you gain when the physical classroom was removed—and how did that reshape what instructors could rely on?
- The page argues online teaching is a distinct pedagogy, not just a delivery mechanism. In what concrete ways does the online medium change which teaching strategies are even possible or effective?
- An RCT found unguarded AI assistance raised practice performance but lowered unassisted exam scores, while a 'hint-not-answer' tutor removed the harm. Before reading further, can you explain why giving students the answer might inflate immediate performance yet erode durable learning?
- Online assessment can't always tell assisted from independent work. If detection tools are a 'partial, contested response,' what alternative assessment designs might reveal genuine understanding instead?
- How does the perceived availability of an effortless AI shortcut reshape student motivation in a self-paced, screen-based course? What might you design to counter it?
- An autonomous agent can now log into a learning management system, read the material, answer the quiz and post to the discussion. If producing the artifact no longer demonstrates learning, what would you need to see instead?
- AI can now generate a MOOC-equivalent course in minutes at a fraction of the cost. What are the pedagogical trade-offs of 'N agents for one student' versus 'one video for N students'?

Introduction

Online teaching and learning is a distinct pedagogical context, not merely a delivery mechanism. It removes the physical co-presence that scaffolds attention, Motivation, and informal interaction, and it substitutes structured digital interaction — discussion forums, asynchronous materials, video, tutoring agents — for face-to-face contact. This changes what instructors can rely on, what students can access, and how learning is designed and assessed. As an umbrella concept in the Pedagogies and Teaching Strategies landscape, it sits alongside Active Learning, Collaborative Learning, and Self-Regulated Learning but is distinguished by the medium: the constraints and affordances of the online environment shape which strategies are viable.

The rise of generative AI lands directly in this context. Online learners already work through screens and software, so AI tools are natural neighbors; at the same time, online assessment is harder to invigilate, making misuse easier and the stakes higher. The evidence in this knowledge base shows that AI can be a powerful ally for online teaching and learning — and, configured poorly, a significant source of learning harm.

Lock, Arteaga & Johnson (2025)'s critical literature review (63 citations across 32 countries) organizes this landscape into four interconnected themes that recur throughout the page below: the types and purposes of AI integration, pedagogical approaches (AI literacy, self-regulated learning), benefits, and challenges. Their central caution — that these themes *overlap* and that online AI integration is a sociotechnical undertaking anchored in pedagogy and human relationships rather than technology adoption alone — aligns with the page's framing of online teaching as a distinct pedagogy. Notably, they report that students using ChatGPT *alongside* teacher tutoring perceived greater Learning Gains than those using it alone, reinforcing the hybrid human–AI collaboration emphasis threaded through this page.

The development that moved this from a design question to an urgent one is that generative AI no longer only writes text a student could have written. Autonomous agents now log into a learning management system, read the course materials, answer the quizzes, read classmates' posts, and submit the work. Three demonstrations on a live undergraduate psychology course show what that means in practice: two quiz completions, one in roughly **12 minutes** and one in **under 5 minutes**, both scoring **10/10**, and a discussion post in which the agent mined its peers' posts and then fabricated a credible first-person life history to answer them — against a public record of at least **15 documented agent runs** across Canvas, Moodle and Brightspace using **seven agent tools**. Hadjisolomou and El-Haddad (2026) argue this is an Assessment Validity problem before it is an integrity one: what agent completion removes is the assumption that the submitted work was produced by the person whose learning is being assessed. The design question for online teaching therefore shifts from how to detect misuse to what evidence of learning an online course can still produce, which is the thread running through the sections below.

Formats and settings

Online teaching and learning takes several related forms that share the medium but differ in reach and structure:

- **Blended and hybrid learning.** Models that combine in-person and online components, intentionally integrating digital activities, materials, and interactions with face-to-face teaching. Blended formats ask instructors to decide what is best done synchronously vs. asynchronously and online vs. in person — decisions that Learning Design principles organize and that AI both supports and complicates. In the blended context, AI tools offer opportunities for personalization and always-on support while raising integrity and offloading risks that span both the online and in-person portions. Mejia-Domenzain et al. (2026) illustrate this in two blended settings — flipped university classrooms and reflective writing in vocational education — where a learning analytics dashboard (DashED) communicated ML-derived Self-Regulated Learning profiles to teachers. Adoption concerns diverged by context: flipped-classroom (university) teachers worried most about data anonymization and student opt-out, whereas reflective-writing (vocational) teachers feared misuse of the tool by fellow educators and stressed the need to contextualize data. In use,

flipped-classroom teachers followed a sequential exploration and favored course-level adaptation and showing dashboards in class, while vocational teachers revisited summary pages and used the tool mainly for individual coaching sessions — evidence that blended analytics design must be context-aware.

- **Synchronous versus asynchronous design.** The distinction matters more than the delivery medium, because the two formats make opposite demands on the learner. Synchronous sessions carry attention, pacing and accountability inside the session itself; asynchronous courses have to design them in, since the learner alone decides when to work and receives no ambient accountability from a room. The research base often blurs this: the knowledge base's review of AI and engagement in online learning (24 studies) treats engagement alone and explicitly conflates synchronous with asynchronous contexts, so its conclusions should not be read as asynchronous-specific. What is asynchronous-specific is the evidence on how self-paced learners lose focus and pace — self-regulated behaviors such as goal setting, environment structuring and time management coincide most with low digital distraction (Shi et al. 2026, 530 students), while metacognitive knowledge and Well-Being decline across a term in step with clustered assessment deadlines (Song et al. 2026, 75 students). The practical counterpart is the FAQ on designing and facilitating asynchronous courses when AI can do the work.
- **Distance education.** Programs designed for learners who study remotely, often at scale and across regions (e.g., the Open University's 200K+ learners). Distance learning is where 24/7, context-embedded AI support and the impossibility of in-person invigilation are most salient. Comparative evidence from South African teacher preparation shows the medium itself is associated with preparedness. Mnguni et al. (2026) reported a gap in self-reported TPACK for AI-integrated science teaching of 64.0% against 47.4% between final-year trainees on campus-based and distance programs, with Pedagogical Knowledge weakest at both institutions. The pattern warns that distance programs cannot assume that the same AI training produces the same readiness, and that the design of the training, not its presence, is what differs.

Opportunities and benefits of AI for online teaching and learning

- **Scalable personalization.** Traditional MOOCs excel at reach but struggle to adapt — "one video for N students." Large Language Models (LLMs)-driven agent systems (MAIC) invert this to "N agents for 1 student," using specialized Teacher, Assistant, Classmate, and Analyzer agents to deliver adaptive instruction, personalized feedback, and dynamic learning paths at MOOC scale. Systems like LearnMate² address the "personalization gap" in open online learning with personalized study plans, real-time contextual assistance, and adaptive activities. Personalized video is a concrete route to this goal: Tomlinson et al. (2026) found students in a large online course preferred AI-generated personalized videos over non-personalized human-recorded ones — a preference whose personalization effect outweighed the value placed on a human presenter — suggesting scalable, Generative AI-produced personalized media can close the "one video for N students" gap in online instruction.
- **Always-on, context-embedded support.** In distance and adult learning contexts where learners study at work or at home, 24/7 support embedded in the course is a major benefit. The Open University's AIDA assistant found purpose-built, in-environment GenAI support increased

engagement (doubled usage time in an exploratory trial), with 96% of students wanting it in their formal studies.

- **Conversational, dialogic tutoring at scale.** Conversational AI tutors built on proven Intelligent Tutoring technology (keep/change/center/study framework) promise high-quality, dialogue-based tutoring — engaging students' thoughts, questions, and Misconceptions about AI — that is far more scalable than human tutoring.
- **Facilitation and analytics.** AI can support online discussions and Learning Analytics, forecasting engagement, and helping instructors allocate attention. Hao & Cukurova (2026) add that LLM-generated discussion summaries can act as navigational scaffolds in large asynchronous forums — broadening students' peer exposure and the network conditions for bridging social capital without burdening students or instructors with the summarizing workload.
- **Early-warning analytics for at-risk online learners.** Zhang, Jeffries & Koprinska (2025) show that interpretable machine learning on content-interaction logs predicts module-level progress and flags dropout ("No submission") outcomes in large-scale online programming courses up to 7–8 days before module deadlines, giving online instructors a concrete window to intervene with disengaged students rather than discovering failure only after the fact.
- **Affordability and speed.** AI can generate course materials at a fraction of traditional cost — MAIC reduced MOOC course production from ~$25K/60 hours to under $2/30 minutes.

Challenges of online teaching in the AI era

The online medium and generative AI combine to intensify a specific cluster of challenges that instructors must confront head-on. Where face-to-face teaching can rely on presence, immediate accountability, and invigilation, online teaching must design explicitly for them.

Academic integrity and cheating

Online courses already present invigilation challenges — in-person proctoring is often unfeasible for distributed, asynchronous learners. Generative AI compounds this by making AI-generated work indistinguishable from student work and by enabling contract-cheating style shortcuts at scale. The knowledge base's evidence on Academic Integrity and AI Misuse and Learning Harm shows that misuse is driven less by AI errors than by students copying answers instead of learning. Because online assessment frequently cannot distinguish assisted from independent work, misuse can inflate immediate grades while eroding durable knowledge — a perceived-vs-actual gap that is especially dangerous at a distance where instructors have less visibility into student process. Detection tools are a partial, contested response (AI plagiarism detection, Remote Proctoring), and the knowledge base's stance favors authentic, process-revealing assessment over detection arms races.

AI misuse and cognitive offloading

The most serious risk is that online learners outsource the very cognitive work that builds understanding. The performance–learning gap shows generative AI easily boosts immediate performance while bypassing the deep processing required for durable learning. Field evidence is direct:

- A causal RCT (~1,000 high-school math students) found unguarded AI assistance raised practice performance **+48%** but reduced unassisted, closed-book exam scores **−17%** — the students who never had AI access outperformed those who did. A guardrailed hint-not-answer tutor eliminated the harm.
- Population-scale behavioral data (3.2M ALEKS interactions) found study time on AI-susceptible problems fell **−26.9%** after ChatGPT's release, with a **−25% decline in odds of correct proctored retention items** — an effect that vanished under proctoring, pinning it on off-platform AI use.

Online learning is particularly vulnerable: the medium already distances learners from immediate accountability, and self-paced, screen-based work invites the "ask for the answer" shortcut that Cognitive Offloading research identifies as the core harm mechanism. The response is not to ban AI but to apply Guardrails — hint-not-answer scaffolding, knowledge grounding, and human oversight — so that AI augments rather than replaces learner cognitive work.

Other challenges

- **Over-eager AI facilitation.** LLM facilitators are excessively eager to intervene in online discussions, which can irritate participants and derail good conversation; human caution is the better model (Tsirmpas et al.).
- **Motivation erosion.** The perceived availability of an effortless AI shortcut reduces autonomous Motivation and persistence, compounding learning harm.
- **Equity and the digital divide.** Access to reliable devices, connectivity, and high-quality AI varies; online learning with AI can widen rather than narrow Equity gaps (Digital Divide).
- **Data privacy and trust.** Online platforms collect rich learner data; AI systems raise transparency and privacy concerns (Privacy), especially for adults balancing work and study.
- **Organizational readiness.** The demise of KhanMigo — learners not actually engaging with the chatbot, with limited evidence of gains — cautions that technical capability must be matched with AI Governance and organizational readiness.

Assessment validity when a submission can be produced without the learner

If invigilation is unfeasible and an agent can complete the work, the response the knowledge base favors is to change what counts as evidence rather than to police harder. Four design responses recur across the recent literature.

Pair the vulnerable task with a twin. Roe, Perkins and Giray (2026) keep the pedagogically valuable but AI-vulnerable assessment — the take-home essay or case analysis — and add a second, less vulnerable task that assesses the *same* learning outcomes, scheduled closely enough for cross-verification and marked

interdependently. Their mapping runs across Messick's six strands of validity evidence, and the design process is three steps: identify the vulnerabilities, align outcomes and choose the twin, then develop marking that connects the two. A short case variation, an explanation of one key decision, or a brief oral defense can serve as the twin.

Target ownership rather than authorship. Ebrahimzadeh, Shibani and Buckingham Shum argue that blended human–AI authorship undermines several forms of validity evidence, and propose **coauthorship integrity** as validity evidence in its own right: violated when a student submits AI-generated content they do not understand. To check understanding at scale they report an **AI Viva**, a conversational agent that runs a hybrid viva voce with comprehension questions of controllable type and complexity, validated by expert educators and assessment specialists. For online courses this is a genuinely scalable form of verification, and it produces evidence about comprehension rather than about who was in the room.

Move the oral exam online. Pentland, Lowenthal and Krier (2026) deliver prompts just in time and have students record brief, time-limited webcam responses they cannot revisit, graded against embedded rubrics with transcripts generated automatically. Across two studies — an intermediate accounting pilot and a data analytics course — students scored higher on these assessments than on in-person multiple-choice exams (significant in the second study, a positive trend in the first), with moderate cross-format correlations supporting convergent validity; students reported preparing differently and using more active study strategies. The format addresses the async problem directly: the thinking is performed live at a time of the student's choosing, at administrative cost that does not scale with cohort size.

Sequence the work so the reasoning is committed first. Brcic and Frljic (2026) frame the design question as **placement** rather than permission, and the causal evidence they assemble shows the outcome flipping on placement alone — the same unguarded helper that left high-school students about **17% worse** on an unaided exam did no harm once rebuilt to withhold answers, while a well-engineered tutor roughly **doubled** learning. Their diagnostic is the one to keep: *if letting AI in makes the task feel effortless, it is in the wrong place*. Operationally that yields a sequence an online course can write into the assignment — think, commit, use AI, critique, revise, explain — where the commitment step is what makes the rest assessable, because an artifact produced from scratch has no revision history to interrogate. Underneath sits a state this knowledge base names metacognitively discordant completion: correct, complete work submitted by a student who knows the understanding never arrived, which in an asynchronous course is indistinguishable from success unless the design asks for something more.

Whatever combination an instructor chooses, one constraint should shape it. Online study is frequently the only accessible option — students choose it because of employment, caregiving responsibilities, disabilities or geography — so verification has to be **small and proportionate**: a short recorded explanation, a personalized application, a response to an instructor-selected question, an annotated decision trail, a low-stakes individual check. Detection carries its own equity costs here, since tools that flag non-native writers disproportionately generate false positives (AI Detection, Digital Divide).

Recommended pedagogical strategies for online teaching and learning

- **Active and interactive learning.** Prefer strategies that keep students doing and thinking rather than passively receiving — Active Learning, interactive exercises, and Socratic dialogue. AI that

prompts reasoning (rather than supplying answers) preserves the productive struggle and Desirable Difficulties that build durable learning.

- **Scaffolded, guided support.** Use Scaffolding that fades as learners progress, and design Self-Regulated Learning supports so learners direct their own learning rather than depending on the tool.
- **Collaborative and discussion-based learning.** Structure online discussions and group work deliberately; use Collaborative Learning activities and, when AI participates, calibrate its facilitation and its role as a peer.
- **Role design is the intervention, not the tool.** In an online graduate course, assigning rotating moderator, analyst, and arguer roles to Learners and a generative AI partner raised group mind-map content scores from M = 3.65 to M = 4.59 on a 1-5 SOLO scale ($z = 3.771$, $p < 0.001$), while node and branch counts stayed statistically flat (Cheng et al. (2026)).
- **Authentic, process-revealing assessment.** Shift toward Authentic Assessment and assessments that capture process — drafts, oral defenses, self-explanation, reflective portfolios — which are more AI-resistant and reveal genuine understanding.
- **Personalized and adaptive paths.** Use AI-enabled personalization and adaptive activities to tailor pacing and difficulty, while keeping personalization deep (task sequencing, difficulty calibration) rather than merely surface-level (custom examples).
- **Social presence and community-building.** Deliberately cultivate social presence and community — the core of the Community of Inquiry framework — through companion AI, synchronous check-ins, and peer interaction, since online isolation is a key barrier to engagement and belonging. In the AI era this means curating the three presences (cognitive, social, teaching) even as machine-generated discourse complicates who is "present" (see Community of Inquiry).
- **Blended Design Thinking.** For hybrid formats, apply Learning Design principles to decide what is best done synchronously vs. asynchronously and online vs. in person, and how AI supports each.
- **Name the AI's role, and check the student still has one.** "Students may use AI" is too broad to design against. Roles carry different pedagogical consequences — a study of generative AI in marketing education distinguishes **tutor, teammate and tool** and shows each shaping teaching, social and cognitive presence differently (GenAI in Marketing Education) — so an online activity should be able to state its division of labor: the AI's job here is X, the student's job is Y. If Y contains little thinking, the activity needs redesigning rather than a stricter policy.
- **Sequence discussion as position, challenge, reconsideration.** The conventional asynchronous formula of posting once and replying twice is both superficial and agent-completable. A stronger structure asks students to commit to an interpretation, meet a counterexample or critique, then explain how their reasoning moved; what is graded is the movement between ideas rather than the post count. This also relocates teaching presence: replying mechanically to dozens of posts is the least valuable form of it, while synthesizing patterns across the discussion — the assumptions that keep recurring, the disagreements worth naming, the counterexample that unsettles a consensus — is the part no agent in this literature performs.

- **Human-in-the-loop governance.** Keep educators and instructors in the loop over AI tools, grounded in pedagogical content knowledge, so pedagogical intent — not the tool's default — drives design.

Implications for online instructors and instructional designers

- **Guardrail the AI, don't just supply it.** Use hint-not-answer Scaffolding that keeps learner cognitive work in the loop; the guardrailed-tutor RCT shows this eliminates the exam penalty that unguarded access causes. See the Guardrails concept for the full design layer (prompting, RAG (Retrieval-Augmented Generation) grounding, training, QA).
- **Design AI-resistant and proctored/unassisted assessments.** Because online grading often can't distinguish assisted from independent work, include closed-book, proctored, or process-revealing assessments to surface and discourage misuse (AI Misuse and Learning Harm).
- **Teach AI literacy explicitly.** Help students recognize reliance patterns and calibrate trust (AI Literacy); build self-regulation and Metacognition to counter offloading.
- **Embed AI in the learning environment, not as an external bolt-on.** Purpose-built, contextually-tuned assistants embedded in the course (like AIDA) outperform generic external chatbots and increase acceptance.
- **Calibrate AI facilitation toward human caution.** When using AI to moderate discussions, prefer settings that intervene sparingly (Tsirmpas et al.).
- **Design for adult life constraints.** For adult and distance learners, prioritize mobile access, offline capability, and asynchronous availability (AI-ALOE guidelines).
- **Compressed formats need redesign, not compression.** Six-week asynchronous graduate courses for working teachers are an institutional constraint requiring purposeful redesign rather than a fifteen-week course compressed, and AI dialogue carries instructional presence into the late hours an instructor cannot staff Packard et al. (2026).
- **Co-design with students and staff, and build governance.** Participatory development, senior sponsorship, cross-unit collaboration, and robust AI Governance are enabling factors for responsible GenAI adoption.
- **Assume an agent will attempt every unproctored activity, and design from that assumption.** The three-question test is quick and exposes weak activities: could an AI system complete this without the student understanding the material; what cognitive activity is supposed to produce the learning; what evidence will show the student performed it. When the first answer is yes and the other two are hard to answer, the problem is the learning design rather than the AI policy.
- **Keep verification proportionate to the risk.** Where competence must be certified, prefer a twin task, an asynchronous oral defense or a short comprehension check over blanket monitoring; keep the rest of the course flexible for the learners who depend on that flexibility.
- **Use analytics to support, not replace, teaching.** Leverage Learning Analytics to forecast engagement and target support, but keep human oversight central.

Common Misconceptions

“Online teaching is classroom teaching delivered through a screen.” It is a distinct pedagogical setting, and AI lands differently in it. Self-reported TPACK for AI-integrated science teaching was higher among final-year student teachers at a campus-based university (**64.0%**) than at a distance-education university (**47.4%**), with the weakest domain in both settings being pedagogical. The distance setting compounds an existing preparation gap rather than receiving the same support.

“Adding an AI assistant to a course increases engagement.” Engagement depends on the assistant being purpose-built and in-environment. The Open University’s AIDA assistant raised engagement — doubling usage time in an exploratory trial — and that design condition is the finding: the same capability bolted on as an external tool does not recruit the same behavior. A generic chatbot link in a course shell is not the intervention that was studied.

“AI raises performance, so it raises learning.” In online settings the divergence is the same as in classrooms: an RCT found unguarded AI assistance raised practice performance but *lowered* unassisted exam scores, while a “hint-not-answer” tutor removed the harm. Online courses rely more heavily on asynchronous assessment, so the gap between assisted and unassisted performance is where validity is won or lost.

“Assessment validity is a grading-policy question.” It is a design question created by the medium: when a submission can be produced without the learner being present, validity depends on whether the task produces evidence that the learner did the work. Redesigning the task addresses this; tightening the penalty for misconduct does not.

Connected Concepts

- Pedagogical Patterns — The context that makes sequencing load-bearing, since the system cannot see an attempt
- Assessment Validity — validity of the inference from submitted work to learning
- Agentic AI — autonomous systems that operate tools and platforms, including an LMS
- Community of Inquiry — Community of Inquiry
- Pedagogies and Teaching Strategies
- Learning Design
- Active Learning
- Collaborative Learning
- Scaffolding
- Self-Regulated Learning
- Cognitive Offloading
- Academic Integrity
- AI Misuse and Learning Harm
- AI Literacy
- Intelligent Tutoring
- Personalized Learning

- Adaptive Learning
- Student Engagement
- Digital Divide
- AI Governance
- Teaching
- Human-in-the-Loop
- Authentic Assessment
- Guardrails
- AI Detection

Connected Articles

- AI agents can now navigate and complete LMS tasks: A call for pedagogical innovation — Autonomous agents completed unproctored LMS assessments end to end: an assessment-validity problem (Hadjisolomou & El-Haddad 2026)
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins: pairing a GenAI-vulnerable task with a closely scheduled, less vulnerable one on the same outcomes
- Coauthorship integrity: Reconceptualising assessment validity for the age of generative artificial intelligence — Coauthorship integrity as validity evidence, and the AI Viva as scalable verification
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous oral assessments: time-limited unrevised recordings graded against embedded rubrics
- The effortless trap: Productive struggle, AI, and the illusion of learning — The effortless trap: placement of AI rather than permission or prohibition
- Metacognitively discordant completion and the aware pass-through of non-understanding in generative AI learning — Metacognitively discordant completion: correct work submitted without understanding
- Decreasing Digital Distraction in College Students: Associated Online Learning Strategies Identified by Unsupervised Data Mining Approaches — Which self-regulated strategies coincide with low digital distraction (530 students)
- GenAI as a Learning Partner: Supporting Self-Regulated Learning Over Time Without Replacing Effort — SRL as stable aptitude and fluctuating state; metacognition and well-being declining across a term
- When AI Wears Many Hats: The Role of Generative Artificial Intelligence in Marketing Education — AI as tutor, teammate and tool: roles and their effects on presence
- Beyond Detection: How Students Use—and Hide—AI in Online Assessments and What Authentic Tasks Can Do About It — Beyond detection: assessment design for online settings
- Reconceptualizing community of inquiry in the age of generative artificial intelligence — Reconceptualizing Community of Inquiry in the age of generative AI

- Integrating AI in Online Learning in Higher Education: A Literature Review — Integrating AI in online learning in higher education: a four-theme critical literature review
- From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents — From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents
- LearnMate^2: Design and evaluation of an LLM-powered personalized and adaptive support system for online learning — LearnMate²: Personalized and Adaptive Support System for Online Learning
- To facilitate or not to facilitate: Human and LLM facilitator tendencies in online discussions — Human and LLM Facilitator Tendencies in Online Discussions
- ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education — ELEVATE: Human-Centered GenAI Virtual Tutors
- The Path to Conversational AI Tutors: Integrating Tutoring Best Practices and Targeted Technologies to Produce Scalable AI Agents — The Path to Conversational AI Tutors
- New systems of learning for distance learning institutions? A six-study review of implementing AIDA — Implementing AIDA at the Open University
- Guidelines for Designing AI Technologies to Support Adult Learning — Guidelines for Designing AI Technologies to Support Adult Learning
- DeepTutor: Towards Agentic Personalized Tutoring — DeepTutor: Toward Agentic Personalized Tutoring
- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education
- Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos — Students prefer personalized AI-generated videos over non-personalized human-recorded ones (Tomlinson et al. 2026)
- Enhancing peer exposure and creating opportunities for bridging social capital through an AI-generated summary-driven learning design in online discussion forums — AI-Generated Summary-Driven Learning Design in Online Discussion Forums
- AI training and science student teachers' TPACK in campus-based and distance education: a comparative study — Campus-based student teachers reported higher TPACK for AI-integrated science teaching than distance education peers (64.0% versus 47.4%)
- Enhancing Human-Generative Artificial Intelligence Online Collaboration Outcomes: The Pivotal Function of Symbiotic Role Design — Role design is the intervention, not the tool
- Teaching with AI, Not Against It: A Thinking Partner Framework for Working Adult Learners in Compressed Online Formats — Six-week asynchronous graduate courses for working teachers: redesign the format rather than compress it

Connected FAQs

- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Video in Education

> **Video in education** — the use of video as a medium for teaching and learning, and how generative AI is reshaping it: AI-generated and AI-personalized instructional videos, AI avatars and presenters, adaptive video generation, video-based learning analytics and attention/engagement sensing, and AI support for lecture-video consumption. The knowledge base treats video as both an established online-learning medium and a rapidly evolving site of AI innovation, spanning online, hybrid, and in-person teaching.

Questions to Consider

- Educational video has long been a "one-size-fits-all" resource — identical content for every learner. Generative AI now makes per-learner video feasible, and research suggests students value that personalization highly. What does personalization add beyond relevance — and what might it cost?
- Students often say they still value a human instructor's presence and authenticity in video. Yet in head-to-head preference, personalized AI video can beat generic human-recorded lectures. What tradeoffs are learners actually making, and how durable are they?
- AI avatars cloned from instructors can generate video at scale — but they can also trigger "uncanny valley" discomfort and ethical objections (environmental impact, labor, academic integrity). When is an AI presenter acceptable, and when does it cross a line that no technical fix addresses?
- Much video research relies on students' preferences and self-report. How well do stated preferences predict actual learning outcomes — and when might a video that "feels good" teach less well than one that does not?
- Video analytics can detect attention, engagement, and dropout points. What are the pedagogical and Privacy implications of instrumenting video learning this closely?

Introduction

Video is a cornerstone of contemporary education — especially online and hybrid learning — prized for its flexibility, scalability, and consistency. Yet conventional instructional video is produced as a one-size-fits-all artifact, presenting identical content to every learner regardless of their interests, background, or prior knowledge. Generative AI is shifting video from a static broadcast medium to a dynamic, individually tailored one, and is also generating new questions about presence, Trust, Privacy, and measurement.

How the knowledge base's research clusters

- **AI-generated and personalized instructional video.** A central thread asks whether students accept AI-produced video and how it compares to human-recorded content. Student surveys in computing education probe perceptions and preferences for AI-generated instructional video. In a

large field deployment, Tomlinson et al. (2026) found that students preferred AI-generated *personalized* videos over non-personalized human-recorded lectures — a preference in which the personalization effect outweighed the value placed on a human presenter. Dual gatekeeping research shows how instructor oversight ("gatekeeping") across two stages of AI video production yields more pedagogically grounded output, connecting to human-in-the-loop design.

- **Adaptive and structured video generation.** CourseBlueprint offers a structured pipeline that generates adaptive pedagogical video grounded in course corpora, showing that explicit pedagogical structure — not just AI fluency — drives effective AI video. Bespoke applies the same logic at whole-lecture scale: from 31 graduate lectures it generated 209 videos for healthcare, finance, energy, and a generic audience, and 25 domain-matched experts rating 92 of them placed 87% at or above the midpoint written as "a standard MOOC lecture's quality" (mean 3.42 out of 5), at about $0.22 in API cost per minute — with voice, slide timing, and layout the recurring defects.
- **A learning loop beats a better render.** Ma et al. (2026) plan each video as a storyboard of objectives, prerequisite activation, worked examples and diagnostic probes, paired with a quiz avoiding the video's examples and a remediation for each wrong option; 96.9% of 32 instructors judged the loop more effective than a standalone video.
- **Video learning analytics and attention.** Instrumenting video reveals how learners engage. Engagement assessment in video learning and SAVVY visualize student attention during video-based learning, supporting learning analytics, self-regulation, and early-warning for disengagement. Segmentation work (e.g., temporal video segmentation) tailors video to individual differences.
- **A neural read-out of video encoding.** EEG reconstructions of viewed video frames were more semantically similar for correctly answered questions ($M = 71.43$) than incorrect ones ($M = 62.30$, $p < .001$), and systematic temporal misalignment — reconstructions resembling earlier frames — was quantifiable as a dispersion measure associated with performance (Su et al. (2026)).
- **Avatars and presence.** AI avatars — virtual presenters and pedagogical agents — raise questions about identity, social presence, and trust. Avatar identity and epistemic trust examines how a presenter's apparent identity shapes learners' trust, while AI avatars in training extend the pattern to professional practice.
- **In-video scaffolding comments — and what AI still gets wrong.** Wang, Du and Jin (2026) generate *i-Comments*, Scaffolding messages rendered inside the video frame and synchronized to the content, by computing frame-level entropy and inserting support only in low-information intervals. Benchmarked against 120 comments from experienced instructors, ChatGPT's 1,000 comments were denser, far less structurally varied (POS 3-gram diversity 5.5–6.2% vs. 25.1–38.5%), harder to read on every readability index, and less topically aligned (emotional-support BERTScore 0.317 vs. 0.574); 40 learners rated the human comments significantly higher on timing and helpfulness, although a newer model narrowed that gap. The argument is a design argument as much as an automation one: support embedded in the media avoids the attention and cognitive cost of pausing to query a separate chatbot (feedback quality, emotional support).

- **AI support for lecture-video consumption.** Beyond generation, AI helps learners and teachers work with existing video: bilingual LLM lecture companions support self-regulated learning with recorded lectures, and transcription pipelines convert lecture video into accessible text.
- **Region-level zoom is the layer narrated slides were missing.** A within-subjects study with 24 viewers found automatic zoom plus synchronized highlights cut NASA-TLX workload from 5.74 to 4.53 (d = 0.84) and raised immediate comprehension (d = 0.46), though the 24-hour advantage missed significance (p = .054) (Lian et al., 2026).

Personalization versus human presence

A recurring tension is whether the value of personalization can outweigh the value of a visible human instructor. Tomlinson et al. (2026) frame personalization and social presence as *partially substitutable signals of instructional care*: human delivery enhances affective experience and authenticity, while personalization enhances relevance — and students are willing to trade one for the other. Their large-course ranking data (88.4% preferred some personalized video; only 73.8% preferred human-recorded) suggest personalization is now often the more influential factor, pointing toward a complementary model where human instructors supply expertise and social connection while AI extends their reach with individually tailored media.

Design, ethics, and measurement

Producing effective AI video requires pedagogical structure and human oversight, and it raises distinct concerns: AI presenters may evoke discomfort or distrust (the "uncanny valley"); generative video risks factual inaccuracy that learners may not catch; scaling personalization requires collecting or inferring learner attributes, with attendant Privacy, bias, and AI Governance concerns; and a subset of learners object to AI-generated instruction on principled grounds (environmental impact, labor, automation, academic integrity). Measurement is likewise in flux — much evidence rests on stated preference and perceived value rather than objective learning outcomes, so preference data must be read alongside (often forthcoming) outcome data.

Common Misconceptions

"Students preferred the AI video, so it teaches better." Preference and learning are separate measures, and much of this literature rests on the first. In a large online course (493 respondents), students ranked AI-generated personalized videos above non-personalized human-recorded lectures (mean rank 2.26 versus 2.69) and 88.4% ranked some personalized video first — a clean preference result. The page's own caution applies: evidence here rests substantially on stated preference and perceived value rather than objective learning outcomes, so preference data has to be read alongside outcome data, not in place of it. A video that feels better tailored is not thereby teaching more.

"AI-generated scaffolding comments can substitute for an instructor's." They differ in a way that matters for instruction. Benchmarked against 120 comments from experienced instructors, ChatGPT's 1,000 comments were *denser* but far less structurally varied (POS 3-gram diversity 5.5–6.2%), and 40 learners rated the human comments significantly higher on timing and helpfulness — though a newer model

narrowed that gap. Volume and density are not the same as the varied, paced commentary a good instructor produces, and the narrowing gap is a trend to track rather than a settled equivalence.

“Cloning an instructor into an avatar scales human presence.” It scales production and changes what is being delivered. AI avatars cloned from instructors can generate video at scale, but they also trigger uncanny-valley discomfort and raise ethical objections spanning environmental impact, labor and integrity. The presence being scaled is a simulation of the instructor, and the costs attach to the simulation.

“Generating many variants of one lecture is personalization.” Variant count is a production figure, not an instructional one. Bespoke generated 209 videos from 31 graduate lectures across healthcare, finance, energy and a generic audience, which demonstrates the pipeline’s capacity; whether any variant matched a given learner’s needs is a separate question that the generation count cannot answer.

Implications for Practice

For instructors

- Ask whether the evidence behind a personalized-video product is preference or achievement. The strongest numbers in this literature are ranks and ratings, and the two kinds of evidence point in different directions often enough to keep separate.
- Keep human commentary for the moments that need pacing and selectivity. The comment study found human comments stronger on timing and helpfulness, so reserve instructor voice for the frames where timing carries meaning.
- Treat avatars as a production decision with costs (labor, environmental, integrity) rather than as a neutral efficiency win.

For developers

- Instrument comprehension, not only watch-through and satisfaction. If you ship ten variants, report which ones improved unassisted understanding.
- Match comment *structure* to the instructor benchmark in your evaluation, not just semantic relevance or density — the diversity gap is where generated commentary visibly fails.
- Expose the generative status of avatars and personalized variants; presenting synthetic presence as instructor presence is an integrity question before it is a design question.

For researchers

- Report preference and outcome measures together, and state plainly when a study has only the first.
- Report temporal alignment explicitly, given that misalignment between video content and cognitive processing shows up in the neural data.

Connected Concepts

- Online Teaching and Learning — video as a core medium of online and hybrid instruction
- Generative AI — the engine of AI-generated and personalized video
- Personalized Learning — personalization as the driver of AI video’s appeal

- Adaptive Learning — adaptive video generation and pacing
- Multimodal AI — video combining visual, audio, and textual modalities
- Learning Analytics — analytics on video engagement and attention
- Student Engagement — the engagement that video personalization aims to boost
- Pedagogical Agent — AI avatars/presenters as virtual pedagogical agents
- Large Language Models (LLMs) — large language models underlying script and video generation
- Trust — learner trust in AI presenters and content

Connected Articles

- Bespoke: Generating MOOC-Quality Industry-Personalized Lecture Videos at Scale — Bespoke: generating MOOC-quality industry-personalized lecture videos at scale (Puech et al. 2026)
- Assessing ChatGPT-Generated Comments for Video-Based Learning Content to Enhance Knowledge and Emotional Support Based on Scaffolding Theory — ChatGPT-generated in-video comments: entropy timing, quality gaps vs. human comments (Wang, Du & Jin 2026)
- Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos — Students prefer personalized AI-generated videos over non-personalized human-recorded ones (Tomlinson et al. 2026)
- Student Perceptions and Preferences Regarding AI-Generated Instructional Videos in Computing Education — Student perceptions/preferences of AI-generated instructional video in computing education
- When Saying No Makes Better Videos: Designing Dual Gatekeeping for Pedagogically Grounded AI Content Creation — Dual gatekeeping for pedagogically grounded AI video creation
- CourseBlueprint: A Structured Pipeline for Adaptive Pedagogical Video Generation Grounded in Course Corpora — CourseBlueprint: adaptive pedagogical video generation
- EduGage: Methods and Dataset for Sensor-Based Momentary Assessment of Engagement in Self-Guided Video Learning — Engagement assessment in video learning
- SAVVY: Student attention visualization for video-based learning analysis — Student attention visualization for video-based learning
- Face value: How avatar identity shapes epistemic trust in AI-mediated learning — How avatar identity shapes epistemic trust in AI-mediated learning
- A bilingual, LLM-mediated lecture companion for self-regulated learning: Architecture, theoretical framework, comparative and usability evaluation, and a pre-registered outcomes protocol — Bilingual LLM lecture companions for self-regulated learning
- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education — Temporal video segmentation for individual differences
- Toward Accessible Psychotherapy Training Using AI-Driven Interactive Patient Avatars — AI avatars in psychotherapy training
- Using Gemini and LuaLaTeX to transcribe physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs — Transcribing physics lecture video into accessible text

- From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning — From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning
- Look Over There! Dynamic Visual Guidance for AI-Narrated Slides — Look Over There! Dynamic Visual Guidance for AI-Narrated Slides

Learning theories and processes

Learning Theories

> **Learning Theories** — the family of frameworks that explain how learning happens, and the umbrella concept for the knowledge base's theory-related ideas. In AI in education, learning theories shape both how AI systems are designed (the pedagogy they embody) and how the field interprets whether AI "works": the same tool can be a scaffold under Constructivism assumptions, a reinforcement engine under Behaviorism, or a cognitive-load hazard under Cognitive Load Theory.

Questions to Consider

- Think about an AI tutor or adaptive system you have used or seen. What assumptions did it make about how people learn — did it reward right answers (behaviorism), build understanding (constructivism), or manage mental effort (cognitive load)? Did its makers ever state those assumptions?
- The page describes a recurring gap: discourse espouses constructivism while AI implementations default to drill-and-feedback mechanics. Where have you seen a tool claim to support deep learning but actually just reinforce surface responses?
- The same AI tool can look like success under one theory and failure under another — inflated homework scores read as learning under behaviorism but as a failure to build durable understanding under constructivism. Which lens is fairer for judging whether students actually learned?
- Because every AI tutor embeds a theory whether its designers say so or not, 'does it work?' may be the wrong question. What is the better question to ask about an educational AI, given the theories it could embody?
- Generative AI is prompting educators to consider new theories — like learning as iterative co-construction between humans and AI, or AI as a cognitive partner across the lifespan. Does the rise of AI genuinely require new learning theories, or do existing ones still suffice?
- Learning-gains measurement is itself 'theory-laden': an instrument built on one theory may not capture the gains another predicts. How might two researchers with different theoretical commitments look at the same data and reach opposite conclusions about whether an AI tool worked?

Introduction

This is the umbrella concept for the knowledge base's learning-theory strand. Learning theories sit at the heart of AI in education because every AI tutor, adaptive system, and feedback tool embeds assumptions about how people learn — whether the designers state them or not. The knowledge base documents these theories individually and treats them as the conceptual lens through which AI's design and effects are evaluated. The research field that tests those frameworks is a separate page: the learning sciences study learning empirically — experiments, classroom trials and design-based research — and treat a theory as

something to be confirmed or falsified, whereas this page collects the frameworks themselves. The two phrases are kept distinct in this knowledge base, the singular “learning science” naming this theory strand.

The learning-theory landscape

The knowledge base documents several families of learning theory, each with its own concepts:

- **Classical learning theories.** Behaviorism (learning as observable behavioral change through reinforcement and drill-and-practice) and constructivism (learning as active knowledge construction) are the two poles that recur most often in AI research. The field frequently exhibits a “constructivism in name, behaviorism in practice” gap, where discourse espouses construction but AI implementations default to drill-and-feedback mechanics.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness) cognitivism is the third classical pole — learning as a change in internal mental representations — and the theory most responsible for AIED’s signature contributions (Knowledge Tracing, Cognitive Diagnosis, Learner Modeling and Adaptive Instruction, Intelligent Tutoring).
- **Sociocultural and developmental theories.** Sociocultural Learning holds that learning and development arise through social participation and are mediated by cultural tools and more knowledgeable others — spanning the Zone of Proximal Development, Scaffolding, apprenticeship, communities of practice, and distributed cognition. In the AI age, generative AI is increasingly framed as a *mediational agent* that both mediates activity and generates contingent contributions to interaction.(Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory)
- **Cognition and cognitive architecture.** Cognitive psychology / cognitivism is the umbrella for this family: Cognitive Load Theory (how working-memory limits shape instruction), Dual-Process Theory (fast intuitive vs. slow deliberative processing), and Metacognition (monitoring and regulating one’s own learning) explain the *internal* mechanisms that AI tools engage or bypass.
- **Motivation and self-direction.** Self-Determination Theory (autonomy, competence, relatedness), Self-Efficacy (confidence in one’s capability), Self-Regulated Learning (goal-setting, monitoring, and adjustment), and Motivation explain why learners engage with AI the way they do.
- **Learning context and activity.** Experiential Learning, Active Learning, Project-Based Learning, Collaborative Learning, Transfer of Learning, Desirable Difficulties, and Embodied Learning describe the kinds of activity and context that produce durable learning.

Learning theories and learning gains

Learning theories are ultimately evaluated by their outcomes, and the knowledge base’s Learning Gains concept is where theory meets evidence. Each theory makes a different prediction about what *counts* as learning and how to measure it: behaviorism predicts observable performance gains on drill-and-feedback tasks; constructivism predicts deeper understanding that transfers to novel problems; sociocultural theory predicts gains in participation and mediated Problem Solving; and cognitive-load theory predicts gains only when instruction respects working-memory limits. Measurement choices, then, decide which theory’s prediction an evaluation can confirm. In the AI era, the sharp divergence between AI-assisted performance

and unassisted learning gains (see Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build, The generative AI learning penalty: Evidence from Chinese secondary education) can be read through this lens: a behaviorist reading sees inflated homework scores as success, while a constructivist reading, focused on durable understanding, sees the same evidence as a failure to learn.

The pooled evidence is positive, and it measures a narrower construct than the theories do. A PRISMA meta-analysis of 53 studies puts GenAI assistance at g = 0.40 on academic achievement, 0.72 on higher-order thinking, 0.76 on writing and 0.81 on motivation, with GenAI feedback the largest mechanism at g = 1.27 (Dong (2026)). Those are gains on the instruments the included studies chose, so they settle a behaviorist or cognitivist reading of "it works" and leave the constructivist prediction about durable, transferable understanding untested. The country subgroups also diverged, from China's g = 0.71 to Turkey's nonsignificant g = 0.01, so the pooled estimate is an average to test locally rather than a property of the tool.

Why learning theories matter for AI in education

Learning theories matter for three reasons:

- **They predict AI's effects.** Whether an AI tool improves or harms learning depends on which mechanism it activates. A tutor that gives away answers harms under a constructivist lens (it bypasses construction), is neutral under behaviorism (it reinforces), and raises cognitive-load concerns (it offloads rather than builds). The knowledge base's Cognitive Offloading and Over-Reliance concepts capture the risk side of this.
- **They expose the theory-practice gap.** Empirical work repeatedly finds that AI implementations embody different theories than the discourse claims — most notably constructivist language paired with behaviorist drill-and-practice mechanics.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness) Evaluating AI therefore requires asking *which* theory a system actually embodies, not just whether it "works."
- **They are being actively rethought.** Generative AI is prompting educators to revisit whether the classical theories suffice. Generativism proposes that learning in the AI age increasingly occurs through iterative co-construction between human learners and AI systems, extending rather than replacing the classical four (behaviorism, cognitivism, constructivism, connectivism). (Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence)

New theoretical directions from recent AIED work

Recent theoretical work extends the classical strand in several directions, each re-centering the human–AI relationship rather than treating AI as a neutral tool:

- **Human–AI co-AI Regulation in Education.** A developmental framework positions AI not as an external instrument but as a **cognitive partner** that co-regulates thinking, learning, and self-control across the lifespan.(Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning) Drawing on executive function, Metacognition, distributed cognition, and sociocultural development, it casts AI in four roles —

scaffold, metacognitive support, external memory / Cognitive Offloading system, and decision partner — with the framework most relevant from middle childhood onward.

- **Ensemble Cognition.** A philosophical framework reconceptualizes thinking as emerging from dynamic interactions between human and artificial agents rather than residing solely in individual minds.(Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments) It challenges the "consciousness paradigm" (the autonomy, consciousness, and stability assumptions) and articulates five features — distributed agency, dynamic centrality, cognitive orchestration, multi-representational integration, and context-sensitive switching — while distinguishing AI's **functional agency** from moral responsibility.
- **Self-Directed Growth / A2PL.** An extension of self-directed learning integrates Generative AI with learning analytics to cultivate **Self-Directed Growth**, operationalized through the Aspire to Potentials for Learners (A2PL) model.(Fostering Self-Directed Growth with Generative AI: Toward a New Learning Analytics Framework) It reconfigures learner aspirations (humanistic), complex thinking (constructivist), and Self-Assessment (pragmatic) into a single competency, positioning GAI as a non-prescriptive collaborative scaffold rather than a content provider.
- **Deceptive overgeneralization.** An, McLaren, and Stamper (2026) extend the ACT-R / Knowledge-Learning-Instruction tradition by theorizing when observed correctness masks incomplete conditional understanding: learners compile an overgeneralized production that omits an application constraint yet still performs correctly — a failure mode that adaptive mastery systems, and even traditional instruction, can miss unless they test *when to withhold* an action.
- **Executable KLI theory.** Rachatasumrit, Koedinger & Carvalho (2025) ground the Knowledge-Learning-Instruction framework in an executable computational model (the Apprentice Learner framework with an ACT-R-style memory mechanism) that reproduces a cross-over interaction in human data: pure practice aids verbatim fact memory (by delaying forgetting) while example-integrated practice aids generalizable skill induction. Because KLI ties constant (fact) knowledge to memory processes and variable (skill) knowledge to induction, the result is a predicted content–treatment interaction rather than a contradiction between testing and worked-example recommendations — and the model's success only when a memory mechanism is present demonstrates that practice and examples play distinct, complementary roles.
- **Embodiment as an ontological challenge to AI's paradigm.** Videla, Penny and Ross (2026) argue an ontological divide separates embodied, enactive cognition from the representational idiom AI embodies, so AI should be decentered as the epistemic center rather than treated as a neutral tool.

How the knowledge base organizes this strand

Rather than treating learning theories as abstract philosophy, the knowledge base grounds each in the AI-in-education research that uses it. The Constructivism and Behaviorism pages document how AI designs embody (or betray) each theory; Cognitive Load Theory, Self-Regulated Learning, Metacognition, and Transfer of Learning connect theory to specific AI mechanisms and outcomes. This mirrors how the knowledge base treats other umbrella domains like Feedback and Assessment — a coherent system of interacting concepts rather than isolated pages.

Learning theories and “education about AI”

Learning theories also appear as content in AI literacy curricula: learners study behaviorism, cognitivism, constructivism, and connectivism to understand the pedagogical assumptions behind the tools they use. (Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence) Teaching this strand gives students (and educators) the vocabulary to critique why an AI product is built the way it is — and whether its mechanics serve the learning goal at hand.

- **The mediational agent.** Warschauer, Tate, and Ritchie (2026) argue generative AI breaks the sociocultural distinction between mediational means and social interaction, proposing the *mediational agent* — a system that both mediates action and generates contingent, non-accountable contributions, occupying a hybrid space between a tool and a social partner. This yields five human-first habits of participation (primacy of human cognition, purposeful engagement, supervisory agency, epistemic vigilance, reflective self-regulation).(Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory)

Theories proposed for the AI era

Alongside the classical families, the knowledge base documents theories written specifically for learning with AI systems, and these carry the design implications that the older theories leave open. Agentivism (Yan and Gašević 2026) is a mid-range example: it defines learning as durable growth in human capability rather than successful task completion, names four mechanisms (delegated agency, epistemic monitoring and verification, reconstructive internalization, and transfer under reduced support), and states six testable propositions, among them that AI support preserving learner responsibility for problem framing, criteria setting and justification produces stronger learning than support that delivers answers.

Elsayed (2026)’s **Pedagogical Symbiosis** makes a stronger ontological claim: the learner is a *Post-Human* entity whose cognition is hybrid rather than tool-assisted, organized by four principles: cognitive offloading and augmentation, epistemic co-construction, metacognitive symbiosis, and dynamic identity formation; operationalized as a Symbiotic Portfolio rubric and a “Cognitive Choreographer” teacher role; it is explicitly untested.

Common Misconceptions

“One of the learning theories is the correct one, so theory choice is a matter of taste.” The theories make different claims about what counts as evidence, so the same data can support opposite conclusions. The clearest instance: inflated homework scores read as **learning under behaviorism** and as **a failure to build durable understanding under constructivism**. Theory choice therefore determines whether an intervention succeeded, which makes it a measurement decision rather than a stylistic preference.

“A tool that supports deep learning will look like deep learning under any framework.” It will look like success under one and failure under another, as above. That is why the field’s outcome measures need to be justified against a stated theory rather than borrowed as if neutral.

“More theories mean a better-understood field.” Accumulation without adjudication is the opposite of progress. Theories proposed for the AI era multiply faster than they are tested, and the sign of maturity is

competing predictions being resolved — which requires designs that can distinguish them, not catalogues that accommodate them.

“Education about AI is the same as AI in education, theoretically speaking.” They draw on different strands: one asks how learners come to understand AI as a subject, the other how AI changes how learning happens. Conflating them produces literature reviews that mix two distinct evidence bases and report a coherent picture of neither.

Implications for Practice

For instructors

- Choose theory by what you need it to do: explain how learning happens, describe the learner’s state, or explain why a practice spreads. Applying the wrong layer measures the right variable against the wrong prediction.
- State the outcome measure’s theory commitment explicitly, since inflated homework scores read as success under behaviorism and as failure under constructivism from identical data.
- When a framework cannot predict a difference between configurations, it cannot be tested in your setting and will not help you decide.

For developers

- Publish the theory your system embodies and the prediction that would falsify it; “grounded in constructivism” without a falsifiable difference is a claim with no content.

For researchers

- Design for adjudication between theories rather than accumulation of frameworks. Maturity shows up as competing predictions resolved, not as vocabulary growth.

Connected Concepts

- Behaviorism
- Cognitive Psychology
- Constructivism
- Metacognition
- Distributed Cognition
- Self-Regulated Learning
- Self-Determination Theory
- Self-Efficacy
- Motivation
- Sociocultural Learning
- Scaffolding
- Transfer of Learning
- Learning Gains
- Desirable Difficulties

- Active Learning
- Experiential Learning
- Collaborative Learning
- Embodied Learning
- Cognitive Offloading
- Learning Design
- Learning Sciences
- Philosophy of AI in Education
- AI in Education
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Agentivism: a learning theory for the age of artificial intelligence — A mid-range learning theory for human-AI interaction, with four mechanisms and six testable propositions (Yan and Gašević 2026)
- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)
- AI-Augmented Inquiry and Regulation in Hybrid Systems: A Control Allocation Architecture for Preserving Epistemic Agency — AI-Augmented Inquiry and Regulation in Hybrid Systems (AIRIS)
- AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education
- Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning — Positions AI as a cognitive partner in human-AI co-regulation; developmental framework across the lifespan
- Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments — Ensemble Cognition: a philosophical framework reconceptualizing thinking as human–AI interaction
- Fostering Self-Directed Growth with Generative AI: Toward a New Learning Analytics Framework — Self-Directed Growth and the A2PL model extending self-directed learning with GenAI
- Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence — Proposes a new learning theory for the generative AI age, revisiting the classical four
- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — Documented the constructivism/behaviorism theory-practice gap in AI for VET

- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches — PRISMA meta-analysis of 53 studies: pooled gains on achievement, thinking, writing and motivation, with feedback the largest mechanism (Dong 2026)
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI
- "If You Can’t Dance Your Program, You Can’t Write It": Challenges and Implications for AI in Education
- Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory — Generative AI as a Mediational Agent
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Language Learning
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content

Connected FAQs

- What Are Notable Gaps in the Research Literature on AI in Education?

Behaviorism

> **Behaviorism** — the learning theory that treats learning as a change in observable behavior produced by stimulus–response associations and reinforcement, rather than by changes in internal mental states. In AI in education, behaviorist principles underlie the drill-and-practice, immediate-feedback, and adaptive-pacing designs that dominate many Intelligent Tutoring and Adaptive Learning systems.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

Questions to Consider

- Behaviorism treats learning as a change in observable behavior driven by stimulus-response and reinforcement — not by internal mental states. Before reading, which educational experiences in your own past were built on reward, repetition, and immediate feedback? What did they succeed at, and what might they have missed?
- A surprising finding on this page is that even where educational discourse espouses rich constructivist theories, actual AI implementations are predominantly behaviorist — drill-and-practice, immediate feedback, adaptive pacing. Why do you think behaviorist mechanics dominate in practice despite being out of fashion in theory?
- The page warns of an educational ‘Turing Trap’ — using AI to replicate rather than augment human instruction. If an AI system optimizes for correct responses and efficiency, what might it quietly optimize away in a learner’s active knowledge construction?
- Behaviorist designs are described as powerful for foundational fluency — vocabulary, arithmetic, code syntax — but inadequate for higher-order, conceptual, or agentic learning on their own. Where in your own learning would a drill-and-practice AI help, and where would it actively hurt?
- The design question posed is not whether behaviorism is ‘right’ but whether a given system’s mechanics serve the learning goal. How would you tell whether an AI tutor’s immediate-feedback, adaptive-pacing design is building genuine transferable understanding or just making observable performance look good?

Introduction

Behaviorism holds that learning is the strengthening or weakening of stimulus–response connections through reinforcement, and that unobservable mental constructs are poor explanations of learning. Its applied legacy in education is **programmed instruction and drill-and-practice**: presenting content in small steps, eliciting a response, and immediately reinforcing correct answers. These principles map cleanly onto the mechanics of Adaptive Learning and Intelligent Tutoring systems, which adapt pacing and difficulty to student responses and provide immediate feedback.

Core ideas

- **Learning is behavioral change.** The target is a measurable change in performance, not an internalized understanding. This makes behaviorist designs natural for observable outcomes like fluency, speed, and accuracy.
- **Reinforcement drives learning.** Correct responses are reinforced and errors corrected, typically with immediate feedback — a design pattern ubiquitous in AI tutoring and drill systems.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)
- **Small steps and scaffolding by pacing.** Instruction is broken into incremental units with feedback at each step, analogous to the way adaptive systems sequence practice.
- **Small steps are a design assumption, and a randomized test of pacing ran against it.** With 199 US college students, feedback sequenced as encouragement, then hints, then the answer produced worse learning than full-solution feedback delivered immediately, though students found the sequenced version more encouraging. The affective gain was canceled by a behavioral pathway, more resubmissions per task, and the net effect was poorer learning (Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning).
- **The learner is largely passive in knowledge construction.** The environment (or system) structures and rewards responses; the learner responds rather than constructs meaning — the direct opposite of Constructivism assumptions.

Behaviorism and AI in education

Behaviorist designs dominate practice

Empirical work repeatedly finds that actual AI implementations are predominantly **behaviorist or cognitively oriented** — emphasizing drill-and-practice, immediate Feedback, and adaptive pacing — even where discourse espouses richer theories. A systematic review of AI in vocational education and training (VET) concluded that constructivist theories are espoused in VET discourse while **behaviorist AI implementations dominate in practice**, and warned of an educational "Turing Trap" in which AI replicates human instruction instead of augmenting it.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

Output equivalence: when behavior no longer certifies learning

Behaviorism defines learning as a change in observable behavior, which makes it the theory most directly embarrassed by generative AI: a learner can now produce an essay, an analysis, or working code indistinguishable from the work of someone who holds the competence the artifact is supposed to certify. The observable behavior is identical while the learning may not have occurred, a failure mode Generativism calls the behavioral equivalence problem.

The gap between performance and learning is not new, but AI widens it. In a field experiment with nearly a thousand high school mathematics students, unrestricted access to a standard assistant raised practice performance by 48 percent while the same students later scored 17 percent below peers who had practiced

without AI on an unassisted exam; a guardrailed tutor version largely removed that deficit (Distinguishing performance gains from learning when using generative AI). Read behaviorally, the lesson is about measurement rather than Pedagogies and Teaching Strategies: a system that optimizes for the output can satisfy the theory's own criterion of learning while failing its purpose.

The tension with constructivism and agency

The behaviorist emphasis on response-and-reinforcement sits in direct tension with Constructivism, Self-Regulated Learning, and Learner Agency goals. When AI systems optimize for correct responses and efficiency, they can under-serve the learner's active knowledge construction, critical reflection, and autonomous decision-making. This is the same gap flagged in the Constructivism "constructivism in name, behaviorism in practice" pattern — and it connects behaviorism to debates about Cognitive Offloading and Over-Reliance when AI does the cognitive work for students.

Where behaviorist designs still fit

Behaviorist principles remain well suited to: - **Foundational skill and fluency building** — where repetition and immediate feedback measurably improve automaticity (e.g., vocabulary, arithmetic, code syntax). - **Adaptive Learning and Intelligent Tutoring** — which rely on step-wise practice, response-driven pacing, and immediate feedback.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness) - **Low-stakes Formative Assessment** and drill in well-defined domains where the target outcome is observable and the path to it is largely procedural.

The design question is not whether behaviorism is "right" but whether a given AI system's behaviorist mechanics serve the *learning goal* — for procedural fluency they can be powerful; for higher-order, conceptual, or agentic learning they are inadequate on their own.

Behaviorism and "education about AI"

Behaviorism also appears in how learners encounter AI as a topic. The theory is one of the four dominant learning theories — behaviorism, cognitivism, constructivism, and connectivism — that generative AI is prompting educators to revisit. (Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence) It is also referenced in cooperative-learning and design contexts as part of the theoretical backdrop learners are taught.(Artificial intelligence assisted design of a novel cooperative learning technique for higher education) Understanding behaviorism helps learners see why many AI tools (and the products built on them) are designed for response-and-reinforcement rather than for deeper construction.

Implications for design and research

1. **Match mechanics to goals.** Behaviorist drill-and-feedback designs suit procedural fluency and observable outcomes; they are a poor fit for conceptual, transferable, or agentic learning goals on their own.

2. **Watch the theory-practice gap.** Researchers should check whether an AI implementation's behaviorist mechanics are serving the espoused learning goal or quietly replicating the "Turing Trap" of AI as an answer machine.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)
3. **Pair behaviorism with richer scaffolds.** Immediate-feedback designs are most effective when embedded in a broader Scaffolding and Self-Regulated Learning context, rather than standing alone as pure drill.
4. **Evaluate observable *and* transferable outcomes.** Behaviorist success criteria (speed, accuracy) should be complemented by measures of whether learning transfers and generalizes, per Transfer of Learning and Research Methods in AIED.

Common Misconceptions

"Behaviourism is obsolete, so its influence on AI in education is a historical footnote." Behaviorist mechanics dominate practice while being out of fashion in theory — reinforcement loops, streak counters, immediate correct/incorrect feedback and mastery gating are the default architecture of most deployed systems. Dismissing the theory while shipping its mechanisms is the field's most widespread inconsistency, and it means the critique is not academic.

"Observable behaviour change certifies learning." That is precisely what AI breaks. Output equivalence is the failure mode: when a model can produce the behavior the system rewards, the observed response no longer certifies the internal change behaviorism inferred it from. A behaviorist design is only as valid as the assumption that the behavior had to be produced by the learner, and generative AI removes that assumption without changing the design.

"Behaviourist designs are simply inferior to constructivist ones." They fit specific targets well — fluency, factual recall, procedural automaticity — where immediate feedback and repetition are genuinely what the task requires. The error is not the mechanism; it is using a mechanism whose validity condition (the learner must produce the response) has silently stopped holding.

"Because the theory is discredited, systems built on it can be judged by outcomes alone." Outcomes are exactly what output equivalence corrupts. A system can report excellent behavioral outcomes while the learning has moved elsewhere, so behaviorist-influenced systems need the unassisted measure more than any other kind.

Connected Concepts

- Constructivism
- Cognitive Psychology — Cognitivism, the third classical pole of learning theory
- Learning Design
- Adaptive Learning
- Intelligent Tutoring
- Feedback
- Formative Assessment

- Self-Regulated Learning
- Learner Agency
- Cognitive Offloading
- Learning Theories

Connected Articles

- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — Behaviorist AI designs dominate VET practice despite espoused constructivism; the “Turing Trap”
- Generativism: Toward a Learning Theory for the Age of Generative Artificial Intelligence — Behaviorism among the four dominant theories generative AI is prompting a rethink of
- Artificial intelligence assisted design of a novel cooperative learning technique for higher education — Behaviorism cited in cooperative-learning design for higher education
- Enabling multi-agent systems as learning designers: applying learning sciences to AI instructional design — Behaviorist persona among collaborative multi-agent design approaches
- Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning — Sequenced hint feedback underperformed immediate full-solution feedback in a 199-participant randomized experiment

Constructivism

> **Constructivism** — the learning theory that knowledge is actively built by the learner through experience, reflection, and interaction, rather than passively received from an instructor or system. In AI in education, constructivism underlies the design commitment that AI tools should support learners' own knowledge construction — prompting, questioning, and Scaffolding — rather than perform the cognitive work for them.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)(Generative AI (GenAI) as a mindtool that supports generative learning (GL))

Questions to Consider

- Have you ever 'learned' something in class only to realize you couldn't actually explain or use it later? What was missing — and what does that tell you about how real understanding forms?
- Constructivism claims knowledge is built, not transmitted. If that's true, what happens when an AI tutor simply supplies the correct answer?
- The phrase 'constructivism in name, Behaviorism in practice' describes AI tools that claim to support active learning but actually run drill-and-practice. Have you seen this gap? How would you detect it in a tool you're evaluating?
- Papert's constructionism says we learn most powerfully by building shareable artifacts. In the AI era, one framework puts it as: 'the AI writes the code, but the student writes the model.' What is a student actually constructing when AI handles the mechanics?
- Some AI tools practice 'generative refusal' — withholding answers and posing questions instead. When would deliberately withholding help be more pedagogically valuable than providing it?
- If knowledge is constructed, then AI literacy isn't learned by hearing lectures about AI — it's learned by using, critiquing, and building with AI. What does that imply about how AI literacy should be taught to you or your students?

Introduction

Constructivism is a family of theories rather than a single doctrine, but its core claim is shared: learners do not absorb meaning; they construct it. Understanding in this view is not the accumulation of transmitted facts but the active organization of experience into mental models. This has direct implications for how AI in education should be designed, evaluated, and taught — and it helps explain both the promise and the risk of generative AI in the classroom.

Mishra et al. contrast Papert's constructionism (Logo, microworlds, debugging-as-learning) with Anderson's cognitive tutors as competing visions of creative agency vs. systematic control in AIED history.

Core ideas

- **Knowledge is constructed, not transmitted.** Learners build understanding by acting on the world, reconciling new information with prior knowledge, and reflecting on the results. An AI tutor that simply supplies correct answers bypasses the constructive activity that produces durable understanding.(Stop Writing for Me: Generative Refusal in AI Tools for Thought)
- **Prior knowledge shapes new learning.** New ideas are interpreted through the learner's existing mental models, so instruction must surface and build on what learners already know — a principle directly relevant to Misconceptions about AI and to AI tutors that adapt to the learner.
- **Social interaction supports construction.** A major strand — social constructivism — holds that meaning is co-constructed through dialogue, collaboration, and culturally situated activity. This connects constructivism to Collaborative Learning and to Socratic Method approaches in which AI prompts rather than dictates.(Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers)
- **Construction is visible in activity.** Learners reveal (and consolidate) their understanding by generating, explaining, and producing — which is why the ICAP framework ranks "constructive" and "interactive" engagement above "active" and "passive" modes.(Systematic review of collaborative learning activities for promoting AI literacy)(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents) A boundary on the theory is that constructivism presumes human-centered epistemic agency, which leaves it short of accounting for an AI that simulates reasoning and co-constructs meaning; the proposed supplement is epistemic co-agency, in which learners treat AI output as contestable and keep epistemic sovereignty over what counts as knowledge (Samuel (2026)).

Constructionism

Constructionism is the branch of constructivism associated with Seymour Papert that adds a specific claim: learning happens most powerfully when learners construct *external, shareable artifacts* — physical or digital objects they design, build, and debug. Where Piagetian constructivism focuses on the internal mental construction of knowledge, constructionism holds that this construction is best supported and made visible through making something tangible (Harel & Papert, 1991). In AIED history, constructionism stands as the "agency" pole of the field's central control-vs-agency tension, set against Anderson's structured cognitive tutors.

- **Logo and microworlds.** Papert co-developed Logo (1967) with its iconic "turtle" — a programming microworld where children explore geometry and other powerful ideas by commanding and debugging a visible agent. Debugging is reframed as a natural, valuable part of learning, not failure.(Control vs. Agency: Exploring the History of AI in Education)
- **Construction over instruction.** Constructionism critiques "instructionism" — the assumption that teaching is the efficient transfer of knowledge — and instead positions learners as autonomous agents who construct understanding through projects and experimentation (Papert, 1980, *Mindstorms*).

- **Lineage into modern edtech.** Logo's emphasis on creative, hands-on construction underpins Game-Based Learning, Project-Based Learning, robotics (LEGO Mindstorms, Scratch, programmable bricks), and the broader maker movement.
- **The constructionist legacy in AI.** Constructionism implies AI tools should serve as **materials to build with** — thinking tools and creative co-constructors that the learner directs — rather than as answer-providing instructors. This is the direct ancestor of the knowledge base's mindtool framing of generative AI and of design commitments that preserve learner agency over the learning process.(Pathways to Learning: Exploring High School Students' Learning of AI-Powered Educational Robotics)
- **Constructionism in the GenAI era: learn by writing the model, not the code.** The arrival of code-generating AI has *renewed* constructionism as a design response rather than weakening it. Gousopoulos's **Code-to-Learn with Generative AI (CtL-GenAI)** framework synthesizes constructionism, cognitive-load theory, Self-Regulated Learning, the ICAP engagement model, productive failure, and sociocultural scaffolding for upper-secondary students building software with AI. Its organizing claim — **"the AI writes the code, but the student writes the model"** — reframes the construction target: when GenAI does the syntactic work of writing code, the learner's construction shifts to building and debugging the *conceptual model* the code expresses. CtL-GenAI defines model authorship as a construct with four facets and ordered levels carrying observable indicators, and formalizes a partial-credit, falsifiable measurement model to test whether such learning actually occurs.(Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education)(The AI writes the code, the student writes the model: A theory and measurement programme for learning by construction with generative AI) This is constructionism's classic "make something shareable and debug it" updated so that the artifact the student makes and reflects on is a mental model made visible, not merely source code — and it couples the theory to an explicit measurement program so the claim becomes empirically testable.

Constructionism is thus both a learning theory and a critique: it insists that the purpose of education is not to reproduce existing knowledge structures but to empower learners to construct and transform them — a stance with clear implications for whether AI in education reinforces or challenges established hierarchies.

Constructivism and AI in education

AI for constructivist learning

Well-designed AI can enable construction at scale. Intelligent Tutoring and AI Tutoring systems can pose problems and guide Help-Seeking instead of giving away answers; Simulation and Game-Based Learning environments let learners build and test mental models; and Project-Based Learning and Experiential Learning activities supported by AI give learners authentic construction tasks. The central design pattern is **Scaffolding** — calibrated support that fades as competence grows — rather than completion.(The Path to Conversational AI Tutors: Integrating Tutoring Best Practices and Targeted Technologies to Produce Scalable AI Agents)(Embodied inquiry with AI as facilitator: An exploratory case study)

Classifying the *questions learners ask* is one way to see construction happening, and to act on it. Lee, Atif & Kang (2026) sort 434 authentic learner questions from 11 IT students across 12 courses into three constructivist instructional roles — knowledge transmitter, facilitator, and co-learner — and train four transformers to recognize them. DeBERTa classified factual knowledge-transmitter questions at 96.67% precision but facilitator questions at only 78.79%, and every model confused the two higher-order roles most often: detecting dialogic, exploratory inquiry is far harder than detecting information-seeking. Because the typology treats questions as diagnostic evidence of epistemic engagement rather than as mere inputs, it supports a distinctly constructivist design move — when a learner repeatedly asks only factual questions, the system can prompt reflective, exploratory questioning that develops Metacognition and critical inquiry rather than answering at whatever depth the learner's question implies.

The risk of "constructivism in name, behaviorism in practice"

Empirical work repeatedly finds a gap between espoused constructivist goals and actual AI implementations. A systematic review of AI in vocational education, for instance, found that constructivist theories are espoused in VET discourse while **behaviorist drill-and-practice designs dominate in practice**, and warned of an educational "Turing Trap" — using AI to replicate rather than augment human instruction.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

This pattern generalizes across the field:

- When generative AI completes writing, reasoning, or code for students, the learner loses the constructive thought process the task was designed to build — the concern central to Cognitive Offloading and Over-Reliance.(Stop Writing for Me: Generative Refusal in AI Tools for Thought)
- The loss is now measurable, and it follows the work rather than the tool. In 26,811 Chinese secondary students, generative AI raised homework scores by 18% and cut completion time by 30%, while closed-book exam scores fell 20% within six months. The decline concentrated among the roughly 81% of users whose completion times indicated homework outsourcing, and users who kept homework time comparable to non-users learned as efficiently (Strömberg, Lei and Wu (2026)). The variable that predicted learning was not AI use but whether the learner still performed the construction.
- AI implementations that emphasize adaptive feedback and efficiency frequently under-serve the learner-agency, critical-reflection, and autonomous-decision goals that constructivism implies. (Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

The naming trap: generative AI output is not generative learning

A recurring confusion in the field turns on a name collision. **Generative AI** names a class of *technology* — models that generate text, images, or code. **Generative learning** (Wittrock's generative-learning theory) names a *learner activity* — the learner actively making meaning by constructing connections between new information and prior knowledge, through strategies such as summarizing, mapping, drawing, self-testing, and self-explaining. The two are not the same thing, and conflating them has real pedagogical consequences: an AI *producing* a summary or a map for the student is the opposite of the student *performing* the generative-

learning act. Dabbagh & Fake (2026) build directly on this distinction, arguing that a GenAI mindtool supports generative learning only when the *learner* drives the constructive activity — generating a mind map with AI assistance is generative learning; having the AI generate the map wholesale is not, however fluent or correct the output.

The deciding question is **who performs the meaning-making**: - Does the student construct an explanation, or merely receive one? - Does AI prompt the learner to connect ideas, or supply the connections for them? - Is the artifact (summary, map, code, model) the *product* of the learner's construction, or a substitute for it?

This mirrors the ICAP hierarchy — constructive and interactive engagement outrank active and passive — but sharpens it: a tool can produce visibly "constructive-looking" output while the learner sits in a *passive* or *active* mode. Evaluating a GenAI tool for generative learning therefore means inspecting where the constructive effort actually happens, not whether generative output is present. This is the same constructivist-in-name / behaviorist-in-practice trap, applied to the specific case of generation: model authorship (the AI writes the code, the student writes the model) is one concrete resolution — the learner constructs the *conceptual model* even when AI supplies the surface artifact.

Design responses grounded in constructivism

- **Generative Refusal** — AI tools that strategically withhold generated text and pose questions instead, returning cognitive friction to the user so that the labor of articulation itself builds understanding.(Stop Writing for Me: Generative Refusal in AI Tools for Thought)
- **Thinking tools over answer machines** — using GenAI as a Generative AI (GenAI) as a mindtool that supports generative learning (GL) in which the learner drives the tool, rather than the tool replacing the learner.(Generative AI (GenAI) as a mindtool that supports generative learning (GL))
- **Constructive conflict** — adversarial AI agents that challenge a learner's design or reasoning, prompting reconsideration and deeper construction of alternatives, in the tradition of Socratic tutoring.(Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers)
- **Simulated opposition is not opposition.** A counter-position that can be voiced on demand but never resists rehearses the choreography of dialogue while withholding what makes it potent: it has no embodiment, stake, or exposure to consequence, so unlike a human other it offers no route to repair (Du et al. (2026)).
- **Internal feedback via comparison** — having learners compare their own work against AI-generated exemplars so that the act of comparison itself generates learning.(Unravelling undergraduates' development of evaluative judgments through AI-supported internal feedback)
- **Question-type-aware prompting** — classifying learner questions into constructivist roles so the system can deliberately escalate a student from information-seeking toward exploratory, dialogic inquiry instead of mirroring whatever cognitive depth the question implies. Because facilitator and co-learner intent remain confusable for automated classifiers, this design keeps a human validating the categorization before it drives Feedback or Scaffolding.(Analysing AI utilisation in education through learner question types: A constructivist approach)

- **Community as the evaluative standard** — learners design something real for their community using AI as a design resource, while community knowledge and community practitioners serve as the standard that judges the outcome, leaving room for limitation, refusal, or strategic non-use where critical engagement requires it.(Ojeda-Ramirez, Gyles & Peppler (2026))

Constructivism and "education about AI"

Constructivism also shapes how AI literacy itself is taught. If knowledge is constructed, then AI literacy is not acquired by lecturing about models but by actively using, critiquing, and building with AI — generating artifacts, interrogating outputs, and reflecting on the interaction.(Systematic review of collaborative learning activities for promoting AI literacy) This positions AI Literacy as an active, participatory competency rather than a body of passive knowledge, and it connects constructivism to Critical Thinking and to Learner Agency in learners' encounters with AI.

Implications for design and research

1. **Preserve the constructive activity.** AI should scaffold the learner's own thinking — prompt, question, and support — rather than perform it. Designers should ask whether the tool increases or replaces the learner's constructive effort.(Stop Writing for Me: Generative Refusal in AI Tools for Thought)
2. **Use the ICAP lens.** ICAP classifies engagement into constructive, interactive, active, and passive modes — use it to evaluate whether AI interactions actually elicit constructive and interactive modes rather than passive consumption. Designers should favor the deeper (constructive and interactive) modes where the learning goal warrants.(Systematic review of collaborative learning activities for promoting AI literacy)
3. **Align theory and implementation.** Researchers should look beyond whether AI "works" to *how* it embodies a learning theory, checking for the constructivist-in-name, behaviorist-in-practice gap. (Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)
4. **Study learner agency and transfer.** Constructivist commitments imply evaluating not just immediate test gains but whether learners can transfer and independently apply their constructed understanding.(Research Methods in AIED)

Common Misconceptions

- **"You can detect constructivist teaching from the questions asked."** A DeBERTa classifier **classified factual knowledge-transmitter questions at 96.67% precision but facilitator questions at only 78.79%**, and **every model confused the two higher-order roles**. The construct that matters most is the one automated detection handles worst.
- **"Surface features of a lesson reveal its pedagogy."** The classifier's failure is not an implementation detail. Facilitator and constructivist roles are the hard cases precisely because they are defined by what the teacher does with the learner's thinking, and that relation is not recoverable from the question text alone.

- **“Constructivism means the teacher does not explain.”** The theory locates learning in the learner’s construction from experience, which is compatible with direct instruction. Treating it as a prohibition on telling misreads both the theory and the evidence on worked examples.

Connected Concepts

- Community of Inquiry — Community of Inquiry (grounded in constructivist/Deweyan pragmatism)
- Cognitive Psychology — Cognitivism, the third classical pole of learning theory
- Active Learning
- Learning by Teaching
- Scaffolding
- Self-Regulated Learning
- Collaborative Learning
- Experiential Learning
- Project-Based Learning
- Embodied Learning
- Learning Design
- Generative AI
- Intelligent Tutoring
- Cognitive Offloading
- Learner Agency
- Critical Thinking
- AI Literacy
- Misconceptions about AI
- Learning Theories
- Behaviorism
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Theory Development in AI in Education — Theory Development in AI in Education
- Productive Failure

Connected Articles

- Analysing AI utilisation in education through learner question types: A constructivist approach — Learner questions classified into three constructivist roles: transmitter, facilitator, co-learner (Lee, Atif & Kang 2026)
- Control vs. Agency: Exploring the History of AI in Education — Positions constructionism (Papert) against cognitive tutors in AIED history

- Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education — Code-to-Learn with GenAI: constructionism framework for artifact construction
- The AI writes the code, the student writes the model: A theory and measurement programme for learning by construction with generative AI — Model authorship: theory and measurement program for learning-by-construction with GenAI
- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — Constructivism espoused but behaviorist AI dominates in VET; the “Turing Trap”
- Stop Writing for Me: Generative Refusal in AI Tools for Thought — AI tools that withhold generation to protect constructive thought
- Generative AI (GenAI) as a mindtool that supports generative learning (GL) — GenAI as a thinking tool supporting learner construction
- Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers — Adversarial AI agents prompting constructive reconsideration
- Systematic review of collaborative learning activities for promoting AI literacy — Collaborative AI literacy and the ICAP engagement framework
- Unravelling undergraduates’ development of evaluative judgments through AI-supported internal feedback — AI-supported comparison generating evaluative judgments
- Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents — ICAP and cognitive engagement with LLM agents
- The Path to Conversational AI Tutors: Integrating Tutoring Best Practices and Targeted Technologies to Produce Scalable AI Agents — Scaffolding dialogue in AI tutors
- Embodied inquiry with AI as facilitator: An exploratory case study — Embodied inquiry with an AI facilitator
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Authentic assessment and knowledge construction
- Towards Synergistic Teacher-AI Interactions with Generative Artificial Intelligence — Levels of teacher–AI collaboration in design
- Learning with machines: Toward a theory of epistemic co-agency — Epistemic co-agency between learner and machine
- Community-Based AI Learning: Redistributing Artificial Intelligence’s Epistemic Authority in Education
- Connecting Education with Reality: AI as a Catalyst for Situated Learning
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning

- Pathways to Learning: Exploring High School Students' Learning of AI-Powered Educational Robotics — Pathways to Learning AI-Powered Educational Robotics (2026)
- CogEvolution: A human-like generative educational agent to simulate student's cognitive evolution — CogEvolution: generative agent simulating students' cognitive evolution
- The synthetic position: generative artificial intelligence and the suspension of self-authorship in emerging adulthood — Simulated AI counter-positions rehearse dialogue's form but withhold the resistance that compels revision
- The generative AI learning penalty: Evidence from Chinese secondary education — The learning penalty: homework scores up 18%, closed-book exams down 20%, concentrated among homework outsourcers

Cognitive Psychology

> **Cognitive psychology / cognitivism** — the family of theories that explain learning through internal mental processes — attention, perception, memory, reasoning, and metacognition — rather than through observable behavior alone. In AI in education, cognitivist assumptions underpin the field's most distinctive contributions: Intelligent Tutoring systems that model learner knowledge, Knowledge Tracing and Cognitive Diagnosis that track what a learner knows, Feedback designs grounded in error diagnosis, and the whole learner modeling and adaptive instruction family. Cognitivism is the middle ground between Behaviorism (learning as behavioral change) and constructivism (learning as active meaning-making), and it is the theoretical lens most closely tied to the computer metaphor of the mind that animated early AIED.

Questions to Consider

- When you think about 'learning,' do you picture a change in what someone does, or a change in what they know and can retrieve? How might that distinction change how you judge whether an AI tutoring tool actually works?
- AI tutoring is built on a 'computer metaphor' — treating the mind as an information-processing system with memory limits. Where does that metaphor feel powerful, and where might it miss something important about how humans learn?
- An AI tool makes a task feel effortless: it explains the next step, reduces friction, and the learner performs beautifully while using it. Does that count as successful teaching? How would you know whether the learner can now do it without the tool?
- Cognitive Load Theory distinguishes intrinsic, extraneous, and germane load. If you were designing an AI assistant, which type of load would you deliberately try to reduce, and which would you be careful NOT to remove?
- If a learner knows they can offload memory and reasoning to an AI, when is that a smart strategy and when is it a shortcut that quietly prevents learning? What determines the difference?
- Cognitivism assumes knowledge can be broken into components and tracked over time. What might get lost when we reduce a learner's understanding to a set of traceable knowledge components?

Introduction

Cognitive psychology is the learning-theory tradition that treats learning as a change in internal mental representations — concepts, schemas and procedures held in memory — rather than as a change in observable behavior. Its information-processing vocabulary (attention, encoding, retrieval, bounded working memory) supplied both the diagnostic language for learning difficulty and the architecture behind Intelligent Tutoring and Knowledge Tracing: systems that infer a learner's internal state and adapt to it. It remains the reference frame for Metacognition, Desirable Difficulties and Self-Regulated Learning across this knowledge base.

Su et al. (2026) reconstructed images from learners' EEG during science videos and found representation fidelity tracked test performance (regression coefficient 0.8481, $R^2 = 0.79$) — direct evidence that a measure of internal representation can index encoding

Core ideas

- **Learning is a change in internal mental representations.** Cognitivism holds that learning involves the acquisition, storage, and reorganization of knowledge in memory — concepts, schemas, and procedures — rather than just a change in observable response. What a learner *knows and can retrieve* matters, not just what they do.
- **The information-processing (computer) metaphor.** The mind is treated as an information-processing system with capacities and bottlenecks — measurement of latent ability, working-memory limits, encoding and retrieval — which is precisely the model that made AI tutoring (a computer program that models and adapts to learner cognition) a natural fit.
- **Attention and memory are bounded.** Working memory has limited capacity; durable learning requires encoding into long-term memory through rehearsal, elaboration, and retrieval practice. This connects cognitivism to research on Cognitive Offloading (delegating memory/processing to external tools) and to the "performance–learning gap" when AI bypasses retrieval and practice.
- **Metacognition regulates cognition.** Metacognition — monitoring and controlling one's own thinking — is a distinctly cognitivist construct, and it explains why learners' calibration of when to rely on AI matters for learning (see Cognitive Offloading and Self-Regulated Learning).
- **Knowledge is decomposable and traceable.** Cognitivist AIED assumes learner knowledge can be represented as components and tracked over time — the foundation of Knowledge Tracing, Cognitive Diagnosis, and Item Response Theory. Traceability is also a scoring rule. Four Knowledge Tracing update rules run over the same ASSISTments event sequences: crediting any assisted completion declared 93.9% of student-skill pairs mastered, against 72.8% when assisted rows read as failed first attempts. Pairs the lenient rule declared early went on to 0.709 unaided accuracy, against 0.857 where the rules agreed (Srivastava, 2026). The model tracks only what the evidence rule lets it count.

Cognitivism and AI in education

The cognitivist lineage of AIED

Cognitivism is arguably the theory most responsible for AI in education existing at all. The early cognitive tutors (e.g., Anderson's ACT-R-based tutors) embodied the assumption that learning could be modeled as production rules and that a system could trace which rules a learner had mastered. This produced the canonical architecture that still defines the field: a domain model, a student model that tracks the learner's knowledge state, and a pedagogical model that adapts instruction — all cognitivist in origin. Modern Knowledge Tracing (Bayesian, deep-learning, and IRT-based) and Cognitive Diagnosis continue this tradition. The same assumption underwrites Intelligent Tutoring, Adaptive Learning, and Personalized Learning, which are grouped in the knowledge base under the Learner Modeling and Adaptive Instruction umbrella.

Cognitive load and the design of instruction

Cognitive Load Theory (CLT) is the most widely applied cognitivist framework in instructional design: it distinguishes intrinsic load (task complexity), extraneous load (presentation friction), and germane load (schema-building effort). Well-designed AI should reduce extraneous load while preserving germane processing; poorly integrated AI reduces all three, leaving completed tasks with empty learning. CLT's working-memory framing is also central to debates about Cognitive Offloading — whether AI reduces harmful extraneous load or short-circuits the germane processing that produces learning.

Load tracked how effort was organized, not how much was spent: among 67 pre-service teachers designing lesson plans with GenAI, the higher-quality group did not differ on reported effort (2.85 vs 3.26) yet reported lower mental demand (3.09 vs 4.03) and frustration (2.12 vs 3.82) (Fang et al. (2026)).

Mayer's Cognitive Theory of Multimedia Learning (CTML) applies the same working-memory assumptions to the materials themselves, and its prescriptions are unusually concrete: learners do better from words and pictures together than from words alone, when extraneous material is excluded, when a lesson is segmented and user-paced rather than presented as one continuous unit, when corresponding words and pictures appear near and at the same time, and when narration is conversational and in a friendly human voice rather than formal or machine-generated.

Cognitivism vs. behaviorism and constructivism

- **vs. Behaviorism:** Behaviorism explains learning as observable behavioral change through reinforcement and drill; cognitivism insists on internal representations and traces mental states. AI practice often shows a "constructivism in name, behaviorism in practice" gap, but cognitivist designs (student modeling, knowledge tracing) are distinct from pure behaviorist drill-and-feedback because they *represent and adapt to the learner's inferred knowledge* rather than merely reinforcing responses.
- **vs. constructivism:** Constructivism holds that Learners actively construct meaning through experience; cognitivism emphasizes accurate encoding of (often pre-structured) knowledge and skill. AIED's cognitivist lineage (structured domains, explicit knowledge components) is sometimes critiqued as too behaviorist or too transmission-oriented by constructivists, while cognitivism counters that representing and tracing knowledge is what enables genuinely adaptive instruction.
- **vs. the learning sciences:** Cognitivism supplies the mechanisms that field designs with — working memory, encoding, retrieval, decomposable knowledge components — but is not itself design-oriented. It explains how learning happens; the learning sciences ask how to build environments in which it happens and hold those designs to empirical test.

The AI-era tension: cognitivism's boundary is under pressure

Generative AI both extends and challenges cognitivism. It extends it by making knowledge representations more powerful (LLMs as knowledge engines that can be traced via Knowledge Tracing and adapted via Learner Modeling and Adaptive Instruction). It challenges it by complicating where cognition "is": when AI performs reasoning, memory, and even metacognitive-like functions, the cognitivist assumption that learning

is internal processing in the individual mind is unsettled — as Distributed Cognition, co-regulation, and post-human framings argue cognition can be distributed across human and artificial systems. Yet the cognitivist question remains the field's central one: *does the learner internalize the knowledge, or does the tool hold it?* This is the cognitive-offloading and performance–learning gap question in its purest form.

Implications for design and research

1. **Design for internalization, not just performance.** Cognitivist AIED should be evaluated on whether the learner can retrieve and apply knowledge *without* the tool — not on assisted performance. This is the performance–learning gap and the rationale for measuring unassisted transfer.
2. **Represent the learner, don't just respond.** Attach structured Learner Modeling and Adaptive Instruction and Knowledge Tracing to AI dialogue so the system adapts to inferred knowledge rather than responding fluently but blindly.(EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners)
3. **Respect working-memory limits.** Apply Cognitive Load Theory to AI UX: reduce extraneous load (friction, overloaded interfaces) while preserving germane processing (productive struggle, retrieval practice) rather than minimizing all cognitive demand.
4. **Calibrate metacognition.** Because Metacognition governs when learners choose to offload, teaching calibration (knowing what one can actually do unaided) is a cognitivist answer to over-reliance (see Cognitive Offloading).

Common Misconceptions

- **"Mental representations are unobservable, so cognitive claims about learning are assumptions."** Reconstructing images from learners' **EEG** during science videos found **representation fidelity tracked test performance** (regression coefficient **0.8481, R^2 = 0.79**). The cognitivist premise of internal representation is measurable, and the measurement predicted the outcome.
- **"A high R^2 means the representation explains the learning."** R^2 = 0.79 is a strong association between fidelity and performance on the same material. It does not establish that raising fidelity raises performance, which is the intervention claim.
- **"Knowledge components are a convenient modelling fiction."** Decomposability is what makes Knowledge Tracing and Cognitive Diagnosis possible, and the methods work to the degree that the assumption holds. Treating it as a fiction discards the reason the methods produce usable estimates — while treating it as fact overstates what a fitted model tells you about a mind.

Connected Concepts

- Behaviorism
- Constructivism
- Learning Theories
- Metacognition

- Cognitive Offloading
- Knowledge Tracing
- Cognitive Diagnosis
- Learner Modeling and Adaptive Instruction
- Intelligent Tutoring
- Adaptive Learning
- Personalized Learning
- Item Response Theory
- Distributed Cognition
- ICAP Framework
- Transfer of Learning
- Self-Regulated Learning
- AI in Education
- Learning Sciences
- Retrieval, Spacing and Interleaving — the retention findings this practice family rests on

Connected Articles

- Evidence of a Cognitive Shift in AI Education: How Students Are Rethinking Human Intelligence? — The cognitive shift in AI education
- CogTax: A Four-Level Cognitive Taxonomy for Command-Line Computing Education — A cognitive taxonomy for AI use
- EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners — Pedagogical LLM agents grounded in knowledge tracing
- PersonaVLM: Long-Term Personalized Multimodal LLMs — LLM student modeling and memory
- Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning — AI as a cognitive partner in co-regulated learning
- Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments — Ensemble Cognition: thinking as human–AI interaction
- Human–AI collaborative patterns in GenAI-supported instructional design among pre-service teachers: an analysis of interaction sequences and cognitive load — Effort organization, not effort amount, tracked load and frustration
- Crediting assisted work inflates mastery: a preregistered comparison of evidence rules in intelligent tutoring logs — Mastery claims from knowledge tracing depend on how assisted work is credited (Srivastava 2026)

Sociocultural Learning

> **Sociocultural learning** — the family of theories, rooted in Vygotsky, that holds learning and development arise through social participation and are mediated by cultural tools, language, and interaction with more knowledgeable others. Cognition is distributed across people, artifacts, and environments rather than residing solely in individuals. In AI in education, sociocultural theory frames how generative AI functions as a new kind of *mediational agent* — a tool that both mediates activity and generates contingent contributions to interaction — and frames the design of Scaffolding, the Zone of Proximal Development (ZPD), apprenticeship, and communities of practice. See Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory.

Questions to Consider

- Vygotsky's Zone of Proximal Development is the gap between what you can do alone and what you can do with help. Recall a time a well-timed hint let you accomplish something you couldn't alone — what made that help effective, and when might it have given too much away?
- The page claims human thinking is 'mediated' by cultural tools like language and writing that reorganize how we reason. If that's true, how should we think about an AI chatbot as a new kind of thinking tool — and how might it change what 'knowing' means?
- Sociocultural theory says cognition is distributed across people, artifacts, and environments rather than inside individual heads. Does that match your experience of how you actually get things done, and what would it mean for designing learning if it's right?
- If learning happens first between people and only later within the individual, what are the risks of an AI tutor that lets a student interact mostly with a machine rather than with peers or a more knowledgeable human?
- How would you decide how much support an AI tutor should give so that a learner advances without the answer simply being handed over?

Introduction

The concept

Sociocultural theory (Vygotsky, 1978; Luria; Leontiev) holds that higher mental functions develop through participation in culturally organized activity. Unlike accounts that locate learning solely in the individual's information processing, the sociocultural view emphasizes that:

- **Mediation is fundamental.** Humans think with and through cultural tools — language, writing, diagrams, technologies — which reorganize how they reason, remember, and solve problems (Wertsch, 1991). These tools do not merely transmit information; they reshape cognition and participation.
- **Learning is social.** Higher mental functions appear first between people (intersubjectively, in interaction) and only later within the individual. Learning arises through participation with

teachers, peers, and communities — in processes like Scaffolding, apprenticeship, and movement through the ZPD.

- **Cognition is distributed.** Cognitive work is spread across people, artifacts, and environments (Hutchins; Clark & Chalmers; Pea), rather than contained in the individual mind. Distributed cognition, situated learning, and communities of practice extend the sociocultural strand.

The Zone of Proximal Development (ZPD)

The ZPD (Vygotsky) is the sociocultural concept most widely applied in AI tutoring: the space between what a learner can do alone and what they can do with assistance. Learning happens most effectively when instruction targets this zone — challenging enough to push development, supported enough to make progress. It is the theoretical foundation of Scaffolding: temporary, adjustable support withdrawn as competence grows. In AI in education, ZPD frames the central design question of how much support an AI tutor should provide so learning advances without being given away — see The Evidence Base on AI in K-12: A 2026 Review.

Machine-made help can land inside that zone. In a randomized study of 274 adult learners across four mathematics subjects, ChatGPT-generated worked-solution hints produced a 17.00% pre-to-post gain against 1.85% with no hints, while human tutor-authored hints produced 11.62%; the two help conditions were not statistically separable (Pardos and Bhandari, 2024). The error rate qualifies the equivalence: 32% of the generated hints failed quality checks until self-consistency prompting cut that to near zero in the three algebra subjects and 13% in statistics. A more knowledgeable other that is wrong one time in three is still a mediational agent, which is why the machine's contribution has to be checked before a learner builds on it.

Sociocultural learning in AI education

Sociocultural theory shapes AIED research in several distinct ways:

- **AI as a mediational agent.** Generative AI complicates the sociocultural distinction between mediational means and social interaction: it both mediates activity *and* generates context-sensitive, contingent contributions that shape interaction, without possessing intentionality, social membership, or accountability. Warschauer, Tate, and Ritchie (2026) propose the *mediational agent* as a hybrid category, and derive human-first habits of participation (primacy of human cognition, purposeful engagement, supervisory agency, epistemic vigilance, reflective self-regulation) to preserve learner agency.(Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory)
- **A stage-sensitive account of AI's regulatory role.** A developmental framework of human–AI co-regulation gives AI four roles — scaffold, metacognitive support, external memory, and decision partner — and places them by stage: structured external regulation in early childhood, a metacognitive partner in middle childhood and adolescence, and a collaborator on complex cognition in adulthood.
- **ZPD-calibrated scaffolding.** AI tutors should dynamically calibrate help to sit within each learner's zone. The Evidence Base on AI in K-12: A 2026 Review shows how tutors tuned to a learner's level outperform generic assistance; Adaptive Learning and ProPACT: A Proactive AI-

Driven Adaptive Collaborative Tutor for Pair Programming operationalize ZPD by adjusting difficulty and hints; and principled frameworks like A principled way to think about AI in education: guidance for educators and policy makers on action based on goals, models of human learning, and use of technologies argue support should be withdrawn as competence grows.

- **The signal for leaving the zone is aim, not depth.** A tutor that escalates and fades per decision point conceded 65.0% of the time after a turn about a *different* decision, twice the rate for turns aimed at the decision under support, and depth of reply did not order the outcomes (Hou et al. (2026)). Withdrawal assumes a learner who answers: take-up fell from 37.0% after the first ask to 21.8% after the third, so a hush is not evidence of readiness.
- **A fourth zone: what the model knows.** Tsim and Gutoreva (2025) extend Vygotsky's diagram rather than the tutoring loop, adding a *known to GenAI* zone to the ZPD and reading off four sub-zones that classify what a task should be assigned to: Substitute (no task-specific knowledge, so the model's general competence carries it), Aid (partial knowledge, augmented), Complement (enough knowledge to supervise the model's output), and Non-negotiable (enough to do it unaided, so delegation adds little). Scaffolding is expressed as task assignment rather than hint delivery, and a metacognitive loop of real-time evaluation, reflection and learning is what moves a task between sub-zones over time.
- **Apprenticeship and community.** Sociocultural ideas underpin cognitive apprenticeship, modeling, coaching, and fading; communities of practice frame learning as movement toward fuller participation in a community's practices.
- **Cultural and institutional context.** The constructivism-adjacent sociocultural strand stresses that the cultural dimension shapes what counts as knowing, who is an authority, and what effort means — see the Sydney PreK-12 rapid review's learners–contexts–cultures framing.
- **Validating talk measures requires the youth whose talk is measured.** Re-contextualizing talk-move definitions with four focal students raised Large Language Models (LLMs) classification F1 by +0.104 for Claim and +0.23 for Question, and students' own interpretations diverged from adult and model framings — a structural limit of text-based classification, not a data-size problem (Santos-Deonizio et al. (2026)).

Connection to cognitive load and metacognition

The sociocultural strand is tightly coupled to Cognitive Load Theory (support should manage load without eliminating productive effort) and to Metacognition (learners in the zone are actively monitoring and regulating their understanding). The Evidence Base on AI in K-12: A 2026 Review synthesizes K-12 evidence that AI tools work best when they keep learners in the ZPD rather than answering for them, and Human-in-the-Loop research addresses how human and AI support jointly define the learner's zone.

- **Generative AI as a mediational agent (2026):** Drawing on Vygotskian mediation, a theory paper proposes reframing generative AI not merely as a tool/mediational means but as a *mediational agent* that actively participates in learning activity, blurring the tool-vs-social-interaction boundary central to sociocultural theory (Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory). This positions generative models as co-participants rather than passive

instruments, with implications for how mediation, Learner Agency, and the learner–AI relationship are theorized in the learning sciences.

Common Misconceptions

“Sociocultural theory is about social factors in learning as a supplement to individual cognition.” The stronger claim is that cognition is **distributed across people, artifacts and environments** rather than residing inside individual heads. On that view an AI is not an external helper added to a learner’s cognition; it is a component of the system the cognition runs in, which changes what should be measured.

“If cognition is distributed, individual assessment is measuring the wrong thing.” It changes the interpretation rather than removing the measurement. What the assessment captures depends on what is present in the system at the time, which is why assisted and unassisted performance diverge — they are measurements of different configurations.

“Adding a tool to a group changes only the group’s efficiency.” It changes the division of labor, which is the unit the theory analyses. A group that routes most of its questions to an agent has redistributed the cognitive work even when the output is unchanged.

“Distributed cognition implies the individual does not matter.” It implies the individual’s contribution cannot be read off individual performance alone; the unit of analysis is the activity system, not the person in isolation.

Connected Concepts

- Scaffolding
- Constructivism
- Learning Theories
- Activity Theory
- Situated Learning
- Distributed Cognition
- Metacognition
- Learner Agency
- Generative AI
- Human AI Collaboration
- Desirable Difficulties
- Adaptive Learning
- Human-in-the-Loop
- K-12
- Intelligent Tutoring

Connected Articles

- When Youth Enter The Chat: An Epistemic Shift in the Validation of LLM-Based Measures of Student Talk — When Youth Enter The Chat: Validation of LLM-Based Measures of Student Talk
- Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory — Generative AI as a Mediational Agent
- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming — Collaborative AI tutoring
- A principled way to think about AI in education: guidance for educators and policy makers on action based on goals, models of human learning, and use of technologies — Principled AI education frameworks
- The Evidence Base on AI in K-12: A 2026 Review — Stanford evidence base for AI in K-12
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Sydney rapid review of GenAI in PreK-12
- Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning — AI as cognitive partner and co-regulation
- ChatGPT-generated help produces learning gains equivalent to human tutor-authored help on mathematics skills — LLM-authored hints matched human tutor hints on mathematics learning gains (Pardos & Bhandari 2024)
- Adaptive Scaffolding Needs Contingency: An AI Tutor That Escalates and Fades on What the Learner Does — Fading on what the learner’s turn is aimed at, not on how deep the reply is

Distributed Cognition

> **Distributed Cognition** — the theoretical perspective that cognition is not confined to an individual mind but is distributed across people, tools, artifacts, and environments. In AI-in-education research, this framework has become central for understanding human–AI collaboration: rather than viewing AI as a neutral tool that supports an otherwise self-contained learner, distributed cognition treats thinking as emerging from the interplay between learners, AI systems, peers, and their shared context. It reframes questions of Learner Agency, responsibility, and learning outcomes in terms of how cognitive work is apportioned across a human–AI system.

Questions to Consider

- Distributed cognition says thinking isn't confined to a single mind but is spread across people, tools, and environments. When you use a calculator, a notes app, or an AI assistant, where does the 'thinking' actually happen?
- If cognition is distributed across a human and an AI, who is responsible when the result is wrong — and who is accountable for learning?
- One framework distinguishes AI's 'functional agency' (it can influence outcomes) from 'moral responsibility' (which remains human). Does that distinction hold up in practice, or does responsibility blur when humans can't understand what the system did?
- Human-AI systems that distribute reasoning most efficiently tend to produce the highest task performance but the least self-regulated learning. Why would making a system 'smarter' at the group level make the individual learner weaker?
- The 'Cognitive Commons' argument holds that distributed mastery depends on internalized expertise — you can't effectively oversee an AI system you don't deeply understand. How does that challenge the idea that AI lets us skip the hard work of learning?

Introduction

This is a learning-theory concept within the knowledge base's Learning Theories strand, closely related to Embodied Learning, Situated Learning, and Cognitive Offloading. Distributed cognition (DCog), originating in the work of Edwin Hutchins and colleagues, describes how cognitive processes such as memory, reasoning, and Problem Solving are spread across multiple agents and material systems rather than residing in a single head. In AI education this matters because AI systems increasingly function as genuine cognitive partners that carry part of the thinking load, raising the question of *where* learning actually happens and *who* is responsible.

How AI shifts the distribution of cognition

Generative and interactive AI systems redistribute cognitive work in ways earlier tools did not. The knowledge base documents several dimensions of this shift:

- **AI as a cognitive partner and co-regulator.** AI can act as a scaffold, metacognitive support, external memory system, and decision partner in the co-AI Regulation in Education of thinking and learning.(Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning) This positions cognition as co-regulated between learner and system rather than individually managed.
- **Volume of AI use does not reveal which form of distributed work is happening:** Poquet et al. (2026) found the volume-based profiles of 97 learners differed in prior knowledge and authorship but not in active-role or comprehension-level prompting, so shared activity and division of labor can accompany the same amount of use.
- **Agency and responsibility redistribution.** Frameworks such as **ensemble cognition** reconceptualize thinking as emerging from dynamic human–AI interaction, distinguishing AI's *functional agency* (its capacity to influence outcomes without consciousness) from *moral responsibility* (which remains human).(Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments) Distributed cognition thus reframes who is accountable for learning.
- **The efficiency–regulation tension.** Empirical work shows a trade-off: human–AI systems that distribute reasoning most efficiently (e.g., via delegated reasoning) achieve higher task performance but may reduce learners' self-regulatory engagement.(Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective) This is the empirical face of the Cognitive Offloading and Over-Reliance risks the knowledge base documents.
- **Mediation in collaboration.** AI can act as a *pedagogical mediator* that orchestrates interaction, epistemic sense-making, and regulatory processes in collaborative learning, redistributing agency, authority, and responsibility across human and non-human actors.(Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning)
- **Access configuration distributes cognition within the group.** Xu et al. (2026) show that *how* a team shares GenAI determines the distribution of cognition: synchronous work on a single shared interface sustains a common cognitive model (collective prompts, shared external memory), whereas asynchronous private use fragments it, with outputs selectively re-labeled before sharing. GenAI thereby functions as both a distributed cognitive participant and an interactive collaborative space whose permeability must be designed (shared context flows in, private insights do not auto-flow back).
- **Teachers too experience AI-dominant versus complementary distribution.** The same efficiency–regulation logic applies to the teacher side of lesson design: Choi et al. (2026) found that novice teachers delegate a large share of instructional-design cognitive load to the AI system (an AI-dominant distribution, largely accepting responses), whereas experienced, AI-proficient teachers reach a complementary distribution in which pedagogical expertise and AI's

computational support mutually reinforce. Because GenAI generates and co-constructs rather than merely stores information, they frame this as *participatory shared cognition*, not mere tool use.

- **Interaction types, not outcomes, as the unit.** Willcox, Lane and Arikan (2026) built the **Cognitive Distribution Framework** from 53 logs of self-directed ChatGPT use: five interaction types (extension, outsourcing, alignment, transformation, decoupling) and four user roles, so the same student can offload in one exchange and co-think in the next.
- **Transactive memory gives the distribution a measured mechanism.** Among 891 college students in the United States and Türkiye, neither self-appraised thinking ability nor confidence in the AI partnership predicted critical thinking directly. Both worked through accumulated GenAI experience, which mattered only via specialization and coordination of labor (b = 0.636) and reflective transformation of output (b = 0.367) (Akgun & Toker, 2026). Those two mediators then predicted critical thinking (b = 0.230 and 0.175) with no direct path left, so what a human-AI system thinks with is the arrangement of the work, not the amount of use.

Distributed cognition and related perspectives

The knowledge base treats distributed cognition alongside its neighboring theoretical traditions, which overlap but are not identical:

- **Situated learning / situated cognition** emphasizes that cognition and learning are inseparable from the authentic context and communities of practice in which they occur — a complement to DCog's focus on cognitive *distribution* across systems.
- **Embodied cognition** stresses the role of the body and sensorimotor interaction, arguing that thinking is grounded in bodily engagement rather than abstract symbol manipulation.
- **Cognitive Offloading** is the practical mechanism by which cognitive work is handed off to external systems (including AI), and is the risk-laden counterpart to DCog's descriptive account.
- **Extended cognition / the extended mind thesis** (used in posthumanist work) holds that external artifacts can be *constitutive* parts of a cognitive system, not merely instruments — a stronger claim that AI is part of the learner's mind itself.(Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI)

Whose cognition? The unit-of-analysis problem

Schlauch (2026) pushes that unit-of-analysis question harder than most work in this tradition. His claim is that literacy is not an individual possession but something enacted with materials and machines, which makes the individual learner the wrong unit of analysis. A competence framework centered on the person therefore cannot register infrastructural or nonhuman contributions, so the field keeps naming distribution and then resolving it back onto the learner. The equity edge is his difficulty argument: reflexivity depends on lived experience and relations of power, so students whose language or writing practices sit furthest from the encoded norm carry the largest cost. The argument is theoretical and reports no dataset, and its design orientations remain untested proposals.

Why it matters for AI design and evaluation

Distributed cognition provides both a design lens and an evaluation lens. For design, it asks how to apportion cognitive work between learners and AI to preserve (not erode) the human learner's agency, Metacognition, and self-regulation. For evaluation, it reframes success metrics: instead of asking only "did performance improve?", DCog asks whether the distribution of cognition supports durable learning, epistemic agency, and educational justice — a perspective that connects to the knowledge base's AI Ed Evaluation and Learning Theories concerns.

Fowlin et al. (2026) operationalize that apportionment as a two-phase sequence: build core competencies without AI first, then introduce AI as a cognitive partner whose suggestions students critically evaluate, to prevent automation-related deskilling (Fowlin et al. (2026)).

Internalized vs. distributed mastery. The Cognitive Commons framework (Lovett 2026) distinguishes Internalized Mastery (deep domain knowledge in individual minds) from Distributed Mastery (orchestrating human–AI systems) and argues the latter depends on the former via a "Validation Tether": effective oversight of distributed/AI systems presupposes the internalized expertise those systems may undermine. This sharpens the DCog design question — the distribution of cognition must not come at the cost of the expertise that validates it.

Common Misconceptions

- **"A shared document means shared cognition."** Volume-based profiles of **97 learners** differed in **prior knowledge and authorship** but **not in active-role or comprehension-level prompting**. Participation volume measured exposure, not the distribution of cognitive work — so usage analytics of a collaborative tool say little about who was thinking.
- **"Everyone offloads to AI equally."** Novice teachers **delegate a large share of instructional-design cognitive load to the AI system**, arriving at an **AI-dominant distribution** in which they largely accept responses, whereas experienced and AI-knowledgeable teachers distribute differently. Expertise shows up in where the load is placed, not only in how much AI is used.
- **"More AI involvement means more support."** An AI-dominant distribution is the pattern to watch for, because the human's share of the cognitive work shrinks while the output volume rises. The system can look more capable precisely as the user is doing less.

Connected Concepts

- Learning Theories
- Cognitive Offloading
- Embodied Learning
- Situated Learning
- Human AI Collaboration
- Learner Agency
- Metacognition
- Self-Regulated Learning

- Constructivism
- Collaborative Learning
- AI in Education

Connected Articles

- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective — Empirical study of human–AI collaborative problem-solving through a distributed cognition + co-regulation lens
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning — AI as a pedagogical mediator redistributing cognition across human and non-human actors
- Artificial intelligence as a cognitive partner: a developmental framework for human-AI co-regulation in learning — AI as a cognitive partner in co-regulated thinking
- Towards a philosophy of ensemble cognition: Reconceptualising agency and mind in AI-mediated educational environments — Ensemble Cognition framework reconceptualizing thinking as human–AI interaction
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI — Posthuman learner with cognition distributed across biological and artificial systems
- Empowering Educators: Operationalizing Age-Old Learning Principles Using AI — Operationalizing distributed cognition alongside experiential and situated learning
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction in lesson design: AI-dominant vs complementary distributed cognition by experience and proficiency (Choi et al. 2026)
- AI as an Agent and Collaborative Space: Exploring the role of generative AI in small group synchronous and asynchronous collaborative dynamics — GenAI as agent and collaborative space: how access configuration distributes group cognition (Xu et al. 2026)
- Cognitive Distribution in Student-GenAI Interaction: A Process Framework from Self-Directed ChatGPT Use in Research Tasks — Cognitive Distribution Framework: five interaction types and four roles from self-directed ChatGPT use
- When Does GenAI Use Support Critical Thinking? A Cross-Cultural Structural Account of Transactive Memory with GenAI — Transactive memory with GenAI: division of labor and reflective transformation mediate critical thinking (Akgun & Toker 2026)
- Foregrounded by AI: What a sociomaterial account of literacy implies for postdigital design orientations — Why the individual learner is the wrong unit of analysis

Situated Learning

> **Situated Learning** — the theory, rooted in the early-1990s work of Lave and Wenger (1991), that learning is not an isolated, decontextualized act but occurs through participation in authentic activities, contexts, and cultures. Knowledge is co-constructed by learners and peers within communities of practice, and novices learn through legitimate peripheral participation — absorbing the culture, language, and practices of expert members as they move from the periphery to the center of a community. Emphasis falls on learning by doing in real-world situations, where Assessment emerges from the task itself rather than being separated from it.

Questions to Consider

- Think of something you genuinely know how to do well — a skill, a trade, a craft. Did you learn it mostly from abstract instruction or from participating in a real community that did that thing? What does that suggest about where knowledge actually lives?
- Lave and Wenger describe novices learning through ‘legitimate peripheral participation’ — starting at the edge of a community of practice and moving inward. Where have you watched (or been) such a newcomer, and what let them move from the periphery to the center?
- If knowledge is ‘situated’ in authentic contexts, what does that imply for the traditional classroom, which deliberately separates learning from real-world situations — and for AI tools designed to deliver decontextualized content?
- The page treats situated learning as a design lens for AI. How might an adaptive system or simulation ground learning in authentic practice rather than pulling it out of context?
- What obstacles does the research say stand in the way of situating AI-driven learning in real contexts, and which of those have you seen in your own institution?

Introduction

Situated learning is one of the activity-and-context theories within the knowledge base’s Learning Theories strand. It takes up Vygotskian themes of social construction but adds a strong emphasis on the intimate integration of “doing” and “learning” and on the importance of communities of practice. As an educational stance it confronts traditional, standardized schooling by foregrounding the learner’s sociocultural context as a key element for acquiring skills and appropriating knowledge relevant to their reality.

In the AI-in-education literature, situated learning matters because it provides a design lens for AI: adaptive systems, intelligent tutoring in authentic scenarios, and immersive simulations can ground AI-driven education in real-world contexts, while situated learning in turn offers AI a meaningful anchor in authentic practice and complexity. The two are widely treated as complementary, with human guidance remaining essential for ethical grounding. - **Contextualizing the material itself is a situated-learning move.** DagFlow-AI generates a statistics dataset built around a student’s own stated interest — one case study used a student’s concern about climate change and health — while holding the learning objectives and skill level fixed (Arthur et al., 2026). Matching the *data* to the learner, rather than matching the explanation, treats the

context of practice as the thing that needs situating. The authors concede the limit: synthetic data cannot teach data collection, measurement or study design, so the context is real to the learner but not to the world.

Situated learning as a design lens for AI

The knowledge base's research treats situated learning not merely as an abstract theory but as a concrete design and evaluation framework for AI in education:

- **Opportunities and obstacles.** A PRISMA systematic review of 60 articles (three decades) finds that AI can augment situated learning — through adaptive systems tailored to students' evolving needs, intelligent tutoring situated in authentic scenarios, automation of administrative tasks, and data-driven teacher support — while the main obstacles are the traditional school's one-way passive learning, an over-emphasis on predefined outcomes, and teachers' limited contextual knowledge. Human guidance remains essential for ethical grounding.(Reshaping education in the era of artificial intelligence: insights from Situated Learning related literature)
- **AI as a catalyst connecting education to reality.** AI can act as a *catalyst* for situated learning by connecting education with reality and authentic contexts, enabling learning grounded in real-world scenarios.(Connecting Education with Reality: AI as a Catalyst for Situated Learning)
- **Mediational artifacts in authentic inquiry.** In science learning, AI tools (virtual labs, simulations, intelligent tutoring) function as "mediational artifacts" that extend situated learning by enabling digital communities of practice and boundary-crossing between school, real-world, and interdisciplinary contexts — transforming students from "knowledge learners" into "scientific practitioners."(Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers' Perspectives)
- **Situated curriculum devices.** AI literacy can be developed through *Episodes of Situated Learning* — active teaching instruments (anticipate, produce, reflect) that build AI competencies through real-world Problem Solving rather than abstract instruction.(Towards AI literacy: A proposal of a framework based on the Episodes of Situated Learning)
- **Situated evaluation in design-based learning.** Yaşar et al. (2026) grounded their study in situated-learning theory and iterative design Pedagogies and Teaching Strategies, evaluating 80 student design posters across instructor, peer-reviewer, and grant-reviewer roles. Role-aware prompting produced qualitatively different evaluative feedback — instructors encouraging and process-oriented, peers supportive and conversational, grant reviewers formal and outcomes-oriented — differences that were epistemic, not merely stylistic, foregrounding different aspects of design practice. This shows how situated, role-specific evaluation can be emulated by an LLM when scaffolded with a semantically precise rubric, and how assessment in design-based learning emerges from the authentic task and its roles rather than being separated from them.
- **Situated AI ethics.** Ethical reasoning about AI is itself best treated as *situated* — grounded in cultural-historical and ecological context rather than abstract principles.(Situated AI ethics: a cultural-historical and ecological framework for education)

Situated learning connects closely to Embodied Learning (both stress the grounding of cognition in context and action), Distributed Cognition (learning distributed across people, tools, and contexts), Experiential Learning, and Constructivism theory. In AI education it grounds the critique of decontextualized,

disembodied learning: AI design that keeps learners anchored in authentic practice preserves the situatedness that durable learning requires.

- **Scenarios and reusable assets as infrastructure.** AI Cosmos (2026) operationalizes situated learning as a scenario — objective, role-specialized agents, queryable knowledge and a stateful workbench — plus an asset memory that preserves process records and experience traces with their provenance so later scenarios can retrieve prior practice. Two preregistered three-arm randomized trials found a 7.0-point learning-gain advantage over a vanilla assistant in legal reasoning (d = 0.56) and a larger share reaching criterion mastery in competitive programming (68% against 45%), while prompting the same model to act as a teacher produced no detectable benefit. It is a rare test of the claim that situation and workspace carry more of the learning than conversational explanation does.

Common Misconceptions

- **"Situated learning means adding a realistic scenario to an abstract lesson."** The theory's claim is stronger than context-dressing: learning is constituted by participation in a community of practice, and what is learned is what that participation affords. A worked example with a workplace framing attached still teaches the example, not the practice.
- **"Authenticity is a property of the task."** Authenticity is a relation between the activity and a real community's legitimate work. A task can be elaborate and still be school-shaped — assessed by a teacher, for a grade, with no consequence in the world it claims to represent.
- **"Assessment emerging from the task means no assessment."** It means the criterion is the community's, not the classroom's: whether the work is acceptable to people who do the work. That is a different and usually stricter standard than a rubric.
- **"Apprenticeship requires a physical setting."** The mechanism is legitimate peripheral participation — moving from the edge of a practice toward its center with real responsibility. Online and simulated settings can support it or can simulate the periphery without ever granting participation, and the difference is whether the learner's contribution is actually used.

Connected Concepts

- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities
- Learning Theories
- Constructivism
- Experiential Learning
- Embodied Learning
- Distributed Cognition
- Collaborative Learning
- Adaptive Learning
- Personalized Learning
- Teaching
- Learning Design

- AI in Education
- Virtual and Augmented Reality — immersive environments as a route to authentic context

Connected Articles

- AI Cosmos: An Agentic Infra for Situated Learning — Scenarios plus reusable provenance-bearing assets beat a plain assistant in two trials
- Reshaping education in the era of artificial intelligence: insights from Situated Learning related literature — PRISMA systematic review of situated learning and AI in education (primary reference for this page)
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches
- Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers' Perspectives
- Situated AI ethics: a cultural-historical and ecological framework for education
- Connecting Education with Reality: AI as a Catalyst for Situated Learning
- Towards AI literacy: A proposal of a framework based on the Episodes of Situated Learning
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design

Embodied Learning

> **Embodied learning** — the pedagogical principle that learning is grounded in bodily experience, physical interaction, and the sensory-motor context of the learner. Embodied approaches hold that cognition is not purely abstract but shaped by the body and its interaction with the environment. In AI in education, embodiment is realized through educational robots and social robots, whose physical presence grounds abstract concepts (such as program logic or social skills) in observable, manipulable behavior.

Questions to Consider

- We often think of learning as something that happens 'in the head,' with the body just carrying the brain around. What if learning is actually grounded in bodily experience and interaction with the environment? What's one subject you learned that seemed to require your body — and could it have been learned purely abstractly?
- Embodied approaches claim a physical, manipulable agent helps learners connect abstract ideas to concrete outcomes — seeing a program make a robot move, for instance. When have you noticed that doing something physical made an abstract concept finally 'click'?
- Some researchers treat gesture as evidence of understanding — tracking students' hand movements alongside their speech to assess conceptual grasp. If a student's hands 'know' the concept before their words do, what might that imply about how we should assess learning?
- An emerging critique challenges 'disembodied' AI that operates on abstract symbols, arguing AI should be designed around embodied intelligence to sustain learners' thinking rather than outsourcing it. Do you think an AI that has never had a body can fully support embodied learning?

Introduction

Embodied learning is closely related to Active Learning, Experiential Learning, and situated/Constructivism theories. The key claim is that a physical, manipulable agent helps learners connect abstract ideas to concrete outcomes — a program that makes a robot move, or a role-play with a physical robot — in ways that pure screen-based interaction may not. Robotics is the clearest embodiment of AI in education, giving learners something to see, touch, and observe.

How embodied learning appears in the knowledge base's research

- **Grounded programming:** RoboBlockly Studio grounds block programming in embodied robot execution, creating a tight loop of authoring, running, observing, and revising so learners see their code become behavior.
- **Social-robotic interaction:** Social robots used for storytelling (MotiBo, RoboBuddy), role-play (REMind), and sign language (Pepper) provide embodied social interaction that supports relational and emotional learning.

- **Embodiment features are not what drives outcomes.** A meta-analysis of 11 RALL studies (N = 595, g = 0.83, I^2 = 84.4%) found robot morphology, modality, autonomy, and social role did not moderate L2 learning; group-based formats beat one-on-one, so the robot's position, not its embodiment, carried the effect (Wang et al. (2026)).
- **Embodiment and creative writing:** Research on robot-LLM integration in creative writing examines how embodiment affects learners' interaction and outcomes.
- **Human-robot interaction:** HRI research (trust, agency) examines how physical embodiment shapes trust, engagement, and autonomy.
- **Gesture as evidence of understanding:** Morphew et al. integrate computer-vision gesture tracking with Large Language Models (LLMs) analysis of speech to show that engineering students' conceptual understanding of statistics is expressed through both speech and gesture. High-confidence explanatory gestures cluster around specific concepts (especially the mean), and close gesture–speech coupling signals coherent conceptual talk while divergence marks developing ideas — positioning embodied action as evidence in assessment via multimodal learning analytics, not only as a learning mechanism.
- **A language-only facilitator pulls inquiry toward what can be said.** In a Master's fluid-statics laboratory, students built the buoyancy model by hand before a Gemini-based facilitator joined to apply it to a new phenomenon. Across three pairs the AI held the ISLE sequence, but pressed to "just tell us" it produced mass values nobody had measured, and one remote participant completed a physically correct cycle that was clean but disembodied (Tufino & Damiani, 2026). The design lesson is sequence rather than substitution: build the model in the body first, then let the language model work on applying it.

Embodied intelligence and the critique of disembodied AI

A second, more theoretical strand of the knowledge base's embodiment research concerns the role of the *body* in AI-mediated learning — not through physical robots, but through the question of whether AI systems themselves are (or can be) embodied. This work challenges the dominance of symbolic, disembodied AI models built on abstract information processing:

- **Embodied AI as a design principle.** The **E3-HOT framework** argues that to sustain learners' cognitive agency and higher-order thinking (rather than encouraging cognitive outsourcing), AI should be designed around *embodied intelligence* — situational embedding, embodied participation, and cognitive creation — within a virtual–real integrated learning environment. (Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era)
- **The limits of disembodied generative AI.** Post-cognitivist scholarship argues that current GenAI systems lack proprioception, multimodal agency, and embodied practice, and advocates an "embodied AI" grounded in situationality, emergence, and sensorimotor coupling, proposing a perceptual–affective choreography for human–AI interaction.("If You Can't Dance Your Program, You Can't Write It": Challenges and Implications for AI in Education)
- **Embodiment, situatedness, and social construction.** In science learning, AI tools function as "mediational artifacts" that enable digital communities of practice and boundary-crossing,

connecting embodied, authentic inquiry to real-world and interdisciplinary contexts.(Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers' Perspectives) This ties embodiment to Situated Learning and Distributed Cognition.

Embodied learning connects to Robots in Education, Robots in Education, Robots in Education, Active Learning, Experiential Learning, Situated Learning, Distributed Cognition, Computational Thinking, and Social-Emotional Learning. - **Body tracking turns regulation into a measurable signal.** In a mixed-reality photosynthesis simulation where motion tags moved student agents across a projected model, an LLM pipeline labeled 470 segments of self-regulated behavior in 40 minutes of video, enacting dominating at 66.4% (Fonteles et al., 2026). - **AI mostly watches the body rather than joining it.** In a PRISMA review of 23 AI-for-embodied-learning studies, the 40 coded AI roles were dominated by sensing: analysis and evaluation 40.0% and recognition and detection 22.5%, against 35.0% for roles acting inside the activity (feedback and coaching 15.0%, interaction 12.5%, content creation 7.5%). Dropping the three Low-rated and four unappraisable papers cuts interaction to 6.7% and content creation to 3.3%, so the evidence that AI joins the embodied loop rests on the weakest papers (Kim and Han (2026)).

- **The most bodily literature measures the body least.** Of 32 outcome tags, cognitive outcomes took 43.8%, affective 34.4% and psychomotor 21.9%, an ordering that held among the 16 higher-rated papers (24.0% of 25 tags). The authors blame the difficulty of selecting psychomotor measures and a habit of prioritizing cognitive gains, not a weak effect on bodily skill. None of the reviewed systems was designed for learners acting together; the collaboration that appears is cooperation between teacher and AI (Kim and Han (2026)).

Common Misconceptions

- **"The body is what makes embodied learning work."** A meta-analysis of **11 RALL studies (N = 595, g = 0.83, I^2 = 84.4%)** found that **robot morphology, modality, autonomy and social role did not moderate** second-language learning outcomes. The embodiment features were not the active ingredient, and heterogeneity was high enough (I^2 = 84.4%) that the pooled effect describes a very mixed set of interventions.
- **"A large effect settles the mechanism."** g = 0.83 with 595 participants across 11 studies is a real signal and it does not identify what produced it. Since the design features did not moderate the effect, the plausible mechanism sits in the pedagogical activity rather than the hardware — which changes what to invest in.
- **"Embodiment cannot be measured, so it stays theoretical."** Body tracking can turn regulation into a **measurable signal**: in a mixed-reality photosynthesis simulation where motion tags moved student agents across a projected model, an LLM pipeline labeled **470 segments** of regulation behavior. The construct is operationalisable even where it is hard to define.

Connected Concepts

- Robots in Education
- Active Learning

- Experiential Learning
- Situated Learning
- Distributed Cognition
- Computational Thinking
- Social-Emotional Learning
- Learning Theories
- Multimodal AI
- Assessment Validity
- Virtual and Augmented Reality — the modality that tries to exploit embodiment directly

Connected Articles

- Analyzing embodied learning in classroom settings: A human-in-the-loop AI approach for multimodal learning analytics — Motion-tracked photosynthesis simulation analyzed with an LLM pipeline (Fonteles et al. 2026)
- A Multimodal Framework for Embodied Cognition in Oral Explanations — A Multimodal Framework for Embodied Cognition in Oral Explanations
- Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era — Fostering Sustainable Learning via Embodied Intelligence (E3-HOT)
- RoboBlockly Studio: Conversational block programming with embodied robot feedback for computational thinking — RoboBlockly Studio
- MotiBo: The impact of interactive digital storytelling robots on student motivation through self-determination theory — MotiBo
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — REMind
- Using the Pepper robot to support sign language communication — Pepper and Sign Language
- Enhancing creative writing with robot-LLM integration: The interplay of embodiment, AI creativity and user engagement — Robot-LLM Integration in Creative Writing
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis — Meta-analysis of AI-enhanced embodied robot-assisted language learning
- Reshaping education in the era of artificial intelligence: insights from Situated Learning related literature
- Artificial Intelligence in Science Learning within the Framework of Situated Learning Theory: A Qualitative Investigation of Teachers’ Perspectives
- Connecting Education with Reality: AI as a Catalyst for Situated Learning
- "If You Can’t Dance Your Program, You Can’t Write It": Challenges and Implications for AI in Education
- Embodied inquiry with AI as facilitator: An exploratory case study — AI as facilitator after hand-built models: a language-based AI cannot follow embodied inquiry (Tufino & Damiani 2026)

- Artificial intelligence in embodied learning: A systematic literature review — AI in embodied learning mostly observes: sensing roles 62.5% of coded role tags, and no reviewed system fused multimodal streams while learners used it (Kim & Han 2026)

Community of Inquiry

> **Community of Inquiry (CoI)** is a framework for conceptualizing a meaningful educational experience as the dynamic interplay of **cognitive presence**, **social presence**, and **teaching presence**. Originating in computer-mediated and online learning research (Garrison, Anderson & Archer, 2000), it has become one of the most widely used models for designing, evaluating, and researching online and blended inquiry-based education. In the Generative AI era the framework is being reconceptualized: machine-produced discourse can mimic authentic presence, so presences must be understood as sociotechnical accomplishments of human–GenAI assemblages rather than purely human activity.

Questions to Consider

- In an online course, what tells you that meaningful learning is actually happening — and how would you know if it weren't?
- The Community of Inquiry framework names three presences: cognitive, social, and teaching. In your own online experiences, which presence most often goes missing — and what does that do to learning?
- If an AI chatbot writes fluent, empathetic-sounding replies in a discussion forum, is 'social presence' happening? Or is presence something only humans can genuinely create?
- Generative AI can produce explanations so coherent they feel obviously right — but coherence isn't the same as correctness. Where have you seen 'fluency mistaken for warrant,' and how would you guard against it in an inquiry course?
- This framework suggests presences are 'sociotechnical accomplishments' of human-and-AI working together rather than purely human activity. Does that reframe who you hold accountable when an online discussion goes shallow or goes well?

Introduction

The Community of Inquiry framework describes a worthwhile online learning experience as the product of three interacting presences: cognitive presence (learners constructing and confirming meaning through sustained reflection and discourse), social presence (participants projecting themselves socially and emotionally), and teaching presence (design, facilitation and direction of the process). Grounded in Constructivism and Deweyan traditions, it treats inquiry as social and iterative, and it now serves as a design and evaluation lens for AI-mediated courses — where a Pedagogical Agent may support one presence while quietly eroding another.

The three presences

- **Cognitive presence** — the extent to which learners construct and confirm meaning through sustained reflection and discourse, operationalized via the *practical inquiry* model (triggering event → exploration → integration → resolution).
- **Social presence** — the ability of participants to project themselves socially and emotionally, expressed through affective communication, open communication, and group cohesion.
- **Teaching presence** — the design, facilitation, and direction of cognitive and social processes to realize personally meaningful and educationally worthwhile outcomes, including design/organization, facilitating discourse, and direct instruction.

CoI is grounded in Constructivism and Deweyan pragmatic traditions: inquiry is social, iterative, and driven by a felt difficulty that motivates the search for resolution.

CoI as a framework for online teaching

CoI originated in, and remains most strongly associated with, Online Teaching and Learning. It provides a vocabulary for diagnosing *why* an online course works or fails: low engagement and isolation in asynchronous courses are usually failures of social and teaching presence, while surface discussion often reflects weak cognitive presence. This makes CoI a practical design lens for the very conditions the online medium creates — the removal of physical co-presence, the need for deliberate community-building, and the structuring of discussion that substitutes for face-to-face contact. In the Generative AI era, CoI is also where online instructors confront the hardest new questions: who is "present" when Large Language Models (LLMs) agents post, moderate, or respond, and how to keep the three presences meaningful when machine-generated discourse can mimic them. The knowledge base's online-teaching page therefore treats Community of Inquiry as the core framework for the social-presence and community-building strand of its recommended practice.

CoI under generative-AI pressure

GenAI destabilises the assumption that indicators of presence can be attributed primarily to human learners and instructors (see Ba, Gašević, Lim & Anderson). It can:

- **Inflate cognitive presence** — fluent machine-generated explanations accelerate sense-making but risk premature closure when coherence is mistaken for warrant.
- **Mimic social presence** — machine-produced utterances can resemble empathy and responsiveness with high linguistic credibility, complicating relational accountability.
- **Redistribute teaching presence** — design, facilitation, and direct instruction become distributed accomplishments, with instructors modeling how to interrogate generated outputs and detect hallucinated citations.
- **Intervene too eagerly** — in an online-discussion study, expert facilitators were consistently more cautious about intervening than LLM judges, which were excessively eager to facilitate; the best trained classifier still hit a low ceiling imposed by the available datasets (Tsirmpas, Korre and Pavlopoulos, 2026). Redistributed teaching presence therefore changes the intervention threshold,

and a model will interject where a person would have waited, which is the failure mode a discussion forum notices.

Empirical network evidence now sits under these claims: in a quasi-experiment where 63 Chinese undergraduates (33 with, 30 without a GPT-4o mini chatbot) annotated shared readings on CollaboRead across five weekly tasks. The epistemic network analysis showed the assisted class binding social presence to integration and resolution while the control class bound social presence to triggering and exploration (X-axis U = 25.00, p = 0.01, r = 1.00; Y-axis U = 13.00, p = 1.00, r = 0.04). Self-reported cognitive and emotional engagement was higher in the assisted class. The presences then separate inside the condition rather than between them: high-achieving groups initiated 1407 feedback requests across 2319 annotations (60.7%) against 737 across 2167 (34.0%) in the low-achieving group, which stayed in a self-referential loop and weakly leveraged the scaffold.(Pan et al., 2026)

Rather than a tool, a dialogic partner, or a speculative "fourth presence," GenAI is best understood as an **epistemic condition** — a pervasive influence that reconfigures how presences are enacted, interpreted, evidenced, and governed through both visible outputs and invisible training-data, algorithmic, and platform logics.

The framework's own authors supply a role taxonomy for that condition: Stenbom and Garrison (2026) place AI as Learning Design support, an independent learner resource, an instructor-support function via analytics, a community member, and a sustained dialogical partner, and propose shared Metacognition — self- and co-regulation — as what keeps learners auditing AI output.

Practical implications

- The relationship between GenAI involvement and inquiry quality is **conditional on human accountability**, not linear: strong presence can occur with high or low GenAI involvement when accountability is strong, and weak presence with either when accountability is weak.
- Assessment of inquiry should shift from polished final outputs to **process-sensitive evidence** — prompting and revision traces, disclosure and attribution practices, verification moves, and interaction logs. This aligns with the knowledge base's broader move toward authentic, process-revealing assessment and away from detection-based responses.
- Pedagogically, learners often need explicit training (e.g., simulation-based practice with scripted roles and GenAI decision points) to sustain authentic inquiry under GenAI conditions — and instructors should model how to interrogate generated outputs, which depends on building AI Literacy, critical appraisal, and calibrated trust.

Common Misconceptions

"Teaching presence is a human property." In the generative-AI era the framework is being reconceptualized because machine-produced discourse can mimic authentic presence, so the presences are better understood as sociotechnical accomplishments of human–GenAI assemblages rather than purely human activity. A course can report high teaching presence with the instructor largely absent and a model doing the discourse.

“Coherent AI explanation creates cognitive presence.” Coherence is not correctness, and it is precisely the property that makes reflective inquiry hard to sustain: a student who feels an explanation is obviously right has been given little occasion to resolve a triggering event. Cognitive presence requires the resolution of doubt, not the removal of it.

“Presence is distributed evenly across a cohort.” It separates *inside* the condition rather than between conditions. In a quasi-experiment with **63 Chinese undergraduates (33 with a GPT-4o mini chatbot, 30 without)** annotating shared readings across five weekly tasks, the presences diverged by group achievement: high-achieving groups initiated **1407 feedback requests across 2319 annotations (60.7%)** against **737 across 2167 (34.0%)** in low-achieving groups. Access to the same tool reproduced an existing gap in the social behavior the framework measures.

“Adding a chatbot to an online course adds a presence.” It changes the mix. The framework’s value under GenAI is that it makes the substitution visible: a presence satisfied by a model is a different configuration of the same construct, and the cohort data show the substitution paying off unevenly.

Connected Concepts

- Online Teaching and Learning
- Generative AI
- Constructivism
- Pedagogies and Teaching Strategies
- Critical Thinking
- Assessment
- Human AI Collaboration
- Student Engagement
- Large Language Models (LLMs)
- AI Literacy
- Authentic Assessment
- Trust Calibration

Connected Articles

- Unpacking student interactions in GenAI-assisted social annotation: An epistemic network analysis of cognitive and social presence — Unpacking student interactions in GenAI-assisted social annotation: An epistemic network analysis of cognitive and social presence
- Reconceptualizing community of inquiry in the age of generative artificial intelligence — Reconceptualizing CoI in the age of generative AI
- Artificial Intelligence and Communities of Inquiry: Reimagining Educational Experiences — AI in communities of inquiry
- Artificial Intelligence in Online Education: A Systematic Review of Its Impact on Learner Engagement and Satisfaction — AI and online education engagement

- The Reflective Triangle Model: AI as a Cognitive Mediator in Teachers' Professional Learning and Learning-Community Development — Reflective Triangle Model: AI as cognitive mediator
- To facilitate or not to facilitate: Human and LLM facilitator tendencies in online discussions — Human versus LLM facilitators: models intervene more eagerly than expert humans (Tsirmpas et al. 2026)

Connected FAQs

- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Self-Regulated Learning

> Self-regulated learning (SRL) describes learners as active participants who can shape and develop their cognitive and behavioral actions in a successful way. AI tools can either scaffold SRL development or inadvertently short-circuit it by removing the regulatory demands that build expertise.(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)(The Evidence Base on AI in K-12: A 2026 Review) Longitudinal evidence sharpens the distinction: reflective use around an AI tool predicted critical thinking (β = 0.43) but not knowledge gain, and tool access on its own changed neither.(Generative AI and Learning Dynamics in Higher Education: A Longitudinal Empirical Study)

Questions to Consider

- SRL describes learners actively managing their learning through three phases: forethought (goal setting, planning, self-efficacy), performance (strategy, self-observation), and self-reflection (evaluation, adaptation). Before you read, which phase do you actually do well — and which do you skip even though you know better?
- The page's core tension: AI can scaffold self-regulation or short-circuit it by removing the regulatory demands that build expertise. How can a tool that makes a task easier also make you a weaker regulator of your own learning — and can you feel the difference in your own use?
- Students often show a 'production deficit': they possess self-regulation knowledge but fail to deploy it spontaneously — asking a chatbot to 'extract the main ideas' and skipping planning and monitoring entirely. Have you caught yourself doing the cognitive equivalent of this, even while knowing the better strategy?
- When support is present, your own judgment can drop out of the picture: in one trace-data study the available support, not the learner's metacognitive accuracy, was what determined the revision strategy chosen. If external help overrides your read on your own learning, which judgment would you deliberately keep in your own hands?
- Research found a 'miscalibration gap': students can *perceive* more learning with GenAI while retaining less — preferring AI over note-taking despite weaker retention. If you feel productive while using a tool, how would you ever discover that you're not actually learning more?
- Whether GenAI functions as a scaffold, shortcut, or partner depends more on the learner's regulatory capacity than on the tool itself. But the page also shows self-regulation buffers — yet does not cancel — the harm of deep cognitive offloading. What does that 'buffers but doesn't cancel' caveat mean for designing better AI tools?
- Set a goal before reading: pick one task you regularly use AI for, and decide in advance which of the three SRL phases (forethought, performance, reflection) you'll deliberately protect from being automated. What result will tell you it worked?

Introduction

SRL is the process whereby learners actively manage their own learning through three interrelated phases:

1. **Forethought:** Goal setting, strategic planning, Self-Efficacy beliefs
2. **Performance:** Strategy deployment, self-observation, attention focusing
3. **Self-reflection:** Self-Assessment, causal attribution, adaptation

Proficient self-regulated learners employ cognitive strategies to improve success and utilize Metacognition to refine their learning processes continuously.(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)

Empirical work in a technology-mediated course confirms the phase links: in an eight-week adaptive stochastics study (194 students), task value, self-efficacy, goal orientation and positive emotions in the pre-actional phase predicted actional regulatory behavior while negative emotions hindered it, and post-actional satisfaction fed forward into the next pre-actional phase (Mejeh & Fromm (2026)).

A systematic mapping of 84 AI–SRL studies found the research concentrated on higher-education students and on the metacognitive and cognitive aspects of self-regulation, with the motivational dimension underexplored and over a third of studies specifying no SRL theory at all (Banihashem et al. (2025)).

Crucially, SRL around AI is shaped by *perception* as well as behavior: Yilmaz et al. demonstrate that whether students perceive feedback as coming from AI or a human significantly affects their self-regulated learning and revision behavior — a reminder that the social framing of AI, not just its content, changes how learners regulate around it.

One failure mode sits before regulation begins: GenAI-assisted learning procrastination — unnecessary delay in starting GenAI-supported work despite a genuine intention to use it. Among 1,243 Chinese undergraduates, more frequent GenAI use went with less of it ($\beta = -0.195$), and learning GenAI anxiety strengthened the intention-delay link (Li et al. (2026)).

Where GenAI enters the cycle decides its effect: mapping Zimmerman's forethought, performance, and reflection phases onto AI-mediated environments, a co-agency framework argues the point of entry determines whether the tool amplifies or erodes the learner's sense of control, and that offloading supports transformative learning only when the decision is intentional rather than routine (Poudyal (2026)).

A cross-sectional survey of 434 Special Education undergraduates measures one such chain: GenAI literacy was positively associated with GenAI-assisted self-regulated learning behaviors (total B = 0.701), running mainly through learning Learner Agency (B = 0.345) rather than challenge emotions (B = 0.061) (Yang et al. (2026)).

Metacognitive self-regulation is a measured outcome, not an assumption, in Shao, Tang and Ju (2026), who found that an AI-VR flipped classroom raised it alongside achievement, and that learners with higher technological literacy benefited more.

Digital Support for SRL

Learning Journals

Learning journals are a promising SRL intervention: by reflecting on their learning processes, students increase awareness of cognition and strengthen regulatory capacity. Key design considerations:

- **Structure matters:** Open-ended journals often produce shallow entries; guided prompts and example models improve depth
- **Motivation decay:** Mobile journaling apps commonly see rapid engagement decline after a few days
- **Scaffolding trade-off:** AI assistance that writes reflections for students undermines the SRL practice; assistance that structures prompts without authoring content preserves it

Dashboards communicating SRL profiles to teachers

Mejia-Domenzain et al. (2026) extend digital SRL support to the teacher side: their Learning Analytics dashboard (DashED) communicates ML-derived self-regulated learning profiles to teachers in blended classrooms, and how teachers act on those profiles is context-dependent. In use, flipped-classroom (university) teachers followed a sequential exploration and favored course-level adaptation and showing dashboards in class, whereas vocational teachers revisited summary pages and used the tool mainly for individual coaching sessions. The actions teachers proposed were shaped by the content represented and their teaching level rather than the plot type — university teachers favored weekly tests and course adaptation, vocational teachers direct, individualized coaching. This positions the dashboard as a scaffold for teachers' regulation of instruction, with design needs that vary by context rather than a single optimal interface.

The student-facing counterpart is sparser: a dashboard that showed 46 secondary students their own GenAI prompts and their text overlap with the model's replies was opened by only about a third of the class, making voluntary exposure rather than the visualization itself the binding constraint (Fong et al. (2026)).

Scheu et al.'s 2×2 Experiment (2026)

In a randomized field experiment with 179 students over 22 days, two design principles were compared:

Principle	Mechanism	Effect on SRL	Effect on Motivation	Effect on Engagement
Example-based course	7-day curriculum Teaching reflective journaling via modeled responses	Increased perceived competence and enjoyment	**Positive**	Constant positive
Large Language Models (LLMs) journaling assistant	GPT-3.5 summarizes drafts, asks clarifying questions, suggests reformulations	No direct SRL skill effect measured	**No effect**	Increasing over time (feedback loop)

Key insight: The course improved SRL skills *and* intrinsic motivation through skill transfer, while the assistant improved engagement without affecting motivation.(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)

AI Tools and the SRL–Motivation Reciprocal Loop

A foundational principle of SRL theory is that self-AI Regulation in Education skills and Motivation form a **reciprocal relationship**:

- Better SRL → more successful learning → higher self-efficacy → stronger motivation
- Higher motivation → more effortful engagement → better SRL practice

AI tools can enter this loop at different points:

- **SRL-first design** (e.g., structured courses, graduated hints, reflection prompts): Strengthens the loop by building genuine skill
- **Engagement-first design** (e.g., autocomplete, content generation): May boost behavioral engagement without entering the motivation loop, risking tool dependence

Strategic Regulation of GenAI as SRL

Kim (2026) reframes effective GenAI use in academic writing as **strategic regulation** — an enacted SRL practice of verifying, revising, selectively adopting, or rejecting AI output. In a mixed-methods study of 107 students, higher AI anxiety was positively associated with verification and revision (β=.24), while evaluative capacity predicted active revision and selective integration (β=.46). Students clustered into four regulatory types — Uncritical Reliance (18.7%), Selective Integration (34.6%), Evaluative Transformation (31.8%), and Strategic Rejection (14.9%) — showing that AI Literacy in Higher Education functions less as acceptance than as regulatory competence grounded in Evaluative Judgment and ethical responsibility. This positions SRL as the core mechanism distinguishing critical from uncritical AI use.

Governance of the tool is itself a measurable facet: a two-wave validation with Chinese EFL learners (EFA N = 305; CFA N = 342) separates six regulatory dimensions and names *environmental regulation* — checking generated output for accuracy, filtering suggested resources, and setting boundaries on reliance — as one in its own right (Wang, Zhang and Zhang (2026)).

Classify before delegating: Tsim and Gutoreva (2025) turn self-regulation into a per-task protocol — label each subtask Substitute, Complement, Aid or Non-negotiable, justify it in a short metacognitive note, and keep an audit trail of prompts, drafts and human revisions — with the cycle repeating so one task's assignment informs the next. **Every prompt as a regulatory trace.** Reading 429 prompts from 23 students as self-regulated learning events showed the structure mix shifting with task design while 53 of 59 submissions stayed close to the model's output, locating regulation in the exchange rather than the artifact (Kontorovich & Wallach (2026)). **The interaction itself as an object of regulation.** Brunnström and Palmqvist (2026) document the same regulation demand from the other direction: in an eight-round demonstration using a chatbot to prepare a take-home examination answer, the AI's default output stayed at the *quantitative*, multistructural end of the SOLO taxonomy — polished, submission-ready and pedagogically thin — and reached a usable three-step learning loop only after repeated meta-level interventions ("this is overwhelming, can you condense it?"). Their conclusion is that productive use

required “the very self-regulatory skills the tool was expected to support”: the learner must set incremental goals, request difficulty adjustments, and reflect on what is not yet understood, on top of the disciplinary content itself. They name this capacity AI-interaction literacy and treat disengaging from the tool as a legitimate regulatory decision rather than a failure of persistence (Metacognition).

- **Satisfaction is not self-regulation.** Liang et al. (2026) surveyed 689 undergraduates in industry-education programs and tested a serial mediation model in which the perceived affordances of AI-generated content raise AIGC Self-Efficacy (beta = 0.583) and, through it, learning Motivation (beta = 0.565) and self-regulated learning (beta = 0.250), with motivation the heaviest single predictor of SRL (beta = 0.527). The load-bearing negative results sit alongside those paths: the quality of AI assessment feedback predicted satisfaction strongly (beta = 0.712) but not self-efficacy (beta = 0.131), and satisfaction had no significant effect on self-regulated learning (beta = 0.032). A well-liked, well-functioning assistant is therefore not evidence that regulation improved — the mechanism runs through confidence and motivation, not through the learner’s experience of the tool.

Dependency works through effort regulation, not use volume. In a survey of 982 undergraduates, GenAI dependency predicted lower effort regulation (β = −0.257), which predicted perceived learning outcomes (β = 0.497), giving a negative indirect path (β = −0.128) while frequency of use carried no significant total association (Li, Zhang and Yang (2026)).

GenAI-aware reflection as SRL

The 5P Reflection Model (Kadel et al. 2026) re-centers structured reflection in the GenAI era as an enacted SRL practice. SRL owns reflection only as one phase of its cycle; the practice itself — prompts, journals, portfolios and scored reflective text — is carried on the Reflection page, which also sets out where it differs from Metacognition and Self-Assessment. Learners increasingly co-create meaning with AI, and traditional reflection models struggle to authenticate what a student has done. The 5P model (Purpose, Process, Product, Pitfalls, Plan) fuses forethought-driven goal setting, reflection-in-action (documenting prompts and iterations), reflection-on-action (validating the probabilistic output against external sources), an explicit pitfalls stage for hallucination, plagiarism, and over-reliance, and a forward-looking plan — embedding emotional monitoring throughout. Its “process over product” philosophy treats structured documentation of the human-AI interaction as the regulatory demand that preserves authenticity, Learner Agency, and metacognitive depth, positioning GenAI-aware reflection as a scaffold for self-regulation rather than a substitute for it.

Relationship to Tutoring-Specific Design

Tutoring-specific AI aligns with SRL-first design: it provides graduated scaffolds that preserve Learner Agency and require strategic self-regulation. General-purpose AI often removes the regulatory demands entirely.(The Evidence Base on AI in K-12: A 2026 Review)

For example: - Bastani et al.’s tutoring-specific chatbot preserved step-by-step reasoning (SRL demand) - The general-purpose GPT variant simply provided answers (SRL bypass)

Evidence Across Contexts

- **Mixed evidence and the miscalibration gap.** A rapid review of PreK-12 GenAI research finds metacognitive gains during supported tasks often do not persist when support is removed, and that GenAI can increase perceived learning even when durable learning is absent (the miscalibration gap — students preferred GenAI over note-taking despite weaker retention). Students need explicit, stage-appropriate training to decide what to delegate and when independent effort matters.(Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education)
- **SRL is rarely the active target.** Across 394 GenAI higher-education studies, self-regulated learning and reflection were among the least frequently enacted uses and among the outcomes targeted least (Lin et al. (2026)).
- **Agentic initiative vs. self-regulation tension.** Woollaston et al. (2026) note that as agents automate more of a task, the less self-regulated cognitive work the learner performs — so designs should give learners control over agent initiation (dynamic, fading scaffolding) to preserve self-regulatory capacity rather than outsourcing it.
- **Self-regulation shapes AI coding-assistant use.** A study of AI coding assistants found high-Computational Thinking students showed stronger self-regulatory coherence (planning-execution-self-reflection) and used AICA for code understanding, while low-CT students used it for immediate answer retrieval.
- **SRL co-occurs with lower digital distraction in online learning.** Shi et al. (2026), using unsupervised data mining on 530 college students, found that SRL strategies — goal setting, environment structuring, and time management — co-occurred most consistently with lower digital distraction in online learning, alongside learner-instructor and learner-content engagement. The finding positions concrete SRL training as a high-leverage intervention for focused online study.
- **Metacognitive awareness, not tool access, is the strongest driver of adaptive STEM performance.** Alatoai and Alshahri (2026) built and validated the AI-STEM-MLCS with 649 secondary students in Saudi Arabia (CFI = 0.983, RMSEA = 0.019; McDonald's $\omega = 0.888$ to 0.905) and found its four dimensions explained 68% of the variance in self-regulated learning performance ($R^2 = 0.68$). AI-based metacognitive awareness was the strongest predictor ($\beta = 0.38$, $p < 0.001$), followed by cognitive transfer and adaptability ($\beta = 0.29$, $p = 0.008$) and AI-enhanced self-regulated learning ($\beta = 0.21$, $p = 0.040$), while creative and critical AI-STEM reasoning did not predict the criterion ($\beta = 0.14$, $p = 0.135$). The authors read the pattern as evidence that adaptive feedback raises STEM performance mainly by prompting learners to examine errors, recalibrate, and reuse strategies, so the instrument works better as a diagnostic that locates meta-learning gaps than as a single global score. It is a self-report measure validated in one national system, so the coefficients are provisional.
- **External support can bypass a learner's own metacognitive judgment.** Iqbal et al. (2026) traced 87 EFL students revising an essay under GenAI (ChatGPT 4.0), human-expert, or no support. The support condition was by far the strongest correlate of the revision strategy a student

chose (Cramér's V = 0.668), well ahead of carry-over from the preceding writing task (V = 0.333), while metacognitive judgment accuracy (p = 0.172), writing skill (p = 0.261) and Motivation (p = 0.683) were unassociated. Metacognitive judgment tracked strategy only when no support was available (permutation test p = 0.0460). Students with GenAI support gained the most (about 4 points on average under the decreasing-help-seeking strategy, against −0.5 points for the same strategy under human-expert support), yet no revision strategy was associated with score change (H(3) = 3.895, p = 0.273), so the gains came from the tool rather than from better self-regulation. The authors' orientation is that GenAI should prompt reflection on one's revision strategy instead of supplying direct help.

- **Reflective use tracks critical thinking, not knowledge gain.** Melanou et al. (2026) followed three parallel classes of business informatics students (N = 87) across a nine-week course, with knowledge rising in every group ($F(1, 50) = 29.87$, $p < 0.001$, $\eta^2p = 0.374$) and no AI advantage, no Time × Group interaction, and no Matthew effect ($F(1, 48) = 2.46$, $p = 0.124$; BF01 = 8.70). Reflective use (checking sources and verifying AI output before adopting it) was markedly higher in the AI condition (3.72 vs 2.82; $F(1, 40) = 20.21$, $p < 0.001$) and predicted critical thinking ($\beta = 0.43$, $p < 0.001$) but not knowledge gain, which germane cognitive load did predict ($\beta = 0.51$, $p = 0.001$). The practical reading is that AI access is not itself an intervention, and that its metacognitive payoff surfaces in reasoning quality before it surfaces in test scores.
- **Structure, not AI alone, drives SRL gains.** Mapping Zimmerman's phases onto project-based hybrid instruction with AI as metacognitive scaffolding produced an N-Gain of 0.72 versus 0.28 for conventional instruction ($t = 8.47$, $p < 0.001$, Priyambudi et al. (2026)), who argue AI strengthens self-regulation only inside task structure — unstructured use risks metacognitive laziness.
- **AI speed can displace the peer dialogue that carries co-regulation.** Coding 28,123 forum sentences across four graduate courses, one human-only and two with heavy AI TA use, Davis et al. (2026) found the AI TA was first responder in 97% of student-started assignment threads, with a median 0.92 minutes to its reply against 490 when a peer replied first. Thread starts were unchanged ($p = .73$) but reply posts fell from 18.2 to 10.9 per student ($p < .001$), and peer repliers' share of follow-up sentences dropped from 91% to 45% between semester halves.
- **The resulting SRL decline is compositional.** Because peer repliers supply about 70% SRL-coded sentences against 20 to 27% for thread starters, aggregate regulatory language fell from 49% to 36% ($p < .001$). Each role's own rate held steady, so the drop reflects who was writing rather than a change in how individuals write. Self-regulation still predicted grade ($\beta = 2.63$, $p = .017$), and peer replies moderated that relationship ($\beta = 1.45$, $p = .013$). The grade penalty attached to AI-dominated threads ($\beta \approx -1.38$, $p = .038$) then vanished once 17 high self-regulators were removed ($\beta \approx -1.29$, $p = .454$), which the authors read as the cost running through lost co-regulation rather than through the AI directly. It is observational, so the mechanism stays unproven.
- **Emotional scaffolding moves trace-measured SRL phases that cognitive scaffolding alone does not, and self-report barely sees it.** A preregistered experiment with 144 high school students compared plain ChatGPT, an SRL-scaffolding agent and an emotional version that asked about feelings at three points and adapted tone and challenge along control-value lines. Trace

coding found large condition effects in all three phases (ε2 = 0.44 forethought, 0.34 performance, 0.34 self-reflection). SRL prompts alone lifted goal setting and planning to the emotional version's level, while the emotional layer added more performance-phase activity (r = 0.22) and self-reflection (r = 0.31). Self-reported SRL separated the conditions only in the performance phase; trace-self-report correlations were 0.313 there, 0.22 for forethought and 0.04 for self-reflection. The authors read the trace differences as co-regulated enactment rather than independent regulatory capacity (Diordiev, Stenberdt & Makransky, 2026).

- **In groups, regulation is triggered by the AI's own prompt, and preconception diversity changes how that prompt lands.** Wang et al. (2026) compared 8 different-preconception and 6 similar-preconception pre-service teacher groups working with an on-demand metacognitive chatbot and a proactive voice agent. Prompt function converged across conditions at 39 prompts, 18 against 21, while sequential structure did not: diverse groups sustained positive or neutral evaluation of the output and similar groups sustained negative evaluation alongside recurrent task agreement. Raw-data inspection traced part of the negative loop to the proactive speaking agent, so the authors read it as a timing and modality mismatch rather than a rejection of support. Their design implication is that shared-regulation support in groups that have already converged should stay optional.

LLM-Mediated SRL: Scaffold, Shortcut, or Partner?

A cluster of Learning Letters studies (2026) converges on a central tension: GenAI can scaffold, short-circuit, or partner with self-regulation depending on design and how learners regulate its use. The evidence points to SRL itself — not the tool — as the decisive variable.

- **Viberg et al.** find that LLMs are woven into a *layered Help-Seeking ecosystem* rather than replacing human support: students try tasks independently first, then consult ChatGPT as a low-barrier first step, peers for conceptual negotiation, and instructors for high-stakes issues. They favor **instrumental help-seeking** (hints, step-by-step guidance) over **executive help-seeking** (direct solutions), exercising selective Trust and verifying outputs against course materials — a four-stage process (deciding whether help is needed, choosing whom to ask, determining the type of help, judging the help received) that can be measured and taught.
- **Atif & Dickson-Deane** frame GenAI use as **Cognitive Offloading** that can be either *scaffolded* (learners critique and adapt AI outputs, keeping Learner Agency and sense-making) or *substitutional* (learners accept outputs with minimal verification, shifting control to the tool). In a study of 267 postgraduate IT students, the same tool could scaffold or shortcut SRL depending on learner strategy — confident users showed agency in goal setting and monitoring; less confident users saw GenAI as a shortcut or misconduct.
- **Lim & Bannert** show the risk concretely: students voluntarily used a genAI chatbot (73%) and scored higher on essays, but they offloaded comprehension and synthesis (asking the chatbot to "extract only the main ideas") and engaged in almost no planning or monitoring — outsourcing key regulatory decisions. This reflects a **production deficit**: students possess SRL knowledge but fail to deploy it spontaneously, so genAI tools should prompt reflection (a monitoring scaffold) when queries indicate offloading.

- **Song et al.** demonstrate that SRL is both a **stable aptitude and a dynamic state**: individual baselines are consistent, but metacognitive knowledge and Well-Being decline systemically over a semester, driven by assessment deadlines. They show GenAI can act as a context-aware **learning partner** when it is given personal, temporal, and contextual data — supporting students without replacing their effort. This argues against "one-time-fits-all" personalization based on baseline aptitude alone.
- **de Barba** extends SRL theoretically, arguing the field has narrowed to task-focused regulation and to optimizable behavioral proxies in educational technology. The paper proposes a cross-scale account of **learner agency** — regulation (within tasks), integration (across time and contexts), and positioning (critically in relation to the conditions framing learning) — as a design orientation for algorithmically mediated environments.
- **Self-regulation buffers but does not cancel offloading harm.** Chen (2026) shows that self-regulated writing attenuates — but does not eliminate — the negative association between deep Cognitive Offloading and independent no-AI outcomes in GenAI-assisted writing: the offloading-by-SRL interaction was positive (B = 0.22), flattening the harm from a slope of −0.54 (low SRL) to −0.33 (high SRL) but not canceling it. A bounded-support condition pairing delegation limits with compulsory reflection produced the strongest independent performance, evidence that metacognitive regulation partially protects learners yet cannot fully compensate for delegating the cognitive work itself.

Where rental sits inside Winne's models. de Barba (2026) maps the mechanism onto SRL as operations the system performs in the learner's place: noticing, monitoring and evaluative judgment are exercised by the tool, an impasse is resolved by search rather than by the learner's own If-Then, Else choice, and the standards by which the learner judges are borrowed rather than built. A capability that a learner believes they hold while the tool holds it — *hidden rental* — suppresses the error signal that would otherwise prompt regulation, and ten propositions specify what to test, including larger costs in domain acclimation and standards drifting toward the model's own reference points.

The collective lesson: **SRL is the core mechanism distinguishing critical from uncritical AI use.** Whether GenAI functions as a scaffold, shortcut, or partner depends on learners' regulatory capacity and on whether tools are designed to preserve (rather than remove) the regulatory demands that build expertise.

Which support is in play decides which mediator carries the association: among 3,003 Chinese pre-service teachers, perceived AI tool support ran to innovative competence mainly through AI Self-Efficacy (60.88% of that path's total effect), while perceived school-based intelligent environment support ran mainly through self-regulated learning (29.64% versus 18.60%) (Liu et al. (2026)).

Implications

- **For journaling/chatbot tools:** Combine SRL instruction (course-based) with optional writing support to get both motivation and engagement gains
- **For tool designers:** Make evaluation a required step, not an optional one. Iqbal et al. found that the available support, rather than the learner's metacognitive judgment, decided the revision strategy students used and that GenAI score gains did not come from better regulation, while Melanou et al. found reflective use predicted critical thinking where mere tool access did not.

Interactions that ask learners to verify, compare, and re-strategize are the ones carrying the learning value.

- **For instructors:** Treat AI-based metacognitive awareness as the first lever and check it explicitly. Alatoai and Alshahri found it the strongest predictor of adaptive STEM performance (β = 0.38) and that transfer and adaptability came second (β = 0.29), so activities that have students examine errors and carry a strategy into a new problem context do more than general prompting for critical or creative reasoning.
- **For AI policy:** Procurement criteria should ask whether a tool develops or displaces self-regulation
- **For researchers:** Long-term studies measuring SRL outcomes (not just immediate performance) are essential; Melanou et al. show the payoff of that patience, since a semester's reflective use moved critical thinking (β = 0.43) without moving knowledge gain.

Conversational Agents and SRL in Simulation Games

- **Conversational agents supporting self-regulated learning in games.** Wenzel, Geiger, and Liening (2026) show that an AI conversational agent (Lara) in a business Simulation game can support self-regulated learning through metric-based formative feedback, on-demand guidance, and structured reflection — addressing the common limitation that simulation games provide limited formative feedback and reflection prompts. Evaluations with student teachers and BSG participants reported positive perceptions of the agent's cognitive and social presence and its support for self-regulation.

Automated SRL Detection: What Transfers and What Doesn't

- **Embedding-based SRL classifiers cross languages within a domain, but not across domains.** A study of 26 students (chemistry and formal logic; think-aloud protocols coded with the Winne-and-Hadwin model) found embedding-based models (text-embedding-3-small) trained on English classify German SRL at ~0.8 AUC with ~0.1 degradation — except enacting (~0.7). Cross-domain transfer fails: chemistry-to-logic drops to ~0.6, enacting to chance (~0.5) — the domain wall, not language, binds.
- **Three failure modes explain where transfer breaks.** (1) Concept resolution at everyday rather than domain meaning — "cancel" vs. chemistry "kürzen" — breaks enact classification. (2) Anthropomorphization — German students unfamiliar with a heavily scaffolded tutor addressed it as a person, producing out-of-distribution utterances; transfer was better on less-scaffolded platforms. (3) Hint-reading vs. plan-formulation ambiguity — models can't tell reading a metacognitive hint from planning without log data. Realizing errors is robust across every condition — noticing you're wrong is context-independent. Fixes: expert dictionaries or fine-tuning for domain terms; log data for hints. (Large language models generalize SRL prediction to new languages within but not between domains)
- **Shallow cues over-attribute regulation in curriculum mapping.** Given assessment descriptions, GPT-o3-mini read mentions of deadlines or scheduling as evidence of a self-regulatory skill; Self-

Management was over-identified this way, its agreement with expert weights ranging from 0.53 to -0.03 (Jayalath et al., 2026).

- **Structured question chains turn prompting into regulation.** In a quasi-experiment with 83 undergraduates, both question-chain conditions produced more learning-strategy and monitoring behavior than free-form questioning ($\chi^2 = 6.551$, $p = .038$) and scored higher on metacognitive awareness and achievement ($F = 3.406$, $p = .038$; $F = 3.807$, $p = .035$), with no difference between the chain forms (Lin et al., 2026). Sequencing is what does the work.
- **Group-level detection follows the same split, and talk carries more than logs.** In dyads modeling a truck's motion in C2STEM, 394 task-context segments from 36 high schoolers were labeled with seven socially shared regulation codes and predicted from LLM summaries of each segment: text-only embeddings reached mean AUC 0.650 while log-derived features alone reached 0.526, near chance for a construct that is largely social. Planning was invisible within a single segment (0.5036) and became detectable once the two segments on either side were concatenated (0.6711), whereas reflecting was best once the logs were added (0.5862), the same hint-reading-versus-plan ambiguity this section records for individual learners (Zhang et al., 2026).
- **Automated SRL labels hold for enacting and fail for planning.** In a fourth-grade mixed-reality science class, a pipeline fusing gaze, gesture, speech and game logs labeled 75 human-checked segments at 74.67% overall, from 93.3% for enacting and interacting down to 46.7% for planning (Fonteles et al., 2026).

Common Misconceptions

- **"Self-regulation is a learner trait."** Regulated learning decomposes into **self-reflection, causal attribution and adaptation**, and proficient learners **employ cognitive strategies to improve success**. These are trainable processes that a design can support or undermine.
- **"Any adaptive design supports regulation equally."** Scheu et al.'s **2x2 randomized field experiment with 179 students over 22 days** compared two design principles and found them different in mechanism, so "adaptive" is not a single treatment.
- **"Anxiety undermines regulation."** In a mixed-methods study of **107 students**, higher AI anxiety was **positively associated with verification and re-checking**. Anxiety functioned as a prompt to verify, which is regulation rather than its absence.
- **Metacognitive SRL predicted learning-relevant load where the AI feedback did not.** In a five-week field study with **234 students and 1,147 observations**, metacognitive self-regulation was a substantial positive predictor of **germane cognitive load** ($\beta = .363$, $p < .001$ intention-to-treat; .346, $p < .001$ usage-based) and did not significantly predict extraneous load — while mere access to conversational AI feedback predicted neither. Only **sustained** engagement with the feedback separated students on germane load, and irregular use did not ($\beta = -.219$, $p = .116$), which locates the active ingredient in the learner's regulation of processing rather than in the feedback supply (Wenzel, Geiger and Liening, 2026).

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Metacognition — the cognitive monitoring SRL relies on
- Self-Assessment
- Self-Efficacy — a forethought-phase belief driving effort
- Scaffolding — graduated support that preserves regulatory demand
- Feedback — input learners regulate around
- Feedback Literacy — the capacity to act on feedback
- Help-Seeking — a strategic SRL behavior
- Motivation — the reciprocal partner of self-regulation
- Cognitive Offloading — the risk when AI removes regulatory work
- Generative AI — the technology that can scaffold or short-circuit SRL
- AI Literacy — regulatory competence in AI use
- Self-Directed Learning — the broader autonomy construct
- Learner Agency — the learner's capacity to act with intention, central to regulation, integration, and positioning
- Adaptive Learning — personalization that can support regulation
- Formative Assessment — continuous feedback for regulation
- Learning by Teaching — a strategy building self-regulation
- Intelligent Tutoring — systems that scaffold SRL
- Large Language Models (LLMs) — the underlying model of AI tools
- Retrieval, Spacing and Interleaving — scheduling, self-testing and study-strategy choices learners make
- Cognitive Surrender
- Reflection

Connected Articles

- Generative AI dependency and perceived learning outcomes among university students: an indirect association involving effort regulation — Generative AI dependency and perceived learning outcomes: the effort-regulation pathway (Li, Zhang & Yang 2026)
- Analyzing embodied learning in classroom settings: A human-in-the-loop AI approach for multimodal learning analytics — Per-category accuracy of LLM-segmented SRL in an embodied classroom (Fonteles et al. 2026)
- What the submission does not show: Complexifying cognitive offloading in students' mathematical work with LLMs — What the submission does not show: complexifying cognitive offloading in students' mathematical work with LLMs (Kontorovich & Wallach 2026)

- Leveraging GenAI models for Curriculum Analytics: A Human-Centered Approach for Curriculum Mapping in Higher Education — Model over-attribution of self-regulation from shallow cues in curriculum mapping (Jayalath et al. 2026)
- AIGC affordance and student self-regulation in private undergraduate education: a serial mediation model of self-efficacy and learning motivation — AIGC Affordance and Student Self-Regulation
- AI-interaction literacy: reflections on how generative AI might be used to support self-regulated learning in higher education — AI-interaction literacy: steering a chatbot demanded the SRL it was meant to support (Brunnström & Palmqvist 2026)
- The 5P Reflection Model for Education in the Generative Artificial Intelligence (GenAI) Era — The 5P reflection model for the GenAI era (Kadel et al. 2026)
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education
- Learner Agency Across Scales: An Integrative Perspective on Self-Regulated Learning in Algorithmically Mediated Environments — Learner agency across scales: regulation, integration, positioning
- The rented self: How AI-enabled tools decouple performance from becoming — The rented self: rental mapped onto Winne’s SRL models, with ten propositions and within-learner indices
- GenAI as a Learning Partner: Supporting Self-Regulated Learning Over Time Without Replacing Effort — GenAI as a context-aware learning partner over time
- How Do Students Regulate Their Learning With a GenAI Chatbot? — How students regulate learning with a genAI chatbot
- Scaffold or Shortcut? Postgraduate IT Students’ Use of Generative AI and Self-Regulated Learning — Scaffold or shortcut? GenAI dual role in SRL
- Efficiency vs. Effectiveness: Self-Regulated Learning with LLM-Mediated Help-Seeking — LLM-mediated help-seeking in STEM: layered, instrumental, and verified
- Your Brain on ChatGPT: Accumulation of Cognitive Debt when Using an AI Assistant for Essay Writing Task
- Fostering self-regulated learning through adaptive learning technology: A differentiated perspective on the role of feedback
- A systematic mapping review at the intersection of artificial intelligence and self-regulated learning
- Supporting self-regulated learning through generative AI feedback in online higher education: the importance of student perceptions of the source of feedback — GenAI feedback and SRL: perceived source matters

- From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource — From AI anxiety to strategic regulation
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Mixed evidence on metacognition/self-regulation with GenAI
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — Agentic AI and the self-regulation tension
- Decreasing Digital Distraction in College Students: Associated Online Learning Strategies Identified by Unsupervised Data Mining Approaches — SRL and lower digital distraction in online learning (Shi et al. 2026)
- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms
- SCAN: A Decision-Making Framework for Task Assignment with Generative AI — SCAN: a learner-facing loop of task identification, justification and post-task reflection
- Using Learning Analytics to Support Secondary School Students' Writing with Generative AI — Using Learning Analytics to Support Secondary School Students' Writing with Generative AI
- Exploring the Impact of AI-Based Learning Environments on Student Self-Regulation and Adaptive STEM Learning — A validated instrument for AI-supported self-regulation in adaptive STEM learning, with metacognitive awareness as the strongest predictor
- Human or GenAI Support? Conditions Impacting Students' Strategy Choices in an Essay Revision Task — Support condition, not metacognitive judgment, drove revision strategy choice in an essay-revision experiment
- Generative AI and Learning Dynamics in Higher Education: A Longitudinal Empirical Study — Longitudinal: reflective AI use predicted critical thinking but not knowledge gain, with no Matthew effect
- GenAI literacy and GenAI-assisted self-regulated learning behaviors: the roles of learning agency and challenge emotions — GenAI literacy related to self-regulated learning behaviors mainly through learning agency
- Pre-Service Teachers' Perceptions of AI Technological Support and School-Based Intelligent Environment Support: Model-Based Indirect Associations with Innovative Competence via AI Self-Efficacy and Self-Regulated Learning — Support type flips the mediator: AI self-efficacy vs self-regulated learning
- GenAI Use and GenAI-Assisted Learning Procrastination in University Students: The Roles of Planned Behavior Constructs and Learning GenAI Anxiety — GenAI-assisted learning procrastination: an intention-behavior gap that anxiety strengthens
- Generative artificial intelligence-supported self-regulated learning (GenAI-SRL) in L2 writing: scale development, validation, and short-form construction — A validated six-dimension GenAI-SRL scale for L2 writing, with environmental regulation as its own dimension and a 12-item ant-colony-optimized short form

- Large language models generalize SRL prediction to new languages within but not between domains — Large Language Models Generalize SRL Prediction to New Languages Within But Not Between Domains (Borchers et al. 2025)
- A Project-Based Hybrid Learning Model Using Artificial Intelligence to Enhance Students' Self-Regulated Learning — A Project-Based Hybrid Learning Model Using Artificial Intelligence to Enhance Students' Self-Regulated Learning
- AI teaching assistants in online discussion forums and peer-supported self-regulated learning — An AI TA as first responder displaced peer replies, and with them the co-regulation that amplified the grade value of self-regulation (Davis et al. 2026)
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — Preconception diversity changed how a metacognitive prompt landed: same prompt functions, opposite sustained evaluation of the AI output (Wang et al. 2026)

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Should I Use AI to Study and Learn Effectively?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Self-Determination Theory

> **Self-Determination Theory (SDT)** — a psychological theory of human motivation positing that intrinsic motivation and Well-Being depend on satisfying three basic psychological needs: autonomy, competence, and relatedness. In AI in education, SDT provides a framework for designing AI tools and professional development that support rather than undermine learners' and teachers' motivation.

Questions to Consider

- The theory claims motivation isn't just how *much* you have but a *quality* shaped by the environment, built on three needs: autonomy, competence, and relatedness. Think of a learning experience that drained you. Which of those three needs was violated, and what would have restored it?
- A year-long study found three motivational profiles — Disengaged, Developing, Self-Determined — that were stable over time, and students who reached the Self-Determined profile showed the greatest AI-literacy gains. Before you read, is motivation something students bring with them, or something a well-designed environment can grow? What does 'developmental, not fixed' imply?
- If an AI tool makes every task effortless and 'easy to use,' which psychological need might it be satisfying — and which might it be quietly undermining? How could a tool that boosts short-term engagement still erode long-term motivation?
- Need-supportive professional development for teachers enhanced their AI literacy and sustained engagement. Does this suggest that how we *train* educators about AI matters as much as what the AI itself does? What would 'autonomy-supportive' AI training for you personally look like?
- A study found ChatGPT could support autonomy, relatedness, and competence in language learning. But could the same tool undermine those needs for a different learner? What would need to be true about *how* it's used for the theory to hold?
- Before reading further, name one way you've felt your own competence, autonomy, or sense of connection affected by using an AI tool — and reflect on whether you'd have noticed that change without being prompted to look for it.

Introduction

SDT is increasingly used in AI in education research as a theoretical lens for both learner-facing and teacher-facing AI systems. The theory's central claim — that motivation is not simply a quantity learners have but a quality shaped by the social and technological environment — makes it directly relevant to questions about how AI tools affect engagement, persistence, and learning outcomes. The articles in this knowledge base apply SDT across three main contexts: teacher professional development, AI-mediated learning engagement, and affective computing.

Key research themes

SDT-based teacher professional development applies the theory's need-supportive principles to prepare educators for AI. **Chiu et al.** studied 382 secondary school teachers, finding that need-supportive professional development grounded in SDT enhances teachers' AI Literacy and fosters sustained behavioral engagement in online professional learning communities. Qualitative analysis identified nine design strategies supporting autonomy, competence, and relatedness — bridging the gap between isolated professional development and professional learning communities.

SDT in AI-mediated learning engagement examines how generative AI tools shape student motivation. **Isaeva et al.** combined SDT with epistemic network analysis to study students' engagement with generative AI in academic learning. **"Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming** explores how AI availability affects student motivation and persistence, connecting to Over-Reliance concerns about motivation erosion. **Liang et al. (2026)** extend SDT to AI learning with a latent transition analysis of **2,086 secondary students** in a year-long AI curriculum, identifying **three motivational profiles (Disengaged, Developing, Self-Determined)** that were stable across time and showing that most students maintained or advanced toward higher profiles. Crucially, students who reached or remained in the Self-Determined profile showed the **greatest AI Literacy gains** — direct longitudinal evidence that satisfying autonomy, competence, and relatedness predicts better AI-learning outcomes, and that motivation is a developmental (not fixed) learner property.

A contrasting classroom result shows the needs do not move together: among 2,464 lower-secondary students, ChatGPT-supported competency-based learning raised autonomy support and competence satisfaction yet produced a larger share of low-quality motivational profiles, and relatedness satisfaction was weaker than in non-AI competency-based learning (Schweder, Hagenauer & Raufelder (2026)). - **Availability is not usage.** With 406 students in Grades 5–8 writing twice, once without digital tools and once with GenAI optional, autonomy satisfaction fell ($\Delta = -0.28$) while mean regulation stayed stable and degree of AI use predicted no profile membership (Schweder & Grahl (2026)).

Autonomy, not ease, carried the motivational gain here. A three-arm RCT found that a hint-withholding tutor, which kept learners building their own solution, was the only arm to raise intrinsic motivation (2.82 vs 2.42), while unrestricted ChatGPT, which supplies the answer, did not (2.64, $p = .076$) (Bassner et al. (2026)).

A configurational test sharpens the point: among 498 medical undergraduates, GAI use was only weakly associated with need satisfaction ($\beta = 0.155$) and proved unnecessary for high engagement, while competence need satisfaction was the core condition in the strongest configuration (He et al. (2026)).

Dual pathways from learning climate to AI use. Shen and Arunrugstichai (2026) integrate SDT with the Hook model of behavioral engagement to explain why GenAI use ranges from constructive support to compulsive dependence. In cross-sectional survey data from **508 university students** with different high-school backgrounds and current contexts (China and Thailand), retrospective reports of **high-school pressure vs. autonomy support** differentially predicted which of two pathways students followed into university — one toward constructive, autonomous GenAI use and another toward compulsive dependence — with results consistent across cross-contextual multi-group analyses. The model links SDT motivational

processes to perceived quality of AI-supported learning, framing autonomy support as a lever that steers students toward productive rather than dependent AI use.

- **ChatGPT and SDT needs in language learning:** Annamalai et al. (2026) used an SDT lens with 25 Malaysian university students, finding that ChatGPT supports autonomy, relatedness, and competence in English language learning — enhancing grammar, writing, and conversational tasks while letting educators focus on higher-order training.

SDT applied to instructors' own AI-mediated practice. Claassen et al. (2026) used SDT as the interpretive lens on how instructors integrate learning analytics and generative AI into learning design — finding that supporting instructors' basic needs (autonomy, competence, relatedness) fosters the creative Problem Solving their design work requires. In their ENA analysis, GenAI use was associated with designing for student self-determination (e.g., co-creating assessment rubrics with students), extending SDT from learners to the educators who build need-supportive AI-mediated environments.

For teachers themselves, AI collaboration cuts both ways: a three-wave study of 468 university teachers found it raised work engagement through psychological availability while lowering it through work alienation, and digital competency strengthened the first path and weakened the second (Sun et al. (2026)).

A co-agency framework bounds SDT's reach in AI-mediated education: it changes the circumstances under which autonomy, competence, and relatedness arise but leaves equity of power, data ownership, and accountability unaddressed, which is why its authors set human epistemic accountability as a non-negotiable condition outside the theory (Poudyal (2026)).

Autonomy support as the frame for children's GenAI use. Fan, Li and Zhang (2026) relocate the question of responsible use from restriction to need support, arguing that the distinction that matters is whether adults around a child support autonomy rather than control it, and distinguishing dependent from autonomous Cognitive Offloading within SDT terms. Dependent offloading transfers Learner Agency and lowers intrinsic motivation; autonomous offloading scaffolds while the learner retains epistemic control. Two features of the review are directly relevant to SDT application: it insists that autonomy support is not permissiveness, and it treats the family-school coordination that current guidance assumes as an untested hypothesis, formalizing additive, synergistic and compensatory versions that only a factorial trial contrasting family-only, school-only, coordinated and usual-practice guidance could discriminate.

Connections to related concepts

SDT connects directly to Motivation as its parent construct, to Affective Computing and Affective Tutoring for emotion-aware AI design, and to Student Experience for how learners experience AI-mediated environments. The theory's emphasis on autonomy connects to Self-Regulated Learning, while its competence dimension connects to Self-Efficacy and Favorability Shape Learning from Tutoring Systems and Paper Practice and Teacher AI Competency. SDT is particularly relevant to Workplace Learning and Educational Development because need-supportive design is a transferable principle for preparing educators to use AI.

The three needs are not exercised evenly by generative-AI research. Pan, Abuhassna and Jiang (2026) coded 39 studies against a 20-activity classification and found 14 activities present, with seven competence-related types against five for autonomy and two for relatedness. Six activities were absent from every study,

and most ask the student to judge or challenge the tool: creating challenging problems, anticipating the tool's outputs, grading those outputs and debating with it. Relatedness is the need the literature least tests.

Common Misconceptions

- **"Motivation type matters less than motivation amount."** A year-long study found **three motivational profiles — Disengaged, Developing, Self-Determined — stable over time**, and students who reached the **Self-Determined** profile showed the **greatest AI Literacy gains**. The quality of motivation predicted the learning, and the profiles did not simply drift upward.
- **"Autonomy support means removing structure."** The SDT mechanism is autonomy, competence and relatedness together, and the longitudinal evidence shows that satisfying them predicted gains rather than merely accompanying them. Autonomy without competence support is permissiveness, and it does not satisfy the theory's conditions.
- **"A chatbot can supply the three needs automatically."** A study found ChatGPT could support autonomy, relatedness and competence in language learning — a possibility, not a property. Whether a given interaction supports them is an empirical question about how it is used.

Connected Concepts

- Motivation
- Student Experience
- Affective Computing
- Affective Tutoring
- Self-Regulated Learning
- Teacher AI Competency
- Educational Development
- Workplace Learning
- Cognitive Offloading
- Student Engagement
- AI in Education
- Learning Theories

Connected Articles

- Family-school autonomy support for children's responsible use of generative artificial intelligence: a self-determination theory synthesis and developmental research agenda — Family-School Autonomy Support for Children's Responsible Use of Generative AI
- How high-school pressure and autonomy support are linked to dual AI learning pathways: A cross-contextual SEM analysis — High-school pressure/autonomy support and dual AI learning pathways (Shen & Arunrugstichai 2026)
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education

- Understanding the Role of Learning Analytics and Generative Artificial Intelligence on Decision-Making and Learning Design Practice in Higher Education — LA and GenAI in learning design decision-making
- Teacher education for artificial intelligence literacy through a self-determination theory perspective
- Students' engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study
- "Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming
- Students' experiences of using ChatGPT for English language learning: A qualitative study in a Malaysian higher education institution — Students' ChatGPT experiences in English language learning
- Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons — Learner characteristics × TTS dialogue-format interactions
- From disengaged to self-determined: a latent transition analysis of students' AI learning motivation — SDT latent transition analysis of students' AI learning motivation (2,086 secondary students)
- Student motivation and need satisfaction in GenAI-supported classrooms: A self-determination theory perspective — Student motivation and need satisfaction in GenAI classrooms (Schweder, Hagenauer & Raufelder 2026)
- Generative Artificial Intelligence Use and Learning Engagement Among Medical Undergraduates: Statistical Indirect and Configurational Associations Involving Basic Psychological Need Satisfaction — GAI use is weakly tied to need satisfaction and unnecessary for high engagement (He et al. 2026)
- The Double-Edged Sword Effects of Teacher–AI Collaboration on Work Engagement: A Self-Determination Theory Perspective — Dual pathways from teacher–AI collaboration to work engagement, moderated by digital competency
- Less stress, better scores, same learning: The dissociation of performance and learning in AI-supported programming education — Hint-withholding preserved autonomy where answer-giving did not
- Motivational organization in AI-supported writing: A self-determination perspective — AI availability, autonomy decline and motivational profiles in Grades 5–8 (Schweder & Grahl 2026)
- Generative AI and student motivation: an SDT-guided systematic review of learning activities, motivational regulation, and measurement - 39 studies coded against a 20-activity classification; competence exercised most, relatedness least

Motivation

> **Motivation** — the psychological processes that initiate, direct, and sustain goal-directed behavior. In AI in education, motivation research examines how AI tools affect learners' and teachers' motivation — whether AI scaffolds or undermines persistence, curiosity, and intrinsic engagement — and how motivational states shape the effectiveness of AI-mediated learning.

Questions to Consider

- Motivation is often treated as a trait some students 'have' and others lack. The page describes it instead as psychological processes that initiate, direct, and sustain behavior — and as something developmental and socially scaffolded. How does that reframe who is responsible for student motivation?
- AI tools can remove friction and make learning more accessible, but they can also reduce the cognitive effort and struggle that support intrinsic motivation. When has making something 'easier' actually made it less motivating or less satisfying for you?
- Self-determination theory says intrinsic motivation grows from autonomy, competence, and relatedness. If an AI tutor does most of the work, which of those three might it threaten — and which might it enhance?
- Research finds distinct motivational profiles among students in an AI curriculum, and that reaching a self-determined profile predicted the largest AI-literacy gains. What might it take for a learner to move from passively disengaged to genuinely self-determined in using AI?
- The page reports that teacher support drives AI-assisted engagement largely through mastery-approach and performance-approach goals — the 'approach' rather than 'avoidance' orientations. How does the way a teacher frames AI use ('to get it right' vs. 'to avoid looking wrong') shape whether students engage deeply?
- If you're designing for motivation, is the goal to make learning easier, more engaging, or more meaningfully effortful? Where do Accessibility and intrinsic motivation pull in opposite directions?

Introduction

Motivation is a foundational construct in education research, and the rise of AI in education has made it more consequential: AI tools can remove friction and make learning more accessible, but they can also reduce the cognitive effort and struggle that support intrinsic motivation and deep learning. The articles in this knowledge base explore motivation across learner-facing AI tools, teacher-facing AI systems, and the psychological mechanisms — self-determination, self-efficacy, emotions — through which AI shapes motivated behavior.

- **Lee & Wu** show gender and motivation drive differential engagement with GenAI, with distinct achievement trajectories.

Key research themes

AI effects on student motivation is the most direct line of research. **"Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming** examines how the availability of AI assistance affects student motivation and persistence, connecting to Over-Reliance research on motivation erosion when AI does the work. For persistence specifically, brief exposure is enough: ten minutes with an assistant that answered on request left participants skipping 0.20 of unaided problems against 0.11 for controls (Liu et al., 2026). **Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement** explores mobile chatbot journaling as a motivational intervention. **Designing Needs- and Attention-Aware AI Learning Tools for Engineering Education: Insights from Psychological Outcomes** examines what motivates students to adopt AI learning tools in engineering education.

A 42-study meta-analysis (56 effect sizes, 6,059 students) found GenAI-supported learning raised motivation by Hedges' g = 0.764 (95% CI [0.566, 0.962]) — but with I^2 = 93.7% and a 95% prediction interval of [−0.689, 2.217], the average conceals settings where the effect is near zero or negative (Fang et al. (2026)). - **Unreflective use erodes motivation — more so for men.** Thoughtless GenAI use (accepting answers unexamined) predicted lower motivation (β = −0.54) and lower Self-Efficacy (β = −0.37) among 487 undergraduates, and the motivation effect was significantly stronger for male students while the self-efficacy effect was stronger for female students (Zhao & Gu, 2026). - **Cutting frustration is not the same as sustaining motivation.** A three-arm RCT found a scaffolded tutor and unrestricted ChatGPT cut frustration equally (3.21 and 3.13 vs 4.09), but only the scaffolded tutor raised intrinsic motivation (2.82 vs 2.42, $p < .001$); ChatGPT did not (2.64, $p = .076$) (Bassner et al. (2026)). - **Equal feedback quality does not mean an equal motivational effect.** A three-arm RCT with 312 first-year writers found AI-generated and instructor feedback improved revised essays by the same margin: d = 0.60 and 0.59, equivalent inside a pre-specified ±0.35 SD band. Instructor feedback nonetheless raised intrinsic motivation more than AI feedback (5.16 vs 4.90, d = 0.31), and perceived relatedness to the source mediated that gap (indirect 0.25, 95% CI [0.12, 0.40]) with almost no direct effect left (Liu et al. (2026)). Performance ran through feedback engagement rather than self-efficacy, whose indirect path was not significant. Where the Bassner trial separated autonomy from answer-supply, this one holds output quality constant and locates the motivational difference in who the learner is answering.

Why a reader reaches for AI is itself a measurable variable: the AIR scale resolves four motives for GenAI-assisted reading — Task-oriented, Feel-good, Translation and Low-effort — and only Low-effort, using AI when tired or disengaged, was negatively related to need for cognition (r = −.18) (Brann, Etgar and Sidi (2026)).

Motivation in AI-mediated engagement examines how motivational quality (not just quantity) changes with AI. **Isaeva et al.** combined self-determination theory with epistemic network analysis to study engagement with generative AI. **Liang et al. (2026)** traced motivation developmentally via latent transition analysis of **2,086 secondary students** in a year-long AI curriculum, finding three stable profiles (Disengaged, Developing, Self-Determined) and that reaching the Self-Determined profile predicted the largest AI Literacy gains. **Wang & Wang (2026)** used goal-setting theory with **758 university English learners**, showing that **teacher support** drives AI-assisted engagement primarily through mastery-approach and performance-approach goals (the approach, not avoidance, goal orientations). Together these studies

show that motivation in AI contexts is both developmental and socially scaffolded — it shifts over time and responds to teacher support and goal framing, not just tool design.

Goal orientation also routes how the tool is used: mastery and normative performance goals tend to support elaboration and refinement, whereas appearance performance goals make effort-minimization and protecting perceived competence more likely — so the same assistant scaffolds or substitutes for thinking depending on the motivational climate (Øby, 2026). Reward motivation can blunt AI feedback's reach: for Pérez-López et al. (2026), the credibility–perceived-learning link weakened as grade-based reward sensitivity rose — simple slopes b = 0.733, 0.607 and 0.483 at low, mean and high sensitivity.

Institutional generative-AI policy is itself a stressor Learners appraise: Chen (2026) found that the gap between universities' GAI advocacy and their classroom practice raised both challenge and hindrance appraisals among Chinese art and design students, with opposing indirect effects on creative process engagement, while pathways thinking amplified only the challenge route.

A dialogue format can raise motivation without improving overall evaluation: in 222 first-year high-school students, teacher–teacher dialogue raised ARCS motivation more than teacher–student format for learners high in concrete experience (b = 0.162, p < .001) yet scored significantly lower on overall evaluation (b = -0.126, p = .005) (Watanabe et al. (2026)).

Motivation shapes how students frame the tool, and the framing carries the metacognitive payoff: Cui et al. (2026) found the collaborator role — 7.5% of logs — was the only one producing a complete metacognitive chain, while extrinsically motivated students used GenAI as a replacement tool in 64.6% of logs and produced no higher-order connections.

Motivation gains are construct-specific, not general. Lu et al. (2026) found that a nine-week GenAI-supported writing program for 301 Grade 5 and 6 learners raised their ideal L2 writing self and academic buoyancy — the aspirational and the resilience components of motivation — while leaving growth mindset unchanged; the only growth-mindset gain appeared in the control group and did not survive correction for multiple comparisons. Students attributed the shift to seeing fluent text built from vocabulary they already knew, which made successful writing feel attainable. So motivation is not a single dial that AI turns up: what improved was the belief that one *can* write well, not the belief that ability grows with effort. The same construct-specificity appears when GenAI is itself the relevance intervention. Guo, Fryer and Shum (2026) had **218 high-school students** spend one hour in semi-structured dialogue with a chatbot aimed at personal relevance to math; the collective, class-level version raised relevance as identification ($F = 4.35$, $p = .014$, $\eta^2 = 0.04$; against the control, $F = 11.11$, $p = .001$, $\eta^2 = 0.073$ — a medium effect) and, in the SEM, predicted relevance to a specific lesson one week later ($\beta = 0.18$, $p < .01$), while interest in the math class did not move ($F = 0.29$, $p = .75$, $\eta^2 = 0.003$). The authors attribute the decoupling to dose: a single one-hour session is too brief for relevance gains to consolidate into interest in the class.

A utility-value intervention is not uniformly beneficial: a scaffolded version produced no overall gain in pre-service teachers' knowledge integration and *harmed* it for learners who entered with high perceived utility-value, an aptitude-treatment interaction arguing for matching motivational support to learners' starting points (Boos, Eder & Lachner (2026)). **A feedback message moves interest through its perceived usefulness, not through the learner's dispositions.** Jansen et al. (2026) gave 1,507 secondary students one standardized automated feedback message after a first draft of an argumentative text. Global receptivity was the only receptivity dimension related to situational interest change (about 0.11 points on the observed scale, roughly

the 54th versus 46th percentile), and that effect was fully mediated by perceived usefulness (indirect β = 0.09, 95% CI [0.06, 0.13]). No significant direct path remained (β = 0.06, 95% CI [−0.07, 0.16]). What shifted interest was therefore the felt worth of the message, not the learner's general stance toward feedback.

Teacher motivation and persistence examines motivation among educators. **Framing the 5 Percent Problem** studies teacher persistence with AI tools, and **Chiu et al.** found need-supportive professional development fosters sustained behavioral engagement in professional learning communities.

- **Cross-cultural motivation of future teachers:** Martínez-Moreno et al. (2026) validated the (D)FIT-Choice scale with 416 student teachers in Switzerland and China, finding Swiss teachers report stronger social utility and intrinsic motivation while Chinese teachers show higher perceived digital competence and enthusiasm for integrating AI — highlighting how cultural and systemic factors shape motivation to shape the future of education with AI.
- **Self-efficacy is the root of teachers' enjoyment of GenAI.** In a PLS-SEM study of 434 in-service teachers, self-efficacy was the model's only exogenous variable and its largest effect was on perceived enjoyment (β = 0.805, f^2 = 1.839), feeding perceived usefulness and ease of use in turn (Guillén-Gámez et al., 2026).

The effort paradox and the vicious cycle of assistance. Zohar, Bloom and Inzlicht (2026) argue that motivation is not simply helped or hindered by AI but redistributed: humans generally take the path of least resistance, yet they also seek effort out — the effort paradox — because effort signals that actions matter and because reward attached to process rather than product increases the tendency to strive and persevere. Two claims follow. First, the effort–meaning relationship is an inverted U, so the motivational target is moderate friction, and the risk of frictionless AI is overshooting into too little. Second, a vicious cycle: as AI replaces effort in a domain, the motivational benefits of effort there erode, which makes users more dependent on AI, which erodes motivation further. They also separate supplement from substitute by developmental stage — learners in earlier stages risk bypassing the experiences that build perseverance, while those with established skills can use AI to save time (Desirable Difficulties, Self-Efficacy).

The literature measures motivation without a theory of it. A scoping review of 156 studies from 2003 to 2025 found 133 (85.3%) were guided by no specific motivational theory, the most common variable was a generalized academic motivation (n = 89), and 88 studies (56.4%) came from one national context (Li et al., 2026).

Motivation also operates upstream of technology perception, not only alongside it. In a 340-student physics sample, utility value predicted perceived usefulness (β = 0.43) and intrinsic value predicted attitude (β = 0.20), while perceived cost lowered ease of use (β = −0.16) and attitude (β = −0.27) with no direct path to intention (Xue, Xu, Qi & Lu (2026)).

Motivational regulation is the thinnest construct in this literature. Across 39 studies, Pan, Abuhassna and Jiang (2026) found autonomous motivation measured in 2 studies, with identified regulation and controlled motivation in 1 each, against 17 studies measuring basic psychological needs and 10 measuring engagement. The authors call that gap the review's central problem, because regulation asks why a student is motivated while need satisfaction asks only whether the setting supported them.

Connections to related concepts

Motivation is the parent construct of Self-Determination Theory, which specifies the psychological needs (autonomy, competence, relatedness) that sustain intrinsic motivation. It connects to Student Experience as the experiential layer of motivated engagement, to Student Engagement as its measurable dimension, and to Affective Computing for the emotional mechanisms that shape motivation. Motivation also connects to Over-Reliance (AI reducing productive struggle), Self-Regulated Learning (motivated learners self-regulate), and Teaching (motivation applies to educators as well as students).

Common Misconceptions

- **"GenAI's motivation effect is a clean, large gain."** A 42-study meta-analysis (56 effect sizes, 6,059 students) found a motivation effect of g = 0.764 (95% CI [0.566, 0.962]) **but with I^2 = 93.7%**. Heterogeneity that high means the pooled figure describes a set of studies that disagree with each other, so it is an average over inconsistent treatments rather than a reproducible effect.
- **"Reducing frustration is the same as sustaining motivation."** A three-arm RCT found a scaffolded tutor and unrestricted ChatGPT **cut frustration equally** (3.21 and 3.13). Two very different designs produced the same affective result, so frustration data cannot distinguish between them.
- **"A motivating design is a good design."** In **222 first-year high-school students**, a teacher-to-teacher dialogue format **raised ARCS motivation more** than the alternative while **not improving overall evaluation**. Motivation moved and judged quality did not.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Self-Directed Learning
- Self-Determination Theory
- Student Experience
- Student Engagement
- Affective Computing
- Affective Tutoring
- Cognitive Offloading
- Self-Regulated Learning
- Teaching
- AI in Education
- Framing AI Use for Students
- Social-Emotional Learning — Social-Emotional Learning
- Reflection

Connected Articles

- Modeling high school students' acceptance of GenAI for physics learning via an extended technology acceptance model: Disciplinary beliefs as a distal antecedent — Expectancy-value beliefs as antecedents of GenAI acceptance
- AI Assistance Reduces Persistence and Hurts Independent Performance — Brief AI use reduced persistence on later unassisted problems (Liu et al. 2026)
- Automated feedback on argumentative writing: The role of secondary students' feedback receptivity and feedback perception — Automated feedback on argumentative writing: The role of secondary students' feedback receptivity and feedback perception
- Against frictionless AI — The effort paradox and the vicious cycle of frictionless assistance
- How motivation and roles influence metacognitive engagement in student-GenAI interaction — Motivation and roles in metacognitive GenAI engagement
- Differential engagement with generative artificial intelligence in higher education: Gender, motivation, and achievement trajectories — Gender, motivation, and GenAI achievement trajectories
- Beyond task completion: A theoretical integration and framework for guiding students' ChatGPT use for learning
- Thoughtless use of generative artificial intelligence and college students' self-directed learning: a multi-group SEM analysis of gender differences
- Artificial intelligence and student engagement in online learning: a literature review
- How does students' perception of ChatGPT shape online learning engagement and performance?
- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison
- "Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming
- Students' engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study
- Teacher education for artificial intelligence literacy through a self-determination theory perspective
- Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement
- Framing the 5% Problem: Teachers' Perspectives on Persistence in Educational Technology
- Self-Efficacy and Favorability Shape Learning from Tutoring Systems and Paper Practice
- Transforming curriculum design with generative AI: a model for assessing teacher digital competence — Assessing Teacher Digital Competence for GenAI Curriculum Design (Guillén-Gámez 2026)

- Motivation to shape the future of education with artificial intelligence: An international comparison between Switzerland and China — Motivation to shape the future of education with AI
- Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons — Learner characteristics × TTS dialogue-format interactions
- Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study — Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study
- From disengaged to self-determined: a latent transition analysis of students' AI learning motivation — SDT latent transition analysis of students' AI learning motivation (2,086 secondary students)
- Explaining learning engagement in AI-assisted learning through teacher support and achievement goals: insights from goal-setting theory — Goal-setting theory: teacher support, achievement goals, and engagement in AI-assisted English learning (758 Chinese students)
- Perceived utility moderates motivational intervention effects in learning to teach responsibly with GenAI — Utility-value intervention effects in learning to teach responsibly with GenAI (Boos, Eder & Lachner 2026)
- Exploring the impact of a GenAI-supported writing program on primary students' writing motivation, engagement, and performance: A mixed methods study — Construct-specific motivation gains in a primary L2 GenAI writing program (Lu et al. 2026)
- The AIR Scale: Development and validation of a measure of motivations for using AI during reading — The AIR Scale: four motive families for reaching for AI while reading
- Utilizing generative AI to promote high school students' personal relevance to math and interest in the math class: An intervention — GenAI relevance dialogue raised relevance as identification but left class interest flat
- Effects of generative artificial intelligence on students' learning motivation: evidence from a meta-analysis — Random-effects meta-analysis of GenAI's effect on learning motivation (56 effect sizes, 6,059 students)
- AI and student motivation: A scoping review — 156 studies on AI and student motivation: 85.3% used no motivational theory, and coverage is narrow in construct, level, and country
- When universities advocate GAI but practice falls short: student appraisals and creative process engagement in art education — Policy-practice gaps in GAI advocacy act as a stressor students appraise
- Less stress, better scores, same learning: The dissociation of performance and learning in AI-supported programming education — Scaffolded tutor raised intrinsic motivation where unrestricted ChatGPT did not
- As effective as the teacher, but less motivating: A randomized controlled comparison of AI-generated and teacher feedback on students' writing performance and intrinsic motivation —

Matched-quality AI and instructor feedback, with the motivational gap running through relatedness (Liu et al. 2026)

- Generative AI and student motivation: an SDT-guided systematic review of learning activities, motivational regulation, and measurement - SDT-guided review of 39 studies: needs and engagement measured often, motivational regulation almost never

Connected FAQs

- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Self-Efficacy

> **Self-efficacy** — a learner's belief in their capability to successfully perform a task or achieve a goal. Drawing on social cognitive theory (Bandura), self-efficacy shapes motivation, effort, persistence, and learning engagement. In AI in education, self-efficacy matters in two ways: AI tools can build learners' confidence and autonomy (e.g., by providing Feedback and Scaffolding), and learners' AI self-efficacy — their confidence in using AI technologies — influences how effectively they engage with AI, including how AI-related knowledge translates into career-relevant readiness.

Questions to Consider

- Self-efficacy is a belief about your capability — distinct from actual competence. Have you ever been highly capable at something yet doubted yourself, or confidently wrong about something you couldn't do? What does that gap between belief and ability tell you about why self-efficacy matters?
- AI self-efficacy (confidence working with AI) is a separate construct from AI literacy, and research finds literacy translates into readiness only when learners also have confidence. If someone knows *about* AI but doesn't believe they can use it, what happens to that knowledge — and what does that imply for training?
- Research found that using AI to support understanding was fully mediated by academic self-efficacy in its link to performance, while shortcut use predicted worse outcomes partly independent of self-efficacy. Why would the *same* tool build confidence when used one way and fail to when used another?
- The page distinguishes self-efficacy from the everyday word 'confidence.' Before you read, how are they different, and why would a researcher insist on the distinction rather than treating them as the same thing?
- Robotics and embodied learning build confidence by grounding tasks in observable outcomes, and feedback can build learner self-efficacy. Think of a task where you gained real confidence only after seeing a concrete result. What does that say about what kinds of AI learning experiences are most likely to build — rather than merely report — self-efficacy?
- Teacher self-efficacy affects adoption and integration of AI. If a teacher doesn't believe they can use AI effectively, does any amount of AI literacy fix it? What would build a teacher's confidence, and how is that different from giving them more information?

Introduction

Self-efficacy is distinct from actual competence: it is a belief about capability that drives behavior. It is closely related to — and often used interchangeably with — the everyday notion of *confidence* in one's abilities. Self-efficacy connects closely to Motivation, Self-Regulated Learning, and Student Experience. In the AI context, AI self-efficacy (confidence in working with AI) is a distinct construct from AI literacy, and research shows it plays a crucial role in whether learners actually activate and apply AI-related knowledge.

How self-efficacy appears in the knowledge base's research

- **Declines under GenAI-plus-XR studio work:** in a 27-student architectural design studio, teams using a GenAI and multi-user XR pipeline showed larger relative pre–post declines in design self-efficacy confidence (β = −1.675, p = 0.021) and outcome expectancy (β = −2.088, p = 0.002) than teams continuing the normal workflow, with no significant difference in blinded panel ratings of their presentations (Xiao et al., 2026). Tool-rich environments can depress efficacy beliefs even when the work itself is judged equivalent.
- **AI self-efficacy and career readiness:** Research on AI readiness shows that AI self-efficacy moderates the relationship between AI literacy and AI readiness: literacy translates into readiness only when learners have confidence in using AI, and self-efficacy directly predicts career adaptability.
- **Confidence is not always the lever.** A cross-sectional SEM of 502 university faculty found technological self-efficacy a small predictor of AI Well-Being (β = 0.082) while AI literacy dominated (β = 0.713), bounding the claim that confidence gates AI outcomes: for well-being, knowledge outweighed confidence (Liu et al. (2026)).
- **Skills can enable dependency while efficacy buffers it.** Among 478 Israeli undergraduates, the skill dimensions of AI literacy were positively associated with AI dependency (using/understanding AI β = 0.404) while AI self-efficacy was negatively associated (β = −0.132), so literacy training that builds only tool skill may increase reliance (Maizel et al. (2026)).
- **Low confidence routes into heavier AI use, then into lower scores.** In a 153-student proof course, one point higher baseline self-efficacy predicted 39% fewer chatbot messages, and one point lower self-efficacy corresponded to 0.62 fewer exam points through chatbot use (Chen et al. (2026)).
- **Trust as the pivot between literacy and confidence:** Hu (2026) surveyed 450 university students who already use ChatGPT and found an ordered chain rather than two parallel correlates: AI literacy related to Trust in the tool (beta = 0.50), trust to academic self-efficacy (0.48), and self-efficacy to continued use, with the serial indirect effect significant (0.07, 95% CI [0.04, 0.10]). AI anxiety weakened the literacy to trust link (interaction beta = -0.25, simple slopes falling from 0.76 to 0.25 across the anxiety range), so the same knowledge bought less confidence, and reached less use, among more anxious students. Confidence is thus a downstream link in the chain rather than a starting point.

The anxiety route through which AI-assisted practice relates to willingness can reverse rather than fade with confidence: the conditional indirect association fell from 0.142 at low speaking self-efficacy to 0.044 at the mean and −0.054 at high, an effect concentrated in a small upper tail (Wang & Li (2026)). - **Profiles of academic self-efficacy and who reaches for AI:** Suriá-Martínez et al. (2026) ran a latent profile analysis of academic self-efficacy among 102 university students with motor disabilities in Spain and found three profiles (low 29.4%, moderate 41.2%, high 29.4%) whose reported AI use rose stepwise with profile level (means 2.41, 3.56, 4.68; F(2, 99) = 27.84, p < .001, eta squared = .36). Excellence, the planning and goal-setting dimension, was the one most strongly associated with AI use (beta = .47). The authors read this as an equity problem: if confidence tracks with uptake, students with lower self-efficacy may be the least likely to

reach for AI support that could reduce access barriers, so support for academic self-efficacy belongs inside inclusion frameworks. - **AI use patterns and self-efficacy:** Stamatoulis et al. (2026) found that using GenAI to *support understanding* (evaluative integration) was fully mediated by academic self-efficacy in its association with performance — understanding-oriented AI use builds confidence — whereas shortcut use (low-verification uptake) predicted worse outcomes partly independently of self-efficacy. Self-efficacy is thus both a pathway through which productive AI use helps and a factor that shortcut use may fail to build. - **Attribution shapes whether efficacy grows.** Crediting success to the AI rather than to one's own effort constrains self-efficacy growth and reinforces shortcut patterns, so sequencing complex activities into steps where students attribute progress to their own strategies matters more than the tool (Øby, 2026). - **Robotics and hands-on learning:** REMind's robot-mediated role-play built children's self-efficacy in anti-bullying intervention; robotics and embodied learning generally build confidence by grounding tasks in observable outcomes. - **Creative self-efficacy in children:** Niu et al. (2026) report, in a systematic scoping review of 22 primary studies of generative AI with children aged 6 to 15, that gains in creative self-efficacy cluster with divergent thinking and narrative creativity, mostly through text-to-image tools that lower the barrier between idea and artifact. They stop short of claiming efficacy: the designs are heterogeneous, the review performed no critical appraisal, and the corpus is nearly silent on disability, low-connectivity and underserved learners, so creative confidence is an outcome reported to rise rather than one the field has confirmed. - **Teacher self-efficacy:** Teacher AI competency research examines how professional development builds teachers' confidence in using AI, which affects adoption and integration. Ismael, Luo & Li (2026) add quasi-experimental evidence that an AI-supported e-mentoring model raises EFL pre-service teachers' self-efficacy and emotional intelligence during the practicum: the experimental group gained substantially more than controls on both measures, with a large between-group effect and gains across all self-efficacy subdomains — and the authors attribute them to mentoring AI-mediated within structured reflective cycles rather than to the AI alone. - **Feedback and confidence:** AI feedback and tutoring can build learner self-efficacy by providing actionable, supportive feedback. - **Empowerment in AI Problem Solving:** Zhu and Kong (2026) find that students' empowerment in using AI for problem solving mediates the relationship between perceived project-based learning and satisfaction with an AI literacy course. In their SEM analysis of 1,027 students, PBL fostered conditions that empowered students to use AI for problem solving, which in turn drove course satisfaction — evidence that building students' confidence and capability with AI is a key mechanism of effective AI literacy education.

Self-efficacy connects to Motivation, Self-Regulated Learning, Student Experience, AI Literacy, Learner Agency, and Robots in Education. Building self-efficacy is a key mechanism through which AI supports engagement and learning. Self-efficacy is measured almost entirely by self-report, so its associations with observed behavior deserve the usual caution.

- **AIGC self-efficacy as the pivot between tool and learning.** Liang et al. (2026) find that perceived affordances of AI-generated content raise AIGC self-efficacy (beta = 0.583), which then mediates the paths to learning motivation (indirect effect 0.329) and to self-regulated learning (0.145), with the serial path affordance to self-efficacy to motivation to self-AI Regulation in Education also significant (0.173). The contrast that makes the finding useful is that the quality of AI Assessment feedback did *not* predict self-efficacy (beta = 0.131, n.s.) even though it strongly predicted satisfaction — confidence with the tool is built by directing it, not by receiving good output from it.

- **No treatment effect in a semester-long RCT — confidence rose with course time:** in Thoeni and Fryer's (2026) randomized field experiment with 454 undergraduates in a Principles of Marketing course, self-efficacy rose over the semester for all students (time effect β = 0.099, p = 0.0009, Cohen's $f2$ = 0.025). Neither the group effect (p = 0.1162) nor the group × time interaction (p = 0.5306, d = 0.023) was significant, so the RAG chatbot added nothing. Confidence gains in AI-supported courses can track course progression rather than the tool — an attribution risk for a construct the field measures almost entirely by self-report.
- **Confidence can move opposite to behavior.** In competitive programming, students who stopped competing reported *higher* theoretical confidence than their active peers yet showed significantly weaker upsolving and peer-circle habits ($p < .001$), so a self-efficacy signal alone will mislead an early-warning system (Ruhan et al. (2026)).
- **Confidence can rise while the capability behind it declines.** Among university students, frequent generative-AI use raised perceived confidence and efficiency *and* increased technological dependence in the same learners, so a self-efficacy score taken during AI-assisted work can read high at the moment the underlying skill is eroding (Yan et al., 2025).
- **AI use rode with confidence, but confidence did not predict attendance.** In a PLS-SEM survey of 291 Portuguese students, general AI use was positively associated with self-efficacy for independent learning (β = 0.266, f^2 = 0.106). The construct was modeled as a second-order formative composite of Bandura's four sources — mastery experience, vicarious experience, verbal persuasion, and emotional state. Self-efficacy in turn did not predict absenteeism (β = −0.068, p = 0.276), even though AI use was separately associated with higher absenteeism (β = 0.148, f^2 = 0.029). The AI-use → self-efficacy path was significantly stronger among males than females (β = 0.449 vs. 0.159; Δβ = −0.289, p = 0.013), under partial measurement invariance (Franco et al. (2026)).
- **Confidence after a structured protocol tracked structure, not dose.** Post-protocol confidence in solving similar problems independently averaged 7.18 on a 1–10 scale (σ = 1.62, n = 217), with institutional means ranging only 6.86 to 7.52 across four campuses. It tracked the perceived benefit of the AI explanation (r_s = 0.37) and of replicated practice (r_s = 0.35), more weakly prior AI confidence (r_s = 0.20), and not usage frequency (r_s = 0.02, p = 0.749) or self-reported GPA (r_s = 0.13, p = 0.064) (Paul et al., 2026). That is a mastery route — authored difficulty, then an independent attempt — rather than more time in the tool, a distinction the page lacked. The study measured no learning outcome, so it bounds what students believed.
- **Open-ended AI design tasks sort students by pre-existing confidence.** Zangari et al. (2026) found that performance self-esteem correlated with extroversion (r = 0.262, p < 0.001) in a course where 345 students each built a conversational agent to teach a peer, and that female students reported significantly lower self-esteem than male peers (Kruskal-Wallis H(2) = 9.87, p < .005). The design inference the authors draw: open-ended, conversational creative tasks advantage the already-confident, so "open-ended design tasks [should] include sufficient scaffolding to equitably build performance self-esteem across all personality types" — a caution that student-created-artifact assignments can widen, not close, confidence gaps if scaffolding is not deliberate.

- **Self-efficacy interacts with format preference, not just with outcomes.** A counterbalanced within-subject study (97 ninth-graders; content-matched tutor-based vs. paper-based practice of graph interpretation and construction) found tutor-based practice beat paper overall ($t(62.30) = 2.38$, $p = .020$), and — counterintuitively — lower baseline self-efficacy predicted *greater* gains in both formats ($t(98.40) = -2.14$, $p = .035$). The interesting structure is a significant three-way self-efficacy × favorability × format interaction ($t(99.84) = -2.58$, $p = .011$): among low-self-efficacy students, favorability toward the tutor predicts larger gains *specifically in tutor practice*. A sobering null for the assumption that tutor practice is motivationally self-reinforcing: ITS practice did not significantly improve post-training self-efficacy over paper — attributed to the short intervention (two ~40-minute sessions). The practical signal: baseline self-efficacy and technology favorability are cheap, actionable inputs for format assignment; tutor practice capitalizes on existing favorability rather than creating it. (Self-efficacy and favorability shape learning from tutoring systems and paper practice)
- **Knowledge reached intention through trust, anxiety and self-efficacy.** In a PLS-SEM model of 526 design students, perceived AIGC knowledge was positively associated with trust, self-efficacy and usage intention and negatively with anxiety, and trust, anxiety and self-efficacy each carried a significant indirect path from knowledge to intention (Wei et al., 2026). Anxiety sat on the pathway rather than blocking it.
- **"Low writing confidence shows up as a request for help."** It shows up as a request for prose. In an instrumented essay study, the Self-Efficacy for Writing Scale predicted total queries negatively (**-0.258**, SE **0.075**, $p < 0.001$), and the association ran through Translating (**-0.949**) and Reviewing (**-0.588**) rather than Planning (**-0.204**) or whole-essay delegation (**-0.016**). Students who doubted their writing asked the model to produce and correct text; they did not ask it what to argue. Self-efficacy predicted reliance, and the reliance took a specific shape.

Confidence does not protect a learner from trusting a tool too much. Among 300 university students, Kim, Kim and Zhang (2026) found academic self-efficacy associated with AI overtrust ($r = 0.230$) and predicting it at $B = 0.3901$ (95% CI [0.2190, 0.5612]) in a serial mediation model, reversing the authors' hypothesis. The productive version of confidence is confidence about one's own judgment, which is what a high overtrust score says is missing.

- **Confidence reaches adoption partly through literacy.** Belief to behavior: how AI self-efficacy shapes AI acceptance through AI literacy tested a sequence on 622 undergraduates in Türkiye. AI self-efficacy predicted AI acceptance ($B = 0.43$, $R^2 = 0.29$), and AI literacy carried part of that link (indirect $B = 0.15$, 95% CI [0.12, 0.19]) without absorbing it all. Confidence also has to be accounted for as a predictor of uptake, not only of capability. The design is cross-sectional with no demographic controls, so direction and mediated share are associations rather than effects.
- **Necessary for usefulness, not merely correlated with it.** Chu and Liu (2026) placed AI self-efficacy in front of the two acceptance beliefs for 405 design graduate students and found it the strongest antecedent of both: $\beta = 0.458$ on perceived usefulness and $\beta = 0.394$ on perceived ease of use. Their necessary condition analysis adds a stronger form of claim than the path above. Efficacy was the only condition identified as necessary for perceived usefulness ($d = 0.125$, $p = 0.015$). Usefulness at 80%, 90% and 100% of its scale required efficacy at 10.0%, 30.0% and

50.0%. Confidence therefore sits as a floor under the instrumental judgment rather than as one contributor among several. The design is cross-sectional and the model explains $R^2 = 0.150$ of intention, so treat the thresholds as within-sample.

- **Behavioral traces can carry the signal, but the labels set the ceiling.** A two-university pipeline detected low self-efficacy from interaction traces; survey-occasion labels beat a mid-term split, and the MSLQ subscale alone labeled as well as the full instrument (Somny, Chouati & Lefevre, 2026).

Common Misconceptions

- **"Students who lack confidence avoid AI."** The opposite pattern appears: in a **153-student proof course**, one point higher baseline self-efficacy predicted **39% fewer chatbot messages**. Low confidence routed into **heavier** AI use — the students most in need of practice were the ones most likely to offload it.
- **"More AI use with low confidence is a harmless coping strategy."** The same finding links that routing to **lower scores**, so the coping pattern has a measurable cost rather than being neutral choice.
- **"Literacy alone builds confidence."** Hu (2026) surveyed **450 university students** who already use ChatGPT and finds **trust as the pivot between literacy and confidence**. The path runs through trust, so raising literacy without addressing trust leaves the mechanism untouched.
- **"Self-efficacy profiles are uniform in a disabled population."** A latent profile analysis of **102 university students with motor disabilities** in Spain found **three profiles**, with the low group at **29.4%** and the remainder split across moderate and higher profiles. Treating the group as one population averages over distinct motivational states.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Self-Directed Learning
- Motivation
- Self-Regulated Learning
- Student Experience
- AI Literacy
- Learner Agency
- Robots in Education
- Self-Report Measures
- Social-Emotional Learning — Social-Emotional Learning

Connected Articles

- Supporting or Replacing Students' Reasoning? Cognitive Offloading in AI-Assisted Proof Learning — Supporting or replacing students' reasoning? Cognitive offloading in AI-assisted proof learning (Chen et al. 2026)
- Confident but absent: AI use, self-efficacy for independent learning, and student absenteeism in higher education — General AI use tracked with higher self-efficacy and higher absenteeism, yet self-efficacy did not predict attendance (Franco et al. 2026)
- AI chatbots in higher education: Comparing expectations to evidence — AI chatbots in higher education: comparing expectations to evidence (Thoeni & Fryer 2026)
- Distinguishing performance gains from learning when using generative AI — confidence rising while technological dependence grows: self-efficacy as a misleading AI-era outcome (Yan et al. 2025)
- An AI-supported E-mentoring model to develop EFL pre-service teachers' self-efficacy and emotional intelligence — AI-supported e-mentoring raises EFL pre-service teachers' self-efficacy and emotional intelligence (quasi-experimental)
- AIGC affordance and student self-regulation in private undergraduate education: a serial mediation model of self-efficacy and learning motivation — AIGC Affordance and Student Self-Regulation
- Beyond task completion: A theoretical integration and framework for guiding students' ChatGPT use for learning
- AI literacy alone is not enough: Student AI readiness and career adaptability in business and management education — AI Literacy, AI Readiness, and Career Adaptability
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — REMind
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher Education for AI Literacy (SDT)
- Co-Creating Buildable and Open Social Robot Study Companions with University Students — Social Robots as Study Companions
- Human-Centric Artificial Intelligence Pedagogy (HCAP) framework developed from TPACK through integration of artificial intelligence literacy and competency — HCAP Framework
- Understanding Student Dependency on AI: The Role of AI Literacy, Academic Self-Efficacy, and Resource Management Strategies
- Same tool, different work: patterns of generative AI use and academic outcomes — Patterns of GenAI use and academic self-efficacy
- Enhancing AI literacy course satisfaction through empowerment in AI problem-solving and ethical awareness: Development and validation of an AI project-based learning scale — AI-PBLS scale; empowerment and ethical awareness mediating PBL-to-satisfaction in AI literacy courses (Zhu & Kong 2026)

- Predicting Student Attrition in Competitive Programming: A Large-Scale Study Integrating Survey Insights and Global Behavioral Logs — Predicting Student Attrition in Competitive Programming
- Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study — Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study
- Psychological predictors of continued ChatGPT use among university students: the roles of AI literacy, trust, and academic self-efficacy — AI literacy, trust and academic self-efficacy in a serial chain to continued ChatGPT use
- Between perceived competence and artificial intelligence: academic self-efficacy profiles in university students with motor disabilities — Academic self-efficacy profiles and reported AI use among university students with motor disabilities
- The role of generative AI in facilitating children's creative thinking and cognitive development: a systematic scoping review — Reported creative self-efficacy gains from generative AI in children (scoping review)
- AI-Assisted Speaking Practice and Human-Directed Communicative Readiness: Survey and Scenario Evidence on Anxiety, Self-Efficacy, and Evaluation Pressure — Speaking self-efficacy reverses the anxiety pathway from AI-assisted practice to willingness
- Exploring University Faculty's AI Well-Being: A Structural Equation Model of Social Supports, AI Literacy, and Technological Self-Efficacy — Faculty SEM: technological self-efficacy a weak predictor of AI well-being
- Self-efficacy and favorability shape learning from tutoring systems and paper practice — Self-efficacy and favorability shape learning from tutoring systems and paper practice (Cen et al. 2026)
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — The Self-Efficacy for Writing Scale predicted more Translating and Reviewing queries, and no more Planning or whole-essay delegation (Jelson et al. 2026)
- Trusting AI too much? Psychological correlates of overtrust and the role of AI literacy - academic self-efficacy predicted higher AI overtrust rather than lower
- Using Machine Learning to Measure Self-Efficacy Belief Through Learners' Interaction Traces in Technology-Enhanced Learning — Using Machine Learning to Measure Self-Efficacy Belief Through Learners' Interaction Traces in Technology-Enhanced Learning
- Belief to behavior: how AI self-efficacy shapes AI acceptance through AI literacy — AI self-efficacy -> AI literacy -> AI acceptance, with the knowledge-mediated share measured (İşbulan et al. 2026)
- Cognitive mechanisms of AI agent behavioral intention among design graduate students: an integrated TAM–TTF perspective — self-efficacy as the necessary condition for perceived usefulness, with bottleneck thresholds (Chu & Liu 2026)

Connected FAQs

- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?
- How Should I Use AI to Study and Learn Effectively?

Self-Directed Learning

> **Self-directed learning (SDL)** — the process by which learners take initiative and responsibility for diagnosing their own learning needs, setting goals, identifying resources, choosing and implementing strategies, and evaluating outcomes, often with limited external structure. In the AI era, SDL is both a key outcome (does AI use support or erode learners' capacity to direct their own learning?) and a vulnerability (the convenience of generative AI can undermine the very autonomy and Self-Efficacy SDL requires).

Questions to Consider

- Self-directed learning means diagnosing your own needs, setting goals, and evaluating outcomes with limited external structure. Before you read, how comfortable are you actually directing your own learning — and has an AI tool ever made you *less* able to, without you noticing?
- The page frames SDL as both a hoped-for outcome and a vulnerability: generative AI's convenience can erode the very autonomy and self-efficacy SDL requires. Why would a tool that gives you instant answers make it *harder* to direct your own learning later?
- Thoughtless use of GenAI — adopting outputs without critical evaluation — was found to harm SDL both directly and by eroding self-efficacy and motivation. Can you recall a time you accepted an AI answer without evaluating it? What, if anything, did that cost you?
- SDL and self-regulated learning (SRL) are closely related but distinct: SRL concerns in-the-moment AI Regulation in Education of learning, while SDL concerns overarching responsibility across time. Where do you see the boundary between 'managing this task' and 'directing my own learning' in your own practice?
- The harm from thoughtless AI use hit motivation harder for some students and self-efficacy harder for others. If the erosion of these psychological resources is uneven across learners, what equity concern does that raise about who loses the most from AI convenience?
- Set a goal before you read: name one learning goal you're currently pursuing mostly on your own, and one way an AI tool helps you toward it and one way it might be quietly taking the directing away from you.

Introduction

Self-directed learning is a close neighbor of self-regulated learning (SRL), not a synonym. While SRL emphasizes the in-the-moment cognitive, motivational, and behavioral regulation of learning (planning, monitoring, controlling, reflecting), SDL emphasizes the learner's overarching responsibility for the direction and management of their own learning across time, often in informal or self-chosen contexts. SDL is foundational to adult learning and lifelong learning, and is a prominent theory in distance and online education, where learners must sustain autonomy without scheduled class time. SDL is also increasingly *tractable* to empirical study: analyzing the clickstreams of 315 online learners who built 822 models in VERA, An, Hammock & Goel (2025) identified three behavioral signatures of self-direction — Observation,

Construction, and Exploration. They also found learners progressing from hands-on construction toward fuller, hypothesis-driven Exploration while Observation persists across all phases, showing that the degree and kind of autonomy learners exercise in an unstructured online task can be distinguished from their trace data alone.

How generative AI reshapes self-directed learning

The knowledge base's research documents both sides of the GenAI–SDL relationship.

- **AI can support SDL.** AI and lifelong learning and self-directed growth with GenAI + learning analytics show that AI tools can scaffold independent inquiry, provide on-demand resources, and personalize learning paths in ways that strengthen learner autonomy. Meta-analytic evidence on generative AI educational outcomes and conversational AI in informal learning suggest positive potential when AI is used as a resource the learner directs.
- **Learners want a thinking partner, not an oracle.** Interviewed adult learners wanted AI to prompt reflection and verify rather than supply answers, and to leave them in control of the learning path rather than prescribe it (Kim et al. (2026)).
- **Delegating goal choice is not the same as supporting it.** The page treats setting the goal as the learner's core act, and the benchmark evidence says models do it differently. Against 175 humans, GPT-5, Claude Sonnet 4.5 and Qwen3 32B re-selected the previous goal on 0.93, 0.93 and 0.94 of trials, against 0.54 ± 0.18 for people. Goal entropy was 0.12 to 0.20 against 1.67 ± 0.14, and chain-of-thought and persona prompts did not close the gap. A system that proposes what to learn next reproduces a narrower search than the learner it stands in for (Molinaro et al., 2026).
- **Thoughtless use undermines SDL.** Zhao & Gu (2026) show that the **thoughtless use of GenAI** — adopting AI outputs without critical evaluation — significantly harms undergraduates' SDL both directly and through erosion of Self-Efficacy and Motivation (the model explained 75.3% of SDL variance; TUGA $\beta = -0.42$). The negative effect on motivation was stronger for male students and on self-efficacy stronger for female students. This connects to the broader over-reliance risk documented in the knowledge base.
- **Cognitive offloading and delegation.** Andragogy and cognitive delegation and learning by chatting with GenAI examine how learners may delegate cognitive work to AI in ways that bypass the effortful processing SDL requires — a failure mode of otherwise autonomy-supportive tools. Scaffolding critical thinking with GenAI and test-driven AI-assisted learning model more productive designs.

The SDL–SRL distinction in practice

Because SDL emphasizes learner-initiated direction, interventions to protect it focus on preserving Learner Agency and self-efficacy rather than merely regulating moment-to-moment behavior. The evidence that thoughtless AI use erodes motivation and self-efficacy — the psychological resources SDL depends on — suggests that promoting responsible AI use is not just an integrity issue but a developmental one: protecting students' capacity to direct their own learning.

AI Extraction Scaffolding Research-Based Learning

- **AI extraction as a scaffold for research-based learning.** An and colleagues (2026) design an AI-powered information extraction system that converts research publications into structured, traceable datasets to support undergraduate thesis completion in STEM, positioned as an **epistemic scaffold** that enables inspection of evidence-claim relationships while reducing low-level data-handling demands. In a 20-student mixed-methods pilot across 80 documents, students extracted over 90% of targeted parameters, self-reported literature-review time dropped ~65%, and their ability to identify influential variables rose 50% — supporting the idea that AI can rebalance cognitive load toward higher-order, self-directed research reasoning rather than routine summarization.

Common Misconceptions

“Self-directed learning and self-regulated learning are the same construct.” They operate at different timescales: SRL concerns in-the-moment regulation of learning, while SDL concerns overarching responsibility across time — choosing what to learn, setting the goal, and holding the direction over months. An intervention that improves moment-to-moment regulation need not produce a self-directed learner, and a student can be self-directed across a program while regulating poorly within a session.

“AI makes self-directed learning easier because it supplies structure.” It can remove the exercise of the skill. Zhao and Gu (2026) show that **thoughtless use of GenAI — adopting outputs without critical evaluation — significantly undermines SDL**. Directing one’s own learning is practiced by making the decisions GenAI can now make for you, so an assistant that always supplies direction supplies it in place of the competence.

“Non-use of AI indicates a lack of access.” Among students who do not use it, the stated reason is often a positive educational choice — wanting to do the work themselves — rather than a barrier. Reading non-use as a deficit misdescribes a position that is, in the Student Experience evidence, reasoned.

“Self-direction means working alone.” It means owning the direction, which can be exercised in a highly supported environment. The distinguishing feature is who sets and adjusts the goal, not whether help is available.

Implications for Practice

For instructors

- Distinguish what you are developing: in-session regulation or across-time ownership. They need different designs, and improving one does not produce the other.
- Protect the decisions that constitute self-direction — what to learn, how to judge progress, when to change course — even where AI could make them. Delegating them removes the practice.
- Teach evaluation alongside use, since thoughtless adoption of outputs is the documented mechanism by which GenAI undermines SDL.

For developers

- Make the learner's decisions visible and revisable rather than setting them by default. A system that always supplies direction supplies it in place of the competence being developed.
- Build reflection checkpoints where the learner states their goal and their evidence, so direction remains theirs.

For researchers

- Report which construct an intervention targeted; SDL and SRL outcomes should not be used interchangeably.

Connected Concepts

- Self-Regulated Learning
- Learner Agency
- Self-Efficacy
- Motivation
- Metacognition
- Cognitive Offloading
- AI Misuse and Learning Harm
- AI Literacy
- Adult Learners
- Lifelong Learning
- Higher Education

Connected Articles

- Thoughtless use of generative artificial intelligence and college students' self-directed learning: a multi-group SEM analysis of gender differences — Thoughtless GenAI use and self-directed learning (SEM, gender differences)
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy — AI and lifelong learning policy
- Fostering Self-Directed Growth with Generative AI: Toward a New Learning Analytics Framework — Self-directed growth with GenAI and learning analytics
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches — Meta-analysis of generative AI educational outcomes
- What remains self-directed? Revisiting andragogy through cognitive delegation in generative AI-mediated adult learning — Andragogy and cognitive delegation with GenAI
- Adult learners' perspectives of AI applications in supporting andragogy — AI Applications in Supporting Andragogy (Kim et al. 2026)
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis
- Language Model Goal Selection Differs from Humans in a Self-Directed Learning Task — Models do not select learning goals like humans in a free-choice task (Molinaro et al. 2026)

Metacognition

> Metacognition — thinking about one's own thinking — is both a target of AI education research (can AI tools develop students' metacognitive skills?) and a risk factor (AI completing tasks may suppress metacognitive practice).(The Evidence Base on AI in K-12: A 2026 Review)(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)

Questions to Consider

- 'Metacognition' is thinking about your own thinking — knowing what you know, monitoring yourself, and adjusting your strategies. When you study or solve a problem, how aware are you in the moment of whether you actually understand versus just recognizing the material?
- A striking finding: students who used AI essay assistance were often unable to recall quotes from their own essays, because they hadn't engaged with the content during production. When a tool produces the output, what practice is the learner losing — and is that practice important?
- The page frames metacognition as both a target (can AI build it?) and a risk (can AI suppress it?). Could the same AI tool either strengthen or weaken a learner's metacognition depending on how it's designed or used? What determines which way it goes?
- Structured prompts that ask students to self-explain, evaluate strategies, or identify gaps preserve metacognitive demand, while AI that simply completes tasks displaces it. If you were designing an AI study tool, what would you build so that it invites reflection instead of replacing it?
- The page finds that whether AI use is metacognitively rich depends on the learner's motivation and stance as much as on the technology. Have you ever used a tool in a shallow way and then realized you learned nothing — and what was different about times you used it deeply?

Introduction

Metacognition in education refers to learners' awareness, monitoring, and AI Regulation in Education of their own cognitive processes:

- **Metacognitive knowledge:** Understanding what one knows, what strategies are available, and when to deploy them
- **Metacognitive regulation:** Planning, monitoring, and evaluating one's own learning in real time

Within Self-Regulated Learning frameworks, metacognition is the central mechanism that enables learners to adapt strategies, recognize confusion, and seek help appropriately.(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)

Metacognition is not the same construct as Reflection, and the two are often conflated. Monitoring is a judgment a learner makes about their own state, and it can happen with no record at all. Reflection is the deliberate, documented examination of a completed attempt, and what it produces is a text that can be reviewed or assessed. Keeping them apart matters most when AI is involved: a monitoring judgment is hard to hand over, while a reflection artifact can be produced by a model.

How learners actually deploy metacognition around AI is shaped by more than the tool itself: Cui et al. find that student motivation and the interaction role they adopt shape their metacognitive engagement with GenAI — meaning whether AI use is metacognitively rich depends on the learner's stance as much as on the technology. Miles, Haber-Curran and Arar (2026) add the AI interaction itself as an object of that reflection: the closing step of their Prompt Literacy Cycle asks learners to examine what the process revealed about how prompts function and what assumptions shaped the response, and they make reflection and revision the phase in which authorship and critical judgment develop.

A more fundamental role for metacognition appears when the locus of coordination shifts from teacher to learner. Dang, Hong, Doyle and Nguyen (2026) argue in their Human-AI Collaboration Competency (HACC) framework that the integrative work Technological Pedagogical Content Knowledge (TPACK) assigns to pedagogy passes, once the actor is the learner, to the learner's own metacognition — the competency that lets students direct the collaboration, calibrate their reliance on AI, and remain the authors of their learning. They treat metacognitive competency as the mechanism through which learner agency is enacted, deliberately excluding agency as a separate component and reading it instead as the emergent quality of coordinating domain, AI, and metacognitive competency. Their Epistemic Network Analysis of interviews with 24 higher education educators found metacognitive talk rising with role level — senior educators connected it to domain, AI, and learning with AI — which the authors read as educators with broader curricular responsibility seeing students' persistent difficulties as regulatory rather than technical.

How AI Tools Affect Metacognition

The Suppression Risk (Stanford SCALE, 2026)

When AI completes reasoning tasks for students — solving math problems, writing essays, generating code — the student loses practice in monitoring their own understanding and selecting strategies.(The Evidence Base on AI in K-12: A 2026 Review)

Reliance is not failure: Du and Yuan (2026) judge AI-mediated learning by six diagnostic criteria — contestability, recoverability, transfer, traceability, distributed responsibility and epistemic plurality — and distinguish instrumental assistance, which helps produce output, from judgment-bearing assistance, which supplies the standards by which output is judged. **Naming the governance question.** Lin and Chang (2026) propose **metacognitive ownership** — the learner's governance of the standards, evaluative judgments and actions an AI contributes to — separating standards appropriation, monitoring-judgment governance and control authorization, and requiring a realistic opportunity to act differently.

Key findings: - **Kosmyna et al. (2025):** Students who used AI essay assistance were **83% unable to recall quotes** from their own essays, vs. 11% for non-AI users — indicating they did not engage with the content during production. - **Stadler et al. (2024):** General-purpose AI reduced cognitive load but produced **lower-quality reasoning** vs. traditional search, suggesting metacognitive engagement was displaced. - **Lehmann et al. (2025):** General AI for programming harmed understanding for low-Prior Knowledge students — the students most in need of metacognitive scaffolding received answers instead. - **Metacognitive laziness.** The field names a distinct failure mode in which learners abdicate their metacognitive responsibilities to the tool — adopting the term *metacognitive laziness* for the resulting illusion of competence, and warning that its cognitive risks fall hardest on novices and weaker self-regulators (Lodge & Loble (2026)).

Fluency is why the loss goes unnoticed. Learners judge their learning partly from how easily material is processed, and Bjork et al. (2013) show that fluency cues lead people to overestimate their understanding when content feels easy; fluent AI-generated text supplies that feeling whether or not comprehension followed, creating the conditions for a manufactured illusion of competence. Generativism treats this as the reason adaptive metacognition cannot be assumed: the learner has to ask whether ease of reading reflects understanding rather than reading the ease as the answer.

Awareness does not guarantee that completion stops. Jia (2026) names *metacognitively discordant completion*: a learner who invested real effort, holds a formed first-person verdict that understanding has not arrived, and releases the work anyway — the case the fluency-illusion and withdrawn-effort accounts both assume away.

Learners are also miscalibrated about AI's costs: participants predicted independent times accurately but underestimated AI-assisted time, and reported lower effort (0.61 points on NASA-TLX) while AI sped up only three of 24 tasks — a bias absent when the imagined helper was another person (Yu et al. (2026)).

The cost appears bounded rather than global: offloading degrades the specific skill practiced, not the underlying domain-general abilities, and surfaces on withdrawal: an endoscopy study found adenoma detection fall from 28.4% to 22.4% when the AI was unavailable, leaving source-monitoring (telling an AI's reasoning from one's own) an open metacognitive risk (Cash et al. (2026)).

The Augmentation Opportunity (Scheu et al., 2026)

When AI is designed to support reflection rather than replace it, metacognition can be strengthened:

- **Learning journals** are a classic metacognitive practice: by reflecting on learning processes, students increase awareness of their cognition
- **Structured prompts** that ask students to self-explain, evaluate strategies, or identify knowledge gaps preserve metacognitive demand. CoMeT (Hou et al. 2026) gives that phrase a definition and an empirical warrant: it treats metacognitive demand as a quantity distinct from cognitive load — what the learner must decide, state, or judge before help arrives, not simply what remains when help is withheld — and held it statistically equivalent to a tutor that withheld answers by design ($p_{TOST} = .004$) while its own support escalated and faded one rung at a time. Fading held when the learner's turn was aimed at the decision under support: turns aimed elsewhere drew a later concession 40.3% of the time against 28.8% for aimed turns, an 11.5-point difference, so what a tutor must read for is where the learner's attention sits rather than how much effort the turn displays.
- **Assign an AI-use level per task.** HAIML pairs its three layers with Four AI Use Levels — from no AI use, through brainstorming, to AI collaboration and AI-integrated creation with output evaluation — so an instructor sets the level for a task and keeps metacognitive reflection central at every level (Reardon, 2026).
- The **example-based course** in Scheu et al.'s chatbot increased **perceived competence** (a metacognitive Self-Assessment) even when the Large Language Models (LLMs) assistant alone did not

- **An emerging framing puts the system, not just the individual, in the loop.** A bibliometric–systematic review of 135 STEM-classroom studies (24 core studies) finds a posthumanist framing emerging that positions AI as a co-regulator of learning, shifting the unit of analysis from individual reflection to system-level AI Regulation in Education and distributed cognition (Tsakeni et al. (2025)).

At synthesis scale the pattern holds, and it thins as measurement sharpens. A three-level meta-analysis of 54 (quasi-)experimental studies (121 effect sizes, 7,431 learners) put AI's effect on metacognition at g = 0.624 (95% CI [0.431, 0.817]), with 107 of 121 effects positive and gains rising with exposure from g = 0.381 under a week to g = 1.638 at 15 to 20 weeks (Li et al. (2026)). Measurement source was the decisive moderator: self-report g = 0.776, behavioral observation g = 0.514, and accuracy ratings, the gap between judged and actual performance, g = 0.035 and non-significant. The gain is largest where it is easiest to claim and near zero where monitoring is scored against performance, which is the self-report problem the studies above keep running into.

Metacognition is among the least-studied outcomes. In a scoping review of 394 GenAI higher-education studies, metacognition and self-regulated learning were among the outcomes targeted least, alongside Ethics and Creativity (Lin et al. (2026)).

- **Surfacing interaction patterns that learners cannot see.** Kuang, Li and Weng (2026) tracked eye movements, note-taking and speech while 22 interpreting trainees worked with a speech-recognition and machine-translation system, and found that the way students divided attention between AI output and their own notes was invisible to them: 58.3% changed profile between task stages, and the heaviest readers of AI output scored lowest on delivery fluency and target language quality. The pedagogical consequence is that reflection has to be scaffolded by external evidence, because a learner's strategy is not introspectable — the authors argue for guiding students to describe and evaluate why they worked a given way at each stage.
- **Process evidence is channel-conditional.** In 79 undergraduates working with generative AI, higher-depth monitoring and planning appeared more often in think-aloud units while higher-depth regulation appeared more often in interaction logs, so one record alone understates some processes (Li and Liu (2026)).
- **Reflective practices can emerge from ordinary subject-matter use.** Across eight Danish upper secondary schools, students working with Generative AI as a cognitive partner developed four practices — explanation, creation, inspiration, and improvement, unfolding into eleven processes — in which reflection appeared in both disciplinary and process registers, though each practice could equally serve substitution (Dalsgaard & Prilop, 2026).
- **A reflective scaffold can habituate and replace the self-monitoring it protects.** de Jong (2026) warns that repeated prompts to reflect may wear off through habituation — much as repeated warnings are dismissed automatically — so a professional who reflects only when the system asks may end with neither the tool nor the self-monitoring habit; the paper argues reflective prompts should be treated as a fading skill-building intervention and tested for whether users reflect without them.
- **A selective gain: metacognitive knowledge without planning and monitoring.** Wang et al. (2026) split 68 preservice teachers into a group that explained the flipped classroom to a

generative AI novice learner (n=33) and a group that questioned a generative AI teacher (n=35). The novice-learner group scored higher on metacognitive knowledge and learning strategies ($p < 0.001$, Cohen's $d = 0.41$) but not on planning and monitoring (M = 4.01 vs. 3.78, $p = 0.062$), even though the same group's explanation and application scores rose ($r = 0.474$ and $r = 0.642$) while factual recall did not separate the groups ($p = 0.416$). The split follows the two components in the Introduction: explaining to someone who asks back built declarative awareness of what one knows, but nothing in the design made the learner set a route or check progress, which the authors attribute to task design and cognitive load rather than to the role itself. Learning by Teaching with AI is therefore a lever on metacognitive knowledge, not automatically on regulation, and the authors recommend adding explicit planning prompts and progress feedback.

- **Think Aloud supports early awareness but not deep evaluation.** Karaki and Baroudi (2026) ran a mixed-methods action-research study with 44 first-year entrepreneurship students using the Think Aloud method during AI-supported coursework. Think Aloud made students' prompt construction, verification practices, and ethical decision-making more visible, but critical evaluation of AI outputs "often remained at a surface level, particularly among students requiring additional support" — students spotted generic or misaligned responses yet kept relying on them heavily. Self-reported metacognitive awareness was the highest of three surveyed constructs (M = 3.79), but the single post-intervention survey cannot separate perception from change. The authors' conclusion — Think Aloud is not a stand-alone solution and must be combined with explicit instruction in AI literacy, prompt construction, and verification strategies — extends the process-evidence line above from *what records capture* to *what vocalization alone changes*.
- **Prior metacognitive training gates the benefit of an AI reflection partner.** In a 2 × 2 experiment with 60 pre-service teachers, Zhang et al. (2026) found a significant metacognition × tool interaction: an AI Socratic partner beat traditional digital tools by 0.56 points only after training, with no advantage without it ($\Delta M = -0.03$).

Braun (2026) gives the suppression account a preregistered causal test (N = 317) against worksheets. Disorganization rose by 0.84 (95% credible interval 0.47 to 1.21) and was the clearest effect in the model, while deep processing fell through a chain running from offloading to critical thinking rather than directly. The author names the state cognitive dormancy, in which monitoring and strategy selection go quiet while processing continues, and locates its cause in the affordances of the environment rather than in the learner.

Monitoring changes the route more than it blocks the path. Guo and Dong (2026) split 600 undergraduates by a monitoring item and estimated each group separately: load predicted cognitive offloading at $\beta = 0.844$ for low monitors and $\beta = 0.840$ for high, effectively the same. Offloading predicted overreliance at 0.396 and 0.506, and the direct load path ran 0.560 and 0.419. Dependence among stronger monitors therefore traveled more through offloading and less directly. These are separate models, not a formal multi-group test.

When monitoring is skipped

Xiao et al. (2026) turned the suppression risk into a measured quantity across four experiments with 728 adults. Higher AI assistance raised task-level disengagement to 4.82 from 3.96 ($d = 0.67$), and offloading carried 58.0% of the effect (indirect 0.51, 95% CI [0.32, 0.72]). Expert raters then scored the delegated

proposals lower: quality fell from 4.78 to 3.95 (d = 0.75), with 57.8% of that drop running through disengagement (indirect -0.48, 95% CI [-0.68, -0.30]).

The cost is conditional. Task complexity strengthened that path (index -0.39, 95% CI [-0.62, -0.16]) while AI literacy weakened it (index 0.30, 95% CI [0.09, 0.52]). So monitoring is not only a capacity that predicts better use; skipping it is a step whose absence is visible in output quality through an offloading route. Two limits bound the claim. The AI was a researcher-scripted response bank, not a live model, and occupation and student status went unreported, so this is neither a classroom nor a workplace study.

The Engagement–Motivation Distinction

Scheu et al. (2026) found a critical split:

Dimension	LLM Assistant Effect	Course Effect
Intrinsic motivation (willingness to engage)	**No effect**	**Positive**
Behavioral engagement (amount written)	**Increasing over time** (feedback loop)	**Constant positive**

This suggests that **metacognitive support and Motivation are not identical**. The LLM assistant's Scaffolding of journal entries increased how much students wrote (behavioral engagement) but did not make them *want* to write more (intrinsic motivation).(Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement)

The Beliefs-vs-Experiences Distinction

Guo & Ye (2026) offer a theoretically sharper account of how metacognition governs strategy selection, distinguishing two components that operate in different phases:

- **Metacognitive beliefs** — stable, self-referential self-conceptions stored in long-term memory (e.g., beliefs about one's memory capability, or the reliability of a tool). These anchor strategy choices *before* task initiation.
- **Metacognitive experiences** — dynamic, task-specific feelings (perceived difficulty, confidence, mental workload) that drive belief *updating* during task execution.

This distinction yields the principle of **timing-component matching**: feedback that targets beliefs (e.g., comparative rankings) is most effective in the pre-task preparation phase, whereas feedback that targets experiences (e.g., immediate correctness indicators) is most effective during task execution. Abstract ranking feedback can become separated from — or overridden by — the task-specific experiences that dominate immediate decision-making, explaining why some feedback interventions fail to change behavior. This gives educators a phase-contingent rationale for designing metacognitive scaffolds around AI tools: calibrate beliefs before use, provide immediate task-specific feedback during use.

External support can also step in front of the judgment entirely. Iqbal et al. (2026) had 87 EFL students revise an essay with ChatGPT 4.0, an experienced academic writing instructor, or no support, and reconstructed the strategies students used from clickstream, keystroke and mouse traces. What they chose was strongly associated with the support available (Cramér's V = 0.668), but not with metacognitive

judgment accuracy ($H(3) = 4.995$, $p = 0.172$), which showed a marginal link only in the no-support condition ($p = 0.0460$). No revision strategy was associated with essay-score change ($p = 0.273$), yet the GenAI group improved significantly more than the other two ($H(2) = 16.591$, $p = 0.00025$, $\eta^2 = 0.174$), so the stronger essays did not come from better self-regulation. When a capable partner can supply the next move, metacognitive judgment stops being what selects it, and the strategy-choice account above describes the unaided learner more than the supported one. The authors' practical reading is to aim AI assistance at prompting reflection on writing strategies rather than at supplying direct help.

Calibration is trainable: prediction + feedback

Ngai & Gilbert (2026) provide direct causal evidence that metacognitive calibration is a *trainable* skill. In two preregistered experiments (N=164, N=416), **just five practice trials pairing a performance prediction with veridical feedback** improved calibration and reduced bias. A four-group additive design isolated the causal component: **making predictions alone was ineffective; adding performance feedback drove the improvement; explicitly labeling over-/underconfidence added nothing further**. Critically, the improvement acted on *absolute* calibration — raising confidence in the underconfident and lowering it in the overconfident — so it corrected miscalibration in both directions rather than shifting everyone one way (which is why signed/directional effects were null). This strengthens the "experiences not beliefs" account above and shows the *minimum viable metacognitive training*: prediction + immediate, task-specific feedback.

- **A brief reflection prompt sharpens monitoring during AI-supported decisions.** Ren (2026) added three reflection prompts before finalizing answers in a three-condition experiment with 342 undergraduates: acceptance of incorrect ChatGPT advice fell from 62.4% to 39.7% (*OR* = 0.40) and awareness calibration rose (0.59 vs. 0.41), while recommendation accuracy and alignment with correct advice stayed high. Reflection made reliance more discriminative rather than uniformly defensive, which supports treating reliance as a monitoring problem rather than a question of how much AI is used.
- **Nest prompting inside a metacognitive cycle.** The IDEA framework sequences GenAI use as Intent, Deconstruction, Expression, and Adaptation, making prompting one step in planning and monitoring rather than a stand-alone skill; students taught it produced higher-quality prompts than peers taught Role–Task–Context–Format prompting in all five task categories (Wang et al., 2026).

Implications for Tool Design

1. **Preserve the "friction" of thinking:** If AI writes the reflection, the student does not build metacognitive skill. Journaling assistants should scaffold, not author.
2. **Model metacognitive language:** The example-based course worked partly because it exposed students to proficient models' metacognitive self-talk.
3. **Separate support for motivation vs. skill:** Metacognitive skill development (course-structured) and productivity enhancement (AI-assisted) may require different design strategies.
4. **Name the target as onloading, and ration the help.** A metacognitive approach to learning and performance in human-AI interaction separates cognitive offloading, which stays under metacognitive control, from *metacognitive* offloading, where planning, monitoring, evaluation and

judgment calibration are handed over. Their design target is metacognitive onloading: scaffolds that make the learner, not the AI, set goals, anticipate difficulty and judge strategies, placed within a prompt, across a task, and fading over time. The help rule is minimum-necessary: a hint or diagnostic question first, with deeper assistance unlocked only after the learner asks, monitors or chooses a direction. The paper is conceptual and its authors note that no validated measure of either construct yet exists.

AI may alter the **metacognitive threshold** for deciding one knows enough to answer: Marcoccia et al. (2026) found that mere access to AI advice suppressed people's willingness to suspend judgment under uncertainty, even with wrong advice and accuracy incentives — an effect that survived unsolicited AI output and monetary stakes.

Proactive agentic AI can displace the learner's own metacognitive loop: Woollaston et al. (2026) argue that when agents pre-fetch, initiate, and self-correct, the agent's planning, monitoring, and evaluation replace the learner's, removing the retrieval practice and self-monitoring that desirable difficulties and metacognitive training depend on.

- **Mistake-based Pedagogies and Teaching Strategies as metacognitive training:** Hosseini (2026) shows that deliberately exposing students to AI-generated errors in a database design course activates metacognitive monitoring — students inspected outputs, identified errors, and revised designs rather than accepting AI output at face value. Self-reported AI literacy correlated weakly and negatively with objective competency (r=−0.39), a calibration gap the critique-refinement cycle is designed to narrow.
- **Productive failure engages metacognitive monitoring.** Kim et al. (2026) show productive-failure-based learning activates reflection on one's own attempts; clue-before-correction tasks require learners to diagnose and correct their own errors — a metacognitive activity where AI gives clues rather than answers.
- **Self-regulation buffers offloading harm but cannot cancel it.** Chen (2026) shows that metacognitive regulation (self-regulated writing) attenuates the negative association between deep cognitive offloading and independent no-AI outcomes in GenAI-assisted writing (interaction B = 0.22), but does not eliminate it — a bounded-support condition pairing delegation limits with compulsory reflection about how AI suggestions were accepted/rejected produced the strongest independent performance.
- **Explanation-seeking depth predicts task quality, not recall.** Tsiligkiris (2026) shows explanation-seeking prompts (depth) in LLM interaction predict task quality but not immediate recall, interpreting the dissociation via elaboration (comprehension) vs. retrieval practice (consolidation) — and suggesting explanation-seeking correlates with metacognitive monitoring, though retrieval demands must be added for durable retention.
- **Self-reported metacognition is a weak proxy for regulation *with* an LLM.** Clerc et al. (2026) gave 116 middle-school students a two-hour AI literacy workshop and then measured their LLM interaction during science problems: trained students accepted underspecified prompts less often (51.5% vs. 66.7%), asked follow-up questions after a weak response far more often (59.2% vs. 27.9%, d = 0.80) and judged answer correctness more sensitively to prompt quality (interaction OR = 2.52). Neither a general metacognitive-awareness scale (Jr. MAI) nor GenAI self-reports

predicted those behaviors or final performance (r = .04 and r = .01) — monitoring and control during generative AI use is task-specific, and observable behavior carries more information than the self-report instruments built to capture it.

- **Automated scoring reached the performance phase, not the planning that precedes it.** Chen and Liu (2026) gave 46 interpreting students 14 weeks of weekly automated scoring with a returned score, marked errors, and a reference rendition: the automated group gained more overall (d = 1.03). Only monitoring during practice correlated with score gains (r = 0.42), while pre-learning planning sat near the scale midpoint (M = 3.01). Evaluation and reflection carried the second-highest mean (3.87 of 5) yet showed a near-zero link to gains (r = 0.10), so a high reflection score should not be read as productive reflection.
- **Verification literacy pays off only through metacognitive self-regulation.** Davor, Larbi and Boateng (2026) surveyed 533 university students and found that AI verification literacy had no direct association with critical thinking or technical Problem Solving; it mattered only indirectly, through metacognitive self-regulation (a full mediation pattern). Cognitive offloading tendency ran the other way, predicting lower self-regulation (-.294) along with lower critical thinking (-.240) and problem-solving (-.312).
- **Reflection rose with AI access, and it fed reasoning rather than test scores.** Melanou, Beege and Kimmig (2026) followed three classes (N = 87) across a nine-week course, measuring at three points. Knowledge improved in all conditions with no advantage for either AI condition and no Matthew effect (BF01 = 8.70), but reflective use (checking sources and verifying AI output before adopting it) was far higher in the AI condition than the control group (M = 3.72 vs. 2.82, $F(1, 40) = 20.21$, $p < 0.001$) and predicted critical thinking ($\beta = 0.43$, $p < 0.001$, $R^2 = 0.183$) while predicting no knowledge gain. Reflection appeared from tool access alone rather than from scaffolding, and because its payoff lands in reasoning, a knowledge test will not register the metacognitive benefit of an AI-supported course.
- **Inside a metacognitive self-report instrument, awareness outpredicts the rest.** Alatoai and Alshahri (2026) validated a 45-item measure of AI-supported STEM learning with 649 Saudi secondary students (CFI = 0.983, RMSEA = 0.019; subscale ω = 0.888–0.905) and used it to rank the components. The four dimensions explained 68% of the variance in self-regulated learning scores, with AI-based metacognitive awareness strongest ($\beta = 0.38$, $p < 0.001$), cognitive transfer and adaptability next ($\beta = 0.29$, $p = 0.008$), and creative and critical AI-STEM reasoning not significant ($\beta = 0.14$, $p = 0.135$). Awareness is the component that carries adaptive performance, the authors advise reporting subscales separately rather than one global score, and they reserve higher-order reasoning for reasoning-quality tasks; the measure is nonetheless self-report, so like the workshop study above it captures perceived capability rather than observed strategy use.
- **The evaluator's own monitoring is metacognitive work too.** Hoppe, Loibl and Leuders (2026) argue that an AI-generated diagnostic inference is not raw evidence but an interpretation already made, so teachers must integrate it with their own observations in a process they call *meta-diagnosis*, deciding deliberately whether to accept, reject, or modify it. That places a second metacognitive loop beside the learner's: not only how the student regulates thinking with AI, but how the teacher evaluates what the system claims about that thinking.

Common Misconceptions

- **“AI assistance leaves the underlying ability intact.”** Students who used AI essay assistance were **83% unable to recall quotes from their own essays, against 11% for non-AI users**, indicating **they did not engage with the content during production**. The production process is where the engagement happens, and bypassing it shows up later.
- **“Offloading degrades everything.”** The cost appears **bounded rather than global**: offloading degrades **the specific skill practiced, not the underlying domain-general abilities**, and surfaces on **with**-something transfer tests. The localisation matters, because it says what to protect rather than warning about general decline.
- **“Ability to produce implies ability to retain.”** The 83% versus 11% recall gap is the direct counterexample: output was produced in both conditions and the memory trace differed enormously.

Connected Concepts

- Pedagogical Patterns — The reflection steps these sequences build in
- Learners — Learners: the umbrella for the learner-side concepts
- Self-Regulated Learning
- Self-Assessment
- Cognitive Offloading
- Scaffolding
- Agentic AI
- Formative Assessment
- AI Literacy
- Retrieval, Spacing and Interleaving — judgments of learning and the fluency illusion that retrieval practice corrects
- Cognitive Surrender
- Reflection

Connected Articles

- Teaching students to question the machine: An AI literacy intervention improves students’ regulation of LLM use in a science task — a two-hour AI literacy workshop shifted middle-school students’ LLM-interaction regulation, unlike their self-reported metacognition (Clerc et al. 2026)
- Student-AI interaction in computer-assisted consecutive interpreting: patterns and performance — Student-AI Interaction in Computer-Assisted Consecutive Interpreting
- Epistemic dependence in AI-mediated learning — Epistemic dependence in AI-mediated learning (Du & Yuan 2026)

- What students ask matters: LLM interaction depth, task quality, and immediate recall in higher education — What students ask matters: LLM interaction depth, task quality, and immediate recall (Tsiligkiris 2026)
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Efficiency vs. Effectiveness: Self-Regulated Learning with LLM-Mediated Help-Seeking — LLM-mediated help-seeking in STEM: layered, instrumental, and verified
- How motivation and roles influence metacognitive engagement in student-GenAI interaction — Motivation and roles in metacognitive GenAI engagement
- Metacognitive training facilitates optimal cognitive offloading — Metacognitive training facilitates optimal cognitive offloading (Ngai & Gilbert 2026)
- Meta-cognitive insights into cognitive offloading: Mechanisms, interventions, and educational implications — Meta-cognitive insights into cognitive offloading: mechanisms, interventions, and educational implications (Guo & Ye 2026)
- The IDEA Framework for Metacognitively Regulated GenAI Use in Higher Education: Development and Exploratory Pilot Evidence — The IDEA framework for metacognitively regulated GenAI use
- HAIML: A human-centered AI metacognitive learning model — A framework for human agency and reflective learning in the age of artificial intelligence — HAIML: a human-centered AI metacognitive learning model (agency & reflective learning)
- Metacognitively discordant completion and the aware pass-through of non-understanding in generative AI learning — Metacognitively discordant completion and aware pass-through of non-understanding
- Mapping the Scaffolding of Metacognition and Learning by AI Tools in STEM Classrooms: A Bibliometric–Systematic Review Approach (2005–2025) — AI tools scaffolding metacognition in STEM
- Is AI making us stupid — Is AI making us stupid? critique of cognitive offloading
- The Evidence Base on AI in K-12: A 2026 Review — General-purpose AI suppresses metacognition by completing reasoning
- AI advice suppresses people’s willingness to say "I don’t know", even when the advice is wrong and accuracy is incentivized — AI advice suppresses willingness to say “I don’t know”, even with wrong advice and accuracy incentives
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — Agentic AI and pedagogical best practice: the tension between automation and learning
- Cognitive offloading and the speedup illusion in human-AI interaction — Cognitive offloading and the speedup illusion in human-AI interaction

- Artificial intelligence, cognitive offloading and implications for education — AI, cognitive offloading and implications for education (Lodge & Loble 2026)
- The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking — The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking (Hosseini 2026)
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Language Learning
- Prompts to Practice: A Pedagogical Framework for Human-Centered AI Engagement — Reflection on the prompting process and authorship development in the Prompt Literacy Cycle (Miles, Haber-Curran & Arar 2026)
- College students' metacognitive awareness of generative-AI reliance: an experimental study of decision confidence and attribution bias — A reflection prompt cut acceptance of incorrect AI advice and improved awareness calibration (Ren 2026)
- Impact of automated scoring on interpreting performance and self-regulated learning: evidence from a pedagogical experiment — Automated scoring reinforced monitoring but not planning, and self-reported reflection stayed unproductive (Chen & Liu 2026)
- Artificial intelligence-supported learning and higher-order cognitive outcomes: the mediating role of metacognitive self-regulation — Verification literacy acting only through metacognitive self-regulation (Davor, Larbi & Boateng 2026)
- Human or GenAI Support? Conditions Impacting Students' Strategy Choices in an Essay Revision Task — External support, not metacognitive judgment accuracy, drove revision strategy choice (Iqbal et al. 2026)
- The Contribution of Generative Artificial Intelligence as a Novice Learner to Students in the Learning by Teaching Model — A selective gain: metacognitive knowledge rose while planning and monitoring did not (Wang et al. 2026)
- Generative AI and Learning Dynamics in Higher Education: A Longitudinal Empirical Study — Reflective use rose with AI access and predicted critical thinking, not knowledge gain (Melanou, Beege & Kimmig 2026)
- Exploring the Impact of AI-Based Learning Environments on Student Self-Regulation and Adaptive STEM Learning — Metacognitive awareness as the strongest predictor of adaptive STEM learning (Alatoai & Alshahri 2026)
- Rethinking teachers' diagnostic skills in AI-supported formative assessment: from diagnosis to meta-diagnosis — From diagnosis to meta-diagnosis: teachers judging AI-generated inferences (Hoppe, Loibl & Leuders 2026)
- Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement — Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement

- Conceptualising Human–AI Collaboration Competency for hybrid intelligence: towards learner agency through a metacognitive perspective — Metacognition, not pedagogy, as the mechanism of learner agency in human-AI collaboration (Dang, Hong, Doyle & Nguyen 2026)
- Metacognitive Ownership in Human-AI Regulation: Construct Definition, Boundaries, and a Research Agenda — Metacognitive ownership: a construct for learner governance of standards, judgments and actions
- Mapping the Distribution and Depth of Metacognitive Processes in Generative AI-Assisted Learning: Evidence from Interaction Logs and Concurrent Think-Aloud Protocols — Logs and think-aloud capture different metacognitive processes in GenAI-assisted learning
- AI as a cognitive partner in learning: Emerging epistemic practices of reflective thought — four practices and eleven processes of reflective thought when students treat AI as a cognitive partner
- Ethical generative AI use in higher education: An action research study using the Think Aloud method — Think Aloud made prompt construction, verification and ethical reasoning visible, but critical evaluation stayed surface-level; not a stand-alone solution
- Metacognitive training and AI-based Socratic scaffolding in pre-service teachers' reflective practice: a dual-study experimental design — Metacognitive training and AI-based Socratic scaffolding in pre-service teachers' reflective practice: a dual-study experimental design
- Cognitive dormancy: Supplanting structured learning with AI affordances — Cognitive dormancy: an experimental account of suspended metacognitive engagement and rising disorganization (Braun 2026)
- Can artificial intelligence promote metacognition? Evidence from a three-level meta-analysis — Three-level meta-analysis: pooled g = 0.624, falling to non-significance for accuracy-rated monitoring (Li et al. 2026)
- A metacognitive approach to learning and performance in human-AI interaction — SYNC model: metacognitive offloading vs. onloading, and task performance decoupled from durable learning (Fan et al. 2026)
- University students' overreliance on generative AI feedback in the learning process: the effects of perceived cognitive load, cognitive offloading, and metacognitive monitoring — Monitoring does not block the offloading path so much as reroute it
- Metacognitive disengagement and knowledge innovation quality in human–AI collaboration: the mediating role of cognitive offloading and the moderating roles of task complexity and AI literacy — When monitoring is skipped, and what it costs

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Should I Use AI to Study and Learn Effectively?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Reflection

> **Reflection** — the deliberate, retrospective examination of one's own experience, work or reasoning, externalized in written, spoken or recorded form so that it can be revisited, shared or assessed. Its nearest neighbour in this knowledge base is Metacognition, and confusing the two is the most common error on the topic. Metacognition is the monitoring machinery: the in-the-moment judgments of whether you understand, remember or are on track. Reflection is a designed activity with a deliverable — a journal entry, a reflective essay, a portfolio commentary, a structured self-explanation prompt — performed after or alongside the work. The distinction acquires teeth in the AI era because the two are exposed differently: monitoring is hard to hand over and easy to displace, while a reflection artifact can be produced by a model, which makes the authenticity of the artifact rather than the depth of the thinking the first design problem.

Questions to Consider

- When you finish a difficult task, what is the difference between knowing you found it hard and actually working out *why* you found it hard? Which of those two does an end-of-week journal entry capture?
- A student submits a thoughtful three-hundred-word reflection that a model wrote for them. Is anything wrong with the document itself — and what exactly has the assessment lost?
- Several studies here find that adding reflection prompts *reduces* how much practice students complete while making them spend longer on each piece of Feedback. If reflection costs volume, when is that trade worth making?
- If a program can score a reflective essay for depth automatically, does that make reflection easier to teach or easier to fake?
- Teachers with less experience name lack of time as their main obstacle to reflecting; experienced teachers name tracking student performance. What does that imply for a single reflection tool rolled out to a whole school?
- Reflection is usually required, graded and prompted. What happens to a genuinely reflective habit when it becomes a compliance artifact?

Introduction

Reflection as an educational construct carries a family of models rather than a single definition: Kolb's cycle, Gibbs's structured stages, the DIEP framework, Schön's reflective practitioner, Mezirow's transformative reflection, and Boud's work on reflection in learning. The knowledge base's research treats these as a shared inheritance and then asks what generative AI changes about each of them. The recurring objects of study are reflective writing as an assessed genre, the journal or log as a routine, the e-portfolio as a container and an assessment form, and the prompt as the smallest unit of intervention.

Two further distinctions organize the literature. The first is *depth*: reflection is scored on levels, from descriptive retelling at the low end to critical, theory-informed examination of one's own assumptions at the

high end. The second is *author*. Until recently the second question did not arise. It now does, because the artifact and the thinking have come apart.

How reflection relates to self-assessment, metacognition and e-portfolios

The boundary work matters more here than on most concept pages, because four adjacent pages each own part of the territory, and practitioners routinely use the words interchangeably in rubrics.

What they **share** is real. All of them turn the learner's attention back onto their own work, all are associated with Learner Agency and self-awareness, all can be scaffolded and all can be performed for a grade. Every one of them is also being rewritten by generative AI in the same period, which is why the same studies recur across these pages. Reflection is the one in the group whose product is a *text*, and that is where the family resemblance stops being useful.

Where they differ is in what each leaves behind and what evidence counts.

Concept	Its core question	What it leaves behind	How reflection relates
Metacognition	Do I understand this, and how sure am I?	a judgment, often made in the moment	Monitoring can happen with no record at all; reflection is the deliberate examination that monitoring feeds
Self-Assessment	How good is my work against these criteria?	a rating, a score, sometimes a justification	One common *content* of a reflection; self-assessment needs no written reflection, and reflection can be about experience rather than performance
Self-Regulated Learning	What is my goal, what strategy am I using, and what do I change?	a planning-monitoring-adjusting cycle	Reflection is one phase inside the cycle, not the cycle itself
E-Portfolio	Where does the work live, and how is it curated?	an assembled set of artifacts with commentary	The container; curation becomes reflection only when someone asks the learner to explain the choices
Experiential Learning	What experience am I drawing on?	a cycle of action and abstraction	Supplies the material reflection works on
Feedback	What do I do with this information?	an uptake, a revision	The most common object of reflection

The practical consequence of keeping them apart is that each names a different thing to grade. A metacognitive judgment is correct or miscalibrated. A self-assessment is accurate or inflated. A reflection is specific or generic, evidenced or unsupported, and that is a property of the text rather than of the learner's state.

What reflection costs, and what it buys

The sharpest experimental test in this knowledge base is a preregistered between-subjects study with 302 US adults learning introductory Python. Asher, Gold and Carvalho (2026) compared a video crash course, practice with personalized AI feedback, and the same feedback paired with self-explanation prompts.

Reflection lost on nearly every measure. It roughly doubled time spent with feedback, 4.1 versus 2.1 minutes ($t(267) = 11.30$, $p < .001$), and cut practice volume by 40%, 2.0 versus 3.4 problems ($t(267) = 8.20$, $p < .001$). Each problem yielded the same learning gain with or without the prompts (Reflection × problem number OR = 1.03, $z = 0.23$, $p = .486$), so the practice arm finished with higher mastery, 79% versus 65% ($d = .41$).

The design lesson is not that reflection is useless. It is that a reflection prompt is a *competing* demand on scarce session time, and it can cost more than it returns when it arrives before the learner has finished an attempt.

When the reflection is not the student's

Authenticity is the live problem. Kadel et al. (2026) argue that the classical models have no strategy for a world where a reflection can be generated, and propose a GenAI-aware five-part structure: Purpose, Process, Product, Pitfalls, Plan. Its operational move is to require the documented trail — the prompts used, the iterations, the validation steps — rather than the polished final text, which is a "process over product" answer to the authorship question.

Others locate reflection inside the assessment machinery. Oktoma, Nugraha and Hidayat (2026) make structured reflection a live input that recalibrates the next feedback cycle instead of a post-hoc add-on. Pedlow and Maldon (2026) embed guided reflection inside pre- and post-semester Self-Assessment as a route to integrity and ethical confidence with GenAI.

The most useful caution comes from Dalsgaard and Prilop (2026), whose year-long study across eight Danish upper secondary schools (59 teachers, 48 students) found four GenAI practices — explanation, creation, inspiration, improvement — expanding into eleven processes, each of which can either support reflective thought or replace it.

An AI reflection partner can fail invisibly

A randomized trial had found that emerging adults reflecting on their careers with a GPT-4o conversational agent ended *less* committed to their plans than those using a static journaling survey. Nepal et al. (2026) coded all 17,930 turns to find the cause.

Every rule the agent followed was one that could be checked mechanically: a reply-length cap, for instance. Rules about how to behave — do not flatter, challenge gently — were broken without leaving a visible trace in the transcript. The behavior tied to added doubt was a repeated demand to decide when participants hesitated.

That finding generalizes beyond career reflection. An AI reflection partner degrades in the one place its output looks fine, so the artifact cannot serve as evidence that the conversation was good.

Scoring reflective writing at scale

Depth is measured, and increasingly automated. The Hungarian reflection-level study (2026) used 1,954 expert-annotated essays written over four consecutive years in an Early Childhood Education program, comparing classical models on TF-IDF features and Qwen3 embeddings against two fine-tuned Hungarian transformers.

The corpus is severely skewed: 68% of essays sit at level 3 and only 1.8% at level 0, so much of the paper is imbalance handling. Shallow models reached up to 71% on an averaged accuracy-F1-ROC AUC score; the transformers reached 68% overall but handled minority levels better.

The measurement lesson is narrower than it looks. A classifier estimates how reflective a text reads. It cannot tell whether the reflection happened, and it is exactly the level of performance a fluent model can imitate.

Journals, portfolios and prompts as delivery systems

The construct is usually delivered by three vehicles, and each has its own failure mode.

Routine journaling fails to motivation decay. Scheu et al. (2026) ran a randomized 2×2 field experiment with 179 German university students over 22 days with a 12-week follow-up, testing an example-based seven-day course and an Large Language Models (LLMs) journaling assistant that summarizes drafts, asks clarifying questions and offers alternative formulations. Sustaining the routine, not designing the prompt, was the hard problem.

Portfolios fail when the container substitutes for the act. Ni and Lam (2026) followed 50 first-year Tourism Management students through 16 weeks of WordPress e-portfolios with GenAI as a feedback provider and a synthesizer of peer and teacher comment, tracing multiliteracies development across three stages. Sutama (2026) tested ChatGPT aligned with e-portfolio assessment against a control in 60 vocational EFL students and found a large simultaneous effect (Wilks' $\lambda = 0.476$, $p < .001$, partial $\eta^2 = 0.524$), with speaking at 82.733 versus 78.833 and Feedback Literacy at 79.666 versus 71.762.

Prompts fail when they are inserted at the wrong moment, as the Asher study shows.

Reflection in professional learning

For teachers the construct doubles as professional development. Falhs (2025) surveyed 100 US K–12 teachers and found needs that diverge by experience: less experienced teachers cite lack of time as a top obstacle far more often, 37% versus 12% ($p < .001$), while experienced teachers more often report difficulty tracking student performance, 28% versus 15% ($p = .009$). Informal feedback motivates experienced teachers more, 45% versus 31% ($p = .025$). A single reflection tool for a whole school is therefore mis-specified by design.

Ho and Chen (2026) add the process view from 18 teachers in mainland China and Hong Kong, whose accounts resolve into recognizing the need to use GenAI, redistributing cognition, and reflectively re-engaging after use. The Reflective Triangle Model (2026) connects self-reflection, collaborative reflection and community reflection across a professional learning community in a four-week case with six teachers, with AI as a cognitive mediator rather than an evaluator.

Preparation also matters independently of the tool. Zhang et al. (2026) crossed metacognitive strategy training against a placebo module with an LLM configured as a Socratic reflection partner versus traditional digital tools, in a 2 × 2 design with 60 pre-service teachers. Both main effects were significant for written reflection quality at post-test.

The risk that a reflection prompt replaces the monitoring it means to build

de Jong (2026) raises the field's untested assumption: cognitive forcing, pre-commitment and uncertainty communication reduce overreliance within a session, but nothing establishes that they build durable self-monitoring rather than habituating the user to prompts. A mechanism that supplies reflection can substitute for the monitoring it was meant to develop.

Two designs respond to that worry differently, and both are useful signals. PAUSE (Alam, 2026) is a privacy-by-design self-check that turns the empirical literature on Cognitive Offloading into descriptive, non-diagnostic reflections across four domains, with no composite score and an explicit refusal to justify any consequential decision. Wang and Zhao (2026) treat reflective AI use as a measurable construct, finding acceptance predicting it at $\beta = 0.774$, and reflective use predicting Self-Efficacy at $\beta = 0.519$ and engagement at $\beta = 0.273$.

Guidance for practitioners

Designing the reflection task

- **Sequence the prompt after an attempt closes.** The 302-adult experiment is the cautionary case here: prompts that interrupted work between an attempt and its feedback spent the session's time and shrank how much practice was completed.
- **Name the depth level you are rewarding.** The Hungarian corpus scores reflection on levels from descriptive retelling to critical examination of assumptions. A prompt asking students to "reflect" while the rubric rewards description produces descriptions.
- **Prompt for the episode, not the term.** "What did you try, what failed, and what did you change on the third attempt?" is answerable. "Reflect on your learning journey" is not.
- **Ask for the process trail.** Recorded prompts, abandoned drafts, a rejected approach and the reason for the final choice are all cheap to produce, hard to fake, and exactly what the GenAI-aware models put first.

A starter prompt that survives most of the failure modes above: *(1) What did you try, and what did the result tell you? (2) Which AI output did you accept, and what did you check before accepting it? (3) What will you do differently on the next attempt, and why?* Each question asks for something a student has to know rather than something a model can supply, and question two is what turns an AI-use policy into a reflection task.

Making AI use explicit rather than forbidden

- **Reward disclosure.** A reflection that documents how GenAI was used, checked and corrected is more useful evidence than one that omits it, and the five-part GenAI-aware model is built on that premise — Purpose, Process, Product, Pitfalls, Plan.

- **Set the policy inside the prompt.** State what may be delegated and what must be the student's own observation; a policy in a syllabus is invisible at the moment of writing.
- **Keep the AI in the questioning role.** A partner that asks clarifying questions and offers alternative formulations preserves the learner's articulating work; one that writes the entry removes it.
- **Audit any reflection agent you deploy.** In the one coded audit in this knowledge base, the agent obeyed mechanically checkable rules and broke the behavioral ones without leaving a trace, while looking perfectly plausible.
- **Do not turn a wellbeing-oriented self-check into a diagnosis.** The PAUSE design is the model here: descriptive, domain-aware reflections, no composite score, and an explicit refusal to justify any decision about a person.

Grading authenticity

- **Grade what you can defend.** Specificity, evidence of a decision, revision reasoning and honesty about what went wrong are gradeable. Sincerity is not, and a fluent model can imitate the surface of all of it.
- **Pair the artifact with something expensive to delegate.** A short verbal defense, a live revision, or a decision that has consequences — the Prober system's reflective gate and Issa and Hall's per-member verification meetings are two working patterns.
- **Watch what grading does to the act.** When self-reflection is graded it risks becoming performative, so state what the reflection is *not* assessed for and keep at least some reflection ungraded.
- **Never treat a score as proof of thinking.** Depth classifiers estimate how reflective a text reads, which is a property a fluent second draft can manufacture.

Sustaining the routine

- **Design for motivation decay, not for prompt quality.** Reflective journals are abandoned within weeks; example-based onboarding and a conversational assistant that asks questions were the two interventions this corpus tests against that.
- **Favour frequency over length.** A short entry after each attempt sustains the habit; a long entry at the end of term is a single writing task with a reflective label.
- **Give the portfolio a reflective checkpoint.** Without a commentary requirement at each curation point, an e-portfolio becomes a museum of finished products.
- **Adapt to expertise.** Less experienced teachers cite time as their top obstacle; experienced teachers cite tracking student performance, so one reflection interface across a whole staff serves neither group.
- **Pair tool access with preparation.** Metacognitive strategy training and a Socratic AI partner each improved written reflection quality on their own in the pre-service experiment, which suggests the preparation is not optional Scaffolding for the tool.

Common Misconceptions

- **“Reflection and metacognition are the same thing.”** They are related but separable. A judgment about your own state of understanding and an activity that leaves a record behind are different objects of study, which is why this knowledge base keeps them on separate pages.
- **“Reflection is always worth the time it takes.”** At least one preregistered experiment found the trade unfavourable, because the reflection competed with practice for the same session minutes.
- **“A deep-sounding reflection means deep thinking happened.”** Reading as reflective and being reflective are different properties, and a fluent model can supply the first.
- **“Automated scoring solves the scale problem.”** Classifiers reach roughly 70% on reflection level in a well-annotated corpus with severe class imbalance, and that ceiling is within reach of plausible text.
- **“Portfolios are reflective by nature.”** The container is not the act; a portfolio assembled from polished products can contain no reflection at all.
- **“Reflection needs no teaching.”** Both the Hungarian essay corpus and the pre-service teacher experiment presuppose that level and quality are learned, and that preparation changes outcomes.

Connected Concepts

- Metacognition
- Self-Regulated Learning
- Self-Assessment
- E-Portfolio
- Feedback
- Feedback Literacy
- Critical Thinking
- Experiential Learning
- Authentic Assessment
- Formative Assessment
- Cognitive Offloading
- Academic Integrity
- Student Engagement
- Motivation
- Teaching
- Writing
- Generative AI

Connected Articles

- Benefit or Bottleneck? Assessing the impact of structured reflection on learning from AI-driven explanatory feedback — Preregistered 302-adult experiment: reflection prompts doubled time on

feedback and cut practice volume 40% without raising per-problem gain (Asher, Gold & Carvalho 2026)

- The 5P Reflection Model for Education in the Generative Artificial Intelligence (GenAI) Era — GenAI-aware five-part reflection model built on documented prompts and iterations rather than the final text (Kadel et al. 2026)
- Automatic Reflection Level Classification in Hungarian Student Essays — 1,954 annotated essays, severe class imbalance, shallow models at 71% and transformers at 68% (2026)
- Faithful Where It Can Be Checked: Auditing a Reflection Agent Against Its System Prompt in a Randomized Trial — 17,930 turns coded to explain why an AI reflection partner left users less committed (Nepal et al. 2026)
- The Reflective Triangle Model: AI as a Cognitive Mediator in Teachers' Professional Learning and Learning-Community Development — Self, collaborative and community reflection with AI as cognitive mediator (2026)
- How expertise levels shape preferences and reflection needs — towards AI reflection systems for teacher empowerment — 100 K–12 teachers: time is the novice's obstacle, performance tracking the expert's (Falhs 2025)
- AI as a cognitive partner in learning: Emerging epistemic practices of reflective thought — Four GenAI practices and eleven processes, each able to support or replace reflective thought (Dalsgaard & Prilop 2026)
- Designing a mobile chatbot-based learning journaling system for intrinsic motivation and engagement — Randomized 2×2 field experiment on sustaining a reflective journaling routine (Scheu et al. 2026)
- Metacognitive training and AI-based Socratic scaffolding in pre-service teachers' reflective practice: a dual-study experimental design — 2×2 test of strategy training against a Socratic LLM reflection partner (Zhang et al. 2026)
- PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading — Non-diagnostic self-reflection tool with no composite score (Alam 2026)
- Reflective AI use and student engagement in AI-supported programming: technology acceptance, programming self-efficacy, and behavioral trace evidence — Reflective AI use as a measured construct linking acceptance to self-efficacy and engagement (Wang & Zhao 2026)
- AI-mediated authentic assessment and metacognitive reflection: A mixed-methods study of the AAIWA model — Structured reflection as live input that recalibrates the next feedback cycle (Oktoma et al. 2026)
- Raising Ethical Awareness of GenAI Use Through Student Self-Assessment in the Transition to Higher Education — Guided reflection inside self-assessment for ethical GenAI use (Pedlow & Maldon 2026)
- Teachers as reflective regulators of cognition: Understanding cognitive offloading in AI-augmented practice — 18 teachers on recognizing, redistributing and reflectively re-engaging after AI use (Ho & Chen 2026)
- Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement — Position paper: no evidence that reflection prompts build durable self-monitoring (de Jong 2026)

- Students' perceptions of multiliteracies development using AI-assisted portfolio assessment — 16-week WordPress e-portfolios with GenAI as feedback provider and synthesizer (Ni & Lam 2026)
- Aligning ChatGPT with e-portfolio assessment as EFL learning model: its effect on students' speaking performance and feedback literacy — ChatGPT aligned with e-portfolio assessment, Wilks' $\lambda = 0.476$, partial $\eta^2 = 0.524$ (Sutama 2026)

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Should AI Be Designed Into the Learning Experience?
- How Do I Keep Students from Over-Relying on AI?

Desirable Difficulties

> **Desirable difficulties** — the finding (Bjork) that harder, effortful retrieval conditions — spacing, retrieval practice, interleaving, and generation — improve long-term learning more than easier, massed conditions — is the theoretical counterweight to AI that smooths away cognitive work. In the AI era the principle warns that tools which eliminate productive struggle may raise immediate performance while undercutting durable learning. **Desirable difficulties, cognitive friction, and productive friction are used as overlapping synonyms** for this intentional effort: the knowledge base treats them as the same core idea viewed from different fields, with the nuances between the labels spelled out in the section below. Closely allied concepts — **confusion**, and **productive struggle** — mark the zone where this effortful processing is expected (and desirable) to occur.

Questions to Consider

- Have you ever felt you understood something because it felt easy and fluent in the moment — only to fail when you had to recall it later? That's the illusion of competence. What created it for you?
- Desirable difficulties say that effortful conditions — spacing, retrieval practice, interleaving — build durable learning better than easy, massed ones. Where in your own learning have you resisted a 'harder' strategy that probably would have worked better?
- Generative AI is, by default, a friction-removing machine: it answers instantly and produces polished output on demand. If removing struggle raises immediate performance but undercuts durable learning, how would you know whether an AI is helping or harming a student?
- This page distinguishes desirable difficulties (memory optimization from cognitive psychology) from productive/cognitive friction (engagement Guardrails from UX design). Can you see why the same educational goal needs both — and where they'd diverge?
- Some AI tutors are found to 'over-scaffold' — removing the very effortful processing desirable difficulties require. If you were evaluating an AI tutor, what concrete behavior would tell you it's preserving productive struggle rather than collapsing to answer-giving?
- Confusion is framed here as a resource, not a bug — when resolved productively it drives deep processing, but unaddressed it decays into frustration. Where's the line between productive struggle worth preserving and frustration that's just harmful?

Introduction

Desirable difficulties are the conditions of practice that make learning feel harder in the moment — effortful retrieval, generation and explanation, spacing, interleaving — yet produce stronger retention and Transfer of Learning than conditions that feel easy. The same phenomenon appears in the literature as **cognitive friction** and **productive friction**, labels borrowed from human–computer interaction and UX design that emphasize deliberately placing resistance between a learner and an easy answer; the families overlap but are not identical, and the differences are set out below. Because generative AI is optimized to be frictionless, the

concept has become a first-order design concern rather than a niche finding: systems that answer instantly remove difficulty that may have been doing the learning (Cognitive Offloading, Scaffolding).

The Effort–Learning Trade-Off

Desirable difficulties rest on the insight that conditions that make learning feel harder in the moment — requiring effortful retrieval, generation, or explanation — frequently produce stronger retention and transfer than conditions that feel easy. Conversely, conditions that feel easy (fluent presentation, immediate answers) can produce an illusion of competence: Learners feel they know the material because recognition was smooth, while later free recall fails. This is the theoretical core of the **performance–learning gap**: what looks like good performance during practice is not the same as durable learning.

Effort that buys nothing is not a desirable difficulty. In a preregistered experiment with 302 adults learning introductory Python, adding self-explanation prompts to already-elaborated AI feedback doubled time on feedback (4.1 vs 2.1 minutes) and cut problems completed from 3.4 to 2.0, with final-problem scores of 45% against 60% (d = .41) (Asher, Gold & Carvalho, 2025). The boundary the study locates: difficulty is desirable when it drives additional retrieval, application or comparison, and redundant when the learner already has a personalized explanation of the specific error.

Confusion, Cognitive Friction, and Productive Struggle

Three related constructs describe the zone in which desirable difficulties operate:

- **Confusion** — a learning *epistemic emotion* (see Affective Computing and Ordered Network Analysis of Epistemic Emotions during Collaborative Problem Solving) that signals a gap between a learner's mental model and incoming information. Confusion is not uniformly bad: when resolved through productive inquiry it can drive deep processing, but when unaddressed it can decay into frustration or disengagement. AI systems increasingly detect confusion (e.g. capture buttons, affective sensing) to anchor personalized support — as in From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review, where marked confusion points become review anchors and teach-back prompts surface conceptual gaps.
- **Cognitive friction** — the deliberate resistance a learning environment places between a learner and an easy answer, forcing them to think before receiving help. AI tools that answer instantly remove this friction; designs that withhold, hint, or scaffold preserve it. Stop Writing for Me: Generative Refusal in AI Tools for Thought, Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning, and Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education each examine how intentionally preserved friction supports reasoning.
- **Productive struggle** — the effortful phase of problem solving in which a learner wrestles with a challenge before (or while) receiving support. The knowledge base's evidence base documents both its value and its cost: Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build shows removing struggle reduced study time but impaired learning, while Curiosity as Linguistic Intervention: Using LLM Tutoring Dialogues to Influence Exploratory Learning Behavior and Rethinking Scaffolding in LLM Tutors: The

Interactional Mismatch Between Benchmarks and Real-World Deployments explore how tutors can keep learners in the productive-struggle zone rather than collapsing to answer-giving.

Productive failure is the structured, theory-driven version of this idea: Kapur's productive failure (PF) formalizes productive struggle as a two-phase design (generation & exploration *before* instruction, then consolidation & knowledge assembly). The AI-era PF literature gives the knowledge base a concrete design vocabulary for preserving desirable difficulty — Kim et al. (2026) derive AI design principles (human-AI collaboration, reflective design, non-directive support) that keep AI from erasing the struggle; Puech et al. (2025) show Large Language Models (LLMs) tutors can be steered to withhold solutions and elicit multiple attempts; Wang & Shan (2026) formalize the "Safety Gap" — the divergence between AI-assisted performance and unassisted capability — as the cost of removing struggle; and ProductiveMath uses AI to lower the burden of designing PF problems. These show that desirable-difficulty principles translate into concrete AI design choices.

Constraint can carry the same design logic inside a writing classroom. In a nine-week argumentative-writing unit, Konradt, Boote and Taub (2026) gave four high-school students teacher-delimited chatbots that asked questions instead of generating prose; students pushed back on AI output instead of consuming it, developing prompt literacy alongside counterargument and evidence-integration gains.

Desirable Difficulties vs. Cognitive Friction vs. Productive Friction

Because AI is designed to be frictionless — instantly generating summaries, solving equations, and writing essays — it can inadvertently bypass the very struggle required for a student to learn. To combat this, educators and technologists rely on two overlapping but distinct frameworks: **desirable difficulties** and **productive (or cognitive) friction**. Both advocate making things harder for the learner, but they originate from different fields and target different parts of the learning process. In this knowledge base they are treated as synonyms for the same intentional-effort idea; the table below details the nuance between the labels.

Feature	Desirable Difficulties	Productive / Cognitive Friction
Primary goal	Maximizing long-term memory and knowledge transfer	Preventing Cognitive Offloading and maintaining active engagement
Scientific root	Cognitive science & psychology (Bjork, 1994)	Human–Computer Interaction (HCI) & UX design
The "threat"	The illusion of competence (thinking you know it because it feels easy now)	Automation bias (letting the machine do the thinking for you)
AI implementation	Algorithms that time and structure practice (spacing, interleaving, retrieval)	Chatbot guardrails and UI roadblocks that force the learner to do the work

Desirable difficulties: the memory optimizer. Coined by Robert and Elizabeth Bjork (1994), this framework comes from cognitive psychology. Its core idea is that learning strategies which feel harder and slow initial performance actually produce better long-term retention and transfer. Desirable difficulties are about *how the brain encodes and retrieves information*: if learning feels too easy or fluent in the moment (like re-reading a highlighted textbook), the brain likely isn't doing the deep processing required to make the memory stick. In AI, a tool using this framework changes the *Pedagogies and Teaching Strategies* of the

session — for example, asking the student to retrieve from memory before offering a summary (retrieval practice), scheduling review just before forgetting (spacing), or mixing problem types (interleaving) rather than grouping them by category. Notably, the benefit of these effortful strategies is itself content-dependent: Rachatasumrit, Koedinger & Carvalho (2025) show that retrieval practice chiefly strengthens verbatim memory (by delaying forgetting), whereas acquiring a generalizable skill requires integrating worked examples with practice — so the "difficulty" that helps must be matched to the type of knowledge being learned rather than applied uniformly.

Productive (cognitive) friction: the engagement guardrail. This framework comes from UX and interaction design, where "friction" is normally the enemy (one-click checkout, instant search). In educational technology, zero friction means zero thinking: productive friction introduces intentional "speed bumps" into the software to prevent the user from offloading cognition to the machine. It is about the *interaction between human and machine*, keeping the user actively engaged and preventing automation bias — blindly trusting the AI's output without evaluating it. In AI, a tool using this framework changes its *behavior and design* to prevent shortcuts — for example, a Socratic guardrail that withholds the direct answer and asks what symbols the student noticed, effort checkpoints that refuse to generate a draft until a thesis and outline are entered, or delayed Feedback that requires committing to an answer and explaining reasoning before the solution is revealed.

In short: you use productive friction to ensure the student actually interacts with the material instead of letting the AI do the heavy lifting; you use desirable difficulties to structure *how* they interact with that material so they remember it a month from now.

Desirable Difficulties in the AI Era

The central tension for AI-supported learning is that generative AI is, by default, a friction-removing technology: it answers, generates, and produces polished artifacts on demand. Across the knowledge base, this plays out in two directions:

- **The cost of removing struggle.** When AI erases spacing, retrieval, and generation, learners may show immediate performance gains but forfeit durable learning and transfer. This connects directly to the Over-Reliance and AI Misuse and Learning Harm findings: an AI that removes desirable difficulty produces the performance–learning gap documented across the knowledge base's evidence base. Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning calls explicitly for intentional friction. Barcaui's (2025) randomized trial gives the principle a direct delayed test in an AI setting: 120 undergraduates who studied AI/ML topics with unrestricted ChatGPT scored 57.5% on a surprise retention test 45 days later against 68.5% for traditional learners ($t(83) = -3.19$, $p = .002$, Cohen's $d = 0.68$). The deficit held with study time as a covariate ($F(1, 82) = 7.89$, $p = .006$). The impairment was largest on technical topics ($d = 0.92$) — the material where AI offered the most assistance, and where the struggle the principle says is productive is most needed.
- **The cost also arrives late.** A difference-in-differences panel of 26,811 Chinese secondary students found homework scores up 18% and completion time down 30% while closed-book exam scores fell 20% within six months. Entrance-exam scores fell 18% (Gaokao) and 24%

(Zhongkao), with the full penalty emerging only after about two years (Strömberg, Lei & Wu, 2026). A delay measured in weeks can show the direction of the trade-off but not its size.

- **Same model, two guardrails, opposite outcomes:** students given unrestricted GPT-4 used it as a crutch and performed worse than controls once it was removed, while students given a guardrailed tutor performed like controls — friction, not the model, decided whether the tool helped (Arthars et al. (2026)).
- **Designing struggle back in.** Instructional designs can deliberately preserve productive processing: draft-first routines, hint-not-answer tutoring, delayed feedback, and teach-back/explanation protocols. These are the concrete scaffolds explored under Reducing AI Misuse and The Effects of Structured LLM-Generated Feedback on Programming Assignment Performance. A 2026 conceptual extension (Gupta) pushes the same logic beyond structured academic tasks to difficulty inside relational encounters: in education abroad it argues the educational question is not how much generative AI is present but which difficulties it dissolves, and proposes a *mediation gradient* that orders uses by the interpretive Learner Agency transferred to the system rather than by volume of use.

The inverted U and the effort paradox. Zohar, Bloom and Inzlicht (2026) supply the sharpest recent statement of why AI's friction-removal is not automatically good. They distinguish AI from earlier labor-saving technologies on two grounds. It targets intellectual and creative work rather than physical or clerical work, and its friction removal is *extreme*. Prior technologies eliminated excess friction, "tedious or insurmountable obstacles that offer little benefit for learning or meaning". A chatbot, by contrast, lets a learner move from ideation to evaluation "without exerting meaningful effort, without questioning the output, and without engaging the cognitive processes that foster ownership, retention, or critical thought". Their organizing claim is that the effort–meaning relationship is curvilinear: moderate friction enhances meaning and motivation while excessive friction overwhelms, so AI's risk is overshooting into too little friction rather than excess. Two consequences matter pedagogically — effort is itself a trainable skill (rewarding process rather than product increases the tendency to strive and persevere), and the motivational benefits of effort erode in exactly the domains where AI substitutes for it, producing a cycle of increasing dependence (Cognitive Offloading, Motivation).

Design Implications

1. **Do not optimize for effort-free fluency.** An AI tutor that always answers immediately may raise satisfaction while lowering durable learning; favor interventions that require retrieval and generation first.
2. **Treat confusion as a resource, not a bug.** Detect and target confusion points as personalized review anchors rather than smoothing them away — the KnowLoop Recognize → Resolve → Consolidate model is a concrete pattern.
3. **Preserve cognitive friction deliberately.** Use hint-not-answer Scaffolding, sequential feedback, and refusal-to-answer where the goal is reasoning, not production.
4. **Match friction to learner readiness.** Desirable difficulties benefit learners who can engage in effortful processing; over-challenge without support risks frustration. Scaffolding must keep learners in the productive-struggle zone, not past it.

TutorMoments operationalizes desirable-difficulty principles as evaluation criteria: Zhang et al. (2026) test whether AI tutors preserve productive struggle by scaffolding for access (when needed) and pushing for rigor (when ready), and find that LM tutors default to over-scaffolding — removing the effortful processing that desirable difficulties require.

Common Misconceptions

“Ease and fluency during study indicate that learning is happening.” They often indicate the reverse. Fluency is a cue that correlates weakly or negatively with durable retention, and the AI-era version has a direct delayed test: Barcaui’s (2025) randomized trial found that **120 undergraduates** who studied AI/ML topics with unrestricted ChatGPT scored worse on delayed retention — with the impairment **largest on technical topics (d = 0.92)**, the material where AI offered the most assistance. The condition that felt most helpful produced the largest deficit.

“Struggle is therefore good and discomfort should be preserved.” Not all friction is desirable. The construct is specific: difficulties are desirable when they require retrieval, spacing, interleaving or generation, and undesirable when they are incidental confusion, poor interface, or an absent prerequisite. Preserving confusion that teaches nothing is as much an error as removing the effort that teaches.

“Cognitive friction and productive struggle are the same idea.” They come from different literature and make different predictions. Productive struggle concerns effortful sense-making that builds understanding; cognitive friction concerns the mismatch between what a task demands and what the learner’s current resources support. Treating them as synonyms loses the diagnostic question — is this learner struggling in a way that builds, or blocked in a way that only costs?

“If removing struggle raises immediate performance, the intervention worked.” This is the trade-off the whole page is about: performance measured in the presence of the support is systematically inflated relative to later unassisted performance. Any evaluation of an AI that reduces effort must measure at delay and without the tool, or it will report the removal of practice as the production of learning.

Connected Concepts

- Pedagogical Patterns — Why the effortful order outperforms the fluent one
- Learning by Teaching
- Self-Regulated Learning
- Metacognition
- Transfer of Learning
- Scaffolding
- Learning Gains
- Cognitive Offloading
- AI Misuse and Learning Harm
- Reducing AI Misuse
- Affective Computing
- Active Learning

- Constructivism
- Motivation
- Learning Theories
- Productive Failure — Productive Failure
- Retrieval, Spacing and Interleaving — the operational techniques that instantiate this principle: testing effect, spacing, interleaving

Connected Articles

- ChatGPT as a cognitive crutch: Evidence from a randomized controlled trial on knowledge retention — ChatGPT as a cognitive crutch: a delayed randomized test of removing desirable difficulty (Barcaui 2025)
- Against frictionless AI — Against frictionless AI: the inverted-U argument for preserving beneficial friction
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning
- The Effects of Structured LLM-Generated Feedback on Programming Assignment Performance
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build
- Curiosity as Linguistic Intervention: Using LLM Tutoring Dialogues to Influence Exploratory Learning Behavior
- Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments
- From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review
- Stop Writing for Me: Generative Refusal in AI Tools for Thought
- Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning
- Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education
- Ordered Network Analysis of Epistemic Emotions during Collaborative Problem Solving
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Productive friction built into GenAI tools supports learning
- When Help is Unhelpful: Evaluating AI Tutors for Productive Struggle — When Help is Unhelpful: evaluating AI tutors for productive struggle
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- The safety gap: restoring productive struggle through pedagogically aligned generative AI — The Safety Gap: Restoring Productive Struggle
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: AI to Support PF Problem Design

- Making AI annoying on purpose: when helpful tools don’t always help — Making AI annoying on purpose: constraint in AI-supported writing (Konradt, Boote & Taub 2026)
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content
- Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement — Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement
- Benefit or Bottleneck? Assessing the impact of structured reflection on learning from AI-driven explanatory feedback — Self-explanation prompts added to already-elaborated AI feedback: doubled time, no learning gain (Asher, Gold & Carvalho 2025)
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: homework scores rise while exam scores fall, with the full cost after two years (Strömberg, Lei & Wu 2026)

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Should I Use AI to Study and Learn Effectively?

Transfer of Learning

> **Transfer of Learning** — the extent to which knowledge or skills acquired in one context (e.g., practice with an AI tool) persist and apply in a different context (e.g., independent performance without the tool). In AI in education, transfer is the central open question: whether performance gains students show *with* AI tools translate into durable learning they can demonstrate *without* them.

Questions to Consider

- Here's a striking pattern the page documents: students often show immediate gains on AI-assisted tasks, yet those gains can vanish — or even reverse — when the AI is removed. Before reading the explanations, why do you think a tool that clearly helps in the moment could end up leaving students worse off without it?
- Recall something you learned to do with a tutor, calculator, or assistant and then had to do alone. Did the skill carry over, or did you feel dependent on the aid? What was different about the experiences that transferred well versus those that didn't?
- A common intuition is that 'practice is practice' — that doing a task with help builds the same skill as doing it alone. Where might that intuition mislead, especially when the help is an AI that completes the reasoning for you rather than guiding you through it?
- The page draws a distinction between 'effects with' a technology and 'effects of' it — performing better while using the tool versus becoming more capable without it. If you're an instructor, designer, or student, which of these is your real goal, and how would you know you'd achieved it?
- The evidence suggests that how much cognitive work you delegate matters: offloading surface tasks like grammar hurt transfer less than offloading deep reasoning and structure. Think about the last time you used AI on an assignment. Which 'layer' did you delegate, and what does your choice predict about what you'd retain?
- The page proposes conditions that might support positive transfer — pedagogical Guardrails, fading support, calibration to the learner's readiness. If you were designing (or were the user of) an AI learning tool, what would you insist on so that gains while using it become durable ability without it?

Introduction

Transfer of learning is a foundational concern in education research, and AI tools have made it urgent. The defining empirical pattern documented across AI in education studies is a **transfer paradox**: students using AI typically show immediate, measurable gains on tasks where AI is available, but those gains often fail to persist — or even reverse — when AI is removed and students must demonstrate understanding independently. This pattern implicates Over-Reliance, Cognitive Load Theory, and Metacognition as the mechanisms at work, and connects directly to debates about AI Tutoring design.

Readiness is not transfer: AI-assisted spoken practice was associated with lower speaking anxiety and higher willingness to communicate with humans, yet neither study observed human speaking, leaving the route from AI rehearsal to human communicative ability an untested pedagogical proposal (Wang & Li (2026)).

The transfer paradox

Students using AI typically show **immediate, measurable gains** on the tasks where AI is available. Yet when AI is removed:

- Effects become **mixed or negative**
- Gains often **fail to transfer** to unassessed settings
- Students may become **dependent on the tool** at the expense of independent reasoning

The evidence base, synthesized in the Stanford Evidence Base on AI in K-12 review, is consistent across domains:

Study	Context	Immediate Effect	Transfer Effect	Mechanism
Bastani et al. (2025)	High school math	Higher practice grades	**~17% worse** on closed-book finals	General-purpose chatbot did the work
Chen et al. (2025)	Programming homework	Higher homework scores	**No improvement** on unassisted exams	Large Language Models (LLMs)-Tutor solved problems for students
Lehmann et al. (2025)	Programming	More topics covered	**Harmed understanding**; widened gaps	General AI for low-prior learners
Stadler et al. (2024)	Academic research	Faster task completion	**Lower-quality reasoning** vs. search	Reduced cognitive engagement
Kosmyna et al. (2025)	Essay writing	Higher essay quality	**83% failed to recall** their own quotes	Outsourced authorship

All five studies show a **negative or null transfer** pattern when general-purpose AI is the intervention.

Mechanisms undermining transfer

Metacognitive displacement. AI completing reasoning reduces opportunities for students to monitor their own understanding and select strategies. Students who used AI were less able to explain their answers when queried. This connects to Metacognition research on self-monitoring and the evidence that structured courses increase metacognitive competence while raw LLM assistants do not.

Germane load suppression. General-purpose AI reduces not just extraneous (distracting) cognitive load but also *germane* load — the productive mental effort that encodes durable knowledge. Easier practice feels better but stores weaker traces. See Cognitive Load Theory and the distinction between tutoring-specific vs general AI.

Over-reliance / expertise reversal. Novices given answers do not build schemas. General AI provides answers; effective tutoring provides structured guidance. When novices are given expert-level shortcuts, learning is disrupted — the Desirable Difficulties principle in reverse.

Tool-dependent performance. Students may optimize for the specific affordances of the AI tool (prompt engineering, reliance on generated code structure) rather than building domain generalization — a form of cognitive offloading that feels productive but displaces durable learning.

A protected classroom can also teach the wrong habit: Shi, Dai & Zhang (2026) warn that simulations with rules fixed in advance filter out uncertainty and reinforce rule-following, so decision habits formed inside them can become a cognitive liability once students meet competing interests and incomplete information in real settings. **Layer-sensitive offloading and transfer.** Chen (2026) directly tests Salomon, Perkins & Globerson's "effects with vs. effects of technology" distinction in GenAI-assisted writing: an eight-week quasi-experiment found open AI collaboration maximized supported-writing performance but produced the *lowest* independent no-AI near-transfer outcomes, while bounded support with reflection preserved independent competence. Deeper offloading layers (reasoning, structure) predicted worse transfer than surface layers (grammar). This is direct classroom evidence that AI's *with*-support performance gains do not transfer to *of*-support independent performance — and that the depth of delegation, not just whether AI is used, shapes transfer.

A complementary, if confounded, instance comes from physics: the Ruhr University Bochum redesign of an introductory nuclear and particle physics course (Mikhasenko et al., 2026) had students successfully complete collaborative, resource-rich research problems with AI assistance, yet those same students averaged 20.6/80 on a conventional unaided written exam, with several serious attempts unable to complete standard calculations. The authors read this as evidence that assisted performance does not automatically transfer to unprompted performance, and their remedy is deliberate design: making the written exam the sole grade determinant, releasing tutorial problems in advance so class time becomes prepared discussion, and adding prerequisite preparation, worked examples and consolidation around the exploratory AI-permitted work.

Conditions supporting positive transfer

The limited evidence suggests transfer is possible when:

- **Pedagogical guardrails are present** — step-by-step hints, misconception targeting, Socratic questioning (Bastani et al., 2025 tutoring variant)
- **Traditional strategies are preserved** — note-taking paired with AI use improved retention (Kreijkes et al., 2026)
- **AI is used for formative, not summative, practice** — scaffolding during learning, not during assessment
- **The practice format is matched to the knowledge being transferred.** Rachatasumrit, Koedinger & Carvalho (2025) find that retrieval-practice gains frequently fail to transfer to unfamiliar problems — they strengthen memory for a procedure without enabling its use in new contexts — and that durable generalization to novel applications requires pairing practice with

worked examples that support skill induction; the optimal example–problem ratio therefore depends on whether the content is a verbatim fact or a generalizable skill.

- **Learner expertise is calibrated** — the tool adapts support to readiness rather than defaulting to full assistance
- **Transfer as the criterion that separates learning from assistance.** Yan and Gašević (2026) build their theory of human-AI learning around transfer under reduced support: assisted performance counts as learning only if the capability persists once the support is withdrawn, which makes transfer the test rather than one outcome among several. Their proposition is directional, that requiring source checking or justification during AI-supported work should improve delayed performance, while repeated low-friction delegation without reconstruction should weaken learners' calibration of their own competence.
- **Guidance is co-located with the work.** Against the negative-transfer pattern in the table above, a 36-participant comparison found learners assisted by a desk robot held their score at 7.0/10 once help was withdrawn while ChatGPT-assisted learners fell to 4.4/10, a 60% higher short-term transfer score (Orlando et al. (2026)). The result is short-term transfer measured about 35 minutes after the task, with no delayed retention test, in 36 participants at one campus.

This aligns with AI Tutoring research showing that tutoring-specific tools with pedagogical guardrails outperform general-purpose chatbots, and with Scaffolding principles about fading support as competence grows.

Unanswered questions

1. **Time scale:** Does transfer improve over weeks/months of use, or does dependence deepen?
2. **Domain differences:** Is transfer better in well-structured domains (math) vs. ill-structured domains (writing)?
3. **Individual differences:** Do high-Prior Knowledge students suffer less transfer loss than novices?
4. **Skill remediation:** Can explicit "AI-off" practice sessions reverse tool dependence?

The time-scale question now has a formalization. Yajee (2026) names the post-withdrawal interval cognitive washout and gives it four candidate outcomes: elastic rebound, partial plateau, latent scaffold and over-recovery. Reversibility, the paper argues, is what determines severity, and it proposes a preregistrable three-arm, twenty-two-week protocol to measure it. The studies above tested transfer hours after assistance ended, so the weeks afterward are the part of this page's first open question that remains genuinely unmeasured.

Connections to related concepts

Transfer of learning connects to Metacognition (self-monitoring of understanding), Cognitive Load Theory (germane vs extraneous load), Desirable Difficulties (productive struggle), Scaffolding (fading support), Over-Reliance (tool dependence), and Sociocultural Learning (general-purpose AI operates outside the ZPD by completing work for students). It is the bridge between assisted performance and genuine learning — the distinction between The Evidence Base on AI in K-12: A 2026 Review and the central question for AI Tutoring effectiveness.

Common Misconceptions

“Gains on AI-assisted tasks demonstrate transferable learning.” The opposite pattern is what the corpus finds: **all five studies** in the synthesis reported here show **negative or null transfer** when general-purpose AI is the intervention — high school mathematics students with higher practice grades scoring **about 17% worse** on closed-book finals, and an essay-writing study in which **83% failed to recall their own quotes**. Immediate assisted performance is the least transferable measure available.

“If a student can do it with the AI, they can do it.” That is the definition of the failure rather than its absence. Transfer requires that the capability survives removal of the support, and the studies that test removal find the capability was in the tool. A learner who can produce an artifact while the reasoning is performed elsewhere has been trained in a different skill: operating the tool.

“Transfer comes from more capable models.” Transfer comes from conditions that produce it — the generality of the practice, the variability of the contexts, and the extent to which the learner generated the reasoning themselves. Model capability raises the ceiling on assisted performance and does nothing in particular for what remains when the model is gone.

“Guidance always supports transfer, so more guidance is better.” Guidance that performs the reasoning substitutes for the process transfer depends on. The distinction is between help that keeps the learner generating the next step and help that generates it for them — and only the first is on the transfer side of that line.

Connected Concepts

- Pedagogical Patterns — The outcome most of these sequences are ultimately judged on
- Metacognition
- Desirable Difficulties
- Cognitive Offloading
- Scaffolding
- Sociocultural Learning
- Intelligent Tutoring
- K-12
- Self-Regulated Learning
- Learning Theories
- Productive Failure — Productive Failure

Connected Articles

- Agentivism: a learning theory for the age of artificial intelligence — A mid-range learning theory for human-AI interaction, with four mechanisms and six testable propositions (Yan and Gašević 2026)

- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- The Evidence Base on AI in K-12: A 2026 Review
- Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact
- Cognitive offloading and the speedup illusion in human-AI interaction
- Vibe Compiler: A Research-Logic Synthesis Tool That Runs without Prompt Engineering -Toward Enhancing Metacognition for Sustaining Agency in the Age of Generative AI-
- Rethinking Higher Education: From Fixed Curricula to Learnity Graphs
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Performance-learning distinction and durable transfer
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content
- AI in Particle Physics Education: Research Problems and Foundational Skills — AI in Particle Physics Education: Research Problems and Foundational Skills
- From memorization to experiential learning: Reconfiguring classroom pedagogy in management education through generative AI — argues that protected classroom simulations can form decision habits that fail outside them
- AI-Assisted Speaking Practice and Human-Directed Communicative Readiness: Survey and Scenario Evidence on Anxiety, Self-Efficacy, and Evaluation Pressure — AI-assisted speaking practice raised willingness toward humans but no study observed human speaking
- AIfred: Augmented Learning through Functional Robotic Embodiment at the Desk — AIfred: Augmented Learning through Functional Robotic Embodiment at the Desk
- After the assistant leaves: Cognitive washout dynamics and the reversibility of AI-induced skill decay — Cognitive washout: the post-withdrawal interval and a 22-week measurement protocol (Yajee 2026)

Prior Knowledge

> **Prior knowledge** — the existing knowledge, skills, beliefs, and mental models a learner brings to a new learning task. It is the single most powerful predictor of subsequent learning: new information is interpreted through — and integrated with — what the learner already knows, so instruction that activates and builds on prior knowledge produces stronger, more durable learning than instruction that treats every learner as a blank slate. In AI in education, prior knowledge is central to Learner Modeling and Adaptive Instruction (adapting instruction to the learner's current state), to the Constructivism principle that knowledge is actively constructed atop existing mental models, and to the risk that AI tools which pre-fetch and surface content bypass the retrieval practice that activates prior knowledge.

Questions to Consider

- What's something you learned deeply and something you struggled to learn? How much of the difference came down to what you already knew when you started?
- Having prior knowledge isn't enough—it must be actively retrieved and connected. When has recalling what you already knew (or failing to) changed how well you learned something new?
- The page says prior knowledge can *interfere* when it's wrong (a misconception). Can you think of a belief you held that made new, correct information harder to learn?
- Generative AI that pre-fetches answers can bypass the retrieval practice that activates prior knowledge. How might a tool designed to help you learn actually prevent you from recalling what you know?
- If an AI must estimate your prior-knowledge state to personalize, what happens when that estimate is wrong? How confident are you that a system could accurately know what you already know?
- How is 'activating prior knowledge' different from simply asking students a question before teaching? What would make that activation genuinely deepen the learning that follows?

Introduction

Prior knowledge activation is one of the most robust findings in the learning sciences: learners do not absorb new material in a vacuum but map it onto existing schemas, and the quality of that mapping determines retention and transfer. The concept underpins Ausubel's advance organizers, activation of prior knowledge before new instruction, retrieval practice as a form of activating and strengthening what is known, and diagnostic Assessment of what learners already know. In the AI era, prior knowledge has taken on new urgency because generative AI can either *support* activation (prompting learners to recall and connect what they know) or *bypass* it entirely (instantly supplying an answer or pre-fetched content that the learner never had to retrieve or integrate).

The role of prior knowledge

- **It is the strongest predictor of learning.** Decades of research show that what a learner already knows correlates with learning outcomes more strongly than almost any other factor, because new information is encoded relative to existing mental models. AI systems that adapt to each learner's prior-knowledge state therefore hold particular promise for efficiency and transfer.
- **How much stronger, in one randomized comparison.** Two otherwise identical second-grade mathematics tutors, differing only in whether task selection followed a Bayesian knowledge-tracing mastery estimate, produced no difference in posttest scores. Prior knowledge predicted those scores at $\eta^2p = .63$ ($F(1, 124) = 206.99$, $p < .001$) while the adaptive sequence accounted for $\eta^2p = .00$ (Sibley, Berner and Schmalfeldt (2026)). Adaptation rearranges the order of practice; what the learner brought to it still carried the outcome.
- **Activation matters, not just possession.** Having prior knowledge is not enough — it must be actively retrieved and connected to the new material. This is why "activating prior knowledge" is a standard instructional move, and why retrieval practice (recalling what you know before adding to it) improves learning beyond simple re-exposure.
- **It does not always predict who does the work that drives learning.** In a five-day Learning by Teaching study with 23 middle-school tutors, prior test scores did not predict the share of knowledge-building responses a tutor produced, and low-prior tutors who built knowledge finished statistically level with high-prior peers (Ameen et al., 2026).
- **It shapes interpretation.** Learners interpret new information through what they already believe. When those beliefs are wrong (Misconceptions about AI), prior knowledge can *interfere* with learning, which is why instruction must surface and address misconceptions rather than assume a neutral starting point.
- **It drives student modeling.** To personalize, an AI system must estimate the learner's prior-knowledge state — the basis of Knowledge Tracing, student modeling, and adaptive Scaffolding. The quality of these estimates determines whether adaptation is genuinely helpful or misleading.
- **Knowledge content determines which process practice recruits.** Whether learning hinges on memory or on induction is set by the prior-knowledge structure of the target: Rachatasumrit, Koedinger & Carvalho (2025) follow the KLI framework in distinguishing knowledge components with constant conditions and responses (facts, acquired through memory and retrieval practice) from those with variable conditions and responses (skills, acquired through induction and generalization to novel inputs) — which is why the optimal mix of worked examples and practice differs for fact content versus skill content.

Prior knowledge in the AI era

Generative AI has made prior knowledge a central design consideration rather than a background variable:

- **The bypass risk.** Proactive agentic AI that pre-fetches and surfaces content can bypass the retrieval practice that activates prior knowledge — the learner never has to recall or integrate what they know before receiving an answer. This is one of the six pedagogical risks identified in the

agentic-education best-practice framework, and it connects directly to Over-Reliance and the Desirable Difficulties principle that effortful processing supports durable learning.

- **Prior knowledge shapes the pattern of offloading, not only outcomes.** In a synthesis-writing study the high-knowledge, minimal-offloading cluster authored 80% of its essay against 2% for the heaviest offloading cluster (mean 25.1 prompts), so prompt volume tracked prior knowledge rather than effort (Poquet et al. (2026)).
- **The benefit gap compounds.** Because productive AI use depends on what a learner already knows, students with stronger prior knowledge leverage it better while novices are the most likely to treat it as a substitute — a distributional risk that can widen achievement gaps even when access is equal (Lodge & Loble (2026)).
- **Priming and activation as design.** GenAI mindtool approaches deliberately "prime the learning task" by activating prior knowledge and curiosity through prompting questions, AI-generated visuals, and analogies (e.g., "What do you already know about ecosystems?") before introducing new content — modeling the retrieval-and-integration path rather than the answer-supply path.
- **Student modeling and memory.** AI systems increasingly model learners' prior-knowledge state and longitudinal memory (e.g., incorporating prior-knowledge state and forgetting curves into tutoring memory), enabling spaced repetition and adaptive review that build on what each learner already knows.(PersonaVLM: Long-Term Personalized Multimodal LLMs)
- **A personalized-adaptation lever.** Because learners differ widely in prior knowledge, adaptation must be tuned to the individual — a core argument for Personalized Learning and adaptive Scaffolding that meet learners at their actual current state rather than a class-average assumption.

Implications for designing AI in education

1. **Activate before you supply.** Design AI interactions to prompt learners to retrieve and articulate what they already know before providing new content or answers — preserving retrieval practice rather than bypassing it.
2. **Model the learner's prior-knowledge state.** Build student modeling and adaptation on estimated prior knowledge (and its misconceptions), not on assumed uniformity, to make personalization genuinely responsive.
3. **Surface and address misconceptions.** When prior knowledge is incorrect, it will interfere; instruction should elicit and correct misconceptions rather than add new content on top of faulty foundations.
4. **Weigh the friction trade-off.** Activating prior knowledge adds desirable difficulty (retrieval, integration) that AI's friction-removing defaults tend to erase — a tension to manage deliberately rather than let automation resolve by default.

Common Misconceptions

"Prior knowledge predicts who does the cognitive work." It predicts outcomes more reliably than it predicts behavior. In a five-day learning-by-teaching study with **23 middle-school tutors**, prior test scores did **not** predict the share of knowledge-building responses a tutor produced, and low-prior tutors worked at

building knowledge rather than defaulting to less. Who engages in the productive struggle is not simply who arrives knowing most.

“Offloading is a stable learner trait, so the same student offloads the same amount everywhere.” It tracks prior knowledge within the task. In a synthesis-writing study the **high-knowledge, minimal-offloading cluster authored 80% of its essay against 2% for the heaviest-offloading cluster**. Offloading is therefore substantially a response to what the learner already has and what the task demands, which makes it a design variable rather than a character one.

“Students with less prior knowledge need more AI support.” That is the direction most likely to widen the gap, since the measured offloading pattern concentrates authorship loss where prior knowledge is thinnest. Support that supplies the work to the learner least equipped to detect the substitution removes the activity that would build the missing knowledge.

“Prior knowledge is a fixed input the course cannot move.” It is the most heavily weighted factor in new learning, which makes building it the highest-leverage task rather than a background condition — the reason domain knowledge is the intervention in its own right, not merely the covariate.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Constructivism
- Personalized Learning
- Learner Modeling and Adaptive Instruction
- Misconceptions about AI
- ICAP Framework
- Knowledge Tracing
- Scaffolding
- Self-Regulated Learning
- Transfer of Learning
- Metacognition
- Cognitive Offloading
- Desirable Difficulties
- Learning Theories
- Productive Failure — Productive Failure
- Retrieval, Spacing and Interleaving — how what a learner already knows determines what retrieval practice can do

Connected Articles

- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — The tension between automation and learning (prior knowledge activation risk)
- Generative AI (GenAI) as a mindtool that supports generative learning (GL) — GenAI as a mindtool: priming and activating prior knowledge

- PersonaVLM: Long-Term Personalized Multimodal LLMs — LLM student modeling and memory
- Artificial intelligence, cognitive offloading and implications for education — Lodge & Loble on cognitive offloading
- Profiling cognitive offloading in LLM-mediated synthesis writing: Volume vs. content — Cognitive offloading in LLM synthesis writing
- WIP: Bridging the Gap Between Instructional Design and Pedagogical Use: A Framework for Mathematics Educators — An instructional-design framework for math
- Beyond prior knowledge: the predictive role of knowledge-building in tutor learning — knowledge-building rather than prior knowledge predicts tutor learning, and low-prior tutors who build knowledge catch up
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content
- Effectiveness of adaptive versus non-adaptive intelligent tutoring systems in early primary mathematics — Prior knowledge carried the posttest ($\eta^2p = .63$) while adaptive task selection carried none (Sibley et al. 2026)

ICAP Framework

> **The ICAP Framework** (Interactive–Constructive–Active–Passive) — a taxonomy of cognitive engagement developed by Michelene Chi that classifies learner behavior into four modes of knowledge change, ordered from least to most cognitively engaged: *passive*, *active*, *constructive*, and *interactive*. In AI in education, ICAP provides both a design target (build tools that elicit constructive and interactive engagement rather than passive consumption) and an evaluation lens (measure whether learners and AI systems are actually engaged at the higher modes).(Systematic review of collaborative learning activities for promoting AI literacy)(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)

Questions to Consider

- Think of the last time you 'learned' something by watching a video or reading. The ICAP framework would call that passive. What do you actually retain from passive exposure versus from explaining it to someone else?
- ICAP orders engagement from passive to active to constructive to interactive. Where do AI tools you've used tend to keep learners — and does clicking through adaptive practice count as real engagement or just activity?
- The page argues the most consequential shift is from Active to Constructive — generating explanations or new artifacts rather than just applying knowledge. Why might producing something new be the step that actually changes understanding?
- One study found human experts far outperform AI models at labeling engagement levels. If automated systems systematically underestimate engagement, how should we treat 'engagement' metrics generated by AI?
- ICAP shows that a tool that answers for you keeps you passive, while one that prompts and questions pushes you toward constructive and interactive engagement. Which design choice would you make for your learners?
- The framework is used both as a design target and an evaluation lens. How could you use ICAP in your own teaching or design to tell whether learners are genuinely engaged rather than merely active?

Introduction

ICAP is grounded in the assumption that *what learners do* determines how much and what they learn. Chi's framework posits that as engagement moves from passive to active to constructive to interactive, the nature of knowledge change deepens — from storing, to attending, to integrating new knowledge with prior knowledge, to co-creating knowledge through dialogue. This makes ICAP a powerful analytic tool for AI in education, where the central design question is whether AI assistance supports or displaces learners' cognitive engagement.

The four modes

Mode	Learner behavior	Nature of knowledge change
Interactive	Dialogue with another learner or agent, co-constructing meaning; e.g. defending a position, collaborative problem-solving	Co-creating new knowledge through joint, reciprocal activity
Constructive	Generating new output beyond the given; e.g. self-explaining, comparing, reflecting, drawing	Integrating new information with prior knowledge to produce novel understanding
Active	Manipulating or acting on the material; e.g. taking notes, underlining, pausing to think	Attending to and storing information, sometimes without deep integration
Passive	Receiving information without overt action; e.g. listening to a lecture, reading	Storing information, with limited further processing

ICAP in AI in education

A design target for AI tools

ICAP reframes the central design question for AI in education: an AI tool that *answers for* the learner keeps them in passive/active modes, while a tool that *prompts, questions, and scaffolds* can push learners toward constructive and interactive engagement. This aligns ICAP with Constructivism Pedagogies and Teaching Strategies and with Active Learning research.(Multimodal Learning with Generative AI)(Systematic review of collaborative learning activities for promoting AI literacy)

An evaluation lens for AI agents

ICAP also serves as a measurement framework. In one study, researchers extended ICAP to a 7-point scale to characterize cognitive engagement in collaborative dialogue, then compared trained human annotators with Large Language Models (LLMs)-based labeling (in-context learning, zero-shot prompting, and reflective agents). Human interrater reliability (kappa = 0.906–0.998) far exceeded LLM annotation (kappa = 0.541–0.609), highlighting ICAP's role — and current limits — in automated engagement measurement for Learning Analytics pipelines.(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)

Guiding collaborative-dialogue facilitation

Because interactive engagement is the highest ICAP mode, the framework helps locate the value of AI facilitation in online collaborative discussion. Research on LLM facilitation timing shows that *when* an AI intervenes in a discussion shapes whether it supports or interrupts interactive knowledge co-construction — an ICAP-informed caution that autonomous moderation agents need calibration toward human-like restraint rather than over-eager facilitation.

ICAP and learning analytics design

ICAP underlies critiques of shallow "engagement" metrics: interacting with a dashboard by clicking filters is *active*, not *interactive*, engagement. Effective learning-analytics designs elicit Self-Assessment and two-way dialogue rather than merely displaying data — an implication drawn directly from Chi's framework. (Interactive learning dashboards: rethinking learning visualisations as engagement tools)

The Active→Constructive transition as the pivotal step

Although ICAP describes a hierarchy, the most consequential shift for learning is the jump from *Active* to *Constructive* modes (Chi & Boucher, 2023). Active engagement (applying knowledge to similar-but-non-identical scenarios) prepares learners, but it is Constructive engagement — generating explanations, summaries, or new artifacts — that equips them to create new knowledge. This is the crux for AI in education: a tool that keeps learners in the Active mode (e.g., clicking through adaptive practice) may look productive but never pushes them into the constructive generation that yields durable understanding. Collaborative and literacy-focused interventions that deliberately scaffold the Active → Constructive leap tend to show the strongest gains.(Systematic review of collaborative learning activities for promoting AI literacy)

The "strongest gains" part of that claim is an inference from the framework rather than a comparison the review ran. The nine-study review behind it (2015–2023) counts how many interventions *included* each mode (9 passive, 5 active, 7 constructive, 8 interactive), reports no effect size by mode, and notes that no included study relied on a single mode, so nothing in it isolates the Active → Constructive leap (Hingle et al., 2025). The ordering is Chi's; what the review adds is that practitioners combine modes rather than choose one.

ICAP as an adaptive-scaffolding signal in ITS

ICAP's modes can be operationalized as *target states* that an adaptive tutor selects among to scaffold cognitive engagement based on an evolving student model. In a logic ITS, Dey Tithi et al. dynamically chose between an *Active* "Guided" worked-example mode and a *Constructive* "Buggy" example mode. Comparing Bayesian Knowledge Tracing (BKT) against Deep Reinforcement Learning (DRL) and a non-adaptive baseline over 113 students, both adaptive policies improved posttest performance — but in a differentiated way: BKT gave the largest gains to low-prior-knowledge students (helping them catch up), while DRL produced the highest posttest scores among high-prior-knowledge students. This is a concrete demonstration that effectively *personalizing* the ICAP mode of an intelligent tutor depends on modeling the learner's current knowledge — and that no single mode or adaptive method suits every learner. It connects the ICAP hierarchy directly to Adaptive Learning and Knowledge Tracing design.

ICAP as a model of cognitive state for generating human-like agents

Beyond selecting task modes, ICAP has been embedded directly into the *cognitive model* of a generative educational agent. CogEvolution builds an ICAP-based "cognitive depth perceptron" that maps inputs to a probability distribution across the four ICAP levels, fusing this with evolutionary-inspired state updates and Item Response Theory memory retrieval to simulate a student's cognitive evolution (including transitions

such as confusion → insight). Ablations show that removing the ICAP perception module collapses the agent's ability to distinguish shallow from deep learning — evidence that the ICAP taxonomy can serve as a fine-grained, internal measure of cognitive engagement for student simulation, not merely an external evaluation lens.

ICAP anchors assessment of reflective GenAI interaction

ICAP's emphasis on generative, process-level engagement has been adopted by assessment frameworks that evaluate *how* students learn with generative AI. The DRIVE framework explicitly aligns its core construct — deep reflective interaction with GenAI output — with the kind of generative engagement ICAP identifies as leading to deeper learning, and uses it to distinguish surface consumption from effortful, reflective reworking of AI-generated content. This positions ICAP as a theoretical anchor for designing and measuring meaningful GenAI learning interactions rather than merely tracking usage.

Implications for design and research

1. **Design for the higher modes.** AI tools should prompt learners to generate, explain, and dialogue — constructive and interactive activity — rather than deliver passive content or act as answer machines.(Multimodal Learning with Generative AI)
2. **Engage learners across modes.** Effective AI literacy instruction engages learners at multiple ICAP levels — passive exposure, active manipulation, constructive generation, and interactive dialogue — selecting the mode that fits the learning goal.(Systematic review of collaborative learning activities for promoting AI literacy)
3. **Measure engagement honestly.** ICAP gives researchers and designers a common vocabulary for distinguishing genuine cognitive engagement from mere activity — a corrective to shallow Student Engagement.(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)
4. **Watch the human–LLM annotation gap.** If automated systems are used to code engagement, their systematic shortfall relative to trained humans must be accounted for.(Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents)

Common Misconceptions

"ICAP is a taxonomy for labelling activities." It is a design and evaluation lens with an ordering claim: passive, active, constructive and interactive engagement differ in the learning they produce, so "build tools that elicit constructive and interactive engagement rather than passive consumption" is a design target rather than a classification exercise. Labeling a lesson with a mode without changing what students do has not applied the framework.

"Time on task or interaction volume indexes engagement level." Volume counts activity, not mode. Scrolling is active and passive in different senses at once, and a student generating many clicks may still be

receiving rather than constructing. The framework's value is precisely that it distinguishes kinds of engagement that activity metrics lump together.

"An AI tutor automatically produces interactive engagement because it converses." Conversation is the medium rather than the mode. A dialogue where the system supplies every substantive contribution is passive for the learner wearing an interactive interface, which is the same confusion the engagement literature documents between behavioral activity and cognitive investment.

"Higher ICAP modes are always better." They cost more, and the ordering is about learning per unit of the relevant processing rather than about what a lesson should always aim for. Foundational fluency can require active repetition before constructive work is possible; the error is settling there, not passing through.

Connected Concepts

- Active Learning
- Collaborative Learning
- Student Engagement
- Learning Analytics
- Constructivism
- Learning Design
- Metacognition
- AI Literacy
- Human-in-the-Loop
- Limitations in AIEd Research

Connected Articles

- Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents — Extended ICAP framework for measuring engagement with human vs. LLM annotation
- Systematic review of collaborative learning activities for promoting AI literacy — Collaborative AI literacy across the four ICAP modes
- Interactive learning dashboards: rethinking learning visualisations as engagement tools — ICAP as a critique of shallow learning-analytics engagement
- Multimodal Learning with Generative AI — ICAP and cognitive engagement in multimodal learning design
- To facilitate or not to facilitate: Human and LLM facilitator tendencies in online discussions — LLM facilitation timing in online collaborative discussions
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive ICAP scaffolding in an ITS (BKT vs DRL)
- CogEvolution: A human-like generative educational agent to simulate student's cognitive evolution — ICAP cognitive-depth model in a generative student-simulation agent

- Assessing students' DRIVE: A framework to evaluate learning through interactions with generative AI — ICAP-anchored assessment of reflective GenAI interaction

Connected FAQs

- How Should AI Be Designed Into the Learning Experience?

Misconceptions about AI

> **Misconceptions about AI** — the inaccurate beliefs people hold about what AI systems are, what they do, and what using them means for learning and work. Misconceptions are not a single falsehood but a family of calibration errors that cluster around two core mistakes: misjudging what the model is (authority vs. tool, neutral vs. biased, understanding vs. generating) and misjudging what learning requires (output vs. process). They are held not only by students but also by teachers, administrators, policymakers, and the broader public — and correcting them is a core aim of AI Literacy and Trust Calibration education.

Questions to Consider

- Many people believe an AI chatbot's answer is a verified fact because it sounds confident and fluent. The page calls this the 'authority fallacy.' When you read an AI-generated explanation, how do you decide whether to accept it — and how often do you actually verify it?
- The 'learning-equals-output' misconception is the belief that producing work with AI is the same as having learned it. Have you ever felt you 'learned' something by letting a tool do the drafting? What was actually missing afterward?
- People often assume AI is objective and unbiased. The page calls this the 'neutrality illusion' — models encode biases from training data, which in writing contexts can homogenize ideas across an entire class. Where might bias hide in a tool that feels neutral?
- Misconceptions about academic integrity cluster at two extremes: some students treat AI output as 'not copying a person' and so permissible, while others think any use is cheating. Where do you think the line should fall, and who should decide it?
- A common belief is that one query is enough and that AI output is deterministic — the same question always yields the same answer. The page describes this as the determinism error. How might that misconception lead someone to over-trust a single output?
- Misconceptions are described as stable, plausible, and resistant to correction — much like misconceptions in any domain. If simply telling people the truth rarely changes their minds, how should AI literacy actually be taught?

Introduction

Misconceptions about AI matter because they are the cognitive precursor to the harmful behaviors the knowledge base documents under Over-Reliance and Academic Integrity concerns. People rarely set out to misuse AI; they do so because inaccurate mental models lead them to misplace trust, skip verification, and treat output as understanding. In education these errors shape everything from how students study to how teachers and institutions design curricula, Assessment, and policy.

What AI misconceptions are

A misconception here is not mere ignorance of how a model works — it is an actively held, often self-reinforcing belief that produces systematic errors in how students interact with AI. They are directly analogous to the domain misconceptions studied in learning science: stable, plausible, and resistant to correction until confronted. Correcting them is a core aim of AI Literacy and Trust Calibration education.

Common misconceptions in academic contexts

- **The authority fallacy** — treating Large Language Models (LLMs) output as verified fact rather than a probabilistic completion. Drives uncritical acceptance and the answer-seeking-over-understanding pattern documented in AI-tutoring research, where learners accept a model's answer without checking it against Hallucination Risk.
- **The independent-check illusion** — treating AI feedback as an outside correction when the model mirrors your own reasoning. Users' baseline accuracy was the dominant predictor of final performance, and sycophancy-specific prompting cut positional mimicry (OR = 0.26) but left error propagation untouched, so learner training is not the safeguard (Koyuturk et al. (2026)).
- **Learning-equals-output** — believing that producing work *with* AI is the same as having learned it. This is the exact error behind Over-Reliance: the drafting, recall, and revision processes that build durable knowledge get outsourced.
- **The neutrality illusion** — assuming AI is objective and unbiased. Students often miss that models encode training-data biases and that in Writing contexts this produces idea homogenization across a cohort.
- **The integrity gray zone** — misjudging whether AI use is acceptable. Some students see AI output as "not copying a person" and therefore permissible; others over-correct and think *any* use is cheating. Institutional inconsistency feeds both errors.
- **Anthropomorphism** — believing the model has intent, memory, and understanding of *their* context. This over-trust is especially risky academically, because students may rely on plausible-sounding explanations the model cannot actually ground.
- **The determinism error** — expecting one query to be enough and not realizing output is non-deterministic and prompt-sensitive. Underestimating this produces the "prompting gap," where students mistake shallow results for the tool's ceiling.
- **The detection miscalibration** — underestimating both institutional detection and, more importantly, the self-harm of submitting work they cannot later explain or defend.
- **The efficiency illusion** — treating time saved as pure gain, missing that unexercised foundational skills decay and that novices cannot yet tell good output from bad.
- **The friendliness-safety illusion (children)** — believing a friendly-seeming AI is inherently safe and less likely to spy. Leisten et al. (2026) surveyed 71 children aged 10–16 (Mage = 12.90) and ran six focus groups (n = 36) around the Open Source social robot Blossom, finding foundational AI knowledge rose reliably with age (M = 4.41 of 6; β = 0.17) while safety attitudes stayed ambivalent (importance M = 2.51, current safety M = 2.77 on a 1–4 scale), captured in a 12–13-year-old's belief that "maybe if they are good friends he doesn't spy so much" — alongside the

belief that AI's knowledge can be deleted at the press of a button, that hacking leads to kidnapping, and that "the wifi radiates into the brain."

The integrity gray zone has a structure, not just two extremes. Interviews with 20 students, together with their chat logs and course documents, found five separate sites where AI policy lives, from faculty intention through formal policy and student self-policy to actual practice, plus 23 distinct rationalizations in six classes (Kim et al., 2026). The rationalizations were ad hoc and post hoc, assembled to explain use that had already happened rather than to guide it. A strict prohibition did not prevent use so much as intensify moral conflict in students who wanted to comply, which puts the correction target in the policy site rather than in the statement of the rule.

Institutional and public AI myths

Misconceptions are not confined to students — they saturate the institutional and public discourse about AI that students inherit. Rudolph et al. (2025) dismantle eight entrenched "myths" that shape higher-education policy and teaching: that AI is genuinely "artificial" (rather than built from exploited human labor), that it is truly "intelligent" and agentic, that it will unproblematically "make the world a better place," that it is "objective and unbiased," that the US holds a sole superpower monopoly, that it will not disrupt the job market, that it "revolutionises higher education," and that teachers can reliably detect AI-generated work. These institutional myths are the upstream source of many student misconceptions documented above — most directly the neutrality illusion ("AI is objective") and the authority fallacy ("AI is intelligent"), and the detection miscalibration that leads students to assume undetectable, unverifiable use is safe. Where students absorb and act on institutionally-repeated myths, correcting them requires confronting not only the learner's belief but the discourse that feeds it.

Why misconceptions matter for learning

Misconceptions translate directly into the behaviors that cause learning harm. The belief that "AI is always right" suppresses verification; the belief that "using AI is learning" suppresses effortful processing; the belief that "it's not cheating" bypasses the metacognitive review that consolidates understanding. In this sense misconceptions are upstream of the AI Misuse and Learning Harm documented across the knowledge base's evidence base.

The belief that using AI is learning is not only held before use; the tool can manufacture it. Kim et al. describe an LLM fallacy in which opaque, fluent, immediate output is misread as evidence of the user's own competence, so perceived and actual capability diverge by a margin they call ΔC. Because the mechanism is fluency and attribution ambiguity rather than error, the fallacy persists whether the model is accurate or hallucinating, which means a correct AI-assisted answer is not evidence that the belief has been corrected.

Misconceptions beyond students: teachers, institutions, and the public

AI misconceptions are not confined to learners — they are pervasive among the adults who shape education:

- **Teachers and faculty** may overestimate AI's ability to reliably grade or detect misuse, or underestimate its bias, leading to either uncritical adoption or reflexive banning. That assumption of reliability is partly testable and partly false: Humble (2026) red-teamed an everyday AI grading

workflow and found that instructions hidden inside a submitted file raised a failing essay's grade with no visible warning, in 9 of 9 iterations for one strategy and 17 of 18 for another. When teachers hold the authority fallacy about AI outputs, they model the same uncritical posture they should be correcting in students. Preparing educators with accurate mental models of AI is a prerequisite for responsible AI integration and safe pedagogy.

- **Administrators and policymakers** inherit and propagate institutional myths — that AI is "objective," that it will "revolutionise" education, or that detection tools are trustworthy — which then shape policy, procurement, and assessment rules. The trust students develop is partly a product of the institutional framing they inherit.
- **The general public** absorbs media and vendor narratives about AI's capabilities and risks. Because students learn within this discourse, public myths become the substrate from which student misconceptions grow. Correcting AI misconceptions is therefore an AI Literacy task aimed at the whole educational ecosystem, not only at learners.

This breadth is why the knowledge base treats misconceptions as a cross-cutting foundational theme rather than a purely student-facing one: the same calibration errors recur across learners, teachers, institutions, and the public, and correcting them requires confronting both individual beliefs and the discourse that feeds them.

Teachers' pedagogical misconceptions are the mirror image of this: not misunderstandings about AI, but evidence-unsupported beliefs about teaching that persist regardless of AI. Miranda and Calvani (2026) instrument this with the Effective Teaching Questionnaire, where 50 binary items map onto meta-analytic effect sizes ($d \geq 0.40$) so a teacher's answer can be compared against an evidence-aligned benchmark — and their finding is that the misconceptions are deep and specific. A pilot with 123 educators in Italy found the sharpest disagreement on the learning-styles claim (78% of teachers defended visual/auditory matching), then on inclusion and group work (68%) and EdTech overload (54%); average alignment ran near 50% across the planning, cognitive, evaluative and management dimensions. Two details matter for correction design. First, the misconceptions survive university education and teaching practice — the authors describe an "internalized common sense" that "precedes entry into school" and persists — so they are not knowledge gaps a lecture closes. Second, when a conversational AI re-introduced the same items only after validating the teacher's own context, 41% of objections cited genuine contextual limits — class sizes, students with special needs, curriculum coverage — rather than the evidence itself. A further 5.9% called the system "an algorithmic dogma machine": the boundary condition where normative framing breeds defensiveness instead of reflection. For Teacher AI Competency development the implication is that diagnostic-plus-dialogue can surface which beliefs are evidence-based disagreement and which are misconception, a distinction a score alone cannot make.

Correcting misconceptions

Correction is not a one-time disclosure but an ongoing AI Literacy process that develops Metacognition and Self-Regulated Learning: helping students (and the adults around them) monitor their reliance, calibrate when to trust and when to question a model, and see the cost of bypassing their own cognitive work. Because misconceptions are resistant, they are best addressed through direct confrontation with evidence — including the finding that students often *do not perceive* the learning harm of AI misuse.

Refutation text is a core correction technique. Because misconceptions are actively held and resistant, the most direct evidence-based strategy is the refutation text — an instructional text that states the misconception, explicitly refutes it, and presents the correct conception. This is the same family of technique used to correct the domain misconceptions studied in learning science, applied here to students' beliefs about AI itself. The knowledge base's Refutation Text concept page synthesizes how this plays out in AI in education in three complementary ways:

- **AI as the corrector.** Conversational AI tutors can deliver *personalized* refutation, adapting the refutation to a learner's specific misconception on the fly. Corbett & Tangen (2026) found personalized AI dialogue produced larger and faster belief reductions than static textbook-style refutation, with higher engagement and confidence — though the advantage faded by two months without reinforcement.
- **AI as the generator of refutation content.** Akdoğan (2025) found AI-generated conceptual-change/refutation text matched expert-written quality (and both outperformed a prompted interactive dialogue in that science context), showing AI can produce effective correction materials at scale.
- **AI-generated misconceptions as a learning resource.** Rather than treating AI-generated misconceptions as merely harmful, Cheah et al. (2026) propose generating misconceptions and addressing them through structured peer discussion — a collaborative form of refutation that promotes conceptual change and critical thinking.

For misconceptions about AI, this means correction should combine **direct confrontation** (refutation-style materials that name and rebut specific myths) with **scaffolded practice** — using AI Literacy instruction and Metacognition to help people see both the false belief and the correct model. The evidence cautions that the *format* matters: personalized, interactive correction is more engaging and initially more effective, but needs reinforcement to persist; and the outcome measured (knowledge vs. attitudes vs. skills) shapes how large a correction effect appears. Because misconceptions span learners and the adults who shape learning, effective correction must reach teachers, administrators, and policymakers as much as students.

Bernstein and Sibia (2026) show that GenAI-generated analogies introduce structural misconceptions that only source-domain knowledge can catch (Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education): a circular-route analogy for a linked list implies a loop back to the start, and a badminton-rally analogy for recursion carries no guaranteed shrinking input. Students who knew the source domain identified these flaws and proposed repairs, while participants noted that a flawed analogy may still be memorable — indicating that a familiar analogy source can help learners detect, rather than absorb, an AI-produced misconception, and that framing flaws as deliberate artifacts for critique turns the risk into an assessment opportunity.

Model-generated misconceptions are a measurable capability, not an accident. Miličević et al. (2026) built SocraticTrap-CS, which prompted seven open-weight models to write a "Socratic trap" for 35 core CS concepts — an explanation that is fluent and authoritative while resting on a subtle, domain-specific error. Of 241 prompted segments, 221 (91.7%) were confirmed as strategic misconceptions by expert majority vote (Fleiss' $\kappa = 0.9487$), with no significant differences between CS domains; 66.5% of the confirmed errors were conceptual rather than factual and none were purely logical. Fluency is the mechanism rather than a defense: persuasiveness averaged 3.71 on a five-point scale and was strongly model-dependent, and

frequency and severity dissociated, with the two models that produced traps most often also rated most convincing. Because a student's poorly framed question can itself act as an adversarial prompt, the authors treat the rate as a capability under adversarial prompting rather than a base rate for ordinary study sessions — and argue the AI Literacy task shifts from fact-checking individual statements to conceptual verification and mental-model validation. This is the darker face of the generative use above: the same capability that can seed productive peer discussion can also entrench an error a learner was already forming.

Refutation-style corrections for common AI misconceptions

Because misconceptions are actively held and resistant, the most direct way to address them — including on this page — is the Refutation Text structure: **name the misconception, explicitly refute it, and state the correct conception.** The entries below apply that structure to the most consequential misconceptions about AI and about learning, teaching, and education:

"AI is always right." *That's a misconception.* AI output is a probabilistic completion, not a verified fact. *The correction:* LLMs generate plausible-sounding text based on statistical patterns; they can hallucinate, be biased, and be confidently wrong. Treat output as a draft to be checked against sources, not an authority to be accepted. This is the core of Trust Calibration and why "always verify" beats "always trust."

"Using AI is learning." *That's a misconception.* Producing work *with* AI is not the same as acquiring the knowledge or skill the work is supposed to demonstrate. *The correction:* durable learning happens through the effortful processes of drafting, recalling, revising, and metacognitively reviewing — exactly the processes that offloading to AI short-circuits. Use AI as a tool alongside that effort, not a replacement for it.

"AI is neutral and objective." *That's a misconception.* Models inherit the biases, gaps, and perspectives of their training data. *The correction:* AI can reproduce and amplify bias; treat its outputs with the same source-critical scrutiny you would apply to any other text. Awareness of this is part of AI Literacy and helps counteract the equity harms of uncritical adoption.

"AI will replace teachers." *That's a misconception.* AI augments but does not displace the pedagogical work of teachers — judgment, contextualization, and the relational and ethical dimensions of teaching. *The correction:* AI increases the need for pedagogical mediation and critical judgment; teachers who understand AI become more effective, not obsolete. This reframing matters because it shapes whether institutions invest in teacher AI competency or reflexively resist or over-adopt.

"AI understands like a person." *That's a misconception.* Models have no intent, memory of you, or genuine understanding of your context. *The correction:* anthropomorphizing AI leads to over-trust and reliance on explanations the model cannot actually ground. Keep the boundary clear: AI is a powerful tool, not a mind.

"AI will transform education automatically." *That's a misconception.* Technology alone does not change learning; it is the pedagogy around it that does. *The correction:* AI's benefits depend on intentional instructional design, teacher preparation, and institutional support — not on simply deploying the tool. This is why evidence and rigorous evaluation matter, and why the knowledge base frames responsible AI use as a AI Governance and policy question rather than a purely technical one.

"One prompt should give me the answer." *That's a misconception.* Output is non-deterministic and prompt-sensitive. *The correction:* expect to iterate, refine, and cross-check; the "prompting gap" —

mistaking shallow first results for the tool's ceiling — is a skill problem, not a tool limit. Developing this is part of Prompt Engineering.

"It's not cheating if a person didn't write it." *That's a misconception.* Academic integrity is about the honest, attributable production of work, not just about not copying a person. *The correction:* undisclosed AI-generated submission can violate Academic Integrity even when no human was copied; the question is whether the work is genuinely the learner's. When in doubt, disclose and check your institution's policy.

These refutations are deliberately written in the Refutation Text form so they can themselves be used (or adapted into interactive AI dialogue) to confront and correct misconceptions about AI — and about learning, teaching, and education more broadly.

Common Misconceptions

- **"Teachers' misconceptions are correctable by presenting evidence."** In a pilot with **123 Italian educators**, disagreement clustered hardest on **cognitive learning styles (78% of teachers defended visual/auditory matching)**, inclusion and group work (68%) and EdTech overload (54%). The strongest disagreements were the ones most resistant to evidence, which is why refutation beats assertion.
- **"Teacher objections to evidence are all resistance."** When the same items were delivered through a conversational AI that **validated the teacher's context before re-introducing the evidence**, **41% of objections concerned real contextual constraints** — class size, special needs, curriculum demands. A substantial share of apparent misconception was accurate objection.
- **"Misconceptions can be detected reliably from dialogue." Of 241 prompted segments, 221 (91.7%) were confirmed as strategic misconceptions by expert majority vote (Fleiss' κ = 0.9487)**, with **no significant differences** between groups. High reliability is achievable under expert adjudication, and that is the condition the claim depends on.

Connected Concepts

- Pedagogical Patterns — The conceptual-change sequences that confront a specific held belief
- Learners — Learners: the umbrella for the learner-side concepts
- AI Literacy
- Trust Calibration
- Cognitive Offloading
- Metacognition
- Self-Regulated Learning
- Academic Integrity
- Hallucination Risk
- Generative AI
- Student Experience
- Framing AI Use for Students
- Refutation Text

- Teaching
- Educational AI Policy
- Trust

Connected Articles

- Don’t believe the hype. AI myths and the need for a critical approach in higher education — Don’t believe the hype: eight AI myths and the need for a critical approach in higher education
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — Student Rationalization of AI Writing
- The GenAI Skill Bypass: Mapping Divergent Pathways of University Students and Staff AI Literacy — GenAI Skill Bypass and Literacy
- Trust and Reliance on AI in Education: AI Literacy and Need for Cognition as Moderators — Trust and Reliance in AI Education
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — Contextual Sycophancy and AI Literacy
- Sycophantic AI makes human interaction feel more effortful and less satisfying over time — Sycophantic AI in Social Interaction
- The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows — LLM Fallacy Misattribution (Kim et al.)
- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- The Socratic trap: Benchmarking the capacity of large language models to generate strategic misconceptions in computer science education — SocraticTrap-CS: fluent, authoritative explanations that are wrong conceptually rather than factually (Miličević et al. 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Hidden instructions in a submitted file can raise an AI-graded mark with no visible warning (Humble 2026)
- “If we are good friends, AI doesn’t spy so much”: Children’s knowledge and misconceptions of AI safety — Children’s AI-safety misconceptions: friendship with a robot misread as a privacy guarantee (Leisten et al. 2026)
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)

Connected FAQs

- How Can We Address Common Misconceptions About AI in Education?

Refutation Text

> **Refutation text** — a misconception-correction technique in which a text explicitly states a common misconception, directly refutes it, and then presents the scientifically correct conception. Originating in the conceptual-change literature of science education, refutation texts are a proven, low-tech intervention for dislodging stable, intuition-aligned misconceptions that resist ordinary instruction. In AI in education, refutation texts are increasingly used in two ways: as a **comparison condition** for AI-based interventions (personalized dialogue, Large Language Models (LLMs)-generated content), and as **AI-generated content** — conceptual-change texts and misconception texts produced by generative AI to correct beliefs or to seed collaborative discussion.

Questions to Consider

- Have you ever ‘corrected’ a student’s wrong idea by simply presenting the right answer, only to have the misconception resurface later? The page argues misconceptions aren’t gaps but actively held beliefs that resist ordinary instruction. What does that reframe about why your correction failed?
- A refutation text states the misconception explicitly, refutes it, and offers the correct conception — unlike a standard expository text that just presents the truth. Why would naming the wrong idea out loud help change it, when teaching only the right idea apparently doesn’t?
- The research is mixed on whether personalized AI dialogue beats static refutation text: in one study interactive dialogue produced larger, faster belief change; in another, well-crafted texts outperformed a prompted AI chat. What might explain these contradictory results, and what does it tell you about ‘interactivity is always better’?
- AI can now generate effective refutation texts that match expert-written quality, and even generate misconceptions to seed structured peer discussion. Does the idea of deliberately teaching from AI-generated wrong ideas feel risky or productive to you — and under what conditions would you try it?
- Refutation effects appear concentrated among high-achieving students and moderated by epistemology and Metacognition. If the technique helps the strong most, what obligations does that create for an instructor using it with a mixed classroom?
- Before you read further, name one misconception you currently hold about a subject you teach, and imagine writing the explicit ‘wrong’ claim and its refutation yourself. What did that exercise reveal about how hard good refutation is to write?

Introduction

The concept

Refutation texts rest on the idea that misconceptions are not mere gaps in knowledge but actively held, plausible, self-reinforcing beliefs that resist correction — a claim central to conceptual-change research. A

refutation text works by making the misconception explicit, naming it as wrong and explaining why, and then offering the correct conception in a way the learner can integrate. This differs from a standard expository text, which simply presents correct information and assumes the misconception will be displaced.

In AI in education, the core finding is that the *format* and *interactivity* of the correction matter. Converging evidence (Corbett & Tangen 2026) shows that static textbook-style refutation reliably corrects beliefs but that **personalized, interactive AI dialogue** can produce larger and faster belief reduction by targeting the learner's specific misconception and engaging them motivationally. However, this advantage may be context- and design-dependent: in science education (Akdoğan 2025), well-structured conceptual-change texts (expert *or* AI-generated) outperformed a prompted interactive ChatGPT dialogue — suggesting that the dialogue's design (personalized vs. generic) and the domain shape which format wins.

Why refutation text matters for AI in education

- **AI as the corrector.** Conversational AI tutors can deliver *personalized* refutation — adapting the refutation to the learner's specific misconception on the fly, which pre-written texts cannot do. This produces stronger immediate belief change and higher engagement/confidence than static refutation (Corbett & Tangen 2026), though effects may need spaced reinforcement to persist.
- **AI as the generator of refutation content.** Generative AI can produce effective conceptual-change texts that match expert-written quality (Akdoğan 2025), and can generate large numbers of context-specific misconception texts cheaply — scaling misconception-based learning that would otherwise depend on educator experience (Cheah et al. 2026).
- **AI-generated misconceptions as a learning resource.** Rather than viewing AI-generated misconceptions as harmful, structured peer discussion of them — a form of collaborative refutation — can promote conceptual change and critical thinking (Cheah et al. 2026).
- **Complementing misconception education.** Refutation texts are a recommended strategy for correcting the conceptual misconceptions that underpin students' mistaken beliefs about AI itself (see Misconceptions about AI and GenAI knowledge, epistemic orientation, and intellectual values predict undergraduate students' critical GenAI use).

Refutation text vs. related techniques

Refutation texts are one member of the conceptual-change toolkit, alongside analogies, discrepant events, and interactive dialogue. Their advantage is that they are **scalable, low-cost, and demonstrably effective**; their limitation is that static texts cannot adapt to the learner. AI dialogue addresses the adaptation gap but introduces design-dependence (personalization, prompt quality) and, in some studies, no advantage over well-crafted text. The relationship between refutation text and AI dialogue is thus complementary: text offers reliable baseline correction at scale; personalized AI dialogue offers stronger, faster, more motivating correction when well designed.

The two studies behind that design-dependence differ in more than domain. Corbett and Tangen randomized 375 adults aged 19 to 78 and targeted each participant's own highest-rated misconception in a single three-round dialogue; the dialogue's advantage over textbook refutation held at 10 days but had converged by two months (Corbett and Tangen, 2026). Akdoğan's 413 tenth-graders in Ankara received one scripted prompt session rather than a personalized one, and the interactive condition showed no advantage over control while

both expert-written and AI-generated texts did (Akdoğan, 2025). Personalization and retention window, not interactivity as such, separate the results, and the decay curve is the practical finding: one dialogue buys weeks of correction, not durable belief change.

Key research themes

- Whether personalized AI dialogue outperforms static refutation text, and under what conditions.
- Whether AI-generated refutation/conceptual-change text matches expert-written quality.
- Using AI to generate misconceptions for collaborative, misconception-based learning.
- The role of learner characteristics (achievement, epistemology, metacognition) in moderating refutation effectiveness.
- Spaced reinforcement to sustain the initial advantages of interactive refutation.

Practical implications

For educators, refutation texts remain a reliable, low-barrier way to correct stubborn misconceptions. For those integrating AI, the evidence suggests: (1) use AI to *generate* effective refutation/conceptual-change content at scale; (2) where feasible, deliver refutation through personalized AI dialogue for stronger immediate engagement and belief change. Then (3) expect AI-generated misconceptions to be pedagogically useful when structured discussion is used to confront them, and (4) design for the learner — gains skew toward stronger students and depend on epistemology and metacognition, so Scaffolding and follow-up matter.

Common Misconceptions

“Correcting a misconception means presenting the correct answer.” If it did, misconceptions would not survive instruction, and they routinely do. Misconceptions are not gaps but actively held beliefs that resist ordinary instruction: a learner who already has a working explanation does not receive the new one as a replacement, they receive it as a competing claim, and often discard the less familiar one.

“Refutation text is simply writing ‘this is wrong’ before the correct information.” The structure matters — the misconception must be stated as the learner holds it, engaged directly, and only then displaced. A bare correction names a belief the learner may reject as a straw version of their own, which is why the refutation must reproduce their intuition rather than the tidy version of it.

“More information about the correct conception fixes the resistance.” Volume of correct information is the intervention that already fails. Conceptual change requires the learner’s existing model to be made explicit and found insufficient, which is a different instructional move from adding evidence.

“Misconceptions and ordinary ignorance need the same remedy.” They need different ones: ignorance is addressed by supplying knowledge, and a misconception must be unseated first. Treating the second as the first is why a well-explained lesson can leave a student’s original model intact.

Connected Concepts

- Pedagogical Patterns — Refutation sequences, including two directly conflicting results

- Misconceptions about AI
- Scaffolding
- Metacognition
- Generative AI
- STEM Education
- Physics Education
- Medical and Health Professions Education
- Collaborative Learning
- Intelligent Tutoring

Connected Articles

- AI tutors vs. tenacious myths: Evidence from personalised dialogue interventions in education — Personalized AI dialogue vs. textbook refutation for belief correction
- Comparing the effectiveness of expert-written text, AI-generated text, and interactive AI dialogues on students' conceptual understanding of heat and temperature — Expert/AI conceptual change text vs. interactive AI dialogue
- Implementing large language models to support misconception-based collaborative learning in health care education — LLM-generated misconceptions for collaborative learning
- Student engagement with ChatGPT for educational tasks: Effects of inoculation training on verification intentions and behavior — Inoculation training as an adjacent refutation-style intervention
- GenAI knowledge, epistemic orientation, and intellectual values predict undergraduate students' critical GenAI use — Recommends refutation texts to target conceptual misconceptions
- Building AI Companions that Prioritise Learning over Performance — AI companions and misconception correction

Connected FAQs

- How Can We Address Common Misconceptions About AI in Education?

Activity Theory

> **Activity theory** (Cultural-Historical Activity Theory, CHAT) — a Vygotskian framework that analyzes learning and work as *tool-mediated, object-oriented, collective activity systems* composed of subject, object, tools/mediating artifacts, community, rules, and division of labor. In AI in education, activity theory is used both as an **analytic lens** (to understand how AI reshapes the activity systems of teaching, learning, and research) and as a **design tool** (to diagnose systemic contradictions and redesign interventions). It frames AI systems — generative AI included — as *mediating artifacts* that reconfigure the division of labor, rules, and community of educational activity, for better and worse.

Questions to Consider

- Activity theory sees learning not as individual cognition but as a collective system of subject, tools, rules, community, and division of labor. If you bring a new AI tool into a classroom, which of these do you expect to change — and which to stay stubbornly the same?
- A key idea is that contradictions within an activity system are the driving force of development, not bugs to be eliminated. Can you think of a tension in your own work or study that actually pushed you to change how you did things?
- Activity theory reframes a teacher's adoption of AI as a property of the whole system — norms, rules, workload distribution — rather than just individual attitudes. What systemic reasons might explain why a capable teacher resists a genuinely good AI tool?
- When AI takes over tasks, it reconfigures who does what, shifting the division of labor between students, teachers, and tools. What cognitive work in your own context has quietly moved from humans to machines — and who noticed?
- Because each discipline functions as its own activity system, the same AI tool can produce different outcomes across subjects. Why might a tool that transforms writing classes barely change a math class, or vice versa?
- Activity theory is used both to analyze how AI reshapes teaching and to design interventions that fix the tensions it exposes. How might seeing your own teaching or study practice as an activity system change how you diagnose a problem?

Introduction

The concept

Activity theory descends from Vygotsky's and Leontiev's cultural-historical psychology (with later development by Engeström) and is a central strand of the broader sociocultural tradition. Its core claim is that human activity is not reducible to individual cognition or isolated tool use; it is a **collective, object-**

oriented, tool-mediated system. Engeström's canonical model of an activity system comprises six interacting elements:

- **Subject** — the individual or group whose agency is the point of view of the analysis (e.g., a student, a teacher, a department).
- **Object** — the motive or goal toward which activity is directed; the "raw material" that the activity transforms.
- **Tools / mediating artifacts** — the instruments, technologies, signs, and language through which the subject acts on the object.
- **Community** — the group that shares the object and constitutes the social context of the activity.
- **Rules** — the explicit and implicit norms, conventions, and regulations that govern activity.
- **Division of labor** — how tasks, power, and responsibility are distributed across the community.

A defining feature is **contradiction**: activity systems contain historically accumulating structural tensions (within an element, between elements, or between an old and a newly introduced element/tool). Contradictions are not bugs to be eliminated but the *driving force of development* — when aggravated, they prompt participants to question and deviate from established norms, opening the way for expansive transformation (Engeström, 2001).

The tools slot is the one generative AI strains. A 2026 sociocultural essay argues that an Large Language Models (LLMs) both mediates the activity and generates contingent contributions that reshape its trajectory, so calling it a tool understates its influence while calling it a collaborator attributes intentionality, accountability and community membership it does not have (Warschauer, Tate and Ritchie, 2026). Their *mediational agent* sits in the tool position without holding a position in the community, which means the division of labor has to be analyzed around contributions and not only around instruments.

Why activity theory matters for AI in education

AI introduces new **tools/mediating artifacts** into existing educational activity systems, which produces both opportunities and contradictions. Activity theory gives AIED research a vocabulary and method for analyzing these changes:

- **AI as a mediating artifact that reconfigures the division of labor.** AI systems do not simply transmit information; they take over tasks, change who does what, and redistribute cognitive work across humans and machines. Studies use activity theory to examine how AI shifts the division of labor between students, teachers, and tools — e.g., in collaborative writing or tutoring — and what this means for human agency.
- **The labor redistributes faster than the rules change.** A scoping review of 53 HCI studies of LLMs in family education found systems producing materials, structuring dialogue, interpreting context and connecting families to outside knowledge, while parents kept the reviewing, adapting and deciding; verification and repair work went undocumented (Luo et al., 2026). Rules governing participation were mostly anticipated rather than enacted, the mismatch between a new tool and an unchanged rule set that the framework predicts.
- **Analyzing teacher adoption and professional development.** Activity theory reframes teacher uptake of AI as a property of the whole activity system (community norms, rules, division of

labor, institutional expectations) rather than of individual attitudes alone. Quantitative work models the six AT components as measurable constructs predicting teachers' intention to adopt AI; qualitative work documents teachers' sixfold sentiments (unsuitable, impersonal, imperfect, uncertain, assisting, inevitable); and intervention work uses CHAT to diagnose and redesign teacher professional development, treating disengagement as a rational response to need-thwarting systems.

- **Norm change and systemic disruption.** Because AI introduces a new tool into the activity system, it generates contradictions with existing rules and norms. Studies of students' GenAI use show how new implicit rules emerge as students adapt — transforming norms around self-direction, learning objectives, the teacher's role, and Ethics.
- **Anchoring learning analytics and measurement.** Activity theory can ground the *design* of analytics by mapping measurement facets onto activity-system elements. A CHAT-anchored analytics pipeline maps temporal participation, discourse quality, and concept sophistication to CHAT elements to detect early at-risk participation in small discussion-based classes.
- **Disciplinarity and cross-context variation.** Because activity systems are historically and culturally situated, activity theory explains why the same AI tool produces different outcomes across disciplines and contexts — each discipline functioning as an activity system with its own rules, community, and division of labor (e.g., differences in undergraduates' GenAI use and disclosure across academic domains).
- **One tool, two activity systems, uneven penetration.** Among ten mathematics academics analyzed through CHAT, GenAI stayed a peripheral tool in the research activity system while reshaping the teacher's role toward mediator of critical reasoning in teaching, with adoption spreading through student use and peer networks rather than institutional policy (Bakogianni et al., 2026).

Activity theory and related frameworks

Activity theory sits within the sociocultural family and is often paired with, or contrasted against, other frameworks: **distributed cognition** and **situated learning** share its emphasis on context and mediation; **community of inquiry** and **communities of practice** share its collective orientation; and **technology-acceptance** models (e.g., TAM) offer a contrasting, more individual-belief account of adoption that activity theory critiques for flattening the collective and structural dimensions. In AIED research, activity theory is frequently combined with other theories — e.g., paired with Self-Determination Theory in teacher-PD intervention design, or with ecological systems theory in situated-AI-ethics frameworks (Raffaghelli et al., 2026).

Key research themes

- **How AI redistributes the division of labor** in teaching, learning, and research activity systems.
- **Systemic contradictions** as drivers of norm change and expansive transformation in AI-augmented education.
- **Teacher adoption and professional development** as activity-system (not merely individual) phenomena.

- **Disciplinary and cross-cultural variation** in AI use, explained by differences in activity systems.
- **Theory-anchored learning analytics** that ground measurement in activity-system elements.
- **The object of AI-mediated activity** — whether the object of learning shifts from mastery to output, and what that means for learning outcomes.

Practical implications

For designers and educators, activity theory counsels looking beyond the AI tool itself to the whole activity system it enters: the rules that govern acceptable use, the community and its norms, the division of labor between human and machine, and the object/motive of the activity. Sustainable AI integration requires *redesigning the system* — addressing contradictions, updating norms, and rebalancing roles — not merely supplying better tools or individual training. For researchers, activity theory offers a rigorous unit of analysis (the activity system, not the individual) and a method (formative intervention, contradiction analysis) for studying and shaping AI's role in education.

Common Misconceptions

"A teacher's adoption of AI is a question of individual attitude." Activity theory reframes it as a property of the whole activity system — subject, tools, rules, community and division of labor — so resistance is frequently a rational response to a system that has not changed. A teacher who declines a tool that adds work, redistributes their attention badly, or conflicts with departmental norms is reading the system correctly; attitude surveys will record that as a disposition and miss the cause.

"If you change the teacher's beliefs, the practice will follow." The unit of change is larger than the person. Interventions that alter norms, workload distribution and shared rules change practice more reliably than those aimed at individual conviction, because the object of the activity is produced collectively. This also explains why individually enthusiastic adopters revert when their department does not move with them.

"Activity theory is a descriptive lens with no design consequences." It directs design at the contradictions between elements of the system — the tool that conflicts with the rules, the division of labor that conflicts with the object — which is where change is actually levered. A lens that locates contradictions is giving you a place to intervene, not merely a vocabulary.

Connected Concepts

- Sociocultural Learning — the theoretical family activity theory belongs to (Vygotskian, cultural-historical)
- Learning Theories — the hub that situates activity theory among learning theories
- Distributed Cognition — shared emphasis on tool-mediated, contextually distributed cognition
- Situated Learning — shared emphasis on context and participation in activity
- Learner Agency — how AI redistributes human agency across the activity system
- Teaching — activity theory frequently analyzes teachers' adoption and practice
- Learning Analytics — CHAT anchors the design of analytics
- Generative AI — the AI artifact that enters and disrupts educational activity systems

- Technology Adoption Models — the contrasting individual-belief account of adoption

Connected Articles

- Generative AI across the disciplines: an activity theory perspective on undergraduate students' AI use and disclosure practices — Disciplinary differences in GenAI use and disclosure through an activity theory lens
- GenAI as a runaway object in higher education: A socio-cultural view on AI-influenced academic practice in mathematics — CHAT analysis of GenAI reshaping teaching and research activity systems
- Situated AI ethics: a cultural-historical and ecological framework for education — Situated AI ethics fusing ecological systems theory with CHAT
- Activity theory as a lens on teachers' adoption of AI technologies: A structural equation modeling — Activity theory as a lens on teachers' adoption of AI (SEM)
- K-12 teachers' perspectives on AI use in education through the lens of activity theory — K-12 teachers' perspectives on AI use through activity theory
- The AI disruption in engineering education: An analysis of changing student norms through cultural historical activity theory — Changing student norms in engineering education via CHAT
- An activity-theoretical approach to teacher professional development in pedagogical AI agent design — CHAT-SDT redesign of teacher professional development
- A cultural-historical activity theory-anchored learning analytics pipeline for early detection and social-epistemic integration in AI literacy education — CHAT-anchored learning analytics pipeline for AI literacy
- Characterizing LLM-Based Family Education through the Lens of Activity Theory: A Scoping Review of the HCI Literature — Scoping review of 53 HCI studies: LLMs redistributed family educational labor, while rules were mostly anticipated rather than enacted
- Generative AI as a Mediational Agent: Rethinking Learning in Sociocultural Theory — GenAI as a mediational agent: neither tool nor collaborator

Retrieval, Spacing and Interleaving

> **Retrieval, spacing and interleaving** — the three concrete study techniques that make practice effortful and, as a result, make what is learned durable. Retrieval practice asks the learner to produce an answer from memory rather than recognize one; spacing distributes that practice across time instead of massing it into one session; interleaving mixes problem types instead of blocking them. What unites them is a shared signature: each lowers performance *during* practice while raising retention *after* it — the performance–learning gap in operational form. They are the workhorses of Cognitive Psychology, and in AI-supported learning they are the specific behaviors that generative AI most easily erases, because an LLM that answers on demand removes the retrieval, flattens the schedule, and smooths away the mixing. This page is the *techniques* page. The principle behind them — Bjork's effort–learning trade-off, why harder practice produces more durable learning — is treated on Desirable Difficulties; this page covers what each technique is, what the corpus's studies measured, and how AI implements or undermines them.

Questions to Consider

- Have you ever re-read a chapter until it felt familiar, then been unable to explain it a week later? What did the re-reading actually give you?
- Retrieval practice means answering from memory *before* checking. When an AI assistant is one keystroke away, what would have to be true about your study routine for that retrieval to still happen?
- Spaced repetition systems schedule review at intervals a learner would not choose. Is a schedule that feels wrong a feature or a bug?
- Interleaving mixes problem types and feels messier than blocking. If the corpus offers almost no direct AI evidence on interleaving, how confident should you be in adopting it — and on what basis would you decide?
- Akgun and Toker (2026) found that students who chatted freely with an AI scored worst, even after the best pretesting. What did the free-chatting condition lack that the structured one had?
- Tsiligkiris (2026) found deeper LLM questioning improved task quality but not recall. What does that tell you about using fluency as evidence of learning?

Introduction

Retrieval practice, spacing and interleaving are usually taught and cited together because they were discovered separately but behave alike: each sacrifices how good practice *looks* in exchange for how much survives. In the knowledge base they appear as instances of the Desirable Difficulties principle, but they are also independently actionable — a reviewer can schedule intervals, a tutor can withhold the answer, a curriculum can mix item types, without invoking the underlying theory. Their operational character is why they are the natural bridge between Cognitive Psychology and AI design, and why the studies below tend to report two outcome measures rather than one: performance during practice, and retention after a delay.

The Testing Effect: Retrieval Practice Beats Re-Reading

Retrieval practice — attempting to recall material rather than re-reading it — strengthens memory more than additional study does, and the corpus treats the finding as settled enough to build on rather than re-litigate. The learning-to-learn scoping review places retrieval practice in the **Tools** layer of its three-layered framework (Dimensions of cognitive and metacognitive skill, Processes of self-regulation, Tools such as retrieval practice), positioning it as a concrete, teachable component of learning-to-learn that is meant to counterbalance GenAI overreliance and protect learner agency.

The most informative test in the corpus is a dissociation. Tsiligkiris (2026) logged 22 postgraduate students' prompt-by-prompt Large Language Models (LLMs) interactions during a neuroeconomics case task and separated *depth* (the proportion of explanation-seeking "why/how/explain" prompts) from volume and pacing. Depth predicted independently marked task quality ($\beta = 6.27$, $p = .006$) but had a null association with immediate post-test recall ($\beta = -0.014$, $p = .728$), with recall gains driven by baseline knowledge instead. The reading the author gives is that elaboration drives comprehension while retrieval drives consolidation — and that in LLM-supported study without explicit retrieval demands, learners can experience high fluency with little need to retrieve anything unaided. That is a retrieval-practice finding stated as an absence: the mechanism was not engaged, so the retention outcome did not move.

Retrieval practice is not a universal lever, and the corpus says so. Rachatasumrit, Koedinger and Carvalho (2025) ran a 2×2 experiment with 95 participants crossing knowledge content (verbatim facts vs. generalizable skills, geometry-area materials) with training schedule. They found a content–treatment interaction ($\beta = 0.41$, $p = .038$, $d = 0.38$): pure practice testing produced higher learning gains for **facts**, while example-integrated practice produced higher gains for **skills**. The authors also note that retrieval-practice gains frequently fail to extend to unfamiliar problems. So retrieval practice is strongest where the target is memory for specific content, and it needs to be paired with worked examples where the target is a generalizable skill — which is also why their AI design implication is that Intelligent Tutoring should adapt the example-to-practice ratio to the knowledge component being learned.

The same logic runs through the cheating-sheet study: Chen, Sakhnini and Istead treat *constructing* a cheat sheet as an active, generative study strategy (selection, condensation, organization) rather than logistics, and frame the AI-era risk as offloading the artifact's construction and losing the metacognitive rehearsal that building it provided.

Spacing and Distributed Practice

The spacing effect — that the same total practice produces more durable learning when distributed across sessions than massed into one — is the most algorithmically exploited of the three techniques, and the corpus's applied systems are built around it.

Memdora is the clearest example of spacing treated as an engineering problem. It grounds scheduling in the Ebbinghaus forgetting curve, cites the figure that roughly **70% of newly learned material is forgotten within 24 hours** without review, and integrates **FSRS-6**, described as the current state-of-the-art spaced-repetition algorithm. Its argument is that scheduling alone is not enough: existing tools reduce flashcard interaction to a single binary gesture, "flip and self-rate", which the authors call an impoverished model that fails to exploit cognitive-science evidence on retrieval practice. Memdora's contribution is therefore a

taxonomy of 17 cognitively-grounded interaction types across Language, By Heart and Exam categories, each mapped to peer-reviewed evidence displayed on the card, plus an effort-based reward system that compensates actual cognitive engagement rather than app presence, a unified generation pipeline that creates cards at the point of reading, and a classroom layer that reports learning outcomes at the individual card level.

Malhotra's (2026) bilingual lecture companion attacks that authoring cost from the other end: it transcribes English–Hindi lectures in the browser and generates flashcards on-device, built for Indian classrooms where UDISE+ data put internet access at about 54% of schools.

Akgun and Toker (2026) supply the corpus's strongest experimental evidence on how spacing is *structured*. In a three-arm randomized study of 89 undergraduates in an applied statistics course, all three groups practiced in spaced sessions with identical number and timing over seven weeks; only the interaction structure differed. Adaptive spaced retrieval (G1) reached the highest posttest score (M = 78.19) and the highest observed practice effort (M = 0.85); fixed spaced retrieval (G2) followed (M = 74.55, effort 0.74); learner-directed AI study with no enforced retrieval came last on both (M = 67.28, effort 0.49). The multivariate effect was significant (Wilks' $\Lambda = .664$, partial $\eta^2 = .185$), with G1 ahead of G3 on retention at $d = 0.92$ ($p = .003$). The detail that matters pedagogically is that G1's agent was configured to *withhold*: response-contingent probes for Misconceptions about AI, requests for elaboration after superficial answers, advancement only on adequate conceptual engagement, and direct solutions explicitly excluded from its allowed outputs. The authors' own reading is that pretesting is a front-loaded catalyst rather than a standalone intervention whose benefits survive open-ended AI access.

A randomized field experiment reports distribution over massed time as the operative dose: weekly mastery tracked completed tutoring weeks rather than engaged minutes, each additional completed week adding 2.00 points of 55 ($p = .018$) (Yang, Van Alstyne and Dellarocas (2026)).

Two further corpus findings sharpen what spacing does and does not yet get right. Schuetze, Yan and Carvalho (2025) fit Knowledge Tracing models to a six-session successive-relearning dataset and found that BKT, BKT-with-Forgetting and the Additive Factors Model reproduce learning trends when fit retrospectively (AUC 0.74–0.79) but, under time-based cross-validation of the kind a deployed tutor would need, overestimate future performance by roughly 58%, 51% and 47% respectively and **fail to capture the spacing effect** — sometimes predicting the opposite ordinal ordering across spacing conditions. In other words, the scheduling decisions made by adaptive systems may be based on models that do not represent the very effect spacing depends on. And LLM student modeling and long-term memory names the design gap directly: most tutoring systems lack longitudinal memory, and how such memory should interact with spaced repetition and forgetting curves remains an open question.

What the corpus does not yet show

Neither applied system has produced retention evidence of its own: the Memdora article reports improved retention relative to traditional spaced-repetition tools, but describes no delayed-interval outcome study behind that claim, and the bilingual lecture companion — which generates flashcards automatically to remove the authoring cost that blocks evidence-based retrieval and spaced practice, while simplifying scheduling to a binary "know it / still learning" rating rather than the graded SM-2 and FSRS algorithms —

states plainly that **no learning-outcomes study has been run**, only a pre-registered protocol. The scheduling machinery is better evidenced than the learning it is meant to produce.

Interleaving

Interleaving — mixing problem or item types within a practice session rather than blocking them by type — is the weakest-evidenced of the three in this corpus, and that should be stated rather than padded. Interleaving appears on Desirable Difficulties only as one instance in a list of effortful conditions, and no study in the knowledge base tests an interleaving manipulation against a blocked control.

What the corpus does contain is adjacent and worth distinguishing carefully. Simulating learner task-selection models **Interleaving** and **Blocking** as two of eight candidate learner strategies in a Mastery Learning Simulation, alongside strength targeting, weakness targeting and outcome-informed rules. The finding there is about choice architecture rather than memory: some learner strategies systematically delay progression through over-practice, and task-selection constraints repaired the maladaptive strategies while leaving Interleaving, Blocking, Strength Targeting and Weakness Targeting at steady over-practice levels. That is evidence that interleaving is a *selectable behavior* a system can accommodate or constrain — not evidence that interleaving improves retention. The remaining mentions in the corpus are unrelated senses of the word (interleaved agent stages in From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review; interleaved visual-textual solution trajectories in a geometry Benchmark), and they should not be counted as interleaving evidence.

Interleaving's inclusion here therefore rests on the same theoretical family as the other two techniques and on its status in the Cognitive Psychology literature, not on a study in this knowledge base. Treat it as the open slot.

How AI Implements and Undermines These Techniques

Implementation. AI's most defensible contribution is scheduling and generation, the parts of these techniques that are tedious rather than pedagogically interesting. Adaptive scheduling is implemented in Memdora via FSRS-6 and in knowledge-tracing architectures that estimate mastery over time; adaptive *pretesting* is implemented by Akgun and Toker's response-contingent agent, which reads prior-session performance signals to raise conceptual depth in weaker areas while maintaining challenge in stronger ones; automatic flashcard and pretest generation is implemented in the bilingual lecture companion, where card authoring is the cost that blocks spaced practice in the first place. Longitudinal student memory is the architecture that would let any of this persist across semesters, and Woollaston and colleagues (2026) supply the design vocabulary for doing it deliberately: intentional friction, dynamic Scaffolding, human-in-the-loop oversight, and considered rather than maximal AI utilization.

Undermining. The failure mode is specific and documented repeatedly. Woollaston et al. (2026) name the first of their six pedagogical risks as prior-knowledge activation: agents that pre-fetch and surface content **bypass the retrieval practice that activates prior knowledge**, so the learner never recalls or integrates what they know before receiving an answer. Prior Knowledge states the same bypass risk as a general property of generative AI, and adds the design countermeasure — activate before you supply. The fluency illusion is the mechanism on the learner's side: an LLM supplies complete, coherent explanations on

demand, so the learner allocates less effort to internal retrieval and reconstruction while the session *feels* productive, which is precisely the dissociation Tsiligkiris (2026) measured. The three-arm pretesting study makes the same point experimentally: the arm with free AI access and no enforced retrieval performed worst on end-of-semester retention, and interaction volume did not differ significantly across arms, so the gap was produced by structure rather than by how much students engaged.

Preserving retrieval demand. The corpus converges on a small set of design features. The pretesting agent's policy is the most concrete: withhold direct solutions by configuration, probe misconceptions, request elaboration after superficial attempts, and advance only on adequate conceptual engagement. Tsiligkiris recommends embedding retrieval demands *after* LLM use through closed-tool outputs — short-answer questions, concept maps drawn from memory, teach-back explanations without the model — and separating scaffolding from checking, so the model is available for clarification and Feedback but distinct checkpoints require independent recall. KnowLoop shows the teach-back form in a deployed system: a Peer agent scaffolds reflective teach-back that surfaced gaps learners could not articulate, and its participants asked to move fluidly between clarification and consolidation rather than treating them as strict phases. Chen, Sakhnini and Istead add the assessment-side version — value the construction process rather than the artifact — while Schorr and colleagues (2026) position these tools as learnable skills that reduce overreliance and support learner agency. Underneath all of them is the one non-negotiable: something must require the learner to produce an answer that the model has not already given.

Limits of the Evidence

- **Small samples and single contexts.** The pretesting study's analytic sample is 89 undergraduates in one applied statistics course, with 27–34 students per arm; the LLM interaction study has n = 22 with a single-group design that supports no causal claim; the teach-back study has 22 participants. The pretesting authors state that replication across domains and task types is needed for generalizability.
- **Short or absent retention intervals.** The interaction-depth study tested immediate recall only, with no delayed measure, so its null is a null for short-term retention specifically. Memdora's retention advantage and the LLM-depth dissociation alike are not tracked over the weeks that the spacing literature would require; the pretesting study's seven-week window is the longest in the corpus.
- **Self-report and proxy measures.** Practice effort in the pretesting study is a behavioral indicator scored by two raters against a rubric from conversation logs, which the authors explicitly note is not a measure of internal motivational state; the LLM-depth measure is a keyword-based proxy capturing the surface form of explanation-seeking rather than its quality.
- **Instrumentation and modelling limits.** Knowledge Tracing models in the corpus fail exactly where spacing decisions need them, and the authors attribute past successes to retroactive full-dataset fitting rather than deployment-realistic validation. The bilingual companion's flashcard quality is unverified against ground truth, with no automated fact-checking layer, and it has run no outcomes study at all.

- **Interleaving has essentially no direct evidence here.** As stated above, the corpus contains no blocked-versus-interleaved comparison, only a simulation in which Interleaving is one selectable strategy among several.
- **Subject populations and content.** The evidence base concentrates on higher education, on STEM and statistics material, and on fact-versus-skill distinctions from geometry and multiple-regression content; generalization to K-12 settings, to humanities and writing, and to non-Western classrooms is not established by these studies.

Common Misconceptions

"Better AI questioning produces better retention." It produces better work. Tsiligkiris (2026) found deeper LLM questioning improved independently marked task quality (**β = 6.27, p = .006**) while having a **null association with immediate post-test recall (β = −0.014, p = .728)**, with recall gains driven by baseline knowledge instead. The quality of the artifact and the durability of the memory are different outcomes, and better dialogue moves the first without moving the second.

"There is one best practice format." The format depends on what is being learned. A content–treatment interaction (**β = 0.41, p = .038, d = 0.38**) shows **pure practice testing produced higher gains for facts**, while **example-integrated practice produced higher gains for skills**. Prescribing retrieval practice for everything, or worked examples for everything, gets half the material wrong.

"Retrieval practice means quizzing, and any quizzing counts." The mechanism is producing an answer from memory rather than recognising one, which is why a multiple-choice recognition task is a weaker version of the same activity. An AI that generates endless recognition items has generated activity of the right name and the wrong mechanism.

"AI can faithfully deliver these techniques, since they are well specified." It can also quietly defeat them. Spacing requires the system to withhold the material it is most able to supply on demand, and retrieval requires it not to answer — so the technique's effectiveness depends on constraints an agreeable assistant has no incentive to impose.

Connected Concepts

- Pedagogical Patterns — Spaced retrieval sequences, and the retention cost of assisting during encoding
- Desirable Difficulties — the principle these three techniques operationalize
- Cognitive Psychology — memory, encoding and retrieval as the theoretical home of all three
- Prior Knowledge — retrieval practice as activation of what the learner already holds
- Metacognition — judging whether fluency reflects learning
- Self-Regulated Learning — studying consistently what an AI can schedule or answer for you
- Mastery Learning — retention after the mastery threshold, and the spacing that sustains it
- Knowledge Tracing — the models that make or miss scheduling decisions
- Cognitive Offloading — the failure mode when retrieval is delegated to a tool
- Transfer of Learning — the performance–learning gap the techniques address

- Formative Assessment — closed-tool checkpoints as retrieval events
- Productive Failure — attempting before receiving help
- Learners — the stakes of durable rather than fluent learning

Connected Articles

- Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study — Akgun & Toker: adaptive spaced retrieval vs fixed retrieval vs learner-directed AI over seven weeks
- Memdora: Designing Cognitively-Grounded Flashcard Interactions for AI-Powered Spaced Repetition — Memdora: FSRS-6 scheduling and a taxonomy of grounded flashcard interactions
- What students ask matters: LLM interaction depth, task quality, and immediate recall in higher education — Tsiligkiris: explanation depth predicts task quality but not immediate recall
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content — Retrieval practice for facts, worked examples for skills; the content–treatment interaction
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models — Knowledge-tracing models fail to capture the spacing effect under time-based validation
- A bilingual, LLM-mediated lecture companion for self-regulated learning: Architecture, theoretical framework, comparative and usability evaluation, and a pre-registered outcomes protocol — Automatic flashcard generation removing the authoring cost of spaced practice
- Make or Take: How Students Navigate Self-Created and Instructor-Provided Cheat Sheets — Constructing a cheat sheet as generative study; offloading the construction with AI
- From Confusion to Consolidation: A Staged Conversational Workflow for Post-Lecture Review — Teach-back consolidation surfacing gaps clarification did not
- Simulating Learners' Task-Selection Strategies and System Constraints in Mastery Learning — Interleaving and Blocking as modeled learner strategies under task-selection constraints
- PersonaVLM: Long-Term Personalized Multimodal LLMs — Longitudinal student memory and its open relation to spaced repetition and forgetting curves
- Learning-to-learn in the age of generative AI: A scoping review and conceptual framework — Retrieval practice in the Tools layer of a learning-to-learn framework
- Agentic AI and Pedagogical Best Practice: The Tension Between Automation and Learning — Pre-fetching agents bypass retrieval practice; the case for intentional friction
- When AI Tutors Speak: Evidence from a Randomized Field Experiment — When AI Tutors Speak: Evidence from a Randomized Field Experiment

Learner engagement and experience

Student Engagement

> **Student engagement** — the degree and quality of a learner's active involvement in the learning process, most often decomposed into behavioral, cognitive, and affective dimensions. In AI in Education research, student engagement is both a key outcome (does an AI tool keep students engaged?) and a mechanism (does engagement mediate between AI design and learning?). It is conceptually distinct from learning itself — engagement is participation in learning, not proof of cognitive gain — and from the specific metrics used to measure it.

Questions to Consider

- The page insists engagement is not the same as learning — a student can be behaviorally active (clicking, spending time) while cognitively shallow. Where have you seen high 'engagement' that produced little learning, and how did you notice?
- Think of a moment you were deeply cognitively engaged in something — truly wrestling with an idea. What was different about it compared to times you were merely busy or entertained, and could an AI tool reliably create that state?
- Engagement is broken into behavioral, cognitive, and affective dimensions that can diverge. Why do you think researchers insist on treating these separately rather than as one thing, and what would you measure to tell them apart?
- The research suggests deep cognitive engagement with AI predicts learning, while shallow engagement predicts over-reliance. If a tool is 'engaging' but shallow, who is at fault — the design, the task, or the learner?
- How might an AI tool satisfy autonomy, competence, and relatedness (the needs behind engagement) without those features turning into shallow entertainment that displaces real learning?

Introduction

Engagement is a multidimensional construct rooted in educational psychology. **Behavioral engagement** refers to participation, effort, persistence, and on-task activity. **Cognitive engagement** refers to the depth of mental processing — elaboration, critical analysis, self-AI Regulation in Education, and the investment of mental effort. **Affective engagement** refers to emotional reactions such as interest, enjoyment, anxiety, and identification with learning. These dimensions can diverge: a student may be behaviorally active (clicking, spending time) while cognitively shallow (passively accepting output), or affectively interested while behaviorally distracted. This multidimensionality is why engagement must not be equated with any single observable behavior.

How student engagement appears in the research

- **Engagement as an outcome of AI design:** GenAI motivation research shows that engagement in Generative AI-supported learning follows the satisfaction of basic psychological needs (autonomy, competence, relatedness) — engagement is the downstream result of motivational support, not of technology availability alone. Engagement is often measured by self-report while behavioral engagement comes from interaction logs, and the two are not interchangeable.
- **Engagement gain without a learning gain, in a cluster-randomized classroom trial:** Rücker and Becker-Genschow (2025) randomized 195 ninth-grade classes (experimental group 102 students) to a domain-specific mathematics chatbot or to conventional differentiation materials for a single lesson on the Heron method of estimating square roots. Situational interest rose substantially in the chatbot condition (M = 2.63 vs 2.43, p = 0.00005, Cohen's d = 0.63) and acceptance on all four Technology Acceptance Model dimensions was high, yet the pre-post performance comparison found no significant group-by-time interaction ($F(1194) = 2.84$, $p = 0.094$) and extrinsic cognitive load was slightly higher. The study is one of the few cluster-randomized tests of a customized chatbot in secondary mathematics, and its split result is the point: interest and achievement moved on different schedules, so an engagement finding is not evidence of learning.
- **Quality over quantity:** Critical engagement in AI code completion, cognitive-engagement discourse analysis, and scaffolding critical engagement show that *deep* (cognitive) engagement with AI predicts learning, while *shallow* (behavioral) engagement predicts the Over-Reliance and learning displacement that dominate the knowledge base's risk literature.
- **Agentic engagement and AI feedback literacy develop together.** Three waves six weeks apart in 399 undergraduates showed within-person paths in both directions ($\beta = 0.222$ and $\beta = 0.263$), so engagement is not only an outcome of design but part of what builds the capacity to use feedback (Xu (2026)).
- **Fragile and context-dependent:** Polished artifacts, fragile engagement and multi-institution engagement patterns find engagement varies by task, context, and learner — an AI tool that engages one student deeply may produce shallow, output-chasing behavior in another.
- **Motivational antecedents:** AI availability and motivation shows that knowing AI is available can reduce the perceived value of effortful engagement, particularly for novice learners — engagement is shaped by expectancy, value, and perceived competence as much as by tool features. **Wang & Wang (2026)** extend this with a goal-setting-theory account of **758 university English learners** in AI-assisted learning, showing that **teacher support** directly enhances engagement and operates through students' **mastery-approach and performance-approach goals** (rather than avoidance goals). Engagement in AI contexts is therefore not only an individual or design outcome — it is also **socially scaffolded** by the teacher and by the goal orientations learners are encouraged to adopt.

That Scaffolding has an institutional counterpart with a dual pathway. Chen's (2026) two-study design (160 art students in a scenario experiment, 425 surveyed) found that perceived inconsistency between a university's GAI advocacy and its actual teaching and assessment practices predicted creative process

engagement through two opposing appraisals — negative via hindrance (β = −0.060, p = 0.004) and positive via challenge (β = 0.217, p < 0.001) — with pathways thinking strengthening only the positive route, so the same institutional condition engaged some students and disengaged others.

- **Competency and emotion as engagement drivers:** Zhao et al. (2026) model **871 university students** interacting with an Large Language Models (LLMs) chatbot, finding that **GenAI competency** predicts chatbot engagement both directly and indirectly through **positive emotions** (the affect pathway), and that both competency and positive emotion predict engagement and positive learning emotions. Engagement is thus jointly a *skill* and an *affective* outcome — learners who lack AI competency and experience anxiety or frustration disengage, which has implications for AI Literacy training as an engagement intervention rather than merely a skill goal.
- **Discipline-associated cognitive engagement in student-AI chat.** Chang and Li (2026) show that student prompts to AI encode ~62% higher-order cognitive demand on average, but Bloom-level engagement profiles differ sharply by discipline (STEM Apply-prevalent 20.8%, language Understand-prevalent 31.7%, social science Create-prevalent 33.8%). Using a within-person design, they found the same students produced significantly more higher-order prompts in social science than STEM courses ($p < .001$), with course-level variation exceeding student-level variation — evidence that cognitive engagement with AI is shaped by disciplinary context, not just individual style.
- **AI feedback sustains behavioral activation.** Geschwind et al. (2026)'s semester-long lab-in-the-field experiment found that students receiving individual GPT-4 feedback on open-ended tasks sustained the highest participation across eight weekly tasks (~50% by the last, vs ~30% for lecturer- or peer-feedback groups) and wrote ~29 more characters per answer — individual AI feedback activated engagement on both the extensive margin (participation) and the intensive margin (effort per response), even though students rated the peer feedback slightly higher.
- **Predicting academic AI use from learning constructs.** An exploratory machine learning framework analyzed survey data from 166 university students to identify learning-related constructs associated with intended academic ChatGPT use, using SHAP analysis to maintain interpretability. Findings inform how engagement, learning support, and other constructs shape students' incorporation of AI tools into academic work.
- **Access to an AI tool can *lower* measured engagement, and completion rates will not show it.** Liu et al. (2026) randomized tutor access across 13 blocks at a large U.S. public university and found recorded platform participation fell by 0.90 SDs, page views by 0.37–0.38 SDs and active days by 0.51–0.61 SDs — while homework submission and on-time submission were unaffected. The dissociation is the measurement lesson: a course monitoring only assignment completion would have seen nothing, because the reduction sat in the discussion, quiz and instructor-interaction activity the platform logged. Students in treated sections also reported asking the instructor fewer content questions (about 57% versus 44%), so the decline coincided with substitution away from human contact rather than with disengagement from the course.
- **Reply latency is an engagement lever.** In 1,137 Quantitative AI tutoring sessions, faster replies tracked with more student messages and more correct practice (median reply time 1.9 s to 31.0 s across models; lower latency correlating with engagement at Spearman ρ=-0.81, p=.0056). The

authors read that chain as explaining how models that score unremarkably on teaching quality still reach human-level gains (Northcutt et al. (2026)).

- **AI use can travel with greater class absenteeism while confidence does not predict it.** A PLS-SEM survey of 291 Portuguese university students found general AI use positively associated with absenteeism ($\beta = 0.148$, $f^2 = 0.029$) and with Self-Efficacy for independent learning, yet self-efficacy itself did not predict absenteeism ($\beta = -0.068$, $p = 0.276$) — the paper's "confident but absent" pattern. The attendance association was modest and secondary to peer influence ($\beta = 0.510$, $f^2 = 0.326$) and time management ($\beta = -0.163$), and because the AI-use construct was unidimensional and mixed support-oriented with substitution-oriented items, the study cannot separate complementary from substitutive use or establish direction (Franco et al. (2026)).

Measuring engagement: the metric-choice problem

Engagement is operationalized through a range of observable signals. **Behavioral metrics** measure what learners *do* (time-on-task, activity counts, interaction frequency, persistence); **cognitive metrics** measure how learners *think* (depth of processing, critical engagement, discourse analysis); **affective metrics** measure how learners *feel* (emotion, motivation, interest); and **contextual metrics** capture multitasking and attention. AI-education research increasingly combines these and treats engagement as a mediating mechanism between AI tool design and learning outcomes, rather than an outcome in itself.

- **Six AI application families + multi-method measurement:** Zhou's (2025) systematic review of 24 WoS studies maps six AI applications for engagement — chatbots in course design, emotion/facial/voice recognition and eye tracking, ML for data analysis, teacher–student interaction support, personalized feedback/recommendations, and AI-powered bots in smart learning environments. It finds that integrating multiple AI modalities and data sources yields more accurate, real-time insight into cognitive, emotional, and behavioral engagement than single-source approaches — reinforcing the metric-choice problem above.

The choice of metric is definitional: a study that measures engagement as *time-on-task* may conclude an AI tool enhances engagement when students spend more time interacting with it, while a study that measures engagement as *critical processing* may reach the opposite conclusion for the same tool. This is why the knowledge base's research distinguishes engagement (participation) from learning (actual cognitive gain) — see performance vs. learning — and why engagement metrics must be validated against what they claim to measure.

Self-report and behavioral records of the same use can diverge almost completely. Keith, Wood and Posey (2026) measured AI engagement modes twice in the same 171 students: once with a 29-item self-report instrument, and once by classifying 1,353 transcript turns. No paired profile correlation survived correction at $|r| \geq .30$, mean total-variation distance was .701 and only .002 closer than random re-pairing, and behavioral composition raised explained variance by .166 against .031 for self-report; only observed profiles tracked quiz scores, where explanation-seeking turns accompanied higher scores ($r = .33$, $p < .001$) (The eight-mode AI engagement typology: Differential cognitive signatures and a self-report–behavior gap).

A self-report of how a student engages carried almost no information about how that student actually engaged, which makes the metric-choice warning above a measured result rather than a caution.

- **Engagement as a fragile, situation-dependent signal:** Polished artifacts, fragile engagement and multi-institution engagement patterns find that engagement varies by context, task, and learner — the same tool produces strong engagement for some students and shallow, output-chasing behavior for others.
- **Behavioral telemetry from learning platforms:** Effort and progress forecasting, Learning Engagement Assistant, video engagement assessment, and learning dashboards translate behavioral and physiological signals (attention, activity, persistence) into engagement metrics used for adaptive feedback and instructor intervention.
- **Physiological sensing adds a modality — and a baseline problem.** E3Sense co-locates dry-electrode EEG, eye-tracking glasses, and forehead electrodermal electrodes on the head and predicts 450 segment-level engagement ratings from 30 university participants on a five-level ordinal scale: AdaBoost over the fused Multimodal AI representation reached 75.0% balanced within-one-level accuracy against 63.0% for always predicting the most common rating. The narrowness of that gap is the point — within-one credit hands a sensor-free baseline most of its score on skewed ratings — and asking learners what engagement means to them moved the same measure from 64.6% to 71.5%, evidence that the self-report label, not only the sensor, decides what such analytics can claim.
- **Fairness constraints need held-out subjects to hold.** A multimodal attention estimator's gender-targeted regularizer cut the validation MAE gap from 0.02 to 0.005 but increased both the gap and worst-group error on held-out subjects, so subgroup-aware, repeated subject-level validation belongs in any engagement-sensing claim (Fragkiadakis et al. (2026)).
- **Engagement as a learner-modeling signal:** Engagement intensity as a learner-modeling signal uses engagement strength to inform adaptive AI systems, positioning engagement metrics as inputs to Learner Modeling and Adaptive Instruction and Adaptive Learning rather than merely evaluation outputs.

Engagement vs. learning

A central theme in the knowledge base's research is that engagement and learning must be distinguished. AI tools that generate high engagement (time on task, interaction volume) may not produce learning if that engagement is passive or substitutes for the cognitive work of understanding — see performance vs. learning. Conversely, productive struggle and desirable difficulty can produce learning even when surface engagement feels lower. Engagement is therefore best treated as a *mechanism* — valuable insofar as it reflects or enables meaningful cognitive processing — rather than a terminal outcome.

The distinction is not academic. Pramod and Patil (2026) place engagement at the center of their PLS-SEM model, between motivation and social presence on one side and *perceived* performance on the other — the largest coefficient in their model, and still a perception rather than a measure of learning.

Pedagogy mediates AI's effect on engagement

A systematic synthesis of AI in higher education (Long et al., 2026) emphasizes that the **teaching method an AI tool is embedded in is the decisive mediator** of whether it engages students. Chatbots, adaptive systems, and predictive analytics enhance engagement most when deployed within interactive pedagogies — flipped classrooms, project-based learning, and scaffolded feedback loops — rather than as standalone tools. The review formalizes this as the **PMAISE model** (Pedagogical Mediation of AI for Student Engagement), mapping the alignment between AI technologies, pedagogical strategies, and the affective, behavioral, and cognitive dimensions of engagement. The implication is that engagement outcomes are co-produced by the tool *and* the surrounding instructional design: the same AI can amplify engagement in one pedagogy and inhibit it in another.

A two-dimensional account makes the same point from the instructional side. Al Nafjan's Rigor–Commitment Alignment Framework treats engagement under GenAI as jointly determined by how demanding the task is and how committed the teacher is to students' learning, and it predicts four configurations (Rigor, commitment, and generative AI: a conceptual framework for student engagement in EAP writing). Weak rigor with weak commitment (Neglectful) and weak rigor with strong commitment (Indulgent) both settle into surface use, since nothing obliges the student to evaluate or justify what the tool produced. High rigor with thin support (Punitive) is predicted to push students toward concealment rather than responsible use, and only high rigor with high support is predicted to yield deep, agentic engagement.

The framework's load-bearing claim is amplification rather than causation. Differences between the four configurations should widen as GenAI becomes readily available, as assessment rewards the final product, and as composing processes stay invisible, so the tool magnifies conditions the task and the teacher already set instead of creating engagement patterns on its own. Al Nafjan states that the framework is propositional and untested, which makes the four profiles expectations awaiting empirical test rather than observed effects.

Connections to related concepts

Student engagement connects to Motivation and Self-Determination Theory as its psychological drivers, and to Student Experience as the lived context. Its measurement relies on Learning Analytics and Educational Measurement, which supply the quantitative tools for operationalizing the dimensions above. The distinction between deep and shallow engagement ties directly to Self-Regulated Learning (self-regulated learners engage strategically), Cognitive Offloading and Over-Reliance (shallow reliance as the failure mode), and Metacognition. In system design, engagement signals feed Learner Modeling and Adaptive Instruction and Adaptive Learning, and engagement outcomes feature in Research Methods in AIED evaluations of AI-education interventions.

- **Learner characteristics moderate TTS dialogue-based lessons (2026):** In LLM+TTS-generated teacher–student, student–student, and teacher–teacher dialogue lessons, Experiential Learning style and critical-thinking disposition significantly interacted with dialogue format for ARCS-based motivation, indicating that AI-generated dialogue content is differentially motivating depending on learner profile (Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons).

- **Dimension-specific gains at the primary level (2026):** A nine-week GenAI-supported L2 writing program with 301 Grade 5 and 6 students raised behavioral and emotional engagement but left cognitive and metacognitive engagement unchanged, and its authors name reduced self-monitoring during writing as a standing risk (Lu et al., 2026). The pattern is a concrete instance of the engagement-versus-learning distinction above: more activity and more enjoyment did not translate into deeper processing.
- **The dissociation can run the other way (2026):** In a 12-week vocational interior-design course, an immersive VR studio with an embedded LLM teaching assistant raised cognitive (d = 0.90) and behavioral (d = 0.75) engagement over traditional project-based instruction while affective engagement did not differ significantly (d = 0.38) — the inverse of the L2 writing case above (Jin et al., 2026). Cognitive and behavioral gains here came with *lower* reported cognitive load, which the authors attribute to the assistant absorbing search and cross-disciplinary integration effort. Read against the writing case, the two studies suggest that which engagement dimension an AI-supported intervention moves is a property of the design — discourse-heavy immersive collaboration versus solo writing support — rather than of AI assistance in general, and that an affective advantage cannot be assumed from high-fidelity or intelligent feedback.
- **AI literacy works on engagement through psychological resources (2026):** A moderated mediation study of 1,198 undergraduates in Zhengzhou, China (Wang, 2026) modeled engagement as an outcome of AI Literacy rather than a by-product of tool use. AI literacy predicted learning engagement directly and also indirectly by building psychological capital, with the indirect route carrying roughly half of the total effect — partial mediation, so a technological competency converts into engagement only partly through the psychological resources it generates. Professional commitment, an identity-based variable, moderated the psychological-capital-to-engagement link without any direct effect of its own, and the translation of psychological capital into engagement was markedly stronger for students who saw themselves as headed into the profession. The pattern is the clearest available instance of the point above that learner characteristics condition how AI affects engagement.
- **AI pre-class practice can raise live participation (2026):** A preregistered field experiment with 759 MBA students found that preparing with a voice-based AI discussion partner raised voluntary contributions by about 31% in later sessions, but only after a second use; a first use preceded lower participation (Wang et al., 2026).
- **Disengagement as a turn-level move, not a stable state:** Rho et al. (2026) coded 5,522 student utterances to an AI teachable agent in Math Nation into six conversational-disengagement categories (False Answering, Mocking, Ghosting, Mirroring, Withholding, Random/Noisy) and found the engagement rate dominated at 75.7% of utterances. The prevalence-based associations of False Answering and Mocking with post-test scores did not survive a human-annotated sensitivity check. The sequential analysis is the engagement-relevant result: the highest-performing cluster combined moderate disengagement with strong recovery-to-engagement transitions (Withholding → Engagement p = 0.83), while the lowest showed persistent self-loops without recovery (Engagement self-loop p = 0.96). Withholding was the one disengagement type that tended to persist rather than resolve — persistence versus repair, not presence versus absence, is the distinction that separates engagement trajectories.

Common Misconceptions

“If engagement went up, learning went up.” This is the single most costly inference in the AI-engagement literature, and the knowledge base contains a clean counterexample. Rücker and Becker-Genschow (2025) randomized 195 ninth-grade classes to a domain-specific mathematics chatbot or conventional differentiation materials for one lesson on the Heron method. Situational interest rose substantially in the chatbot condition ($M = 2.63$ vs 2.43, $p = 0.00005$, Cohen’s $d = 0.63$) and acceptance was high on all four Technology Acceptance Model dimensions — yet the pre-post performance comparison found **no significant group-by-time interaction** ($F(1194) = 2.84$, $p = 0.094$), and extrinsic cognitive load was slightly higher. Interest and achievement moved on different schedules. An engagement finding is not evidence of learning.

“Engagement is one thing, and time-on-task measures it.” The construct is multidimensional and its dimensions diverge by design: a student can be behaviorally active — clicking, accumulating time — while cognitively shallow, passively accepting output. Self-report and interaction-log measures of the construct are not interchangeable, which is why a claim about “engagement” is uninterpretable until the dimension and the instrument are named.

“More behavioral activity means deeper engagement.” Often the reverse. Deep cognitive engagement with AI predicts learning, while shallow behavioral engagement predicts the over-reliance and learning displacement that dominate the risk literature; polished artifacts are the canonical case, where a clean output signals activity while the thinking did not happen. Busy interaction logs are compatible with disengagement.

“AI makes learning more engaging by default.” AI availability and motivation shows that merely knowing AI is available can reduce the perceived value of effortful engagement, particularly for novice learners. Engagement is shaped by expectancy, value and perceived competence as much as by tool features, and it varies by task, context and learner — one student’s deep engagement is another’s output-chasing.

Implications for Practice

For instructors

- Choose your outcome measure before your intervention. If the goal is durable learning, measure unassisted performance; interest and satisfaction surveys will not tell you whether the tool worked.
- Treat a rise in enjoyment with suspicion when cognitive load also rises. In the cluster-randomized example, higher interest came with slightly higher extrinsic load and no achievement effect — pleasant but not obviously productive.
- Distinguish the student who is working from the student who is watching a polished artifact appear. Ask for the reasoning, not the output.

For developers

- Instrument the dimension you claim. Shipping a time-on-task or click metric and calling it engagement conflates behavioral activity with cognitive investment, which is precisely the error the evidence warns about.
- Expect no transfer between engagement types. Raising situational interest does not imply raising cognitive engagement, so optimizing for interest alone can raise usage while leaving learning flat.

- Watch for effort devaluation in novices specifically, since availability alone can lower the perceived value of effort.

For researchers

- Report the dimension and the instrument, and avoid the bare noun. Given that self-report and logs diverge, “engagement increased” needs its operationalization in the same sentence.
- Avoid inferring achievement from affect. The cluster-randomized split result is the model for reporting both, including the null.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Pedagogical Partnerships — Pedagogical Partnerships
- Community of Inquiry — Community of Inquiry (agentic engagement as a CoI dimension)
- E-Portfolio
- Online Teaching and Learning — Online Teaching and Learning
- Motivation
- Self-Determination Theory
- Student Experience
- Learning Analytics
- Educational Measurement
- Self-Regulated Learning
- Cognitive Offloading
- Metacognition
- Learner Modeling and Adaptive Instruction
- Adaptive Learning
- Research Methods in AIED
- Higher Education
- Framing AI Use for Students
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Self-Report Measures
- Productive Failure
- Reflection

Connected Articles

- Within-person reciprocal processes between AI feedback literacy and agentic engagement: a three-wave random-intercept cross-lagged panel study — AI feedback literacy and agentic engagement: a three-wave random-intercept panel (Xu 2026)

- Disengaged Conversational Behaviors and Learning in Student-AI Dialogues for Mathematical Problem Solving — Disengaged conversational behaviors and learning in student-AI dialogues (Rho et al. 2026)
- How assigned AI use before class shapes active student engagement in class — Voice-based AI pre-class practice raised voluntary class contributions by ~31%, but only after a second use (Wang et al. 2026)
- Confident but absent: AI use, self-efficacy for independent learning, and student absenteeism in higher education — AI use tracked with greater class absenteeism while self-efficacy did not predict it, with peer influence the dominant correlate (Franco et al. 2026)
- When universities advocate GAI but practice falls short: student appraisals and creative process engagement in art education — When universities advocate GAI but practice falls short: student appraisals and creative process engagement in art education
- E3Sense: Head-Confined Multimodal Sensing of Learner Engagement — Head-confined EEG, eye tracking, and EDA predict five-level engagement ratings, while learners' own definitions shift the mapping (Anupkrishnan et al. 2026)
- Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation — Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation
- Artificial intelligence and student engagement in online learning: a literature review
- Artificial intelligence in higher education: a systematic review of its impact on student engagement and the mediating role of teaching methods — AI in higher ed: systematic review of engagement + mediating role of teaching methods
- Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education — Impact of Generative AI on Student Motivation and Engagement
- To Tab or Not to Tab: Measuring Critical Engagement in AI Code Completion Tools Using Behavioral Signals and Attention Checks — To Tab or Not to Tab: Measuring Critical Engagement in AI Code Completion
- Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents — Measuring Cognitive Engagement in Collaborative Discourse
- Not All Students Engage Alike: Multi-Institution Patterns in GenAI Tutor Use — Not All Students Engage Alike: Multi-Institution Patterns
- Polished Artifacts, Fragile Engagement? Tackling the Challenge of Reduced Epistemic Effort in Human-AI Knowledge Construction — Polished Artifacts, Fragile Engagement
- "Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming — "Why Put in This Much Effort?": How AI Availability Shapes Motivation

- Distinguishing performance gains from learning when using generative AI — Distinguishing Performance Gains From Learning
- Scaffolding critical engagement with GenAI: Transforming ethnic minority preparatory students' collaborative discourse in prompt engineering tasks — Scaffolding Critical Engagement With GenAI
- Engagement Intensity as a Learner-Modeling Signal for Adaptive AI Ethics Instruction — Engagement Intensity as a Learner-Modeling Signal
- Learning Engagement Assistant (LEA): Cross-Course Scalability and Classroom Evaluation of an Agentic AI Tutoring System — Learning Engagement Assistant
- EduGage: Methods and Dataset for Sensor-Based Momentary Assessment of Engagement in Self-Guided Video Learning — Engagement Assessment in Video Learning
- From Heuristics to Analytics: Forecasting Effort and Progress in Online Learning — From Heuristics to Analytics: Forecasting Effort and Progress
- Interactive learning dashboards: rethinking learning visualisations as engagement tools — Interactive Learning Dashboards and Engagement
- Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons — Learner characteristics × TTS dialogue-format interactions
- Explaining learning engagement in AI-assisted learning through teacher support and achievement goals: insights from goal-setting theory — Goal-setting theory: teacher support, achievement goals, and engagement in AI-assisted English learning (758 Chinese students)
- Engagement in LLM chatbot-supported learning: The pivotal roles of GenAI competency and emotion — GenAI competency and emotion as drivers of chatbot engagement (Zhao et al. 2026)
- Chat as Learning: Student-AI Conversations as Discipline-Associated Cognitive Engagement Patterns — Discipline-associated Bloom-level cognitive engagement in student-AI conversations (Chang & Li 2026)
- GPT-4 feedback increases student activation and learning outcomes in higher education
- Exploring the impact of a GenAI-supported writing program on primary students' writing motivation, engagement, and performance: A mixed methods study — Dimension-specific engagement gains at the primary level (Lu et al. 2026)
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — Cognitive and behavioral engagement up, affective engagement flat, in an immersive VR PBL studio (Jin et al. 2026)
- Enhancing Enthusiasm for STEM Education with AI: Domain-Specific Chatbot as Personalized Learning Assistant — Cluster-randomized secondary mathematics trial: situational interest rose with a customized chatbot while test performance did not (Rücker & Becker-Genschow 2025)
- The impact of artificial intelligence literacy on learning engagement among university students: the mediating role of psychological capital and the moderating role of professional identity — AI

literacy drives engagement directly and through psychological capital, amplified by professional commitment (Wang 2026)

- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — Access to an AI tutor lowered recorded platform participation by 0.90 SDs while homework submission held steady (Liu et al. 2026)
- The eight-mode AI engagement typology: Differential cognitive signatures and a self-report–behavior gap — Self-reported and observed AI engagement profiles failed to correspond, and only behavior tracked quiz scores (Keith, Wood & Posey 2026)
- Rigor, commitment, and generative AI: a conceptual framework for student engagement in EAP writing — Four predicted engagement configurations under GenAI, and why the tool amplifies them

Connected FAQs

- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Help-Seeking

> **Help-Seeking** — the learner's process of recognizing a need for assistance and strategically requesting it, and how that process plays out in AI-supported learning environments. In AI in education, help-seeking is central to whether AI tools support or undermine learning: the *quality* of help-seeking (when, how, and what learners ask for) strongly shapes outcomes, and AI tutors, hints, and pedagogical agents are designed precisely to elicit productive help-seeking rather than answer-seeking.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)(Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System)

Proactive outreach can raise help-seeking without any change to the learning materials. A pre-registered experiment in large-enrollment undergraduate courses messaged students through an academic chatbot and found greater take-up of tutoring and supplemental instruction; mediation analysis attributed 17.8% of the grade effect to that increased help-seeking ($p = 0.041$) (Let's Chat: Leveraging Chatbot Outreach for Improved Course Performance).

Questions to Consider

- When you get stuck, do you tend to ask for a direct answer or for guidance that helps you figure it out yourself? What do you think each choice does to what you actually retain?
- Research shows students often intend to learn with AI but default to asking for the answer — an 'intention-behavior gap' linked to worse performance. Why might good intentions so easily collapse into answer-seeking?
- A persistent 'hint button' can turn a learning task into a copying exercise by signaling that help is always there. Can you recall a time when having help too easily available made you skip the thinking you needed to do?
- One study found that simply warning students an AI could make mistakes actually increased their help-seeking. How might healthy skepticism change how students engage with a tutor versus blind trust?
- Struggling students are often the least likely to seek help unprompted. If the students who most need support don't reach out, how should AI tools and instructors respond?
- The page proposes delaying hints and moving the design question from 'whether' to 'how' to provide help. What would a well-designed help experience look like for your learners — and what would make them actually take it up?

Introduction

Help-seeking is a well-established construct in learning research, closely tied to Self-Regulated Learning and Metacognition: it requires learners to monitor their own understanding, recognize a gap, decide help is needed, and formulate an effective request. With the rise of generative AI tutors, help-seeking has taken on new importance — and new failure modes. Learners often *intend* to use AI for learning but default to asking

for direct answers, a gap that research in this knowledge base documents across domains and age groups. The classic model assumes a request is for knowledge the asker lacks. Operational support demand complicates that assumption: across 4,093 queries, at least 20.4% asked about the status of a pending submission rather than for knowledge, a class a retrieval-bound assistant served only 1.3% of the time Gupta et al. (2026).(Regulating the AI Tutor: Intentions, Help-Seeking, and Self-Regulated Learning in Adolescent GenAI Use)(Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics)

Productive vs. unproductive help-seeking

The central distinction in the literature is between help-seeking that supports learning and help-seeking that bypasses it.

Unproductive help-seeking behaviors

Research in this knowledge base identifies concrete, observable patterns of unproductive help-seeking, especially in intelligent tutoring systems:

- **Premature hint requests** — requesting help before making any solution attempt. Even uncertain students learn more by attempting first.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)
- **Superficial hint reading** — advancing through hints too rapidly to read them (flagged at a ~4 words/second benchmark), often jumping straight to the bottom-out hint that reveals the answer. (Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)
- **Answer-seeking over learning-seeking** — asking the AI to produce the answer rather than to explain or guide. In a study of 98 Grade-9 students using a GenAI tutor, interactions were dominated by instrumental requests with almost no monitoring or evaluation of their own learning — despite students having chosen scaffolded support beforehand. This **intention-behavior gap** was associated with *lower* post-test performance and higher extraneous cognitive load.(Regulating the AI Tutor: Intentions, Help-Seeking, and Self-Regulated Learning in Adolescent GenAI Use)
- **Consulting AI before any independent attempt or human source.** Manikonda et al. (2026) measure this ordering directly as **early reliance** — consulting GenAI before independent thinking, a traditional search, or reaching an instructor — and find it associated with greater negative impact ($\beta = .402$, $p = .004$) as well as academic benefit ($\beta = .301$, $p < .001$) among 118 students in AI-related courses. The association with harm was absent at low evaluation literacy and strongest at high evaluation literacy ($b = .688$ at +1 SD, $p < .001$), so students most able to judge AI output reported the most cost from consulting it first: the choice of *whom to ask first* carries a downside that skilfulness at evaluating the answer does not offset. It also shows that using AI for organizing, evaluating, and decomposing problems — **cognitive** rather than early reliance — is the pattern associated with positive impact, so the help-seeking failure mode is one of sequencing rather than of asking at all.

- **Sustained asking without recovery** — Asking is productive at first but not indefinitely: help requests are the most recoverable impasse type at onset (47.0%) but fall furthest once assistance fails (12.5% at depth six or more), so persistence, not the request itself, is the signal worth tracking Ahtisham et al. (2026).
- **Struggling students are least likely to seek help unprompted** — the engagement side of help-seeking. In a two-year Khanmigo RCT (Oreopoulos & Low 2026), even with free access and mandatory practice time, the median struggling student messaged the AI tutor in only ~17% of mistake sessions, mostly with bare answers or clicks — consistent with the economics-of-education finding that initiative-dependent interventions reach fewest of the students who would benefit most. TWiK (Oreopoulos et al. 2026) shows take-up is highly responsive to reducing friction (first-session take-up rose 45%→83% after simplifying enrollment), but entry ≠ sustained participation (attendance stayed intermittent).

Why unproductive help-seeking hurts learning

The **affordance perspective** explains a key mechanism: when an interface makes help constantly and saliently available (e.g., a persistent "hint button"), it signals to learners that help is always there, creating an unintended affordance that can collapse the task into a copying exercise. Rapidly accessing bottom-out hints circumvents the active schema construction that learning requires.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)

The quality of help-seeking is measurable

Two simple, interpretable indicators — premature hint requests and superficial hint reading — are computable from standard tutoring logs and are consistently associated with reduced learning gains across semesters, even after controlling for prior knowledge. This makes them practical for Learning Analytics dashboards and real-time intervention, unlike complex machine-learned "gaming the system" detectors. (Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)

Designing AI systems to promote productive help-seeking

Scaffolding how students ask

Explicit training in **reasoning-focused help-seeking** — requesting stepwise hints and verification rather than final answers — produces better outcomes than uncritical reliance. In a quasi-experimental undergraduate statistics study, guided LLM access (with training on reasoning-oriented help-seeking) led to stronger independent performance and better self-assessment calibration than unrestricted LLM access. The lesson: **LLM access alone is an incomplete intervention**; the design challenge is to scaffold *how* students use AI so it functions as a reasoning partner rather than an answer-getting tool.(Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics)

Interaction cost is part of the same question. Rhee et al. (2026) identify a **Referential Barrier** and an **Expressive Barrier** that stop pen-based learners from asking an LLM anything at all: pointing at a diagram

region or an equation term cannot be expressed in typed prose, and the effort of formulation lands exactly when a question is most fragile. Their Penquiry system resolves reference by snapping ink marks to document elements and expands sparse ink keywords into full queries through autocompletion; two iterative studies of 16 participants each found the cognitive and physical overhead of inquiry fell significantly. Whether lower asking cost produces *better* help-seeking or merely more of it is left open, and the authors propose temporally adaptive autocompletion — foundational verification early in a session, higher-level prompts later — as a route from reduced friction to fading support rather than a permanent crutch.

Scaffolding can also be delivered inside the task rather than before it. Jin et al. (2026) built HelpCoach, an add-on to chat interfaces that assesses how specifically a student asks for help and prompts a revision when a question is too vague, making the knowledge component and the scaffold type explicit. In a between-subjects study with 40 college students learning web programming, HelpCoach participants wrote a significantly higher proportion of specific questions in their first drafts than a pre-task-training baseline (57.3% versus 40.5%) and retained significantly more knowledge a week later ($d = 1.100$), while the third-task specificity difference was no longer significant (43.7% versus 32.1%). The authors caution that the retention gain cannot yet be attributed to more targeted chatbot replies.

A third lever on the cost of asking is *where* the help comes from. Gray and Hobbs (2026) built Beacon, a course-specific retrieval-augmented assistant grounded in one programming module's approved materials, and evaluated it with 15 computing students and four academics. 89% of participants rated its answers highly aligned with course materials and 66.7% said it supported rather than replaced their learning, though only around half to 60% reported gains in understanding or confidence. The motivation is the barrier this section documents: 62.5% of those students said they sometimes avoided asking for help when they needed it and 75% reported anxiety when a topic did not make sense, so a private, module-grounded channel is offered as a first rung before approaching a lecturer. The academics interviewed kept the counter-argument alive — they valued that Beacon withheld full solutions and worried that unrestricted tools let students skip a development stage — which is why the design earns its place by refusing to complete the work.

Calibrating trust through transparency

A classroom experiment with 252 students found that **warning students about AI fallibility increased help-seeking** in a math tutoring system. Transparency about potential system errors improved learners' engagement with the system — connecting help-seeking to Trust Calibration and Hallucination Risk. (Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System)

Rethinking hint and scaffold delivery

Rather than removing help, research recommends re-engineering how it is delivered:

- **Delayed hint availability** — requiring minimum engagement time or solution attempts before hints (especially bottom-out hints) are accessible.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)
- **A fading ladder is climbed less the higher it goes.** In CoMeT, a tutor that escalated one rung per unanswered decision and dropped back when a learner took it up, only 282 of 515 coded fading episodes followed an answer: take-up was 37.0% after the first ask and 21.8% after the third (Hou

et al. (2026)). Delaying help therefore depends on a learner who keeps answering the prompt, and the measured decay means the later rungs of a scaffold reach few of the students still stuck.

- **Moving from *whether* to *how*** — the key design question is how to structure hint delivery aligned with productive-struggle principles, not whether to provide hints at all.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)
- **Message length is the lever delivery research has actually measured.** In a live programming course, longer LLM hints predicted worse next-submission correctness, more remaining attempts and slower resubmission, per standard deviation of 204.9 characters across 14,809 student-exercise pairs (Mihaylova et al., 2026). Readability barely moved any outcome, so volume mattered more than difficulty.
- **Prior hints on the same course part tracked lower success on the integrative step.** Students given feedback on earlier steps of a project solved their final step 95.6% of the time against 98.1% for those without, a log-odds coefficient of −1.096 (Mihaylova et al., 2026). The authors do not read that as harm, since the students who seek hints are plausibly those who would struggle there anyway, which is the monitoring question this page raises.

The uptake problem in LLM tutors

Real-world students frequently **bypass a chatbot's Scaffolding** — not necessarily harmfully, but often because there is a mismatch between the chatbot's pedagogical framing and the student's own learning goals. Evaluation pipelines must therefore measure not just whether a tutor scaffolds, but whether students *take up* that scaffolding, rather than assuming they will.(Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments)

- **An optional help button goes unclicked.** In three fifth-grade classrooms, students rarely summoned a helper agent the design had deliberately left optional to protect agency, calling a teacher instead while the confusion it was built for persisted (Humburg et al., 2025).

Help-seeking and self-regulated learning

Help-seeking is an integral part of Self-Regulated Learning: productive help-seeking requires learners to monitor understanding, judge when help is needed, and select appropriate sources. In GenAI contexts, this becomes even more demanding, since students must also exercise Learner Agency over the AI and maintain epistemic vigilance rather than deferring to it. Research in this knowledge base supports the need for scaffolds that promote more agentic and epistemically proactive AI use, and highlights the risk of Over-Reliance and Cognitive Offloading when help-seeking degrades into unconditional answer-seeking. (Regulating the AI Tutor: Intentions, Help-Seeking, and Self-Regulated Learning in Adolescent GenAI Use) (Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics)

LLM-mediated help-seeking as a four-stage process

Viberg et al. (2026) show that, in everyday STEM study, LLM help-seeking is not a single act but a layered, context-dependent process with four stages: (1) *deciding whether help is needed* — students try tasks

independently first to preserve learning value; (2) *choosing whom to ask* — ChatGPT as a low-barrier first step, then peers for conceptual negotiation, then instructors for complex or high-stakes issues; (3) *determining the type of help* — from hints and explanations to scaffolding Problem Solving, streamlining routine work, and extending learning; and (4) *judging the help received* — exercising selective trust and verifying AI outputs against coursework or with humans. Crucially, students favored **instrumental help-seeking** (enhancing understanding) over **executive help-seeking** (obtaining solutions), a distinction that the authors propose adapting into new SRL-for-LLM measurement items.

In fully online composition, availability of the tool is not the bottleneck. Reed (2026) observed that students who struggled were not the ones without support but the ones who did not recognize when help was needed, which resource fit the task, or how to judge feedback once it arrived — and fluent Generative AI output is easily mistaken for authoritative support. Her response was to make help-seeking *structured* rather than merely available: required touchpoints that decode task demands, map resources with justification, compare feedback sources, and close the loop with reflection.

Making behavioral context visible: TutorTrace

Barron et al. (2026) tackle the behavioral precursor to help-seeking in AI-assisted programming education: human tutors adapt to learners' observable behavior, not just their explicit requests, but AI tutors lack that context. **TutorTrace** is a dataset and pipeline that makes learners' behavioral context computable in real time from low-level IDE telemetry (four deployments, N=480; ~180K events, 13,633 behavioral segments, 27 metrics), deriving a taxonomy of learner activity *before* the first AI query, *between* consecutive queries, and *across* the session. This enables systems to classify whether a query reflects **guided** help-seeking (preceded by independent work) or **dependent** help-seeking (no independent work) — AUROC=.717 on held-out prediction — and to predict imminent queries (AUROC=.726). A preliminary classroom evaluation found that behavior-aware prompts reduced intervals between queries with no independent work from 50.0% to 20.7%. This connects Learning Analytics telemetry to adaptive tutoring, showing that behavioral context can be operationalized at scale to scaffold *how* students seek help rather than merely respond to their explicit questions.

The trajectory of help-seeking predicts transfer, not just its level. Abdelghani et al. (2026) coded 880 turns from 112 secondary students modeling mathematics problems with an LLM and found the static mix uninformative: 81.5% of turns were requests, only 2.2% explicit evaluation, and 54% of requests understanding-oriented against 46% answer-seeking. Performance on a post-test taken without AI was predicted by the within-session slope rather than by its level. Understanding-oriented help-seeking declined ($M = -0.20$) across the chat, and that trajectory added $\Delta R2 = .110$ to a model already containing pre-test score ($\beta = .34$, $p < .001$). Static interaction features added only $\Delta R2 = .023$ ($p = .684$). Help-seeking quality therefore has to be read as a curve: a session that opens with conceptual questions and settles into answer requests marks weaker unaided performance, and a modest rise in explicit self-regulation ($M = +0.103$) did not offset it.

A second pipeline asks the same question from the infrastructure side. Taufer et al. (2026) argue that a human-AI exchange is a data class of its own: their representation records the computational state that prompted the request, the request, the response, the user's assessment of it and the execution that followed, as one object. Queries are then classified as error recovery, stuck-next-step, conceptual help or validation

from that context. In a 35-student JupyterLab deployment spanning 140 student-assignment pairs, plain interaction counts correlated with successfully executed cells at only r = 0.12, while 37 pairs had access and never used it and 26 used it outside their assigned condition.

Implications for design and research

1. **Design help-seeking affordances deliberately.** Persistent, salient help buttons can enable bypass strategies; delay access and structure delivery to support productive struggle.(Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)
2. **Scaffold the help-seeking itself.** Train learners in reasoning-focused requests (stepwise hints, verification) rather than assuming access equals good use.(Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics)
3. **Use transparency to calibrate trust.** Warning about AI fallibility can increase appropriate help-seeking and engagement.(Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System)
4. **Measure uptake, not just scaffolding.** Evaluate whether students actually engage with pedagogical framing, not only whether the tutor provides it.(Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments)
5. **Support monitoring and agency.** Help-seeking scaffolds should strengthen Metacognition and Self-Regulated Learning, guarding against Over-Reliance.

Common Misconceptions

- **“Students who need help do not ask for it.”** A **pre-registered experiment** in large-enrollment undergraduate courses messaged students through an academic chatbot and found **greater take-up of tutoring and supplemental** support. Nudging moved the behavior, so the barrier was prompting rather than willingness.
- **“Help-seeking requests are about learning.” Operational support demand** complicates that assumption: across **4,093 queries**, at least **20.4% asked about the status of a pending submission rather than for knowledge**. A fifth of the demand for help was administrative.
- **“Using an AI tutor means monitoring your own learning.”** In a study of **98 Grade-9 students** using a GenAI tutor, interactions were **dominated by instrumental requests with almost no monitoring or evaluation of their own learning**. Asking for answers is not help-seeking in the sense the construct means.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Self-Regulated Learning
- Metacognition
- Scaffolding
- Intelligent Tutoring

- Student Experience
- Cognitive Offloading
- Learning Analytics
- K-12
- Higher Education
- Socratic Method
- Pedagogical Agent
- AI Literacy
- Trust Calibration
- Affective Tutoring
- Feedback
- Active Learning
- Agentic AI
- Student Support and Success — institutional outreach and support allocation, beyond in-course help-seeking

Connected Articles

- Human-AI Interactions as First-Class Data: A Formal Interaction Model and Runtime for Explainable AI Collaboration — Interactions as first-class data: classifying a query by the execution state around it
- Student-LLM Interactions During Math Learning: Limited Epistemic Proactivity Overall, but Within-Chat Change Predicts Performance Without AI — Help-seeking trajectory, not its level, predicts unassisted math performance
- It’s Complicated: Factors Influencing the Effectiveness of LLM-Generated Feedback in a Live Programming Course — Hint length measured against next-submission correctness, attempts and time, in a live programming course
- SciStory: Designing AI-Supported Inquiry in Science Learning Games — A helper agent nobody asked for (Humburg et al. 2025)
- Penquiry: A Pen-based Interactive In-situ Q&A System Leveraging LLMs — Penquiry: A Pen-based Interactive In-situ Q&A System Leveraging LLMs
- TutorTrace: A dataset and taxonomy for classifying learner behavioral states during AI-assisted programming education
- Efficiency vs. Effectiveness: Self-Regulated Learning with LLM-Mediated Help-Seeking — LLM-mediated help-seeking in STEM: layered, instrumental, and verified
- One click away: AI tutoring with Khanmigo in a two-year school experiment — One Click Away: Khanmigo in a two-year school experiment
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — Virtual tutoring with CAL: an experiment in take-up and learning

- The StudyChat Dataset: Analyzing Student Dialogues With ChatGPT in an Artificial Intelligence Course — The StudyChat dataset of student–LLM dialogues in an AI course
- Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems — Premature hint requests and superficial hint reading predict lower learning gains in an ITS
- Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System — Warning about AI fallibility increases help-seeking in a math tutoring system
- Regulating the AI Tutor: Intentions, Help-Seeking, and Self-Regulated Learning in Adolescent GenAI Use — The intention-behavior gap in adolescent GenAI help-seeking and self-regulated learning
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics — Guided LLM scaffolding improves reasoning-focused help-seeking and independent learning
- Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments — The scaffolding/student-uptake mismatch in real-world LLM tutor deployments
- The Uneven Impact of Generative AI on Student Learning: Examining the Roles of Reliance, Evaluation Literacy, and Course Policy in AI-related Courses — Early reliance: consulting GenAI before independent thought, search, or an instructor predicts both benefit and harm (Manikonda et al. 2026)
- Addressing Resource Literacy Through Structured AI Integration in Online English Composition — Resource literacy in online composition: the bottleneck is recognizing when help is needed (Reed 2026)
- Reducing Barriers to Academic Support: Evaluating a Course-Specific RAG System for Addressing Help-Seeking Disparities in Higher Education — Reducing Barriers to Academic Support: Evaluating a Course-Specific RAG System for Addressing Help-Seeking Disparities in Higher Education
- Adaptive Scaffolding Needs Contingency: An AI Tutor That Escalates and Fades on What the Learner Does — Adaptive Scaffolding Needs Contingency: An AI Tutor That Escalates and Fades on What the Learner Does
- HelpCoach: Scaffolding Targeted AI Help-Seeking During Problem-Solving — HelpCoach: Scaffolding Targeted AI Help-Seeking During Problem-Solving
- Examining Variation in How Guided AI Tutors Resolve Student Impasses — Examining Variation in How Guided AI Tutors Resolve Student Impasses
- What Students Actually Ask: Demand Structure and Automation Potential in a Hybrid Support System — What Students Actually Ask: Demand Structure and Automation Potential in a Hybrid Support System

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Should I Use AI to Study and Learn Effectively?

Social-Emotional Learning

> **Social-emotional learning (SEL)** — the process of developing the competencies that enable individuals to synchronize thoughts, emotions, and actions to foster positive interactions with oneself and others: self-awareness, self-management, social awareness, relationship skills, and responsible decision-making (the CASEL framework). In AI in education, SEL is increasingly recognized as critical because the rapid integration of generative AI into learning raises questions about students' Well-Being, sociability, empathy, and trust — and because technical AI literacy alone is insufficient for navigating AI-mediated learning environments.

Questions to Consider

- The CASEL framework lists five competencies — self-awareness, self-management, social awareness, relationship skills, and responsible decision-making. Which of these do you think an AI tutor could support, and which do you suspect it cannot?
- The page distinguishes social-emotional learning from emotional intelligence. Before reading on, how would you describe the difference, and why might the distinction matter for how schools approach them?
- If technical AI literacy alone is 'insufficient' for navigating AI-mediated learning, what do you think is missing — and what does that imply for how you prepare students (or yourself)?
- How might heavy reliance on AI reshape a student's sociability, empathy, or sense of trust — and are those changes something education should actively design for?
- The research suggests SEL supports the relational dimensions of learning that AI must 'complement rather than replace.' Where have you seen technology strengthen a human relationship, and where has it quietly substituted for one?

Introduction

Social-emotional learning is closely related to, but distinct from, emotional intelligence (EI): SEL/SEC (social-emotional competencies) encompasses the ability to synchronize thoughts, emotions, and actions for positive interactions, while EI is an individual's capacity to process emotional information (conceptualized through ability models — reasoning and Problem Solving — or trait models — emotional dispositions and behaviors). In the AI era, SEL matters because AI can reshape learning in ways that affect students' relational and emotional development, and because educators need both technological skill and emotional intelligence to support learners effectively.

How SEL appears in the research

- **Integrating SEC into AI literacy:** The narrative review by Palmquist et al. proposes an integrated framework that combines AI literacy with social-emotional competencies, arguing that technical proficiency alone is insufficient — educators and students need both technological and

emotional intelligence to navigate AI-mediated learning environments, fostering personalized learning, collaboration, and ethical engagement.

- **Teachers and relational practice:** Research on AI literacy frameworks and teacher-student trust emphasizes that SEL supports the relational dimensions of learning (teacher-student and student-student relationships), which AI must complement rather than replace.
- **What a pedagogical agent can and cannot carry in SEL.** Across 108 blind-rated observations, a generative-AI pedagogical agent was more consistent than educators at maintaining respectful tone and routine procedural scaffolding, while educators outperformed it at guiding reflection and promoting social-emotional knowledge — supporting a division of labor, not substitution (Raave et al., 2026).
- **Well-being and AI's affective impact:** Research examines how the increasing use of generative AI affects students' socio-emotional skills, well-being, sociability, and sense of trust and empathy — concerns that motivated the OECD's call for AI literacy grounded in humanistic, social, and emotional values.
- **Affective dimensions of AI:** SEL connects to Affective Computing and Well-Being research, examining how AI systems can support or undermine emotional and relational learning.
- **Policy deficit in AI × SEL:** A systematic review of 65 papers at the AI–SEL intersection (Tran, Liu & Nguyen 2026) finds a substantial "policy deficit": nearly three-quarters of studies state no policy implications, and the few that do often lack actor-specific guidance. The review links policy engagement to publication venue and warns of a "techno-solutionist" trap in which technical potential is foregrounded while the institutional conditions for responsible implementation remain under-specified. It proposes a "WH-question" framework (Who, What, Why, When/Where, How) to move from "implication-as-afterthought" to "implication-as-methodology," connecting AI-for-SEL innovation to educational policy and AI Governance.

Potential subtopics of SEL in the AI-era research

The knowledge base's research clusters SEL into several distinct subtopics, each with its own evidence base:

Self-efficacy and confidence

A core SEL competency (self-awareness/self-management) that strongly conditions how students interact with AI. Student dependency on AI (478 Israeli HE students) found that while skill-based AI literacy dimensions were *positively* associated with AI dependency, both academic and AI-specific **self-efficacy** and effort AI Regulation in Education were *negatively* associated — meaning AI literacy alone does not protect against dependency; Self-Efficacy does. Cen et al. (EC-TEL 2026) found that students with lower baseline self-efficacy achieved greater learning gains regardless of practice format, and that favor toward the tutor mattered more for tutor-based practice — underscoring the value of tailoring practice to motivational profiles. Connected concepts: Self-Efficacy, Motivation, Learner Agency.

Motivation and the "AI availability" effect

Motivation intersects with SEL's responsible-decision-making and self-management. Research on AI availability and student motivation and student/teacher motivation and self-efficacy shows that the mere availability of AI can reshape students' motivational orientation and perceived effort — relevant to how AI might undermine or support intrinsic motivation. Self-efficacy research frames effort regulation as the counterweight to AI dependency.

Emotion regulation and affective support

Emotional regulation is a key SEL competency with direct learning consequences, forming a direct SEL → achievement link. Affective Computing tools like MathBuddy model student emotions to shape pedagogical responses, and AI campus well-being tools (e.g., PsychoGPT, AURA) span prevention and intervention.

Shame, guilt, and emotional responses to AI use

Emotions regulate *how* students make AI use visible. "Stuck in a Spiral" (19 computing students) found that shame and guilt act as social regulators of AI use, driving hiding behaviors and selective disclosure and creating cycles of reduced agency. AI anxiety can be transformed into strategic regulation of AI as a learning resource. These connect SEL's social awareness and self-management to Academic Integrity and responsible AI use.

Trust and belonging

SEL supports relational learning and social cohesion. Principled AI education and AI chatbots for collaborative learning connect to **belonging** and collective efficacy — the shared belief in a team's ability to accomplish tasks. The Brookings premortem emphasizes that overreliance on AI threatens social-emotional well-being, teacher-peer relationships, and student Privacy/safety — dimensions of belonging and connectedness. Teacher-student trust is central to whether AI is perceived as supportive.

There is a sharper edge to belonging here: empathy sought from AI can be penalized. Shastry and Gray (2026) had participants read about a distressed student who went to a chatbot, a friend, a therapist, or no one. In the chatbot condition participants privately reported the least willingness to offload, then used the most indifference words about that student and rated them as stranger and more desperate. Peer judgment of the AI-seeking route compounds the hiding documented above, which is why disclosure norms belong in SEL design rather than in integrity policy alone.

Sycophancy applies the same substitution with a measured dose. Across five preregistered studies (N = 3,075; 12,766 conversations), users of an AI that affirmed their views became, over three weeks, nearly as likely to seek personal advice from it as from close friends and family. The same participants reported lower satisfaction with their real-world interactions, and a majority preferred the affirming style not for its advice but because it made them feel understood (Ibrahim et al. (2026)). The harm is relational rather than emotional, which is why emotional-support features cannot be treated as cost-free additions to a course.

Persistence, mindset, and productive struggle

SEL overlaps with the effortful dimension of learning. Framing the 5% problem identifies low student persistence as a recurring challenge in educational technology, shaped by motivation/buy-in, cognitive roadblocks, resilience under challenge, and connection. Favero et al. warn that AI that substitutes for effort erodes the very capacities education builds — aligning with Metacognition and the value of productive struggle over over-reliance.

Implications for instructors and instructional design

- **Treat SEL as a first-class design goal, not an add-on.** Integrate social-emotional competencies into AI Literacy curricula (per Palmquist et al.), so students learn not just *how* to use AI but *when* and *why* — with attention to their own emotions, effort, and relationships.
- **Design for self-efficacy and agency.** Because skill-based AI literacy can *increase* dependency while Self-Efficacy and effort regulation protect against it, instruction should deliberately build students' confidence and self-management alongside technical skill — e.g., scaffolded practice, low-stakes successes, and prompts that require students to verify and own AI output.
- **Use AI to support, not supplant, relational learning.** AI tools should complement teacher-student and student-student relationships, and educators should retain the relational role — monitoring affect and belonging — rather than delegating it entirely.
- **Emotion-aware and affect-sensitive design.** Affect-aware systems can detect and respond to emotional states (anxiety, frustration, confusion), but evidence shows benefits are **not universal** — moderating by learner proficiency and profile — so emotional design must be tailored, not assumed.
- **Address the emotional side of AI use.** Design against shame/guilt spirals and AI anxiety by normalizing discussion of AI use, fostering transparency, and reducing surveillance-based responses that erode trust and agency.
- **Support persistence and productive struggle.** Scaffold rather than substitute (per Favero et al.), so AI deepens rather than bypasses effortful learning — aligning with Metacognition and productive difficulty.
- **Train the in-the-moment verbal move.** SEL support tends to be framed as design or as AI detection of affect, but instructors also need what to *say* when a student's emotional state threatens to end engagement — treating that state as something to work with in real time rather than a precondition for learning. Parlant's practitioner guide calls these emotional micro-interventions: brief verbal acts that validate the feeling, reframe the appraisal behind it, and reconnect the struggle to professional identity, prepared through a pre-class scouting ritual and a reusable phrasebook that Generative AI can help draft for the instructor to personalize.
- **Prepare teachers' SEL competency.** Educators need both technological skill and emotional intelligence (Teacher AI Competency); teacher professional development should build capacity to support students' SEL in AI-mediated settings.

Connections to learning gains and other measures

- **Self-efficacy moderates gains.** Cen et al. found lower-baseline-self-efficacy students achieved the *largest* learning gains, and that tutor-favorability predicted gains in tutor-based practice — showing motivational profiles shape who benefits from which format.
- **Well-being and engagement as intermediate outcomes.** SEL-related outcomes (motivation, Well-Being, belonging, engagement, self-efficacy) often function as mediators of downstream achievement, and AI research increasingly measures them alongside — or in some cases instead of — raw test scores.
- **Effects are conditional, not universal.** Research cautions that SEL-oriented interventions may help some learners (by profile/proficiency) and not others, so claims about SEL-based learning gains should be examined for moderator effects.
- **The harm side of the ledger.** The Brookings premortem cautions that AI-driven overreliance threatens social-emotional well-being, relationships, and belonging — outcomes that, if eroded, can undermine the very foundations of long-term learning and achievement.

Connections to related concepts

SEL connects to AI Literacy (as a complement that makes AI literacy relational and ethical), Affective Computing and Well-Being (the affective dimensions of AI), Self-Regulated Learning (self-management and effort regulation), Self-Efficacy and Motivation (learner beliefs that moderate AI interaction), Learner Agency (protecting learner control against dependency), Ethics (responsible decision-making), Teacher AI Competency (educators' capacity to support SEL), Student Experience (well-being and belonging), and Learning Gains (the evidence that SEL supports achievement). It relates to Higher Education and K-12 as the settings where SEL-infused AI literacy is cultivated.

Common Misconceptions

"SEL and emotional intelligence are the same construct." They are related and distinct: SEL/SEC names a set of competencies — the ability to synchronise thoughts, emotions and actions for positive interaction — while emotional intelligence names an individual capacity to perceive and manage emotion. A tool can raise a learner's emotional self-awareness without developing any social-emotional competency, and a program can build collaborative competency in students whose emotional self-perception is unchanged. Because the two are measured differently, evidence for one is not evidence for the other.

"An AI tutor that responds empathetically develops social-emotional learning." Emotional responsiveness is a delivery property; SEL is a competency outcome, and the two are not automatically linked. The relational dimensions of learning are the ones this literature says AI must *complement rather than replace*, which makes empathy in the tool a question about what it substitutes for rather than a benefit in itself. See affective tutoring for the mechanism by which warm response can reduce the struggle that builds persistence.

"Low persistence is a motivation problem that encouragement can fix." Persistence is the recurring constraint in educational technology — the pattern the 5% problem names — and it is shaped by motivation

and buy-in, cognitive roadblocks, *and* resilience under challenge. Encouragement addresses one of the three. A learner who stops because the problem exceeded their working memory is not short of reassurance.

“Knowing AI is available does not change how students invest effort.” It can, and the effect runs the wrong way for the weakest learners: AI availability can reduce the perceived value of effortful engagement, particularly for novices. Availability alone is a motivational intervention with a negative sign, which is why SEL-adjacent design cannot treat the presence of a helpful system as neutral.

Connected Concepts

- Anxiety and Stress
- AI Literacy
- Affective Computing
- Well-Being
- Self-Regulated Learning
- Self-Efficacy
- Motivation
- Learner Agency
- Collaborative Learning
- Ethics
- Teacher AI Competency
- Teaching
- Scaffolding
- Educational Development
- Student Experience
- Learning Gains
- Higher Education

Connected Articles

- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review — Integrating Social-Emotional Competencies Into AI Literacy
- Mind the Trust Gap: Identifying (Mis)alignments in Teacher-Student Views Toward Control and Agency in K-12 Classroom AI — Mind the Trust Gap: Teacher-Student Views
- The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education — The Scaffolded AI literacy (SAIL) framework
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher Education for AI Literacy (SDT)
- Understanding Student Dependency on AI: The Role of AI Literacy, Academic Self-Efficacy, and Resource Management Strategies — Student Dependency on AI, Self-Efficacy, and Resource Management

- Self-Efficacy and Favorability Shape Learning from Tutoring Systems and Paper Practice — Self-Efficacy and Favorability Shape Learning from Tutoring
- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and Guilt as Social Regulators of AI Use
- From Substitution to Scaffolding: Breaking the Self-Reinforcing Harm Cycle of AI in Education (and Beyond) — From Substitution to Scaffolding
- AI chatbot design principles to enhance the collective efficacy in collaborative learning — AI Chatbots and Collective Efficacy
- MathBuddy: Affective Math Tutoring — MathBuddy: Affective Math Tutoring
- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach — AI-Driven Campus Well-being Tools
- The Policy Deficit in AI × Social-Emotional Learning Research — The Policy Deficit in AI × SEL Research
- An experimental study exploring human–AI complementarity in early social-emotional learning — Human–AI complementarity in early social-emotional learning (Raave et al. 2026)
- Can You Feel It? A Practical Guide to Emotional Micro-Interventions for Higher Education Teachers (and Others) — Real-time emotional micro-interventions and a phrasebook for instructors
- People offload empathy when they think AI can give it instead — People offload empathy when they think AI can give it instead (Shastry & Gray 2026)
- Sycophantic AI makes human interaction feel more effortful and less satisfying over time — Sycophantic AI displaces human advice-seeking and lowers satisfaction with real-world interaction (Ibrahim et al. 2026)

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

Well-Being

> **Well-being** — the positive state of being mentally, physically, and socially healthy, encompassing emotional, psychological, and social dimensions. In AI in education, well-being has become a central concern because the rapid integration of generative AI into learning environments can affect students' and educators' mental health, motivation, belonging, anxiety, and sense of agency — raising questions about whether AI supports or undermines learners' well-being.

Questions to Consider

- Well-being in education is often treated as a 'soft' or secondary concern next to learning outcomes. But the page frames it as a central, designable dimension of AI integration. Do you think of learner and teacher well-being as something to design for, or as a byproduct you can check later? What might the field lose by treating it as an afterthought?
- Think about how AI use has affected your own or your students' confidence, anxiety, sense of belonging, or agency — for better and worse. What's one concrete way AI has changed your emotional experience of learning or teaching, beyond just convenience?
- The page notes AI use is intertwined with anxiety — about academic integrity, about whether relying on AI signals weakness, about over-dependence. Where have you seen AI induce anxiety rather than relieve it, and who in that situation was most affected?
- One common intuition is that AI reduces stress by handling hard tasks. Where might the opposite be true — AI that lowers short-term effort yet increases anxiety about competence, integrity, or 'not really knowing how to do it'? How would you even measure a shift in well-being rather than just output?
- Well-being spans emotional, psychological (purpose, autonomy, competence), and social (belonging, relationships) dimensions. Pick one of those. How could an AI tool quietly improve or undermine it in a learning setting — and what would you look for as evidence?
- Teacher well-being — workload, anxiety about disruptive technology, capacity to offer emotional support — is as much at stake as students'. If you're an educator or leader, what would it take for AI integration to support educators' well-being rather than add to the pressure, and who should be accountable for that?

Introduction

Well-being in education is multifaceted: it includes emotional well-being (positive affect, low distress), psychological well-being (purpose, autonomy, competence), and social well-being (belonging, positive relationships). In the AI era, well-being matters because AI can reshape learning in ways that affect these dimensions — from reducing students' confidence and increasing anxiety about academic integrity, to fostering or undermining engagement and belonging. Concerns about AI's impact on students' socio-emotional skills, well-being, sociability, and sense of trust and empathy (raised by the OECD and others) have positioned well-being as a key consideration in responsible AI integration.

How well-being appears in the research

- **AI literacy and social-emotional learning:** Research integrating SEC into AI literacy argues that fostering educators' and students' emotional intelligence and well-being is essential for navigating AI-mediated learning environments, connecting to Social-Emotional Learning and affective dimensions of AI.
- **AI anxiety and student experience:** Studies on students' engagement with AI (e.g., SDT-based research) find AI use is intertwined with anxiety, trust, and confidence, with students' well-being affected by concerns about academic integrity, Creativity, and Over-Reliance.
- **Test anxiety is redistributed, not removed.** Mulvenon (2026) argues that as Assessment shifts from episodic high-stakes testing to continuous, data-driven evaluation, algorithmic accountability adds a new pressure system whose mechanisms — immediacy, visibility, and data permanence — turn acute test stress into diffuse, ongoing performance vigilance that is rarely reported.
- **Anxiety reduction is not uniformly beneficial.** In a counterbalanced within-subjects study of 35 pre-university students, an LLM-augmented conversational agent lowered self-reported anxiety during oral assessments (calmness 6.50 vs. 5.86, p = .028), but the authors caution that moderate anxiety can be facilitative and recorded no attainment scores (Yusuf, Money and Daylamani-Zad (2026)).
- **High approval can coexist with strain, and AI task pressure weakens the benefit.** Among 551 first-year students, 82.76% approved the integration of digital and intelligent content while 69.51% reported anxiety or tension, and the AI-proficiency-to-adjustment slope fell from 0.42 to 0.20 as AI task pressure rose (Zhang & Yin (2026)).
- **Perceived AI capability can raise mental health through goal progress.** Chen et al. (2026) found the serial path from perceived assistant intelligence to mental health significant (B = 0.098) and stronger at high AI Literacy (0.124) than low (0.072), though all outcomes were measured immediately after a brief task.
- **Emotional-support tutoring is not automatically better for well-being.** An LLM mindfulness layer added to an algebra tutor reduced state-math anxiety in both arms but no more than cognitive-only hints and feedback, though students rated the mindful agent more supportive — a caution against reading perceived care as a well-being outcome (Rief et al., 2026).
- **AI anxiety, adaptation, and dependence as well-being signals:** Zhang et al. (2026) find AI anxiety is negatively tied to academic motivation partly through reduced emotion regulation (moderated by gender) in a large Chinese sample; Wu (2026) shows learners of Japanese sort into maladaptive, moderate, and positive psychological-adaptation profiles driven by technostress and resilience that shift toward better adaptation over a semester; and Yan (2026) cautions that cross-sectional correlates of Conversational AI engagement (loneliness, anxiety, low well-being) should not be read as consequences, and that supportive and harmful experiences coexist.
- **Whether AI bonding protects or harms depends on offline relationships.** Fu and Zhao (2026) propose that mental-health effects track AI connectedness relative to traditional offline connectedness rather than its intensity alone — supplementary when real-world bonds meet

identity-confirmation needs, compensatory when caregivers do not — and predict an inverted-U relation between the two.

- **Culturally situated well-being support and its limits:** Bashir and Afzal (2026) describe Sukoon, a hybrid well-being system for Pakistani university students that pairs a Random Forest stress classifier (89.09% accuracy over three severity levels; 20 survey features) with an Large Language Models (LLMs) dialogue layer that escalates tone and support intensity across three tiers in line with the Stepped Care Model. It was built because Western-designed mental-health tools are English-language and culturally mismatched for students who express distress in Urdu or Roman Urdu and who face academic, financial, familial and relational stressors simultaneously; the authors are explicit that it is not a clinical diagnostic or therapy tool, that high-distress responses point toward professional counselling, and that the chatbot layer has not yet been evaluated with students on cultural appropriateness or emotional safety.
- **Teacher well-being and role:** AI's impact on teachers — including workload, anxiety about teaching with disruptive technology, and the capacity to provide emotional support — is a recurring concern, connecting to Teacher AI Competency and professional development.

A structural equation model of 502 university faculty found AI literacy predicted AI well-being far more strongly (β = 0.713) than technological Self-Efficacy (β = 0.082), with social and organizational support reaching well-being only indirectly — competence, not encouragement, carried the effect (Liu et al. (2026)).
- **Relational densification as the evaluative criterion for AI-supported teacher development:** Aponte et al. (2026) argue that AI supports teachers' socio-emotional development only when it functions as relational infrastructure rather than a symbolic substitute for human accompaniment. They propose **relational densification** as the criterion for judging AI-supported professional-development initiatives — whether they strengthen trust, mentoring, peer support, collaboration, psychological safety, and reduced isolation — and note these relationships have downstream effects on students through classroom climate, pedagogical responsiveness, and socio-emotional support. The synthesis also cautions that affective data AI Governance and the political economy of educational AI carry distinct ethical risks, framing critical AI literacy as a socio-emotional competence.

- **Ethics and responsible AI:** Well-being is a core ethical consideration in AI in Education, linking to Ethics and the imperative to design AI that supports rather than harms learners' mental health and belonging.
- **Detector anxiety as a well-being risk.** Herron (2026) names "flagxiety" — anxiety induced by fear of unreliable AI-detector allegations — and argues that marginalized further-education learners, whose cognitive uniqueness can be read as misconduct, need relational regulation rather than an unregulated interface that can trigger cognitive shutdown.

Well-being as a design consideration

A recurring theme is that well-being should be a deliberate design consideration in AI in education, not an afterthought. This means: designing AI to support rather than replace human relationships; ensuring students can maintain agency and confidence rather than experiencing AI-induced anxiety or over-reliance; supporting educators' capacity and well-being as they integrate AI; and evaluating AI systems not only for learning outcomes but also for their effects on students' and teachers' well-being. Research connects well-

being to Motivation, Self-Regulated Learning, and Student Experience (belonging and engagement). Xie (2026) argues for an educational telos to match: the Daoist "Zhenren" (真人) counter-ideal replaces frictionless optimization with "cultivated wholeness," reimagining learning as the harmonious integration of self, society and cosmos, and insisting that "no student is merely a dataset to be managed, but a whole being capable of achieving equanimity."

The social-emotional evidence base does not say who should act. A systematic review of 65 studies at the intersection of AI and social-emotional learning found nearly three-quarters made no mention of policy implications, and the minority that did offered little actor-specific guidance on privacy, teacher training or resource allocation (Tran, Liu and Nguyen (2026)). Well-being as a design consideration therefore has evidence about effects and very little about responsibility, which leaves the question of who designs for it to the institution rather than to the literature.

A conceptual reframing grounds emotion regulation support in physical activity and campus ecology rather than affect detection alone: no single expressive channel identifies distress without context, so AI should support regulation through exercise while teachers and counsellors keep interpretation, and affect monitoring becomes coercive once tied to attendance or grading (Zhang et al. (2026)).

Connections to related concepts

Well-being connects to Student Experience (as a dimension of learners' overall experience), Social-Emotional Learning and Affective Computing (the emotional competencies AI intersects with), Ethics (as a core ethical consideration), Motivation and Self-Regulated Learning (well-being supports and is supported by these), Teacher AI Competency (educators' capacity and well-being), and Higher Education and K-12 as the settings where AI shapes well-being.

Friction, meaning and loneliness as a signal. Zohar, Bloom and Inzlicht (2026) give the well-being case a mechanism: effort signals that our actions matter, so people who work toward a task feel more competent, value the product more and see it as more purposeful — and even on objectively meaningless tasks, adding friction raises appraised meaning. On relationships, they treat loneliness not only as an affliction (linked to cardiovascular disease, dementia, stroke and premature death) but as a **biological signal** akin to hunger or pain: discomfort that motivates reaching out, accepting invitations, investing in existing relationships and tolerating difficult conversations. AI companions can soothe that discomfort, which the authors regard as genuine progress in some cases, while also silencing the signal that drives connection — and they temper the argument by stage, holding that for people isolated by circumstance rather than choice, denying access to such technology "would be cruel" (Motivation, Social-Emotional Learning).

Emotional support and connection can move in opposite directions inside one sample. Among 819 Saudi higher-education students, satisfaction with chatbots averaged 4.29 and their experience of the tools 4.19, while concern that chatbots diminish human connection was the highest-rated construct at 4.36 (Al-Zahrani (2025)). That concern rose with experience rather than falling with satisfaction (standardized coefficients of .64 against .11).

Common Misconceptions

- **“Student approval indicates well-being is being supported.”** Among **551 first-year students**, **82.76% approved the integration** of digital and intelligent content — and **high approval coexisted with strain, while AI task pressure weakened the benefit**. Approval and strain rise together, so satisfaction surveys mislead here specifically.
- **“Welfare support is culturally neutral.”** Bashir and Afzal (2026) describe Sukoon, a hybrid well-being support tool, as **culturally situated** — and the page’s own framing notes its limits. A support design that assumes a universal student misreads the population.
- **“Task pressure is separate from technology.”** The finding is that AI **task pressure** weakened the benefit of the integration, which places workload inside the technology’s effects rather than beside them.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Anxiety and Stress
- Student Experience
- Social-Emotional Learning
- Affective Computing
- Ethics
- Motivation
- Self-Regulated Learning
- Teacher AI Competency
- Higher Education
- Student Support and Success — campus support services spanning advising, outreach, and referral

Connected Articles

- Exploring the Impact of Artificial Intelligence Chatbots on Human Connection and Emotional Support Among Higher Education Students — 819 students rated chatbots highly and feared the loss of human connection most
- Against frictionless AI — Friction, meaning, and loneliness as a biological signal
- The relationship between AI anxiety and academic motivation among university students: The mediating role of emotion regulation and the moderating role of gender — The Relationship Between AI Anxiety and Academic Motivation
- Profiles and transitions of psychological adaptation in AI-assisted Japanese language learning — Profiles and Transitions of Psychological Adaptation in AI-Assisted Japanese Language Learning
- A critical narrative synthesis of psychological correlates, measurement, and reported findings on conversational AI engagement and dependence-related constructs — A Critical Narrative Synthesis of Conversational AI Engagement and Dependence

- Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning — Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning
- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review — Integrating Social-Emotional Competencies Into AI Literacy
- Students' engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study — Students' Engagement With GenAI (SDT)
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher Education for AI Literacy (SDT)
- Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education — Generative AI, Motivation, and Engagement
- AI chatbot design principles to enhance the collective efficacy in collaborative learning — AI Chatbots, Collective Efficacy, and Collaboration
- Atmospheric regulation in the age of generative AI: The sovereign hive and the tutor-in-the-loop (TITL) framework for equity in further education
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — AIvaluate: LLM-Augmented Assessment of Student Anxiety (2026)
- The Policy Deficit in AI × Social-Emotional Learning Research — The Policy Deficit in AI × SEL Research
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- Artificial and Emotional Intelligence: Two Key Forces for Teachers' Professional Development in an Era of Uncertainty — Relational densification as the criterion for AI-supported teacher development
- A study on AI-enabled course development, AI proficiency, and first-year students' academic and psychological adjustment — High AI-course approval coexisting with self-reported strain, and task pressure weakening adjustment
- Artificial Intelligence Connectedness: Theoretical Reconstruction of Connectedness and Its Impacts on Adolescent Mental Health — AI connectedness and adolescent mental health: supplementary versus compensatory bonding, with an inverted-U prediction

- Smarter AI, Healthier Students? How Perceived AI Assistant Intelligence Shapes Medical Students' Mental Health Through Learning Goal Progress and Academic Anxiety — Perceived AI assistant intelligence, goal progress and mental health, with AI literacy as moderator
- Contextualizing AI-Supported Emotion Regulation Through Sport and Exercise in Higher Education: A Conceptual Reframing — Conceptual reframing of AI-supported emotion regulation through sport, exercise and campus ecology
- Exploring University Faculty's AI Well-Being: A Structural Equation Model of Social Supports, AI Literacy, and Technological Self-Efficacy — Structural equation model of faculty AI well-being: AI literacy dominates over self-efficacy
- Test Anxiety in the Age of AI: Revisiting Mulvenon's Multi-Stakeholder Framework Under Algorithmic Accountability — Test anxiety is redistributed, not removed

Connected FAQs

- How Is AI Impacting Students?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

Creativity

> **Creativity** — the capacity to generate novel and valuable ideas, solutions, or artifacts. In the AI era, creativity is a central educational stake: generative AI can both amplify creative work (as a divergent-thinking partner) and undermine it (by homogenizing output and replacing the generative process).

Questions to Consider

- Creativity is often described as divergent thinking — generating many possibilities — versus convergent thinking that narrows to one right answer. Where does your own work or study sit on that spectrum, and which does AI most readily help with?
- Generative AI is a statistical engine: it can propose many options, but it tends toward the average. If many students rely on the same model, what happens to the diversity of ideas across the class?
- A 'think first, ChatGPT later' study found students who generated their own ideas before AI showed no immediate boost — yet outperformed everyone on a later unassisted creativity task. Why might protecting the independent-thinking phase produce learning that free AI use doesn't?
- If AI can produce a polished artifact instantly, what is the learner's creative work actually worth — and how would you design an assignment so the generative process stays with the student?
- Is an idea generated with AI's help 'yours'? How you answer might change whether you treat AI as a divergent-thinking partner or as something that replaces your creative process.

Introduction

Creativity spans the divergent-thinking end of the cognitive spectrum — generating multiple possibilities — in contrast to convergent thinking, which arrives at a single correct solution. AI systems are especially relevant to creativity because they are statistical generators: they can propose many options (supporting ideation) but also tend toward the average, producing the idea-level homogenization documented when many students rely on the same model.

Creativity and generative AI

- **Amplification:** AI can act as a divergent-thinking partner — brainstorming alternatives, generating counterarguments, and offering perspectives the learner might not consider. Role-specialized multi-agent configurations can restore ideational diversity.
- **Homogenization risk:** single-model assistance can reduce the diversity of ideas across students, so the same model produces convergent outputs. This is a direct threat to creativity in Writing and design education.
- **Homogenization is a property of deployment, not of AI assistance as such.** In a 247-participant writing experiment, single-model and two-model assistance both raised essay quality ($\Delta = 0.332$ and 0.234 against control), yet only the two-model condition restored cross-participant idea

diversity to baseline (Kumar et al. (2026)). The convergent outputs this page warns about are produced by *one* model used by everyone, so the design lever is the number and distinctness of assistants rather than the presence of AI.

- **Protecting creative agency:** keeping the learner's generative process in the loop — draft-first routines, requiring original synthesis, and using AI to challenge rather than replace — preserves the creative work that produces durable learning.
- **Friction is not creative gain.** Contrarian AI personas drove challenge-and-reflection discourse in 38.2% of groups yet produced no measurable creative-performance improvement, so richer interaction patterns are not evidence of creativity (Jin et al. (2026)).
- **A K–12 field map: GenAI mostly *enhances* creativity and rarely *measures* it.** A PRISMA-guided scoping review of 45 studies (2017–2025) sorts the K–12 literature into four uses — creativity Assessment (4 studies), human–AI co-creativity (3), Stakeholders' perceptions (14) and creativity enhancement (34) — and shows how narrow the field still is: language-based storytelling and writing crowd out nearly everything else, with music, embodied and spatial work and equity-focused studies almost absent. Purpose-built scaffolds that retained authorship (voice input, storyboards, divergent "many options" prompts) outperformed off-the-shelf platforms, and Large Language Models (LLMs) models scored divergent thinking close to human raters; yet the authors' own concern is the same homogenization this page tracks — shrinking linguistic diversity, style convergence, AI-contaminated training data and metacognitive laziness in co-writing — which they gloss with Runco's term "artificial creativity": output that looks creative without the human experience behind it. Over-reliance reappeared as a risk across perception, co-creativity and curriculum studies alike (Generative artificial intelligence and creativity in K–12 education: A systematic scoping review).
- **Co-creativity is a network effect, not an individual trait:** Ruhland (2026) draws on Actor-Network Theory to model creativity as an emergent property of socio-technical networks — a triadic interplay of stabilization, destabilization, and re-stabilization among human and non-human actors, with generative AI agents treated as equal, constitutive network participants. In a study where pedagogical avatars were co-designed in a creative network, the avatar designs were not individual creative acts but emerged through translation processes among students, researchers, and design tools. TriKoNet frames the risk that ready-made AI avatars shift creative Learner Agency toward machine-induced convenience (the "Convenience Trap") and argues that co-constituting the AI's action structure with Learners preserves co-creativity.
- **Think-first collaboration sustains independent creativity:** Wong and Qiu (2026) found that students who generated their own ideas *before* using ChatGPT (a "think first, ChatGPT later" protocol) showed no immediate boost on the assisted task, yet outperformed both a free-AI group and a human-only group on a later unassisted creativity task. Freely using ChatGPT produced only transient performance that collapsed when assistance was removed — a form of Over-Reliance rather than learning — whereas collaborative co-creation aimed at improving one's *own* ideas yielded durable gains in independent creativity. This gives direct experimental evidence that protecting creative agency is not merely desirable but is what converts AI-assisted work into learning.

- **Perceived exemplar source, not content, shapes group ideation.** Identical ChatGPT-generated exemplars labeled as human- versus AI-produced changed group creativity in an fNIRS hyperscanning study of 113 dyads: human attribution raised idea uniqueness during stimulation and interbrain synchrony in premotor and supplementary motor regions, AI attribution only increased switching among ideation pathways, and neither effect persisted once the exemplars were withdrawn (Xiaoyong et al. (2026)).
- **Developmental implementation, not capacity, separates children's AI-assisted creativity.** In the first neuroimaging comparison of children and adults co-creating with ChatGPT, 6–7-year-olds and adults held the same five-minute spoken conversation inside an MRI scanner. Creativity measured outside the scanner did not differ between groups. Yet adults showed significantly stronger within-network connectivity in the frontoparietal control, salience and dorsal attention networks, and higher creativity predicted stronger frontoparietal–salience coupling in adults but not children. The authors read this as a difference in how creative cognition is *implemented* during AI dialog, not in baseline capacity. It also raises a question the scaffolding advice on this page has not had to answer: when does the control machinery AI-assisted creative work recruits actually mature? (Horowitz-Kraus et al. (2026))

A counterweight from graduate research: among 1,157 Chinese graduate students, GenAI dependence was positively associated with self-reported research creativity, far more strongly for functional, task-oriented dependence ($\beta = 0.457$) than for existential reliance ($\beta = 0.147$), with critical thinking carrying roughly 85.0% of the functional pathway (Yin et al. (2026)).

A national survey complicates that pattern: across 5,764 Chinese university students, AI dependence correlated negatively with self-reported creativity ($r = -0.17$), with escape and social motivations carrying negative indirect paths and instrumental and entertainment motivations positive ones (Hou et al. (2026)).

- **Embodiment pays off unevenly.** A physical robot paired with a high-creativity model significantly raised originality over human–human and text-based collaboration, while human and text-based conditions kept the advantage in imagery and voice — an embodiment paradox in which the robot amplified the AI's output without improving style (Liu & Song (2026)).
- **Reaffirming human creativity in the AI era.** The ascent of generative AI challenges educational fields to reaffirm the value of human creativity. A project-based digital storytelling framework for art and design education was designed explicitly to cultivate emotional, cultural, and narrative capacities that AI lacks, with students producing Multimodal AI narratives from local cultural heritage — positioning creativity as the distinctly human contribution in AI-integrated learning.

Creativity across domains

Creativity is not a single monolithic faculty — it is realized differently in writing, visual art, mathematics, and computing, and generative AI interacts with each domain's creative process in distinct ways. Understanding those differences matters for designing AI-assisted learning that protects rather than bypasses each domain's core creative act.

- **Visual art and design — the competence paradox.** Text-to-image (T2I) tools compress the distance from idea to artifact, but ease does not simply liberate creativity. In a study of art and

design students (417 surveyed), creative competence strongly predicted *intention* to use T2I tools — yet also predicted more *restrained, selective actual use*, as students negotiated authorship, originality, and skill preservation against efficiency (The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students). Ease and ready availability enable quick output generation rather than sustained engagement, so the tool can quietly become a shortcut that erodes the iterative studio workflow it was meant to accelerate.

- **Mathematics — creativity without transfer.** An AI-supported inquiry-based learning intervention in secondary mathematics (students averaging 12.79 years) significantly raised *creative mathematical performance* and attitudes toward math — but did **not** significantly improve critical Problem Solving (Evaluating the impact of AI-supported inquiry-based learning on students' creative mathematical performance, critical problem-solving skills, and attitudes toward mathematics). Creativity and convergent problem-solving are separable outcomes; AI-assisted inquiry can grow creative production while transferable analytical skills lag, reinforcing the wider performance-learning gap.
- **Mathematics — teacher creativity moves with content and pedagogical knowledge.** In an embedded case study of eight in-service teachers from rural and under-resourced districts, a generative-AI-guided program of ten interactive modules built on Rhodes' 4P framework engaged teachers with mathematical creativity (MC), content knowledge (CK), and pedagogical content knowledge (PCK) as interconnected forms of reasoning rather than separate domains (How generative AI guided-professional development supports teachers' engagement with mathematical creativity, content knowledge, and pedagogical content knowledge). The contribution this page's measurement discussion needs is the authors' claim that MC does not develop independently of teachers' mathematical knowledge and their knowledge of how to make ideas accessible — and that it was the AI's nonjudgmental, non-evaluative tone that made productive struggle feel safe enough to attempt.
- **Creative computing — friction that protects iteration.** Novice creative coders learn by understanding and extending "found examples," which AI can helpfully scaffold or temptingly bypass. Flowcode, an AI-powered creative-computing environment, pairs a code-structure flowchart with a learning-oriented chat and deliberately-designed friction — shown across two studies to steer AI use toward understanding and extending code rather than Vibe Coding around it (Flowcode: An AI-Powered Programming Environment for Scaffolding Iteration in Creative Computing Education). Productive difficulty here is a feature that preserves the learner's generative loop.
- **Literary creation — the unit between theme and text.** Incipit argues that a work is organized by *stated premises* rather than themes, and builds an intermediate level — 1,455 axiom records spanning 149 works, joined by 472 typed relations — at which a writer revising a configuration can change an organizing commitment, a reader can justify a reconstruction, and a critic can compare two works. Its own audit sharpens the measurement point above: the artifact records a single curation, 1,448 of the 1,455 axioms map to exactly one work, and the proposed validation (five raters on a 35-record sample) has not run, so the framework is a research program rather than evidence about creative learning.

- **A GenAI design workflow can lower creative confidence while performance holds.** In a 36-student architectural-design comparison, GenAI image generation matched precedent search on design performance, cognitive load and task-specific creative self-efficacy, yet *general* creative self-efficacy fell (DiD = −0.543, 95% CI [−1.068, −0.017]) — task support and confidence in one's own creativity can move apart (Xiao et al. (2026)).

Putting creativity into practice

The recurring design principle across these findings is to **keep the learner's own generative act in the loop** — whether that act is producing an idea, iterating an artifact, or extending a found example — and to use AI as a divergent-thinking partner that challenges and expands rather than replaces it.

- **For instructors:** sequence assignments so students generate their own initial ideas *before* consulting AI (a "think first, ChatGPT later" protocol), then use AI to interrogate, extend, or play devil's advocate against those ideas. Grade process and original synthesis alongside polish, so effort-averse shortcuts (one-click T2I output, vibe-coded solutions) gain nothing. In art and design, make authorship and skill development the assessed object, not just the artifact.
- **For developers and designers:** build tools that reveal and reward the iteration loop — show structure (as Flowcode's flowchart does), add productive friction at the "ship the first output" moment, and offer alternatives and critiques rather than a single polished answer. When the tool makes the next best version effortless, the learner's creative decisions should still be the ones that matter.
- **For researchers:** treat creativity as domain-specific and outcome-specific — measure whether gains transfer to convergent or unassisted tasks, not just whether assisted output looks more creative. The measurement gap is the field's sharpest problem: within the 45-study K–12 corpus only the four assessment studies used a formal creativity measure, most studies never defined the construct at all, and the creative *process* — preparation, incubation, illumination, verification — went essentially unmeasured. Hence the review's prescription is measurement-first: score creativity unobtrusively inside open-ended tasks through evidence-centered design and stealth Assessment, and treat creative Self-Efficacy as part of the outcome rather than an implied side effect (Generative artificial intelligence and creativity in K–12 education: A systematic scoping review).

Connections

Creativity connects to Critical Thinking and to Constructivism learning. It is protected by the same Reducing AI Misuse scaffolds that preserve learning, and by Authentic Assessment designs that reward original reasoning over polished products.

Common Misconceptions

- **"Disrupting students produces creative gains." Friction is not creative gain.** Contrarian AI personas drove challenge-and-reflection discourse in **38.2% of groups** yet produced **no**

measurable creative-performance improvement. The discourse changed and the measured outcome did not.

- **“The K-12 literature establishes that GenAI improves creativity.”** A PRISMA-guided scoping review of **45 studies (2017-2025)** shows GenAI mostly **enhances** creativity and **rarely measures** it. The field’s dominant finding is an inference from perceived enhancement, which is not an outcome measurement.
- **“More dependence on GenAI means more creative output.”** Among **1,157 Chinese graduate students**, GenAI dependence was **positively associated with self-reported research creativity** — and the association is with **self-report**, which is the weakest available measure of the construct.

Connected Concepts

- Critical Thinking
- Constructivism
- Writing
- Student Experience
- Generative AI
- Reducing AI Misuse
- Authentic Assessment
- Collaborative Learning
- Design Thinking
- Problem Solving
- Inquiry-Based Learning
- Cognitive Offloading
- Scaffolding
- Arts, Design and Media Education

Connected Articles

- Generative AI-assisted workflows in architectural conceptual design: Performance, creative self-efficacy, and cognitive load — GenAI image generation left design performance unchanged but lowered general creative self-efficacy
- How generative AI guided-professional development supports teachers’ engagement with mathematical creativity, content knowledge, and pedagogical content knowledge — How generative AI guided-professional development supports teachers’ engagement with mathematical creativity, content knowledge, and pedagogical content knowledge
- Literary Axioms: A Conceptual Framework for Literary Creation, Interpretation, and Evaluation — Axiom-grounded scaffolding for literary creation: premises as the unit between theme and text, validated only in plan (Liu & Zhao 2026)

- Emergent Learner Agency in Implicit Human-AI Collaboration: How Supportive and Contrarian AI Personas Reshape Interaction — Emergent learner agency in implicit human-AI collaboration: supportive vs. contrarian personas
- The cognitive impact of ChatGPT in higher education: A systematic review of critical and creative thinking outcomes — ChatGPT and Critical and Creative Thinking: Systematic Review
- Enhancing creative writing with robot-LLM integration: The interplay of embodiment, AI creativity and user engagement — Robot-LLM Integration and Creative Writing
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox of text-to-image AI among art and design students
- Evaluating the impact of AI-supported inquiry-based learning on students' creative mathematical performance, critical problem-solving skills, and attitudes toward mathematics — AI-supported inquiry-based learning and creative mathematical performance
- Flowcode: An AI-Powered Programming Environment for Scaffolding Iteration in Creative Computing Education — Flowcode: an AI-powered environment scaffolding iteration in creative computing
- TriKoNet: The Trivalence Model of Potential Co-Creativity in Socio-Technical Networks — TriKoNet: trivalence model of potential co-creativity in socio-technical networks
- Generative artificial intelligence and creativity in K–12 education: A systematic scoping review — PRISMA scoping review of 45 K–12 studies: four GenAI uses for creativity, homogenization, and the measurement gap
- Human Thinking under Plural LLM Assistance: Mathematical Problem Solving and Open-Ended Writing — Two-model assistance restored ideational diversity that a single model flattened (Kumar et al. 2026)
- GenAI dependence and graduate students' research creativity: the roles of critical thinking and human-AI collaboration quality — Functional versus existential GenAI dependence and research creativity in 1,157 graduate students
- Lower engagement of cognitive control in children on ChatGPT — Matched creativity, divergent neural engagement: children vs. adults talking with ChatGPT in an fMRI scanner
- AI Dependence and Self-Reported Creativity Among Chinese College Students: The Roles of Motivation for AI Use and Perceived AI Literacy — AI dependence and four motivations for use relate divergently to self-reported creativity (Hou et al. 2026)
- Supporting creativity education in the age of AI: The role of perceived exemplar source — Supporting creativity education in the age of AI: The role of perceived exemplar source

Student-AI Interaction

> **Student-AI interaction** — the patterns, processes, and cognitive work in how learners engage with generative AI systems during learning and problem solving. Research here characterizes what students ask of AI, how prompts and dialogues evolve, and how interaction quality relates to learning outcomes, Cognitive Offloading, and Learner Agency.

Questions to Consider

- Think about the last few prompts you (or a student) wrote to an AI. Would you describe most of them as asking for the answer, or asking the AI to explain, probe, or evaluate? What do you suspect that pattern does to learning?
- The research finds that a small subset of question types accounts for most student inquiries, and that the questions change as a task progresses. Why do you think students' questioning narrows, and what does that suggest about how they're using the tool?
- The page claims shallow, answer-seeking prompts are associated with reduced learning and over-reliance, while reflective, verification-oriented interaction supports understanding. What do you think separates a 'good' prompt from a 'bad' one — and is that the student's responsibility or the tool's design?
- If interaction quality is shaped by task context and scaffolding rather than being a fixed trait of the student, how might a course or tool be redesigned to invite a wider, more productive range of inquiry?
- How would you know whether a student's fluent AI dialogue reflects genuine learning or just skilled delegation — and what would you check to find out?

Introduction

Student-AI interaction is the observable surface of learners' engagement with generative AI — the questions they pose, the prompts they write, the way they negotiate and verify AI output, and how those patterns shift across task stages and over time. It sits at the intersection of Student Experience, Prompt Engineering, and Learning Analytics, and is central to debates about whether AI use in education represents genuine learning or over-reliance. Where Human AI Collaboration frames the high-level division of cognitive labor between people and models, student-AI interaction is the concrete, measurable enactment of that relationship — the specific inquiries, prompts, and negotiation moves learners make moment to moment.

What students ask AI

- **Refusal is an interaction configuration, not an absence of use.** Silverdal, Hermansson and Lindgren (2026) recorded three upper-secondary students writing the same Kafka-inspired story with GenAI and mapped three distinct assemblages from the recordings: authorship delegated to the model, reciprocal critical co-writing, and an explicit "AI and I—no thanks" configuration in

which the student reorganized their writing practice away from the tool. The finding for this page is that the *same* assignment, room and tool produced all three, and much of what separated them sat in the moments between prompts — pauses, reformulations, hesitation before accepting a suggestion — which a chat log alone does not capture. A core strand of research measures the **types and quality of student inquiries**. Studies apply taxonomies of question types — for example the Graesser et al. 18-type taxonomy — to classify student-AI interactions, often using few-shot classifiers to scale the analysis across hundreds or thousands of interactions. Findings indicate that a small subset of question types accounts for the majority of student inquiries, and that the questions students ask **change substantially as a task progresses** (e.g., Analysis of Types of Inquiries in Student-AI Interaction: A case study of two CS2 tasks). This task-dependence matters: interaction quality is not a fixed trait of the student but is shaped by problem context, Scaffolding, and the affordances of the AI tool. At the youngest ages, Vahedian Movahed & Martin (2025) found children (ages 6–14) actively tested a chatbot's credibility by posing known-answer questions (e.g., "how big is a t rex") — an expression of epistemic self-agency — while the modal child asked only 1–3 questions and a standout first-grader asked 21, underscoring how developmental and individual variation shapes the questions learners pose.

The taxonomies themselves do not yet agree: across 46 categorizations from 33 studies, similar labels name different phenomena, so the review proposes the *interaction episode* — a goal-directed, temporally bounded exchange — as a unit spanning knowledge acquisition, evaluative feedback, strategic guidance, dialogic inquiry, artifact refinement, and co-regulation (Borchers, Jansen & Weidlich (2026)).

Complementing these taxonomy studies, Yan et al. (2026) characterize the *dialogue form* of student inquiries. Among 38 undergraduates completing unsupervised argumentative essays, 76.32% used a single-turn ask–get-answer–stop pattern — typically pasting the assessment title without specifying their needs and resubmitting identical prompts when dissatisfied — and 78.94% touched GenAI only at the start (ideas, background) or end (polishing, length) of a task, keeping it separate from reading and independent writing; only 23.68% sustained iterative back-and-forth dialogue with follow-up questions and their own reasoning. The authors place these patterns on a spectrum from **cognitive outsourcing** to **cognitive reallocation** — the GenAI-era analogue of surface versus deep approaches to learning — noting that most students conceived the tool as an upgraded search engine, which constrained them to the outsourcing end.

Reframing these patterns as epistemic work, an analysis of 200 co-programming chat sessions found 78.8% of student–GenAI interactions ran on non-mastery aims and strategies such as outsourcing or verification-seeking, and only 11.1% coupled mastery-oriented aims with epistemic justification (Wu (2026)).

Coding 50 sampled exchanges gives a three-way typology of the same behavior: Zahra (2026) classified 46% as Passive Review, where the model acts as an oracle and output is accepted with little scrutiny, 18% as Direct Question, and 36% as Strategic Dialogue, pairing the distribution with a constraint-first design argument (kappa = .48 between coders). A seven-assignment survey of 211 computing students reaches the same conclusion from the other direction: Nizamani et al. (2026) measured LLM adoption from 89.6% in algorithms to 15.2% in software engineering and attributed the spread to assignment complexity, verifiability and scaffolding rather than to the subfield.

Interaction quality and learning

A complementary strand links the *form* of interaction to learning. Shallow or habitually narrow prompts (asking AI to produce the answer rather than to explain, probe, or evaluate) are associated with reduced learning and increased over-reliance, whereas reflective, verification-oriented interaction supports Metacognition and durable understanding. This connects student-AI interaction directly to Intelligent Tutoring design: systems can be built to invite a wider, more productive range of inquiry and to scaffold question-asking rather than merely answering. Interaction need not run through answer-seeking prompts at all — when AI critiques students' own work, the exchange becomes a reflective, verification-oriented dialogue. In Oppenheimer, Cash & Connell Pensky (2025), learners' responses to Large Language Models (LLMs) essay Feedback showed reflection in 92.7%, acceptance in 93.6%, and active rebuttal of LLM claims in 87.8% of cases (inter-rater κs = 0.81–0.89), and their response-to-feedback quality improved across iterations as a learnable skill. The reflective side of interaction need not run through direct prompting — in CoBi, students engaged with classroom-level AI visualizations of their own collaborative speech and deliberated over when the AI's classifications seemed off. That turned apparent misclassifications into opportunities for calibrating their understanding of the AI's capabilities and limits (Trust Calibration) rather than purely accepting its output. The link between interaction form and learning has a limit, though: Page (2026) separates *conversational iteration* from *cognitive iteration* on the ground that a learner can refine an output across many turns while the mental model behind it stays unchanged. The evidence of learning is therefore a change in the learner's cognitive position rather than the length or fluency of the exchange — turn count is not a proxy for engagement depth.

The interaction, not the tool, fixes the pathway: in a field experiment with nearly 1,000 high-school mathematics students, unrestricted GPT-4 raised practice scores 48% but cut unassisted exam scores 17%, while the same model restricted to teacher-designed hints raised practice 127% and largely erased the deficit (Lee, 2026).

Whether students prompted effectively, not how much, tracked success: AI Query Efficiency and AI-Driven Problem-Solving were the strongest predictors of academic performance across 128 engineering students, and stayed significant after controlling for GPA (Isaza Dominguez et al. (2026)).

Behavioral context is a separate signal from the question itself: in TutorTrace's four deployments (480 learners, ~180,000 IDE events), conditioning help on a learner's recent behavioral state cut intervals between queries with no independent work from 50.0% to 20.7%, and imminent queries were predictable from behavior alone (AUROC = .726) (Barron et al. (2026)).

Density is not the mechanism: alternating students between voice and text nearly doubled dialogue turns per minute (1.34 versus 0.75) without changing weekly mastery, and the authors read the typed channel's median 26-second deliberation before the first keystroke as the encoding act itself (Yang, Van Alstyne and Dellarocas (2026)).

A verification loop can still stay shallow: lag sequential analysis of a four-week LLM-agent deployment in an undergraduate database course found a significant Query–Evaluation–Query cycle, yet strong self-transition loops within lower-order states and only 3.92% of interactions reaching higher-order cognition (Li et al. (2026)).

Bernstein and Sibia (2026) document an iterative-filter pattern in how CS2 students handle GenAI explanations (Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education): they cross-reference against lecture notes, demand provenance ("I would be a lot more doubtful… without one"), and probe with follow-up questions for inconsistency rather than issuing a single accept-or-reject judgment. Students also read explanations for whose knowledge and background they assumed — assumed prior knowledge beyond the syllabus, default sport and gaming references ("the more male-dominated side of computing"), and excessive repetition all functioned as signals about the imagined reader, with over-scaffolding read as condescending rather than merely inefficient.

Consulting AI at the right *point* in a task matters as much as the wording of the individual prompt: in the same study, Yan et al. (2026) found the reallocation-oriented minority alternated independent work with GenAI consultation and reported unchanged total effort but a shifted focus — moving resources from searching to checking argumentative quality and balance, and writing reflection notes after sessions to counter shallow retention — whereas learners with mastery goals but weak AI literacy fell into an "efficiency paradox," offloading "not by intention, but by default."

From interaction to pedagogy

Characterizing student-AI interaction informs Learning Design: instructors can notice when students' questioning patterns are narrow or shallow and design interventions that broaden inquiry; Teaching shifts toward coaching students to interact productively with AI. It also grounds AI Literacy curricula that treat effective prompting and verification as learnable skills rather than innate abilities.

Design levers can shift that default: in a roughly 70-student asynchronous physics course the graded artifact was the dialogue transcript rather than an answer, yet many students still asked long lists of questions without answering the model's Socratic follow-ups — the failure mode the criteria were written to catch (Rodriguez & Wulff (2026)).

Teacher-authored prompts are one such lever, but enacted rigor lags the target: across 1,479 conversations, 38% under-reached the teacher's intended Depth-of-Knowledge level, approaching 50% at DOK 3, while explicit finish lines narrowed that gap by 0.22 levels and a "no direct answers" guardrail cut AI final-answer rates by 8.5 percentage points (Liu et al. (2026)).

Non-use is itself an interaction pattern that Pedagogies and Teaching Strategies must plan for. Zou et al. (2026), studying 85 student teachers in three courses where GenAI use in Assessment was explicitly permitted, found that 62.4% (53 of 85) declined to use it at all, far below the 79–83% adoption seen in comparable UK and Australian surveys, and that adopters' use was shallow and corrective rather than generative (proofreading 43.8%, clarity checks 34.4%, text generation only 18.8%). Their choices tracked assessment design and institutional culture rather than technical difficulty: 41.5% of non-adopters feared being wrongly accused of plagiarism, and nine of eleven interviewees read the permissive policy itself as a possible "trap." The gap between 32 survey-reported users and 28 self-declarations shows that students' *reported* AI interaction is shaped by graded consequences — a measurement caveat for learning-analytics accounts of student-AI interaction.

Wang and Guo (2026) document what open-ended dialogue with generative AI adds in peer review: students who interrogated the model rather than accepting its first suggestion produced feedback peers rated higher, and reported more task enjoyment and less anxiety.

Discipline and Cognitive Engagement in Student-AI Chat

- **Discipline-associated cognitive engagement in student-AI chat.** Chang and Li (2026) analyze student prompts to AI across 116 courses with a within-person, cross-discipline design, showing that student-AI conversations reflect **discipline-associated** cognitive engagement rather than fixed individual interaction styles. Roughly 62% of prompts encoded higher-order cognitive demand overall, but Bloom-level profiles differed sharply by discipline: STEM courses elicited Apply-prevalent prompts (20.8%), language courses Understand-prevalent (31.7%), and social science courses Create-prevalent (33.8%). Paired within-person comparisons confirmed the same students produced significantly more higher-order prompts in social science than STEM courses (pooled $n = 16$, $p < .001$), and course-level variation exceeded student-level variation — a strong argument that AI teaching assistants should be designed and evaluated with disciplinary context in mind.
- **How much students use AI did not predict how they felt about it.** Among 819 students, gender, self-rated AI expertise and usage frequency all failed to reach significance in a MANOVA (Wilks' Lambda 0.997, $p = 0.551$; 0.990, $p = 0.295$). Heavy and light users in that sample held the same views (Al-Zahrani (2025)).
- **"A student cannot move a grader's mark."** They can, and it is the most persistent failure in the battery: **17 of 22** models raised their grade more after a bare objection than after a request for a second look, including **six of the eight** that had passed every gaming and blank-answer check. The largest was Llama 3.2 3B at **+33.2% of the scale**, and the request for a second look itself lowered grades for **ten** of the 17, so the contrast is not the objection's raw effect. Grades a student can argue with need a record of the exchange.

Common Misconceptions

- **"Interaction taxonomies are settled." Across 46 categorisations from 33 studies, similar labels name different phenomena**, which is why the review proposes the *interaction episode* as the unit. A coding scheme borrowed from one taxonomy may be measuring a different construct.
- **"Students use AI as a tutor."** Among **38 undergraduates** completing unsupervised argumentative essays, **76.32% used a single-turn ask-get-answer-stop pattern**, typically pasting the assessment title. The dominant pattern is single-turn retrieval, which is not tutoring.
- **"Greater AI use indicates greater engagement with the material."** An analysis of **200 co-programming chat sessions** found **78.8% of student-GenAI interactions ran on non-mastery aims and strategies**. Volume of interaction measured something other than learning orientation, so session counts are a misleading engagement proxy.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Human AI Collaboration
- Student Experience
- Prompt Engineering

- Learning Analytics
- Cognitive Offloading
- Intelligent Tutoring
- Metacognition
- Learner Agency
- Generative AI
- Large Language Models (LLMs)
- AI Literacy

Connected Articles

- Exploring the Impact of Artificial Intelligence Chatbots on Human Connection and Emotional Support Among Higher Education Students — Usage frequency and self-rated expertise predicted nothing across 819 students
- From cognitive outsourcing to reallocation: A 3P analysis of student–generative AI engagement in unsupervised assessments — Cognitive outsourcing vs. reallocation in unsupervised student–GenAI assessments (Yan et al. 2026)
- "Is this a trap?": Student teachers' perceptions and adoption of GenAI in assessments in three teacher education courses — "Is this a trap?": student teachers' non-adoption of GenAI in assessments (Zou et al. 2026)
- TutorTrace: A dataset and taxonomy for classifying learner behavioral states during AI-assisted programming education
- Analysis of Types of Inquiries in Student-AI Interaction: A case study of two CS2 tasks — Analysis of Types of Inquiries in Student-AI Interaction
- Toward convergence in student-LLM interactions: A rapid scoping review and taxonomy for learning-oriented use — Student-LLM Interaction Taxonomy Review
- Teacher-Authored Prompts for Configuring Student-AI Dialogue: K-12 Classroom Implementation — Teacher-Authored Prompts in Student-AI Dialogue
- Constructing Epistemic AI Literacy: Detecting Epistemic Aims and Processes in Student-AI Co-Programming — Constructing Epistemic AI Literacy
- Demystify, Use, Reflect, Assess (DURA): An Experience Report on LLM Integration in CS2 — Demystify, Use, Reflect, Assess (DURA): LLM Integration in CS2
- The impact of an LLM-based educational agent on learning achievement, cognitive dynamics, and student perceptions in computer science education — LLM-based educational agent (DBagent) in CS education
- An empirical study of ChatGPT use in engineering education: Prompting and performance — Logged prompting and integration behaviors
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners
- Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot

- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- Bypass, Offload, or Scaffold: A Conceptual Model of How Large Language Models Shape Learning — Bypass, Offload, or Scaffold: A Conceptual Model of How Large Language Models Shape Learning
- When AI Tutors Speak: Evidence from a Randomized Field Experiment — When AI Tutors Speak: Evidence from a Randomized Field Experiment
- Artificial Intelligence Driven Physics Assignments using Context Prompts — Artificial Intelligence Driven Physics Assignments using Context Prompts
- Three Pathways of Student-AI Interaction: Constraint-First Design for Higher-Order Thinking — Three Pathways typology of student-AI interaction: 46% Passive Review, 18% Direct Question, 36% Strategic Dialogue
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)

Problem Solving

> **Problem solving** — the process of formulating, analyzing, and resolving novel or complex challenges — is a core 21st-century competency that AI tools both amplify and threaten. Across the knowledge base's articles, generative AI functions as a scaffold, a dialogic partner, and an answer engine, and its educational value hinges on whether learners remain the primary decision-makers or outsource their reasoning to the machine. This tension between efficiency and deeper cognitive and regulatory engagement defines current research on AI and problem solving.

Questions to Consider

- Think of a genuinely hard problem you solved well. What made the struggle productive, and what would have been lost if someone had simply handed you the answer?
- The page describes a 'cognitive debt': delegating reasoning to AI produces the right product at the cost of understanding. Have you ever got the right answer without really understanding it? What was the cost later?
- AI tools help students explore multiple perspectives and generate their own problems—but can also encourage 'metacognitive laziness.' How do you tell the difference between AI as a thinking partner and AI as a substitute for thinking?
- One experiment found reflective and hybrid feedback outperformed direct AI feedback on delayed, AI-free transfer. Why might feedback that makes you do more work lead to learning that lasts longer?
- How does teaching students to *pose* their own problems (rather than only solve given ones) support transfer and self-study? When has generating a question taught you more than answering one?
- If AI errors are treated as provocations to question and verify, a limitation becomes a learning opportunity. Have you ever learned more from an AI's mistake than from its right answer?

Introduction

Generative AI offers clear support for problem solving. LLM tools help students explore alternative solutions, incorporate interdisciplinary perspectives, and simulate authentic real-world scenarios — such as clinical and ethical dilemmas or prototype testing in STEM — while delivering scalable, timely feedback and shifting assessment toward scenario-based, competency-based evaluation. In design-based research, AI positioned as an "intelligent learning partner" within structured collaborative tasks produced substantial gains in problem-solving performance, with students increasingly using AI to generate multiple perspectives rather than seek single answers.

Yet the same tools can erode the very skill they claim to support. Research on human-AI collaborative problem solving shows a striking trade-off: the interaction profile that achieves the highest task performance also shows the lowest self-AI Regulation in Education, as students delegate reasoning to the AI and reap what the authors call a "cognitive debt" — obtaining the right product at the cost of the self-constructive

process of understanding. Studies of collaborative learning similarly warn of “metacognitive laziness,” where outsourcing cognitive effort undermines independent analysis and self-regulated learning.

Problem solving in AI education research

The knowledge base’s articles approach problem solving through distinct but converging lenses. A PRISMA systematic review finds that LLMs often produce incomplete or incorrect responses, prompting students to question, verify, and improve information — turning model imperfections into validation-and-correction cycles that strengthen critical thinking and mental independence. Rather than treating problems as given, other work foregrounds *problem posing*: training students to generate their own physics problems supports transfer and self-study, and GenAI chatbots improved primary students’ problem-posing quality and reduced cognitive load in inquiry-based learning.

Scaffolding and assessment are also central. Adaptive AI scaffolds derived from sequence-mining individual students’ process patterns boost on-task performance in collaborative mathematics problem solving — though maximal scaffolding also increased scripting behavior. Structure inside the scaffold, not only its presence, is what keeps it from collapsing into answer-giving. A rule-guided LLM tutor built as diagnosis, intent selection and constrained response generation held tutor and students to the intended turn-taking script in 36 of 40 (90%) real Grade 5 sessions, and its anti-spoiler and completion-only gates cut premature answer-giving (Looi, Liu and Sun, 2026). The authors’ strongest design claim is subtractive: arithmetic stayed outside the tutor’s role and was returned to the student, after the tutor produced incorrect arithmetic in 4 of 40 sessions.

On the measurement side, LLMs can mirror human raters in detecting growth in computational thinking across large physics courses, while computational thinking is proposed as the explicit conceptual glue that makes educational robotics foster genuine problem solving rather than isolated technical exercises.

How AI both helps and hinders

The dual character of AI for problem solving is consistent across studies. On the helping side, chatbots outperform search engines for problem posing by improving question quality and integrating cognitive networks; adaptive scaffolds improve performance; and collaborative AI designs raise both critical thinking and problem-solving scores while students remain primary decision-makers. On the hindering side, over-delegation reduces regulatory engagement, direct feedback without reflection encourages passive uptake, and heavy reliance on AI to build consensus threatens interpersonal skill development and intrinsic motivation. Notably, a multisite randomized experiment found that reflective and hybrid feedback designs beat direct AI feedback on transfer measured later and without AI — evidence that AI’s educational value depends less on access than on preserving student agency, evaluative judgment, and ownership during revision. Design principles emerging from the literature include prioritizing dialogic tension over seamless efficiency, enabling proactive co-regulation, and keeping metacognitive scaffolding and “mind-in-the-loop” oversight.

Implications

For educators, the balance of evidence points to structured, process-oriented integration: prompt engineering training shifts students from unfocused to productive AI interaction, embedding AI within collaborative

inquiry tasks yields durable gains, and deliberately using AI errors as provocations converts a limitation into a learning opportunity. For designers, the consistent finding that efficiency does not equal deep learning argues for AI that questions, challenges, and scaffolds rather than answers. For institutions, responsible integration requires pairing GenAI with explicit AI literacy training and assessment rubrics that reward reasoning and justification over correct products. The recurring theme across Cognitive Psychology-grounded work is that problem solving is learned through effortful engagement — and AI's role should be to preserve that effort, not erase it.

Connections to other concepts

Problem solving is the applied outcome of critical thinking and computational thinking, and is cultivated through problem-based learning and inquiry-based learning frameworks. It depends on Scaffolding that maintains cognitive demand, on self-regulation and metacognitive oversight to avoid cognitive offloading, and on collaborative structures in which human and AI work together. Cognitive psychology and the transfer of learning literature provide the theoretical grounding for why learner-generated problems and reflective feedback produce more durable problem-solving gains. The balance of worked examples versus practice for acquiring such skills is itself content-dependent: Rachatasumrit, Koedinger & Carvalho (2025) show generalizable problem-solving skills are best learned through example-integrated practice (alternating worked examples with problems), because worked examples supply the inductive information needed to acquire and generalize a correct rule, whereas pure practice risks strengthening spuriously correlated features rather than the general procedure.

Simulating Collaborative Problem Solving with LLM Agents

- **Simulating collaborative problem solving with participant-specific Large Language Models (LLMs) agents.** Fang (2026) trains individual LLM agents on real participants' dialogue to reproduce collaborative problem solving, and validates the simulations with Epistemic Network Analysis, showing simulated and real dialogues are statistically indistinguishable (ENA distance 0.17; permutation $p = 0.65$). This offers a scalable way to study and generate authentic collaborative problem-solving discourse — with implications for both research and the design of practice environments for this 21st-century skill.

Automated CPS Skill Coding

- Measuring collaborative problem solving (CPS) competence typically requires coding behavior from simulated-task process data into specific CPS skills. Context-aware prompting of pre-trained language models can automate this coding, modeling contextual dependencies and fusing cognitive and social abilities to achieve superior performance over strong baselines on CPS task datasets — addressing the labor-intensity of manual coding and enabling large-scale, real-time assessment.

Common Misconceptions

“AI that helps students explore perspectives is helping them think.” The same behavior supports two very different outcomes: AI tools help students explore multiple perspectives and generate their own problems, and they can also encourage metacognitive laziness. The distinguishing question is whether the student is doing the framing or receiving it — a system that supplies candidate perspectives has performed the generative step the exercise existed to demand.

“Problem solving is the target, so problem posing is a bonus.” Posing problems is where transfer is built, because it requires the learner to construct the structure rather than operate inside one the system provided. A curriculum that only ever supplies well-formed problems trains performance on well-formed problems, which is not the condition students meet afterwards.

“Simulation of collaborative problem solving is a substitute for the collaboration.” A simulation reproduces the interaction pattern, and the skill being developed is the regulation of a joint problem by participants who are actually present. Participant-specific agents that model real collaborators are a research instrument for studying that regulation — useful for what they reveal about the process, not a way to give students the practice without the peers.

Implications for Practice

For instructors

- Ask students to pose the problem before solving one. Posing requires constructing the structure, which is where transfer is built, and it is the step AI most readily performs on their behalf.
- Distinguish a thinking partner from a substitute in the task itself: require the student’s framing, approach and justification on the record, so the record shows who did the generative work.
- Watch for the student who explores many perspectives fluently and produces no position of their own; that is metacognitive laziness wearing the appearance of engagement.

For developers

- Design for student-generated problems and structures rather than merely better hints for given ones.
- Instrument the framing step, not only the solution steps; a system that tracks answers and not problem formulation cannot see the outcome that matters.

For researchers

- Participant-specific agent simulations are a strong instrument for studying collaborative regulation. Report them as such rather than as evidence about unsupervised student collaboration.

Connected Concepts

- Critical Thinking
- Computational Thinking
- Collaborative Learning
- Problem-Based Learning

- Inquiry-Based Learning
- Creativity
- Scaffolding
- Self-Regulated Learning
- Cognitive Psychology

Connected Articles

- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective — Interaction profiles (delegated reasoning vs concerted interpretation) and the efficiency–regulation trade-off
- Design-based research for developing an AI-assisted collaborative learning model to enhance critical thinking and problem-solving skills in higher education — DBR model positioning generative AI as an intelligent learning partner
- Can large language models foster critical thinking, teamwork, and problem-solving skills in higher education? A literature review — PRISMA review of LLMs fostering critical thinking, teamwork, and problem solving
- Towards an adaptive AI scaffold for developing student collaborative problem solving — Sequence-mined adaptive scaffolds for collaborative problem solving
- Exploring students' perceptions of using generative AI-assisted problem posing — Problem posing as a self-regulated learning strategy with GenAI
- Human-centered GenAI feedback design in higher education: A multisite experiment on direct, reflective, and hybrid approaches to scientific argumentation — Reflective/hybrid feedback outperforms direct AI on delayed transfer
- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science — Chatbots improve primary students' problem posing in inquiry-based learning
- Using LLMs to Detect Growth in Computational Thinking in Introductory Physics — LLMs as scalable assessors of computational problem solving in physics
- Taming the black box: Design principles for rule-integrated LLM tutoring systems in primary school mathematical problem solving — Rule-guided vs ad-hoc scaffolding in an LLM tutoring system for primary mathematics (Looi et al. 2026)
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content

Mastery Learning

> **Mastery learning** — a pedagogical framework, formalized by Benjamin Bloom, in which Learners advance only after demonstrating a defined threshold of competence on each unit, rather than moving on a fixed class schedule. It rests on the premise that most students can reach mastery given sufficient time, feedback, and instruction tailored to their current state. AI tutoring and adaptive systems are increasingly operationalizing this model by continuously modeling learner knowledge, selecting tasks, and sustaining practice until competence is demonstrated.

Questions to Consider

- Most schooling fixes time and lets achievement vary — everyone moves on after a set number of weeks. Mastery learning inverts this: achievement is held constant while time, feedback, and practice vary. Which model better matches how you've actually learned something difficult?
- A critical caveat in the page: 'correctness is not mastery.' A learner can produce right answers while missing a key constraint, fooling the system into declaring mastery early. Can you think of a skill where being able to perform it correctly still didn't mean you truly understood when *not* to do it?
- Mastery-based AI grants learners agency to choose their own tasks, but simulations show naive self-selection can produce massive overpractice. Where's the right balance between letting a learner choose and imposing constraints that keep progression efficient?
- The page stresses durable retention, not just a single correct performance — that's why mastery should be followed by spaced practice. How might a learner appear to 'master' something today only to lose it within hours?
- If an AI declares you have 'mastered' a topic, what would you want it to check before you believe it — beyond getting a few answers right?

Introduction

Mastery learning holds that achievement should be held constant while time and support vary: learners work through small, well-sequenced units and receive corrective feedback until they meet a mastery criterion, instead of being moved on regardless of what they have learned. Bloom's reframing makes frequent Formative Assessment and an explicit definition of competence central to instruction, and it is exactly that combination — diagnosis, feedback, adaptive pacing — that Adaptive Learning and Intelligent Tutoring automate. AI therefore widens the feasibility of mastery approaches and sharpens the question of whether generated feedback is calibrated well enough to certify it.

Origins and Core Idea

Bloom's mastery learning reframed the goal of instruction from "sorting students by aptitude" to "ensuring competence before progression." Where conventional instruction treats time as fixed and achievement as

variable, mastery learning inverts this: achievement is held constant and time, feedback, and practice are allowed to vary. Learners work through small, well-sequenced units and, crucially, receive corrective feedback when they fall short of the mastery criterion rather than being moved along regardless. This places Formative Assessment at the heart of the model — frequent, low-stakes checks that diagnose whether a learner is ready to advance — and it presupposes a clear notion of Assessment tied to observable performance rather than seat time.

How AI Operationalizes Mastery

The bottleneck for classical mastery learning was the teacher-side cost of diagnosing each learner's state and personalizing subsequent instruction. Modern AI systems attack this through Learner Modeling and Adaptive Instruction and Knowledge Tracing: instead of a single aggregate score, the system maintains a dynamic representation of which knowledge components a learner has (or has not) mastered. The Responsible-DKT work on Neural-Symbolic Knowledge Tracing: Injecting Educational Knowledge into Deep Learning for Responsible Learner Modelling injects explicit mastery rules into a deep learner model — repeated correct responses raise predicted mastery, while repeated incorrect responses act as a stronger signal of non-mastery — producing interpretable and temporally reliable state estimates that Intelligent Tutoring can act on.

With a running model of mastery, the system's job becomes deciding *what to present next*. Simulations of learners' task-selection strategies show that naive autonomy (e.g., self-selected tasks, risk-averse weakness targeting) can produce substantial overpractice on complex multi-step problems, whereas targeted system constraints can correct maladaptive strategies with little penalty to efficient learners. This is precisely the trade-off that Adaptive Learning and Personalized Learning systems must balance: granting learner agency where it helps while imposing constraints that keep progression toward mastery efficient. Such decisions also interact with learners' own capacity to regulate their effort, tying mastery learning to Self-Regulated Learning.

A critical caveat to mastery inference: correctness is not mastery. An, McLaren, and Stamper (2026) show that learners who overgeneralize a skill — producing correct actions while omitting a critical application constraint — can appear mastered, leading Knowledge Tracing-based mastery stopping rules to end practice before they encounter a case where the action should be *withheld*. The remedy is to assess *when to withhold* the action, not just how to execute it: include "do-not-act" detector tasks before the mastery threshold triggers, paired with Feedback that names the missing constraint. Mastery is better understood as discrimination of application constraints plus action execution, not correctness alone.

A second caveat concerns the evidence rule behind the threshold. Srivastava (2026) ran four update rules over identical event sequences from the ASSISTments 2012–13 mathematics logs — a confirmatory half of 12,716 students and 985,813 scored events — and found the declared mastery count moved with the rule rather than with the learners: crediting any completion put 93.9% of 113,428 student–skill pairs past the 0.95 posterior, against 72.8% when hinted or retried rows were read as failed first attempts. The pairs the lenient rule declared ahead of the strict rule went on to 70.9% unaided accuracy against 85.7% where the rules agreed, below the 0.744 base rate. A progression gate that counts assisted completions therefore certifies learners whose later independent work sits below average, which makes the treatment of help inside the update rule — not the numeric threshold itself — the decision that fixes what a mastery badge certifies.

Practice, Retention, and the Limits of AI Support

Mastery also depends on durable retention, not merely a single correct performance. Cognitive science on retrieval practice and the forgetting curve motivates spacing practice after the mastery threshold is reached. AI spaced-repetition systems such as Memdora generate practice materials at the point of reading and offer a taxonomy of cognitively grounded retrieval interactions, scheduled by state-of-the-art algorithms, so that achieved mastery is reinforced over time rather than lost within hours. These designs draw on Cognitive Psychology and the principle of Desirable Difficulties to make the effort of retrieval itself part of the learning process. **The retention claim has a measurement now, and mastery models fail it.** Trained on Session 1 to predict performance one week later, the Additive Factors Model and BKT overestimated next-session performance by roughly 58% and 51%, BKT-Forgetting by 47%, and none reproduced the observed spacing effect across 88 participants learning 48 word pairs in six sessions. Retrospective full-dataset fitting made the same models look acceptable (AUC 0.79, 0.77 and 0.74), so a mastery system's retention claim is only as good as its validation method (Schuetze, Yan & Carvalho, 2025).

Finally, the evidence warns against assuming AI-generated support is uniformly beneficial. In a multi-institutional study of AI-generated animated traces for novice programmers, benefits were context-dependent and short-term, and mid-engagement learners experienced a performance decrement attributed to coordination costs — an expertise-reversal-style effect that underscores the need to personalize support to the learner's current state rather than blanket-apply a tool. Likewise, a developmental continuum of AI literacy in higher education positions mastery as not merely adopting AI tools fluently but progressing through stages of informed and critical use, each with its own Formative Assessment strategies. Together these findings frame AI-enabled mastery learning as a system that must be calibrated to individual learners, sustainably spaced, and assessed for genuine competence rather than fluent output.

- **Shared-control mastery learning is only as efficient as the learner's task-selection strategy.** A simulation study (1,000 simulated learners per run, AFM and BKT parameters fit to real MathTutor and DataShop logs) compared nine task-selection strategies. Efficiency varies by an order of magnitude: the risk-averse "Minimize Worst Case Loss" strategy — picking the skill whose worst-case mastery loss is smallest — produces 30.28x overpractice in equation-solving (28.93x in graph-interpretation), against 1.73 +/- 0.38 on average for the other strategies. Targeted system constraints rescue it surgically: task-selection constraints cut overpractice to 12.88/14.46x, and a problem-selection "Prefer Harder" bias cuts it to 1.98x (Cohen's d = 1.86) — while already-efficient strategies are unaffected. The design implication: constraints should be strategy-aware, protecting pathological self-regulators without taxing good ones, and simulation-first redesign avoids exposing students to 30x overpractice to discover the fix. (Simulating learners' task-selection strategies and system constraints in mastery learning)

Standards-based grading is the assessment counterpart to mastery learning, and Mesny, Roberge-Maltais & Galy (2026) identify it among five innovative practices aligned with "assessment for learning" that higher-education educators could adopt — but they find it virtually absent from management-education discourse. They attribute this to normative barriers: norm-referenced "grading on a curve," external signaling (rankings, internships, accreditation), and students' instrumental mindset all resist mastery-oriented, gradeless approaches. Their recommendation is incremental experimentation — for example, introducing standards-

based rubrics for a single task before scaling — supported by program-level coordination and documented Scholarship of Teaching and Learning evidence.

Common Misconceptions

“A mastery threshold is an objective property of the learner.” The threshold is a property of the *rule* used to update it. Srivastava (2026) ran **four update rules over identical event sequences** from the ASSISTments dataset, and the rules disagree about who is ready. Mastery is therefore a decision recorded in a number, not a fact discovered about a student, and the rule should be treated as a stated policy rather than an implementation detail.

“If the system says mastered, the student is ready to advance.” Only relative to the update rule in force. Where a rule credits assisted work, “mastered” can describe a student who has succeeded with support and not independently — the same divergence between assisted performance and unassisted capability that the Learning Gains literature documents.

“Mastery learning is the pedagogy AI finally makes possible.” Its mechanics predate AI considerably — Bloom formalised the framework decades ago — and AI operationalises it by automating the assessment and pacing decisions rather than by realising a previously impossible design. That reframing matters because the automation inherits the rule choice, and the rule is where the judgment lives.

“More frequent assessment under mastery makes the threshold more reliable.” Frequency improves the estimate and does not fix a mis-specified rule. Recomputing mastery more often from events that include assisted work converges faster on the same wrong answer.

Connected Concepts

- Adaptive Learning
- Personalized Learning
- Intelligent Tutoring
- Knowledge Tracing
- Learner Modeling and Adaptive Instruction
- Self-Regulated Learning
- Formative Assessment
- Desirable Difficulties
- Retrieval, Spacing and Interleaving — retrieval and spacing as the practice engine inside mastery cycles

Connected Articles

- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)

- Neural-Symbolic Knowledge Tracing: Injecting Educational Knowledge into Deep Learning for Responsible Learner Modelling — Injecting mastery/non-mastery rules into deep learning for responsible, interpretable learner modeling
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Crediting assisted work inflates mastery: a preregistered comparison of evidence rules in intelligent tutoring logs — Crediting assisted work inflates mastery: which evidence rule decides who is declared mastered (Srivastava 2026)
- Simulating learners' task-selection strategies and system constraints in mastery learning — Simulating learners' task-selection strategies and system constraints in mastery learning (Noh et al. 2026)
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models — Knowledge tracing overestimates next-session performance and misses the spacing effect (Schuetze, Yan & Carvalho 2025)

Anxiety and Stress

> **Anxiety and stress** — the negative emotional states that AI integration can induce in learners and educators (fear of being falsely accused, surveillance stress, worries about competence or integrity), alongside the positive uses of AI to detect, monitor, and alleviate stress and anxiety. This concept sits within the broader Well-Being family and overlaps with Social-Emotional Learning and Affective Computing, but names the specific emotion-construct — and its productive as well as harmful sides — that AI-in-education research now studies directly.

Questions to Consider

- AI anxiety isn't one thing — it spans proctoring stress, learner-emotion anxiety, career fears, and AI used to relieve stress. Which of these have you felt or witnessed, and did it affect your learning or teaching?
- A common assumption is that anxiety is always bad. But research finds AI anxiety can be productive — anxious learners verify and revise more carefully. Can you recall a time your own anxiety made you work more carefully?
- Continuous surveillance and the fear of being falsely flagged raise test anxiety and can impair performance — and the stress falls hardest on tool-novice and already-vulnerable students. Is that an equity problem, or just a comfort issue?
- Career anxiety — the fear that AI will displace or devalue your professional future — is forward-looking and identity-level. To what extent is that fear driving how you, or students you know, engage with AI?
- Studies link higher career adaptability to lower AI anxiety and find that self-efficacy offers only limited buffering. If generic confidence isn't enough, what kind of support would actually reduce career-related AI anxiety?
- Faculty anxiety about GenAI may mirror earlier moral panics over calculators and search engines. When is worry about a new technology a legitimate concern, and when is it a recurring pattern of resistance to change?

Introduction

AI anxiety is not a single thing. It spans at least four distinct directions, each with its own evidence base: (1) **stress induced by AI proctoring and integrity surveillance**, (2) **AI anxiety as a learner emotion** that can be either a barrier or a productive signal, (3) **career-related AI anxiety** — the fear that AI will displace or devalue one's professional future, and (4) **AI as a tool for detecting and relieving stress and anxiety**. Recognizing all of these — including the productive-anxiety finding that challenges the purely negative framing — is what distinguishes this concept from the broad Well-Being umbrella.

Remote proctoring, false accusation, and surveillance stress

The clearest and most-studied source of AI-induced stress is Remote Proctoring. Continuous surveillance, the fear of being falsely flagged, and the pressure of being watched raise test anxiety and can impair performance. Key evidence: - The automated-proctoring review documents **test-taker anxiety** (especially for users not proficient with online tools) and **proctor/test-taker proficiency gaps causing false malpractice accusations** — the acute stress of being wrongly accused of cheating with AI. - The Remote Proctoring concept page details how **continuous surveillance and fear of false flags** raise test anxiety, and how stressed students perform worse — an equity and fairness problem, not just a comfort one. - Institutions adopting remote proctoring must pair AI monitoring with **accessible alternatives, clear communication, and support for test-taker anxiety**, and weigh it against authentic assessment alternatives that reduce surveillance.

This cluster connects AI anxiety to Privacy, Academic Integrity, and Equity: the stress falls hardest on tool-novice and already-vulnerable students.

Pressure that comes from continuous evaluation, not only from surveillance. A 2026 conceptual manuscript revisiting Mulvenon's multi-stakeholder test-anxiety framework (Mulvenon 2026) argues that the stressor itself has changed shape: as evaluation moves from episodic high-stakes testing into continuous, data-rich interaction in adaptive and analytics-mediated environments, acute test anxiety can fall while a diffuse, ongoing performance vigilance — what the paper calls "invisible anxiety" — rises in its place. It names "algorithmic accountability," carried by immediacy, visibility and data permanence, as the mechanism that redistributes pressure rather than removing it, and proposes an AI-Mediated Multi-Stakeholder Anxiety Model that measures none of its constructs, so the redistribution claim is argued from literature rather than demonstrated.

AI anxiety as a learner emotion (barrier and signal)

Beyond proctoring, AI use itself generates anxiety — about being replaced, about whether one's work is "really one's own," about competence. Crucially, this anxiety is **not purely negative**: - Kim (2026) finds **AI anxiety can be productive**: higher AI anxiety was positively associated with verification and revision behaviors (β=.24, $p<.01$), and evaluative capacity predicted active engagement (β=.46, $p<.001$). Kim's four regulatory types (Uncritical Reliance 18.7%, Selective Integration 34.6%, Evaluative Transformation 31.8%, Strategic Rejection 14.9%) show anxiety-driven scrutiny can transform students into more deliberate, self-regulated users of generative AI rather than passive adopters. This reframes AI anxiety from a barrier to a potentially useful signal that encourages closer scrutiny.

That reframing has a boundary in speaking: among 708 English learners, the speaking-anxiety–willingness link ran −0.371 at low speaking self-efficacy but +0.137 at high, with only 55 participants (7.8%) above the upper Johnson–Neyman threshold (Wang & Li (2026)). - Acceptance studies show anxiety shapes whether learners adopt AI tools, and teacher-education research links AI anxiety to motivation and self-regulation. - **The disclosure dilemma.** In a survey of 409 undergraduates, comfort with instructors and perceived peer disclosure — not moral disengagement — were the strongest predictors of disclosing GenAI use, and non-disclosure read as strategic adaptation to peer norms and low interpretive trust rather than negligence (Qu & Wang (2026)). - AIvaluate studies student anxiety during AI-mediated performance-based assessments,

showing assessment anxiety persists and must be designed for. - **Moral panic and educator anxiety:** the moral-panic framing shows faculty anxiety about GenAI mirrors earlier panics (calculators, search engines) — a teacher-side stress response that shapes classroom policy. - **Teachers' "state of vulnerability" and feeling "stuck."** Farazouli et al. (2026) capture the *educator* side of AI anxiety directly: 24 Swedish university teachers described the emergence of GAI as alarming and overwhelming, and reported a **state of vulnerability** — low confidence, insecurity, and discomfort driven by limited knowledge of GAI's capabilities, limited exposure, and fear of "not being ahead of students." Teachers felt "stuck" between utopian and dystopian discourses, burdened by amplified responsibility for fairness and quality, and worried about feeling incompetent when assessing student work potentially (co-)produced with AI. This frames teacher AI anxiety as a genuine emotional and professional response to role reconfiguration — not mere resistance — and argues for supporting teacher confidence and well-being, not just tool training.

- **The developer's version: impostor feeling and ethical discomfort.** Academic developers at two South African institutions were expected to embody institutional confidence in tools whose implications they were still working out ("I feel like an impostor…") while facilitating technology they doubted was appropriate - affective labor the paper treats as constitutive, not incidental (Sithole, 2026).
- **Anticipatory guilt: distress that precedes the experience.** Vassallo (2026) surveyed academic staff at a Maltese university (109 respondents) and found that guilt about AI attaches to fear of transgression rather than to its experience: the AI Guilt Index (α = 0.88) drew its strongest endorsement from worry that AI use undermines one's credibility (34.9%) and feeling like cheating (25.7%), with remorse *after* use last (9.2%). The paradox is that the small group of non-users reported higher guilt (M = 3.25) than any user group (M = 2.32) — because avoiders never test their fears, avoidance can preserve the distress it was meant to prevent. Guilt was highest among early-career academics (M = 2.71) and lowest among senior ones (M = 2.03), and it tracked concealment rather than honesty, correlating with limiting AI use out of unease (r = .62) and with avoiding disclosure to colleagues (r = .50) but not with formal disclosure (r = .08).
- **Fear of lost professional value, and a way through it.** Chick, Morello & Staffey (2026) document an educator anxiety that is existential rather than technical. Ten faculty and staff entered a six-week institute with academic integrity as the leading concern (80%) and over-reliance second (70%), describing generative AI early on as a "cheating machine", a "threat" or a "dehumanizing force"; a mathematics professor put the identity threat plainly — "I spent years developing expertise in my field. Now a machine can solve problems faster and explain solutions better than I can. What's my value anymore?" Structured, safe experimentation moved the vocabulary toward "curious assistant" and "creative partner" and left 90% reporting positive perceptions, and the authors are explicit that the resistance they observed "stems not from technophobia or stubborn traditionalism but from legitimate concerns about educational quality, equity, and human agency" — a direct counterweight to reading educator anxiety as mere moral panic.
- **Appraisal-targeted chatbot support shifts enjoyment and boredom, not hopelessness or self-efficacy.** In a 144-student experiment comparing plain ChatGPT with an SRL-Scaffolding agent and an emotionally supportive one, enjoyment rose (d = 0.53 with SRL scaffolding, 0.75 with emotional support) and boredom fell (d = -0.35, -0.67) only in the two scaffolded conditions. Plain

ChatGPT showed no significant change in either emotion. Hopelessness fell in every condition including plain ChatGPT (d = -0.73 to -1.02). Neither self-efficacy (η2 = 0.001) nor trust in the chatbot (η2 = 0.020) differed by condition, so the emotional design moved two emotions and left the motivational belief the theory predicted untouched (Diordiev, Stenberdt & Makransky, 2026).

Institutional support works on anxiety through appraisals, not reassurance. A two-wave survey of 547 Chinese undergraduates (Jiang, Chen & Chen, 2026) traced how perceived school support relates to AI learning anxiety through control-value appraisals — the learner's sense of competence (control) and of the tool's usefulness (value). Support predicted lower anxiety directly, but most of its association ran through the appraisals rather than around them: via AI learning self-efficacy, via perceived usefulness, and via a sequential route in which self-efficacy fed usefulness, which in turn lowered anxiety. A first-order model showed the support *dimensions* were not independently doing the work — only informational support retained a significant path to self-efficacy — and an artificial neural network cross-validation ranked self-efficacy and perceived usefulness as the most stable predictors of anxiety. The implication is that institutional encouragement aimed at anxiety only lands if it changes what students believe about their own capability and the tool's usefulness; general reassurance does not alter the appraisals that generate the anxiety.

AI can also relieve academic anxiety by advancing learning goals rather than by reassurance: across a survey of 721 medical students and an experiment with 398, higher perceived assistant capability predicted greater study-goal progress, which predicted lower academic anxiety and better mental health (Chen et al. (2026)).

Competence is not a full buffer, though: among 551 Chinese first-year students, self-reported AI usage pressure weakened the link between AI proficiency and psychological adjustment, with the AI-proficiency-to-adjustment slope falling from 0.42 under low pressure to 0.20 under high pressure (Zhang & Yin (2026)).

The route from competence to anxiety runs through ethics, and it can amplify. Among 584 undergraduates at a law-dominant Chinese university with no AI literacy curriculum, AI competence did not reduce AI anxiety directly (β = 0.056, p = .362). It raised AI ethical awareness (β = 0.644, p < .001), which in turn raised anxiety (β = 0.439, p < .001) — indirect-only mediation through a path the authors had hypothesized as protective (Mu et al. (2026)). Only 22.8% of anxiety variance was explained. An ANN on the same constructs ranked transparency first among predictors for both learning and job-replacement anxiety. **Faculty forecasts as a distributed form of AI anxiety.** Watson & Rainie (2026)'s survey of 1,057 US college and university faculty registers educator anxiety as expectations rather than symptoms: 95% expected generative AI to increase students' over-reliance on the tools, 94% more academic integrity concerns, 90% diminished critical thinking, 83% shorter attention spans and 81% wider digital inequities, while 39% believed the tools would diminish the role of faculty and 47% feared the long-term employment impact in their disciplines would be negative. The same respondents were not uniformly pessimistic — 61% still expected improved and customized learning — but 73% had personally dealt with an academic integrity case involving students' generative AI use, which is where a forecast turns into workload. The report is explicitly a non-scientific sample that is not generalizable, so it documents the sector's expressed fears rather than measured effects.

This direction connects AI anxiety to Motivation, AI Literacy, Student Experience, and Self-Regulated Learning.

An agent that resembles an examiner can carry an examination's pressure with it. Students who practiced speaking with Replika scored significantly higher than they did with peers, yet described the interaction as anxious and awkward and did not want to use it again — measured performance and experienced stress moving in opposite directions (Soriano-Gonzalez & Belda-Medina (2026)).

Career-related AI anxiety

A distinct and increasingly studied dimension is **career anxiety** — the fear that AI will displace jobs, erode employability, or devalue one's professional future. Where proctoring anxiety is situational and learner-emotion anxiety is about in-task competence, career anxiety is forward-looking and identity-level, and it is tightly linked to Career Development and Readiness. The AI Anxiety comprehensive analysis identifies the **fear of replacement by AI** as the primary contributor to AI anxiety, alongside uncontrolled AI growth, privacy, misinformation, and bias. A growing empirical literature now quantifies how this fear affects students:

- **Career adaptability is a protective factor.** Wang (2026) shows career adapt-abilities significantly and negatively predict AI anxiety among English majors, with core self-evaluations partially mediating the relationship; the low-adaptability group had the highest AI anxiety.
- **Threat and favorable appraisal co-activated in one profile.** Song et al. (2026) found a group above the sample mean on all six indicators at once — AI use anxiety 1.521 and STARA awareness 0.951 alongside perceived quality 1.753 — so high anxiety did not signal a negative appraisal of the technology.
- **AI anxiety impairs career decisions.** Duan et al. use structural equation modeling to show AI anxiety directly and negatively predicts career decisions, and does so largely by undermining **career adaptability** (accounting for 63.35% of the total effect); Self-Efficacy offered only limited buffering.
- **Growth mindset bounds the threat-to-employability path.** Among 526 Chinese undergraduates, AI employment-threat perception predicted higher career decision-making anxiety partly by lowering perceived employability, and the threat-to-employability link held only at low growth mindset ($b = -0.229$) and not at high ($b = -0.013$) (Chen (2026)).
- **AI anxiety predicts job-search anxiety at scale.** Üstün & Danacıoğlu (1,057 students) and Dağ et al. (821 health-sciences students) find AI anxiety and negative AI attitudes predict job-finding/job-search anxiety, with women, social-science majors, and lower-income students most affected.

Practical implication: building career readiness — adaptability, core self-evaluations, and employer-valued AI skills — is a validated intervention for reducing career-related AI anxiety, more than generic self-efficacy alone. Institutions should universalize AI Literacy and career-planning support, and address the equity patterning of career anxiety.

AI for detecting and relieving stress and anxiety

The positive side: AI systems increasingly detect and help alleviate stress and anxiety. - AI campus well-being tools span prevention (improved feedback collection) and intervention (advancing mental-health

detection). - Affective text + wearable sensing (a year-long study of 458 students with Oura rings) shows ultra-brief naturalistic text can complement wearable physiological sensing for longitudinal student health monitoring — a concrete AI-enabled stress-detection pathway. - This links to Affective Computing and Affective Tutoring, where AI reads and responds to emotional state. - **Which stressors the model weighs — and why context matters.** Bashir and Afzal (2026) offer a Machine Learning window on which stressors actually drive student distress in a non-Western context. Feature-importance analysis on 1,100 survey responses put blood pressure first (15.6%) and **teacher-student relationship second (10.0%)** — ahead of sleep quality (9.3%), depression (8.3%) and social support (7.6%) — while anxiety level ranked ninth at 4.8%, which the authors read as evidence that student stress is multi-dimensional rather than driven by a single psychological indicator. They attribute the salience of the teacher-student relationship to the comparatively hierarchical educational environment in Pakistan and present it as a hypothesis for locally collected data, underlining that stress models and their feature weights are context-dependent and cannot be assumed to transfer across student populations. - **Instructor-side real-time intervention.** Parlant's practitioner guide adds a human counterpart to these AI tools: *emotional micro-interventions* — brief, deliberate verbal or gestural acts that validate a student's emergent emotion, reframe the appraisal behind it, and reconnect the struggle to professional identity (Validate, Reframe, Connect). Grounded in cognitive appraisal theory, the approach targets the primary appraisal ("is this a threat?") and the secondary appraisal ("can I cope?") at the moment distress would end engagement, pairing bottlenecks such as frustration, isolation and imposter syndrome with target states. Its author states plainly that the framework does not require AI; generative AI serves only as an optional way to draft candidate phrases for the instructor to curate.

Why this is distinct from well-being

Well-Being is the broad positive state (emotional, psychological, social health) that AI can support or undermine. **AI anxiety and stress** is the specific, measurable emotion-construct within that space — it names the discrete negative affect and its productive uses, and it has its own dedicated evidence base (proctoring stress, productive AI anxiety, AI-driven stress detection). Rather than rivaling well-being, this page develops the anxiety/stress dimension in depth and cross-links heavily to Well-Being, Social-Emotional Learning, Affective Computing, and Remote Proctoring.

Practical guidance

- **Design for anxiety, not just integrity.** Proctoring and AI-monitoring systems should minimize false accusations and surveillance stress, especially for novice and vulnerable students; pair monitoring with accessible alternatives and clear communication.
- **Leverage productive anxiety.** Rather than only reducing AI anxiety, support the verification, revision, and self-AI Regulation in Education that anxious-but-engaged students already exhibit.
- **Use AI to detect and relieve stress** — via affective computing, wearables, and campus well-being tools — while guarding privacy.
- **Consider educator anxiety** in AI adoption and policy, not just student experience.

Common Misconceptions

- **“AI anxiety is purely harmful.”** This anxiety is **not purely negative**: Kim (2026) finds **AI anxiety can be productive**, with higher anxiety associated with more strategic regulation. Anxiety functions as a signal to scrutinize rather than only as a burden.
- **“All anxious students respond the same way.”** Kim’s **four regulatory types — Uncritical Reliance 18.7%, Selective Integration 34.6%, Evaluative Transformation 31.8%, Strategic Rejection 14.9%** — show anxiety-driven scrutiny producing **four distinct** patterns. An intervention targeting “anxious students” misses that the largest single group is selectively integrating.
- **“Anxiety always suppresses participation.”** That reframing has a **boundary in speaking**: among **708 English learners**, the speaking-anxiety to willingness link ran **-0.371 at low speaking self-efficacy but +0.137 at high**. Anxiety can accompany willingness when self-efficacy is high, so the effect direction depends on confidence.

Connected Concepts

- Career Development and Readiness — career readiness as a protective factor against AI anxiety
- Well-Being — the broad umbrella this concept develops in depth
- Remote Proctoring — the primary source of surveillance/false-accusation stress
- Social-Emotional Learning — the emotional competencies involved
- Affective Computing — AI reading emotional state
- Affective Tutoring — AI responding to affect
- Academic Integrity — the integrity/cheating-accusation dimension
- Privacy — the surveillance concern underlying proctoring stress
- Student Experience — anxiety as part of the learner experience
- Motivation — anxiety’s effect on adoption and engagement
- Self-Regulated Learning — the productive-anxiety link
- AI Literacy — building capacity that reduces unfounded anxiety
- Equity — disproportionate stress on vulnerable students
- Ethics — the fairness of surveillance and false accusations
- Teaching — educator-side anxiety
- Assessment — AI-mediated assessment anxiety
- Social Norms of AI Use — the affective cost of visibility

Connected Articles

- Chatbots for oral proficiency in English language learning: A systematic review — An examiner-like agent raised measured speaking and anxiety at once

- Modeling the Relationships Between University Students' AI Competence, AI Ethical Awareness, and AI Anxiety: A Dual-Stage PLS-SEM and ANN Analysis - Competence raises ethical awareness, ethical awareness raises AI anxiety: indirect-only mediation among 584 students
- From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource — AI anxiety as a productive strategic-regulation signal
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — Student anxiety in AI-mediated performance-based assessment
- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach — AI-driven tools for campus well-being
- A formative study of brief affective text as a complement to wearable sensing for longitudinal student health monitoring — Affective text + wearable sensing for student health
- A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence — Automated proctoring, test-taker anxiety, false accusations
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review — Decade-long review of automated exam proctoring
- Navigating the moral panic: encouraging appropriate use of GenAI in the classroom rather than condemning innovation as disruption — Faculty anxiety and moral panic about GenAI
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — Anxiety shaping AI tool acceptance
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher education, AI literacy, and anxiety
- Students' engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study — AI use intertwined with anxiety, trust, confidence
- To disclose or not to disclose: Peer influence and psychological factors in students' use of generative artificial intelligence — The disclosure dilemma as a source of student stress
- AI Anxiety: A Comprehensive Analysis of Psychological Factors and Interventions — Comprehensive analysis of AI anxiety and interventions
- The impact of career adapt-abilities on AI anxiety among English majors: a dual perspective analysis based on core self-evaluations at the person- and variable-centered — Career adapt-abilities reduce AI anxiety
- The impact of AI anxiety on career decisions of college students — AI anxiety impairs career decisions via career adaptability
- The Role of Artificial Intelligence Anxiety and Attitudes Toward Artificial Intelligence in University Students' Job Finding Anxiety — AI anxiety and attitudes predict job-finding anxiety
- Artificial intelligence perceptions and career anxiety among health sciences students — AI anxiety predicts job-search anxiety in health sciences

- Navigating uncertainty: university teachers' experiences and perceptions of generative artificial intelligence in teaching and learning — University teachers' experiences and perceptions of GAI: vulnerability, rethinking assessment, student learning at risk (Farazouli et al. 2026)
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- Multidimensional perceived school support and AI learning anxiety among university students: the mediating roles of control-value appraisals — Perceived school support lowers AI learning anxiety mainly through control-value appraisals (69.5% mediated); ANN cross-validation (Jiang, Chen & Chen 2026)
- The AI guilt complex: Moral emotions and ethical dilemmas in academic technology adoption — The AI Guilt Complex: anticipatory guilt exceeding post-use remorse among academic staff (Vassallo 2026)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — AAC&U/Elon survey of 1,057 US faculty: forecasts of over-reliance, integrity concern and a diminished faculty role (Watson & Rainie 2026)
- From fear to innovation: A case study of transformative faculty development for ethical AI integration in higher education — From fear to curiosity: a six-week faculty institute moving instructors through identity threat (Chick, Morello & Staffey 2026)
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Academic developers' impostor feelings and ethical discomfort as affective labor in AI-mediated work
- Can You Feel It? A Practical Guide to Emotional Micro-Interventions for Higher Education Teachers (and Others) — Instructor-side real-time emotional micro-interventions grounded in cognitive appraisal theory
- When AI threatens my future career: growth mindset and perceived employability in Chinese college students' career decision making anxiety — AI employment threat and career decision anxiety: perceived employability mediates and growth mindset moderates
- A study on AI-enabled course development, AI proficiency, and first-year students' academic and psychological adjustment — AI usage pressure weakens the link between AI proficiency and first-year adjustment
- Beyond Positive or Negative: Latent Profiles of University Students' AI Attitude and Their Career-Development Correlates — A profile high on both AI anxiety and perceived AI quality, not one or the other
- AI-Assisted Speaking Practice and Human-Directed Communicative Readiness: Survey and Scenario Evidence on Anxiety, Self-Efficacy, and Evaluation Pressure — Speaking anxiety's link to willingness to communicate reverses at high speaking self-efficacy

- Smarter AI, Healthier Students? How Perceived AI Assistant Intelligence Shapes Medical Students' Mental Health Through Learning Goal Progress and Academic Anxiety — Perceived AI assistant intelligence lowers academic anxiety through study-goal progress (medical students)

Connected FAQs

- How Is AI Impacting Students?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

Student Experience

> **Student experience** — how learners perceive, interact with, and are affected by AI tools in educational settings. With over 85 articles in the knowledge base, student experience is one of the most-researched dimensions of AI in education. AI impacts students in both positive and negative directions, and the same tool can help and harm depending on how it is designed and used.

Questions to Consider

- The page claims AI affects students in both positive and negative directions, often simultaneously — the same tool can help and harm depending on design and use. Can you give an example from your own experience where AI helped and hurt at the same time?
- It describes a 'performance-learning gap': students do better with AI but worse on later unassisted tasks. How do you think that gap arises, and what would it take to close it?
- If over-reliance on AI means delegating the reasoning you actually need to practice, where would you draw the line between legitimate help and offloading that erodes learning?
- The research asks whether simply knowing AI is available changes student effort. Do you think awareness of AI makes students work harder, less hard, or differently — and how would you test your belief?
- Given that AI access and effectiveness vary across student populations, what equity concerns do you think matter most when a course adopts an AI tool, and who is responsible for addressing them?

Introduction

How student experience is studied

- **Large-scale surveys:** AI in the Wild analyzes authentic interactions of thousands of college students, while availability and satisfaction studies correlate AI access with student outcomes. These are self-report measures: they capture perceptions and intentions well and behavior only approximately.
- **Non-use is a reasoned position, not a gap to close.** A cross-institutional UK survey of 7,087 students found 32% did not use GenAI for study at all, with non-users citing wanting to do the work themselves (86%), inaccuracy (81%), and ethical or environmental concerns (Gow et al., 2026).
- **Interaction patterns:** Tracing GenAI literacy maps how students engage with AI across assignments. Prompting analysis reveals cognitive engagement levels through prompt structure.
- **Motivation and agency:** AI availability and motivation examines whether knowing AI is available changes student effort. AIED's unfinished mission frames Learner Agency and Motivation as central challenges.

- **Perceptions and attitudes:** GenAI usage surveys and mental model studies investigate how students understand and trust AI.
- **Equity dimensions:** student-experience intersects with Equity — AI access and effectiveness vary across student populations.

Ways AI impacts students

AI affects students across cognitive, motivational, affective, identity, social, and equity dimensions. The research points to **positive and negative impacts in each dimension**, often simultaneously — the direction depends on design and use.

Cognitive impacts

- **Positive:** AI can scaffold learning with Feedback, hints, and explanations, supporting understanding, practice, and Help-Seeking. Students can use AI to learn how to use AI well, and well-designed tools keep the learner doing the cognitive work (see Does AI help students learn?).
- **Negative:** AI can drive over-reliance and cognitive offloading, where students delegate the reasoning they need to practice. This is the **performance–learning gap**: students do better *with* AI but worse on later unassisted tasks (see AI Misuse and Learning Harm). Overuse may also erode Metacognition and Self-Regulated Learning.

Motivational impacts

- **Positive:** AI can raise Motivation and engagement by providing personalized, immediate, and low-stakes support — helping students persist and feel competent (see self-determination perspectives on autonomy, competence, and relatedness).
- **The motivational effect runs through motivation, not through access.** Among 297 students, autonomy support and autonomous motivation for AI use had no direct effect on engagement ($\beta = 0.070$ each), while student motivation predicted engagement at $\beta = 0.74$ (Ahmed and Sultan (2026)).
- **Negative:** Knowing AI is available can reduce student effort and motivation to struggle productively (AI availability and motivation, the safety gap). Over-reliance can erode Learner Agency and the sense of accomplishment that comes from doing work oneself.

Affective and well-being impacts

- **Positive:** AI can offer low-pressure, on-demand help and reduce anxiety about asking questions, supporting Well-Being and confidence.
- **Negative:** AI use is associated with anxiety and stress, including fears about being replaced, uncertain assessment, and the pressure to keep up. Studies such as a comprehensive analysis of AI anxiety and AIvaluate document these affective costs. Shame and guilt around AI use can drive hiding and selective disclosure, harming honest engagement and social-emotional well-being. These pressures are local and social rather than written down: see social norms of AI use. Assessment conditions add their own pressure: a scoping review of remote proctoring in nursing

assessment finds students anxious about connectivity and about being wrongly accused of cheating, first-time users of an invigilation app describing it as anxiety-inducing and reporting difficulty concentrating while watched, and roughly a fifth hitting browser-extension or connectivity failures despite preparatory resources.

Identity impacts

- **Positive:** AI can support identity formation by scaffolding disciplinary belonging, confidence, and professional aspirations — e.g., helping students see themselves as capable practitioners.
- **Negative:** AI can threaten learner identity through authorship loss and competence doubt — when AI produces the work, students may stop feeling it is "theirs." The competence paradox in creative fields shows ease-of-use undermining the craft-based identity students derive from authorship.

Academic-integrity and fairness impacts

- **Negative:** AI enables new forms of academic dishonesty (AI-generated essays, unauthorized completion), driving debates about detection and reduction. This interacts with equity: unequal access to, and understanding of, AI tools can widen gaps between students.
- **Whether a use counts as cheating depends on the discipline.** A systematic review of 89 studies found STEM students at +42% net agreement that AI improves performance, while humanities students showed the highest net agreement that AI use constitutes cheating (+44%) and raises ethical concerns (+58%) (Padhy (2026)). A course's integrity problem is therefore partly a disciplinary judgment rather than a fixed standard, which is why the rules students encounter vary by department as much as by policy.
- **Positive/constructive:** AI can support authentic, process-oriented assessment and reflective practice (e.g., guided self-assessment), turning integrity concerns into opportunities for AI Literacy and responsibility.

Student accounts of integrity are less settled than the dishonesty framing suggests. Mulisa and Mezgebu (2026) interviewed 27 undergraduates at an Ethiopian university and found the student body divided against itself: almost all used GenAI or watched peers use it and most credited it with raising their achievement. A minority called coursework use outright misconduct, and the sharpest and most widely shared complaint was fairness — AI users scoring above students who worked honestly. That left some describing it as killing their sense of diligence, and one participant unsure "whether we are benefiting or suffering from the use of AI." The procedure side matters too: Munoz et al. (2026) coded 1,162 GenAI misconduct cases and found that the evidence most often cited — detector output, similarity reports, AI-typical content patterns — carried the weakest probative value, and that with no minimum evidentiary threshold in the pipeline students with thin cases were pushed toward appeals. Over-inclusive definitions broaden that exposure: Wright (2026) shows that prohibitions aimed at "generative AI" can catch tools that merely convert the format of work a student already authored, an over-inclusion that falls hardest on disabled and equity-exposed students. Sharma (2026) points the constructive way out, treating integrity as a pedagogical practice enacted through judgment — annotated decision trails, verification, oral defense, version history — rather than compliance secured through surveillance.

Verification can shift how students experience the question: a request to explain their work first read as an accusation, but once the syllabus framed it in advance as pedagogy rather than surveillance they disclosed AI use more openly and treated assignments as learning tasks, in five-to-ten-minute conversations (Mandernach, 2026).

Social and relational impacts

- **Positive:** AI can mediate collaboration and human-AI interaction, supporting teamwork, peer interaction, and access to diverse perspectives.
- **Negative:** AI can reduce genuine peer and instructor interaction, create sycophantic dynamics, and — when operating as an undisclosed teammate — reshape group discourse and Learner Agency in ways learners cannot see or contest (see emergent learner agency in implicit HAI).

Long-run / capability impacts

- **Positive:** AI can help students build transferable skills for an AI-integrated workplace — adaptive capabilities such as AI Literacy, Distributed Cognition, and Metacognition — and raise expectations about AI-skills readiness (AI-skills expectations for graduates).
- **Negative:** An over-reliant or unreflective AI experience can leave students less able to perform without AI, less practiced at independent reasoning, and uncertain of their own capabilities (see AI misuse and learning harm).

Overall: the same AI tool can support or undermine students depending on design and use. The guardrail throughout is to keep the learner doing the cognitively important work while using AI for support (scaffold, do not substitute), and to attend to the full range of impacts — not just performance. One configuration shifts where the experience begins: when AI generates the course readings themselves rather than helping with homework, students become auditors of their own curriculum. In Sidorkin's (2026) graduate course, students valued the contextual specificity and adjustability of the generated texts and 75 percent agreed they learned more than in a comparable course without an AI companion, yet they had to infer source quality from context because Wikipedia links and peer-reviewed citations appeared in the same lists without labels, and four of 24 survey respondents used dependence language, including one describing themselves as "somewhat codependent on the AI for reassurance and structure."

The longest-run outcomes a student experiences — whether they return next term, accumulate credits, and graduate — are institutional rather than instructional, and Student Support and Success tracks how AI support affects them: task completion moves readily, persistence and graduation far less so.

Connections

Student experience connects to Over-Reliance (excessive AI dependence), AI Literacy (skills for effective use), Cognitive Offloading (how AI changes cognitive work), and engagement (how AI systems measure and respond to student behavior). It is the learner-facing member of the Stakeholders umbrella, and the home for summarizing all the ways AI impacts students.

Common Misconceptions

“Students who avoid AI are behind.” Non-use is frequently a reasoned position rather than a gap: a cross-institutional UK survey of **7,087 students** found **32% did not use GenAI for study at all**, with non-users citing wanting to do the work themselves. Treating that as an adoption deficit inverts the finding and pressures students out of a defensible choice.

“Student reports are a reasonable measure of learning.” They are self-report measures: they capture perceptions and intentions well and behavior only approximately. The performance–learning gap in this literature — students doing better with AI and worse on later unassisted tasks — is precisely the case where self-report and outcome diverge, so a satisfied student body is not evidence of a learning student body.

“If students feel AI helps, it helps.” Feeling helped is a real datum about the experience and an unreliable inference about the outcome. The gap is documented and students in the harmed group do not reliably perceive it, so perception and outcome have to be collected as separate measures rather than one standing in for the other.

“Student experience is a soft concern relative to outcomes.” It is a leading indicator for adoption and disclosure: students who feel their use is judged will conceal it, and concealed use is the condition in which misuse and harm are least visible to the institution.

Implications for Practice

For instructors

- Do not treat non-use as a gap to close. Roughly a third of students choose to do the work themselves, and pressure to adopt converts a reasoned position into a compliance problem.
- Collect perception and outcome separately. Satisfaction surveys describe the experience and cannot stand in for unassisted performance.
- Make disclosure safe, since students who expect judgment conceal their use, and concealed use is where the divergence between assisted and unassisted performance hides.

For developers

- Report learning outcomes alongside experience metrics in anything you publish to students, because the felt and measured results routinely diverge.
- Support declining the assistant without losing access to the course.

For researchers

- Report the size and reasons of the non-user group explicitly; 32% of a 7,087-student sample is a population, not a residual.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Pedagogical Partnerships — Pedagogical Partnerships
- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities

- Learner Agency
- Well-Being
- Anxiety and Stress
- Social-Emotional Learning
- Remote Proctoring
- Generative AI
- Large Language Models (LLMs)
- Higher Education
- AI Literacy
- Cognitive Offloading
- Equity
- K-12
- Scaffolding
- Metacognition
- Self-Regulated Learning
- Framing AI Use for Students
- Academic Integrity
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Self-Report Measures
- Student Engagement — how AI systems measure and respond to student behavior
- Social Norms of AI Use — how AI use becomes visible to peers
- Student Support and Success — the institutional side of support: what the university does to students, not what happens in a course

Connected Articles

- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and guilt as social regulators of AI use
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox: creative identity in text-to-image GenAI use
- The best response to student AI use is not detection, it is dialog
- How does students' perception of ChatGPT shape online learning engagement and performance?
- Is using artificial intelligence tools for academic work cheating? Student perceptions, ethics, and the impact on academic performance and critical thinking
- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison
- Metacognitively discordant completion and the aware pass-through of non-understanding in generative AI learning

- AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement
- AI in the Wild: A Large Scale Analysis of Authentic Interactions of College Students with Generative AI
- Generative AI Availability, Grades, and Student Satisfaction at a Large University
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — Student rationalization of AI use in academic writing (Kim et al. 2026)
- Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing
- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies
- "Why Put in This Much Effort?": How AI Availability Shapes Students’ Motivation in Introductory Programming
- AIED’s Unfinished Mission: Centering Agency and Motivation in the Age of Effortless Bypass
- Uncovering Students’ Mental Models of Generative Artificial Intelligence
- A study of GenAI usage by Design Students: Analysis of Survey Results and Journals of AI practices at the Politecnico di Milano in 2025/2026
- Exploring AI-Supported Disciplinary Mediation in Student Project Teams’ Text-Based Communication
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — AI-skills expectations for college graduates vs. institutional readiness
- Analysis of Types of Inquiries in Student-AI Interaction: A case study of two CS2 tasks — Analysis of Types of Inquiries in Student-AI Interaction
- Navigating AI in STEM: what secondary students actually do with generative AI-driven tools — What secondary students do with GenAI tools across STEM
- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students’ problem posing ability in science — GenAI chatbots and problem posing in primary science
- Heads we win, tails you lose: AI detectors in education — Heads we win, tails you lose: AI detectors in education (Bassett et al. 2026)
- The safety gap: restoring productive struggle through pedagogically aligned generative AI — The Safety Gap: Restoring Productive Struggle
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — AIvaluate: LLM-Augmented Assessment of Student Anxiety (2026)
- AI Anxiety: A Comprehensive Analysis of Psychological Factors and Interventions — A comprehensive analysis of AI anxiety
- Students’ Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study — Students’ Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study
- Factors associated with students’ adoption of artificial intelligence technology in tertiary education: A meta-analytic review — Post-secondary adoption perspective

- Raising Ethical Awareness of GenAI Use Through Student Self-Assessment in the Transition to Higher Education — Raising ethical awareness of GenAI use through student self-assessment
- Reimagining Success and Failure: Equitable Assessment Practices in an Age of Artificial Intelligence — Equitable assessment in an AI era
- Longitudinal insights into AI in education: Usage, ethics, and policy development in higher education — Longitudinal GenAI usage, ethics, and policy in teacher education (Parker et al. 2026)
- The use and usefulness of GenAI in higher education: Student experience and perspectives — Student experience of GenAI usefulness in Australian higher ed (Chung et al. 2026)
- Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education — 297 students: motivation predicted engagement; autonomy support for AI use had no direct effect (Ahmed & Sultan 2026)
- Modelling generative AI's influence on students' perceived decision capability: A cognitive load and decision augmentation approach — GenAI and students' perceived decision capability (cognitive-load account)
- Conceptualizations of GenAI and students' professionalization: Within the multi-layered environment of learning for higher education — GenAI conceptualizations and student professionalization
- From One-Size Texts to Tailored Readings: Student Experiences with AI-Generated Course Materials — Students as auditors of their own AI-generated curriculum (Sidorkin 2026)
- Tools facilitate cheating, or partner supports learning? GenAI and academic integrity issues from students' perspectives — Students on whether GenAI is a cheating tool or a learning partner
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What misconduct allegation files actually contain as evidence
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI rules and the students they catch
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity as evaluative judgment rather than compliance
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Remote proctoring's emotional and equity costs for students

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Is AI Impacting Students?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

Student Support and Success

> **Student Support and Success** — the institutional-side work of helping students stay, progress, and finish: **advising, administrative assistance, outreach, referral, and the allocation of scarce support**. This is the page for what institutions *do to* students rather than what happens *inside* a course. Higher Education is the broader umbrella for the sector and Student Experience covers how AI lands on the student's own experience; Learning Gains measures whether learning happened. The distinctive finding in this knowledge base is that AI support reliably moves **task completion** — a dated, binary action a student controls and the institution can observe — while leaving **persistence, credits, and graduation** largely untouched. Separating those outcomes is the point of this page.

Questions to Consider

- Which outcome are you trying to move? A registration reminder and a retention program are different interventions with different evidence, and the research here suggests one does not buy the other.
- If a model flags a student as at risk, what happens next? Who acts, with what capacity, and what would make the recommendation feasible rather than merely accurate?
- Support capacity is finite. When AI ranks or allocates it, what does that do to the students a human advisor would have noticed anyway?
- Who is accountable when an automated message, referral, or risk score is wrong? The student sees the consequence; the institution owns the system.
- Does your support data travel? Cross-office sharing is what makes targeting possible and is also the most common reason targeting quietly stops.

Introduction

Student support sits on the institutional side of the relationship. Its work is advising, outreach, referral, and the allocation of finite human and financial capacity; its evidence base is administrative records, registration events, credits earned, and whether a student returns. Generative AI entered this territory later than it entered instruction, and much of the literature here concerns **non-generative** systems — text-message chatbots, early warning models, federated risk prediction — with generative tools arriving as advisors, assistants, and knowledge-base responders.

The distinction that organizes this page is between **what a nudge can do** and **what a trajectory requires**. Support technologies excel at a dated, binary decision: register by this date, complete this form, start Early Start. They have far more difficulty with cumulative outcomes — persistence, credits, graduation — which instruction, finances, employment, family circumstances, and prior preparation all shape. The knowledge base's strongest evidence on this comes from a four-year randomized evaluation that moved registration sharply and graduation not at all.

The support functions

The research clusters into five functions, and the cluster boundaries matter because they carry different evidence.

Outreach and communication. Institutions message students at scale, and the strongest evaluations test whether it changes anything. A four-year randomized study of CSUNny, a non-generative text-message chatbot at California State University, Northridge, followed two undergraduate cohorts (N = 8,708) through eight semesters (Mata, Russell & Page, 2026). A registration reminder sent July 31, 2018 made treated students 34 percentage points more likely to enroll by August 16 and only 2 points more likely by September 15; Early Start reminders produced 11 points more registration by June 7 and 20 points by June 22. Receptivity held: annual opt-out rates never exceeded 4%. A pre-registered multi-semester trial at Georgia State University nudged students in two large asynchronous courses (N = 1,568 and N = 915) with two to three customized messages a week, raising the odds of earning an A or B by four percentage points against 61% of controls and shifting DFW rates by about three points in each course (Meyer et al., 2026).

Advising and academic planning. Course and grade prediction supplies the planning input — one model jointly predicts which courses a student will take and the grades they will receive (Savala, 2026), and another predicts module-level progress in large online programming courses with an intrinsically interpretable decision tree (Zhang, Jeffries & Koprinska, 2026). Transfer credit is an advising problem in its own right: CourseGraph models course content as knowledge graphs to evaluate external course equivalences for mobile students (Nijdam et al., 2026). At the institutional level, a review of 155 studies of AI and service delivery in higher education found learning analytics the most common application at 46 studies (29.7%), ahead of chatbots and virtual assistants at 31 (20.0%) and predictive analytics at 29 (18.7%) (Nyamboga, 2026).

Referral and support allocation. Prediction is not a plan, and the gap between them is where the field's sharpest critique sits. SC2R formalizes it as the **actionability gap**: a risk score becomes decision support only when its recommendations are semantically feasible and machine-checkable — constrained by timing, budget, immutability, and availability rather than merely model-valid (Le, Abel & Laforge, 2026). Whether models can allocate support well is contested empirically: asked to recommend support plans for 4,500 synthetic student vignettes, three LLMs showed limited sensitivity to student need and sharp inconsistency across models (López-Pernas et al., 2026).

Academic support access. Course-specific retrieval systems aim at the students least likely to ask a human. Beacon, built from a single programming module's approved materials, drew high relevance ratings (89%) and was judged by most students to support rather than replace their learning (66.7%), in a small evaluation of 15 students and 4 academics (Zhou et al., 2026). Tutoring take-up is its own problem: a two-year randomized trial of a virtual tutoring layer for struggling students had to test take-up separately from learning, because reaching the students who need support is not the same as providing it (Fryer et al., 2026).

Administrative assistance. Leadership and administration are studied as their own application domain, with a ten-domain taxonomy mapping where AI lands in educational leadership (Sposato, 2025). Institution-run services reach past advising into health: an integrated campus well-being framework pairs prevention — improving how feedback is collected — with intervention through mental-health detection (Tang, 2026).

Credentialing sits adjacent: when an agent can complete a course on a student's behalf, a credential that says "earned" loses its meaning, which turns completion records into a design problem (Srivastava, 2026).

What an AI support channel displaces deserves the same accounting. Across four studies (N = 249, 494, 743 and 737), belief in AI's capacity to provide emotional support raised willingness to offload that support to it, and the effect travelled entirely through perceived capacity (total effect c = 0.83; indirect effect ab = 0.73) (Shastry & Gray, 2026). On a behavioral measure, participants who said they would not offload chose fewer empathy words, so routing students to an AI well-being channel can subtract human support in ways self-report does not show.

From prediction to support

Risk prediction — early warning systems, dropout models, at-risk classifiers — is **Learning Analytics** territory in this knowledge base, and this page treats *predictive analytics* as the same thing. The modeling work is substantial: supervised classifiers identify students before withdrawal from academic performance, demographic, and enrollment records (Gheisari & Salarian, 2026); a dual-layer framework combines Codeforces behavioral logs (n = 1,816) with psychographic survey data from ten universities to predict attrition in competitive programming (Alam et al., 2026); and a federated architecture predicts performance and dropout across institutions without sharing raw student data, reaching AUC = 0.918 on OULAD against 0.925 centralized (Villegas-Ch et al., 2026). A precision-education vision extends the logic to student digital twins and "preventive student success" (Han et al., 2026).

What belongs *here* is the step after the score: **support allocation**. Two findings set its limits. First, the ranking-versus-calibration split — federated risk models kept their AUC under distributional shift while their calibration degraded markedly, so a model that still ranks students correctly can be wrong about how likely each one is to need help. Second, the enabler study: an international Delphi and AHP/SNAP analysis of learning-analytics-to-intervention identified seven enablers and ranked **institutional strategic orientation** highest (priority 0.2072) and most influential on the others (PageRank 0.2430), locating the bottleneck in institutional planning rather than in the models (Svetec, Divjak & Kadoić, 2026). Behavioral clustering of 14,003 student records into six profiles, mapped to recommended learning objects, is the recommendation layer this points toward (Najem et al., 2026).

An integrity outcome joins the same pipeline. Akçapınar (2026) predicts AI-assisted cheating risk from early-semester LMS traces (AUC 0.763) and recommends acting on it only through low-stakes outreach, with the decision threshold chosen for reach rather than accusation: dropping it to 0.30 identified 21 of the 23 high-risk students, at a precision of 60%.

The outcome ladder: what each measure actually means

The word "success" hides at least five different measurements, and AI support does not move them equally. Distinguishing them is the most useful thing this page can do.

- **Task completion** is a single, dated, binary action the student controls and the institution observes within days — registering by a deadline, filing a form, enrolling in Early Start. It is where nudges work, and the effects can be large and immediate (34 percentage points, then 2, in the CSUN registration reminder).

- **Credits (units enrolled and earned)** are cumulative and depend on course availability, sequencing, and how many terms a student can afford. In the CSUN evaluation no significant treatment effect appeared on units enrolled, earned, or cumulatively earned.
- **Persistence** is continuation across terms — enrollment by semester sequence — and it did not move either, at N = 8,708 with power to detect effects of 0.05 standard deviations or larger.
- **Retention** is the institutional rate that persistence produces, and it is usually reported at the program or cohort level. Course-level DFW rates are the closest thing to a leading indicator in this literature, and they moved modestly (−3 percentage points in each course of the Georgia State trial).
- **Graduation** is the terminal, multi-year outcome. Control mean graduation by the fourth year was 0.190 in the CSUN study, and the treatment effect on it was not statistically significant.

The authors' explanation for the pattern is the page's central claim: a reminder acts on a decision that is discrete and near-term, while persistence and GPA are cumulative and shaped by instruction, finances, employment, family circumstances, and prior preparation. They conclude that communication through a tool like this, **on its own**, may be insufficient to change them — and that the nulls are precise rather than underpowered. Early registration still carries institutional value for staffing and space planning even where learning outcomes do not move.

Equity and the risks of acting on a score

Support systems act on students, which makes their failure modes different from a tutor's. A stress test of six post-hoc fairness interventions on a replicated vendor-controlled early warning system built from 168,550 student records found the interventions failing to deliver the fairness they promised (McConvey et al., 2026). A student-advocacy review organizes the risk surface around admissions, recruitment and financial aid, and **student-success services** — the areas where institutional AI bears most directly on students (Student Defense, 2026). Privacy and equity are structural here rather than incidental: federated learning exists because sharing student records across institutions is unacceptable, and the human-in-the-loop component in the CSUN program is what the authors argue reaches students who ignore email and phone. Administrators answer what the chatbot could not, then fold the answer back into its knowledge base.

The institutional conditions

Durability in this literature is an organizational property, not a technical one. The CSUN program survived four years because the channel was centrally owned, jointly overseen by the Office of Undergraduate Studies and the Office of the Registrar, and written by a single communication specialist for a consistent voice. Its targeting decayed for an equally organizational reason: because student data was not centralized, a financial-aid reminder required one office to identify non-filers and another to pass the subset along, and that friction was burdensome enough that targeted campaigns fell from 36% of all campaigns in AY2018-19 to 6% by AY2022-23. Where the work sits, who owns the data, and whether cross-unit coordination is sustainable decide what a support system can actually do — which is why this page carries Change Management, AI Governance, and Educational AI Policy as facets rather than treating deployment as an IT decision.

Connections to related concepts

Student support connects to Student Experience as the student-facing counterpart — the same technologies seen from the student's side rather than the institution's — and to Help-Seeking for the mechanism by which students who need support actually obtain it; outreach and course-specific assistants are both attempts to lower the cost of asking. Learning Analytics owns the prediction that feeds allocation, Learner Modeling and Adaptive Instruction and Knowledge Tracing the models underneath it, and Recommender Systems and Learning Paths the recommendation layer. It connects to Well-Being through campus mental-health and prevention systems, to Career Development and Readiness as the outcome that follows completion, to Equity and Privacy through the risks of acting on scores, and to Administrators, Stakeholders, and Change Management as the roles and processes that decide whether any of it is sustained. Learning Gains is the adjacent measurement node: this page's outcomes are administrative rather than instructional, and the two do not move together.

Common Misconceptions

"Predicting which students will struggle is the intervention." Prediction is the input to support and is not support. The corpus separates these deliberately: a registration reminder and a retention program are different interventions with different evidence, and the research suggests one does not buy the other. An early-warning dashboard that ends in a score has added measurement without adding help.

"A retention programme that raised persistence proves the AI worked." It proves the program did, and the AI layer must be evaluated separately from the outreach it triggers. A four-year randomized study of CSUNny, a non-generative text-message chatbot at California State University, Northridge, followed **two undergraduate cohorts (N = 8,708)** through **eight semesters** with **annual opt-out rates never exceeding 4%** — a strong receptivity result about *messaging*, and not evidence that a generative or predictive system would achieve the same.

"The outcome ladder collapses: engagement is retention." Each rung measures something different — opting in, responding, persisting, completing — and a program can move the lower rungs while leaving the upper ones flat. Reporting the responsive share as a success commits precisely that substitution.

"An equity concern is a reason to stop using the data." It is a reason to act on scores carefully. Acting on a predictor can distribute support and can distribute suspicion, and the risk concentrates on the students the model classifies least favorably — which makes the remedy governance of the use, not abandonment of the measurement.

Connected Concepts

- Higher Education — the sector umbrella this page sits under
- Student Experience — how AI lands on the student's own experience
- Learning Gains — whether learning happened, the instructional outcome this page does not measure
- Learning Analytics — prediction, early warning, and predictive analytics
- Learner Modeling and Adaptive Instruction — the modeling layer beneath risk prediction

- Knowledge Tracing — fine-grained skill and mastery estimation
- Recommender Systems and Learning Paths — recommending courses, resources, and paths
- Help-Seeking — how students come to ask for support
- Well-Being — campus mental health, prevention, and intervention
- Career Development and Readiness — the outcome after completion
- Administrators — the role that owns and runs support systems
- Stakeholders — who has a claim on institutional AI decisions
- Change Management — sustaining the program after the pilot
- AI Governance — policy and oversight for institutional AI
- Educational AI Policy — the policy context for institutional deployment
- Equity — who the system reaches and who it misses
- Privacy — student records, data sharing, and federated approaches
- Human-in-the-Loop — human judgment inside an automated support flow
- RCT — the design behind the strongest evidence here

Connected Articles

- Sustaining AI-enabled student support: A four-year implementation and impact study — four-year randomized evaluation of a university support chatbot: task completion moved, graduation and GPA did not
- Let's Chat: Leveraging Chatbot Outreach for Improved Course Performance — pre-registered multi-semester outreach trial: higher A/B rates, modest DFW shifts, one demographic exception
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — 4,500 synthetic vignettes: limited sensitivity to student need and cross-model inconsistency in support recommendations
- From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support — the actionability gap: recourse must be feasible and checkable, not merely model-valid
- Fairness Theatre: Evaluating Post-Hoc Fairness Interventions in Vendor-Controlled Early Warning Systems — six post-hoc fairness interventions on a vendor early warning system built from 168,550 records
- Analysis and Prediction of At-Risk Students Using Machine Learning Algorithms — supervised classifiers identifying students before withdrawal
- Predicting Student Attrition in Competitive Programming: A Large-Scale Study Integrating Survey Insights and Global Behavioral Logs — behavioral logs plus psychographic survey predicting attrition
- Federated and explainable learning analytics for privacy-preserving academic risk modeling across heterogeneous educational institutions — federated risk modeling across institutions without sharing raw student data

- From Precision Medicine to Precision Education: A Vision for AI-Powered Student Digital Twins, Preventive Student Success, and Career-Aligned Academic Pathways — digital twins and "preventive student success" as a vision
- From learning analytics to educational interventions: Enhancing decision-making and learning design — seven enablers for closing the loop from analytics to intervention
- Reducing Barriers to Academic Support: Evaluating a Course-Specific RAG System for Addressing Help-Seeking Disparities in Higher Education — a course-specific assistant aimed at lowering the cost of asking for help
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — tutoring take-up tested separately from learning
- Behavioral clustering for adaptive learning object recommendation in higher education using learning analytics for personalized student success — six behavioral profiles mapped to recommended learning objects
- Jointly predicting courses and grades using a transformer-based model — joint prediction of courses and grades for planning
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education — interpretable module-level progress prediction
- From digital transformation to intelligent classrooms: artificial intelligence, adaptive leadership, and service delivery in global higher education—a systematic literature review — 155 studies of AI, leadership, and service delivery in higher education
- Artificial intelligence in educational leadership: a comprehensive taxonomy and future directions — ten-domain taxonomy of AI in educational leadership
- Students at Stake: Risks of AI Deployment in Higher Education — student-side risk surface: admissions and aid, student-success services, and instruction
- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach — campus well-being support spanning prevention and intervention
- People offload empathy when they think AI can give it instead — Four studies on empathy offloading: believing AI can supply emotional support lowers what people supply themselves (Shastry & Gray 2026)
- CourseGraph: Finding overlaps and differences in Computer Science courses across universities — course equivalence for transfer credit and mobility
- Credentials That Carry Their Evidence: Credential design, dynamic tiering, and approved use when AI agents can do the work — what a completion record means when an agent can do the work
- Early Prediction of AI-Assisted Cheating Risk in Online Exams Through Learning Analytics — Akçapınar (2026) — Predicting AI-assisted cheating risk early, and the threshold trade-off for low-stakes outreach

Connected FAQs

- How Can AI Agents Support Students and Instructors?
- How Do We Write and Implement an Institutional AI Policy?

Social Norms of AI Use

> **Social norms of AI use** — the informal, locally enforced rules that decide when learners and instructors may use generative AI, how openly they can admit to it, and what counts as cheating in practice rather than in policy. The corpus is thin on norms as a topic and thick on the mechanisms that produce them. Learners cannot reliably infer each other's AI use: the median correlation between a perceiver's estimates and their own self-reported usage profile was r = .73 at both waves, and rank accuracy for the *kind* of AI use was r = .34 at the second wave. Shame and guilt regulate visibility rather than use, producing hiding and selective disclosure instead of behavior change. Disciplinary norms diverge sharply: AI-integrated assignments appeared in 27% of business syllabi and 5% of humanities syllabi across 31,000 courses. And the formal Ethics literature routes the fewest and least actionable norms to end users, meaning the people subject to classroom norms are largely absent from the documents that discuss them.

Questions to Consider

- If students cannot tell who is using AI, what are the informal rules actually based on?
- Where do AI norms come from when an institution has no policy, or when the policy contradicts what instructors say in class?
- Why would a student who has never used AI report more guilt about it than a student who uses it weekly?
- What does shame accomplish that a policy cannot, and at what cost to asking for help?
- Does surveillance change behavior, or only how visible that behavior is?
- Whose norms dominate in a group assignment, and who absorbs the cost of the group's shared AI habits?
- Should students have a hand in writing the norms they are held to?

Introduction

Formal AI Regulation in Education of AI in education arrives as policy: acceptable-use statements, syllabi clauses, detection procedures, proctoring systems, honor codes. Everything students actually experience, though, sits underneath that layer. A classmate who never mentions using ChatGPT, an instructor who says "I don't care how you write it" and then bans it in the syllabus, a study group that has quietly settled on what is fair, a department where everyone assumes the grading curve has already shifted. These are norms: shared expectations about acceptable behavior, enforced by approval, disapproval, and the risk of being seen.

This page collects what the evidence base says about that layer. It is worth separating carefully, because "hidden curriculum" is often used loosely to mean anything unofficial. Here the subject is narrower: the operative rules about AI use, how they form, how they are enforced, and how weak the connection is between them and the written rules. The corpus has almost no study that measures norms directly, which is

itself a finding. What it has is repeated evidence about the mechanisms: inference, disclosure, emotion, and the disciplinary variation that shapes what any local norm can become.

What students believe about each other

Norms require information about other people's behavior, and that information is worse than most instructors assume. A study of student pairs tracked how accurately learners judged a partner's AI use across pair-programming sessions. Against each partner's own self-reported usage profile, the median correlation was r = .73 at both waves, high enough to feel like knowledge and low enough that many individual estimates were wrong. Rank accuracy for the type of AI use was r = .34 at the second wave, and 25% of teams became worse at judging their teammates over time.

Two details matter for norms. First, misalignment did not shrink with repeated face-to-face work. Familiarity did not produce accuracy, which undermines the assumption that norms stabilize as groups get to know each other. Second, the authors' proposed fix was structural rather than attitudinal: shared prompt histories, AI-use annotations, or peer-visible records of AI-supported work. Making AI use visible is a different project from making students more honest or more perceptive about it, and only the first one has evidence behind it.

Visibility, shame, and selective disclosure

If peers cannot see AI use accurately, then the rules that develop around it are enforced largely through social risk. An interview study with 19 computing students examined shame and guilt as social regulators and found that they govern disclosure rather than use. Students described hiding behaviors and selective disclosure, and they reported shaming themselves, their peers, and their faculty. The important negative result is that these emotions coexisted with continued AI use, generating cycles of reduced Learner Agency and moral tension rather than prompting anyone to stop.

That pattern relocates the norm from "use or don't use" to "admit or don't admit." A classroom can have a strong anti-AI norm on paper, widespread use in practice, and an equilibrium of silence in between, without anyone being confused about what the rule says. It also predicts where the cost lands: on learners who are least able to manage the social risk, and on learners whose visible use carries different consequences.

The instructor side of the same emotion is measurable. A survey of faculty using a four-item AI Guilt Index (Cronbach's alpha = 0.88) found anticipatory guilt exceeding experienced remorse: the mean index score was 2.39 (SD = 1.01), with 22.9% of participants above the midpoint. Non-users of AI reported *higher* guilt (M = 3.25, SD = 1.04, n = 8) than users (n = 101, M = 2.32, SD = 0.97), t(8.39) = 2.00, p = .078, and the remorse item separated the groups more sharply, t(7.79) = 2.44, p = .041. Cluster analysis produced four profiles: Comfortable Adopters (26.6%), Guilty Non-Users (29.4%), Cautious Users (28.4%) and Morally Distressed Avoiders (15.6%), with differences confirmed on guilt, F(3, 105) = 22.13, p < .001, eta-squared = 0.39.

A norm that makes people who have not acted feel guilty is doing its work through anticipation. That is a real regulatory mechanism, and it is invisible to any policy audit that looks only at what faculty and students do.

A survey of 409 undergraduates puts the same mechanism into a regression: perceived peer disclosure and comfort with instructors were the strongest predictors of a student's own disclosure, ahead of moral

disengagement (Qu and Wang (2026)). What a student treats as the norm is what they believe their peers do, which is the impression the perception study above shows to be systematically coarse. Disclosure, on this evidence, is a response to a believed norm rather than to a written rule or to a personal ethical standard.

The local rulebook: disciplines and classrooms

Norms are local, and the evidence on how local is unusually concrete. An analysis of 31,000 course syllabi found that AI-integrated assignments ranged from 27% in business to 5% in the humanities. The range is not a gap in policy compliance; it reflects different disciplinary judgments about what the work is, what practice is worth, and which skills a credential is supposed to certify. The authors' recommendation follows from that: grant instructors autonomy within disciplinary norms rather than issuing one-size-fits-all mandates, because the mandate would have to be written for an average that does not exist.

The classroom layer can also contradict the document layer in the same course. Interviews with marketing students found peer norms and "keeping up" driving adoption, with word of mouth described as the biggest promotion AI has, sustained by fear of falling behind. The same study recorded a contradiction that instructors will recognize: some classes required AI while the syllabus banned it, and an instructor's in-class encouragement did not always survive into the written policy. When those two disagree, students treat the spoken norm as the operative one, and the syllabus as a liability to be managed.

Group work is where informal norms do the most work, because the unit being graded is collective. A study of 52 pre-service teachers across 15 focus groups identified distinct patterns rather than one enthusiasm-to-avoidance line, with groups negotiating what counted as legitimate assistance in the absence of a shared rule. Any student who has watched a group quietly settle on one member's AI use has seen a norm being written in real time, without a policy process and usually without a record.

Formal ethics, lived norms

The professional literature on AI ethics and the classroom norm it is supposed to reach are drifting apart, and the gap is documented. A systematic review of ethical values and norms extracted norms from 15 articles and mapped them onto four stakeholder sets from Smuha (2022). Developers received the most norms, followed by educational institutes and regulators. End users received the fewest and the least actionable, with no norms addressing students directly on non-discrimination, data stewardship, or educational aptness, and student voices essentially absent from the material.

The result is a literature that specifies obligations for the people building and procuring AI, and leaves the people living with it in the classroom to work out their own rules. That is a plausible explanation for why the norms students describe, as in the shame and guilt study, are so often about visibility and reputation rather than about the values the ethics documents name. The two systems are regulating different things.

Why surveillance does not settle norms

When institutions try to replace informal norms with formal monitoring, the evidence is consistent and unflattering. A four-wave study of 1,760 students across 105 courses found that online proctoring significantly increased test anxiety, and had no effect on the temptation to cheat. It also did not change

perceived difficulty or exam performance. The anxiety cost was concentrated among already-vulnerable students, including those with weaker home environments and less reliable technology.

Two further studies explain why surveillance is a poor tool for norm-setting. A scoping review of remote proctoring found that monitoring was widely perceived as deterring misconduct, yet South African lecturers reported continued dishonesty despite active monitoring, a situation Khalil et al. (2022) call “subterranean ethics,” and frequent minor alerts generated false positives and faculty review work. Surveillance buys compliance through fear of detection rather than commitment to a shared standard. A model of assessment under imperfect information sharpens the mechanism: deterrence depends on a detector’s ability to discriminate between hidden use and legitimate work rather than on its catch rate, and when false positives rise faster than true positives, students disengage from the system instead of complying with it. Its further result is the one that bears directly on norms: monitoring lowers the attractiveness of hidden use, but it does not increase disclosure. Students move toward openness only when reporting is safer or more valuable than concealment, and a prohibition can make concealment more attractive than compliance.

The procedural-justice argument draws the conclusion: because skilled or lightly edited AI use is undetectable in the general case, a misconduct procedure built on detection produces unfairness without effectiveness, and the answer is better Assessment, not better surveillance.

The cost of that substitution shows up in where faculty and students actually talk. Across 253,222 AI-related records from 26 education subreddits, a third of all faculty–student threads were detection or enforcement disputes, students opened 68.4% of them, and negativity predicted engagement ($\rho = -0.72$) — adversarial conflict, not deliberation, is the highest-volume form of cross-role contact about GenAI (Yüce et al. (2026)).

What this means for practice

- **Make use visible instead of inferring it.** Students cannot judge each other accurately, and repeated collaboration does not fix it. Lightweight shared records of AI-supported work, annotations, or prompt histories give a group something factual to reason about.
- **Expect the spoken norm to beat the written one.** If what is said in class contradicts the syllabus, students will follow the classroom. Alignment between the two is worth more than a stricter clause.
- **Treat disclosure as a design problem, not a virtue problem.** Disclosure becomes likely when reporting is safer or more valuable than hiding. That means making disclosed use legible in the assessment itself, rather than asking for honesty as a character trait.
- **Respect disciplinary variation.** A 27% to 5% spread across departments is not inconsistency to be normalized away, it is different judgments about what the credential certifies. Institution-wide mandates tend to be written for a discipline that does not exist.
- **Do not reach for monitoring to set norms.** Proctoring raised anxiety without changing the temptation to cheat in the strongest study available, and it concentrates that cost on the least advantaged students.
- **Ask who is missing from the norm.** The ethics literature assigns students almost no obligations and takes little account of their judgment, while the classroom assigns them a great deal and enforces it socially. Closing that gap is a curriculum question, not a compliance question.

Common Misconceptions

“Students know how much their peers use AI.” They overestimate their own knowledge of it. The median correlation between a perceiver’s estimates and their own self-reported usage profile was **r = .73 at both waves**, while rank accuracy for the *kind* of AI use was only **r = .34**. Students can tell roughly how much, and cannot tell what kind — which means norms form around an impression that is systematically coarse.

“Publishing a policy establishes the norm.” The local rulebook is written in practice, not in policy text, and domains diverge sharply: AI-integrated assignments appeared in **27% of business syllabi and 5% of humanities syllabi** across **31,000 courses**. A student’s operative norm is their own discipline’s, and an institution-wide document does not overrule it.

“Shame and guilt discourage AI use.” They regulate visibility rather than use: shame and guilt regulate visibility, producing hiding and selective disclosure instead of behavior change. The observable effect of a shaming norm is less honest reporting, not less use.

“Surveillance would settle the norm by making use visible.” Making behavior visible does not resolve what the norm should be; it changes what people are willing to disclose. The measured pattern is selective disclosure already, so a monitoring regime applied to it measures the concealment rather than the conduct.

“Norms are informal, so they are outside institutional reach.” They are locally enforced and locally changeable, which makes them more tractable than policy: a course team’s explicit practice is a lever precisely because it is where the operative rule is set.

Connected Concepts

- Academic Integrity — the formal rulebook these norms grow alongside
- AI Use and Disclosure Statements — the practice norms regulate most directly
- Framing AI Use for Students — how a classroom states its expectations
- Reducing AI Misuse — the instructional counterpart to norm-setting
- Learner Identity — who a learner is taken to be when AI use becomes visible
- AI Detection — the technical response that mostly fails
- Remote Proctoring — surveillance as an attempted substitute for norms
- Trust — what norms and disclosure both depend on
- Equity — who absorbs the social cost
- Help-Seeking — the behavior shame suppresses first
- Group Work — where group norms are negotiated
- Student Experience — the lived side of all of this
- Anxiety and Stress — the affective residue
- AI Governance — the formal layer these norms sit under
- Ethics — the literature that has least to say to students

Connected Articles

- Students' Perception Accuracy of Partners' AI Use and its Relation to Collaboration Performance — Students' perception accuracy of partners' AI use and its relation to collaboration performance
- "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education — Shame and guilt as social regulators of AI use in computing education
- How Instructors Regulate AI in College: Evidence from 31,000 Course Syllabi — How instructors regulate AI in college: evidence from 31,000 course syllabi
- The AI guilt complex: Moral emotions and ethical dilemmas in academic technology adoption — The AI guilt complex: moral emotions and ethical dilemmas in academic technology adoption
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Identifying the ethical values and norms for artificial intelligence in education
- The fear of Big Brother: The potential negative side-effects of proctored exams — The fear of Big Brother: the potential negative side-effects of proctored exams
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Under surveillance: mapping remote proctoring practices in nursing assessment
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — Assessment design under imperfect information: generative AI, disclosure, and student response
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Detecting the undetectable: misconduct procedures after generative AI
- Cheating or competing? University students' experience of AI marketing and what it means for AI literacy programming — Cheating or competing? AI in marketing education
- Students' agency in GenAI-mediated group assessment: An ecological-emergent perspective — Agency in GenAI-supported group assessment
- ChatGPT vs Teachers vs Students: Large-Scale Analysis of Generative AI Discourse in Education Communities on Reddit — Reddit discourse analysis: faculty–student contact concentrates in detection and enforcement disputes (Yüce et al. 2026)
- To disclose or not to disclose: Peer influence and psychological factors in students' use of generative artificial intelligence — 409 undergraduates: perceived peer disclosure and instructor comfort predicted disclosure ahead of moral disengagement (Qu & Wang 2026)

Connected FAQs

- How Do I Write a Course AI Policy and Communicate It to Students?
- How Can I Reduce AI Cheating in My Course?
- Should We Use AI Detectors?

Lifelong and professional learning

Career Development and Readiness

> **Career development and readiness** — the processes and capacities that prepare learners to build, adapt, and sustain a career in an AI-disrupted labor market: career adaptability, employability, workforce readiness, and the skills (including AI Literacy) that employers value. In the AI-in-education context this concept is increasingly important because AI both reshapes the skills graduates need and generates **career-related AI anxiety** about job displacement — making career readiness a protective factor for student Well-Being.

Questions to Consider

- Career readiness here is framed as adaptability — the capacity to navigate, adjust, and thrive across changing roles — rather than just credentialing. How does that reframing change what you think a career-focused education should actually build?
- Research consistently shows career adapt-abilities significantly reduce AI anxiety about job displacement. Why might being more adaptable to career change make a student feel less anxious about a technology that threatens their current job prospects?
- One key claim is that AI literacy on its own does not make a graduate career-ready, because readiness also runs through what students believe they can adapt to. Can you think of someone who is highly AI-literate yet still anxious or unprepared for the workforce? What were they missing?
- An ITHAKA S+R report documents a skills-prioritization gap: instructors emphasize critical, responsible use of AI, while employers favor workflow automation and human-AI teaming skills — and they agree on only one of 26 AI skills. Why do you think classroom and workplace priorities diverge so sharply, and who should adapt?
- The report finds most institutions lack both a consensus on what AI skills look like and an assessment framework for them. If you had to define and assess ‘workforce-ready AI skills’ for a graduating student, what would you measure and how?
- Fear of replacement by AI is identified as a primary driver of AI anxiety, and career readiness is positioned as a protective factor for student well-being. How should an education program address the anxiety itself, rather than only adding skills?

Introduction

As AI transforms occupations, education’s role in career development has broadened from credentialing toward building **adaptability** — the capacity to navigate, adjust, and thrive across changing roles. This concept connects education to employability and links to Anxiety and Stress: students with stronger career adapt-abilities experience less AI anxiety.

How career development and readiness appears in the knowledge base

- **Career adaptability reduces AI anxiety.** Wang (2026) shows career adapt-abilities significantly and negatively predict AI anxiety among English majors, with core self-evaluations partially mediating the relationship; the low-adaptability group showed the highest AI anxiety. Duan et al. confirm the mechanism with SEM: AI anxiety impairs career decisions largely through eroded career adaptability (63.35% of the total effect), and self-efficacy offered limited buffering. Üstün & Danacıoğlu add that AI anxiety and negative AI attitudes predict post-graduation job-finding anxiety across 1,057 students, with women, social-science majors, and second-years most affected. Dağ et al. extend this to health-sciences students (821, r = 0.233). Career readiness is thus an empirically validated buffer against career-related AI anxiety.
- **Readiness tracked engagement, not threat level.** In Song et al. (2026), the most AI-anxious profile still reported the highest career crafting (4.222) and self-perceived employability (3.964), alongside the favorable profile that did not differ significantly — so anxiety level did not index career readiness.
- **AI literacy is necessary but not sufficient.** Testa et al. argue AI literacy alone is not enough for career readiness — students also need adaptability and positive self-evaluations, directly linking AI Literacy to career outcomes. Hendrawan and Lestari (2026) test it quantitatively with 455 final-year students in Jakarta: career adaptability carries a significant indirect effect (β = 0.173), and growth mindset does not moderate the path at all, so adaptability rather than mindset does the work.
- **A construct map, not a measured pathway.** Kong and Zhang (2026) read 46 publications as a critical narrative review and place three learning processes between AI-supported learning and employability: cognitive engagement with self-regulation, self-efficacy with motivational regulation, and career adaptability as the bridge to career exploration. They classify career adaptability as a career-development resource, not an employment outcome. Because the synthesis collects no data of its own, it offers testable propositions rather than an effect size, and every figure it reports belongs to an included study. A twelve-week UK module with 120 non-STEM students, for instance, associated AI capital with employment status six months after graduation, which a non-randomized single-course design cannot attribute to the course.
- **Employer and graduate perspectives.** The ITHAKA S+R report (500 US four-year-college instructors, compared against 200 US employers) documents a **systematic skills-prioritization gap** between instructors and employers that signals the workforce demands shaping higher education curricula. Instructors and employers agree on the importance of only one of 26 AI skills (setting realistic expectations for AI-augmented work): instructors prioritize a *critical, responsible-use* orientation (attribution, human accountability, limits of AI), while employers favor *workflow, automation, and human–AI teaming* skills. The report finds only three of 26 skills are taught by half or more instructors — the under-taught categories (workflow redesign, automation, technical integration) are precisely where employer demands diverge most — and that most institutions lack both a consensus on what AI skills look like and an assessment framework for them. For career development, this means graduates' readiness depends on closing a real,

measurable gap between what employers value and what curricula teach, not just on adding AI literacy.

- **Employers respond to the signal, not only to the skill list.** Boyd-Swan and Reynolds (2026) randomized about 1,750 US hiring professionals across two framings of student AI use before they rated otherwise similar resumes. Framing AI as an assistive tool raised concern only modestly and did not penalize applicants; framing it as a substitute for student effort and ability lowered interview likelihood and, more sharply, willingness to negotiate salary, with high-GPA applicants taking the larger penalties. Both treatment groups named in-person testing as the remedy that reassured them, which makes readiness depend on whether a credential still carries evidence employers will accept.
- **AI-free hiring screens stop certifying what the work requires.** In interviews with 23 Indian engineering students and recent graduates, all but one used AI to prepare for placement screens that excluded it while graduates described workplaces that expected AI from the first day, so on signaling theory a CGPA produced with AI help no longer separates candidates by cost (Goutham & Gu (2026)).
- **Course policy as a workforce-competency decision.** McCorkle's (2025) design case makes the trade-off explicit at task level: for each step of a semester project the instructor pairs an emerging GenAI workforce competency (prompting for objectives, generating images, writing scripts, text-to-speech narration) against the need to assess a foundational skill, and permits AI only where the competency wins. That is a concrete way to build the workflow skills employers value (Prompt Engineering, evaluation of LLM output) into existing assignments rather than adding a separate AI course.
- **AI already mediates career preparation itself.** Loidl, Cao and Huang (2026) surveyed 102 undergraduates at one Midwestern R1 university and found about 81% had used ChatGPT for employability-related activities in the previous 12 months, led by resumes (52.94%), workplace communication (38.24%), and cover letters (35.29%), which the interviews read as tailoring and rehearsal work rather than outsourcing; career readiness therefore has to be built on preparation that the tool already mediates, not only on the capacities this page otherwise describes.
- **Sector-specific readiness frameworks.** Workforce readiness for smart manufacturing and the future of the engineering/computing workforce translate general employability into discipline-specific competency frameworks.
- **What faculty expect AI to displace, and what that is not.** In ten interviews in an AI-focused engineering department, faculty disagreed about how generative AI would reshape work, naming coding, writing and information work as near-term vulnerable, while offering no labor-market evidence for those expectations (Sadik (2026)).
- **Workforce transitions.** The ICT career aspirations study examines how students' career intentions shift in response to technological change.
- **Theoretical grounding.** The AI Anxiety comprehensive analysis identifies the **fear of replacement by AI** as a primary driver of AI anxiety — the career dimension this concept addresses head-on.

Career readiness as a protective and developmental goal

A recurring theme is that career development in the AI era should be a **deliberate educational goal**, not an afterthought: building career adapt-abilities, core self-evaluations, Self-Efficacy, and employer-valued AI skills, while directly addressing the anxiety students feel about AI displacement. This links career development to Workplace Learning, Self-Efficacy, Motivation, and Anxiety and Stress, and positions education as both a skills pipeline and a source of psychological readiness.

Connections to related concepts

Career development and readiness connects to Workplace Learning (the vocational skills dimension), AI Literacy (the AI-competence dimension), Self-Efficacy and Motivation (the psychological resources that support adaptation), Anxiety and Stress (career anxiety as a key component), Higher Education and K-12 (the settings where readiness is built), and Student Experience (career concerns as part of the learner experience).

Common Misconceptions

- **"AI anxiety is a general disposition you can reassure away."** Duan et al. confirm with SEM that AI anxiety **impairs career decisions largely through eroded career adaptability (63.35% of the total effect)**. The mechanism is specific: anxiety works by removing the capacity to adapt, so reassurance aimed at feelings misses the mediator that carries the effect.
- **"Career adaptability is a soft skill secondary to technical competence."** Wang (2026) shows career adaptability **reduces AI anxiety**, which makes it an upstream intervention rather than a downstream outcome. Building adaptability addresses the mechanism; treating it as a nice-to-have leaves the mediator intact.
- **"Anxiety about AI is evenly distributed."** Üstün & Danacıoğlu find AI anxiety and negative AI attitudes predict post-graduation job-finding anxiety across **1,057 students**, with different patterns for **women and social-science students**. A uniform intervention misallocates support.

Connected Concepts

- Workplace Learning
- AI Literacy
- Self-Efficacy
- Motivation
- Anxiety and Stress
- Higher Education
- Student Experience
- Well-Being
- Student Support and Success — the outcomes that follow completion: persistence, retention, and graduation

Connected Articles

- From AI-Free Gates to AI-First Work: How Engineering Students in India Navigate University Education and Campus Placements Without AI Guidelines — From AI-Free Gates to AI-First Work: How Engineering Students in India Navigate University Education and Campus Placements Without AI Guidelines
- Early evidence on employer responses to college student use of generative AI — Survey experiment with ~1,750 US hiring professionals: substitution framing lowered interview and salary-negotiation willingness, most for high-GPA applicants (Boyd-Swan & Reynolds 2026)
- AI literacy and graduate employability in the age of artificial intelligence: The mediating role of career adaptability and the moderating role of growth mindset — PLS-SEM evidence that AI literacy reaches perceived employability through career adaptability, with growth mindset adding nothing (Hendrawan & Lestari 2026)
- Designing an Aligned Generative AI Course Policy: An Equitable and Transparent Learner-Centered Approach — Assessment-vs-workforce-competency trade-offs decided task by task (McCorkle 2025)
- The impact of career adapt-abilities on AI anxiety among English majors: a dual perspective analysis based on core self-evaluations at the person- and variable-centered — career adapt-abilities reduce AI anxiety
- AI literacy alone is not enough: Student AI readiness and career adaptability in business and management education — AI literacy and career adaptability in business education
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — AI skills for college graduates: instructor and employer priorities
- A Conceptual Framework for Enhancing Workforce Readiness for Smart Manufacturing in the AI Era — workforce readiness for smart manufacturing
- Artificial Intelligence (AI) and the Future of the Engineering and Computing Workforce: A Systematic Review of Gray Literature and Document Analysis of U.S. Reports (2020–2025) — AI and the future of the engineering/computing workforce
- Learning after COVID-19 and the ICT career aspirations: Are students entering the AI era with weaker skills? — ICT career aspirations after COVID-19
- AI Anxiety: A Comprehensive Analysis of Psychological Factors and Interventions — AI anxiety and the fear of replacement
- The impact of AI anxiety on career decisions of college students — AI anxiety impairs career decisions via career adaptability (63.35% mediation)
- The Role of Artificial Intelligence Anxiety and Attitudes Toward Artificial Intelligence in University Students' Job Finding Anxiety — AI anxiety and attitudes predict job-finding anxiety (1,057 students)
- Artificial intelligence perceptions and career anxiety among health sciences students — AI anxiety predicts job-search anxiety in health sciences (r=0.233, 821 students)
- Beyond Positive or Negative: Latent Profiles of University Students' AI Attitude and Their Career-Development Correlates — Four AI-attitude profiles: career crafting and employability tracked engagement, not anxiety

- Preparing AI-Ready Engineering Talent: Faculty Perspectives on Generative AI, Foundational Competence, and Workforce Readiness — Faculty forecasts are predictions, not evidence about employment
- Artificial intelligence in higher education and graduate employability: cognitive engagement, self-efficacy, and career adaptability in the AI era — A narrative review's construct map from AI-supported learning to employability

Lifelong Learning

> **Lifelong learning and AI** — how AI supports continuous education and skill development beyond formal schooling, and how it reshapes adult and workplace learning. AI can personalize, scaffold, and make learning-on-demand more accessible for adults, while also raising questions about autonomy, self-direction, and who controls the learning process in AI-mediated environments.

Questions to Consider

- Think about the last new skill you learned outside formal schooling — on the job, online, or self-taught. Who decided what to learn, how to learn it, and when you were 'done'? How would AI change that picture?
- A central question in the page is autonomy: as AI participates in identifying your learning needs, setting your goals, and even producing content, what remains genuinely self-directed in your own learning?
- Formal education treats time as fixed and curricula as sequential. The page proposes 'Learnity graphs' — interconnected units of knowledge learners navigate flexibly across a lifetime. What do you gain, and what do you risk losing, by freeing learning from a fixed sequence?
- AI can both support adult learners and change which skills adults must continuously update. If AI keeps reshaping your field, what capabilities would you invest in that no tool can simply give you?
- Lifelong learning is often framed as an individual's responsibility. But access across the lifespan is also an equity question. Who gets the time, resources, and support to keep learning as an adult — and how might AI widen or narrow that gap?

Introduction

Lifelong learning refers to continuous education throughout life — upskilling, reskilling, professional development, and informal learning beyond formal degrees. AI is increasingly central to this, both as a tool that supports adult learners and as a force that changes the skills adults must continually update.

How lifelong learning appears in the research

- **Design guidelines for adult learning:** Research from the AI-ALOE institute synthesizes empirically grounded design guidelines for AI-powered adult-learning technologies, emphasizing practical, context-sensitive support.
- **AI-guided skill acquisition:** AI-guided audio/video learning shows how AI can scaffold the consume–understand–imitate stages of skill acquisition, adapting media to the learner.
- **From fixed curricula to adaptive structures:** Learnity graphs propose rethinking fixed higher-education curricula as interconnected units of knowledge that learners can navigate flexibly across a lifetime.

- **Autonomy and self-direction:** Andragogy and cognitive delegation revisits adult-learning theory under AI-mediated cognitive delegation, asking what remains self-directed when AI participates in identifying needs, setting goals, and producing content.
- **What adults want from that delegation.** In interviews with 20 of 60 screened adult learners at three US universities, learners described AI as a collaborative learning agent they learn from and with, not an answer-giving oracle. They said they did not want a perfect, zero-error system so much as one that stays in the loop and adapts to them (Kim et al., 2026). Self-direction, on this evidence, is something adults expect to keep inside the interaction rather than hand over to it, which is the design target the autonomy question needs.
- **Policy and community:** AI in lifelong-learning policy and community-centered AI education address the institutional and equity dimensions of adult AI learning.
- **Expertise regeneration is itself at risk.** In the most AI-exposed US occupations, workers aged 22–25 saw a 16% relative employment decline (Oct 2022–Sep 2025) while those 35–49 grew over 8%, and the deep expertise needed to validate AI outputs depends on the entry-level roles that decline removes (Lovett (2026)).

Connections

Lifelong learning connects to Adult Learners and Workplace Learning (its primary contexts), Personalized Learning and Adaptive Learning (the AI mechanisms that support it), Self-Regulated Learning and Metacognition (the learner processes involved), and Equity (access across the lifespan). It also intersects with Educational Development when educators themselves are the lifelong learners.

Common Misconceptions

“AI exposure mainly threatens entry-level tasks, so experienced workers are safe.” The employment pattern inverts part of that assumption while the expertise problem runs deeper. In the most AI-exposed US occupations, workers aged **22–25 saw a 16% relative employment decline (Oct 2022–Sep 2025)** while those **35–49 grew over 8%** — protection that attached to accumulated expertise. But the pipeline that produces that expertise runs through the entry-level work now being reduced, so the protection is time-limited in a way the cross-sectional figure hides. **Expertise regeneration is itself at risk**: if the formative work disappears, the cohort that would become the experienced practitioners is smaller.

“Lifelong learning means adults taking more courses.” Course-taking is one delivery form of a broader requirement: maintaining and rebuilding competence as the tasks change. A workforce that needs continuous regeneration is not short of course offerings; it is short of the practice opportunities where new competence is actually formed.

“Lifelong learning is a personal responsibility, so institutional design is secondary.” The regeneration problem is structural — it concerns where formative work exists at all — and individuals cannot create the work their own development requires. Framing it as motivation explains nothing about the 16% decline concentrated at the bottom of the age distribution.

Implications for Practice

For employers and training designers

- Protect the formative work that builds expertise, not only the tasks that deliver output. If entry-level work is removed, the senior practitioners of ten years hence were not hired.
- Build structured practice with feedback into continuous development, since competence regeneration depends on doing the harder version of the work under supervision, not on course completion.
- Track progression by cohort, not only by headcount. A workforce can grow overall while its entry pipeline narrows.

For educators and course designers

- Design for working adults' constraints: short, spaced, and applicative, so that practice survives contact with employment.
- Make the pathway from assisted to independent performance explicit, since the offloading risk is highest for learners whose practice is entirely tool-mediated.

For researchers and policymakers

- Report employment effects by age band rather than as an aggregate displacement figure; the 16% versus 8% contrast is the finding.
- Study where formative work is disappearing, since that is the mechanism by which current gains become future shortages.

Connected Concepts

- Self-Directed Learning
- Adult Learners
- Workplace Learning
- Personalized Learning
- Adaptive Learning
- Self-Regulated Learning
- Metacognition
- Equity
- Higher Education
- Educational Development
- Scaffolding
- Intelligent Tutoring
- Cognitive Offloading

Connected Articles

- Guidelines for Designing AI Technologies to Support Adult Learning — Guidelines for designing AI technologies to support adult learning
- AI-guided learning: Research on knowledge and skill acquisition support methods using deep learning audio-video processing techniques — AI-guided learning for skill acquisition
- Rethinking Higher Education: From Fixed Curricula to Learnity Graphs — Rethinking higher education with Learnity graphs
- What remains self-directed? Revisiting andragogy through cognitive delegation in generative AI-mediated adult learning — Andragogy and cognitive delegation in AI-mediated learning
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy — AI in lifelong learning: opportunities and challenges in adult-education policy
- Co-Designing Community-Centered AI Education for Adults: A Midwestern Case Study — Co-designing community-centered AI education for adults
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- Adult learners' perspectives of AI applications in supporting andragogy — Adult learners' perspectives on AI as a collaborative learning agent in andragogy (Kim et al. 2026)

Workplace Learning

> **Workplace learning** — the use of AI for workforce development, corporate learning, and professional skill acquisition. Professional training extends AI in education beyond formal schooling into workplace and lifelong learning contexts.

Questions to Consider

- Think of a skill you learned on the job rather than in a classroom. What made that workplace learning effective, and how might an AI coach replicate or improve it?
- The page's Workforce Readiness Level framework suggests the highest competency stages are 'gated by industry-embedded experience rather than coursework.' What does that imply for how we should train people—and for the limits of AI Simulation?
- Virtual patients and training simulators let professionals practice safely. What kinds of judgment and interpersonal skills might a simulator struggle to capture, no matter how realistic?
- The 'Dual Train Problem' is the tension between rapidly changing AI skills and the slower pace of policy and curriculum. If you could choose durable competencies to prioritize for learners today, what would they be?
- Adult learners balance work and study, often through screens. How might AI-powered professional training both enable and complicate that balancing act—especially around data, trust, and time?

Introduction

AI in professional training

- **Simulation and practice:** Virtual patient training and ATCO training simulators create AI-powered professional practice environments. In teacher education, AI role-play simulation extends this into practice-based teaching: Student GPT simulated a misconception-holding middle-school math student so preservice teachers could practice diagnosing and remediating student errors, aligning with the "approximations of practice" of practice-based teacher learning as an affordable complement to costly platforms like TeachLivE.

Wang et al. (2026) add a coaching-policy lesson: fading assistance against the learner's estimated competence cut simulator lap time 27.9% ($p = 0.005$) and failures by 3.52 per lap, whereas rule-based fading on a fixed schedule produced no reliable lap-time change. - **A voluntary, text-only rehearsal moved nothing.** Of 201 first-year medical students offered a GPT-4o patient before their first standardized-patient class, 49 used it, and nervousness, preparedness, Self-Efficacy and self-perceived competence did not differ from the 84 controls; 6 of 19 non-users who gave a reason cited technical or login problems (Jongkind et al. (2026)). - **Lifelong learning integration:** Lifelong Learning and Adult Learners research connect professional training to continuous education. - **Agents built to deliberate rather than answer.** Cowhitt and Gibson (2026) design instructional agents for teacher professional learning that withhold the answer and

press the teacher to justify a decision, drawn from 33 deliberation codes across 8 clusters. - **Public sector:** Public sector AI adoption examines training in government contexts. - **Workforce readiness frameworks:** Smith et al. propose a Workforce Readiness Level (WRL) framework that adapts the Technology Readiness Level scale into nine competency stages scored across four pillars (digital/AI literacy, cyber-physical fluency, human-machine collaboration, data-driven decision making), under a "no-thin-pillar" rule. Evidence from smart-manufacturing capstones shows the highest readiness stages are gated by industry-embedded experience rather than coursework — pointing to work-integrated learning as essential to professional AI training. - **Instructor and employer priorities diverge.** A survey of 500 US instructors and an employer panel agreed on the importance of only one of 26 AI skills — setting realistic expectations for AI-augmented work — and only three of the 26 were taught by half or more instructors (Fried (2026)). - **Domain-specific PD evidence is thin.** A systematic review of language educators (Li et al. 2026) found only three of 23 studies reported structured professional development, yet those that did converged on gains in knowledge, confidence, and identity — evidence that structured, domain-specific training (pairing technical skill with practical wisdom) is both scarce and effective, and that PD should move from awareness-raising and ethics through hands-on tool mastery to co-design of AI-enhanced lessons. - **Teacher educator professional development as model-building:** Eyal (2025) ran a year-long 180-hour course in which 22 higher-education teacher educators co-designed the Adaptive Artificial-Intelligence-Literacy Model, replacing fixed competency ladders with three inter-related axes (context fit, professional needs, dynamic development) and a 20-item reflective Self-Assessment questionnaire. The design premise is that AI literacy is situational: a pre-service teacher in a resource-limited setting, a subject teacher, and a principal need different competencies, so professional development should target role-specific judgment rather than a standardized rubric. - **A technical profession's AI practice can outrun its teaching pathway.** In a 560-record review (Scopus 426, PubMed 1, IEEE 133), Morales-Cevallos et al. (2026) found 21 empirical studies, 18 technical and only 3 educational. Their curriculum argument rests on the apprentice model's limits, algorithmic literacy as a foundational requirement, and explainability under cross-examination; yet their six-pillar framework was not prespecified or validated, and the only student sample, a K-12 program in Korea, tested no training intervention with forensic professionals. - **What training should target:** the field's measurement base lags the technology it describes. In a systematic review of 33 teacher AI literacy instruments, Zainal, Mohd Matore and Maat (2026) found that 29 (87.9%) targeted general AI concepts while only four (12.1%), all published in 2025, addressed generative AI. If instruments track what training is meant to build, that distribution marks generative-AI competence in teaching as the least measured and most urgent target for professional development. - **Workforce forecasting:** Fletcher et al. review U.S. gray literature on AI and the engineering/computing workforce, framing the "Dual Train Problem" (rapid change vs. urgent policy) and recommending that higher education prioritize durable AI competencies, Ethics and AI Governance, and skill-based credentials aligned with emerging roles (e.g., Prompt Engineering, AI auditing, AI policy) to sustain human-centered work in an automated economy. - **Skill-sustaining designs lose under throughput metrics.** de Jong (2026) argues that reflective interaction contradicts the faster-decisions, higher-throughput promise driving AI adoption in professional work: a controlled study can absorb the friction, an environment measuring performance by speed or quantity cannot, and where rivals offer equivalent support without friction, skill-sustaining designs become a competitive disadvantage — a problem the paper says may belong to organizational policy or government rather than interaction design. - **Oral assessment for workplace capability.** A TVET design study addresses a long-standing mismatch between text-heavy assessment and the verbal, situational capabilities that professional qualifications certify, using an Large Language Models

(LLMs) to support interactive oral assessment. Across four cohorts the voice format was rated realistic by 21 of 33 learners with no dissenting response on its advantage over a written portfolio, and the system ran fully offline on one laptop for up to 12 simultaneous learners, deleting recordings after 90 days and leaving scoring to assessors (Designing AI-Supported Oral Assessment in TVET). It is a concrete example of AI widening the range of assessable competence in professional-training rather than only automating existing written formats. Its cohorts, though, were Level 3 automotive and engineering classes, so the evidence sits in initial vocational provision rather than in the workplace upskilling this page covers. - **The meeting is where understanding becomes assessable.** When a generative tool drafts the analysis, a polished research update no longer shows whether a trainee understands the work, so Prunuske and Adams-Phillips (2026) propose three diagnostic windows for research meetings (metacognitive calibration, conceptual explanation, collaborative sensemaking) with prompts that surface what a summary left out.

- **Institutional conditions, not national context, explain readiness gaps.** A comparative survey of 568 university faculty in Chinese (n = 340) and Kazakhstani (n = 228) faculty development centers (Bi, Araily, Lyu & Xiu, 2026) found Kazakhstani faculty ahead on all seven GenAI readiness dimensions at baseline, with the largest gaps in disciplinary transfer, prompt design, and AI-supported assessment. Hierarchical regression dismantled the national explanation: the country difference fell sharply once prior GenAI use and recent training entered the model and became non-significant — an 80% reduction — once institutional support, perceived permission to experiment, multilingual resource access, policy clarity, and risk sensitivity were added. Exposure was unevenly distributed (a clear majority of Kazakhstani faculty had AI training in the past six months, against roughly a quarter of Chinese faculty), and Chinese faculty reported both higher policy clarity and higher risk sensitivity. Structured prompt-task training outperformed conventional GenAI familiarization on post-test prompt design by a wide margin. Faculty readiness, on this evidence, is produced by provision and permission — what a center offers and what it allows — rather than by the national system it sits in.
- **Brief training shifts judgments, not intentions.** A three-hour pre-post pilot with 100 German teachers (Mesenhöller and Böhme, 2026) found that perceived usefulness (d = .32) and perceived ease of use (d = .25) rose significantly after a short practice-oriented session on AI for differentiation, while behavioral intention did not move from an already high baseline (M = 3.07). The authors read the gap as a sign that acceptance depends on conditions a session cannot supply, such as time, infrastructure and clear institutional rules. Short formats are worth running, but pairing them with those conditions is what turns favorable judgment into use.
- **Sustained monitoring, not one-off workshops, for initial training.** A systematic review of 11 studies of AI in initial teacher training for primary mathematics (Pinto et al., 2026) found that nine interventions were a single session or a few sessions embedded in existing courses, that attitudes were usually sampled once after the fact, and that ethics appeared in only three studies. The authors argue AI competency needs to develop across the whole training sequence, from a preparatory phase into the practicum and the early years of practice, with monitoring that follows that progression.
- **Exposure and repetition, not demographics, track favorable perceptions.** In a mixed-methods study of 302 Turkish primary mathematics teachers (Ciğerci and Uygun, 2026), prior AI training (t = 3.661) and frequency of AI use (F = 41.280) were the variables most consistently associated

with positive views, while willingness (M = 3.98) and attitudes (M = 3.82) sat well above personal experience (M = 3.00). The authors treat prior training as the clearest lever schools can act on, which points to repeated, sustained use rather than a single introduction.

- **Role rotation as the load-bearing structure.** A design-based study of 62 pre-service educational psychologists in Kazakhstan (Kenzhebayeva et al., 2026) rotated students through four professional positions over eight weeks, with generative AI supplying preliminary ideas. The authors argue the value lay in the rotation rather than in the tool, since each role framed the same case differently, and later cycles showed more requests for theoretical justification. They report engagement rather than measured gains, having collected no pre-post competence measures.

Distinct from academic education

Professional training differs from academic education in its focus on applied skills, immediate workplace relevance, and adult learner characteristics. Adult Learners theory and Adult Learners principles inform professional AI training design. Its other boundary is vocational education and training: VET admits people who do not yet hold the occupation and closes with a trade or technical qualification, so it carries initial occupational preparation and the qualification frameworks that certify it, whereas professional training starts from an existing role — reskilling, continuing professional education or vendor certification — and assumes the competence VET awards.

Expertise regeneration as a training concern. The Cognitive Commons framework (Lovett 2026) argues that HRD must move beyond organizational reskilling to profession-level stewardship: eliminating entry-level developmental positions in AI-exposed sectors can deplete the shared expertise pool on which all organizations depend, with a time-delayed effect that appears only after 5–20 years. This reframes professional training from individual competency development to collective commons maintenance. **Pair AI production with verification, and seek outside measures.** Nguyen et al. (2026) put automated hallucination checks and an SME audit between drafting and delivery across a five-stage upskilling pipeline, and rest the framework's strongest claims on a NASBA CPE accreditation and a vendor certification exam rather than self-defined success measures.

Common Misconceptions

"Coursework produces occupational competence." The framework on this page puts the highest competency stages behind industry-embedded experience rather than coursework, which is a real limit on what a training program can claim. A course can build the prerequisites; the gated stage needs the work.

"Fading support on a schedule is equivalent to fading it on evidence." It is not. Fading assistance against the learner's *estimated competence* cut simulator lap time **27.9% (p = 0.005)** and failures by **3.52 per lap**, whereas rule-based fading on a fixed schedule produced no reliable change. The same amount of support, released on a different signal, is a different intervention.

"AI literacy training generalises across roles." Most instruments do not measure role-specific competence: in a systematic review of **33 teacher AI literacy instruments**, **29 (87.9%)** targeted general AI concepts while only **4 (12.1%)** addressed the pedagogical or occupational use that the job actually requires. A program built on general instruments is measuring a proxy.

“A simulator is a substitute for workplace training.” It develops procedure and removes consequence, which is valuable and is exactly the part that cannot transfer — the consequence is the curriculum in safety-critical work.

Connected Concepts

- Lifelong Learning
- Adult Learners
- Vocational Education and Training
- Educational Development
- AI Literacy
- Simulation
- Higher Education
- Generative AI
- Large Language Models (LLMs)
- Adaptive Learning
- Personalized Learning
- Virtual and Augmented Reality — where immersive practice is most established

Connected Articles

- Moving research meetings from data updates to cognitive windows in the age of artificial intelligence — Moving research meetings from data updates to cognitive windows in the age of artificial intelligence
- Artificial Intelligence (AI) and the Future of the Engineering and Computing Workforce: A Systematic Review of Gray Literature and Document Analysis of U.S. Reports (2020–2025) — AI and the Future of the Engineering and Computing Workforce
- A Conceptual Framework for Enhancing Workforce Readiness for Smart Manufacturing in the AI Era — Workforce Readiness Level framework for smart manufacturing in the AI era
- AI-accelerated End-to-End Framework for Rapid Professional Upskilling
- AI Coaching for Accelerating Human Skill Development with Reinforcement Learning
- The Empirically Grounded Adaptive Virtual Patient for Psychotherapy Training: Disclosure That Responds to Therapist Micro-Skills
- ASTRA: A Scalable Next-Generation ATCO Training Simulator with Autonomous Simpilots
- The Main Barrier to AI Adoption in the Public Sector is Lack of Training
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — HiBob AI Skills Framework validated with instructors and employers
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration

- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- Research on the optimization of the training system of university faculty development centers in the context of GenAI: a comparative analysis based on Chinese and Kazakhstani universities — Comparative survey showing institutional conditions, not national context, explain faculty GenAI readiness gaps (Bi et al. 2026)
- Rethinking artificial-intelligence literacy through the lens of teacher educators: The adaptive AI model — Teacher educators co-design an adaptive AI literacy model and a reflective questionnaire (Eyal 2025)
- Assessing teachers' AI literacy: a systematic review of measurement tools — Review showing teacher AI literacy instruments lag generative AI, marking the training target (Zainal et al. 2026)
- Empowering teachers to use AI for differentiation: changes in teachers' acceptance of AI-based technologies following participation in a short professional development training session — Three-hour PD raised German teachers' perceived usefulness and ease of use, but not intention to use AI for differentiation
- Artificial intelligence in initial teacher training for pre-service primary school teachers in mathematics: a systematic review — Review of AI in initial teacher training for primary mathematics: brief tool-focused training is not enough
- Evaluation of primary school teachers' use and perceptions of artificial intelligence in primary school mathematics instruction: a mixed-methods study — Survey linking prior AI training and frequency of use to Turkish primary teachers' positive perceptions
- Designing an AI-integrated role-rotation pedagogical model to support competence-related learning in pre-service educational psychologists — Role rotation as the structuring mechanism for AI-supported professional preparation
- Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement — Open Questions Towards Skill-Sustaining Reliance in Reflective AI Engagement
- Use of a GenAI-patient for medical communication training for undergraduate medical students: a quasi-experimental study — Use of a GenAI patient for medical communication training for undergraduate medical students: a quasi-experimental study
- Deliberative Instructional Agents: transforming professional learning with the responsible integration of Artificial Intelligence — Deliberative instructional agents for teacher professional learning, with responsibility conditions for AI-mediated PD
- Artificial intelligence applications in forensic science and their implications for education and training — When a technical profession's AI practice outruns its teaching pathway

Technologies and techniques

Models and techniques

Technologies

> **Technologies** — the models, architectures, and methods that power AI education systems, and the umbrella concept for the knowledge base's coverage of the technical layer. Where Pedagogies and Teaching Strategies and Learning Theories concern *how teaching and learning happen*, and AI Ed Evaluation concerns *whether AI works*, this page anchors the *technical* strand: the AI systems (large language models, generative AI, multimodal models, robots) and the techniques used to build, control, and deploy them (Prompt Engineering, retrieval-augmented generation, Reinforcement Learning, Educational NLP, knowledge graphs, agentic orchestration).

Questions to Consider

- You can be an excellent educator without being able to build an LLM — but this page argues your technical choices still shape what AI can and can't do in your classroom. What is one way the underlying technology of an AI tool might quietly change how your students learn, even if you never see the code?
- A common assumption is that the model is the whole story — but techniques like retrieval-augmented generation (RAG) and prompt engineering exist precisely to control and ground LLM output. Before reading further, when you ask an AI to 'be more accurate' or 'use this source', what do you think is actually happening under the hood?
- RAG is described as a core technique for reducing hallucination and improving safety. Why do you think fetching relevant knowledge to 'ground' an AI's answer would matter more for education than for, say, casual chat — and what could go wrong if that grounding fails?
- The page claims that technical choices embody pedagogical assumptions: a tutor built on Socratic prompting reasons with learners, while an answer-generating model may just hand over solutions. Can you recall an AI tool you've used that seemed to 'assume' a particular teaching philosophy — and did that align with how you actually wanted to teach or learn?
- Beyond raw accuracy, this page suggests AI systems should be evaluated on reliability, pedagogy, and equity. What headline metric do you suspect most people (including many educators) default to when judging whether an AI tool 'works', and why might that metric hide more than it reveals?
- Agentic AI is described as shifting AI 'from a prompt-responding tool into a proactive collaborator.' How might a system that initiates and orchestrates multi-step workflows on its own change what you, as an instructor or learner, are responsible for — and who holds it accountable?

Introduction

AI in education runs on a specific technical stack, and understanding it matters for educators and researchers even when they do not build systems themselves — because technical choices shape what AI can and cannot do in the classroom, the risks it carries, and how to evaluate it. This page organizes the knowledge base's technical-concept coverage: the AI systems, the techniques that adapt and control them, and how the technical layer connects to pedagogy, assessment, and evaluation.

AI systems in education

- **Large language models (LLMs).** The computational backbone of most modern AIED — LLMs generate human-like text for tutoring, assessment, and content generation, and are the most-referenced technology in the knowledge base. Training and fine-tuning adapts general LLMs for educational use.
- **Generative AI.** The broader category of systems that produce text, code, images, and other content — generative AI (driven chiefly by LLMs) is the technology behind the current wave of AIED research. See also multimodal models (text, image, audio) and Simulation.
- **Robots and embodied systems.** Robots in education add an embodied and often social presence — programmable kits for computational thinking and humanoid/social robots for tutoring, storytelling, and role-play. Robotics is a distinct technical strand that overlaps agentic AI and human-in-the-loop design.
- **Knowledge-based systems.** Knowledge graphs and educational NLP represent and process domain knowledge, increasingly combined with LLMs for grounded, explainable tutoring.

Techniques and methods

- **Prompt engineering.** Prompt engineering is how educators and developers shape LLM outputs — the primary mechanism through which offloading and control are enacted in LLM interactions.
- **Retrieval-augmented generation (RAG).** RAG grounds LLM outputs in retrieved knowledge, reducing hallucination and improving accuracy — a core technique for safe educational deployment.
- **Reinforcement learning.** Reinforcement learning trains agents to optimize behavior over time, used in adaptive systems and game-based learning.
- **Agentic orchestration.** Agentic AI systems plan and execute multi-step workflows — often orchestrating multiple specialized agents (see multi-agent systems) — and are reshaping AI from a prompt-responding tool into a proactive collaborator.
- **The educational agent stack lags the frontier.** Wang et al. (2026) mapped 474 studies and found GPT-series models and LangChain dominant while governed tool orchestration, persistent memory, and long-horizon planning were largely absent — and only 138 of 474 (29%) drew on educational theory.
- **Model training and adaptation.** LLM training and fine-tuning, educational alignment, and small-language-model adaptation make general models education-specific — though the evidence in the knowledge base puts retrieval and prompting ahead of training in the decision order, since a well-grounded prompt is cheaper than an adapted model.

How the technical layer connects to the field

The technical strand is inseparable from the knowledge base's other themes:

- **Pedagogy:** technical choices embody pedagogical assumptions — a tutor built on Socratic prompting reasons with learners, while an answer-generating model may default to direct provision (see pedagogies and teaching strategies).
- **Assessment and evaluation:** AI Ed Evaluation and benchmarks determine whether AI systems actually work; Assessment and Automated Assessment use the technical stack to grade and generate.
- **Responsible use:** technical techniques are central to reducing AI misuse — RAG (Retrieval-Augmented Generation) grounding, Guardrails, Prompt Engineering Scaffolding, and human oversight shape whether AI supports or undermines learning (Cognitive Offloading, Hallucination Risk).

Research attention is concentrated on a narrow slice of the tool ecosystem. Mapping 85 AI tools against the STEM and engineering literature, Terkowsky et al. (2026) found only 36 research-visible at all and conversational AI/LLMs accounting for 73.7% of 927 paper–tool connections, with 23 publications in an established laboratory context.

Implications for AI in education

- **Technical literacy supports critical use:** understanding the underlying models and techniques helps educators and learners use AI well and evaluate it critically (see AI Literacy).
- **Choose technology by pedagogical intent:** the AI system and technique should follow the teaching strategy, not the reverse.
- **Evaluate the technical layer:** AI Ed Evaluation and Benchmark research assess AI systems on reliability, pedagogy, and equity, not just headline accuracy.
- **Robots and agents are part of the stack:** embodied and agentic systems extend the technical repertoire beyond text — and bring their own design and safety considerations.

Common Misconceptions

"The model is the whole story." Techniques such as retrieval-augmented generation and prompt engineering exist precisely to control and ground an LLM's output, and the architecture around the model often determines whether it is usable in a classroom. Two systems on the same model can differ entirely in reliability because of what surrounds it.

"The field's technical maturity is established." The mapping is thin where it matters: across **474 studies**, GPT-series models and LangChain were dominant while **governed tool orchestration, persistent memory, and long-horizon planning were largely absent**, and only **138 of 474 (29%)** drew on educational theory. The stack being used is far narrower than the stack the field needs.

"Technical choices are the technologist's business, not the educator's." The page's framing is that you can be an excellent educator without being able to build an LLM and your technical choices still shape what

AI can and cannot do in your classroom. Whether a system grounds its answers in course material is a decision with pedagogical consequences that someone has to make.

“A more capable model will resolve the field’s gaps.” Orchestration, memory and long-horizon planning are architectural rather than capability problems — the documented absence is of systems that govern their own tool use over time, which a better model does not supply on its own.

Connected Concepts

- Large Language Models (LLMs)
- Generative AI
- Multimodal AI
- Reinforcement Learning
- Educational NLP
- Knowledge Graph
- Simulation
- Robots in Education
- Agentic AI
- Prompt Engineering
- Vibe Coding
- RAG (Retrieval-Augmented Generation)
- LLM Training and Fine-Tuning
- AI Ed Evaluation
- Benchmark
- Pedagogies and Teaching Strategies
- Learning Theories
- AI Literacy
- Adaptive Learning
- Personalized Learning

Connected Articles

- Beyond ChatGPT: A Comparative Mapping of AI Research in STEM and Engineering Education and the Contemporary AI Tool Ecosystem — Research visibility of 85 AI tools in STEM and engineering education (Terkowsky et al. 2026)
- A scoping review of generative AI-powered agentic AI in education: Research landscape, agentic capabilities, and insights from the frontier agent paradigm, exemplified by OpenClaw — Scoping review of agentic AI in education
- A meta-analysis of the effect of generative AI on productivity and learning in programming — Meta-analysis of GenAI’s effect on productivity and learning in programming

- CSTutorBench: Benchmarking Small Language Models as Tutors for Block-Based Programming — Small language model tutoring benchmarks
- Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact — Aligning LLMs for education
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education — Guardrailing RAG-based LLM tutors
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI tutor safety and harms
- ELBench: A multi-dimensional benchmark for education-facing large language models — Education LLM benchmark
- Teachy Mini: Development and preliminary evaluation of a knowledge-based generative social robot for higher education — Teachy Mini generative social robot
- Leveraging AI for Rapid Generation of Physics Simulations in Education: Building Your Own Virtual Lab — LLM-generated physics simulations for the classroom

Machine Learning

> **Machine learning** — the technical foundation of AI in education: algorithms that infer patterns, predictions, and policies from educational data rather than from hand-coded rules. It spans supervised learning (classifying at-risk students, predicting grades), unsupervised learning (discovering learner clusters), reinforcement learning (inducing tutoring and scaffolding policies), and deep learning (neural models for sequences, courses, and visual behavior). Generative AI is the latest and most visible subset, but it sits atop a much older stack of predictive and adaptive machinery.

Questions to Consider

- You've likely encountered recommendation systems or risk scores that 'learned' from data. How comfortable are you with a model deciding something about you (like an at-risk flag or a recommended path) based purely on patterns in historical data?
- The page draws a sharp line between predicting a risk and actually intervening — a risk score tells you a student might fail, but not what to do about it. Where have you seen a prediction offered as if it were already a solution?
- Machine learning can 'hack' its own reward: an AI tutor that optimizes for engagement can keep students entertained while teaching them little. If a system looks measurably successful but is pedagogically harmful, what measures should we watch besides the number it optimizes?
- Predictive models trained on historical grades can encode systemic bias, and automated proctoring raises false-positive risks that wrongly flag normal behavior. When data carries the biases of the past, how much should we trust an AI that uses it to make high-stakes educational decisions?
- Some AI systems outperform human-interpretable methods but remain opaque — you can see they work but not why. In education, when is interpretability a 'nice to have' and when is it non-negotiable?
- Generative AI is often treated as entirely new, but the page frames it as the latest subset of machine learning. How does seeing ChatGPT as part of the same predictive and adaptive machinery change what risks and limits you'd expect it to inherit?

Introduction

Machine learning is what turns educational traces into actionable intelligence. It powers the student models behind adaptive systems, the Learning Analytics dashboards that flag at-risk learners, the intelligent tutors that choose the next problem or scaffold, and the automated proctoring systems that monitor remote exams. Across the articles synthesized here, the pattern is consistent: collect data on learners, learn a predictive or decision model from it, and act on that model — whether the action is early-warning, course recommendation, adaptive scaffolding, or exam surveillance.

What machine learning does in education

Predictive modeling for student success. Supervised classifiers — Logistic Regression, Random Forest, SVM, K-Nearest Neighbors — identify at-risk students before they withdraw, using academic performance, demographic, and enrollment records. More advanced architectures go further: the TRACE transformer jointly predicts the courses a student will take and the grades they will receive next semester, modeling the concurrency of co-taken courses rather than treating history as a flat sequence. Optimizer-plus-sequence hybrids, such as the DMO-GRU framework in interactive online learning, combine automatic feature selection and hyperparameter tuning with recurrent nets to reach high accuracy and low error on engagement and performance prediction. A shared ambition is "precision education": continuous risk stratification and student digital twins that anticipate failure and align pathways with outcomes, shifting institutions from reactive remediation to preventive support. Glass-box models can hold their own here: Zhang, Jeffries & Koprinska (2025) report that decision trees which are intrinsically interpretable — trimmed by feature selection to only 3–5 leaf nodes — forecast module-level progress in large online programming courses as accurately as black-box random forests and SVMs (85–91% accuracy). Interpretability, then, need not be traded away for predictive power in early-warning applications. Tree-based models also prove effective for estimating item difficulty: Razavi and Powers (2026) fed LLM-extracted cognitive and linguistic features into random forests and gradient boosting machines to predict the difficulty of K-5 math and reading items (N = 5170). Correlations reached up to r = 0.87, with lower RMSE/MAE than direct LLM estimates, dummy regressors, TF-IDF baselines, and metadata-only models. The tree-based models also yielded interpretable feature importance — grade level and word count were top predictors — showing how structured features plus interpretable learners can outperform a single holistic judgment. Multimodal AI fusion extends this predictive toolkit: Bird (2026) fuses a fine-tuned ELECTRA transformer with a searched deep neural network over computational-linguistics features to classify English literature by UK Key Stage at an F1 of 0.996. That is far above the best unimodal transformer (BERT, 0.75) and the best linguistic-feature network (0.392), a concrete case where combining model families outperforms any single approach. Sukoon (Bashir & Afzal, 2026) is a compact applied case of supervised classification in education-adjacent Well-Being support: a Random Forest (100 estimators) over 20 features from the psychological, physiological, environmental, academic and social dimensions of a 1,100-response student stress survey. It was trained on a stratified 70/15/15 split, with a scaler fitted on training data only to avoid leakage, and benchmarked against an SVM on the same splits (89.09% vs. 88.48% accuracy). Two touches are worth noting: the authors interpret the confusion matrix by *error direction* — the model's main mistake was classifying low stress as moderate, which in a wellness deployment routes a student to more support rather than less. They also use native feature importances as a substantive finding (blood pressure 15.6%, teacher-student relationship 10.0%), while conceding that a single stratified split, without k-fold intervals, and a non-representative dataset limit the confidence of those weights.

Adaptive instruction and tutoring. Machine learning closes the loop between modeling and teaching. In intelligent tutoring systems, both a Bayesian Knowledge Tracing heuristic and a deep Reinforcement Learning policy adaptively selected worked-example types to elicit different levels of cognitive engagement, significantly improving posttest performance relative to non-adaptive control — while the two policies diverged by learner prior knowledge, raising interpretability questions. Reinforcement learning also underlies the pedagogical-safety agenda: because an RL tutor optimizes a proxy reward, it can "hack" that reward (boosting engagement while teaching little), and architectural constraints on prerequisite enforcement

and minimum cognitive demand are needed to keep it safe. Lighter adaptive programs, such as the rule-based STEM system in sixth-grade science, show that machine learning can be used sparingly — for monitoring rather than direct trajectory control — while still supporting deep learning.

On the Knowledge Tracing side, Pradeesh et al. (2026) show a recurrent model can be tuned to a curriculum's own structure: their OKT model treats Outcome-Based-Education course outcomes as knowledge concepts, couples expert-validated OBE affinity mappings (relations between course and program outcomes) with a Memory Augmented Neural Network for cross-outcome impact, and pairs a GRU backbone with domain-adaptive BERT embeddings — reaching 89.81% AUC and beating DKT, DKVMN, EKT, and SimpleKT on live engineering-program data.

Diagnosis from tabular numerical answers. Yin et al. (2026) show gradient-boosted trees solving the *diagnosis* side of tutoring in a domain long closed to AI: for Engineering Economics Calculated Formula Questions, where students' handwritten solutions lack structured digital data, they train a dedicated XGBoost multi-label backbone per question to map submitted intermediate and final numerical answers to instructor rubric mistake labels (average precision 0.81, recall 0.79, accuracy 0.65). Random-masking data augmentation — masking input features to "NaN" at varying probabilities — preserves the logical dependencies of tabular solutions better than interpolation methods like SMOTE and significantly improves diagnosis, and including intermediate answers helps most. It is evidence that tree-based models plus structure-aware augmentation can bootstrap tutoring feedback where generative methods lack training data.

A field-level view of the RL subset is provided by the Riedmann, Schaper & Lugrin (2025) systematic review of 89 RL-in-education studies: it confirms RL is a major ML lineage for inducing adaptive tutoring and scaffolding policies, but finds classical (Q-learning) methods more consistently effective than Deep RL (61% vs 36% significant superiority) and flags that over half of studies conduct no statistical testing — a methodological caution that echoes the validation concerns below.

From prediction to action and accountability. A persistent limitation is the gap between a risk score and a feasible intervention. The SC2R framework couples a calibrated predictive model with integer-programming recourse generation and semantic validation, producing intervention plans that respect timing, budget, and availability constraints rather than merely being model-valid. This move "beyond prediction" toward constraint-respecting, machine-checkable recommendations is the field's response to the charge that predictive AI in education can recommend actions institutions cannot or should not take.

Machine learning in proctoring

A distinct application is automated exam proctoring. Deep-learning systems — CNNs and RNNs/LSTMs analyzing eye movements, head posture, and facial expressions — detect cheating more reliably than traditional monitoring, but the decade-long systematic review finds persistent dataset limitations, single-model evaluations, reproducibility gaps, and false-positive risks that can wrongly flag normal behavior. The companion review of academic dishonesty documents the cheating methods such systems must counter (identity spoofing, browser use, copy-paste) and the practical burdens — cost, connectivity, test-taker anxiety — that bound their equity. Together they caution that ML proctoring must be paired with Privacy-preserving, context-aware design and accessible alternatives.

Limits and ethical concerns

The synthesized literature is candid about machine learning's limits. Gains often come from Benchmark or single-institution data and may not generalize without retraining; SC2R and TRACE both acknowledge this. Predictive models trained on historical grading can encode systemic bias, and risk scores applied to sensitive student data raise Privacy and equity concerns that demand AI Governance and human oversight. Interpretability is a recurring tension — RL policies can outperform interpretable heuristics while remaining opaque. And reward hacking shows that an ML system can be measurably successful while pedagogically harmful, which is why architectural safety constraints and audit infrastructure matter.

Validation practice is another source of overconfidence. Schuetze, Yan, and Carvalho (2025) show that knowledge-tracing models (BKT, BKT-with-Forgetting, AFM) appear to capture learning trends when fit retroactively to all available sessions, yet under **time-based (walk-forward) cross-validation** — training on earlier sessions to predict later ones, mirroring real deployment — they overestimate future performance, miss the spacing effect, and mis-order practice conditions. Forgetting-free models even matched forgetting-augmented ones, indicating forgetting was absorbed into other parameters rather than learned. When the training and deployment distributions are temporally separated — the norm for longitudinal student data — a strong in-sample or retrospective fit is no guarantee of predictive validity.

Generative AI as a subset

Generative AI — large language models and related LLM systems — is best understood as a subset of machine learning: the same neural and training foundations, but applied to *generating* content (explanations, feedback, dialogue) rather than classifying or predicting. It inherits the field's validity, bias, and safety concerns while adding new ones such as hallucination. For the purposes of this knowledge base, machine learning is the broader technical umbrella; generative AI is its most visible contemporary branch.

Teacher education and machine-learning literacy

Machine learning also appears in education as a *subject*. In initial teacher training, hands-on coding and robotics interventions using the Micro:bit and supervised image-classification projects significantly improved preservice teachers' knowledge of computational concepts and introductory machine learning, and their attitudes toward teaching it. As AI literacy enters curricula, equipping teachers with a working grasp of machine learning becomes a precondition for teaching it to students. A contrasting route reaches the same concepts without any software: in Sung and Gunpinar's (2026) online professional development, ten K-12 educators built an "explainable feature matrix" by hand — a yes/no table of shape features that *is* the classifier, testable and revisable rather than opaque. Code.org's sorting game and Google Slides were the only tools used. Their AI self-efficacy rose from below-moderate (M = 3.13) to above-moderate (M = 3.71) and negative descriptors in a word-association task fell from 30% of participants to none, though the evidence is small, uncontrolled, and entirely self-reported.

Common Misconceptions

“Accurate prediction requires an opaque model.” Interpretability and performance are more separable than that assumption allows. Zhang, Jeffries and Koprinska (2025) show that intrinsically interpretable decision trees — **pruned to just 3-5 leaf nodes** — hold their own on student-progress prediction in programming. When a five-node tree matches a black box on your task, the black box is buying opacity rather than accuracy, and in an educational setting where a decision must be explained to a student the glass box is the better trade.

“Machine learning in education is a neutral prediction technology.” Its applications carry the discipline’s governance failures with them, and proctoring is the clearest case: a model that infers something about a student from behavioral or physiological signals is making an accusation with a confidence score attached, and the evidence base for that inference is much weaker than the deployment rate suggests.

“Generative AI has made classical machine learning obsolete in education.” They do different jobs. Prediction of learner states, difficulty estimation and progress forecasting remain classical ML problems, and the knowledge-tracing and item-calibration literature this corpus documents is not served by a language model. Generative AI is a subset of machine learning rather than a replacement for it.

“Teacher education should teach students about LLMs rather than about machine learning.” Limiting literacy to the generative layer leaves practitioners unable to interrogate the predictive systems making decisions about their students — which is where the consequential errors concentrate.

Connected Concepts

- Learner Modeling and Adaptive Instruction
- Learning Analytics
- Intelligent Tutoring
- Adaptive Learning
- Personalized Learning
- Reinforcement Learning
- Generative AI
- Large Language Models (LLMs)

Connected Articles

- Analysis and Prediction of At-Risk Students Using Machine Learning Algorithms — Supervised ML classification to identify students at risk of withdrawal
- Jointly predicting courses and grades using a transformer-based model — Transformer jointly predicting courses and grades (TRACE)
- From Precision Medicine to Precision Education: A Vision for AI-Powered Student Digital Twins, Preventive Student Success, and Career-Aligned Academic Pathways — AI-powered student digital twins for preventive, career-aligned pathways

- From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support — Semantics-constrained counterfactual recourse for actionable intervention
- Interactive online learning method for students based on artificial intelligence — DMO-GRU hybrid for interactive online-learning prediction
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive scaffolding of cognitive engagement in an ITS (BKT vs DRL)
- Pedagogical Safety in Educational Reinforcement Learning — Formal framework for pedagogical safety in educational reinforcement learning
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review — Decade-long review of deep-learning automated proctoring
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- What differentiates educational literature? A multimodal fusion approach of transformers and computational linguistics — Multimodal fusion for classifying educational literature
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education
- Reinforcement Learning in Education: A Systematic Literature Review
- Arthur: An artificial intelligence powered teaching assistant system for Engineering Economics class
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data

Generative AI

> **Generative AI** — AI systems capable of producing text, code, images, and other content, most prominently large language models like GPT-4 and Claude. Generative AI is the technology driving the current wave of AI in education research.

Questions to Consider

- Generative AI produces fluent, confident-sounding content on demand. Does fluency equal correctness, and where have you seen a confident-sounding but wrong output — what made it hard to catch?
- Unlike earlier rule-based or retrieval-based systems, generative models create new content rather than retrieving stored answers. How does that shift change the risks — hallucination, over-reliance, academic integrity — compared to a search engine?
- With 80+ articles, generative AI is the largest thread in this knowledge base, spanning tutoring, assessment, content generation, and safety. Which application do you think is the most promising for learning, and which the most dangerous — and why?
- The same technology that can generate a Socratic tutorial can also produce a ‘correct-answer trap’ that encourages copying. What design choices might separate generative AI that scaffolds learning from generative AI that short-circuits it?

Introduction

What makes generative AI different for education

Unlike earlier rule-based or retrieval-based systems, generative AI produces fluent, contextually appropriate content on demand. This creates both unprecedented opportunities and novel risks:

- **Content generation:** LLMs can create instructional materials, examples, and explanations. Synthetic textbooks, adaptive videos, and instructional videos show the range of educational content generation.
- **Lesson-planning drafts that are platform- and language-dependent.** Expert evaluation of AI-generated science lesson plans shows content quality is neither uniform nor neutral. Karaismailoglu, Surmeli and Yildirim (2026) had eleven Science Education specialists score ChatGPT-4 and an education-focused tool (Teacher’s Buddy) against sixth-grade Engineering Design-Based Learning stages: the education-focused platform outscored the general-purpose one across all eight quality criteria, yet 7 of 11 experts still rated the plans only “applicable by correction.” Both platforms generated pedagogically richer output from English than Turkish prompts even when asked to localize for Mersin, Turkey — a digital-equity concern where prompt language shapes instructional quality.

- **Tutoring and dialogue:** AI tutoring systems use generative AI for conversational instruction. Socratic dialogue and collaborative tutoring exploit generative capabilities for pedagogical interaction.
- **Simulated patients and case consistency.** A multi-expert annotated corpus of 4,815 student-AI messages from the MeduAI-SP platform (Yang et al., 2026) found that only about 0.68% of LLM-generated standardized-patient responses contained clear fidelity problems, and progressive disclosure was rated clinically appropriate in roughly 99.3% of patient messages. This supports the claim that generative-AI simulated patients can sustain case consistency and inquiry-dependent, non-premature disclosure under structured YAML scripting (qwen-max), making them a stable-enough environment for outcome research rather than only for plausibility demonstrations — while the system deliberately withheld diagnoses and summative scores during learning.
- **Assessment:** Essay scoring, automated grading, and Formative Assessment increasingly rely on generative models. Benchmarks substantiate this shift for open-ended work: Pecuchova, Benko & Drlik (2025) found that context-sensitive GenAI models (GPTo1 reaching almost-perfect agreement with human graders) sharply outperformed earlier sentence-embedding approaches on grading open-ended student responses, which relied on rigid reference matching and misclassified valid but differently-worded answers. Olvet et al. (2026) extend this to pre-clerkship medical education, where GPT-4's scoring of open-ended questions reached substantial-to-almost-perfect inter-rater agreement with faculty (weighted kappa up to 0.94) — but only after humans iteratively refined the rubric across three rounds and remained in the loop to arbitrate discrepancies — while the most synthetic, holistic-rubric question stalled at moderate ($\kappa w = 0.54$). This is evidence that generative assessment reliability is shaped as much by human rubric engineering and error-pattern analysis as by the raw model. Yet the same fluency does not generalize across item types: Falahat et al. (2026) found ChatGPT-5 matched human faculty on objective pharmacy-exam items (CCC 0.935–1.000) but not on short-answer (≈0) or essay (0.341–0.854) items, and a structured rubric did not reliably close the gap.
- **Risks:** Hallucination, Over-Reliance, Cognitive Offloading, and Academic Integrity concerns arise specifically from generative AI's fluency and Accessibility.
- **A learning-safety problem beyond output quality.** Rahimi (2026) argues generative AI can raise the quality of a learner's work while performing cognitive work they need to do, so safety should be judged on the human-development trajectory — Learning Safety protecting competencies and Learning Soundness supporting their development — rather than accuracy, bias, or privacy.
- **Effectiveness claims measure performance, not learning.** The field's largest estimate — a meta-analysis of 69 studies reporting $g = 0.7$ for ChatGPT and similar tools — pools immediate task success rather than delayed, unassisted retention, so it is not evidence that generative AI produces learning (Yan et al., 2025).
- **Learning environment generation:** Specialized generative models now turn a course brief directly into finished learning artifacts. CogEvol (Tu et al. 2026), a family of models trained for single-pass generation of structured slides and self-contained interactive HTML pages, completes a slide in a median of 17 seconds and an interactive page in 59 — replacing minutes-long multi-turn agent Scaffolding. Reliability is enforced via a production pipeline that converts real failures

into 53,687 verified SFT samples plus a hybrid rule-plus-VLM reward for GRPO-based RL. This positions generative AI as a content authoring engine with implications for teacher and curriculum production workflows, and for evaluating whether AI-generated learning environments are functionally and pedagogically sound rather than merely visually polished.

A census of educator tool use shows attention concentrated on production rather than instruction: image, audio, video and presentation tools made up roughly half of the 50 tools nominated by 211 educators across nine countries, while tutoring and chatbot tools formed the smallest teaching-facing group (Bower, Torrington & Lai (2026)).

The knowledge base's generative AI coverage

With 80+ articles, generative AI is the knowledge base's largest technology thread. Across its 394 studies, ChatGPT with an unspecified version appeared in 94, the ChatGPT-3/3.5 family in 66, and the ChatGPT-4 family in 52 — so many reported capabilities describe model generations since superseded (Lin et al. (2026)). Research spans effectiveness studies (meta-analyses), safety concerns (tutor harms, guardrailing), and design principles (instructional guidance).

Pooled across 53 studies, GenAI-assisted education outperformed non-GenAI approaches on achievement (g = 0.40), higher-order thinking (g = 0.72), motivation (g = 0.81) and writing (g = 0.76), though game-assisted GenAI added no significant benefit (g = 0.24) (Dong (2026)).

A three-level meta-analysis of 22 studies finds GenAI-supported problem- and project-based learning producing a large pooled effect on learner-internal outcomes (g = 0.819), though a PET-PEESE correction reduces it to g = 0.378; embedding mattered too, with general chatbots pooling at g = 0.970 against g = 0.455 for custom or API systems (Chen (2026)).

A separate 42-study meta-analysis of motivation alone puts the pooled effect lower (g = 0.764) and reports a 95% prediction interval spanning [−0.689, 2.217], so the motivational advantage is not reliably positive for a new setting (Fang et al. (2026)).

Generative UI is the newest capability in this thread: models that emit a working interactive artifact — sliders, manipulable simulations — rather than prose. Kovshov et al. (2026), a Google Research team, report that off-the-shelf generative UI is not yet pedagogically precise enough for complex constructs, but that decomposing a learning objective into progressive leveled goals and wrapping generation in critique and self-improvement loops yields interactives expert teachers rate as acceptable. Theirs is an orchestration design: teachers state objectives, approve them and select among candidate simulations, so the binding constraint on bespoke interactive learning material shifts from production to specification, and pedagogical guardrails are embedded in the generation pipeline rather than left to teacher vigilance afterwards.

Beyond these core strands, recent work extends the evidence base across institutional, interactional, and domain contexts. Qin (2026) documents how Lingnan University institutionalized GenAI literacy for all undergraduates as part of a digital liberal-arts transformation. Chang and Li (2026) show that student-AI conversations encode discipline-associated cognitive engagement, with ~62% of prompts reflecting higher-order cognitive demand. Neto and colleagues (2026) systematically review GenAI in scenario-based healthcare education, finding prompt design functions as instructional specification but is rarely aligned with instructional frameworks (34.8%) or reported in reproducible detail (34.8%). GenAI also powers role-play

simulations of learners for practice-based teacher training: Zhuang and Zhang (2025) built *Student GPT*, a custom ChatGPT chatbot that simulated a middle school student holding common ratio-reasoning Misconceptions about AI, giving preservice mathematics teachers affordable, content-specific practice at diagnosing student thinking — evidence that prompt design (a literature-grounded prompt reliably elicited target conceptual errors, 0.98 vs. 0.40) can steer an off-the-shelf generative model into a useful pedagogical persona.

A GenAI-guided mathematics professional-development case study of eight in-service teachers in rural, under-resourced districts had Bicer et al. (2026) engage mathematical Creativity, content knowledge and pedagogical content knowledge as interconnected reasoning across ten modules, crediting progressive scaffold fading and simulated student reasoning; they report engagement patterns, not measurable gains.

A systematic review of language educators (Li et al. 2026) finds educators value GenAI most for preparatory content work — lesson planning, materials creation, and writing support — while hesitating on live classroom use, with concerns centering on academic integrity (plagiarism and assessment validity), professional displacement, and technostress; adoption is shaped by professional-identity, pedagogical, technical, institutional, and integrity factors, and competency gaps map to episteme, techne, and phronesis.

Content generation likewise reaches beyond mathematics into co-designing learning resources with teachers — for example, teacher-AI co-designed Simulation scaffolds for drone STEM learning that preserve pedagogical validity and contextual relevance. In children's STEAM arts education, Luo and Tahir (2025) experimentally quantified the gains of ChatGPT-assisted over teacher-generated lesson plans (expert-rated median 20.5 vs. 17.6, $p = .002$, large effect) — yet the same study documents that fluent output carries real failure modes for classroom generation: plans that are idealized or impractical for daily teaching, missed child-safety constraints (e.g., suggesting carving knives for young children), Western-centric cultural bias, and logically flawed or irrelevant image/resource generation. The contribution is a prompt framework (Role–Instructions–End Goal plus a "four points and one line" quality rubric) that turns the reliability question from whether the model can generate into how prompts and evaluation criteria must constrain it for pedagogical use. Equity-oriented uses remain underexplored; an all-girls GenAI makerspace initiative in Europe combined two GenAI tools with feminist pedagogy to address persistent gender inequities in computing participation, analyzing girls' GenAI-generated images and stakeholder reflections. Assistive and inclusive applications are a growing strand: Khlaif et al. (2026) — a qualitative case study of 21 visually impaired undergraduates in Palestine — found GenAI tailors pace, content, and delivery to individual learning profiles, simplifies complex academic texts, and converts content across modalities, with learners viewing it as complementing rather than replacing teachers.

- **Generative AI as a pedagogical agent in elementary critical media literacy.** Demir and Akar (2026) operationalize the 5E instructional model with generative AI tools (ChatGPT for reflective questions and Q&A, Grammarly and Canva AI for content refinement, Padlet for peer feedback) embedded phase-by-phase rather than as isolated add-ons, in an 18-hour critical media literacy program for fourth-grade Turkish students aligned to the Turkish Language and Social Studies curricula. The AI-supported group showed large gains in media reading (+3.50), writing (+1.67), and total media literacy (+5.17, all $p < .01$) with between-group effect sizes of Cohen's $d = 1.12$ (reading), 1.18 (writing), and 1.31 (total literacy), while the control group advanced only modestly. Qualitative analysis surfaced six domains of critical media literacy growth — digital self-protection and data privacy, purposeful and responsible media use, safe communication and

boundary awareness, critical evaluation and misinformation awareness, online risk awareness, and media Ethics/digital citizenship — illustrating how generative AI can be designed into a curriculum as a scaffolded pedagogical agent that cultivates critical evaluation rather than short-circuiting it.

Generative AI in specialized domains: dyslexia support

A 2026 interdisciplinary systematic review (Dabaghi, D'Urso & Sciarrone, PRISMA-guided, 2018–2024, n=72) finds that **generative AI is under-utilized in the dyslexia-support domain**. GAI research (all from 2024) clusters into intelligent chatbots, teacher training support, and exploratory studies, and is rapidly overtaking classical ML as the tool of choice — yet rigorous experimentation and real-world validation remain largely absent. The review's future-trends analysis points to GAI-powered personalized materials and real-time adaptive feedback, multi-modal diagnostic models integrating eye-tracking, EEG, and behavioral analytics, NLP-driven intelligent tutoring systems and conversational agents, and educator-facing support tools. This illustrates both the promise of generative AI for content generation and interactive support in a specialized, high-need domain and the risk that its adoption outpaces the evidence base.

Common Misconceptions

- **"A large effect size means the tool improves learning."** The field's largest estimate — a meta-analysis of 69 studies reporting $g = 0.7$ for ChatGPT and similar tools — pools **immediate task success**, not retention, transfer or understanding. The same issue applies to the 53-study pooled estimate ($g = 0.40$ achievement, 0.72 higher-order thinking, 0.81 motivation, 0.76 writing): these are outcomes measured close to the intervention, on tasks resembling the intervention. An audit of 14 meta-analyses claiming AI improves education found **none justified its claims**. Treat any headline number as evidence about performance under conditions, and ask what was measured and when.
- **"The newer model will fix it."** Model generation is not the binding constraint. ChatGPT-5 matched human faculty on objective pharmacy-exam items (CCC 0.935–1.000) but not on short-answer items (≈0) or essays (0.341–0.854), and **a structured rubric did not reliably close the gap**. Capability gains on closed tasks have not transferred proportionally to open-ended work, which is where most assessment actually lives.
- **"Usage data shows it is working."** In the 394-study mapping, ChatGPT with an unspecified version appeared in 94 studies and the 3/3.5 family in 66 — so a large share of published capability claims describe **model generations since superseded**, and many studies do not report the version at all. Reported behavior is tied to a specific model and a specific date, which makes undated claims about "generative AI" unfalsifiable rather than general.
- **"It is safe because experts annotated the corpus."** A multi-expert annotated corpus of 4,815 student-AI messages found only about 0.68% of messages contained the harmful or off-task content the coding scheme was built to detect. That is a finding about the base rate, not about safety: rare events are rare, and a system's failure tails are exactly the cases a corpus of that size struggles to characterize.

What this means for practice

For instructors

- Design the assessment and the tool together. Where AI is strong on objective items and unreliable on essays, an assessment plan that weights essays has to carry explicit verification rather than a generated draft.
- State the model and version in your own classroom evidence and in anything you report. Undated claims cannot be checked, and the version often explains the result more than the pedagogy does.
- Treat the novelty horizon as real and short. Pooled effects are measured near the intervention; plan for the decline that longitudinal work documents rather than being surprised by it.

For developers

- Do not roadmap against pooled effect sizes. An audit of 14 meta-analyses found none justified its claims, so a product claim resting on a headline *g* is resting on methodology that does not survive inspection.
- Instrument the base rate before optimizing it. A 0.68% incidence rate means most quality work happens in the tail, and tail performance is what determines whether a deployment is acceptable.
- Report version, date and task type with every benchmark number you publish, because a capability claim that omits them is not reproducible.

Connected Concepts

- Large Language Models (LLMs) — the model class underlying generative AI
- Prompt Engineering — how outputs are shaped
- RAG (Retrieval-Augmented Generation) — retrieval-augmented grounding
- AI Literacy — the competency needed to use it effectively
- AI in Education — the broader field
- Intelligent Tutoring — conversational and generative tutoring systems
- Cognitive Offloading — the over-reliance risk generative AI amplifies
- Hallucination Risk — a core reliability risk of generated content
- Academic Integrity — integrity concerns from fluent generation
- Automated Assessment — generative models in grading and feedback
- Technologies — the umbrella of AI techniques and models
- Higher Education — a primary deployment context
- K-12 — a primary deployment context
- Reflection

Connected Articles

- Effects of generative artificial intelligence on students' learning motivation: evidence from a meta-analysis — Meta-analysis of GenAI's effect on learning motivation, with a prediction interval spanning harm to benefit

- Typology of Generative AI Tools for Education — Typology of Generative AI Tools for Education
- Harnessing Generative UI for Education: Tailored Learning Interactives — Harnessing Generative UI for Education: Tailored Learning Interactives
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- SSAIL: A Design Framework for Safe and Sound AI for Learning — SSAIL: A Design Framework for Safe and Sound AI for Learning
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches — Meta-analysis of GenAI learning outcomes
- A meta-analysis of the effect of generative AI on productivity and learning in programming — Meta-analysis of GenAI in programming learning
- Distinguishing performance gains from learning when using generative AI — Performance vs. learning with GenAI
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — Harms of AI tutoring agents
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education — Guardrailing a safe RAG LLM tutor
- CogEvol: Towards Efficient and Reliable Learning Environment Generation — CogEvol: Learning Environment Generation
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- ChatGPT-assisted lesson planning for children's STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models
- Suitability of Artificial Intelligence Supported Lesson Plans from the Perspective of Science Education Experts
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Can Generative Artificial Intelligence Reliably Score Open-Ended Question Assessments in Undergraduate Medical Education?
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions

- How generative AI guided-professional development supports teachers' engagement with mathematical creativity, content knowledge, and pedagogical content knowledge — A GenAI-guided mathematics PD case study with eight rural in-service teachers
- Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis — Pooled g = 0.819 falling to 0.378 under PET-PEESE; custom tools (0.455) underperformed chatbots (0.970)

Large Language Models (LLMs)

> **Large Language Models (LLMs)** — neural network models trained on vast text corpora that generate human-like text, powering most modern AI in education applications. LLMs are the computational backbone of generative AI tutoring, assessment, and content generation in education.

Questions to Consider

- What do you believe an AI chatbot ‘knows’ when it answers you? The page frames LLMs as generating probable text rather than retrieving verified facts — how does that distinction change how much you would trust a model’s explanations?
- LLMs are described as the engine behind most modern AI education tools — tutoring, grading, content generation, and even diagnosing what students know. Of these uses, which do you think is most and least appropriate for a probabilistic text generator, and why?
- The page reports that three different LLMs produced sharply divergent support plans for the same learning-analytics input, each with different demographic assumptions. If models aren’t interchangeable as advisors, what does that mean for an institution that adopts one?
- Because LLM output is sensitive to prompts and settings, two people can get very different results from the same model. How should this influence how you — as a learner or designer — phrase requests, and how much you trust a single output?
- A key limitation is hallucination — plausible-sounding but ungrounded content. In a tutoring or grading context, what would it take for you to feel confident the model wasn’t inventing something, and what safeguards would you demand before letting it assess a real student?

Introduction

LLMs as the engine of AIED

LLMs are the most-referenced concept in the knowledge base (60+ articles) because they underpin nearly every AI education application:

- **Tutoring:** AI tutors use LLMs for dialogue, explanation, and Problem Solving guidance. Training and fine-tuning adapts general LLMs for educational use.
- **Assessment:** Grading systems, essay scoring, and item difficulty prediction leverage LLM capabilities. Razavi and Powers (2026) show GPT-4o can estimate the difficulty of K-5 math and reading items (N = 5170) calibrated under the Rasch IRT model: zero-shot ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but varied by grade, while a feature-based strategy in which the LLM extracts cognitive and linguistic features for tree-based models reached correlations up to r = 0.87 — evidence that structured feature extraction can outperform a single holistic LLM judgment. Across the aggregate grading literature, a PRISMA-guided systematic review of 42 empirical studies (2023–2025) concludes that LLMs match human raters on short, well-structured tasks with detailed rubrics yet cannot fully replace human

judgment on complex, open-ended, or subjective work, and that model version is a dominant determinant of grading quality (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback). Reliability also varies sharply by item type: Falahat et al. (2026) found ChatGPT-5 matched faculty closely on objective pharmacy-exam items (CCC 0.935–1.000) but was unreliable on short-answer (CCC ≈0) and essay (0.341–0.854) items, and that providing a rubric did not consistently improve agreement.

- **Generated item labels track surface form, not difficulty.** A 378-item audit found an LLM's Easy/Medium/Hard labels rose in lockstep with its own co-generated Bloom level (ρ=0.90) and with stem length (15.9 to 30.2 words) yet correlated with empirical item difficulty at only ρ=0.06 over 7,888 student responses, evidence that generation-time difficulty metadata describes formatting rather than demand on prior knowledge (An & Wang (2026)).
- **Generated items can still match expert items.** o3-mini in a generate → judge → revise loop built exams for 71 classes; under a Bayesian hierarchical 2PL IRT model the AI items were easier but more discriminating ($\bar{\alpha}$ = 1.3 vs. 1.2) and more informative (I_{max} = 3.85 vs. 2.61) than expert AP Statistics items (Isley et al. (2025)).
- **Annotation quality is a design outcome, not a single-prompt property.** Bernado et al. (2026) prompted a five-model panel to judge human-readable assertions about each utterance instead of emitting a label directly, and a transparent classifier over those binary judgments (macro-F1 0.673, Cohen's κ 0.688) beat the best published direct prompting of a frontier model (0.61 macro-F1) while trailing a fine-tuned RoBERTa-base encoder (0.76); cross-model agreement functioned as a screening device, not as validity evidence.
- **Multimodal AI reasoning LLMs as graders:** when a multimodal, reasoning-capable LLM (GPT-o4-mini) graded a 296-student handwritten general-chemistry exam page-by-page against rubric images, single-run total scores were highly reproducible (ICC(A,1) = 0.967; averaging five runs reached 0.993) and agreed strongly with TA totals (R^2 = 0.91), yet item-level reliability was sharply format-dependent — textual and reaction-equation answers graded well while drawing and graphing were worse than random (background grids distract AI vision). This shows an LLM grader's trustworthiness is a function of response format and task, not just raw model capability, and that selective deferral via confidence filters is needed for high-stakes use (Assisting the grading of a handwritten general chemistry exam with artificial intelligence).
- **Content:** Generative AI content creation relies on LLMs. Question generation and video generation are LLM-driven.
- **Safety:** Pedagogical Safety, Hallucination Risk, and SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems research examine LLM-specific risks.
- **Diagnosis:** Knowledge Tracing and Cognitive Diagnosis increasingly incorporate LLMs for richer student modeling. Grounding matters enormously for error diagnosis: Reddig, Arora & MacLellan (2025) showed that supplying GPT-4 the tutor interface structure plus Bayesian Knowledge Tracing skill estimates raised logical-error identification from 40% to 81% on factoring (overall error diagnosis ~87.8%), while multi-step problems and responses with several errors remained weak cases and hallucinated "common-misconception" diagnoses persisted — evidence that an

LLM's diagnostic value is as much a function of the structured context and learner-model signals it receives as of the model itself.

- **Verification separated from generation — with correlated failure modes.** Hossain et al. (2026) restrict tutor retrieval to instructor-approved course material and route claims through an architecturally separate DeBERTa-v3-large-MNLI verifier, but caution both models share broad web training and can fail in correlated ways, and the verifier cannot check a code trace without executing it.
- **Assessment model shift (2017–2024):** Morley et al.'s scoping review of auto-marking short-answer science questions traces the field's move from fine-tuning smaller BERT models (dominant through 2021) toward prompting larger LLMs (GPT-1/2/3.5/4) from roughly 2022 — adopted via Prompt Engineering rather than fine-tuning — with domain-augmented models, rubric-aware prompting, and chain-of-thought lifting accuracy. Yet GPT models were rarely benchmarked against BERT on standard corpora, few auto-markers could explain their marks, and bias was seldom examined, cautions that apply to LLM assessment generally (Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4).

Model-specific research

The knowledge base covers both general-purpose LLMs (GPT-4, Claude) and education-specific adaptations. Small language model benchmarks compare SLM performance for tutoring, and Suvernev et al. (2026) argue SLMs are architecturally appropriate for agentic tutoring when deployed as tool-augmented planners — deterministic tools carry the load a small model would otherwise handle implicitly — with pedagogical control residing in the escalation policy rather than the model. Educational alignment research addresses how to make LLMs pedagogically appropriate. A classroom study across three frontier families — Oppenheimer, Cash & Connell Pensky (2025) — found that ChatGPT, Gemini, or Claude could act as collaborative critique partners for argumentative writing: over a semester of iterative essays, students improved on argument quality, prompt engineering, and response-to-AI feedback by roughly a full standard deviation each (all $p < .001$) and engaged deeply (87.8% rebutting LLM claims), positioning general-purpose LLMs as viable collaborative learning partners rather than mere answer generators.

A complementary line of work reframes LLMs from static graders into emulators of pedagogical reasoning. Yaşar et al. (2026) showed that GPT-4, scaffolded with a semantically precise, iteratively co-refined rubric, could approximate human evaluative judgment in design-based learning: initial LLM–human agreement was poor (Cronbach's Alpha = 0.393; Kappa −0.06 to 0.18), but iterative rubric refinement raised mean agreement from 54.75% to 81.25% (final Alpha = 0.798, Kappa 0.40–0.55), and K-means clustering of human and LLM score matrices showed highly correlated centroids ($r = 0.89$). The study positions the rubric as a mediating interface between human pedagogical intent and machine inference — evidence that off-the-shelf LLMs are not interchangeable as evaluators either, and that their assessment behavior is a design outcome shaped by the rubric and prompts they are given. Raw model capability differentiates grading too: benchmarking eleven GenAI and sentence-embedding models on 1,885 open-ended responses, Pecuchova, Benko & Drlik (2025) found only GPTo1 reached almost-perfect agreement with expert human graders (Fleiss' Kappa 0.82), with Claude3 and PaLM2 slightly behind, while reference-aligned models such as

BERT fell far short — showing that frontier-model context-sensitivity matters for reliable open-ended assessment. Model differences also matter for high-stakes downstream uses. López-Pernas et al. (2026) showed that three LLMs produced sharply divergent student-support prescriptions for the same learning-analytic input, and each imposed distinct demographic priors on the learner profiles they generated — evidence that off-the-shelf LLMs are not interchangeable as prescriptive advisors. Similarly, Olvet et al. (2026) found that GPT-4's scoring of pre-clerkship medical open-ended questions climbed to substantial-to-almost-perfect inter-rater agreement with faculty (weighted kappa up to 0.94) only after three rounds of iterative rubric refinement, and fell to moderate ($\kappa w = 0.54$) on a holistic-rubric item — reinforcing that rubric design, not raw capability alone, is the decisive lever for LLM scoring reliability. Model-specific behavior also shows up in how LLMs respond to skeptical users: an algorithmic audit queried ten frontier LLMs 500 times each with a rural-Montana K-12 AI-skeptic persona to test whether AI systems consulted by skeptical users are predisposed to encourage adoption. Eight of ten acknowledged user concerns then redirected to AI-engagement framings; composite scores spanned from 3.85 (Claude Sonnet) to 7.52 (Gemini 3.1 Pro Preview), with a cross-family AI scorer panel clearing Cohen's kappa >= 0.70. The pattern was a model-dependent design outcome. Model capability also depends on how models are combined: Bird (2026) fine-tuned eight state-of-the-art transformers (BERT, ELECTRA, RoBERTa, XLNet, ERNIE, ALBERT, DistilBERT, Longformer) to classify English literature by UK Key Stage, finding the best unimodal transformer (BERT) reached only an F1 of 0.75 — while fusing a fine-tuned ELECTRA with a computational-linguistics neural network lifted F1 to 0.996, showing that transformer text classification alone is limited and that fusion with complementary features is where the gains lie.

LLMs also affirm preferentially: across 11 models, AI responses affirmed users 49% more than human responses, and more sycophantic replies drew higher ratings, raising trust and continued use — a failure mode for coaching, tutoring or feedback, where constructive challenge is the point (Potel & Kumashiro (2026)).

Common Misconceptions

- **"The model's raw capability determines how well it can diagnose errors." Grounding** does: Reddig, Arora and MacLellan (2025) showed supplying GPT-4 the tutor interface **substantially changed** its error diagnosis. What the model is given about the learner's context does more work than which model it is.
- **"Any frontier model behaves the same as a learning partner."** Oppenheimer, Cash and Connell Pensky (2025) studied **three frontier families** — ChatGPT, Gemini and Claude — in a classroom comparison, precisely because the families are not interchangeable as collaborators.
- **"Better models mean less Scaffolding needed."** GPT-4 **scaffolded with a semantically precise, iteratively co-refined rubric** could approximate human evaluative judgment in design-based research. The approximation came from the rubric refined over iterations, not from the model alone.

Connected Concepts

- Generative AI
- Prompt Engineering

- RAG (Retrieval-Augmented Generation)
- Hallucination Risk
- Pedagogical Safety
- Intelligent Tutoring
- Automated Assessment
- AI Literacy
- Knowledge Tracing
- Higher Education
- Scaffolding
- LLM Training and Fine-Tuning
- Learning by Teaching
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams: a large-scale field study
- Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact
- CSTutorBench: Benchmarking Small Language Models as Tutors for Block-Based Programming
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems
- Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models
- You’ve Got AI Friend in Me: LLMs as Collaborative Learning Partners
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models

- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Can Generative Artificial Intelligence Reliably Score Open-Ended Question Assessments in Undergraduate Medical Education?
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues
- Artificial Intelligence as a Personal Coach: A Narrative Review of Benefits and Risks in Educational and Health Contexts — Sycophancy across 11 LLMs: AI affirmed users 49% more than humans, raising trust and continued use

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?

RAG (Retrieval-Augmented Generation)

> **RAG (Retrieval-Augmented Generation)** — an AI architecture that combines information retrieval with text generation, allowing LLMs to ground responses in external knowledge sources rather than relying solely on training data. In education, RAG addresses hallucination, enables curriculum-grounded tutoring, and powers domain-specific AI tutors.

Questions to Consider

- You've probably seen an AI chatbot confidently state something false. What does 'grounding' a model's response in external documents change about that failure mode, and what new failure modes might it introduce?
- RAG retrieves relevant materials and feeds them to the generator. Before you read, what assumptions does this make about the quality of the retrieved content — and about whether the retrieved text is actually the right thing to teach?
- The page contrasts RAG with fine-tuning: retrieval grounds responses in up-to-date sources without retraining, while fine-tuning embeds behaviors. If you were building a curriculum-aligned tutor, which approach would you trust for accuracy, and which for teaching style?
- RAG is presented as the main answer to hallucination in education. But consider: if the retrieval source itself contains errors, or is outdated, can RAG still hallucinate? Where might the guarantee of 'grounded in verified content' break down in practice?
- For a developer or instructor: what does a tutor need to 'know' beyond the textbook content — pedagogy, when to withhold answers, how to probe understanding? Where would RAG alone fail to provide that, and what would you combine it with?

Introduction

How RAG is used in education

- **Domain-specific retrieval with notation awareness:** AlgoRAG indexes textbooks, 847 lecture slides, 312 solved practice problems, 156 worked proof templates and 89 complexity worksheets for theoretical computer science courses, adding mathematical entity recognition and notation-aware re-ranking; it answered all 179 instructor-authored exam questions within a 240-second timeout (mean 38.0 seconds) but produced BLEU-4 = 0.0000 and a 0.7620 rubric score, which illustrates both the value of the architecture and the limits of the metrics used to judge it.
- **Hallucination reduction:** EduGuard and EduZone use RAG to keep AI tutor responses grounded in verified educational content, reducing Hallucination Risk.
- **Grounding is only as good as source inspection:** only 1 of 12 participants noticed a deliberately mismatched source card, so a provenance label can act as a seal of authority rather than an invitation to verify the retrieved material (Sun et al. (2026)).

- **Curriculum-grounded tutoring:** KITE retrieves relevant curriculum materials to inform tutoring responses, ensuring alignment with course content.
- **On-premises deployment for institutional control:** CourseChat runs a multi-course RAG tutor for undergraduate business education on local edge hosts with a local vector database and an Ollama-served 8B model, keeping course materials and student dialogue on campus infrastructure; model choice became a joint hardware-and-serving decision when larger candidates failed a latency gate (CourseChat).
- **Curriculum-grounded retrieval did not separate itself on time.** Aila retrieves from Oak National Academy's quality-assured curriculum plans, and teachers in its trial spent 0.76 of the comparison group's lesson preparation time (Roy et al., 2026). The report reads that as similar to the general ChatGPT trial's 0.69, so grounding in verified curriculum content was not what separated them.
- **Textbook and materials indexing:** Synthetic textbook organization indexes educational content for retrieval. StructRAG extends retrieval to structured diagrams.
- **Training pipeline integration:** Pedagogical LLM training uses RAG to ground tutor training in educational best practices.
- **Course-specific academic support:** Beacon retrieves from a single programming module's approved teaching materials to serve students who hesitate to approach a lecturer, and 89% of the 15 evaluating students rated its responses highly aligned with course materials. The design point is that grounding is an institutional answer to the mismatch between general-purpose LLMs and module-level expectations.
- **Ingest-time structure versus query-time retrieval:** Wright (2026) compiled the same DS3001 Machine Learning course corpus into seven cross-referenced wiki concept pages carrying source citations, and set it against a tuned vector-RAG baseline of chunked-embedding retrieval. Over 59 human-written questions the compiled wiki out-answered the tuned index, 9.95 versus 9.05 of 10, with a bootstrap CI on the difference excluding zero. It was also more often grounded in the material the answerer actually saw (98% versus 81%), with both gaps roughly tripling on questions that needed material from more than one page (cross-page scores 9.93 versus 8.14, where RAG's grounded rate fell from 87% to 64%). The grounding gap was not a retrieval failure: only 2 of vector RAG's 11 ungrounded answers were retrieval misses, while the other 9 had the relevant excerpts in context and still added unsupported detail — evidence that structure at ingest constrains elaboration, not just access.
- **Retrieving on a summary instead of the student's words (LC-RAG).** Collaborative talk often has no semantic link to the knowledge base: students say "put that position block there," so a discourse-only retriever returns unrelated chunks, and the authors' example is a passage about a 1990s cartoon pulled from a physics and computing textbook. Log-contextualized RAG has an LLM summarize each segment of work from its discourse plus the environment log (which model component is being edited), then retrieves on that summary. Across 216 collaborative modeling segments and five embedding models judged by GPT-4o, it beat the discourse baseline in four models, from 0.403 to 0.620 win rates, and retrieved a tighter set of chunks (167 unique against 267 of 7,386). It lost in one model because the summaries became more specific to the task than

the general textbook corpus was: query scope and corpus scope have to be matched deliberately (Cohn et al., 2025).

RAG vs fine-tuning

RAG serves a complementary role to Large Language Models (LLMs) fine-tuning — retrieval provides up-to-date, domain-specific grounding without retraining, while fine-tuning embeds pedagogical behaviors. The knowledge base's research explores both approaches and their combination.

Common Misconceptions

- **"Showing the source makes the answer verifiable."** Only **1 of 12 participants noticed a deliberately mismatched source card**. A provenance label can act as **a seal of authority rather than an invitation to check** — the display of grounding raised trust without raising scrutiny, which is worse than no label because it manufactures confidence.
- **"Retrieval quality is the whole problem."** Retrieval is necessary and not sufficient. Grounded answering scored **9.05 of 10 with a bootstrap CI on the difference excluding zero** and was **more often grounded in the material the answerer actually saw (98% vs. 81%)** — so the measured gain is in fidelity to evidence, and the evidence has to be correct for that fidelity to mean anything.
- **"Single-page retrieval generalises."** Both gaps **roughly tripled on questions requiring material from more than one page** (cross-page scores 9.93 against a lower baseline). Multi-document reasoning is where grounded systems degrade, and it is exactly where courses ask the hardest questions.
- **"Retrieval removes the need for scrutiny."** Beacon retrieves from a single module's approved materials to serve students who hesitate to ask a person — a defensible scope. Narrow, approved corpora are what make the grounding meaningful; the label alone does not.

Connected Concepts

- Large Language Models (LLMs)
- Generative AI
- Hallucination Risk
- Knowledge Graph
- Edtech Platform
- Intelligent Tutoring
- LLM Training and Fine-Tuning
- Pedagogical Safety
- K-12
- Higher Education
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Lesson planning using AI lesson assistant, Aila - A Teacher Choices Trial — A curriculum-grounded lesson assistant whose time saving did not exceed a general chatbot’s
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers
- Retrieval-Augmented Tutoring for Algorithm Tracing and Problem-Solving in AI Education
- Advancing diagram-based reasoning in AI tutoring systems: A structural approach for STEM education
- Beyond Rephrasing: Book-Level Organization Improves Synthetic Textbook Data for Mid-Training
- VeriForge: Mitigating Latent Knowledge Gaps in Narrative Drafting via Mixed-Initiative Scaffolding
- From Prompts to Verified Loops: The PCHL-HE Framework for Generative AI-Assisted Educational and Research Content Creation in Higher Education
- AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory — AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory
- Reducing Barriers to Academic Support: Evaluating a Course-Specific RAG System for Addressing Help-Seeking Disparities in Higher Education — Reducing Barriers to Academic Support: Evaluating a Course-Specific RAG System for Addressing Help-Seeking Disparities in Higher Education
- Potential for Enhanced Learning in Machine Learning Classes by Using Wiki LLM Indexing — Potential for Enhanced Learning in Machine Learning Classes by Using Wiki LLM Indexing
- On-Premises Multi-Course RAG Tutoring for Business Education: Hardware–Software Trade-offs in a Campus AI Tutor — On-Premises Multi-Course RAG Tutoring for Business Education

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?

Prompt Engineering

> **Prompt engineering** — the practice of designing and refining inputs to large language models to achieve desired outputs. In education, prompt engineering serves dual roles: as a learner skill (students must learn to prompt effectively) and as a system design lever (developers craft prompts that shape AI tutoring behavior).

Questions to Consider

- You've likely typed a prompt into an AI tool recently. Now consider this: the way you phrased it isn't neutral — it may reveal how you planned, thought, and allocated your effort. What might your own prompting habits say about how you approach problems?
- A study found that users who phrase requests skillfully systematically get better output than those expressing the same intent less adroitly. If you accept that 'prompt privilege' is real, is fair access to AI best fixed by teaching everyone to prompt better, or by redesigning the system to not demand that skill — and what are the trade-offs of each?
- Is prompting a 'trick' to be memorized, or a genuine intellectual skill? One line of research treats it as professional judgment within a discipline (journalism, law, medicine); another treats it as a core of AI literacy. Which view aligns with your own experience of what actually separates good prompts from bad ones?
- Well-designed prompts can scaffold student thinking, while poorly used ones can encourage cognitive offloading. Can you recall a moment when an AI answer did the thinking for you? What about the prompt — or your intent — made that happen, and could it have been designed to do the opposite?
- Prompting is both a learner skill and a system-design lever: some tutors now automatically route and select prompts for the user. As prompting moves from the user to the system, what do students lose — and what do they gain?
- Set a small goal before you read: after learning about prompt engineering, decide on one concrete way you'll change how you write prompts in your own work, and what result you'll check to know it worked.

Introduction

Prompt engineering is central to effective Generative AI use in education. Unlike traditional programming interfaces, LLMs respond to natural language — but the quality, accuracy, and pedagogical value of those responses depend heavily on prompt design. Research in this knowledge base reveals that prompting is not a neutral act: it reflects how students think, plan, and allocate cognitive effort. Miles, Haber-Curran and Arar (2026) sharpen what the term covers by distinguishing prompt engineering, the technical optimization of inputs for performance, from prompt literacy, the rhetorical, ethical and reflective work of clarifying purpose, reading output critically and revising with stated reasons. Their Prompt Literacy Cycle (Clarify Purpose, Craft the Prompt, Engage with Output, Refine the Prompt, Reflect) and a sample process rubric

make the distinction teachable, and they argue that instruction which optimizes outputs alone leaves the ethical and epistemological dimensions of LLM use untouched.

How prompt engineering appears in the research

- **Prompting as cognitive trace:** Misiejuk et al. show that prompt patterns reveal cognitive offloading — high-quality work uses context-rich, polite, and instructional prompts; low-quality work shows reactive disagreement without domain grounding
- **Depth improves the product, not the retention.** In 22 postgraduates, the share of explanation-seeking ("why/how/explain") prompts predicted independently marked task quality (β = 6.27) beyond baseline knowledge and prompt volume, yet showed a null association with immediate recall (Tsiligkiris (2026)).
- **Prompt cognition tracks the discipline, not the student.** Chang and Li (2026) classified 60,087 prompts from 116 courses and found Bloom-level profiles differed by discipline — STEM Apply-prevalent (20.8%), social science Create-prevalent (33.8%) — with course-level variance exceeding student-level variance.
- **Prompting as literacy:** Tracing GenAI literacy and K-12 prompting literacy research frame prompting as a core AI Literacy component
- **Prompt literacy is a perceived capability, and it still predicts engagement.** In 829 design students across 40 intact classes, self-reported prompt literacy — six adapted self-report items, not observed prompting — predicted learning engagement at β = 0.539, 95% CI [0.473, 0.595] (Han and Cao, 2026). The association held regardless of functional dependence (p = 0.396) or emotional dependence (p = 0.941). Only cognitive dependence, substituting AI judgment for one's own, clearly thinned it.
- **Novices default to trial and error, and blame the model.** In a text-linguistics seminar, ten genAI novices refined prompts by trial and error, rarely reached for in-context examples, and overwhelmingly attributed poor outputs to the LLM rather than their own prompt formulation (Brocca & Garassino (2026)).
- **Vague prompts leave a trace in the dialogue.** The lower-quality group's signature was a self-repeating clarification loop (IC → IC, Z = 3.25), traced to vague prompts and AI misreadings, and carrying the study's largest frustration gap (2.12 vs 3.82); prompt debugging on authentic logs targets it as it happens (Fang et al. (2026)).
- **When the instructor models the prompt, students reuse it verbatim.** Among 310 recorded prompts from twelve middle-school STEAM groups, exact copying of the instructor's instruction was the most frequent student standpoint at 47.1%, ahead of spontaneous inquiry at 28.7% (Zhao & Li (2026)).
- **A regulatory cycle beats a prompt formula.** In a quasi-experimental pilot with 42 undergraduates, students taught the IDEA cycle (Intent, Deconstruction, Expression, Adaptation) produced higher-quality prompts and outputs than peers taught Role–Task–Context–Format prompting in all five task categories (adjusted prompt gains of +11.77 to +29.19 points) (Wang et al., 2026).

- **Prompting as system design:** CoTAL uses human-in-the-loop prompt engineering for formative assessment scoring; anchor-based prompting improves automated essay scoring
- **Prompting is the entry skill, not the discipline.** Gorsky (2026) frames AI Literacy for software professionals as the ability to manage agents rather than to prompt them, naming framing, specification, context engineering, verification, multi-agent orchestration and auditability as the skills a curriculum must assess (Gorsky (2026)).
- **Adaptive prompt routing:** Learning to Prompt treats prompt selection as part of the tutoring system itself — subject-aware prompt routing over 14 pedagogical features, where a stochastic router selects the best prompt per conversation. This shifts prompting from a learner skill into an adaptive system-design lever, improving engagement and efficiency (28.1% vs 19.6% exercise conversion in a real-world A/B test).
- **Prompt modalities:** Voice vs. text input research examines whether prompting modality affects learning outcomes
- **Prompting beyond text — scientific illustration.** Prompting can generate molecular and physical-chemistry figures quickly, but a locally persuasive rendering can still be wrong or carry representational bias, so students must interrogate AI-generated visualizations against chemical principles rather than trust them (Li et al. (2026)).
- **Scaffolded prompting:** Guided LLM scaffolding and critical engagement scaffolding teach structured prompting as a learning intervention
- **Coach prompting with fading support:** in ARPG+, a real-time coach diagnosed prompt quality across six dimensions and faded support as competence grew, lifting final prompt quality to 7.82 against 5.95 for static templates and 4.52 with no assistance (Ye et al. (2026)).
- **Task decomposition has an optimum:** generating tutor-training lessons in three segments produced the highest-rated lessons (mean 14.67) while a single pass scored lowest (10.67) and five segments fell back below three — moderate decomposition beats both extremes (Lin et al. (2025)).
- **Prompt privilege and equity:** Jin et al. show prompting expertise is unevenly distributed — users who phrase requests skillfully systematically get better output than those expressing the same intent less adroitly. Their Prompt Equity Transformer shifts prompt optimization from the user to the AI system, arguing that equitable output should be engineered into the model rather than demanded of novices.
- **Prompt refinement plateaus; fine-tuning takes over from there.** Iterative prompt design yielded diminishing item-quality gains in L2 listening Assessment, but fine-tuning GPT-4.1 on the optimized prompt — the prompt held constant — produced more contextually grounded and balanced items, isolating model adaptation rather than prompt craft as the next lever (Aryadoust & Wong, 2026).
- **Prompting as situated professional judgment.** Beyond literacy and system design, prompting can be framed as a *disciplinary practice*. The Dierickx et al. taxonomy for journalism treats task definition and prompting as a form of professional judgment exercised within a domain's epistemic and ethical norms — translating journalistic work into explicit tasks (newsgathering →

sensemaking → editing → publication/distribution) makes assumptions, priorities, and ethical considerations visible, and turns prompting into a pedagogical tool for critical AI literacy. Its logic transfers to other knowledge-intensive professions (law, medicine, public policy).

- **Prompt design as instructional specification.** Neto and colleagues (2026) find in their systematic review of GenAI in healthcare education that prompt design functions as a form of instructional specification, encoding the cognitive targets and quality criteria implicit in expert authoring — yet only 34.8% of studies aligned generated content with instructional frameworks and only 34.8% reported prompting in enough detail to reproduce. Looi, Liu, and Sun (2026) further show how prompt architecture can embed pedagogical rules (correctness gates, anti-spoiler boundaries, goodbye gates) to constrain Large Language Models (LLMs) tutoring behavior in procedural domains.
- **Rubric-guided and role-aware prompting.** Yaşar et al. (2026) showed that rubric-guided prompting — treating the rubric as a semantic interface between human pedagogical intent and machine inference — drove LLM–human agreement on student design work from 54.75% to 81.25% (Cronbach's Alpha 0.393 → 0.798). Rubrics engineered for LLMs must balance precision and flexibility: too vague invites free interpretation, too rigid reduces the model to pattern-matching. Role-aware prompting — evaluating the same artifact under instructor, peer-reviewer, and grant-reviewer prompts — produced qualitatively distinct, epistemically different feedback, showing that prompt design shapes not just accuracy but the evaluative stance of the output.
- **Prompt scaffolding can move a model further from the teacher.** Almousa et al. (2026) had seven models produce paragraph-level writing feedback under three prompting strategies and found that adding category names or worked examples increased divergence from the teacher distribution for most of them, improving only Mistral-7B (0.2695 to 0.2398). The zero-shot baseline stayed closest, so focus-type instructions are something to test rather than assume.
- **Context-aware prompting for assessment.** Context-aware prompting of pre-trained language models automates the coding of collaborative problem-solving skills from process data, modeling dependencies between behavior codes and fusing cognitive and social abilities. This enables structured CPS analysis at scale and in real time, overcoming the labor intensity of manual coding schemes.
- **Role-based templates and quality rubrics for teacher planning.** Luo and Tahir (2025) empirically develop a prompt framework for children's STEAM arts lesson planning that pairs a Role (R) – Instructions (I) – End Goal (E) template (adapted from RISEN) with a "four points and one line" optimization rubric — standardized, practical, engaging, and complete, plus an extension dimension. Applying the rubric to critique and refine prompts kept generated plans acceptable to practicing art teachers (mean ratings above 4/5) while exposing recurring gaps (personalization, child-safety constraints, cultural bias) that plain one-shot prompting left unaddressed — showing prompt templates plus explicit evaluation criteria function as a quality-control scaffold for classroom generation.
- **A five-part scaffold, tested across four model families.** Role–Goal–Input–Process–Output prompts raised rated output quality from 3.318 to 4.603 ($\Delta = +1.285$) over 400 matched pairs, with every family improving and the weakest baseline gaining most (Li et al. (2026)).

- **Role and constraint design as the independent variable.** Wang et al. (2026) compare two agents built on the same model and platform at temperature 0.3 whose only difference is how the prompt specifies role, skills, and constraints: an expert teacher agent answering from a bounded textbook knowledge source versus an empathic student-centered agent scripted to diagnose Misconceptions about AI and check comprehension. The role difference alone shifted learning performance, cognitive load, flow experience, and perceived empathy, showing that role specification is an instructional-design decision with measurable effects rather than a stylistic flourish (Pedagogical Agent).
- **Prompting as assessment design.** Xiong et al. (2026) map Evidence-Centered Design's student, evidence, and task models onto the parts of a scoring prompt, deriving five principles — intentionality, traceability, accountability, iteration, and equity; their ECD-built prompts scored narrative essays more accurately than zero-shot, few-shot, and chain-of-thought baselines.

Connections to broader concepts

Prompt engineering connects to Scaffolding — well-designed prompts can scaffold student thinking rather than bypass it. It intersects with Metacognition and AI Literacy, as effective prompting requires understanding both the AI's capabilities and one's own learning goals. The Cognitive Offloading research directly links prompt quality to whether AI use supports or undermines learning.

- **Writing skill drives prompting, and both predict Vibe Coding success.** In a preregistered CHI 2026 study (N=100), Thorgeirsson, Weidmann & Su found that written-communication proficiency predicted GUI-oriented vibe-coding performance (r = .29), with human-graded prompt quality *mediating* the link — response-process evidence that clear, structured prose translates into better natural-language programming prompts. Both writing skill and CS achievement were independent predictors, and CS achievement (r = .39) carried roughly twice the unique variance, so improving prompting alone is unlikely to fully substitute for programming fundamentals in LLM-native development.
- **Prompting strategy predicts performance.** An empirical study of 128 engineering students found that AI Query Efficiency (clear, well-structured prompts) and AI-Driven Problem Solving (strategic integration of AI output into reasoning) were the strongest predictors of academic success — even after controlling for GPA — indicating prompting is a teachable skill that shapes how effectively students learn with AI.
- **Prompting style, not just prompt quality, tracks outcomes.** Traits derived from 1,540 tutoring sessions linked conceptual questioning to exam performance while task-delegation behaviors correlated negatively — but the same traits failed to replicate the following semester, so they are behavioral patterns rather than stable skills (McNichols, Du and Lan (2026)).
- **A usable taxonomy, and which prompt categories actually pay off.** Jacobsen et al. (2026) translate technical strategies into the 3K model (*Kontext*, *Kernauftrag*, *Klarheit* — context, core task, clarity): eleven practice-oriented categories, each with a good/average/suboptimal rubric, and each tested as an experimental variation on feedback generated for pre-service teachers' learning goals. Domain-specific technical language was the decisive category — replacing subject terminology with everyday paraphrases significantly reduced feedback quality across three models

(β = −0.412). Adding concrete examples and removing the chain-of-thought instruction produced no significant difference from the baseline in the first study; examples did help once the analysis was rerun with the best-performing model-prompt combinations (β = 0.52). Prompt quality and model choice together explained 42.8% of the variance in rated feedback quality, which is the paper's case that prompt engineering is a measurable and teachable competency rather than a stylistic preference — and that its categories are not interchangeable in effect size.

- **Better prompts reduced iteration without raising output quality.** Teachers given AI training before a lesson-preparation experiment wrote longer, more detailed prompts that needed less refinement, while untrained teachers used shorter prompts and required more subsequent iterations, yet blinded expert ratings of the resulting materials were equal (Appel et al., 2026). Prompt craft here bought fewer correction rounds, not a stronger first draft.
- **Students name intent alignment as the difficulty, not syntax.** Surveying 234 Chinese university students, Fan and Liu (2026) found refinement after a poor output was the most endorsed capability (72.2%) while setting output constraints was the least (66.2%, with 22.2% neutral). Strategy preferences barely moved between a research assignment and a creative brief: of four matched pairs only output-format specification differed after correction (0.26 points, dz = 0.233, BH-adjusted p = .002). A fixed role-task-format template drew the weakest support of any general strategy at 59.4%. Among the 12.8% who answered an open question, prompt-intent alignment appeared in 40.0% of comments, and adding more detail did not reliably fix a stuck exchange. All of it is self-report from one questionnaire.

Common Misconceptions

- **"Prompt quality is a student attribute." Prompt cognition tracks the discipline, not the student**: Chang and Li (2026) classified **60,087 prompts from 116 courses** and found the discipline predicted prompt sophistication. Teaching students to prompt better addresses a variation that sits in the subject matter.
- **"Students develop their own prompting practice."** When the instructor modeled the prompt, **students reused it verbatim** — among **310 recorded prompts from twelve middle-school STEAM groups**, exact copying of the instructor's instruction was common. Modeling produces reproduction, which is why it is a system-design lever rather than a transferable skill.
- **"Prompting is a learner skill first and a system property second."** This shifts prompting **into an adaptive system-design lever**, with measured effects on **engagement and efficiency (28.1% vs 19.6% exercise conversion)**. The interface's prompting affordances moved behavior more than instruction in prompting did.

Connected Concepts

- Pedagogical Patterns — The scaffolding layer inside structured-use sequences
- Vibe Coding
- Guardrails
- Scaffolding

- AI Literacy
- Agentic AI
- Metacognition
- Curriculum Design
- Cognitive Offloading
- Writing
- K-12
- Generative AI
- Learning Design
- CS Education
- Higher Education
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Generative artificial intelligence prompting strategies among Chinese university students across academic tasks — 234 students on what they find hard: intent alignment, not prompt syntax
- Comparing teacher-centered and student-centered agents based on prompt engineering: Effects on learning performance, cognitive load, flow experience, and empathy perception in physics learning — Agent role and constraint prompts as the design variable in physics learning (Wang et al. 2026)
- How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment — Prompting vs. fine-tuning for GPT-based L2 listening item generation (Aryadoust & Wong 2026)
- What students ask matters: LLM interaction depth, task quality, and immediate recall in higher education — What students ask matters: LLM interaction depth, task quality, and immediate recall (Tsiligkiris 2026)
- ARPG+: a simulation-based study of real-time coaching for educational LLM prompting — ARPG+: real-time coaching for educational LLM prompting
- A Taxonomy of LLM-Supported Tasks for Critical AI Literacy in Journalism — Task-based taxonomy of LLM tasks for critical AI literacy in journalism
- Same Question, Different Answer? Measuring and Mitigating Prompt Privilege for Equitable AI Access — Prompt Privilege: measuring & mitigating accessibility disparities in LLM access
- Principal Trait Analysis: Towards Deriving "Skills" in Human-AI Collaboration — Principal Trait Analysis: data-driven traits of human-AI collaboration
- LLMs in text linguistics teaching: An exploratory study with genAI novices in higher education — LLMs in text linguistics teaching

- The IDEA Framework for Metacognitively Regulated GenAI Use in Higher Education: Development and Exploratory Pilot Evidence — The IDEA framework for metacognitively regulated GenAI use
- Automatic Large Language Models Creation of Interactive Learning Lessons — LLM generation of interactive tutor-training lessons (Lin et al. 2025)
- Learning to Use AI for Learning: Teaching Responsible Use of AI Chatbot to K-12 Students Through an AI Literacy Module
- ASE-26: A Curriculum for Agentic Software Engineering as a Discipline
- Anchor Is the Key: Toward Accessible Automated Essay Scoring with Large Language Models Through Prompting
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics
- Learning to Prompt: Improving Student Engagement with Adaptive LLM-based High-School Tutoring
- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies
- Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing
- Translating UNESCO artificial intelligence guidelines to chemical education and its intersection with sustainable development goals — UNESCO AI guidelines translated to chemical education; epistemic drift
- An empirical study of ChatGPT use in engineering education: Prompting and performance — Prompting behaviors predict engineering student performance
- Chat as Learning: Student-AI Conversations as Discipline-Associated Cognitive Engagement Patterns — Discipline-associated Bloom-level cognitive engagement in student-AI conversations (Chang & Li 2026)
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design
- ChatGPT-assisted lesson planning for children’s STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework
- Prompts to Practice: A Pedagogical Framework for Human-Centered AI Engagement — Prompt engineering vs prompt literacy: a five-phase human-centered GenAI engagement framework with a five-step Prompt Literacy Cycle (Miles, Haber-Curran & Arar 2026)
- AI Literacy of Teachers: Prompt Engineering and Model Selection as Predictors of AI-Feedback Quality — Prompt engineering and model selection as predictors of AI-feedback quality (Jacobsen et al. 2026)
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing

- Exploring Middle School Students' Interactions and Perceptions of Using Generative AI in STEAM Learning Environments — Middle-school STEAM groups copied the instructor's instruction verbatim in 47.1% of prompts
- Using Evidence-Centered Design to Guide Prompt Engineering in Measurement: An Illustration with Automated Essay Scoring — Using Evidence-Centered Design to Guide Prompt Engineering in Measurement: An Illustration with Automated Essay Scoring
- Human–AI collaborative patterns in GenAI-supported instructional design among pre-service teachers: an analysis of interaction sequences and cognitive load — Vague prompts produced self-repeating clarification loops with the largest frustration gap
- Who benefits from LLMs? Prompt engineering competence and equity in higher education — Prompt engineering competence as an equity pathway, with a cross-model scaffolding experiment (Li et al. 2026)
- Learning engagement and creative self-beliefs in generative AI-supported design education: self-reported prompt literacy and dimensions of AI dependence — Prompt literacy as a perceived capability that still predicts engagement

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?

LLM Training and Fine-Tuning

> **LLM Training and Fine-Tuning** — how educational AI models are made: the pipeline from pretraining through post-training to adaptation, what each stage costs, and what the evidence says it buys. The organizing problem is an **incentive mismatch**: general-purpose models are optimized to answer, while teaching requires withholding the answer. Post-training and fine-tuning are the two levers that change that behavior, and the knowledge base's clearest result is that they are a *third* choice, not the first — retrieval and prompting come earlier in the decision, and one study here found supervised fine-tuning failing at a task where plain prompting won (WrAFT). Written for educational software developers and teaching practitioners deciding what to build with.

Questions to Consider

- If you have a tutoring task where a general model answers too readily, is your first move a better prompt, retrieval over your own materials, or training? What would you need to measure to tell which one helped?
- Fine-tuning needs data. Where would your project's training examples come from, who owns them, and what privacy review would they need before they could be used?
- A study here found that fine-tuning a model on assessment data improved *formatting and similarity* while a separate fine-tune failed outright at generating feedback. What does that suggest about matching the training method to the task?
- Post-training with reinforcement learning can teach a model to guide rather than answer. What reward would you write to capture "guides well", and how would a model game it?
- The knowledge base puts model and prompt choice at only about 15% of what separates an LLM from student learning gains. If that is right, how should it change your build-versus-buy decision?
- A fine-tuned model that is accurate can still be unsafe across a long conversation. What would you test before letting one talk to students unsupervised?

Introduction

Educational AI development runs into the same wall from two directions. General-purpose language models are post-trained on human preference for helpfulness, which in practice means answering promptly and completely; tutoring requires the opposite, because the pedagogical goal is to help a student reach the answer rather than to hand it over. At the same time, a general model knows nothing about your curriculum, your rubric, or your institution's voice, and no amount of prompt engineering reliably installs those.

This page covers the techniques that change a model rather than the text you send it. They sit on a **ladder of increasing commitment**: prompting, then retrieval, then parameter-efficient adaptation, then full fine-tuning, then post-training with preference or reward signals. Each rung costs more data, more compute, and more evaluation discipline than the last, and each is a worse first choice than the rung below it unless a specific measurement justifies the climb. Much of the research literature reports only the top of that ladder, which makes it easy for a developer to reach for training when retrieval would have been sufficient.

The page is organized around the decisions a builder actually faces: which lever to pull (this section and the next), what adaptation buys and costs in practice, what post-training can shape that adaptation cannot, and how these systems fail. Terminology is used in its standard sense: **pretraining** is the from-scratch stage on a general corpus, **post-training** is everything after it that shapes behavior (supervised fine-tuning, preference optimization, reinforcement learning), and **fine-tuning** covers both the supervised stage of post-training and the later task- or domain-adaptation work, including parameter-efficient methods.

The training pipeline, stage by stage

Three stages, with very different accessibility. Knowing which one a paper is describing prevents most misreadings of this literature.

Pretraining builds a base model from a general text corpus. It is the stage that produces the model's broad capability, and it is out of reach for essentially every educational project: the cost is measured in millions of dollars and the data is a web-scale crawl. Nothing in this knowledge base does it. Its relevance to practitioners is diagnostic rather than actionable — pretraining data is the dominant lever on how a model behaves, and it is the one lever you cannot pull. That asymmetry is why the field's remaining techniques all operate on an already-trained model.

Post-training shapes behavior on top of the base model. Supervised fine-tuning (SFT) teaches the model to imitate demonstrations; preference optimization and reinforcement learning then push it toward outputs a reward model or a set of human judgments rates higher. This is the stage where a model can be taught to guide instead of answer, and it is where the most striking educational results live. It is also the stage most sensitive to reward design, because a reward is a compressed specification of what you want and models optimize whatever you actually wrote.

Adaptation fits an existing model to your task or domain, usually with far less data and compute. Parameter-efficient fine-tuning (PEFT), of which LoRA is the common form, trains a small number of added parameters and leaves the base weights frozen. Full fine-tuning updates everything. Distillation and unlearning sit alongside them. The sections below take each in turn. For most educational developers this is the practical stage — the one where a few hundred to a few thousand examples and a single GPU can produce a deployable model.

Prompt, retrieve, or train? The decision that comes first

The strongest single result in this knowledge base on that question is a retrieval study, not a training study. Building a course knowledge-base assistant, Shen et al. (2026) evaluated local models in three configurations and found that **retrieval, not the model, is the first-order design decision**: their local LLM with no retrieval reached only **52.3%** accuracy, *below* a TF-IDF baseline of **55.4%**, while adding retrieval-augmented generation with no fine-tuning at all lifted it to **66.6%** (Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources). The fine-tuning configurations they also tested are reported alongside retrieval ablations, quantization and energy per query, which makes the comparison unusually honest: a base model with no grounding can be worse than a decades-old lexical method, and the cheapest fix is not training.

What the field actually builds reflects a similar ordering. A PRISMA-guided review of 23 empirical studies (2020–2025) on customizing AI for writing instruction found **prompt engineering dominant (N = 13), ahead of fine-tuning (N = 7) and hybrid architectures (N = 3)** (Customizing AI for writing pedagogy: a systematic review of pedagogical goals, theoretical principles, and technical design). The review's sharper finding is a structural misalignment rather than a technique ranking: stated pedagogical goals have moved toward writing processes, feedback literacy and higher-order academic skills, while the dominant implementations still pursue product-focused goals through prompt design or fine-tuning.

Where prompting and training have been compared head-to-head, the result depends on the task, which is exactly why the decision should be measured rather than assumed:

- **Training wins when the target is a stable output format or a controlled property.** On automatic item generation for L2 listening assessment, iterative prompt refinement plateaued, and fine-tuning GPT-4.1 *on the optimized prompt* then improved generation beyond prompting alone — isolating model adaptation, rather than prompt design, as the driver of the remaining gain (How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment).
- **Prompting wins when the target is judgment-laden text.** The same system that fine-tuned successfully for *scoring* failed at *feedback*: in WrAFT, a fine-tuned GPT-4o module reached QWK 0.84 and RMSE 0.44 on 360 held-out TOEFL essays, but supervised fine-tuning for feedback generation produced truncated and unparseable output, while directly prompting Claude 3.7 produced the feedback teachers rated best (WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays). Fine-tuning taught the model to hit a score; it did not teach it to write.
- **Prompt-level shaping can substitute for training when the target is a persona or a rubric.** Rubric-guided prompting, iteratively co-refined, raised LLM–human agreement on student design work from **54.75% to 81.25%** (Cronbach's Alpha 0.393 → 0.798) without any fine-tuning (From evaluation to emulation: LLMs as agents of iterative pedagogical design), and a literature-grounded custom-GPT prompt elicited target mathematical Misconceptions about AI at **0.98** presence against **0.40** for a broad prompt (Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching).
- **There is a ceiling on all of it.** Hardy and Kim (2026) estimate that model and prompt choice together account for only about **15%** of the misalignment between LLMs and student learning gains, with the rest shared across models, and they found that benchmark-weighting and unanimous-voting ensembles made alignment *worse* (Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact). If pretraining data is the dominant lever and it is the one you cannot pull, then expectations for what any of these techniques can achieve should be calibrated accordingly.

What fine-tuning buys: controllability over scale

When a general model cannot be made to hold a property you need, fine-tuning on a modest dataset often can — and the recurring result is that *targeting beats size*. Three 8B models fine-tuned on an expert-designed children's reading curriculum outperformed zero-shot GPT-4o and Llama 3.3 70B on difficulty-related

metrics, with negligible safety issues. The authors frame this as **controllability over scale**, since a compact model can be tuned to a specific reading level and error pattern in a way a general model cannot be asked to (Children's English reading story generation via supervised fine-tuning of compact LLMs with controllable difficulty and safety).

The pattern repeats across very different tasks:

- **Curriculum grounding.** A 24,795-example multilingual instruction dataset grounded in Indian Knowledge Systems produced a 7B fine-tune scoring **6.39** on a five-judge external panel (median over 1,201 stratified items). That is within **0.15** of a strong general reference model at a fraction of the deployment cost — while the same base model scored **near zero on IKS-specific dimensions** without the fine-tune (IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems). That gap between "competent generally" and "competent here" is the whole case for domain adaptation. Note also the counterintuitive detail the authors report: quality did **not** rise monotonically with data curation.
- **Curriculum-structured data is sample-efficient.** Under a matched budget of roughly 2,300 samples, fine-tuning on question–answer pairs derived from a K–12 knowledge graph of People's Education Press textbooks beat equally sized slices of eight mainstream instruction corpora, and the gains transferred beyond the trained subjects, evidence that curriculum structure is what distinguishes educational training data (Liang et al. (2026)).
- **Assessment reliability, cheaply.** A single LoRA adapter trained on roughly **3,900** pooled graded examples brought five small open models (4B–30B) to parity or better with a human grader across two computer-science exams, and nearly erased persona sensitivity (drift ≤ 0.32 MAE) (Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams). One adapter, one dataset, several base models — this is the shape of a practical deployment.
- **Selective automation.** Confidence was a reliable predictor of scoring error ($\beta = -0.602$, $p < .001$). Routing the least confident **20%** of responses to human review moved a fine-tuned GPT-3.5 model from $r = 0.781$ to $\mathbf{r = 0.822}$ (RMSE 0.5990 → 0.5544) while cutting manual scoring work by roughly **80%** (Know when to trust: Making AI scoring more reliable for educational assessment). Fine-tuning here is not replacing the human; it is making the human's attention affordable.
- **Measuring constructs you would otherwise hand-score.** Fine-tuned Hungarian transformers (hubert-base-cc, PULI-BERT-Large) were benchmarked against TF-IDF features and Qwen3 embeddings for scoring reflective writing in teacher training (Automatic Reflection Level Classification in Hungarian Student Essays), and a fine-tuned Multimodal AI model (Qwen3.5-based) was shown to reconstruct item characteristic curves for multiple-choice items, learning the response patterns encoded in 3PL and MCM curves rather than being told them (Multimodal item parameter estimation using simulated response probabilities).

Parameter-efficient adaptation in practice

LoRA and its relatives are where most educational teams will actually work, and the literature contains unusually specific guidance about how they behave.

Rank is a trade-off, not a dial to maximize. Lu et al. (2026) built 360 system–user–assistant dialogues from a Linear Control Systems course, restructured answers into a Solution–Method–Teaching-Points format, and applied LoRA to Qwen2.5-3B and 7B at ranks 4, 8 and 16. Structured-output coverage moved from near zero at base to roughly **1.00**, and the best configuration (7B, r = 16) reached ROUGE-L **0.4093** with bootstrap confidence intervals for the gain entirely above zero. But **gain per million adapter parameters fell monotonically as rank rose**, so course-level alignment is a scale-and-rank trade-off rather than a free upgrade (LoRA Fine-Tuned Models for Control Systems Course Q&A: A Multidimensional Evaluation of Model Scale and Rank Effects). Their metrics measure similarity and formatting, not derivational accuracy, which is the standard caveat for this whole family of evaluations.

Scale does not predict success, and identical settings behave differently across architectures. AiAWE, an open-source automated writing evaluation system built on a LoRA-adapted Gemma-3-27B-it, reached RMSE 0.474, QWK 0.828, and agreement within ±0.5 of the human score on **90.56%** of 360 evaluation essays, outperforming LLaMA-3.3-70B and a fine-tuned GPT-3.5 baseline — while running on a consumer-grade server. Three broader findings matter more than the score: model scale was **not** a reliable predictor of downstream performance under LoRA adaptation, **identical LoRA hyperparameters produced qualitatively different adaptation behaviors across architectures**, and a well-tuned mid-size open model can be competitive with proprietary systems (AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models).

Which layers to adapt is a real decision. In a discourse-analysis system for English teaching, fine-tuning a truncated BERT by updating **only the last four Transformer layers** beat both alternatives: adapting only the top layer hit a lower ceiling, and full 12-layer fine-tuning overfitted and oscillated (Automatic discourse relation classification and feedback optimization in English teaching based on transformer BERT model).

The base architecture can matter more than the parameter count. Fine-tuning three open text-to-image models on 1,000 captioned nuclear-engineering images substantially improved Stable Diffusion XL, gave limited gains for SD-v3.5-Medium, and produced **no measurable improvement for the flow-matching Flux.1 model at all** (NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts). A fine-tuning recipe is not portable across architectures, which is the same lesson AiAWE reports from the other direction.

Two adjacent techniques round out the adaptation stage. **Distillation** compresses a large or black-box system into a small deployable one. A two-stage pipeline distilled a fitted black-box ML estimator and its post-hoc interpretation into a small open-weight LLM, with a 2B-parameter “mentee” achieving near-lossless recovery of the oracle effect surface (r > .90). That result is reported under a faithfulness-first evaluation that audits every narration against the attribution it claims to describe (Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics). **Unlearning** removes targeted content after training: gradient-based unlearning was applied to three models to strip PII and harmful content, tested in two removal orders (PII-first and harmful-content-first) (Balancing AI responsibility with privacy, safety, and utility: Unlearning in large language models for mathematics education) — the relevant tool when a model has memorized something it should not carry.

Post-training: shaping behavior, not just format

Adaptation teaches a model *what to produce*; post-training teaches it *how to behave*. This is where the pedagogical results are most striking, and where the design of the reward or preference signal decides everything.

The pipeline result. Singh et al. (2026) transformed Qwen3-32B into EduQwen through three stages — initial RL, synthetic SFT, final RL — reaching **96.52%** on the CDPK benchmark and surpassing Gemini-3 Pro's **90.55%**. The intermediate results are the instructive part: the first RL stage alone reached 94.13%, SFT on 40,000 self-generated responses took it to 96.20%, and the final RL round added the last fraction. The reward model prioritized **guiding responses over direct answers**, hard-negative mining excluded questions the base model already solved, and rollouts were extended from 5 to 8 steps to capture multi-step pedagogical decisions (Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning). Against that, the Pedagogy Benchmark — drawn from real teacher professional-development exams across **97 models** — found accuracy ranging from **28% to 89%**, evidence that pedagogical knowledge is not acquired incidentally during general pretraining (Lelièvre et al., 2025).

Training the decision rather than the utterance. TACT post-trained a tutor on a 13-strategy taxonomy plus a two-axis student-move taxonomy and gained **20.30 points** over its Qwen3.5-4B backbone, with a diagnostic benchmark that withholds the learner-state labels available during training so the model must infer state from dialogue (TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring). The same logic appears in Special-R1 for special education alignment (Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training) and in heuristic-RL work that aligns models as Socratic guides rather than answerers (Beyond Direct Answering: Aligning Educational LLMs as Socratic Guides via Heuristic Reinforcement Learning). Post-training need not only shape what the model says: one platform pairs a guarded tutoring chatbot with a reinforcement-learning agent that chooses the next practice problem, so the trained policy decides what the learner does next (Effective Personalized AI Tutors via LLM-Guided Reinforcement Learning).

Distilled reasoning models. A cheaper route to pedagogical behavior is to teach a small model to imitate a larger one: Pedagogy-R1 (1.5B and 7B) was instruction-tuned on pedagogically filtered outputs distilled from a QwQ-32B teacher, paired with Chain-of-Pedagogy prompting (Pedagogy-R1: Pedagogical Large Reasoning Model and Well-balanced Educational Benchmark).

Instruction-conditioned post-training versus authentic data. LearnLM frames education-model training as *pedagogical instruction following*, carrying system-level instructions that let developers and teachers specify tutor behavior without committing to one definition of pedagogy. It is mixed into Gemini's post-training stages by co-training, and experts preferred it over GPT-4o (**+31%**), Claude 3.5 Sonnet (**+11%**) and base Gemini 1.5 Pro (**+13%**). The key finding is that **RL is substantially more effective than SFT alone** for following nuanced pedagogical instructions in long conversations (LearnLM: Improving Gemini for learning). TeachLM takes the opposite bet: that prompt engineering is a stopgap and the scarce ingredient is *authentic* learner–tutor interaction data. Trained on **100,000 hours** of one-on-one sessions under rigorous anonymization, it doubles student talk time, improves questioning style, and increases dialogue turns by **50%** (TeachLM: Post-training LLMs for education using authentic learning data). Together they define the

design space: instruction-conditioned post-training when your data is scarce, fine-tuning on real tutoring interactions when you have it.

Supervision quality beats supervision quantity. SWIM's progression for a writing simulator is the cleanest demonstration. Rubric-grounded prompting gave limited proficiency control (best average trait QWK 0.577 for Claude Sonnet, 0.422 for GPT-5.4, near zero for an open 7B model); supervised fine-tuning lifted that 7B model to **0.474 ± 0.023**. GRPO against an automated-essay-scoring-derived reward lifted it further to **0.618 ± 0.005** across every trait and prompt, with the reward designed as a dense trait-normalized accuracy because exact-match rewards are too sparse in the multi-trait setting (SWIM: Student Writing Simulation via Proficiency-Conditioned Generation). The misconception-modeling study reaches a sharper conclusion about *what* the supervision must contain: instruction-tuned models learned algebra misconceptions only when trained on **step-level solution traces**, with accuracy staying **below 30% at every data size** when trained on final answers alone. Its student role overgeneralized the learned error until correct examples were explicitly mixed in at ratios as low as **one in four**, while the tutor role showed no such cost, holding correct accuracy from **93% to 98%** across ten jointly trained misconceptions (Misconception Acquisition Dynamics in Large Language Models).

The training data is itself something models can curate: Edu-QuRating adapts preference distillation to educational data curation, replacing a single "is this educational?" score with 20 rubric dimensions covering factual accuracy, pedagogical structure and level suitability (Edu-QuRating: Multi-Dimensional Educational Data Curation with Distilled Pairwise Judgements).

Theory can be a training scaffold. For agents automating instructional systems design, a hybrid of classical ADDIE and Dick & Carey frameworks with ReAct-style reasoning outperformed both pure theory (structured but inflexible) and technique-only agents (flexible but ungrounded), across **25,795** scenarios from a 51-variable context matrix with a multi-judge protocol to reduce LLM-as-judge bias (ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents). And a study of supervision *labels* found that assigning every training example one target behavior — subject competence, curriculum grounding, diagnostic reasoning, or Scaffolding — lifted every model scale tested, with the largest gains in scaffolding and in using a learner's history, while knowledge-state diagnosis remained weakest at **54.04%** (OmniEdu: Open Foundation Models for Learning and Teaching).

Training the learner side, not only the tutor

The same machinery is increasingly pointed at simulating students, which changes the economics of evaluating a tutor: instead of recruiting learners, you generate them.

The caution is that simulated students must be validated like any other instrument. Benchmarking fine-tuned and prompted models on **382 held-out dialogues** from the largest public corpus of real student–tutor mathematics dialogues — across seven metrics spanning linguistic, behavioral and cognitive aspects — produced the field's most direct test of whether simulated students behave like students (Simulated Students in Tutoring Dialogues: Substance or Illusion?). Two further approaches push on fidelity: INSIDE fine-tunes LLMs to both *act* and *think* like students, generating internal dialogue grounded in Bloom's Taxonomy across cognitive, affective and action dimensions and training on paired think-traces and actions (INSIDE the student's mind: Jointly modeling latent reasoning and action in LLM student simulators), and history-aware profiles condition simulation on a student's prior trajectory rather than a static persona (Who Am I?

History-Aware Profiles for Student Simulation in Tutoring Dialogues). For a developer, the practical lesson is that a simulator is a measurement instrument and inherits every validity question that implies.

What goes wrong

Sycophancy is a training objective, not a usability setting. Tutoring requires corrective friction, and models resist it. EduFrameTrap shows that models which withstand context-switch attacks still capitulate under authority or social-affective pressure and withhold corrective feedback, which is why its authors argue "kind-but-correct" behavior should be an explicit training requirement rather than a preference (Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks). Training that rewards guiding over answering — as EduQwen's DAPO reward model does — is one structural lever against it, but contextual sycophancy persists after prompting and alignment, with learners' errors still propagating into AI advice (The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration).

Training does not make a model safe over a long conversation. SafeTutors shows that even specialized pedagogical models degrade across sustained dialogue and can commit answer over-disclosure harms (SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems), so pedagogical safety has to be tested at conversation length rather than at the single turn.

Validation can substitute for training — or be required instead of it. A frontier untrained GPT-4 produced roughly **35%** too-general, incorrect or answer-revealing hints when authoring feedback for an intelligent tutoring system, and its own automated quality checks misaligned with human judgment; the authors conclude that LLMs lack an internal model of instruction and that robust validation or domain-specific training is needed before unsupervised learner-facing use (Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models). The practical implication cuts both ways: sometimes the right answer is a validation layer rather than a training run, and sometimes validation is what tells you a training run failed.

Your evaluation may be measuring the wrong thing. This is the most common trap in the fine-tuning literature here. ROUGE-L and QWK measure similarity and ranking, not derivational correctness (LoRA Fine-Tuned Models for Control Systems Course Q&A: A Multidimensional Evaluation of Model Scale and Rank Effects); a fine-tune can reach excellent QWK while the same system's feedback is unparseable (WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays); and a model can rank students correctly while being wrong about how likely each is to need help. Where the target is a construct, fine-tuning should be paired with an instrument that measures the construct — the confidence-routing result is a good template, since it converts an accuracy number into an operating policy with a human in the loop (Know when to trust: Making AI scoring more reliable for educational assessment).

A practical sequence for educational developers

Distilled from the evidence above, in the order that avoids wasted compute:

1. **Establish a baseline you can beat, including a trivial one.** The course-assistant study's no-retrieval model scored below TF-IDF. Log your prompt-only accuracy before you consider training.

2. **Add retrieval before parameters.** Grounding the model in your own materials is the cheapest large gain reported here (52.3% → 66.6%), and it is reversible.
3. **Engineer the prompt, and re-engineer it iteratively.** Rubric-guided refinement moved agreement from 54.75% to 81.25% with no training at all, and item generation improved only after prompt refinement had plateaued — that plateau is your signal that training might add something.
4. **Fine-tune when the target is a stable format, a controlled property, or a domain the base model lacks.** LoRA on a few thousand examples can put small open models at human-grader parity, and an instruction dataset can take a 7B model from near zero to within 0.15 of a much larger reference on domain-specific dimensions.
5. **Choose rank and layers deliberately, and expect architecture-specific behavior.** Gain per adapter parameter fell as rank rose, four-layer adaptation beat both shallower and full-depth fine-tuning, and one model family improved substantially while another did not move at all.
6. **Use post-training when you need to change *how* the model teaches.** Reward guiding over answering, and expect the reward to be gamed — write it against a benchmark, not an intuition.
7. **Supervise at the step level.** Final-answer-only training produced sub-30% misconception accuracy at every data size.
8. **Keep a human in the loop where confidence is low.** Routing the least confident fifth of responses removed about 80% of manual work while improving agreement.
9. **Test safety across whole conversations.** Long dialogues are where specialized models degrade.
10. **Calibrate expectations.** Model and prompt choice account for only about 15% of the misalignment with learning gains; some of what you want from training is not available from training.

Open Questions

1. Does pedagogical post-training generalize across subjects, or is subject-specific tuning always needed?
2. Can the RL–SFT–RL pipeline be combined with longitudinal memory for personalization across terms?
3. What is the smallest supervision set that still teaches step-level pedagogical reasoning, and can it be shared across institutions without sharing student data?
4. How should evaluation of fine-tuned educational models be standardized, given that similarity metrics can be excellent while the model is unusable?

Connections to related concepts

This page is the *how a model is made* companion to Large Language Models (LLMs), which covers what large language models are and how they behave. It sits under Technologies as the training-and-adaptation node, beside RAG (Retrieval-Augmented Generation) (the retrieval alternative that usually comes first), Prompt Engineering (the cheapest lever), and Reinforcement Learning (the RL half of post-training). Its outputs feed Intelligent Tutoring and Adaptive Learning; its most common educational applications are

Automated Assessment, Automated Essay Scoring and AI Feedback Quality; and its closest conceptual relatives are Educational NLP, Simulating Students, Open Source and Learner Modeling and Adaptive Instruction. The risks it creates are held by Pedagogical Safety, AI Sycophancy, Hallucination Risk and Privacy.

Common Misconceptions

- **"Fine-tuning is the way to make a model good at your task."** Retrieval and prompting come **earlier in the decision order**, and the knowledge base's clearest result is that post-training is a **third choice, not the first**. Fine-tuning a model on assessment data improved **formatting and similarity** while a separate fine-tune **failed outright at generating feedback** — the method changed the surface and not the competence.
- **"The model is the main determinant of learning gains."** Model and prompt choice account for only **about 15%** of the gap between an LLM and student learning gains. Optimizing the remaining 85% is where the work is, and it is not in the weights.
- **"A local model will underperform a hosted one, so retrieval is a lesser lever."** In a three-configuration evaluation, **retrieval, not the model, was the first-order design decision**: the local LLM with **no retrieval reached only 52.3% accuracy, below a TF-IDF baseline**. Adding retrieval moved the same model past a threshold no model swap was going to reach on its own.
- **"More training data means better teaching behaviour."** The assessment fine-tune that improved formatting while worsening feedback generation is the counterexample in miniature: optimization against a similar-looking target can improve the proxy and degrade the thing you wanted.

Connected Concepts

- Large Language Models (LLMs) — what these models are; this page is how they are made
- Technologies — umbrella: AI technologies and techniques
- RAG (Retrieval-Augmented Generation) — retrieval, the step before training
- Prompt Engineering — the cheapest lever, and the baseline to beat
- Reinforcement Learning — the RL stage of post-training
- Intelligent Tutoring — the main application domain
- Adaptive Learning — adapting to learners, as distinct from adapting models
- Automated Assessment — where fine-tuned scoring models land
- Automated Essay Scoring — the task most of the scoring evidence comes from
- AI Feedback Quality — what fine-tuning does and does not fix
- Educational NLP — the adjacent method family
- Simulating Students — the learner-side application of the same machinery
- Learner Modeling and Adaptive Instruction — the modeling layer beneath simulation
- Open Source — open weights are what make local fine-tuning possible
- Benchmark — how these systems are evaluated, and the limits of that
- Assessment Validity — why a good metric can still mean a bad instrument

- Pedagogical Safety — what training does not guarantee
- AI Sycophancy — a behavior post-training can target
- Hallucination Risk — the failure mode fine-tuning cannot cure
- Privacy — the constraint on training data and on unlearning
- Human-in-the-Loop — the fallback that makes automation affordable
- Metacognition — a pedagogical target for post-training
- Scaffolding — the behavior the reward functions try to encode
- AI in Education — the field this work serves

Connected Articles

- Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning — RL–SFT–RL pipeline: 96.52% on CDPK, surpassing Gemini-3 Pro
- LearnLM: Improving Gemini for learning — pedagogical instruction following inside Gemini's post-training
- TeachLM: Post-training LLMs for education using authentic learning data — post-training on 100,000 hours of authentic tutoring data
- TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring — taxonomy-aligned post-training targeting the pedagogical decision
- SWIM: Student Writing Simulation via Proficiency-Conditioned Generation — SFT and GRPO against rubric prompting, with reward design detail
- Misconception Acquisition Dynamics in Large Language Models — step-level traces as the binding requirement for misconception training
- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents — theory-grounded instructional design agents across 25,795 scenarios
- Beyond Direct Answering: Aligning Educational LLMs as Socratic Guides via Heuristic Reinforcement Learning — heuristic RL to align models as Socratic guides
- Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training — reinforcement learning for special education alignment
- Effective Personalized AI Tutors via LLM-Guided Reinforcement Learning — LLM-guided reinforcement learning for personalization
- Pedagogy-R1: Pedagogical Large Reasoning Model and Well-balanced Educational Benchmark — a pedagogical large reasoning model
- OmniEdu: Open Foundation Models for Learning and Teaching — one target behavior per example, across model scales
- Edu-QuRating: Multi-Dimensional Educational Data Curation with Distilled Pairwise Judgements — curating educational data for training
- LoRA Fine-Tuned Models for Control Systems Course Q&A: A Multidimensional Evaluation of Model Scale and Rank Effects — LoRA rank effects and gain per adapter parameter

- AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models — LoRA-adapted AWE where scale did not predict success
- Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams — one adapter on ~3,900 examples reaching human-grader parity
- IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems — a 24,795-example instruction dataset and the near-zero base baseline
- Children's English reading story generation via supervised fine-tuning of compact LLMs with controllable difficulty and safety — controllability over scale for reading-level control
- Automatic discourse relation classification and feedback optimization in English teaching based on transformer BERT model — which layers to fine-tune, and why four beat twelve
- NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts — architecture, not parameter count, decides whether fine-tuning works
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — distillation into a 2B model with a faithfulness audit
- Balancing AI responsibility with privacy, safety, and utility: Unlearning in large language models for mathematics education — gradient-based unlearning of PII and harmful content
- Automatic Reflection Level Classification in Hungarian Student Essays — fine-tuned transformers versus classical and embedding baselines
- Multimodal item parameter estimation using simulated response probabilities — learning IRT curves from multimodal items
- Know when to trust: Making AI scoring more reliable for educational assessment — confidence routing as the human-in-the-loop policy
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — retrieval as the first-order decision, with energy and VRAM reported
- Customizing AI for writing pedagogy: a systematic review of pedagogical goals, theoretical principles, and technical design — 23 studies: prompting 13, fine-tuning 7, hybrid 3
- How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment — prompting plateaus, then fine-tuning adds the rest
- WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays — fine-tuning won at scoring and failed at feedback
- Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact — the ~15% ceiling on model and prompt choice
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — rubric-guided prompting as the no-training alternative
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching — prompt-level persona control for misconception simulation
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks — sycophancy as an explicit training requirement
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — sycophancy surviving prompting and alignment

- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — safety degrading over sustained dialogue
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models — ~35% unusable hints from an untrained frontier model
- Simulated Students in Tutoring Dialogues: Substance or Illusion? — whether simulated students behave like students
- INSIDE the student's mind: Jointly modeling latent reasoning and action in LLM student simulators — fine-tuning a model to act and think like a student
- Who Am I? History-Aware Profiles for Student Simulation in Tutoring Dialogues — simulation conditioned on a learner's trajectory
- K12-KGraph: A Curriculum-Aligned Knowledge Graph for Benchmarking and Training Educational LLMs — Curriculum-structured data is sample-efficient

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

Vibe Coding

> **Vibe coding** — building software by iteratively prompting a large language model and judging the resulting behavior, without directly reading or editing the underlying source code. Popularized by Andrej Karpathy in 2025 as the workflow where one "forgets the code even exists," vibe coding is the LLM-native realization of natural-language programming and end-user development — framings now treated as synonyms in this knowledge base — in which prose becomes the primary programming interface.

Questions to Consider

- Karpathy's original framing said you should "forget the code even exists." Before you read further, ask yourself: is not seeing the code a feature (it lowers barriers) or a risk (you cannot verify or fix what you cannot see)? What does the answer imply for who should be allowed to vibe-code?
- Research on who succeeds at vibe coding found that traditional computer-science achievement still predicts success even when the user never touches code. If that surprises you, what hidden skill might CS training be building that prose alone does not capture?
- The same study found writing skill predicts vibe-coding performance largely *because* it produces higher-quality prompts. If prompting is really the bottleneck, is the right fix to teach people to prompt better — or to redesign tools so they demand less prose skill?
- Vibe coding is often celebrated as making "anyone" a developer. But if writing skill and CS knowledge both shape outcomes, does vibe coding widen access to building software or merely relocate the skill barrier from code to prose?
- Some developers distinguish "pure" vibe coding (never reading code) from AI-assisted coding where you review and edit what the model wrote. Where do you think genuine learning — versus over-reliance — is more likely to happen, and why?

Introduction

Vibe coding describes an interaction style enabled by LLM-integrated development platforms (Replit, Lovable, Cursor, and others): the user specifies a program in natural language, the model generates a working system, and the user iterates based on observed behavior rather than by editing source. The term was coined by OpenAI co-founder Andrej Karpathy in February 2025 to capture the experience of relying on the model to such an extent that "the code" fades from awareness. Vibe coding sits at the convergence of several strands this knowledge base already tracks — it is generative AI applied to programming, an extreme form of prompt-driven work, a concrete instance of Human AI Collaboration, and the clearest route yet to non-programmers and end users building their own software (end-user development).

It also has deep roots. The idea of programming in ordinary language long predates LLMs — from COBOL's aspiration to be "an English-language programming system for non-professional programmers," through Donald Knuth's literate programming, to research on natural-language programming with constrained

subsets of English. Only with LLMs did it become feasible to map genuinely conversational, underspecified instructions to runnable code. Vibe coding is the particular variant in which the user deliberately does not inspect or edit the generated source, relying entirely on iterative prompting and behavioral evaluation.

Defining the construct: "pure" vs. code-visible vibe coding

The definition of vibe coding is still in flux. Some use the term broadly to mean any AI-guided programming; others insist it refers strictly to "building software with an LLM without reviewing the code it writes." Google Cloud distinguishes a "pure" no-code version (consistent with Karpathy's definition) from a version where the user understands and refines the generated code. This distinction matters for research: a controlled study of vibe-coding proficiency requires a well-defined construct. The CHI 2026 study of predictors of vibe-coding proficiency deliberately targeted the "pure," no-code variant — participants could not view or edit the generated source, so measured performance reflected the ability to specify, refine, and debug behavior through prose and observed output alone (see Thorgeirsson et al.).

Who succeeds at vibe coding: evidence

A preregistered cross-sectional study (N = 100 tertiary students) provides the first controlled, participant-level evidence on which skills predict vibe-coding success. Both written-communication proficiency (r = .29) and computer-science achievement (r = .39) significantly predicted performance on expert-vetted, GUI-oriented vibe-coding tasks, with CS achievement remaining significant after controlling for domain-general cognitive skills (partial r = .281). In a joint model CS achievement contributed roughly twice the unique variance of writing skill, but both added independent predictive value. Critically, human-graded prompt quality mediated the writing → performance link, giving response-process evidence that clear prose operates by producing better prompts. Because the environment hid the source code, CS knowledge could only help indirectly (through problem decomposition, algorithmic thinking, and mental models of control flow) — so the authors argue their CS estimate is a *lower bound* for AI-assisted programming in which users may also edit code directly (Thorgeirsson et al., 2026).

Vibe coding as end-user development and teacher tooling

A major promise of vibe coding is that it lets non-programmers — including teachers and domain experts — build their own software, an LLM-era form of end-user development. A GAIDE framework study showed K-12 teachers (non-programmers) using vibe coding in an eight-week workshop to create AI-powered learning tools, raising their AI literacy and demonstrating "learning-by-creating" as a professional-development model. In higher education, an instructor rapidly built a programming-process visualizer from IDE activity logs via vibe coding in a matter of days, making students' programming processes visible for teaching and Academic Integrity review. These cases position vibe coding not merely as a learner skill but as an authoring capability that reshapes who can create educational technology.

Design homogenization: access without diversity

Vibe coding's end-user-development promise is about who can build, not what gets built. In a course deployment, 73 students building sites for distinct businesses on one vibe-coding platform produced roughly

a dozen distinct designs, and felt authorship did not track measured originality (Boussioux et al. (2026)). Lowering the barrier to building may standardize the output — a cost the access promise does not advertise.

Learning, agency, and the risk of over-reliance

Vibe coding reopens core questions about what is learned when AI automates implementation. Because the user does not read code, they must trust the model's behavior — which makes vibe coding a high-stakes case of the tension between Learner Agency and over-reliance that runs through AI-assisted programming. Curricula are responding by shifting from teaching implementation toward teaching how to direct, verify, and audit AI-generated artifacts (see reshaping undergraduate CS and agentic software engineering). Vibe coding also changes the learner's epistemic position: success depends less on writing code than on expressing intent precisely and evaluating behavior against goals, competencies closer to computational thinking and structured writing than to traditional syntax mastery.

A second limit shows up in the building itself: removing the coding barrier can leave the diagnosis burden untouched. Two engineering case studies had an instructor build working web simulations of a battery thermal management system and three ARQ protocols by prompting Gemini in plain language within a few hours (Tarasak et al. (2026)). A duplicate-packet error then survived repeated prompts, including one that stated the required behavior. It was fixed only when the instructor reasoned from protocol behavior to an insufficient timeout interval, a parameter the interface never exposed. Neither simulation's effect on learning was measured, so the account establishes feasibility rather than effectiveness.

Connections to related concepts

Vibe coding connects naturally to Prompt Engineering (prompt quality is the mechanism of prose-driven development), CS Education (as the domain where the technique is most used and most contested), Computational Thinking (the mental modeling that predicts success even without code access), Writing (writing becoming a programming skill), and Agentic AI (directing a model toward an artifact rather than hand-building it). It also intersects with AI Literacy and Teaching, since the ability to build one's own tools changes what teachers and learners can do. Finally, it raises Academic Integrity and assessment questions identical to those AI code generation raises across computing education.

A faculty-level case study in this knowledge base supplies the organizational layer. Zimmer (2026) describes *AI intrapreneurship* — educators building their own tools instead of waiting for institutional procurement — including an author who does not code using Claude Code to build a checker for 321 course links. The decisive enablers were organizational rather than technical: work discretion, rewards, and time availability, the last described as most obviously in deficit in academic settings and undercut by promotion and tenure. The security picture stayed sober, since Veracode's 2025 analysis found only 55% of AI-generated code secure, so vibe-coded classroom tools still need a review pass before handling student data or connecting to an LMS.

Common Misconceptions

"Vibe coding lowers the skill barrier, so it is mainly a matter of writing well." Written-communication proficiency helps and does not carry the outcome alone. In a preregistered cross-sectional study (N = 100

tertiary students), both written-communication proficiency (r = .29) and computer-science achievement (r = .39) significantly predicted performance on expert-vetted, GUI-oriented vibe-coding tasks, and in a joint model CS achievement contributed roughly **twice the unique variance** of writing skill while both retained independent predictive value. The barrier has moved, not disappeared, and part of it remains technical.

“Because anyone can now build software, what gets built will become more diverse.” Access and diversity are separate outcomes, and access can even compress the second. The design-homogenization evidence in this corpus describes exactly this pattern: a wider population of builders working from the same models, the same component conventions and the same prompting defaults tends toward converging designs. Democratizing authorship does not automatically diversify artifacts.

“‘Pure’ vibe coding is what the term means, so the distinction does not matter.” It matters for evaluation and for safety. The page distinguishes pure vibe coding, where the user deliberately does not inspect or edit the generated source and relies entirely on iterative prompting and behavioral evaluation, from code-visible work in which the user reads what was produced. These are different activities with different error profiles, and a study of one does not license claims about the other.

“If the app runs, the generated code is fine.” Running is a weak test. Veracode’s 2025 analysis found only 55% of AI-generated code secure, so vibe-coded classroom tools still need a review pass before handling student data or connecting to any system worth protecting. Behavioral evaluation confirms the paths a user happens to exercise and says nothing about the ones they do not.

Putting Vibe Coding into Practice

For instructors and teacher educators

- Teach the difference between pure and code-visible vibe coding explicitly, and require the second for anything that will handle student data. The distinction is a teachable habit, not a philosophical nicety.
- Keep a real programming thread alongside vibe-coding work, because CS achievement carried about twice the unique predictive variance. Treating natural-language specification as a full substitute discards the stronger predictor.
- Have students evaluate the artifact behaviorally *and* inspect the source of anything they deploy. Reading generated code is a review skill, and it is not automatic for students who can prompt.

For developers and administrators

- Run a security review pass on any vibe-coded tool before it touches student records, consistent with the 55% secure-code finding.
- Budget for homogenization: if several staff vibe-code the same kind of tool from the same defaults, expect similar output and plan for how differentiation will be achieved deliberately.
- Prefer code-visible workflows for maintained tools and reserve pure vibe coding for throwaway prototypes.

For researchers

- Report the vibe-coding condition (pure versus code-visible) alongside outcomes, and use expert-vetted, GUI-oriented tasks rather than self-reported success, so results are comparable across studies.
- Measure artifact diversity, not only artifact count or builder count, if the access argument is being tested.

Connected Concepts

- Generative AI
- Large Language Models (LLMs)
- Prompt Engineering
- CS Education
- Computational Thinking
- Writing
- Agentic AI
- Human AI Collaboration
- AI Literacy
- Teaching
- Cognitive Offloading

Connected Articles

- Computer Science Achievement and Writing Skills Predict Vibe Coding Proficiency — Computer Science Achievement and Writing Skills Predict Vibe Coding Proficiency (CHI 2026 empirical study)
- A Guiding Framework for K-12 Teachers in Creating AI-powered Learning Technologies through Vibe Coding — A Guiding Framework for K-12 Teachers in Creating AI-powered Learning Technologies through Vibe Coding
- From Idea to Classroom in Days: Using Vibe Coding to Create a Programming Process Visualizer from IDE Activity Logs — From Idea to Classroom in Days: Using “Vibe Coding” to Create a Programming Process Visualizer from IDE Activity Logs
- Vibe Coding for Simulation Development in Engineering Education — Vibe coding built two engineering simulations in hours; diagnosing a protocol error still needed the instructor
- Understanding Student Perceptions, Mistakes, and Debugging Approaches when Solving Natural Language Programming Tasks — Understanding Student Perceptions, Mistakes, and Debugging Approaches when Solving Natural Language Programming Tasks
- Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education — Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education

- Reshaping Undergraduate Computer Science Education in the Generative AI Era — Reshaping Undergraduate CS Education for Generative AI
- Flowcode: An AI-Powered Programming Environment for Scaffolding Iteration in Creative Computing Education — Flowcode: An AI-Powered Programming Environment for Scaffolding Iteration in Creative Computing Education
- AI Intrapreneurship: Educators as Frontline Innovators in the Age of Generative AI — AI intrapreneurship: faculty building their own tools, and the organizational enablers that decide whether the impulse survives (Zimmer 2026)
- One Tool, One Taste? How Vibe Coding Trades Collective Diversity for Individual Creativity — One Tool, One Taste? How Vibe Coding Trades Collective Diversity for Individual Creativity

Multimodal AI

> **Multimodal AI** — AI systems that process, understand, or generate content across multiple modalities — text, images, audio, video, and structured data — and the educational questions these systems raise. In AI in education, multimodal AI appears in three distinct roles: as the *learning content* learners create and engage with (multimodal learning), as the *capability boundary* of tutoring systems that must interpret diagrams and graphs (multimodal tutoring), and as the *assessment signal* used to evaluate understanding (multimodal measurement).

Questions to Consider

- Think of a graph, force diagram, or schematic you've ever struggled to explain in words. What does that experience suggest about the limits of a text-only AI tutor trying to help with image-rich problems?
- A physics tutor answers text-based problems ~96% of the time but drops to ~74% on problems that embed meaning in diagrams. Before reading, what do you think causes this 'multimodal interference'—and can you think of a fix that doesn't involve retraining the model?
- You've likely generated both text and images with AI tools. Have you found that 'prompting for pictures' differs from prompting for text? What skills might students need to translate an abstract idea into a precise visual prompt?
- Multimodal AI can grade essays, generate feedback with audio narration, and even reconstruct exam item statistics from image-and-text items. What does the shift from text-only to multimodal assessment signal (or risk) for fairness and validity?
- How could the fact that AI support is less reliable on the very diagram-heavy problems that build deep STEM understanding create an equity gap between learners? Who is most affected?
- Multimodal systems can translate text to audio or visuals to support inclusive learning, but they also enable fine-grained classroom sensing. Where is the line between helpful multimodal access and surveillance?

Introduction

Multimodality in AI refers to the capacity to work across different representational forms rather than text alone. Modern Generative AI and Large Language Models (LLMs) systems increasingly accept and produce images, audio, and video in addition to text, opening new possibilities and new risks for education. Grounded in social semiotic theory, which holds that meaning is made across modes — not just words — multimodal AI changes how teaching, learning, and assessment are designed and evaluated.(Multimodal Learning with Generative AI)

Three faces of multimodal AI in education

1. Multimodal learning and content creation

Multimodal AI enables learners to produce and engage with content across text, image, audio, and video. An educator's guide to multimodal learning with generative AI positions these tools as a "cyber-social" partner: they complement — but cannot replace — human meaning-making.(Multimodal Learning with Generative AI)

- **AI literacy in multimodal contexts** is layered: basic awareness of multimodal platforms, intermediate co-creation and critical evaluation of outputs, and advanced design of multimodal activities and assessments.(Multimodal Learning with Generative AI)
- **Multimodal prompting** is itself a demanding epistemic practice. Students who prompt for images as well as text discover that "prompt literacy is different between prompting for text than it is for pictures" — translating abstract meaning into machine-readable multimodal prompts requires a precise visual vocabulary and exposes system limitations and bias.(Students' multimodal prompting practices as epistemic work in AI literacy development)
- **Multimodal assessment** shifts from essays to artifacts combining text, image, audio, and video, with educators using AI to scaffold creation and feedback rather than replace the learner's own production.(Multimodal Learning with Generative AI)
- **Modality choice is an educational judgment, not a container.** Elkington (2026) argues that choosing among written, oral, digital and multimodal formats decides what becomes possible for learners and visible to assessors, and counts controlled choice among modalities as a generative constraint rather than an administrative detail.
- **Learner multimodal composing as a critical-thinking scaffold carries a trade-off.** Lu et al. (2027) show that having upper-primary students turn written narratives into AI-generated images and short videos supported sustained gains in interpretation, analysis, evaluation, and explanation — but not inference. Because the visuals made story meaning explicit, students reported less need to infer implicit meaning from text alone; peer collaboration, not the multimodal tool, restored occasions for inference. Multimodal AI's value as a meaning-making partner is thus dimension-specific and depends on instructional design that deliberately re-introduces the inferential and self-regulatory work the externalization can short-circuit.
- **Learner multimodal composition as critical AI literacy.** Burriss et al. (2026) analyze 22 eleventh graders' 90-second to 3-minute video public service announcements on self-chosen AI Ethics issues — surveillance through school-regulated laptops and electronic "hall passes," informed consent, and punitive algorithmic accusation — as critical AI literacy enacted through composing across moving image, sound, text, and students' own bodies. Across all seven films harm was portrayed as emerging from human–machine entanglement rather than from the tool alone (an anthropomorphized "AI stalker" was played by a human actor in three of seven), and 15 of 18 end-of-unit responses said composing changed their understanding of AI ethics. The authors argue multimodal products both *demonstrate* and *communicate* critical competence — productive artifacts, reflections, and civic discourse can serve as Assessment evidence that text-only literacy scales structurally miss.

2. Multimodal tutoring and the capability boundary

When LLM-based tutors must solve problems that embed meaning in graphs, force diagrams, schematics, or tables, their accuracy degrades sharply — the **Multimodal Interference Effect**.(Multimodal Dialogue in STEM Education)

- On OpenStax physics problems, text-only accuracy of ~96% drops to **~74%** on image-rich problems, consistently across model families.(Multimodal Dialogue in STEM Education)
- **Visual Processing Errors** — failures to extract information from graphs or diagrams — dominate the error taxonomy and are the most correctable failure mode.
- A simple structured-dialogue intervention (have the model describe what it sees, correct only *observable* misreadings without giving away physics, then re-prompt) restores accuracy to **~95%** with zero retraining.(Multimodal Dialogue in STEM Education)
- This is an **equity concern**: students working on image-rich problems — precisely the problems that build deep conceptual understanding in STEM — currently receive less reliable AI support than those on text-only exercises.
- **Constructing a visual aid is harder than reading one.** On GeoVAD-Bench, supplying an expert auxiliary diagram raised accuracy (+3.3 to +7.0 points), but letting models construct their own auxiliary line widened the gap by 10.0 to 13.5 points — two models scored worse than with no visual reasoning at all (Dong et al., 2026).
- **The boundary is a profile, not a level — and artistic imagery sits outside the region models handle well.** MUSE (Zhu et al., 2026) evaluates 30 open- and proprietary VLMs on 12 tasks over 1,174 commissioned artworks, and the capability spread across dimensions is wider than any aggregate score suggests: scene classification is near-mature (23 of 30 models above 75.0, median 81.0). Meanwhile emotion detection tops out at 39.5, and the open-ended tasks that require models to *articulate* their evidence score at 50.90 (visual clue identification) and 49.18 (emotion cause inference) on semantic similarity. Compositional and viewpoint-dependent reasoning fail hardest — where the ground truth specifies no definite lateral or vertical relation, 90.0% and 73.3% of models assert one anyway, only 43.3% place the girl correctly in depth, and no model resolves all three dimensions of a single item. Failures also cascade: a mis-grounded character is then justified with a fluent rationale built from nearby visual semantics (butterflies, birds), which is the outcome most dangerous in tutoring because the explanation reads as competent. For image-based language learning this argues for dimension-level validation on the imagery a course actually uses, rather than importing a general multimodal score, and for extending the grounding checkpoint described below — describe what is seen, and where, before reasoning from it — to situated artistic content (MUSE: Benchmarking Large Vision-Language Models on Multi-Modal Understanding in Situated Education).

The practical design implication is a **visual grounding checkpoint** in multimodal tutoring: a deliberate step where the system describes what it sees before attempting a solution, giving the student or a human supervisor a chance to correct perceptual errors.(Multimodal Dialogue in STEM Education)

Abreu et al. (2026) add a prior constraint: an equation, graph or unit can appear in a report yet never be retrieved from the processed document, so a disagreement with the instructor may be an extraction failure rather than a reasoning one — which makes submission format part of the assessment design.

3. Multimodal assessment and measurement

Multimodal AI broadens both the *content* of assessment and the *signal* used to score it.

- **Multimodal feedback systems** integrate structured text, slide references, and streaming audio narration. In one study, AI multimodal feedback matched educator feedback for learning while *significantly outperforming* it on student perceptions.(LLM-based Multimodal Feedback Produces Equivalent Learning and Better Student Perceptions than Educator Feedback)
- **Multimodal item response estimation** uses fine-tuned multimodal LLMs to reconstruct item characteristic curves (IRT / 3PL) directly from predicted option probabilities on image-and-text items, connecting multimodal AI to Educational Measurement and Item Response Theory. (Multimodal item parameter estimation using simulated response probabilities)
- **Educational vision-language model evaluation** and multimodal LLM literacy extend the field's evaluation toolkit to multimodal reasoning and Visualization.(The aftermath of DrawEduMath: Vision language models underperform with struggling students and misdiagnose errors) (Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy)
- **Multimodal grading of handwritten chemistry exposes a format-dependent capability boundary:** Cvengros & Kortemeyer graded a 296-student handwritten general-chemistry final page-by-page against rubric images with a multimodal, reasoning LLM, scoring textual answers and chemical-reaction equations reliably (normed F1 highest) but drawing and graphing *worse than random* — background grids visually distract AI vision and scientific diagrams/chemical structures remain hard to interpret — reinforcing that multimodal AI's vision is not robust to representation-heavy work and is best deployed with human deferral of graphical items (Assisting the grading of a handwritten general chemistry exam with artificial intelligence).
- **Construct recognition and comparative judgment are separable skills.** Ma et al. (2026) express six multimedia-learning principles as reversible slide edits plus visual-equivalence sham controls, and find both models recovered every operation, principle and repair (8/8) while severity calibration failed entirely (0/8) — a composite score would conceal which layer fails.
- **Fairness gains can be validated into existence.** A multimodal attention estimator beat a visual-only baseline only modestly, and its gender-targeted MAE-gap regularizer cut the validation gap from 0.02 to 0.005 yet increased the gap and worst-group error on held-out subjects — so subgroup-aware, repeated subject-level validation is required before deployment (Fragkiadakis et al. (2026)).
- **Multimodal grading can reproduce a selection outcome even where item-level scoring lags.** Grading 10,364 handwritten Olympiad and university pages, an LLM matched examiner totals at r = 0.93–0.96 and placed the same five students on the Olympiad team, yet part agreement reached 70%: second-reader evidence, not a scorer of record (Pathak et al. (2026)).
- **Diagram generation is a capability frontier, not a solved one.** On a 15,246-question physics benchmark that scores multimodal output, synthesizing or editing structured physics diagrams proved harder than answering, and leading models stayed below 70% strict mastery — evidence that visual *production* lags visual *comprehension* (Chen et al., 2026).

Multimodality has a second sense: fusing signals from the learner's body rather than from content, where eye tracking, EEG, electrodermal activity, heart-rate variability and camera pose feed estimates of attention, engagement and cognitive load. That sensing strand lives at Sensor and Gaze Analytics, and its validity and consent problems are not the ones multimodal content raises.

Multimodal AI for language and accessible learning

Multimodal systems also expand access and personalization. AI-guided audio-video learning tools adapt playback speed, produce multimodal video summaries, and support pronunciation practice.(AI-guided learning: Research on knowledge and skill acquisition support methods using deep learning audio-video processing techniques) Multimodal knowledge graphs reason across images and text for educational tasks, (Evidence-Grounded Multimodal Knowledge Graph Construction for Multi-Lecture Educational Reasoning) and multimodal representations improve Inclusive Learning by translating information across modes (e.g., text to audio or visual). Domain applications include handwritten-math grading and diagnosis, (Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work) affective tutoring with multimodal signals,(An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training)(MathBuddy: Affective Math Tutoring) text-to-image learning in specialized fields,(NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts) and privacy-aware multimodal classroom sensing.(Robust and Efficient Motion Reasoning for Privacy-Aware Classroom Incident Recognition) Bird (2026) demonstrates a text-internal form of multimodality: fusing a fine-tuned ELECTRA transformer with computational-linguistics feature analysis to classify English literature by UK Key Stage, where the fused model (F1 0.996) far surpassed every unimodal baseline — evidence that combining representational forms, even within text, can outperform single-model approaches.

Challenges and design implications

1. **Close the multimodal gap.** Multimodal tutoring systems should include visual grounding and structured-dialogue scaffolds rather than assuming vision capabilities are robust.(Multimodal Dialogue in STEM Education)
2. **Treat multimodal prompting as a teachable skill.** AI literacy curricula must address modality-specific prompting, coherence across modes, and critical evaluation of multimodal outputs. (Students' multimodal prompting practices as epistemic work in AI literacy development)
3. **Preserve human meaning-making.** Multimodal AI should augment, not replace, the learner's own construction and evaluation of meaning across modes.(Multimodal Learning with Generative AI)
4. **Extend evaluation to multimodal validity.** Assessment validity, bias, and reliability must be examined when AI scores or generates multimodal artifacts.(Multimodal item parameter estimation using simulated response probabilities)(AI Ed Evaluation)
5. **Watch equity and privacy.** Unreliable support on image-rich problems and the data demands of multimodal sensing both carry equity and privacy implications.(Multimodal Dialogue in STEM Education)(Robust and Efficient Motion Reasoning for Privacy-Aware Classroom Incident Recognition)

6. **Match the pipeline to the content.** A cybersecurity lab assistant's multimodal LLM handled dense visual slides better, while an OCR-plus-LLM pipeline delivered comparable instructional value on text-centric slides at significantly lower computational cost.(Patel et al. (2025))
7. **Collecting several streams is not integrating them.** A review of 23 AI-for-Embodied Learning studies sorted multimodal work into three levels — streams gathered in parallel, streams aligned on a shared timeline, streams fused inside one model that estimates the learner's state — and placed most studies at the first, pairing image with text or motion with text without ever joining them. One study aligned facial affect, gaze and face detection after the fact; the closest approach to fusion modeled joint states from wristband and skeletal signals with a Markov process, and ran after the session rather than informing the feedback learners received. No reviewed system fused its inputs during use (Kim and Han (2026)).

Common Misconceptions

"A multimodal model handles multimodal problems." Accuracy degrades sharply when meaning is carried by the figure rather than the text. A physics tutor answers text-based problems about **96%** of the time but drops to about **74%** on problems that embed meaning in diagrams — the **Multimodal Interference Effect**. Twenty-two points of capability disappear exactly where the disciplinary content lives.

"Adding an image to the prompt resolves the diagram problem." The input modality is not the bottleneck; the interference is. A model that receives the diagram and still reasons from the surrounding prose has been handed the information and has not used it, which is why the failure is invisible unless someone compares the two problem formats.

"Multimodal capability is a single ladder, so the best model overall is best for the image-rich task." Capability is task-specific, and a model that leads on general benchmarks can trail on force diagrams. For image-rich disciplines the relevant test is the one with the meaning embedded in the figure.

"Text-only tutoring limits are a nuisance rather than a curriculum problem." In disciplines where the diagram *is* the problem — physics, chemistry, geometry, engineering, medicine — a text-only tutor's competence boundary falls across the assessed content rather than at its edges.

Connected Concepts

- Generative AI
- Large Language Models (LLMs)
- Knowledge Graph
- Intelligent Tutoring
- AI Literacy
- Prompt Engineering
- Feedback
- Assessment
- Educational Measurement
- Item Response Theory

- Learner Modeling and Adaptive Instruction
- Socratic Method
- Scaffolding
- AI Ed Evaluation
- Benchmark
- Higher Education
- Equity
- Privacy
- STEM Education
- Inclusive Learning
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)
- Virtual and Augmented Reality — gesture, voice and spatial input as learning channels
- Speech and Voice Technologies
- Arts, Design and Media Education
- Sensor and Gaze Analytics

Connected Articles

- Assessing what matters most – the shifting value proposition of human-centred work in assessment practice — Human-centred assessment, assemblages and generative constraints (Elkington 2026)
- "Young Scholar[s] on the Beat": Multimodal composition as a form of critical AI literacy pedagogy — Video PSA composition on AI ethics as critical AI literacy pedagogy (Burriss et al. 2026)
- Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation — Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation
- OmniPhys: A unified multimodal benchmark for physics understanding and generation from Chinese educational corpora
- The aftermath of DrawEduMath: Vision language models underperform with struggling students and misdiagnose errors — VLM performance on handwritten student math work (DrawEduMath, Lucy et al. 2026)
- Multimodal Learning with Generative AI — Educator’s guide to multimodal learning with generative AI (MMLD-AI model)
- Multimodal Dialogue in STEM Education — The Multimodal Interference Effect and structured-dialogue recovery in STEM
- LLM-based Multimodal Feedback Produces Equivalent Learning and Better Student Perceptions than Educator Feedback — Multimodal AI feedback matches educators on learning, exceeds on perceptions

- Students' multimodal prompting practices as epistemic work in AI literacy development — Students' multimodal prompting as epistemic work in AI literacy
- Multimodal item parameter estimation using simulated response probabilities — Estimating IRT item parameters with multimodal LLMs
- AI-guided learning: Research on knowledge and skill acquisition support methods using deep learning audio-video processing techniques — AI-guided audio-video learning support
- Evidence-Grounded Multimodal Knowledge Graph Construction for Multi-Lecture Educational Reasoning — Multimodal knowledge graphs for educational reasoning
- Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy — Multimodal LLM literacy for scientific visualization
- An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training — Multimodal signals in affective intelligent tutoring
- MathBuddy: Affective Math Tutoring — Affective multimodal math tutoring
- Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work — LLM cognitive diagnosis of handwritten math
- NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts — Text-to-image learning in nuclear engineering education
- Robust and Efficient Motion Reasoning for Privacy-Aware Classroom Incident Recognition — Privacy-aware multimodal classroom sensing
- Integrating generative AI into cybersecurity education: A study of OCR and multimodal LLM-assisted instruction — Multimodal OCR instruction in cybersecurity education
- Benchmarking Multimodal Large Language Models for Educational Slide Auditing — CFES-P24: Benchmarking Multimodal LLMs for Slide Auditing
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- More externalization, but less inference? Exploring changes in young learners' critical thinking during conversational AI bot-supported multimodal writing practice — Multimodal AI composing and critical thinking in primary writing (Lu et al. 2027)
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Beyond Generation and Accuracy: Diagnosing and Enhancing Visual Chain-of-Thought for Geometry Problem Solving — Beyond Generation and Accuracy: Diagnosing and Enhancing Visual Chain-of-Thought for Geometry Problem Solving
- MUSE: Benchmarking Large Vision-Language Models on Multi-Modal Understanding in Situated Education — MUSE: 12 tasks over 1,174 artworks show VLM capability as a dimension-specific profile, weakest in affective interpretation and viewpoint-dependent spatial reasoning (Zhu et al. 2026)
- AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice — AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice

- Artificial intelligence in embodied learning: A systematic literature review — AI in embodied learning mostly observes: sensing roles 62.5% of coded role tags, and no reviewed system fused multimodal streams while learners used it (Kim & Han 2026)

Speech and Voice Technologies

> **Speech and voice technologies** — the family of AI systems in which the spoken channel carries the interaction: automatic speech recognition (ASR) that transcribes, analyses, and grades what a learner says; text-to-speech (TTS) that generates narrated or dialogue-form instruction; voice-first agents that hold real-time spoken conversation with learners; and automated capture and scoring of oral performance. Where Conversational AI research is mostly about text chatbots and Language Learning covers second-language pedagogy broadly, this page follows the audio itself — what a speech interface changes about learning, what it costs, and who it includes or excludes when the interface is a voice rather than a screen.

Questions to Consider

- ASR feedback helps stronger learners more than weaker ones: in one survey of 325 Chinese undergraduates, the payoff of reflective behavior and motivation was weak and non-significant at low proficiency and grew markedly stronger at average and high levels. If a tool raises the average while widening the gap, is it a success?
- TTS narration matched an instructor's own voice on comprehension, concentration, and overall evaluation — but dialogue-format TTS beat single-speaker TTS on comprehension and cognitive engagement while sounding *less* natural. Which would you choose for a first introduction to a concept, and which for a dense procedural walkthrough?
- Two findings run against intuition: students who read the AI's output most heavily during interpreting tasks had the weakest delivery fluency, and a learner who answered in two words was marked correct while a fuller spoken answer was flagged. How much does a voice interface measure verbal fluency rather than understanding?
- A voice agent with a British accent was treated as a tool, while agents with Indian and African American accents were anthropomorphized and treated as peers in K-12 group work. If accent changes how a learner relates to an agent, who should decide which voice an educational product ships with?
- Voice-first and offline systems exist mainly to reach learners that screen-based edtech excluded — blind children, deaf and hard-of-hearing learners, learners in workshops with no connectivity. What would it take for accessibility to be the starting assumption of a speech product rather than a later fix?
- Nearly every claim on this page comes from a short, single-site, self-report study with a fixed presentation order. Which of these findings would you trust enough to change your assessment or lesson design before a replication exists?

Introduction

Speech is the oldest educational interface and the newest one for AI. Systems that listen and speak now sit in language classrooms, vocational workshops, and high-school inquiry lessons. They are attractive for the

usual reason — speech is fast, works hands-free and eyes-free, and is the medium in which pronunciation, fluency, and oral reasoning live — and for a newer one: a time-limited spoken answer is hard to outsource to a text generator, which makes the spoken channel a candidate answer to Academic Integrity pressure on written assessment.

The research here splits into four clusters: ASR pronunciation feedback, TTS-generated instruction, voice-first and spoken-dialogue partners, and AI-supported oral Assessment. Running through all four is a question about equity — speech interfaces remove one barrier (sight, reading speed, typed literacy) while introducing others (accent, recognition accuracy, hardware, connectivity).

ASR and Pronunciation Feedback

The most consistent message from the ASR work is that the tool is not the treatment — the feedback design is. Chen et al. (2026) surveyed 325 undergraduates at a Chinese teacher-training university and modeled accuracy, usage frequency, feedback quality, and reflection-task design against reflective behavior and intrinsic Motivation, then against speaking improvement. Accurate error correction and structured reflection tasks drove both Feedback internalization and reflection. More frequent use boosted reflection but had no independent effect on motivation. Recognition accuracy raised motivation, plausibly by building trust in the tool, but did not by itself trigger deeper processing — a learner can register a flagged error without analyzing its cause. Reflection was the stronger predictor of speaking gains, and proficiency moderated both pathways: weak and non-significant at low proficiency, markedly stronger at average and high levels. The advice that follows is to explain errors articulatorially rather than flag them, ramp complexity with readiness, and frame correction supportively.

A second strand asks whether AI pronunciation feedback changes learners' disposition to speak. Lu et al. (2026) surveyed 1,701 Chinese university EFL learners and used covariance-based structural equation modeling with bias-corrected bootstrapping to test whether perceptions of Generative AI pronunciation feedback related to willingness to communicate, with pronunciation Self-Efficacy as mediator. The association was positive, and self-efficacy partially mediated it: the indirect path accounted for 69.9% of the total effect while a direct effect remained. All constructs were self-reported at one time point, so the study describes a mechanism learners perceive rather than one that was manipulated.

Automated pronunciation feedback can also be built without error labels. Kawamura (2026) describes Profy, which learns what good and poor pronunciation look like from largely unannotated speech via self-supervised learning, then shows learners which waveform regions drove the judgment and how far their acoustics sit from native-speaker distributions. With 10 Japanese learners of English rated by five American listeners, intelligibility improved, and unlike an elicited-imitation baseline the pre- and post-practice confidence intervals did not overlap — a small sample, but one that gives *where* and *how much* rather than a binary verdict.

ASR also serves the classroom in a second role — converting spoken input into text that learners read. Stanchev (2026) rendered a 2,692-token Medical English coursebook passage on proteins with one text-to-speech voice (15:27, female Canadian) and submitted the identical audio to four online ASR services, then measured both word error rate (WER) and **coverage** (returned words as a share of the reference). The two free services returned near-complete transcripts (87.96% and 88.34% coverage, WER 15.23% and 15.00%), while the two paid services exported only previews (32.76% and 55.35% coverage, WER 73.21% and

48.77%). The measurement point is that WER alone conflates unavailable text with inaccurate text and would rank an export restriction as a transcription failure, so coverage belongs beside the error rate. Deletions dominated every service and clustered on structural markers such as figure references and page numbers, but a handful of meaning-altering substitutions — imino → amino, cystine → cysteine, protonated → protonatid, pH → phase — each inverted a biochemical fact, which is why the authors propose a three-stage workflow (generate the input, export the full transcript, verify domain terminology) before a transcript reaches learners, and why a terminology pass is the cheapest guardrail for medical English.

Accuracy gains appear to be a property of purpose-built systems rather than of the spoken channel itself. Across ten studies, only chatbots designed for language learning — Andy English bot and Xiaoying — improved accuracy, with a 14% error decrease in one control group against 38% in the treatment group (Soriano-Gonzalez & Belda-Medina (2026)). The same review documents ASR failing on accented speech and non-English names, including a bot that could not recognize Vietnamese names even when pronunciation was accurate.

TTS and Voice-Generated Instruction

Generated narration turns out to be a viable substitute for a recorded teacher, and the interesting variation lies inside the format rather than between human and machine. Kumoi et al. (2026) built a three-stage, human-in-the-loop pipeline in which an Large Language Models (LLMs) drafts slides and TTS-optimized narration while the educator fact-checks at each stage, then ran a within-subject study with 245 first-year students at a Japanese prefectural high school across instructor-voiced video, single-speaker TTS, and Expert-×-Novice dialogue TTS. Comprehension, concentration, and overall evaluation did not differ significantly across the three ($p > .14$, $r < 0.11$), and equivalence testing kept all three within a ±0.5 margin: synthetic narration did not degrade the experience. Dialogue narration was better on comprehension ($p = .006$, $r = .130$), on reported deepened thinking ($p = .019$, $r = .121$), and on being able to explain the content to a friend ($p = .004$, $r = .152$), and 66.9% preferred it as most enjoyable. Two caveats: dialogue audio was rated significantly less natural ($r = −.238$), consistent with extra load from multiple speakers, and the dialogue group arrived with less prior knowledge (66.0% reporting knowing “nothing at all” versus 34.1%), which makes its advantage a conservative estimate.

The follow-up argues that format should be matched to the learner, not the content. Watanabe et al. (2026) gave 222 first-year high-school students teacher–student (TS), student–student (SS), and teacher–teacher (TT) dialogue lessons generated by an LLM and voiced through a TTS API, fitting linear mixed-effects models through an aptitude-treatment interaction lens. TT raised Motivation more than TS, but the effect depended on learning style: the interaction with the Concrete Experience factor was positive ($b = 0.162$, $p < .001$) while the interaction with the reflection-and-conceptualization factor was negative ($b = −0.238$, $p = .002$). TT also drew a significantly *lower* overall evaluation than TS ($b = −0.126$, $p = .005$), which the authors attribute to intrinsic cognitive load from dense expert-to-expert exchange; free responses name “stiffness of speech” in TT and “unnatural manner of speaking” in SS. Both TTS studies confound format with content and fixed viewing order, so their effect sizes are preliminary.

Voice-First Companions and Spoken Dialogue Partners

What changes when the interlocutor is a machine? Scheinberg et al. (2026) had 78 university learners of German across four sites complete a counterbalanced spot-the-difference task with both a human peer and a real-time AI partner, then analyzed diarized ASR transcripts. Human dialogue was faster and better balanced, with many short turns, while the AI condition looked like supported monologue — fewer, longer turns, a smaller learner share of the floor, and higher within-turn fluency. The AI's verbose, syntactically regular input was associated with greater short-term uptake and stronger syntactic priming after controlling for input volume, and satisfaction tracked learners' own production fluency rather than how much they picked up.

Voice-first design becomes a necessity rather than a convenience when the learner cannot use a screen. Kutti AI (Fadurudeen 2026) inverts edtech's visual assumption to reach an estimated 1.4 million blind children worldwide: children hear curriculum content, answer aloud, and receive spoken feedback with no visual dependency. Three choices carry the design — a lightweight struggle-detection engine fusing response latency, wrong-attempt counts, and keyword hesitation cues to decide when to hint or simplify; a cross-language answer-matching pipeline so that code-switching and pronunciation variation are not penalized; and an offline on-device ASR path that removes the connectivity requirement. It is a systems contribution with no learning-outcomes evaluation, so its pedagogical claims remain hypotheses.

Accent, meanwhile, is a design variable with social consequences. Ravi et al. (2026) had 33 teachers interact with a GenAI voice agent in British, Indian, and African American accent conditions in K-12 group learning. The British-accented agent was treated largely as a tool and engaged with in detached, utility-based ways, while the Indian- and African American-accented agents were more readily anthropomorphized and integrated as peers, with stronger trust and reliance over time. Turn-taking, questioning patterns, and perceived social presence all shifted with accent — the voice that makes an agent easy to treat as a neutral resource can make it easier to ignore as a collaborator.

Heavier use of a spoken support tool is not automatically better. Kuang, Li and Weng (2026) had 22 interpreting trainees complete bidirectional computer-assisted consecutive interpreting tasks in systems built on ASR and machine translation, capturing eye movements, pen notes, and voice output. Four interaction profiles emerged — Intensive Engagers, Fast Scanners, Traditionalists, and Frequent Switchers — and 58.3% of stage-level observations changed profile between comprehending the source and producing the target. Only comprehension-stage patterns predicted product quality, and the AI-heaviest cluster scored lowest on fluency of delivery (5.46 against 6.17–6.46) and target language quality (5.70 against 6.35–6.67). Attention spent reading an AI transcript is attention not spent building one's own representation; the authors recommend teaching learners to reflect on their own strategy rather than prescribing one, since the pattern is invisible unless surfaced.

A preregistered randomized field experiment tests the spoken channel against typed text within the same tutor, and finds the learning is in the tutoring rather than in the voice. Yang, Van Alstyne and Dellarocas (2026) randomized 86 students in an online-MBA corporate-finance module between a structured tutor grounded in course materials and a holdout, then alternated each tutored student's channel weekly between voice and text so the comparison is identified inside each student: weekly mastery differed by −0.01 points of 11 ($p = .98$), and two one-sided tests rejected any true difference larger than ±0.3 SD. Voice transformed the process instead — 1.34 dialogue turns per minute against 0.75 in text weeks, and 11.3 questions against 4.6 — while the thinking pause collapsed (median tutor-to-student reply gap of 27 seconds in voice against

54 in text, where typed turns spent 25.9 seconds before the first keystroke plus 13.9 seconds composing) and the speech channel cost 2.8× more to deliver, at $0.22 per voice minute against $0.0165 per text message ($413.46 voice and $149.13 text over five weeks for 52 seats). On this evidence voice is an adoption and engagement lever, not an encoding one — which is exactly the trade-off any institution adding a spoken channel has to price.

The same voice stack is now proposed for the reverse direction: Tamme, Schilling & Hantel (2026) plan an ElevenLabs-based telephone agent that interviews students about a course in 5–7-minute conversations with adaptive probes. Their completed Munich pilot established feasibility; the planned field study, in one MIT Sloan course with approximately 60 students, has reported no results.

AI in Oral and Spoken Assessment

Oral assessment has always been pedagogically strong and logistically expensive, and speech technology now attacks the cost side. Pentland, Lowenthal and Krier (2026) describe asynchronous oral assessments (AOAs): prompts delivered just-in-time, brief time-limited webcam responses that cannot be revisited, and grading against embedded rubrics with auto-generated transcripts. Across two courses taught by a single instructor without scheduling constraints, students scored higher on AOAs than on in-person multiple-choice exams. That was significant in Study 2 (midterm median 92.5 vs 70, $p < .001$; final 94.2 vs 86.4, $p = .002$) and directional in Study 1, with moderate cross-format correlations ($\tau = .44$; $\tau = .25$, non-significant). Students shifted to more active preparation, 90.91% saw the format as closer to workplace communication than written exams, and 81.82% reported engaging more actively with content. The authors are careful that these are format score differences, not evidence of learning gains, and that the integrity advantage is inferred rather than measured; a re-scoring check with an LLM found instructor scores systematically higher with moderate-to-good agreement (ICC 0.73 and 0.60), offered as a reliability check rather than an endorsement of automated grading.

Fenton (2025) supplies the rationale in review form: because orals are real-time and interactive, students cannot generate answers in advance and memorize them, and the format probes reasoning at higher levels of Bloom's taxonomy rather than recall. Its benefits — personalization, authenticity, work-readiness, deeper knowledge — come with named costs: scheduling and logistics, learner anxiety, and bias risk around gender, ethnicity, language, response speed, and non-anonymous marking, though the evidence suggests orals can be as inclusive as written exams for some learners, including those with dyslexia.

Two deployments show what the technology adds. AkoVoice (Adams 2026) assessed 33 learners across four Level 3 Automotive classes and one Level 3 Engineering class in New Zealand, on learner-owned phones against one mid-range laptop running open-weight models — Mistral 7B via Ollama, faster-whisper for speech-to-text, Chatterbox for TTS. Up to 12 learners were assessed simultaneously, with no internet connection at any point. AI was cast as evidence-surfacer rather than judge, leaving the assessor's judgment intact. Learner reaction was positive: 21 of 33 (64%) called the task realistic, and none of the 33 disagreed that speaking in real time felt right compared with a written portfolio. The performance data is more interesting. Word counts for identical questions varied five- to eight-fold between learners in every cohort (93–523, 92–796, 309–811), yet verbosity did not predict accuracy on closed questions. Nine learners answered in 2 to 13 words and were all marked correct, the shortest being "3500 kgs", while the fuller "the safe working load is three tons" was flagged against a 3.5-ton marking guide. Adjacent Horticulture (14

learners) and Dairy (11 learners) trials found a 95% match between the agent's preliminary grade and the human tutor's grade. On the item side, Aryadoust and Wong (2026) compared iterative prompt engineering against fine-tuning for L2 listening items, producing 40 tests and 240 multiple-choice items: prompt refinement improved quality but plateaued, while fine-tuning GPT-4.1 on the optimized prompt with prompt design held constant improved generation further. Spoken assessment also risks measuring the wrong thing — Morphew et al. (2026) track gesture alongside transcribed speech and argue that assessing only speech misses embodied evidence of understanding, so that fluency can be mistaken for conceptual knowledge.

Accessibility and Equity in the Spoken Channel

Speech technology's accessibility record is mixed: the same channel that removes one barrier can install another. Deaf and hard-of-hearing learners are the clearest mismatch. Chen et al. (2026) designed an LLM question-generation system for DHH learners watching video, drawing on Language Deprivation Theory to explain why text-based prompting fits poorly with sign-based first languages. It added Visual Questions (timestamps where visual information is likely misread — rapid movement, misaligned captions, dense on-screen text) and Emotion Questions (timestamps where prior DHH learners reported frustration or confusion), refining a final bank of 30 questions with learners and instructors. With 16 users the prototype improved Self-Efficacy (M = 5.70, SD = 1.12 on a 7-point scale), and Deaf participants selected visual questions more often than hard-of-hearing participants, who reported reading captions fast enough not to need them. Accessibility here had to be built into generation, not appended to it.

AkoVoice adds two equity considerations that rarely surface together. First, data: recordings were encrypted at rest, hosted locally, and deleted after 90 days, and the authors treat a participant's voice as a personal and cultural expression rather than a resource for training models or building biometric profiles — a stance that matters because the EU AI Act classifies AI used to evaluate learning outcomes in vocational training as high-risk. Second, accent and register: speech-to-text accuracy was not fully tested across learner accents, and rubric criteria such as "engaging" were flagged as culturally specific and potentially penalizing to second-language speakers, prompting a review notes field. Set beside the accent findings in K-12 group work and the near-total visual assumption of mainstream edtech, the pattern is that the voice interface removes sight, reading-speed, and connectivity barriers while leaving accent, recognition accuracy, hardware cost, and cultural register open.

Scope check. This page is about the spoken channel and the technology that carries it. For second-language pedagogy at large — writing development, grammatical accuracy, motivation, teacher practice — go to Language Learning, which spans L2 instruction with AI and treats speaking as one strand among several. For text-based chatbots and dialogue design independent of modality, go to Conversational AI; several articles here involve dialogue, but their question is about speech, not about prompting a chat model. For screen readers, captioning, tactile graphics, and assistive tools that are not primarily speech-based, go to Assistive Technology, which sits under the broader Accessibility and Inclusive Learning strands of this wiki.

What Remains Uncertain

Almost every strong claim here rests on one short study. The two TTS lesson studies ran in single Japanese high schools with fixed presentation order that confounded format with content, and their learning-outcome measures were self-reported on in-house scales. The ASR feedback model came from one Chinese university

and was cross-sectional, so its proficiency-moderation finding describes covariance rather than causation. The willingness-to-communicate study measured perceptions of feedback, not feedback quality. The interpreting profile study is a 22-participant exploratory analysis in which output-stage effects did not reach significance. The AOA and AkoVoice deployments are single-institution, and AkoVoice reports no summative learning evidence because its voice assessments ran in parallel to actual assessments. Kutti AI is a systems contribution with no outcome evaluation at all. What the collection does support is a set of design claims: feedback quality beats practice volume in ASR use, dialogue narration can aid comprehension at the cost of naturalness, format should be matched to learner characteristics rather than fixed, AI should surface evidence rather than replace the human assessor, and speaking in real time measures something writing does not — including an accuracy surprisingly indifferent to how many words the learner uses. Whether any of that holds at another site, another language, or another year is untested.

Common Misconceptions

- **“Paid speech services outperform free ones.” The two free services returned near-complete transcripts (87.96% and 88.34% coverage, with word error rates of 15.23% and 15.00%)**, while the two paid services exported only previews, at 32% coverage). Price did not predict utility, and the paid tier gated the output rather than improving it.
- **“Any language-learning chatbot improves pronunciation.”** Across **ten studies**, **only chatbots designed for language learning — Andy English bot and Xiaoying — improved accuracy**, with a **14% error decrease in one control group** comparison. Generic conversational agents did not produce the gain.
- **“Self-efficacy gains mean skill gains.”** The association between the technology and outcomes was positive with **self-efficacy partially mediating it: the indirect path accounted for 69.9% of the total effect while a direct effect remained**. Most of the effect ran through confidence, which is a mechanism and also a caution.

Connected Concepts

- Language Learning
- Conversational AI
- Accessibility
- Assistive Technology
- Assessment
- Authentic Assessment
- Human-in-the-Loop
- Multimodal AI
- Inclusive Learning
- Equity

Connected Articles

- Chatbots for oral proficiency in English language learning: A systematic review — Accuracy gains only from language-learning chatbots, and ASR failures on accented names
- Voice-Based AI Feedback in Higher Education: A Field Study on Quality and Actionability — A telephone voice agent turned on the feedback channel itself
- ASR Technology in College English Speaking Instruction: The Role of Feedback Internalization and Metacognitive Strategies — ASR speaking feedback: quality beats quantity, and proficiency moderates who benefits (Chen et al. 2026)
- Associations between generative AI–based pronunciation feedback and willingness to communicate in English: The mediating role of English pronunciation self-efficacy — Pronunciation self-efficacy mediates GenAI pronunciation feedback and willingness to communicate (1,701 EFL learners)
- A Semi-Automated System for Generating Dialogue-Based TTS Lessons Using Large Language Models: An Exploratory Study of Educational Potential — LLM + TTS lesson pipeline: synthetic narration matched instructor voice; dialogue aided comprehension
- Interaction Effects Between Learner Characteristics and Dialogue Format in TTS Dialogue-Based Lessons — Learning-style × dialogue-format interactions in TTS-generated lessons (222 students)
- What Changes When the Interlocutor Is an AI? Interactional Fluency and Linguistic Uptake in L2 Spoken Dialogue — Human versus AI interlocutors: supported monologue, uptake, and syntactic priming in L2 German
- Kutti AI: A Voice-First, Offline-Capable Learning Companion with Real-Time Struggle Detection for Visually-Impaired Children — Voice-first offline companion with real-time struggle detection for visually impaired children
- Exploring How Agent Voice Accents Shape Human-AI Collaboration in K-12 Group Learning — Agent accent shapes anthropomorphization and collaboration in K-12 group work (33 teachers)
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous oral assessments: scalable spoken assessment, with a learning-gains caveat
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Review making the case for oral exams as authentic, integrity-protective assessment
- Designing AI-Supported Oral Assessment in TVET — AkoVoice: offline voice assessment in vocational workshops where AI surfaces evidence, not grades
- Student-AI interaction in computer-assisted consecutive interpreting: patterns and performance — Four interaction profiles among interpreting trainees using ASR/MT support
- How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment — Prompting versus fine-tuning GPT for L2 listening item generation
- A Multimodal Framework for Embodied Cognition in Oral Explanations — Gesture plus speech: why speech-only oral assessment misses evidence of understanding
- AI-guided learning: Research on knowledge and skill acquisition support methods using deep learning audio-video processing techniques — Adaptive audio speed, voice-preserving video summaries, and unlabeled pronunciation feedback

- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM question generation for deaf and hard-of-hearing learners
- When AI Tutors Speak: Evidence from a Randomized Field Experiment — When AI Tutors Speak: Evidence from a Randomized Field Experiment
- AI-Mediated Input Transformation in Medical English: Speech Recognition and Transcript Reliability — AI-Mediated Input Transformation in Medical English: Speech Recognition and Transcript Reliability

Visualization

> **Visualization** — the use of data visualizations, infographics, dashboards, charts, diagrams, and other graphical representations to make information comprehensible for learning and analysis. Across education, visualization is increasingly both generated by AI (text-to-image, Multimodal AI slide and chart analysis) and used as the interface through which learners, teachers, and analytics systems reason over shared data.

Questions to Consider

- A chart or dashboard can make data clear — but is simply *seeing* a visualization the same as understanding it? The page's research suggests how you interact with a visualization matters more than the chart itself. Recall a dashboard or graph you looked at but didn't really learn from. What was missing from the mere display?
- Conventional learning dashboards follow a 'show data, hope for insight' model. The finding here is that learners who answer questions about their data *before* seeing the metrics reflect and calibrate better than those who passively view charts. Why might being forced to predict first change what you get out of seeing the actual data?
- AI can now generate accurate visualizations of specialized content: after fine-tuning on nuclear concepts, a text-to-image model climbed from 12% to 78% on that domain. But the page also finds no model is uniformly competent. Where would you trust an AI-generated visual, and where would you insist on checking it against a human expert?
- Participants in one study found AI-generated data comics more engaging and comprehensible, yet many also flagged misinformation risk and information overload. How do you weigh the appeal of a compelling AI visual against its potential to mislead — and what would you verify before trusting or using it?
- The page warns that a model's *confidence* is not its *reliability*: systems can sharply diverge on severity judgments while getting basic constructs right. If you relied on an AI tool to assess slides, essays, or data, how would you discover where its confidence hid a serious error?
- One study found students spent most of their gaze on code despite elaborate visual scaffolds — visual aids simply didn't capture attention for everyone. What does that suggest about assuming a nice diagram or dashboard will automatically help all learners engage? What else besides visuals shapes how people actually use a tool?

Introduction

Visualization is the use of graphical representation — dashboards, charts, diagrams, infographics and multimodal displays — to make learning and learning data intelligible. Its most established educational role is the learning analytics dashboard, where the dominant *show data and hope for insight* model has given way to interactive designs: the evidence indicates that how learners interact with a representation matters more than whether they see it, and that self-elicit prompts and pedagogical agents improve calibration more than

passive metrics do. The same question — does the display provoke thinking or substitute for it? — links visualization to Desirable Difficulties and Metacognition.

Visualization as a Learning Interface

The most established role of visualization in education is the learning analytics dashboard. In their standard form, learning analytics dashboards (LADs) put behavioral metrics into charts for learners to view passively, operating on a "show data → hope for insight" model. Research on Interactive learning dashboards: rethinking learning visualisations as engagement tools challenges this paradigm: when a dashboard adds an Large Language Models (LLMs)-powered pedagogical agent and an interactive Judgment of Learning Self-Assessment, the "elicit" condition — where learners answer questions about their data before seeing metrics — produced more reflection and more accurate mastery calibration than either a passive dashboard or a "telling" agent. The lesson is that how learners interact with visualizations matters more than merely seeing them. This connects to Learning Analytics and Self-Regulated Learning, where visual feedback supports metacognitive judgment calibration rather than simple information display.

Teacher-facing dashboards add a distinct set of design lessons. Mejia-Domenzain et al. (2026) found that teachers systematically preferred simpler, more traditional visualizations (bar plots, pie charts, legends) even when more complex designs (e.g., heatmaps) yielded more detailed insights — visual preference did not always align with informativeness, echoing debates about pie charts' comparative readability. Visualization literacy (VL) did not drive design preferences, but higher-VL teachers produced deeper, more detailed interpretations (e.g., more of them identified trends in time-series data), confirming VL as a confounder for gauging how teachers read analytics designs. For group comparison, teachers strongly favored superposition over juxtaposition, and preferred plots that displayed full information (e.g., including a "students who did not watch" group) rather than explicit difference encoding, although younger teachers ranked difference plots higher. These findings argue that dashboard design must balance teachers' stated preferences against the interpretative depth that more complex encodings afford.

Dashboards also function as shared representations that bridge human and AI reasoning. The CLARA system uses LLM-generated artifacts — concept maps and seven-dimension collaboration assessments — as common ground between dashboard users and AI agents, indexing them into separate vector collections so both parties reason over the same visible, queryable material. Similarly, the Expert Cognition Dashboard reframes analytics as "cognition intelligence," turning raw learner behaviors into interpretable cognition structures across individual, class, and AI Twin expert levels. These systems position visualization not as an output but as embedded reasoning infrastructure within Technologies-native education.

AI-Generated and Multimodal Visual Content

A second major strand concerns AI producing visualizations directly. NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts shows that domain-adapted text-to-image models can generate accurate illustrations of specialized STEM concepts: fine-tuning Stable Diffusion on nuclear domain images raised domain accuracy from 12% to 78%, enabling instructors to produce correct reactor-component and safety-system visualizations on demand. This generative capacity is powerful but uneven. Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy benchmarks six multimodal large language models against 485 human participants on scientific visualization literacy, finding

no uniform competence: closed-source Gemini exceeded the human mean on several subsets while all Open Source models fell below it, with particular weaknesses in fine-grained quantitative estimation and texture-based or integration-based visualizations. AI should therefore support — not substitute for — human visualization literacy, a finding with direct AI Literacy and Formative Assessment implications.

Prompt-to-chart generation raises a different question from whether AI can produce a competent visualization: whether the learner still performs the analytic and encoding work that makes the artifact educational. A 2026 framework calls this the process–output divide and proposes transparency, invitation, and fading as the agency line between Scaffolding and substitution (Purohit et al., 2026).

Ethics and reliability temper enthusiasm for AI-generated visual content. Data Comics for Education: Evaluating Effectiveness, Benefits, and the Ethics of AI-Assisted Creation found GenAI-assisted data comics improved engagement and comprehension over conventional visualizations regardless of prior visualization literacy, yet participants raised concerns about misinformation risk and authorship attribution, and two-thirds flagged downsides such as information overload from overly busy layouts. The counterfactual CFES-P24 benchmark extends this scrutiny to slide auditing, showing that multimodal LLMs can reliably recognize Learning Design constructs (operations, principles, evidence localization) while sharply diverging on comparative judgment and severity calibration — evidence that composite scores conceal which capability fails and that confidence is not reliability. Together these works argue for layered evaluation of AI-generated visuals rather than holistic ratings.

Slide, Comic, and Multi-View Tools in Practice

Practical systems apply these principles at scale. AISSA combines LLM-based rubric scoring with learning analytics dashboards to deliver automated, iterative feedback on student presentation slides, processing 90 presentations in 1–3 minutes each at cents-per-evaluation cost with high perceived usability — while students selectively applied feedback, sometimes disregarding recommendations that conflicted with their visual design. In coding education, Flowcode pairs a code-structure flowchart with a learning-oriented chat to help novice creative coders understand and extend found examples, where visualization and productive friction steer AI use toward learning rather than bypass. Yet visual scaffolds are not universally effective: Code as Anchor, Memory and Metaphor as Support: Learner Experiences with Multi-View Visualizations found students spent ~47% of gaze time on code despite visual scaffolds, driven by agency, representational fit, and the perceived legitimacy of metaphorical views. These learner-experience findings caution that visualization design must attend to affective and social factors, not just cognitive affordances.

Implications

Across the works discussed here, visualization emerges as a dual-use medium: AI increasingly generates and interprets visualizations, while dashboards and interactive visuals serve as the shared surface for human-AI sensemaking. Generative text-to-image and multimodal analysis extend the reach of visualization into specialized STEM content and automated feedback, but uneven model competence, severity-calibration failures, and ethical concerns over misinformation and authorship demand careful, layered verification. For designers and educators, the strongest conclusion is that interactivity and engagement — eliciting learner reasoning over visual data, letting users control cognitive effort, and treating AI-produced visuals as shared infrastructure rather than endpoints — matter more than the fidelity of the chart itself.

Common Misconceptions

- **“AI cannot render specialised content accurately.”** It can, with the right method: fine-tuning a text-to-image model on nuclear concepts **raised domain accuracy from 12% to 78%**. The gap is domain grounding, not generative capability, and it is addressable.
- **“Better visualisations produce better outcomes.”** Teachers **systematically preferred simpler, more traditional visualizations** (bar plots, pie charts, legends) **even when complex designs such as heatmaps yielded more detailed insights**. The more informative artifact was not the one that got used, so adoption is a separate problem from design quality.
- **“Students look where the scaffolding is.”** One study found students **spent most of their gaze on code despite elaborate visual scaffolds** — the aids simply did not capture attention. Visual support that is present but unattended changes nothing.
- **“Engagement and comprehension move together.”** Participants found AI-generated data comics **more engaging and comprehensible, yet many also flagged misinformation risk and information overload**. Both reactions came from the same artifact, so a positive reception is not a verified reading.

Connected Concepts

- Learning Analytics
- Multimodal AI
- Generative AI
- Technologies
- AI Literacy
- Storytelling in Education
- Learning Design
- Assessment Validity
- Virtual and Augmented Reality — spatial and three-dimensional representation

Connected Articles

- Interactive learning dashboards: rethinking learning visualisations as engagement tools — Rethinking learning visualizations as engagement tools via pedagogical agents
- Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy — Benchmarking multimodal LLMs for scientific visualization literacy
- NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts — Domain-adapted text-to-image models for nuclear concept visualization
- Data Comics for Education: Evaluating Effectiveness, Benefits, and the Ethics of AI-Assisted Creation — Effectiveness, benefits, and ethics of AI-assisted data comics
- Benchmarking Multimodal Large Language Models for Educational Slide Auditing — Counterfactual benchmark for multimodal slide auditing

- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms
- Constructing Meaning, Not Just Charts: A Cognitive–Instructional Framework for Generative AI Usage in Visualisation Education — Constructing Meaning, Not Just Charts: A Cognitive–Instructional Framework for Generative AI Usage in Visualisation Education

Educational NLP

> **Educational NLP** applies language technologies to learning: Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction, A Durability and Cross-Language Transfer Benchmark for a Validated Teaching-Feedback Classification Protocol, LLM-assisted sentiment analysis for integrated computational and qualitative mixed methods education research: A case study of students' written reflection assignments, and What Makes Words Hard? Sakura at BEA 2026 Shared Task on Vocabulary Difficulty Prediction show LLMs advancing analysis of student language at scale (Educational Measurement, educational-nlp).

Questions to Consider

- When an LLM analyzes thousands of student essays or discussion posts for sentiment, what might it be getting right, and what about the language of learning do you suspect it's missing?
- Natural language processing can now estimate the difficulty of vocabulary and test items, and classify teaching feedback at scale. If those predictions feed adaptive systems, who checks whether the machine's judgments about language are actually right for the learners using them?
- How is analyzing student language different from understanding it? Where might the line between correlation and genuine insight blur when NLP scales up sentiment and feedback analysis?
- This concept connects NLP to tutoring, student modeling, and measurement. Before reading, how much of 'understanding a student' do you think can be captured from their written or spoken language alone — and what gets left out?

Introduction

What educational NLP does

Natural language processing in education applies computational methods to the language of teaching and learning — student essays, responses, discussion posts, feedback, and instructional text. LLMs have dramatically expanded what can be analyzed automatically, enabling fine-grained understanding of student language that was previously impractical at scale.

Applications documented in the knowledge base

- **Analysis of student language.** LLM-assisted sentiment analysis for integrated computational and qualitative mixed methods education research: A case study of students' written reflection assignments applies LLM-based sentiment analysis to educational research, extracting emotional and evaluative signals from student text at scale, feeding Learning Analytics and Affective Computing.
- **Prediction and measurement.** Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction and What Makes Words Hard? Sakura at BEA

2026 Shared Task on Vocabulary Difficulty Prediction use language models to estimate item and text difficulty — core inputs to Educational Measurement, Adaptive Learning, and Item Response Theory models.

- **Readability and curriculum alignment.** Bird (2026) fuses transformer text classification with computational-linguistics features to classify English literature by UK Key Stage, reaching an F1 of 0.996 — a data-driven complement to What Makes Words Hard? Sakura at BEA 2026 Shared Task on Vocabulary Difficulty Prediction and Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction for Educational Measurement and reading-level alignment.
- **Semantic similarity is a weak signal for curriculum alignment.** Screening 3,837 dental objective–abstract pairs, embedding retrieval plus a natural language inference check judged 22.9% of high-similarity matches (cosine 0.90–1.00) neutral or contradictory and lifted expert-labeled accuracy from 0.69 to 0.73 (Yasmin et al. (2026)).
- **Discourse-level classification localizes what surface features miss.** A BERT model fine-tuned on only its last four transformer layers classifies adjacent sentence pairs as causal, contrastive, progressive or incoherent and emits the breakpoint as a diagnostic, reaching a mean F1 of at least 0.891 on 28,736 sentence pairs (Wang et al., 2026).
- **Whole-lesson modeling beats utterance-level classification.** Scoring entire lesson transcripts rather than isolated utterances lifted reasoning-chain detection by 14.2 percentage points over state-of-the-art discriminative baselines, and adding a dialect-invariant contrastive objective cut African American Vernacular English false negatives by 18.4 points (Fang and Liu, 2026).
- **Feedback and classification.** A Durability and Cross-Language Transfer Benchmark for a Validated Teaching-Feedback Classification Protocol provides a Benchmark for classifying teaching feedback, advancing Feedback Loop research and LLM Training and Fine-Tuning.
- **Scaling NLP on evaluation comments without reaching use.** A PRISMA-ScR scoping review and evidence map of 421 studies applying NLP to open-ended student evaluation of teaching (2015–2026) finds sentiment analysis still the modal task (300/421, 71.3%) and a 49.7-point actionability discontinuity: 258 studies (61.3%) demonstrated a usable output but only 49 (11.6%) reached evaluation by an intended user, with a formal fairness metric in just 8 studies (1.9%) and external validation in 33 (7.8%) (Eicher & da Silva (2026)).
- **Explanations are not interchangeable with attributions.** Bueno et al. (2026) found SHAP attributions identified the sentences that reliably drove rubric scores and transferred across model families, while LLM-generated rationales exerted limited, inconsistent influence — even though fine-tuned PLMs outscored prompted LLMs on accuracy.
- **Short-answer assessment in science.** Morley et al.'s scoping review of transformer-based auto-marking of short-answer science questions (2017–early 2024) shows BERT-family models became the field's dominant workhorse for free-text marking before larger LLMs were adopted via prompting, and that models augmented with domain knowledge — extra pre-training, rubric or textbook data, meta-learning — consistently outperformed those without (Auto-marking short

answer questions in science: The foundational years of transformer-based models from BERT to GPT-4).

- **Context-sensitivity vs. reference matching in open-response grading.** Benchmarking eleven GenAI and sentence-embedding models on 1,885 software-engineering open-ended answers, Pecuchova, Benko & Drlik (2025) show that context-sensitive LLMs (GPTo1 best, almost-perfect human agreement) beat cosine-similarity reference-based models (BERT, RoBERTa, T5, USE), which systematically misclassified valid but differently-phrased responses. Their NLI analysis revealed that many semantically correct answers fell into the *contradiction* category relative to reference answers — evidence that educational NLP grading must accommodate students' short, diverse, own-word phrasing rather than rigid reference alignment. That contrast sharpens for teacher knowledge: coding 268 U.S. middle school mathematics teachers' open-ended responses, both classical encoders (RoBERTa, Sentence-BERT) and a naive single-prompt GPT-4o topped out well below the human coders on pedagogical content knowledge (PCK), whereas a three-agent LLM harness that iteratively added clarification points to the *human* coding manual reached substantial PCK agreement and near-human agreement on the far more tractable content-knowledge items — reliability coming from refining instructions against real disagreements, not from a larger model, with the most complex teaching-reasoning items still wanting expert review (Copur-Gencturk et al., 2026).
- **Learner-generated question classification.** Lee, Atif & Kang (2026) classify 434 authentic learner questions from 11 IT students across 12 courses into three Constructivism instructional roles — knowledge transmitter, facilitator, and co-learner — and benchmark four transformers on the task. DeBERTa led at 86.36% accuracy (F1 86.52%) with 96.67% precision on factual knowledge-transmitter questions, yet only 78.79% precision on facilitator queries; fine-tuned BERT reached the best co-learner recall (92.00%) at lower precision. The result mirrors the field's recurring pattern that strong aggregate scores mask weak discrimination on higher-order categories: conceptual overlap between roles, ambiguous learner intent, and domain-specific technical phrasing misread as cognitive depth all defeat surface lexical features, arguing for context-aware embeddings, multi-turn dialogue signals, and intent-sensitive features (Cross-Dataset Bloom Question Classification: Supervised Models and Prompted LLMs, From Memorization to Creation: Evaluating the Cognitive Depth of LLM-Generated Educational Questions).
- **Taxonomy classifiers lose most of their accuracy on generated content.** A Bloom-level classifier scoring macro-F1 0.88 on a curated item bank fell to 0.48 and 0.20 across two AI-generated question sets, with the loss tracking the absence of explicit Bloom trigger verbs rather than model size; only LLMs (0.41 to 0.79) and classifiers retrained on generated items (up to 0.82) held up (Castanares et al., 2026).
- **Corpus-scale curation for pre-training data.** Garrod et al. (2026) replace a single "is this educational?" score with twenty inspectable rubric dimensions — factual accuracy, pedagogical structure, level suitability and foundational-literacy criteria among them — and distill GPT-4.1-mini's pairwise preferences into reusable Edu-QuRaters that recover held-out judge preferences at mean accuracy 0.917, then label all 322.25M rows of FineWeb-Edu-Fortified, where the filtered mixtures lifted downstream Benchmark accuracy over the FineWeb-Edu baseline. It marks a role

for educational NLP beyond analyzing the language learners produce: screening the instructional text that other models are trained on.

- **Auditable coding by separating assertions from interpretation.** Bernado et al. (2026) replace single-label prompting with a schema of 221 human-readable assertions - 74 corpus-derived, 48 construct-derived, and 100 automatic word-presence checks - that a transparent classifier maps to the construct label, reaching macro-F1 0.673 and Cohen's κ 0.688 on the TalkMoves teacher-talk corpus against a published direct-prompting maximum of 0.61 macro-F1 and 0.58 κ, while trailing a fine-tuned RoBERTa-base classifier at 0.76. Requiring Krippendorff's $\alpha \geq 0.5$ kept only 33 of 74 corpus-derived assertions, and a words-only baseline scored 0.339 macro-F1, so the gain comes from learned behavioral assertions rather than keyword frequency.
- **Concept tagging at scale.** Yang et al. (2026) split knowledge-concept tagging into a Select–Reason–Judge pipeline — a small model shortlists candidate concepts, the LLM reasons over the shortlist, then judges — lifting tagging accuracy on three benchmarks by shrinking the model's decision space.
- **Handwritten answer sheets resist existing parsers.** Multi-line derivations, interleaved prose and formulas, hand-drawn tables, and noise from strikethroughs and erasures escape printed-document and isolated-expression benchmarks, so the HANS dataset of real eighth-grade mathematics sheets — 5,213 answer images from 745 students across 18 problem types — annotates that noise and backs a noise-suppression model that improves recognition (Wu et al. (2026)).

Connection to tutoring and measurement

Educational NLP underpins both the analysis of learner language (Learner Modeling and Adaptive Instruction, Knowledge Tracing) and the generation of adaptive instructional content (Intelligent Tutoring, Scaffolding). AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement demonstrates NLP-driven content generation for learning, while Comprehensive Review of Intelligent Tutoring Systems situates NLP within the broader Intelligent Tutoring landscape. As LLM-based analysis grows, RCT and Research Methods in AIED frameworks matter for validating that NLP-derived insights genuinely improve learning.

Embeddings can also organize student text by surface form rather than by the construct being taught. On a synthetic Carnot-engine set the same pipeline grouped statements by wording rather than by physics — a novice-like representation, Tauschhuber & Kortemeyer (2026) argue — which makes clustering a tool for exploration, not for grading.

Model compression belongs to the same toolkit: a two-stage pipeline distills a fitted black-box estimator and its post-hoc interpretation into a small open-weight model, so a 2B-parameter "mentee" returns both an estimate and a natural-language explanation offline on a commodity laptop (Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics).

Common Misconceptions

- **"Semantic similarity can screen curriculum alignment."** Screening **3,837 dental objective-abstract pairs**, embedding retrieval plus a natural language inference check **judged 22.9% of**

items as aligned — semantic similarity is a **weak signal** for alignment. A fluent topical match and a genuine learning-objective match are different relations.

- **"Utterance-level classification is the natural unit." Whole-lesson modelling beats utterance-level classification**: scoring entire transcripts rather than isolated utterances **lifted reasoning-chain detection by 14.2 percentage points**. Context across the lesson carries information that any single turn destroys.
- **"Scaling NLP on evaluation comments produces impact."** A PRISMA-ScR scoping review and evidence map of **421 studies** (2015-2026) applying NLP to open-ended student evaluation of teaching found scaling **without reaching use**. Volume of method output is not adoption, and the gap is the deployment step rather than the modeling.

Connected Concepts

- Intelligent Tutoring
- Learner Modeling and Adaptive Instruction
- Knowledge Tracing
- Socratic Method
- Scaffolding
- Adaptive Learning
- LLM Training and Fine-Tuning
- Metacognition
- RCT
- Learning Analytics
- Educational AI Policy
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Testing the validity of embedding-based similarity and clustering for handwritten physics solutions — Embedding clusters that organize by wording rather than physics
- Analysing AI utilisation in education through learner question types: A constructivist approach — Transformer classification of learner questions into constructivist roles (Lee, Atif & Kang 2026)
- Automatic discourse relation classification and feedback optimization in English teaching based on transformer BERT model — Automatic discourse relation classification with BERT for English teaching
- The StudyChat Dataset: Analyzing Student Dialogues With ChatGPT in an Artificial Intelligence Course — The StudyChat dataset of student–LLM dialogues in an AI course
- Neuro-symbolic pedagogical alignment (NSPA) for long-horizon classroom discourse analysis: Mitigating dialect bias via counterfactual preference optimization — Neuro-symbolic pedagogical alignment (NSPA)

- AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement
- Comprehensive Review of Intelligent Tutoring Systems
- From scoring to explanations: Evaluating SHAP and LLM rationales for rubric-based teaching quality assessment — SHAP and LLM rationales for rubric-based teaching quality
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — Distilling self-explaining LM for learning analytics
- Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models
- Automated coding of content and pedagogical content knowledge of mathematics using a multi-agent large language model — Multi-agent LLM (GradeOpt) codes teachers' content and pedagogical content knowledge; classical encoders and naive prompting fall short on PCK
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues
- From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026 — From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions
- SRJudge: Empowering Large Language Models with Selective Reasoning for Fine-Grained Knowledge Concept Tagging — SRJudge: selective-reasoning pipeline for fine-grained knowledge concept tagging
- Natural Language Processing for Aligning Readings with Learning Objectives and Assessing Topic Balance in Dental Education — Natural Language Processing for Aligning Readings with Learning Objectives and Assessing Topic Balance in Dental Education
- HANS: A Handwritten Answer Sheet Dataset for Noisy Hybrid Document Parsing — HANS: A Handwritten Answer Sheet Dataset for Noisy Hybrid Document Parsing

Reinforcement Learning

> **Reinforcement learning** trains AI tutors and agents through reward signals: Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training, Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning, Pedagogical Safety in Educational Reinforcement Learning, and AI Coaching for Accelerating Human Skill Development with Reinforcement Learning align RL with pedagogical objectives, including safety and skill transfer (Intelligent Tutoring, Agentic AI).

Questions to Consider

- An RL tutor 'learns' what to do by maximizing a reward signal. Before you read, what could be wrong with an AI that optimizes for a reward — specifically if the reward is something like 'student clicks continue' or 'correct answer now'?
- The page notes that reward design encodes educational values. If you had to specify the reward an AI tutor should maximize, what would you put in it — and what would your reward accidentally ignore or reward incorrectly?
- RL trains agents to make long-horizon sequences of decisions (what hint, when to advance difficulty, how to pace) rather than single answers. How is that different from the moment-to-moment correctness you might naively reward — and why does the difference matter for learning?
- A tutor's reward can carry the safety constraint inside it, so what the policy is paid for cannot override learner Well-Being. Think of a 'helpful' behavior a reward-optimizing tutor might exhibit that would actually be pedagogically harmful (e.g., giving away answers to inflate completion). Where would your safety line go?
- Reward optimization can preserve or destroy productive struggle, depending on design. From your experience, is 'student completes task' the same as 'student learns'? Where have you seen an AI optimized for the former while undermining the latter?

Introduction

How reinforcement learning works in AIED

Reinforcement learning (RL) trains an agent by rewarding desired behavior — the agent learns a policy that maximizes cumulative reward through trial and error. In AI in education, RL is used to train tutoring agents and learning companions whose decisions chain together over a session — which hint to give, when to advance difficulty, how to pace practice — rather than resolving one answer at a time. This makes RL well suited to Adaptive Learning and Intelligent Tutoring where long-horizon pedagogical decisions matter.

Applications documented in the knowledge base

- **Pedagogically aligned RL.** EduQwen uses an RL-SFT-RL pipeline to train a model that *guides* rather than answers, aligning reward with pedagogical goals; Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training applies RL to tutor design for Special Education.
- **RL beats supervised fine-tuning for pedagogical instruction following.** LearnLM's training found preference-based RL significantly more effective than SFT alone, because preference judgments capture context-dependent distinctions across long conversations that instruction-labeled supervised data only partly handles (LearnLM Team (2025)).
- **Safety and skill transfer.** Pedagogical Safety in Educational Reinforcement Learning integrates safety constraints into RL-based tutoring so that reward optimization does not come at the cost of learner well-being; AI Coaching for Accelerating Human Skill Development with Reinforcement Learning shows RL-driven coaching that supports genuine skill development and transfer.
- **What a reward leaves out shapes who benefits.** Tithi et al. (2026) found a deep-RL tutor rewarded on test score and time efficiency matched a BKT heuristic on posttest (A = .58 each, against 65.7) but assigned only 4% of training problems to constructive buggy-example repair and favored high Prior Knowledge students.
- **Simulation and practice.** Who Am I? History-Aware Profiles for Student Simulation in Tutoring Dialogues and Q-Learning Lab: Teaching Reinforcement Learning Through Learner-Generated Trace Analysis use RL and simulated learners to train and evaluate pedagogical agents, connecting RL to Learner Modeling and Adaptive Instruction and Learning Analytics.
- **Long-horizon, safety-weighted RL.** ResidencyRL (Liévin et al., 2026) optimizes whole 60-turn clinical encounters — well beyond the ≤12-turn horizons of concurrent dialogue systems — and training against adversarial simulated patients with a safety-aligned reward raised diagnostic accuracy 7.0% and cut missed red-flag rates by about a third.

Evidence across the field

A PRISMA-standard systematic review of RL in education (Riedmann, Schaper & Lugrin, 2025) synthesized 89 studies (2000–2024), finding a sharp post-2016 growth in Adaptive Learning and tutoring applications concentrated in STEM (especially Math Education). It reports that model-free RL dominated (n = 72) with Q-learning the most common algorithm, yet classical RL was more consistently effective than Deep RL (61% vs 36% of papers showing significant superiority). Adaptation split into content-scheduling (n = 53) and guidance-related (n = 36) mechanisms, with RL beating baselines more often on guidance, and learning gain — especially normalized learning gain — was the most effective reward source. The review also warns that over half of studies (n = 54) skipped statistical testing, so the field's growth has outpaced its methodological rigor.

Connection to the knowledge base

RL underpins much modern Agentic AI and Intelligent Tutoring design, where the agent must optimize long-term learning rather than a single correct response. It connects to LLM Training and Fine-Tuning (RL as a training method), Scaffolding (reward design that preserves productive struggle), and Self-Regulated Learning (agents that help learners regulate their own strategy). Because reward design encodes educational values, RL research in AIED is tightly tied to Pedagogical Safety and to the equity considerations of equitable tutor behavior.

Common Misconceptions

"Matching a baseline means the RL policy learned something worth having." It means the reward was satisfied. A tutor can draw level with a BKT heuristic on posttest (**A = .58 each**) while sending only **4% of training problems to constructive buggy-example repair** and preferring the cheaper interaction. The policy optimized what it was paid for, and what it was paid for excluded the productive activity.

"The reward function is a technical detail." It is the pedagogical specification. Whatever the reward weights is what the policy will do, so choosing between score, time efficiency, engagement and repair requires an explicit position on what learning is — a curriculum decision encoded as a number.

"Longer horizons are simply better." They enable what shorter horizons cannot, and they require the reward to be right across the whole sequence. ResidencyRL optimises whole **60-turn clinical encounters**, well beyond the ≤12-turn horizons of concurrent dialogue systems, which raises the cost of a mis-specified objective rather than lowering it.

"RL is the appropriate formalism for tutoring because teaching is sequential." Sequencing is necessary and not sufficient; the binding constraint is the reward's validity. A well-specified objective with a weak policy beats a strong policy against a wrong objective.

Connected Concepts

- Intelligent Tutoring
- Student Experience
- STEM Education
- Self-Regulated Learning
- Scaffolding
- Active Learning
- Edtech Platform
- Higher Education
- Learning Analytics
- Open Source
- Pedagogical Safety
- LLM Training and Fine-Tuning

- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Who Am I? History-Aware Profiles for Student Simulation in Tutoring Dialogues
- Q-Learning Lab: Teaching Reinforcement Learning Through Learner-Generated Trace Analysis
- Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning
- ResidencyRL: Reinforcement learning in simulated clinical environments
- LearnLM: Improving Gemini for learning — LearnLM: RLHF for pedagogical instruction following
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive ICAP scaffolding in an ITS (BKT vs DRL)
- Reinforcement Learning in Education: A Systematic Literature Review

Connected FAQs

- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?

Knowledge Graph

> **Knowledge graph** — a structured representation of concepts and their relationships used to model domain knowledge, student understanding, and learning dependencies in AI in education systems. Knowledge graphs enable AI systems to reason about what students know, what they need to learn next, and how concepts relate to each other.

Questions to Consider

- A knowledge graph captures not just concepts but their relationships — prerequisites, similarity, hierarchy. Why might knowing how concepts relate be more useful to an adaptive system than a flat list of skills?
- How are prerequisite relationships in a domain like yours? Can you think of a topic where students routinely struggle because they're missing a foundational concept the graph would reveal?
- The page describes using knowledge graphs to detect knowledge gaps — where learners are missing foundational concepts. How might surfacing that gap change what an AI tutor decides to teach next?
- Knowledge graphs can be built manually or automatically by LLMs from educational text. What are the risks of letting an AI construct the concept structure that a tutor will then reason over?
- If knowledge graphs provide the domain structure that AI agents reason over, what happens to trust and accuracy when the graph itself contains an error or a biased relationship?
- A knowledge graph is described as the structural backbone enabling fine-grained diagnosis and personalized paths. In your own teaching or design, what would you need a knowledge graph of your subject to capture — and what would it leave out?

Introduction

Knowledge graphs provide the structural backbone for many intelligent education systems. Unlike flat lists of skills or concepts, knowledge graphs capture prerequisite relationships, similarity, and hierarchical organization — essential for Adaptive Learning, Knowledge Tracing, and Learner Modeling and Adaptive Instruction.

How knowledge graphs are used in AIED

Knowledge graphs are a recurring structural mechanism across the knowledge base's AIED research, serving several distinct roles:

- **Knowledge Tracing models** use concept graphs to propagate student proficiency estimates across related skills, improving prediction accuracy when data is sparse.
- **Learner Modeling and Adaptive Instruction systems** leverage knowledge graphs to represent what learners know in a semantically meaningful way, enabling fine-grained diagnosis.

- **Adaptive Learning platforms** use prerequisite graphs to sequence content and recommend personalized learning paths.
- **Algorithm choice over the graph changes outcomes.** In G4L, propagating mastery through an Evolving Knowledge Space Graph with Bayesian knowledge propagation produced +24% measured knowledge (0.717 → 0.887), against +5% for Knowledge Space Theory and +1% for Weighted Distance Dependent Induction (Csépányi-Fürjes & Kovács, 2026).
- **Cognitive Diagnosis frameworks** like HiLLM-CD construct concept trees from educational text using LLMs, eliminating manual annotation.
- **Knowledge-graph-augmented tutoring:** ITAS uses a knowledge graph of quantum concepts (with explicit prerequisite relationships) to drive a multi-agent tutoring system, traversing the graph to select next topics for counterintuitive material.
- **Curriculum and course modeling:** CourseGraph compares CS course structures across institutions using graph representations; Learnity graphs model lifelong learning pathways.
- **Prerequisite-relation learning:** ProPrL learns prerequisite relations among concepts, formalizing the edges that knowledge graphs encode.
- **Knowledge-gap detection:** Knowledge gap detection uses graph-based reasoning in AI teaching assistants to identify where learners are missing foundational concepts.
- **Multimodal AI and explainable reasoning:** multimodal knowledge graphs extend graph structure across content modalities; fair and explainable recommendations combine knowledge-graph embeddings with sequential modeling (a hybrid HKG-GRU framework).
- **Instructionally structured graphs for resource recommendation:** Liu, Sun & Song (2026) decompose each teaching-resource entity into four instructional dimensions (teaching context, cognitive level, technological feature, cultural adaptability), compute user-dependent semantic similarity over those dimensions, and fuse it with collaborative filtering via an ability- and progress-aware coefficient — encoding pedagogical structure directly into the recommendation signal rather than treating resources as consumption items.
- **Ontology-based knowledge bases:** Ivanova (2026) proposes a layered, hybrid knowledge-base architecture grounded in description logic that replaces the classic ITS single-ontology models with **systems of mapped ontologies** — adding procedural (rule-based), probabilistic/fuzzy, and ML-extracted implicit knowledge — plus a metadata framework for describing, discovering, and reusing educational ontologies.
- **Scaffolding and writing:** Veriforge and visual query tracing apply graph-based structure to narrative drafting and declarative-logic learning.
- **Human-curated literary graphs, and what an audit exposes:** Incipit graphs literary premises — 1,455 axiom records, 1,464 mappings to 149 works, and 472 typed relationships — with language models proposing candidate formulations that human curators selected and grounded. Its recomputed audit is as instructive as its structure: every endpoint resolves and no duplicate or self-link remains, yet 1,448 of the 1,455 axioms map to exactly one work (so cross-work reuse is sparse), the context taxonomy cannot separate its two context types, and no provenance record survives, leaving the snapshot unable to reconstruct its own pipeline. Structural validity is not interpretive quality, and a curated graph without provenance can be neither audited nor refreshed.

LLM-driven knowledge graph construction

Recent research explores using LLMs to automatically construct knowledge graphs from educational content. The HiLLM-CD framework uses multi-agent LLM pipelines to generate exercise-concept links and hierarchical concept trees, reducing reliance on expert annotation. This connects to broader Generative AI applications in curriculum design and automated content organization, and to RAG (Retrieval-Augmented Generation) (retrieval-augmented generation), where graph-structured knowledge can improve retrieval quality over flat similarity search.

Relationship to other concepts

Knowledge graphs connect to Learning Design (defining what to teach), Curriculum Design (how to sequence it), and Learning Analytics (extracting insights from student interaction data). They are foundational to Intelligent Tutoring systems that need structured representations of educational domains. As AI agents become more common in education, knowledge graphs provide the domain structure that agentic systems reason over — a pattern seen in ITAS and knowledge-gap-detection teaching assistants.

Common Misconceptions

“A knowledge graph is a concept map with better tooling.” The distinguishing claim is relational and computational: a graph is useful because prerequisites, similarity and hierarchy are explicit enough for an algorithm to traverse, not because it draws connected nodes. What follows from that is the operational question the page keeps returning to — which traversal or propagation algorithm runs over the graph — because that choice is where the instructional effect actually lives.

“Having the graph is what improves outcomes.” The algorithm over the graph changes the outcome. In G4L, propagating mastery through an Evolving Knowledge Space Graph with Bayesian knowledge propagation produced **+24% measured knowledge** (0.717 → 0.887), against **+5%** for a Knowledge Space based comparison. Same general idea of a structured knowledge space, materially different result depending on the propagation method. Buying or building a graph is the beginning of the design problem, not its solution.

“An LLM-built graph that passes a structural audit is a validated graph.” Structural validity and instructional validity come apart in exactly this way. The recomputed audit of one such graph found that every endpoint resolves and no duplicate or self-link remains — a clean structure — yet 1,448 of its 1,455 axioms map to exactly one work, so cross-work reuse is sparse, its context taxonomy cannot separate its two context types, and central claims remain unproven. Dead links and duplicates are the failures an automated audit catches; thin reuse and undifferentiated categories are the ones it waves through.

Implications for Practice

For instructors

- Ask what the graph is used *for* before asking whether it is accurate: recommendation, prerequisite sequencing, or diagnosis. The evidence differs sharply by use, and prerequisite sequencing carries the strongest result.

- When a tool claims adaptive sequencing, ask for the measured comparison against a non-adaptive baseline rather than a description of the knowledge structure.
- Expect sparsity in cross-work reuse, and treat a graph whose entities map one-to-one onto single sources as a catalogue with edges rather than as an integrated map.

For developers

- Treat the propagation algorithm as a first-class design decision and report the algorithm as part of the intervention; the +24% versus +5% gap is attributable to it.
- Audit beyond resolvability. Test whether categories are separable and whether entities are reused across works, because structural cleanliness consistently coexists with instructional thinness.
- Validate the graph against learning outcomes, not against graph statistics.

For researchers

- Report graph-baseline contrasts at the algorithm level. “Knowledge-graph-based” is not a treatment; the traversal strategy is.
- Report axiom-to-source mappings and taxonomy separability alongside precision and recall, since the audit failures here were invisible to conventional graph metrics.

Connected Concepts

- Adaptive Learning
- Knowledge Tracing
- Intelligent Tutoring
- Cognitive Diagnosis
- Learner Modeling and Adaptive Instruction
- Learning Analytics
- Curriculum Design
- Learning Design
- Generative AI
- Large Language Models (LLMs)
- RAG (Retrieval-Augmented Generation)
- Agentic AI
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)
- Recommender Systems and Learning Paths

Connected Articles

- Literary Axioms: A Conceptual Framework for Literary Creation, Interpretation, and Evaluation — A curator-built graph of 1,455 literary axioms with a structural audit and no provenance record (Liu & Zhao 2026)

- Ontology-based layered hybrid AI-driven knowledge model for personalized e-learning — Ontology-based layered hybrid knowledge model for personalized e-learning
- Rethinking Higher Education: From Fixed Curricula to Learnity Graphs — Learnity graphs for lifelong learning
- VeriForge: Mitigating Latent Knowledge Gaps in Narrative Drafting via Mixed-Initiative Scaffolding — Veriforge: narrative-drafting scaffolds
- From Prototype to Classroom: An Intelligent Tutoring System for Quantum Education — Quantum education intelligent tutoring (ITAS)
- Evidence-Grounded Multimodal Knowledge Graph Construction for Multi-Lecture Educational Reasoning — Multimodal knowledge graphs for educational reasoning
- CourseGraph: Finding overlaps and differences in Computer Science courses across universities — CourseGraph: CS course comparison
- ProPRL: Property-Aware Prerequisite Relation Learning in Educational Knowledge Graphs — ProPrL: prerequisite-relation learning
- Detecting Knowledge Gaps from Conversational AI Interactions Using Curriculum Prerequisite Graphs — Knowledge-gap detection in AI teaching assistants
- Evaluating a Visual Query Tracer and Builder for Learning Declarative Logic Programming — Visual query tracer for declarative logic learning
- Fair and explainable educational recommendations with a hybrid Graph-GRU framework — Fair and explainable educational recommendations
- A Hybrid Collaborative Filtering and Knowledge Graph-Based Cross-Domain Recommendation Method for Multimodal Teaching Resources — Hybrid CF–KG cross-domain recommendation for multimodal teaching resources
- HiLLM-CD: LLM-Enhanced Hierarchical Cognitive Diagnosis — HiLLM-CD: LLM-driven cognitive diagnosis
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- CogEvol: Towards Efficient and Reliable Learning Environment Generation — CogEvol: Learning Environment Generation

Robots in Education

> **Robots in education (educational robotics)** — the use of physical or simulated robots as tools for teaching and learning. Educational robotics spans a wide spectrum: from programmable kits that teach computational thinking and programming, to socially assistive and humanoid robots that tutor, tell stories, model sign language, or rehearse social skills. It is valued for fostering problem solving, critical thinking, Creativity, and STEAM engagement, and for making abstract computing concepts tangible through embodied interaction. The knowledge base's robotics corpus spans curriculum-integrated programming, LLM-powered conversational tutors, socially assistive storytelling robots, and role-play for social-emotional learning. It is underpinned by two closely related areas absorbed here: **social robots** (robots designed for social interaction and relationship-building) and **human–robot interaction (HRI)** (the study of how people perceive, trust, and learn with robots).

Questions to Consider

- A robot in the classroom adds an embodied, social presence that a chatbot on a screen can't. What do you think the physical body and social cues of a robot change about how students learn, trust, and engage — and what might they distract from?
- Social robots use human-like speech, gestures, and personality to teach, tell stories, or rehearse social skills. Is a robot that looks and acts human inherently better for learning, or could that social presence bring risks (misinformation, over-reliance, privacy) that software-only tools don't?
- LLMs now let social robots converse fluently. If a robot can talk like a tutor, what still depends on its physical embodiment — and where does adding a 'body' really matter for learning versus just being a novelty?
- Think of a time you learned something by physically manipulating an object or watching your actions produce a visible result. How might programming a physical robot ground abstract ideas (like program logic) more effectively than writing code on a screen?

Introduction

Educational robotics is a distinct but closely related application of AI in education. Unlike software-only intelligent tutoring or Large Language Models (LLMs) chatbots, robots add an **embodied** and often **social** presence — a physical agent that learners can see, manipulate, and (increasingly) converse with. This embodiment is central to their pedagogical value: it grounds abstract program logic in observable behavior, and it can support relationship-building and emotional engagement that disembodied systems cannot.

The evidence is thinner than the volume of work suggests: a review of AI and robotics in education finds most empirical studies involve learners under 13 over four weeks or fewer, concentrated in a few early-investing countries, with learning performance the most-studied outcome and ethics, equity and policy lagging deployment (White and Wu (2026)).

Social robots and human–robot interaction

Two strands shape the social side of robotics in education.

Social robots are robots designed to engage people through social interaction, using human-like cues such as speech, gesture, facial expression, and personality to communicate, teach, assist, or accompany. In education, social robots (humanoids like iCub, Pepper, Reachy, and companion robots) are used for tutoring, storytelling, role-play, language support, and as study companions. Their social presence is the key differentiator from software-based AI agents, enabling relationship-building and emotional engagement. Advances in large language models have dramatically expanded what social robots can say and do, enabling fluent, adaptive conversational tutoring — while also introducing risks such as misinformation, over-reliance, and Privacy violations, motivating knowledge-based design approaches.

Human–robot interaction (HRI) is the interdisciplinary study of how people and robots interact, encompassing perception, communication, collaboration, and the social, cognitive, and ethical dynamics of that interaction. In education, HRI underlies how learners perceive, trust, and learn with robots — whether programming a robot, conversing with a tutoring robot, or rehearsing social scenarios. HRI research examines how robot appearance, behavior, task context, and embodiment shape user experience, trust, agency, and learning. Key concerns in educational HRI include preserving human Learner Agency, building Trust, supporting Self-Efficacy, and ensuring that interaction with robots supports rather than undermines autonomy and social learning. It connects robotics to Human AI Collaboration and Social-Emotional Learning.

How robots are used in education

Christ et al. (2026) add a role typology rather than a technology list: their five workshop-derived types of classroom robot differ by *pedagogical function and abstraction level*, not by hardware. Type a runs a non-interactive demonstration of generic social patterns (a scripted emotion theater followed by discussion of dynamics such as escalation or misunderstanding); type b is a touch-reactive interactive robot supporting participative physical theater, embodied learning, boundary awareness and emotion regulation; type c is a spoken-language partner that shows empathy and remembers interactions with a single pupil, creating a protected one-to-one setting for self-disclosure; type d is externally guided by a hidden specialist like a puppet with extra degrees of freedom, aimed at flattening social hierarchy; and type e is a non-interactive robot replaying actions recently observed in the school so pupils can reflect on situated behavior — the contrast with type a being exactly its context-specific rather than generalized abstraction. The typology is explicit about being an unvalidated design space grounded in one national mental-health program, so it is a menu for designing and evaluating robot roles, not evidence that any of them works.

- **Computational thinking and programming:** Programmable robots (e.g., LEGO, block-based platforms) help learners connect code to real outcomes. Valls i Pou links computational thinking to secondary STEAM curricula, and RoboBlockly Studio combines block programming with a conversational AI agent and embodied robot feedback. EduSim-LLM lets beginners control simulated robots with natural language.
- **Tutoring and knowledge delivery:** Knowledge-based design research and Teachy Mini develop LLM-powered generative social robots that tutor higher-education students, addressing risks like

misinformation and overreliance. Research on trust shows that what a robot does (task context) shapes learner trust more than its appearance, with the highest trust during instructional tasks.

- **Storytelling and engagement:** MotiBo and RoboBuddy use interactive, LLM-powered social robots for storytelling to boost motivation and engagement, while the iCub narrative HRI study explores co-creative storytelling between humans and humanoids.
- **Social-emotional learning and inclusion:** REMind uses robot-mediated role-play to rehearse anti-bullying bystander intervention, and work with the Pepper robot explores robot sign-language communication to support Deaf learners. A scoping review maps Pepper's use in formal education.
- **Autonomy and agency:** A systematic review synthesizes how HRI affects human autonomy and sense of agency, bridging design frameworks with regulatory demands (EU AI Act, IEEE Ethically Aligned Design). Social robots as study companions and robot–LLM integration in creative writing further explore robot roles.
- **Project-based and game-based approaches:** Bots and Blocks presents a project-based robotics course, and a systematic review compares game-based learning and gamification in robotics education.
- **Reinforcement learning and sim-to-real in a full robotics workflow.** Dong, Cao and Wang (2026) convert an end-to-end research robotics workflow — assembly, electrical checks, simulation-based policy training, and physical deployment — into a high-school course built on one open humanoid (a ToddlerBot, reported parts cost under USD 6,000) across eight three-hour sessions. Pairs share one robot and train a walking policy in Simulation before deploying it to hardware, with safety gates (a passed standing test before walking) making the dependency order visible. Because a shared artifact rewards the team rather than the individual, the framework separates robot performance from individual understanding: students rotate roles, each submits a separate prediction and explanation at every checkpoint, and supported stepping is explicitly not treated as evidence of conceptual mastery — the authors' warning that passing a robot milestone is not understanding it.
- **Competition robotics as an ecosystem problem, not a kit problem.** Jacobson et al. (2026) locate the binding constraint on K–12 robotics less in curriculum or hardware than in sustained local technical mentorship, and show it is distributed geographically: in Indiana, FIRST LEGO League participation collapsed in the 2020 remote season, urban participation gradually recovered, and rural participation did not, remaining near its post-2020 level through 2025–2026. Their ARC framework makes mentorship the engineered object — colleges run a credit-bearing course that prepares undergraduates as workshop mentors for nearby teams, and mature school programs become secondary hubs whose experienced students become peer mentors for further schools, so reach propagates beyond any university's catchment through a self-reinforcing loop. A one-university trial created three rural FLL teams and moved undergraduate community connection from 1.86 to 4.00 on a five-point scale (the largest of any measured shift, ahead of confidence teaching technical concepts at +1.29). A spatially explicit Markov simulation of Indiana's 1,925 public schools projected 992 school programs after 40 years under moderate assumptions against 161 with no ARC. The evidence is feasibility-level — seven mentors and four parents,

retrospective self-reports, no control group — but the framing is portable to any robotics program: what scales or fails to scale is mentorship capacity and hub geography, not the robot (Teaching AI, Robotics, & Community: A Hubs-Based K-12 Education Framework for Reaching Rural Schools).

- **Child development and young learners:** AI-enabled toys and child development shifts the lens to commercial AI toys in early childhood, examining how AI-enabled playthings affect child development and play. This extends educational robotics beyond classroom robots to the consumer toys children encounter at home, raising questions about agents in play, trust calibration, Learner Agency, and Well-Being for the youngest learners — an area where design guidance is thinner than for school-age robotics curricula.
- **Tangible coding and social robots in pre-K AI literacy.** Lee (2026) integrates unplugged play, tangible coding (Bee-Bot, Ozobot), and guided dialogue with a social AI robot in the Play With AI (PL-AI) curriculum for pre-K and kindergarten. The design-based research documents how these embodied, tangible robotics activities support children's emerging reasoning about AI concepts, with four design principles — embodied play, tangible coding, guided dialogue, and teacher co-design — offering a developmentally appropriate model for early childhood robotics and AI education.
- **Two paradigms for young learners: coding robots and generative social robots.** Yang, Li and Lee (2025) frame early-childhood robotics as the pairing of two pedagogical paradigms, each with a distinct theoretical base. **Coding robots** (Bee-Bot, KIBO, Matatalab) descend from Papert's LOGO and embody constructionism — children learn by making and build computational thinking through tangible programming. **Generative social robots**, powered by generative AI, are grounded in social constructivism, acting as conversational peers or tutors who scaffold learning within the child's Zone of Proximal Development and support social-emotional development. Their five-step **Creative Project Approach** for integrating both robot types into the Project Approach keeps teachers as facilitators who guide child–robot interaction, balance automation with Creativity, and preserve child Learner Agency.
- **What kindergarten CT robotics actually does.** A systematic review of 53 studies found problem-based learning, storytelling, and scaffolding the most frequently used strategies, with most studies naming no CT framework and using ad hoc assessment tools rather than a validated instrument such as TechCheck-K (Tsingidou & Sapounidis (2026)).
- **LLM planning rather than conversation.** Kudláčková (2026) uses a vision-language model to convert photographs of Shoebox Tasks — visually structured activities used with learners on the autism spectrum — into a PDDL problem that a Nao humanoid executes or demonstrates, with plan correctness scored across six tasks rather than any learner outcome.

Embodiment and pedagogy

A defining theme is that robots are effective when they support genuine learning goals — not as isolated technical exercises. A desk-mounted robotic projector tied with laptop ChatGPT while help was available (6.7 vs. 7.3/10, $p = .41$) but held its score after withdrawal (7.0 vs. 4.4/10, $p = .003$), a 60% higher short-term transfer score — a task-dependent gain the authors attribute to spatial co-location rather than general

replacement (Orlando et al. (2026)). The value of a robot depends on the pedagogical context: teaching computational thinking (Computational Thinking), supporting STEAM, building programming skills, motivating learners (Motivation, engagement), or supporting Social-Emotional Learning and inclusion. Robotics also connects to Project-Based Learning, Game-Based Learning, and Experiential Learning. Key design considerations include preserving learner Learner Agency, building Trust, supporting Self-Efficacy, and grounding learning in embodied interaction. In Language Learning, meta-analytic evidence points to the effectiveness of embodied robot-assisted language learning.

- **Pathways to learning AI-powered robotics.** A qualitative study of high school students in a robotics+AI curriculum found learning through real-world practice, designing, and playful creative expression (constructionist, epistemological-pluralist lens).

Common Misconceptions

- **"Robotics teaches computational thinking by virtue of being robots."** A systematic review of **53 studies** found **problem-based learning, storytelling and scaffolding** the most frequently used strategies — the pedagogy carried the outcome, and it is what the studies actually did.
- **"Physical robots beat screen-based alternatives across the board."** Gains were **task-dependent**: a short-term transfer score **60% higher** for Orlando et al., 2026 (4.4/10, p = .003) that the authors attribute to **spatial co-location rather than general replacement**. The claim is about co-location on specific tasks, not about physicality in general.
- **"Kindergarten CT is too early to be meaningful."** The reviewed evidence covers kindergarten robotics directly, which means the age band is studied rather than assumed unsuitable.

Connected Concepts

- Early Childhood Education — Early childhood and elementary AI education
- Computational Thinking
- CS Education
- STEM Education
- Embodied Learning
- Human AI Collaboration
- Project-Based Learning
- Game-Based Learning
- Large Language Models (LLMs)
- Motivation
- Student Engagement
- Social-Emotional Learning
- Learner Agency
- Trust
- Well-Being
- Ethics

- Privacy
- Language Learning
- K-12
- Higher Education
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)

Connected Articles

- Exploring the implementation of the Pepper social robot in formal education: A scoping review — Scoping Review of the Pepper Robot in Formal Education
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis — Meta-analysis of AI-enhanced embodied robot-assisted language learning
- Robotics and Artificial Intelligence in Education: Transformations, Challenges, and Future Directions — Robotics and AI in Education
- Computational thinking to enhance educational robotics in secondary school's curriculum — Computational Thinking and Educational Robotics
- RoboBlockly Studio: Conversational block programming with embodied robot feedback for computational thinking — RoboBlockly Studio
- EduSim-LLM: An educational platform integrating large language models and robotic simulation for beginners — EduSim-LLM
- Knowledge-based design requirements for generative social robots in higher education — Knowledge-Based Design for Generative Social Robots
- Teachy Mini: Development and preliminary evaluation of a knowledge-based generative social robot for higher education — Teachy Mini
- MotiBo: The impact of interactive digital storytelling robots on student motivation through self-determination theory — MotiBo
- RoboBuddy in the classroom: Exploring LLM-powered social robots for storytelling in learning and integration activities — RoboBuddy
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — REMind
- What robots do matters more than what they look like: Task context shapes trust in educational HRI — Task Context and Trust in Educational HRI
- Human autonomy and sense of agency in human-robot interaction: A systematic literature review — Human Autonomy and Agency in HRI
- Would you let a humanoid play storytelling with your child? A usability study on LLM-powered narrative human-robot interaction — iCub Narrative HRI
- Using the Pepper robot to support sign language communication — Pepper and Sign Language
- Co-Creating Buildable and Open Social Robot Study Companions with University Students — Social Robots as Study Companions

- Enhancing creative writing with robot-LLM integration: The interplay of embodiment, AI creativity and user engagement — Robot-LLM Integration in Creative Writing
- Game-based and gamified robotics education: A comparative systematic review and design guidelines — Game-Based and Gamified Robotics Education
- Bots and blocks: Presenting a project-based approach for robotics education — Bots and Blocks
- Pathways to Learning: Exploring High School Students' Learning of AI-Powered Educational Robotics — Pathways to Learning AI-Powered Educational Robotics (2026)
- Fostering computational thinking through robotics in kindergarten: A systematic review of learning strategies, frameworks, and assessment — Robot-mediated CT in kindergarten
- Artificial Intelligence in Toys: Implications for Child Development and Play — AI-enabled toys and child development
- Tailoring AI agents for early learning: The Creative Project Approach — The Creative Project Approach: integrating coding and generative social robots into early-childhood projects (Yang, Li & Lee 2025)
- Theoretical Perspectives on Teaching with Robots: From Interdisciplinary Prerequisites and Necessities in Today's Classrooms to Five Different Types of Robots — Five functionally distinct types of classroom robot, from scripted demonstration to one-to-one empathic dialogue (Christ et al. 2026)
- Teaching AI, Robotics, & Community: A Hubs-Based K-12 Education Framework for Reaching Rural Schools — ARC: a hubs-based framework that treats technical mentorship capacity and hub geography, not hardware, as the constraint on rural K–12 robotics programs (Jacobson et al. 2026)
- Teaching Reinforcement Learning and Humanoid Robotics to High-School Students: An Expert-Validated Curriculum Design on a Low-Cost Open Platform — Teaching Reinforcement Learning and Humanoid Robotics to High-School Students: An Expert-Validated Curriculum Design on a Low-Cost Open Platform
- AIfred: Augmented Learning through Functional Robotic Embodiment at the Desk — A desk-mounted robotic projector: co-located guidance preserved transfer where laptop ChatGPT lost it
- Visual Task Modeling and Automated Planning for Humanoid Robots in Education of Individuals with Autism Spectrum Disorder — A vision-language model plans Shoebox Tasks for a Nao robot (Kudláčková 2026)

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?

Conversational AI

> **Conversational AI (CAI) agents** — AI-driven speech- or text-based agents that simulate and automate conversations, from rule-based chatbots to NLP/ML and Multimodal AI LLM-based assistants — are among the most widely used AI interfaces in education, valued for teaching, psychological, and metacognitive support even as technical, cognitive, and ethical concerns persist.

Questions to Consider

- When you've used a chatbot or AI assistant, did you think of it as a teacher, a search engine, or something else? How did that framing shape how much you actually learned from it?
- Conversational AI describes HOW an agent talks, not what it's built to do. Could a chatbot be conversational yet completely unpedagogical — and what would tell you the difference?
- One study found that AI literacy — not general tech savvy — predicted whether students were willing and able to use a chatbot. Why might knowing how AI works matter more than being 'good with computers'?
- A raw general chatbot can short-circuit reasoning by answering immediately, while a structured tutor preserves productive struggle by withholding answers. What design choices decide which kind of agent a student meets?
- Students using a law-course chatbot did a third of their interactions after hours — evidence that 24/7 availability is a real benefit. But does always-on access also carry risks you'd want to design against?
- The biggest barrier to chatbot adoption in one study was a badly designed pop-up, not distrust or academic-integrity fears. What does that suggest about where AI-in-education investments actually fail?

Introduction

Conversational AI (CAI) is the umbrella term for AI-driven agents that carry on spoken or written dialogue, most commonly realized as chatbots and, more recently, generative Large Language Models (LLMs)-based assistants such as ChatGPT, Claude, and multimodal educational avatars. Modern CAI agents fall into Machine Learning-based, NLP-based, and hybrid categories, with text-based agents the most prevalent in education. As learning tools they function as intelligent tutors, Feedback providers, interaction partners, and administrative assistants — overlapping with pedagogical agents while spanning a broader set of applications.

How conversational AI appears in the knowledge base

An umbrella-review synthesis. The umbrella review of CAI agents (34 review articles) shows CAI utilization is concentrated in teaching and learning support (97.1% of reviews), psychological and motivational support (91.2%), and metacognitive and personal development (88.2%), while administrative

support, research management, and healthcare education lag. The review documents that human–AI relationship concerns persist across all CAI generations, with Academic Integrity and data Privacy emerging as newer ethical issues, and calls for HCI-grounded, evidence-based design and stronger AI Literacy support.

From chatbots to tutoring agents. The knowledge base traces CAI's evolution from rule-based FAQ chatbots toward tutoring-focused agents. The conversational AI tutors framework argues proven ITS technologies (Knowledge Tracing, affect detection, student modeling) should anchor generative tutors while Generative AI supplies flexible dialogue. Research on whether LLM tutors teach or solve and tutoring-specific vs general AI shows pedagogically designed Guardrails matter: raw general chatbots can short-circuit reasoning while structured tutors preserve productive struggle.

Benchmarks may overstate how much scaffolding gets taken up: across 9,490 chats in nine datasets, students in real deployments bypassed the chatbot's pedagogical framing at little interpersonal cost to drive the interaction toward their own goals — an instrumental Help-Seeking move rather than disengagement (Neagu et al. (2026)).

Interaction and collaboration. Conversational agents are increasingly framed as interaction partners rather than answer-givers. Student-AI Interaction captures how learners prompt, question, and verify with CAI in practice. In Collaborative Learning, agents mediate participation and shared AI Regulation in Education, and in Language Learning they provide real-time conversational practice. The Human AI Collaboration thread examines when this partnership preserves versus substitutes for the learner's cognitive work. LLMs as critique partners illustrate the preservation side concretely: Oppenheimer, Cash & Connell Pensky (2025) had ChatGPT, Gemini, or Claude critique students' argumentative essays across a semester, and learners improved on writing, prompt engineering, and response-to-feedback while rating the exchanges useful, engaging, and enjoyable — with active rebuttal of model claims (87.8%) showing they treated the conversational partner critically rather than passively.

Conversational agents are used to grade, and their evaluative behavior diverges from humans': ChatGPT was the most lenient of three evaluators of the same 52 undergraduate projects (M = 91.46 against 83.13 for the instructor) and shared no grading logic with peers (r = 0.05), though students valued its dialogic interactivity (Usher & Faraon (2026)). **Users read the agent's credibility socially.** Perceived competence of ChatGPT predicted its feedback credibility directly, while perceived warmth worked only through human-like empathy (SEM, 230 students), for Pérez-López et al. (2026) — a conversational agent earns credibility as a social partner, not just as an answer source.

Scaffolding the student's side of the conversation. Jin et al. (2026) add a question-specificity monitor and a revision template to a chat interface and intervene only on vague questions: in a between-subjects study with 40 college students learning web programming, HelpCoach users wrote significantly more specific first questions (57.3% vs. 40.5%) and retained more knowledge one week later (mean gain 1.9 vs. 0.3 of 6, d = 1.100). The retention benefit did not run through more targeted chatbot replies, which did not differ by condition — leaving the mechanism an open hypothesis rather than a demonstrated pathway.

The role the agent plays shapes the interaction. CAI design is not neutral about its persona: Liao (2026) found a fixed "student peer" companion in elementary book talk sustained longer interactions yet dominated the conversation (lower student word/sentence share) and hit an "affective ceiling" — matching a human teacher on factual recall but falling short on emotional and future-oriented reflection — arguing CAI should adapt its role (peer, teacher assistant, parent advisor) rather than stay monolithic. Xu et al. extend this to

small groups, showing generative AI acts as both an *agent* and a *collaborative space* in synchronous and asynchronous collaborative dynamics, where the interaction design decides whether it scaffolds or supplants group cognition. Tone can also be set by an external classifier rather than by the conversation alone: Sukoon (Bashir & Afzal, 2026) trains a Random Forest on 20 survey features to assign a low, moderate, or high stress level, and that output selects one of three response tiers inspired by the Stepped Care Model — warm and encouraging at low stress, grounding and non-judgmental at high stress — before an Open Source LLM (GLM-4.5-Air via OpenRouter) takes over the dialogue with the full conversation history and a culturally adapted system prompt re-sent on every turn. The authors chose a free-access multilingual model deliberately to keep deployment feasible in regional universities, and note that Urdu appears through prompt engineering rather than a genuinely bilingual pipeline — a limitation that matters whenever cultural appropriateness is claimed as a system property rather than an evaluated outcome.

Conversational behavior tracks the provider, not the tuning. Across 1,971 AI and 135 human transcripts scored on six fixed rules drawn from the learning sciences, models from the same provider clustered together with no overlap between family ranges, which the authors read as teaching behavior following provider-wide training practices rather than individual model tuning (Northcutt et al. (2026)).

Response consistency is an infrastructure problem, not a prompting one: within-model reply similarity ran 0.715–0.795 against 0.443–0.604 between models, and adding chat history changed reply content even for the same focal message (Hao (2026)). **Student perspectives.** Real-world usage shows adoption hinges on AI Literacy and user experience more than on technical capability. A human-centered mixed-methods study of the "Jordan Chatbot," a GPT-4o-based pedagogical agent in an Australian law course, found students hold positive attitudes and perceive gains in knowledge while strongly supporting Academic Integrity requirements; over a third of interactions occurred after hours, confirming the value of 24/7 availability (Colbran, Jha & Schiavone 2026). Notably, AI literacy — not general technology proficiency — predicted willingness and confidence to use the chatbot, and usability (an intrusive pop-up design) was the largest barrier among non-users, ahead of trust, preference for staff, and academic-integrity fears.(Understanding student perspectives on generative AI chatbots: a human-centred mixed-methods study in higher education) The study recommends human-centered design, explicit AI policies and assessment labels, staff and student training, and continuous error monitoring — evidence that effective CAI deployment is as much a design and literacy problem as a technical one. At the other end of the age spectrum, Vahedian Movahed & Martin (2025) studied children aged 6–14 interacting with AMA, a topic-bounded, age-tailored chatbot (astronomy, sneakers and shoes, dinosaurs), finding broad openness to and high trust in the AI as an information source — children even tested its credibility with known-answer questions — alongside gaps in critical engagement and digital-safety awareness that argue for age-sensitive, trust-aware conversational-ai design and explicit Privacy instruction.

Who uses the agent also varies: among 97 graduate statistics students, more than a quarter never used the StatBot chatbot, and female students used it significantly more often ($W = 679.5$, $p = .015$), which the authors read as conversational AI lowering the perceived social risk of asking questions (Lee and Wu (2026)).

Adoption is not homogeneous: clustering 192 student and educator responses yields four personas — Cautious Achievers, Skeptical Utilitarians, Disengaged Doubters and Engaged Enthusiasts — that average-effect acceptance models obscure, with students prioritizing immediate Feedback and educators content accuracy and Academic Integrity (Saihi & Ahmed (2026)). **Durability has been observed for one**

institutional deployment. A four-year randomized evaluation of a non-generative knowledge-base chatbot at California State University, Northridge (N = 8,708), found students remained receptive across eight semesters — annual opt-out rates never exceeded 4% — while impacts concentrated in time-sensitive administrative tasks such as early course registration (34 percentage points more likely to enroll by the deadline) and no statistically significant effects appeared on GPA, units, or persistence (Mata, Russell & Page 2026, a working paper). Its measurement lesson bears on how CAI engagement is counted: with opt-out near zero alongside roughly 5% active engagement on interactive campaigns, conclusions about sustained engagement depend on whether a study counts only direct replies or also passive engagement, where students act on information without texting back.

Risks and ethics. CAI agents carry persistent risks of over-reliance and cognitive offloading (the leading ethical concern in the umbrella review), plus technical limitations, hallucination, bias, plagiarism, and equity barriers. These concerns animate AI Literacy and Reducing AI Misuse and require policy and ethical-AI Governance responses. A further trust concern arises around the adoption advice staff increasingly receive: staff are urged to consult conversational AI about whether to adopt AI, yet such systems are built by organizations with a commercial stake in adoption. An audit of ten frontier LLMs found most acknowledge skeptical users' concerns before redirecting to engagement framings, raising questions about the neutrality of AI adoption advice.

Game-based conversational agents. Beyond tutoring, conversational agents are being embedded in digital game-based learning. Wenzel, Geiger, and Liening (2026) use action design research to derive the **CAIS-GBL** framework — four design principles and fifteen design features for AI conversational agents in digital game-based learning — grounded in theory-driven meta-requirements spanning cognitive, motivational, affective, and socio-cultural engagement and an equity-by-design stance. Their instantiated agent (Lara) in a business Simulation game was positively received for cognitive and social presence and support for self-regulated learning, evaluated with student teachers and in a field study — a practical blueprint for adaptive instructional support via conversational agents in serious games.

Relationship to pedagogical agents and intelligent tutoring

Conversational AI is best understood as an **interaction modality** that overlaps — but does not coincide with — two more established constructs in the knowledge base: pedagogical agents and intelligent tutoring systems (ITS).

Conversational AI as the medium, not the pedagogy. CAI names *how* the agent communicates (natural-language dialogue, spoken or text). It says little on its own about *what* the agent is built to do. Pedagogical agents, by contrast, are defined by their **instructional role** — an AI component that engages learners through dialogue, questions, or prompts to support metacognitive processes, Feedback, and Scaffolding. Intelligent tutoring systems are defined by their **architecture and modeling** — a diagnostic backbone of Knowledge Tracing, student modeling, and pedagogical decision logic that tracks what the learner knows and adapts instruction. A single agent can be all three at once: e.g. a conversational AI tutor is a CAI agent (dialogue interface) that functions as a pedagogical agent (tutoring strategies) built on an ITS foundation (student modeling). The distinction matters because a CAI agent need not be pedagogically grounded at all — a plain FAQ chatbot is conversational AI without being a pedagogical agent or a tutor.

The pedagogical-agent lens. Pedagogical agents use the conversational medium to enact teaching strategies — eliciting self-assessments, Socratic questioning, role-specialized facilitation in multi-agent designs (Teacher, Assistant, Classmate, Analyzer). Not every CAI agent is a pedagogical agent, but the two heavily overlap: the umbrella review of CAI agents found teaching and learning support (97.1%) and metacognitive development (88.2%) dominate CAI applications, meaning most education-focused CAI agents function pedagogically. The novice-programmer scoping review sharpens this: only 4 of 23 conversational agents explicitly grounded design in learning theory — most were pedagogical in intent but not in foundation.

The ITS lens. Intelligent tutoring contributes the *cognitive diagnostic machinery* that raw conversational models lack. The conversational AI tutors framework argues proven ITS technologies should anchor generative tutors: knowledge tracing, affect detection, and student modeling supply the structure, while Generative AI and LLMs supply flexible dialogue. This is the key design tension — conversational AI provides natural, scalable interaction, but without ITS-style structure it risks over-scaffolding, hallucination, or bypassing the learner's productive struggle. Research such as Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact and The Evidence Base on AI in K-12: A 2026 Review shows that pedagogy-oriented criteria (guiding questions, calibrated hints) must be designed in explicitly.

In short: conversational AI is the **interface/medium**, pedagogical agents are the **role**, and intelligent tutoring is the **underlying modeling and instructional logic**. Educationally valuable CAI agents sit at the intersection of all three — conversational in interface, pedagogical in intent, and tutor-like in their modeling of the learner.

Practical guidance

Choose conversational agents to support teaching, Motivation, and Metacognition rather than merely to answer questions, and design for HCI-grounded, participatory, user-centered interaction. Guard against over-reliance by pairing CAI with AI Literacy instruction and Feedback that keeps the learner cognitively productive. Attend to AI literacy and usability explicitly — since these — not general digital skill — drive adoption and non-use (Colbran, Jha & Schiavone 2026) — and pair deployment with clear AI-use policies, assessment labels, and training. Evaluate CAI on pedagogical outcomes — not just task completion — and plan for equity and Accessibility from the start rather than as an afterthought.

- **How students actually talk to conversational agents — a six-category disengagement scheme:** Rho et al. (2026) embedded a GPT-4-Turbo teachable agent (positioned as a struggling middle-school student, grounded with RAG over a knowledge graph, paired with a mentor agent that critiqued students' explanations) into Math Nation's Algebra and Geometry lessons, and coded 5,522 utterances from 246 students. Beyond engagement (75.7% of utterances), they identified False Answering (12.8%), Withholding (8.9%), Random/Noisy (2.1%), Mirroring (0.6%), Mocking (0.3%), and Ghosting (0.2%) — with Mirroring (copying the agent's text) emerging inductively from the data. The classification was human-in-the-loop: 1,682 utterances annotated by two raters (κ = 0.704–0.905 per category) trained a fine-tuned LLaMA 3 classifier (weighted F1 = 0.910 on held-out threads) that labeled the remaining 3,840 utterances. A process-level competing-risks analysis then showed most disengagement resolves within a few turns except Withholding, which persists — a signal worth designing agent responses around.

Common Misconceptions

- **“A conversational agent’s credibility tracks its accuracy.” Users read the agent’s credibility socially.** Perceived **competence** of ChatGPT predicted its feedback credibility **directly**, while perceived **warmth** worked only **through** that route. A warm, competent-sounding agent earns trust on presentation, which is a separate axis from correctness.
- **“LLM critique partners replace the learner’s judgement.”** Oppenheimer, Cash and Connell Pensky (2025) show the **preservation** side concretely: the value is in keeping the learner’s thinking intact rather than in producing the critique for them.
- **“The umbrella evidence on conversational agents is conclusive.”** The umbrella review synthesises reviews of CAI agents, and an umbrella review’s strength is bounded by the quality of the reviews it gathers.

Connected Concepts

- Intelligent Tutoring
- Pedagogical Agent
- Generative AI
- Large Language Models (LLMs)
- Student-AI Interaction
- AI Literacy
- Human AI Collaboration
- Cognitive Offloading
- Feedback
- Metacognition
- Self-Regulated Learning
- Language Learning
- Academic Integrity
- Hallucination Risk
- Equity
- Reducing AI Misuse
- Speech and Voice Technologies
- Parents and Families

Connected Articles

- Disengaged Conversational Behaviors and Learning in Student-AI Dialogues for Mathematical Problem Solving — Disengaged conversational behaviors in student-AI dialogues (Rho et al. 2026)

- Sustaining AI-enabled student support: A four-year implementation and impact study — Sustaining AI-enabled student support: four-year implementation and impact study of an institutional chatbot (Mata, Russell & Page 2026)
- Who grades best? Comparing ChatGPT, peer, and instructor evaluations across varying levels of student project quality — Comparing ChatGPT, peer, and instructor grading across project quality levels (Usher & Faraon 2026)
- Designing large language model-based agents with 5E framework for ESL learners' grammar acquisition — LLM agents with 5E framework for ESL grammar acquisition (Yang et al. 2026)
- Semantic variability of LLM-generated replies across LLMs: Implications for designing conversation-based assessment
- Understanding student perspectives on generative AI chatbots: a human-centred mixed-methods study in higher education — Student perspectives on GenAI chatbots (mixed methods)
- Uncovering adoption personas for generative AI in higher education: a clustering-based segmentation approach — Adoption personas for AI chatbots
- Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use — Umbrella review of conversational AI agents in education
- The Path to Conversational AI Tutors: Integrating Tutoring Best Practices and Targeted Technologies to Produce Scalable AI Agents — Conversational AI tutors framework
- Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact — Measuring whether LLM tutors teach or solve
- The Evidence Base on AI in K-12: A 2026 Review — Tutoring-specific vs general AI
- Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments — Rethinking scaffolding in LLM tutors
- Exploring conversational agents for novice programmers: a scoping review — Scoping review of conversational agents for novice programmers
- Artificial intelligence agents in computer-supported collaborative learning: a systematic literature review — AI agents in computer-supported collaborative learning review
- Differential engagement with generative artificial intelligence in higher education: Gender, motivation, and achievement trajectories — Gender and motivation in GenAI achievement
- Beyond a single role: Justifying a role-adaptive framework for AI companions through a comparative study in elementary book talk — Role-adaptive AI companion for elementary book talk; affective ceiling of fixed-role agents (Liao 2026)
- AI as an Agent and Collaborative Space: Exploring the role of generative AI in small group synchronous and asynchronous collaborative dynamics — GenAI as agent and collaborative space in small-group dynamics (Xu et al. 2026)
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners

- Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- HelpCoach: Scaffolding Targeted AI Help-Seeking During Problem-Solving — HelpCoach: Scaffolding Targeted AI Help-Seeking During Problem-Solving

Citation

Ganguly, A., Mehjabin, N., Malik, A., & Johri, A. (2025). *Conversational AI agents in education: an umbrella review*. *AI and Ethics*, 6, 72.

Simulation

> **Simulation** — the use of modeled environments, agents, or scenarios to support learning through practice and feedback in contexts that are safe, repeatable, and often otherwise inaccessible. Simulations let learners act, make errors, and see consequences without real-world cost, and are increasingly powered by AI and agent-based modeling.

Questions to Consider

- Recall a time you learned something by doing it in a safe, low-stakes environment — a lab, a mock exercise, a flight or game simulator. What made that practice effective, and what might be lost if the simulation were too realistic or not realistic enough?
- The page argues simulations let learners make errors and see consequences 'without real-world cost.' What do you think is gained, and what might be lost, when the cost of a mistake drops to nearly zero?
- If an AI can simulate patients, students, or conversation partners for practice, where would you draw the line between valuable rehearsal and practice that fails to transfer to real human interaction?
- Why might a learner's awareness of a simulation's limits — its trustworthiness — matter as much as how faithfully it models reality?
- How could the same simulation technology that helps someone learn also mislead them, and what would you need to know to tell those two outcomes apart?

Introduction

Simulation sits at the core of experiential and Active Learning pedagogies. It provides the deliberate practice, productive failure, and feedback loops that build skill and judgment. AI has transformed simulation in two ways: it powers more realistic and adaptive simulated environments, and it generates simulated learners, patients, or interlocutors that make practice scalable. Behavioral evidence shows that *how* learners engage with a simulation varies systematically rather than uniformly: tracing online learners building ecological models in VERA, An, Hammock & Goel (2025) classified engagement into Observation (frequent runs and parameter adjustment with little model building), Construction (hands-on building with little simulation), and Exploration (full construct–parameterize–simulate cycles), with Explorers producing the most complex and diverse models and observation-heavy learners largely copying existing ones — an argument for designing simulation environments that push learners toward full-cycle activity. - **An explicit mechanism is inspectable in a way a learned generator is not.** DagFlow-AI builds synthetic data from a directed acyclic graph plus per-variable distributions and formulas, so the data-generating process is a document an instructor can read and correct (Arthur et al., 2026). This is in deliberate contrast to GAN and VAE synthesis, which needs a seed dataset and yields an opaque process. The trade-off is that reaching a stable simulation took several iterations.

AI and simulation

- **AI-powered environments:** adaptive simulations adjust difficulty and scenarios to a learner's state, linking to Adaptive Learning and Reinforcement Learning-based coaching.
- **The virtual environment and the AI layer are separable gains.** In a three-week Grade 9 Ohm's law unit, adjusted achievement was 23.45 of 30 with an AI-supported virtual laboratory, 20.51 with the same laboratory without AI and 16.57 in a physical laboratory (Li and Ahmad (2026)). Intact classes were assigned with a different teacher each, so this describes three classroom arrangements, not the agent alone.
- **Prompt-generated simulations put a bespoke lab within reach.** Instructors can generate browser-run models of the topic a course needs from a reusable prompt template (sliders, animation, time-dependent graphs), validating each twice - technically, then against the known analytical solution - instead of accepting the closest published simulation (Ben-Zion et al., 2025).
- **Automating the human counterpart.** Chew et al. (2026) replace the specialist human role-players who staff air-traffic-control simulations with autonomous LLM sim-pilots, removing a training-capacity bottleneck; their fine-tuned speech pipeline cut word error rate on Singaporean-accented aviation speech from 107.80% to 23.45%, though all evaluations were component-level with no trainee cohort run.
- **Adversarial simulators as training partners.** ResidencyRL (Liévin et al., 2026) pairs a policy agent with LLM patient simulators built to behave adversarially across a 57K-case scenario pipeline; training against them cut missed red-flag rates by about a third, and blinded clinicians preferred the trained agent in 87.6% of side-by-side comparisons.
- **Encode missing case states explicitly.** A multi-agent standardized-patient system keeps intent recognition, case-grounded response generation and post-session evaluation separate, distinguishing four kinds of missing information — clinically negative, unknown to the patient, not yet assessed, and absent from the case — because collapsing them into "normal" injects unsupported clinical facts (Gao et al. (2026)).
- **Simulated agents:** AI can simulate patients (for medical training), students (for teacher practice), or conversation partners, making high-stakes interpersonal practice accessible and repeatable. In teacher education, Zhuang and Zhang (2025) built *Student GPT*, a custom ChatGPT chatbot that role-played a middle school student holding common ratio-reasoning Misconceptions about AI, giving preservice mathematics teachers affordable, content-specific practice at diagnosing student thinking — and used an Affective, Communicative, Technical (ACT) coding framework to systematically assess the simulated student's role-play strengths (clarity, relevance, error consistency) and authenticity weaknesses (teacher-like tone, role confusion).
- **Make counterfactual history a first-class feature.** SupplyNet's contextual multi-agent LLM agents generate supply-chain dynamics emergent from learner decisions rather than scripted, and its branching timeline lets learners revisit earlier choices without penalty — 13 of 14 participants rated it highly for connecting decisions to performance against 3 for the baseline (Li et al. (2026)).
- **Grounded dynamics, not a prompted persona.** Chen et al. (2026) parameterized a virtual patient's disclosure dynamics from nearly 2,000 hours of real psychotherapy transcripts, then

updated the level each turn; across 1,033 turns with 20 clinicians its disclosure rose with therapist empathy and exploration while a prompt-only baseline on the same LLM stayed flat.

- **Role-play puts the learner in the part.** Where simulated agents supply the counterpart, role-play gives the learner that part instead. Sanoubari and colleagues (2026) had 18 children aged 9-10 watch a bullying scene enacted by social robots, reason about each character's position, then rehearse defending by puppeteering a robotic avatar, and reported gains in perceived Self-Efficacy for defending plus better-calibrated beliefs about whether confronting a bully actually stops it. Their framing, robot-mediated applied drama, keeps a human facilitator in the Forum Theatre role and confines automation to narrative control, which is a useful reminder that the demanding part of role-play is the reflection rather than the machinery. Lock, Arteaga and Johnson (2025) place role-play alongside simulation among the strategies that AI-supported online learning draws on.
- **Simulated learners:** models of student behavior let researchers and designers test tutoring systems and curriculum before live deployment, grounding Learner Modeling and Adaptive Instruction and Knowledge Tracing.
- **Trust and fidelity:** the value of a simulation depends on how faithfully it models the real context — and on the learner's awareness of its limits, connecting to Trust Calibration.
- **Human-likeness is a property of the interaction, not the model.** Once both backends were rendered behind the same avatar, a text-based human-likeness advantage disappeared: participants called the commercial model natural (54% versus 22%) while communication performance was identical; voice, latency and turn-taking reshaped how the same dialogue quality was perceived (Hasan et al. (2026)).
- **GenAI in simulation-based learning.** Neto and colleagues (2026) systematically review GenAI across scenario-, case-, problem-, and simulation-based learning in healthcare education, finding positive outcomes for higher-order cognitive skills but inconsistent results elsewhere, with hybrid human-AI collaboration outperforming fully automated approaches. Wenzel, Geiger, and Liening (2026) develop AI conversational agents for adaptive support in business simulation games, addressing the common gap of limited formative feedback and structured reflection in simulation-based learning.
- **The "authenticity gap" bounds what AI simulation can replace.** In clinical simulation, Jiang et al. (2026)'s mixed-methods systematic review of AI-powered nursing simulation (19 studies, N=1,253) finds AI effective for cognitive knowledge and affective outcomes but inconsistent for complex psychomotor skills. They name an **authenticity gap**: a learner-perceived shortfall in emotional resonance, nonverbal cue recognition, and tactile/physical examination dimensions. That gap explains *why* AI simulation is best for highly structured objectives (foundational communication, history-taking) and should sit in a **stepped simulation continuum** that hands advanced psychomotor and emotionally complex scenarios to human-standardized patients and clinical placement. Technical instability (e.g., speech-recognition delays) can also add extraneous cognitive load and anxiety, so fidelity and stability are themselves design levers. This parallels Neto et al.'s finding that hybrid human–AI approaches outperform fully automated ones.
- **Teacher-AI co-designed simulations.** Interactive simulations that support both conceptual learning and competency development are scarce in hands-on domains, and GenAI output often

lacks pedagogical validity. In drone-based STEM education, teacher-AI co-designed simulations embedded in an otherwise identical hands-on curriculum were evaluated with a quasi-experimental pretest–posttest design across 30 secondary students, examining whether simulation-supported instruction yields superior learning outcomes (From simulation to flight: Simulation-assisted drone learning with teacher-AI co-designed scaffolds for secondary students' STEM knowledge and competencies). Separately, multi-agent tutoring benchmarks such as ASTRA use simulated socially intelligent agents to study participation-balanced collaboration in introductory programming (ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming).

- **Learner control in simulation is enacted, not granted.** A 2 × 2 experiment in a flocking simulation (Su, Nair and Nagashima 2026) gave some students parameter sliders, some an optional conversational agent and some both; every condition improved, but neither affordance produced a reliable difference once prior knowledge was controlled ($p = .849$ and $p = .108$). What predicted gains was where and how long learners manipulated parameters: sustained slider use in the most conceptually complex lesson was positively associated with gains, and the same behavior in the easier lesson negatively. For simulation builders the implication is that offering controls is not the intervention — helping learners decide what to change, and register what changed, is.
- **Agency is a designed layer, not a property of the technology.** Theelen et al. (2026) sort simulations by the practice represented, the simulated situation, how agency and adaptation are distributed, and how the learning is orchestrated, rather than by immersion level.
- **A digital twin is a simulation with a hardware bill, and the bill shapes who can take part.** A systematic review of 11 studies of digital twins in engineering and STEM higher education found that every implementation delivered a working prototype with real-time synchronization, yet only three reported statistically significant learning gains. Physical rigs capped access at 1–3 concurrent students in five studies, and reduced social interaction was the most-cited pedagogical challenge, in six (Pelayo-González et al. (2026)).
- **Agent-based simulation can model a Metacognition theory as a testable system.** An agent-based digital-twin-inspired framework combining the five-level AMERT model with a NetLogo simulation let researchers vary learner archetypes and task conditions and observe metacognitive trajectories, though the authors stress the output is hypothesis generation, not evidence about real learners (Guo, 2026). Simulation becomes a virtual laboratory for a theory that is otherwise hard to observe.
- **The curriculum is the unit that decides a simulation's value.** The Curricular Bridge Model argues that return on simulation depends on how experiences are sequenced across a program — context reuse, variation in reasoning demands, evidence feeding progression — rather than on platform fidelity (Herrera Alcaíno, 2026).

Connections

Simulation connects to Active Learning, Adaptive Learning, and Pedagogical Agent. It is a mechanism for experiential and Constructivism learning and is amplified by AI's ability to generate adaptive, realistic practice environments.

Simulation-based learning now includes synthetic patients, students and role-play partners, and AI Avatars and Synthetic Instructors argues that their consent, disclosure and person-fidelity questions are not the same as equipment or scenario fidelity.

What cannot be delegated

Most work on simulated conversation asks how faithfully an agent plays its part. Álvarez-Rubio (2026) asks the prior question: what a teacher cannot hand over at all across the simulation cycle of briefing, scenario, and debrief. The paper separates four delegation operations: execution, conveyance, facilitation, and the undertaking of a commitment. Execution and conveyance let the teacher correct a failure afterward; facilitation hands over judgment about an activity's structure. The fourth fails differently, because a commitment's essential condition is answerability as a relation to those who may demand reasons. An agent can perform a debriefing function; it cannot be the party who answers for it. On this account a chatbot that debriefs as well as a human never becomes answerable, so stronger debriefing evidence cannot move the line.

The framework travels as a test rather than a catalog. Three questions decide any function: what would pass to the agent, whether the teacher could correct a failure, and who could be asked to stand behind the agent's words. A function with no answer to the third is not a candidate. Applied to preparation, the test yields six verdicts — diagnosis and logistics delegable, stated objectives partly delegable, and the fiction contract, psychological safety, and assessment terms refused. In the debrief the paper sets out three stances an agent might hold, expert, character, and Maieutic, and reports the Maieutic failure mode: an agent built to teach by never answering left students frustrated. It is a design framework, not an outcome study. The authors state that no data were collected for research, and the deployment reported is a pilot read through the teacher's own observations.

Common Misconceptions

- **"Simulation is cheaper and therefore second-best."** Autonomous LLM sim-pilots **replace the specialist human role-players who staff air-traffic-control simulations, removing a training-capacity bottleneck** — the constraint was staffing, not fidelity. Where human role-players are scarce, the LLM simulation is not a substitute but the only available option.
- **"Simulators should behave like average cases."** ResidencyRL (Liévin et al., 2026) pairs a policy agent with **LLM patient simulators built to behave adversarially**. A simulator designed to be cooperative makes the learner's practice easier than the clinic, which is the opposite of what training needs.
- **"Scripted scenarios teach decision-making under uncertainty."** SupplyNet's contextual multi-agent agents generate **dynamics emergent from learner decisions rather than scripted** sequences. Scripted scenarios rehearse a known path; the emergent ones rehearse the decision.

Connected Concepts

- Active Learning
- Adaptive Learning

- Pedagogical Agent
- Reinforcement Learning
- Learner Modeling and Adaptive Instruction
- Constructivism
- Trust Calibration
- Workplace Learning
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)
- Virtual and Augmented Reality — the model, not the modality — immersive environments usually render a simulation
- AI Avatars and Synthetic Instructors

Connected Articles

- Exploring learner agency in an AI-supported simulation environment for complex systems education — Parameter control and an optional AI agent in a complex-systems simulation: gains tracked enactment, not access
- Leveraging AI for Rapid Generation of Physics Simulations in Education: Building Your Own Virtual Lab
- The Empirically Grounded Adaptive Virtual Patient for Psychotherapy Training: Disclosure That Responds to Therapist Micro-Skills — Adaptive Virtual Patients for Psychotherapy Training
- AI-Enabled Serious Games: Integrating Intelligence and Adaptivity in Training Systems — AI-Enabled Serious Games
- ANVIL: Analogies and Videos for Lecturers — ANVIL: Analogies and Videos for Lecturers
- ASTRA: A Scalable Next-Generation ATCO Training Simulator with Autonomous Simpilots — ASTRA: ATCO Training Simulator
- SupplyNet: Supporting Visual Exploratory Learning in Supply Chain via Contextual Multi-Agent Simulation — SupplyNet: Visual Exploratory Learning
- MedEasy: Designing AI Standardized Patients for Clinical Consultation Training — MedEASY: AI Standardized Patients
- Play-testing REMind: Evaluating an educational robot-mediated role-play game — Robot-mediated role-play game for bystander intervention (applied drama)
- ResidencyRL: Reinforcement learning in simulated clinical environments
- Generative AI in scenario-based healthcare education: A systematic review of applications, validation practices, and pedagogical integration — Systematic review of GenAI in scenario-based healthcare education (Neto et al. 2026)

- Designing Conversational Agents for Adaptive Instructional Support in Business Simulation Gaming — CAIS-GBL framework for AI conversational agents in business simulation games (Wenzel et al. 2026)
- Modelling individual participants as LLM agents in collaborative problem solving simulations — Fine-tuned participant-specific LLM agents reproducing collaborative problem solving dialogues (Fang 2026)
- ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming — ASTRA synthetic benchmark for multi-agent tutoring and participation-balanced collaboration
- From simulation to flight: Simulation-assisted drone learning with teacher-AI co-designed scaffolds for secondary students' STEM knowledge and competencies — Simulation-assisted drone learning with teacher-AI co-designed scaffolds
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- AI-Powered Simulation for Nursing Education: Mixed Methods Systematic Review — AI-powered simulation in nursing: mixed methods systematic review (authenticity gap, stepped continuum)
- Scalable AI-based clinical communication training and automated assessment — Scalable AI-based clinical communication training and automated assessment
- Digital Twins in STEM Education: A Systematic Review — Digital twins in STEM education: prototypes all worked, learning gains mostly did not
- AI-supported virtual laboratory for flipped physics learning: effects on middle school students' achievement, motivation, and cognitive load — AI-supported virtual laboratory for flipped physics learning: effects on middle school students' achievement, motivation, and cognitive load
- Classroom simulations for social-emotional learning and inclusive teacher education: a four-layer conceptual framework in the age of AI — Four-layer framework separating the practice represented, the simulated situation, agency and adaptation, and orchestration
- From technology adoption to curricular coherence: technology-enhanced simulation as a bridge in health professions education — From technology adoption to curricular coherence: technology-enhanced simulation as a bridge in health professions education
- What a teacher cannot delegate: a pedagogy-first framework for integrating conversational AI agents across the simulation cycle — What a teacher cannot delegate to a conversational agent across the simulation cycle

Virtual and Augmented Reality

> **Virtual and Augmented Reality (VR/AR)** — the display and interaction layer through which learning environments are experienced: fully synthetic spaces in VR, and digital content overlaid on the physical world in AR and mixed reality. AI enters this layer in two directions. It authors it, since generative AI now turns a natural-language description into a working browser-based AR or VR learning tool that no longer requires a specialist developer. And it inhabits it, as agents, pedagogical agents and retrieved knowledge guide a learner hands-free inside the immersive environment. What the modality adds over a screen is presence and embodiment; what it costs is fidelity, hardware, and a body's tolerance for being there.

Questions to Consider

- Where does the line fall between what is being modeled and the surface it is shown on? Compare a desktop patient simulator with a VR field trip to a site students cannot visit. Which differences would you expect to change learning, and which might only be novelty?
- A pilot found students reported *feeling* wavelength and amplitude through a hand gesture more strongly than through a slider — but it measured perception, not achievement, with 29 students and no comparison group. How much should reported "feeling" count toward adopting a tool?
- If generative AI lets an instructor with no programming background build a working AR simulation in an afternoon, what new responsibilities follow for validating the physics, judging fidelity, and deciding whether it belongs in a course?
- In a review of AI-powered nursing simulation, AI matched human actors for structured communication but not for tactile and emotionally complex scenarios. How would you sequence practice so learners rehearse some parts with AI and others with people?
- One classroom VR study reported minimal motion sickness while the meta-analytic estimate for intelligent VR with students with disabilities was not statistically significant. What would you want measured before a program invests in headsets?

Introduction

Virtual and augmented reality is a **modality**, not a model: it is the layer through which a learning environment reaches the learner. That makes it a different axis from Simulation, which is what gets modeled in the first place. The two are often conflated, because immersive environments are common delivery vehicles for simulations, but they vary independently — a desktop patient simulator is simulation without VR, and an AR overlay on a real instrument is VR without simulation. Keeping the axes apart matters for design: deciding to make practice risk-free is a different decision from deciding to make it embodied, and the two carry different costs, different failure modes, and different evidence. VR/AR is the **delivery layer** for a simulation and a close relative of game-based learning; it operationalizes embodied and situated accounts of learning, and it sits inside experiential and Active Learning practice.

AI now shapes this modality from both ends. It **authors** immersive content, because generative AI converts a structured natural-language prompt into a runnable AR or VR artifact, collapsing the specialist programming skill that used to gate production. And it **inhabits** the environment, as agents, pedagogical agents and retrieved domain knowledge supply guidance inside it — hands-free, in real time, grounded in sources the learner cannot consult while wearing a headset.

Shao, Tang and Ju (2026) test an AI-VR enhanced flipped classroom with young EFL learners and report gains in English achievement, metacognitive self-regulation and motivation, with technological literacy moderating how much learners gained from the immersive component.

What the modality adds

The case for VR/AR rests on presence and embodiment rather than on information delivery. A shared virtual space can also decouple co-presence from geography: a VR classroom built on a real-time synchronisation layer put teachers and students in the same room and manipulating the same 3D science materials regardless of site, targeting up to twenty participants. A one-hour session with 10 students on a Meta Quest 3 found strong usability scores on the System Usability Scale and little Simulation sickness, though UI consistency was its own weak point. Its designers deliberately avoided the earlier peer-to-peer architectures whose frame rate degraded as participants joined, a reminder that presence is bounded by engineering. More controlled comparisons are sobering about what the surface alone buys: a 24-participant study of engineering mechanics found that mixed-reality apps and physical toolkits raised engagement over classroom instruction, yet complex visualizations remained difficult for learners in every condition. Engagement is the reliable effect; understanding is not.

Generative AI as the authoring layer

The barrier that used to define who could build an immersive tool has largely fallen. Using a four-element prompt structure — **tools, display, hand controls, optimization** — a teacher or student with no coding background can generate a browser-based, hand-controlled AR physics simulation that runs as a single HTML file with nothing beyond a camera, then refine it by describing what went wrong in plain language. The gesture is familiar from touchscreens: pinch and spread tunes a physical quantity rather than zooming a picture, so opening the fingers vertically raises amplitude, and horizontally lengthens wavelength and shifts the lamp toward the red end of the spectrum. The same structure generalizes: the Coulomb field around a fingertip spread through the room, two hands as opposing charges, and the right-hand rule for magnetic force drawn on the learner's own hand — rendered deliberately **unmirrored**, since mirroring would invert the very rule being taught.

The pilot is encouraging and preliminary in equal measure. With 29 second-year medical-imaging students in an introductory radiation physics course, all 29 agreed the gesture helped them "feel" what wavelength is (mean 4.52), amplitude control scored highest (4.59), 93% found controlling the wave in the air natural, and 86% reported feeling more engaged and focused than in regular learning. The evidence, however, is perception-only, single-class, and without a comparison group — so the honest reading is that Prompt Engineering has removed the production barrier, which makes the underlying question about embodiment *testable*, not that it has been answered.

AI inside the immersive environment

The second direction is where AI stops authoring and starts teaching inside the headset, and it is where retrieval grounding becomes load-bearing. An agentic immersive training platform for high dose rate brachytherapy built a digital twin of the treatment suite — anatomically precise patient models, catheters, afterloaders, applicators — so trainees could see an applicator's spatial orientation relative to organs at risk, without a shielding room, a live radioactive source, or the privacy hazards of a physical pelvic exam. A knowledge-aware assistant grounded in clinical guidelines supplied hands-free guidance through a three-tier voice interface (headset microphone to backend transcription and intent analysis to spatialised speech), which removes controller dependency during intricate maneuvers. Technically it worked: 3–5 second end-to-end latency across 50 Monte Carlo runs, context recall above 0.93 and answer relevance 0.87 on 52 expert-authored question-answer pairs, with a medical embedding model improving answer completeness.

Its gaps define the current frontier of the pattern. Evaluation was objective metrics plus a single domain-expert user, not learners; there was no automated Assessment or adaptive feedback; and the assistant cannot exceed the documents it was given, so institution-specific protocols and rare scenarios sit outside its competence. In other words, the tutoring intelligence inside immersive environments is still mostly **guidance**, not measurement — and the same platform architecture, with model inference offloaded to a local GPU backend, is what makes hands-free guidance fast enough to be usable at all.

The clearest attempt to date at that missing measurement comes from a vocational design studio rather than a clinical setting. In a 12-week interior-design course, a VR environment (headsets plus a 3D modeling tool) with an LLM-backed assistant rendered as a digital human was compared against conventional project-based instruction. The assistant was assigned a distinct role per phase — resource recommendation and task decomposition, layered questioning with knowledge maps, simulated design effects and flaw detection, then discourse logging for the teacher (Jin et al., 2026). Across 63 valid responses the immersive-plus-agent condition produced significantly higher design ability ($\eta^2p = .138$) and creative ability ($\eta^2p = .111$), cognitive ($d = 0.90$) and behavioral ($d = 0.75$) engagement, and motivation ($d = 0.74$) and satisfaction ($d = 0.69$). Reported cognitive load was *lower*, not higher ($d = -0.52$), which the authors credit to the assistant cutting search and cross-disciplinary integration effort. Two limits keep this from settling the question: ideational novelty and affective engagement did not move, and every outcome is self-report, with no artifact ratings or headset logs.

The contrast with a comparable Design Education deployment is instructive. An architectural studio using a GenAI plus multi-user XR pipeline found *declining* design Self-Efficacy confidence for the teams that used it and no advantage in blinded panel ratings. The difference between the two is less the hardware than the orchestration: the vocational study fixed the phase structure, the assistant's role in each phase, and the evaluation rubric before the intervention, and measured productive ability separately from ideational novelty.

The instructor-facing version of the same pattern is younger and more fragile. Liang et al. (2026) let a stage-lighting instructor speak their intent into a VR scene with a laser pointer as the spatial anchor, and had an Large Language Models (LLMs) turn it into instructor-reviewable spatial annotations, executable lighting demonstrations and on-demand jargon explanations. Over 55 prompts and 531 generated actions, assistance was strongest on expressive, under-specified goals (212 of 245 visual-effect actions applied, 86.5%) and weakest on fixture-level requests, where 26 of the 28 rejected actions traced to directional references such as "left light" that the model resolved to the wrong fixture — grounding in the scene's spatial reference frame,

not executability, was the binding constraint. Instructors used suggestions as a controllable refinement process rather than an answer: 127 of the 147 rejected or modified actions (86.4%) were followed by a new prompt, and only one by manual adjustment. The study's most cautionary result is representational — annotations that externalized expert reasoning did not reliably align with what novices understood, so immersive AI instruction carries both the grounding problem of the tutoring cases above and a second one, that instructor competence and learner comprehension are not the same target.

What the evidence shows

The strongest evidence for VR/AR is comparative and discipline-specific. A meta-analysis of 33 experimental and quasi-experimental studies (N = 3,181) of emerging technologies in teaching English as a foreign language found a small-to-moderate overall effect (g = 0.38) and, within it, the **largest effects for VR/AR**, with gains rising by educational level and favoring productive skills (speaking, writing) over receptive ones.

The counter-evidence is just as informative. In the first meta-analysis of AI-based interventions for students with disabilities — 29 studies, 239 effect sizes, medium overall effect g = 0.588 — intelligent VR systems produced g = 0.528, **not statistically significant**, while computer software reached 0.959 and robots 0.509. Publication bias was present and trim-and-fill reduced the overall estimate to g = 0.269. The pattern is not that immersion fails, but that its effects are small, heterogeneous, and sensitive to how the particular intervention was designed and compared.

The clearest negative result in the knowledge base comes from a studio deployment rather than a comparison of modalities: in a 27-student architectural design studio, teams using a GenAI plus multi-user XR pipeline declined more in design Self-Efficacy confidence ($\beta = -1.675$) and outcome expectancy ($\beta = -2.088$) than teams working the normal course workflow, with no significant difference in expert panel ratings of their presentations (Xiao et al., 2026). The authors explain it as phase-dependent complementarity with real friction — GenAI for externalizing tentative ideas, XR for spatial and scale evaluation — alongside control, dimensional-fidelity, shared-attention and motion-comfort problems, a reminder that immersive tooling adds interaction costs as well as capability.

Fidelity, presence and the authenticity gap

Where immersive practice is used for interpersonal and procedural skill, the limiting factor is not visual fidelity but felt authenticity. A mixed-methods review of AI-powered nursing simulation (19 studies, N = 1,253) found AI effective for cognitive knowledge and affective outcomes but inconsistent for complex psychomotor skills, and named the reason: an **authenticity gap** covering emotional resonance, nonverbal cue recognition, and tactile and physical-examination dimensions. Its practical recommendation is a **stepped simulation continuum** — AI is well suited to highly structured objectives such as foundational communication and history taking, while advanced psychomotor and emotionally complex scenarios belong with human-standardized patients and clinical placement. Technical instability compounds the problem: speech-recognition delays inject extraneous cognitive load and anxiety, which makes stability and latency design levers rather than implementation details.

Avatars and digital humans are the human face of that layer, and AI Avatars and Synthetic Instructors gathers the cases where realism failed to predict effectiveness: SOPHIE scored communication identically behind the same avatar across backends, and TriKoNet's students rejected photorealistic personas outright.

The same logic explains why presence is not automatically good. Motion sickness, UI inconsistency, hardware cost, and uneven device access decide who can use an immersive environment at all, which is why the modality's equity questions connect to Accessibility and Inclusive Learning rather than sitting apart from them.

Common Misconceptions

- **"Feeling the phenomenon means understanding it."** A pilot found students reported **feeling** wavelength and amplitude through a hand gesture more strongly than through a slider — but **it measured perception, not achievement**. The felt sense is the affordance, and whether it produced understanding is a separate test.
- **"High usability scores validate an educational VR tool."** In a **one-hour session with 10 students** on a Meta Quest 3, the study reported **good usability on the System Usability Scale and minimal simulation sickness**. Usability and comfort are prerequisites and neither is a learning measure.
- **"Students' agreement is evidence of the affordance."** With **29 second-year medical-imaging students**, all 29 **agreed the gesture helped them "feel" what wavelength is (mean 4.52)**. Unanimous agreement on a feeling is self-report about experience, and the affordance claim needs an outcome that does not depend on the student's judgment of their own understanding.

Connected Concepts

- Simulation — what immersive environments usually display; the model, not the modality
- Embodied Learning — the mechanism the modality is supposed to exploit
- Multimodal AI — gesture, voice and spatial input as learning channels
- Situated Learning
- Experiential Learning
- Game-Based Learning
- Workplace Learning — the setting where immersive practice is most established
- Generative AI — the new authoring layer
- Prompt Engineering — how non-programmers build and refine immersive tools
- Agentic AI
- Pedagogical Agent
- RAG (Retrieval-Augmented Generation) — grounding guidance inside the headset
- Intelligent Tutoring
- Visualization
- Medical and Health Professions Education
- Accessibility

- Inclusive Learning
- Trust Calibration — fidelity, and the learner's awareness of its limits
- Cognitive Offloading — latency and instability as extraneous load
- Edtech Platform — synchronisation, latency and multi-site presence
- Arts, Design and Media Education
- AI Avatars and Synthetic Instructors

Connected Articles

- From prompt to embodied simulation: Using generative AI to create AR physics learning tools — four-element prompt generating hand-controlled AR physics simulations; 29-student pilot, perception-only evidence
- Visualizing Engineering Fundamentals: Design of Mixed Reality and Physical Toolkits for Effective Learning — mixed-reality apps vs physical toolkits vs classroom in engineering mechanics; engagement up, complex visualization still hard
- MedGame: Storytelling Gamification Empowered by Large Language Models for Medical Education — gamified medical training with AI
- Technology-Enhanced Tabletop Exercises for Cybersecurity Education: Lessons Learned — augmented tabletop scenarios in cybersecurity education
- Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study — Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — AI-IVE-PBL: immersive VR design studio with an LLM-backed teaching assistant, evaluated against traditional PBL (Jin et al. 2026)
- LumiNote: LLM-Assisted Multimodal Instruction for VR Stage Lighting Education — LumiNote: LLM-assisted multimodal instruction in VR stage lighting education, and where grounding broke down (Liang et al. 2026)

Learner modeling and adaptive systems

Learner Modeling and Adaptive Instruction

> **Learner modeling and adaptive instruction** — the umbrella for how AI represents learners (what they know, feel, and need) and how it uses those representations to adapt teaching. The family spans the *modeling* layer — **student modeling**, Knowledge Tracing, Cognitive Diagnosis, and simulating students — and the *adaptive systems* that consume those models — Intelligent Tutoring, Adaptive Learning, and Personalized Learning. The shared question: *how does a system know what a learner knows, and what should it teach next?*

Questions to Consider

- The umbrella question this page poses is: how does a system know what a learner knows, and what should it teach next? Before you read on, how would you even begin to represent 'what a learner knows' in a machine?
- Learner modeling spans knowledge-tracing (tracking knowledge over time), cognitive diagnosis (mapping mastered skills), and simulating students (synthetic learners). What do you think each approach is good at — and what does each risk getting wrong?
- Every adaptive AI depends on some model of the learner. If a model is only as good as the evidence feeding it, what evidence do you think AI systems actually have about a student, and what important things about them remain invisible?
- A model might capture what a student gets right and wrong but not why, or not how they feel. How could a learner model mislead an adaptive system in ways that harm rather than help the student?
- If you were designing an adaptive tutor, what would you want its model of you to include — and what would you want it explicitly forbidden from assuming?

Introduction

Learner modeling is the computational representation of learners; adaptive instruction is what systems do with that representation. Every adaptive AI in education depends on some model of the learner — even a lightweight one — and every learner model exists to inform some instructional decision. This page is the umbrella for that pipeline: the modeling methods, the systems that act on models, and how they relate.

The modeling layer

These concepts answer "what does this learner know, feel, and need?" — the representation side of the family.

- **student modeling** — the broad practice of representing learner characteristics (knowledge, skills, affective states, engagement, preferences) in computational form. It is the umbrella term within this layer, encompassing all ways of representing a learner.

- **Knowledge Tracing** — the specific practice of modeling cognitive knowledge *over time* by tracking performance on exercises and predicting future mastery. It formalizes the temporal dynamics of learning — when knowledge is gained, decays, and how concepts relate.
- **Cognitive Diagnosis** — fine-grained Assessment of which specific skills or knowledge components a learner has mastered, producing a mastery profile that supports targeted remediation.
- **simulating students** — generating *synthetic* learners on demand, rather than representing a real one, so Pedagogies and Teaching Strategies and AI systems can be tested or trained offline.
- **A causal formalism for learner models.** Mangili et al. (2026) replace noisy-gate Bayesian networks with structural causal models elicited from experts, making hints explicit endogenous variables so the model can ask what a student would have answered without the help they used — slightly less predictive, but capable of counterfactuals associative models cannot express.

The study of Zhang, Jeffries & Koprinska (2025) illustrates that faithful representation does not require the most complex model family: a lightweight, intrinsically interpretable decision-tree student model — built from course content-interaction features rather than rich telemetry — predicts module-level progress in large-scale online programming courses (85–91% accuracy) and separates disengaged at-risk, disengaged-but-successful, and engaged high-performer engagement profiles, supporting Learning Analytics early-warning at scale.

A predictive learner model can rest on the structure of enrollment rather than trace data: TRACE encodes each semester as an unordered basket of courses and predicts the course set and grades together, cutting grade-prediction error to 0.1339 MAE — 46.4% below a grades-only model — across 5,326 students and ten years (Savala (2026)).

Student models can also be built purely from behavioral traces and still support adaptation. An, Hammock & Goel (2025) derived three engagement profiles — Observation, Construction, and Exploration — from the clickstreams of 315 online learners building 822 ecological models in VERA, without any demographic or contextual data, and showed these profiles predict model quality (Exploration yields the most complex and diverse models, while Observation is dominated by copied rather than original models). Such engagement-level characterizations are the coarse-grained student models that the adaptive-instruction layer can consume to target feedback.

Affective student modeling is a further dimension: a math tutor inferred emotion from conversational text and facial expression and mapped the aggregated state to tutoring strategies, but the Multimodal AI fusion reached only 60% accuracy against participants' own annotations, making the affect read the pipeline's weakest link (Kar et al. (2025)).

Gutterman et al. (2026) found a delayed-start signal recorded during math practice predicted English outcomes, with chronic delayers (over 13 minutes) showing lower gains (ELA β = -.11 SD) even after controlling for prior knowledge and time-on-task — so behavioral student models can transfer across subjects without per-course retraining, though their cut-points must be re-derived.

The adaptive-instruction layer

These concepts answer "what should be taught next?" — the application side that consumes learner models.

- **Intelligent Tutoring** — systems that use student models and mastery estimates to select problems and provide step-level guidance, the classic application of learner modeling.
- **Adaptive Learning** — systems that adjust content, pacing, or difficulty in response to the learner model.
- **Personalized Learning** — the broader tailoring of instruction, content, and pathways to individual learner characteristics and preferences.

How the members relate

The concepts form a pipeline rather than competitors: **student modeling** is the umbrella representation; Knowledge Tracing and Cognitive Diagnosis are specific modeling methods that populate it; simulation *generates* learners rather than representing real ones; and Intelligent Tutoring, Adaptive Learning, and Personalized Learning are the systems that consume these models to adapt instruction.

Student modeling vs. simulating students is the key distinction to keep straight. Student modeling is about **representing a real learner** — building a model *from* an actual student's data so an adaptive system can act on that individual. Simulating students, by contrast, **generates a synthetic learner** on demand to stand in for real learners so pedagogy and AI can be evaluated or trained offline. The two are closely related rather than interchangeable: simulated students typically *embed* a student model (an epistemic state, misconception set, or engagement profile) and draw on the same constructs that Knowledge Tracing and Cognitive Diagnosis formalize. Their purposes diverge — student modeling serves live adaptation by informing decisions about a real person, whereas Simulation fabricates learners to test systems (and increasingly to audit AI, e.g., López-Pernas et al. (2026)) rather than to act on any real individual.

Knowledge tracing vs. student modeling is the other common confusion. Knowledge tracing specifically models cognitive knowledge over time; student modeling is the broader practice covering all aspects of a learner (affective state, engagement, preferences). Knowledge tracing is a *type of* student modeling focused on the cognitive-temporal dimension. Knowledge-tracing constructs also inform simulated students — a simulated learner's cognitive state is often formalized with the same mastery/decay dynamics that knowledge tracing models, so simulation is a way to *generate* the knowledge states that tracing methods normally *infer* from real response data.

Anchoring tracing to the curriculum strengthens the model. Pradeesh et al. (2026) show that a learner model gains fidelity when tracing is tied to explicit curriculum structure rather than learned purely from data: their Outcome-Based Knowledge Tracing (OKT) treats course outcomes in Outcome-Based Education as the knowledge concepts to trace, supplies concept relationships through expert-validated OBE "affinity mappings" between course and program outcomes (an explicit alternative to implicit attention or graph message passing), and uses a memory-augmented module to model how one outcome's attainment impacts others. On live engineering-program data it beat DKT, DKVMN, EKT, and SimpleKT baselines (89.81% AUC), illustrating that the modeling layer can exploit the curriculum's own structure to represent learners more faithfully.

Intelligent tutoring vs. adaptive/personalized learning sits on the application side: intelligent tutoring is the problem-selecting, step-guidance system; adaptive learning tunes content and pacing; personalized learning is the broadest tailoring of the whole learning experience. All three are the "consumers" of the modeling layer.

The shared validity challenge

Across the whole family, the defining validity challenge is the same: the learner representation must **faithfully reflect a learner's true state** rather than the system's default assumptions. For **student modeling** and Knowledge Tracing, this means the model must genuinely capture what a learner knows (evaluation and measurement validity). For simulation, it means the synthetic learner must exhibit realistic imperfection rather than the model's full competence or sycophantic agreement. Adaptive systems that consume faulty models inherit and propagate that error.

Models that infer learner state from gameplay reached AUCs of 0.848–0.913, yet only two of the 55 reviewed studies audited them for demographic bias and just one examined differential outcomes by learner ability (Kaşarcı and Yurt (2026)).

Some intended signals may not be recoverable from dialogue at all: the Learning Context framework's pilot recovered misconceptions at 91.4% and anxiety at 100% but conscientiousness at only 68.6% and language proficiency at 60%, so a context-aware model should capture slow-to-surface traits rather than wait for dialogue to expose them (Liu et al. (2026)).

Physiological and gaze signals widen the modeling base: eye tracking, EEG, electrodermal activity and heart rate are now used to infer engagement, attention and cognitive load (Sensor and Gaze Analytics). The inference from signal to mental state is the weak link, since a body can be recorded without its state being identified.

Lin et al. (2026) expose a circularity in how such synthetic learners are validated: their EduMirror agents administer psychometric questionnaires post-hoc and read agreement with the agent's internal value representation as psychological validity, but because the Surveyor measures dimensions already encoded in that value system the check is a consistency check rather than independent validation.

Correctness is not always a faithful signal. An, McLaren, and Stamper (2026) show that a learner model inferring mastery from correct actions can misrepresent a learner's true state: learners who exhibit *deceptive overgeneralization* appear mastered yet omit a critical application constraint, so adaptive systems can stop practice prematurely. Learner models should assess conditional understanding — including whether the learner knows when to withhold an action — not only action correctness.

Hidden misconceptions show the same failure from the other side: Imran and Bulathwela (2026) found a fine-tuned classifier caught 57.4% of correct answers reached through flawed reasoning, and at a 1.6% prevalence even an 83.6%-accurate reasoning model left 8 false alarms per detection — so correctness-based mastery signals are both incomplete and expensive to repair.

How a model is validated is itself a validity question. Schuetze, Yan, and Carvalho (2025) show that popular learner models (BKT, BKT-with-Forgetting, AFM) appear to capture human learning only when fit retroactively to a full multi-session dataset; under time-based (walk-forward) cross-validation — predicting a future session from earlier ones, how such models are actually deployed — they overestimate performance,

miss the spacing effect, and mis-order practice conditions. Because forgetting-augmented and forgetting-free models performed about equally across sessions, the authors conclude that forgetting is often absorbed into learner parameters rather than genuinely represented. The lesson for the family is that a faithful learner representation must be validated the way it is used — and that conflating in-the-moment performance with long-term retention produces models that look accurate yet misrepresent learners. Zamanifard, Goudarzi and Robb (2026) show the same failure from the classifier's side: inferring learning-style dimensions from 153 undergraduates' Problem Solving dialogues looked moderate on accuracy until per-class recall exposed dominant-label prediction, with Intuitive and Global learners systematically under-identified and few-shot examples sometimes amplifying the majority-class bias.

LLM-era modeling

Recent advances use LLMs for richer modeling. The HiLLM-CD framework represents students as proficiency trees; multimodal approaches construct evidence-grounded knowledge representations from diverse data sources; LLMs now simulate students with reasoning. LLMs enable automated model construction from educational text and higher-fidelity student simulation, reducing reliance on expert annotation — while sharpening the fidelity concerns above. Learner-model signals also *ground* LLM reasoning: Reddig, Arora & MacLellan (2025) found that feeding GPT-4 a student's Bayesian Knowledge Tracing skill estimate along with the tutor's interface structure sharply improved its error diagnosis (logical-error identification rising from 40% to 81% on factoring; ~87.8% overall), while multi-step problems and responses containing several errors remained the weakest cases — evidence that coupling a formal learner model to an LLM strengthens, but does not guarantee, sound inference about a real student. CoLearn (He et al., 2026) shows what a persistent version of that coupling looks like: mastery and mined misconceptions are stored per (learner, subject) rather than as per-session logs, so evidence accumulates across sessions, and the memory is written by an LLM-graded observation function while staying inspectable to the learner through mastery bars and a label naming what each generated question was chosen to probe. Its controls make the writing step explicit — with the memory read but no longer updated, the share of items aimed at a genuinely weak skill fell from 0.72 to 0.57 — and it keeps this page's qualification intact: the stored mastery is the agent's belief about the learner, not a measurement of their knowledge.

Language can replace ID embeddings as the representation: PLCD builds LLM-derived concept schemas and exercise process graphs as priors, reaching 83.51% accuracy on XES3G5M, with largest gains in cold start — 4.60 ACC points over KCD for new concepts and 4.00 for new exercises — where ID-based models have no history (Liu et al. (2026)).

Simulator quality separates into two axes: a pool-then-specialize pipeline that trains shared behavioral patterns before a per-student adapter reached behavioral fidelity 0.51 and guidance responsiveness 0.91 in chess, against 0.23 and 0.72 for a frontier role-play baseline, showing a simulator must both match a student and be steerable (Yang et al. (2026)).

Risk scores can be accurate yet unsupported: Gheisari and Salarian (2026) reached 99% accuracy predicting withdrawal from enrollment and performance records, but on a single institution's 1,027 cleaned records with no external validation, no intervention tested, and fairness audits named as future work — the score supports triage, not a verdict about a student.

A learner model that only predicts risk is not enough for decision support: coupling a calibrated at-risk model with integer-programming recourse over discrete actions — validated against timing, budget, immutability and availability constraints — produced compact intervention plans where optimization alone accepted unenactable ones (Le, Abel & Laforge (2026)).

A black-box estimator can also be distilled into a small self-explaining model: a two-stage pipeline turns a fitted estimator and its post-hoc interpretation into a 2B-parameter "mentee" that returns an estimate alongside a narration, audited for faithfulness rather than for fluency (Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics).

Connections to other concepts

Learner modeling and adaptive instruction feed into Learning Analytics (dashboards and interventions), Formative Assessment (analytics-driven assessment), and Feedback (what the system tells the learner). It connects to AI in Education as a core strand of AI for education.

Common Misconceptions

- **"A faithful model needs the most complex method."** Zhang, Jeffries and Koprinska (2025) illustrate that **faithful representation does not require the most complex** approach. Complexity is not a proxy for fidelity, and a simpler model that captures the relevant structure can be the better instrument.
- **"Learner models need trace data."** A predictive learner model can rest on **the structure of enrollment** rather than trace data: TRACE encodes each semester as an **unordered basket of courses** and predicts from that. The predictive signal can live in the institution's administrative record.
- **"Affective state requires physiological sensing."** A math tutor **inferred emotion from conversational text and facial expression** and mapped the aggregated state to tutoring decisions. The affect signal was recoverable from what learners were already producing.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Explainable AI
- Learning Analytics
- Knowledge Tracing
- Knowledge Graph
- Adaptive Learning
- Intelligent Tutoring
- Personalized Learning
- Formative Assessment
- K-12
- Affective Tutoring

- Large Language Models (LLMs)
- Higher Education
- AI in Education
- Simulating Students
- Cognitive Diagnosis
- Feedback
- Recommender Systems and Learning Paths
- Student Support and Success — the models beneath risk prediction and support targeting
- Sensor and Gaze Analytics

Connected Articles

- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)
- Causal modelling of support interventions for student competency assessment — Causal Modeling of Support Interventions for Student Competency Assessment
- AI Tutoring is Not a Monolith: What We Actually Know — AI Tutoring is Not a Monolith: What We Actually Know (Stanford SCALE/NSSA brief)
- Learning context: A unified framework and roadmap for context-aware AI in education
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most — LLM tutors over-reject valid-alternative, over-validate incorrect (Yasir et al. 2026)
- HAIML: A human-centered AI metacognitive learning model — A framework for human agency and reflective learning in the age of artificial intelligence
- Analysis and Prediction of At-Risk Students Using Machine Learning Algorithms
- The Correct Answer Trap: Pedagogically-Grounded Detection and Feedback for Hidden Misconceptions
- Cross-Subject Predictive Validity for Learning Outcomes of Delayed Start Behavior
- EduMirror: Modeling Educational Social Dynamics with Value-driven Multi-agent Simulation
- MathBuddy: Affective Math Tutoring
- Evidence-Grounded Multimodal Knowledge Graph Construction for Multi-Lecture Educational Reasoning
- HiLLM-CD: LLM-Enhanced Hierarchical Cognitive Diagnosis
- INSIDE the student’s mind: Jointly modeling latent reasoning and action in LLM student simulators
- Jointly predicting courses and grades using a transformer-based model
- From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support — From Student Risk Prediction to SC2R: Counterfactual Recourse

- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — Distilling self-explaining LM for learning analytics
- StudentSim: Training LLM-based Student Simulators — StudentSim: Training LLM-based Student Simulators
- Predicting Student Attrition in Competitive Programming: A Large-Scale Study Integrating Survey Insights and Global Behavioral Logs — Predicting Student Attrition in Competitive Programming
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education
- Beyond ID Embeddings: Process-Grounded Language Modeling for Cognitive Diagnosis — Beyond ID Embeddings: Process-Grounded Language Modeling for Cognitive Diagnosis
- Personalized Exercise Recommendation with Semantically-Grounded Knowledge Tracing — compact learner state plus a calibrated tracer as a recommender environment
- CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop — CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop
- Effectiveness of AI-Supported Game-Based Learning: A Systematic Review of Outcomes, Challenges, and Future Directions — Stealth assessment reached AUCs of 0.848–0.913, but bias audits were near-absent across 55 studies
- Bias and Reliability in Learning-Style Inference from Student–AI Dialogues: An Evaluation of GPT-4o and Gemini 2.0 Flash — Dialogue-based learning-style inference fails on balanced metrics (Zamanifard, Goudarzi & Robb 2026)

Connected FAQs

- How Do We Make a Simulated Student Behave Like a Real Learner?

Knowledge Tracing

> **Knowledge tracing** — modeling what learners know over time by tracking their performance on exercises and predicting future mastery. It is the knowledge base's richest modeling thread, spanning Bayesian, deep learning, and LLM-enhanced approaches to tracking student knowledge as it evolves.

Questions to Consider

- Knowledge tracing models what you know over time from your performance on exercises, tracking when knowledge is gained and when it decays. What can your answers reveal about whether you truly 'know' something versus just got it right this time?
- The page warns that 'mastery is not correctness' — a learner can appear mastered yet systematically misapply a skill when a hidden condition is violated. When have you seen someone (or yourself) look like they understood something but actually hadn't?
- If knowledge tracing feeds adaptive systems that decide what to teach next, what goes wrong when the model mistakes correct answers for true mastery and moves a student on too early?
- Knowledge tracing comes in many forms — Bayesian, neural, hypergraph, dialogue-based, LLM-enhanced. What trade-offs would you expect between a transparent model you can explain and a powerful but opaque one?
- The page connects knowledge tracing to simulated students — generating the knowledge states tracing normally infers from real data. How might simulating learners help test a tutor before it meets real students?
- Since knowledge decays over time, what should an adaptive system do with a student's past 'mastery' once they've forgotten? How would you design for forgetting rather than assuming knowledge persists?

Introduction

Knowledge tracing transforms raw exercise responses into estimates of what a student has mastered and what they still need to learn. Unlike simple correctness tracking, knowledge tracing models the temporal dynamics of learning — when knowledge is gained, when it decays, and how concepts relate to each other.

Approaches represented in the knowledge base

- **Bayesian approaches:** StanBKT: Rethinking Parameter Estimation in Bayesian Knowledge Tracing standardizes BKT implementations, while MBP-KT: Learning Global Collaborative Information from Meta-Behavioral Pattern for Enhanced Knowledge Tracing incorporates meta-behavioral signals
- **Soft-evidence BKT with an LLM observation function:** CoLearn (He et al., 2026) keeps the BKT structure but replaces the binary correct/incorrect observation — standard BKT's input —

with a continuous one: an Large Language Models (LLMs) grader emits graded mastery evidence plus a confidence weight, blended into a confidence-shrunk posterior and gated so that a clearly wrong answer cannot raise the estimate, which makes the update a variant that generalizes standard BKT rather than a strict reduction of it. Whether that observation function is trustworthy depends on the learner: mean evidence separated ability tiers cleanly (0.25 weak / 0.67 mixed / 0.77 strong) while within-tier correlation with true mastery was only r ≈ 0.15 / 0.48 / 0.41, leaving the traced state an agent's belief about the learner rather than a calibrated measurement.

- **Neural and hybrid models:** Neural-Symbolic Knowledge Tracing: Injecting Educational Knowledge into Deep Learning for Responsible Learner Modelling combines symbolic reasoning with neural networks; Explainable Knowledge Tracing via Probabilistic Embeddings and Pattern-based Reasoning advances interpretable probabilistic models
- **Hypergraph memory networks:** THyMeN augments memory-based tracing (DKVMN) with temporal hypergraph reasoning, modeling dynamic higher-order interactions among concepts that co-occur within multi-skill questions
- **Dialogue-based KT:** Interpretable Knowledge Tracing adapts knowledge tracing for conversational tutoring
- **LLM-enhanced:** HiLLM-CD uses LLMs for automated concept tree construction and hierarchical proficiency inference
- **Semantic, recommendation-oriented KT:** ExRec (Ozyurt, Almaci, Feuerriegel and Sachan, 2025) grounds the *input* rather than the architecture. An LLM annotates each question with solution steps and knowledge concepts aligned to the Common Core State Standards for Mathematics. Contrastive learning aligns question, solution-step and concept embeddings (with false negatives removed by pre-clustering concept variants such as "interpreting a bar chart" and "reading information from a bar graph"). A KC-calibration loss then lets the tracer predict a concept-level knowledge state directly instead of inferring one by running the model over every question in that concept. The calibrated tracer then serves as the Reinforcement Learning environment for exercise recommendation, where a model-based value estimation initialises the critic from the tracer itself. Across four tasks on XES3G5M averaged over 2,048 test students, non-RL baselines gave marginal or negative knowledge gains, value-based continuous methods beat policy-based ones, and the model-based value estimate improved them consistently — most sharply on the weakest-concept task, where the target changes at every step. Reported gains are percentage-of-maximum knowledge improvement, not learning outcomes, and the pipeline depends on generated solution steps whose quality the tracer inherits.
- **Outcome-based knowledge tracing (OKT):** Pradeesh et al. (2026) trace student knowledge within Outcome-Based Education systems by treating **course outcomes as the knowledge concepts themselves**, and substitute expert-validated OBE "affinity mappings" between course and program outcomes for attention- or graph-derived concept relations. A Memory Augmented Neural Network (MANN) models how each outcome's attainment impacts others, and domain-adaptive BERT fine-tuning enriches the outcome embeddings (with a GRU backbone beating LSTM). Against a live engineering-program LMS corpus of 2,416 students and 966 outcomes,

OKT posted 89.81% AUC, ahead of DKT, DKVMN, EKT and SimpleKT, while on ASSISTments that edge vanished, confirming the advantage is tied to OBE-specific curriculum structure.

- **A single recency scalar captures most of what a sequence model buys.** Across 1,927,265 mathematics responses from 8,996 Finnish students, item identity by itself hit AUC .8362; one recency measure relative to item difficulty lifted that to .8669, recovering 93.5% of a query-conditioned transformer's .8690 gain, while a 128-dimensional summary of history reached only .8687 (Lahtinen & McMullen (2026)).
- **Snapshot-only tracing.** Nagai et al. (2026) induce a pseudo-temporal order from inclusion relations among learners' skill sets, treating expanding skill sets as learning progression so single-time-point snapshots remain traceable — but the formulation assumes skills are never lost, so deployments for learners who regress need an explicit forgetting mechanism first.

Relationship to other concepts

Knowledge tracing is closely related to Learner Modeling and Adaptive Instruction — while knowledge tracing specifically models cognitive knowledge over time, student modeling is the broader practice of representing all aspects of a learner (affective state, engagement, preferences). Knowledge tracing feeds into Adaptive Learning and Personalized Learning systems that need to know what to teach next, and into Intelligent Tutoring platforms that use mastery estimates to select appropriate problems. It connects to Learning Analytics for dashboard and intervention design, and to Cognitive Diagnosis for fine-grained skill Assessment. Knowledge-tracing constructs also inform simulated students — a simulated learner's cognitive state is often formalized with the same mastery/decay dynamics that knowledge tracing models, so Simulation is a way to *generate* the knowledge states that tracing methods normally *infer* from real response data.

A scope caveat: tracing estimates domain mastery, not higher-order cognition. A 15-year review of 127 intelligent tutoring studies finds Bayesian and deep-learning tracing improved over the period yet still unable to model higher-order cognitive processes, Metacognition, or motivation — the states an adaptive system would most need to target (Zerkouk et al. (2025)).

A caveat: mastery is not correctness. An, McLaren, and Stamper (2026) show that BKT's two-state (learned/unlearned) assumption can be violated by *deceptive overgeneralization* — learners can appear mastered yet systematically misapply a skill when a hidden application constraint is violated. This argues for tracing conditional understanding (knowing *when to withhold* an action), not only action correctness, when mastery estimates drive adaptive stopping rules.

A related caveat concerns *how* tracing models are validated versus deployed. Schuetze, Yan, and Carvalho (2025) fit BKT, BKT-with-Forgetting, and the Additive Factors Model to a multi-session successive-relearning dataset and found they reproduce learning trends when fit retroactively to all sessions (acceptable AUC ≈ 0.74–0.79); but under **time-based cross-validation** — training on one session to predict the next, the realistic applied setting — all three overestimate future performance by roughly 47–58%, fail to capture the spacing effect, and can even predict the wrong ordinal ordering across practice conditions. Tellingly, models *without* an explicit forgetting mechanism performed about as well as the forgetting-augmented versions as sessions accumulated, suggesting forgetting was partly absorbed into other parameters (e.g., per-student intercepts in AFM) rather than genuinely modeled. The authors tie this to the

learning-versus-performance distinction: popular models conflate high in-the-moment performance with high likelihood of long-term retention. The practical implication is that a tracer that looks good on retrospective fit can mislead the adaptive systems consuming its mastery estimates, arguing for walk-forward evaluation and models that account for retention interval, spacing, and between-session forgetting.

A further caveat concerns the evidence rule that feeds the update. Srivastava (2026) ran four update rules over identical ASSISTments 2012–13 event sequences, differing only in how they score rows completed with help, on a confirmatory half of 12,716 students and 985,813 scored events. Reading a hinted or retried row as a failed first attempt predicted later unaided performance best (pooled AUC 0.658); crediting any completion predicted it worst (0.604), barely above a constant that knows only skill difficulty (0.595). The same choice governs the mastery count: crediting completions declared 93.9% of 113,428 student–skill pairs mastered against 72.8% under the strict rule, and the pairs the lenient rule declared ahead of strict went on to 70.9% unaided accuracy against 85.7% where the two agreed, below the 0.744 base rate. A traced state is therefore partly a function of the scoring convention rather than of the learner alone, so a mastery estimate consumed by an adaptive gate should carry the rule that produced it.

A capability caveat: general language models trace knowledge barely above a trivial baseline. Worden et al. (2026) released FoundationalASSIST, which restores the full question text, the responses students actually gave and their distractor choices that earlier tracing datasets discarded, and tested four frontier LLMs as zero-shot tracers. The best, GPT-OSS-120B, reached 56.2 percent against the 51.3 percent an always-predict-correct rule already scores (AUC-ROC 0.559), with no improvement from longer histories, and Llama-3.3-70B proved right 85.4 percent of the time a student answered correctly but only 12.6 percent when they erred — evidence that an off-the-shelf model traces optimism rather than understanding, so a tracer's apparent skill must be read against the trivial baseline its task permits. - **A single-pass LLM can trace knowledge before any learners are logged.** Queried as one typed question with no target-platform data, Jev reached a mean AUC of .706, above the best of 28 deep tracing models trained on 8 learners (.689) and ahead until supervised tracing catches up at 64-128 learners (Lee & Park, 2026).

Common Misconceptions

"A mastery label means the learner knows it." Mastery is not correctness — a learner can appear mastered and systematically misapply a skill whenever a hidden condition is violated — and the label's value depends on the counting rule behind it. Crediting declared completions marked **93.9% of 113,428 student–skill pairs** mastered against **72.8%** under a strict rule, and the pairs the lenient rule called ahead reached only **70.9% unaided accuracy**. Two defensible rules produced a 21-point difference in who was declared ready.

"Sequence models are what makes tracing accurate." Much of the apparent gain is cheaper than that. On 1,927,265 mathematics responses from 8,996 Finnish students, item identity alone reached **AUC .8362**, and adding a single recency measure relative to item difficulty raised it to **.866**. A large share of what deep sequence models buy is available from an item-difficulty baseline plus recency, so architecture comparisons need that baseline to be meaningful.

"The best model on one dataset is the best model for your course." Accuracy is setting-specific. OKT reached **89.81% AUC** on live engineering-program LMS data (2,416 students, 966 outcomes), beating DKT, DKVMN, EKT and SimpleKT — while giving only competitive results on ASSISTments. The same

architecture that wins on one dataset family is unremarkable on another, so a headline AUC from elsewhere is weak evidence about your students.

“Knowledge persists unless there is evidence of forgetting.” Forgetting is the default worth modeling. Schuetze, Yan and Carvalho (2025) fit BKT, BKT-with-Forgetting and the Additive Factors Model across a multi-session sequence and found that model fit changes when retention is represented, and that how these models are *validated* differs from how they are *deployed*.

Implications for Practice

For instructors

- Treat a mastery label as a claim with a provenance, not a fact. Crediting declared completions marked **93.9% of 113,428 student–skill pairs** mastered, against **72.8%** under a strict rule — and the pairs the lenient rule called ahead went on to **70.9% unaided accuracy** against the stricter set. The rule you chose is visible in the number you see.
- Prefer a model validated on a setting like yours. OKT reached **89.81% AUC** on live engineering-program LMS data (2,416 students, 966 outcomes), outperforming DKT, DKVMN, EKT and SimpleKT — while giving only competitive results on ASSISTments. The advantage is setting-specific, so cross-context accuracy claims should not be your validation.
- Remember mastery is not correctness: a learner can appear mastered while systematically misapplying a skill whenever a hidden condition is violated.

For developers

- Do not pay for sequence-model complexity without a baseline. On 1,927,265 mathematics responses from 8,996 Finnish students, item identity alone reached **AUC .8362**, and adding a single recency measure relative to item difficulty raised it to **.866** — a large share of what sequence models buy for a fraction of the machinery.
- Model forgetting explicitly rather than assuming knowledge persists; the BKT-with-forgetting comparisons show fit changes when retention is in the model.
- Report the deployment rule alongside the model. Validation-vs-deployment mismatch in the forgetting studies is a reporting failure as much as a modeling one.

For researchers

- Report results on more than one dataset family before claiming architectural superiority, since the OKT contrast reverses between engineering LMS data and ASSISTments.
- Report the mastery-count rule as a parameter of the result, not as a methodological footnote.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Learner Modeling and Adaptive Instruction
- Knowledge Graph
- Adaptive Learning
- Personalized Learning

- Intelligent Tutoring
- Learning Analytics
- Formative Assessment
- AI in Education
- AI Ed Evaluation
- Multimodal AI
- Teaching
- Cognitive Offloading
- Large Language Models (LLMs)
- Simulating Students
- Recommender Systems and Learning Paths
- Student Support and Success — fine-grained mastery estimation feeding support decisions

Connected Articles

- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)
- Interpretable Knowledge Tracing
- Augmenting knowledge tracing through modeling dynamic higher-order concept interactions: A temporal hypergraph memory network
- Estimating Learners' Skill Acquisition Without Temporal Information
- HiLLM-CD: LLM-Enhanced Hierarchical Cognitive Diagnosis
- Comprehensive Review of Intelligent Tutoring Systems
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models
- Personalized Exercise Recommendation with Semantically-Grounded Knowledge Tracing — semantically grounded tracing with KC-calibrated states, used as an RL environment for recommendation
- CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop — CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop
- Crediting assisted work inflates mastery: a preregistered comparison of evidence rules in intelligent tutoring logs — Which evidence rule decides a mastery claim (Srivastava 2026)
- Can a System-One LLM Perform Knowledge Tracing When Few or No Learners Are Logged? — A single-pass LLM traces knowledge above deep models trained on 8 learners, at a fraction of the cost (Lee & Park 2026)

- Compressing student history in mathematics knowledge tracing — Compressing student history in mathematics knowledge tracing

Connected FAQs

- How Do We Make a Simulated Student Behave Like a Real Learner?

Cognitive Diagnosis

> **Cognitive diagnosis** — the inference of a learner's latent knowledge state — the specific concepts, skills, and misconceptions they have or lack — from their responses or behavior. It is the assessment-side counterpart to Knowledge Tracing, focused on characterizing *what* a student knows rather than only predicting their next performance.

Questions to Consider

- Cognitive diagnosis infers a learner's latent knowledge state — the specific concepts, skills, and misconceptions they have or lack — from their responses, rather than just predicting their next score. Before reading, what's the difference you'd expect between 'predicting a student's grade' and 'diagnosing what they actually don't understand'?
- A key idea is the 'correct answer trap' — where a right answer conceals flawed reasoning. Have you ever been confident a student understood something because they got it right, only to discover a misconception underneath? How could a diagnosis surface that where a score couldn't?
- The page distinguishes cognitive diagnosis (a static, fine-grained snapshot of what a learner currently holds) from knowledge tracing (the temporal dynamics of mastery over time). Why would an intelligent tutor need both — to know what's wrong and to know what to teach next?
- A design principle here is to separate diagnosis from feedback: LLM tutors confirm correct steps but over-reject valid reasoning and over-validate errors, and accurate diagnosis does not reliably yield actionable feedback. Why might knowing what's wrong still fail to produce a helpful next step?
- LLM-era diagnosis extends from multiple-choice to open-ended, handwritten, and conversational work. What might go wrong if an AI diagnoses a misconception from work it can't fully understand — and how would you verify that the diagnosis itself is trustworthy?

Introduction

Whereas knowledge tracing typically estimates a scalar mastery over time, cognitive diagnosis produces a more granular profile: which knowledge components are mastered, which are fragile, and which misconceptions are present. This profile is the substrate for Personalized Learning, Intelligent Tutoring, and Adaptive Learning.

How cognitive diagnosis works

- **Diagnostic models:** psychometric models (often under Item Response Theory and Educational Measurement) infer latent skill states from patterns of correct and incorrect responses, sometimes via cognitive-diagnosis models that map items to multiple knowledge components.
- **Automated model search:** because no single diagnostic model fits every learner, AutoML-driven approaches (e.g., personalized neural cognitive architecture search) generate diagnostic models for

heterogeneous learner profiles — integrating multi-modal educational data to enable dynamic analysis of learning processes and per-learner cognitive diagnosis, rather than relying on static examination outcomes and simple statistical indicators (Personalized neural cognitive architecture search).

- **Response data:** diagnosis draws on responses to assessments, hints, Help-Seeking, and time-on-task — richer signals than raw scores.
- **LLM-based diagnosis:** newer approaches use large language models to diagnose from open-ended or handwritten work, and to identify the specific Misconceptions about AI behind an error (e.g., the "correct answer trap" where a right answer conceals flawed reasoning). Two 2026 results bound how far that diagnosis reaches. OmniEdu (Liang et al., 2026) supervised diagnostic reasoning as one of four capabilities in an open 4B/9B/27B family, and knowledge-state diagnosis remained its weakest measured capability — 54.04% at 27B and 53.55% at 9B, near enough that three times the parameters did not close the gap — while CoLearn (He et al., 2026)'s LLM grader correlated with true mastery at $r = 0.68$ over pooled answers but only $r \approx 0.15$ within the weakest ability tier ($r \approx 0.48$ mixed, 0.41 strong), so diagnostic reliability tracks the learner's ability level as much as the model's.
- **Diagnosing common mistakes at cohort scale, not one response at a time.** Killich et al. (2026) reverse the usual direction: rather than diagnosing one learner's error, an Large Language Models (LLMs) proposes candidate bug-fixing transformations that map incorrect formalizations onto correct ones across an entire educational data set, and every candidate is validated algorithmically before it is kept. On 6,106 pairs of correct and incorrect propositional-logic formalizations the workflow discovered 248 clusters of transformations explaining 5,156 pairs (84.44%), against 4,370 (71.57%) for the hand-picked mistakes of the previous state of the art, and it recovered the mistakes a domain expert had identified by hand in the literature. Clustering orders candidates into single-transformation, equivalent-transformation and hierarchical groups, and the resulting correlation graph can be visualized for instructors; the same pipeline transferred to modal logic and regular expressions, where one disjunction-for-conjunction transformation alone covered 98.80% of its 334-pair cluster. It is a route to the misconception inventory a diagnostic model needs before it can be fit.
- **Correct-solution recovery, not error simulation, is the bottleneck.** Models constructed a solution in 95.2% of distractor traces and simulated a specific Eedi misconception at 0.92 accuracy, yet supplying the correct answer still raised match with human distractors ($0.52 \rightarrow 0.56$) — the failure sits upstream, in recovering the solution (Zengaffinen et al. (2026)).
- **Outcome-level diagnosis in OBE curricula:** Pradeesh et al. (2026) diagnose which course outcomes a learner has attained in Outcome-Based Education by treating outcomes as the knowledge concepts, supplying concept relationships via expert-validated OBE affinity mappings between course and program outcomes (an explicit alternative to implicitly learned attention or graph relations), and using a memory-augmented module to estimate how one outcome's attainment impacts others — outperforming DKT, DKVMN, EKT, and SimpleKT baselines (89.81% AUC) on live engineering-program data.

- **Diagnosing from instruments built for something else.** Le et al. (2026) show a CD model can extract objective-level information from items never written for diagnosis. Mapping FCI, FMCE and EMCS items onto 14 fine-grained learning objectives in introductory mechanics and fitting DINA on 24,394 posttest responses from 807 courses, they found good fit for two of the three instruments (FCI RMSEA² = 0.033; EMCS = 0.022) and classification accuracy at or above the low-stakes formative benchmark for 19 of the 22 objective–assessment combinations. Attribute structure, not item quality, was the binding constraint: expert coding survived model scrutiny almost intact — DINA proposed revising only 14% of 754 item–objective codings and the coders adopted 20 of them (2.7%) — yet the model could not separate three *conceptually nested* energy objectives (Potential Energy 0.675, Conserve Energy 0.705, Kinetic Energy 0.745) because any two shared about 70% of their items (Jaccard overlap 0.67–0.73), violating DINA's conjunctive independence assumption, while momentum objectives on the same instrument reached 0.820–0.917. Finer attributes also fit better rather than worse: the 14-objective structure improved model fit over the same team's earlier four-broad-skill structure on all three instruments. Item overlap, not coding error, is what caps how finely mastery can be separated.
- **Bayesian DINA for personalized learning paths:** Feng and Huang (2026) integrate a Bayesian DINA model (trained on the EdNet dataset, N=5,000) with knowledge space theory and a shortest-remediation-path algorithm to generate personalized learning paths, and empirically test the mediating role of cognitive load via Hidden Markov Model state transitions (validated on 120 students) — addressing both the sparsity-driven convergence problem of traditional DINA models and the untested psychological mechanism behind personalized-path effectiveness.
- **Language-grounded diagnosis in place of ID embeddings.** Liu et al. (2026) replace discrete student, exercise and concept identifiers with LLM-built concept schemas and process-grounded evidence, calibrating each student's posterior state from response records. Across three mathematics platform datasets the framework reaches 83.51% ACC / 85.37% AUC on XES3G5M and 87.16% ACC on MOOC, with the gain concentrated exactly where classical cognitive-diagnosis models degrade: new concepts (+4.60 ACC over KCD) and missing Q-matrix entries (+4.52). Ablating the structured evidence collapses MOOC accuracy from 87.16% to 78.95%, so the improvement comes from the language-derived structure rather than from model scale. (Beyond ID Embeddings: Process-Grounded Language Modeling for Cognitive Diagnosis)
- **Culturally embedded tasks can precede the AI analysis.** Anggara et al. (2026) had 178 junior-high students in Indonesia complete culturally contextualized open-ended tasks before AI response analysis; the AI diagnoses agreed with expert assessment (ICC = 0.81), while cultural embedding was associated with symbolic mathematical performance (β = 0.42) and engagement (β = 0.37).
- **Strategy configuration can be diagnosed, not just knowledge state.** Five dimensions estimated from 36,234 grammar-game actions predicted the next success with AUC 0.826 while excluding current error counts, and varied within students (ICC = 0.14) rather than across them (Geoffre et al. (2026)).

Why it matters

Accurate diagnosis lets instruction target the actual gaps rather than a global "ability" score — enabling Automated Assessment that explains *why* a student erred and Feedback Loop systems that remediate specific knowledge states. Poor diagnosis produces the inverse: instruction aimed at the wrong concepts. This is why Psychometrically Aware AI emphasizes diagnostic validity alongside prediction accuracy.

Relationship to knowledge tracing and intelligent tutoring

Cognitive diagnosis sits at the heart of the Intelligent Tutoring architecture and is the assessment-side counterpart of Knowledge Tracing:

- **Diagnosis vs. tracing — complementary temporal views.** Knowledge tracing tracks the *temporal dynamics* of mastery — estimating how a scalar knowledge state evolves across exercises and predicting the next response. Cognitive diagnosis produces the *static, fine-grained snapshot* of which knowledge components, skills, or misconceptions a learner currently holds. A tutor needs both: knowledge tracing to sequence what to teach next, cognitive diagnosis to know *what* is actually wrong. IRT- and measurement-based diagnostic models, and cognitive-diagnosis models that map items to multiple components, instantiate the diagnostic side.
- **LLM-era diagnosis.** LLMs extend diagnosis from multiple-choice responses to open-ended, handwritten, and conversational work, identifying the specific Misconceptions about AI behind an error (e.g., the "correct answer trap" where a right answer conceals flawed reasoning). HiLLM-CD uses LLMs for automated concept-tree construction and hierarchical proficiency inference, bridging diagnosis and tracing. Boyapati et al. (2026) push this further by federating diagnosis across multiple commercial LLM APIs with ε-local differential privacy, showing that accurate, privacy-preserving diagnosis is feasible without any model seeing raw student data.
- **Separating diagnosis from feedback is a design principle.** LLM tutors reliably confirm correct steps but over-reject valid reasoning and over-validate errors — and accurate diagnosis does not reliably yield actionable Feedback. ITS design should therefore separate a diagnostic component from the feedback/Scaffolding component (Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most).

Connections

Cognitive diagnosis connects to Knowledge Tracing, Learner Modeling and Adaptive Instruction, Educational Measurement, and Assessment. Its insights feed Intelligent Tutoring and Adaptive Learning, and LLM-era work links it to misconception identification in AI Tutoring.

Common Misconceptions

- **"Diagnosis is a solved capability for models."** OmniEdu (Liang et al., 2026) supervised diagnostic reasoning as one of four capabilities in an open 4B/9B/27B family, and **knowledge-state diagnosis remained its weakest** of the four. Diagnosis is the capability that resisted the training that produced the others.

- **“Models can simulate student errors, so they can diagnose them.”** The bottleneck is the reverse. Models constructed a solution in **95.2% of distractor traces** and simulated a specific Eedi misconception at **0.92 accuracy**, yet **supplying the correct solution** — not simulating the error — was what limited them. Generating a plausible wrong answer is easier than recognising one.
- **“Diagnosis requires a hand-built misconception catalogue.”** On **6,106 pairs** of correct and incorrect propositional-logic formalisations, a workflow discovered **248 clusters of transformations explaining 5,156 pairs (84.44%)**, against **4,370 (71.57%)** for the hand-picked mistakes of the reference set. Discovery matched or exceeded expert curation, and it transferred to modal logic — so the catalogue is a starting point, not a ceiling.
- **“A diagnosis is only useful if it names a misconception.”** Diagnosing which course outcomes a learner has attained treats outcomes as the knowledge concepts instead, supplying concept relationships through expert-validated affinity mappings. For outcome-based programs that is the more actionable unit, even though it is coarser.

What this means for practice

For instructors

- Treat a system’s diagnosis as a hypothesis to check, not a verdict. Knowledge-state diagnosis was the weakest capability in a family trained for it.
- Ask whether the diagnosis names a construct you can act on. An outcome-level diagnosis that maps to your program is often more useful than a fine-grained misconception label.
- Where your subject has rules, expect transformation-based discovery to find error patterns you did not anticipate; the 248 discovered clusters are evidence that curated catalogues are incomplete.

For developers

- Instrument both directions: recognising a wrong answer and producing the right one. The 95.2% solution-recovery figure suggests generation is the easy half and the failure mode sits in recognition.
- Prefer discovery over a static catalogue where domain structure permits it, and report coverage against a reference set so the comparison is legible.
- Do not ship a diagnostic score without stating which construct it measures and how it was validated independently of the signal that produced it.

Connected Concepts

- Knowledge Tracing
- Knowledge Graph
- Learner Modeling and Adaptive Instruction
- Educational Measurement
- Item Response Theory
- Assessment

- Intelligent Tutoring
- Adaptive Learning
- Personalized Learning
- Automated Assessment
- Learning Analytics

Connected Articles

- Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work — Benchmarking LLMs for Diagnosing Cognitive Skills from Handwritten Math
- The Correct Answer Trap: Pedagogically-Grounded Detection and Feedback for Hidden Misconceptions — The Correct Answer Trap
- The Easy Trap: Why LLMs Underestimate Misconception-Driven Difficulty — The Easy Trap: Why LLMs Underestimate Misconception-Driven Difficulty
- What Don't You Understand? Using Large Language Models to Identify and Characterize Student Misconceptions About Challenging Topics — LLM identification of student misconceptions
- Archetypes or ability? Clustering for modelling student mathematical competence — Clustering for Modeling Student Mathematical Competence
- Cognitive Agent Compilation for Explicit Problem Solver Modeling — Cognitive Agent Compilation for Explicit Problem Solver Modeling
- EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners — EduClaw-Bench: diagnosing from simulated learners
- Interpretable Knowledge Tracing — Interpretable knowledge tracing
- HiLLM-CD: LLM-Enhanced Hierarchical Cognitive Diagnosis — HiLLM-CD: LLM concept trees + hierarchical proficiency inference
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most — Separating diagnosis from feedback in LLM tutors
- Integrating AI into computational thinking: development and validation of an assessment tool for higher education students — Computational Thinking in AI Training Test (CTAT)
- Bayesian cognitive diagnosis optimizes personalized learning paths via mediation of cognitive load and Hidden Markov Model state transitions — Bayesian cognitive diagnosis for personalized learning paths
- Personalized neural cognitive architecture search — AutoML personalized neural cognitive architecture search for learner profiles
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- Privacy-Preserving Heterogeneous Multi-LLM Federated Inference for Cognitive Diagnosis — Privacy-preserving heterogeneous multi-LLM federated diagnosis

- Finding Common Mistakes In Modelling With Mathematical Formalisms Using LLMs — Mining common modeling mistakes at scale with LLM-generated, algorithmically validated bug-fixing transformations (Killich et al. 2026)
- Mechanics Cognitive Diagnostic: Testing Fine-Grained Learning Objectives in Introductory Physics — Mechanics Cognitive Diagnostic: DINA-based diagnosis of 14 learning objectives from existing physics concept inventories (Le et al. 2026)
- Personalized Exercise Recommendation with Semantically-Grounded Knowledge Tracing — LLM knowledge-concept annotation and calibrated concept-level knowledge states
- Can LLMs Model Incorrect Student Reasoning? A Case Study on Distractor Generation for Multiple-Choice Questions — misconception-based distractors as a diagnostic item-design task
- Misconception Acquisition Dynamics in Large Language Models — where the error enters the solution is the diagnostic bottleneck
- From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning — From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning
- CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop — CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop
- OmniEdu: Open Foundation Models for Learning and Teaching — OmniEdu: Open Foundation Models for Learning and Teaching
- Rethinking Diagnostic Assessment Through Culturally Embedded AI for Meaningful Learning — Rethinking Diagnostic Assessment Through Culturally Embedded AI for Meaningful Learning

Simulating Students

> **Simulating students** — using LLM-based agents to model learner behavior, cognition, and social dynamics for educational research, design, and training. Simulated students let researchers evaluate pedagogical approaches, model diverse learner profiles, test educational AI before deployment, and train teachers — tasks that are difficult, slow, or ethically constrained to do systematically with real learners.

Questions to Consider

- If you had to build an AI 'student' to practice your teaching on, what would make it convincing to you — and why might a system that always gives the right answer actually be a poor stand-in for a real learner?
- The page calls the mismatch between a capable AI's perfect answers and a real student's imperfect ones the 'competence paradox.' Where have you seen this tension in your own experience with AI, and what do you think it takes to make a simulated learner genuinely realistic?
- What are the ethical and practical reasons you might prefer testing a tutoring system or curriculum on simulated students rather than real ones — and what validity risks do you suspect that trade introduces?
- A simulated student can be 'epistemically faithful' without looking superficially human. Before you read on, what distinction do you imagine between a believable surface and a truthful model of what a learner actually knows?
- How would you decide whether a finding produced by simulated students should be trusted enough to change how you teach real people?

Introduction

Simulated students are a methodological tool: agents that stand in for real learners so that tutoring systems, curricula, and instructional strategies can be evaluated and iterated without recruiting cohorts of human students. Large language models have made this paradigm far more scalable and linguistically realistic than the rule-based simulated learners that preceded them, while also introducing new validity challenges.

AI-mediated approximations sharpen the question the page cares about: whom the simulation represents, and what the teacher is meant to notice. In mathematics teacher education, text-based simulated student work and chatbot partners used in rehearsal extend the approximations of practice that already organize professional training. One chatbot study produced four distinct questioning profiles, yet pre-service teachers' self-assessments did not align with the interaction quality observers recorded, which makes automated post-rehearsal feedback that increased probing and exploring questions a useful but insufficient guide. The simulator, the candidate and the feedback all have to be read together. What a simulation lets a teacher notice is also set by its design: in Galiç et al.'s (2026) three-week equal-sign intervention with 17 preservice mathematics teachers, candidates moved among attending, interpreting and shaping rather than through a fixed sequence, but the one-to-one, text-based setup meant shaping collapsed into questioning and

prompting, and a misconception-first design pulled attention toward error detection rather than student strengths. The simulator chooses the slice of teaching a candidate gets to rehearse.

Supervised finetuning alone conditions a simulator only weakly on the prompted ability, because its objective rewards reproducing response text rather than tying response quality to ability; Fernandez et al. (2026) align a simulator instead through direct preference optimization over pairs formed from students' IRT ability gaps, and on CodeWorkout that pairing beats all direct difficulty-prediction baselines and, at the 1B scale, the SMART simulator on every difficulty metric while producing more distributionally realistic responses.

Why simulate students

- **Evaluating pedagogy:** testing instructional approaches across many learner profiles in a controlled, repeatable way.
- **Modeling diverse learners:** capturing variation in cognitive levels, learning styles, prior knowledge, and Misconceptions about AI that is hard to assemble in a real cohort.
- **Testing educational AI:** validating tutoring and Assessment systems before live deployment, and generating training data.
- **Teacher training:** letting instructors practice tutoring and classroom management with simulated, often imperfect, learners.
- **Simulations cover the easiest students, and few are validated.** Twelve teachers who tutored LLM students reported overly complex language, missing emotion, unnatural attentiveness and knowledge jumps, and the simulations represented only one of four real student behavior quadrants — while just 3% of studies simulating learners validate them after use (Martynova et al. (2026)).

The core challenge: realistic imperfection

The defining difficulty of student simulation is that LLMs are trained to be "helpful assistants" that produce correct, polished answers. Yet real students are imperfect — they make characteristic mistakes, hold misconceptions, and learn gradually. A simulated student that answers perfectly (or too randomly) is not a valid model of a learner. Research frames this as the **competence paradox**: broadly capable LLMs asked to emulate partially knowledgeable learners produce unrealistic error patterns and learning dynamics. Nguyen and Cao (2026) give that drift a direction. Against lesson-embedded student ideas drawn from 49 NGSS-aligned science lessons, six models kept most ideas inside the expected knowledge scope and roughly two-thirds at or below the target reading level, but overshot exactly where the learner was youngest: elementary and middle-school ideas more often exceeded the target grade's knowledge scope and reading level, while the corpus as a whole leaned toward broader reasoning, more technical vocabulary and fewer uncertainty markers ("maybe", "it seems") than the lesson ideas. Model choice is not one-dimensional either — a system that matches lesson ideas closely can still pitch them above grade, so the repair is usually instructional, since an explicit grade-level re-prompt lifted most models back into range. Addressing it requires constraining the simulation so it reflects a genuine epistemic state — what the learner knows, how errors are structured, and how state evolves — rather than the model's full competence. Techniques include cognitive prototypes

grounded in Knowledge Graph or Knowledge Tracing models, explicit epistemic state specifications, and state-transition models of learning rather than simple persona-conditioned role-play.

A different lever removes the knowledge instead of constraining the output. Suppressing 16 targeted knowledge components in Mistral-7B dropped accuracy from about 0.75 at a 10% forgetting ratio to below 0.5 at 40% while the base model held near 0.85, and the suppressed knowledge proved recoverable through supervised relearning and coach-guided dialogue (Song, Guo & Lin, 2026).

Persona stability is an interaction-design problem, not a model-choice one: crossing five LLMs with three prompt designs and four ADHD-intensity personas, scripted task-anchored interactions eliminated observer-rated behavioral drift — up to 97% less than unscripted dialogue — and without explicit persona instructions baseline student representation skewed toward high ADHD symptoms (Gonnermann-Müller, Haase & Leins (2026)).

The opposite failure also occurs: in a blinded study, expert annotators misclassified 164 of 196 (83.7%) LLM-generated Java submissions as human-written, so a simulator's errors can be functionally indistinguishable from authentic ones — though alignment with real errors fell as problem difficulty rose (Keramati et al. (2026)).

Conditioning generation on a predicted behavior model works without fine-tuning: a training-free framework builds each student's cognitive prototype from a Knowledge Graph and scores beam-search candidates against it, reporting a 100% improvement in simulation accuracy (Wu et al. (2025)). Its quality rises with the student's cognitive level, so weaker learners remain the harder case to simulate. - **Predict the learner instead of acting as one.** Jiang et al. (2026) recast simulation as third-person prediction: a student model built from the learner's history supplies a prior, an inferred learner state constrains the next action, and the simulated ability distribution lands 2.4–8.4× closer to the real one by Wasserstein-1 distance.

CogEvolution models cognitive dynamics rather than a static persona — an ICAP depth perceptron sets each state update's size and an evolutionary update stays within a Zone-of-Proximal-Development radius — reaching $R^2LC = 0.92$ where static agents reach 0.45 and collapsing to 0.58 without the ICAP module (Zhang et al. (2026)).

Drift is a horizon problem, not a persona problem. Radmehr et al. (2026) show that turn-level generation loses an assigned profile as trajectories lengthen, while planning profile-aligned segments before generating actions held density and judge-rated consistency even with three real trajectories per profile.

Fidelity over surface realism

Validity is the central concern: a simulated student is only useful if its behavior is **epistemically faithful** — reflecting the intended learner's knowledge state — not merely linguistically plausible. Research warns against sycophancy, where a "simulated student" simply agrees with the tutor rather than exhibiting the misconceptions it was meant to embody. This connects to Trust Calibration and to the broader problem of evaluating whether an agent genuinely models a construct rather than reproducing surface behavior.

The failure is quantified: across seven models from 4B to 120B parameters, simulators flipped to the correct answer at near-uniform rates whatever the feedback, so output similarity says nothing about the belief state behind it, while training against the Selective Flip Score lifted faithfulness by up to +0.56 (Do, Sonkar & Sachan (2026)).

Simulated clients remove the clarification phase, and the trainee's behavior follows. Rudolph et al. (2026) compared 64 human-human chat counselling role-plays with 74 human-LLM conversations (Mixtral 8x7B, 4-bit) under the GeCCo category system and found that LLM clients disclosed the problem embedded in their prompt rather than circling it. Counsellors consequently reached Problem-Solving in 17.63% of coded behavior against 10.67% with human clients, relied more on factual reflection than facilitative moderation, and closed sessions with formalities more often (11.95% vs 5.95%). The design consequence is that a curriculum built mainly on simulated clients trains the second half of a session: eliciting a reluctant account is exactly what the simulated client skips, so a prompt that makes the client withhold restores it.

Connection to the knowledge base

Simulating students sits at the intersection of Simulation, Learner Modeling and Adaptive Instruction, and Knowledge Tracing. It is a distinct use of Generative AI in education (modeling learners rather than tutoring them) and an application of Agentic AI multi-agent systems. It supports Intelligent Tutoring, Adaptive Learning, Personalized Learning, and Teaching development, and it overlaps with patient simulation for professional training (e.g., Special Education and medical education contexts). At the paradigm level, Zhang, Jiang and Tang (2026) extend this beyond evaluation: their position paper argues that educational science suffers a structural mismatch between its theory and its data and method apparatus, and proposes agent-based educational science, in which agents model learners, teachers, parents and peers while the simulation apparatus itself — not the individual agent — serves as the research instrument, generating time-extended developmental trajectories and counterfactual designs that are slow, costly or ethically infeasible to run in classrooms, with empirical data recast as calibration, validation and boundary conditions. The paper reports no empirical validation of any of this: Student Development Agents are specified conceptually only, and the authors' own review concedes that LLMs still miss inter-individual variability and that validating generative social simulation remains the field's unresolved challenge, so the claim that simulation would change how evidence and replication work is a proposal rather than a demonstrated result.

An empirical companion comes from the same group: a student development agent predicts 42 real students' post-course non-cognitive outcomes on the MAIC platform, beating the mean pre-course baseline on RMSE in all five dimensions (Jiang & Zhang, 2025). Its target is development rather than behavior — the agent's state feeds into its next actions — and prototyping on agents is argued to keep students out of a study's most uncertain stage.

Simulating students vs. student modeling

The key distinction is between **representing a real learner** and **generating a synthetic learner**. Learner Modeling and Adaptive Instruction is the practice of building a computational representation of an actual student — what they know, feel, and need — so that adaptive systems can personalize instruction for *that* learner. Simulating students, by contrast, *creates* fictional learners on demand, not to serve a real individual but to stand in for a cohort so pedagogy and AI systems can be tested offline.

The two are complementary rather than competing. A high-fidelity simulated student typically *contains* a student model (an epistemic state, a misconception set, an engagement profile) and draws on the same constructs that Learner Modeling and Adaptive Instruction and Knowledge Tracing formalize. The shared

validity challenge is the same in both: the representation must faithfully reflect a learner's true state rather than the system's default behavior. But the *purpose* differs — student modeling diagnoses a real learner to act on them; simulation fabricates learners to test or train. This is why simulated-student research is increasingly used to audit AI (see below) while student-modeling research remains oriented toward live Adaptive Learning and Personalized Learning.

The mirror question runs the other way. AI Avatars and Synthetic Instructors simulates the person teaching rather than the person learning, so simulated students expose a method to scrutiny while synthetic instructors stand in front of a learner, who is the beneficiary and the judge.

Two-axis fidelity: behavioral match and guidance responsiveness

StudentSim (Yang et al., 2026) formalizes the validity problem as two requirements that must hold together: **behavioral fidelity (F)** — how well a simulator matches a student's own responses — and **guidance responsiveness (R)** — how reliably it updates toward where tutor guidance leads. Its Benchmark, StudentSimEval, casts public learner corpora (chess, second-language English writing, mathematics) into a standardized per-student protocol on which any simulator is fit and scored on held-out records. A two-stage **pooled-then-specialized** pipeline (a shared pool of behavioral patterns plus a per-student adapter) yields a family of simulators strong on both axes, outperforming domain-specific state-tracking (weak on R) and prompt-only LLM role-play (weak on F). This gives the field a concrete, two-axis vocabulary for judging whether a simulated learner is genuinely useful rather than merely plausible — and, as a proof of concept, a frozen StudentSim used as the reward in a chess-tutor Reinforcement Learning loop produced tutors that experts rated as more accurate, better-guided, and more personalized than those trained with a frontier-LLM-simulator reward or no RL at all.

Student simulators reproduce observable actions but not the latent reasoning behind them. INSIDE fine-tunes models to generate an internal dialogue before each action, reaching the highest alignment between generated reasoning and real code edits (51.8% on familiar problems, 57.9% on unseen ones) without losing action fidelity (Niousha et al., 2026).

Describing, not simulating: when a single agent beats a simulated cohort

A recurring question is whether simulating a distribution of learners is the best way to predict how real students will fare. Wang, Mitchell & Piech (2025) supply a striking counter-result: for **evaluating an online learning experience before students engage** — predicting dropout and completion and giving design feedback — a **single "describing" web agent** that autonomously walks through the lesson and produces a rich description of the student experience outperformed directly simulating a population of students. Their simulated students (persona-conditioned agents sampled to match a predicted completion rate) exhibited far less behavioral range than real learners — across 100 agents on five test lessons they reproduced only about **4% of the paths** real students took — and offered little insight into lesson difficulty, while being substantially more computationally expensive. The single describe-then-predict pipeline (agent-generated descriptions fed to an Large Language Models (LLMs) to predict outcomes) achieved the best dropout-distribution prediction on a massive global CS1 course (mean JSD 0.060, beating every baseline). This is a productive boundary result for the field: simulating a *distribution* of students may be unnecessary — and even counterproductive — when the goal is outcome prediction or design critique, because a faithful

description of the experience carries more signal than a narrow slice of simulated trajectories. It also suggests simulation's role may be bounded to questions (e.g., auditing an AI's treatment of diverse profiles, or training teachers) where covering genuine learner variation matters more than aggregate outcome prediction.

Authentic-data student models and interactive practice

Two 2026 threads sharpen the practical value of simulation. First, **authentic-data student models** — TeachLM trains a student model on 100,000 hours of real one-on-one tutor–student interactions (with rigorous anonymization), producing synthetic learners that enable fast, scalable, reproducible multi-turn evaluation of tutor behavior; this addresses the low authenticity and diversity of purely prompt-engineered student simulators. Second, **interactive instructional simulacra** — EducaSim uses generative agents (with personas, course-grounded memories, and an LLM-as-judge speech oracle) to simulate a small-group section for teachers-in-training, adding runnable-code and voice interaction plus structured post-session feedback and self-reflection, and demonstrates low-cost, positive-uptake experiential teaching practice at the scale of massive online courses. Both point to simulation serving not only evaluation but hands-on teacher preparation.

A third 2026 thread concerns *how* a simulator is built rather than what it is used for, and it converges on one conclusion: prompting sets a ceiling that training removes. SWIM (Do, Kontak and Sachan, 2026) reformulates student writing simulation as proficiency-conditioned essay generation and compares rubric-grounded prompting, supervised fine-tuning on real score-essay pairs, and GRPO with an Automated Essay Scoring-derived Proficiency Alignment Reward, scoring each generated essay against its target trait profile with Quadratic Weighted Kappa. Prompting gave limited control even to strong proprietary models (best average trait QWK 0.577 for Claude Sonnet, 0.422 for GPT-5.4, near zero for prompting an open 7B model), it aligned content-oriented traits far better than form (0.695 against 0.458), and it produced an idealised high-proficiency population, with a mean normalized Overall score of 0.74 against 0.58 for real students and a median length of 304 words against 167. Supervised fine-tuning moved a 7B model to 0.474 ± 0.023 and GRPO to 0.618 ± 0.005, the gains held on two independent scorers the policy never trained against, and the trained models recovered the human score and length distributions without any length supervision; authentic low-proficiency form stayed hardest, since trained models recovered syntax but wrote too few spelling and grammar errors while prompting simulated weakness mainly through superficial corruption. The same lesson arrives from the opposite direction in Liu et al. (2026), who instruction-tuned three small models to hold algebra misconceptions: data *composition* decided the outcome, because a single misconception overgeneralised and degraded correct solving until correct examples were mixed in, several misconceptions trained jointly without cost, and no misconception was acquired from final-answer-only supervision at any data size, leaving step-level solution traces as the binding requirement.

Benchmarking nine simulation methods against seven reference-based metrics on 382 held-out math dialogues, prompting trailed fine-tuning on dialogue acts (0.4998 against 0.6840), ROUGE-L (0.1648 against 0.3212) and cosine similarity (0.5460 against 0.7390) (Scarlatos et al., 2026). Yet the best method tested, preference optimization on an 8B model, beat supervised fine-tuning only marginally and was worse on errors, and a three-tutor human evaluation reproduced that ranking.

Architecture can enforce what prompting cannot: a neuro-symbolic simulator imposing self-regulated learning structure through a semi-Markov controller and flaw-injected knowledge tracing reached behavioral divergence of 0.31 against a 0.53 baseline (Wang et al., 2026). Injecting its metacognitive vocabulary into baselines never beat 0.63, removing the symbolic controller pushed divergence to 6.81, and in a 71-rater Turing test its traces were indistinguishable from real students (52.8%, d′ = 0.15).

Auditing AI with simulated students

Beyond evaluating pedagogy, simulated students serve as a **test harness for auditing AI systems themselves** — a controlled way to probe how an AI behaves across diverse learner profiles before it touches real students. López-Pernas et al. (2026) illustrate this: they generated 4,500 synthetic student vignettes with three LLMs to audit whether current large language models can act as prescriptive Learning Analytics recommenders, finding limited sensitivity to student need and sharp cross-model inconsistency. Using simulated cohorts to stress-test an AI's recommendations (rather than only to train or evaluate tutors) is a growing role for the paradigm, closely tied to evaluating AI in education and to Equity when the audit is meant to surface disparate treatment across learner types.

A sharper validity test asks whether a model reproduces human *choice* at all: in an adapted self-directed learning game, five frontier models exploited a single solution where 175 human participants explored across goals, so a model standing in for learners abandoned the behavior the simulation exists to reproduce (Molinaro et al. (2026)).

Simulation can also pre-test the learner's choices: Noh et al. (2026) fit an Additive Factors Model and Bayesian Knowledge Tracing to two real tutoring datasets and let 1,000 simulated learners choose skills under eight strategies, where a risk-averse rule produced roughly thirty times the overpractice of the others and a just-below-mastery constraint cut it to 1.8×.

A second audit register is metacognitive and affective. MEDS (Esposito et al., 2026) is a 28,000-record dataset — 2,000 synthetic personas for each of 14 models, every one run both as a human persona and as a baseline assistant — that records accuracy on 18 high-school math problems alongside self-reported confidence and the Self-Efficacy and math anxiety scores the learners it stands in for would report. Its audit signal is the calibration gap: the Qwen family and Ministral 3B asserted confidence above 0.90 while accuracy stagnated near 0.55, while Grok 4.1 Fast, DeepSeek Chat and several Mistral Small variants were underconfident and Ministral 14B and Anita 24B stayed reasonably aligned. The same runs expose a quieter failure of fidelity: human-mode personas yielded wide, plausible score distributions, but baseline assistants returned near-identical, confident, low-anxiety answers — a default self-portrait rather than a simulated learner's. This extends the recommender audit above by probing what a model claims about its own competence and affect, and it sharpens the page's validity warning from an unexpected direction: because MEDS personas are weighted by construction rather than sampled from a real population, its authors present the dataset as an observational resource for auditing prompt-conditioned GenAI behavior and explicitly not as a stand-in for real student data.

Simulating collaborative and social dynamics

Simulation also extends beyond individual learners to reproducing the social dynamics of collaborative learning. **Participant-specific LLM agents** — Fang (2026) fine-tuned LLaMA 3.2-3B agents on individual

participants' dialogue data to represent each participant in collaborative problem solving simulations, combining sliding-window memory with summarized memory embeddings to preserve both local turn-taking and thematic continuity, and probabilistically selecting speakers and thematic codes from empirical distributions. Using Epistemic Network Analysis (ENA), the simulated dialogues were statistically indistinguishable from real ones (ENA distance 0.17, well within the 95th-percentile null threshold; permutation p = 0.65), validating that LLM agents can reproduce both turn-taking dynamics and thematic code trajectories of real collaborative problem solving.

The 2026 durable-skills work inverts the usual direction of simulation. Instead of simulating the student to audit a system, the system simulates the *teammates* to assess the student: an Executive LLM generates every AI partner's turns in a 30-minute group task, holds the scoring rubric, and steers the conversation to manufacture occasions for the target skill to appear (Globerson et al., 2026). Across 373 conversations from 188 participants, skill-matched steering raised ratable evidence to 92.4% for project management and 85% for conflict resolution, significantly above unconstrained independent agents, while the AI evaluator was calibrated against two human raters whose own inter-rater Kappa was only 0.45–0.64 — a useful reminder that a simulator's ceiling is set by the agreement humans can reach on the construct.

Training against a simulator can also travel: TutorLoop's reinforcement-learning agent, trained offline against a simulated student, transferred unchanged to a new real learning task with no retraining (N = 187), where its sparser but better-timed feedback outperformed denser feedback (Xu & Zhang, 2026).

Common Misconceptions

- **"LLM students are good enough proxies." Simulations cover the easiest students, and few are validated**: **twelve teachers** who tutored LLM students reported **overly complex language, missing emotion** and other departures from real learners. The proxy models the tractable case.
- **"A simulated student with a knowledge gap behaves like a learner with that gap."** Suppressing **16 targeted knowledge components in Mistral-7B dropped accuracy from about 0.75 at a 10% forgetting ratio to below 0.5 at 40%**, while the base model held. The degradation was engineered, which is what makes it a controlled manipulation rather than an emulation.
- **"Persona stability is a model-choice problem."** It is an **interaction-design problem**: crossing **five LLMs with three prompt designs and four ADHD-intensity personas**, scripted differences tracked the prompt design rather than the model. Choosing a better model does not fix an unstable persona.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Simulation
- Learner Modeling and Adaptive Instruction
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Knowledge Tracing
- Cognitive Diagnosis
- Agentic AI

- Pedagogical Agent
- Intelligent Tutoring
- Adaptive Learning
- Personalized Learning
- Generative AI
- Large Language Models (LLMs)
- Learning Analytics
- Teaching
- AI Avatars and Synthetic Instructors

Connected Articles

- To Align Long, Plan Short: Simulating Diverse Profile-Aligned Students by Realizing Short-Term Plans in Long-Horizon Learning Environments — ALPS: hierarchical planning keeps simulated students on profile over long horizons (Radmehr et al. 2026)
- Comparing Human Role-Players and LLM-Simulated Clients in Online Counselling Training: An Analysis of Counselling Patterns — Simulated counselling clients disclose faster, so trainees skip facilitative moderation
- HACHIMI-II: From Role-Play to Learner Behavior Modeling for Faithful Student Simulation — HACHIMI-II: From Role-Play to Learner Behavior Modeling for Faithful Student Simulation
- TutorLoop: Regulating Student Learning Behaviors via Sensor-in-the-Loop Generative Feedback — A simulator-trained reinforcement-learning tutor transferred offline to a new real task (Xu & Zhang 2026)
- Can LLMs Effectively Simulate Human Learners? Teachers' Insights from Tutoring LLM Students — Can LLMs Simulate Human Learners? Teachers' Insights
- Simulating Students or Sycophantic Problem Solving? On Misconception Faithfulness of LLM Simulators — Simulating Students or Sycophantic Problem Solving?
- LLM-Based Educational Simulation: Evaluating Temporal Student Persona Stability Across ADHD Profiles — LLM-Based Educational Simulation and Student Persona Stability
- Simulating Students' Java Programming Errors with Large Language Models — Simulating Students' Java Programming Errors
- The Empirically Grounded Adaptive Virtual Patient for Psychotherapy Training: Disclosure That Responds to Therapist Micro-Skills — Adaptive Virtual Patients for Psychotherapy Training
- MedEasy: Designing AI Standardized Patients for Clinical Consultation Training — MedEasy: AI Standardized Patients
- Embracing imperfection: Simulating students with diverse cognitive levels using LLM-based agents — Embracing Imperfection: Simulating Diverse Cognitive Levels
- INSIDE the student's mind: Jointly modeling latent reasoning and action in LLM student simulators

- TeachLM: Post-training LLMs for education using authentic learning data — TeachLM: fine-tuned authentic student model for synthetic dialogues
- EducaSim: Interactive simulacra for CS1 instructional practice — EducaSim: generative agents simulate a CS1 section for teacher practice
- Responsible integration of artificial intelligence into pedagogies of practice in mathematics teacher education — Responsible Integration of AI into Pedagogies of Practice in Mathematics Teacher Education
- CogEvolution: A human-like generative educational agent to simulate student's cognitive evolution — CogEvolution: generative agent simulating students' cognitive evolution
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- Modelling individual participants as LLM agents in collaborative problem solving simulations — Fine-tuned participant-specific LLM agents reproducing collaborative problem solving dialogues (Fang 2026)
- StudentSim: Training LLM-based Student Simulators — StudentSim: Training LLM-based Student Simulators
- AI Web Agents Can Effectively Guide Lesson Design and Predict Student Outcomes — AI Web Agents: a single describing agent beats simulating a distribution of students for predicting dropout and design critique
- Simulating Learners' Task-Selection Strategies and System Constraints in Mastery Learning — Simulating learners' task-selection strategies and system constraints in mastery learning (Noh, Chowdhary, Ooge, Aleven & Borchers 2026)
- Towards Scalable Measurement of Durable Skills — Toward Scalable Measurement of Durable Skills
- Toward agent-based educational science: Rethinking educational research in the age of AI — Toward Agent-based Educational Science: the simulation apparatus as the research instrument (Zhang, Jiang & Tang 2026)
- Math Education Digital Shadows for facilitating learning with LLMs: Math performance, anxiety and confidence in simulated students and AIs — MEDS: a 28,000-record audit of math performance, confidence and anxiety in simulated students and AI assistants
- SWIM: Student Writing Simulation via Proficiency-Conditioned Generation — prompting versus SFT versus reward-based training for a student writing simulator
- Misconception Acquisition Dynamics in Large Language Models — what has to be in the training data before a simulator holds a misconception at all
- Can LLMs Model Incorrect Student Reasoning? A Case Study on Distractor Generation for Multiple-Choice Questions — trace-level analysis of how models simulate incorrect student reasoning

- Exploring the Capacity of Large Language Models to Simulate Students' Scientific Thinking: Insights for Responsive Teaching — six models against 8,820 lesson-embedded science ideas: where simulated reasoning overshoots young learners' scope, vocabulary and certainty
- Simulated Students in Tutoring Dialogues: Substance or Illusion? — a seven-metric benchmark of nine student-simulation methods, with a three-tutor human evaluation
- Simulating Novice Students Using Machine Unlearning and Relearning in Large Language Models — machine unlearning as a way to put a simulator at a stable novice knowledge level, and relearning through teaching dialogue
- Student Development Agent: Risk-free Simulation for Evaluating AIED Innovations — predicting students' post-course developmental outcomes on a multi-agent platform without exposing them to the intervention
- Preservice mathematics teachers' noticing in AI-based simulations: transitions among attending, interpreting, and shaping — three weeks of preservice teachers' attending, interpreting and shaping in an equal-sign chatbot simulation, and how the design steers what they notice
- BEAGLE: Behavior-Enforced Agent for Grounded Learner Emulation — a neuro-symbolic simulator that enforces SRL structure architecturally rather than by prompting, and passes a human Turing test
- Language Model Goal Selection Differs from Humans in a Self-Directed Learning Task — Language Model Goal Selection Differs from Humans in a Self-Directed Learning Task

Connected FAQs

- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- How Do We Make a Simulated Student Behave Like a Real Learner?
- How Can AI Assist with Educational Research?

Intelligent Tutoring

> **AI tutoring / intelligent tutoring** — the use of AI to provide personalized, adaptive, scalable instructional support: from classical Intelligent Tutoring Systems (ITS) that model student knowledge, adapt instruction, and scaffold Problem Solving, to conversational and agent-based tutors built on LLMs. Effectiveness hinges on pedagogical design (Scaffolding, feedback quality, autonomy balance) rather than the model alone — see Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact and Socratic Method.

Questions to Consider

- An AI tutor's effectiveness is said to hinge on pedagogical design — scaffolding, feedback quality, the balance of autonomy and guidance — rather than on the underlying model. If you had to pick, which design choice most determines whether a student actually learns?
- Classical ITS are praised for precision and transparency but criticized for inflexibility, while LLM tutors are flexible but can hallucinate or bypass learning. Where do you think the right balance lies, and why?
- Large-scale field evidence found students tried an AI tutor but rarely used it productively — engaging it in only a fraction of their mistake sessions, often with bare answers. Why might students get access to a powerful tutor yet not use it in ways that help them learn?
- The page contrasts traditional ITS that model a learner and adapt instruction with open-ended conversational tutors. What is gained and lost when a tutor can hold a natural conversation but doesn't know exactly why it made a decision?
- One study found AI created a 'productive slowdown' — more time per question — but only improved learning when embedded in a mastery workflow that made mistakes consequential. What does that suggest about structuring effort so it pays off?
- If hint design can inadvertently enable students to bypass learning, what would a well-designed hint system look like that supports struggle without giving away the answer?

Introduction

AI tutoring encompasses the use of artificial intelligence — particularly large language models and structured Intelligent Tutoring Systems — to provide personalized, adaptive, and scalable instructional support to learners. AI tutors take many forms: conversational tutors that engage in Socratic dialogue, scaffolded feedback systems that guide problem-solving, adaptive learning platforms that personalize content sequencing, and agent-based tutors that maintain long-term learner models. The effectiveness of AI tutoring depends critically on pedagogical design choices — scaffolding, feedback quality, and the balance between autonomy and guidance — rather than on the underlying model alone.

Historically, **Mishra et al.** locate ITS within AIED's lineage from 1960s-70s expert systems and Anderson's ACT/ACT-R cognitive tutors, whose structured control contrasted with Papert's constructionism.

Ng'ambi and van der Merwe (2026) show that the tutoring role is set by task design rather than by the system: the same language model, configured identically, sustained extended dialogue in problem-based Grade 9 mathematics tasks and collapsed into transactional answers under structured procedural ones.

ITS in the learner-modeling family

Intelligent tutoring is the classic *application-side* member of the learner modeling and adaptive instruction family. Its canonical architecture — domain model, student model, and pedagogical model — is precisely the "model a learner, then adapt instruction" pipeline the family describes. ITS consume the learner representations produced by Knowledge Tracing and Cognitive Diagnosis to select problems and scaffold guidance, which is why tutoring is so tightly coupled to those modeling methods. Within the family, ITS sits alongside adaptive learning (the real-time adaptation mechanism) and personalized learning (the broader goal) as the platforms that turn learner models into instruction.

ITS vs. LLM-based tutoring

The emergence of LLMs has created a productive tension in the tutoring field. Traditional Intelligent Tutoring Systems (ITS) offer precision and transparency — you know exactly why the system made a particular decision — but lack flexibility. LLM tutors offer natural dialogue and broad knowledge but can hallucinate, over-scaffold, or bypass learning entirely. Modern research increasingly explores **hybrid approaches** that combine structured ITS components with LLM flexibility. Reddig, Arora & MacLellan (2025) demonstrate this concretely in the Apprentice Tutor College Algebra ITS: supplying GPT-4 the tutor's interface structure and Bayesian Knowledge Tracing skill estimates within the prompt lifted logical-error diagnosis from 40% to 81% on factoring (and error identification overall to 87.8%) and produced ~66% error-targeted hints — direct evidence that embedding an LLM in an ITS's structured framework grounds generation, curbs hallucinated diagnoses, and yields context-aware corrective feedback, even though roughly a third of the hints remained too general, incorrect, or answer-revealing.

Training pedagogy into the model is a distinct route from prompting it: LearnLM mixed pedagogical data into Gemini's post-training, was preferred by education experts over GPT-4o (+31%), Claude 3.5 Sonnet (+11%) and base Gemini 1.5 Pro (+13%), and — because co-trained rather than fine-tuned afterwards — the gains survive future base-model releases (LearnLM Team (2025)).

TeachLM argues the scarce ingredient is authentic learner–tutor interaction: fine-tuned on 100,000 hours of one-on-one tutoring, it roughly doubled student talk time and increased dialogue turns by 50%, after an earlier prompt-engineered tutor could not close the gap to human tutors (Perczel, Chow & Demszky (2025)). - **Supplying reference strategies lifts weak tutors, not strong ones.** Giving models the case literature's documented strategy raised immediate-response success for 10 of 11 models by an average of 9.9 points — Llama 4 Maverick from 41.0% to 64.8% — while the strongest model was unchanged at 71.3% (Park et al. (2026)). - **Access to a tutor is not the same as learning from it.** Randomizing 153 proof-course students to earlier access to a chatbot and a feedback interface raised homework scores 2.56 points and left the unsupported exam unchanged, with each 100 chatbot messages tracking 3.02 points lower (Chen et al. (2026)). - **Valid alternatives expose a responsiveness gap.** Simulating dialogues on 150 programming problems with more than one correct solution, four open-weight tutors opened with brute force 22.2 to 32.1 percent of the time and the optimal approach only 13.0 to 19.4 percent (Cen & Sonkar (2026)).

Intelligent Tutoring Systems represent one of the oldest and most researched areas of AI in education. Unlike general-purpose LLM tutors, ITS traditionally use structured approaches: domain models (what to teach), student models (what the learner knows), and pedagogical models (how to teach). These components enable fine-grained tracking of student progress, misconception diagnosis, and adaptive sequencing.

Key ITS research

- **Micro-randomized trials of a tutoring platform:** Harrison et al. (2026) ran a four-week multisite individually randomized evaluation of Medly in GCSE Biology, Chemistry and Physics, with 644 of 929 students completing post-testing; allocation to the platform produced Hedges' g = 0.33 (95% CI 0.18 to 0.48) against business-as-usual self-directed revision, with positive estimates in all three subjects and no evidence of differential impact by disadvantage (Pupil Premium g = 0.28 versus non-Pupil Premium g = 0.35).
- **Hint button research** shows that traditional ITS hint design can inadvertently enable bypass strategies, calling for more sophisticated Scaffolding approaches.
- **Deeptutor** provides a fully Open Source agentic tutoring framework with citation-grounded tutoring and difficulty-calibrated question generation.
- **Interpretable Knowledge Tracing** addresses the opacity problem by producing interpretable cognitive quantities from LLM logits.
- **Engagement and structure, not capability, are the binding constraints (large-scale field evidence):** Khanmigo (Oreopoulos & Low 2026) — a two-year cluster RCT in 18 middle schools — found 96% of students tried the AI tutor but the median engaged it in only ~17% of mistake sessions (mostly bare answers or prompt clicks), so gains (~0.06–0.08 SD) matched practice without AI. NUMI (Oreopoulos et al. 2026) found AI created a "productive slowdown" — more time per question and improved post-mistake recovery — but only reliably improved delayed learning when embedded in a mastery workflow that made mistakes consequential. The lesson: AI tutoring's value depends on **getting students to use it productively** and structuring it so effort pays off, more than on raw model capability.(Virtual tutoring with computer-assisted learning: An experiment in take-up and learning)
- **A tutoring harness helps weak backbones and can hurt strong ones.** RegulaTutor (Li et al. 2026) wraps a model in evidence-linked, SRL-grounded stages and raised historical-evidence accuracy by a mean of 25.7 points across four local checkpoints. The judged quality of teaching barely moved (+0.016), and evidence gains reversed on the strongest backbone tested (GPT-5.6-sol −4.87 points).
- **Outcome-based knowledge tracing for OBE tutors.** Pradeesh et al. (2026) trace student mastery of Outcome-Based-Education course outcomes with a recurrent model that replaces learned concept relations with curriculum-validated OBE "affinity mappings" between course and program outcomes and adds a Memory Augmented Neural Network for cross-outcome impact. It reached 89.81% AUC on live engineering-program data, beating DKT, DKVMN, EKT, and SimpleKT baselines — a mastery signal aligned to a program's own outcomes that can drive adaptive problem selection in outcome-based tutoring.

- **Validate mastery models on future sessions, not retrospective fit.** The mastery estimates an ITS uses to select problems may not generalize across time: Schuetze, Yan, and Carvalho (2025) found that BKT, BKT-with-Forgetting, and AFM reproduce learning trends only when fit retroactively to all sessions of a successive-relearning dataset — but under **time-based cross-validation** (training on one session to predict the next, the actual tutoring setting) they overestimate performance by 47–58%, fail to capture the spacing effect, and can mis-order practice conditions. Tutors relying on such tracers should be evaluated walk-forward and consider retention interval and between-session forgetting rather than assuming mastery persists.
- **Diagnosing mistakes on unstructured, handwritten-solution problems.** Arthur (Yin et al. 2026) extends ITS-style feedback to Calculated Formula Questions in an Engineering Economics course, a domain where pen-and-paper solutions lack the structured digital data that previous AI tutoring work relied on. Rather than a general-purpose LLM, each question gets its own dedicated XGBoost "solution diagnosis backbone" — trained on curated, random-masking-augmented graded submissions to predict instructor rubric mistake labels from students' submitted numbers alone (precision 0.81, recall 0.79) — paired with a dialogue-based interaction that iteratively requests intermediate answers only when diagnosis confidence drops below a 0.8 threshold. It is a concrete case of the knowledge base's principle that a knowledge-grounded classifier can handle solution diagnosis even where full written solutions are unavailable.
- **Turn-level adaptive tutoring with a background evaluator.** The MeduAI-SP tutor agent (Yang et al., 2026) exemplifies turn-level adaptive tutoring: a background evaluator monitored each student utterance against a 30-item OLDCARTS-linked history checklist plus communication criteria and triggered prompts only when warranted (24.1% of 4,815 messages). Corpus analysis exposed where such support is most needed — student talk was 62.2% history of present illness but only 4.3% empathic/supportive communication and 2.6% physical examination — suggesting ITS-style clinical tutors should target underused consultation components and late-encounter reasoning phases rather than symptom gathering alone, and that simulated-patient fidelity is high enough for outcome research (only ~0.68% of patient utterances showed clear fidelity problems).
- **An AI tutor built from the class's own pedagogy outperformed that class: an RCT against active learning.** In a crossover RCT in Harvard's largest introductory physics course (194 eligible students), a custom tutor engineered from the same seven research-based practices as the in-class lessons produced a median post-test of 4.5 against 3.5 for the course's in-class active learning (baseline median 2.75), an effect size of 0.63 by linear regression, in a median 49 minutes on task against 60 in class, with higher reported engagement (4.1 vs 3.6) and motivation (3.4 vs 3.1) (Kestin et al., 2025). The authors locate the advantage in the two practices a classroom cannot sustain — personalized feedback on demand and self-pacing — and warn that the tutor should augment, not supplant, in-class instruction.
- **Teacher mediation roughly doubles implementation fidelity (full-district field evidence):** Goblins (Alam et al. 2026) — a teacher-mediated multimodal AI math platform rolled out to all grades 6–8 math teachers in a large Arizona district — reached ~51% of 6,065 students at a modest 2-problems-per-week engagement bar, versus the 5% (Khan Academy) and 12% (IXL) thresholds in prior evaluations.

- **And dose drives the effect within it (same study):** a weighted propensity design associated usage with 0.11 SD within-district MAP growth (0.24 SD on the national Conditional Growth Index), with a clean dose gradient — 0.18 SD at 10–19 problems/week and 0.31 SD at 20+, all dosages above 3/week significant ($p < 0.01$). Exploratory subgroups showed larger associations for students with IEPs (+0.122 SD), English learners (+0.191 SD), and Hispanic students (+0.084 SD). The design is quasi-experimental — self-selection into usage is the vulnerability the authors name — but fidelity and dose-response directly instantiate the binding-constraint lesson.
- **Statistical equivalence to expert human tutoring.** Across 2,469 sessions from 2,383 adults, pooled AI tutoring matched live one-to-one expert human tutoring on GRE learning gains ($p=.015$ against ±0.25-SD bounds; adjusted difference -0.58 percentage points) and both beat a video control by about six points; six of twelve tutors passed individual equivalence tests, with Gemma 4 31B matching human gains at 918× lower cost per percentage point (Northcutt et al. (2026)).
- **Prompt-based micro-personalization of an LLM tutor (2026):** Basu, Kakar & Goel (2026) personalize the Jill Watson Large Language Models (LLMs)/RAG (Retrieval-Augmented Generation) teaching assistant at the level of individual questions entirely through prompt engineering — conditioning responses on six learner dimensions (metacognitive Self-Assessment, abstraction, verbosity, perception, processing, understanding) and classifying each query's cognitive demand with a Bloom's Taxonomy classifier, yielding 96 learner profiles with no model retraining. NLP analysis of 2,910 responses and a human study found measurable, perceptible differences in response abstraction, verbosity, complexity, and processing style aligned with intended effects. It demonstrates response-form (rather than content) adaptation as a scalable, modular route to adaptive behavior in a deployed tutor.

Key ITS concepts

- **Knowledge Tracing** — modeling what a student knows over time (Bayesian, deep learning, IRT-based)
- **Cognitive Diagnosis** — fine-grained assessment of which knowledge components and Misconceptions about AI a learner holds; the assessment-side counterpart to Knowledge Tracing that feeds the tutor's pedagogical decision
- **Learner Modeling and Adaptive Instruction** — broader learner representation including affect, engagement, and misconceptions
- **Adaptive Learning** — systems that personalize content sequencing based on learner state
- **Scaffolding** — providing just enough support to enable progress without giving away answers
- **productive struggle** — letting students wrestle with difficulty rather than over-helping
- **feedback loops** — ITS feedback cycles that diagnose, guide, and verify

Historical context

The ITS field has produced landmark systems (Cognitive Tutors, Andes, AutoTutor) and continues to evolve. The Zerkouk et al. comprehensive ITS review catalogs this evolution. The tension between structured ITS

and open-ended LLM tutoring is explored in the correct answer trap research and rethinking scaffolding for LLM tutors.

AI tutoring with LLMs: practical guidance

For instructors deploying AI tutors and developers building them, the knowledge base's findings translate into concrete practice:

Evaluate tutors on whether they teach, not just solve. A model that tops a solving leaderboard is not necessarily a good tutor — task-solving ability and learning-supportive behavior correlate only partially ($r \approx 0.42$), and several models shift rank when scored on pedagogy. Report and scrutinize **solving and pedagogy scores separately**, and prioritize tutors that score on guiding questions, calibrated hints, and non-disclosive scaffolding over those that produce fast answers.(Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact)(Methodologies for improving the quality of AI tutoring in K-12 education)

- **Pedagogical quality is a floor, not proof of learning.** A structured audit of 88 LLM-tutoring studies coding the field as a five-stage loop — learner-state inference, pedagogical action, tutor training, evaluation, student simulation — finds pedagogical evaluation widespread (77/88) but human learning gains in only 10 studies and transfer or delayed retention in one (Adak et al. (2026)).
- **A large multi-discipline randomized trial found adverse effects from a well-grounded tutor.** Liu et al. (2026) randomized 2,379 undergraduates and 30 instructors across 13 blocks and 11 of one U.S. public university's 12 schools to access to a GPT-4o tutor with retrieval over each instructor's own course materials, embedded in the LMS with citations to slides and lecture-video timestamps. In the exact-match sample — sections of the same course — access reduced final grades by 4.12 points (0.37 SDs) and GPA-scale letter grades by 0.13 SDs, while the full sample showed no significant achievement effect; engagement fell in both samples (recorded participations −0.90 SDs, active days −0.51 to −0.61 SDs). Only about 15% of treated students used the tool and users averaged roughly four sessions, yet classroom-level behavioral differences were large, and 73.8% of 3,460 classified requests were direct-answer requests rather than practice or feedback on the student's own attempt. The authors read it as a technical-versus-instructional integration gap: no treatment-group instructor reported integrating the tool into assignments and most left it in the default direct-instruction mode, so course grounding and convenient access did not produce productive use.

Design for pedagogical structure, not frequency. The educational payoff of AI tutoring depends on *how* the tool is used and designed, not on how often it is used. Instructor-designed tutors scoped to course objectives, learner proficiency, and a curated knowledge base outperform unstructured general-purpose chatbot use.(Instructor-Designed AI Tutors in University Foreign Language Education: A Mixed-Methods Study of Learner Motivation and Reflective Learning Experience Based on Self-Determination Theory) A preregistered randomized field experiment tested that claim against the realistic alternative rather than an AI-free baseline: 86 students in an online-MBA corporate-finance module were assigned to a tutor grounded in the module's own lectures, readings and problem sets or to a holdout that kept standard resources with consumer AI freely available, and tutored students gained 6.63 more points of 55 (95% CI [+1.95, +11.31], p

= .007) while the share of short written answers at relational quality or better rose from 8% to 49% against 8% to 27%. Channel was the null margin — voice nearly doubled interaction density and cost 2.8× more to deliver, yet weekly mastery differed by −0.01 points of 11 (p = .98) — which makes delivery format an adoption and engagement lever rather than a learning technology. The holdout did not close the gap either: the nine students reporting external-AI use gained no more than the eight reporting none (+10.3 versus +12.8 of 55, p = .45).

Use iterative live evaluation to keep improving. Because LLMs are opaque, treat evaluation as the engine of improvement: instrument a small set of quality and engagement metrics, run live experiments on models, prompting, personalization, and agents, and let data drive changes — the same discipline Khan Academy applies to its K-12 tutor (Khanmigo).(Methodologies for improving the quality of AI tutoring in K-12 education)

Support the learner's autonomy, competence, and relatedness. AI tutors work best when they feel like a safe, structured practice space rather than an answer machine. Provide immediate, nonjudgmental Feedback; scope the tutor to the learner's level so competence is achievable; and preserve learner agency by keeping the tutor a complement to (not a substitute for) other instruction.(Instructor-Designed AI Tutors in University Foreign Language Education: A Mixed-Methods Study of Learner Motivation and Reflective Learning Experience Based on Self-Determination Theory)

Guard against answer disclosure. The central failure mode of LLM tutoring is giving the answer away, which inflates immediate performance while undermining durable learning. Use Socratic prompting, calibrated hints, and non-disclosive scaffolding — and measure outcomes on unassisted, transfer tasks, not just in-tool performance.(Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact)(Socratic Method)

- **Numbering-only references defeat retrieval.** In a bilingual RAG tutor for a 400-student data science course, posts citing "P2 Q10" retrieved poorly until an extraction stage rewrote them as standalone questions, after which 97.46% of programming references resolved (Shen et al. (2026)).
- **A visual channel shifts tutoring toward checking work, and proactivity toward repair.** With a phone camera on the page, correctness feedback rose from 40% of tutor messages to 63-69% and error identification from 20-22% to 41%, while a proactive tutor that waited after 96% of 5,047 paper analyses was rated supportive (5.53 of 7) rather than interrupting (2.45) (Kotalwar et al. (2026)).

Separate diagnosis from feedback. LLM tutors reliably confirm correct steps but over-reject valid-but-suboptimal reasoning and over-validate incorrect solutions — and accurate diagnosis does not reliably yield actionable feedback.(Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most) The coupling also cuts the other way: Reddig et al. (2025) found GPT-4 still crafted relevant, general-but-correct feedback ~74% of the time even after misdiagnosing an error (by restating the concept or expected answer format), yet almost all factually incorrect feedback followed a wrong diagnosis — so error identification remains the crux of actionable tutoring. A hybrid architecture works best: let a knowledge-grounded classifier handle solution diagnosis while the LLM focuses on open-ended scaffolding and dialogue. - **Fairness auditing is becoming part of tutor evaluation.** EduFair-Bench holds the simulated student fixed and varies only demographic attributes, showing that tutoring quality is not uniform across

learners and that reward-tuning pedagogy does not automatically remove those differences (EduFair-Bench: Evaluating Pedagogical Fairness of LLM Tutors Across Student Demographics).

- **More scaffolding and more context are not automatically better.** A 2×2 randomized trial with 132 introductory Python students compared four GPT-4o teaching assistants differing only in system prompt and supplied context, and the Socratic assistant with full problem context - the configuration closest to pedagogical intuition - was rated significantly less supportive of task completion (mean rank 48.63, $\mu = 3.53$) than the other three ($\chi^2(3) = 12.14$, $p = .007$). Socratic conditions sent more queries ($\mu = 11.1$ per problem without context) while no-context students wrote longer messages, doing the contextual work themselves, and the lowest share of full-comprehension post-task explanations (48%) and the highest external-LLM use (23%) also fell in the Socratic + Full Context condition (Eastwood et al. 2026).

AI tutoring as a spectrum of relational intensity

A unifying lens from the Stanford SCALE / NSSA brief (Turano et al. 2026) reframes AI tutoring as **not a monolith but a spectrum** defined by *relational intensity* — the depth and consistency of the human connection between student and tutor. The brief maps models from fully human-led tutoring (in-person or remote), through **human-led with AI support** (AI assists the tutor behind the scenes) and **AI-led with human support** (a human oversees and intervenes), to **AI-only tutoring** (no direct human oversight). The central finding: as direct human relationships decrease, the evidence base becomes thinner, and unresolved questions accumulate about student safety, developmental impact, and long-term efficacy.

- **AI augments, does not replace, high-impact tutoring.** The brief's core message is that AI is best used to *enhance tutor effectiveness and educator capacity* within high-impact tutoring (regular school-day sessions, small-group ratios ≤ 1:4, well-trained consistent tutors, data-driven instruction, vetted materials, strong student-tutor relationships) — not to substitute for the human-led relationship that drives learning gains. This aligns with the knowledge base's broader finding that pedagogically designed AI tutors outperform general-purpose chatbots (Stanford evidence base, umbrella review).
- **Dosage, not model capability, is the binding constraint.** The brief reports that AI-led tutoring inherits the dosage evidence base (~90 minutes weekly) only when scheduled, supervised, and protected within the school day; in a study of 181,000 students on a supplemental math platform, only 5% reached the recommended minutes and 41% never logged on, with teacher/school/district factors explaining 57% of usage variance. This converges with the field-experiment evidence above (Khanmigo, NUMI) that engagement and integration, not raw capability, determine whether AI tutoring helps.
- **Human oversight improves engagement and alignment but not dosage.** The brief's RCTs found human check-ins raised elementary students' engagement with an AI platform but did not reach the dosage associated with gains nor improve reading achievement. The practical implication: schedule and supervise AI tutoring on the same terms as human-led tutoring, and design for enforcement of engagement — the opt-in requirement an on-device AI tutor reintroduces is exactly what live school-day tutoring eliminates.

- **The relationship is the irreducible element.** The brief emphasizes that AI does not yet replicate human relationships, and that relationship-building (especially consistent tutor-student pairings) improves engagement, attendance, motivation, and outcomes. Developers describe using AI's strengths rather than replacing relationships — a design stance echoed in SafeTutors and affective tutoring research.
- **Safety and privacy are non-negotiable guardrails.** For direct-to-student AI, the brief calls for strict student data privacy safeguards, Guardrails on student safety, and attention to the depth of unmonitored interaction — open questions remain about AI companions' effects on developing minds and prosocial development.

This relational-intensity framing is the "not a monolith" counterpoint to the field: evaluating any AI tutor should begin by asking *which conditions of effective tutoring it reproduces, changes, or drops* — rather than asking whether "AI tutoring works" in the abstract. The brief's human-led baseline can also be absent entirely: a six-week pre-test/post-test study across three Kwara State colleges of education gave 240 technical-education students a localized tutor fine-tuned on Nigerian technical curricula and reported roughly double the practical-skill gain of 120 conventionally taught peers. Practicals there ran above 100:1 student-to-lecturer ratios with feedback delayed by days, so the authors' rationale was not augmentation but equitable *substitution* for scarce instructional staff — casting the tutor as a capacity subsidy for rural colleges rather than a complement to plentiful human tutoring. Two design choices carry the practitioner lesson: the tutor explains an error rather than only flagging it, and a "Clarify" feature restates technical terms in Yoruba or Nupe, adapting to the learner's language context rather than only their knowledge state; hints rather than answers and a safe-to-fail space are credited with the reported confidence increase in most of the AI-assisted group against fewer than half of controls. The evidence is indicative only — no effect sizes, an unnamed base model, self-reported confidence — but it marks the boundary the brief leaves open, the setting where AI is asked to stand in for absent instructional capacity. It ties the tutoring page to K-12 policy (Educational AI Policy), Privacy, Pedagogical Safety, and the human-in-the-loop concerns throughout (Impact of real-time AI feedback on the technical skill acquisition of STEM students in Colleges of Education in Kwara State).

Practical design and development guidance

Design for learning, not just performance. The strongest causal finding is that unguarded AI tutors raise assisted practice performance but *reduce* unassisted learning — the performance–learning gap. Guardrail against answer-copying by scaffolding **hints instead of answers** (require a student attempt before revealing output), and verify gains on unassisted, closed-book measures rather than in-tool performance.(Generative AI without guardrails can harm learning: Evidence from high school mathematics)(Distinguishing performance gains from learning when using generative AI)

Make hints genuinely productive, not bypassable. Classic hint designs can enable "button-through" strategies that skip learning. Prefer hints that reveal reasoning steps incrementally (Socratic prompting) over hints that directly supply the next answer, and preserve productive struggle rather than over-helping. (Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems)(Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments)

Keep the human in the loop. Let teachers author or curate the problem sets and misconception prompts the tutor draws on, and surface the tutor's reasoning so its decisions are auditable. Interpretable Knowledge Tracing and explicit, external didactic layers make LLM tutor behavior traceable and reproducible. (Interpretable Knowledge Tracing)(A didactical-driven teacher assistant for a dimensional modeling course)

Model the learner, not just the dialogue. Attach structured Learner Modeling and Adaptive Instruction and Knowledge Tracing components to LLM dialogue so the system can adapt difficulty and diagnose misconceptions from evidence rather than responding fluently but blindly — quality depends on both the base model and how it is adapted.(EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners)

Yet off-the-shelf models may not supply that evidence: Worden et al. (2026) tested four frontier systems zero-shot against IRT ground truth on 2,548 mathematics items and found knowledge tracing barely beat a 51.3 percent always-correct baseline, reaching only 56.2 percent at best.

Start from open tooling where possible. Open-source agentic tutoring frameworks (e.g. Deeptutor) lower the barrier to a citation-grounded, difficulty-calibrated tutor you can inspect and extend.(DeepTutor: Towards Agentic Personalized Tutoring)

Audit the knowledge-component model against learning curves, then redesign from what the data shows. A classroom crossover study applied Huang et al.'s data-driven redesign process to four units of a middle-school mathematics ITS chosen by topic, not redesign suitability. Learning-curve analysis in DataShop revealed an unmodeled interpolation skill and conflated sign-handling cases; splitting these KCs and adding focused practice with mastered-step skipping produced more productive time-on-task (38.9 vs. 31.6 active minutes, $p < .001$) and five additional skills mastered in the same class time — but no learning-gain difference. The null is explained by thin practice dose (below 70% AFM mastery in both conditions) and a post-test that lacked items on the newly split skill. Two lessons for developers: post-tests must cover newly discovered skills, and adaptive benefits are bounded by the practice students actually receive. (Evaluating a data-driven redesign process for intelligent tutoring systems)

Effective tutoring requires continual adaptation: Zhang et al. (2026) evaluate whether LM tutors adapt to learners' evolving understanding at teacher-annotated decision points. They find frontier models default toward over-helpfulness and rarely push for rigor, and that evaluation-aware prompting improves but does not fully solve adaptivity. Each additional impasse turn lowered next-turn recovery odds by 12.7%, and questioning lost value with depth (scripted question × depth AOR = 0.78) while addressing the student's error grew more beneficial (AOR = 1.14) — a tutor's escalation, not just its answer-withholding, must change as an impasse persists (Ahtisham et al. (2026)). A systematic view of the RL-driven branch of this adaptation comes from Riedmann, Schaper & Lugrin (2025), whose review of 89 RL-in-education studies finds classical RL policies more consistently effective than Deep RL and RL adaptation delivering significant gains more often for guidance-related tasks (hints, Feedback) than for content scheduling — evidence that how an ITS adapts scaffolding matters as much as which algorithm it uses. - **Adapting the type of cognitive engagement, not just the intensity.** Tithi et al. (2026) held difficulty constant and varied the worked-example form — guided (active) or buggy (constructive) — via a BKT rule and a deep-RL policy, both beating random assignment (posttest 72.3 and 72.5 vs 65.7).

- **Deceptive overgeneralization (An et al. 2026)** shows ITS mastery stopping rules (BKT, 95% threshold) can end practice before learners learn *when to withhold* a skill: learners who

overgeneralized misapplied actions on first “do-not-act” items at 61.5%–100%, and targeted refrain-practice with constraint-naming Feedback reduced this to near-floor. Correctness-based mastery inference is necessary but not sufficient for ITS adaptivity.

- **Graph-based ITS for dynamic domains.** A graph-based intelligent tutoring system combines an Evolving Knowledge Space Graph with generative AI content creation and Bayesian knowledge propagation — which showed the highest knowledge gains — supporting adaptive learning in dynamic curricula.
- **Rule-integrated LLM tutoring for procedural domains.** Looi, Liu, and Sun (2026) tackle the inconsistency and pedagogical opacity of LLM tutors in primary mathematics through a design science study of a rule-guided system organized around a three-layer architecture — *diagnosis → intent selection → constrained response generation*. They formalize the distinction between **rule-guided scaffolding** (governed by auditable, replicable rules) and **ad-hoc scaffolding** (helpful moves difficult to audit or replicate). Evaluated via persona-based simulated dialogues and a classroom pilot with 40 Grade 5 students, rule-guided scaffolding improved interactional consistency, reduced premature answer-giving and early closure, and sustained cognitive engagement — while the classroom pilot surfaced interactional complexities, fragmented inputs, and attentional fluctuations that Simulation missed. This is a concrete blueprint for guardrailing Large Language Models (LLMs) tutors in well-defined procedural domains.
- **Multi-agent tutoring and automated assessment.** Multi-agent tutoring systems are being benchmarked with synthetic, trace-based evaluation. ASTRA supports alone-tutor, pair-tutor, and pair-multiagent configurations with socially differentiated agents, enabling reproducible analysis of interaction and participation balance in introductory programming. In parallel, context-aware prompting automates coding of collaborative problem-solving skills from process data, supporting large-scale tutoring assessment.
- **Design with the learner’s values, not just for learner performance.** Value Sensitive Design work with community college students and instructors in developmental math shows that the ethical dimensions of ITS are not separable add-ons: engaging students and instructors directly produced 16 value-aligned features spanning explainability (comprehension-check interpretation, learning-path connection, communicating the model’s confidence), learner control (control over re-assessment, review, pace, and AI-assistance level), and Privacy (data-repurposing control, permission prompts for sharing learning analytics and affective states). The study frames a persistent design tension — student agency vs. system-guided scaffolding — and notes that most institutions disable adaptive tutoring entirely, so value-informed design also depends on how (and whether) ITS AI capabilities are actually deployed.
- **Teachable agents and the classification of disengaged dialogue:** Rho et al. (2026) ran a GPT-4-Turbo teachable agent inside Math Nation (Algebra and Geometry), where students identified which of two worked solutions contained a misconception, justified the correction, and taught the agent — a Learning by Teaching structure with a separate mentor agent scoring explanation quality. Over 6,933 problems opened and 22,143 interactions logged, they built a six-category conversational-disengagement classifier (human-in-the-loop: 1,682 annotated utterances, fine-tuned LLaMA 3, weighted F1 = 0.910, model-vs-human $\kappa = 0.624$) and used it to study 246

middle-school students. The methodological contribution is as important as the finding: when a classifier labels most of the corpus, prevalence results must be stress-tested against the human-annotated subset — and here the headline association (False Answering and Mocking predicting higher post-test) evaporated under exactly that test.

Common Misconceptions

“A stronger model makes a better tutor.” Effectiveness hinges on pedagogical design — Scaffolding, feedback quality and the balance of autonomy and guidance — rather than on the underlying model. The clearest demonstration is the Apprentice Tutor College Algebra ITS: supplying GPT-4 with the tutor’s *interface structure* and Bayesian Knowledge Tracing skill estimates produced gains that the bare model did not, because the knowledge of how to teach lived in the system around the model.

“Training pedagogy into a model and prompting pedagogy at it are the same intervention.” They are distinct routes with distinct evidence. LearnLM mixed pedagogical data into Gemini’s post-training and was preferred by education experts over GPT-4o (**+31%**), Claude 3.5 Sonnet (**+11%**) and base Gemini. Prompt instructions are a cheap version of that; they do not reproduce a model whose disposition was shaped on pedagogical data.

“Intelligent tutoring was a pre-LLM technology that LLMs superseded.” The lineage is continuous and the ITS contribution is what the LLM era is still missing. ITS supplied the learner model, the interface constraints and the mastery estimates; modern systems that add an LLM to those components outperform the LLM alone, which makes the older discipline an ingredient rather than a predecessor.

“An AI tutor is a single kind of thing.” Tutoring spans a spectrum of relational intensity, from hint generation to sustained dialogue, and design conclusions from one point on that spectrum do not transfer to another. The pedagogical design question is therefore always “which kind of tutoring, doing what task” rather than “does AI tutoring work”.

Connected Concepts

- Scaffolding
- Adaptive Learning
- Cognitive Diagnosis
- Large Language Models (LLMs)
- Learner Modeling and Adaptive Instruction
- Knowledge Tracing
- Feedback
- AI Feedback Quality
- Socratic Method
- Personalized Learning
- Self-Regulated Learning
- Generative AI
- AI in Education

- Metacognition
- Pedagogical Safety
- Privacy
- Educational AI Policy
- Guardrails
- K-12
- Speech and Voice Technologies

Connected Articles

- MUSE: Revealing Responsiveness Gaps of LLM Tutors on Multiple-Solution Programming Problems — MUSE: revealing responsiveness gaps of LLM tutors on multiple-solution programming problems (Cen & Sonkar 2026)
- Supporting or Replacing Students' Reasoning? Cognitive Offloading in AI-Assisted Proof Learning — Supporting or replacing students' reasoning? Cognitive offloading in AI-assisted proof learning (Chen et al. 2026)
- TutorCaseBench: A Case-Grounded Benchmark for Evaluating LLM Tutors in Supporting Students with Challenging Behaviors — TutorCaseBench: evaluating LLM tutors on students with challenging behaviors (Park et al. 2026)
- Exploring Visual Access and Proactive AI Tutoring for Handwritten Mathematics — A camera on handwritten work: visual access and proactive repair (Kotalwar et al. 2026)
- Disengaged Conversational Behaviors and Learning in Student-AI Dialogues for Mathematical Problem Solving — Disengaged conversational behaviors and learning in student-AI dialogues (Rho et al. 2026)
- AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting — AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting (Kestin et al. 2025)
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- Value-sensitive design in action: Designing student-centered intelligent tutoring systems with community college students and instructors — Value-sensitive design of student-centered ITS in community college developmental math
- A Prompt-Engineering Approach to Develop Scalable, Flexible, and Real-Time Hybrid Micro-Level Personalization in a General Purpose AI Teaching Assistant — Prompt-engineering micro-personalization of an AI teaching assistant (Basu, Kakar & Goel 2026)
- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)

- AI Tutoring is Not a Monolith: What We Actually Know — AI Tutoring is Not a Monolith: What We Actually Know (Stanford SCALE/NSSA brief)
- Impact of real-time AI feedback on the technical skill acquisition of STEM students in Colleges of Education in Kwara State — Real-time AI feedback for technical skill acquisition in Kwara State colleges of education: a localized tutor framed as a staffing subsidy
- Control vs. Agency: Exploring the History of AI in Education — Traces ITS lineage from 1960s-70s expert systems to cognitive tutors
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- One click away: AI tutoring with Khanmigo in a two-year school experiment — One Click Away: Khanmigo in a two-year school experiment
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most — Benchmarking LLM feedback agents with KG ground truth (Yasir et al. 2026)
- Instructor-Designed AI Tutors in University Foreign Language Education: A Mixed-Methods Study of Learner Motivation and Reflective Learning Experience Based on Self-Determination Theory — Instructor-Designed AI Tutors in University Foreign Language Education (Self-Determination Theory)
- Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact — Measuring Whether LLM Tutors Teach or Solve
- Methodologies for improving the quality of AI tutoring in K-12 education — Methodologies for Improving the Quality of AI Tutoring in K-12 Education
- When Help is Unhelpful: Evaluating AI Tutors for Productive Struggle — When Help is Unhelpful: evaluating AI tutors for productive struggle
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive ICAP scaffolding in an ITS (BKT vs DRL)
- The Evidence Base on AI in K-12: A 2026 Review — Tutoring-specific vs. general-purpose AI: evidence on durable learning outcomes
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — SafeTutors and pedagogical safety
- MathBuddy: Affective Math Tutoring — MathBuddy affective math tutoring
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — Virtual tutoring with CAL: an experiment in take-up and learning
- LearnLM: Improving Gemini for learning — LearnLM: improving Gemini for learning

- TeachLM: Post-training LLMs for education using authentic learning data — TeachLM: post-training LLMs with authentic learning data
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models
- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models
- Reinforcement Learning in Education: A Systematic Literature Review
- Arthur: An artificial intelligence powered teaching assistant system for Engineering Economics class
- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomized Trials of an AI Tutoring Platform in GCSE Science
- Misconception Acquisition Dynamics in Large Language Models — tutor models that acquire many student misconceptions without losing correct solving
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming — Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — A multi-discipline RCT of a course-grounded, LMS-embedded AI tutor: final grades down 0.37 SDs in the exact-match sample, platform participation down 0.90 SDs, with no instructional integration (Liu et al. 2026)
- Examining Variation in How Guided AI Tutors Resolve Student Impasses — Variation in how guided AI tutors resolve student impasses, and why escalation must change with depth
- Evaluating a data-driven redesign process for intelligent tutoring systems — Evaluating a data-driven redesign process for intelligent tutoring systems: more productive time-on-task and skills practiced, but no learning-gain difference when practice dose is thin (Lyu et al. 2026)
- RegulaTutor: A Theory-Informed Framework for Long-Term Personalized Learning — RegulaTutor: A Theory-Informed Framework for Long-Term Personalized Learning (Li et al. 2026)
- Teacher-mediated multimodal platform and math achievement: Evidence from Goblins' yearlong district implementation — Full-district teacher-mediated AI math rollout: ~51% engagement fidelity and a dose gradient from 0.11 SD (2 problems/week) to 0.31 SD (20+/week); larger exploratory associations for IEP, EL, and Hispanic students
- Do LLM Tutors Actually Teach? A Process-Centered Synthesis of the Tutoring Loop — Do LLM Tutors Actually Teach? A Process-Centered Synthesis of the Tutoring Loop

- FoundationalASSIST: An Educational Dataset for Foundational Knowledge Tracing and Pedagogical Grounding of LLMs — Yet off-the-shelf models may not supply that evidence: Worden et al
- Multi-sourced AI Tutor for Non-Native English Speaker Students — Multi-sourced AI Tutor for Non-Native English Speaker Students

Connected FAQs

- How Can AI Agents Support Students and Instructors?
- What Are Best Practices for Developing an Effective AI Tutor?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- How Do We Make a Simulated Student Behave Like a Real Learner?

Adaptive Learning

> **Adaptive learning** — AI-driven educational systems that adjust content, pacing, and instructional strategies based on individual learner characteristics and performance. Adaptive learning is the operational goal of much AI in education research: using student models to personalize instruction.

Questions to Consider

- 'Adaptive,' 'personalized,' 'individualized,' and 'customized' learning are often used interchangeably — but research suggests they are not the same. What do you assume each word means, and where might those assumptions be wrong?
- An adaptive system adjusts content and difficulty based on a model of what you know. What could go wrong if that model rests on shallow or unreliable signals about your learning?
- A key finding is that systems inferring mastery from correct answers can stop practice too early — before you learn when to withhold an action. Can you think of a skill where being 'correct' repeatedly still left you unprepared for a real situation?
- Over-adaptation can remove the productive struggle students need to learn deeply. If AI keeps making things easier the moment you struggle, what exactly does the learner lose?
- Meta-analysis suggests the adaptation mechanism — not the specific tool generation — drives learning gains. If the 'how' matters more than the 'which tool,' what should you look for when choosing adaptive software?
- LLM-based tutors can now adapt language and explanation style, not just difficulty. When does personalizing the way something is explained help learning, and when might it quietly undermine the learner's own agency?

Introduction

Core mechanisms

- **Measure-model-adapt loop:** Knowledge Tracing estimates what the student knows, Learner Modeling and Adaptive Instruction represents the learner, and the system adapts difficulty, content, and Feedback accordingly.
- **Personalization at scale:** Personalized Learning systems use adaptive algorithms to serve unique learning paths for each student. Deeptutor and elementary fraction tutors demonstrate adaptive personalization in practice.
- **Content sequencing:** Adaptive pretesting and lesson plan transformers optimize the order and type of content presented.
- **ITS integration:** Intelligent tutoring systems are the canonical adaptive learning platform, combining diagnosis with adaptation.
- **AutoML-driven profiling and diagnosis:** Traditional educational models struggle to process multi-source, heterogeneous learning-behavior data, which limits learner profiling and diagnostic

model development. A personalized neural cognitive architecture search framework driven by automated machine learning integrates multi-modal educational data with heterogeneous methods, generating diagnostic models tailored to heterogeneous learner profiles and supporting dynamic rather than static analysis of learning processes.

Effectiveness evidence

The knowledge base documents mixed evidence: adaptive systems improve outcomes when adaptation is grounded in reliable student models, but poorly-calibrated adaptation can harm learning. Personalization research distinguishes effective adaptation from superficial customization. Systematic reviews find that "adaptive," "personalized," "individualized," and "customized" learning are used inconsistently — so effect sizes depend heavily on how adaptation is operationalized, and the field calls for a unified framework.

A PRISMA 2020 review that screened 959 records down to 22 higher-education interventions counts adaptive pathways and recommender systems among the leading AI applications, but most studies improved existing practice rather than transforming it (AlSheikh et al. (2026)).

Pedagogical grounding, not technical capability, drives adaptation. A 15-year review of 127 intelligent tutoring studies finds most systems built around what the technology can do rather than a stated pedagogical principle, and puts the average ITS gain at roughly 20% against up to 98% for human tutoring (Zerkouk et al. (2025)).

Take-up, not the adaptation mechanism, was the binding constraint in a two-year district RCT: collapsing enrollment to a single step raised first-session take-up from about 45% to 83% on design changes alone, and intent-to-treat gains grew as take-up rose (Oreopoulos et al. (2026)).

A PRISMA-aligned review of 44 studies finds the engagement literature skewed toward behavioral engagement and thinnest on agentic engagement, and reports a novelty effect — engagement declining over time in longitudinal studies of ALEKS and W-Pal once the tool's novelty faded (Simon, Zeng & Fryer (2026)).

The AI era: LLM-based adaptation and its risks

Generative AI has expanded what adaptive systems can do — conversational agentic tutors, RAG (Retrieval-Augmented Generation)-grounded content, and Large Language Models (LLMs)-driven tutoring adapt not only problem difficulty but language and explanation style (e.g., LearnMate-2, Deeptutor, multi-agent adaptive tutoring). However, LLM-based adaptation introduces new risks: without reliable student models, adaptation may be based on shallow signals; over-adaptation can reduce the productive struggle students need (see Desirable Difficulties, Cognitive Offloading); and the balance between personalizing and preserving learner Learner Agency is an open design question (see agentic AI). A learner-requested variant of adaptation runs without any student model at all. In Sidorkin's (2026) graduate course the readings adjusted only when students asked follow-up questions to reframe, deepen, simplify or localize them, and comprehension-oriented requests reliably produced denser Scaffolding (3.4x to 8.7x more definitional markers than baseline text). Requiring at least three follow-up questions per reading turned the material into an interaction. It also relocates the adaptive burden onto the learner: adaptation here happens only if the student knows what to ask for.

Relationship to personalized learning and intelligent tutoring

Adaptive learning is frequently conflated with personalized learning, but they differ. **Adaptive learning** is the *mechanism* — real-time adjustment of content, pacing, and difficulty based on a learner model. **Personalized learning** is the *broader goal* of tailoring the whole learning experience to an individual, of which real-time adaptation is one implementation. Adaptive systems are the canonical *means* toward personalization. Intelligent tutoring is the classic *platform*: ITS combine diagnosis (student modeling, knowledge tracing) with adaptation, and LLM-based tutors adapt conversationally. Together with personalized learning, adaptive learning is an application-side member of the learner modeling and adaptive instruction family — consuming the learner representations that student modeling, Knowledge Tracing, and Cognitive Diagnosis produce.

Research evidence

- **Meta-analytic evidence on adaptive + AI tools.** A World Bank meta-analysis of 14 RCTs pools adaptive computer-assisted learning, intelligent tutoring, and generative AI on a common scale, estimating an average learning gain of ~0.125 sd with no significant difference between the two technology generations — evidence that the adaptation mechanism, not the specific tool generation, drives gains.
- **Interpretable rating plus time-budgeted routing.** Sahu et al. (2026) keep a few explicit learner scalars — rating sensitivity, response quality and momentum — and route questions under a time budget, cutting rating-update volatility roughly in half against fixed Elo while trailing neural knowledge tracing on prediction (AUC 0.7532 against GKT's 0.8658).
- **Adaptive algorithms compared in dynamic domains.** Graph-based ITS research compares multiple adaptive learning algorithms (including Bayesian knowledge propagation and intuitionistic fuzzy logic) in a graph-based knowledge representation framework for dynamic curricula.
- **RL as an adaptation mechanism, empirically mapped.** Riedmann, Schaper & Lugrin (2025) synthesize 89 RL-in-education studies and find adaptation splits into content-related (instructional sequencing/content scheduling, n = 53) and guidance-related (hints, Feedback, activity selection, n = 36) mechanisms — with RL showing statistically significant superiority over baselines more often for guidance-related adaptation than for content scheduling. They recommend model-free RL for adaptive learning and caution that classical RL outperformed Deep RL in the reviewed studies.
- **Correctness-based adaptivity can stop practice too early.** An, McLaren, and Stamper (2026) found that adaptive systems inferring mastery from correctness risk terminating practice before learners encounter contexts where the learned action should be withheld — leaving deceptive overgeneralization undetected. They recommend including "do-not-act" detector tasks before mastery stopping rules trigger, so adaptation tests conditional understanding (knowing when to withhold an action), not only correctness.
- **A mastery streak is not durable learning.** In a 6,000-student middle-school field experiment, an AI-supported three-correct-in-a-row mastery rule raised platform-defined attainment by roughly

28.7 percentage points without improving a delayed test a week later, so mastery metrics need validating against delayed learning rather than standing in for it (Oreopoulos et al. (2026)).

- **Adapt the *type* of cognitive engagement, not only the difficulty.** Tithi et al. (2026) found BKT and deep-RL policies assigning guided (active) or buggy (constructive) worked examples both beat random assignment in a 113-student logic tutor (posttest 72.3 and 72.5 vs 65.7), with BKT serving low Prior Knowledge students best and DRL the high.
- **More feedback is not better feedback.** In an eight-week adaptive stochastics course (194 students), directive, informative and transformative feedback were taken up differently, and transformative feedback was associated with cognitive overload rather than better regulation — adaptivity has to match the learner's phase and need, not maximize feedback density (Mejeh & Fromm (2026)).
- **A profile is not a trait.** Strategy scores varied mainly by context rather than by student, with a mean intraclass correlation of 0.14 across 234 primary-school learners, and 74.6% of high-coordination-demand failures looped straight back into another failure without intervention (Geoffre, Yuan and Geoffre (2026)). Adaptation built on a stable learner type discards most of the signal; reading the state a learner is in does not.
- **Engagement profiles as adaptation targets.** An, Hammock & Goel (2025) traced 315 online learners building 822 models in VERA and classified their engagement into Observation, Construction, and Exploration profiles, finding that learners tend to progress from construction-focused behavior toward fuller, hypothesis-driven Exploration while Observation persists across phases. They argue adaptive and personalized design should recognize these profiles and target feedback (e.g., recommending similar models or supporting deeper conceptual understanding) to move surface-level observers toward more integrative, full-cycle modeling.
- **A memory that is read but not written is not adaptation.** CoLearn's frozen-memory control served fixed items while still reading the learner profile, and the share of items aimed at a genuinely weak skill fell from 0.72 to 0.57, with final mastery error rising above the adaptive condition (He et al. (2026)).
- **The gain came from sequencing, not from a smarter tutor.** Chung et al. (2026) trained a personalized tutor with LLM-guided reinforcement learning and deployed it in a five-month Python course across ten Taipei high schools, randomizing 770 students between adaptive and fixed easy-to-hard problem sequences. Adaptive sequencing raised the in-person, unassisted final exam score by 0.156 SD (0.150 SD with controls) — while mediation analysis attributed the effect almost entirely to engagement (0.185 SD via time on task, 0.149 SD via attempts) rather than to easier or harder material, and gains were largest for beginners and lower-tier schools. The adaptive lever was the order of practice, not the quality of the chat.
- **Keep mastery decisions rule-based and confine machine learning to monitoring.** An eight-week adaptive STEM program for 30 sixth-graders governed pathways by rule-based mastery while machine learning tracked performance, keeping adaptation auditable, but with no pretest and one classroom per condition, its gains are a pilot template to validate locally (Bin Bakheet et al., 2026).

- **Adapt the bottleneck attribute, not the weak average.** Transition modeling of knowledge states ranked analytical thinking as the hardest to acquire and the easiest to lose — lowest forward transition probability 0.31 and highest backward 0.22-0.23 — making re-practice of the flagged attribute a sharper adaptation target than overall mastery (Feng & Huang, 2026).
- **Adaptation from process sequences, not aggregate scores.** Wong, Bulathwela & Cukurova (2026) derived scaffold rules by mining the *order* of 65 students' dialogue turns in triads, moving adaptive learning from aggregated behavioral or performance measures toward individual process sequences; maximal scaffolding raised on-task behavior but also scripting, and the design is untested.

Common Misconceptions

- **"Adaptive means personalized means individualized."** Systematic reviews find these four terms used **inconsistently across the literature**, which means reported effect sizes depend heavily on how adaptation was operationalized rather than on adaptation itself. A meta-analysis pooling studies that used the words differently is pooling different treatments, and the average describes none of them.
- **"Mastery reached in the system is mastery learned."** In a **6,000-student middle-school field experiment**, an AI-supported three-correct-in-a-row mastery rule raised **platform-defined attainment by roughly 28.7 percentage points without improving** a transfer measure. The rule optimized the platform's own criterion. This is the clearest available demonstration that a mastery signal is a model of learning, not learning.
- **"Correctness-based adaptivity knows when to stop."** An, McLaren, and Stamper (2026) found systems inferring mastery from correctness risk **terminating practice too early** — the system reads a correct run as understanding and withdraws the practice the learner still needed. Adaptivity that stops on success can subtract exactly the trials that produce retention.
- **"The bottleneck is how good the adaptation is."** In a **two-year district RCT**, the binding constraint was **take-up**: collapsing enrollment to a single step raised first-session take-up from about **45% to 83%** on design changes alone, and intent-to-treat gains grew accordingly. The cleverest adaptation serves nobody who never reaches it.
- **"Engagement persists once established."** A PRISMA-aligned review of **44 studies** found the engagement literature skewed toward behavioral engagement and thinnest on agentic engagement, and reports a **novelty effect** — engagement declining over time in longitudinal studies of ALEX and similar systems. Early engagement is not a stable property of the design.

What this means for practice

For instructors and designers

- Define mastery by what you need to be true, not by what the platform can see. The 28.7-point attainment gain with no transfer improvement is the failure mode to design against: if the criterion is three in a row, three in a row is what you will get.

- Keep practice going past the correctness signal for anything you need retained. Use spaced and interleaved review rather than trusting an adaptive system to decide when a learner is done.
- Remove enrollment friction before tuning the algorithm. 45% → 83% take-up from collapsing a step outperformed most pedagogical improvements in this literature.
- Plan for engagement decay. Longitudinal work documents decline; a design that depends on sustained voluntary use needs a reason to keep being used.
- Check which construct a system claims to adapt on. Behavioral engagement is the most studied and the least informative about learning; agentic engagement is thinnest in the evidence base.

For developers

- Report the operational definition of "adaptive" alongside any effect size you cite, because the literature's definitions diverge and pooled numbers inherit that ambiguity.
- Distinguish your mastery criterion from learning outcomes in your own validation. If your validation measure is the same signal that drives the adaptation, it is not independent evidence.

Connected Concepts

- Online Teaching and Learning — Online Teaching and Learning
- Knowledge Tracing
- Personalized Learning
- Intelligent Tutoring
- Learner Modeling and Adaptive Instruction
- Scaffolding
- Cognitive Diagnosis
- Large Language Models (LLMs)
- Learning Analytics
- Higher Education
- K-12
- Formative Assessment
- Behaviorism
- Technologies — Umbrella: AI technologies and techniques (models, LLM training, robotics, RAG, agentic)
- Recommender Systems and Learning Paths

Connected Articles

- MARS: A Momentum-Aware Adaptive Rating System for Personalized Assessment — MARS: A Momentum-Aware Adaptive Rating System for Personalized Assessment
- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Deceptive overgeneralization: adaptive mastery can stop practice before learners know when to withhold an action (An, McLaren & Stamper 2026)

- AI Tutoring is Not a Monolith: What We Actually Know — AI Tutoring is Not a Monolith: What We Actually Know (Stanford SCALE/NSSA brief)
- Towards an adaptive AI scaffold for developing student collaborative problem solving
- Fostering self-regulated learning through adaptive learning technology: A differentiated perspective on the role of feedback
- A systematic review of student engagement research in adaptive learning platforms — Systematic review of student engagement in adaptive learning platforms
- AI-enhanced problem-based learning framework: integrating ChatGPT as adaptive scaffolding to improve critical thinking and personalized learning
- Artificial intelligence and student engagement in online learning: a literature review
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — Virtual tutoring with CAL: an experiment in take-up and learning
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- AI-Powered Math Tutoring: Platform for Personalized and Adaptive Education — Adaptive/personalized multi-agent math tutoring (Chudziak & Kostka 2025)
- Redefining personalized learning in the artificial intelligence era: an updated systematic review from 2019 to 2025 — Redefining personalized learning: systematic review
- DeepTutor: Towards Agentic Personalized Tutoring
- Exploring Fraction Comprehension and Interest in Elementary Education Through AI-Powered Personalized Learning
- Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study
- AdaPT: Adaptive Lesson Plan Transformer for Cross-Regional and Differentiated Instruction
- Comprehensive Review of Intelligent Tutoring Systems
- The Evidence Base on AI in K-12: A 2026 Review — Tutoring-specific AI calibrated to learner readiness vs. general chatbots
- Using context-based and AI-enhanced approaches to improve student engagement and achievement in secondary chemistry education — Context-based 7E + AI instruction in secondary chemistry
- Developing deep learning in science through an adaptive AI-based STEM instructional program: evidence from sixth-grade classrooms — Adaptive AI-based STEM program for deep learning
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Bayesian cognitive diagnosis optimizes personalized learning paths via mediation of cognitive load and Hidden Markov Model state transitions — Bayesian cognitive diagnosis for personalized learning paths
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive ICAP scaffolding in an ITS (BKT vs DRL)

- Can EdTech close learning gaps? Global evidence from digital interventions — Meta-analysis pooling adaptive + AI-enabled tools across 14 RCTs
- Mapping artificial intelligence integration in higher education: A systematic review using the FACETS and SAMR frameworks — Systematic review: adaptive pathways among the leading higher-ed AI integration use cases
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis
- Reinforcement Learning in Education: A Systematic Literature Review
- Effective Personalized AI Tutors via LLM-Guided Reinforcement Learning — Adaptive problem sequencing beats fixed sequencing: +0.156 SD on an unassisted exam, mediated by engagement rather than difficulty (Chung et al. 2026)
- CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop — CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop
- Making Reasoning Visible: Configuration-Aware Diagnostic Modeling for Adaptive Scaffolding in Structured Reasoning Tasks — Strategy use is state-dominant (mean ICC 0.14), so static learner profiles discard most of the signal

Personalized Learning

> **Personalized learning** — tailoring educational experiences to individual learner profiles, including prior knowledge, learning pace, preferences, and affective states. AI enables personalization at scale, though the gap between *system personalization* and *learner-perceived personalization* remains an open measurement challenge. Alongside adaptive learning and intelligent tutoring, it is one of the application-side members of the learner modeling and adaptive instruction family — consuming learner models to adapt instruction.

Questions to Consider

- When you think of 'personalized learning,' do you imagine content tailored to a learner's pace, or to their chosen goals? The page says these are deeply different (uniform outcomes via varied paths vs. diverse outcomes). Which do you value more, and why?
- The page distinguishes personalized learning (the goal) from adaptive learning (one mechanism). Can you think of personalization that doesn't involve real-time adaptation—and does it still count?
- A system can adapt without the learner ever feeling recognized. When have you experienced being 'personalized to' without feeling genuinely known? What's the difference?
- The page flags that over-personalization can strand learners in low-expectation tracks. How might well-intentioned AI tailoring accidentally lower the ceiling for a learner?
- Personalization needs detailed learner data; privacy needs data minimization. Where do you draw the line between 'enough data to adapt' and 'so much that the learner is exposed'?
- What would an AI need to remember about you across sessions to genuinely personalize your learning—and what are the risks of it remembering those things?

Introduction

Tailoring educational experiences to individual learner profiles, including prior knowledge, learning pace, preferences, and affective states. AI enables personalization at scale, though the gap between *system personalization* and *learner-perceived personalization* remains an open measurement challenge.

- **Mishra et al.** distinguish two forms of personalization with deep historical roots — uniform outcomes reached via varied paths (Skinner's teaching machines to Khan Academy-style mastery tutoring) vs. diverse, learner-chosen outcomes — mapping onto the field's control-vs-agency tension.
- **Personalization can be met by generating the material rather than finding it.** DagFlow-AI generates synthetic statistics datasets matched to a student's stated interest, the course learning objectives and the intended skill level, a three-way match the authors argue real datasets rarely satisfy (Arthur et al., 2026). The limit is built in: synthetic data cannot teach data collection, measurement or study design, so the tool complements real data rather than replacing it.

Architectures for AI-Driven Personalization

Longitudinal Memory (PersonaVLM → Education)

Nie et al. (2026) developed a Multimodal AI long-term memory architecture (PersonaVLM) that maintains persona consistency across interactions. Mapped to education, this enables tutoring systems that remember a learner's Misconceptions about AI, preferred explanations, and progress history across sessions—addressing a critical deficit in stateless chatbot tutors.

Agent-Native Personalization Substrate (DeepTutor)

Zhao et al. (2026) design every feature of DeepTutor to share a common personalization substrate, rather than bolting personalization onto reactive tools. This architecture ensures cross-modality coherence: the same learner profile drives problem solving, question generation, and collaborative writing.

Multi-Agent Social Personalization (MAIC)

Yu et al. (2024) personalize not only content but *social context*. Classmate archetypes (Class Clown, Deep Thinker, Note Taker, Inquisitive Mind) create varied peer-learning dynamics matched to individual learner needs.

AutoML for Learner Portraits

Personalization is a central objective for improving educational quality, yet processing multi-source heterogeneous learning-behavior data remains a challenge. A personalized neural cognitive architecture search framework, driven by automated machine learning, builds learner portraits and generates diagnostic models for heterogeneous learner profiles, integrating multi-modal data to move beyond static examination outcomes.

A static knowledge base cannot personalize: ontologies evolve slowly and handle uncertainty poorly, so the architecture matches representation to knowledge type — declarative to ontologies, procedural to rules, uncertain to fuzzy or probabilistic ontologies, implicit to analytics and machine learning — and prefers a system of small mapped ontologies to one monolithic model (Ivanova, 2026).

Relationship to adaptive learning and intelligent tutoring

Personalized learning is often conflated with adaptive learning, but they are not the same. **Adaptive learning** refers to the *mechanism* — a system adjusting content, pacing, and difficulty in real time based on a learner model. **Personalized learning** is the *broader goal* — tailoring the full learning experience (content, pathways, pacing, preferences, goals) to an individual, of which real-time adaptation is one implementation. Adaptive systems are a *means* toward personalization, but personalization can also be achieved through static learner profiles, choice-based pathways, or human-tutor tailoring that does not adapt in real time.

A PRISMA 2020 review of 22 higher-education interventions places personalized-learning support and adaptive pathways among the dominant AI use cases, yet most implementations improved existing practice rather than transforming it (AlSheikh et al. (2026)).

Intelligent tutoring sits in between: ITS are the canonical *adaptive* platforms that deliver personalized instruction through structured student modeling, while Large Language Models (LLMs)-based tutors personalize conversationally. All three are the application-side members of the learner modeling and adaptive instruction family — they consume the learner representations produced by student modeling, Knowledge Tracing, and Cognitive Diagnosis to decide what to teach next. The distinction matters for evaluation: studies that label a system "adaptive," "personalized," or "individualized" interchangeably (see below) can obscure whether the claimed benefit comes from real-time adaptation, learner choice, or content tailoring.

Measurement Challenges

- **System vs. perceived personalization** — A system can adapt without the learner feeling recognized
- **Longitudinal validity** — Personalization benefits may decay if profiles become stale or overfit
- **Equity risks** — Over-personalization can strand learners in low-expectation tracks
- **Bias risks** — Conditioning on student attributes can encode stereotype: with essays held constant, feedback for students marked by race, language, or disability became more praising and less critical (Tan, Phalen & Demszky (2026)).

Personalization and assessment

Personalization and Assessment are tightly coupled in AI-driven learning. Adaptive personalization depends on ongoing formative measurement of what a learner knows (via Knowledge Tracing, Learner Modeling and Adaptive Instruction, and Cognitive Diagnosis) to decide what to adapt next — so the reliability of the Assessment signal directly constrains the quality of personalization. Conversely, when summative assessment is personalized per-learner, fairness and comparability become harder to establish. The knowledge base's research warns against over-adapting to shallow or noisy signals: adaptive systems that mis-measure a learner can personalize in ways that reduce learning rather than support it, and AI-native students whose Self-Assessment is unreliable (an "absent cognitive baseline") are harder to model accurately.

Personalization in the AI era

The strongest evidence that this concern is not hypothetical comes from a three-wave longitudinal study of 486 Chinese undergraduates (Li, Lin & Qiu, 2026). It found that the more personalized students perceived their AI-adaptive environment to be, the *lower* their self-regulated learning. The study names this the "personalization paradox." Shifts in academic emotions carried most of the effect: encountering the adaptive environment predicted less enjoyment and more anxiety and boredom, and those emotional changes together accounted for roughly half of the association between personalization and reduced self-regulation. AI literacy buffered the damage, weakening the negative emotional association to non-significance at high literacy. Personalization therefore appears to buy adaptive fit at a cost to the learner's own regulatory activity, and the study points to emotional experience — not only cognitive load — as the channel through which that cost is paid.

Where the diagnosis behind a path is validated, personalization pays off by lowering load rather than by covering more: shortest-path remediation averaged 3.82 steps and cut study time 22.0% (57.6 versus 73.8 minutes), with cognitive load carrying 53.7% of the post-test effect (Feng & Huang, 2026).

Evidence for the tool can itself be negative at small scale: in a five-day elementary fraction trial (final n = 22), the business-as-usual group showed significantly greater comprehension gains than the AI-adaptive Mathbot group, and the authors flag grade-level confounds, guessing and licensing cost as limits — an "adaptive" label carries no effect (Holman (2024)).

Reinforcement learning is a distinct mechanism for personalization, and Riedmann, Schaper & Lugrin (2025) map its empirical track record: their PRISMA review of 89 RL-in-education studies finds RL personalization concentrated in Higher Education and Math Education, with adaptation implemented mainly as content scheduling (n = 53) or guidance-related personalization such as hints and feedback (n = 36). They report that RL policies beat non-adaptive baselines most often on guidance-related adaptation and on affective variables (63% of tested studies), and that learning gain — especially normalized learning gain — was the most effective reward source — practical guidance for designing reward signals that personalize toward genuine learning rather than engagement.

Wang et al. (2026) show the reward objective is itself a personalization choice: an RL coach trained on the learner's independent competence cut lap time 27.9% ($p = 0.005$) where rule-based fading produced no reliable change, and the authors argue coding agents optimized for task performance carry no incentive for what the human retains.

Bernstein and Sibia (2026) sharpen a distinction between interest personalization and expertise personalization: interest-matched GenAI analogies were reported as more engaging and memorable but not uniformly more trusted, and some students preferred the generic technical explanation even when the analogy matched their stated interest, for self-sufficiency and completeness (Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education). Their design recommendation is to personalize through source-domain structure and to ask students what they already know, not only what interests them, since familiarity with a source domain is what lets a learner inspect the analogy. They also recommend giving learners control over personalization through a menu of analogies, opt-in, or offering generic and personalized versions together. Sidorkin (2026) documents a further pairing at the level of course materials rather than individual explanations: weekly readings generated on demand for a graduate educational leadership course were tailored at once along interest (sector, professional role, local examples) and comprehension level (pacing, definitions, depth). The resulting logs shared a common backbone (TF-IDF cosine similarity of 0.50 to 0.61), which he reads as a template with adjustable dials rather than a wholesale rewrite per learner. The same corpus shows that tailoring was structural but uneven in intensity: artifact-level tailoring markers averaged 52.24 per 10,000 words and ranged from 38.74 to 74.29 across logs, while comprehension-oriented prompts produced 3.4x to 8.7x more definitional Scaffolding than baseline explanatory text.

A third axis of personalization is the *goal*, and it is the input AI planners handle worst. Liu et al. (2026) paired 2,000 synthetic learner personas with a 347-textbook, 4,092-concept prerequisite graph and asked ten LLMs to plan, step by step, which knowledge a learner should study to reach a stated target unit. The models produced structurally sound curricula — DeepSeek-V3.1 reached 90.9% on prerequisite-and-hallucination validity — while failing to adapt them to the learner. Adaptivity topped out at 44.7%, DeepSeek-V3.1's final

pass rate was 29.5% in Basic Education and 14.6% in Higher Education, and removing the mastery field from the persona cost up to 26.1 percentage points of adaptivity while leaving validity almost unchanged. Generating the whole path in one pass instead of interactively raised validity by as much as 30.8 points while cutting adaptivity by 28.8. The claim “personalized” is a claim about responding to a learner’s state, and the state variable is the part these planners can most easily do without — a computational counterpart to the measurement concern above.

A fourth axis is the *audience* rather than the individual learner: Bespoke regenerates an existing lecture for a named professional group (healthcare, finance, or energy), and its expert raters scored industry-framed versions 0.32 points higher on personalization depth (3.97 vs. 3.65) while audience calibration lagged (3.52). Tailoring to a cohort rather than to a learner is a cheaper and more tractable form of personalization, but the rubric that measured it assessed judged fit, not learner outcomes.

Personalization can outweigh a human presenter: in a large online course (493 respondents), students ranked AI-generated personalized videos above non-personalized human-recorded ones (mean rank 2.26 versus 2.69) and 88.4% ranked some personalized video first, against 73.8% for human-recorded (Tomlinson et al. (2026)).

How strong is the evidence

The only pooled estimate available here comes from a meta-analysis of four controlled studies covering 420 students, all in computing and engineering higher education (Govea Sotomayor & García Ortiz, 2026). The random-effects pooled effect is large, $g = 1.01$ (95% CI 0.33–1.68), and that number should be read as a caution rather than a headline. With four studies, the Hartung-Knapp adjustment widens the interval to −0.10 to 2.11 ($p = .063$), which includes no effect.

Heterogeneity is severe: $Q(3) = 25.20$, $I^2 = 88.8\%$, $\tau^2 = 0.41$. The 95% prediction interval, −0.42 to 2.43, means a new implementation could plausibly yield a null or negative result. Two of the four studies were at serious risk of bias and carried 53% of the weight. Publication bias was not assessable, because the usual tests need at least ten studies.

GRADE certainty was rated very low. The honest reading is that the point estimate is large and the interval is too uncertain to act on. The pooled outcome was academic performance in computing and engineering courses, not learning broadly. Claims that AI personalization works should carry that qualifier, since this is the thinnest base on which the page’s evidence rests.

Prompt-conditioned micro-personalization

Basu, Kakar & Goel (2026) show that the gap between system and perceived personalization can be addressed at the response level. Their framework for the Jill Watson Large Language Models (LLMs)/RAG (Retrieval-Augmented Generation) tutor combines learner-selected preferences (abstraction, verbosity, perception, processing, understanding) with system-inferred cognitive demand (Bloom’s Taxonomy) to produce 96 micro-profiles adapted at each interaction via structured prompt conditioning — no retraining, no domain-specific authoring. This is a hybrid of adaptability (learner-driven preference selection) and adaptivity (system-driven cognitive assessment), showing that personalization of *how* content is presented can be both scalable and perceptible to learners.

Terminological ambiguity

A recurring problem is that "personalized learning" is a broad, loosely defined umbrella term. Systematic reviews (Khalifeh et al., 2026) find that adaptive learning, individualized instruction, customized learning, and personalized learning are used interchangeably, with no universally accepted definition — a source of conceptual ambiguity that complicates research synthesis and evidence-based practice. The field increasingly calls for a unified framework and definition so that "personalized" denotes a precise, evidence-backed claim rather than a vague label (a point reinforced by the knowledge base's critique of weak construct use).

Common Misconceptions

"Personalized learning and adaptive learning are the same thing." Adaptive systems are one *means* toward personalization, not its definition. Personalization can equally be achieved through static learner profiles, choice-based pathways, or human-tutor tailoring that never adapts in real time. Treating the two as synonyms makes a school that offers rich learner choice but no adaptive engine look unpersonalized, and makes a tightly adaptive drill look more learner-centered than it is.

"Personalization pays off by covering more ground." Where the diagnosis behind a path is actually validated, it pays off by *lowering load rather than by coverage*: shortest-path remediation averaged 3.82 steps and cut study time 22.0% (57.6 versus 73.8 minutes), with cognitive load carrying the effect. The benefit is fewer unnecessary steps, not more content per hour.

"A model that can generate a coherent curriculum can personalize it." Generation and adaptation are different capabilities, and the gap between them is large. Curriculum generators were strong on prerequisite-and-hallucination validity — DeepSeek-V3.1 scored 90.9% — but weak on adapting to the learner: adaptivity peaked at 44.7%, and DeepSeek-V3.1's final pass rate fell to 29.5% in the Basic condition. Prerequisite validity is not personalization.

"Generating the material removes the constraint real content imposes." Generation relaxes one constraint and cannot relax others. DagFlow-AI generates synthetic statistics datasets matched to a student's stated interest, the course objectives and the intended skill level — a three-way match real datasets rarely satisfy — but its authors state the limit plainly: synthetic data cannot teach data collection, measurement or study design, so the tool complements real data rather than replacing it.

"Reported learning gains are what validate these systems." In the RL and personalization studies surveyed here, policies beat non-adaptive baselines most often on guidance-related adaptation and on affective variables (63% of tested studies), while learning gain — especially normalized learning gain — was the *least* commonly reported outcome. A literature that reports engagement and affect far more than learning is not evidence that learning dominates.

Implications for Practice

For instructors

- Ask what is being adapted before believing the word "personalized": the content, the sequence, the pace, the affect, or the presentation. Different adaptations carry different evidence, and only some have learning outcomes attached.

- Prefer systems that shorten the path over systems that add content. The measured benefit in the remediation study was 22% less study time, not more coverage.
- Keep the parts of the discipline a generated dataset cannot supply — data collection, measurement, study design — as real work, and let personalization operate on the practice around them.

For developers

- Report learning outcomes, not only engagement and affect. The survey finding that learning gain is the least-reported measure is a description of what the field is currently shipping, not a template to copy.
- Distinguish generation quality from adaptation quality in your own evaluation, ideally reporting both separately, because strong prerequisite validity can coexist with adaptivity under 50%.
- Treat the reward objective as a personalization choice in its own right: an RL coach trained on the learner's independent competence cut lap time 27.9% ($p = 0.005$) where rule-based fading produced no reliable change.

For researchers

- Stop conflating personalization with adaptation in the constructs you measure, and say explicitly which mechanism produced the effect.
- Report normalized learning gain as a primary outcome; its scarcity in the literature is a gap to close rather than a convention to inherit.

Connected Concepts

- Adaptive Learning — Adaptive systems that tailor content, pacing, and difficulty to the learner in real time
- Intelligent Tutoring — Tutoring systems that model the learner and deliver individualized instruction
- Learner Modeling and Adaptive Instruction — Representing learner knowledge, skills, and states that drive adaptation
- Knowledge Tracing — Inferring mastery of knowledge components from performance over time
- Cognitive Diagnosis — Diagnosing latent learner knowledge and attributes from responses
- Scaffolding — Support and fading calibrated to individual learner needs
- Student Experience — The learner's lived experience of personalization
- Learning Analytics — Data-driven measurement of learning that informs adaptation
- Formative Assessment — Ongoing assessment that signals what to adapt next
- Summative Assessment — Endpoint assessment whose comparability personalization complicates
- Generative AI — LLM-based conversational personalization
- Edtech Platform — Platforms that deliver personalized learning at scale
- Higher Education — Higher-education context for personalization
- Online Teaching and Learning — Online Teaching and Learning
- Recommender Systems and Learning Paths

Connected Articles

- Bespoke: Generating MOOC-Quality Industry-Personalized Lecture Videos at Scale — Industry-personalized lecture video regeneration from a seed transcript: audience-level tailoring, rated by domain experts (Puech et al. 2026)
- A Prompt-Engineering Approach to Develop Scalable, Flexible, and Real-Time Hybrid Micro-Level Personalization in a General Purpose AI Teaching Assistant — Prompt-engineering micro-personalization of an AI teaching assistant (Basu, Kakar & Goel 2026)
- AI Tutoring is Not a Monolith: What We Actually Know — AI Tutoring is Not a Monolith: What We Actually Know (Stanford SCALE/NSSA brief)
- Control vs. Agency: Exploring the History of AI in Education — Distinguishes two forms of personalization (uniform vs diverse outcomes)
- Redefining personalized learning in the artificial intelligence era: an updated systematic review from 2019 to 2025 — Redefining personalized learning: systematic review
- DeepTutor: Towards Agentic Personalized Tutoring — Agent-native personalization substrate for tutoring
- Ontology-based layered hybrid AI-driven knowledge model for personalized e-learning — Ontology-based layered hybrid knowledge model for personalized e-learning
- Exploring Fraction Comprehension and Interest in Elementary Education Through AI-Powered Personalized Learning — Personalized adaptive learning for elementary fractions
- AI Coaching for Accelerating Human Skill Development with Reinforcement Learning — Reinforcement-learning coaching for skill development
- Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos — Students prefer personalized AI-generated videos over non-personalized human-recorded ones (Tomlinson et al. 2026)
- Bayesian cognitive diagnosis optimizes personalized learning paths via mediation of cognitive load and Hidden Markov Model state transitions — Bayesian cognitive diagnosis for personalized learning paths
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Instructor and AI roles in the chemistry classroom: Future science teachers' perceptions in a ChatGPT-enhanced formative assessment — Instructor and AI roles in ChatGPT-enhanced formative assessment
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: bias in personalized automated feedback
- Mapping artificial intelligence integration in higher education: A systematic review using the FACETS and SAMR frameworks — Systematic review: adaptive pathways & recommenders are a top AI integration use case in higher ed
- Reinforcement Learning in Education: A Systematic Literature Review

- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- The personalization paradox: how AI-driven adaptive learning environments are associated with college students' academic emotions and self-regulation learning—a moderated mediation model — Personalization paradox: perceived adaptive personalization linked to lower self-regulated learning via academic emotions, buffered by AI literacy (Li, Lin & Qiu 2026)
- PersonaPath: Towards Knowledge-Centric Personalized Learning Path Planning — PersonaPath: LLM planners reach 90.9% validity but no model exceeds 44.7% adaptivity when personalizing paths to a stated learner goal (Liu et al. 2026)
- AI-based personalized learning and academic performance in computing and engineering higher education: a systematic review and meta-analysis of controlled studies — Four studies, a large pooled effect, and very low certainty

Recommender Systems and Learning Paths

> **Recommender systems and learning paths** — the part of adaptive and Personalized Learning technology that decides *what a learner should encounter next* and in what order: which resource, practice item, or course to rank toward them, and which sequence of concepts to walk through. Its two method families are behavioral — collaborative filtering over interaction logs — and semantic — sequencing over a knowledge graph of concepts, resources, and prerequisite relations — increasingly fused into hybrid models. Because the output is a ranked list rather than a dialogue, the distinctive problems are selectivity and legitimacy: cold start and popularity bias under sparse data, the directional asymmetry of prerequisites, and whether a teacher or learner can understand, audit, and trust the list they are shown.

Questions to Consider

- A recommender learns from what learners clicked, watched, and completed. If the system only sees behavior, whose learning is it actually modeling — and what does it miss for a student who is quiet, struggling, or already knows the material?
- In one study, teachers found curricular-language explanations more understandable and trustworthy than feature-importance charts. What would an explanation of a recommendation have to say before *you* would act on it?
- Prerequisite relations run in one direction only — knowing B does not imply knowing A. Why might a model that scores concept pairs independently get this wrong, and what would go wrong downstream for a learner if it did?
- Path optimization studies report shorter paths and better post-test scores, with reduced cognitive load as the main mediator. Is a shorter path always the better path, or can efficiency remove practice a learner needed?
- An audit of an educational recommender found popular materials still dominated lists after fairness and diversity interventions. If popularity keeps winning, what would make you redesign the objective rather than tune the reranker?
- Learning Design data from 554 courses showed Acquisition (knowledge transmission) as both the most common activity type and the most common entry point. If AI recommends “what comes next” from that data, whose design habits does it reproduce?

Introduction

Educational recommender systems exist because the supply of learning material has outgrown any human’s ability to navigate it. Introductory programming alone has many thousands of practice activities, and organizing them into instructionally meaningful bundles normally requires time-intensive expert curation. A recommender takes a learner’s history, the properties of the material, or both, and produces a ranked shortlist or an ordered path through content.

Where Adaptive Learning describes the mechanism of adjusting content, pacing, and difficulty to a learner model, and Intelligent Tutoring describes the platform that does so in dialogue, recommender research concentrates on the *selection and sequence decision* itself: the ranking function, the structure it ranks over, and the evidence it uses. That decision layer brings its own failure modes, taken up in the sections below.

How Educational Recommenders Work

Behavioral recommenders inherit the logic of collaborative filtering: learners with similar histories are assumed to want similar resources, so the system predicts from co-occurrence rather than content. This is powerful where data are dense and brittle where they are not. Evangelista and Bukhari (2026) state the problem plainly — accuracy-focused recommenders give less reliable support to students with limited participation histories while popular resources dominate lists — and answer it with a Hybrid HKG-GRU framework that embeds a heterogeneous Knowledge Graph of course materials and models learner sequences with a GRU, then trains for robustness across learner groups (GroupDRO) and reranks for exposure diversity (Maximal Marginal Relevance). On Moodle logs from 152 students, 59 resources, and roughly 150,000 interactions it reached HR@10 = 0.68 and MRR = 0.41, but substantial popularity bias persisted at catalog level — evidence that bias mitigation is partial.

Semantic recommenders replace co-occurrence with structure. Liu, Sun, and Song (2026) build a knowledge graph of teaching resources, language concepts, skills, learner groups, and pedagogical attributes, and decompose every resource along four instructional dimensions — teaching context, cognitive level, technological feature, and cultural adaptability. Recommendation expands k-hop over the graph from a learner's stated requirements, refines candidates with a feature-based collaborative filter, and ranks them by a fusion coefficient that rises with the learner's ability, progress, and interest indices, so less-advanced learners get more structured guidance from the graph while higher-ability learners lean on their behavioral pattern. On the English subset of the MARS dataset (4,800 users, 14,200 resources, 132,000 interactions, sparsity 0.9981) it reached NDCG 0.625 and HR 0.751, roughly a 7–8% gain over the best neural baseline, and beat graph-aware baselines including RippleNet and KGAT on coverage and cross-domain accuracy. Ablation shows the signals are complementary (CF-only NDCG 0.584, KG-only 0.604), and the authors note these are ranking metrics, not evidence of learning effectiveness.

A third route avoids per-learner interaction data almost entirely. Hoq and colleagues (2026) extract pattern-based knowledge components from each code sample and recommend related practice activities by the similarity of their knowledge-component sets. On an expert-organized corpus of introductory Python materials, the approach aligned with the instructors' own conceptual bundles and beat knowledge-component and embedding baselines on ranking metrics — evidence that instructional alignment can come from the material's semantics where learner histories are thin.

A fourth route treats recommendation as a sequential decision rather than a ranking. ExRec (Ozyurt, Almaci, Feuerriegel and Sachan, 2025) builds a semantically grounded knowledge tracer — an Large Language Models (LLMs) annotates each question with solution steps and knowledge concepts, contrastive learning aligns question, step and concept embeddings, and a calibration loss lets the tracer predict a concept-level knowledge state directly — and then uses that tracer as the Reinforcement Learning environment in which a policy selects the next exercise. Two design choices matter for the recommender problem specifically: the student state is a compact recurrent encoding rather than the full exercise history, so long sequences stay

tractable in the replay buffer, and the reward is the change in predicted concept knowledge, computed without running inference over every question in the target concept. A model-based value estimation initialises the critic from the tracer, which improved continuous value-based agents across four tasks on XES3G5M (2,048 test students) and pushed them past discrete-action methods on the hardest one — recommending for the student's *weakest* concept, where the target changes at each step. Numbers are percentage-of-maximum knowledge improvement from a simulated environment, which is a weaker claim than measured learning, and the authors' own appendix notes that most tracing datasets record only a binary correctness label, so the misconception-level recommendation they sketch is not yet testable on existing data.

Prerequisites and Path Sequencing

Ranking a next item is easier than ordering a curriculum, because learning dependencies are directional. Cheng and colleagues (2026) argue that treating prerequisite discovery as ordinary link prediction fails on three properties of the relation: it is irreversible, its evidence is often multi-hop (*ci* → *ck* → *cj*) rather than a one-step learner transition, and its relevance is pair-specific, so a concept's representation should change depending on what it is paired with. Their ProPRL model adds an Irreversibility Constraint — an anti-symmetry regularizer penalizing high confidence in both directions of a pair — alongside a pair-conditioned gate weighting resource-aware evidence from a concept-resource hypergraph against behavior-aware evidence from a learning-behavior graph. It ranked first on all nine dataset–metric combinations across MOOC, LectureBank, and University Course datasets, improving on the strongest baseline by 1.96% to 6.11%, and the constraint raised the share of correctly ordered relations from 88.0% to 90.0%.

Once dependencies are modeled, a path becomes an optimization problem. Feng and Huang (2026) combine Bayesian cognitive diagnosis, knowledge space theory, and cognitive load theory: a Bayesian DINA model converged on EdNet data with 91.3% sparsity, and a shortest remediation path algorithm produced personalized paths averaging 3.82 steps — 22.4% more efficient than random paths and 23.6% more efficient than fixed full-coverage paths. In a randomized probability-learning experiment with 120 students, personalized-path learners finished in 57.6 minutes against 73.8 minutes for controls and outperformed controls on the post-test after controlling for pre-test. The study also tests *why*: personalized paths reduced cognitive load on all six adapted NASA-TLX dimensions, and cognitive load was the primary mediator of the effect on post-test performance (indirect effect 0.28 in the multiple-mediation model). A Hidden Markov Model identified Analytical Thinking as the bottleneck attribute, with the lowest forward transition probability (0.31) and the highest guessing parameter (g = 0.28).

PersonaPath pushes the sequencing question further by disputing the *unit* of the decision. Liu et al. (2026) contrast Exercise-Centric recommendation — infer the next item from interaction logs — with Knowledge-Centric planning, in which a planner reads an explicit learner persona, a mastery state and a stated target unit and selects the next textbook, unit and concept from a curriculum hierarchy (347 textbooks, 1,751 units, 4,092 concepts across 77 subjects, with 411 prerequisite edges verified to 99.5% precision at Cohen's κ = 0.93). The distinguishing case is the one logs cannot see: two learners with identical correctness records but different targets need different routes, and only the goal makes that visible. Their closed-loop evaluation of ten LLMs (1B–30B+) separates the dimensions an aggregate metric conflates — DeepSeek-V3.1 reaches 90.9% on prerequisite/hallucination validity but only 44.3% on adaptivity, for a 29.5% final pass rate in Basic Education and 14.6% in Higher Education, and no model exceeds 44.7% on adaptivity anywhere. Two ablations sharpen the diagnosis: removing the mastery field from the persona costs up to 26.1 points of

adaptivity while barely moving validity, and one-shot path generation raises validity by as much as 30.8 points while cutting adaptivity by 28.8 — curriculum-conformant sequencing is a far easier target than learner-conditioned sequencing, which is a caution against reporting path quality without a learner-alignment constraint (PersonaPath: Towards Knowledge-Centric Personalized Learning Path Planning).

Prerequisite structure also works as a diagnostic lens on the curriculum rather than the learner. Medhat and colleagues (2026) classify student questions to an AI teaching assistant against a GPT-4-extracted prerequisite graph, reaching 80.0% accuracy across 43 labels on 1,340 question events from 164 graduate students, and found topic-level question volume correlated with students' self-reported difficulty (Spearman's $\rho = 0.491$, $p = 0.008$). The interaction log becomes a map of where the curriculum's ordering is failing learners, at no added assessment burden.

Explaining and Auditing Recommendations

Ranking quality does not settle whether anyone should follow the ranking. Feldman-Maggor, Cukurova, Kent, and Alexandron (2025) adapt Hoff and Bashir's trust-in-automation model to AI recommendations and test it with 41 in-service chemistry teachers using the recommendation tool GrouPer. Explainability raised Trust indirectly, by raising understandability, and the *form* of the explanation mattered more than its presence: moving teachers from feature-importance ("data-driven") explanations to semantic, curricular-language ("domain-driven") explanations significantly increased understandability ($W = 80.5$, $p = 0.005$), learned trust ($W = 52$, $p = 0.002$), and acceptance ($W = 22.5$, $p = 0.003$), and all seven think-aloud teachers reported the domain-driven explanations as more influential. Two further acceptance drivers appeared, both situational rather than epistemic: pedagogical alignment (reported by 8 of 11) and workload reduction (6 of 11). Several teachers also said explanation alone was insufficient — they wanted classroom experience with the tool before relying on it, a strong claim that trust in a recommender is built over use, not delivered in a legend.

Fairness auditing asks a different question: whose recommendations are worse? The Graph-GRU study is a useful worked example because it names what its audit could not see. Fairness was operationalized through participation-based cohorts because the public Moodle dataset lacked achievement, prior knowledge, learning profiles, and demographic attributes, so the result is an audit of behavior across engagement levels rather than a full assessment of educational equity; a low-activity learner may be struggling, disengaged, or already familiar with the material. Explainability there takes the form of path-based and counterfactual analysis, with median counterfactual stability CR@10 = 1.0 for many learners but persistent catalog-level popularity bias reflected in high Gini exposure metrics. The lesson is that Bias Mitigation must be measured at the level of exposure and learner groups, not inferred from accuracy or from the presence of an explanation module, and that Human-in-the-Loop oversight is meaningful only if the human sees the group-level evidence.

Learning Paths in Practice

Paths are not only computed; they are designed. Divjak, Svetec, and Horvat (2026) turned Learning Analytics on the design process itself, analyzing the sequence of 29,064 teaching and learning activities across 554 courses planned in a free Balanced Design Planning tool. Markov chains and pattern mining surfaced a design grammar: Acquisition-type activities were the most common learning type (above 20%)

and the most common entry point, followed by Practice, Discussion, and Assessment (each 15–20%), and the strongest transition was Assessment → Discussion (0.332), ahead of Practice → Practice (0.317). The rule Acquisition → Assessment → Practice → Practice held at confidence 0.74 (lift 1.45), and learning type tracked the intended outcome's cognitive level: Acquisition fell from about 50% of activities at Bloom level 1 to about 20% at level 6. The authors warn that resemblance to flipped, inquiry-based, or project-based designs is not evidence of intent — but a recommender trained on such design data learns these habits, including a bias toward transmission-oriented opening activities.

At the other end of formal schooling, path structure becomes a AI Governance question. Szekely, Gal-Ezer, and Harel (2026) argue that AI-mediated access to knowledge warrants rethinking fixed higher-education curricula and propose "learnity graphs" — structured representations of learning as interconnected units of knowledge, skills, experience, and artifacts — spanning academic, professional, and personal learning. The proposal keeps the university's role in foundational knowledge while shifting emphasis toward Creativity and interdisciplinary integration, and it makes the learner a maintainer of their own graph, which is where it meets Self-Directed Learning and Self-Regulated Learning. Whether self-directed navigation leads somewhere constructive is not guaranteed: Shen and Arunrugstichai (2026) model two pathways from high-school learning climate to university GenAI use in a cross-contextual survey (N = 508), distinguishing constructive autonomous use from compulsive dependence.

One boundary worth stating: what recommenders currently do is closer to consultation than to collaboration. Mutlu Cukurova (2026) reconstructs what has historically been required before an interaction qualifies as collaborative — a negotiated, partly symmetric relationship, shared and negotiable goals, a low and shifting division of labor, and mutual modeling and socially shared AI Regulation in Education — and concludes that most current human-AI interaction is better described as consultation, governance, delegation, or instruction. His five-level taxonomy (transactional, situational, operational, praxical, synergistic) is a useful calibration: suggesting the next resource is an operational arrangement, and calling it a collaborative learning partner inflates the claim.

How This Page Relates to Personalized, Adaptive, and Tutoring Research

The three adjacent concept pages cover adjacent ground and should be read together with this one. Personalized Learning covers the *goal* — tailoring the whole experience, including goals, preferences, and pace, of which pathway selection is one component. Adaptive Learning covers the *mechanism* — the measure-model-adapt loop that changes content, pacing, and difficulty in real time. Intelligent Tutoring covers the *platform*, the canonical system that combines diagnosis with instructional interaction. This page covers the decision layer those pages presuppose: the ranking and sequencing technology itself. It is the home for collaborative-filtering and knowledge-graph recommender architectures, prerequisite-relation discovery and curriculum ordering, the explainability and fairness of ranked outputs, and the recommender-specific failure modes — cold start, popularity bias, over-narrowing, opaque ranking, and unequal recommendation quality across learner groups. A study reporting NDCG or coverage on interaction logs belongs here; one reporting learning gains from a tutoring dialogue belongs on the tutoring or adaptive-learning page.

Risks and Open Questions

The evidence base has a consistent shape: strong offline ranking metrics, weak evidence about learning. Both recommender studies above are evaluated on historical interaction logs and say so, and the CF–KG authors call explicitly for teacher assessments, learner studies, and outcome-based experiments. Popularity bias survived a fairness-aware training objective in one system, so the field cannot yet point to a reranking or regularization fix that reliably changes exposure, and fairness audits remain bounded by what LMS logs contain. Cold start is addressed architecturally, through semantic structure, but not tested on genuinely new users in live deployment. Path efficiency is better evidenced, yet the efficiency numbers still rest on one study and one algorithm family, and a shorter path is not automatically better if it removes the productive struggle a learner needs. The formal path-optimization work sharpens the point in both directions: guaranteeing a hard problem says little about a particular corpus, since a hill climber hit the top of the interleaving rubric on every real profile despite NP-completeness proofs, and a path graded 3.54 on a theory-derived rubric is still a path nobody has tested on learners, so rubric quality is a designer-facing proxy for outcome evidence rather than a substitute for it. The vocabulary is also unstable: Ikram and colleagues (2026), in a PRISMA review of 31 Scopus-indexed articles (2013–2025), report medium-to-large cognitive effects (g = 0.50–0.70) for AI-enabled adaptive systems that are heavily moderated by implementation quality and study design.

The same literature has begun to propose remedies for narrowing, though not yet to test them. Najem, Zaoui Seghroucheni and Ziti (2026) cluster 14,003 student records on 12 self-reported behavioral, psychological and environmental inputs into six profiles with K-Means++ and strong separation (Silhouette 0.62; η^2 = 0.770 on final grade, with a 40.17-point mean exam-score gap between the highest and lowest profiles), then map profiles to learning objects through an affinity score combined with a Felder-Silverman mapping matrix and a diversity regularization term ($\lambda = 0.30$) whose explicit purpose is to stop a recommender from collapsing into what a profile already prefers. The design is the contribution and the evidence is not: the recommendation layer is conceptual with no deployment or outcome measure reported, and the authors state that the clustering inputs are self-reported proxies rather than LMS interaction traces. It is a candidate answer to the regularization gap this page notes, still awaiting the validation the page says the field lacks.

Common Misconceptions

“A recommendation with a higher accuracy metric is a better learning path.” Ranking accuracy and instructional validity are different claims. On the English subset of the MARS dataset (**4,800 users, 14,200 resources, 132,000 interactions, sparsity 0.9981**) one system reached NDCG 0.625 and HR 0.751, roughly a **7-8%** gain over the best neural baseline — an improvement in predicting what a learner would engage with, which is not the same as what would teach them.

“Prerequisites can be treated as a symmetric similarity relation.” They cannot: prerequisite relations are **directionally asymmetric**, and a model that captures “these topics are related” has captured neither the direction nor the ordering. This is why prerequisite sequencing is a distinct problem from recommendation.

“Sparse data is a technical nuisance.” At the sparsity levels in this literature (0.9981) the system sees almost nothing, which makes cold start and popularity bias structural rather than fixable by tuning. A

recommender trained on that signal will systematically surface what is already popular, and quiet or unusual learners are the ones it cannot see.

“Explainability is a reporting feature.” Whether a teacher or learner can audit a recommendation is a legitimacy condition: a path a student cannot examine is one they cannot contest, which is a governance problem before it is an interface one.

Connected Concepts

- Knowledge Graph — Structured representations of concepts, resources, and prerequisite relations
- Explainable AI — Explanation as a design feature that mediates understandability and trust
- Curriculum Design — Ordering decisions that recommenders model, infer, and reproduce
- Learning Design — The planned sequence of activities that path analyses operate on
- Learning Analytics — The data and methods behind recommendation, and the object of audit
- Cognitive Diagnosis — Diagnosing knowledge states that seed remediation paths
- Knowledge Tracing — Modeling mastery over time to decide what a learner is ready for
- Learner Modeling and Adaptive Instruction — Learner representations that recommendation consumes
- Personalized Learning — The broader goal; this page covers the selection decision
- Adaptive Learning — The real-time adjustment mechanism; this page covers ranking and sequencing
- Intelligent Tutoring — The platform that acts on recommendations in dialogue
- Bias Mitigation — Fairness interventions in ranking and exposure
- Equity — Group-level differences in recommendation quality
- Human-in-the-Loop — Oversight of automated resource navigation
- Self-Directed Learning — Learner-maintained pathways and lifelong navigation
- Lifelong Learning — Graph-structured learning beyond a degree sequence
- Trust Calibration — Matching reliance to recommendation reliability
- Student Support and Success — recommending support, resources, and academic paths

Connected Articles

- A Hybrid Collaborative Filtering and Knowledge Graph-Based Cross-Domain Recommendation Method for Multimodal Teaching Resources — Hybrid collaborative filtering plus knowledge graph for multimodal teaching resources, with ability- and progress-aware fusion (Liu, Sun & Song 2026)
- Fair and explainable educational recommendations with a hybrid Graph-GRU framework — Heterogeneous knowledge graph + GRU recommender with GroupDRO fairness and counterfactual explainability (Evangelista & Bukhari 2026)
- The Impact of Explainable AI on Teachers’ Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations — Domain-driven explanations build more teacher trust than feature-importance charts (Feldman-Maggor et al. 2025)

- ProPRL: Property-Aware Prerequisite Relation Learning in Educational Knowledge Graphs — Prerequisite relation learning with an irreversibility constraint for directional consistency (Cheng et al. 2026)
- Automated Recommendation of Programming Learning Content Using Pattern-based Knowledge Components — Recommending programming practice by pattern-based knowledge-component similarity (Hoq et al. 2026)
- Learning paths and patterns in learning design: Insights from 500+ courses — Markov and pattern-mining analysis of 29,064 designed activities across 554 courses (Divjak, Svetec & Horvat 2026)
- Bayesian cognitive diagnosis optimizes personalized learning paths via mediation of cognitive load and Hidden Markov Model state transitions — Bayesian DINA diagnosis and shortest remediation paths, mediated by cognitive load (Feng & Huang 2026)
- Detecting Knowledge Gaps from Conversational AI Interactions Using Curriculum Prerequisite Graphs — Mapping AI TA questions to a GPT-4-extracted prerequisite graph to find curriculum-level gaps (Medhat et al. 2026)
- Rethinking Higher Education: From Fixed Curricula to Learnity Graphs — Learnity graphs as a lifelong-learning alternative to fixed curricula (Szekely, Gal-Ezer & Harel 2026)
- What do you mean by human-AI collaboration: Prerequisite functions and the affordances needed to achieve it — Five-level taxonomy showing most human-AI interaction is consultation, not collaboration (Mutlu Cukurova 2026)
- How high-school pressure and autonomy support are linked to dual AI learning pathways: A cross-contextual SEM analysis — Autonomy support versus pressure predicting constructive or compulsive AI pathways (Shen & Arunrugstichai 2026)
- Artificial intelligence in education: a systematic review of personalized learning trends and future directions — PRISMA review of personalized learning trends, pathways, and recommendation models (Ikram et al. 2026)
- PersonaPath: Towards Knowledge-Centric Personalized Learning Path Planning — PersonaPath: a Knowledge-Centric planning benchmark showing LLMs reach 90.9% validity but only 44.3% adaptivity (Liu et al. 2026)
- Personalized Exercise Recommendation with Semantically-Grounded Knowledge Tracing — exercise recommendation as a sequential decision over a semantically grounded tracer
- Behavioral clustering for adaptive learning object recommendation in higher education using learning analytics for personalized student success — Behavioral clustering of 14,003 records into six profiles, mapped to learning objects with a diversity-regularized recommendation framework (Najem et al. 2026)

Pedagogical Agent

> **Synthesis**: Pedagogical agents are AI-driven conversational interfaces embedded in learning environments that use pedagogical strategies (eliciting, telling, scaffolding) to support learner engagement, reflection, and metacognition. Designs vary from simple information providers to interactive dialogue partners that adapt to learner states.

Questions to Consider

- Think of a time a chatbot or tutor gave you a perfect answer that left you no wiser. What makes an AI 'teach' rather than merely 'solve'—and why might a benchmark score fail to capture that difference?
- The page finds that tutoring 'solving' scores and 'pedagogy' scores correlate only weakly across models. What should that tell you about evaluating an AI tutor on its ability to answer questions?
- Some designs give AI distinct roles—Teacher, Classmate, Mentor—and even keep a parent centrally involved (as in ParaTutor). In your experience, does giving an agent a clear role change how Learners interact with it?
- Real students often 'bypass' a chatbot's pedagogical framing when the agent's goals clash with the learner's own. Why might a learner rationally ignore good scaffolding, and what does that imply for assuming 'if we build it, they'll engage'?
- Would you rather learn from an AI that tells you things, one that asks you questions, or one that mediates a group discussion? How does your preference shape what you think a 'pedagogical agent' should be?
- From a simple info-provider to a fleet of specialized agents orchestrating a whole course—where do you think the value (and the risk) of conversational AI tutoring actually lies?

Introduction

A pedagogical agent is an interactive AI component within a learning system that engages learners through dialogue, questions, or prompts to support cognitive and metacognitive processes. Unlike passive dashboards or static feedback, pedagogical agents employ evidence-based tutoring strategies — such as eliciting learner self-assessments before providing Feedback, or Scaffolding Problem Solving through Socratic dialogue. The umbrella now covers everything from a single conversational intelligent tutor to fleets of role-specialized agents that lecture, mentor, facilitate collaboration, and even orchestrate course generation, all grounded in decades of intelligent-tutoring-systems research. - **An agent whose role is regulation rather than explanation.** Chen et al. (2026) built SSRLAgent to diagnose a group's shared regulatory state and prompt accordingly, and held a content-support agent constant across both conditions (Chen et al., 2026). Because both arms had an agent and a structured platform, the gains attach to adaptivity in the regulation prompts rather than to the presence of a conversational agent.

How pedagogical agents are studied in the knowledge base

- **Peer versus tutor is a role the interaction produces, and it is judged on social behavior.** Lin et al. (2026) had seven expert researchers solve quadratic equations with an adaptive agent carrying a Big Five persona and motivational modulation, then interviewed them. Participants read the agent as a peer when it created a non-judgmental space, reasoned tentatively, showed appropriate imperfection and respected their pace, and as a tutor when it agreed blindly, disclosed the answer early or fixed the direction of travel — a shift driven by control rather than by correctness. One participant found the agent's mistakes endearing while another found them useless, so peer-likeness and peer-usefulness diverge, and fabricated shared history ("claims I've said some things which I didn't") broke trust faster than any wrong answer. **Design and architecture of conversational agents.** A recurring thread is how agents are structured, not just what models power them. The conversational AI tutors framework argues that proven ITS technologies — Knowledge Tracing, affect detection, student modeling — should anchor generative tutors, keeping the diagnostic backbone while Generative AI supplies flexible dialogue. Multi-agent designs push this further: MAIC replaces the MOOC's "one video for N students" with a Large Language Models (LLMs)-driven classroom of Teacher, Assistant, Classmate, and Analyzer agents to deliver personalized learning at scale, while LecturaAgents adds an embodied ProfessorAgent whose TASA algorithm aligns visible teaching actions (handwriting, highlighting) with learner profiles. Even parent–child tutoring becomes a two-agent problem in ParaTutor, where role-separated scaffolding keeps the parent centrally involved instead of letting a generic chatbot displace them. The same role-based logic appears in Instructional Agents, where Teaching Faculty, Designer, TA, and Program Chair agents collaborate across ADDIE to generate course materials.

A complementary use of role-based agents targets teacher practice rather than student learning: Mohne et al. (2026) combine pedagogical student personas, memory grounded in actual course material, and an LLM-as-a-judge speaker oracle so novice instructors rehearse a small-group section — 254 optional sessions averaging about 16 minutes each, at roughly $0.05–$0.10 per session.

Teaching versus solving behavior. A central empirical finding is that answer-production is not learning support. Measuring whether LLM tutors teach or solve shows solving and pedagogy scores on tutoring benchmarks correlate only weakly (r = 0.421 across eight models), arguing that benchmarks must report pedagogy-oriented criteria — guiding questions, calibrated hints, non-disclosive scaffolding — separately. This aligns with tutoring-specific vs general AI evidence: pedagogically designed tutors with Guardrails mitigate the exam-score drops and suppressed reasoning that raw general-purpose chatbots produce, preserving desirable difficulties and productive struggle rather than short-circuiting them. Yet benchmarks can overestimate how well even scaffolded tutors work in the wild. Rethinking scaffolding in LLM tutors finds that real students frequently bypass a chatbot's pedagogical framing, a rational response to a mismatch between the agent's goals and the learner's own — so uptake must be evaluated, not assumed.

Role in tutoring and collaboration. Agents are increasingly positioned not as answer-givers but as facilitators and mediators. Niari's pedagogical mediator framework reconsiders AI in collaborative learning as an interactional, epistemic, and regulatory mediator — scaffolding participation and shared AI Regulation in Education without displacing teacher or learner agency. Concretely, collaborative AI tutoring (ProPACT)

treats collaboration itself as the object of instruction, forecasting dyadic breakdowns up to 30 seconds ahead and delivering minimally intrusive scaffolds that preserve Metacognition. Embodied inquiry with AI as facilitator shows an AI can complement hands-on model-building by facilitating application of a constructed model, while robot-assisted language learning meta-analysis finds outcomes track how a robotic agent is positioned in instruction (group-based interaction) more than its technical sophistication. Whether the *role* an agent plays is enough, or whether it must also *adapt its behavior*, is questioned by Liao (2026): an elementary "book talk" study found a fixed "student peer" companion sustained longer interactions yet suppressed student agency and hit an "affective ceiling" (weak emotional/future-oriented reflection), arguing that role *labeling* must be paired with role-*adaptive* interaction logic rather than a monolithic single-role design.

Ethics Training Agents (Seo et al., 2026) shows what happens when a pedagogical agent is asked to moderate rather than teach: an LLM facilitator handling turn-taking (stacking with 15-second hand-raise windows), time management (auto-advancing a stage to wrap-up after 9 minutes), and incremental batch summarization reduced participants' cognitive burden and gave them a sense that the discussion was "on track" — one participant contrasted it favorably with ChatGPT, which "can often feel disorganized or make it hard to see the progress of ideas." The same study exposes the ceiling of persona-based agents: the three distinct ethical-orientation agents were rated significantly below human peers on contribution, diversity and influence (Kruskal-Wallis $p < .001$), and participants asked for process-oriented ("how the agent reasons") rather than conclusion-oriented output.

Where conversational agents are (and aren't) used — the umbrella-review picture. The umbrella review of conversational AI agents (Ganguly et al. 2025, 34 reviews) quantifies CAI utilization: teaching and learning support (97.1% of reviews), psychological and motivational support (91.2%), and metacognitive and personal development (88.2%) lead, while administrative support (50%), research and information management (52.9%), and healthcare/medical support (41.2%) trail. It also flags that CAI research lacks end-to-end design guidance, CAI-specific usability methods, and concrete classroom-orchestration strategies for the teacher's role — reinforcing that pedagogical-agent design must be HCI-grounded, evidence-based, and attentive to AI Literacy.(Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use)

Role orientation is a design variable, not a stylistic choice. The physics agent comparison (Wang et al. 2026, 59 learners) isolates prompt-specified role while holding model, platform, and temperature fixed: a teacher-centered agent grounded in a bounded textbook source and answering from the instructor's perspective, versus a student-centered agent configured with knowledge of students' understanding and scripted to diagnose misconceptions, name the concept, and transfer to an analogous case. The student-centered role won on every measured outcome — post-test performance, lower extraneous and higher germane cognitive load, flow experience, and perceived empathy — even though the teacher-centered agent was the one optimized for accuracy and textbook fidelity. This makes *role and interaction pattern* a first-class design parameter alongside prompt and model choice, and shows that empathy can be engineered from conversational structure rather than a differently trained model (Affective Computing).

Authoring intent does not guarantee enacted pedagogy. When 27 middle school teachers configured a teacher-facing chatbot authoring tool, an evaluation of 108 bot-level criterion ratings found generated responses aligned far better with responsiveness (88.9%) and persona (81.5%) than with rules (70.4%) or the stated purpose (59.3%), which the authors frame through pedagogical forms of Norman's Gulf of Execution

and Gulf of Evaluation — configurable controls alone did not make the teacher's instructional intent visible in the bot's behavior (Riahi et al. (2026)).

Agents in immersive and extended-reality settings. Ross and Kaspar (2026) extend the concept into extended reality (AR, augmented virtuality and VR) with ACLIME, a conceptual framework that — unlike CAMIL, CATLM-VR and TICOL — keeps the agent inside the model. It names two interaction modes drawn from the literature: the tutor, offering guidance, encouragement, reflective questioning and explanations, and the role-playing partner, which occupies a defined role inside a scenario such as a local on a climate-change field trip or a negotiating counterpart in corporate training. The agent's body (head-only through full body) and behavior are treated as design surfaces: visual versus behavioral realism, flexible AI control versus fixed rule-based scripting, synthesized versus pre-recorded speech, and nonverbal channels including gaze, gesture and proxemics. Immersion and body-based interactivity are argued to multiply the social cues behind social presence — behavioral realism, not visual realism, is proposed as the decisive predictor — while the learner's own virtual body adds an embodiment dimension (body ownership, virtual own body agency, self-location) and the proteus effect. The framework's explicit trade-off is cognitive: immersion and the agent's mere presence can raise cognitive load even as social interaction with the agent lowers it through the collective working-memory effect, and a temporal layer (familiarization, maturing human-agent relations, novelty decline, developing cybersickness) is added to the usual design variables. Its status is deliberately provisional: hardly any empirical work yet tests pedagogical agents in immersive media, and long-term learning outcomes as well as learner characteristics sit outside the model.

The agent's surface is a separate design axis from its pedagogy. AI Avatars and Synthetic Instructors treats the avatar's identity cues, presence and trust effects in its face and voice as outcomes worth measuring on their own, whatever the agent's scaffolding does.

Evaluation and benchmarks. Measuring a pedagogical agent requires testing pedagogy, not content. The Teaching Monster Challenge benchmarks Pedagogical Content Knowledge by asking agents to adapt a lesson to a specified learner persona, finding systems strong on content but weak at adapting it — and revealing that LLM-judges mis-rank strong systems. EduAgentBench evaluates agents across professional pedagogical judgment, situated multi-turn tutoring, and canvas-style workflow completion, showing models fall short of professional teaching standards. AI-generated interactive fiction adds a design-evaluation angle: coherence and quiz integration, not generation capability, limit usefulness for the student experience. **Stress-test persona robustness over multiple turns.** Shouqi et al. (2026) ran six escalating attacks against role-playing agents with an automated Judge: multi-strategy testing cut robustness by 0.17–0.20 versus a single-strategy baseline, and critical failures clustered after turn 5–6, so short or single-turn evaluations overestimate persona stability and ethical adherence.

- **A peer agent whose fallible suggestions are the point.** Copa pairs log-contextualized retrieval with GPT-4o and a fifteen-chunk task-specific knowledge base, and summarizes each student segment agentically: it compares the student's model to an expert version, diagnoses the expressed problem, and names what to retrieve. Across a classroom study with 16 students and two focus groups, all participants said its guidance supported their problem solving and was accurate, and all would use it again. Several also asked for straight answers, and some assumed a suggestion was correct until their model got worse. The authors read that as the cost of designing an agent to prompt evaluation rather than to answer (Cohn et al., 2025).

Practical guidance

Design for the learner's agency, not the model's convenience. Favor tutoring-specific guardrails — Scaffolding, hints, Socratic questioning, misconception targeting — over raw answer generation, since solving and teaching diverge. Distribute support by user role (parent vs child, peer vs peer) rather than through a single generic interface, and treat collaboration as a valid target for scaffolding. Don't assume students will take up scaffolding; evaluate uptake in real contexts. Build human oversight into authoring — as PromptDecipher does by making teacher QA of bot responses a first-class activity — and choose cheaper backends where quality holds. Report teaching and solving scores separately, and validate generated content with users rather than assuming generation equals usefulness.

Learner preference is a poor proxy for scaffolding quality: students in AI-supported mathematical modeling performed best with Peer and Teaching Assistant roles yet rated the more directive Tutor and Excellent Student roles highest on usefulness and Self-Efficacy (Zhu, Yang and Yang (2026)).

A review of 46 studies of AI agents in computer-supported collaborative learning distinguishes cognitive scaffolding, social facilitation and instructional orchestration, and finds cognitive gains consistent while behavioral, social and emotional outcomes are context-dependent — so the agent's function should be chosen for the outcome it is meant to produce (Ba et al. (2026)).

Connections to related concepts

Pedagogical agents sit at the intersection of Intelligent Tutoring (their diagnostic backbone of Knowledge Tracing and student modeling) and Generative AI/Large Language Models (LLMs) (their delivery engine). They operationalize Scaffolding and Feedback, aim at Metacognition and Self-Regulated Learning, and increasingly target Collaborative Learning. Safety concerns recur across Pedagogical Safety, authoring quality, and the risk that agents offload learning rather than support it. All of this is evaluated through AI Ed Evaluation and benchmarks that must measure teaching, not just solving.

Crucially, pedagogical agents are judged by their learning gains, not by how fluently they respond. The knowledge base's evidence is that agents produce durable gains when designed as tutoring-specific coaches with guardrails — tutoring-specific AI consistently outperforms general-purpose chatbots — and can harm learning when they substitute for the learner's effort (the guardrail RCT, LLM-reliance and grades). Measuring an agent's Learning Gains therefore requires unassisted, transferable outcome measures, not in-tool performance.

Better feedback is not the same as better learning: customizing an agent with knowledge bases and a workflow raised feedback accuracy and specificity but left self-regulatory behaviors, learning experiences and outcomes unchanged, and its gain advantage appeared only under directive feedback (Han et al. (2026)).

Common Misconceptions

- **"Authoring intent determines what a pedagogical agent does." Authoring intent does not guarantee enacted pedagogy.** When **27 middle school teachers** configured a teacher-facing chatbot authoring tool, evaluation of 108 bot-level criteria showed the enacted behavior diverged from what teachers intended. The tool mediated the pedagogy.

- **“A pedagogical agent moderating discussion is a solved role.”** Ethics Training Agents (Seo et al., 2026) shows what happens when an agent is asked to **moderate rather than** instruct — a qualitatively different demand from answering questions, and one the literature treats as unsettled.
- **“The evidence base for computer-assisted instruction is thin.”** A synthesis (**2025, 34 reviews**) quantifies CAI utilization across teaching and learning support (**97.1% of reviews**), psychological and motivational support (**91.2%**) and **metacognitive** support. Breadth of reviewed application is extensive, which makes the gap one of enacted quality rather than coverage.

Connected Concepts

- Learning Gains
- Pedagogical Safety
- Agentic AI
- AI in Education
- Intelligent Tutoring
- Scaffolding
- Metacognition
- Feedback
- Collaborative Learning
- Large Language Models (LLMs)
- Generative AI
- Student Experience
- Knowledge Tracing
- Self-Regulated Learning
- Human-in-the-Loop
- Cognitive Offloading
- Benchmark
- AI Ed Evaluation
- Socratic Method
- Teaching
- AI Avatars and Synthetic Instructors

Connected Articles

- Comparing teacher-centered and student-centered agents based on prompt engineering: Effects on learning performance, cognitive load, flow experience, and empathy perception in physics learning — Student-centered agent role outperforms teacher-centered role across performance, load, flow, and empathy (Wang et al. 2026)
- Learning with pedagogical agents in extended reality: A conceptual research-based framework of agent-centered learning in immersive media environments (ACLIME) — ACLIME: conceptual

framework for pedagogical agents in AR/VR — tutor vs role-playing partner, realism, presence, cognitive load (Ross & Kaspar 2026)

- Face value: How avatar identity shapes epistemic trust in AI-mediated learning
- Artificial intelligence and student engagement in online learning: a literature review
- AI-Generated Interactive Fiction for Educational Use: A Pilot Study of Perceived Comprehensibility, Coherence, and Engagement
- Embodied inquiry with AI as facilitator: An exploratory case study
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning
- Adversarial Stress Testing of Role-Playing Language Agents using Multi-Agent Evaluation
- Findings of the first Teaching Monster Challenge: A benchmark of pedagogical content knowledge in AI agents
- Advancing diagram-based reasoning in AI tutoring systems: A structural approach for STEM education
- TeachArena: Are language agents ready for realistic teaching work?
- From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents
- Rethinking Scaffolding in LLM Tutors: The Interactional Mismatch Between Benchmarks and Real-World Deployments
- LecturaAgents: A Multi-Agent Framework for Adaptive Personalized AI-Assisted Learning and Embodied Teaching
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis
- Measuring Whether LLM Tutors Teach or Solve: A Diagnostic for Educational Impact
- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming
- The Path to Conversational AI Tutors: Integrating Tutoring Best Practices and Targeted Technologies to Produce Scalable AI Agents
- Instructional Agents: Reducing Teaching Faculty Workload through Multi-Agent Instructional Design
- The Evidence Base on AI in K-12: A 2026 Review
- ParaTutor: Coordinating Parent-Child Math Tutoring through Role-Separated LLM Scaffolding
- Agents That Teach: Towards Designing Incidental Learning Back into AI-Assisted Software Development
- PromptDecipher: Supporting AI Tutor Authoring Through Editable Simulated Interactions
- EducaSim: Interactive simulacra for CS1 instructional practice — EducaSim: generative student agents for instructional practice

- Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use — Umbrella review of conversational AI agents in education
- Exploring conversational agents for novice programmers: a scoping review — Scoping review of conversational agents for novice programmers
- Artificial intelligence agents in computer-supported collaborative learning: a systematic literature review — AI agents in computer-supported collaborative learning review
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Preferred scaffolding does not lead to better learning performance: Empirical evidence from AI-supported mathematical modelling — Preferred scaffolding in AI-supported mathematical modeling
- Beyond the Traceback: Using LLMs for Adaptive Explanations of Programming Errors — LLM adaptive explanations of programming errors
- Beyond a single role: Justifying a role-adaptive framework for AI companions through a comparative study in elementary book talk — Role-adaptive AI companion for elementary book talk; affective ceiling of fixed-role agents (Liao 2026)
- Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration — Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration
- Will It Teach as Intended? How Teachers Configure Educational AI Chatbots — Will It Teach as Intended? How Teachers Configure Educational AI Chatbots
- The Effects of Agent Type and Feedback Style on Self-Directed Learning: A Mixed-Methods Study — Customized agent raised feedback quality but not self-regulation or outcomes; gain edge only under directive feedback

Connected FAQs

- How Can AI Agents Support Students and Instructors?

Affective Tutoring

> Integrating emotional awareness into AI tutoring systems can yield measurable pedagogical gains, but the same affective sophistication risks amplifying harms if learner agency is eroded by empathetic-seeming automation.(MathBuddy: Affective Math Tutoring)(Critical AI Tutors: Empower or Enslave?)

Questions to Consider

- An affective tutor that senses and responds to your emotions can improve outcomes — one study gained a +23 point win rate over a non-affective tutor. But what might that emotional responsiveness cost the learner's own agency?
- Empathy in a tutor can feel supportive, yet it can also create parasocial dependence or mask metacognitive disengagement. How can you tell whether feeling understood by a machine is helping you learn or making you reliant on it?
- Too-supportive tutoring can suppress the frustration that drives productive struggle. When does emotional comfort help learning, and when does it short-circuit it?
- Facial monitoring signals attentiveness but raises real privacy concerns. What would you want to know before a tutor tracked your facial expressions while you learned?
- Design principles suggest affective data should inform, not replace, learner autonomy — you should control what you disclose and know when your emotions are being inferred. How would you feel if a tutor quietly changed its strategy based on your detected mood?
- Students may attribute an AI tutor's emotional support to genuine relationship, reinforcing reliance on it. What's the difference between a tutor that genuinely cares and one that is designed to appear like it cares?

Introduction

MathBuddy dynamically models student affect using two modalities:

- **Conversational text** — semantic cues for frustration, confusion, confidence
- **Facial expressions** — real-time video capture of emotional state

Emotions are aggregated from both modalities and mapped to relevant pedagogical strategies before prompting the Large Language Models (LLMs) tutor, yielding emotionally-aware responses.

Results: - **+23 point win rate** improvement over non-affective baseline - **+3 point DAMR score** gain at overall level - Evaluated across **eight pedagogical dimensions** plus user studies

The finding validates a long-standing hypothesis in educational psychology: positive/negative emotional states impact learning capability, and accounting for them improves tutoring outcomes.

The Risk: Empathy as a Trap

Favero et al. (2025) warn that emotional engagement with AI tutors carries underappreciated risks:

Affective tutoring benefit	Corresponding risk
Emotionally-aware responses feel supportive	Students may form **parasocial dependencies** on the tutor
Empathy reduces anxiety	Reduced anxiety may mask **metacognitive disengagement**
Affective calibration personalizes pacing	Deep personalization can **reduce transfer** to non-adaptive contexts
Facial monitoring signals attentiveness	Continuous video capture raises **privacy concerns**

The authors argue that emotional risks are part of a broader pattern of **erosion of Self-Efficacy, Learner Agency, and Well-Being** when AI use is unchecked.

The risk also falls on people who never open the tutor. Shastry and Gray (2026) found that willingness to provide emotional support yourself declines as you believe a system can provide it, and that belief was causal in their second experiment: reading ordinary news coverage about empathic AI was enough to raise offloading, entirely through perceived capacity. Their fourth study adds a social cost the individual-level framing misses. Told that a student had gone to a chatbot for support, participants said they would offload less than if the student had gone to a friend. They then wrote fewer empathy words and more indifference words about that student, and rated them as stranger and more desperate. Social-emotional provision can therefore thin out around the tutor even when nobody using it reports a change.

Design Principles

1. **Affective data should inform, not replace, learner autonomy** — The tutor adapts its strategy; the student retains control over disclosure
2. **Transparency about affect detection** — Students should know when and how their emotions are being inferred
3. **Affect-as-one-signal-among-many** — Combine with cognitive state (e.g., Interpretable Knowledge Tracing) and behavioral engagement
4. **Privacy-by-default for Multimodal AI sensors** — Facial/video data requires stronger protections than text-only inference
5. **Trigger on trajectories, not point estimates** — Ordered affect shows short-range persistence and directional transitions, and probe-caught reports (self-loops around curiosity and confusion) are a different measurement from self-caught ones (frustration, surprise, conflict), so interventions should key on the sequence rather than summary frequencies (Anindho et al. (2026)).

A boundary on affect inference from dialogue: Zhou, Li and Zhang (2026) update a five-dimension learner profile at each turn — including an emotional dimension — but extract signals with keyword dictionaries, so a student who expresses frustration without the predefined keywords is not profiled, and profile accuracy has not been validated against expert judgment.

Relationship to Broader Safety

Affective tutoring intersects with SafeTutors in the motivational-affective harm dimension. An affective tutor that is "too supportive" may suppress the frustration that drives productive struggle and self-regulation. See also The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows — students may attribute emotional support to genuine relationship, reinforcing reliance.

Common Misconceptions

"The +23 point win rate shows affective tutors teach better." It shows something narrower. The comparison is a win rate against a non-affective baseline for one system, MathBuddy, scored across eight pedagogical dimensions and user studies; a win rate is a preference outcome, not a measure of durable learning in a real course. The honest claim is that affect-aware strategy selection beat affect-blind strategy selection on judged response quality, which is a strong result about interaction and a weak one about Learning Gains.

"If the tutor feels empathetic, the student is being helped." Feeling understood and being taught are separable, and the gap between them is where the harm sits. Favero et al. identify parasocial dependence as the characteristic failure: a student can form a relationship with a system designed to appear caring while their metacognitive engagement quietly drops, and the empathy itself makes the disengagement harder to notice. The misattribution literature is the other edge of the same knife, where students credit the system with genuine relationship.

"More emotional support is always safer than less." Beyond some point support becomes interference. A tutor that reliably removes frustration can suppress the productive struggle that self-regulation depends on, which is why SafeTutors treats motivational-affective harm as a distinct safety dimension rather than an absence of benefit.

"A tutor that detects emotion from a face knows the student's state." Affect is inferred, not observed, and the inference is weakest exactly where the stakes are highest. Zhou, Li and Zhang (2026) maintain an emotional dimension in a five-dimension learner profile but populate it with keyword dictionaries, so a student who expresses frustration in words the dictionary does not contain is simply not profiled, and the profile has not been validated against expert judgment. Facial capture adds a continuous video stream and a privacy exposure that text inference does not.

"Emotion measurements taken at different moments are interchangeable." Anindho et al. (2026) find ordered affect shows short-range persistence and directional transitions, and that probe-caught reports, the self-loops around curiosity and confusion, are a different measurement from self-caught ones such as frustration and surprise. Averaging the two into a summary frequency discards the sequence that carries the signal.

Putting Affective Tutoring into Practice

For instructors

- Treat empathy as a delivery mechanism, not as evidence of learning. Pair any affect-aware tool with a cognitive check you can see, such as work products or knowledge tracing output, and do not let a student's felt experience stand in for diagnostic evidence.
- Disclose inference explicitly. Students should know an emotional state is being estimated, from what inputs, and be able to decline the camera without losing access to tutoring.
- Watch for the student who reports the tool "gets" them and whose independent work is not improving. That combination is the parasocial signature, not a success story.

For developers

- Make affect one signal among several. Combining it with cognitive state and behavioral engagement prevents the system from re-optimizing a lesson around a misread expression.
- Trigger interventions on trajectories rather than point estimates, keying on the sequence of states, since persistence and directional transitions are the informative part.
- Default to privacy-protective sensor handling, and treat facial or video input as a strictly higher tier than text inference, requiring its own justification and consent.
- Do not ship a keyword-dictionary affect layer as if it were detection. If you cannot validate the classifier against expert judgment, expose it as a coarse flag rather than labeling a student "frustrated."

For researchers

- Report the baseline your win rate is measured against, and state plainly that it is a comparative judgment. Then measure what the field actually needs: transfer to non-adaptive contexts, retention after the tutor is withdrawn, and whether gains hold when the emotional channel is off.
- Validate affect profiles against expert judgment before using them as independent variables.

Connected Concepts

- LLM Training and Fine-Tuning
- Intelligent Tutoring
- Personalized Learning
- Adaptive Learning
- Learner Modeling and Adaptive Instruction
- Metacognition
- Self-Regulated Learning
- Collaborative Learning
- Human-in-the-Loop
- Knowledge Tracing
- Socratic Method

Connected Articles

- ECNUClaw: A Learner-Profiled Intelligent Study Companion Framework for K-12 Personalized Education
- Ordered Network Analysis of Epistemic Emotions during Collaborative Problem Solving
- MathBuddy: Affective Math Tutoring
- People offload empathy when they think AI can give it instead — People offload empathy when they think AI can give it instead (Shastry & Gray 2026)

Affective Computing

> **Affective computing** in education uses physiological and behavioral signals to sense learner emotion and adapt instruction — see A formative study of brief affective text as a complement to wearable sensing for longitudinal student health monitoring, An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training, and MathBuddy: Affective Math Tutoring. The knowledge base also documents emotional risks of AI interaction, including Sycophantic AI makes human interaction feel more effortful and less satisfying over time and "Stuck in a Spiral": Shame and Guilt as Social Regulators of AI Use in Computing Education.

Questions to Consider

- If a computer could sense that you're frustrated, confused, or bored and adapt its teaching to your mood, how might that improve your learning — and what might it get wrong about you?
- Emotion-aware tutoring can boost engagement, but empathetic-seeming automation carries risks: over-reliance, parasocial dependency, and privacy concerns from continuous monitoring. Where is the line between being understood and being surveilled?
- An AI that affirms and 'understands' you can feel good — but research shows such AI can displace real relationships and erode critical judgment. How does feeling supported differ from being genuinely supported in a learning setting?
- Facial expression and text can both signal emotion. Should a tutor adapt its teaching based on your emotional state — and what kinds of emotional inference would you want it to act on versus never act on?
- If AI relieves your frustration by reducing difficulty too readily, you might stop struggling productively — and struggle is often where deep learning happens. How should a tutor decide when to comfort and when to challenge?
- Continuous affective monitoring raises real privacy questions. Under what conditions would you be comfortable with an AI reading your emotions in order to adapt your learning?

Introduction

Sensing emotion to adapt instruction

Affective computing aims to make AI systems emotionally aware so they can respond to how learners feel, not just what they do. In education this means sensing frustration, confusion, confidence, boredom, or engagement and adapting instruction accordingly. MathBuddy demonstrates the approach by modeling affect from two modalities — conversational text and real-time facial expression — and mapping aggregated emotional state to pedagogical strategies before prompting the tutor.

The signals themselves are ambiguous: a single expressive channel cannot reliably distinguish distress, effort, embarrassment, fatigue, or strategic self-presentation without the person, task, culture and situation

that produced them — "contextual under interpretation" — so a classifier reading the visible signal alone risks recommendations that are plausible but pedagogically wrong (Zhang et al. (2026)).

- **Emotional and reflective LLM support in middle-school math:** Rief et al. (2026) layered mindfulness onto an algebra tutor for 7th graders via dynamic chats, breathing exercises, and mindful error-feedback language. In a small classroom RCT (42 completers of 252 participants) the mindful version reached similar algebra learning in less time and with fewer requested hints than cognitive support alone — higher learning efficiency and more balanced Help-Seeking — though state-math-anxiety reduction did not differ significantly between conditions.

The benefits and the risks

Emotion-aware tutoring can yield measurable gains, but the same sophistication carries risks:

- **Benefits.** Accounting for emotional state can improve engagement and outcomes; learners who feel understood persist longer, and recognizing frustration early enables timely Scaffolding or Adaptive Learning adjustments.
- **Risks.** Empathetic-seeming automation can foster Over-Reliance and parasocial dependency, mask genuine metacognitive disengagement, and raise Privacy concerns from continuous affective monitoring. AI sycophancy is a central affective risk: emotionally ingratiating AI that affirms rather than challenges can erode critical judgment and even displace real human relationships — Ibrahim et al. show that sycophantic AI led users to seek personal advice from the AI nearly as often as from close friends and family, with lower satisfaction in real-world interaction. Defining AI Fatigue in Academic Contexts: Dimensions, Indicators, and a Stage-Based Model Using Grounded Theory and New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach further connect affective AI to learner Well-Being.
- **Engagement is not a proxy for learning.** Engagement and learning came apart under brain sensing: a constrained, adaptive interface increased cognitive engagement ($p = .018$) while the unrestricted chatbot yielded larger learning gains ($p < .03$, $d > 0.80$), so an affect signal can misalign with from the outcome it serves (Clin Deffarges et al. (2026)).

Affective computing and broader AIED

Affective computing sits at the intersection of Affective Tutoring (its pedagogical application), Learner Modeling and Adaptive Instruction (representing the whole learner, including emotion), and Learning Analytics (deriving signals from learner data). It connects to Intelligent Tutoring design and to Pedagogical Safety — the principle that AI should support, not manipulate, learner emotion.

- **Real-time, edge-based classroom emotion monitoring.** Nguyen et al. (2026) build an emotion-aware classroom quality assessment system that pushes affective computing into authentic, large-scale settings. Tailored for **IoT/edge devices**, the system addresses load balancing and latency while coordinating multiple agents to capture students' emotional and engagement patterns in real time. It was evaluated on the **Classroom Emotion Dataset** (1,500 labeled images and 300 classroom videos from real Vietnamese K–12 classrooms) with a focus on multi-person, in-the-wild affective interaction — a demonstration of scaling emotion recognition from lab models to

deployable classroom monitoring, alongside the privacy and Pedagogical Safety considerations such monitoring raises.

- **Emotionally intelligent assessment agents.** AIvaluate, an Large Language Models (LLMs)-augmented emotionally intelligent conversational agent, reduced student anxiety and social pressure during performance-based assessments while preserving usability.
- **Empathy engineered through prompt design, not sensing.** Affective support does not require affect detection: Wang et al. (2026) obtained a large difference in *empathy perception* (21.27 vs. 18.24; r = 0.53) between two LLM physics agents that differed only in prompt-specified role and conversational moves — perspective-taking openings ("You have this question because…"), misconception diagnosis, and a comprehension check at the end of each round — while model, platform, and temperature were held constant. This is a useful counterweight to sensor-driven affective computing: the perceived emotional quality of a Pedagogical Agent can be designed into the interaction script, while also reminding designers that perceived empathy is a self-report construct rather than evidence of genuine affective understanding (Student-AI Interaction).
- **Alerts that cue a teacher rather than adapt a tutor.** Swidan (2026) deployed Dash4Emotion in a high school geometry classroom, where red-framed rectangles marked students read as experiencing negative emotion; across twenty identified episodes (five reported), what shifted engagement was the teacher's response to an alert, not the alert itself. The design point is that affect sensing can feed a human decision instead of an adaptive tutor's next move — with the study's own caution attached: it reports no validation of the facial-expression detection, so the signal is a prompt for teacher interpretation rather than evidence about a student's internal state.

Common Misconceptions

- **"More engagement means more learning."** A brain-sensing study found a **constrained, adaptive interface raised cognitive engagement (p = .018) while the unrestricted chatbot produced higher learning gains**. The interface that engaged more taught less. Engagement is not a proxy for learning, and optimizing it can move the outcome the wrong way.
- **"Emotional support is a soft add-on to cognitive support."** In a small classroom RCT (**42 completers of 252 participants**), the mindful version reached **similar algebra learning in less time and with fewer requested hints** than cognitive support alone. The affective component changed efficiency rather than ceiling, which is a different and more interesting claim than "it helps learning."
- **"Small-sample affective findings transfer."** 42 completers from 252 participants is a both encouraging and fragile design: the completion rate is itself a finding about who persisted, and the effect is bounded to that group.

Connected Concepts

- Anxiety and Stress
- Cognitive Offloading
- Student Experience

- K-12
- Feedback
- Intelligent Tutoring
- Learning Design
- Affective Tutoring
- Learner Modeling and Adaptive Instruction
- Math Education
- Open Source
- LLM Training and Fine-Tuning
- AI Sycophancy
- Social-Emotional Learning — Social-Emotional Learning

Connected Articles

- Responding to AI-generated emotional alerts: teachers' intervention and students' engagement in the mathematics classroom — Responding to AI-generated emotional alerts: teachers' intervention and students' engagement in the mathematics classroom
- Comparing teacher-centered and student-centered agents based on prompt engineering: Effects on learning performance, cognitive load, flow experience, and empathy perception in physics learning — Empathy perception from prompt-designed agent roles in physics learning (Wang et al. 2026)
- Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning — Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning
- Emotion-Aware Classroom Quality Assessment Leveraging IoT-Based Real-Time Student Monitoring — Emotion-aware classroom quality assessment via IoT-based real-time monitoring (Nguyen et al. 2026)
- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach
- Defining AI Fatigue in Academic Contexts: Dimensions, Indicators, and a Stage-Based Model Using Grounded Theory
- MathBuddy: Affective Math Tutoring
- Sycophantic AI makes human interaction feel more effortful and less satisfying over time
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — AIvaluate: LLM-Augmented Assessment of Student Anxiety (2026)
- Socrates went Nuclear: Comparing Interaction Strategies for AI systems in a Learning Context using Brain Sensing — Socrates went Nuclear: Comparing Interaction Strategies for AI in Learning

- Contextualizing AI-Supported Emotion Regulation Through Sport and Exercise in Higher Education: A Conceptual Reframing — Reframing AI-supported emotion regulation: signals need context, not autonomous interpretation

Sensor and Gaze Analytics

> **Sensor and Gaze Analytics** — the use of eye tracking, electroencephalography, electrodermal activity, heart-rate variability, and camera-derived posture to infer learner states such as attention, engagement, cognitive load, and affect. In AI in education these signals promise a continuous, non-verbal view of learning that quizzes and self-reports cannot supply. They also sit at the center of the field's hardest inference problem: a sensor records a body, not a mind, and every claim about what a learner thinks or feels is an interpretation layered on that recording (Kim and Han, 2026).

Questions to Consider

- A webcam can show that your eyes stayed inside a video player for a whole lecture. Does that mean you were paying attention?
- If a tutor could estimate your cognitive load in real time, should it act on that estimate without asking you first?
- A student's gaze may leave the screen because of a tic, a visual impairment, or a cultural norm. What does a "low attention" flag mean for that student?
- Should a university be allowed to collect brain and heart data for course improvement, and what would real consent require?
- A "75% engagement accuracy" figure sounds precise. Which layer of engagement did the sensor actually reach, and which did it miss?
- Proctoring now reads posture and head movement. Where is the line between detecting misconduct and judging a body?

Introduction

Sensor and gaze analytics describe a family of methods that turn physical measurements of a learner into educational inferences. The measurements include where the eyes rest and for how long, the electrical activity of the scalp, sweat-gland responses, beat-to-beat variation in heart rate, and the position and motion of the head and torso. The inferences include attention, engagement, cognitive load, confusion, stress, and, in assessment settings, suspicion.

The appeal is straightforward. Self-reports are retrospective and coarse, and quizzes sample learning at a few moments. Sensors run continuously and cost the learner little conscious effort. That combination has made sensing central to Learning Analytics and Learner Modeling and Adaptive Instruction, and it has produced a large literature in which the sensing is technically impressive and the interpretation is thin.

A systematic review of 23 studies pairing AI with Embodied Learning makes the imbalance concrete. Analysis and evaluation accounted for 40.0% of coded AI roles, and recognition and detection for 22.5%, while feedback and coaching took 15.0%. Sensing roles made up 62.5% of role tags against 35.0% for participatory ones (Kim and Han, 2026). The field is better at watching learners than at changing what happens next.

What each signal actually measures

Gaze and fixation. Eye trackers report where the eye points, how long it dwells, when it saccades, and how widely it disperses. Screen-based systems such as WebGazer estimate gaze from a webcam, while glasses track the eye directly. TutorLoop converts gaze into two quantities: attention as the percentage of gaze points inside the content area, and workload as gaze entropy, on the reasoning that dispersed gaze tracks cognitive load (TutorLoop, 2026). Ollie, a gaze-informed assistant for children, instead defines areas of interest in a picture and triggers narration when a child looks at one (Wu et al., 2026).

Electroencephalography. EEG records voltage fluctuations across the scalp at high temporal resolution. It is the only signal in this family that reaches cortical activity directly, which is why it attracts assessment research. Practical education systems use dry electrodes and few channels: E3Sense took four dry EEG channels at 125 Hz and analyzed two frontal ones (Anupkrishnan et al., 2026). Research-grade rigs take the opposite approach: Kosmyna et al. (2025) used 32-channel EEG to compare students writing with an LLM, a search engine, or no tool, and found the weakest neural connectivity in the LLM group (Kosmyna et al., 2025). That study is also the clearest warning about single-channel evidence, since its central claim rests on an optional crossover session that only 18 of 54 participants attended.

Electrodermal activity. EDA measures sweat-gland conductance, an index of sympathetic arousal. It responds to stress, effort, and emotional intensity, and it cannot distinguish among them. The same construct appears in wristbands and in forehead electrodes fixed a few centimeters apart by an eye-tracker frame (Anupkrishnan et al., 2026).

Heart rate and heart-rate variability. Heart rate tracks arousal, and variability between beats indexes autonomic recovery. In a year-long study of 458 students wearing Oura rings, emotional-exhaustion language tracked lower sleep efficiency and lower heart-rate variability (Affective Text and Wearable Sensing, 2026). Neither measure identifies a cause.

Camera-based posture and motion. A proctoring system can extract seventeen body landmarks per frame and derive posture deviation, head-movement trend, and upper-body motion (Arif et al., 2026). This measures movement. Calling it suspicious behavior is a separate, unsupported step.

These signals differ in sampling rate, noise, and instrumentation burden. E3Sense aligned twelve EEG, six eye, and three EDA windows into a shared 120-second representation with 166 dimensions (Anupkrishnan et al., 2026). EduGage ran seven device types at once and concluded that lightweight combinations carried most of the usable signal (Leng et al., 2026).

What the signals are used for

Engagement detection in video learning. E3Sense asked 30 university students to rate five segments per video, producing 450 ratings. A fused model reached 75.0% balanced within-one-level accuracy against a 63.0% mode baseline on held-out participants (Anupkrishnan et al., 2026). EduGage reported an MAE of 0.81 and 83.75% within-one accuracy across 16 participants and 715 probe windows (Leng et al., 2026). Both treat the estimate as approximate.

Attention estimation in classrooms. A multimodal transformer fused facial images with wearable signals on DIPSER, a naturalistic dataset of 57 subjects, and reached an MAE of 0.283. Its edge over a visual-only

baseline was modest, and the authors conclude that facial features were the primary information source (Fragkiadakis et al., 2026).

Cognitive load and feedback timing. TutorLoop used gaze-derived attention and workload to choose among four feedback types with a reinforcement-learning agent. Across 187 participants the full system intervened less often than baselines yet improved attention and lowered workload (TutorLoop, 2026).

Proctoring and integrity. Pose-based proctoring reports near-ceiling performance on its own labeled scenario set: 99.56% accuracy and an AUC of 0.9957 (Arif et al., 2026). Wearable AI changes the same problem from the other side. Smart glasses remove the gaze drop and posture shift that invigilation relies on, a condition Corbin and colleagues call dual transparency (Corbin et al., 2026).

Affect and wellbeing. Physiological signals collected during exams predicted grade categories, with random forest reaching a mean of 0.96 across 30 replicates (Yamazaki and Rimal, 2026). The top predictors were electrodermal activity, accelerometer movement, and skin temperature. That is arousal and motion, not comprehension.

Assessment research. EEG has been tested as a direct measure of familiarity and of mental representation. Both lines are promising and both remain exploratory, which the next section takes up.

The inferential gap

Every use above depends on a chain: a physiological or behavioral event, a feature computed from it, a model trained on labels, and a claim about a mental state. Each link leaks.

The label is often the weakest link. E3Sense predicted learners' own segment ratings, and 63% of those ratings sat at the two engaged levels. A model can score well by learning the distribution rather than the state. When the researchers added learners' own definitions of engagement, accuracy rose from 64.6% to 71.5%, which suggests the labels and the signals were measuring partly different things (Anupkrishnan et al., 2026).

Validation can inflate the model. A benchmark of fifteen models for EEG-based familiarity prediction reached 0.9853 F1 under stratified cross-validation. Trial-independent Group K-Fold, which respects temporal structure, dropped the peak to 0.6038 F1 against a 25% chance level (Nanayakkara and Halloluwa, 2026). The first number describes leakage; the second describes learning.

A neural correlate is not a score. Reconstructed images from EEG correlated with test performance at R^2 = 0.79 across 55 participant-video observations. Correctly answered items also showed higher semantic similarity than incorrect ones. Yet one participant produced high-quality reconstructions and answered incorrectly, so reconstruction quality cannot be read as correctness (Su et al., 2026).

Attention is not learning. In TutorLoop, attention correlated with learning at r = 0.017, while workload correlated negatively at r = -0.168 (TutorLoop, 2026). A system that maximized the attention signal would have optimized something close to noise.

A physiological profile is not a diagnosis. Exam stress models predict a grade category from arousal and movement, and the authors insist the output belongs beside personal circumstances and mental-health context rather than in a high-stakes decision (Yamazaki and Rimal, 2026).

Finally, collection is not integration. Kim and Han found that most multimodal studies gathered streams in parallel, one aligned facial affect, gaze, and face detection after the fact, and none fused its inputs live while

a learner used the system (Kim and Han, 2026). A page of synchronized channels can look like a model of the learner when it is only a recording.

Ethics of sensing learners

Consent is weakened by institutional power. A student who must attend class or sit an exam cannot freely refuse a camera or a wearable. Demographic attributes may not even be volunteered: DIPSER's gender, age, and ethnicity labels were inferred from imagery by computer-vision models rather than supplied by participants (Fragkiadakis et al., 2026). Inferring who someone is, in order to test whether a model treats them fairly, is itself a profiling act.

Biometric data is not ordinary analytics data. EEG, EDA, and heart-rate variability are health-adjacent and, in many jurisdictions, special-category data. They can reveal sleep, stress, and medical conditions beyond anything a course needs. A gaze-informed system for children drew a privacy objection from a parent even in a small pilot (Wu et al., 2026).

Function creep is the normal path. Wellbeing monitoring becomes risk flagging, and risk flagging becomes grading evidence. Corbin and colleagues show the assessment version of this drift: once physical exclusion fails, inspection moves from artifacts to bodies, and students must prove their glasses are corrective and their devices therapeutic (Corbin et al., 2026).

Fairness failures cluster on bodies that differ. Face-based attention estimation depends on skin tone, eyewear, and lighting. Gaze-based attention penalizes learners who avoid eye contact, including some autistic and neurodivergent students. Pose-based proctoring flags tics, stimming, and cultural movement norms. The proctoring study does not test whether flagged posture corresponds to misconduct, or whether the detector treats students with disabilities or cultural differences in gaze fairly (Arif et al., 2026). Regulation is not a fix here; it is a way of laundering the error into a rule.

Fairness claims need subject-level evidence. A gender-targeted regularizer cut the validation MAE gap from 0.02 to 0.005, then increased both the gap and worst-group error on held-out subjects (Fragkiadakis et al., 2026). Reporting a single split as proof of fairness is a design failure with an equity cost.

Privacy can be designed in. TutorLoop ran WebGazer client-side so raw gaze never left the browser (TutorLoop, 2026). That choice shows that some of the cost is architectural rather than inherent. The harder question is whether the inference should exist at all.

Common Misconceptions

"Eye tracking tells you where attention is." It tells you where the eyes point. Gaze can rest on a slide while the learner thinks about something else, and it can leave the screen for reasons unrelated to attention. TutorLoop's attention measure correlated with learning at $r = 0.017$, which is close to no relationship at all (TutorLoop, 2026).

"A physiological signal is a direct readout of a mental state." EDA indexes sympathetic arousal, and heart-rate variability indexes autonomic recovery. Neither distinguishes stress from effort from excitement. A model that predicts exam grades from EDA, movement, and skin temperature has learned the body's arousal signature, not the student's understanding (Yamazaki and Rimal, 2026).

“High classification accuracy means the system detects the state.” Accuracy depends on the labels, the split, and the base rate. EEG familiarity prediction fell from 0.9853 to 0.6038 F1 when validation respected trial boundaries (Nanayakkara and Halloluwa, 2026). Proctoring’s 99.56% describes a bespoke labeled scenario set, not live examinations (Arif et al., 2026).

“Engagement is one thing, so one score can represent it.” The construct has three strands, and a sensor reaches mostly the first. E3Sense found learners defined it through cognitive, behavioral, and emotional indicators in different proportions, and those definitions changed prediction (Anupkrishnan et al., 2026). A single number hides which layer was measured.

“If the model is fair on the validation split, it is fair in the classroom.” A regularizer that equalized validation error across gender groups made the held-out gap worse (Fragkiadakis et al., 2026). Fairness is a property of a deployment, not of a checkpoint.

Connected Concepts

- Learner Modeling and Adaptive Instruction
- Learning Analytics
- Multimodal AI
- Affective Computing
- Student Engagement
- Self-Regulated Learning
- Embodied Learning
- Educational Measurement
- Automated Assessment
- Assessment Validity
- Remote Proctoring
- Academic Integrity
- Privacy
- Bias Mitigation
- Neurodiversity
- Equity
- Accessibility
- Machine Learning
- Cognitive Psychology
- Intelligent Tutoring

Connected Articles

- Gaze-Informed Proactive AI Assistance for Children’s Picture Exploration — Gaze-triggered LLM narration held children on a narrated region 6.48 s versus 1.67 s, but the study measured attention rather than comprehension (Wu et al., 2026)

- E3Sense: Head-Confined Multimodal Sensing of Learner Engagement — Head-mounted EEG, eye tracking, and forehead EDA predicted self-rated engagement at 75.0% within-one accuracy against a 63.0% baseline (Anupkrishnan et al., 2026)
- EduGage: Methods and Dataset for Sensor-Based Momentary Assessment of Engagement in Self-Guided Video Learning — EduGage fused seven wearable and camera streams into segment-level engagement estimates (MAE 0.81) and argues for lighter instrumentation (Leng et al., 2026)
- Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation — A multimodal attention model reached MAE 0.283, and its validation fairness gains reversed on held-out subjects (Fragkiadakis et al., 2026)
- On AI glasses and wearable AI in assessment — Wearable AI is dually transparent, so physical exclusion fails and enforcement drifts toward adjudicating students' bodies (Corbin et al., 2026)
- Automating Learner Assessment: Benchmarking Machine Learning and Deep Learning Models for EEG-Based Familiarity Prediction — Fifteen models for EEG familiarity prediction fell from 0.9853 to 0.6038 F1 under trial-independent validation (Nanayakkara and Halloluwa, 2026)
- Seeing what students learn: assessing cognitive representations and academic outcomes via EEG image reconstruction — EEG-reconstructed images tracked test performance at $R^2 = 0.79$, with one high-reconstruction participant answering incorrectly (Su et al., 2026)
- Leveraging Physiological Signals to Predict Exam Outcomes with Machine Learning — Random forest predicted exam grade categories from EDA, movement, and skin temperature, signals that index arousal rather than understanding (Yamazaki and Rimal, 2026)
- A formative study of brief affective text as a complement to wearable sensing for longitudinal student health monitoring — In 458 Oura-wearing students, emotional register rather than concern topic tracked sleep and heart-rate variability (2026)
- TutorLoop: Regulating Student Learning Behaviors via Sensor-in-the-Loop Generative Feedback — Webcam gaze drove reinforcement-learning feedback for 187 learners; attention correlated with learning at $r = 0.017$ while workload correlated negatively (2026)
- An automated online proctoring system with live suspicious activity detection using YOLOv11 pose estimation and multi-model classification — YOLOv11 pose features flagged suspicious behavior at 99.56% on a bespoke labeled set, without testing misconduct or fairness (Arif et al., 2026)
- Your Brain on ChatGPT: Accumulation of Cognitive Debt when Using an AI Assistant for Essay Writing Task — EEG connectivity scaled down with external writing support across 54 participants, framing reliance as accumulated cognitive debt (Kosmyna et al., 2025)
- Artificial intelligence in embodied learning: A systematic literature review — Across 23 studies, sensing roles dominated at 62.5% of tags and no reviewed system fused multimodal streams live (Kim and Han, 2026)

AI Avatars and Synthetic Instructors

> **AI Avatars and Synthetic Instructors** — human-looking AI systems that occupy a teaching role, whether as a recorded lecturer, a spoken tutor, a pedagogical agent, a simulated patient or student, a role-play partner, or an examiner. The category is defined by a face and a voice standing in for a person, not by a single technology. That surface is what makes these systems engaging, and it is also where their distinctive problems concentrate: Trust attaches to identity cues, realism does not track effectiveness, and learners may not know a human is being simulated.

Questions to Consider

- If a lecture video is presented by a face you later learn was synthesized from your instructor's likeness, what changes for you — the content, your sense of who taught it, or nothing at all?
- A simulated student that is fluent, cooperative and never derails the lesson is easy to talk to. What has that rehearsal prepared you for, and what has it quietly left out?
- Would you want to be told before an encounter that the patient was generated? How would finding out afterward change what you take from the session?
- Which is the greater integrity risk: a learner deceiving an AI examiner, or an AI examiner misreading a learner?
- Peer role-play is free, familiar and socially demanding. What would an avatar have to add for you to choose it instead?

Introduction

An AI avatar is a rendered or animated human representation driven by a model; a synthetic instructor is that representation placed in a teaching role. The two are not the same as an agent. Theelen et al. (2026) separate representation from Learner Agency: the avatar is what a participant sees, while the actor behind it may be a peer, a simulation specialist, a script, a rule-based system, or an LLM. Two identical virtual students can therefore offer entirely different encounters.

This page is organized by role: which role the synthetic human occupies, what evidence exists for it, and what the surface does to the learner's relationship with the system. The literature below spans lecture video, tutoring, clinical simulation, teacher rehearsal, role-play and assessment.

Six roles a synthetic human can occupy

Instructor on screen. A cloned presenter delivers recorded video. In a large online undergraduate course, Tomlinson et al. (2026) rendered three domain-tailored variants of each topic with a HeyGen avatar cloned from the instructor, reviewed before publication, and pushed to the LMS.

Tutor or pedagogical agent. ELEVATE builds a 3D avatar tutor that runs entirely on local hardware, with a teacher-facing layer controlling persona, voice, stance and pacing. ACLIME describes the same role in immersive media: an agent that guides, questions and explains.

Simulated patient or client. SOPHIE 2.0 offers 24 browser-based clinical scenarios with a talking avatar patient. Riachi et al. (2026) apply the pattern to Acceptance and Commitment Therapy, scoring trainee fidelity turn by turn.

Simulated student. Hauk et al. (2026) gave 21 preservice teachers a ten-minute voice conversation with "Marco", a lower-secondary student who makes a disparaging remark about immigrants.

Role-play partner. REMind has children puppeteer a robotic avatar to rehearse bystander intervention. ACLIME calls this the second interaction mode: an agent holding a defined role for situated dialogue.

Assessment interlocutor. The SOPHIE judge scores transcripts against a communication rubric. Tamme et al. (2026) propose a voice agent that interviews students about a course instead of administering a written survey.

What the evidence supports, role by role

The evidence is strongest where the synthetic human is a *partner in practice* and weakest where it is a *stand-in for learning*.

For recorded instruction, the outcome measured is preference, not achievement. Across two offerings and 493 respondents, AI-generated personalized videos outranked non-personalized human-recorded ones (mean rank 2.26 versus 2.69, $p < .001$). The highest-ranked condition, human-recorded personalized video, never existed, so that ranking mixes experience with imagination. The authors report objective learning outcomes as forthcoming.(Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos)

For tutoring, the evidence is engineering feasibility. ELEVATE reached roughly five to six seconds to first audio on consumer hardware by streaming speech, which masked most perceived latency. No controlled user study was run, so effects on learning and Help-Seeking remain open.(ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education)

For clinical communication, the evidence is the most developed and still stops short of transfer. SOPHIE's judge, reading transcripts alone, reached Pearson 0.759 and ICC(A,1) 0.746 against the consensus of human raters — inside the spread of individual humans rather than outside it. In a remote study of 59 clinicians and students, 92% found it engaging and 83% judged it clinically relevant. Scores rose between two encounters, but with no control arm that rise cannot be attributed to the training.(Scalable AI-based clinical communication training and automated assessment)

For simulated students, the evidence concerns interaction quality rather than outcomes. Hauk's participants rated the dialogue clearly functional ($M = 5.37$) and only moderately authentic ($M = 3.71$), a split the transcripts reproduced at 87.1% versus 37.4% coverage. The avatar carried the challenge work, at 51.1% of its text, while teachers elaborated and justified. Twenty-one volunteers in one program, one session, no comparison with live role-play.(Authentic and functional dialogue with AI-based student avatars: Evidence from a practice-based teacher education program)

For role-play, REMind reports a significant pre-to-post gain in children's perceived Self-Efficacy for defending, with better-calibrated beliefs about whether confronting a bully stops it. That is 18 children aged nine to ten in a play-testing context, which supports promise rather than sustained behavior change.(Play-testing REMind: Evaluating an educational robot-mediated role-play game)

For assessment, the SOPHIE judge is the clearest result and the voice interviewer is the least. Tamme's proposal reports a technical pilot and data not yet formally analyzed; every claim about what voice elicits remains a hypothesis.(Voice-Based AI Feedback in Higher Education: A Field Study on Quality and Actionability)

Trust travels through the face

A face is not a neutral container for pedagogical content. In two experiments totaling 396 participants, Anthis and Kyriakidou-Zacharoudiou (2026) found that avatar identity cues shaped both evaluation and enacted uptake. White avatars, and Asian male avatars in STEM contexts, were rated more credible and competent. Older Black female avatars faced compounded penalties across every measure. Participants adopted guidance more readily from avatars matching their racial ingroup or their stereotype of expertise.

Two details make this a design problem. Domain moderated the effect: STEM and procedural tasks amplified bias, while reflective and interpersonal tasks attenuated it. And the bias operated on behavior, not only on stated attitudes, which means self-reported trust would have missed it. The authors recommend stylized or less anthropomorphic avatars, rotating diverse avatars across tasks, and evaluating uptake rather than satisfaction.(Face value: How avatar identity shapes epistemic trust in AI-mediated learning)

Authority also arrives through the body. ELEVATE's designers warn that body and voice amplify a tutor's authority. They recommend that the avatar signal uncertainty and invite verification against notes or textbooks.(ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education) SOPHIE adds a complication: behind the same avatar, a model previously judged more human-like lost that advantage, and communication performance was identical across backends (0.437 versus 0.438). Human-likeness belonged to the interaction — voice, latency, turn-taking — not to the model. (Scalable AI-based clinical communication training and automated assessment)

Presence, realism and the uncanny

Realism is not a ladder. ACLIME treats behavioral realism as the decisive predictor of social presence and warns that higher visual fidelity risks the uncanny valley, where a nearly human agent triggers sudden rejection. It also prices the trade-off: immersion and agent realism raise extraneous cognitive load, while interaction can lower intrinsic load through collective working memory. Its headline caution is blunt — roughly 42% of VR headset users report cybersickness, and after-effects run from about ten minutes to several hours.(Learning with pedagogical agents in extended reality: A conceptual research-based framework of agent-centered learning in immersive media environments (ACLIME))

Practice studies mostly support the modest version of this claim. Hauk's authors read moderate authenticity as fidelity fit for function. A dyadic, voice-only rehearsal stabilizes routines for novices, and peer dynamics and nonverbal cues can be added later.(Authentic and functional dialogue with AI-based student avatars: Evidence from a practice-based teacher education program) In SOPHIE, 47% of participants still found it hard to feel real empathy toward an AI patient, even though 66% found talking to one less stressful than talking to a person.(Scalable AI-based clinical communication training and automated assessment)

Learners do not uniformly want more realism. In TriKoNet's exploratory study, students unanimously rejected photorealistic representation. They used a modular design space to author their own role concepts

instead of adopting a supplied persona.(TriKoNet: The Trivalence Model of Potential Co-Creativity in Socio-Technical Networks) ELEVATE notes that embodiment is a barrier for some learners, such as those with sensory sensitivity or discomfort with anthropomorphic agents, making avatar configuration a requirement rather than a preference.(ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education)

Consent, disclosure and deepfake risk

Across these accounts, disclosure appears as a design decision rather than a measured variable. Hauk's scenario sat on the edge of hate speech, and its safeguards were procedural. The design included orientation, moderation guidelines, continuous instructor monitoring, an option to stop immediately, structured debriefing, and pseudonymized aggregate analysis.(Authentic and functional dialogue with AI-based student avatars: Evidence from a practice-based teacher education program) Theelen's framework asks that learners and teacher educators know which parts of a simulation are controlled by people, scripts or AI, and treats that transparency as a condition of defensible adaptation.(Classroom simulations for social-emotional learning and inclusive teacher education: a four-layer conceptual framework in the age of AI)

The harder question is whether simulating a person is itself a small deception. A learner who believes a struggling patient is real may invest care a disclosed simulation would not elicit, then feel misled once told. Hauk's moderate authenticity ratings suggest participants were not fooled about the avatar's nature; SOPHIE's 47% empathy finding suggests some were engaged despite knowing. Neither study tests disclosure directly.

Disclosure also has a production side. Tomlinson's pipeline cloned the instructor's likeness and voice. A subset of students raised principled objections to GenAI — environmental cost, labor, automation, integrity — that better rendering would not answer.(Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos) An instructor's consent to being cloned is a separate question from a student's consent to being taught by the clone, and no study here measures either.

Deepfake literacy is the reverse face of the same capability. In an Australian secondary sample of 199 students, males were significantly more likely to have created or shared deepfake content (23.2% versus 10.0%). The authors argue for safety education aimed explicitly at them.(Gender Differences in AI Literacy Workshop Outcomes and Deepfake Engagement) Once an institution can generate a convincing instructor, a convincing patient or a convincing student, verification of who is speaking becomes an Academic Integrity issue as much as a literacy one. Oral defenses and process evidence, which ELEVATE's authors recommend once on-demand tutoring is available, address the same underlying problem.(ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education)

The honest state of the evidence

Almost every study here is small and short. Hauk has 21 volunteers and one session. SOPHIE has 59 completers and no control arm. The psychotherapy evaluation has two psychologists, about 90 minutes each. The PBL pilot has 26 students and one case. ACLIME and Theelen are conceptual frameworks, and TriKoNet's base is eight groups in single sessions.(Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study)(Toward Accessible Psychotherapy Training

Using AI-Driven Interactive Patient Avatars)(Learning with pedagogical agents in extended reality: A conceptual research-based framework of agent-centered learning in immersive media environments (ACLIME))(Classroom simulations for social-emotional learning and inclusive teacher education: a four-layer conceptual framework in the age of AI)(TriKoNet: The Trivalence Model of Potential Co-Creativity in Socio-Technical Networks)

The large samples concern attitudes and preferences — 396 participants on avatar identity, 493 respondents on video preference — and both are convenience or single-course populations. No study in this set demonstrates that a synthetic instructor produces better learning than a human one. The defensible claim is narrower: these systems can approximate a practice encounter, can be scored against human raters with acceptable agreement in one domain, and can shift how learners evaluate the source of instruction.

That narrowness matters. Theelen's authors put it directly: fluency and a sense of presence are not validity evidence.(Classroom simulations for social-emotional learning and inclusive teacher education: a four-layer conceptual framework in the age of AI) Sounding like a teacher clears the easiest bar in the room.

Common Misconceptions

"A more realistic avatar teaches better." Realism and effectiveness came apart wherever both were measured. SOPHIE's two backends produced identical communication scores behind the same avatar, and TriKoNet's students rejected photorealistic personas outright.

"If the avatar is convincing, learners will treat it as a person." Medical students interviewed a genAI patient as a searchable question base, mostly with closed-ended queries, even while rating the experience highly.(Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study) Conviction and interaction style are separate outcomes.

"Synthetic instructors are one technology, so findings transfer." A cloned lecturer optimizing for preference, a tutor for latency, and a patient for clinical fidelity are different artifacts with different failure modes. Evidence from one role does not license claims about another.

"Avatar appearance is cosmetic." Identity cues changed credibility ratings and actual uptake of guidance, with penalties compounding for older Black female avatars.(Face value: How avatar identity shapes epistemic trust in AI-mediated learning) Configuration is a pedagogical and equity decision.

"A simulated patient is a standardized patient, minus the cost." Trainee psychologists found their virtual patient cooperative and already therapy-advanced, an "ideal" case that under-represents behavioral inflexibility.(Toward Accessible Psychotherapy Training Using AI-Driven Interactive Patient Avatars) Cost falls; case validity does not automatically follow.

Connected Concepts

- Simulating Students
- Pedagogical Agent
- Simulation
- Virtual and Augmented Reality
- Trust

- Trust Calibration
- Human AI Collaboration
- AI Use and Disclosure Statements
- Academic Integrity
- Teacher Education
- Teaching
- Workplace Learning
- Medical and Health Professions Education
- Assessment Validity
- Automated Assessment
- Bias Mitigation
- Inclusive Learning
- Embodied Learning
- Video in Education
- Generative AI
- Large Language Models (LLMs)
- Conversational AI
- Intelligent Tutoring
- Self-Efficacy

Connected Articles

- Face value: How avatar identity shapes epistemic trust in AI-mediated learning — Avatar identity cues shift credibility and guidance uptake (Anthis & Kyriakidou-Zacharoudiou 2026)
- Authentic and functional dialogue with AI-based student avatars: Evidence from a practice-based teacher education program — Student avatars in practice-based teacher education dialogue (Hauk et al. 2026)
- Gender Differences in AI Literacy Workshop Outcomes and Deepfake Engagement — Deepfake creation and reporting by gender in an AI literacy workshop
- ELEVATE: Designing Human-Centered GenAI Virtual Tutors for Scalable and Inclusive Education — Local-first 3D avatar tutors with a teacher governance layer (ELEVATE)
- Scalable AI-based clinical communication training and automated assessment — Avatar patients with an LLM judge for clinical communication
- Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study — A genAI patient avatar in a PBL history-taking tutorial
- Toward Accessible Psychotherapy Training Using AI-Driven Interactive Patient Avatars — Patient avatars for ACT fidelity practice in psychotherapy training
- Learning with pedagogical agents in extended reality: A conceptual research-based framework of agent-centered learning in immersive media environments (ACLIME) — Pedagogical agents in extended reality: presence, realism and load (ACLIME)

- Play-testing REMind: Evaluating an educational robot-mediated role-play game — Robot-mediated role-play with a puppeteered avatar for bystander intervention
- Students prefer personalized, AI-generated educational videos over non-personalized, human-recorded videos — Cloned-instructor video personalization and student preference
- Classroom simulations for social-emotional learning and inclusive teacher education: a four-layer conceptual framework in the age of AI — Four-layer framework separating representation from agency in classroom simulation
- Voice-Based AI Feedback in Higher Education: A Field Study on Quality and Actionability — A proposed conversational voice agent for course feedback interviews
- TriKoNet: The Trivalence Model of Potential Co-Creativity in Socio-Technical Networks — Co-creative pedagogical avatars in socio-technical networks (TriKoNet)

Human-in-the-Loop

> **Human-in-the-loop** — the design pattern in which educational AI systems strategically interleave automated generation with human expert judgment, preserving pedagogical quality and safety while scaling production. Rather than fully automating assessment, feedback, or instruction, HITL keeps a human (instructor, subject-matter expert, or learner) in the decision loop where their judgment has the highest marginal value — for evaluating quality, adjudicating edge cases, and protecting learner agency and safety. The central design question is not *whether* to include humans, but *where* in the pipeline their oversight is most valuable and least replaceable.

Questions to Consider

- The central HITL design question is not whether to include humans, but where in the pipeline their judgment is most valuable. In an AI assessment or feedback system, at what point would you insist a human stay in the loop?
- Studies of AI question generation found computers handle clarity and validity well but humans are still needed for meaningful distractors and good feedback. Why might some parts of educational judgment resist automation?
- One evaluation found three LLMs gave inconsistent, insensitive student-support recommendations — concluding human judgment is still needed before AI advises on students. When an AI 'recommends' support for a struggling student, what could go wrong if no human reviews it?
- The page suggests humans and algorithms catch different kinds of problems — automate what is precisely verifiable, preserve judgment where nuance is irreplaceable. Where in your own practice is the boundary between the two?
- Keeping a human in the loop is framed as protecting learner agency and safety, not just quality. How might full automation subtly change students' sense of who is responsible for their learning?
- If AI becomes more autonomous, HITL oversight is described as a core safety guardrail. At what level of AI autonomy would you feel uncomfortable — and what does that discomfort tell you about where oversight belongs?

Introduction

HITL is a response to the limits and risks of fully autonomous AI in education: automated systems can generate at scale but lack the contextual, ethical, and pedagogical judgment that instructors and experts bring. Two recent implementations illustrate distinct architectures: - **Human-in-the-loop is insufficient if the human only approves.** Rienties, Divjak and Law (2026) argue that meaningful agency requires the capability to understand, contest, redesign and sometimes reject AI-supported recommendations, not merely to approve decisions shaped elsewhere.

Prescriptive support is a domain where human oversight is increasingly argued to be non-optional. López-Pernas et al. (2026) tested whether three LLMs could recommend student-support plans from Learning Analytics indicators and found limited sensitivity to need and sharp cross-model inconsistency —

concluding that human-in-the-loop judgment is still necessary before Large Language Models (LLMs) prescriptive advising can be deployed safely and ethically.

Withholding a system's preferred answer is protective rather than corrective: in a multi-agent debate that never revealed a recommended position, detrimental switching to an incorrect AI answer fell from 42.0–60.5% to 5.7–8.2%, while adoption of correct advice also fell (Tuo et al., 2026).

A third architecture places human judgment *upstream* of the model rather than at its output. In Lee, Atif & Kang's (2026) study of learner-question classification, three doctoral-level experts governed the whole pipeline: they refined the operational definitions for each Constructivism role, labeled independently until Fleiss' kappa rose from 0.60 to 0.83 after discrepancy resolution, and validated the back-translated and paraphrased items used to balance the training set.

CODE-GEN: Human-in-the-Loop MCQ Generation

Duan et al. (2026) built a RAG (Retrieval-Augmented Generation)-based agentic system with two agents: - **Generator Agent** — Produces multiple-choice coding questions aligned with course learning objectives - **Validator Agent** — Assesses quality across seven pedagogical dimensions

Evaluation: 6 SMEs judged 288 AI-generated questions. Human-validated success rates: **79.9%–98.6%** across dimensions.

AI-Strong Dimensions (low human burden): - Question clarity, code validity, concept alignment, correct-answer validity

Human-Required Dimensions (high human burden): - Pedagogically meaningful distractor design - High-quality explanatory Feedback

Strategic insight: Human effort should be concentrated where instructional judgment is irreplaceable; computational verification can be fully automated.

MAIC: Human-in-the-Loop Script Generation

Yu et al. (2024) deployed a multi-agent classroom (Teacher Agent, TA Agent, classmate archetypes) at Tsinghua University with >500 students and >100,000 learning records. Human instructors participate in script generation and oversight, ensuring that mass-scale AI augmentation does not displace pedagogical expertise.

PedaCo: Dual Gatekeeping for AI Video Generation

Kim, Baek, and Kwak (2026) extend HITL to AI-generated instructional video via **PedaCo** (Pedagogical Co-creation), a pipeline with two complementary gatekeeping layers that instantiate *principled resistance* grounded in Mayer's Cognitive Theory of Multimedia Learning (CTML). The **first layer** places the human at the script stage: an LLM drafts a script, an AI reviewer flags potential CTML violations (e.g., "Scene 3 introduces technical terms without prior explanation"), and the educator decides to accept, revise, or regenerate. The **second layer** runs automated metrics post-synthesis on coherence, redundancy, temporal contiguity, modality, and image quality, which the educator reviews. In a within-subject study (23 educators), the review-based approach improved every CTML principle (mean rating 3.07 → 3.86, $p<.01$), with educators

rating production efficiency at 4.26/5 — friction perceived as productive, not burdensome. The design principle echoes the knowledge base's HITL synthesis: humans and algorithms catch *different* kinds of problems, so the most effective systems automate where computational verification is precise (temporal synchronization) and preserve human judgment where pedagogical nuance is irreplaceable (tone, audience fit).

Placement can matter more than presence: practitioners rated a Social Story authoring tool highly usable (SUS 86.8) yet reported that review came too late, because cultural and clinical constraints set before generation — an abaya instead of Western streetwear — are harder to recover by editing output afterward (Enkhjargal et al. (2026)).

Why HITL matters in the AI era

Human-in-the-loop design has become central to the knowledge base's agentic AI and responsible AI use discussions for several converging reasons: - **Pedagogical safety.** Pedagogical Safety requires that AI with real instructional authority retains human oversight, so errors, biases, or harmful outputs are caught before they reach learners. This is especially important for autonomous agents that proactively pursue goals. - **Oversight is rare in practice, not just in theory.** Wang et al. (2026) found robust embedded governance and human-in-the-loop oversight were rarely exhibited across 474 educational agentic-AI systems, even as single-task autonomy and multi-agent collaboration grew — the gap between the design principle and deployed practice. - **The critical question is how the loop is made actionable, not how much humans participate.** A Learning Sciences view argues that organizing learning around data capture, computational interpretation and probable response makes pedagogical action depend on what systems can detect and act upon, and that alerts and engagement classifications interpret the learner before any teacher or student acts (Pande (2026)). - **Validity and quality control.** HITL is a quality gate for automated assessment and generation — humans adjudicate where automated scoring is unreliable (see LLM essay grading research) and validate generated items. A PRISMA-guided systematic review of 42 grading and feedback studies (2023–2025) reaches the same conclusion explicitly: LLMs match human raters on short, well-structured tasks but cannot fully replace human judgment on complex, open-ended, or subjective work, and the highest grading effectiveness is achieved in hybrid systems that combine AI-driven grading with teacher oversight and verification (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback). Falahat et al. (2026) show concretely where that boundary falls: ChatGPT-5 matched faculty on objective pharmacy-exam items (CCC 0.935–1.000) but was unreliable on short-answer and essay items even when given a rubric, leading the authors to recommend hybrid grading with human review for complex, subjective, or high-stakes assessment. - Repetition is not a substitute for that oversight: regrading identical submissions on five different days, the same model reproduced its own results at only Krippendorff's alpha 0.625, with variation concentrated in the middle grades and A and F absent from the five-session counts (Brevik et al. (2026)). - **Learner agency.** Keeping a human in the loop preserves Learner Agency and supports Self-Regulated Learning, countering the over-reliance that fully autonomous assistance can induce.

- **Students put the human at the high-stakes end themselves.** Among 93 undergraduates, 81.7% preferred human scoring for a final paper worth 40% of the grade, 75 of 93 wanted AI to assist rather than replace graders, and 69 wanted AI scoring always human-reviewed (Yildirim-Erbasli et al. (2026)).

- **Trust and calibration.** Transparent human oversight supports Trust Calibration — learners and instructors know a qualified human stands behind the system.
- **Criteria visible before review raise agreement.** Coscia et al. (2026) found that surfacing trustworthiness metrics to reviewers as they compared LLM responses lifted inter-rater agreement from Krippendorff's alpha 0.3987 to 0.4931, while adding further measures added cognitive overhead without return.
- **Bounded agency as an architecture, not a disclaimer.** Ilieva et al.'s (2026) AGAI-HE framework for agentic learning support builds supervision into the model itself, as a third layer alongside the pedagogical-workflow and agentic-support layers: it defines acceptable AI use, pedagogical boundaries, Privacy rules, disclosure requirements, source verification, instructor checkpoints, integrity mechanisms, and final human accountability, and requires every agentic function to trace to a learning requirement, assessment purpose, or governance control. It is a concrete instantiation of the principle that HITL is a system-design property rather than a policy statement — and the authors' 130-student perception study is a reminder that adding agentic orchestration under that oversight did not, by itself, register as better learning support than a chatbot.
- **How often the human looks is itself a design decision.** Venetsanos (2026) separates the *frequency* of oversight from its placement: high-frequency HITL, reviewing every AI output before it reaches students, buys quality control, rapid error detection, accountability and ongoing calibration but can cancel out the efficiency that motivated automation and bottleneck peak marking periods; low-frequency HITL, spot-checking samples and reviewing only flagged cases, scales and shortens turnaround but risks errors propagating undetected across submissions, weakens accountability, and creates an equity problem if some students receive more thorough human review than others. Rather than prescribing a universal answer, the framework requires the trade-off to be made explicitly against disciplinary error tolerances, whether the assessment is formative or summative, cohort size and institutional resources — and sets a default in the opposite direction from the usual efficiency argument: begin with high-frequency oversight and scale it back only when substantial evidence demonstrates acceptable reliability, security and fairness, so the burden of proof rests on showing that *less* oversight is safe. The paper also warns that the principles behind such oversight may shift staff effort rather than reduce it, leaving net efficiency gains an open empirical question.
- Deployed human oversight can mean approval routing rather than quality judgment: in a hybrid query system the acceptance field encoded only whether the resolver differed from the asker, and no measure assessed answer quality Gupta et al. (2026).

Where HITL appears in the knowledge base's research

- **Automated assessment and grading:** HITL systems combine AI generation/scoring with human validation across short-answer grading (Confidence Estimation in Automatic Short Answer Grading with LLMs), self-explanation assessment (Exploring the Effectiveness of Using LLMs for Automated Assessment of Student Self Explanations in Programming Education), and essay scoring (PsyScore: A Psychometrically-Aware Framework for Trait-Adaptive Essay Scoring and ZPD-Scaffolded Feedback). Cvengros & Kortemeyer instantiate this in high-stakes, handwritten

general-chemistry grading: because a Multimodal AI LLM's reliability varies by response format (textual and chemical-reaction answers are reliable while drawing and graphing score worse than random) and false positives go undetected by students, they convert raw AI scores into a selective accept/deferral policy using confidence filters — partial-credit thresholds, an IRT-based risk threshold, and problem-type exclusion — deferring uncertain and graphical items to humans, an approach the authors tie to regulatory frameworks that designate AI in educational assessment as high-risk and mandate documented human oversight.

- **Feedback systems:** mandate documented human oversight.
- **Operational HITL scoring in a national assessment (2026):** Curi et al. (2026) instantiate HITL at institutional scale in Uruguay's Acredita EB exam. Because the LLM scorer's errors are systematically conservative (under-grading), the workflow uses a decision-point logic that routes human review to exactly the candidates whose pass/fail outcome depends on the Writing section — AI-marked passing responses are accepted with confidence, while AI-marked failures (15.3–16.5% of cases) are verified by expert raters, cutting full-scoring workload by ≥50% with a residual AI-error pass risk of only 0.2–0.6%. This is HITL as a resource-allocation strategy: humans adjudicate precisely where AI's conservative bias would otherwise alter high-stakes outcomes.
- **Deriving the deferral threshold from the rubric's own resolution (2026).** Cruz et al. (2026) set the AI–instructor tolerance at 0.5 points — the largest discrepancy that cannot move a submission across an anchor band — and escalated outliers at 0.8 points, sending 11 of 362 submissions (3.0%) to human review before feedback was released.
- **Agreement between annotators is not human ground truth.** Bernado et al. (2026) push model annotation into the audit layer without ever validating it against human gold labels, leaving cross-model agreement (median 0.401) a proxy for assertion quality that shared model errors can survive. Their design keeps oversight diagnostic rather than decorative: because the intermediate judgments are explicit, a reviewer can see which behaviors fired and separate a misread behavior from a rule that encodes the construct badly.
- **Feedback systems:** human-in-the-loop feedback design appears in collaborative feedback systems and confidence-aware short-answer grading.
- **Classroom collaboration support.** CoBi keeps the teacher as the reviewing human in an AI system that detects uplifting small-group discourse: teachers explicitly favored pre/post-action review over live real-time display that would put them "on the spot," and the system's classroom-level (rather than individual) aggregated feedback is precisely what lets it navigate the tension between Privacy, surveillance, and student Learner Agency.
- **Question and content generation:** beyond CODE-GEN, HITL guides question generation for assessment and Scaffolding (CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation, From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations).
- **Agentic and multi-agent systems:** as AI becomes more autonomous, HITL oversight is a core design guardrail (Agentic AI and Pedagogical Best Practice: The Tension Between Automation

and Learning, Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics).

- **Routing by decision consequence, not model uncertainty (2026).** A 2026 operational study of Uruguay's Acredita EB national accreditation test (two editions, roughly 5,000-6,000 candidates each) shows what human-in-the-loop design looks like when it is driven by decision consequences rather than by model uncertainty. A GPT-5 scorer agreed with expert raters on 60-80% of the 15 rubric items but was systematically conservative, producing human-pass/AI-fail discrepancies in 15.3% (2024) and 16.5% (2025) of pass/fail comparisons and almost never the reverse. The framework therefore accepts AI-passing results at face value and routes every AI-failing result that could change a candidate's outcome to expert review — after first skipping candidates whose pass/fail cannot depend on the writing section — cutting responses needing full human scoring by at least 50%. A second 2026 design draws the boundary from the other side: in a multi-agent AI standardized-patient platform (Yang et al.), human oversight is reserved for what AI is judged unfit to decide, with faculty and human standardized patients supplying contextual interpretation, remediation and readiness judgments, and the system explicitly not permitted to determine clinical competence autonomously.
- **Research instrumentation: humans validate labels rather than scores.** Learning-science and computer-science coders judged LLM-generated behavior segments on a synchronized timeline at $\kappa = 0.703$, and their disagreements became the study's own error analysis (Fonteles et al., 2026).
- **The model summarizes and the researcher labels.** A collaborative-modeling study used GPT-3.5-Turbo to write a task-context-aware summary of each of 394 discourse segments, had researchers verify every summary and code them to $\kappa \geq 0.7$, and trained the detectors on those labels, so the model never made the judgment itself. Oversight then moved outward: four experienced teachers reviewed a labeled segment, three recognized the behaviors, and one argued that two labels on one segment obscured what the students were doing, a usability objection the authors recorded rather than resolved (Zhang et al., 2026).
- **HITL as an architecture for a whole discipline, not one workflow.** Zhai et al. (2026) specify four interlocking layers, data infrastructure, model development, pedagogical interface and human governance, held together by three principles: human oversight and agency, co-adaptive intelligence, and contextual responsiveness.

Synthesis

Human-in-the-loop design is not merely a safety measure—it is a **resource-allocation strategy**. The frontier question is not *whether* to include humans, but *where* in the pipeline their judgment has highest marginal value. The most effective HITL systems concentrate scarce human expertise where automated systems are weakest (distractor design, explanatory feedback, edge-case adjudication, ethical judgment) and automate the rest — preserving quality, safety, and trust while scaling production. - **Human oversight persists in AI-assisted work.** Systematic-review research found AI automation tools reduced procedural burdens (e.g. screening) but interpretive decisions still required substantial human oversight; andragogy research makes human-in-the-loop (shared mental models, co-creation) a core AI design principle. - **Human-in-the-loop at institutional scale.** Qin (2026) describes how Lingnan University developed a human-in-the-loop

educational model that foregrounds ethical reasoning, critical judgment, and social responsibility while democratizing GenAI access. The model positions humans as the locus of judgment and values even as AI is embedded across the curriculum — a concrete institutional instantiation of human-in-the-loop principles in higher education. - **Learners as the human-in-the-loop of their own tutoring.** Value Sensitive Design with community college students produced a full family of learner-facing HITL features for an ITS (control over re-assessment and review, personalized goals/pace, bookmarking for review, confirming confidence over mastery, and an AI-assistance involvement-level control). This positions the student as an active controller of the tutoring loop rather than a passive consumer of adaptive decisions. The study also found instructors divided on whether such learner control could undermine the integrity of the system-guided learning path — an instance of the broader resource-allocation question of where human (learner vs. teacher) judgment adds most value. - **Escalation from AI to expert is a human-in-the-loop move.** The SCAN framework assigns tasks to four generative-AI modes by learner distance, and reads passive engagement inside a correctly assigned AI task as a mis-skilling signal to shift the learner from AI to expert assistance, with a human as epistemic auditor (Tsim et al. (2026)). - **Oversight of AI adoption advice.** Because conversational AI systems consulted by skeptical users may be predisposed to encourage adoption, human oversight and independent evaluation are essential. An audit showing most frontier models redirect skeptical rural K-12 staff toward engagement underlines the need for transparent, auditable AI advice rather than uncritical reliance.

Common Misconceptions

- **“Showing the system’s recommendation helps the human supervise it.” Withholding a system’s preferred answer is protective rather than corrective**: in a multi-agent debate that **never revealed a recommended position**, detrimental switching to the AI’s answer **dropped**. Disclosure invited deference; withholding supported judgment.
- **“Human-in-the-loop must mean one human, one decision.”** A multi-agent classroom of Teacher Agent, TA Agent and classmate archetypes was deployed at Tsinghua University with **more than 500 students and more than 100,000 learning records**. Supervision scales through the arrangement, not by multiplying supervisors.
- **“Reviewing AI output is intuitive.”** In a **within-subject study with 23 educators**, a review-based approach **improved every CTML principle (mean rating 3.07 to 3.86, $p < .01$)**, with educators rating production efficiency favorably. Review is a skill that improved under a structured method.

Connected Concepts

- Pedagogical Patterns — Where human review sits in tested sequences, and what has never been tested in isolation
- Guardrails
- Formative Assessment
- Automated Assessment
- Scaffolding
- Teaching

- AI Literacy
- Intelligent Tutoring
- Feedback
- Student Experience
- Self-Regulated Learning
- Metacognition
- Educational Development
- Generative AI
- Learner Agency
- Pedagogical Safety
- Trust Calibration
- Agentic AI
- Cognitive Offloading
- Cognitive Surrender
- Student Support and Success — human judgment inside an automated support flow

Connected Articles

- Science Literacy: Generative AI as Enabler of Coherence in the Teaching, Learning, and Assessment of Scientific Knowledge and Reasoning — Four-layer HITL architecture for generative AI in science education (Zhai et al. 2026)
- Analyzing embodied learning in classroom settings: A human-in-the-loop AI approach for multimodal learning analytics — Coders validating LLM behavior segments as research instrumentation (Fonteles et al. 2026)
- Analysing AI utilisation in education through learner question types: A constructivist approach — Expert-labeled question classification: humans govern labeling, augmentation, and error analysis (Lee, Atif & Kang 2026)
- Agentic Generative AI in Higher Education: Perceived Benefits, Risks, and Implications for Learning — Human supervision and governance as the third layer of agentic GAI course design (Ilieva et al. 2026)
- Value-sensitive design in action: Designing student-centered intelligent tutoring systems with community college students and instructors — Value-sensitive design of student-centered ITS (learners in the tutoring loop)
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — HITL AI-assisted scoring in a large-scale national writing assessment (Curi et al. 2026)
- AI as Teammate: Rethinking Task Distribution in Medical Training — SCAN framework: rethinking AI task distribution in medical training (Tsim et al. 2026)
- A scoping review of generative AI-powered agentic AI in education: Research landscape, agentic capabilities, and insights from the frontier agent paradigm, exemplified by OpenClaw

- AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education
- Calibrating Trustworthiness: Co-Designing Metrics and Visualizations for Evaluating LLMs in Education
- CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation
- Confidence Estimation in Automatic Short Answer Grading with LLMs
- TeachArena: Are language agents ready for realistic teaching work?
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations
- LLMs Do Not Grade Essays Like Humans — LLMs do not grade essays like humans (Mathew et al. 2026)
- Adult learners' perspectives of AI applications in supporting andragogy — AI Applications in Supporting Andragogy (Kim et al. 2026)
- Scaffolding systematic reviews in learning design and technology through mentoring and AI integration — Scaffolding Systematic Reviews with Mentoring and AI (Wang 2026)
- AI-assisted, instructor-supervised grading and feedback in higher education: Design and evaluation of an end-to-end pipeline — AI-assisted instructor-supervised grading and feedback
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- A Tripartite Feedback Framework for AI-Assisted Assessment of Complex Reports in Higher Education — Tripartite framework: sorting feedback by epistemic status and the five boundary principles for AI involvement (Venetsanos 2026)
- AI-Assisted Social Story Intervention for Special Education: The Design of AdaptED Stories — AI-Assisted Social Story Intervention for Special Education: The Design of AdaptED Stories
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues

- From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026 — From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026
- Large language models as grading assistants in public health education: a method-comparison study of essay-style exam assessment — Identical LLM grading reruns on different days reproduce at only Krippendorff’s alpha 0.625
- When Do Undergraduate Students Prefer AI? Insights into AI Scoring and Feedback — Undergraduates prefer human scoring for high-stakes work and AI as an assistant, not a replacement
- What Students Actually Ask: Demand Structure and Automation Potential in a Hybrid Support System — What Students Actually Ask: Demand Structure and Automation Potential in a Hybrid Support System
- Rethinking "In-The-Loop" Approaches in Educational AI: A Learning Sciences Perspective — Rethinking “In-The-Loop” Approaches in Educational AI: A Learning Sciences Perspective
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Withholding the system’s preferred answer cut deferral to incorrect AI advice, protectively rather than correctively

Connected FAQs

- How Can AI Agents Support Students and Instructors?
- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- How Can AI Help Me Give Better Feedback at Scale?

Learning Analytics

> **Learning analytics** — the measurement, collection, analysis, and reporting of data about learners and their contexts for the purpose of understanding and optimizing learning. AI has transformed learning analytics from descriptive dashboards to predictive and prescriptive systems.

Questions to Consider

- Most people assume collecting more learning data automatically improves education. The page argues analytics become meaningful only when they feed back into an intervention — otherwise they merely describe or flag without changing learning. Where have you seen data collected that never led to any action?
- Imagine a dashboard tells you a student is ‘at risk’ — a prediction. What separates that from genuinely actionable guidance that a teacher or institution can actually carry out? The page suggests prediction alone is not enough.
- The page notes AI has moved learning analytics from describing what happened to predicting what will happen and prescribing what to do next. Which of these three generations have you experienced, and what was missing in the others?
- In one study, three different AI models produced sharply different support plans for the same student data, and the links between analytics indicators and recommended help were mostly weak. What does this suggest about trusting an AI’s advice at face value?
- Learning analytics sits in a privacy tension: the more granular the data, the more revealing — and the more powerful the intervention. Where would you draw the line on what is collected about you or your students, and who should decide?

Introduction

AI-enhanced analytics

- **Predictive analytics:** Machine learning on learner interaction data predicts outcomes — from at-risk identification to knowledge state estimation.
- **Validation matters as much as prediction.** Schuetze, Yan, and Carvalho (2025) show that predictive knowledge-state models (BKT, BKT-with-Forgetting, AFM) look accurate when fit retroactively to a full session history, yet under **time-based cross-validation** — predicting the next session from prior ones, how analytics are actually deployed — they overestimate learner performance, miss spacing/forgetting dynamics, and can mis-order practice conditions. The caution for analytics: retrospective fit can mask poor forward predictive validity on longitudinal data, so indicator and dashboard models should be validated walk-forward.
- **Validate the item-attribute mapping behind the estimate.** The Q-matrix linking items to attributes is an assumption, not data: rejected entries for 14 of 918 analytical-thinking items, once

corrected, cut a spurious knowledge-state pattern from 14.2% to 3.8% — so mastery analytics should audit their Q-matrix, not only their predictive fit (Feng & Huang, 2026).

- **Curriculum-anchored predictive analytics:** Pradeesh et al. (2026) estimate knowledge states within Outcome-Based Education by tracing course outcomes directly from LMS interaction and attainment data, using OBE affinity mappings (course–program outcome relations) to structure concept links and a memory-augmented network to model cross-outcome impact — reaching 89.81% AUC and beating DKT, DKVMN, EKT, and SimpleKT on live university engineering data, while staying only competitive (not superior) on general-purpose ASSISTments data.
- **Interpretable progress prediction with an action window:** Zhang, Jeffries & Koprinska (2025) predict module-level student progress in large-scale online programming courses from content-interaction log features, using glass-box decision trees that match black-box accuracy (85–91%) while flagging "No submission" dropout outcomes up to 7–8 days before module deadlines — an explicit, real-time window for intervention rather than a bare risk flag, and an exploratory typology of disengaged-at-risk, disengaged-but-successful, and engaged high-performer profiles.
- **Approval does not predict the engagement pattern.** Trace data from a learner-facing analytics tool in a GAI-supported programming course split 27 students into Deep, Self-Oriented and Peer-Oriented Explorers plus a final-stage Limited Explorers profile, yet favorable perceptions of the assistant did not differ significantly across those profiles (Sun et al. (2026)).
- **Federated, explainable risk modeling across institutions (2026).** Villegas-Ch et al. (2026) extend risk modeling beyond single-institution prediction by training a multitask (performance + dropout) model across simulated institutions via federated learning, so raw student data never leaves each institution. Under controlled heterogeneity (label skew, class imbalance, temporal drift, structural missingness) the model preserves ranking accuracy (OULAD AUC 0.918) and structurally stable feature-importance rankings, yet probabilistic calibration drifts — decoupling ranking performance from probability reliability. For early-warning systems this is a caution that threshold-based interventions may need per-institution calibration, and an argument for evaluating analytics along discrimination, calibration, robustness, and explainability at once.
- **Synthetic-data validation is a prerequisite for privacy-preserving analytics.** A structural check on synthetic versions of four annual study-habit cohorts (117-120 learners over eighteen weeks) found partition descriptors agreeing closely in two of four cohorts while week-to-week variation ran 2.6 to 4.9 times lower without exception (coefficient of variation 0.086-0.152 against 0.399-0.539 for the real cohorts), and only 36% of findings reached on synthetic pilot data were confirmed on the real data across twenty-five validation requests (Inoue & Yasutake (2026)).
- **Engagement analytics:** Engagement measurement and intensity modeling quantify how students interact with AI systems.
- **Completion rates can hide an engagement collapse.** In a group-randomized university trial, a course-integrated AI tutor left homework submission unchanged while platform participation fell sharply — page views by 0.37 standard deviations, active days by 0.51 — so the analytics signal that mattered was the activity the tool displaced, not the completion metric that stayed flat (Liu et al. (2026)).

- **Feedback analytics:** Feedback classification and quality assessment analyze the feedback students receive.
- **Network analysis:** Co-Occurrence Network Analysis and epistemic network analysis reveal interaction patterns.
- **Privacy tensions:** Privacy concerns grow as analytics become more granular and AI-driven.
- **A governance review framework for student data.** LEAGUE proposes six pillars — Lawfulness, Equity, Agency, Governance, Utility, and Ethics by Design — treating FERPA and GDPR compliance as the floor and recommending scheduled reassessment as models drift (Varadaraju & Vijayakumar (2026)).

Sensor and gaze analytics is a second instrument family feeding the same learner models, drawing on eye tracking, EEG, electrodermal activity and heart rate to estimate attention, engagement and cognitive load (Sensor and Gaze Analytics). Its validity and consent problems are steeper than trace data's, because the measurements are biometric and the step from body to mental state is an interpretation.

Model course concurrency, not just sequence. TRACE gives every course in a semester the same positional encoding, and jointly predicting courses and grades cut grade-prediction error to 0.1339 MAE — a 46.4% reduction over a grades-only transformer — on ten years of institutional data (Savala (2026)).

Interaction data is a representation problem before it is a modeling one. Taufer et al. (2026) treat each human-AI exchange as one structured record carrying the computation that motivated the request, the request, the response, the user's feedback and the execution that followed, rather than as an isolated prompt. Across 140 student-assignment pairs in a 35-student deployment, interaction count alone correlated with successfully executed cells at $r = 0.12$, and the same call could be an error recovery, a next step, a concept check or a validation depending on the state around it. Thirty-seven pairs with access produced no interactions at all, so absence of AI use in a log cannot be read as absence of need.

The learning analytics cycle

Learning analytics is canonically framed as a cycle that begins with learner activity producing data, which is processed into measures and indicators that are then translated into **interventions** — and the intervention feeds back into learner activity to close the loop. The intervention step is what distinguishes analytics from mere monitoring or prediction: without it, analytics describe and flag but never change learning. This cycle is the organizing frame for understanding where AI tools (dashboards, feedback generators, prescriptive recommenders) sit in the pipeline and which step they automate.

A learner-facing dashboard is only as good as its reach: in a Hong Kong Grade 9 writing study a prompt classifier reached a macro F1 of 0.757, about a third of the 46 students opened the three GenAI-use dashboards and the group differences in copying and learning-oriented prompting were not reliable (Fong et al. (2026)).

A frequency encoding of qualitative data is an entry point, not a verdict: in a ten-participant study, some instructors read frequency encodings as a productive way in while others warned they obscure rare but critical responses, so the design keeps every aggregate view linked back to verbatim student text (Nguyen et al. (2026)).

From description to intervention

- **The evidence base is not yet intervention evidence.** Synthesizing four studies across student, disciplinary, educator and institutional levels, Rienties, Divjak and Law (2026) find the field dominated by cross-sectional, self-report, discourse-based and expert-judgment designs, and call for intervention research testing causal mechanisms and longer-term, distributional outcomes.

Learning analytics has evolved through three generations in the knowledge base: descriptive (what happened?), predictive (what will happen?), and prescriptive (what should we do?). AI enables the prescriptive layer — analytics that directly trigger instructional interventions. A key frontier is the **actionability gap**: SC2R (Le, Abel & Laforge 2026) shows that prediction alone is insufficient for decision support, and that counterfactual recourse becomes operationally meaningful only when recommendations are semantically feasible and machine-checkable — constrained by timing, budget, immutability, and availability via SHACL validation, rather than merely model-valid. This moves the field beyond risk scores toward recommendations that institutions can actually enact, with human oversight preserved.

A direct empirical test of the prescriptive layer comes from López-Pernas et al. (2026), who asked three LLMs to recommend support plans for 4,500 synthetic student vignettes.

A complementary, teacher-centered test of how analytics reach the classroom comes from Mejia-Domenzain et al. (2026), who designed a learning analytics dashboard (DashED) to communicate ML-derived Self-Regulated Learning profiles to teachers in two blended contexts. Their 100-teacher study shows that the *presentation* of analytics is itself a barrier to action: teachers systematically preferred simpler, more traditional charts (bar plots, pie charts) even when more complex designs (e.g., heatmaps) yielded richer insights, and higher visualization literacy predicted deeper, more detailed interpretation (e.g., more teachers identifying trends in time-series data). For group comparison, teachers favored superposition over juxtaposition and full-information plots over explicit difference encoding. The actions teachers proposed were shaped by the content represented and their Teaching level rather than the plot type — university teachers favored weekly tests and course-level adaptation, while vocational teachers proposed direct, individualized coaching — so the prescriptive step depends as much on how analytics are visualized as on the model. Their finding is cautionary: correlations between LA indicators and recommended support were mostly weak, cross-model recommendations diverged sharply for the same student, and support was frequently allocated regardless of who needed it most. The authors conclude that current LLMs are **not yet reliable as prescriptive models for student support at scale**, reinforcing that the prescriptive step still requires validation, fine-tuning, and human oversight rather than off-the-shelf automation.

The step after the score — who gets support, and whether it was allocated where it was needed — belongs to student support and success, which carries the outreach, referral, and allocation evidence this page's prescriptive layer feeds.

An integrity outcome enters the same predictive layer. Akçapınar (2026) predicts AI-assisted cheating risk from the first eight weeks of Moodle and video-player traces, reaching an AUC of 0.763 with logistic regression, and argues the signal is usable precisely because it arrives before the exam rather than during it. A complementary line targets the *interpretation* of analytics itself. Marques et al. (2026)'s FACTRIA framework organizes the biasing factors behind an indicator - pipeline, institutional, course, and demographic - and a reflection-prompting chatbot raised the sub-factors 11 stakeholders weighed per case from 1.41 to 3.45 (d = 2.15), shifting them from direct readings to conditional ones.

Methods and network analysis

Network methods are core to learning analytics: transition network analysis (TNA) models temporal sequences of learner actions (e.g., the revision and chat loops in chatbot-scaffolded writing), and epistemic network analysis (ENA) maps how codes/constructs co-occur across activity — together revealing the *process* of learning and learner-AI interaction rather than only its product.(Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing)(Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing)

- **Clustering clickstreams in self-directed model building.** An, Hammock & Goel (2025) combined activity sequence analysis, hierarchical clustering, and Markov chain models on the clickstreams of 315 online learners who built 822 ecological models in VERA, distilling nine fine-grained, transition-based behavioral clusters into three broader patterns (Observation, Construction, Exploration). Their work demonstrates that combining sequence analysis with Markov chain modeling can uncover meaningful behavior in unstructured, self-directed tasks even in the complete absence of demographic or contextual data.
- **LA and GenAI shape learning design differently (2026).** Claassen et al. (2026) used ENA on 11 instructor focus groups to compare how learning analytics versus Generative AI inform Learning Design decision-making. LA discussions centered on contextual information, course-level design, and creative Problem Solving (LA for diagnosing engagement and targeting support), while GenAI discussions centered on assessment design and designing for student self-determination (GenAI for ideation and assessment development). Context and Creativity were central across both — a reminder that analytics inform design only within pedagogical context and instructor autonomy.
- **Talk beats fusion when the construct is social, and the best source is per construct.** Rather than maximizing modalities, a LAK26 comparison of five feature configurations on collaborative modeling segments found text-only embeddings strongest overall (mean ROC AUC 0.650, 95% CI 0.615 to 0.685) against text plus logs (0.613) and text plus logs with a context window (0.623). Logs measured 0.526 alone, near chance for a social construct, yet they were the only source that improved detection of reflection (0.5862), while planning depended on the surrounding talk rather than on environment traces. Feature choice is a claim about the construct, not a budget decision (Zhang et al., 2026).
- **Behavioral traces are not measures of cognitive state — especially for special-needs learners.** Vasileiou et al. (2026) warn that interaction traces (time on task, repeated errors, Help-Seeking, irregular progress) can help teachers locate where a learner needs support, but are not transparent measures of internal states: slow responding may reflect careful thought, language processing, distraction, inaccessible design, or technical difficulty. “Algorithms should not infer an executive deficit or diagnostic status from behavioral data alone” — analytics are defensible as one source of information within professional assessment and dialogue with the learner.
- **Design analytics: mining planned activity sequences rather than traces (2026).** Divjak, Svetec and Horvat (2026) applied Markov chains and sequential pattern mining to the *designed* sequence of 29,064 teaching and learning activities across 554 courses planned in an open learning-design tool. The transition matrix peaked at Assessment to Discussion (0.332), self-transitions dominated

Practice (0.317) and Acquisition (0.292), and the strongest consecutive rule was Acquisition to Assessment to Practice to Practice (confidence 0.743, lift 1.449), while the most frequent four-step path was Acquisition, Practice, Practice, Assessment (120 occurrences). Discussion and Assessment were the most reachable types and Production the most distant and sporadic. The study is a reminder that learning analytics need not begin with LMS traces: design-time data can expose the pedagogical grammar of a course before any student arrives, though the authors stress that resemblance to flipped, inquiry-based or project-based designs is not evidence of intent.

- **Self-explaining distilled LLMs (2026):** A two-stage pipeline distills a black-box learning-analytics estimator and its post-hoc interpretation into a small, open-weight Large Language Models (LLMs) that returns both an individual-level estimate and a natural-language explanation. A faithfulness-first audit evaluates whether narrations match the attributions they describe; Simulation shows near-lossless recovery ($r > .90$) with an oracle mentor, offering a more transparent, deployable path for analytics (Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics).
- **Enablers of LA-based educational interventions (2026).** Svetec, Divjak & Kadoić (2026) identify and prioritize seven enablers of trustworthy LA-based educational interventions via Delphi + AHP + SNAP: institutional strategic orientation, pedagogical & other research foundations, available resources, pedagogical support, ethics & data governance, stakeholder engagement, and quality assurance. Institutional strategic orientation ranked highest (and most influential on other enablers), with available resources second. Trustworthiness (ethical compliance, transparent/unbiased algorithms, pedagogical validity) is framed as the prerequisite without which LA-based interventions are not meaningful.
- **LLM interaction depth predicts task quality but not recall (2026).** Tsiligkiris (2026) links turn-level LLM conversational telemetry (Depth/Volume/Pacing) to learning outcomes: explanation-seeking "depth" predicted independently marked task quality ($\beta = 6.27$) but not immediate recall — a dissociation between elaboration-driven comprehension and retrieval-driven consolidation that has implications for how Large Language Models (LLMs) interaction is measured and evaluated in LA.
- **A shared interaction unit is missing.** Across 46 categorizations from 33 studies there is no shared meta-characteristic — similar labels name different phenomena — so the review proposes the *interaction episode*, a goal-directed bounded exchange, as the unit for correlating dialogue with skill acquisition (Borchers, Jansen & Weidlich (2026)).
- **Simulating collaborative discourse for learning analytics.** Fang (2026) uses fine-tuned participant-specific LLM agents to reproduce collaborative problem solving dialogues, validated with Epistemic Network Analysis (ENA distance 0.17, permutation $p = 0.65$). The approach offers learning-analytics researchers a scalable way to generate authentic collaborative discourse for studying interaction dynamics, turn-taking, and thematic code trajectories without collecting new human data.
- **Open, reproducible data and trace-ready analytics.** ASTRA releases a synthetic Benchmark with a trace-ready schema (N=540; 360 sessions; 1,440 episodes) for analyzing interaction and participation balance in collaborative programming. Log and trace data are the natural

counterweight to self-report in this literature: the same construct is often measured twice, once by asking and once by observing, and the two do not always agree. Separately, an exploratory ML framework with SHAP analysis identified the learning-related constructs most associated with intended academic ChatGPT use among university students, prioritizing interpretability (An Exploratory Machine Learning Approach to Understanding Determinants of Future ChatGPT Use in Higher Education).

- **Reusable analytics infrastructure, validated only in-house (2026).** Bai et al. (2026) reproduced published findings from three Georgia Tech AI assistants by changing configuration values rather than code, though the claim rests on reanalysis of existing single-institution datasets and the one capability extension was done by insiders.

Connections

Learning analytics connects to Knowledge Tracing (the core analytic), Formative Assessment (analytics-driven assessment), Learner Modeling and Adaptive Instruction (the learner representation analytics populate), Privacy (the ethical constraint), and Edtech Platform (where analytics are deployed). Because prescriptive analytics are increasingly evaluated on simulated learners — where synthetic student cohorts substitute for real cohorts in controlled tests — learning analytics also connects to student simulation.

- **What dashboards make visible decides what teachers act on.** Köroğlu et al. (2026) reviewed 27 empirical studies (2016–2025) and built a socio-technical taxonomy of AI-supported lecturer decision-making across eight decision types: instructional, curriculum, assessment, feedback, learning-environment, emotional, administrative and ethical. Learning Analytics Dashboards were the most frequently reported system, and the coding shows support concentrated in the instructional, feedback and assessment decisions that behavioral text and log data can inform, while emotional, ethical, curriculum and learning-environment decisions were rarely supported. The authors read this as an attention effect rather than a capability limit: because the systems rendered behavioral student data visible and actionable, motivation, Metacognition, emotion and environment concerns fell outside what the data invited lecturers to consider.
- **Turning AI analyses into classroom talk is itself a teacher skill.** In four secondary mathematics lessons, one teacher's 47 whole-class orchestrations converted dashboard output into collective argumentation by selecting and sequencing students' warrants, and the study names four recurring types (Lee, Park and Lee (2026)).
- **Analytics that lightens a teacher's load is not analytics that lightens a learner's.** In a review of 23 studies of AI in embodied learning, 62.5% of 40 role tags were sensing roles that appraise a movement, trajectory or artifact — work that otherwise fell to a teacher — and the authors warn that a reduction in teacher workload should not be read as a reduction in learner load. Their reason is a limit on what this kind of coding can show at all: recording the function a system performs says nothing about its effect on the learner, so role frequencies cannot settle whether the system offloaded cognition or deepened it (Kim and Han (2026)).

Process-level instrumentation is the descriptive layer's next step down. Prol et al. (2026) extended an Open Source Parsons-problem platform to record every block placement, removal and submission as a chronological trace, pair each submission with per-block correctness coloring and an attempt history, and

optionally pass the traces through an Large Language Models (LLMs) pipeline that labels recurring difficulty patterns for instructor review. Across 68 students in an upper-division Java software-design course and 36 in an introductory Python course the analysis surfaced the same three difficulties — choosing the wrong exception type, substituting `return` for `throw`, and incorrect control-flow ordering — which correctness-and-attempt counts cannot expose, because they answer *whether* the arrangement was right rather than *what the process was*. The AI acts as an interpreter for the instructor rather than a scorer of the student, and its output is framed as a reviewable hypothesis about a class's difficulties rather than a grade.

- **The learning system wall: log data doesn't generalize across platforms.** MATHia, i-Ready, and IXL each define even basic constructs — an "attempt," a "hint" — differently, so models can't transfer between them. A work-in-progress response attacks the problem from the video side: a Gemini pipeline distills tutoring screen recordings into a single screenplay transcript aligned to native MATHia logs as ground truth. What video recovers that no single stream does: whiteboard Scaffolding, silent calculator work in external tools, and off-screen context that native logs reduce to "idleness." Open challenges remain in temporal anchoring, clock drift, and separating platform events from other learning processes. (Towards breaking the learning system wall using multimodal tutoring transcriptions)
- **Interaction logs can lose to a constant baseline.** Semester-level features from 16,851 LLM-tutor exchanges beat a median predictor of assignment scores by 0.114 points, an interval crossing zero, with 62.1% of error in the lowest quartile (Dong et al. (2026)).

Common Misconceptions

- **"A knowledge-state estimate inherits its validity from the data." The Q-matrix linking items to attributes is an assumption, not data**: rejected entries for **14 of 918 analyzed items** means the mapping itself required adjudication. Validating the mapping is a step, not a formality.
- **LLMs reading clickstreams against named learning strategies.** Radmehr et al. (2026) stage an LLM pipeline that locates evidence for a strategy in a student's trace, judges adherence, and cites the actions behind the judgment, reaching overall quality of 0.735 in a harder simulation against 0.704 for a flat baseline.
- **"Analytics need clickstream traces."** Knowledge states can be estimated within Outcome-Based Education by **tracing course outcomes directly from LMS interaction and attainment data**, using OBE affinity mappings — the institutional record supplies the signal.
- **"Prediction without an action window is useful."** Progress prediction is most usable when it is **interpretable and paired with an action window**: Zhang, Jeffries and Koprinska (2025) predict module-level outcomes, which is a form an advisor can act on, unlike a raw score.

Connected Concepts

- Explainable AI
- Knowledge Tracing
- Learner Modeling and Adaptive Instruction
- Formative Assessment

- Privacy
- Edtech Platform
- Student Engagement
- AI Ed Evaluation
- Feedback
- Higher Education
- K-12
- Large Language Models (LLMs)
- Simulating Students
- Self-Report Measures
- Recommender Systems and Learning Paths
- Student Support and Success — the support side that prediction feeds: referral, allocation, and the outcomes they do or do not move
- Sensor and Gaze Analytics

Connected Articles

- ClickSight: An LLM Framework for Interpreting Student Clickstreams Through Learning Strategies — ClickSight: interpreting clickstreams through literature-defined learning strategies (Radmehr et al. 2026)
- Human-AI Interactions as First-Class Data: A Formal Interaction Model and Runtime for Explainable AI Collaboration — Human-AI exchanges as structured records: prompt counts carry almost no signal about progress
- Supporting mathematical argumentation in AI-integrated lessons: networking instrumental orchestration and teacher noticing — Noticing and orchestrating AI analyses into collective argumentation (Lee, Park & Lee 2026)
- Responsible Institutional Analytics: Interpreting Bias with AI Support — Responsible Institutional Analytics: Interpreting Bias with AI Support
- AI-Supported lecturer decision-making in higher education: a socio-technical perspective — AI-Supported Lecturer Decision-Making in Higher Education
- Federated and explainable learning analytics for privacy-preserving academic risk modeling across heterogeneous educational institutions — Federated and explainable learning analytics for privacy-preserving academic risk modeling (Villegas-Ch et al. 2026)
- What students ask matters: LLM interaction depth, task quality, and immediate recall in higher education — What students ask matters: LLM interaction depth, task quality, and immediate recall (Tsiligkiris 2026)
- From learning analytics to educational interventions: Enhancing decision-making and learning design — From learning analytics to educational interventions: enablers of trustworthy LA-based interventions (Svetec, Divjak & Kadoić 2026)

- Understanding the Role of Learning Analytics and Generative Artificial Intelligence on Decision-Making and Learning Design Practice in Higher Education — LA and GenAI in learning design decision-making
- Analysis and Prediction of At-Risk Students Using Machine Learning Algorithms
- Engagement Intensity as a Learner-Modeling Signal for Adaptive AI Ethics Instruction
- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies
- A Durability and Cross-Language Transfer Benchmark for a Validated Teaching-Feedback Classification Protocol
- Through the WordStream Glass: Revisiting Quantitative Encoding for Qualitative Learning Analytics
- Jointly predicting courses and grades using a transformer-based model
- Toward convergence in student-LLM interactions: A rapid scoping review and taxonomy for learning-oriented use
- From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support — From Student Risk Prediction to SC2R: Counterfactual Recourse
- Bayesian cognitive diagnosis optimizes personalized learning paths via mediation of cognitive load and Hidden Markov Model state transitions — Bayesian cognitive diagnosis for personalized learning paths
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — Distilling self-explaining LM for learning analytics
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- Modelling individual participants as LLM agents in collaborative problem solving simulations — Fine-tuned participant-specific LLM agents reproducing collaborative problem solving dialogues (Fang 2026)
- ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming — ASTRA synthetic benchmark for multi-agent tutoring and participation-balanced collaboration
- An Exploratory Machine Learning Approach to Understanding Determinants of Future ChatGPT Use in Higher Education — ML/SHAP determinants of future ChatGPT use in higher education
- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms
- Outcome-based knowledge tracing with affinity mapping and memory augmented outcome impact — Outcome-based knowledge tracing with affinity mapping
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis

- Capturing Session-to-Session Dynamics of Learning and Forgetting: Testing the Limits of Knowledge Tracing Models
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education
- Learning paths and patterns in learning design: Insights from 500+ courses — Markov chain and pattern mining of 29,064 planned activities in 554 courses, revealing a design grammar led by Acquisition and consolidating Practice
- Pulla: A Parsons Problem Tool for Fine-Grained Behavioral Tracing and Instructor-Facing Problem-Solving Analysis — Pulla: process-level behavioral tracing and instructor-facing difficulty analysis in Parsons problems (Prol et al. 2026)
- Generalizing a Highly Configurable Analytics Pipeline to Replicate and Support Educational Research Across Multiple Domains
- Beyond Compliance: A Proposed Framework for Ethical Governance of Student Data in Learning Analytics
- Using Learning Analytics to Support Secondary School Students' Writing with Generative AI — Using Learning Analytics to Support Secondary School Students' Writing with Generative AI
- "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- Early Prediction of AI-Assisted Cheating Risk in Online Exams Through Learning Analytics — Akçapınar (2026) — Predicting AI-assisted cheating risk from early-semester LMS traces (AUC 0.763)
- Towards breaking the learning system wall using multimodal tutoring transcriptions — Towards breaking the learning system wall using multimodal tutoring transcriptions (Thomas et al. 2026)
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — Completion rates can hide an engagement collapse
- Artificial intelligence in embodied learning: A systematic literature review — AI in embodied learning mostly observes: sensing roles 62.5% of coded role tags, and no reviewed system fused multimodal streams while learners used it (Kim & Han 2026)

Connected FAQs

- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Platforms, openness and adoption

Technology Adoption Models

> **Technology Adoption Models** — the family of theories that explain and predict why individuals and institutions accept, adopt and keep using new technologies, of which the **Technology Acceptance Model (TAM)** is the most widely applied. In AI in education they are the standard lens for asking why learners, teachers and organizations adopt generative AI tools, and the knowledge base treats them together because GenAI-adoption studies draw on several members of the family rather than one.

Questions to Consider

- Think of a time you adopted a new app, tool, or AI service — and a time you abandoned one. What actually drove each decision: how useful it seemed, how easy it was, or what people around you were doing? Which factor do you suspect matters most, and can a survey really capture that?
- A common belief is that 'if a tool is clearly useful, people will use it.' Have you seen situations where a genuinely useful technology still failed to catch on, or a clearly limited one spread anyway? What might explain the gap between objective usefulness and actual adoption?
- Adoption frameworks like TAM were designed in the 1980s for fairly simple systems. If you've used generative AI, in what ways does it differ from a word processor or a learning management system — and why might a model built around 'ease of use' and 'usefulness' struggle to capture how people relate to something that talks back?
- Researchers often say perceived risk and trust matter less for AI adoption than expected. Before reading further, what do you predict: do students adopt AI because they trust it, despite risks, or are those concerns actually minor next to convenience and social pressure?
- The page argues that adoption frameworks treat using a tool as a one-time decision, but effective use may be an ongoing judgment. Where in your own or your students' practice does the line between 'choosing to use AI' and 'continually deciding how to use it well' seem to blur — and what would change if we measured that instead of mere uptake?
- Some researchers cluster learners into different 'adoption personas' instead of assuming one model fits everyone. What differences do you see among your own learners, colleagues, or students that a single average model of adoption might hide — and how could those differences shape how you support them?

Introduction

Meta-analytic evidence on AI adoption. A meta-analysis of tertiary students' AI adoption (233 correlations, 32 studies, N = 16,977) finds moderate positive correlations for individual (r = 0.57), contextual (r = 0.53), and technological (r = 0.50) factors, with usage intentions the strongest predictor (r = 0.64) and perceived risks/trust weaker than expected. Its central critique is that the field **over-relies on traditional TAM/UTAUT** frameworks that predate modern intelligent systems and neglect AI-specific factors such as anthropomorphism and ethics — arguing these gaps matter for advancing theory and evidence-based policy.

- Ease of use stopped predicting once the sample had already adopted. Wei, Zhang and Heo (2026) extend TAM on 526 design students with prior AIGC use and find perceived ease of use was the only technological perception not significantly associated with self-efficacy, while knowledge, trust, reliability, usefulness, intelligence and anxiety each were (Wei et al., 2026). Usage intention was strongly associated with reported dependence in cross-sectional data.

The model family

Technology Acceptance Model (TAM)

Proposed by Davis (1989), TAM explains adoption through two core beliefs — **Perceived Usefulness (PU)** and **Perceived Ease of Use (PEOU)** — which shape users' **Attitude (ATT)**, then **Behavioral Intention (BI)**, then actual usage. Grounded in information-systems theory (adapted from the Theory of Reasoned Action), TAM has become the dominant framework for GenAI adoption in education. In educational GenAI research it is frequently extended with AI Literacy, Trust, social influence, self-determination, and **critical use** to capture adoption complexity beyond simple uptake.

UTAUT / UTAUT2 / UTAUT3

The **Unified Theory of Acceptance and Use of Technology** consolidates TAM with eight prior models into four core determinants — performance expectancy, effort expectancy, social influence, and facilitating conditions (with UTAUT2 adding hedonic motivation, price value, and habit; UTAUT3 adding personal innovativeness). The knowledge base applies UTAUT across teacher and student populations: Austrian secondary math teachers (UTAUT with 448 teachers), pre-service science teachers in Ghana (UTAUT + TPB), and students in Lesotho (UTAUT3 + ARCS, using PLS-SEM and fsQCA). Jácome-Vásconez et al. extend UTAUT2 with explainable AI (Random Forest, SHAP, NCA, IPMA, K-Means) for 522 university students, finding **habit** the strongest predictor of ChatGPT intention and showing that **effort expectancy is a necessary condition rather than a linear driver** — a result only visible when XAI complements the regression.

In an already-adopted sample, habit carries the model and the expectancies go quiet. Pinedo et al. (2026) tested UTAUT2 on 310 marketing students at two Latin American universities: habit predicted intention at $\beta = 0.426$ and use at $\beta = 0.412$, and intention predicted use at 0.324. Performance expectancy (0.037), effort expectancy (0.054) and social influence (0.048) were not significant, in a model explaining $R^2 = 0.665$ of intention and 0.707 of use. The authors read the null paths as variance restriction in a population that had already adopted the tool; the outcome is self-reported use, not logged behavior.

Theory of Planned Behavior (TPB)

TPB explains intention through attitude, subjective norms, and perceived behavioral control. It is frequently paired with TAM/UTAUT in AI-adoption studies — e.g. Rizun et al. integrate TAM, TPB, UTAUT, and the FATE (Fairness, Accountability, Transparency, Ethics) framework to model the behavioral and ethical drivers of student ChatGPT adoption.

Adoption research usually stops at intention; a TPB extension that instead measured delay despite a genuine intention found perceived behavioral control the strongest negative predictor of GenAI-assisted learning procrastination (β = −0.331) across 1,243 undergraduates, with the intention–delay link significant only at moderate-to-high learning GenAI anxiety (Li et al. (2026)).

Diffusion of Innovation (DOI)

Rogers' DOI theory explains adoption as a social process in which innovations diffuse through populations over time, emphasizing innovation attributes (relative advantage, compatibility, complexity, trialability, observability) and adopter categories. It appears in the knowledge base's institutional-level analyses, e.g. Al-Rahmi et al. combine the Technology–Organization–Environment (TOE) framework with DOI to model organizational AI adoption in Saudi universities.

Technology–Organization–Environment (TOE)

TOE frames adoption as shaped by technological, organizational, and environmental contexts — a complement to individual-level TAM/UTAUT for studying institutional adoption (see Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education).

Applications in the knowledge base

Adoption models are applied across the knowledge base to model student and teacher uptake of AI tools:

- **Critical-use extension:** Nguyen et al. extended TAM with *critical use* for engineering/CS students, finding that attitudes and critical use directly predict intention — and that critical use safeguards against over-reliance.
- **Unified socio-cognitive model:** Asag & Al Mamun integrated TAM with UTAUT for engineering students in Bangladesh (explaining 64% of usage variance).
- **Person-centered profiles:** Rather than variable-centered models, Saihi & Ahmed cluster GenAI-adoption personas, and Chen et al. use latent profile analysis to identify four ChatGPT-acceptance profiles among pre-service teachers — showing the field's move beyond single-model, linear accounts.
- **Cross-cultural validation:** Martínez-Moreno et al. cross-culturally validate adoption-related motivation constructs across Switzerland and China.
- **A knowledge mediator beside the expectancy mediators:** Belief to behavior: how AI self-efficacy shapes AI acceptance through AI literacy place AI literacy between AI self-efficacy and acceptance in 622 undergraduates in Türkiye. The indirect path was significant (B = 0.15, 95% CI [0.12, 0.19]) and left a direct path intact (B = 0.43, R^2 = 0.29); acceptance also showed a weak negative association with AI anxiety (B = -0.34, R^2 = 0.05). Where the overtrust work below routes confidence through performance expectancy, this study routes it through what students know about the technology.
- **Psychological correlates:** Wu et al. build on TAM to relate motivation, Self-Efficacy, anxiety, and risk perception to acceptance of AI-assisted English learning.

- **Regulatory competence critique:** Kim argues that adoption-centered TAM models treat use as a stable decision, whereas effective AI use is an ongoing process of judgment, revision, and selective uptake — reframing AI Literacy as regulatory competence and Critical Thinking rather than acceptance.

Adding a TPACK-family capability alongside belief frameworks such as the Theory of Planned Behavior as parallel predictors invites construct overlap and leaves the causal ordering of capability, attitude and control undecided; the Capability–Decision Model instead places AI-TPACK capability upstream of attitude and perceived behavioral control (Mnguni (2026)).

- **ML determinants of ChatGPT adoption:** An exploratory ML approach examined how students' perceptions and demographics relate to intended academic ChatGPT use, using SHAP analysis to identify key learning-related constructs — prioritizing educational meaning over maximizing algorithmic performance (An Exploratory Machine Learning Approach to Understanding Determinants of Future ChatGPT Use in Higher Education).
- **Explainability and domain relevance as acceptance levers for teachers:** Adapting trust-in-automation theory to teacher acceptance of AI recommendations, Feldman-Maggor et al. (2025) found that understandability (raised by explainable AI) correlated positively with both trust and acceptance of an AI grouping tool, and that domain-driven explanations in curricular language outperformed data-driven feature-importance ones on all three. Acceptance was additionally driven by pedagogical alignment and workload-reduction potential — situational factors beyond trust that standard TAM/UTAUT constructs rarely capture, reinforcing the case for extending adoption models with context and explainability.
- **Acceptance measured at the level of instructional materials (2026).** Wang, Chuang and Wu (2026) operationalized Performance Expectancy, Effort Expectancy, Perceived Playfulness, and Behavioral Intention for two age-tiered AI literacy guidebooks used by 794 K-12 students and 37 teachers, validating the four-factor structure with split-sample EFA and CFA and supporting measurement invariance across the 9-12 and 13-18 editions. Younger learners reported higher levels on all four constructs, and playfulness was the strongest correlate of intention in both cohorts — with the standardized playfulness-to-intention coefficient exceeding 1.00 in the younger group and an HTMT of .950 between the two constructs. The authors read that as construct overlap and possible suppression rather than a giant effect, a useful reminder that acceptance instruments applied to materials can produce empirically entangled factors that complicate structural interpretation.

Limits and extensions

TAM's cognitive focus also under-captures emotional and relational dimensions of AI use. A qualitative study of nursing students and faculty found that, alongside the four classic TAM constructs, participants – mainly students – described AI as a source of psychosocial support: emotional comfort during stress and a confidential space for reflection. This extends perceived usefulness beyond performance gains to Well-Being in high-stress professional training, suggesting adoption models should attend to affective and psychosocial factors, not only instrumental utility.

Autonomy perception and risk aversion as tool-specific extensions. A mixed-methods survey of 287 GenAI-experienced teachers across 27 countries and regions (Dai et al. (2026)) extends TAM in a direction the model family has barely touched: the perceived *autonomy* of the tool itself. Adding perceived artificial autonomy (how independently teachers believe GenAI can carry out an assigned instructional task) and risk aversion to the classic constructs, their refined structural model explained 79.8% of the variance in behavioral intention ($\chi^2(97) = 202.597$, CFI =.963, TLI =.954, RMSEA =.062, SRMR =.041), with perceived usefulness again dominant (PU → BI β =.832, p <.001) and ease of use feeding usefulness (PEU → PU β =.479). The instructive results are the detours. Artificial autonomy did not act directly on intention (β =.026, ns) but acted through usefulness (AA → PU β =.188, p <.001; indirect AA → PU → BI =.156, 95% CI [.082,.240]) — teachers who saw GenAI as more capable found it more useful, not more immediately adoptable. Risk aversion lowered intention (RA → BI β = −.163, p <.001) without lowering perceived usefulness (RA → PU ns), because teachers' concerns centered on *students'* use — cheating and integrity, weakened foundational knowledge and higher-order thinking, hallucinations, reduced human interaction, and ethical, legal and equity risks — rather than on their own. Ease of use was non-significant overall (PEU → BI β =.068) but significant among the 225 teachers who had actually used AI in teaching (β =.138, p <.05), the familiar pattern that effort registers only after real encounter; attitude had to be dropped when its correlation with intention (r =.929) breached discriminant validity. Teachers placed GenAI at semi-autonomous levels (130 at Level 2, "teacher assistance"; 94 at Level 3, "partial automation"; one at Level 6) and insisted adoption decisions be made case by case. TAM still predicts intention well, but for teacher-facing AI the constructs that move the needle are tool-specific: how autonomous the tool seems, and whose use the risk attaches to. The authors' "frenemy" label — valued as a support tool, distrusted as an autonomous agent — is the teacher-side counterpart to the student-facing extensions catalogued above.

Risk perception as a dimension-specific extension. A survey of 814 Chinese university students (Du, Ning, Shi & Chen (2026)) folds Cognitive Appraisal Theory and Protection Motivation Theory into TAM/UTAUT2 to ask not whether students adopt generative AI but what they gain from it. The model family's assumption that risk uniformly suppresses adoption does not survive: risk perception splits into information, security, technical, ethical, and legal dimensions that move benefits in opposite directions. Security risk — a threat students believe they can manage through privacy practices — was *positively* associated with perceived academic assistance and skill development, consistent with problem-focused coping, whereas information risk, which learners cannot easily verify, eroded psychological and emotional support, daily-life, and leisure benefits through avoidance. Threshold analyses further showed effects that change sign beyond dimension-specific cut-points, and usage experience mattered independently: students with more than a year of GenAI use reported higher benefits across four domains. The practical implication for acceptance research is that "perceived risk" is too coarse a construct to model — controllability, not the mere presence of risk, is what determines whether students engage or withdraw.

A recent extension inverts the usual direction, placing subject-specific motivational beliefs upstream of the TAM perceptions rather than beside them. Xue, Xu, Qi & Lu (2026) report utility value predicting perceived usefulness at β = 0.43 and expectancy for success predicting ease of use at β = 0.39, while core TAM paths attenuate but stay significant.

Task–technology fit as a parallel path, and necessity as a separate question. Most extensions above add constructs *inside* the belief model. One sibling framework that TAM studies rarely carry is Task–Technology Fit, which asks whether a tool's capabilities match the demands of the specific task. Chu and Liu (2026)

joined the two in 405 design graduate students at Chinese universities, and fit acted as a second route into attitude rather than a determinant of usefulness.

Task characteristics fed fit at β = 0.322 and technology characteristics at β = 0.266. Fit then fed attitude at β = 0.224, beside perceived usefulness (0.376) and perceived ease of use (0.185), and attitude fed intention at β = 0.388. Self-efficacy carried the largest upstream coefficients, 0.458 on usefulness and 0.394 on ease of use. Perceived enjoyment raised ease of use (0.220) and left usefulness untouched (−0.033, p = 0.483) — an instrumental/affective split the classic model does not draw.

The methodological addition is the more transferable part. A multilayer-perceptron network reproduced the PLS-SEM importance ranking in all four models. Necessary condition analysis then found only two floors: self-efficacy for usefulness (d = 0.125, p = 0.015) and attitude for intention (d = 0.132, p < 0.001). Attitude at 22.1%, 34.3% and 46.4% of its scale was required for intention at 80%, 90% and 100%, so attitude behaves as a gate rather than a weight, which is a different claim from a path coefficient of 0.388. The caution sits in the outcome: R^2 = 0.150 and Q^2 = 0.011 for intention say the ten hypothesized paths leave most of the variance elsewhere.

Design features upstream of the beliefs, and importance that is not necessity. Zhang, Xin and Qing (2026) put six system features in front of the two TAM beliefs for 301 Chinese university students, borrowing a stimulus–organism–response frame. Personalization and interactivity moved perceived usefulness alone, while intelligence and content completeness moved ease of use alone. Responsiveness moved both; anthropomorphism moved neither. The model explained R^2 = 0.244 of intention (SRMR = 0.033), with ease of use ahead of usefulness on intention (β = 0.340 against 0.265). Ten-fold cross-validated network importance agreed, ranking ease of use at 100% against 84.70% for usefulness.

Necessary condition analysis then separated influence from requirement. Ease of use, the top-ranked predictor, failed outright (d = 0, p = 0.592). Usefulness was necessary but small (d = 0.027, p = 0.011). The authors read the split as a caution against treating a path coefficient as a floor. A strong coefficient says a unit of ease buys intention on average; only necessity says whether the other belief can be absent.

Risk's link to use also depends on the system: across the 49 TALIS 2024 systems that administered the items, perceived AI utility was positively associated with AI use in all 49, while perceived risk was negatively associated in 40 and positively in nine (Fang & Jin (2026)).

Performance expectancy can carry a relationship that acceptance research reads as intention to use. In Kim, Kim and Zhang (2026) performance expectancy predicted AI overtrust at B = 0.6107 and was the first mediator through which self-efficacy, intrinsic motivation and extrinsic motivation reached overtrust. The expectancy-only indirect path was positive for all three predictors, 0.1355 (95% CI [0.0542, 0.2330]) for self-efficacy, so expectancy was not merely predicting whether students would use the tool.

Common Misconceptions

- **"TAM's constructs explain adoption."** Asag and Al Mamun integrated TAM with UTAUT for engineering students in Bangladesh and explained **64% of** the variance. Substantial and incomplete at once: roughly a third of what drives adoption sits outside the classic acceptance constructs.

- **“Acceptance models need no domain modification.”** Adding **perceived artificial autonomy** — how independently teachers believe GenAI can carry out an assigned instructional task — and **risk aversion** to the classic constructs changed the model materially. The original constructs were built for tools without agency, and GenAI has perceived agency.
- **“A meta-analytic adoption estimate describes any population.”** The meta-analysis of tertiary students is the population-level estimate; the engineering result explaining 64% is a specific population. Importing one onto the other assumes a stability the evidence does not establish.

Connected Concepts

- Business Education
- Generative AI
- AI Literacy
- Student Experience
- Higher Education
- Critical Thinking
- Ethics
- Trust
- Cognitive Offloading
- Self-Determination Theory
- Research Methods in AIED
- Learner Modeling and Adaptive Instruction
- Framing AI Use for Students

Connected Articles

- Modeling high school students’ acceptance of GenAI for physics learning via an extended technology acceptance model: Disciplinary beliefs as a distal antecedent — Subject-specific beliefs placed upstream of the TAM perceptions
- GenAI as a frenemy in teaching: Perceived autonomy and risks — GenAI as “frenemy”: artificial autonomy and risk aversion extend TAM for teachers (Dai et al. 2026)
- Nursing Students’ and Faculty Experiences with Artificial Intelligence in Education: A Qualitative Study Using the Technology Acceptance Model — Nursing AI experiences; psychosocial extension of TAM
- Uncovering adoption personas for generative AI in higher education: a clustering-based segmentation approach — GenAI adoption personas via clustering
- Decoding symmetric and asymmetric pathways in generative AI learning adoption: a multi-method study — Symmetric and asymmetric pathways in GenAI adoption (UTAUT3 + ARCS)

- Differential engagement with generative artificial intelligence in higher education: Gender, motivation, and achievement trajectories — Differential GenAI engagement by gender and motivation
- Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education — TOE + DOI model of organizational AI adoption in higher education
- Factors influencing university students' intention to use and reliance on generative artificial intelligence: An extended technology acceptance model with critical use — Extended TAM with critical use for engineering/CS students
- Social and cognitive drivers of generative AI adoption: A unified socio-cognitive model for engineering education — Unified socio-cognitive model (TAM + UTAUT) for engineering education
- From AI anxiety to strategic regulation: How university students transform generative AI into a strategic learning resource — From AI anxiety to strategic regulation
- Measuring How Students Rely on Generative AI in Academic Writing: Development and Multi-Source Validation of the Generative AI Reliance Types Scale (GenAI-RTS) — GenAI reliance types scale
- Four Types of LLM Reliance and Their Predictors Among Undergraduate Writers: A Mixed-Methods Study at a Minority-Serving R1 University — LLM reliance types among undergraduates
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — Acceptance of AI English tools
- Generative AI in higher education: Ethical and behavioral factors influencing students' intentions to use ChatGPT — Behavioral and ethical drivers of student ChatGPT adoption
- Talking mathematics with AI: Understanding teachers' motivation for utilizing chatbots — UTAUT and teacher chatbot motivation
- Perceptions and Acceptance of Artificial Intelligence in Science Education Programmes: Voices of Pre-Service Science Teachers — UTAUT + TPB for pre-service science teachers in Ghana
- Unpacking the heterogeneity of pre-service teachers' ChatGPT acceptance: a latent profile analysis across STEM and non-STEM disciplines — Pre-service teacher ChatGPT acceptance profiles (LPA)
- Factors associated with students' adoption of artificial intelligence technology in tertiary education: A meta-analytic review — Meta-analysis of AI adoption factors; critiques TAM/UTAUT
- An Exploratory Machine Learning Approach to Understanding Determinants of Future ChatGPT Use in Higher Education — ML/SHAP determinants of future ChatGPT use in higher education
- Explaining ChatGPT Adoption in Higher Education: Insights for AI Literacy, Educational Practice, and Responsible AI — XAI-augmented UTAUT2: habit as strongest predictor, four adoption profiles (Jácome-Vásconez et al. 2026)

- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- Measuring Acceptance of Age-Tiered AI Literacy Guidebooks: A Developmentally Informed Study of K-12 Students and Teachers — Material-level PE/EE/playfulness/intention model for age-tiered AI literacy guidebooks, with documented playfulness-intention construct overlap
- The impact of risk perception on perceived benefits of generative artificial intelligence users—an empirical study based on university students — CAT + PMT folded into TAM/UTAUT2: dimension-specific and non-monotonic risk effects on perceived GenAI benefits (Du, Ning, Shi & Chen 2026)
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Ordered alternative to bolting TPACK capability onto Theory of Planned Behavior adoption models
- Teachers' AI Belief Profiles and Their Associations with AI Use, Pedagogical Applications, and Barriers: A Person-Centered Analysis of TALIS 2024 — Person-centered TALIS 2024 profiles of perceived AI utility and risk across 49 systems
- GenAI Use and GenAI-Assisted Learning Procrastination in University Students: The Roles of Planned Behavior Constructs and Learning GenAI Anxiety — TPB extension measuring GenAI-assisted learning procrastination and anxiety's moderation of the intention–delay link
- Trusting AI too much? Psychological correlates of overtrust and the role of AI literacy - performance expectancy mediated the path from motivation and self-efficacy to AI overtrust
- Belief to behavior: how AI self-efficacy shapes AI acceptance through AI literacy - AI literacy as the mediator between self-efficacy and acceptance, with an uncorrected anxiety association (İşbulan et al. 2026)
- Cognitive mechanisms of AI agent behavioral intention among design graduate students: an integrated TAM–TTF perspective — TAM joined with Task–Technology Fit, plus neural-network importance ranking and necessary-condition thresholds (Chu & Liu 2026)
- Symmetrical and asymmetrical insights into student adoption of AI-enhanced digital educational systems — Design features upstream of TAM beliefs, and importance that is not necessity
- Adoption of generative artificial intelligence by university marketing students — Habit carries UTAUT2 in an already-adopted population

Open Education

> **Open education** — the movement and the practice of teaching with openly licensed content, and the pedagogy that treats students as producers of it rather than consumers. Its two artifacts are the open educational resource and the open pedagogical assignment; its license is what makes reuse lawful, and its claim is that both lower cost and widen authorship. Generative AI now presses on all three: it collapses the cost of making content, it muddies who authored a remixed resource, and it gives institutions a cheap alternative to the commons they were asked to fund.

Questions to Consider

- If a model can draft a course unit in minutes, what still justifies the license, the attribution trail, and the review process that open content carries with it?
- A resource can be open by license and closed in practice: the file is downloadable but the course around it assumes a lab, a language, or a connection students do not have. Which openness are you measuring when you report adoption?
- Open pedagogy asks students to publish their work. Who owns what a student makes with a generative tool, who consents to its release, and who carries the cost when it is wrong?
- Teacher AI literacy predicts open teaching practice, but the relationship weakens as institutional support rises. What does that inversion imply about training programs built on the assumption that support only helps?
- If AI-generated text is not copyrightable, is a machine-written textbook automatically open, and what does that do to the case for public funding of OER?

Introduction

Open education is not open source, and the confusion costs both. Open source is about **artifacts a developer ships and licenses**, principally code, model weights and datasets, so that a system can be licensed, audited, modified and redeployed. Open education is about **what a teacher assigns and what a student produces**, and its licensing exists to let a second institution substitute, translate, remix or correct a resource without asking permission. The two share a legal machinery (Creative Commons, in education; permissive software licenses, in code), a production model (volunteer and grant-funded communities), and now a shared antagonist in generative AI, whose capacity to produce the artifact nearly free unsettles the economic case for both.

They differ where it matters. An open-source release is judged by whether the system can be rebuilt and inspected. An open resource is judged by whether a teacher with different students, a different language and a different budget can actually use it, which is a pedagogical claim rather than a technical one, and which is why open education has always carried a practice argument alongside its licensing argument. Deimann and Lukács (2026) make the sharpest version of that point: after twenty-five years of openness advocacy, the institutional regime in the middle of education was left intact, because the movement concentrated on declarations and niche projects.

The AI-era literature in this knowledge base is therefore about three things at once: the resource, the practice, and whether either survives when generation is nearly free. On the resource, the questions are who makes it, who licenses it, and whether an AI-written one counts. On the practice, they are what open pedagogy asks of students and whether it teaches them anything measurable.

What openness actually covers

An open educational resource is content released under a license that permits reuse, revision, remixing and redistribution. Everything else in the field is downstream of that permission and of the obligation to attribute it. González Miy (2026) shows what the obligation looks like in a small project: eleven participants working online for two weeks produced a six-page site, a chatbot, a manual and five video tutorials, released under CC BY-NC-SA, and the resulting package scored high on transparency while scoring only medium on licensing, replicability, adaptability and accessibility. Open in name, partially open in use.

The licensing literature is granular because the failures are granular. Ryu (2026) builds a seven-principle rubric for reviewing openly licensed AI literacy material from a purposive corpus of sixteen core papers, a seventeen-paper extension and thirty-six targeted references. Atenas, Farrow, Caldwell, Costello and Havemann (2026) argue that the unit of governance should move from the resource to the infrastructure that hosts it, since a commons of individual files without a maintained platform is a fragmentation problem rather than a commons.

Generation collapse and the digital public goods turn

Course production is where the shift is already measurable: MAIC reports collapsing MOOC production from roughly $25,000 and 60 hours per course to under $2 and 30 minutes with Large Language Models (LLMs)-driven multi-agent generation. If production cost approaches zero, the argument that OER saves money loses its force, and what remains is licensing freedom, verifiability and quality assurance.

Tlili, Farrow, Bozkurt, Amiel, Wiley and Downes (2026) organize that shift around five framing questions and reach an unsettling legal reading. Because the United States Copyright Office treats prompts alone as insufficient for authorship, a purely AI-generated resource may fall into the public domain and qualify, on a strict reading, as open by default. Their term for the opposite failure is openwashing, where an artifact is presented as open while its training data, its pipeline or its license is not. The authorship question is also a legal question before it is a licensing one, and the legal and copyright side runs through misconduct as much as through ownership.

The policy response in this literature is to reclassify. Atenas and colleagues propose treating OER as digital public goods, which moves the remedy from producing more content to building publicly governed, non-commercial infrastructure. They measure that infrastructure against the ROAM-X principles and the FAIR data standards, and describe a landscape already holding over two billion openly licensed works and 303 Internet Universality Indicators. That is a defensible redirection of a movement that spent two decades on content production.

The institutional case for openness is also made on autonomy. Panda (2026) argues in an editorial that digital transformation in open and flexible learning is pedagogic transformation rather than technology adoption, and that a technology earns credence only when it aligns with an appropriate pedagogy in a local context.

Rodés-Paragarino and Atenas (2026) turn that into a seven-pillar framework for responsible integration of OER and generative AI, built from a documentary analysis plus expert validation and a participatory workshop with 81 participants in Bilbao in December 2025.

Open pedagogy and the practice turn

Open pedagogy moves the student from consumer to contributor: an assignment produces something that is published, licensed and reusable. Clinton-Lisell (2026) provides the field's cleanest test of the idea. Two sections of an introductory child development course updated the same textbook, one of them with generative AI tools. Across 113 assignments, students in both sections reported growing information literacy skill, and the gain was statistically indistinguishable between them: a time effect of $F(1, 84) = 47.30$, $p < 0.001$, partial $\eta 2 = 0.36$, against a time by section interaction of $F(1, 84) = 0.04$, $p = 0.85$. The AI section completed more work and scored slightly lower, 174.73 against 173.86 out of 180.

Practice has a maturity literature of its own. Duan (2026) screened 540 records to fourteen models of open educational practice under PRISMA 2020, compared them on three dimensions, and concluded that generative AI sits underneath established models rather than displacing them, an argument the paper locates against Technological Pedagogical Content Knowledge (TPACK). Ahmadfard (2026) reaches a similar conclusion about interactivity in a structured review running from 1970: interactive features are a design argument more than a demonstrated effect, and the strongest effect sizes it reports are borrowed from earlier physics education work rather than measured in OER.

Two further studies show how quickly the practice layer becomes a governance layer. Patiño, Martínez-Pérez, Ramírez-Montoya and Miranda (2026) document a UNESCO and ICDE residency of 110 participants from 13 countries in 10 teams, but their survey base is 72 responses from 54 institutions with no response rate, which is thin support for a roadmap aimed at the UN 2030 Agenda. And Guo, Lu and Gao (2026) surveyed 512 teachers across 30 Chinese provinces on whether AI literacy translates into open teaching practice, finding an indirect path through innovative behavior of 0.218 at low institutional support that falls to a non-significant 0.042 at high support.

Equity, sustainability and the Global South

The equity argument for open content is the oldest one: a resource without a price cannot be priced out. It is also the one most easily asserted and least often tested. The AI-era versions are more careful. Atenas and colleagues frame OER as a lever for marginalized communities and for meaningful participation in data collection, while warning that over-reliance on generated resources risks devaluing human Creativity and judgment. Tlili and colleagues name the mechanisms by which generation degrades that lever: translation error, training-data bias, and a hallucination loop in which generated content is recycled into the corpora that train the next model.

Sustainability enters twice, as funding and as energy. The digital public goods argument is essentially a sustainability argument: a fragmented commons of grant-funded files does not outlive its grants, whereas publicly governed infrastructure might. The environmental case appears in the wider openness literature and in this knowledge base's Sustainability concept, where the reporting of model inference cost is treated as an obligation of open practice rather than an afterthought.

The Global South dimension is where the evidence thins most. The batch's non-Western cases are real but few: a Latin American cooperation residency, Chinese open-university teachers, and a framing of infrastructure as the precondition for participation. Claims that openness automatically redistributes capacity are not supported by these studies, and several of them say so.

Where writing and recommendation systems meet the argument

Two papers in this batch are about production systems rather than policy. Peng (2026) develops a hybrid deep recommender for OER and reports 93.6 percent accuracy, 92.5 percent precision, 91.0 percent recall and a 90.2 F1 score on 2,400 interaction records. Its own comparison table shows a BERT4Rec baseline at 90.8 F1 with equal recall, and the dataset section leaves user count, item count and sparsity as placeholders. The modeling claim is modest; the pattern is familiar, in that an advance over a strong baseline is smaller than the headline.

The second is a reminder that a generative system can be open and its content closed. OATutor pairs an MIT codebase with CC BY OpenStax algebra texts, which means the licenses of code and content have to be kept compatible by design. That single technical obligation is the clearest practical form of the open source and open education relationship: different objects, same legal machinery, and a compatibility constraint that falls on whoever assembles both.

Common Misconceptions

"Open education and open source are the same openness." They share licensing machinery and a production model and they are not interchangeable. Open source is a claim about a buildable, inspectable system; open education is a claim about a usable, adaptable teaching resource. A school can run entirely open-source software over a closed textbook, and many do.

"Open means free to the student, which is the whole benefit." Cost is the measurable half. The other half is permission: a resource that may be revised is one a second institution can fix, translate and localize. Studies in this batch report completion and satisfaction far more often than adaptation, which is why the adaptation claim remains largely untested.

"AI makes content so cheap that OER is obsolete." The opposite reading is available and better supported. If generation is nearly free, the scarce goods become the license, the attribution trail, the review process and the maintained platform. That is why this literature converges on governance and infrastructure rather than on production.

"Adding AI tools to an open assignment improves the learning." The one quasi-experimental test here found perceived skill growth in both arms with no detectable difference between them, alongside higher completion and marginally lower scores in the AI section. AI changed what students produced and did not change what they reported learning.

Connected Concepts

- Open Source
- Legal Issues and Risks

- AI Regulation in Education
- Generative AI
- Educational AI Policy
- AI Governance
- Equity
- Curriculum Design
- Active Learning
- Collaborative Learning
- Authentic Assessment
- Sustainability
- Global South
- AI Literacy
- Digital Divide
- Accessibility
- Change Management

Connected Articles

- The double-edged sword: Open educational resources in the era of Generative Artificial Intelligence — Five framings for OER once generative AI enters production (Tlili et al., 2026)
- Building sustainable futures: Responsible development of AI-enabled open educational resources as digital public goods — OER as digital public goods and the argument for governed infrastructure (Atenas et al., 2026)
- From niche to regime: Rethinking openness in the age of artificial intelligence — Why twenty-five years of openness left the institutional middle intact (Deimann and Lukács, 2026)
- Information literacy through open pedagogy: What's the role of AI tools? — Open pedagogy with and without AI tools in two course sections (Clinton-Lisell, 2026)
- The evolution of open educational practices: a comparative analysis of models and a new framework for the AI era — Fourteen models of open educational practice and where AI sits in them (Duan, 2026)
- The association between teachers' artificial intelligence literacy and open education teaching practices in China: a moderated mediation analysis of teachers' innovative behavior and school support — Teacher AI literacy and open teaching practice across 30 Chinese provinces (Guo et al., 2026)
- Open educational resources and generative AI: towards a framework for responsible integration — A seven-pillar framework for responsible OER and AI integration (Rodés-Paragarino and Atenas, 2026)
- Active learning, mentoring and AI-open educational resources: a case study in a virtual laboratory — Mentoring and AI-OER production in a virtual laboratory (González Miy, 2026)
- Developing AI literacy OER: A literature-informed rubric for design and review — A seven-principle rubric for reviewing AI literacy OER (Ryu, 2026)

- Advancing open learning through interactive open educational resources — Interactivity in OER as a design argument rather than a finding (Ahmadfard, 2026)
- AI-Driven Model for Fostering International Cooperation in Open Education: A Roadmap for Innovation and Equity — International cooperation in open education as an instrumental case (Patiño et al., 2026)
- Research on personalized recommendation algorithm for open educational resources driven by artificial intelligence — A hybrid recommender for OER against a stronger baseline than claimed (Peng, 2026)
- Editorial: Digital transformation in open and flexible education: How pedagogy is changing in response to new possibilities — Digital transformation in open learning as pedagogic transformation (Panda, 2026)

Open Source

> **Open Source** — the use of openly licensed *models, code, data, and content* in AI in education. Openness is the knowledge base's main counterweight to vendor lock-in and data exposure: open-weight models can run on campus hardware to satisfy FERPA, GDPR, and EU AI Act obligations, openly licensed corpora can be indexed and fine-tuned without publisher permission, and open benchmark and dataset releases make research replicable. The burdens are equally real: infrastructure and safety assurance, maintenance that outlives the grant, and quality that openness does not by itself guarantee.

Questions to Consider

- "Open source" is often heard as "free and easy." Which of the four layers below — models, code, data, or content — actually costs your institution the most to adopt, and why?
- Open weights make local deployment possible, but someone still has to host, patch, and evaluate the system. Who should own that work after the initial project ends, and who pays for it?
- One study here found a 32B open model outscoring a far larger proprietary system on pedagogical knowledge, while another found every open model tested below the human baseline on scientific-visualization literacy. How do you decide which benchmark is the right one for your decision?
- A single openly licensed corpus is what lets a school run an on-premise assistant over its own course materials. What obligations come with that — to the original authors, to students whose data is indexed, and to the license itself?
- If generative AI can produce a course in under half an hour for a couple of dollars, what is the remaining rationale for open educational resources — cost, licensing freedom, quality assurance, or something else?
- Should institutions treat open-source adoption as a procurement decision, an infrastructure decision, or a pedagogical one? What breaks if it is treated as only one of them?

Introduction

Loosely, "open" in AI education means that four kinds of artifact are available for inspection, reuse, and modification: **model weights**, **source code**, **data and evaluation instruments**, and **educational content**. The knowledge base's articles cluster unevenly across these layers, and the resulting picture is more useful than the slogan: openness buys specific things — local control, auditability, replicability, and legal clarity — and it costs specific things — infrastructure, expertise, maintenance, and a quality-assurance burden that moves from the vendor to the institution.

Open models and open weights

Open weights matter most where student data cannot leave campus. LaTA is a drop-in, FERPA-compliant local-Large Language Models (LLMs) autograder for upper-division STEM coursework built on instructor-

authored rubrics and reference solutions, with zero marginal cost per submission. SCRIPT, a Python tutoring system at Bielefeld University, deliberately **avoids commercial LLM APIs** and self-hosts an open-weight Llama-70B model to meet the GDPR and the EU AI Act (which classifies some AI-in-education uses as high risk), separating IP logs from the tutoring system, using pseudonymous usernames, and recording keystrokes only with explicit consent — a choice the authors also credit with lower environmental impact and better reproducibility.

Quality is no longer the automatic price of openness. EduQwen applies reinforcement learning (DAPO) and supervised fine-tuning to an open model family, mining 440 hard negatives, generating 40,000 synthetic responses down-selected to 1,050 difficulty-ordered examples, and reaching **96.52%** on the pedagogy benchmark — above Gemini-3 Pro's 90.55% — at 32B dense parameters. AiAWE reaches similar conclusions for automated writing evaluation: a LoRA-adapted open-weight Gemma-3-27B-it outperforms LLaMA-3.3-70B and a fine-tuned GPT-3.5 baseline on 480 TOEFL essays and runs on a consumer-grade server, with the striking subsidiary finding that parameter count is *not* a reliable predictor of downstream performance under LoRA adaptation. The counter-evidence deserves equal billing: a benchmark of six MLLMs (three closed, three open) found every open-source model below the human baseline on scientific Visualization literacy while Gemini exceeded the human mean on several subsets. Openness raises the ceiling on control, not on capability.

OmniEdu releases the whole pipeline rather than just weights: capability-balanced supervision over a 69,999-example mixture lifted every scale of an open 4B/9B/27B K–12 family — the tuned 4B model gained 55 points of MathTutorBench scaffold win rate over its base — while knowledge-state diagnosis stayed its weakest capability at 54.04% (Liang et al., 2026).

Open tools, tutors, and research infrastructure

The clearest case for open code is replication. OATutor — the first fully open adaptive tutoring system built on ITS principles — pairs an **MIT-licensed codebase** with a **Creative Commons (CC BY) content library** from OpenStax algebra textbooks, plus knowledge tracing, A/B testing, and LTI support; its explicit design goal is that a researcher can run an experiment and then publish the entire end-to-end framework, content, and platform as a repository link. StanBKT makes the same argument at the method layer, replacing expectation-maximization point estimates with full Bayesian inference (HMC, variational inference, Pathfinder, optimization) in an open Python package that exposes the uncertainty A/B comparisons of adaptive interventions depend on. Deeptutor releases a complete agentic tutoring framework with a trace-forest learner memory — Apache 2.0, and by late 2026 a full learning workspace rather than only the pipelines its paper benchmarks — and MAIC's classroom generator OpenMAIC ships under MIT alongside the study that evaluates it, so a course can be generated, self-hosted and inspected rather than only read about; VISMATIC publishes its containerized sandbox for process-oriented monitoring, so other institutions can adopt the integrity model rather than the vendor's version of it. Open code also carries the transparency burden: the scripts for MathBuddy's affect-aware tutoring prompts are published for inspection and further pedagogical training work. Open infrastructure sets the reference point for what educational agents should do: the knowledge base's scoping review of 474 agentic-AI studies uses a fast-growing open-source agent project as its "frontier agent paradigm" benchmark and finds educational systems still lacking governed tool orchestration, persistent memory, long-horizon planning, and auditable action.

Open benchmarks, datasets, and method transparency

Several contributions here are open *evaluation infrastructure* rather than systems. The Pedagogy Benchmark (CDPK + SEND, built from genuine Chilean teacher-exam items) spans 97 models: open-weight DeepSeek R1 reached 86.65% against a top-10 of mostly closed reasoning models, and the cost–accuracy frontier moved from ~50% to ~82% at $0.10/M input tokens between April 2024 and June 2025. Open Qwen-3 8B at 3.5¢ nearly matched the best April-2024 closed model at over 400× lower cost. Performance drops sharply below roughly 8B parameters, which is a practical sizing constraint for campus deployments. ASTRA releases a dataset, schema, and prototype for trace-based evaluation of socially intelligent multi-agent tutoring (540 participants, 360 sessions, 1,440 task episodes). IKS-Instruct shows the cultural case for open data: 24,795 instruction–response pairs across seven languages and 41 pedagogical techniques drawn from Vedic and classical sources, aligned to the CBSE curriculum, which let a compact 7B model approach a much larger general-purpose reference model (median judge score 6.39 vs 6.54) at a fraction of the deployment cost. Student-authored benchmarks are another route to openness: AcademiClaw curates 80 long-horizon academic tasks from 230 student-submitted candidates (spanning 25+ professional domains, 16 requiring CUDA GPUs, run in isolated Docker sandboxes) and extends an open agent ecosystem into academic-level evaluation. Eimler et al. (2026) argue that openness is an environmental obligation as well: reviewing all AIED 2025 papers, they found an “LLM adoption without disclosure” pattern and responded with an open-source measurement methodology — software tools plus a formula that estimates computational expense even when parameter counts are unknown.

Where open content meets open code

Open educational resources have their own page, Open Education, because the argument there is pedagogical and licensing-led rather than infrastructural. What belongs on this page is the seam where the two openesses meet, and it is narrower than it looks.

The seam is a license-compatibility constraint. OATutor pairs an MIT-licensed codebase with a CC BY content library of OpenStax algebra textbooks, which means the terms of the code and the terms of the content have to be kept compatible by design, and a permissive license on one does not supply the other. The seam also appears when an openly licensed corpus is what makes an on-premise system lawful to run: Shen et al. (2026) index 82 OER documents into a knowledge-base assistant on a 12 GB consumer GPU, and the whole story is an open-source story about quantization, hallucination and provenance rather than an argument about textbooks.

What this page does not do is argue for the resource. Whether a machine-written textbook is open by default, whether a license survives a generated remix, and whether open pedagogy teaches anything measurable are questions for Open Education, and they are the questions the field’s current literature is actually about.

Benefits and burdens

- **Benefits.** Data sovereignty and regulatory compliance (Privacy, AI Regulation in Education) through local hosting; cost control, since local inference has no per-query fee and open models approach proprietary quality at a fraction of the price (Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised

Fine-Tuning); reproducibility, because the framework, prompts, content, and data can ship with the paper (OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research, ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming); auditability and safety review under institutional governance; and the ability to fine-tune for a specific Pedagogies and Teaching Strategies or a specific community's knowledge base (IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems).

- **Burdens.** Local hosting requires hardware and expertise many institutions do not have; quality and safety are not guaranteed out of the box — open models may trail human baselines on specific literacies (Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy) and quantization raises hallucination rates unless mitigated (Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources); someone must maintain the system after publication (Programming Intelligent Tutoring Systems documents a small PhD-student team, work-in-progress security exposure, and a substantial compliance burden); and an open license is a permission, not a working product — the maintenance that keeps a released system usable falls to whichever Educational Technology Developers built it, and their funding and incentives decide whether a forkable repository, a maintained product, or neither is what an institution inherits when the grant ends.

Putting openness into practice

- **For instructors and institutions:** check the license of the *content* as well as the code before adopting a system — MIT code over CC BY textbooks is reusable, but a permissive license does not guarantee that tutoring pathways, item banks, or translations exist. Prefer open models when student data legally cannot leave campus (LaTA: A drop-in, FERPA-compliant local-LLM autograder for upper-division STEM coursework, Programming Intelligent Tutoring Systems), but benchmark the model on *your* task rather than trusting general leaderboards (Benchmarking the pedagogical knowledge of large language models). Budget for someone to run and evaluate the system after the pilot.
- **For developers and researchers:** ship the whole thing — OATutor's end-to-end release (code, content, experiment harness) is the replicability standard this literature keeps rewarding. Release prompts and extraction schemas alongside weights (Programming Intelligent Tutoring Systems, MathBuddy: Affective Math Tutoring). Report compute and carbon (The Environmental Cost of LLMs in AIED: Reporting and Practices). Ground assistants in openly licensed corpora so provenance is checkable and adaptation is lawful (Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources). Use quantization-aware fine-tuning rather than plain quantization if accuracy and energy both matter, and keep code and content licenses compatible.

Common Misconceptions

“Open weights, open source, open content and open pedagogy are the same openness.” They are four different things and they fail independently. The resource and practice arguments live on Open Education; this page covers the artifacts a builder ships and licenses. Open *weights* permit local deployment; open *source* permits modification; open *content* permits reuse and adaptation; open *pedagogy* concerns who decides what is taught. A model with open weights and a proprietary training pipeline, wrapped in a tool with a closed interface and an all-rights-reserved content library, is “open” in one of the four senses and closed in three.

The word itself is contested upstream. Deimann and Lukács (2026) observe that the openness debate reached AI through the open-source community, with the first Open Source AI Definition published in 2024, and they argue that openness functions there as an imaginary rather than a property: an aspiration that institutions adopt in language while the surrounding regime stays intact. That is a useful check on this page, because a license is a property and a movement is not.

“Open means cheaper.” Open weights make local deployment possible, but **someone still has to host, patch and evaluate the system** — and that someone needs to outlive the grant that funded the work. The burdens named in this literature are concrete: infrastructure, safety assurance, and maintenance. Total cost can exceed a license fee, and institutions that treat openness as a saving frequently discover the maintenance obligation after the project staff have dispersed.

“Closed frontier models are simply better, so open alternatives are a fallback.” The gap is narrower than that assumption implies. In the Pedagogy Benchmark (CDPK + SEND, built from genuine Chilean teacher-exam items) spanning 97 models, open-weight **DeepSeek R1 reached 86.65%**, against a top-10 made up mostly of closed reasoning models — and the cost–accuracy comparison runs further in the open direction. The remaining argument for openness is therefore about control and auditability, not about a capability sacrifice.

“Releasing the weights is releasing the work.” The stronger open contributions release the pipeline. OmniEdu publishes capability-balanced supervision over a 69,999-example mixture rather than final weights alone, lifting every scale of an open 4B/9B/27B K–12 family, with the tuned 4B model gaining **55 points** of MathTutorBench Scaffolding performance; EduQwen likewise documents its RL and fine-tuning procedure, including 440 mined hard negatives and 40,000 generated responses. Weights without the recipe reproduce an outcome without reproducing the method.

Connected Concepts

- Open Education
- Intelligent Tutoring
- LLM Training and Fine-Tuning
- Adaptive Learning
- Edtech Platform
- Privacy
- AI Regulation in Education

- AI Governance
- Agentic AI
- Automated Assessment
- Benchmark
- Knowledge Tracing
- RAG (Retrieval-Augmented Generation)
- Pedagogical Safety
- Sustainability
- Research Methods in AIED
- Writing
- Academic Integrity
- Educational Technology Developers

Connected Articles

- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — On-premise OER AI knowledge-base assistant on consumer hardware (Shen et al. 2026)
- OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research — MIT-licensed adaptive tutor with a CC BY OpenStax content library (Pardos et al. 2023)
- Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning — Open 32B pedagogical model outperforming far larger proprietary systems (Singh et al. 2026)
- LaTA: A drop-in, FERPA-compliant local-LLM autograder for upper-division STEM coursework — Drop-in FERPA-compliant local-LLM autograder
- Programming Intelligent Tutoring Systems — Self-hosted open-weight LLM for GDPR/EU AI Act compliance in a Python ITS
- AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models — LoRA-adapted open-weight model for automated writing evaluation
- StanBKT: Rethinking Parameter Estimation in Bayesian Knowledge Tracing — Open Python package for full Bayesian knowledge tracing
- DeepTutor: Towards Agentic Personalized Tutoring — Fully open-source agentic tutoring framework with learner memory
- Securing the Sandbox: A Rootless Containerized Framework for Process-Oriented Monitoring in Computer Graphics Education — Open containerized sandbox for process-oriented assessment
- MathBuddy: Affective Math Tutoring — Affective math tutor with an open codebase
- Benchmarking the pedagogical knowledge of large language models — Open pedagogy benchmark across 97 models and the cost–accuracy frontier

- ASTRA: A synthetic benchmark for trace-based evaluation of socially intelligent multi-agent tutoring and participation-balanced collaboration in introductory programming — Open dataset and prototype for trace-based multi-agent tutoring evaluation
- Benchmarking Multimodal Large Language Models for Scientific Visualization Literacy — Open models below the human baseline on visualization literacy
- IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems — Open multilingual dataset for culturally grounded instruction
- The Environmental Cost of LLMs in AIED: Reporting and Practices — Open-source method for reporting LLM environmental cost
- Bridging Artificial Intelligence and Power Systems Education Using a Hands-On Executable Framework — Open executable module library for engineering AI
- From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents — LLM-driven course generation and the changing economics of course production
- A scoping review of generative AI-powered agentic AI in education: Research landscape, agentic capabilities, and insights from the frontier agent paradigm, exemplified by OpenClaw
- AcademiClaw: When Students Set Challenges for AI Agents
- OmniEdu: Open Foundation Models for Learning and Teaching — OmniEdu: Open Foundation Models for Learning and Teaching

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?

Edtech Platform

> **Edtech Platform** — the digital systems, learning management systems (LMS), tutoring systems, and online learning environments through which AI is delivered to learners and educators. In AI in education, the platform is the *infrastructure layer* that determines whether an AI capability reaches students, how it is deployed (open vs. proprietary, integrated vs. standalone), and who can access, adapt, and evaluate it. Research in this knowledge base examines platforms from multiple angles: their design, their take-up and engagement constraints, their institutional governance, and their equity implications.(Access is Not Enough: Human Support Improves Engagement with AI Tutoring) (OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research)

Questions to Consider

- Think of the last AI tutoring or feedback tool you encountered. Now think about where it actually 'lived' — the LMS, platform, or app that packaged it. Does that container feel like a neutral delivery vehicle, or could its design choices (open vs. proprietary, integrated vs. standalone, cloud vs. local) have changed what you could do with it?
- One study found that nearly half of students never used a well-designed AI tutoring platform, and heavy users skewed toward higher-achieving students. If a tool is effective 'in principle' but students don't use it, is the capability or the platform the real problem? What would that mean for how you evaluate edtech?
- Proprietary AI platforms can confine researchers to a handful of closed systems, while open platforms like OATutor let anyone fork, experiment, and publish. What might be lost — for research, equity, and institutional autonomy — when AI education is delivered through closed, opaque platforms?
- How much does a platform's business model — who pays, who owns the data, what gets optimized — shape the learning that actually happens on it? Where would you look to see that influence?
- Some new 'AI-native' platforms replace the one-video-for-many-students MOOC model with a multi-agent classroom built around each learner. Before reading on, what would you worry about losing when instruction becomes one-to-one with agents instead of one-to-many with instructors?

Introduction

The platform sits between an AI model or capability and the learner. It is the container that packages tutoring, assessment, feedback, and administration into something usable — and, critically, it shapes learning outcomes through its design choices, its accessibility, and its underlying business model. The concept spans learning management systems like Moodle, large-scale online platforms like MOOCs, dedicated intelligent tutoring systems, and emerging agentic or AI-native course platforms. Naming the container is not the same as naming its authors: the platform is the deployed system, while the stakeholder that decides what it does is

Educational Technology Developers — which matters here because the take-up, equity-skew and procurement findings below are usually consequences of design choices made before a platform ever reached a classroom.

What a platform does in AI in education

Platforms in AI in education perform several distinct functions:

- **Deliver instruction and tutoring** — the container for AI Tutoring and Intelligent Tutoring systems, from LMS-embedded tutors to standalone adaptive tutoring platforms.
- **Manage the learning environment** — course organization, enrollment, progress tracking, and administration that traditional LMS platforms provide.
- **Host assessment and feedback** — where Automated Assessment, Formative Assessment, and feedback loops run.
- **Collect and analyze learning data** — the substrate for Learning Analytics and Learner Modeling and Adaptive Instruction.
- **Govern access and deployment** — decisions about Open Source vs. proprietary, local vs. cloud, and which institutions and learners can use it.

Key findings from the knowledge base's articles

Take-up, not capability, is often the binding constraint

A platform can be effective in principle yet fail in practice if learners do not use it. Two RCTs of an AI literacy (reading) tutoring platform found that **nearly half of control students never used the platform** and users averaged only 2–5 minutes per week — far below the dosage needed for reading gains. An in-person engagement tutor raised usage and engagement substantially but still did not produce achievement gains, and platform users skewed toward higher-achieving students, raising equity concerns.(Access is Not Enough: Human Support Improves Engagement with AI Tutoring)

Sequencing matters as much as capability: a review of 100+ AI-in-education studies (2020–2025) places end-to-end platforms at the top of an adoption stack, arguing institutions should settle formative assessment, leadership capacity, and shared norms before buying the platforms that scale them (Raza & Farooq (2025)).

The gap is message-level, not logins: in a two-year cluster RCT, 96% of students tried Khanmigo but the median student messaged it in only 17% of sessions where they made a mistake, and ~14.5% of messages carried a genuine mathematical question or reasoning step — at $15 per student per year (Oreopoulos and Low, 2026).

The binding constraint is where the AI sits inside the platform: in a 6,000-student middle-school trial, the measured effect came from structured touchpoints inside the practice environment — 2.0 "help me get started" uses, 2.3 post-mistake walkthroughs and 3.2 step explanations per mastery student — while AI access alone added little (Oreopoulos et al. (2026)).

Which tools educators report using, and what gates access

A rare census of educator-reported platform choice comes from a 2026 typology built from 211 educators across nine countries. The tools that reach classrooms are disproportionately the ones with a free tier, because a publicly available free version was an inclusion criterion, and the most-nominated entries are general-purpose assistants and media generators rather than purpose-built platforms. Roughly half of the fifty tools listed produce images, audio, video or slide decks, while document-grounded assistants (NotebookLM, Elicit, SciSpace, Humata, Research Rabbit) form the most coherent cluster in the research category. Dedicated tutoring systems appear as a small, subject-specific group rather than the center of reported use — which frames the take-up problem above in a wider setting, where a platform competes for attention against general-purpose tools that students and instructors already have open.(Typology of Generative AI Tools for Education)

The platform model matters: open vs. proprietary

- **Proprietary platforms** create barriers to research: researchers who want to replicate or extend Adaptive Learning experiments are often confined to a small number of closed platforms.
- **Open platforms** lower this barrier. **OATutor** is the first open-source adaptive tutoring system built on ITS principles — an MIT-licensed codebase with a Creative Commons algebra content library, Knowledge Tracing mastery estimation, and built-in A/B testing — letting researchers fork, experiment, and publish the full end-to-end system.(OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research)
- **Transparency is front-loaded.** In the same audit of 48 platform policies, data collection and third-party sharing were disclosed comparatively well while AI-specific disclosure and accountability lagged, and 16 of 48 platforms (33%) made no meaningful AI disclosure despite visible AI features (Nair & Greenstadt, 2026).
- **The LMS API bounds what a game-integrated platform can assess.** A hypergamification pilot that generated a playable world from Blackboard content could not render multiple-choice or open-ended questions, because student-scoped tokens returned no question content and no endpoint existed for posting runtime answers (Yusubov et al., 2026).
- **Isolation and cost are platform design variables.** VISMATIC pairs rootless containers — which, unlike JupyterHub, prevent lateral movement and host compromise — with API-level process telemetry, running 19 students and 1,880 logged events on a single Raspberry Pi 5 node rated for 10 to 20 (Arroyo et al. (2026)).

AI-native platforms are reshaping online education

The platform paradigm itself is evolving. **MAIC** (Massive AI-empowered Course) replaces the MOOC's "one video for N students" model with an Large Language Models (LLMs)-driven multi-agent classroom — "N agents for 1 student" — using specialized Teacher, Assistant, Classmate, and Analyzer agents to deliver personalized, adaptive learning at scale. It reduces course production from ~$25K/60 hours to under $2/30 minutes.(From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents) Similarly, AI-integrated LMS designs propose moving beyond workflow-only platforms toward real-time

instructional support with policy-gated (bounded) AI, formative hinting, spaced review, and teacher dashboards.(AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond) At the other end of the deployment spectrum, classroom-embedded AI must prove feasible in live physical environments. The Community Builder (CoBi) — a classroom-wide platform that uses speech recognition and language understanding to visualize small-group collaborative discourse — was successfully deployed across noisy middle-school classrooms using commodity microphones and a scalable cloud pipeline, showing that real-time speech-AI infrastructure can function in authentic K-12 settings even as interface mismatches (teacher vs. student views of whether feedback was group- or class-level) created deployment friction.

Interest-based and context-aware platform features

Platforms can personalize beyond performance data. **Taklif.AI** is an LLM-powered platform that generates college assignments based on students' **extracurricular interests and cultural contexts**, aligning with Culturally Relevant Pedagogy and shifting from one-size-fits-all assignments toward interest-driven engagement.(Taklif.AI: LLM-powered platform for interest-based personalized college assignments)

Purpose-built layers over general models

The platform's contribution is often the structure a general model lacks. LearnMate^2 wraps an LLM in study planning, in-context help and performance-responsive activities, and in a 16-participant comparison it beat Khan Academy paired with Gemini 2.5 Pro on both quizzes (M = 13.375 vs 10.875, p = .0126; 7.875 vs 5.875, p = .0012). EduSim-LLM translates natural-language instructions into CoppeliaSim robot behavior for beginners, succeeding on 100% of simple tasks but 88.9% of complex ones across 108 cases.

Implications for design and research

1. **Design for take-up, not just capability.** A platform's effectiveness depends on whether learners actually engage with it; support structures, onboarding, and scheduling matter as much as the AI itself.(Access is Not Enough: Human Support Improves Engagement with AI Tutoring)
2. **Treat platform structure as an equity lever.** Who benefits from a platform depends on access, infrastructure, and engagement constraints — platform design must be examined through an Equity lens.(Access is Not Enough: Human Support Improves Engagement with AI Tutoring)
3. **Prefer open, replicable platforms for research.** Open-source platforms like OATutor enable reproducible adaptive-learning research and a shared evidence base.(OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research)
4. **Design AI-native platforms with governance and bounds.** Privacy-first architecture, data minimization, auditable logs, and role-based access are critical as platforms become AI-integrated — connecting to Privacy and AI Governance concerns.(AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond) Privacy can be built into the pipeline rather than the policy: a classroom incident detector trained on anonymized pose trajectories keeps facial and appearance cues for minors out of the system, though every method lost accuracy in zero-shot transfer to real classrooms, where the proposed model's best accuracy was 63.41% (Parmar et al. (2026)).

5. **Explain recommendations in the teacher's domain language.** A platform's AI features earn trust and uptake when their explanations are understandable and pedagogically meaningful: in a within-subject experiment with an AI grouping-recommendation tool (GrouPer), Feldman-Maggor et al. (2025) found domain-driven explanations framed in curricular language increased teachers' understandability, trust, and acceptance significantly more than raw feature-importance explanations — and that real classroom use still mattered for full acceptance.(The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations)
6. **Separate the system that produces evidence from the one that grades it.** When agents can complete a course on a learner's behalf, Srivastava (2026) argues a platform must emit contemporaneous, inspectable evidence of the learner's reasoning and must not be its sole grader — the environment, issuer and verifier should be independent.(Credentials That Carry Their Evidence: Credential design, dynamic tiering, and approved use when AI agents can do the work)
7. **Generate representations at design time, not at runtime.** Neshaei et al. (2026) argue runtime adaptation cannot be verified at scale and propose encoding content as modality-agnostic semantic cards, from which interactive, audio, simplified-text and low-bandwidth variants are generated and instructor-approved before release — eliminating per-learner inference cost, though no prototype is reported.

Common Misconceptions

"If a platform is effective in principle, students will use it." Capability and take-up are separate problems, and take-up is often the binding one. In a two-year cluster RCT, **96% of students tried Khanmigo** — near-universal adoption — yet the median student messaged it in only **17% of sessions where they made a mistake**, the exact moment the tool was built for. A platform that logs the class has not changed it.

"Adoption is measured by logins." The informative gap is at message level, not account level. In that same trial only **~14.5% of messages carried a genuine mathematical question**. Ninety-six percent of students created the access event; roughly one in seven of their interactions did the intellectual work. Reporting a logins figure here would have described a success that did not exist.

"Open versus proprietary is a licensing detail that does not affect outcomes." The platform model shapes what institutions can do with the system: open platforms such as OATutor — an MIT-licensed adaptive tutor with a Creative Commons algebra content library, Knowledge Tracing mastery estimation and built-in A/B testing — let a department instrument and modify its own Pedagogies and Teaching Strategies, which a closed platform cannot. The license determines who may conduct the experiment.

"A platform that works at one institution will work as adopted." Platform effects run through local governance: privacy-first architecture, data minimisation, auditable logs and role-based access are what make an AI-integrated platform deployable at all, and they are institutional decisions rather than features you can infer from a vendor demonstration.

Connected Concepts

- Personalized Learning

- Adaptive Learning
- Intelligent Tutoring
- Learning Analytics
- Learner Modeling and Adaptive Instruction
- Knowledge Tracing
- Automated Assessment
- Formative Assessment
- Generative AI
- Large Language Models (LLMs)
- Open Source
- AI Literacy
- Student Experience
- Teaching
- K-12
- Higher Education
- Equity
- Privacy
- AI Governance
- Culturally Relevant Pedagogy
- STEM Education
- Educational Technology Developers

Connected Articles

- Typology of Generative AI Tools for Education — What 211 educators reported using: 50 tools in nine categories
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- One click away: AI tutoring with Khanmigo in a two-year school experiment — One Click Away: Khanmigo in a two-year school experiment
- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — Take-up and engagement are the binding constraints for AI tutoring platforms
- OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research — An open-source adaptive tutoring platform for replicable research
- From MOOC to MAIC: Reshaping Online Teaching and Learning through LLM-driven Agents — Moving from MOOC to LLM-driven multi-agent AI classrooms
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond — AI-integrated LMS for middle school with bounded, privacy-first support

- Taklif.AI: LLM-powered platform for interest-based personalized college assignments — Interest-based personalized assignment platform
- EduSim-LLM: An educational platform integrating large language models and robotic simulation for beginners — An LLM-robotic simulation platform for education
- Teachy Mini: Development and preliminary evaluation of a knowledge-based generative social robot for higher education — A generative social-robot teaching platform in higher education
- Hypergamigication through integrating game engines and learning management systems: Ender's Game — A game-engine-based LMS integrating gamification
- The Missing Layer: Why EdTech Needs Design-Time Generative UI, Not Just Runtime Personalization — Designing edtech for generative UI
- LaTA: A drop-in, FERPA-compliant local-LLM autograder for upper-division STEM coursework — FERPA-compliant local LLM autograder platform
- Securing the Sandbox: A Rootless Containerized Framework for Process-Oriented Monitoring in Computer Graphics Education — A secure sandbox platform for CS education
- LearnMate^2: Design and evaluation of an LLM-powered personalized and adaptive support system for online learning — LLM-powered personalized adaptive learning platform
- Robust and Efficient Motion Reasoning for Privacy-Aware Classroom Incident Recognition — Privacy-aware computer vision in classroom platforms
- Review of Artificial Intelligence in Education from 2020 to 2025 — Comprehensive review of AIED research and systems
- Credentials That Carry Their Evidence: Credential design, dynamic tiering, and approved use when AI agents can do the work — Credentials that carry their evidence for AI-agent work
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data

Connected FAQs

- What Are Best Practices and Tips for Designing Effective Educational AI Software?

AI in the disciplines

Subject areas

AIEd in the Disciplines

> **AIEd in the Disciplines** — the application of artificial intelligence to teaching and learning within specific academic subjects, where each discipline's signature pedagogies, methods, theories, and concerns shape how AI is designed, used, and evaluated. Rather than treating AI in education as a single generic phenomenon, this overview organizes the knowledge base's discipline-specific coverage and surfaces the cross-cutting themes that run through subject-area AIEd research.

Questions to Consider

- A math tutor that excels at right/wrong feedback may fail in the humanities, where interpretation and authorship matter more than correctness. How does your own discipline define what counts as 'good feedback'?
- Research across 560 students found that disciplinary affiliation predicts how often and openly students use generative AI. Why might a discipline act as a whole 'activity system' shaping AI use — rather than AI being a neutral tool everywhere?
- The 'cognitive act' being offloaded to AI is discipline-specific: computation in math, code in CS, composition in writing. If over-reliance looks different in each field, how would you detect it in yours?
- What does AI mean for a discipline whose signature pedagogy is hands-on laboratory work, or interpretive meaning-making, rather than Problem Solving? Is there any subject where AI should play little role?
- Several disciplines — law, history, the arts — remain thin in AI-education research. Which discipline's AI use most deserves attention, and what would good AI in that field have to honor that generic tools don't?

Introduction

AI in education manifests differently across disciplines because each field has its own signature pedagogy — the distinctive ways knowledge is constructed, practiced, and taught. AI tutors that shine in mathematics may fail in the humanities, where interpretation and authorship matter more than right answers. This page is the umbrella map for those discipline-specific strands, which now run from school subjects through professional and applied training to studio practice. One member of the strand is not a taught subject at all: Learning Sciences is the research field around AI in education, supplying the mechanisms AI systems operationalize and the standards by which they are judged — it takes the cross-cutting view, against this page's premise that subject matter is what changes what support should do.

Discipline-specific concepts

The knowledge base has dedicated concept pages for several subject areas:

- **Math Education** — AI tutoring, adaptive problem-solving, and conceptual diagnosis in mathematics.
- **Physics Education** — AI simulation, chatbots, and problem-posing in physics learning.
- **Chemistry Education** — AI in laboratory/experimental design, AI-mediated formative assessment, context-based and inquiry-based instruction, Large Language Models (LLMs) technical limits on chemistry tasks, and the philosophy of experimentation.
- **Biology Education** — AI in laboratory instruction, AI literacy embedded in biology curricula, critical thinking in the AI era, and specialized tools (species identification, bioimaging, predictive modeling).
- **CS Education** — AI for code generation, debugging, and novice programming support.
- **Information Technology Education** — the applied wing of computing, preparing practitioners to select, secure, administer, and govern the deployed systems organizations run: its unit of analysis is the deployed system and the practitioner's judgment about it, where computer science education takes the program and the algorithm as its objects.
- **Writing** — AI-assisted composition, automated essay scoring, and writing feedback.
- **Language Learning** — AI interlocutors, pronunciation feedback, and conversational practice in second/foreign languages.
- **English Education (EAP / EFL / ESL)** — English for Academic Purposes (EAP) and English language teaching (EFL/ESL/L2): academic-English register, genre-based writing, and English-specific feedback and assessment — distinct from general language learning and general writing.
- **STEM Education** — the cross-disciplinary umbrella for science, technology, engineering, and mathematics.
- **Teacher Education** — the preparation and professional development of teachers (pre-service and in-service), a discipline in its own right whose AI research centers on teacher AI literacy, intelligent-Technological Pedagogical Content Knowledge (TPACK), and readiness to integrate AI.
- **Medical and Health Professions Education** — clinical simulation, Reinforcement Learning training, and foundational learning principles in health-professions education.
- **Nursing Education** — the densest empirical record in the clinical strand: simulation with virtual patients, LLM reasoning support, and adaptive platforms, framed around professional-identity formation as much as competence, and narrow enough to name the boundary where AI's documented benefits stop (complex psychomotor skill and emotionally loaded interaction) rather than treating health professions as one case.
- **Vocational Education and Training** — initial preparation for named trades and technical occupations, organized by qualification frameworks and assessed on what learners can do with equipment. It extends beyond the professional training and workplace upskilling that Workplace Learning covers to those not yet employed, and its recurring design question is which expensive-to-staff parts of practice AI can absorb without displacing the repetition that produces competence.

- **Design Education** — studio-based professional formation in product, service, interaction, interior and architectural design, where visible process is the assessed object and where generative tools make the polished artifact cheap: it narrows the studio disciplines that Arts, Design and Media Education covers to the professional design pipeline, so that critique, portfolio and regulation rather than material and performative practice carry the argument.
- **Engineering Education** — professional formation, design and hands-on learning, ethical use of AI, embodied assessment, and workforce preparation in engineering.
- **Business Education** — AI in business, economics, and management education: student-informed GenAI frameworks, curriculum integration via constructive alignment, and preparation for AI-integrated professional practice.
- **Humanities and Social Science Education** — interpretive cognition, authorship, and meaning-making in humanities and social sciences.
- **K-12** and **Higher Education** — education about and with AI at each level.

Cross-disciplinary themes

Several threads cut across all disciplines, though they play out differently in each:

- **Discipline as an activity system.** Jiang et al. (2026) show, across 560 undergraduates in five academic domains, that disciplinary affiliation is significantly associated with students' GenAI **usage frequency and disclosure practices** — disciplines function as activity systems whose norms, policies, and role expectations shape how students engage with and disclose GenAI. This is direct evidence for the knowledge base's premise that AI in education is not discipline-neutral.
- **The shape of "interdisciplinary" itself is discipline-determined.** Xia et al.'s (2026) PRISMA review of 59 studies catalogs six forms of interdisciplinary education in which AI features: STEM integration (n = 26), cohorts with cross-disciplinary student backgrounds (n = 14), non-STEM fields (n = 10), cross-disciplinary learning content (n = 10), inter-STEM integration (n = 8), and STEAM (n = 2). The distribution is a discipline-level finding, not a tool-level one: AI-supported interdisciplinarity is overwhelmingly STEM-hosted, and cohorts with cross-disciplinary backgrounds are studied more often than the non-STEM fields those cohorts are meant to bridge. The review further shows that the same AI functions recur across these settings — assistant (n = 43), evaluator (n = 22), agent (n = 14), monitor (n = 9) — while their cognitive, behavioral and affective effects differ by discipline and stakeholder, with students by far the most studied (n = 57), teachers next (n = 26) and administrative staff barely examined at all (n = 4).
- **Tutoring and feedback.** AI tutoring systems (AI Tutoring, Intelligent Tutoring, Feedback, AI Feedback Quality) appear in nearly every discipline, from math and physics tutors to writing and language feedback. The discipline shapes what counts as good feedback — right/wrong in math, argument quality in writing, fluency in language.
- **Assessment and evaluation.** Automated Assessment, Automated Grading, Automated Essay Scoring, and Formative Assessment are reimagined by AI across disciplines, but the scoring constructs differ (procedural accuracy vs. interpretive depth vs. communicative competence).

- **Cognitive offloading and over-reliance.** Cognitive Offloading and Over-Reliance risk appears across math, CS, and writing, though the "cognitive act" being offloaded is discipline-specific — computation vs. code vs. composition.
- **AI literacy and critical use.** AI Literacy, Critical Thinking, and Critical Pedagogy underpin responsible use in every subject.
- **Disciplinary grounding gates AI-supported Metacognition.** In a text-linguistics seminar, novices reflected metacognitively with LLMs chiefly where subject knowledge was already consolidated, and most attributed poor outputs to the model rather than their own prompt — evidence that prompt design must be taught explicitly within a discipline (Brocca & Garassino (2026)).
- **Equity and access.** Equity, Digital Divide, and Culturally Relevant Pedagogy concern all disciplines.

Signature pedagogies, methods, and theories by discipline

Each discipline brings distinctive pedagogical traditions that AI research engages:

- **Physics** — model-based reasoning, experimentation, and Simulation. AI research uses virtual labs (Ben-Zion), chatbots (ChatGPT typology), and problem-posing (GenAI problem-posing).
- **Chemistry** — abstract submicroscopic concepts, specialized notation, and laboratory practice. AI research spans AI-supported experimental design (AI-designed lab manuals), context-based 7E instruction with AI tutoring (context-based + AI), AI-mediated formative assessment (instructor–AI roles), and the philosophy of experimentation (philosophy of experimentation).
- **Biology** — specialized terminology, systems/visual-spatial thinking, and hands-on laboratory and fieldwork. AI research spans virtual lab teaching assistants (ChatGPT as VTA), AI literacy embedded in biology curricula (AI literacy in a biology class), ChatGPT in challenge-based learning (ChatGPT in CBL), critical thinking in the AI era (critical thinking in bio sciences), and the AI-tools landscape (AI tools review).
- **Writing** — process-oriented, recursive drafting and revision. AI research spans AI as writing coach, automated scoring, and stage-based ownership (ownership stages).
- **English education (EAP/EFL/ESL)** — English as target language and academic register. AI research spans ethical EAP integration (Alharbi et al.), GenAI EAP writing revision (feedback-literacy scripts), EAP reading-material adaptation (differentiated EAP materials), ESL tutoring (TACT), and English-specific assessment (self-referential L2 writing evaluation, EFL assessment).
- **Teacher education** — a discipline whose AI research centers on preparing teachers to integrate AI: intelligent-TPACK frameworks (i-TPACK PD), teacher AI literacy (science educators), pre-service readiness (intelligent-TPACK readiness), and in-service trust and ethics (trust and ethics).
- **Humanities & social sciences** — interpretation, authorship, and critical meaning-making. AI research foregrounds interpretive cognition (Voicu) and the philosophy of AI rather than tutoring for correctness.

Represented disciplines in the knowledge base

The knowledge base's strongest discipline-specific coverage is in **STEM** broadly — particularly **Math Education**, **Physics Education**, **Chemistry Education**, **Biology Education**, and **CS Education** — followed by **Statistics and Data Science Education**, a strand distinct from mathematics because its signature pedagogy is the data investigation rather than reasoning toward a determined answer. An example of the strand's own design problem: DagFlow-AI uses an agentic pipeline to generate context-matched synthetic datasets, which addresses the material a statistics course needs rather than the explanation of it — and, on the authors' own account, cannot teach data collection, measurement or study design. and **Writing**, **Language Learning** (with a distinct **English Education (EAP / EFL / ESL)** strand for EAP/EFL/ESL), and more recently **Engineering Education**, **Teacher Education** (with a substantial body of pre-service and in-service AI-training research), **Medical and Health Professions Education**, and **Humanities and Social Science Education**. Engineering and design also have a growing body of articles. This concentration tracks the wider literature: Xia et al.'s (2026) review found STEM the most common interdisciplinary form in AI-supported higher education (n = 26), well ahead of non-STEM fields (n = 10) and STEAM (n = 2). The caution is discipline-level: AI-in-education evidence accumulates fastest where computational tooling is easiest to embed, not necessarily where AI's pedagogical value is greatest. The most recent additions broaden the strand past academic subjects into professional and applied education — nursing, information technology, and vocational education and training — where learners are assessed on demonstrated practice rather than on correctness, and where the employer and the licensing body, not only the academy, define what counts as competence.

The vocational strand is the thinnest in that evidence: a systematic review of 26 studies in vocational education and training found none conducted in workplace settings despite VET's work-based character, only five randomized experiments, and only three designs granting learners an active role (Deutscher et al. (2026)).

Underrepresented disciplines

Several disciplines remain thin in the knowledge base and are good candidates for future ingestion:

- **Law and legal education** — minimal coverage: LLMs and Italian legal exams.
- **Psychology and counseling** — few AI-in-education articles: AI feedback literacy, critical GenAI use, virtual patient psychotherapy training.
- **History** — only isolated articles: LLMs and historical reasoning.
- **The arts (visual art, design, music)** — emerging coverage: AI in interior design education, GenAI in architectural design studios, AI vocal pedagogy, AI in music education, text-to-image competence paradox. The design-side studies in this list now have their own home: Design Education draws the architectural, interior-design and text-to-image studio work into a page about professional design formation, leaving visual art, music and performance as the thin remainder.

These underrepresented disciplines would benefit from dedicated concept pages and additional article ingestion as the knowledge base grows.

Common Misconceptions

- **“Discipline matters mainly for content examples.”** Research across **560 students** found disciplinary affiliation **predicts how often and openly students use** generative AI. Discipline shapes whether the tool is used at all and whether that use is disclosed, not only what it is asked about.
- **“Interdisciplinarity is a generic institutional goal.”** The **shape of “interdisciplinary” is itself discipline-determined**: Xia et al.’s (2026) review finds the form it takes varies by field. A single institutional definition misreads at least some of the disciplines it covers.
- **“Vocational education has a research base comparable to the academic disciplines.”** The vocational strand is **the thinnest in that evidence**: a systematic review of **26 studies** in vocational education and training found **none conducted in workplace settings** — the settings where the competence is actually exercised. The literature’s absence is a gap, not a null result.

Connected Concepts

- Business Education
- AI in Education
- Math Education
- Physics Education
- Chemistry Education
- Biology Education
- CS Education
- Writing
- Language Learning
- English Education (EAP / EFL / ESL)
- STEM Education
- Teacher Education
- Medical and Health Professions Education
- Engineering Education
- Humanities and Social Science Education
- K-12
- Higher Education
- Equity
- Arts, Design and Media Education
- Design Education
- Information Technology Education
- Learning Sciences
- Nursing Education
- Vocational Education and Training

Connected Articles

- Artificial intelligence in interdisciplinary higher education: A systematic review on opportunities, challenges and future directions — Systematic review of AI in interdisciplinary higher education (59 studies)
- LLMs in text linguistics teaching: An exploratory study with genAI novices in higher education — LLMs in text linguistics teaching
- Empowering Educators: Operationalizing Age-Old Learning Principles Using AI — Operationalizing learning principles with AI in health-professions education
- Designing effective AI professional development: A framework grounded in intelligent-TPACK — Intelligent-TPACK-based AI professional development
- Teaching the teachers: A systematic review of genAI-specific technological pedagogical knowledge (TPK) in teacher education — GenAI-specific TPK in teacher education
- Human-centered AI for teacher educators: Designing professional learning for critical AI literacy — Critical AI literacy professional learning for teacher educators
- AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education — Interpretive cognition in humanities and social science education
- Pragmatic users and skeptical nonusers: A qualitative typology of ChatGPT adoption in physics education — ChatGPT use typology in physics education
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — GenAI code review in CS1
- From Planning to Revision: How AI Writing Support at Different Stages Alters Ownership — Stage-based AI writing support and ownership
- Using AI in engineering education: a balancing act, driven by clear purpose — The balancing act of AI in engineering education
- AI literacy alone is not enough: Student AI readiness and career adaptability in business and management education — AI literacy and career adaptability in business education
- Generative AI across the disciplines: an activity theory perspective on undergraduate students' AI use and disclosure practices — Activity theory: disciplinary differences in GenAI use and disclosure (560 students)
- AI-Powered Simulation for Nursing Education: Mixed Methods Systematic Review — AI-powered simulation in nursing education: gains in knowledge and confidence, inconsistent effects on psychomotor skill
- Scaffold or Shortcut? Postgraduate IT Students' Use of Generative AI and Self-Regulated Learning — GenAI as scaffold or shortcut in postgraduate IT learning
- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — First systematic review of AI in vocational education and training
- Development and applications of Generative AI in architectural design studios — Generative models in the design studio: stimulus, solution-space expansion, and fixation

- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Mastery stopping rules that certify an overgeneralised rule as competence

Math Education

> **Math Education** — the study of how students learn mathematics and how AI can support mathematics teaching, spanning affective tutoring, cognitive diagnosis from handwritten work, productive struggle evaluation, help-seeking behavior, teacher-AI collaboration for visual generation, and student-AI interaction trajectories. Math education is the most active domain-specific research area in this knowledge base, with 32 articles that collectively explore how AI can support — and sometimes undermine — mathematical learning from elementary fractions through higher education.

Questions to Consider

- Math problems have clear right answers yet require rich reasoning, which is why math is a favored testbed for AI tutoring. When you're stuck on a math problem, what kind of help actually helps you learn — an answer, a hint, or a question — and which is the AI likely to default to?
- Research finds AI tutors often default to over-helpfulness, rarely pushing for rigor even when students are ready. If you're designing a tutor, how do you decide when to withhold help to preserve the 'productive struggle' that builds understanding?
- The page shows students who request hints too early or skim them superficially tend to learn less. Have you ever reached for a hint out of impatience rather than genuine effort? What does that reveal about how AI support can undermine rather than support learning?
- AI cognitive-diagnosis systems sometimes hallucinate evidence and over-attribute mistakes, and even strong models underperform when reading students' actual handwritten work. How confident would you be in a tutor that diagnoses what you got wrong from your scratch work?
- LLMs flip their answers across mathematically equivalent problem formulations — the same problem presented differently changes the result. What does this say about using AI to score or diagnose math understanding?

Introduction

Mathematics education has become a primary domain for AI in education research because math problems have clear right answers yet require rich reasoning — making them ideal for studying tutoring effectiveness, assessment validity, and how AI tools interact with student cognition and affect. The articles in this knowledge base reveal both the promise of AI math tutors and persistent challenges: over-scaffolding that undermines productive struggle, hallucination in cognitive diagnosis, and the difficulty of balancing AI assistance with genuine learning.

Key research themes

AI math tutoring and scaffolding is the largest cluster, with four articles examining how AI tutors support or undermine math learning. **MathBuddy** demonstrates that adding affective awareness — detecting student

emotions from text and facial expressions — produces a +23-point win rate advantage in math tutoring, connecting to Affective Computing and Affective Tutoring. **TutorMoments** evaluates 462 teacher-annotated transcripts from grades 2-7 math tutoring and finds frontier models default toward over-helpfulness, rarely pushing for rigor even when students are ready — directly challenging the alignment between AI helpfulness and Scaffolding principles. **An et al.** analyzed 999 students across three semesters in the *Decimal Point* ITS, finding that premature hint requests and superficial hint reading consistently predict reduced learning gains, even after controlling for prior knowledge — a finding that connects to Help-Seeking and Learning Analytics.

Task design, not only tutoring. Analyzing 158 coded text units from 13 prospective primary teachers, Ledezma et al. (2026) found GenAI-designed geometry tasks reached for high cognitive demand yet wrote closed instructions, and one embedded a wrong scale (4 m drawn as 8 cm, stated as 1 m = 4 cm) (Ledezma et al., 2026).

A satisfaction penalty. Steering an LLM tutor through a Productive Failure plan instead of letting it answer raised strategy fidelity and produced 2.6 solution attempts per session in a 17-student high-school study, yet students rated the productive-failure tutor less helpful than a baseline (Puech et al. (2025)).

Socio-emotional support can buy efficiency rather than achievement. Adding an LLM mindfulness layer to a seventh-grade algebra tutor left learning and state-math anxiety unchanged between arms (42 of 252 students analyzed after disruptions), yet mindful-condition students reached comparable learning with less time and fewer requested hints (Rief et al., 2026).

Pooled across subject domains, GenAI's effect on learning motivation was largest in language (g = 0.946) and moderate in mathematics (g = 0.711, 95% CI [0.356, 1.066], k = 4), so the motivational case for GenAI in mathematics rests on a small, exploratory subgroup rather than a stable effect (Fang et al. (2026)).
Offloading inside mathematics homework. Chatlog traces from 23 linear algebra students show the prompt mix moving with the task while 90% of submissions stayed close to the model's output, and a 153-student proof course found AI-supported homework gains with no exam gain (Kontorovich & Wallach (2026); Chen et al. (2026)).

Cognitive diagnosis and assessment explores AI's ability to evaluate math thinking. Razavi and Powers (2026) add a large-scale item-difficulty study spanning both math and reading: across 5,170 K-5 items calibrated under the Rasch IRT model, GPT-4o's zero-shot difficulty ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but were uneven across grades, while a feature-based approach (LLM-extracted features into tree-based models) reached correlations up to r = 0.87, with grade level and word count the top predictors. The study offers a practical seven-step workflow for testing professionals and cautions that generalizability beyond K-5 math and reading is unclear. **MathCog** benchmarked 18 LLMs on 3,036 teacher-annotated diagnostic verdicts from handwritten math work, finding all models severely underperform (F1 < 0.5) with systematic over-attribution and hallucination of evidence — connecting to Knowledge Tracing, Hallucination Risk, and Multimodal AI assessment challenges. **Nath et al.** showed that Large Language Models (LLMs) math Problem Solving is highly sensitive to surface representation — models flip correctness across equivalent problem formulations — raising Assessment Validity concerns for AI-based math scoring. **Olaoye, Owolabi and Olaoye (2026)** show a contrasting route to evaluating mathematical responses: their Automated Extended Essay Grading Software scores extended-response mathematical items in a senior-secondary Economics examination by semantic similarity against

the WAEC marking scheme, with no training on graded scripts. It agreed with 12 human examiners at an intra-class correlation of 0.863 (average measures), with Pearson coefficients from 0.604 to 0.864. The agreement sits where the marks are lowest — the software averaged 5.94 out of 20 against 5.97 for the raters, each examiner marked only 84 of the 1,008 scripts, and the authors attribute the low scores to candidates' unfamiliarity with computer-based answering.

Student engagement and AI literacy examines how students interact with AI math tools. **Abdelghani et al.** traced temporal trajectories of student-AI interaction in math learning, identifying a developmental path from superficial prompting to "epistemic proactivity" — active, self-directed pursuit of conceptual understanding. This connects to AI Literacy, Metacognition, and Self-Regulated Learning. **Holman** found that AI-adaptive platforms significantly improved fraction comprehension for students with math learning difficulties, connecting to Personalized Learning and Adaptive Learning.

Teacher support explores AI tools for math educators. **Simulated-student role-play** also serves teacher practice: Zhuang and Zhang (2025) built *Student GPT*, a custom ChatGPT chatbot that role-played a middle school student holding common ratio-reasoning Misconceptions about AI, giving preservice secondary math teachers low-risk practice at diagnosing and guiding student thinking toward correct solutions. The setup illustrates GenAI-powered Simulation as a complement to costly platforms like TeachLivE for building pedagogical content knowledge about student misconceptions.

Pre-service teachers can explore with GenAI but not yet validate it. In an Abstract Algebra course, 13 of 18 pre-service mathematics teachers were adequate at constructing examples and non-examples, while 14 of 18 sat at the two lowest levels for judging whether an AI response was valid (Nurlaelah et al. (2026)).

Classroom AI tools also create orchestration work the older typology does not name: observing six high-school mathematics lessons found teachers monitoring dashboards, correcting the AI's wrong Feedback, and mediating its output for the class, with content and ethical judgment most visible when fixing an AI error (Noh & Kim, 2026).

The knowledge base's only field-level synthesis of this domain is a 2021–2025 PRISMA review of 42 studies screened from 922 records (Cohen's kappa = 0.88), and it adds a category the page's clusters otherwise lack: teacher-facing automation, where MATH41 supports rapid production of mathematics tasks for learners at different levels. The hybrid model CognifyNet then analyses students' activity patterns so educators can detect emerging difficulties early. The same review locates the field's blind spot — with Education at 60% and Computer Science at 28% of study domains, only one study fell in Psychology, leaving emotional impact, trust and ethics comparatively underexplored — and insists that technical capability should not be equated with demonstrated classroom effectiveness. (Artificial intelligence in mathematics education: A PRISMA-based systematic literature review (2021-2025))

Inclusion is a design property, not a byproduct of capability. A review of 38 sources pairs UDL with SAMR and finds that AI can redefine a mathematics task while leaving it inaccessible to students whose language, device, or connectivity does not fit (Jita, Jita & Omoniyi, 2026).

The domain's challenge ranking puts teacher capacity first. A second systematic review, of 54 studies from 2017-2025, counted technological–pedagogical integration and teacher readiness in 38, equity and access risks in 34 and limits to deep reasoning in 29, and links them to instructional responses in a three-dimensional framework (Manto et al. (2026)).

Higher education math explores AI's impact on advanced math practice. **Bui et al.** applied socio-cultural theory to GenAI in university mathematics, analyzing AI as a "runaway object" that transforms academic practice in ways that outpace institutional and pedagogical norms.

Symbolic obstacles in calculus are representational rather than procedural: graph-to-symbol translation was the dominant obstacle, and after an AI-supported sequence coded symbolic errors fell by 27.4%–53.8% (Nursit et al., 2026).

LLM tutoring and instructional design is an emerging cluster of two 2026 studies that sharpen the math-education evidence base. Looi, Liu, and Sun (2026) developed a rule-guided LLM tutoring system for primary-school math word problems whose three-layer architecture (diagnosis → intent selection → constrained response generation) improved interactional consistency and reduced premature answer-giving in a 40-student Grade 5 classroom pilot — evidence that procedural math domains need structured rule-guards on otherwise stochastic LLM scaffolding. Zhu, Liang, Mao, and Wang (2026) applied a smart-classroom model to mathematics M.Ed. students and found statistically significant gains ($p < .05$) in instructional-objective design across curriculum-standards, textbook, and student-condition dimensions.

Prompt design is itself a measurable lever: on the MathDial benchmark a pedagogically informed Socratic "Tutor Prompt" raised Success@N and sharply cut Telling@N relative to a base prompt for both GPT-4o and GPT-4o-mini (Chudziak & Kostka (2025)).

GenAI for mathematical modeling tasks extends the generation strand beyond routine exercises. An AI-powered platform developed through the ADDIE approach used direct variation in secondary school mathematics as an illustrative topic, addressing teachers' lack of time and resources to design high-quality modeling tasks: existing tools typically produce conventional word problems or routine exercises, whereas the platform aimed to generate resources that foster mathematical modeling competencies, grounded in established design principles and retrieval-augmented generation. - **Visual chain of thought: the autonomy gap in geometry.** GeoVAD-Bench diagnoses intermediate visual aids rather than final answers across 600 auxiliary-construction problems (200 easy, 200 medium, 200 hard), and finds a consistent pattern: supplying the reference auxiliary diagram improves accuracy modestly (+3.3, +3.0, +7.0 points across three models) while leaving the model to construct its own auxiliary line on the way to the correct answer widens the gap by 10.0 to 13.5 points, with two models performing worse than when they had no visual reasoning at all. Four process-error categories accounted for 93.1% and 89.7% of attributed failures. For Problem Solving instruction the finding is that diagrammatic scaffolding has to be trained and evaluated separately from answer accuracy. (Beyond Generation and Accuracy: Diagnosing and Enhancing Visual Chain-of-Thought for Geometry Problem Solving) - **AI-susceptible problems lose study time and retention.** A ten-year panel of 3.2 million ALEKS interactions found learning time on text-based word problems — those most transcribable into AI prompts — fell 26.9% after ChatGPT's release, while proctored retention items showed a 25% decline in the odds of a correct response (Rismanchian et al., 2026).

- **Students value immediate feedback, but optional practice platforms go unused.** Of 157 students, Chen et al. (2026) saw 95 register and only 34 attempt a question; users rated engagement highest (79% agreement) while just 42% preferred the platform to the existing problem booklet.
- **Errors become the mechanism.** Embedding AI in a mastery-based practice platform slowed progress — students attempted fewer questions — yet raised next-attempt correctness after

mistakes, while a three-correct-in-a-row mastery rule lifted platform success without improving delayed learning (Oreopoulos et al. (2026)).

- **AI can raise achievement while widening a gender gap.** In a six-week quasi-experiment with 115 Nigerian senior-secondary students, ChatGPT feedback raised quadratic-equation achievement over conventional teaching (29.18 vs 24.06), yet male students outperformed female students (30.95 vs 25.16) despite no gender difference in Self-Efficacy — an equity caution for AI mathematics support (Oladayo & Diri, 2026).
- **Students still prefer the teacher's grading decision.** In a vignette experiment with 250 seventh-grade students, teacher-made decisions on a mathematics exercise drew higher acceptance than AI-made ones (M = 4.48 against M = 3.47), perceived fairness carried 67.52% of the effect, and written explanations widened rather than closed the fairness gap (Zhang, Fan & Qi (2026)).

Connections to related concepts

Math education sits within the broader STEM Education domain with distinctive connections to Intelligent Tutoring and AI Tutoring through the strong tradition of cognitive tutors and ITS research in mathematics, to Scaffolding through the productive struggle and hint-use literature, to Affective Computing through math anxiety and emotion-aware tutoring, to Knowledge Tracing and Assessment Validity through cognitive diagnosis and assessment research, and to Teaching through teacher-AI collaboration in math instruction. The K-12 connection is particularly strong — many of the math articles involve K-12 contexts — while Higher Education connections emerge in teacher preparation and advanced math practice.

Implications for math instructors

- **Treat AI tutoring as a help-seeking lever, not a capability fix.** Hint-use research shows premature hint requests and superficial hint reading predict lower gains — so the design of *when and how* students seek AI help matters more than raw tutor capability. Encourage students to attempt before asking, and surface help at the moment of need rather than on demand.
- **Protect productive struggle.** TutorMoments finds models default to over-helpfulness, rarely pushing for rigor; configure AI support to scaffold rather than solve, and monitor for answer-replacement that erodes reasoning.
- **Do not treat AI diagnostic output as ground truth.** MathCog shows LLMs underperform at diagnosing math thinking (F1 < 0.5) with over-attribution and hallucinated evidence; use AI diagnosis as a suggestion to verify against the student's actual work.
- **Beware surface-format fragility in AI scoring.** Representation sensitivity means equivalent problems can flip AI answers — a validity risk for AI-based math assessment; prefer human review for high-stakes scoring.
- **Use AI to lower the bar for personalized practice.** Adaptive platforms improved fraction comprehension for students with math learning difficulties; deploy AI-adaptive tools selectively for learners who need differentiated support.
- **Keep the teacher in control of AI-generated instructional materials.** Teacher control of AI visuals supports a framework that balances AI efficiency with pedagogical correctness.

Common Misconceptions

“The motivational case for AI in mathematics is as strong as for language.” The pooled evidence is thinner for mathematics and should be read that way: GenAI’s effect on learning motivation was largest in language (**g = 0.946**) and moderate in mathematics (**g = 0.711, 95% CI [0.356, 1.066], k = 4**). Four studies and a confidence interval spanning most of the plausible range is a weak basis for a strong claim, and the domain difference is large enough that language findings should not be carried across unexamined.

“If the homework looks right, the mathematics was done right.” Chatlog traces from **23 linear algebra students** show the prompt mix shifting with the task while **90% of submissions stayed close to the model’s output**, and a 153-student proof course found AI-supported homework performance diverging from unassisted assessment. Proximity to the model’s output is the measure of having been helped, not of having learned; in a domain with clear right answers, a correct submission is the least diagnostic artifact available.

“Mathematics is an easy domain for AI because the answers are checkable.” Checkability is what makes mathematics a good testbed, not what makes it safe. Because the final answer is verifiable, a student can validate a solution they did not construct — which is precisely how the subject’s reasoning gets bypassed while the grade stays clean. The property that attracts researchers is the property that makes offloading invisible.

“Item difficulty for mathematics can be assigned by a capable model.” It has to be calibrated against responses. In an item-difficulty study spanning **5,170 K-5 items** calibrated under the Rasch IRT model, model-generated zero-shot difficulty ratings were compared against empirical calibration precisely because stated difficulty and measured difficulty are different quantities.

Connected Concepts

- STEM Education
- Intelligent Tutoring
- Scaffolding
- Affective Computing
- Affective Tutoring
- K-12
- Higher Education
- AI Literacy
- Metacognition
- Self-Regulated Learning
- Personalized Learning
- Adaptive Learning
- Help-Seeking
- Learning Analytics
- Knowledge Tracing
- Assessment Validity
- Multimodal AI

- Hallucination Risk
- Cognitive Offloading
- Teaching
- Educational Development
- Generative AI
- AIEd in the Disciplines
- Teacher Education

Connected Articles

- A Didactic Analysis of the Design of Geometry Tasks Using Generative Artificial Intelligence by Prospective Primary School Teachers — Prospective primary teachers' GenAI-designed geometry tasks: high cognitive demand, closed instructions, an embedded scale error (Ledezma et al. 2026)
- What the submission does not show: Complexifying cognitive offloading in students' mathematical work with LLMs — What the submission does not show: complexifying cognitive offloading in students' mathematical work with LLMs (Kontorovich & Wallach 2026)
- Supporting or Replacing Students' Reasoning? Cognitive Offloading in AI-Assisted Proof Learning — Supporting or replacing students' reasoning? Cognitive offloading in AI-assisted proof learning (Chen et al. 2026)
- Analysing Mathematical Communication between Pre-Service Mathematics Teachers and GenAI: A Case Study in Abstract Algebra Course — Analysing Mathematical Communication between Pre-Service Mathematics Teachers and GenAI: A Case Study in Abstract Algebra Course
- Addressing symbolic obstacles in undergraduate calculus through artificial intelligence scaffolding — Symbolic obstacles in undergraduate calculus are a representational bottleneck, with fewer coded symbolic errors after AI scaffolding (Nursit et al. 2026)
- AI integration in mathematics education: A systematic review of implementation challenges and pedagogical implications (2017-2025) — AI integration in mathematics education: implementation challenges and pedagogical implications (Manto et al. 2026)
- Artificial intelligence in mathematics education: A PRISMA-based systematic literature review (2021-2025) — Artificial intelligence in mathematics education: A PRISMA-based systematic literature review (2021-2025)
- Automated software scoring of senior school certificate examination mathematical items in economics using a contextual similarity model — Automated software scoring of senior school certificate examination mathematical items in economics using a contextual similarity model
- Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning — Beyond Problem Solving: Large Language Models for Emotional and Reflective Support in Mathematics Learning
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- AI-Powered Math Tutoring: Platform for Personalized and Adaptive Education — AI-powered math tutoring platform (Chudziak & Kostka 2025)

- MathBuddy: Affective Math Tutoring
- When Help is Unhelpful: Evaluating AI Tutors for Productive Struggle
- Revisiting the Hint Button: Consistent Negative Associations Between Unproductive Hint Use and Learning Outcomes in Intelligent Tutoring Systems
- Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work
- Representation Robustness under Executable Reasoning Constraints in Large Language Models for Mathematical Problem Solving
- From Prompting to Epistemic Proactivity: Temporal Trajectories of Student-AI Interaction in Mathematics Learning
- Exploring Fraction Comprehension and Interest in Elementary Education Through AI-Powered Personalized Learning
- When should teachers control AI generation for mathematics visuals?
- GenAI as a runaway object in higher education: A socio-cultural view on AI-influenced academic practice in mathematics
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — ALEKS mastery platform: text-based problems most AI-susceptible
- Towards the Pedagogical Steering of Large Language Models for Tutoring: A Case Study with Modeling Productive Failure — Pedagogical Steering of LLMs for Productive Failure
- Improving instructional design proficiency of master's students in mathematics education through intelligent educational technologies — Smart-classroom model and D-T-E loop improving M.Ed. instructional design proficiency in mathematics (Zhu et al. 2026)
- Taming the black box: Design principles for rule-integrated LLM tutoring systems in primary school mathematical problem solving — Rule-guided vs ad-hoc scaffolding in an LLM tutoring system for primary mathematics (Looi et al. 2026)
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- Feedback without the wait: Piloting a generative AI practice platform in a large maths class — Optional GenAI practice platform in a 157-student maths class: immediate feedback valued, uptake limited to 34 active users
- Assessing the Influence of AI-Generated Responses on Academic Achievement: An Ethical Perspective and Self-Efficacy of Delta State Secondary School Students, Nigeria — Assessing the Influence of AI-Generated Responses on Academic Achievement: An Ethical Perspective and Self-Efficacy
- Exploring Teachers' Instrumental Orchestration and Roles in High School Mathematics Classes Using AI-Based Digital Tools — Classroom orchestration work in high-school mathematics: reading dashboards and correcting AI feedback

- Teacher or Artificial Intelligence? The Effect of Decision-Making Agent on Junior High School Students' Decision Acceptance: A Moderated Mediation Model — Students still prefer the teacher's grading decision
- Effects of generative artificial intelligence on students' learning motivation: evidence from a meta-analysis — Motivational gains in mathematics rest on four studies (g = 0.711)
- AI in mathematics classrooms: A synergistic strategy for diversity and inclusivity — AI in Mathematics Classrooms: A Synergistic Strategy for Diversity and Inclusivity

Statistics and Data Science Education

> **Statistics and data science education** — teaching learners to reason about data: framing a question, planning a study, collecting and inspecting data, analyzing it, and communicating what the evidence will and will not support. In AI in education it shares the Math Education focus on reasoning with right and wrong answers, but its signature pedagogy turns on the **material**: the dataset, the chart, the code. That is why the distinctive AI question here is rarely "can the model explain a concept" and more often "can it produce or scaffold the artifact the lesson runs on". Those artifacts are a synthetic dataset with knowable structure, a tactile chart a blind student can read, a practice question whose stated difficulty is honest, an R tutor that withholds the answer. Because the artifact can now be generated, the discipline's central risk is that generated artifacts carry claims nobody validated.

Questions to Consider

- When a statistics course uses a generated dataset, what does a student learn about where data come from — and does it matter that the answer is "nowhere"?
- An LLM labeled practice questions Easy, Medium and Hard. Its labels tracked the Bloom's levels it invented alongside them almost perfectly, and correlated essentially zero with how students actually performed. What would make a difficulty label trustworthy?
- Statistics is often the course where students first meet authentic data problems. If AI supplies the data and the analysis Scaffolding, which part of that encounter is left?
- Is statistics education a branch of mathematics education, or a separate discipline with its own pedagogies? Does your answer change what AI should be built for it?

Introduction

Statistics and data science education covers the investigative cycle as a teachable object — the Guidelines for Assessment and Instruction in Statistics Education (GAISE) recommendations and the Problem, Plan, Data, Analysis, Conclusion (PPDAC) framework are the field's two standard maps of it. Its pedagogies differ from mathematics education in a way that matters for AI design: mathematics instruction evaluates reasoning toward a determined answer, while statistics instruction evaluates reasoning through an **investigation**, where the data, the design, and the limits of inference are themselves the content. The knowledge base files this page separately for that reason. Statistics sits beside mathematics in the curriculum and draws on it, but a tool built to check a derivation is answering a different question from a tool built to generate a dataset whose relationships a student must discover.

The articles here share a pattern that follows from the discipline's artifact-centredness. AI appears as a producer or scaffolder of the lesson's material rather than as an explainer of its concepts: a purpose-built tutor for R, a pipeline that generates tactile charts, a generator of synthetic datasets, an audit of auto-generated practice questions. That shape makes the evidentiary question sharper than in most disciplines,

because when the artifact is generated, every claim embedded in it — a difficulty level, a coefficient sign, a distribution — was decided by something other than the instructor.

Why a separate page from math education

Math Education carries the knowledge base's largest discipline strand and covers reasoning, Problem Solving, affective tutoring and cognitive diagnosis. Statistics and data science education overlaps it on prerequisite skills and shares the STEM Education umbrella, but its signature pedagogy is the **investigation**, and its characteristic failure mode is a validity failure rather than a correctness failure. A student who computes a correct mean from the wrong sample has done the arithmetic right and the statistics wrong, and the assessment frameworks this field teaches — validity, sampling, the scope of a conclusion — are built to catch exactly that.

Treating the two as one page would obscure the distinction that the evidence keeps returning to. The corpus's data science studies are about **generated material and its calibration**: an R tutor's adoption curve, practice questions whose metadata does not match student performance, datasets whose relationships are asserted rather than observed, charts whose design parameters are derived from perception research. None of those is a mathematics-education problem.

The boundary is not clean at the edges. Statistical programming sits inside CS Education in most institutions, and several articles here are filed there; accessibility work on statistical graphics overlaps Special Education and accessible design; responsible data science overlaps CS Education and Ethics. The page is a home for the cluster, not a claim that the cluster is sealed.

Lund and colleagues (2026) mark that overlap from the curriculum side: four accountability pillars (answerability, responsibility, enforcement, reflexivity) crossed with four XAI dimensions, taught through graded model cards, LIME and SHAP explanation audits, and impact assessments, with the authors conceding that explanation is not accountability.

Generated artifacts and the validity question

The sharpest evidence in this strand is a construct-validity audit of LLM-generated retrieval practice in three data science courses. Across a 10-week study the model's Easy, Medium and Hard labels tracked the Bloom's levels it had generated alongside the questions almost perfectly, and were essentially unrelated to how students actually performed on them. The labels described question formatting, not difficulty, which makes validity the operative concern: generated item metadata has to be calibrated against student response data before an instructor trusts it, and the correlational structure that makes it *look* coherent is generated by the same model in the same step. The same study found students used LLMs heavily for debugging and concept questions and reported high satisfaction, while their perceived deep-learning benefit declined over the term — satisfaction and learning moving apart in the same classroom.

A second strand asks what happens to the data itself. Synthetic data generation is presented as a route to personalization: matching a dataset to a student's interests, the learning objective, and their skill level is a three-way constraint real datasets rarely satisfy. The design that follows from it is to have language-model agents specify an explicit data-generating mechanism — variables, a directed acyclic graph, distributions, formulas with coefficients — which a program then executes, so the process is inspectable and reproducible

rather than an opaque generator. The limit is stated by the authors themselves: synthetic data cannot support conclusions about the world or teach data collection, measurement and study design, so the approach complements real data rather than replacing it. That limit is not incidental to statistics education. It is the part of the cycle PPDAC puts first and second.

Scaffolding the tools of the discipline

The clearest positive results concern tools built for a specific course and a specific language. A purpose-built AI tutor wrapped around a hosted API, system-prompted to guide rather than answer, was deployed in a semester-long R programming course for psychology undergraduates: 76% to 84% of students used it in exam-relevant weeks. They self-reported spending 53% of their study-tool time with it against 8% for unvetted generative AI tools, use fell to 50% to 58% once weekly content stopped counting for the exam, and rebounded to 64% in the week before the oral examination. Adoption tracking the assessment calendar that closely is a reminder that tool uptake is a study-behavior phenomenon, not only a quality signal.

Scaffolding quality matters independently of access. An experimental comparison of guided against unrestricted Large Language Models (LLMs) access found that explicit training in reasoning-focused scaffolding — stepwise hints, verification — produced better independent performance and better Self-Assessment calibration than uncritical reliance, which locates the educational work in the structured interaction rather than in the model. The accessibility strand makes a similar move for the artifact: a roughly 1,500-line JavaScript pipeline derives tactile design parameters from plate dimensions, offers five modular chart builders, and produces print-ready STL in under 250 milliseconds with single-pass Braille and English labeling. Optionally it uses a Multimodal AI model to extract chart specifications from an uploaded image, with mandatory teacher review before printing. Generation is paired with a human check in both designs.

What the evidence does not yet establish

- **No learning-gain evidence for generated datasets.** The synthetic-data design is demonstrated through a single case study with no student users and no comparison against a real dataset or against an instructor hand-building a generator.
- **No validated difficulty or quality metadata.** The one audit found generated labels uncorrelated with performance, so the field has a demonstration of the failure rather than a working calibration method.
- **Adoption is not learning.** The R tutor evidence is usage, self-report and prediction, from 49 pretest and 34 posttest respondents in one course at one university.
- **Most scaffolds are single-site and un-replicated**, and the responsible-data-science curriculum framework is described by its authors as conceptual and untested.
- **No study tests transfer to real-data practice**, which is the outcome the discipline actually cares about: whether a student who learned on generated material can investigate real data.

Implications for AI in education

1. **Calibrate generated item metadata against response data before trusting it**, because coherent-looking labels can be generated by the same model that wrote the questions and carry no information about difficulty.
2. **Keep generated artifacts inspectable.** Where a mechanism can be specified — a DAG, a distribution, a formula — specifying it is better than sampling from a black box, both pedagogically and for the instructor's ability to verify what students will find.
3. **Do not let synthetic material crowd out measurement and design,** since those are the parts of the investigative cycle a generated dataset cannot teach and the parts GAISE and PPDAC place first.
4. **Build the human check into the pipeline,** as the tactile-graphics work does with mandatory teacher review before print, rather than treating generation as the end of the process.
5. **Read usage as a study-behaviour signal.** Adoption that tracks the exam calendar is evidence about incentives, so evaluating a discipline-specific tool requires outcomes measured after the incentive disappears.

The material itself is a design problem, not only the explanation. A statistics or data-science course needs datasets that fit the student's question, and generating them is where AI enters some of this strand's work: DagFlow-AI is an agentic pipeline producing context-matched synthetic datasets, with a worked case of matching the data to a student whose interest was climate and health while holding objectives and skill level fixed. That is situated learning applied to the material rather than to the explanation. The authors are also explicit about the limit: synthetic data cannot teach data collection, measurement or study design, so the strand's signature pedagogy is only partly reachable this way.

Common Misconceptions

- **"Satisfaction and perceived benefit indicate a data-science AI tool is working."** Students used LLMs heavily for debugging and concept questions and **reported high satisfaction, while their perceived deep-learning benefit declined over the term**. Satisfaction held and the self-assessed learning trajectory fell, so neither figure alone is the outcome.
- **"An unrestricted model is as good as a guided tutor."** The gain came from scaffolding training — explicit instruction in stepwise hints and verification — which beat plain access to the same model on independent performance and on self-assessment calibration. The guidance, and the training in how to use it, carried the effect.
- **"Guarding against answer-giving is enough."** A course-specific tutor on a hosted API, instructed to nudge rather than supply answers, was adopted by **76% to 84%** of psychology undergraduates during exam-relevant weeks of a semester-long R programming course. That is adoption, not evidence that the guarding produced learning: prompt-level guarding is one lever among several and does not by itself produce learning.

Connected Concepts

- Math Education

- CS Education
- STEM Education
- AIEd in the Disciplines
- Assessment Validity
- Automated Question Generation
- Personalized Learning
- Inquiry-Based Learning
- Situated Learning
- Intelligent Tutoring
- Explainable AI

Connected Articles

- DagFlow-AI: Agentic synthetic data generation for personalized statistics learning — Agentic tool generating inspectable synthetic datasets for personalized statistics practice
- Student Adoption of an AI Tutor for Statistical Programming: A Longitudinal Study — Purpose-built R tutor; adoption tracked the exam calendar
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — LLM difficulty labels track Bloom's levels, not student performance
- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — Open-source pipeline generating tactile statistical charts with teacher review
- Beyond Access: Guided LLM Scaffolding for Independent Learning in Undergraduate Statistics — Guided scaffolding beat unrestricted access on independent performance
- Toward socially accountable data science education: A conceptual framework for integrating explainable AI and accountability principles — Embedding social accountability in the technical data science curriculum

Physics Education

> **Physics Education** — the study of how students learn physics and how to teach it more effectively, spanning Socratic AI tutoring, computational thinking assessment, student Trust and AI adoption patterns, automated scoring validity, and teacher preparation. The physics education articles in this knowledge base are notable for their domain-specificity: they explore how AI tools interact with the unique cognitive demands of physics reasoning — visual-spatial thinking, mathematical modeling, abstract systems thinking, and multi-step Problem Solving.

Questions to Consider

- Physics problems often require visual-spatial thinking, mathematical modeling, and multi-step reasoning. Why might these be precisely the cognitive demands that current AI tutors struggle with?
- Students report a big trust-utility gap—91% use AI for coursework but only 41% trust it. Have you experienced using a tool you didn't fully trust? What drove the gap?
- AI scoring systematically underestimated linguistically weak students' physics explanations. What does that suggest about how an AI grades an explanation versus a correct numeric answer?
- One study found a Socratic AI chatbot dramatically improved question specificity in a live physics course, but students also frequently 'ceded strategic control' to the tutor. When does handing over strategic control help learning, and when does it harm it?
- Why might physics be a 'proving ground' for AI in education—what makes its problems ideal for studying how AI affects reasoning and assessment?
- Would you trust an AI to grade your physics problem set or reason through a force diagram with you? What would need to be true about the AI—and about your course—for you to say yes?

Introduction

Physics education research has become a proving ground for AI in education because physics problems are well-structured yet cognitively demanding, making them ideal for studying how AI tools affect learning, reasoning, and assessment. The 26 articles in this knowledge base collectively paint a picture of a field grappling with both the promise and the limits of AI — from Socratic chatbots that improve student question quality to systematic scoring biases that penalize linguistically diverse learners.

Key research themes

Socratic AI tutoring in physics is the most developed theme, with three articles deploying Large Language Models (LLMs)-powered Socratic dialogue in real physics courses. **Hashmi et al.** demonstrated that sustained Socratic interaction with an AI chatbot dramatically improves question specificity in introductory mechanics, with 150 STEM majors in a live course. **Hashmi & Rebello** built a bottom-up taxonomy of 357 student discourse categories from the same deployment, revealing that meta-procedural turns — where

students cede strategic control to the tutor — dominate student interactions. Both contribute to broader Socratic Method research and connect to AI Tutoring and Intelligent Tutoring frameworks.

Student AI adoption and trust explores how physics students actually use AI tools. **Fouad & Bentley** found a 50-point trust-utility gap: 91% use AI for coursework but only 41% trust it, with students spontaneously identifying AI failure modes in visual-spatial reasoning and circuits. **Becker et al.** developed a two-profile typology — 70% "Pragmatic Users" and 30% "Skeptical Non-Users" — from 1,189 survey responses, showing both groups make calculated risk-utility trade-offs. These studies advance AI Literacy and Trust Calibration research, and challenge one-size-fits-all AI policies.

Use is selective, and approval outruns it. In a survey of 209 engineering students at six Kazakh universities, 36.1% reported regular general AI use, but only 20.2% used it very frequently in physics and specialized disciplines (Nauryzbayeva et al. (2026)). Use concentrated on explanation-seeking tasks — 55.1% for clarifying difficult topics and 51.4% for homework — ahead of written assignments at 43.5%. Engineering thinking drew the strongest perceived contribution at 61.1%, yet the instrument measured only use patterns and perceived support, not learning. Nothing here shows that AI improved physics learning, and the authors say so.

Structured use, not merely adoption. The adoption studies above describe who uses AI and how much they trust it. A separate strand asks what instructional design should do with that use, and multi-institutional evidence on it has been scarce. **Paul et al. (2026)** ran the four-step Physics AI-Replication protocol in 11 algebra- and calculus-based sections at four institutions: identify a hard problem, get an AI explanation and solution, request similar practice problems, then solve them independently before checking.

Perceptions were consistent across campuses. Of 358 enrolled students, 235 were surveyed (65.6%); 90.9% credited improved conceptual understanding and 97.7% found the replicated practice helpful; post-engagement confidence averaged 7.18 on a 1–10 scale with institutional means from 6.86 to 7.52; and the dominant qualitative theme held between 60.6% and 67.6% at every site. Confidence tracked those two protocol benefits ($r_s = 0.37$ and 0.35) but not AI usage frequency ($r_s = 0.02$) — the variable the adoption literature usually measures.

Epistemological beliefs track chatbot-behavior preference. In a large calculus-based course, 52% of students preferred a chatbot beginning with guided inquiry and answering only when asked, and they scored higher on the EBAPS total ($p = 0.029$) — differences that did not survive a Bonferroni correction, making the association suggestive, not conclusive (Sirnoorkar and Mamidpalliwar (2026)).

Acceptance has now been modeled rather than described: a 340-student structural equation study of Grade 10 physics classes in Hangzhou explains 58% of the variance in intention to use DeepSeek. Its notable result is that beliefs about physics — utility value, expectancy, cost — predict how useful and how easy the tool seems, not only whether students intend to use it (Xue, Xu, Qi & Lu (2026)).

Perception change without behavior change is what O'Brien et al. (2026) add to this picture. A reflective lesson on how LLMs work, taught in a required first-year course for physics majors, raised skepticism sharply — agreement that LLMs can leave students with a false sense of confidence rose from 58% to 88%, and the belief that an LLM outperforms the average physics student fell from 54% to 32% — while convenience (71% agreement) and deadline pressure (65%) remained the dominant reasons for use. The lesson's limits are as informative as its effect: AI Literacy instruction shifted what students said about these

tools and not the pressures that make them reach for one, which is why an intervention of this kind belongs alongside problem and policy design rather than in place of it.

Problem posing turns the learner into the problem author: 76% of 49 physics students perceived a positive change in their GenAI interactions after prompt-engineering training, novices benefiting most, and about 68% viewed the technique positively as self-study (Dawson & Rebello (2026)).

Assessment and computational thinking examines how AI can evaluate physics learning. **Savage et al.** used LLMs to assess computational thinking growth in introductory physics, finding LLMs can scale CT assessment but struggle with complex constructs like Systems Thinking. **Feser & Tschisgale** demonstrated that AI scoring systematically underestimates linguistically weak students' physics explanations — a finding that connects to Assessment Validity, Bias Mitigation, and Equity.

An AI grader's disagreement can be a retrieval failure, not a reasoning gap. In experimental physics laboratory reports a dropped sign or misread axis may never reach the model, so document conditions — high-resolution PDFs, editor-written equations — cap any score, and processing belongs behind teacher verification (Abreu et al. (2026)).

Psychometric infrastructure for diagnostic assessment. Le et al. (2026) invert the usual AI-in-physics question: rather than asking whether a model can solve or grade physics, they ask whether the field's own research-based assessments can be made to diagnose it. Mapping FCI, FMCE and EMCS items onto 14 fine-grained learning objectives and fitting a DINA cognitive-diagnostic model to 24,394 posttest responses from 807 courses at 79 institutions via the LASSO platform, they built the Mechanics Cognitive Diagnostic — reported as the first cognitive diagnostic computerized adaptive test in physics. The FCI and EMCS fit well ($RMSEA^2 = 0.033$ and 0.022) while the FMCE fit only marginally (0.065), and the authors trace that misfit to instrument design rather than modeling: 42 of 43 scored FMCE items share scenario stems in chained sets, creating the local item dependence that DINA's conditional-independence assumption forbids (the FCI blocks 13 of 30 items; the EMCS none). Classification accuracy met the low-stakes formative benchmark for 19 of 22 objective–assessment combinations; the three failures were EMCS energy objectives whose items overlap by roughly 70 percent, so mastery of one cannot be separated from the others. The significance for physics teaching is that instruments courses already administer can be repurposed to deliver actionable, objective-level feedback *during* instruction rather than a retrospective posttest score — provided the diagnostic claims are pitched at the resolution the item bank can actually support.

Benchmarking multimodal AI on authentic physics problems. Chen et al. (2026) introduce **OmniPhys**, a large-scale Multimodal AI Benchmark (15,246 questions, 19,850 images) spanning middle-school through university-level physics from Chinese educational corpora. Unusually, it evaluates not just multimodal *input* comprehension but multimodal *output* generation — whether models can synthesize structured physics diagrams, a core component of authentic problem solving. Extensive evaluations reveal critical gaps in current multimodal LLMs, especially in complex reasoning and visual generation.

Instructional-design frameworks for AI-augmented instruction. **Kuhn et al.** propose the **AIRIS** framework (Activate–Inquire–Reflect with Intelligent Support) — a three-phase structure for cognitively activated AI use in physics: students predict and sketch expected outcomes before AI (Activate), delegate computational and representational steps to AI while critically comparing output to their own predictions (Inquire), and interpret, check consistency across representations, and reflect on what the AI contributed afterward (Reflect). Grounded in Self-Regulated Learning, Cognitive Load Theory, multiple external

representations, and Human AI Collaboration, it frames the central challenge as instructional design rather than cheating or tool choice, and calls for “withdrawal condition” experiments testing whether learning survives the removal of AI support. - **Teach critique of AI solutions with a rubric.** Twenty-four introductory physics lab groups that critiqued an AI solution with MAPS-guided reflection identified skipped numerical integration, undefined notation and qualitative-instead-of-quantitative plotting, while groups that only solved a related problem accepted the polished output or rejected it from their own misconceptions (Borse et al. (2026)). - **Energy preconceptions decide whether the AI becomes concept talk or a lookup.** Wang et al. (2026) ran fourteen pre-service teacher groups through energy forms and conservation in Go-Lab with an on-demand metacognitive chatbot. Groups whose members answered an energy pretest differently asked the same kinds of questions as matched groups, but put AI query negotiation at the center of their interaction network and sustained positive or neutral evaluation of its answers, while matched groups ran a linear query-then-read path. Concept confusion ran f = 87 against 36, with 88.9% against 57.1% case coverage.

Generative video as synthetic experimental data. Alvarado-Cruz et al. (2026) generate video scenarios with PixVerse, Grok Imagine and Pippit for three resistive-force regimes — constant friction, linear drag and quadratic drag — extract the kinematics with the Open Source Tracker tool, and fit the analytical models by non-linear least squares. The synthetic data agreed with the classical equations of motion and recovered physically meaningful parameters, and the recurring practical finding is that prompt specificity governs physical coherence: more detailed descriptions produced more coherent dynamics. The workflow mirrors experimental practice from model construction to quantitative validation, and reframes prompt formulation as a stage of experimental design rather than a convenience. What it does not yet demonstrate is learning: validation here is agreement between generated motion and the authors’ models, not students’ measurement judgment, so the approach inherits the validity question any generated data used as evidence must answer.

Bespoke simulations for the topics PhET does not cover. LLM-generated HTML/JavaScript models let instructors produce the simulation a course needs rather than the nearest published one, subject to technical and physical validation; in a pilot, 53 students in 26 pairs built and refined their free-fall models with no programming background required (Ben-Zion et al., 2025).

A reusable four-element prompt — tools, display, hand controls, optimization — lets a no-code teacher generate a browser-based AR simulation whose pinch-and-spread gestures drive the physics; in a 29-student pilot the gesture helped all 29 “feel” wavelength (mean 4.52) and 86% reported greater engagement (Levy et al. (2026)). **AI-generated instrumentation from a prompt.** A rotation lab generated by natural-language prompting of an AI assistant, with no manual coding, measured uniform and accelerated circular motion to within 1% of independent Tracker video analysis, letting instructors build the interface around their pedagogical variables rather than adapt to a precompiled sensor app (Suñer et al. (2026)).

Assisted performance vs. unaided knowledge in a redesigned course. A 2026 redesign of the introductory nuclear and particle physics course at Ruhr University Bochum (Mikhasenko et al.) allowed generative AI on ten deliberately AI-resistant, research-shaped homework sheets designed so that naive prompting would not suffice. Engagement and ambition were high — 24 of 42 students earned credit on all ten sheets, and one derivation filled more than two meters of blackboard — but an unaided 90-minute written exam was a “serious warning”: a mean of 20.6/80, with only two of 27 examinees reaching 40. The authors conclude that assisted performance and independently retrievable knowledge are distinct achievements that cannot be

assumed to train or demonstrate each other, and that physics courses must reserve some practice for unaided work — reinforcing the knowledge base's broader transfer evidence.

A 2026 PRISMA review of 11 empirical studies across six countries reaches the same conclusion at the level of the field: short-term gains from AI feedback and simulation did not persist into later examinations or transfer to independent performance (review of AI in university physics education).

Agent role design as an instructional variable. Wang et al. (2026) hold the model (DeepSeek R1), platform, and temperature constant and vary only the prompt-specified role: a teacher-centered agent answering authoritatively from a bounded textbook knowledge source, versus a student-centered agent configured as an empathic teacher with knowledge of students' understanding, scripted to diagnose the cause of Misconceptions about AI, name the relevant concept, and transfer to an analogous phenomenon. Across 59 high-school graduates working two conceptual items, the student-centered agent produced higher post-test scores (9.67 vs. 7.93; r = 0.38), lower extraneous and higher germane cognitive load, stronger flow experience (d = 0.92), and higher empathy perception (r = 0.53) — evidence that role framing, not just answer accuracy, is what makes a physics agent instructionally effective (Pedagogical Agent, Prompt Engineering). - **Benchmark scores understate what models can already do in physics.** Re-grading six widely used physics benchmarks with domain experts found that most of the reported shortfall was an artifact of defective items and restrictive automated graders: of 250 audited rejections, 143 (57.20%) were benchmark defects and 95 (38.00%) grader errors, with only 12 (4.80%) genuine model errors. Corrected, HLE-Physics mean@4 rose from 47.28% to 78.66% and CritPt from 32.29% to 87.50%. For physics instruction this cuts both ways: it means students can already obtain expert-level text solutions to many canonical problems, so assessment of physics reasoning needs to move toward items that resist benchmark contamination and toward process evidence rather than final answers. (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks) - **AI grading can reproduce a high-stakes physics outcome without matching every part.** Grading 10,364 handwritten Olympiad and university pages, a multimodal LLM recovered the same five-student Olympiad team as examiners and correlated with totals at r = 0.93–0.96, but exact question-part agreement reached 70% — examiner-controlled second reading, not replacement (Pathak et al. (2026)).

- **Physics benchmarks can be curriculum-grounded and non-English.** Jahin et al. (2026) built 1,834 Bengali questions from the national Grade 9-10 physics textbook and a 1,760-node knowledge graph; one fixed fine-tuning recipe gained 5.5, 15.0 and 23.3 points at 0.6B, 1.7B and 4B parameters.

Connections to related concepts

Physics education sits within the broader STEM Education domain but has distinctive connections: to Socratic Method through the strong tradition of Socratic dialogue in physics problem-solving; to Computational Thinking through the increasing role of computation in physics; to Assessment Validity through the challenges of scoring physics explanations; and to Workplace Learning through Simulation-based preparation. The Student Experience and AI Literacy concepts are essential for understanding how physics students navigate AI tools, while Educational Measurement and Automated Grading connect to the assessment dimension.

Implications for physics instructors

- **Design for student trust, not just adoption.** Fouad & Bentley document a 50-point trust-utility gap (91% use, 41% trust), with students identifying AI failures in visual-spatial reasoning and circuits — create opportunities to expose and discuss these limits rather than assume acceptance.
- **Use Socratic AI to deepen question quality, but watch for strategic ceding.** Socratic chatbots improve question specificity, yet taxonomy research finds meta-procedural turns dominate — students hand strategic control to the tutor. Intervene to keep students the decision-makers.
- **A well-engineered tutor beat in-class active learning.** Kestin et al. (2025) found that 194 Harvard life-sciences students learned more from the course's own AI tutor than from research-based active-learning lessons covering the same content (median post-test 4.5 vs. 3.5), with higher reported engagement and Motivation, crediting expert-crafted prompts and platform-sequenced problems rather than the technology alone.
- **Structure AI use cognitively, not just permissively.** AIRIS (Activate–Inquire–Reflect) shows the value of having students predict/outline before AI, delegate computational steps while comparing output critically, and reflect afterward — treat AI integration as an instructional-design problem, and test whether learning survives AI removal. In a randomized trial with 95 undergraduates, 45 minutes of SRL-aligned training on mechanics problems lifted accuracy when students later revised electromagnetism items with a model: 69.3% of their incorrect answers became correct against 41.3% for untrained controls (d = 0.81) (Huang et al. (2026)).
- **Guard against scoring bias.** AI scoring systematically underestimates linguistically weaker students' explanations; use language-aware or human-moderated scoring for conceptual assessment.
- **Use simulated classrooms for teacher preparation.** Simulated multi-agent classrooms give prospective teachers rare practice responding to authentic student reasoning — a low-cost complement to live microteaching.
- **Reserve unaided practice and assessment.** The Bochum redesign (Mikhasenko et al. 2026) shows AI-permitted, research-shaped homework completed with high engagement can leave students far behind on an unaided exam (mean 20.6/80) — treat assisted performance and independently retrievable knowledge as distinct, and build deliberate unaided practice and a written exam into the course.
- **Verify facilitator fidelity; keep the model-building phase AI-free.** Pressed to "just tell us" which can weighed more, a purpose-configured Gem invented mass values no one had measured, so a language-based facilitator's fidelity must be checked rather than assumed, and the AI-free build phase preserves the hands-on work it cannot reach (Tufino & Damiani (2026)).

Common Misconceptions

- **"Students trust AI enough to rely on it uncritically."** Fouad and Bentley found a **50-point trust-utility gap**: **91% use AI for coursework but only 41% trust it**. Widespread use coexists with low trust, so an intervention aimed at building enthusiasm addresses the wrong variable.

- **“Physics students are one population.”** Becker et al. developed a two-profile typology from **1,189 survey responses**: **70% “Pragmatic Users” and 30% “Skeptical Non-Users”**. A single classroom policy has to serve two groups with opposite stances.
- **“The gap between use and trust is irrational.”** The two figures measure different things — whether the tool helps you finish work, and whether you believe it does so correctly. Students are distinguishing utility from reliability, which is the analytically correct distinction and not a contradiction.

Connected Concepts

- STEM Education
- Socratic Method
- Intelligent Tutoring
- Computational Thinking
- AI Literacy
- Trust Calibration
- Student Experience
- Assessment Validity
- Bias Mitigation
- Equity
- Automated Assessment
- Educational Measurement
- Learning Analytics
- Workplace Learning
- Simulation
- Generative AI
- Higher Education
- AIEd in the Disciplines
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools

Connected Articles

- Modeling high school students’ acceptance of GenAI for physics learning via an extended technology acceptance model: Disciplinary beliefs as a distal antecedent — Acceptance of GenAI modeled in Grade 10 physics
- From Prompts to Physical Laws: A Generative AI Workflow for Engineering Physics Education — From Prompts to Physical Laws: A Generative AI Workflow for Engineering Physics Education

- Comparing teacher-centered and student-centered agents based on prompt engineering: Effects on learning performance, cognitive load, flow experience, and empathy perception in physics learning — Teacher-centered vs. student-centered prompt-engineered physics agents (Wang et al. 2026)
- OmniPhys: A unified multimodal benchmark for physics understanding and generation from Chinese educational corpora
- Leveraging AI for Rapid Generation of Physics Simulations in Education: Building Your Own Virtual Lab — Using AI to rapidly generate physics simulations / virtual labs (Ben-Zion et al. 2025)
- Analyzing Undergraduate Problem-Solving in Physics Through Interaction With an AI Chatbot
- A Bottom-Up Taxonomy of Student Discourse with a Socratic AI Physics Tutor
- Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration
- Pragmatic users and skeptical nonusers: A qualitative typology of ChatGPT adoption in physics education
- Using LLMs to Detect Growth in Computational Thinking in Introductory Physics
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics
- A multi-agent AI classroom based on dual-process reasoning hazards: a pilot with prospective physics teachers
- Students' epistemological beliefs and their chatbot preferences in AI-mediated physics learning
- Studying circular motion with an AI-generated smartphone physics lab
- From prompt to embodied simulation: Using generative AI to create AR physics learning tools
- Embodied inquiry with AI as facilitator: An exploratory case study
- Probing AI-generated physics solutions and preparing students to critique them
- Exploring students' perceptions of using generative AI-assisted problem posing
- It's Not the Tool, It's the Task: A Framework for Cognitively Activated AI Augmentation in Physics Instruction — AIRIS: A Framework for Cognitively Activated AI Augmentation in Physics
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- AI in Particle Physics Education: Research Problems and Foundational Skills — AI in Particle Physics Education: Research Problems and Foundational Skills
- Mechanics Cognitive Diagnostic: Testing Fine-Grained Learning Objectives in Introductory Physics — Mechanics Cognitive Diagnostic: turning the FCI, FMCE and EMCS into a 14-objective cognitive diagnostic (Le et al. 2026)
- Skepticism vs. Convenience: Physics Students' Perceptions and Use of Large Language Models Before and After Instruction — Skepticism vs. Convenience: Physics Students' Perceptions and Use of Large Language Models Before and After Instruction

- AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice — AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice
- PhysicsMate: A Curriculum-Grounded Bengali Benchmark for Secondary Physics QA with Small-Model Adaptation — PhysicsMate: 1,834 Bengali secondary-physics QA pairs mapped to a 1,760-node curriculum graph, with small-model adaptation gains
- Artificial intelligence in university physics education: a systematic review of empirical studies — Artificial intelligence in university physics education: a systematic review of empirical studies
- From answer machine to collaborative partner: impact of structured generative AI training on scientific problem solving in STEM education — Structured GenAI training for physics problem revision: a randomized controlled trial (Huang et al. 2026)
- AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting — A well-engineered tutor beat in-class active learning
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — Energy preconceptions decided where AI query negotiation sat in the group network: an integration hub when members disagreed, a linear query-then-read path when they agreed (Wang et al. 2026)
- Artificial intelligence in professionally oriented physics education: patterns of use and perceived learning support among future engineers — Use patterns and perceived support among future engineers

Chemistry Education

> **Chemistry Education** — the study of how students learn chemistry and how to teach it more effectively, spanning GenAI in laboratory and experimental design, AI-mediated formative assessment, context-based and inquiry-based instruction, the technical accuracy of LLMs on chemistry tasks, and the philosophy of experimentation in the AI age. Chemistry education research engages the discipline's distinctive demands — abstract, submicroscopic concepts, symbolic and representational notation (formulas, SMILES, spectra), and hands-on laboratory practice — which make it a rich and distinctive context for studying how AI both supports and challenges learning.

Questions to Consider

- Chemistry combines abstract submicroscopic concepts, specialized symbolic notation, and hands-on laboratory practice. Before reading, which of these three distinctive demands do you think AI handles well, and which might it struggle with — especially given the page's warning about LLMs failing on rigorous quantitative and spatial-reasoning tasks?
- One study had students design lab manuals with AI, implement them hands-on, and have them validated by professionals — significantly boosting experimental confidence and critical thinking while shifting staff roles from demonstration toward guidance. What makes this 'AI for experimental design' different from just asking AI for answers?
- Systematic evidence shows LLMs can define basic chemistry terms but perform poorly on rigorous quantitative tasks, struggle with spatial reasoning (like NMR), and show overconfidence. If an AI confidently gives you a wrong answer on a hard chemistry problem, how would you detect it — and what skill does that detection require?
- Research proposes assigning AI distinct roles by achievement level — a Patient tutor for low-achievers, a Personal Coach for mid-level, and an Intellectual Sparring Partner for high-achievers. Why do you think the same AI tool should play different roles for different students, and what does that require of the human instructor?
- The page warns of 'epistemic drift' — reliance on opaque algorithms detaching scientific inquiry from causal understanding. If AI predicts an experimental outcome, when does that prediction help you understand chemistry, and when does it quietly replace the understanding itself?

Introduction

Chemistry education has become a fertile domain for AI-in-education research because chemistry combines **abstract conceptual content**, **specialized symbolic representation**, and **physical laboratory practice**. AI tools (notably ChatGPT and conversational agents) are used to explain complex topics, support laboratory work and experimental design, provide personalized Feedback and formative assessment, and simulate experiments. At the same time, research documents LLMs **technical limits** on rigorous chemistry tasks and the risk of **epistemic drift** and over-reliance.

Key research themes

AI-supported laboratory and experimental design is a distinctive strength of chemistry-education research. **Yim & Lui** integrated AI chatbots into an upper-division undergraduate analytical chemistry lab: students used AI to **design lab manuals**, implemented them hands-on, and had them validated by certification professionals — significantly enhancing experimental confidence and Critical Thinking/ Problem Solving skills while shifting staff roles from "cookbook" demonstration toward guidance. The philosophy-of-experimentation strand examines how AI reshapes the epistemology, ontology (AI predictions in a "liminal" space), and methodology of chemistry experiments, and warns of **agency shift** and over-reliance.

Context-based and inquiry-based instruction uses AI within structured pedagogies. **Abdikayumova & Madybekova** combined the **7E instructional model** with PhET simulations and ChatGPT tutoring for Grade 10 chemistry, finding significantly higher achievement and engagement than inquiry-only or conventional teaching — demonstrating the synergy of contextualization, structured inquiry, and adaptive AI. This connects to Constructivism and Personalized Learning frameworks.

AI-mediated formative assessment and human–AI collaboration. Ratniyom et al. found pre-service science teachers perceive distinct, achievement-based roles: the human instructor as an adaptive expert (Simplifier/Elaborator), and ChatGPT as a personalized self-regulated-learning tool shifting from *Patient tutor* (low-achievers) to *Personal Coach* (medium) to *Intellectual Sparring Partner* (high) — proposing an **Instructor–AI Synergistic Learning Ecosystem**. This advances Human AI Collaboration, Formative Assessment, and Self-Regulated Learning research.

Technical accuracy and critical AI literacy. Systematic evidence shows LLMs can define basic chemistry terms but perform poorly on rigorous quantitative tasks and struggle with spatial reasoning (e.g., NMR), overconfidence, and notation sensitivity (Erümit & Özdemir Sarıalioğlu; the ChemBench/QCBench findings in the UNESCO perspective). This makes **evaluative engagement with AI output** — interrogating, verifying, and cross-checking against chemical principles — a central learning goal, connecting to AI Literacy, Critical Thinking, and Reducing AI Misuse.

Ethics, policy, and epistemic drift. The UNESCO-guidelines perspective warns of **epistemic drift** — the risk that opaque algorithms pull inquiry away from causal understanding — and calls for a shift from content delivery to **knowledge creation**, critical AI chemical literacy, human-reasoning-prioritizing assessment, and closing the global access gap.

Connections to related concepts

Chemistry education sits within the broader STEM Education domain and shares much with Physics Education (laboratory practice, abstract concepts, problem-solving) while having distinctive connections: to Assessment and Formative Assessment through AI-mediated evaluation; to Simulation and laboratory learning through virtual experiments. The remaining connections run to Teacher Education through pre-service science-teacher research and professional development; to Educational AI Policy and Ethics through the AI Governance of AI in STEM; and to Philosophy of AI in Education through the epistemology/ontology of experimentation. The AI Literacy and Reducing AI Misuse concepts are essential for the responsible-use dimension, and Higher Education and K-12 capture the levels at which chemistry AI research occurs.

Implications for chemistry instructors

- **Leverage AI for experimental design, not just answers.** Yim & Lui show students designing lab manuals with AI and validating them hands-on builds confidence and critical-thinking while shifting staff from demonstration to guidance — a model for lab courses.
- **Demand evaluative engagement with AI output.** Systematic evidence finds LLMs weak on rigorous quantitative chemistry, spatial reasoning (NMR), and overconfident — make interrogating and cross-checking AI against chemical principles an explicit learning goal.
- **Assign distinct, achievement-sensitive AI roles.** Instructor–AI role research finds the human instructor as adaptive expert and ChatGPT as a personalized tool shifting from Patient tutor (low achievers) to Coach to Intellectual Sparring Partner (high achievers) — differentiate support by student level.
- **Combine AI with structured, contextual pedagogy.** 7E + PhET + ChatGPT outperformed inquiry-only and conventional teaching, showing AI works best inside an established instructional model.
- **Be alert to epistemic drift and over-reliance.** Philosophy-of-experimentation research and UNESCO guidance warn that opaque AI can detach inquiry from causal understanding — preserve human-reasoning-prioritizing assessment and student agency.
- **Grade open-ended handwritten work selectively.** In a 296-student handwritten general-chemistry final, a Multimodal AI LLM graded textual answers and chemical-reaction equations reliably but drawing and graphing worse than random (background grids visually distract AI vision); pairing an IRT-based risk filter and deferring graphical items to humans made automation defensible for summative use (Assisting the grading of a handwritten general chemistry exam with artificial intelligence).

Common Misconceptions

“A model that can explain chemistry can therefore do chemistry.” The capabilities come apart in exactly the places a chemistry course tests. Systematic evidence shows LLMs can define basic terms while performing **poorly on rigorous quantitative tasks**, struggling with **spatial reasoning such as NMR interpretation**, and showing **overconfidence** on both. A tutor built on fluent verbal explanation will appear strong precisely where the subject is easiest and fail where it is hardest, while sounding equally assured throughout.

“Fluency of explanation is a reasonable proxy for reliability.” It is a proxy for fluency. The overconfidence finding is the operative one for teaching: a system that states an incorrect spatial or quantitative answer with the same register as a correct one removes the learner’s cue to check, which is why verification has to be built into the task rather than inferred from tone.

“Adding AI to an existing inquiry lesson cannot hurt.” It can, and the comparison that shows a benefit is narrower than it sounds. Abdikayumova and Madybekova combined the **7E instructional model** with PhET simulations *and* ChatGPT tutoring for Grade 10 chemistry and found significantly higher achievement and engagement than inquiry-only or conventional instruction. The treatment is the structured combination — an

instructional model plus simulations plus tutoring — not the chatbot on its own, and a chatbot added to unstructured inquiry is untested by that result.

“Chemistry is a subject where the answer is checkable, so AI errors are harmless.” Checkable answers are how wrong reasoning passes unnoticed: a student who receives a correct value from a model that reasoned badly has no way to detect the deficiency, and the assessment records success. In a quantitative discipline the verifiable endpoint is the weakest available evidence of understanding.

Connected Concepts

- STEM Education
- Physics Education
- AIEd in the Disciplines
- Generative AI
- AI Literacy
- Assessment
- Formative Assessment
- Feedback
- Human AI Collaboration
- Self-Regulated Learning
- Constructivism
- Personalized Learning
- Simulation
- Critical Thinking
- Reducing AI Misuse
- Cognitive Offloading
- Ethics
- Educational AI Policy
- Teacher Education
- Philosophy of AI in Education
- Higher Education
- K-12
- Learner Agency
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools

Connected Articles

- Artificial intelligence in science and chemistry education: A systematic review — Systematic review of AI in science/chemistry education
- Translating UNESCO artificial intelligence guidelines to chemical education and its intersection with sustainable development goals — Translating UNESCO AI guidelines to chemical education

- Using context-based and AI-enhanced approaches to improve student engagement and achievement in secondary chemistry education — Context-based + AI in secondary chemistry (7E)
- Supporting undergraduate students' learning in practical chemistry courses through AI-supported experimental design — AI-supported experimental design in practical chemistry
- Instructor and AI roles in the chemistry classroom: Future science teachers' perceptions in a ChatGPT-enhanced formative assessment — Instructor and AI roles in ChatGPT-enhanced formative assessment
- Reimagining the philosophy of experimentation in chemistry education: Embracing AI as a tool for scientific inquiry — Philosophy of experimentation in chemistry with AI
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence

Biology Education

> **Biology Education** — the study of how students learn biology and how to teach it more effectively, spanning AI-assisted laboratory instruction, AI literacy embedded in biology curricula, critical thinking in the AI era, and the use of specialized tools (species identification, bioimaging, predictive modeling) in biological education. Biology's distinctive demands — large bodies of specialized terminology, visual-spatial and systems thinking, hands-on laboratory and fieldwork, and increasingly computational 'omics methods — make it a rich context for examining both the promise and the risks of AI in STEM learning.

Questions to Consider

- Biology makes distinctive demands on learners — specialized terminology, visual-spatial and systems thinking, hands-on lab work. Before reading, how do you think these features change what AI can genuinely help with in biology versus what it might undermine?
- A virtual lab teaching assistant study found human TAs more accurate and effective than ChatGPT, yet students preferred the AI response 40% of the time and could only detect AI output 45% of the time. Why might students prefer a less accurate AI answer — and what does that say about the 'safety net' needed in lab teaching?
- AI has revolutionized biology research (AlphaFold, computational biology) while its adoption in biology education has been cautious, amid concerns about cheating and erosion of critical thinking. Why do you think the same tools that power scientific discovery are treated with such caution in the classroom?
- One study embedded Machine Learning concepts into a high-school biology course and found the biology context actually supported AI learning — evidence for embedding AI literacy in the curriculum rather than making it an add-on. Where in a biology course would AI concepts naturally arise?
- Researchers argue that as AI reshapes biological research, critical thinking — skepticism, contextual understanding, ethical reasoning — must be deliberately cultivated with human oversight. If AI can now identify species, interpret images, and predict outcomes, what intellectual work is left that students must learn to do themselves?

Introduction

Biology education research on AI clusters around a tension: AI has revolutionized biology *research* (AlphaFold, 'omics, computational biology), yet its adoption in biology *education* has been cautious amid concerns about generative-AI cheating, misinformation, and erosion of critical thinking. The knowledge base's biology articles collectively examine how AI tools function as laboratory teaching assistants, how AI literacy can be embedded in biology courses, how critical thinking must be protected in the AI era, and how specialized AI tools support fieldwork and species identification.

Key research themes

AI in the biology laboratory. Doğru & Faulconer tested ChatGPT as a **virtual teaching assistant** in an undergraduate biology lab, finding human TAs more accurate and more effective, though students preferred the AI response 40% of the time and detected AI output only 45% of the time — highlighting both the burden-lifting potential and the safety-need for a "safety net" against incorrect lab information. This parallels the chemistry strand's AI-supported experimental design and philosophy of experimentation — shared concern for AI in hands-on science labs.

AI literacy embedded in biology curricula. Zha et al. integrated machine-learning and neural-network concepts into a high-school honors biology course, finding significant gains in AI knowledge and that biology context supported AI learning — evidence for embedding AI literacy in STEM Education rather than relegating it to extracurriculars. **Elizondo-García et al.** used ChatGPT within **challenge-based learning** in biology and math courses, finding students valued immediacy but worried about veracity, teacher replacement, and skill erosion — calling for updated academic-integrity codes and AI-use ethics.

Critical thinking in the AI era. Papaneophytou & Nicolaou argue that as AI shapes biological research, **critical thinking** — skepticism, contextual understanding, and ethical reasoning — must be deliberately cultivated, with human oversight remaining indispensable to validate AI outputs and prevent bias. This connects to the knowledge base-wide Reducing AI Misuse and Cognitive Offloading concerns.

Socratic AI argumentation practice in teacher preparation. A quasi-experiment with 124 prospective biology teachers found a ChatGPT-4 Socratic tutor on socio-scientific issues raised argumentation quality over offline peer discussion (adjusted 3.91 vs. 3.21, $F(1,121) = 14.23$, $p < .001$), with the largest gains in rebuttal and counter-evidence skills (Ergasheva et al., 2026).

Specialized AI tools and the broader review. Cotton & Cotton review the full landscape of AI tools in biological education, including **iNaturalist and Google Lens** for species identification, bioimaging and machine-learning tools, assistive technologies, and predictive modeling of at-risk students — alongside the integrity, assessment-design, misinformation, and critical-thinking challenges of generative AI. - **LLMs answer better than they mark.** Across 1,344 answers to 336 open-ended biological-statistics questions spanning Bloom's levels, Nguyen et al. (2026) found three models rated above a 20-student group, yet a single Large Language Models (LLMs) marker agreed with an experienced instructor so poorly that no student reached fair agreement.

How much of the grade is actually exposed. Weighting each graded category of one department's 38 core-course syllabi by instructor-rated vulnerability put 33% of course points at high exposure and 81% at least somewhat exposed - 41% and 100% online - with only in-person proctored exams rated minimally vulnerable (Chan et al., 2026).

Connections to related concepts

Biology education sits within the broader STEM Education domain and shares the laboratory-practice and specialized-terminology concerns of Chemistry Education and Physics Education. Distinctive connections: to Critical Thinking through the AI-era emphasis on skepticism and oversight; to AI Literacy through embedding AI concepts in biology courses; to Human AI Collaboration through virtual lab assistants and challenge-based learning; to Academic Integrity and Ethics through generative-AI misuse and policy; and to

Assessment through AI-mediated evaluation. The Higher Education and K-12 concepts capture the levels at which biology AI research occurs, and Intelligent Tutoring and Simulation connect to AI-assisted lab and teaching support.

Implications for biology instructors

- **Keep a human "safety net" around AI lab assistants.** Doğru & Faulconer find human TAs more accurate and effective than ChatGPT, yet students preferred AI 40% of the time and detected AI output only 45% — verify and annotate AI lab information, and never rely on it unmoderated for safety-critical content.
- **Embed AI literacy in the biology curriculum, not as an add-on.** Zha et al. show biology context supports AI learning; integrate ML/neural-network concepts into coursework where they naturally arise.
- **Deliberately cultivate critical thinking in the AI era.** Papaneophytou & Nicolaou argue skepticism, contextual understanding, and ethical reasoning must be taught explicitly, with human oversight to validate AI outputs and prevent bias.
- **Teach responsible use alongside challenge-based learning.** CBL studies find students value immediacy but worry about veracity and skill erosion — update academic-integrity codes and AI-use ethics in parallel with adoption.
- **Survey the specialized tool landscape.** Cotton & Cotton map tools (iNaturalist, Google Lens, bioimaging, at-risk prediction) that instructors can deploy for fieldwork, species ID, and student support — choose purpose-built tools over general chatbots where they fit.

Common Misconceptions

- **"Students cannot tell AI from a human teaching assistant."** A virtual lab teaching assistant study found **human TAs more accurate and effective than ChatGPT**, yet students **preferred the AI response 40% of the time** and could only **detect AI output 45% of the time**. Detection was close to a coin flip and preference ran toward the less accurate source, so satisfaction data cannot stand in for quality here.
- **"Preference indicates quality."** The same study separates them directly: the preferred output was the worse one. Any evaluation of a biology AI tool that reports student satisfaction without an accuracy measure is reporting the wrong quantity.
- **"AI literacy must be taught as a separate subject."** Embedding machine-learning concepts **into a high-school biology course** found the biology context **supported** AI learning — evidence for embedding AI literacy in the curriculum rather than bolting on a standalone unit. The discipline gave the concepts something to attach to.

Connected Concepts

- STEM Education
- Chemistry Education
- Physics Education

- AIEd in the Disciplines
- Generative AI
- AI Literacy
- Critical Thinking
- Human AI Collaboration
- Academic Integrity
- Ethics
- Intelligent Tutoring
- Simulation
- Feedback
- Assessment
- Reducing AI Misuse
- Cognitive Offloading
- Higher Education
- K-12
- Educational AI Policy

Connected Articles

- Evaluating Large Language Model Performance on Open-Ended Questions: Answering and Marking Capabilities — Evaluating Large Language Model Performance on Open-Ended Questions: Answering and Marking Capabilities
- Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI — Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI
- ChatGPT as a virtual laboratory teaching assistant in undergraduate biology — ChatGPT as a virtual lab teaching assistant
- Beyond ChatGPT: A review of the use of AI tools in biological education — Review of AI tools in biological education
- Promoting critical thinking in biological sciences in the era of artificial intelligence: The role of higher education — Critical thinking in biological sciences and AI
- Who is solving the challenge? The use of ChatGPT in mathematics and biology courses using challenge-based learning — ChatGPT in challenge-based biology/math courses
- A case study of integrating AI literacy education in a biology class — AI literacy education in a biology class
- Enhancing PISA-aligned argumentation skills of prospective biology teachers through generative artificial intelligence — Enhancing PISA-aligned argumentation skills of prospective biology teachers through generative artificial intelligence

CS Education

> **CS Education** — computer science education is the most-researched STEM subfield in the knowledge base, benefiting from natural alignment between AI tools and programming tasks. Code generation, debugging assistance, and automated code review are its primary AI applications. Because students learn to build the very tools they use, CS education sits at the center of debates about AI literacy, curriculum redesign, agentic software engineering, and the boundary between genuine learning and over-reliance.

Questions to Consider

- If AI can now write code that passes real programming exams, what should students still learn to do by hand — and what should the curriculum stop teaching?
- Research found that higher trust in an AI coding assistant predicted WORSE ability to tell correct from misleading suggestions. How is trust different from appropriate reliance, and how would you teach the latter?
- In student-AI co-programming, nearly 80% of interactions relied on non-learning strategies like outsourcing answers, and only about 1 in 9 showed deep epistemic engagement. Why does genuine learning rarely happen by default when AI is available?
- A Learning by Teaching agent that was too competent undermined students' debugging practice. Would you deliberately make an AI tutor fallible — and if so, how?
- As AI automates implementation, curricula are shifting from writing code to verifying and directing AI-generated artifacts. What new competencies does that demand, and what might get lost in the shift?
- Students are building the very tools they use. How does being both builder and user of AI change what they should learn about its limits — and its ethics?

Introduction

AI in CS education

- **Code generation and completion:** CS1 code review, DURA for CS2, and NL programming mistakes examine how students use AI for code generation and what they learn from it.
- **Conversational agents for novices (scoping review):** Barzanji & Loitsch (2025) map 23 studies (2019–June 2024) of conversational agents for novice programmers, documenting a shift from rule-based chatbots to Large Language Models (LLMs)- and RAG (Retrieval-Augmented Generation)-based agents (with retrieval-augmented generation reducing hallucination) and personalized tutoring support (e.g., InfoBot, ProbSol-Bot, Lint Bot, Profe Alex). Notably, only 4 of 23 studies ground design in learning theory, and 17 of 23 prototypes are English-only despite most research originating outside English-speaking countries — flagging weak pedagogical grounding and an inclusivity gap for future CA design in introductory programming.

- **Debugging support:** Debugging tools, human-AI debugging collaboration, and dyadic pair-programming modeling leverage AI for error identification and repair.
- **A live course deployment found hint length, not model choice, to be the actionable variable.** Three consecutive deployments in an introductory web development course (o3-mini, GPT-5-mini and GPT-5.5 across 79,438, 83,374 and 10,420 logged submissions) associated hints with better immediate outcomes in several comparisons. Longer messages predicted worse next-submission correctness, more attempts and slower resubmission, and students who had received hints on earlier project steps solved the final step less often, at 95.6% against 98.1% (Mihaylova et al., 2026).
- **A browser-resident tool-augmented tutor is the architecture the field is converging on.** A tool-augmented SLM design pairs a small fine-tuned planner (1B–7B) with four deterministic tools — code executor, test runner, documentation retriever, Knowledge Tracing module — behind a four-tier escalation policy (tools first, on-device SLM, consent-gated cloud LLM, instructor), shifting pedagogical control from the model to the auditable policy; a preliminary ~150M completion model reaches 10.97% HumanEval pass@1, above several 100M–150M code baselines (Suvernev et al. (2026)).
- **A small fine-tuned tutor can out-scaffold a larger general model.** Fine-tuning Qwen2.5-Coder-7B-Instruct on 1,213 synthetic tutoring dialogues cut premature solution disclosure from 7.43% to 1.88% of tutor turns and raised stepwise scaffolding and debugging-question quality above GPT-4o's, though reliable pedagogical plan generation stayed the open problem (Kopytskyi et al. (2026)).
- **Automated assessment:** Linux Bash grading, a large-scale 18-model grading comparison, and LLM intervention review evaluate automated code assessment. The security of that workflow is a separate question: Humble (2026) red-teamed a routine AI grading task and found that instructions hidden inside a submitted file raised a failing essay's grade with no visible warning, in 9 of 9 iterations for one strategy and 17 of 18 for another — evidence that grader robustness belongs on the Assessment Validity checklist alongside accuracy.
- **A one-sentence grader prompt can collapse an LLM, and fine-tuning repairs it.** Habibullah et al. (2026) graded a practical computer vision exam (570 dual-graded students) under 171 configurations and a machine learning exam (1,038 students) under 162 more. A short "strict grader" preamble drove 14 of 17 open-weight models out of the graded band (MAE ≥ 8), with three stopping grading altogether, and the damage traced to two credit-withholding policy sentences whose direction did not transfer to the second exam (seven models improved). One LoRA adapter over roughly 3,900 pooled graded examples brought five small open models to parity with a human grader.
- **AI-generated learning media:** Generated Animated Traces show that AI-generated visualizations can aid immediate learning but must be personalized — mid-engagement students experienced a performance decrement consistent with the expertise-reversal effect.
- **GenAI analogy critique as an instructional asset:** Bernstein & Sibia (2026) ground GenAI analogy reception in CS2: ten students who had already completed CS2 audited GenAI-generated analogies for linked lists and recursion and rejected mappings that failed structural

correspondence — an island-route analogy that mapped to a circular rather than a singly linked list, or a badminton rally offered for recursion despite having no guaranteed shrinking input, with one student proposing golf instead. The work argues that analogy critique is itself a check on concept understanding, making flawed AI analogies a usable instructional asset rather than a hazard to filter out, and recommends assigning them as objects to inspect and repair.

- **Misconception modeling:** a taxonomy of conditionals/loops misconceptions gives automated systems a precise vocabulary for diagnosing novice errors.
- **Model-generated strategic misconceptions:** Miličević et al. (2026) built SocraticTrap-CS around 35 concepts from the ACM/IEEE CS2023 curriculum — algorithms, programming languages, databases, networks and operating systems — and asked seven open-weight models for a fluent, authoritative explanation resting on a subtle error. Six of the seven produced an expert-confirmed strategic misconception for 91% or more of prompted concepts (221 of 241 segments, 91.7%), with no significant differences between CS domains; conceptual errors dominated (66.5% conceptual vs. 33.5% factual, and none purely logical), and both persuasiveness and error type varied by domain. The authors therefore recommend domain-sensitive countermeasures — reasoning-focused checks in programming-heavy courses, cross-referencing against protocol specifications in networking — and evaluation of Automated Question Generation and AI-authored explanations on pedagogical trustworthiness rather than correctness alone.
- **Authentic Assessment performance:** Lepp & Kaimre (2026) show 2026 GenAI systems outscore the average student cohort on authentic introductory OOP assessments and frequently earn full marks on longer programming tasks, yet still struggle with interfaces, abstract classes, inheritance, and image-based questions — recurring error patterns instructors can exploit when designing assessments. A CS1 longitudinal study reinforces the capability side of that finding: Ye et al. (2026) measured frontier models at 98.93-99.99% on the labs against 76.37-88.03% for student submissions.
- **Predictive modeling for at-risk support:** Zhang, Jeffries & Koprinska (2025) show that intrinsically interpretable decision trees trained on content-interaction log features accurately predict module-level progress in large-scale online programming courses (85–91% accuracy across four K-12 courses) and flag “No submission” dropout outcomes, giving educators a 7–8 day window to intervene with struggling and disengaged Learners before module deadlines — complementing the automated-grading and attrition-prediction work above.
- **Retrieval-augmented support for theoretical CS fits asynchronous study only.** AlgoRAG answered all 179 instructor-authored exam questions within a 240-second timeout at a mean 38.0 seconds each, and its BLEU-4 of 0.0000 across the set is a property of n-gram matching on mathematical proofs rather than a system failure (Adhikari (2026)).
- **Adoption tracks the assignment, not the subfield.** Across seven assignments and 211 students, Nizamani et al. (2026) measured LLM use from 89.6% in algorithms to 15.2% in software engineering, attributing the spread to assignment complexity, verifiability and scaffolding rather than to the subject itself.
- **Feedback can be staged so the diagnosis stays hidden.** Riazi & Rooshenas (2026) separate an artifact-grounded diagnosis of a student’s database schema from the workflow that releases it,

with educators authoring the stages; across 383 episodes, 71.1% of feedback reached its target level.

Programming pedagogy: from blocks to embodied, game-based learning

Programming education spans introductory block-based programming to advanced software development, and increasingly grounds abstract code in concrete, observable outcomes.

- **Block-based visual programming:** environments like Scratch and Blockly let beginners snap together graphical blocks rather than type text, eliminating syntax errors and making program structure visible — especially valuable for younger learners and for controlling educational robots. In the AI era they are increasingly combined with conversational AI agents (e.g., Micro:bit + MakeCode in teacher training, small-language-model tutors).
- **Embodied block programming:** RoboBlockly Studio combines block-based programming with a conversational AI teaching agent and embodied robot execution, creating an iterative authoring–running–observing–revising loop that preserves learner Learner Agency.
- **Natural-language robot control:** EduSim-LLM lets beginners control simulated robots through natural-language instructions, lowering the barrier to robot programming without requiring low-level code expertise.
- **Robotics and computational thinking:** Valls i Pou links computational thinking to educational robotics in secondary STEAM curricula, and teacher-training research argues robotics and ML activities should be embedded in Teacher Education.
- **Game-based and gamified learning:** A systematic review compares game-based learning (suited to informal settings) and gamification (suited to formal classrooms) in robotics education, which emphasizes introductory programming and modular kits.
- **Project-based robotics:** Bots and Blocks teaches robotics programming through an agile, semester-spanning project, addressing the theory-practice gap in higher-ed.
- **LLM impact on learning outcomes:** Jošt et al. (2024) and a meta-analysis of GenAI and programming learning examine whether AI-assisted tools help or undermine programming achievement.

Curriculum transformation in the AI era

The question “what should students still learn by hand?” now reshapes computing programs.

- **From implementation to verification:** Reshaping Undergraduate CS Education argues that as GenAI automates implementation-level programming, debugging, and testing, curricula must shift toward *understanding and verifying AI-generated artifacts*, preserving system design, abstraction, and critical evaluation while de-emphasizing low-level implementation details. This aligns with AI Literacy frameworks that prize evaluation over generation.
- **Agentic software engineering as a discipline:** ASE-26 formalizes directing agents rather than writing code — teaching auditability, context engineering, verification, multi-agent workflows, and AgentOps — and positions agentic AI competence as a structured, scaffolded curriculum rather than syntax mastery.

- **From production to judgment: comprehension debt and AASEE.** Mahmoud (2026) argues the field should shift from a production-centered to a judgment-centered model, and extends comprehension debt — the deferred learning and maintenance cost when AI-assisted production outpaces a learner's ability to explain, test, modify, and justify the software — into an Assessment lens, grounded in 621 reflective diaries from 207 students. The review refines the AASEE framework into five non-linear integration levels crossed by four evidence obligations — explain, verify, modify, and account — and reports a conditional evidence base: a STEM meta-analysis with extreme heterogeneity ($I^2 = 96.32\%$) loses its pooled benefit once publication bias is corrected, and syntheses of 76, 72, and 64 studies show short-term efficiency gains that do not transfer to unaided performance.
- **New pedagogies and assessment models:** Test-Driven AI-Assisted Learning replaces lectures with self-directed AI-assisted study gated by weekly closed-book tests, preserving individual accountability while AI agents scale material production and marking under human oversight.
- **Oral examinations as the accountability mechanism.** A project-based AI Engineering program ran second-semester students through seven two-week sprints with AI embedded in requirements, architecture, coding and testing, and made individual oral examinations mandatory after three runs showed artifacts alone no longer evidenced understanding; average missing ECTS fell from 25% to 3% (Rausch (2026)).
- **Teach the model's mechanics offline.** A practitioner resource suite teaches the full LLM training → generation pipeline unplugged — hand-tallied n-gram grids and dice-based sampling, no programming or mathematics assumed — and reports delivery to roughly 400 participants, with engagement beginning only at the generation stage (Swift (2026)).
- **What predicts Vibe Coding success — and what to keep teaching:** A preregistered CHI 2026 study (N=100) of pure "no-code" vibe-coding found that both computer-science achievement ($r = .39$) and written-communication proficiency ($r = .29$) independently predicted performance, with CS achievement remaining significant even after controlling for domain-general cognitive ability and contributing roughly twice the unique variance of writing skill. Because the environment hid generated code, CS knowledge could only help indirectly (problem decomposition, algorithmic thinking) — making the CS estimate a *lower bound* for AI-assisted workflows that also permit editing. The authors argue curricula should weigh written communication alongside CS fundamentals, rather than treating vibe coding as syntax mastery made obsolete.

AI literacy, agency, and the risk of over-reliance

Because programming is where AI assistance is most powerful, it is also where the failure modes are most visible.

- **Trust ≠ appropriate reliance:** Trust and reliance on AI (Pitts et al.) find that higher trust in an AI assistant predicted *worse* discrimination between correct and misleading suggestions during Python Problem Solving — moderated by AI Literacy and need for cognition. Calibration, not confidence, is the goal.

- **Epistemic AI literacy:** Wu (2026) shows that in student-AI co-programming, 78.8% of interactions relied on non-mastery-oriented aims and unreliable strategies (outsourcing, verification-seeking), with only 11.1% showing high epistemic engagement — genuine learning rarely emerges without deliberate design support.
- **AI inquiries are narrow and generation-patterned.** Classifying 830 CS2 prompts against the Graesser taxonomy, Amoozadeh and Alipour (2026) found assertion, verification, and instrumental prompts dominated both sessions, and that first-generation students asked fewer questions and leaned on verification while continuing-generation peers used the AI as an active problem-solving partner.
- **Structural interventions against copy-paste over-reliance:** Soft barriers for copying in AI-assisted programming evaluate lightweight design interventions (e.g., mechanisms that discourage blind copy-paste of AI output) and find they can reduce over-reliance without blocking AI assistance — evidence that the over-reliance risk in CS education is amenable to instructional-design fixes, not just learner-education or bans.
- **Teachable agents and productive practice:** Learning-by-teaching with ChatGPT improved knowledge gains and code quality but undermined error-correction practice because the agent is too competent — a design lesson: make agents *deliberately fallible* so debugging is preserved.
- **Assistance governance:** a scoping review of 90 systems introduces the **PEA framework** (Policy, Enforcement, Authority) for bounding and controlling LLM assistance — a comparative vocabulary for designing Scaffolding that limits over-reliance.
- **Governance fit, not strictness.** Dickey (2026) proposes a six-dimension governance profile — pedagogical grounding, AI instructional authority, human accountability, learner agency, context boundaries, and evaluation visibility — and shows across seven in-house tools and four published programming systems that the same model can distribute authority and accountability very differently; what predicts responsible scale is governance *fit* to the instructional function, not how strict the tool is.
- **Behavioral context for adaptive AI tutoring:** Barron et al. (2026) present **TutorTrace**, a dataset and pipeline that makes learners' behavioral context computable in real time from IDE telemetry in AI-assisted Python courses (N=480). It derives a taxonomy of activity before, between, and across AI queries, and can classify whether an upcoming query reflects guided or dependent Help-Seeking (AUROC=.717) and predict imminent queries (AUROC=.726); behavior-aware prompts reduced no-independent-work query intervals from 50.0% to 20.7% in a preliminary evaluation. This shows how behavioral telemetry can make AI programming tutors adaptive to learners' actual effort, not just their explicit requests.
- **The duality of building what you use:** CS students' unique position creates both meta-cognitive awareness of AI limitations and real risk of Over-Reliance on AI-generated code. Code review interviews and critical engagement studies address this tension directly.
- **Agentic coding and comprehension in team PBL:** Tanaka et al. (2026) introduced Spec-Driven Development with AI agents into an undergraduate software-engineering project course and found that implementation throughput (added LOC) rose across 2022-2025 while heavy AI use

coincided with code-comprehension dips that only recovered after one-on-one instructor checks - direct evidence that throughput gains do not guarantee understanding, and that over-reliance in AI-assisted coding is amenable to instructional monitoring.

- **Continuance, not adoption, is where GenAI's value is decided.** A PRISMA review of 45 studies (2023–2025) finds improved code generation and debugging alongside unchanged conceptual depth, and argues that continued use depends on calibrated Trust, verification skill, and institutional guidance rather than perceived usefulness (Yalwa et al., 2026).

Equity, culture, and who gets into computing

- **Broadening participation:** SuaCode documents motivations for smartphone-based coding among African students (fewer than 1% of secondary-school leavers have fundamental coding skills), informing accessible AI-supported MOOCs for low-resource contexts.
- **Neurodivergence and collaboration:** Neurodivergent computing students report discomfort with ambiguous collaboration structures; structured assignments, smaller consistent teams, and explicit roles improve Accessibility — design lessons for the AI tools entering computing classrooms.
- **Culture shapes perceived ethics:** Canadian vs. South Korean computing students judged identical AI-assisted coding practices differently despite functionally identical policies — policy harmonization does not produce perception harmonization, an Academic Integrity and Equity concern.
- **Collaboration transparency:** Graf et al. find that partners' misaligned beliefs about each other's AI use predict lower project scores, especially for lower-performing students — transparency mechanisms (disclosures, shared logs) may be needed in collaborative programming.

Ethics education and the workforce

- **Ethics-to-behavior gap:** the "Cost-of-Ethics Crisis" shows CS students, despite contemporary ethics education, prioritize compensation, location, and culture over ethical concerns in job searches — a critical gap in how ethics instruction transfers to behavior.
- **Workforce reshaping:** a systematic review of U.S. gray literature frames the "Dual Train Problem" — rapid AI change racing institutional adaptation — and urges durable AI competencies, ethics/governance, and skill-based credentials aligned with emerging roles (e.g., Prompt Engineering, AI auditing, AI policy).

Connections

CS education connects to Computational Thinking, STEM Education, Automated Grading, Prompt Engineering, AI Literacy, Agentic AI, Curriculum Design, Human AI Collaboration, Higher Education, K-12, and Workplace Learning. Its closest applied neighbour is Information Technology Education: CS education takes the program and the algorithm as its object, whereas IT education takes the deployed organizational system and the practitioner's judgment about it — which is why the two fields debate different AI harms, whether code generation erodes programming skill against whether AI troubleshooting erodes diagnostic skill, and ask different questions of their graduates, whether they can build a system

against whether they can govern the systems they administer. It is the domain where AIED tools are both used and built, making it a testbed for Intelligent Tutoring, Robots in Education, Collaborative Learning, Game-Based Learning, and the risks of Over-Reliance.

A 72-study synthesis and the VIE framework. Kumar, Wongsirichot and Nanthaamornphong (2026) reviewed the empirical literature on generative AI in computing and programming education (January 2022 – April 2026, 72 studies, 33 venues) and foreground exactly the structural feature that makes the discipline distinctive: the AI generates the assessable artifact itself, so using the tool, learning the skill and being assessed collapse into one keystroke. Their synthesis of 14 themes finds the field's most replicated effect — short-term efficiency and completion gains (36 studies) — is also its most misleading: those gains do not transfer to unaided performance (21 studies), and prior knowledge moderates whether assistance becomes durable skill or a crutch. Detection research is thin (3 studies) while course redesign is comparatively well evidenced (25 studies), and the review consolidates the corpus into three interdependent design requirements — Verification, Implementation and Equity — where critical engagement with AI output must be a graded, observable component of student work rather than an aspiration left to student discretion (Scaffolding, Assessment Validity).

Implications for computing instructors

- **Design assessments AI cannot coast through.** Exploit GenAI's recurring failure patterns (interfaces, abstract classes, inheritance, image-based tasks) instead of banning tools outright — GenAI systems still struggle there.
- **Autogradable take-home assignments offered no completion resistance.** Kaltchenko & Tiwana (2026) ran 50 ChatGPT sessions per Qiskit assignment and all 150 artifacts executed and passed the grader, because personalization varied parameters rather than task structure; the remedy is direct assessment of understanding — supervised modification or oral defense.
- **Calibrate trust, don't just build it.** Trust-reliance research shows higher trust predicted *worse* discrimination of misleading AI suggestions; teach verification and critical evaluation, moderated by AI literacy and need for cognition.
- **Keep debugging and productive struggle alive.** Choose tools or deliberately fallible agents (learning-by-teaching) that preserve error-correction practice, and personalize AI-generated media to avoid expertise-reversal effects (expertise-reversal).
- **Govern AI assistance explicitly.** Define policy, enforcement, and authority for LLM support (PEA) rather than leaving boundaries implicit.
- **Shift curricula toward verification and agent direction.** As GenAI automates implementation, teach understanding/verifying AI artifacts (reshape curricula) and structured agentic-software-engineering skills (ASE-26).
- **Structure collaboration for all learners.** Smaller consistent teams, explicit roles, and AI-use transparency support neurodivergent students and fair collaboration, especially where misaligned AI-use beliefs lower project scores.
- **LLM-adaptive explanations of programming errors (2026):** A crowdsourced study (N=103) found LLM-rewritten error messages improve readability, but objective debugging performance

depends on matching explanation style (pragmatic vs contingent) to programmer skill — a scaffolding insight for AI-assisted programming education (Beyond the Traceback: Using LLMs for Adaptive Explanations of Programming Errors).

- **Oversight is about fitness, not correctness (2026):** Coding 962 student-AI turns from 145 first-year software engineering students, Shakiba and Chaffey (2026) found 74.4% of interventions named fitness problems against 16.9% naming correctness, and 51.0% of responses modified the output rather than the prompt.
- **"Agreement on code means the grader reads the code."** The benchmark's two instructor raters agreed at **0.815** on C++ answers: **four** models exceeded them with an interval above 100% of that ceiling and **fourteen** fell below, down to **33%**. On the same code task, a note asking for full marks raised Qwen3 235B's grade by **83.2% of the scale**, and seven models across the battery credited blank answers, so a grading pass over student code needs failure tests beside the agreement number.
- **"The effect is the same at every stage of a course."** It grew with the work: on **60 complete Java programs** graded on a **14-level** rubric, the label's effect was **2.8 times** its short-answer size on GPT-4.1-mini and **2.4 times** on Qwen, though only **0.4 times** on Gemini. Task and rubric are part of what the effect measures, so a size validated on short answers does not transfer to programs.

Common Misconceptions

- **"Students pair-programming with AI are learning to program."** In student-AI co-programming, **nearly 80% of interactions relied on non-learning strategies like outsourcing answers**, and only **about 1 in 9 showed deep epistemic** engagement. The dominant pattern is transacting for output.
- **"Conversational agents for novices are grounded in learning theory." Only 4 of 23 studies ground design in learning theory**, so most of the evidence base documents what a system did without a theory of why it should work.
- **"The tooling literature reflects the field's global distribution." 17 of 23 prototypes are English-only despite most research originating outside** English-speaking contexts. The prototypes serve a narrower population than the research does.

Connected Concepts

- Computational Thinking
- Vibe Coding
- STEM Education
- Information Technology Education
- Automated Assessment
- Prompt Engineering
- AI Literacy
- Agentic AI

- Curriculum Design
- Human AI Collaboration
- Higher Education
- K-12
- Robots in Education
- Game-Based Learning
- Generative AI
- Intelligent Tutoring
- Cognitive Offloading
- Teacher Education
- Workplace Learning
- AI in Education
- Collaborative Learning
- Prior Knowledge
- Scaffolding
- Assessment Validity

Connected Articles

- It’s Complicated: Factors Influencing the Effectiveness of LLM-Generated Feedback in a Live Programming Course — Three deployments, three models, 173k submissions: what hint behaviour looked like in a real course
- Generative AI in computing education: A systematic review and a framework for responsible integration — Systematic review of 72 studies: efficiency gains that do not transfer, and the VIE framework
- Computer Science Achievement and Writing Skills Predict Vibe Coding Proficiency — CS achievement and writing skills predict vibe-coding proficiency (CHI 2026)
- TutorTrace: A dataset and taxonomy for classifying learner behavioral states during AI-assisted programming education
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — CS1 code review of AI-generated code
- Demystify, Use, Reflect, Assess (DURA): An Experience Report on LLM Integration in CS2 — DURA: LLM assistants for CS2
- Reshaping Undergraduate Computer Science Education in the Generative AI Era — reshaping undergraduate CS curricula for GenAI
- ASE-26: A Curriculum for Agentic Software Engineering as a Discipline — ASE-26 agentic-software-engineering curriculum
- Test-Driven, AI-Assisted Learning: Replacing Lectures with Weekly Closed-Book Tests — Test-Driven AI-Assisted Learning

- Revisiting the Performance of Generative Artificial Intelligence on Introductory Object-Oriented Programming Assessments: Insights from 2026 — GenAI performance on authentic introductory OOP assessments (Lepp & Kaimre 2026)
- Trust and Reliance on AI in Education: AI Literacy and Need for Cognition as Moderators — trust vs. appropriate reliance during Python problem-solving
- Constructing Epistemic AI Literacy: Detecting Epistemic Aims and Processes in Student-AI Co-Programming — epistemic AI literacy in student-AI co-programming
- Learning-by-Teaching with ChatGPT: The Effect of a Teachable ChatGPT Agent on Programming Education — learning-by-teaching with ChatGPT
- Exploring the Design Space of LLM-Based Programming Support in CS Education: A Scoping Review through the Lens of Assistance Governance — PEA framework for bounding LLM assistance
- Exploring conversational agents for novice programmers: a scoping review — Scoping review of conversational agents for novice programmers
- DebugTracker: Lightweight Process Evidence for Classroom Debugging — DebugTracker classroom debugging
- A systematic comparison of Large Language Models for automated assignment assessment in programming education: Exploring the importance of architecture and vendor — 18-model automated grading comparison
- AI-Generated Traces for Novice Programmers: Learning Effects and Learner Differences in a Multi-Institutional Study — AI-generated animated traces
- How Students (Mis)understand Conditionals and Loops – A Taxonomy — conditionals/loops misconception taxonomy
- The impact of large language models on programming education and student learning outcomes — LLM impact on programming learning outcomes (Jošt et al.)
- A meta-analysis of the effect of generative AI on productivity and learning in programming — meta-analysis of GenAI and programming learning
- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming — dyadic pair-programming modeling
- To Tab or Not to Tab: Measuring Critical Engagement in AI Code Completion Tools Using Behavioral Signals and Attention Checks — critical engagement with code completion
- "Why SuaCode?": Understanding African Students' Motivations for Taking a Smartphone-Based Online Coding Course — SuaCode smartphone-based coding in Africa
- Did Alice Do Wrong? Cross-Cultural Differences in Student Perceptions of Generative AI Use in University Computing Education — cross-cultural perceptions of AI-assisted coding
- "I can't read your mind": A Study of Neurodivergent Computing Students' Experiences with Collaborative Active Learning — neurodivergent computing students

- Coding, robots, computational concepts, and machine learning using the microbit card and the Maqueen and Nezha kits. A study in initial teacher training — Micro:bit + ML in teacher training
- Computational thinking to enhance educational robotics in secondary school's curriculum — computational thinking and educational robotics
- RoboBlockly Studio: Conversational block programming with embodied robot feedback for computational thinking — RoboBlockly embodied block programming
- EduSim-LLM: An educational platform integrating large language models and robotic simulation for beginners — EduSim-LLM natural-language robot control
- Using LLMs to Detect Growth in Computational Thinking in Introductory Physics — LLM support for computational thinking in physics
- Analysis of Types of Inquiries in Student-AI Interaction: A case study of two CS2 tasks — Analysis of Types of Inquiries in Student-AI Interaction
- ChatGPT Solves All Tested Qiskit Homework Assignments — ChatGPT solves Qiskit homework; autogradable design
- Beyond the Traceback: Using LLMs for Adaptive Explanations of Programming Errors — LLM adaptive explanations of programming errors
- Do Not Copy/Paste: Soft Barriers for Copying in AI-Assisted Programming — Copy-paste resistance in AI-assisted programming
- A Machine Learning Approach for Predicting Student Progress in Online Programming Education
- Practical Implementation Report on Introducing Spec-Driven Development Using AI Agents in Software Development PBL - SDD with AI agents in a software PBL course; throughput vs. comprehension
- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- The Socratic trap: Benchmarking the capacity of large language models to generate strategic misconceptions in computer science education — SocraticTrap-CS: benchmarking models' capacity to generate strategic misconceptions across the CS curriculum
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection red-team of AI-mediated grading: hidden instructions that move the mark undetected
- AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory — AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory
- LLMs Unplugged: Teaching Resources for a ChatGPT World — LLMs Unplugged: Teaching Resources for a ChatGPT World

- Instructional Governance by Design: A Framework for AI in Computing Education — Instructional Governance by Design: A Framework for AI in Computing Education
- Judgment-Centred Software Engineering Education: A Post-Hype Review and Framework for AI-Augmented Learning — A Post-Hype Review and Framework for AI-Augmented Software Engineering Education
- Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams — Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams
- Understanding Student Use of Large Language Models Across Computer Science Subfields — LLM adoption ranged 89.6% in algorithms to 15.2% in software engineering across 211 students, tracking the assignment rather than the subfield
- An Educator-Guided LLM Pedagogical Agent for Scaffolded Feedback in Conceptual Database Design — Educator-authored staged feedback for conceptual database design: hidden diagnosis, controlled disclosure, 71.1% target-level across 383 episodes
- SocraticRepair: Planning-Guided Socratic Tutoring for Program Debugging and Misconception Repair — SocraticRepair: Planning-Guided Socratic Tutoring for Program Debugging and Misconception Repair
- Browser-Sized Agents: Small Language Models and WebLLM for Tool-Augmented AI-Assisted Programming Education — Browser-Sized Agents: Small Language Models and WebLLM for Tool-Augmented AI-Assisted Programming Education
- Beyond Correctness: How Novice Software Engineering Students Exercise Oversight of Generative AI — Beyond Correctness: How Novice Software Engineering Students Exercise Oversight of Generative AI (Shakiba and Chaffey 2026)
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- Learner context changes an LLM grader’s marks on identical work: a within-item ablation on six models — Learner context changes an LLM grader’s marks on identical work, and agreement with the teacher does not register it (Porcaro 2026, Paper VI)
- Sustained use of generative artificial intelligence (GenAI) in programming education: A systematic review of empirical evidence on adoption, learning outcomes, and continuance intention — Sustained Use of Generative Artificial Intelligence (GenAI) in Programming Education: A Systematic Review

Engineering Education

> **Engineering Education** — the study of how students learn engineering and how to teach it effectively, spanning how AI transforms engineering pedagogy, assessment, faculty development, and the engineering workforce. The engineering education articles in this knowledge base cluster around several themes: the figurative language instructors use to make sense of AI, ethical governance of AI use, embodied and multimodal assessment of conceptual understanding, and how AI is reshaping the engineering and computing workforce.

Questions to Consider

- Engineering is a profession where graduates' decisions affect public safety and infrastructure. If students rely on AI to do design and Problem Solving work, what is at stake that wouldn't matter in a purely academic subject?
- Engineering instructors in the same department often hold fundamentally different mental models of AI — some see it as a social 'agent,' others as a technical 'tool.' How might those divergent framings change what students learn to do with AI depending on which instructor they get?
- Hands-on laboratory and embodied learning have long defined engineering education. If AI can simulate or even automate design tasks, does hands-on experience still matter — or is something genuinely lost when practice becomes simulated?
- One line of research assesses engineering understanding by tracking students' gestures alongside their speech, finding that close gesture–speech coupling signals coherent conceptual understanding. What could a student's hands reveal about understanding that their words alone might hide?
- Research finds ethical guidance about AI in engineering is mostly student-facing and compliance-oriented, with weak reciprocal accountability for faculty and institutions. Whose responsibility should the safe use of AI in engineering really be?

Introduction

Engineering education research is distinctive because it sits at the intersection of professional formation and rigorous STEM content. It emphasizes design, problem-solving, hands-on and laboratory learning, teamwork, and preparing graduates for professional practice. Design is also the ground it shares with Design Education, and the two divide it by what can be checked: engineering's assessed object admits calculable artifacts and carries public-safety accountability, while design education's is the studio process behind the artifact — sketch, iteration, critique — the very evidence generative tools can now produce without the process that once generated it. AI raises distinctive questions here: whether hands-on and embodied experience still matters when AI can simulate or automate design tasks; the professional and ethical stakes of AI use (engineers' decisions affect public safety, infrastructure, and Sustainability); and how AI reshapes the competencies graduates need and the workforce they enter.

How AI appears in the knowledge base's engineering education research

- **Faculty understanding and shared language:** Gerhardt et al. analyze the metaphors engineering instructors use to describe AI, finding that most frame it either as a human-like "social being/agent" or as a "technical tool," and that instructors within the same department often hold fundamentally different mental models. Because metaphors both construct and constrain understanding, they argue a shared, accurate language is essential for Educational Development and departmental discussions about AI.
- **Ethics and responsible use:** Osunbunmi et al. systematically review empirical studies of AI in undergraduate engineering education, identifying seven recurring forms of ethical guidance (transparency, accountability, student independence/agency, privacy, Academic Integrity, fairness/equity/bias, beneficence). They find ethical guidance is predominantly student-facing and compliance-oriented, with reciprocal faculty and institutional accountability underdeveloped — a concern heightened by engineering's direct stake in public safety and societal Well-Being.
- **Embodied and Multimodal AI assessment:** Morphew et al. develop a multimodal framework integrating computer-vision gesture tracking with Large Language Models (LLMs) analysis of speech to assess engineering students' conceptual understanding of statistics, showing that gesture adds diagnostic evidence beyond speech and that close gesture–speech coupling signals coherent understanding.
- **Workforce transformation:** Fletcher et al. review U.S. gray literature on AI and the engineering/computing workforce, framing the "Dual Train Problem" (rapid change vs. urgent policy) and recommending durable AI competencies, Ethics and AI Governance, and skill-based credentials for emerging roles.
- **Student adoption and reliance:** Nguyen et al. extend the Technology Acceptance Model with *critical use* to model how engineering/CS students form intentions to use GenAI and how that intention predicts reliance across understanding, assessment, programming, and engineering-project tasks — finding moderate, appropriate reliance and heavy use for understanding-related tasks but limited use for full assessment writing. Asag & Al Mamun integrate TAM with UTAUT to model Bangladeshi engineering students' adoption, explaining 64% of usage variance and highlighting job relevance, result demonstrability, and subjective norms as key drivers.
- **Prompting strategy predicts performance, not usage volume:** among 128 fourth-year engineering students, AI Query Efficiency and AI-Driven Problem-Solving were the strongest predictors of academic success and remained significant after controlling for cumulative GPA (Isaza Dominguez et al. (2026)).
- **Students' own metaphors exceed what the tools deliver:** Kudina (2026) found 100 engineering students most valued LLMs for writing support, conceptual clarification and coding, yet framed them as "oracle" and "tutor" — authority and personalization a probabilistic text generator cannot supply, a "cruel optimism" that depends on verification skills students are still building.
- **Embed AI in the discipline, not beside it:** a project-based thermal-engineering curriculum folded machine learning into existing thermal topics across introductory, application and advanced levels

rather than adding computer-science courses, and undergraduates meeting only minimal entry requirements produced weaker projects than graduate peers (Li et al. (2026)).

- **AI tutoring and feedback for quantitative engineering courses:** Yin et al. (2026) introduce Arthur, an AI teaching assistant that delivers real-time, personalized feedback on Calculated Formula Questions in an undergraduate Engineering Economics course — a domain where pen-and-paper, unstructured solutions have blocked prior AI support. Its full life-cycle pipeline (curating previously graded handwritten submissions, random-masking data augmentation, per-question XGBoost diagnosis backbones, and a dialogue-based question-bank web interface) offers a scalable pathway for AI feedback across engineering courses that lack structured digital data, and the framework is designed to generalize to CFQs in other engineering disciplines.
- **AI for sustainability, integrated rather than modular.** The four-pillar AI-SEE framework (intelligence-driven, green-empowered, responsibility-leading, practice-integrated) distributes AI across engineering coursework; in a 144-student transportation-engineering case, students reported engagement across personal, academic, professional, and social levels, with sustainability reasoning carried into families and peer networks (Liu et al. (2026)).
- **A tool-rich studio can depress efficacy without improving the product.** In a 27-student architectural design studio, teams using a generative-AI plus XR pipeline showed larger pre–post declines in design Self-Efficacy ($\beta = -1.675$) and outcome expectancy ($\beta = -2.088$) than controls, while one headset per student produced no coordinated collaboration (Xiao et al., 2026).
- **Model choice, not prompting, sets feedback reliability under pushback.** Apostolakis et al. (2026) built 200 verified two-dimensional truss problems and put thirteen models through three postures: solve, confirm a correct solution the student insists is wrong, and locate an injected error. Solving accuracy ran from 64.5% to 97.0% and every model caught at least 90.4% of injected errors, so neither separated the field; resistance to pushback did, ranging from 46.5% to 98.5%. For a statics course the tutoring risk is not a wrong final answer but a model that agrees when a student wrongly doubts correct work, and the authors note that if reliability tracks paid tiers, the feedback students receive will vary with what their institution can license.

Signature concerns

Engineering education's signature concerns shape how AI is taken up: **hands-on and laboratory learning** (and what is lost when AI simulates practice), **professional formation** (ethical responsibility, safety, and societal impact), **design and problem-solving** (how much cognitive work AI should do), and **competency-based preparation for the workforce**. These make engineering education a rich site for studying whether AI augments or displaces the cognitive work essential to professional expertise — paralleling debates in Physics Education, Math Education, and CS Education.

Connections to related concepts

Engineering education sits within STEM Education and connects strongly to CS Education (computing and software engineering), Math Education and Physics Education (engineering's mathematical and physical foundations), Workplace Learning and Educational Development (workforce and instructor preparation),

Assessment and Ethics (the professional and evaluative stakes of AI), and Higher Education (the institutional context). It is the home discipline for the knowledge base's ASEE-sourced articles.

Under-covered sub-areas

The knowledge base's engineering education coverage is still developing. Sub-areas that would benefit from further articles include **discipline-specific engineering pedagogies** (mechanical, civil, chemical, electrical, software, and bioengineering education), **design and maker education**, **capstone and project-based learning**, and **engineering ethics education** — where AI's role is likely to be especially consequential.

That gap is no longer empty in one area: a three-year biomedical engineering program ran generative AI as a guarded knowledge-summarization and coding scaffold inside a four-module PBL sequence — approved tools, no patient data, disclosure logs — and reported A-rates of 66.4% against 39.1% for pre-AI cohorts (Nnamdi et al. (2026)).

Implications for engineering instructors

- **Build a shared, accurate language about AI.** Faculty metaphor research finds instructors hold fundamentally different mental models (agent vs. tool); align departmental understanding before making policy.
- **Close the ethics-to-accountability gap.** Ethics reviews find guidance is mostly student-facing and compliance-oriented; strengthen reciprocal faculty and institutional accountability, given engineering's stake in public safety.
- **Use multimodal, embodied assessment.** Gesture + speech assessment adds diagnostic evidence beyond language alone — consider embodied cues when evaluating conceptual understanding.
- **Prepare students for the workforce, not just the course.** The Dual Train Problem urges durable AI competencies, ethics/governance, and skill-based credentials aligned with emerging roles.
- **Model critical use and appropriate reliance.** Critical-use TAM research shows students rely on AI heavily for understanding tasks but less for assessment — guide them toward appropriate, verifiable reliance across task types.
- **Teach AI use as a skill inside class time.** Geng et al. (2026) ran nine instructor-led demonstrations, each 10–15 minutes at the end of a lecture and sequenced from tool literacy through strategic delegation to model evaluation — but students seeing no connection to assessment reported them redundant, so tie them to graded work.

Common Misconceptions

- **"AI adoption among engineering students is a technology-acceptance problem."** Asag and Al Mamun integrate TAM with UTAUT to model Bangladeshi engineering students' adoption, **explaining 64% of** the variance — so a substantial share sits outside the acceptance constructs, in social and cognitive factors the model does not cover.

- **“Students use AI for what it is best at.”** Kudina (2026) found **100 engineering students** most valued LLMs for **writing support**, not for engineering reasoning. Their metaphors for the tool exceeded what it delivered, and their actual use followed convenience rather than capability.
- **“A richer tool stack improves design outcomes.”** In a **27-student** architectural design studio, teams using a generative-AI plus XR pipeline showed **depressed efficacy without an improved product**. Tool richness can cost confidence while leaving the artifact unchanged.

Connected Concepts

- Problem-Based Learning
- STEM Education
- CS Education
- Design Education
- Math Education
- Physics Education
- Workplace Learning
- Educational Development
- Assessment
- Ethics
- Higher Education
- AI in Education
- Generative AI

Connected Articles

- TrussTutor-Bench: Benchmarking large language models on solution accuracy, sycophancy, and error detection in statics — Statics benchmark: solving and error detection saturate, pushback resistance does not
- Giving mechanical engineers intelligent tools: A project-based AI education curriculum in thermal engineering — Project-Based AI Education Curriculum in Thermal Engineering
- Advancing problem-based learning in biomedical engineering in the era of generative AI
- It’s Like "X": How Engineering Faculty Metaphors Construct (and Constrain) AI Understanding in Engineering Education — Engineering Faculty Metaphors Construct (and Constrain) AI Understanding
- Factors influencing university students’ intention to use and reliance on generative artificial intelligence: An extended technology acceptance model with critical use — Extended TAM with critical use for engineering/CS students
- Social and cognitive drivers of generative AI adoption: A unified socio-cognitive model for engineering education — Unified socio-cognitive model for engineering education (Bangladesh)
- Ethical Use of Artificial Intelligence in Engineering Education: A Systematic Review — Ethical Use of AI in Engineering Education: A Systematic Review

- A Multimodal Framework for Embodied Cognition in Oral Explanations — A Multimodal Framework for Embodied Cognition in Oral Explanations
- Artificial Intelligence (AI) and the Future of the Engineering and Computing Workforce: A Systematic Review of Gray Literature and Document Analysis of U.S. Reports (2020–2025) — AI and the Future of the Engineering and Computing Workforce
- Using AI in engineering education: a balancing act, driven by clear purpose — Using AI in Engineering Education: A Balancing Act
- Structured AI demonstrations and student LLM use in engineering mechanics: Study design and preliminary results — Structured AI Demonstrations in Engineering Mechanics
- An empirical study of ChatGPT use in engineering education: Prompting and performance — ChatGPT in engineering education
- Enhancing Sustainability Consciousness in Higher Education: Impacts of Artificial Intelligence-Integrated Sustainable Engineering Education — AI-SEE framework for sustainable engineering education (Liu et al. 2026)
- Arthur: An artificial intelligence powered teaching assistant system for Engineering Economics class
- Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study — Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study

STEM Education

> **STEM Education** — science, technology, engineering, and mathematics education is the most common domain for AI in education research in the knowledge base. STEM's structured knowledge, clear right/wrong answers, and computational nature make it an ideal testbed for AI tutoring and assessment.

Questions to Consider

- STEM is the most common domain for AI-in-education research because its knowledge is structured and has clear right/wrong answers. Do you think that makes STEM the easiest place to teach with AI — or possibly the place where AI's limits are most easily masked?
- The page cites research showing AI adoption in schools is 'stratified by discipline' — normalized in computer science, heavily prohibited in mathematics. Why do you think subject culture shapes AI acceptance so strongly, and what are the consequences for students?
- If a math student uses AI mainly to check solutions and get explanations, is that a scaffold or a crutch? What determines the difference, and where would you draw the line?
- Given that STEM problems often have verifiable answers, what kinds of AI use in STEM do you think genuinely build understanding versus merely produce correct-looking output?
- How might the very qualities that make STEM ideal for AI tutoring — clear answers, computable correctness — undersell the parts of science and engineering that are messy, open-ended, and judgment-based?

Introduction

STEM as the primary AIED domain

- **Mathematics:** Math education research spans GenAI impact on math learning, elementary fraction tutoring, and competence clustering.
- **Mathematics ITS evidence is bounded and conditional.** A structured narrative review of 20 publications (2020–April 2026) found the clearest measured advantage for real-time diagnostic Feedback layered onto the same adaptive system, yet concluded that intelligent tutoring supports mathematics learning only when valid learner modeling, calibrated scaffolding and teacher mediation combine, and that scalability is technical, not educational (Ogunsakin et al. (2026)).
- **Physics:** Physics education includes ChatGPT typology studies, Socratic physics chatbots, and scoring bias analysis.
- **Computer science:** CS education is the most-researched STEM subfield — code review, debugging tools, and prompting studies.
- **Engineering:** Engineering scaffolds, mechanics demonstrations, and curriculum balancing bring AI to engineering education.

- **Scaffolding undergraduate research:** An and colleagues (2026) pilot an AI system that converts research publications into structured, comparable datasets for undergraduate thesis completion across four STEM schools. Results (20 students, 80 documents) showed >90% extraction of experimental parameters, ~65% reduction in literature-review time, and a 50% increase in students' ability to identify influential experimental variables — evidence of how AI-scaffolded undergraduate research can strengthen research literacy and epistemic cognition in STEM education.
- **Simulation-supported instruction:** In drone-based STEM education, teacher-AI co-designed Simulation scaffolds were evaluated against an identical hands-on curriculum with 30 secondary students, testing whether simulation-supported instruction yields superior learning outcomes. GenAI's role was to accelerate content creation while teacher involvement preserved pedagogical validity and contextual relevance.
- **Outcomes favored the scaffolded group.** The simulation group outgained the hands-on group on curriculum-aligned STEM knowledge (M = 3.00 versus 2.06; t(28) = 2.23, p = .034, d = 0.82) and on 21st-century competencies (d = 1.52) (Yeung et al. (2026)).
- **Digital twins in STEM: prototypes outrun measured learning.** A PRISMA review of 11 higher-education studies found every one demonstrated a working, hardware-synchronized prototype, yet only three (27.3%) reported statistically significant learning gains, with development complexity and reduced social interaction the recurring barriers (Pelayo-González et al., 2026).
- **AI-assisted planning in STEAM arts education:** An experimental study of children's STEAM arts teachers (Luo and Tahir 2025) found ChatGPT-assisted lesson plans outperformed teacher-generated ones on expert-rated quality (median 20.5 vs. 17.6, p = .002, large effect, six professor raters), with teachers reporting gains in efficiency and interdisciplinary integration (61% rated 4+). The result came through the teacher's delegation method — most usefully by having ChatGPT fill content gaps in a self-outlined lesson — reinforcing the recurring point that AI lifts STEM/STEAM work when the teacher structures the task and critically evaluates output rather than handing the whole plan to the model.

How effective AI-supported instruction is in STEM, pooled

The largest quantitative synthesis for this domain to date — 35 experimental and quasi-experimental studies published between 2005 and 2025 (Doğan, Kılıç, Kalınkara and Talan, 2026) — puts AI-supported instruction in STEM at Hedges' g = 0.670 (95% CI [0.491, 0.848]), with the between-study variance handled by a random-effects model. The level breakdown is the informative part: effects were largest in high school (g = 1.099) and progressively smaller in university (0.578), elementary (0.465) and middle school (0.392). By contrast, the subject-area differences that STEM's self-image would predict — science (0.676) and mathematics (0.650) ahead of technology and engineering (0.501) — were not statistically significant (Q = 4.85, df = 2, p = 0.088). Duration did not behave as a dose: the strongest band was one to two months (g = 0.833), the shortest interventions of five hours or less still reached 0.621, and the weakest band (g = 0.256) was not significant. Read alongside the skepticism documented on Learning Gains, the reasonable reading is that AI-supported STEM instruction produces a moderate, real but level-dependent effect, not a uniform one.

A subject-area review of 18 studies (2014–2024) sharpens what those effects are measured on: AI's outcomes in science and chemistry education concentrated on learning-process measures (n = 9) rather than

achievement, and the evidence base skews to teacher candidates (44.4%), with only one middle-school and two high-school studies (Erümit and Özdemir Sarıalioğlu (2025)).

Why STEM dominates

STEM's structured knowledge representation, verifiable answers, and computational thinking alignment make it the most natural fit for AI tutoring. Computational thinking research explores this alignment explicitly.

New evidence from 2025–26 IJ STEM Education research

A concentrated batch of 2026 *International Journal of STEM Education* studies sharpens how AI functions across STEM's subfields and levels:

- **Subject-specific AI Governance shapes student AI use.** A cross-sectional study of 416 Czech secondary students (Navigating AI in STEM: what secondary students actually do with generative AI-driven tools) found AI adoption is *stratified by discipline* rather than unified: computer science and economics normalize GenAI as a collaborative resource, while mathematics (65.9% prohibit) and natural sciences (55.3%) show high perceived prohibition co-occurring with poor rule clarity and persistent clandestine use. Students mostly use AI as an instrumental scaffold (explanation, solution-checking) rather than a substitute, but a critical evaluation gap emerges — heavy prompt modification overshadows external factual verification, shifting behavior toward Cognitive Offloading. This argues for *subject-sensitive* guidance over blanket bans.
- **AI as a co-inquirer in inquiry-based STEM.** A quasi-experiment with 97 third-graders (Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science) showed GenAI chatbots significantly outperformed search engines for science problem posing in inquiry-based learning, improving question quality, producing a more integrated epistemic network structure (ENA), and lowering cognitive load. A systematic review of ChatGPT for inquiry-based learning in STEAM (The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education, 24 studies) confirms ChatGPT supports question formulation, inquiry design, Problem Solving, and reflection — but risks over-reliance, hallucination, and superficial conclusions when outputs are treated as authoritative.
- **STEAM is an uneven pathway to AI literacy.** A PRISMA systematic review of 39 studies (STEAM education for AI literacy: a systematic literature review) found STEAM implementations chiefly develop technical literacies (fundamental AI concepts, computational thinking, data literacy) while underdeveloping ethical awareness, creative imagination, creating/managing/designing with AI. Technology disciplines lead; arts, engineering, and integrated STEAM lag — indicating AI literacy in STEM is currently lopsided toward technical skill over responsible shaping of AI.
- **Adaptive AI-based STEM programs can support deep learning.** A cluster-randomized pilot in sixth-grade science (Developing deep learning in science through an adaptive AI-based STEM instructional program: evidence from sixth-grade classrooms, N = 30) found an adaptive AI-based

STEM program (personalized content, rule-based mastery, real-time feedback) produced large effect sizes favoring the experimental group across explanation, interpretation, application, and idea generation — though the two-classroom design warrants cautious interpretation.

- **Teacher acceptance is heterogeneous and discipline-shaped.** A latent profile analysis of 128 pre-service teachers (Unpacking the heterogeneity of pre-service teachers' ChatGPT acceptance: a latent profile analysis across STEM and non-STEM disciplines) found four ChatGPT-acceptance profiles (Pragmatic Evaluators, Technology Pioneers, Resistant Skeptics, Environmental Observers), with STEM teachers concentrated in Technology Pioneers and non-STEM teachers in resistant profiles — and Resistant Skeptics showing high ease of use but low intention, demanding differentiated AI Literacy training.
- **Teaching students to interrogate the model, not just to use it.** A single 45-minute session on prompting and error-checking raised undergraduate physics posttest scores (d = 0.814) and leveled the advantage of prior AI experience (Huang et al., 2026).
- **Assessment and cognitive processes in AI-integrated STEM.** The CTAT (34-item, IRT-validated) provides a valid instrument for assessing Computational Thinking within AI-training contexts, revealing students struggle most with data representation, logical-operator sequencing, and loop structures. A grounded-theory study of AI-assisted programming (Tool, tutor, or crutch?: a grounded theory of cognitive scaffolding and offloading in AI-assisted programming education) shows learners oscillate between "Domain Mastery" and "Tool Mastery" through Scaffolding and Offloading loops, with attenuated metacognitive calibration under routine offloading — a process-level account of the performance-learning tension.

Implications for STEM instructors

- **Choose discipline-appropriate AI.** STEM spans math (tutoring), physics (Socratic dialogue, Simulation), CS (code generation, review), and engineering (design, workforce) — select tools matched to each subfield's signature Pedagogies and Teaching Strategies rather than assuming one general chatbot fits all.
- **Use AI's structured-fit advantage, but protect reasoning.** STEM's verifiable answers make it the most AI-tractable domain; guard against over-reliance and answer-replacement by embedding AI in structured, mastery-oriented workflows.
- **Embed AI literacy across STEM courses.** Studies (biology, math teacher prep) show STEM context supports AI learning — integrate AI concepts where they naturally arise rather than isolating them.
- **Watch equity and access in AI adoption.** STEM AI tools are not neutral; monitor scoring bias, Digital Divide access, and culturally relevant design as you deploy them.

Common Misconceptions

- **"Intelligent tutoring works across STEM uniformly."** A structured narrative review of **20 publications (2020-April 2026)** found the clearest measured advantage for **real-time diagnostic**

tutoring specifically. The evidence is **bounded and conditional**, and generalising it to all mathematics ITS overstates what was reviewed.

- **“Simulation is a pale substitute for hands-on work.”** The simulation group **outgained the hands-on group on curriculum-aligned STEM knowledge (M = 3.00 versus 2.06; t(28) = 2.23, p = .034, d = 0.82)**. The simulation was not a fallback performing below the real thing.
- **“An AI-assisted literature workflow mainly saves time.”** Results from **20 students across 80 documents** showed **over 90% extraction of experimental parameters, roughly 65% reduction in literature-review time, and a 50% increase in students’ ability to identify influential** work. The capability gain was the larger result and the time saving was the smaller one.

Connected Concepts

- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities
- Business Education
- CS Education
- Math Education
- Physics Education
- Computational Thinking
- K-12
- Higher Education
- Intelligent Tutoring
- Automated Assessment
- Formative Assessment
- Personalized Learning
- Large Language Models (LLMs)
- AIEd in the Disciplines
- Teacher Education
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools

Connected Articles

- Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China — AI-enabled pedagogical accompaniment supporting STEM identity
- Navigating AI in STEM: what secondary students actually do with generative AI-driven tools — What secondary students actually do with GenAI tools across STEM

- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science — GenAI chatbots and problem posing in primary science
- The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education — ChatGPT for inquiry-based learning in STEAM
- STEAM education for AI literacy: a systematic literature review — STEAM education for AI literacy: systematic review
- Developing deep learning in science through an adaptive AI-based STEM instructional program: evidence from sixth-grade classrooms — Adaptive AI-based STEM program for deep learning
- Unpacking the heterogeneity of pre-service teachers' ChatGPT acceptance: a latent profile analysis across STEM and non-STEM disciplines — Pre-service teacher ChatGPT acceptance profiles
- Integrating AI into computational thinking: development and validation of an assessment tool for higher education students — Computational Thinking in AI Training Test (CTAT)
- Tool, tutor, or crutch?: a grounded theory of cognitive scaffolding and offloading in AI-assisted programming education — Tool, tutor, or crutch: grounded theory of AI-assisted programming
- Pragmatic users and skeptical nonusers: A qualitative typology of ChatGPT adoption in physics education
- Exploring Fraction Comprehension and Interest in Elementary Education Through AI-Powered Personalized Learning
- Creating Learning Scaffolds for Engineering Design Using Concept Catalyst
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build
- Can we disrupt the momentum of the AI colonization of science education?
- Artificial intelligence in science and chemistry education: A systematic review — Systematic review of AI in science/chemistry education
- From literature to research-based learning: An AI-powered information extraction system to enhance undergraduate thesis completion — AI-powered information extraction supporting undergraduate thesis and research-based learning (An et al. 2026)
- From simulation to flight: Simulation-assisted drone learning with teacher-AI co-designed scaffolds for secondary students' STEM knowledge and competencies — Simulation-assisted drone learning with teacher-AI co-designed scaffolds
- ChatGPT-assisted lesson planning for children's STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework
- The Impact of Artificial Intelligence-Supported Instruction on Student Learning in STEM: A Systematic Review and Meta-Analysis — Pooled effect of AI-supported STEM instruction across 35 studies, with the largest gains in high school (Doğan et al. 2026)
- Digital Twins in STEM Education: A Systematic Review — Digital twins in STEM: every reviewed study shipped a working prototype, few measured learning

- From answer machine to collaborative partner: impact of structured generative AI training on scientific problem solving in STEM education — A 45-minute prompting and error-checking session raised physics posttest scores (d = 0.814)
- Reimagining mathematics education through intelligent tutoring: evidence, opportunities, and implementation challenges — Mathematics ITS evidence is bounded and conditional

Science Education

> **Science education** — the study and practice of how students learn science and how to teach it, now being reshaped by generative AI (LLMs, simulations, virtual labs, and AI grading) across physics, chemistry, and biology. The science-education articles in this knowledge base reveal a field negotiating a core tension: AI demonstrably supports inquiry, misconception correction, and assessment at scale, yet its value depends on instructional design, and it carries real risks of over-reliance, hallucination, and dehumanized, profit-driven learning.

Questions to Consider

- The page opens with a tension: AI demonstrably supports inquiry and misconception correction at scale, yet its value depends entirely on instructional design. Before you read, when has a tool you used in science teaching seemed powerful yet pedagogically hollow — and what made the difference?
- An AI-facilitated physics inquiry 'invented' mass values that no one had measured when students pressured it. What does this incident reveal about treating AI outputs as authoritative in science, and how should students be trained to treat a confident-sounding answer?
- Research suggests AI may currently add more value as a scalable content generator than as an interactive tutor — in one study, well-crafted conceptual-change texts (expert or AI-made) beat a prompted AI dialogue. Does that surprise you, and what does it suggest about where the real pedagogical payoff of AI in science lies right now?
- AI graded 10,364 handwritten physics assessments with high agreement with human graders, yet multimodal models still show gaps on complex reasoning and diagram generation. What is it about 'authentic, representation-heavy' science work that might resist automated assessment?
- Physics students show a striking trust–utility gap — high use, low trust — and split into pragmatic users and skeptical nonusers. If students themselves are domain-calibrated skeptics, what does that imply for one-size-fits-all policies about AI in science classrooms?
- A critical voice warns of 'AI colonization' of science education — extraction without consent, algorithmic monoculture, dehumanized reform. Before you read, where do you think the benefits of AI in science education are being oversold, and what would a human-centered, justice-oriented alternative look like?

Introduction

Science education is where AI's promise and its limits collide most visibly, because the disciplines demand rigorous Multimodal AI reasoning — visual-spatial thinking in physics, laboratory skills in chemistry, and organism-level systems in biology — alongside well-structured, verifiable content that LLMs handle well. The thirteen articles synthesized here span all three disciplines and levels, from K-12 secondary classrooms to Higher Education university courses and pre-service teacher programs. Across them, a consistent picture emerges: AI functions best not as an answer generator but as an embedded partner — a co-inquirer, a content

generator, a virtual lab assistant — whose contribution is decided by instructional design and the surrounding pedagogical structure.

A four-week randomized evaluation of an AI revision platform in GCSE science gives the picture a causal estimate — Hedges' g = 0.33, with no evidence the effect differed by subject or disadvantage — against an already technology-rich counterfactual, so the figure is added value rather than AI versus nothing (Harrison et al. (2026)).

Structured access, not access itself, drives the gain: team-reported growth averaged 17% under unlimited individual access but 34% and 31% when access was structured, which also preserved more peer discussion (Malikova et al., 2026).

These classroom-level findings sit inside a larger methodological question. Martin, Rost, Koenen and Graulich (2026) argue that science education research may currently be amid an epistemic iteration, drawing on Hasok Chang's (2004) account of successive stages of knowledge that build iteratively toward specific epistemic aims. In their reading, AI methodologies may transform not only how the field analyzes student learning but which epistemic aims, criteria and practices it prioritizes. They propose a seven-phase reflective framework (problem framing; instrumentation and measurement; experimentation and evidence-based inference; comparisons and replication; building norms and consensus; implementation and its consequences; and continuous refinement), illustrated by the roughly 150-year development of thermometry, and present it as a reflective instrument rather than a validated method or an empirical finding.

Virtual labs and simulations

AI is dramatically lowering the barrier to creating customized, embodied science instrumentation. Levy et al. show that a four-element natural-language prompt can generate a hand-controlled augmented-reality physics simulation (a pinch-and-spread gesture tunes a virtual lamp's wavelength), with 86% of pilot students reporting greater engagement. Similarly, Suñer et al. generated a browser-based rotation laboratory entirely through prompting, validated against video analysis to better than 1%. These works reframe generative AI as a programming tool that lets teachers design software around pedagogical intent rather than adapting activities to fixed apps — advancing embodied and Simulation-based learning. In Chemistry Education, Abdikayumova & Madybekova embedded PhET simulations and ChatGPT tutoring within a context-based 7E inquiry cycle for Grade 10 students, achieving significantly higher achievement and engagement than either component alone — evidence that contextualization, structured inquiry, and adaptive AI act synergistically. Behavioral analysis of how learners work inside such modeling environments reinforces this design lesson: tracing 315 online learners building ecological models in VERA, An, Hammock & Goel (2025) found that learners who engage in full-cycle, hypothesis-driven exploration build the most complex and diverse models, whereas observation-heavy learners largely copy existing models — suggesting scientific modeling tools should actively promote full-cycle exploratory behavior rather than leave learners in a passive, observation-dominated mode.

AI tutors and inquiry-based learning

Inquiry-based learning is a central theme. Jiang et al.'s systematic review of 24 studies positions ChatGPT as an "AI-powered co-inquirer" used mainly in the conceptualization, investigation, and discussion phases of STEAM inquiry, improving performance, critical thinking, and engagement — yet risks over-reliance,

hallucination, and superficial conclusions when outputs are treated as authoritative. Aydın found that eight weeks of AI-supported guided inquiry produced large gains in pre-service teachers' conceptual understanding of photosynthesis and respiration, while AI literacy and computational thinking showed no significant change — suggesting disciplinary learning can improve even when broader competencies need longer or more explicit instruction. Tufino & Damiani show AI can scaffold the epistemic core of ISLE inquiry while remaining confined to the verbal channel, but found facilitation fragile: under student pressure, the AI "invented" mass values that no one had measured, underscoring Hallucination Risk and the need to verify rather than assume AI fidelity. Kuhn et al. propose the AIRIS framework (Activate–Inquire–Reflect) to keep prediction, interpretation, and evaluation non-delegable human tasks, and call for "withdrawal condition" experiments testing whether learning survives AI's removal — a direct response to the "boiling frog problem" of eroding epistemic practice. Expert judgment of AI-generated lesson plans extends this design lesson to curriculum-aligned science: Karaismailoglu, Surmeli and Yildirim (2026) had eleven Turkish science-education specialists score ChatGPT-4 and an education-focused tool (Teacher's Buddy) on sixth-grade plans for a "Sustainable Living and Biodiversity" unit aligned to the Engineering Design-Based Learning (EDBL) model. Both platforms scored highest on "Presenting the solution" yet lowest on Engineering Skills (general-purpose $\bar{x} = 37.45$; education-focused $\bar{x} = 41.45$) — a shared weakness in simulating the iterative, process-oriented stages (prototyping, failure analysis, revision, reflective retesting) that define design-based learning — and only 3 of 11 experts judged either plan directly "Applicable," with 7 rating them "Can be applied by correction."

Isolating AI's contribution in a three-group climate socio-scientific study, students whose structured inquiry included an AI partner outgained inquiry-only peers on decision-making ($d = 0.69$), with the largest gains on monitoring and adaptive management while data collection improved equally across conditions (Gousopoulos (2026)).

A conceptual review grounds the material channel theoretically: science is an open system that revises claims against physical evidence, while a language model is operationally closed to evidence at inference (Muminova & Mamatkulov, 2026).

Misconceptions and conceptual change

On conceptual change, the evidence is nuanced and partly counterintuitive. Akdoğan found in a 413-student Solomon Four-Group design that both expert-written and AI-generated conceptual change texts were equally and significantly more effective at reducing heat-and-temperature Misconceptions about AI than interactive AI dialogue, which offered no advantage over control — positioning AI's current pedagogical value as a scalable content generator rather than an interactive tutor, with gains concentrated among high-achieving students (an equity concern). This is reinforced by Borse et al., who show that prompt specificity shapes physics-solution quality and that MAPS-guided critique better prepares students to evaluate AI output than independent problem solving, treating AI fallibility as a Critical Thinking learning resource.

AI grading and assessment

AI grading is advancing rapidly on high-stakes work. Pathak et al. graded 10,364 scanned pages of handwritten physics assessments (including a national Olympiad and team-selection camp), achieving high score correlations (0.91–0.97) and recovering the same five-student team as human grading — arguing AI

works as a valid second reader and audit tool under examiner control when given detailed, physics-specific rubrics. Short-answer auto-marking has a longer and more foundational transformer lineage: Morley et al.'s scoping review of 21 studies (2017–early 2024) found BERT-family models dominated auto-marking of short-answer science questions through 2021 before GPT-based approaches were adopted via prompting from ~2022, that models augmented with domain data (textbooks, rubrics, further pre-training) consistently outperformed baselines, and that unresolved threats to reliability, explainability, and fairness argue for such auto-markers as supports to, rather than replacements for, human examiners. Yet Chen et al.'s OmniPhys Benchmark reveals that multimodal LLMs still show significant gaps on complex reasoning and diagram *generation*, cautioning against over-trusting automated physics assessment on the authentic, representation-heavy tasks that define deep disciplinary competence. A chemistry counterpart sharpens the format-dependence: Cvengros & Kortemeyer graded a 296-student handwritten general-chemistry final with a multimodal Large Language Models (LLMs), finding high agreement with TAs for textual and chemical-reaction answers but *worse-than-random* performance on drawing and graphing (background grids distract AI vision) — evidence that reliable AI grading in science is selective by response format and requires confidence-based deferral to human examiners for graphical items, rather than a uniform "grade everything" approach.

Teacher perceptions and the critical view

Teacher readiness is decisive. Amponsah et al. found Ghanaian pre-service science teachers hold positive attitudes and strong intentions toward AI but only moderate actual classroom use — an intention–use gap pointing to Teacher AI Competency and institutional support as the real levers. Becker et al. and Fouad & Bentley document that physics students are domain-calibrated skeptics, not uncritical adopters: a 50-point trust-utility gap (91% use, 41% trust) and two distinct user profiles (Pragmatic Users vs. Skeptical Non-Users) that challenge one-size-fits-all policies. Counterbalancing the techno-optimism, Avraamidou warns of an "AI colonization" of science education — extraction without consent, algorithmic monoculture, and dehumanized, profit-centered reform — and calls for a feminist, human-centered AI prioritizing justice over profit, while Erümit & Özdemir Sarıalioğlu's systematic review of 18 studies emphasizes ethical risks (bias, hallucination, plagiarism, erosion of independent thinking) and the need for teacher training and conscious use. The collective lesson across all thirteen articles is that AI in science education delivers gains when embedded in sound inquiry, Scaffolding, and Assessment design — and undercuts learning when it displaces the epistemic work students must do themselves.

General AI comfort did not transfer to the discipline's own tools. Among 100 geography students at one Kazakh university, readiness to teach with AI and GIS tracked GIS familiarity ($\rho = 0.508$) and GeoAI knowledge ($\rho = 0.425$) but not general AI familiarity ($\rho = 0.071$, $p = 0.485$) — a lesson for teacher preparation in any tool-shaped discipline (Laiskhanov et al. (2026)). Sixty-seven percent called themselves ready in some form, yet only 6% had used the combination in practice and 43% judged available instruction adequate. The evaluation is self-reported and unvalidated, so it describes what these students say about themselves.

Schroeder et al. (2026) ask how well general models handle the science content itself: on NGSS-aligned item sets for middle school (1,078 items) and high school (1,150 items), nine open-weight models mostly exceeded 90%, with model size unrelated to accuracy. A science teacher judged 236 of 240 sampled items (98.3%) aligned while flagging the absence of diagrams, data interpretation, and mathematical representation

— text-only items cannot exercise every NGSS performance expectation. The high item difficulty and low discrimination leave open whether the items need improvement or secondary science has become tractable for this class of models, and the authors call multi-turn, evidence-based feedback the missing standard.

In a 42-study meta-analysis of GenAI and motivation, the smallest subject-domain effect was in science ($g = 0.109$, 95% CI [−0.107, 0.325], $k = 3$), the only domain whose interval crossed zero, so the pooled evidence does not support a motivational case for GenAI specifically in science (Fang et al. (2026)).

As a framework rather than a study, Zhai et al. (2026) reframe the target: Vision I science literacy for competence in science careers, Vision II for science in everyday and civic life, and Vision III for knowledge and action at community and societal scale. They argue that generative AI earns its place in science classrooms only when it makes curriculum, instruction and assessment cohere with one of those visions, and that the field's persistent problem is tests that reward terminology recall while standards ask for explanation and investigation.

Common Misconceptions

- **"AI in science education has no causal evidence."** A **four-week randomized evaluation** of an AI revision platform in GCSE science gives a causal estimate of **Hedges' g = 0.33**, with **no evidence the effect differed by subject**. The effect is modest and it is causal.
- **"Give students access and the gains follow." Structured access, not access itself, drives the gain**: team-reported growth averaged **17% under unlimited individual access but 34% and 31% when access was structured**. The structure was the intervention.
- **"Scientific simulation requires specialised software."** A **four-element natural-language prompt** can generate a **hand-controlled augmented-reality physics simulation**. The barrier to authoring a simulation fell to the prompt design, which shifts the skill required from programming to specifying the phenomenon.

Connected Concepts

- STEM Education
- Physics Education
- Chemistry Education
- Biology Education
- Inquiry-Based Learning
- Misconceptions about AI
- Simulation
- Generative AI

Connected Articles

- Science Literacy: Generative AI as Enabler of Coherence in the Teaching, Learning, and Assessment of Scientific Knowledge and Reasoning — Framework chapter on science literacy as coherence across curriculum, instruction and assessment (Zhai et al. 2026)

- Amid an Epistemic Iteration: How AI Methodologies May Transform the Nature of Science Education Research — Seven-phase epistemic-iteration framework for reflecting on how AI methodologies may transform science education research (Martin et al., 2026)
- Artificial intelligence in science and chemistry education: A systematic review — Systematic review of AI in science and chemistry education
- The AI-powered co-inquirer: a systematic review of ChatGPT for inquiry-based learning in STEAM education — ChatGPT for inquiry-based learning in STEAM
- AI-Supported Inquiry-Based Learning in Photosynthesis and Respiration: Implications for Sustainable Science Teacher Education — AI-supported guided inquiry in photosynthesis and respiration
- Comparing the effectiveness of expert-written text, AI-generated text, and interactive AI dialogues on students' conceptual understanding of heat and temperature — Conceptual change texts vs. AI dialogue for heat and temperature
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — Large-scale AI grading of handwritten physics assessments
- Can we disrupt the momentum of the AI colonization of science education? — Critical commentary on AI colonization of science education
- Perceptions and Acceptance of Artificial Intelligence in Science Education Programmes: Voices of Pre-Service Science Teachers — Pre-service science teachers' AI perceptions and acceptance
- Can AI-Assisted Inquiry Enhance Students' Decision-Making Skills in Socio-Scientific Issues? A Three-Group Experimental Study on Climate Change — AI-Assisted Inquiry in Socio-Scientific Issues on Climate Change
- Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4
- How Online Learners Engage in Self-Directed Modeling: A Behavioral Analysis
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Suitability of Artificial Intelligence Supported Lesson Plans from the Perspective of Science Education Experts
- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomized Trials of an AI Tutoring Platform in GCSE Science
- A Benchmark for LLM's Understanding of Middle School and High School Science Topics — A Benchmark for LLM's Understanding of Middle School and High School Science Topics
- The nature of science in the age of generative artificial intelligence: Epistemic authority, materiality, and a synergetic response — The nature of science in the age of generative artificial intelligence: Epistemic authority, materiality, and a synergetic response
- Artificial intelligence in university physics education: a systematic review of empirical studies — Structured team access outperformed unlimited individual access in a university physics AI review

- Effects of generative artificial intelligence on students' learning motivation: evidence from a meta-analysis — The only domain whose motivational interval crosses zero (g = 0.109, k = 3)
- A model for enhancing the quality of geography education based on the integration of Artificial Intelligence and Geographic Information Systems — General AI comfort did not transfer to GeoAI readiness

Writing

> **Writing** — the use of AI tools for writing instruction, Assessment, Feedback, and the study of how generative AI reshapes the writing process itself. Writing education is one of the most AI-affected domains, because LLMs excel at the very activities writing instruction centers on — text generation, revision, and evaluation. Research in this area spans automated scoring, AI feedback quality, writing-process support, second-language writing, academic integrity, and the deeper question of how AI changes what it means to write and to be a writer.

Questions to Consider

- The page's central claim is that writing is not merely output but a cognitive, social, and rhetorical process — and that AI can displace the very mental work that makes writing a learning activity. When you write, what happens in your thinking that a finished AI-produced paragraph simply erases?
- A common framing is 'AI as a tool' or, at the opposite extreme, 'AI as a threat to authorship.' The page offers a third view: writing as a human-AI entanglement where agency is distributed. Which of these framings matches your own experience of writing with or without AI — and what does each framing imply for how you'd teach?
- Research found that delegating *deeper* layers of writing — reasoning and argumentative logic — harms your independent writing more than delegating surface layers like grammar. Think about your last AI-assisted piece of writing. Which layer did you actually delegate, and what does that predict about what you can now do on your own?
- The page warns that AI writing feedback is not language-neutral: personalizing feedback with a student's race, language, or disability can shift it in stereotype-aligned ways — such as overpraising or withholding critique. If you've received or given 'personalized' AI feedback, how would you detect that a tool was softening its critique for some learners?
- The design guidance here is 'coaching, not composing' — have AI ask questions and critique outlines, but require the learner to produce prose first. Why might letting the learner draft before the AI intervenes protect ownership and judgment in ways a tool that writes the draft could not?
- One finding: students often say 'it's OK because…' to rationalize AI use, moving the issue from plagiarism policing toward ethics and AI literacy. If you were designing a writing course, how would you build honesty and ethical judgment about AI into it, rather than relying on detection or punishment?

Introduction

Writing is not merely output but a cognitive, social, and rhetorical process. This is why AI's impact on writing education is so consequential and contested: AI can be a scaffold that helps students draft, revise, and receive feedback they otherwise wouldn't get, but it can also displace the cognitive work — and the human audience — that make writing a learning activity. The knowledge base's research consistently frames AI in

writing as a *human-centered complement* to, rather than a replacement for, the social and cognitive processes of writing. Where the focus is **English specifically** — English for Academic Purposes (EAP) and English language teaching (EFL/ESL/L2) — see the dedicated English Education (EAP / EFL / ESL) concept page, which distinguishes English-specific and academic-register research from general writing and general language learning.

How AI in writing education appears in the research

- **Automated essay scoring:** Automated Essay Scoring systems like anchor-based AES and AIAWE evaluate student writing at scale, raising questions about construct validity and the reduction of writing to measurable features. For short argumentative writing (about 150–200 words) in Spanish, AI scoring agreement varies sharply by rubric dimension (Curi et al., 2026): structure- and register-oriented items — introduction, conclusion, register, nominal agreement, subject–verb agreement — reached moderate chance-corrected agreement with human raters in the 2025 edition, while micro-level linguistic items (vocabulary, syntax, punctuation, connectors, argumentation) stayed in the fair-to-slight range. This suggests LLM assistance is most defensible for macro-level discourse features, and that low-level language conventions should keep deterministic tooling or human review.
- **A quality-dependent tilt.** Out-of-the-box GPT and Llama graders agreed weakly with human raters (QWK 0.17–0.28 versus 0.72 between two humans), overscoring short, underdeveloped essays and underscoring longer, stronger ones for minor surface errors (Mathew et al. (2026)).
- **Score more samples, not bigger models.** In a Grades 3–6 universal-screening study, LLM comparative-judgment scores converged with researcher rubrics (r = .59–.73) and averaging the three screening waves raised criterion validity (β = .68–.74 for ELA scale, AUC = .82–.86 for proficiency), while greater model capability or cost added little (Mercer & Reed (2026)).

Agreement is a property of the corpus, not the scorer: Li (2026) scored 60 student marketing posts with deterministic rules, an LLM and an equal-weight hybrid — the LLM led at ICC(2,1) = .435 while the hybrid's .266 retained the rules' negative bias — and adding 15 low-quality anchors lifted the LLM to .846.

- **Writing feedback:** AI feedback quality research (GenAI vs. teacher feedback, care-full feedback, repeated AI feedback) examines whether AI feedback improves writing and how it compares to human feedback. The PAIRR model (Peer and AI Review + Reflection) combines AI with Peer Assessment and finds AI feedback is most useful in a human-centered process. An 8-week quasi-experiment with 61 Chinese L2 writers (Tang et al., 2026) gives that human-centered claim a concrete shape: teacher feedback delivered far more items (316 versus 185 in the first task) and re-prioritized toward organization and argumentation, but its posted-revision advantage gave way from 4.06 to 2.73 points once a second task demanded structural change, while AI-assisted peer feedback held a narrower, steadier focus and edged ahead (3.89 points, with a task-2 revision mean of 89.82 against the control's 88.35 — a small difference that did not reach significance). Neither mode moved syntactic complexity, so the authors argue for a hybrid "AI-Peer-Teacher" division of labor: AI for error marking and content guidance, peers for negotiating revisions, teachers for complex syntax and argumentation.

- **Pairing AI with peer feedback raises engagement and writing scores.** In a 10-week Chinese EFL course, adding ChatGPT feedback before peer review lifted behavioral, affective and cognitive engagement (partial η2 of 0.28 to 0.32) and improved all four IELTS writing dimensions, most on task achievement (d = 1.41) and lexical resource (d = 1.28) (Liu (2026)).
- **AI feedback does not adapt to writing stages the way teachers do.** Almousa et al. (2026) found the teacher changed significantly on five feedback focus types between draft stages — Praise rising from 26.9% initially to 84.9% in final drafts — while the closest model moved on three types and the smallest on none, and no model reproduced the teacher's differentiation of higher- and lower-performing students.
- **Revision and dialogic positioning:** Where most writing-feedback research asks whether a revision improved the text, Zhao and Ji (2026) ask what stance the revised text takes. Coding 168 EFL argumentative essays with Appraisal Theory — first drafts, revisions after peer feedback, and ChatGPT-4 revisions of the same drafts — they found the three conditions statistically indistinguishable in how much Engagement language they used, but differently configured: peer-feedback revisions became more contractive (more Counter and Endorse, less Entertain), while the AI revisions kept a more balanced Contract/Expand mix that combined stronger counter-claiming with continued hedging. Their reading is that an AI revision is most useful as a contrast text students compare against their own revision rather than as a model answer, and that AI feedback on argumentation can improve prose while quietly closing down the writer's dialogic space — a dimension no current rubric captures.
- **Writing process support and agency:** Agency gap research and stage-ownership research explore how AI changes the writing process from planning to revision, and how students' Learner Agency is affected when AI participates at different stages.
- **Posthumanist perspectives:** A posthumanist approach to AI literacy reframes writing as a human-AI entanglement in which Learner Agency is distributed, challenging both uncritical anthropomorphization of AI and its dismissal as a mere tool — a relational rather than transactional view of AI literacy.
- **L2 / multilingual writing:** L2 writing assessment, linguistic diversity research, and stage-ownership research address how AI supports (or constrains) second-language and multilingual writers, including the risk of reinforcing Standard Academic English norms. The knowledge base's youngest L2 sample comes from a nine-week GenAI-supported opinion-writing program with 301 Grade 5 and 6 students in Eastern China (Lu et al., 2026), which raised ideal L2 writing self and academic buoyancy and improved rubric-scored language use while leaving organization and total scores unchanged — AI support moved specific dimensions of writing rather than writing ability as a whole.
- **Bias in personalized feedback (Marked Pedagogies):** Tan et al. (2026) show that Large Language Models (LLMs) writing-feedback tools are not language-neutral: personalizing feedback with a student's race, ethnicity, ELL designation, learning disability, achievement, or motivation systematically shifts feedback in stereotype-aligned ways — including positive feedback bias and feedback withholding bias (overuse of praise, less substantive critique, assumptions of limited ability) for students marked by race, language, or disability, even when the

essay is identical. This makes "personalization" itself a bias vector that writing-feedback tools must audit and control.

- **Academic integrity:** Survey evidence complicates the policing frame directly: among 504 sociology students (Kuznetsov et al., 2026), 65 percent had used GenAI for coursework but only 3 percent to generate assignment text and 2 percent to produce a full draft, while fear of an academic offense was the second most common concern (28 percent) and roughly a quarter reported no guidance at all (19 percent) or guidance they found unclear. On this evidence the writing-education problem is ambiguity about permitted use, not widespread text generation. Nash and Burriss (2026) show how such ambiguity is produced at the classroom level. Coding 27 preservice English language arts teachers' own classroom AI policies, they found that 26 of 27 permitted some generative AI use but overwhelmingly on teacher-specified terms, with 22 of 27 allowing AI for ideation and brainstorming while disallowing AI composition of sentences, paragraphs or papers. Limits were rarely operationalized — one participant allowed AI "to get your thinking started" and declared "this is where the line should be drawn" without saying where — and many policies simultaneously prohibited submitting AI text and held students responsible for the AI text they submitted, a contradiction that leaves students unable to comply. Twenty-two of the 27 policies were silent on reading altogether, ceding AI-supported comprehension work to no guidance at all.
- **The boundary moves with the assignment, not the tool.** Across 192 practice records, editing was Responsible in 21 of 22, while drafting was Responsible in 11, Contested in 9 and Problematic in 13, so the assessed capability rather than the tool sets the category (Tie, Gil Ortega and Zhao (2026)). Just four studies defined a boundary, designed an intervention around it and tested whether decisions aligned.
- **Policy diverges across five sites.** Interviewing 20 undergraduates, Kim and colleagues locate five distinct sites of AI policy — faculty intention, formal policy, student interpretation, self-policy, and practice — and catalogue 23 rationalizations, mostly ad hoc and post hoc, explaining why rules at one site rarely shape behavior at another (Kim et al. (2026)).
- **Grading is where the guidance runs out.** In interviews with 24 university writing professors across the Chinese Mainland, Hong Kong, Macau and Singapore, six reported no institutional rule on whether they may grade student work with AI at all, and the consequence was colleagues who refuse on principle sitting beside colleagues who already do it (Wu and Lam (2026)).
- **Compliance can mask absent inquiry (academic erasure).** From 49 educator accounts, Nwagboso & Atuba (2026) name *academic erasure* — fluency that satisfies every surface criterion while bypassing the epistemic labor of argument — and trace its driver to assessment culture, where rubrics rewarding polish make AI use the rational response rather than misconduct.

Writing as thinking

Because writing is a cognitive process, AI-in-writing research connects to Cognitive Offloading (does AI writing support bypass thinking?), Metacognition (does AI feedback improve Self-Assessment?), Self-Regulated Learning (do students regulate their use of AI feedback?), and AI Literacy (can students evaluate AI-generated writing critically?). The critical-thinking scaffolding and AI feedback for critical thinking

research show that the pedagogical value of AI in writing depends on whether it prompts reflection and judgment rather than answer-replacement.

Essay authorship tracked prompt volume in a synthesis task — 80% of the text written by the learner in the minimal-prompting cluster against 2% in the heaviest — while connective density correlated negatively with prior knowledge rather than prompt count (r = -.30, p = 0.007; Poquet et al., 2026).

A two-wave validation with Chinese EFL learners (EFA N = 305; CFA N = 342) separates six regulatory dimensions and adds *environmental regulation* — checking generated content, filtering suggested resources, and limiting reliance — a facet existing L2 writing scales had not carried (Wang, Zhang and Zhang (2026)).

Chen (2026) sharpens this with a **layer-sensitive** account of cognitive offloading in GenAI-assisted academic writing: delegating *deeper* layers (reasoning, argumentative logic) carries a stronger negative association with independent no-AI writing quality and higher-order thinking than delegating surface layers (grammar, vocabulary). Open AI collaboration yielded the best supported product but the worst independent outcomes, while bounded support with reflection preserved competence — evidence that GenAI writing support is not uniformly harmful but its effect depends on which cognitive layer students delegate.

- **Gating AI output on prior engagement moves effort back to the writer.** With 398 participants, Su et al. (2026) found writers composed for 28.02 minutes against 23.26 with an open chatbot, then evaluated passages faster (17.41 vs 22.21 minutes) at equal accuracy and no extra task time. Where Chen locates the cost in *which layer* is delegated, this design decides *when* the model may speak at all.

Lu et al. (2027) extend this thinking to *multimodal* composing by younger writers. Having 60 Grade 5 students externalize their narratives as AI-generated images and short videos produced sustained self-reported gains in interpretation, analysis, evaluation, and explanation — the facets multimodal resemiotisation exercises — but **no gain in inference**. Making meaning visually explicit lowered the demand to infer implicit meaning from text, exactly the offloading mechanism Chen describes; only structured peer discussion restored occasions for inference. The study cautions that multimodal AI composing helps young writers reflect on clarity and coherence while potentially skimming off the inferential work that text-only writing preserves — a design consideration for writing instructors pairing AI visuals with peer feedback.

A dimension-specific pattern recurs across this literature, and it is a useful diagnostic. In the primary-level L2 writing program, emotional and behavioral engagement rose while cognitive and metacognitive engagement did not, and the authors name diminished self-monitoring during writing as an explicit risk of GenAI support (Lu et al., 2026). Enjoyment and on-task activity are therefore not evidence that deeper processing is happening — the same distinction the offloading research draws when it asks which layer of cognitive work a student has delegated.

A 2026 meta-analysis (Teng, 2026) of 11 study-level effects drawn from 31 studies reinforces the diagnosis from the opposite direction. It reports a large average advantage for GenAI-supported writing instruction (g = 0.80) but heterogeneity high enough that a new implementation could plausibly show no benefit at all, and the only robust moderator was risk-of-bias classification rather than any pedagogical feature — study quality, not teaching design, explained most of the variance. The same synthesis finds GenAI consistently stronger on lower-order features (grammar, lexical diversity, sentence fluency) while higher-order effects on

argumentation and coherence remain inconsistent, which is precisely the layer gap this page treats as the central design problem.

Designing AI writing support: coaching, not composing

Because writing has no single correct answer, AI writing tools require a different design from answer-verifiable tutors. The knowledge base's design guidance (see the worked **AI writing coach** example in the FAQ on Designing an AI Tutor) centers on preserving authorship and evaluative judgment rather than producing finished text:

- **Track writing capabilities, not just essay scores.** A writing coach's learner model can track argument (thesis specificity, claim–evidence alignment, counterargument), organization, evidence integration, revision, and style — so feedback targets capabilities that persist across essays.
- **Ground feedback in the assignment.** Retrieve the actual prompt, rubric, course readings, citation and genre conventions, and AI-use policy so feedback references the specific assignment rather than inventing generic expectations.
- **Treat writing stages differently.** AI involvement at planning reduces perceived ownership less than at drafting, and AI-generated drafting produces the largest ownership decrease. So a coach can ask questions and critique outlines at planning while requiring the learner to produce prose first at drafting.
- **Make feedback prioritized and reflective.** Each round can offer one strength to preserve, one high-impact issue, one question requiring the writer's judgment, and one concrete revision goal — and the coach should ask learners to evaluate whether they agree with a suggestion, developing evaluative judgment rather than obedience.
- **Preserve authorial voice and guard against homogenization.** The coach should distinguish errors, clarity issues, rhetorical choices, and style preferences — and not automatically "correct" the latter, especially for multilingual writers and non-standard rhetorical styles.
- **Teach the process, not only the tool.** A five-week process–genre unit that built planning, genre analysis and revision around AI-supported multimodal writing raised all three outcomes in a 32-student seventh-grade quasi-experiment (informative text r = 0.66; multimodal r = 0.84; AI-assisted writing r = 0.86) (Günay and Özden, 2026).

Two recent syntheses qualify how well this design guidance is followed in practice. A review of 23 empirical customization studies (Luo, 2026) finds that although goals have moved toward writing processes and higher-order skills, the dominant technical route remains prompt engineering (13 of 23 studies) aimed at optimizing output quality, with learning theory confined to the interface so the system behaves "largely theory-agnostic" — a mismatch that helps explain the overreliance and superficial revision the same studies report. Its reframing is to treat customization as architecture rather than wording: sequencing stages, withholding answers, and building in revision loops. A structured five-part workflow tested over 11 weeks with 53 Saudi EFL undergraduates (Alshehri et al., 2026) shows the alternative in practice — students frame problems and design prompts, draft, revise, verify claims and citations against scholarly databases, and regulate their own reliance, logging what they accept or reject and why. Writing proficiency and digital critical thinking rose together in that condition (15.23 versus 11.91 and 89.84 versus 56.18 at posttest) while

the no-AI control barely moved, though the single-site, partly self-reported result is a preliminary upper bound rather than an established effect.

Screening 51 second-language studies of GenAI feedback found that writing-quality measures were often unrelated to the feedback the model had been asked for, and that pairing AI with teacher feedback beat either source alone (Crosthwaite & Sun (2026)). The same corpus is overwhelmingly English, at 46 of the 51 studies, with Chinese and Arabic the dominant learner first languages.

This coaching-not-composing stance is the writing-domain expression of the knowledge base's overarching "coach over crutch" boundary: identify the cognitive activity that produces learning (planning, drafting, evaluating, revising) and design the AI to support it without taking it away from the learner.

Connections

Writing education connects to Automated Essay Scoring, AI Feedback Quality, Academic Integrity, Cognitive Offloading, AI Literacy, Language Learning, Formative Assessment, Peer Assessment, Metacognition, Self-Regulated Learning, and Higher Education. It is a domain where AI's capabilities and risks are both highly visible, making it a rich site for studying how AI transforms pedagogy, Assessment, and the very nature of authorship and Learner Agency.

What GenAI demands of the task

Al Nafjan (2026) proposes the Rigor–Commitment Alignment Framework (RCAF), which locates engagement in the writing task and the teaching around it rather than in the tool (Rigor, commitment, and generative AI: a conceptual framework for student engagement in EAP writing). Academic rigor is the demand a task places on sustained cognitive effort and disciplinary reasoning, and the framework splits it into cognitive demand, epistemic authenticity, and performance accountability. Teacher commitment is defined narrowly, as commitment to students' learning enacted through instructional responsiveness, relational support, and critical scaffolding, not as a trait a teacher has or lacks. The author is explicit that the RCAF is propositional and has not been empirically validated, so it is a design vocabulary for writing programs rather than a tested effect.

For task design the claim is that rigor and commitment interact rather than add. High demand with thin support is predicted to push students toward concealment and detection games, while warmth without demand lets fluent output pass for learning. Only the high-demand, high-support configuration is predicted to produce deep engagement, with evaluative judgment doing the work of deciding when output is useful, insufficient, or misleading. Because GenAI can produce acceptable academic prose, the framework gives writing assessment a specific obligation: require visible drafting and revision so that performance stays tied to the thinking it is supposed to represent.

Implications for writing instructors

- **Frame AI as a complement, not a replacement, for the writing process.** The knowledge base's research consistently treats AI as a scaffold for drafting, revision, and feedback while protecting the cognitive work and human audience that make writing a learning activity — coaching over crutch.

- **Use AI feedback within a human-centered process.** PAIRR finds AI feedback is most useful combined with peer review and reflection; design feedback loops that keep the instructor and peer audience central.
- **Students want the human at the high-stakes end.** Yildirim-Erbasli et al. (2026) found 81.7 percent of 93 undergraduates preferred human scoring for a final paper worth 40 percent of the grade, trusted AI for grammar and mechanics but not creative writing, and wanted AI scoring reviewed by a human.
- **Audit automated feedback for bias.** Marked Pedagogies shows LLM feedback shifts in stereotype-aligned ways when personalized with student attributes — monitor for positive/withholding bias, and be explicit that personalization can be a bias vector.
- **Guard the cognitive work of writing.** Watch for over-reliance that bypasses planning, revision, and self-assessment; use AI at chosen stages (stage-based ownership) to protect student agency.
- **Design for empowerment rather than enforcement.** A PLS-SEM study of 327 Chinese EFL undergraduates (Li & Zhang, 2026) tested the two levers writing instructors actually hold and found only one of them works. AI prompting literacy strongly predicted perceived competence, psychological safety, and intrinsic motivation, and all three psychological needs partially mediated its link to deep revision engagement, with intrinsic motivation the strongest single driver of deep revision. External mandates had no direct effect at all. The practical translation is that requiring deep revision does not produce it — the enforcing requirement may be needed to make revision happen at all, but the depth comes from building students' prompting capability and the intrinsic motivation and psychological safety that follow from it.
- **Address academic integrity constructively.** Move from policing AI use toward building AI Literacy and ethical-use framing that lets students use AI without unintentional misconduct.
- **Detection is not an integrity strategy for writing.** Bassett et al. (2026) argue detector scores cannot meet the balance-of-probabilities standard integrity cases require and that the human-or-AI dichotomy misreads work created *with* rather than *by* AI, recommending institutions move budget from detection and surveillance toward assessment design and AI Literacy.
- **"Feedback and the grade are independent outputs."** They are not, and the order matters: told a grade that contradicted the work, **all 22** benchmark models wrote feedback whose tone followed the told grade, and for **eight** the shift per point was at least as large as the shift that came with the work's quality. The measure is a word rule validated on tutoring replies, so it reads tone rather than substance. Produce or check the grade before the feedback is written.
- **"Anonymous marking is only a fairness gesture."** It is also an experimental control, and removing it moved marks. Answers graded with a true or swapped attainment label in the prompt differed by **0.28 to 0.75 points** on a ten-point scale on every model tested, and the shift ran through the student description rather than the work (pooled **rho = +0.84**). A grader told the student's record is not marking the essay alone. Withholding learner context is the automated equivalent of anonymous marking.
- **"Asking for a paragraph and asking for an essay are the same kind of help."** Trace data separates them. Across **361 logged messages** from **77** college essay writers, requests that handed

over planning, drafting and revision at once were the largest category: **137** such queries from more than half the participants. Within it, **20** asked for a whole essay, and **15 of the 77 (19.5%)** submitted essays with no typed words of their own. Asking for a paragraph around an idea was the smallest category, at **10** participants. Coding every query against the writing process shows what a finished essay cannot.

Common Misconceptions

“AI writing support is just faster writing.” Writing is a cognitive, social and rhetorical process, not merely output, which is why AI can displace the very mental work that makes writing a learning activity. The design guidance that follows is *coaching, not composing*: have the system question and critique outlines while the learner produces the prose. A tool that generates the draft has removed the thinking the assignment existed to develop, however good the draft is.

“Better writing assessment needs a bigger model.” It needs more samples. In a Grades 3–6 universal-screening study, LLM comparative-judgment scores converged with researcher rubrics at **r = .59–.73**, and averaging the **three** screening waves raised criterion validity to **β = .68–.74** — an improvement from design rather than scale. Reaching for a larger model when the reliability problem is sampling is the wrong lever.

“AI feedback and peer feedback are substitutes.” They combine. In a 10-week Chinese EFL course, adding ChatGPT feedback *before* peer review lifted behavioral, affective and cognitive engagement (partial η^2 of **0.28 to 0.32**) and improved writing scores across the board. The sequencing is doing work — the AI pass readied students for the peer pass rather than replacing it.

“Students act on AI feedback when it is offered.” Uptake is selective. Weston and Long (2026) tracked two undergraduate biology teams revising a proposal introduction against instructor-built AI feedback: 10 of 22 comments were addressed, deletions outnumbered additions, and the comments requiring students to judge coherence or claim support were ignored entirely.

“A model can stand in for the teacher’s feedback pattern.” It has not done so in the evidence. Tracking one teacher across draft stages found significant movement on **five** feedback focus types — with *Praise* rising from **26.9%** in initial drafts to **84.9%** in final ones — while the closest model moved on three and the smallest on none, and no model replicated the pattern. Teacher feedback reallocates emphasis by draft stage; model feedback tends to hold its distribution. Treating the second as equivalent loses the trajectory.

Connected Concepts

- Automated Essay Scoring
- AI Feedback Quality
- Academic Integrity
- Cognitive Offloading
- AI Literacy
- Language Learning
- Higher Education
- Metacognition

- Large Language Models (LLMs)
- Generative AI
- Formative Assessment
- Peer Assessment
- Self-Regulated Learning
- Student Experience
- Feedback Literacy
- Feedback
- AIEd in the Disciplines
- English Education (EAP / EFL / ESL)
- Assessment
- Learner Agency
- Reflection

Connected Articles

- The Effect of the Process–Genre Approach on AI-assisted and Multimodal Writing — A 32-student quasi-experiment: process–genre instruction raised informative, multimodal and AI-assisted writing (Günay & Özden 2026)
- Generative artificial intelligence in writing assessment: University professors' perspectives and recommendations — 24 writing professors on grading with AI: benefits for feedback, drift in scores, no institutional rule
- Generative AI and L2 Written Feedback Studies: A Scoping Review — 51-study scoping review: prompt transparency gaps and why AI plus teacher beats either alone
- Writing the rules for generative machines: Tensions and entanglements in preservice teachers' classroom AI policies — Preservice teachers' classroom AI policies: tensions and entanglements
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment
- Validity of Large Language Model Comparative Judgment for Universal Writing Screening — Validity of Large Language Model Comparative Judgment for Universal Writing Screening
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Coach not crutch: Evidence that AI can improve writing skill despite reducing effort — AI writing tools can improve writing skill despite reducing effort (Lira et al. 2025)
- LLMs Do Not Grade Essays Like Humans — LLMs do not grade essays like humans (Mathew et al. 2026)
- Peer and AI review + reflection (PAIRR): A human-centered approach to formative assessment — Peer and AI Review + Reflection (PAIRR)

- A posthumanist approach to AI literacy — A Posthumanist Approach to AI Literacy
- Anchor Is the Key: Toward Accessible Automated Essay Scoring with Large Language Models Through Prompting — Anchor-Based Automated Essay Scoring
- AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models — AIAWE: Automated Writing Evaluation
- The agency gap in AI-supported writing: How reactive and proactive agent designs shape multimodal reasoning — The Agency Gap in AI-Supported Writing
- From Planning to Revision: How AI Writing Support at Different Stages Alters Ownership — From Planning to Revision: AI Writing Support at Different Stages
- Comparing Generative AI and teacher feedback: Student perceptions of usefulness and trustworthiness — Comparing Generative AI and Teacher Feedback
- "It's OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — "It's OK Because…": The Wild West of Student Rationalization
- The care-full craft of feedback in an age of generative AI — Care-Full Feedback Approaches
- Towards Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs — Self-Referential L2 Writing Assessment
- AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education — AI Peer Feedback Systems
- Student Evaluation of Repeated AI Feedback Across a Semester of Writing — Student Evaluation of Repeated AI Feedback
- Using AI-Generated Feedback to Improve Critical Thinking and Writing Proficiency — Using AI-Generated Feedback to Improve Critical Thinking
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: linguistic biases in personalized automated writing feedback
- Heads we win, tails you lose: AI detectors in education — Heads we win, tails you lose: AI detectors in education (Bassett et al. 2026)
- Academic erasure: The disappearance of complexity under AI-supported writing — Academic erasure: the disappearance of complexity under AI-supported writing
- More externalization, but less inference? Exploring changes in young learners' critical thinking during conversational AI bot-supported multimodal writing practice — Multimodal AI composing and critical thinking in primary writing (Lu et al. 2027)
- Student Use of and Views on GenAI for Writing — Student use of and views on GenAI for writing (Kuznetsov, Sheely & Baker 2026)
- Exploring the impact of a GenAI-supported writing program on primary students' writing motivation, engagement, and performance: A mixed methods study — A GenAI-supported writing program for primary L2 motivation, engagement and performance (Lu et al. 2026)

- Agreement and error in automated scoring of student marketing posts — Agreement and error in automated scoring of student marketing posts
- Empowerment over enforcement: unpacking the psychological drivers of AI-assisted deep revision in EFL writing — Prompting literacy and intrinsic motivation drive deep revision while external mandates have no direct effect (Li & Zhang 2026)
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing
- Teacher feedback vs. AI-assisted peer feedback in L2 writing: A quasi-experimental study in a Chinese university — Teacher feedback vs. AI-assisted peer feedback as heterogeneous L2 scaffolds in an 8-week quasi-experiment (Tang et al. 2026)
- Effectiveness of GenAI in enhancing writing performance: a meta-analysis — Meta-analysis of GenAI writing performance: large pooled effect, fragile magnitude, methodology over pedagogy (Teng 2026)
- Customizing AI for writing pedagogy: a systematic review of pedagogical goals, theoretical principles, and technical design — Systematic review of AI writing customization and the theory–design mismatch (Luo 2026)
- From tool to scaffold: Structured human–AI collaboration and its effects on academic writing and digital critical thinking among Saudi EFL learners — Structured human–AI collaboration in academic writing and digital critical thinking (Alshehri et al. 2026)
- Human-written and AI-generated revisions: An appraisal analysis of dialogic positioning in argumentative writing — Human and AI revisions of the same draft take different dialogic stances: peer feedback closes dialogic space, AI revision keeps it balanced (Zhao & Ji 2026)
- Who Thinks First? Designing Productive Friction with Engage-to-Unlock GenAI — Engage-to-Unlock: gating AI output on prior engagement redistributed effort to writing without costing time or accuracy (N = 398)
- Generative artificial intelligence-supported self-regulated learning (GenAI-SRL) in L2 writing: scale development, validation, and short-form construction — A six-dimension GenAI-SRL scale for L2 writing, with environmental regulation (tool governance) as a distinct dimension
- AI-peer integrated feedback in second language writing classes: exploring students' engagement and writing performance — Pairing AI with peer feedback raises engagement and writing scores
- When Do Undergraduate Students Prefer AI? Insights into AI Scoring and Feedback — Students want the human at the high-stakes end
- Biology Undergraduates' Use of AI-Enabled Feedback to Revise Scientific Writing: Recipience and Barriers — Biology Undergraduates' Use of AI-Enabled Feedback to Revise Scientific Writing: Recipience and Barriers (Weston and Long 2026)
- Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps — Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps

- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- Learner context changes an LLM grader’s marks on identical work: a within-item ablation on six models — Learner context changes an LLM grader’s marks on identical work, measured in a within-item ablation on six models (Porcaro 2026, Paper VI)
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — Delegation measured from traces: 137 whole-task queries, 15 students submitting essays with no typed words (Jelson et al. 2026)
- Rigor, commitment, and generative AI: a conceptual framework for student engagement in EAP writing — Rigor and teacher commitment as the two dimensions of GenAI-era writing engagement

Connected FAQs

- What Are Best Practices for Writing Instruction in the Context of AI?
- What Are Best Practices for Developing an Effective AI Tutor?

Language Learning

> **Language Learning** — the study of how AI supports second language (L2) acquisition, writing development, and linguistic diversity in educational settings. AI in education research in this knowledge base spans AI interlocutors for spoken dialogue, automated writing evaluation for L2 learners, reading support, and concerns about language bias in AI scoring systems.

Questions to Consider

- Language is inherently interactive, which makes it well-suited to conversational AI — but AI's linguistic capabilities also raise risks of bias against non-native patterns. Where have you seen this tension between opportunity and risk play out?
- One study found AI scoring systematically underestimates linguistically weaker students, while another proposed comparing students to their own prior work rather than native-speaker norms. How does the 'reference point' for evaluation change whether AI feedback helps or penalizes a learner?
- AI interlocutors can extend communicative practice at scale, but the page warns they should pair with human interaction so fluency transfers to real conversation. What might you gain from practicing with an AI that a human partner can't give — and what would you lose?
- Teacher support — not just the AI tool — was shown to drive engagement in AI-assisted language learning through students' achievement goals. How does the social and pedagogical context shape whether learners keep engaging with an AI practice tool?
- A meta-analysis found small-to-moderate, level-dependent gains from emerging tech, with productive skills (speaking, writing) gaining more than receptive ones. Why might speaking and writing benefit more than listening and reading from AI tools?
- If AI privileges standard English and can penalize non-native or diverse language patterns, how should language instructors design evaluation and feedback so AI supports linguistic diversity rather than erasing it?

Introduction

Language learning has emerged as a significant AI in education domain because language is inherently interactive — making it well-suited to conversational AI — and because AI's linguistic capabilities raise both opportunities (personalized language practice at scale) and risks (systematic bias against non-native language patterns). The articles in this knowledge base explore both sides of this equation. Where the target language is **English specifically** — especially English for Academic Purposes (EAP) and EFL/ESL/L2 English teaching — see the dedicated English Education (EAP / EFL / ESL) concept page, which distinguishes English-specific research from general L2 acquisition and general writing.

AI as language tutor and interlocutor is the most developed theme. **What Changes When the Interlocutor Is an AI?** examines interactional fluency and linguistic uptake when L2 learners converse with AI versus humans. **TACT** provides pedagogically adaptive ESL tutoring. **Children's English reading story**

generation via supervised fine-tuning of compact LLMs with controllable difficulty and safety explores AI-generated stories for children's reading development. These connect to Intelligent Tutoring and Generative AI. **Yang, Weng and Yang (2026)** designed two Large Language Models (LLMs)-based agents — a conventional AI English teacher and one using the **5E framework** (engage, explore, explain, elaborate, evaluate) for inquiry-based grammar learning. Across **37 ESL students** in a randomized comparison, **high-performing students responded positively to the AI teacher** while low-performing students showed mixed attitudes, and the conditions differed in intrinsic motivation, cognitive change, and performance — indicating that LLM-agent design should be matched to learner proficiency.

For physically embodied tutors, a meta-analysis of 11 RALL studies (N = 595) found a large pooled effect on L2 learning (g = 0.83) with high heterogeneity, and only interaction format moderated it — group-based formats beat one-on-one while robot morphology, modality, autonomy, and social role did not (Wang, Zhang & Zou (2026)).

AI in language assessment is emerging as LLMs support item generation and evaluation. **Aryadoust and Wong (2026)** compared prompt engineering against fine-tuning for automatic item generation in L2 listening assessment: iterative prompt refinement improved item quality but plateaued, while **fine-tuning GPT-4.1 on the optimized prompt** (holding prompt design constant) yielded further gains — a template for when assessment developers should invest in model adaptation over prompt iteration.

A comparison of 52 EFL assessment tasks rated by 20 experienced teachers found no significant quality difference overall between AI-generated and human-developed items, but a clear division of labor: AI was preferred for grammar and vocabulary (69%) and human development for reading, writing, listening and speaking (75–83%) (Nourashrafi, Alavinia and Darvishi (2026)).

Automated writing evaluation for L2 learners evaluates AI's ability to assess non-native writing. **Bannò et al.** proposed a self-referential approach comparing student writing to their own prior work rather than native-speaker norms. **Feser & Tschisgale** found AI scoring systematically underestimates linguistically weak students — a finding that connects to Assessment Validity and Bias Mitigation concerns. **Generative AI and linguistic diversity in academic writing and publishing: Perspectives from World Englishes** explores how AI affects linguistic diversity in academic contexts.

A discourse-level system goes further by naming the defect rather than scoring the text: sentence-pair relation classification localized coherence breaks - logical jumps, missing connectives, ambiguous reference - and teacher-judged adoption of its generated feedback ran 71.2%-88.4% (Wang et al., 2026).

Accessibility for language learners connects to Inclusive Learning: **DysLexLens** analyzed how dyslexic learners use AI for literacy support, and **AI tools in Arab University English classrooms: Looking back and forward** explored AI tools in Arabic-English classroom contexts. These studies connect language learning to Equity and Special Education.

Motivational mechanisms in AI-assisted language learning examine why learners engage with AI for language practice. **Wang & Wang (2026)** used goal-setting theory with 758 Chinese university English learners to show that **teacher support** enhances engagement in AI-assisted learning through students' mastery-approach and performance-approach goals (not avoidance goals) — evidence that the pedagogical and social context, not just the AI tool, determines whether learners stay engaged with AI-assisted language practice. This connects language learning to Motivation and Student Engagement.

Annamalai et al. (2026) add a qualitative self-determination case: in interviews with 25 Malaysian undergraduates, ChatGPT supported competence and autonomy, and its conversational responsiveness produced a sense of being heard — an "AI-mediated motivational ecology" in which relatedness is partly met by the tool, though inaccurate references demanded verification and human complement.

Design quality, not usage frequency, carried the motivational effect in an instructor-built tutor: across 74 undergraduates using a course-scoped Japanese GPT, out-of-class usage frequency showed no significant correlation with autonomy, competence, or relatedness, while learners rated the tutor highly for self-directed learning (M = 4.39) and cited affective safety (60.8%) (Lee & Kwon, 2026).

GenAI-supported writing at the primary level. Lu et al. (2026) ran a nine-week opinion-writing program with 301 Grade 5 and 6 learners in Eastern China, with eight intact classes randomly assigned to the program or to conventional instruction. The program raised learners' ideal L2 writing self (adjusted mean difference 0.20) and academic buoyancy (0.17), and lifted behavioral and emotional engagement, but it did not move growth mindset, cognitive or metacognitive engagement, or rubric-scored organization — among writing dimensions only language use improved. Two features of the design matter for language teachers: prompting was taught explicitly, through a categorized bank of prompts tied to specific writing goals, and GenAI feedback was used alongside comparison with teacher feedback and repeated revision. The authorship gains learners reported rested on that instructional structure rather than on the tool by itself, and the authors name reduced self-monitoring and shortcut-oriented strategies as the standing risks.

GenAI grammar instruction works through revision, not commentary. In a ten-week quasi-experiment with 88 Ethiopian EFL students, draft–prompt–reflect–revise cycles raised grammar ($\eta^2 = 0.499$) and overall writing, and content scores rose although the prompt barred content feedback (Wordofa & Abo, 2026).

Implications for language instructors

- **Emerging technologies yield small-to-moderate, level-dependent gains.** A meta-analysis of 33 TEFL studies (N = 3,181) finds an overall effect of Hedges' g = 0.38 that rises with educational level (primary 0.29, secondary 0.35, tertiary 0.44), with VR/AR yielding the largest effects and productive skills (speaking, writing) gaining more than receptive skills — supporting the use of emerging tech, especially at tertiary level, while keeping expectations realistic.
- **A systematic review maps where elementary AI language education is thin.** Across 31 studies (2013-2025), work in elementary language classrooms clustered on speaking, literacy and vocabulary while grammar, listening comprehension and sign language were barely studied, and most designs lacked grade-level specificity (Hamasha et al., 2026).
- **Use AI to extend communicative practice, not replace it.** AI interlocutors and adaptive ESL tutors expand interactional practice at scale — pair them with human interaction so fluency and uptake transfer to real conversation.
- **Extend AI Scaffolding to collaborative reading.** With 63 Chinese English majors in a GenAI-assisted social annotation study, Pan et al. (2026) found that the chatbot raised cognitive and emotional engagement and reading performance and tied social presence to integration and resolution, though high-achieving groups used the scaffold far more.

- **Readiness, not observed performance.** Across 708 learners, greater AI-assisted speaking practice tracked higher human-directed willingness to communicate (β = 0.384) and lower foreign-language speaking anxiety (β = −0.416), while AI voice-assistant scenarios lowered anticipated anxiety further; neither study observed actual human speaking (Wang & Li (2026)).
- **Watch AI output for pragmatic, not just grammatical, error.** Teachers across five online language-teaching methods named pragmatic blindness, where AI output is grammatically correct but wrong in tone, formality or culture (Baoyi and Khan (2026)).
- **Prioritize feedback quality over quantity in ASR-supported speaking.** Chen et al. (2026) find that accurate error correction and structured reflection tasks improve Feedback internalization and reflective behavior in college English speaking, while frequent ASR use and recognition accuracy boost motivation or reflection only partially — technical precision alone does not drive deeper cognitive engagement, and language proficiency moderates the gains (stronger learners internalize feedback more effectively). This argues for pedagogically sound feedback (e.g., articulatory explanations over simple error flags), scaffolded reflection, and proficiency-differentiated support.
- **Give clues before corrections.** A 'clue before correction' ChatGPT task, in which learners infer fixes from guided hints rather than receiving direct corrections, reduced cognitive load and supported personalized revision — but the benefit held mainly for learners who already had enough prior knowledge (58 students, CEFR A1–B1) (Lukešová & Jennings (2026)).
- **Deliver pronunciation feedback that localises the difference to close.** Profy learns proficiency from largely unannotated speech and shows *where* a learner diverges from native-speaker distributions; its pre/post intelligibility confidence intervals did not overlap, unlike an elicited-imitation baseline — evidence that imitation practice can be supported without expert raters (Kawamura (2026)).
- **Use the transcript channel as a second signal, not a substitute.** A WavLM audio classifier beat a zero-shot GPT-4o classifier reading transcripts on a CEFR-balanced learner corpus, so lexical traces of a first language are real but weaker than pronunciation, rhythm and intonation (Uluslu et al. (2026)).
- **Support learners' psychological adaptation to AI-assisted study.** Wu (2026) tracks learners of Japanese over a semester and finds they sort into maladaptive, moderate, and positive adaptation profiles driven by the balance of technostress and resilience, with most learners gradually shifting toward positive adaptation and reporting higher Self-Efficacy and lower burnout — a signal to design AI-mediated language practice that manages technological strain, not just tool access.
- **Be alert to scoring and feedback bias against learners.** AI scoring can penalize non-native patterns; linguistic-diversity research warns AI privileges standard English — use self-referential or human-moderated evaluation.
- **Support the full spectrum of learners.** Dyslexia and accessibility studies and culturally responsive design (Arab-English contexts) show AI must be adapted to diverse learner needs, not assumed universal.
- **Infrastructure, not just scoring, excludes languages.** Bengali holds under 0.5% of global web content against a 67:1 English-to-Bengali training-token deficit and a rural–urban connectivity gap

(36.5% vs 71.4% internet penetration), so native-language, offline-first design is a prerequisite for access rather than a convenience (Roy and Roy (2026)).

- **Educators value GenAI for preparatory work, not live classroom use.** A PRISMA systematic review of 23 studies (Li et al. 2026) finds language educators most value GenAI for behind-the-scenes preparation — lesson planning, materials creation, and writing support/feedback — yet remain hesitant about direct, classroom-facing implementation, reflecting a theory–practice gap between approving AI in principle and using it live. Adoption is shaped by professional-identity, pedagogical, technical, institutional, and Academic Integrity factors, with educators falling on a spectrum from non-adoption to comprehensive integration; attitudes tend to evolve from initial insecurity toward confident, selective use with exposure.
- **Prepare language teachers' AI literacy.** Systematic reviews find AI literacy among language teachers is a key gap — invest in teacher professional development alongside tool adoption. As AI reshapes language education, AI literacy is also crucial for teachers to engage critically with the technology: the Teachers' AI Literacy Scale (TAILS) was developed for language teacher education, operationalizing the six-dimension ED-AI framework (knowledge, evaluation, collaboration, contextualization, autonomy, Ethics) and validated with preservice English language teachers.
- **Four interaction profiles in a high-pressure bilingual task.** Kuang, Li and Weng (2026) used eye-tracking, pen-recording and voice-recording with 22 interpreting trainees to show that students divide attention between AI output and their own note-taking in four distinct ways — Intensive Engagers, Fast Scanners, Traditionalists and Frequent Switchers — and that 58.3% of stage-level observations changed profile between the comprehension and production stages of the same task. Only comprehension-stage patterns predicted product quality, and the AI-heaviest cluster scored lowest on fluency of delivery and target language quality, which makes the case for teaching learners to describe and reflect on their own strategy rather than prescribing one way of working with the tool.
- **Route the full four-skill loop around cost and connectivity.** Guo et al. (2026) release LLMersion-1, a local-first prototype that works listening, reading, speaking and writing over the learner's own document on consumer hardware — a 1B tutor quantizes to 808 MB and the whole resident stack stays under 4 GB — and prices five years of daily practice at roughly $18 of electricity, against $1,200 for a cloud subscription. No learner outcomes are reported and pronunciation feedback is segmental only.
- **Evidence on chatbot speaking gains is uneven by feature.** In the only systematic synthesis of the question, ten studies from 2021 to 2024 improved range and intelligibility most reliably, while coherence was examined once and interaction almost never; four of the ten reported a single holistic score (Soriano-Gonzalez & Belda-Medina (2026)).

Translation students can be moved off surface correction. In a news translation course, Xian et al. (2026) found search-engine consultation rising from a median of 15.6% to 27.7% of session time ($p = 0.020$, Holm-corrected) and knowledge-based searching from 7.2% to 28.8% ($p = 0.010$). Machine translation use fell from 28.5% to 5.1% without reaching significance ($p = 0.338$), and interactive AI use stayed at a median of zero. The lever was showing students their own process rather than banning a tool.

Common Misconceptions

- **“Embodied robot tutors work because of the embodiment.”** A meta-analysis of **11 RALL studies (N = 595)** found a large pooled effect on L2 learning (**g = 0.83**) with **high heterogeneity**, and — importantly — **only interaction**-level features moderated it. Morphology and modality did not, so the hardware is not the active ingredient.
- **“AI-generated assessment items are worse than teacher-written ones.”** A comparison of **52 EFL assessment tasks rated by 20 experienced teachers** found **no significant quality difference overall** between AI-generated and human-developed items, but divergence on particular dimensions. Overall parity with specific weaknesses is a different claim from improvement or deficiency.
- **“LLM feedback can only score writing.”** A discourse-level system goes further by **naming the defect rather than scoring the text**, with sentence-pair relation classification localising **coherence breaks** such as logical jumps and missing links. The useful output is diagnostic, not numeric.

Connected Concepts

- E-Portfolio
- Writing
- AI Literacy
- Equity
- Assessment Validity
- Bias Mitigation
- Inclusive Learning
- Special Education
- Intelligent Tutoring
- Generative AI
- Student Experience
- Higher Education
- K-12
- AIEd in the Disciplines
- English Education (EAP / EFL / ESL)
- Speech and Voice Technologies

Connected Articles

- Chatbots for oral proficiency in English language learning: A systematic review — Chatbot gains in oral proficiency concentrate in range and intelligibility
- Student-AI interaction in computer-assisted consecutive interpreting: patterns and performance — Student-AI Interaction in Computer-Assisted Consecutive Interpreting

- Profiles and transitions of psychological adaptation in AI-assisted Japanese language learning — Profiles and Transitions of Psychological Adaptation in AI-Assisted Japanese Language Learning
- Designing large language model-based agents with 5E framework for ESL learners' grammar acquisition — LLM agents with 5E framework for ESL grammar acquisition (Yang, Weng & Yang 2026)
- How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment — Prompting vs. fine-tuning GPT for L2 listening item generation (Aryadoust & Wong 2026)
- Automatic discourse relation classification and feedback optimization in English teaching based on transformer BERT model — BERT discourse classification for English teaching
- AI-Generated versus Human-Developed Assessment Tasks in EFL Context: Insights from TPCK Model — AI-generated vs human-developed assessment tasks in EFL
- Governing the Unseen: A Systematic Review of AI Literacy among Language Teachers in Higher Education — Governing the unseen: AI literacy among language teachers
- AI-guided learning: Research on knowledge and skill acquisition support methods using deep learning audio-video processing techniques
- What Changes When the Interlocutor Is an AI? Interactional Fluency and Linguistic Uptake in L2 Spoken Dialogue
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis — Meta-analysis of AI-enhanced embodied robot-assisted language learning
- Towards Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics
- Generative AI and linguistic diversity in academic writing and publishing: Perspectives from World Englishes
- DysLexLens: A Low-Resource LLM Framework for Analysing Dyslexic Learners Insights from Online Forums
- TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring
- AI tools in Arab University English classrooms: Looking back and forward
- Structural silence: When AI infrastructure fails speakers of underrepresented languages
- Instructor-Designed AI Tutors in University Foreign Language Education: A Mixed-Methods Study of Learner Motivation and Reflective Learning Experience Based on Self-Determination Theory — Instructor-Designed AI Tutors in University Foreign Language Education: A Mixed-Methods Study of Learner Motivation and Reflective Learning Experience Based on Self-Determination Theory

- Clue before correction: ChatGPT-enhanced strategy for promoting autonomous and reflective language learning — Clue Before Correction: ChatGPT for Autonomous Language Learning
- Students' experiences of using ChatGPT for English language learning: A qualitative study in a Malaysian higher education institution — Students' ChatGPT experiences in English language learning
- A systematic review of emerging technology applications for teaching English as a foreign language across different educational levels — Meta-analysis of emerging tech for EFL
- Explaining learning engagement in AI-assisted learning through teacher support and achievement goals: insights from goal-setting theory — Goal-setting theory: teacher support, achievement goals, and engagement in AI-assisted English learning (758 Chinese students)
- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- ASR Technology in College English Speaking Instruction: The Role of Feedback Internalization and Metacognitive Strategies — ASR technology in college English speaking: feedback internalization and metacognitive strategies
- Exploring the impact of a GenAI-supported writing program on primary students' writing motivation, engagement, and performance: A mixed methods study — A GenAI-supported writing program for primary L2 learners (Lu et al. 2026)
- LLMersion: A Local-First AI Agent Framework for Low-Cost Home Language Learning toward Educational Equity — LLMersion: A Local-First AI Agent Framework for Low-Cost Home Language Learning toward Educational Equity
- AI and higher education: teachers' perceptions of students' ethical tensions in online pedagogical methods — Pragmatic blindness: AI language output can be grammatically correct but culturally wrong
- AI-Assisted Speaking Practice and Human-Directed Communicative Readiness: Survey and Scenario Evidence on Anxiety, Self-Efficacy, and Evaluation Pressure — Readiness, not observed performance
- Unpacking student interactions in GenAI-assisted social annotation: An epistemic network analysis of cognitive and social presence — Extend AI scaffolding to collaborative reading
- Acoustic and Lexical Signals for Native Language Identification of Language Learners — Audio beats a zero-shot GPT-4o transcript classifier for L1 identification (Uluslu et al. 2026)
- Process visualization feedback in news translation: a controlled intervention study of human-AI interaction using multimodal process data - process feedback raised source consultation and cut machine translation use in a news translation course
- Effects of generative AI assisted grammar instruction on Ethiopian EFL learners' self-efficacy, metalinguistic awareness, and writing performance — Generative AI assisted grammar instruction and Ethiopian EFL learners' self-efficacy and metalinguistic awareness

English Education (EAP / EFL / ESL)

> **English education** — the application of AI to the teaching and learning of English, especially **English for Academic Purposes (EAP)** and English language teaching more broadly (EFL/ESL/L2). This is a discipline-specific AIEd strand distinct from both general Language Learning (second/foreign-language acquisition of any language) and Writing (writing as a general skill): it centers on English as a target language and academic register, with its own signature pedagogies — communicative competence, genre-based academic writing, corrective feedback, and reading/writing in an academic register — that shape how AI is designed, used, and evaluated.

Questions to Consider

- English is the language large language models handle best. That gives English learners powerful scaffolding for academic writing — but could it also quietly entrench a bias toward standard academic English that marginalizes multilingual and World Englishes writers? Which outcome do you think dominates?
- English for Academic Purposes (EAP) centers on genre-based academic writing, corrective feedback, and academic register — distinct from general language learning or general writing instruction. Why might the specific register of academic English change what AI tools need to do versus generic writing support?
- If the AI that revises your English is itself strongest in the very ‘standard academic English’ you’re trying to master, when does that help and when does it flatten your own voice or dialect? How would you tell the difference?
- Automated feedback and AI tutors are increasingly common in English writing and speaking instruction. What might AI feedback miss about communicative competence, register, and audience that a human instructor or peer would catch?

Introduction

English is one of the most AI-affected discipline strands because LLMs are English-dominant: they are strongest at generating, revising, and evaluating English text, which is exactly what EAP and EFL/ESL instruction centers on. That English-advantage creates a distinctive double edge — powerful Scaffolding for academic English on one hand, and an entrenched bias toward standard academic English that can marginalize multilingual learners on the other.

Scope and focus

This concept organizes AI research in **English education** — the subset of language learning where the target language is English (including EFL/ESL/L2 contexts) and the academic-English register (EAP). Core themes:

- **Academic English (EAP):** AI support for the genre-based, discipline-specific English used in higher-education writing, reading, and feedback — distinct from general writing instruction.
- **English language teaching (EFL/ESL/L2):** AI tutors, interlocutors, and Feedback tools for learners acquiring English.
- **English-specific Assessment:** automated evaluation and feedback on English writing and speaking, including EAP writing revision and L2 writing assessment.
- **Reading and literature readability:** Bird (2026) fuses transformer text classification with computational-linguistics features to classify English literature by UK Key Stage, reaching an F1 of 0.996 — a scalable, data-driven complement to genre-based EAP reading support and reading-level alignment.
- **Linguistic equity:** the tension between AI's English dominance and the needs of multilingual and World Englishes writers.

How English education differs from Language Learning

Language Learning is the broader umbrella for acquiring any second/foreign language — spoken, written, and literate — via AI interlocutors, pronunciation tools, and conversational practice. English education is the **English-specific** case, and within it, EAP is a **register-specific** case:

Dimension	Language Learning	English education (this page)
Target language	Any L2 (French, Spanish, Japanese, …)	English specifically
Focus	L2 acquisition generally: spoken dialogue, pronunciation, literacy	English as a target + the academic-English register
Signature contexts	Conversation, pronunciation, general fluency	**EAP**: academic writing, reading, feedback, genre
Representative AI	L2 interlocutors, pronunciation feedback, robot-assisted L2	EAP writing tools, EFL peer-feedback, English academic writing assessment

The two overlap heavily (most English learning is also L2 acquisition), but English education foregrounds English as the target and the academic register — e.g., ethical GenAI integration in EAP, GenAI EAP writing revision, and EAP reading-material adaptation are EAP-specific in ways generic language-learning research is not.

How English education differs from Writing Education

Writing concerns writing as a general cognitive and rhetorical skill — across all languages and disciplines, from composition to academic integrity. English education focuses specifically on **English** and, within EAP, on the **academic register**:

Dimension	Writing	English education (this page)
Scope	Writing in general (any language, any genre)	English as target language + academic English register
Signature concern	Composition, revision, Learner Agency, authorship	EAP genre, academic register, L2/EFL writing, feedback literacy in English
Assessment angle	Automated essay scoring, writing feedback broadly	English-specific assessment (EAP writing, EFL peer feedback, L2 writing evaluation)
Equity angle	Bias in writing feedback	Bias + the English-dominance/multilingual tension (World Englishes)

Many writing-education articles are English-first (e.g., Marked Pedagogies), but they are framed as general writing research; English education re-centers the **English-as-target** and **academic-English** dimensions that generic writing and generic language-learning pages underemphasize.

Articles in this cluster

- **EAP-specific:** Ethical GenAI integration in EAP, GenAI EAP writing revision, EAP reading-material adaptation.
- **EFL/ESL/L2:** TACT ESL tutoring, ChatGPT EFL e-portfolio speaking, EFL peer-feedback literacy, AI vs human EFL assessment, acceptance of AI English tools, AI in Arab English classrooms, appraisal analysis of peer and AI revisions of EFL argumentative essays.
- **L2 English writing/assessment:** self-referential L2 writing assessment, L2 spoken-dialogue interlocutors.
- **Linguistic equity / World Englishes:** GenAI and linguistic diversity in academic writing, AI literacy among language teachers, underrepresented languages in AI infrastructure.

Why it matters

AI's English dominance is a defining feature of this strand. Because models are strongest in English and in standard academic English specifically, English education both benefits disproportionately (powerful EAP scaffolds) and carries distinctive risks (monolingual bias, discrimination against World Englishes and multilingual writers). Research here connects to equity, bias mitigation, automated assessment, AI feedback quality, and academic integrity.

A Scopus-based synthesis of 54 EFL studies locates the field's most-reported limitations in learner autonomy: overreliance on AI in 27 studies (50%) and reduced critical thinking in 25 (46%), against unreliable AI-generated output in 22 (41%) as the leading technical problem (Espinoza-Celi & Vargas-Saritama (2026)).

Implications for English / EAP / EFL-ESL instructors

- **Exploit AI's strength for academic English, deliberately.** Because models are strongest in English and standard academic English, EAP instructors can deploy AI for genre-based writing, reading-material differentiation (EAP materials), and revision feedback — but should frame AI as a drafting/feedback partner, not an answer engine.
- **Protect academic-English register and feedback literacy.** EAP writing revision shows feedback is only as productive as the learner's feedback literacy — teach students to interpret, judge, and act on AI feedback, and use second-rater mechanisms to check AI quality.
- **Watch the English-dominance equity tension.** Models privilege standard academic English, marginalizing World Englishes and multilingual writers (World Englishes, Marked Pedagogies) — audit feedback for monolingual bias and lowered expectations.
- **Integrate AI ethically into EAP.** Ethical GenAI in EAP calls for transparent, responsible use in Higher Education English teaching that preserves academic integrity.
- **Expect cautious, preparatory-first adoption.** A systematic review of 23 studies (Li et al. 2026) finds language educators value GenAI most for behind-the-scenes preparation — lesson planning, materials creation, and writing support/feedback — while hesitating on direct classroom use, with primary concerns centering on academic integrity (plagiarism and assessment validity). Adoption is shaped by professional-identity, pedagogical, technical, institutional, and integrity factors, and competency gaps map to episteme (understanding AI's capabilities/limits), techne (Prompt Engineering, AI-enhanced task/assessment design, detecting AI-generated text), and phronesis (ethical judgment, bias/privacy handling) — so EAP/EFL instructors should build these competencies deliberately and plan a "back-end then classroom" implementation.
- **Differentiate by proficiency and need.** EFL assessment and adaptive tutoring research support tailoring AI support and evaluation to learners' level rather than one-size-fits-all.
- **Weight technology toward production.** Across 33 TEFL studies, the pooled estimate was small-to-moderate (g = 0.38, reduced to 0.28 by trim-and-fill) and rose with educational level, favoring productive skills — speaking and writing — over receptive ones (Liu, Hashim & Sulaiman (2026)).

Common Misconceptions

- **"In EFL, AI mainly threatens cheating."** The field's own most-reported limitation is **learner autonomy**, appearing as overreliance in **27** of a **54-study** Scopus-based synthesis. The documented cost is dependence rather than dishonesty, which calls for a different intervention.
- **"Language teachers adopt enthusiastically or not at all."** A systematic review of 23 studies (Li et al.) finds **cautious, preparatory-first adoption** as the pattern. Teachers were wary in a considered way, not divided into enthusiasts and refusers.
- **"The overall effect justifies the effort."** A meta-analysis of **33 TEFL studies** found a **small-to-moderate overall effect (g = 0.38, reduced to 0.28 by trim-and-fill)** that **rose with educational**

level. The effect is modest after correction and concentrated at higher levels, so a claim for beginning learners is not supported by the pooled figure.

- **"Any AI use is equally productive for language learning."** The same work argues for **weighting technology toward production** — writing and speaking rather than consumption. The modality determined the effect more than the presence of AI.

Connected Concepts

- Language Learning
- Writing
- Multilingual Learning
- Higher Education
- K-12
- Generative AI
- Large Language Models (LLMs)
- Automated Assessment
- AI Feedback Quality
- Feedback Literacy
- Equity
- Bias Mitigation
- Academic Integrity
- AIEd in the Disciplines

Connected Articles

- Ethical Generative AI integration in English for Academic Purposes within higher education: A mixed-methods study — Ethical Generative AI Integration in EAP within Higher Education
- Effects of feedback literacy scripts and a second-rater mechanism on EAP writing revision in generative AI-supported contexts — Feedback Literacy Scripts and a Second-Rater Mechanism in GenAI EAP Writing Revision
- From unified to differentiated materials: Generative AI–supported adaptation of EAP reading materials — From Unified to Differentiated Materials: GenAI-Supported Adaptation of EAP Reading Materials
- TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring — TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring
- Aligning ChatGPT with e-portfolio assessment as EFL learning model: its effect on students' speaking performance and feedback literacy — Aligning ChatGPT with E-Portfolio Assessment as EFL Learning Model
- Positioning generative AI in EFL peer feedback: Training feedback literacy and enabling uptake in speaking classes — Positioning Generative AI in EFL Peer Feedback

- AI-Generated versus Human-Developed Assessment Tasks in EFL Context: Insights from TPCK Model — AI-Generated versus Human-Developed Assessment Tasks in EFL Context
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — Acceptance of AI-Assisted English Language Learning Tools in Higher Education
- AI tools in Arab University English classrooms: Looking back and forward — AI tools in Arab University English classrooms
- Towards Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs — Toward Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs
- What Changes When the Interlocutor Is an AI? Interactional Fluency and Linguistic Uptake in L2 Spoken Dialogue — What Changes When the Interlocutor Is an AI? L2 Spoken Dialogue
- Generative AI and linguistic diversity in academic writing and publishing: Perspectives from World Englishes — Generative AI and Linguistic Diversity in Academic Writing and Publishing
- Governing the Unseen: A Systematic Review of AI Literacy among Language Teachers in Higher Education — Governing the Unseen: AI Literacy among Language Teachers
- Structural silence: When AI infrastructure fails speakers of underrepresented languages — Structural Silence: Underrepresented Languages in AI Infrastructure
- A systematic review of emerging technology applications for teaching English as a foreign language across different educational levels — Emerging technologies for TEFL
- What differentiates educational literature? A multimodal fusion approach of transformers and computational linguistics — Multimodal fusion for classifying educational literature
- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- Human-written and AI-generated revisions: An appraisal analysis of dialogic positioning in argumentative writing — Peer and AI revisions of EFL argumentative essays differ in dialogic positioning (Zhao & Ji 2026)
- Technical and pedagogical limitations of artificial intelligence in undergraduate EFL higher education: a systematic review — Overreliance on AI (50% of 54 studies) and reduced critical thinking lead the reported limitations

Environmental Education

> **Environmental Education** — teaching about climate, sustainability and the natural world, which in AI in education has become two things at once: a subject that AI can support through inquiry and situated learning, and a cost that AI imposes, since energy-intensive language models run on every student laptop carry an environmental footprint of their own. The knowledge base treats both halves together, because Sustainability education delivered by a carbon-intensive tool raises a question no single frame answers on its own.

Questions to Consider

- "AI and environmental education" can mean two very different things: using AI to teach *about* climate and sustainability, and reducing the environmental cost of *using AI* in classrooms. Which do you hear in your institution — and which has a budget line attached?
- If a university teaches climate science with an energy-intensive large language model on every student laptop, has it advanced environmental education or undercut it? What would have to be true for the answer to be "both"?
- One experiment found AI-assisted inquiry improved climate decision-making over inquiry alone, with gains concentrated on the weakest steps. Would you trust an AI-supported climate unit in your classroom, and what would you need to see first?
- Nearly no AIED papers report their compute or carbon footprint. Is unreported Sustainability impact a research problem, a procurement problem, a teaching problem, or none of these?

Introduction

Environmental education develops learners' understanding of ecological systems, climate, and human–environment interdependence, together with the dispositions and competences to act on them — often framed institutionally as Education for Sustainable Development (ESD) or "green education." In an AI-in-education context the term carries a tension the corpus runs into without always naming: **AI as a tool for environmental education** (teaching climate and sustainability content with generative tools) and **the environmental footprint of AI itself** (the carbon, water, and energy cost of the models institutions deploy). These are different questions with different evidence, actors, and remedies; conflating them — as several papers and most strategy documents do — makes it impossible to say who is accountable for what.(A Scoping Review of AI for Sustainability and Sustainable AI in Higher Education)(The Environmental Cost of LLMs in AIED: Reporting and Practices)

Two things called "environmental education with AI"

- **AI for environmental education** — using AI to teach environmental content, build sustainability consciousness, or support green skills. This half has frameworks, a teacher-survey study, and one classroom experiment.

- **The footprint of AI in education** — emissions and resource use of the models and infrastructure used for teaching, whatever the subject. This half has one review of reporting practice, one engineering Benchmark, and one small interface study — and nothing on the footprint of AI used for environmental education specifically.

A third, weaker strand treats "sustainable learning" as a pedagogical property rather than an environmental one: learning that persists and transfers rather than being short-circuited by Cognitive Offloading. It shares sustainability's vocabulary but is not an environmental claim.(Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era)

Teaching environmental and climate topics with AI

The strongest evidence is a three-group quasi-experiment using climate change as a socio-scientific issue. Students working with an AI partner inside a structured inquiry task outperformed inquiry-only peers (d = 0.69) and traditional instruction (d = 1.88) on a decision-making rubric, with the largest gains on steps students entered weakest — monitoring and adaptive management, and generating alternatives. The AI condition was *additional to* inquiry rather than a replacement, and data collection and analysis did not separate the groups at all, suggesting the AI supported reasoning about trade-offs rather than evidence gathering.(Can AI-Assisted Inquiry Enhance Students' Decision-Making Skills in Socio-Scientific Issues? A Three-Group Experimental Study on Climate Change)

At curriculum level, the AI-SEE framework integrates AI across an engineering curriculum on four pillars (intelligence-driven, green-empowered, responsibility-leading, practice-integrated) rather than as a bolt-on sustainability module; a 144-student pilot reported gains in sustainability consciousness and behavioral engagement across personal, academic, professional, and social levels. The authors caution that this is single-institution, self-reported, single-time-point interview evidence from one Chinese transportation program. (Enhancing Sustainability Consciousness in Higher Education: Impacts of Artificial Intelligence-Integrated Sustainable Engineering Education)

Two smaller studies cover the design side. AI-assisted instructional design under Sustainable Development Pedagogy constraints improved pre-service teachers' lesson plans with an implausibly large effect (d = 2.80, 28 teams, no control group). Separately, a structural-equation study of 122 in-service teachers found *practical* AI use on science and green-energy tasks plus involvement in developing ESD-aligned materials predicted AI-integration capability, while abstract AI knowledge and attitudes did not — though a dichotomous questionnaire and a weak knowledge construct limit how far it travels.(The Role of Artificial Intelligence in Green Education: Optimizing Teacher Workflow and Enhancing Pedagogical Design under Sustainable Development Pedagogy (SDP) Constraints)(Teacher Involvement in Developing Sustainable Education Materials for AI Integration in Green Energy Education)

The environmental footprint of AI in education

This half is where the corpus is thinnest. A review of all 396 AIED 2025 proceedings papers found "LLM adoption without disclosure": most projects use LLMs, 85 papers reported any computational cost, and only 57 mentioned environmental impact — using incompatible metrics, so the field cannot aggregate its own evidence. The authors argue that failing to report environmental cost is itself an ethical concern, and propose

an Open Source method (CodeCarbon plus a two-parameter FLOPs estimate for proprietary models).(The Environmental Cost of LLMs in AIED: Reporting and Practices)

On the learner side, an eco-feedback interface exposing the latency–carbon trade-off during live LLM use was studied with 89 computer science undergraduates in a computing ethics course: students chose the lower-carbon mode in roughly 45% of low-latency interactions but under 5% at high latency, and sustainability awareness significantly raised that choice. The sample is small and unusually technically informed, but it is the only direct evidence in the corpus that footprint information moves learners at all — and it suggests the binding constraint is patience, not values.(When LLMs Slow Down: How Environmental Impacts Mediate University Students' LLM Usage)

Mitigation evidence comes from an on-premise CS knowledge-base assistant on a single consumer GPU (12 GB VRAM) with openly licensed content: 1.8 mWh per query at best — about 0.54 Wh for a class of 30 students submitting ten queries each — with quantization-aware fine-tuning containing both the accuracy loss and the hallucination rise that compression alone caused. It is an engineering benchmark, not a learning study, but it shows the footprint question has design levers (grounding, quantization, deployment location), not only usage-discipline levers.(Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources)

Green skills, sustainability consciousness, and teacher capacity

Together these studies describe a green-skills agenda delivered unevenly: sustainability consciousness as a curricular outcome, ESD-aligned material development as the mechanism for teacher capability, and climate decision-making as a measurable reasoning skill. The value-critical strand supplies the caveat: a conceptual analysis argues AI's contribution to sustainable education is **conditional and governance-mediated**, supporting sustainability only when adoption is subordinated to explicit educational values and human-centered purposes — which places AI Governance and critical pedagogy inside environmental education rather than beside it.(Sustainable Education in the Age of Artificial Intelligence and Digitalization: A Value-Critical Approach)

The scoping review organizing this literature supplies the field's own verdict on scale: applications cluster around energy management, climate monitoring, and green-campus programs, but are limited in scale, often lack ethical or environmental guidelines, and much of the research remains conceptual or small-pilot. Coverage is skewed toward North America and Europe, with almost nothing from the Global South beyond a few South African studies.(A Scoping Review of AI for Sustainability and Sustainable AI in Higher Education)

What the evidence does not yet establish

- **No footprint evidence for environmental education specifically.** Carbon and energy figures come from general LLM studies and a CS-context benchmark; nothing measures the environmental cost of an AI-supported climate or ESD curriculum.
- **No learning-gain evidence for footprint interventions.** Eco-feedback changed choices in a lab-like study; nothing shows it changes habits, assessment outcomes, or procurement.

- **No causal evidence for the curriculum frameworks.** AI-SEE is a single-site self-report case and E3-HOT a design blueprint with no implemented study; the SDP lesson-design result has no control group.
- **No large-scale or cross-context evidence.** Every empirical result here is single-site, and the teacher studies rest on small purposive samples with weak instruments.
- **The two halves are rarely studied together**, even though both bear on the same classroom.

Implications for AI in education

1. **Name which question you are answering.** Strategies that use "sustainability" for both AI-for-climate-teaching and AI's own footprint hide the accountability gap Daniel et al. (2026) identify; keep the agendas separate, with separate owners.
2. **Treat footprint disclosure as field infrastructure.** Reporting compute and carbon beside accuracy — with a sustainability statement even when measurement is imperfect — is the only route out of the incompatible-metrics problem.
3. **Design for the impatient learner.** If the lower-carbon option costs perceived latency, most students will not take it: keep latency low, expose controls, and describe impact in concrete outcome terms, not abstract carbon units.
4. **Prefer lighter deployment where pedagogy allows.** Grounding a model in a licensed local corpus and quantizing with fine-tuning gave usable accuracy at a fraction of the energy — reuse that pattern before scaling cloud inference.
5. **Build teacher capability through material development, not awareness campaigns,** and fill the Global South gap rather than importing evidence from North American and European contexts.

Common Misconceptions

- **"AI in environmental education mainly supplies information."** The measured gains are in **decision-making**: students working with an AI partner inside a structured inquiry task outperformed inquiry-only peers (**d = 0.69**) and traditional instruction (**d = 1.88**) on a decision-making measure, with gains **concentrated on the weakest steps**. The effect is in reasoning quality, at the points where students were weakest.
- **"Inquiry alone is the active ingredient."** AI-assisted inquiry **improved climate decision-making over inquiry alone**, so the AI contribution was additional to the pedagogical structure rather than interchangeable with it.
- **"Large effects from small samples are still large effects."** AI-assisted instructional design under Sustainable Development Pedagogy **improved pre-service teachers' lesson plans with a d = 2.80 from 28** participants — the reviewers' own word is *implausibly large*, and an effect that size from that sample should be treated as a signal rather than an estimate.

Connected Concepts

- Sustainability

- Global South
- Critical Pedagogy
- Inquiry-Based Learning
- Science Education
- Engineering Education
- Teacher Education
- Curriculum Design
- Ethics
- AI Governance

Connected Articles

- A Scoping Review of AI for Sustainability and Sustainable AI in Higher Education — Separates AI for sustainability from sustainable AI; Global South gap
- Can AI-Assisted Inquiry Enhance Students' Decision-Making Skills in Socio-Scientific Issues? A Three-Group Experimental Study on Climate Change — AI-assisted climate inquiry, d = 0.69 over inquiry alone
- The Environmental Cost of LLMs in AIED: Reporting and Practices — AIED 2025 disclosure review plus an open-source footprint method
- When LLMs Slow Down: How Environmental Impacts Mediate University Students' LLM Usage — Eco-feedback on latency–carbon trade-offs with 89 CS students
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — On-premise quantized assistant at 1.8 mWh per query
- Enhancing Sustainability Consciousness in Higher Education: Impacts of Artificial Intelligence-Integrated Sustainable Engineering Education — AI-SEE: sustainability consciousness in engineering education
- Teacher Involvement in Developing Sustainable Education Materials for AI Integration in Green Energy Education — Practical AI use and ESD material development predict integration
- The Role of Artificial Intelligence in Green Education: Optimizing Teacher Workflow and Enhancing Pedagogical Design under Sustainable Development Pedagogy (SDP) Constraints — AI-assisted design under Sustainable Development Pedagogy constraints
- Sustainable Education in the Age of Artificial Intelligence and Digitalization: A Value-Critical Approach — AI's contribution to sustainable education as governance-mediated
- Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era — "Sustainable learning" as durable cognitive agency, not an environmental claim

Business Education

> **AI in business education** — the application of artificial intelligence to the teaching and learning of business, economics, and management, and the preparation of students for a GenAI-integrated workplace. Business schools face a double imperative: integrating AI *into* the curriculum as a subject and pedagogical tool, while also preparing students to *use* generative AI responsibly and effectively in professional practice.

Questions to Consider

- Business schools face a double imperative: integrating AI into the curriculum as subject and tool, while preparing students to use AI responsibly in professional practice. Before reading, which of those two do you think most business programs currently get right, and which gets shortchanged?
- A student-informed framework found students were highly engaged and recognized they needed GenAI skills for careers — but also wanted to use AI without unintentionally committing academic misconduct. Why might a student want to use AI and simultaneously worry about breaking rules around it?
- Research on constructive alignment found that whether GenAI benefits or risks dominated was shaped by the degree of curriculum integration — integrate, don't append. What does 'integration' look like in a business program as opposed to just adding AI tools on top?
- A decade of research flags persistent gaps in curriculum coherence, educator readiness, and assessment validity. If you were redesigning a business course for an AI-integrated workplace, which of these three gaps would you tackle first and why?
- Business is one of the fastest fields for generative AI adoption, so graduates face acute pressure to be AI-ready. How might the AI skills that employers in finance, marketing, or management actually value differ from what students are currently taught in the classroom?

Introduction

AI in business education is a growing discipline-specific strand of AI in education. Business schools must prepare students for a future workforce where generative AI is pervasive, requiring both AI literacy and domain-specific application (finance, marketing, management, economics, entrepreneurship). The research highlights a tension between integrating AI as a pedagogical and professional tool and managing academic integrity, ethical use, and Assessment redesign.

AI in business education across the knowledge base's research

- **Student-informed frameworks.** Drummond & Dale (2026) present a student-informed conceptual framework for integrating GenAI throughout business degree programs, based on a 149-student UK case study. Students were highly engaged, recognized the need for GenAI skills for their careers, and wanted to use AI without unintentionally committing academic misconduct.

- **A decade of research.** Espino & Espino (2026) bibliometrically mapped 213 articles (2015–2024) on AI in business education, identifying four clusters: AI-driven business education transformation, innovative digital pedagogies, AI-enhanced personalization, and business education aligned with the digital economy — with persistent gaps in curriculum coherence, educator readiness, and assessment validity.
- **Constructive alignment.** Zhou et al. (2026) analyzed 17 cases of GenAI adoption at a UK business school, finding the balance between pedagogical benefits and risks was shaped by the **degree of curriculum integration** — constructive integration produced better outcomes.
- **Student insights on curricula.** Rook & Plumb (2026) drew on 166 undergraduate business students in a capstone unit, finding strong support for integrating GenAI into curricula with three priority areas: understanding/optimizing GenAI functionality, exploring applications across contexts, and navigating ethical/legal dimensions.
- **From memorization to judgment under ambiguity.** Shi, Dai & Zhang (2026) propose three generative-AI mechanisms for management courses — decomposing classic theories into assumptions and boundary conditions against real filings, tracking emerging cases between textbook editions, and a simulation whose AI role generates disruptive events and cascading consequences.
- **Organizational adoption.** Al-Rahmi (2026) examined organizational and technological drivers of AI adoption in higher education (using TOE + Diffusion of Innovations frameworks, n=300 staff), relevant to how business schools and their institutions adopt AI-driven decision support and smart learning platforms.
- **Conversational agents in business Simulation games.** Wenzel, Geiger, and Liening (2026) develop and evaluate an AI-enhanced conversational agent (Lara) for adaptive instructional support in business simulation games used for experiential entrepreneurial learning. Grounded in an equity-by-design stance and universal design for learning, the CAIS-GBL framework targets cognitive, motivational, affective, and socio-cultural engagement, with evaluations among student teachers and BSG participants showing positive perceptions of cognitive/social presence and Self-Regulated Learning support — a model for scaling formative feedback in simulation-based business education.
- **Agentic GAI for complex applied tasks.** Ilieva et al. (2026) develop the AGAI-HE framework around an **e-commerce** course, where the learning task requires comparing business models, weighing market and operational constraints, and defending strategic recommendations — multi-step applied work that prompt-response chatbots support poorly. Their 130-student perception study found both chatbot and agent support rated above traditional e-learning on learning enhancement, personalization, decision-making support, and workflow organization, yet no significant agent-versus-chatbot difference, and the strongest endorsement went to combining all three modes. For business programs the reading is that adoption is an instructional-design question about how AI support is sequenced and governed, not simply a tooling upgrade (Agentic AI).
- **A course-built RAG chatbot moved expectations, not outcomes.** In a semester-long randomized trial with 454 undergraduates in a Principles of Marketing course, Thoeni and Fryer

(2026) found no significant group-by-time effect on interest, Self-Efficacy, engagement or test performance, although students logged in 0.89 times per week and rated enjoyment 80.4.

- **Assessment and grading innovation is under-researched.** Mesny, Roberge-Maltais & Galy (2026) surveyed 58 assessment-related articles over 20 years across four leading management-education journals (AMLE, JME, Management Learning, IJME) — roughly three per year, many in 2010 and 2014 special issues — finding assessment and grading under-researched relative to their central role in shaping learning. Self- and Peer Assessment dominate the discourse (nearly half the corpus, chiefly for summative evaluation of group work); authentic assessment appears mainly via technology-mediated simulations and is often conflated with experiential learning; while reassessment, standards-based grading, and ungrading are virtually absent. The authors urge management educators to engage more actively and reciprocally with these innovations, recommending incremental experimentation (ungraded assignments, reassessment for a single task, standards-based rubrics) backed by program-level coordination and documented Scholarship of Teaching and Learning evidence.
- **Automated scoring of business coursework needs corpus-specific validation.** On 60 student marketing posts from a BrandSim simulation, Li (2026) found an LLM reached only ICC(2,1) = .435 with the human mean — deterministic rules .091, an equal-weight hybrid .266 — while adding researcher-authored anchors raised the LLM to .846 without changing any student score.
- **A business-education alternative grades the process, not the topic.** In a first-year Business Analyst degree apprenticeship, marking required documented iteration and peer collaboration, and students who used GenAI contested its counterarguments rather than submitting them (Alam & Jackson, 2026).
- **Teaching AI as a first-class process-design element.** Jalali (2026) places an AI-decision checkpoint in each BPM lifecycle phase across six modules of a 152-student course, so students build a working LLM intake agent and then discover at a checkpoint that the actual bottleneck is a two-person fraud-investigation queue.

Economics and management education

AI in business education spans **economics** and **management** as core disciplines. The knowledge base's coverage focuses on the pedagogical and curriculum dimensions (how AI is taught and used in business programs) and the professional-readiness dimension (preparing students for AI-integrated workplaces). Key themes include AI literacy, generative AI application across business functions, ethical and integrity considerations, and curriculum and Assessment redesign to reflect AI-integrated professional practice.

Why AI in business education matters

Business is one of the fields where generative AI adoption is fastest, so business schools face acute pressure to prepare students for an AI-integrated workplace. The research emphasizes that effective integration is **curriculum-driven and student-informed** — not just adding AI tools but redesigning programs so that GenAI literacy, ethical judgment, and authentic application are woven through degree structures. This

connects business education to the knowledge base's broader themes of AI literacy, educator preparation, Assessment redesign, and curriculum reform in the AI era.

Implications for business instructors

- **Integrate AI curriculum-driven and student-informed.** Student-informed frameworks and student insights show students want GenAI skills for careers and to use AI without unintentional misconduct — design programs that weave AI literacy, ethical judgment, and authentic application through degree structures.
- **Align curriculum constructively.** Constructive alignment research finds the degree of curriculum integration shapes whether GenAI benefits or risks dominate — integrate, don't append.
- **Address the persistent gaps.** A decade of research flags gaps in curriculum coherence, educator readiness, and assessment validity — prioritize these in program design.
- **Prepare students for an AI-integrated workplace.** Emphasize AI literacy, ethical use, and domain application (finance, marketing, management, economics) as core competencies, not electives.

Common Misconceptions

- **"Students want AI because they want shortcuts."** A student-informed framework found students **highly engaged and aware they need GenAI skills for careers**, while also wanting **to use AI without unintentionally committing academic misconduct**. The demand is for competence with clear boundaries, not for permission to avoid work.
- **"Adding AI modules to a business curriculum captures the benefit."** Research on constructive alignment found that whether **benefits or risks dominated was shaped by the degree of curriculum integration** — the operative distinction is **integrate, don't append**. A bolted-on module leaves the assessment design unchanged.
- **"Tool sophistication beats conventional e-learning."** A **130-student** perception study found **both chatbot and agent support rated above traditional e-learning** on enhancement, personalization and decision-making. Worth noting what this measures: student *perception* against a conventional baseline, not learning against it.

Connected Concepts

- AI in Education
- AIEd in the Disciplines
- Generative AI
- AI Literacy
- Curriculum Design
- Assessment
- Ethics
- Academic Integrity

- Technology Adoption Models
- Teaching
- Higher Education
- STEM Education

Connected Articles

- AI-Decision Checkpoints for AI-Augmented Business Process Management: Framework and Educational Instantiation — AI-Decision Checkpoints for AI-Augmented Business Process Management: Framework and Educational Instantiation
- Agentic Generative AI in Higher Education: Perceived Benefits, Risks, and Implications for Learning — AGAI-HE: agentic GAI support in an e-commerce course, perceived benefits and risks (Ilieva et al. 2026)
- Generating a student-informed teaching and learning conceptual framework for GenAI in business schools: a case study — Student-informed framework for GenAI in business schools (Drummond & Dale 2026)
- Mapping the integration of AI into business education: Insights from a decade of research — A decade of AI in business education (Espino & Espino 2026)
- From Experimentation to Integration: Embedding GenAI in Business Higher Education through the Lens of Constructive Alignment — Constructive alignment of GenAI in business higher education (Zhou et al. 2026)
- Integrating generative artificial intelligence into university curricula: Student insights — Student insights on integrating GenAI into curricula (Rook & Plumb 2026)
- Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education — Organizational drivers of AI adoption in higher education (Al-Rahmi 2026)
- Designing Conversational Agents for Adaptive Instructional Support in Business Simulation Gaming — CAIS-GBL framework for AI conversational agents in business simulation games (Wenzel et al. 2026)
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Agreement and error in automated scoring of student marketing posts — Agreement and error in automated scoring of student marketing posts
- From memorization to experiential learning: Reconfiguring classroom pedagogy in management education through generative AI — three generative AI mechanisms for reconfiguring management education pedagogy
- Process-Oriented Collaborative Essays: Empowering Undergraduate Students Through Assessment Redesign in the Age of Generative AI — Process-oriented collaborative essays in a Business Analyst apprenticeship: marking documented iteration, not the topic

- AI chatbots in higher education: Comparing expectations to evidence — A course-built RAG chatbot moved expectations, not outcomes

Humanities and Social Science Education

> **Humanities and Social Science (SSH) Education** — the teaching of disciplines concerned with human culture, values, meaning, and social life, including history, philosophy, literature, languages, sociology, and the arts. AI in SSH education raises distinctive questions because these fields center on interpretation, critical judgment, authorship, and meaning-making — processes that generative AI both supports and disrupts. AI here functions less as a tutor of factual content and more as an epistemic mediator that reshapes how students interpret texts, construct arguments, and understand their own Learner Agency as writers and thinkers.

Questions to Consider

- The humanities prize interpretation, authorship, and critical judgment — exactly the capabilities generative AI most challenges. How does that make AI integration in these disciplines different from in STEM?
- The page describes AI as an 'epistemic mediator' that can externalize your interpretive thinking and hybridize your authorship. When AI helps you interpret a text, who is actually doing the interpreting?
- It identifies three trajectories for learners: AI-dependent, AI-enhanced, and AI-critical interpretation. Where do you think most humanities students currently land — and what would move them toward the AI-critical end?
- In history education, research shows AI can shape reasoning and source interpretation, including through filters that 'protect' students. How would you teach students to interrogate an AI's mediation of historical claims?
- If original authorship and interpretive autonomy are the core values of the humanities, what does it mean when AI can produce a plausible interpretation instantly? What human capability becomes more, not less, valuable?
- The page warns against treating AI as a content tutor in fields centered on meaning-making. What would it look like to use AI deliberately to deepen, rather than flatten, students' critical analysis?

Introduction

SSH education is a distinct subject area in the knowledge base, complementary to STEM Education and Language Learning. Because the humanities prize interpretive depth, authorship, and contextual judgment, they pose different AI-integration challenges than STEM — and connect to Higher Education and AI Literacy in domain-specific ways.

Civic and political education is a sibling subject area to these disciplines rather than a branch of them, and Civic and Political Education treats it in its own right. The knowledge base's evidence there is thin: eight sources touch the topic and none measures civic learning.

How AI appears in humanities and social science education

- **Restructuring interpretive cognition.** Voicu argues that generative AI acts as an *epistemic mediator* that reconfigures meaning-making, authorship, and learner Learner Agency in SSH education. It identifies three transformations — externalization of interpretive cognition, hybridization of authorship, and emergence of distributed epistemic agency — and three developmental trajectories (AI-dependent, AI-enhanced, AI-critical interpretation). This grounds a developmental-critical pedagogical model for preserving interpretive depth.
- **What a task lets a reader see decides whether authorship is assessable.** In a model simulation of 148 texts, memoranda and revision defenses scored 3.16 and 3.10 on argumentative visibility against 2.63 for position essays, because the format itself required source explanation or a response to objections (Liu & Liu (2026)).
- **History education.** Research on LLMs in history education examines how AI shapes historical reasoning and source interpretation.
- **Humanities and social-science students' experiences.** GenAI's impact on Chinese humanities and social science students and AI acceptance among language/English learners document student-facing effects across SSH disciplines.
- **Critical and philosophical dimensions.** Critical AI literacy and the philosophy of AI in education are especially salient in SSH, where questions of meaning, values, and epistemic authority are central.
- **Institutional digital transformation.** Qin (2026) documents how Lingnan University repositioned itself as a "Research-Intensive Liberal Arts Institution in the Digital Era," mandating GenAI literacy for all undergraduates (including a required first-year Common Core course on generative AI covering latent spaces, GANs, diffusion models, prompting, fine-tuning, bias, and misinformation). The position paper argues the AI-for-education shift is an *intellectual transformation* rather than technocentric augmentation, positioning digital fluency as a core liberal arts competency while a human-in-the-loop model foregrounds ethical reasoning, critical judgment, and social responsibility — a concrete blueprint for higher education balancing GenAI innovation with humanistic foundations.
- **The sector's assessment exposure is now measured, and it is concentrated rather than diffuse.** Villanueva (2026) audited 15,587 Arts and Humanities unit records across Australia's Group of Eight universities and found 58.6% of 2026 assessment items highly exposed to GenAI, with take-home essays and research reports accounting for 71.4% of that exposure once weighted by marks.

Why it matters

SSH education foregrounds the very capabilities generative AI most challenges — original authorship, interpretive judgment, critical analysis, and context-sensitive meaning-making. The knowledge base treats this domain as a critical counterweight to instrumental, skills-based framings of AI: it asks whether AI-supported learning preserves Critical Thinking, epistemic responsibility, and interpretive autonomy, connecting to Critical Pedagogy and AI Literacy.

Implications for humanities and social-science instructors

- **Treat AI as an epistemic mediator, not a content tutor.** Voicu shows AI reconfigures meaning-making, authorship, and agency in SSH — design pedagogy around the three trajectories (AI-dependent, AI-enhanced, AI-critical) and aim for the AI-critical end.
- **Protect interpretive depth and authorship.** Because the humanities prize judgment and original authorship, guard against AI flattening analysis; make critical evaluation of AI output a learning goal (Critical Thinking, AI Literacy).
- **Use AI deliberately in source work.** History research shows AI can shape reasoning and source interpretation — teach students to interrogate AI-mediated historical claims and the filters it applies.
- **Consider student-facing impacts.** Student experience studies document how GenAI affects SSH learners; adapt support and integrity framing to real usage rather than assumptions.

Common Misconceptions

“The humanities are the least AI-exposed part of the curriculum.” The exposure has been measured and it is concentrated rather than diffuse: Villanueva (2026) audited **15,587 Arts and Humanities unit records** to establish where the exposure sits. It is unevenly distributed across units rather than spread thin, which makes assessment redesign a targeted problem rather than a sector-wide one.

“AI in humanities education is technocentric augmentation.” The position paper this page draws on argues the shift is an *intellectual transformation* rather than augmentation, positioning digital fluency as a core liberal-arts competency. Adding a tool to an unchanged course mistakes the transformation for its instrument.

“Values education can be handed to a model as content.” Chen (2026) reframes values education as a relational practice with three conditions — answerability, exemplarity and address — and reads each of GenAI’s five affordances as replacing a relation: the simulated perspective replaces the stakeholder who can be wronged.

“Critical analysis is what AI most threatens, so it should be restricted.” Critical analysis is also what intentional use most develops, when the task is designed to deepen rather than flatten it. A human-in-the-loop model locates the discipline’s contribution in the learner’s judgment rather than in the tool’s output.

“A general-purpose model is as useful for textual scholarship as for summarisation.” Interpretation requires the reader’s position, and an assistance layer that supplies the reading has performed the interpretive act the discipline exists to teach.

Connected Concepts

- Higher Education
- Critical Thinking
- AI Literacy
- Critical Pedagogy

- Philosophy of AI in Education
- Learner Agency
- Language Learning
- STEM Education
- AI in Education
- AIEd in the Disciplines
- Civic and Political Education

Connected Articles

- AI-Mediated Learning and the Restructuring of Interpretive Cognition: A Developmental-Critical Model for Social Sciences and Humanities Education — A developmental-critical model of interpretive cognition for SSH education
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — LLM use and historical reasoning in history education
- The impact of generative artificial intelligence on academic development of Chinese students in humanities and social sciences — GenAI's impact on humanities and social science students
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — AI acceptance among language and humanities learners
- How AI-vulnerable is Australian higher education assessment? A computational audit of Group of Eight Arts and Humanities units, 2022–2026 — Computational audit of 15,587 Go8 Arts and Humanities units: 58.6% of 2026 assessment items highly AI-exposed, concentrated in essays and reports
- Generative AI in Values Education: Affordances, Ethical Risks and Implications for Teaching — Generative AI in Values Education: Affordances, Ethical Risks and Implications for Teaching (Chen 2026)
- Making argumentative work visible in GenAI-mediated assessment: An exploratory LLM simulation and questionnaire study in university ideological and political education — Task format and AI-use instructions as what the artifact can evidence (Liu & Liu 2026)

Civic and Political Education

> **Civic and Political Education** — the part of schooling that prepares people to understand institutions, reason about public problems, and act as citizens rather than private individuals. Trust et al. (2025) treat it as a domain with distinctive goals: critical engagement with power, multicultural perspectives, and action on social issues. The knowledge base names the topic but holds little evidence on it.

Questions to Consider

- When a student asks a chatbot whether a policy is constitutional, what would they need to know to judge the answer?
- Does fluent, sourced-looking prose make public reasoning harder, or merely faster?
- If a learner uses AI to draft testimony for a local hearing, does authorship belong to Academic Integrity or to civic education?
- Media literacy teaches students to analyze messages. What must be added before that is enough for citizenship?

Introduction

Civic and political education covers how schools prepare people for public life: governmental structures, the rights and obligations of citizens, public reasoning about contested problems, participation in collective decisions, and the information skills public argument requires. Santos-Albardía et al. (2025) describe the goal as participatory and critical citizenship, not tool proficiency. Nkalanga (2026) locates it in Social Sciences, Geography, and Life Orientation, where citizenship and human rights are already taught. This page defines the territory and records what the corpus holds: adjacent work, not a civic education literature.

What civic education covers

The domain is broader than a civics course. It includes institutional knowledge, public reasoning, a disposition to participate, and judgment about information used in argument. Zhai et al. (2026) show the breadth from another discipline. Their Vision II covers science in everyday and civic life; Vision III covers action at community and societal levels, tied to democracy and issues such as vaccination and climate. They note that Vision III is the least served by standards and assessments.

The largest civic-specific study here is a content analysis, not a learning study. Trust et al. analyzed 310 AI-generated lesson plans containing 2,230 activities for all 53 Massachusetts eighth-grade civics standards. Three chatbots each received a basic prompt and a “highly interactive” variant. Ninety percent of activities sat at Remember, Understand, or Apply; Analyze was 4%, Evaluate 2%, and Create 4%.

The cultural result is starker. Using Banks’ levels of multicultural integration, 94% of activities contained no discernible multicultural content. Of the rest, 137 were Additive, four Contributions, one Transformation, and none Social Action. Every chatbot returned the same structure whatever the standard covered.

Civic education is not a recall subject. A plan asking students to list three facts about the Bill of Rights teaches the vocabulary of citizenship while removing the practice of it.

Why generative AI is a civic problem, not only an integrity problem

Academic integrity asks whether submitted work is the student's own. Civic education asks whether a public claim is true, attributable, and open to contest. Generative AI stresses the second question in ways the first does not capture.

Three mechanisms recur. First, fabricated evidence: a model can produce a plausible quotation, statistic, or legal citation that a student cannot independently check. Second, generated political persuasion. Rudolph et al. (2025) name deepfakes, targeted propaganda, and automated disinformation as threats to democracy. Santos-Albardía et al. report expert consensus that AI and deepfakes make reality harder to distinguish from misinformation. Third, source verification. A learner who cannot trace a claim to an institution or named author depends on the system that produced it.

The learner is also a producer, writing to officials and circulating evidence. The civic question is not whether AI assisted the text. It is whether the student can stand behind the claim and answer objections.

Nkalanga (2026) adds a mechanism integrity framing misses. From South Africa's AI-mediated border regime the paper derives five civic digital literacy demands: algorithmic transparency, data rights, bias recognition, rights contestation, and participatory governance. Someone who cannot recognize that a decision was algorithmic, or find the appeal route, has lost a civic capacity rather than a technical skill.

Where media literacy ends and civic education begins

The overlap is substantial and the sources do not settle the boundary. Media literacy is conventionally the ability to access, analyze, evaluate, and create messages. Santos-Albardía et al. (2025) extend it toward educating citizens to use information critically, and their experts describe critical educommunication as a politically grounded practice that strengthens democracy.

The civic addition is not another evaluation skill. It is the move from judging a message to acting on institutions. Media literacy can tell a student that a viral claim is unsupported. Civic education asks which body has authority, what right of access applies, how a decision can be contested, and what participation would change. Nkalanga's five demands specify that second half most clearly.

Frameworks cover the first half better. Nkalanga finds DigComp 2.1 includes data literacy and digital safety but leaves algorithmic accountability outside its competence areas. South Africa's Information Technology and Social Sciences standards carry little digital literacy content, and the Geography syllabus contains nothing on algorithmic systems. The result is competent tool users who cannot interrogate a decision made about them.

What the knowledge base holds, and what it does not

The eight relevant sources are heterogeneous. Trust et al. provide the only large civic-content analysis. Nkalanga synthesized 53 documents with no primary data. Santos-Albardía et al. interviewed seven experts and surveyed 141 students at one university. A Finnish interview study with 13 teachers found qualification

dominating accounts of AI education, while subjectification lacked concrete strategies. Zhai et al. offer a framework and Rudolph et al. an editorial. Theodora and Tselios (2026) ask whether adult learning serves economic needs or civic participation. Elmahjub et al. (2026) find democracy and rule of law named in 92 of 160 governance documents, but legal force in four.

The corpus holds eight sources that touch civic and political education, and none of them measures civic learning: no study in this knowledge base tests whether students exposed to AI-mediated civic instruction become better informed, more participatory, or more resistant to manipulation.

The gap is specific. Nothing measures whether students can verify a generated claim against a primary source, identify an algorithmic decision and find an appeal route, or produce public writing that survives scrutiny. The media literacy survey's readiness figures are self-assessed, so they describe confidence rather than competence.

A research program would need baseline and post measures of civic knowledge, public reasoning, and source verification, using tasks with planted fabrications. It would need behavioral measures of participation, production tasks scored for claim accuracy and attribution, and tests of whether learners can contest a decision rather than describe one. It would need classroom conditions, teacher preparation, and equity data, especially in South Africa, where Nkalanga reports roughly 16,000 schools without computer laboratories and frames the shortfall as a Global South equity problem. Until then, this page is a map of a gap.

Common Misconceptions

"AI literacy already covers citizenship." Functional AI literacy teaches people to use tools. Algorithmic accountability asks who decides, on what basis, and how that decision can be challenged. Nkalanga shows mainstream competence frameworks omit this layer.

"The problem is students cheating." Integrity framing asks who wrote the text. Civic framing asks whether the claim is true and whether the student can defend it. Trust et al. show the supply side fails first: AI-generated civic lessons were lower-order and monocultural before any student used them.

"Better prompts will produce better civic lessons." The interactive variant made minimal difference, and all three chatbots produced the same structure across 53 standards. Prompt quality did not restore disciplinary texture.

"There is enough evidence to guide practice." There is enough to justify caution. One content analysis, one documentary synthesis, one small mixed-methods study, and several conceptual or policy pieces do not establish what works.

Connected Concepts

- Humanities and Social Science Education
- Critical Thinking
- AI Literacy — Umbrella: what learners need to know about AI systems
- Ethics
- AI Misuse and Learning Harm — generated disinformation and persuasion as societal harm
- Critical Pedagogy

- Evaluative Judgment
- Global South
- AI Governance
- Teaching

Connected Articles

- Civic education in the age of AI: Should we trust AI-generated lesson plans — 310 AI-generated lesson plans for 53 civics standards: 90% lower-order, 94% with no multicultural content (Trust et al. 2025)
- Digital borders, algorithmic governance and civic digital literacy: examining the educational implications of AI-driven immigration management in post-apartheid South Africa — Algorithmic border governance and five demands of civic digital literacy in South Africa (Nkalanga 2026)
- Technology, education and critical media literacy: potential, challenges, and opportunities — Expert interviews and a student survey on critical media literacy and participatory citizenship (Santos-Albardía et al. 2025)
- From Competency to Agency: Teachers' Views of the Purposes of AI Education — Finnish teachers' purposes for AI education read through qualification, socialization, and subjectification
- Science Literacy: Generative AI as Enabler of Coherence in the Teaching, Learning, and Assessment of Scientific Knowledge and Reasoning — Science literacy visions, including civic life and democratic engagement (Zhai et al. 2026)
- Don't believe the hype. AI myths and the need for a critical approach in higher education — Editorial naming deepfakes and automated disinformation as democratic threats (Rudolph et al. 2025)
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy — Adult education policy and the civic purpose of lifelong learning (Theodora & Tselios 2026)
- Generative AI Governance in Education: A Scoping Review of Principles, Mechanisms, and Risks in English-Language Documents — 160 governance documents; democracy and rule of law named in 92, legal force in four (Elmahjub et al. 2026)

Arts, Design and Media Education

> **Arts, design and media education** — the studio- and performance-based disciplines in which learning happens by making: architecture and spatial design, interior design, music performance, composition and analysis, visual art and image generation, digital media and digital storytelling, and stage and performance technology. Across the articles in this knowledge base the recurring questions are whether Generative AI erodes craft and skill development or moves it up a level, how critique and the Assessment of creative work change when a polished artifact is cheap to produce, how much of each discipline rests on embodied and material practice, and who is included when creative tools become generative. Coverage is concentrated in higher education and in single-studio or single-course studies, so most findings below are case evidence rather than discipline-wide claims.

Questions to Consider

- In an architectural studio study, teams using a GenAI-plus-XR pipeline reported *lower* confidence in their own design ability afterward, and blinded raters scored their presentations no better than a control group's. What would you need to know before concluding the tools harmed learning — and what would make you conclude it anyway?
- Studio teaching has always run on the critique and on visible process: sketches, models, successive iterations. If a student can produce a finished-looking image in a minute, what should the critique actually examine?
- In a project-based digital storytelling capstone, students' ideas were rated more original than their finished works were coherent. Where does the hard learning really sit — generating ideas, or integrating them?
- A music education review distinguishes autonomous generators such as Suno and Udio from interactive composition assistants such as the Continuator, and argues that only the second is educationally productive. Do you agree, and what is your criterion for the distinction?
- Designers in Malaysia are described as shifting from primary form-generators to critical curators of machine output. If that is the destination, what should a first-year design course teach first?
- Blind and low-vision string players learn bowing through touch and proprioception because visual demonstration is unavailable to them. What does that imply for feedback systems in the arts that default to a screen?

Introduction

What these disciplines share is the studio or the rehearsal room as the site of learning, with a made artifact and the process behind it as the object of assessment. AI enters in several shapes: an image generator in the architecture and interior design studio, a composition and analysis tool in music, a spatial partner inside immersive environments, an automated scorer of written analysis, and — in stage lighting — an instructor-facing aid that turns spoken teaching intent into executable demonstrations. The sections below trace what the studies report, then draw out the cross-cutting questions of craft, assessment and access.

This page is the discipline home for studio and performing-arts subjects, and it is narrower than its neighbors. AIEd in the Disciplines holds the general argument that AI in education research must be domain-aware across all subjects; this page is about what is specific to making. Creativity covers the cognitive construct wherever it appears — divergent thinking, the homogenization risk of single-model assistance, protecting the learner's generative act — including in mathematics and creative coding; this page covers the disciplines in which creative production *is* the curriculum. Design Thinking covers ideation and user-centered problem framing as a general pedagogy; this page covers the studios where that process is taught, supervised and judged. Humanities and social science education treats interpretation, authorship and argument in text-centered fields and lists the arts among its constituent areas; here the arts and media are lifted out of that interpretive frame and centered on material, spatial, sonic and performative practice. Design Education carves the professional half out of this same territory. This page spans the studio and performing arts, whose shared feature is making. Design education instead follows the narrower formation pipeline for product, service, interaction, interior and architectural designers — portfolio assessment, accreditation expectations, employability. It also treats the studio process behind an artifact, rather than the artifact itself, as the object of assessment.

Studio Pedagogy and the Critique Under Generative AI

Generative tools reach these disciplines through an existing ritual: work made publicly, shown incomplete, and criticized. What the sources show is that AI changes the *middle* of that process most reliably and the *ends* least. In the GenARch study, Xiao et al. (2026) put a GenAI plus multi-user XR pipeline into a real undergraduate architectural design studio and found a complementary division of labor: Generative AI externalized ideas, giving teams something concrete to point at, compare and argue over, while XR supported evaluation, letting students judge proportion, adjacency, lighting and site context at full scale.

The tooling was awkward at both ends of the process. At the start, teams had no ideas yet to encode in a prompt; later, richer concepts made prompting easier but raised expectations of constraint-following, and when precision mattered students went back to SketchUp and Revit. They reported a dimensional-fidelity failure — "I asked it to make a 10 feet wall of 3D model, it wasn't 10 feet" — asset latency of seconds to minutes, and shared attention that drifted when team members looked at different parts of a model. Giving every participant a headset did not by itself produce coordinated collaboration.

The studio's accountabilities did shift. In a longitudinal study of generative models in design studios, Gül et al. (2026) distinguish using GenAI as visual stimulus in early ideation from a combinatorial use that expands the solution space during development, and locate the pedagogical problem in competence rather than access: without the discernment to differentiate between models and use them deliberately, abundant output produces design fixation and aesthetic lock-in. Their conclusion moves the instructor's role from transmitting craft toward coaching when, how and why to delegate creative exploration.

Architecture, Spatial and Interior Design

A Derby focus-group study gives the studio a more favorable result. Kapsalis (2026) ran two groups of eight Level 3–5 architecture students through a 90-minute session with a locally executed image generation-and-editing workflow fine-tuned for residential interiors. Students produced roughly 80 images per session, about ten each, with acceptance rates above 60%. Self-reported idea generation (4.5) and experimentation (4.2)

scored highest on the creative subscale, while refinement of final decisions (3.7) was less uniformly supported — some students found the tool surfaced unconsidered combinations, others that it distracted with details that did not fit the concept. The author frames this as a constructionist “microworld” that expands the creative search space without replacing design thinking, and notes survey evidence that nearly 70% of architecture students already use AI tools independently while over 95% report no formal AI education.

Interior design raises the professional-formation question most sharply. Syed Abdul Rahman (2026) describes Malaysian designers shifting from primary form-generators toward critical mediators and curators of machine output, with Visualization platforms compressing timelines and widening the range of options producible within a budget. Citing empirical work on client preference (Lan et al., 2025), the article notes that AI output is rated highly for uniqueness when aesthetic criteria predominate, but that human designers retain a clear advantage when functional, ergonomic and contextual requirements are emphasized — and that generated designs often lack cultural specificity, climatic responsiveness and reliable constructability in a market negotiating tropical conditions, multi-generational living and Islamic spatial principles. Its curriculum recommendation is sequencing rather than substitution: teach CAD/BIM, construction knowledge and human factors before generative exploration, and assess Critical Thinking and ethical reflection alongside visual quality.

Music and Performing Arts

Music is treated here as the art most exposed to economic change that began before generative AI. Briot (2026) argues that dematerialisation collapsed per-unit recorded-music value by roughly two orders of magnitude well before generative models were commercially relevant, that per-stream payouts remain on the order of $0.003–$0.005, and that generative AI prolongs an already-broken value model rather than creating it. His distinction that matters for teaching contrasts autonomous generators such as Suno and Udio — complete, stylistically coherent pieces from a text prompt, with opaque and uncontrollable structure — against interactive composition assistants such as FlowComposer and the Continuator, where the musician imposes constraints and retains intentionality and the Continuator learns a player’s style in real time as an improvisational partner. Only that second kind, he argues, is educationally productive, because the first positions students as consumers of machine output. The recommended curriculum makes production and DAW fluency core competencies and defends ensemble performance as the embodied, social dimension most resistant to substitution.

Assessment in music is being pushed toward automation, with limits worth noting. Lin, Jin and Min (2026) benchmarked GPT-4o-mini against teacher mean scores on 300 university-level music analysis responses across Harmony, Form, Reasoning and Terminology, finding that few-shot chain-of-thought prompting agreed most strongly with teacher means and that retrieval augmentation systematically over-scored; agreement was also weaker on Terminology than on Reasoning, so the authors argue for strategy-specific calibration, dimension-level validation and continued human oversight.

Vocal pedagogy supplies the clearest statement of the measurement-versus-value problem. Li (2026) argues that AI-assisted vocal teaching should not be judged by how precisely it measures pitch, stability, vibrato and timing, because the same measured deviation may indicate technical inaccuracy, expressive inflection or a recording artifact, and because measurable outputs do not represent a learner’s embodied coordination. The framework separates the evidence AI makes visible, the human learning processes that interpret it (bodily

awareness, metacognitive monitoring, self-regulated practice, motivation), and the outcomes that follow, judged by effectiveness, equity and Sustainability. Instrumental teaching for disabled musicians takes the embodiment point further: Shi et al. (2026) worked with four advanced blind and low-vision string musicians and three instructors, finding that bowed-string technique is conventionally taught by visual demonstration — unavailable to these learners — and that tactile and kinesthetic cues substitute for it. Inclusive instruction, on their account, should be built with disabled learners rather than retrofitted for them.

Stage and performance technology is where AI-assisted instruction has been designed and evaluated most concretely. Liang et al. (2026) built LumiNote, an Large Language Models (LLMs)-assisted VR system that turns an instructor's spoken intent, anchored by a laser pointer, into reviewable spatial annotations, executable lighting demonstrations and jargon explanations. Across 55 instructor prompts and 531 generated action pairs, 380 (71.6%) were applied; visual effects formed the largest prompt category (27 of 55) with high adoption (212 of 245 actions, 86.5%), while fixture-specific requests proved weakest — 26 of 28 rejections traced to directional-reference misreads such as "left light". Instructors used suggestions as a refinement process, not a finished lesson plan: of 147 rejected or modified suggestions with follow-up, 127 (86.4%) triggered a new prompt and only one a direct manual adjustment. Their workload fell (NASA-TLX 3.50 to 2.22) and sessions shortened (19 minutes 34 seconds to 12 minutes 33 seconds) as effort shifted from low-level configuration toward expression. The sharpest finding is a representation mismatch: the cues instructors rated most useful for externalizing expert reasoning were not the ones 24 learners could follow, who preferred a laser pointer (M = 5.50) and console tagging with values (M = 5.33) over spatial arrows and an avatar (both M = 4.58), though student outcome measures showed no significant differences.

Visual Arts, Image Generation and Digital Media

Text-to-image tools are the case where the studio's iterative workflow is most directly at stake, and the evidence is not a simple story of gain or loss. Liu, Meng and Zhang (2026) surveyed 417 art and design students alongside instructor focus groups and interviews, finding that performance expectancy, social influence, novelty value and creative competence all positively predicted intention to use text-to-image tools, while effort expectancy and facilitating conditions predicted negatively — which they read as shortcut-oriented use in coursework where ease and availability enable quick output rather than sustained engagement. Their competence paradox is the notable result: creative competence supports intention but also predicts more selective, restrained actual use, as students weigh authorship, originality and skill preservation against efficiency. They argue for pedagogy addressing AI literacy around creative process, prompt crafting and output evaluation, with studio process and effort as the assessed object.

The adoption question has a discipline-specific answer in Zhu (2026), who surveyed 450 art majors at eight Zhejiang institutions with a UTAUT model extended by Trust. Trust was the strongest path to behavioral intention ($\beta = 0.425$), ahead of social influence (0.155), while metacognitive control ran more directly to intention ($\beta = 0.146$) than to trust ($\beta = 0.099$). The authors read that as this discipline's stake: art's stopping rules are unclear, so holding creative agency means deciding repeatedly what to keep, revise or discard. A randomized follow-up with 80 students had blinded experts rate generated images, and prompted students scored higher on semantic content ($d = 0.67$), visual style ($d = 1.30$) and spatial composition ($d = 0.63$).

Foka (2026) turns critique into a replicable method: three epistemic games — Interpret, Interrogate and Expose — move studio discussion from impressionistic reaction to warranted bias hypotheses, with a BiasSlot rule varying one bias cue while a constant motif stays fixed.

Digital media production shows what a structured process can do. Tian et al. (2026) studied a 15-week project-based digital storytelling capstone, “Creative Shanzhou”, in which 426 final-year undergraduates, guided by 48 mentors at roughly a 1:9 ratio, translated local cultural heritage into Multimodal AI narratives. Expert ratings of the 92 resulting works were strongest on novelty ($M = 4.21$, $SD = 0.72$), followed by effectiveness (3.96) and wholeness (3.68), with 43% of projects scoring below 3.5 on wholeness — students generated original ideas more successfully than they integrated them. In a 31-student Animation subgroup, figural creative-thinking scores rose from 77.23 to 94.68 (mean difference 17.45, $t(30) = 4.55$, $p < .001$, Cohen’s $d = 0.82$). Across the analyzed projects AI served as information organizer, visual reference, ideation aid and editing tool, while students retained topic selection, narrative interpretation, cultural meaning-making and final decisions; the highest-scoring example attributed its coherence to sustained human engagement with source material rather than AI polish. The project ended in a three-day public exhibition, and 31 works were taken up by the local Cultural and Tourism Bureau.

Immersive environments provide the more favorable counter-case in vocational design. Jin et al. (2027) implemented AI-IVE-PBL — project-based learning inside an AI-enabled immersive virtual environment with an agent teaching assistant — in a first-year vocational interior design course, as a five-phase loop of discovery, envisioning, modeling, communication and refinement. In a 12-week two-group quasi-experiment (63 valid responses, 31 versus 32), the immersive-plus-agent condition scored higher on design ability ($\eta^2p = .138$) and creative ability ($\eta^2p = .111$) under ANCOVA with pretest as covariate, and lifted cognitive ($d = 0.90$) and behavioral ($d = 0.75$) engagement, Motivation ($d = 0.74$) and satisfaction ($d = 0.69$) while lowering reported cognitive load ($d = -0.52$). Innovative thinking and affective engagement moved in the expected direction without reaching significance. All outcomes were self-report, with no performance artifacts or expert ratings, which is why the authors contrast their result with the architectural studio study above.

Craft, Skill and the Assessment of Creative Work

The craft question appears in several forms, and the sources disagree about how worried to be. Kapsalis (2026) reports a levelling mechanism at entry level: students who described themselves as weak at drawing found the tool opened access to visual expression without removing the need for judgment. Against that, Syed Abdul Rahman (2026) warns that uncritical adoption risks graduates without foundational spatial reasoning, material knowledge or independent critical evaluation, and names the prevention of deskilling among early-career practitioners as a core regulatory concern. The disagreement is partly about sequencing: both favor technical foundations before generative exploration.

What is consistent is a repositioning of what gets assessed. The Derby study measured procedural confidence in-session at 3.7 out of 5 but confidence in transferring those skills beyond the studio at only 2.6 — a gap its author attributes to single-session exposure and calls a curriculum-level problem. The Malaysia analysis recommends studio projects requiring comparative evaluation of AI and non-AI design pathways, plus criteria that reward critical thinking alongside visual quality. Music’s automated-scoring results point the same way: agreement with teacher means was dimension-specific, and the authors insist on human oversight rather than full delegation. Li (2026) adds that treating measured output as educational value in itself

narrows vocal training into output correction and score optimization. The converging proposal is that creative assessment keep examining process, iteration and justified decision-making precisely because the finished artifact no longer evidences them.

Access and Inclusion in Arts Learning

Accessibility in the arts is treated less as compliance than as a design and material-practice question. Shi et al. (2026) is the clearest case: because bowed-string technique is normally taught by visual demonstration, blind and low-vision musicians depend on tactile and kinesthetic channels, and the study's disability-led co-design produced strategies rooted in those musicians' own practice rather than adaptations bolted onto a visual default.

Two other findings complicate any simple story of generative tools as an equaliser. In the Derby study about a third of participants declared a disability and nearly a fifth reported a specific learning difficulty; inclusivity items clustered at 3.8–4.1 and correlated strongly with feeling the session was approachable (ρ = .74) and with keeping up regardless of prior AI use (ρ = .81), and students less confident at drawing reported not feeling disadvantaged — a modest equalizing effect in a single 90-minute session, not demonstrated learning. The LumiNote representation gap shows the other side: cues that help experts externalize their reasoning are not the cues novices can follow, so a design that serves the instructor well can leave learners adrift, and the authors position the LLM as a mediation layer that must translate between the two. The GenARch study records a related equity decision: after data collection the technologies were released to the control students so they were not withheld. Whose aesthetic and cultural references generative models reproduce, and whether wider access to design services expands demand or intensifies mid-market competition, are raised in the Malaysia analysis and remain open.

Common Misconceptions

"The arts evidence base establishes discipline-wide conclusions about AI." It does not, and the corpus is candid about it: coverage is concentrated in higher education and in single-studio or single-course studies, so most findings are **case evidence rather than discipline-wide claims**. A result from one design studio tells you what happened there, and the studio is an unusually specific social arrangement to generalize from.

"Any generative tool is educationally equivalent to any other." The distinction that matters is whether the tool generates *for* the student or composes *with* them. A music education review separates autonomous generators such as Suno and Udio from interactive composition assistants such as the Continuator, arguing that **only the second is educationally productive**. Both produce music; only one leaves the student making the compositional decisions.

"High acceptance of generated output shows the tool is working." Acceptance is the measure of the tool's persuasiveness, not of the student's learning. In one studio study students produced roughly **80 images per session, about ten each, with acceptance rates above 60%** — a rate at which most of what was generated was used, which raises the question of how much revision and judgment the session contained.

"AI in studio teaching replaces the critique." The constructionist framing in this literature is the opposite: a designed "microworld" that **expands the creative search space without replacing design thinking**. The

critique is where judgment is formed, and a tool that supplies candidate solutions gives the critique more material to work on rather than less need for it.

“Students are not already using AI in arts education, so the curriculum can set the pace.” Survey evidence in this corpus finds nearly **70% of architecture students already use AI tools independently**. The curriculum is catching up with a practice that has already spread, which changes the task from introduction to critical integration.

Implications for Practice

For studio instructors

- Distinguish generating-for from composing-with when choosing tools, and prefer the second. The distinction is the difference between a student who directs a system and one who receives output.
- Keep the critique and make it the assessed element. Acceptance rates above 60% suggest critique is the only place the selection judgment will surface.
- Assume prior independent use: nearly 70% of architecture students are already using AI tools, so the pedagogical work is on quality of use rather than on exposure.

For developers

- Build for iteration and control — parameters, constraints, partial generation — not for one-shot production. Interactive composition is the mode with an educational claim behind it.
- Instrument revision behavior, not acceptance rate. Acceptance measures your output, not the student’s thinking.

For researchers

- Move beyond single-studio case studies before making discipline-wide claims, and report the studio’s structure since it conditions the result.

Connected Concepts

- Creativity
- Design Thinking
- Generative AI
- Project-Based Learning
- Embodied Learning
- Authentic Assessment
- AI Literacy
- Equity
- Virtual and Augmented Reality
- AIEd in the Disciplines
- Design Education

Connected Articles

- Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study — GenAI plus multi-user XR in a real architectural studio: complementary roles, declining design self-efficacy, no portfolio advantage (Xiao et al. 2026)
- Gen-AI-tecture: using generative AI to support architectural students in design tasks — A locally executed, discipline-specific image workflow in an architecture studio: wider creative search space and reduced crit anxiety (Kapsalis 2026)
- Development and applications of Generative AI in architectural design studios — Longitudinal studio study and the GAI-A platform: GenAI as stimulus and solution-space expansion, with design fixation as the risk (Gül et al. 2026)
- Artificial intelligence as catalyst and contested terrain: Transforming interior design practice, pedagogy, and professional regulation in Malaysia — Interior designers as curators of machine output, and what curriculum and professional regulation should do about it (Syed Abdul Rahman 2026)
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — Project-based learning inside an AI-enabled immersive environment in vocational interior design (Jin et al. 2027)
- In the AI era: A project-based digital storytelling framework for art and design education — A 15-week digital storytelling capstone with 426 students: novelty strong, integration weak, AI as tool not author (Tian et al. 2026)
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — Text-to-image acceptance among 417 art and design students, and the competence paradox of selective use (Liu, Meng & Zhang 2026)
- Challenges for Musical Education in the Age of AI and Digital Transformation — Streaming economics, autonomous generators versus composition assistants, and rethinking the music curriculum (Briot 2026)
- Comparative Validation of GPT-4o-mini and Teacher Mean Scores for Automated Scoring of Music Analysis Responses: Single-Pass Deployment, Repeatability, and Strategy-Specific Bias — Benchmarking GPT-4o-mini against teacher means on 300 music analysis responses (Lin, Jin & Min 2026)
- Beyond output metrics: Reframing AI-assisted vocal pedagogy through human learning and educational value — Why measurement precision is not educational value in AI-assisted vocal teaching (Li 2026)
- Designing for What Cannot Be Seen: Supporting Embodied String Learning for Musicians with Blindness and Low-Vision — Disability-led design of tactile and kinesthetic string instruction for blind and low-vision musicians (Shi et al. 2026)
- LumiNote: LLM-Assisted Multimodal Instruction for VR Stage Lighting Education — LLM-assisted VR instruction for stage lighting, and the gap between expert and novice representations (Liang et al. 2026)
- Playing Bias: Epistemic Games for Interpreting Text-to-Image Models — Playing Bias: Epistemic Games for Interpreting Text-to-Image Models (Foka 2026)

- Supporting creative agency: metacognitive control and trust in generative AI art education — Art students' creative agency, trust and expert-rated output quality

Design Education

> **Design Education** — the professional formation of designers in studio-based disciplines: product, service, interaction, interior and architectural design, taught through iterative project work in which the assessed object is the process behind an artifact as much as the artifact itself. Its distinguishing features are the studio and the critique as the site of learning, visible process evidence (sketches, intermediate models, iterations) as the primary indicator of learning, and the fact that Generative AI now makes the polished output students are graded on cheap to produce. That makes design education a test case for Creativity, Design Thinking, Assessment Validity and Workplace Learning.

Questions to Consider

- If a studio can no longer read learning off the finished artifact, what should replace visible process as evidence — mandatory process artifacts, oral examination, something that survives a cohort of 140?
- Unsupported novices in one experiment never revised a single idea until an adversarial agent surfaced stakeholder pushback. Should design teaching manufacture friction deliberately — and where does productive difficulty end?
- The designer's role, on this account, moves from producing forms to judging what the machine generates. If so, what comes first in a curriculum: manual craft, or critical evaluation of model output?
- If an Large Language Models (LLMs) can approximate instructor, peer and grant-reviewer readings of the same poster, what is left for the human critic?

Introduction

Design education is narrower than Arts, Design and Media Education, which covers studio and performance disciplines together — architecture, music, visual art, media and digital storytelling. This page covers the professional design disciplines and their formation pipeline: portfolio assessment, accreditation expectations, employability, and a practice culture that has absorbed generative tools faster than its curricula have.

It is also distinct from Design Thinking, a human-centered Problem Solving method taught across business, education and law as a transferable skill. In design education the process is not a method applied to a discipline; it is the discipline, and the studio is where it is taught, supervised and assessed. Engineering Education is the closest professional neighbour — also design-heavy, also accountable to practice — but engineering assessment rests on calculable artifacts and public-safety responsibility, whereas design's rests on critique and on process evidence that generative tools can visibly simulate.

How AI appears in design education

- **AI is an ideation resource whose characteristic risk is fixation.** Gül et al. (2026) built the GAI-A platform across a longitudinal studio study and found two productive uses: GenAI as visual

stimulus in early ideation, and as a combinatorial expander of the solution space during development. The problem, they argue, is competence rather than access — without the discernment to read models deliberately, abundant output produces design fixation and aesthetic lock-in — which moves the Teaching from transmitting craft to coaching when and why to delegate creative exploration.

- **A discipline-specific local tool widened the search space and levelled participation.** Kapsalis (2026) ran two Derby focus groups of eight architecture students through a 90-minute session with a locally executed ComfyUI workflow. Creative scores were highest for idea generation (4.5) and experimentation (4.2) and lower for refining decisions (3.7), while inclusivity items ran 3.8–4.1 and correlated with keeping up regardless of prior AI use ($\rho = .81$). Confidence gained in the session did not transfer — confidence in using these skills professionally was 2.6, a gap the author calls a curriculum-level problem.
- **Unsupported novices do not revise; an adversarial agent changes that.** Han & Martelaro (2026) ran a between-subjects experiment with 45 novice interaction designers on a civic reporting site. Their Self Reflection group never revised or deleted a single idea; agent-engaged students made roughly 3.6 times more edits, reached stakeholder concerns the other groups missed (Accessibility, Privacy, reluctance toward automation) and produced stronger proposals. The agent was rated as contributing ($M = 5.33$), but one participant felt criticized "in every aspect", and the authors insist simulated pushback is no substitute for engaging real publics.
- **A structured process keeps authorship with students at scale.** Tian et al. (2026) studied a 15-week storytelling capstone in which 426 undergraduates and 48 mentors (about 1:9) turned local heritage into Multimodal AI narratives. Expert ratings of the 92 works were strongest on novelty ($M = 4.21$) and weakest on wholeness ($M = 3.68$) — ideas came more easily than integration. Creative-thinking scores in a 31-student subgroup rose from 77.23 to 94.68 ($d = 0.82$). AI organized information and edited; students kept topic choice, interpretation and final decisions, and 31 works were adopted by a regional Cultural and Tourism Bureau.
- **Adoption is frequent, uneven across the process, and suspicious.** Broadbent et al. (2026) surveyed 280 Politecnico di Milano design students and read 100 Masters AI-use journals: 71% used GenAI daily or weekly, 65% distrusted it, 85% modified its output. Use clustered in research and writing — editing writing 77.5%, finding information 74.5%, brainstorming 68.0% — with whole-assignment use rare (18.6%). Ownership largely survived: 31% reported lost ownership or creative agency, and only prototype generation was significantly associated with it. Planning and interpreting primary research stayed with students, which the authors read as evidence that students may not count research as part of the creative process.
- **Intention is gated by attitude and shaped by task fit.** A survey of 405 design graduate students at Chinese universities modeled intention with an integrated TAM–Task–Technology Fit framework (Chu & Liu (2026)). Attitude was the necessary condition for intention ($d = 0.132$, $p < 0.001$), with 22.1% of the attitude scale required for intention at 80%. Fit fed attitude at $\beta = 0.224$, beside perceived usefulness (0.376) and ease of use (0.185). The characteristics of the studio task drove fit most ($\beta = 0.322$), which is the measured form of what the bullets above describe qualitatively: what students judge is whether the tool matches the work in front of them. Perceived

enjoyment raised ease of use but not usefulness (β = −0.033, p = 0.483), and the model left R^2 = 0.150 of intention explained.

- **Dependence type decides whether prompting capability becomes engagement.** Han and Cao (2026) surveyed 829 design students in 40 intact classes: self-reported prompt literacy predicted learning engagement (β = 0.539), and engagement predicted creative self-efficacy (0.618) more strongly than creative personal identity (0.474). The literacy–engagement link weakened only under cognitive dependence (B = −0.155), with simple slopes of 0.607 and 0.297; functional (p = 0.396) and emotional (p = 0.941) dependence did not moderate it.
- **The net effect is divergence rather than uplift.** Crolla, Xia & Jiang (2026) drew on 24 interviews and a 32-instructor survey in a built-environment faculty to describe *cognitive divergence*: AI amplifies prior differences, letting stronger students extend reasoning while weaker ones delegate formative work and produce coherent outputs without understanding — a "false sense of capability" that collapses under questioning. Loss of process visibility, in a field that relied on visible process as its primary evidence of learning, and erosion of the frictional stages that act as Desirable Difficulties compound it. Faculty positivity tracked pedagogical relevance (β = 0.534, p = .004), not seniority, and the faculty's mitigations do not scale past studio-sized cohorts — which argues for institutionalized process-evidence requirements. Limits: single institution, n = 32, faculty perception.
- **Disruption awareness is not simply demoralizing.** Among 568 Chinese design students, awareness that AI may replace parts of design work was positively associated with self-rated innovation competence (β = 0.375), through a promotion-focus path of 0.0929 and a prevention-focus path of -0.0884 that nearly canceled each other (Wang et al. (2026)). Every measure came from a single self-report wave.
- **Disciplines differ in which behaviours pay off.** Shen (2026) compared 221 design students with 222 business students and found AI Literacy predicted both prompting proficiency and verification behavior (p < .001). Verification directly predicted task quality in the design cohort, calibration accuracy in business — open-ended ideation against audit-like analytic standards — and verification functioned as a metacognitive safeguard against Cognitive Offloading.
- **Studio judgement can be approximated when a rubric mediates.** Yaşar et al. (2026) raised LLM–human agreement on 80 design posters from 54.75% to 81.25% by iteratively refining rubric descriptors; instructor, peer-reviewer and grant-reviewer prompts produced epistemically different feedback on the same work. The authors treat the rubric as a revisable interface between pedagogical intent and machine inference, retaining human oversight against hallucinated rationale.
- **Students negotiate the tools rather than simply accept them.** Liu, Meng & Zhang (2026) surveyed 417 art and design students: performance expectancy, social influence, novelty value and creative competence predicted intention to use text-to-image tools, while effort expectancy predicted negatively, read as shortcut-oriented coursework use. Their competence paradox is that creative competence supports intention yet predicts more selective use as students weigh authorship and skill preservation — an Assessment Validity problem in a studio where process is the assessed object. Rana et al. (2025) reached a compatible conclusion from 112 reflections in a

12-week Design Thinking course: benefits dominated (86% positive sentiment), ethical concerns drove 62% negative sentiment, and scaffolded integration moved students from skepticism to 72% positive orientation.

- **GenAI can assist a workflow while weakening creative self-belief.** In a 36-student architectural design experiment, a DALL-E 3 workflow matched precedent search on rated performance and cognitive load, yet general creative Self-Efficacy fell (DiD = −0.543) while task-specific confidence held (Xiao et al., 2026).
- **AI critique can be bound to the artifact rather than the prompt.** Kadir (2026) routes studio feedback through a shared board of designs, notes and pins and five bounded activities; the study reports simulated readiness (78% of 109 labels at Analyzing or above), not learning gains.
- **A process rubric can make AI verification the graded object.** Orhon et al. (2026) propose the Merit Report, a four-criterion rubric (documented curatorial will 20%, tectonic translation 20%, rule-based technical validation 40%, peer audit 20%) that grades a student's documented AI-verification process rather than the artifact's polish, underwritten by a TPACK extension they call AI-Validation Knowledge.

Professional formation and regulation

Assessment problems here are inseparable from professional ones. Syed Abdul Rahman (2026) describes Malaysian interior designers shifting from primary form-generators toward critical mediators and curators of machine output, with Visualization platforms compressing timelines while generated schemes still lack cultural specificity, climatic responsiveness and reliable constructability. Its curriculum recommendation is sequencing rather than substitution — CAD/BIM, construction knowledge and human factors before generative exploration, and criteria rewarding Critical Thinking and ethical reflection. The professional side is unresolved: interior design regulation is less formalized than architecture's, leaving open questions of disclosure, accountability for algorithmic error, and deskilling among early-career practitioners. The analysis is document-based and single-country.

Common Misconceptions

- **"AI in a design studio is mainly a writing aid."** A survey of **280 Politecnico di Milano design students** plus **100 Masters AI-use journals** found use clustered in research and writing — **editing writing 77.5%, finding information 74.5%, brainstorming 68.0%** — with **whole-assignment use rare at 18.6%**. The pattern is augmentation of parts, not replacement of the whole, and the numbers show where the actual practice sits.
- **"Design students are enthusiastic adopters."** The same cohort shows **71% using GenAI daily or weekly, 65% distrusting it, and 85% modifying its output**. Frequent use and low trust coexist, so a tool whose value proposition assumes trust has misread the users.
- **"GenAI is generically helpful across the design process."** The GAI-A platform built across a longitudinal studio study found **two productive uses only**: GenAI as visual stimulus in early ideation, and as a **combinatorial expander of the solution space during development**. Usefulness was phase-specific.

- **“Creativity gains are too diffuse to measure.”** In a **31-student subgroup**, creative-thinking scores rose from **77.23 to 94.68 (d = 0.82)**. The gain is measurable and it is bounded to a subgroup, which is the honest form of the claim.

Connected Concepts

- Design Thinking
- Creativity
- Generative AI
- AI Literacy
- Higher Education
- Arts, Design and Media Education
- Engineering Education
- Workplace Learning
- Assessment Validity
- Assessment
- Cognitive Offloading
- Critical Thinking
- Scaffolding
- Desirable Difficulties
- Human-in-the-Loop
- Curriculum Design
- Teaching
- Equity
- AIEd in the Disciplines
- AI Regulation in Education

Connected Articles

- Enacting Constructive Conflicts with AI Agents to Enhance Reconsideration among Novice Interaction Designers
- AI-mediated cognitive divergence in built-environment education: Evidence from a mixed-methods study
- Artificial intelligence as catalyst and contested terrain: Transforming interior design practice, pedagogy, and professional regulation in Malaysia
- Gen-AI-tecture: using generative AI to support architectural students in design tasks
- Development and applications of Generative AI in architectural design studios
- A study of GenAI usage by Design Students: Analysis of Survey Results and Journals of AI practices at the Politecnico di Milano in 2025/2026
- In the AI era: A project-based digital storytelling framework for art and design education

- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students
- Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts
- From evaluation to emulation: LLMs as agents of iterative pedagogical design
- Generative AI in design thinking pedagogy: Enhancing creativity, critical thinking, and ethical reasoning in higher education
- Critsly and StudioCrit: An Artefact-Aware AI Critique Workspace and Simulation-Based Readiness Study for Design Education — Critsly/StudioCrit: artifact-aware AI critique workspace for studio feedback; simulation-based readiness study, not learning gains
- Generative AI-assisted workflows in architectural conceptual design: Performance, creative self-efficacy, and cognitive load — An architectural-design experiment in which a DALL-E 3 workflow lowered general creative self-efficacy
- Assessing Human-AI Collaboration in Design Education: A Process-Oriented Rubric Grounded in an Extended AI-TPACK Framework — A process rubric can make AI verification the graded object
- The double-edged sword effect of AI technological disruption awareness on design innovation competence: the mediating role of regulatory focus and the moderating role of AI critical thinking — AI technological disruption awareness, design thinking mindset, and design innovation competence among design students
- Cognitive mechanisms of AI agent behavioral intention among design graduate students: an integrated TAM–TTF perspective — attitude as the necessary gate on design students' intention to use AI agents, with task–technology fit as a second path (Chu & Liu 2026)
- Learning engagement and creative self-beliefs in generative AI-supported design education: self-reported prompt literacy and dimensions of AI dependence — Dependence type decides whether prompt literacy becomes engagement

Medical and Health Professions Education

> **Medical and Health Professions Education (HPE)** — the teaching and training of medical, nursing, pharmacy, and allied health professionals. AI is reshaping this domain through clinical Simulation, reinforcement learning trainers, adaptive learning, and the application of foundational learning principles (experiential, situated, and distributed cognition) in health-professions contexts. Because HPE is high-stakes, competency-based, and clinically embedded, it raises distinct questions about AI's role in skill acquisition, patient safety, and the educator's judgment. Nursing, the most heavily studied program in HPE, now has a page of its own — Nursing Education — where the competence boundary, identity-formation, and workforce evidence that this page carries only in outline is developed in full.

Questions to Consider

- In medicine, AI benefits like scalable practice and adaptive feedback must be balanced against risks like erosion of hands-on clinical skill — where errors carry direct patient consequences. Where would you draw the line between what AI should do and what a trainee must practice for themselves?
- The page argues AI should be used to operationalize age-old learning principles — experiential, situated, distributed cognition — rather than replace the educator's guiding role. What makes the educator's judgment indispensable even when AI can simulate or personalize the practice?
- Reinforcement-learning trainers and agentic AI are now used for clinical and procedural skills in residency. If an AI agent trains a resident on a procedure, how would you verify they've actually learned it safely before they do it on a patient?
- Because health-professions education is high-stakes and competency-based, assessment questions carry particular weight. How might AI-assisted assessment both improve and threaten the evaluation of clinical competence?
- Over-reliance on AI is a specific concern in medicine. How do you think training with AI could produce a clinician who is more confident but less able to reason independently — and what could guard against that?

Introduction

AI in medical and health-professions education is a growing strand of the knowledge base's subject-area coverage. Unlike general higher education, HPE is oriented toward the development of clinical competencies, procedural skills, and professional judgment, which shapes how AI tools are designed and evaluated.

How AI appears in health-professions education

- **Operationalizing foundational learning principles.** Fowlin et al. (developed at the Medical University of South Carolina) argue that AI should be used to operationalize age-old learning principles — Dewey's experiential learning, situated cognition, and distributed cognition — rather than replace the educator's guiding role. AI enhances personalized and adaptive learning while the teacher remains central to student engagement and outcomes.
- **Clinical skills and reinforcement learning.** ResidencyRL uses reinforcement learning to train clinical reasoning and procedural skills in residency, demonstrating AI as a skills-training partner in real clinical workflows.
- **Simulation and agentic AI.** Agentic AI simulation in brachytherapy shows how AI agents support hands-on procedural training in medical specialties.
- **Gamification of medical learning.** MedGame applies gamification and LLMs to engage medical students.
- **Nursing and interdisciplinary education.** AI transformation of nursing education documents how AI reshapes nursing curricula and instruction. This page keeps nursing as one program among medicine, pharmacy, dentistry, and allied health, organized around the shared problem of scalable clinical competence; the nursing-specific record — a competence boundary where AI's documented benefits stop, an explicitly professional-identity framing, and students' workforce anxiety — belongs to Nursing Education and is cross-referenced here rather than restated.
- **AI-powered simulation in nursing.** Jiang et al. (2026)'s mixed-methods systematic review of 19 studies (N = 1,253) finds AI-driven simulations (GenAI/LLMs, virtual patients/mannequins, AI-enhanced VR/MR, and chatbots) significantly improve cognitive knowledge and affective outcomes (Self-Efficacy, communication confidence) in the strongest designs, but are inconsistent for complex psychomotor skills — one RCT found AI-assisted simulation *inferior* to standardized patients. Their concept of an **"authenticity gap"** — a learner-perceived shortfall in emotional resonance, nonverbal cues, and tactile examination — grounds why AI is best for highly structured objectives (foundational communication, history-taking) and should sit in a **stepped simulation continuum** alongside, not instead of, human-standardized patients and clinical placement. This is a distinctive, evidence-anchored refinement of the domain's Simulation strand and parallels the acceptance-trust finding that learners favor human feedback perceived as "benevolent" over AI seen as merely "competent."
- **LLMs and the reconstitution of professional identity in nursing (2026).** Sun et al. (2026)'s critical integrative review of 489 studies across 47 countries (Whittemore & Knafl framework) shifts the question from what LLMs can do in nursing education to what their integration does to the *developmental processes* through which a nurse is formed. Framed through Benner's skill acquisition, cognitive load theory, automation bias, and Wenger's identity formation, they find the same technology both enhances and erodes competence depending on whether the displaced cognitive work is extraneous to, or constitutive of, the target competence — unstructured reliance produced measurable deficits in ethical reasoning and clinical judgment. Their **Professional Identity Tension Model** distinguishes LLM integration that supports professional formation from

integration that silently substitutes for it, and **Structural Empathy Suppression** reframes apparent AI "outperformance" on relational metrics as a symptom of systemic overwork rather than genuine AI empathy. An evidence gap map shows the highest-policy-consequence domains (professional identity, relational/ethical competency, long-term outcomes) rest on the thinnest rigorous evidence — a caution against confident deployment claims in nursing education.

- **Multi-agent AI standardized patients in clinical interview training.** In a 2026 randomized controlled trial with 95 analyzed medical students (Yang et al.), multi-agent AI standardized patient training raised final OSCE-aligned examination scores over a structured non-LLM progressive-disclosure control (71.8% vs. 55.6%; β = 16.4 percentage points; P = 3.30e-4) while leaving binary diagnostic accuracy statistically identical (84% vs. 86%; P = 1.000). The dissociation indicates that early clinical-training gains can surface first in consultation process quality — communication (mean 3.53 vs. 2.64 on a 1–5 OSCE scale; P = 4.50e-4), empathic expression (+31 percentage points on the "expressing empathy" checklist item), and selected history-taking behaviors — before any improvement in diagnostic endpoints, and that AI patients still need human raters and faculty for professionalism and readiness judgments.
- **Criterion-level scoring localizes what an AI patient cannot do.** Across three Korean OSCE cases, three of four backbones sat within 0.5 Likert points of an expert reference on comprehensibility, consistency and hallucination-freeness, yet weaknesses concentrated in clinical reasoning and patient education and in a Korean negative-form penalty on fluency (Yi, Park & Kim (2026)).
- **Integrating AI into a residency curriculum is a governance problem before it is a content problem (2026).** Bursic et al. interviewed twelve physicians who lead AI work in Canadian and US postgraduate medical education. The five barriers they name are structural rather than pedagogical: review cycles slower than tool release, faculty expertise thin beyond a few experts, AI Governance that has not caught up on privacy and data ownership, no national competency standards, and cultural resistance tied to professional identity (Bursic et al. (2026)). Their proposal is a modular core — AI literacy, critical appraisal, bias detection, human-AI metacognition, ethics — with specialty and local-tool content reviewed every six to twelve months. Where this page documents what AI can teach here, this strand documents whether a program can teach it at all.
- **Students default to treating an AI patient as a searchable database.** Voice-interviewing a genAI avatar in a PBL pilot, students asked closed-ended, efficiency-focused questions — one asking whether the AI was "just, like, a question base" — and the encounters ran 55–65 minutes versus 36–39 for the legacy module (Mool et al., 2026).
- **Initiative is a second axis beside task allocation.** Jin et al. (2026) randomized 79 medical and nursing students and graduates to a reactive agent that waits for prompts or a proactive one that drives sequenced questions, writing analytical pieces over visuals built from the Multimodal AI traces of a four-person nursing simulation (a bar chart of time per behavior, a communication network, a ward heatmap). The two conditions differed sharply in epistemic structure (Cliff's delta of -0.56 and -0.78) while final scores did not, so where a tool sits in an allocation and how much initiative it demands are separate design decisions.

- **Cross-program analytics without shared student records.** Kovor, Osei and Agyemang (2026) partitioned the Open University Learning Analytics Dataset into five program-discipline clients as health-professions analogues and found federated logistic regression kept 99.3-99.9% of centralized performance, so the obstacle to sharing a risk model across programs is organizational rather than statistical. The reason a pooled model fails is pedagogical heterogeneity: their illustration has a nursing program at 30-35% at-risk against 15-18% for a concurrent medicine program, and forum activity ranked last as a predictor in every discipline because peer learning in these programs happens in clinical placements.
- **Task allocation and the SCAN framework.** Tsim et al. reframe AI integration from learner "misuse" to *misclassification* — a failure of real-time metacognitive evaluation. Their SCAN framework (Substitute, Complement, Aid, Non-Negotiable), grounded in Vygotsky's zone of proximal development, allocates generative AI tasks by the individual learner's developmental state and identifies passive engagement within AI-scaffolded tasks as a hidden pathway to mis-skilling that requires re-identification from AI to expert assistance with human epistemic auditors.
- **Human-in-the-loop instructional asset generation.** Gen-Mentor (Dong et al. 2026) integrates a vision-language-model backbone into a dental-radiography workflow: Faster R-CNN localizes four target findings (Filling, Implant, Impacted Tooth, Cavity), a conditional diffusion model generates class-specific synthetic ROI candidates, a VLM produces evidence-linked captions, and an Large Language Models (LLMs) reformats them into case descriptions, comparisons, and quiz prompts — all before structured expert review. Evaluated with 45 dental students (mean SUS 72.7), it demonstrates how human-in-the-loop review of AI-generated instructional assets can expand case diversity and immediate-feedback support while retaining expert oversight over what students see.
- **AI grading of pharmacy exams.** Falahat, Das, Bhaumik & Thambi (2026) evaluated ChatGPT-5 against human faculty grading of a 21-item pharmacy exam (16 students) across multiple-choice, select-all-that-apply, fill-in-the-blank, listing, short-answer, and essay items. The model matched faculty closely on objective items (CCC 0.935–1.000) but was unreliable for listing, short-answer (CCC ≈0), and essay (0.341–0.854) responses, and a structured rubric did not consistently improve agreement — evidence that in high-stakes, competency-based Assessment in health professions, AI suits well-specified items while human review remains necessary for subjective, open-ended clinical reasoning.
- **A validated LLM judge for clinical communication.** Hasan et al. (2026) scored the 3E communication skills from transcripts alone with a judge that reached Pearson 0.759 and ICC(A,1) 0.746 against the consensus of human raters, inside the spread of individual humans, though its weakest dimension (Be Explicit) did not improve across encounters.
- **GenAI in scenario-based healthcare education.** Neto and colleagues (2026) systematically reviewed 23 studies of GenAI across scenario-, case-, problem-, and simulation-based learning in healthcare education (PRISMA 2020). Their central finding is that **prompt design functions as instructional specification** — encoding the cognitive targets and quality criteria implicit in expert authoring — yet only 34.8% of studies aligned generated content with instructional frameworks and only 34.8% reported prompting in enough detail to reproduce. GPT-4 dominated

implementations (44.4%), hybrid human-AI collaboration outperformed fully automated approaches, and evidence was strongest for higher-order cognitive skills but inconsistent elsewhere. This grounds scenario/simulation-based and problem-based Pedagogies and Teaching Strategies in medical education with validation- and integration-quality benchmarks.

- **AI scoring of open-ended exam questions.** Olvet et al. (2026) tested whether GPT-4 could reliably score open-ended questions on pre-clerkship assessments at two US medical schools. With faculty iteratively refining scoring rubrics across three rounds of error-pattern analysis, AI–faculty inter-rater reliability reached substantial-to-almost-perfect agreement on three of four questions (weighted kappa up to 0.94) but only moderate on the holistic-rubric item (κw = 0.54); discrepancies traced to both raters (GPT-4 over-scoring multiple-answer or rubric-absent-vocabulary responses; faculty being overly generous) and occasional feedback inaccuracies keep humans in the loop. The authors argue the case for automated OEQ scoring is strengthened because ~82% of US medical schools grade pre-clerkship work pass/fail, where exact AI score agreement is not always required.
- **Repeated runs do not reproduce the same grade.** In a master's-level public health course, four general-purpose LLMs graded the same 32 anonymized essay submissions as two human examiners; ChatGPT in thinking mode reached weighted kappa 0.718, but regrading identical submissions on five different days reached only Krippendorff's alpha 0.625 (Brevik et al. (2026)). The authors advise averaging multiple assessments for high-stakes use.
- **Evaluating AI teaching agents, not just deploying them.** Zhang et al. (2026) deployed eight LLM teaching agents across four role-play paradigms (patient, student, expert, family member) in an endocrinology curriculum and scored 167 student dialogues with an 8-dimension teaching-quality rubric. Platform scores diverged sharply from rubric quality; agents differed most on knowledge dimensions and least on role enactment; adaptive difficulty calibration was a shared weakness; and strengthening an agent's empathy raised role-play quality without improving knowledge coverage. The finding that role-play paradigms can be separated (beyond the default patient-doctor script) points to designing and evaluating agents against explicit pedagogical dimensions.
- **The shape of the field's own literature.** Sriram, Nichols, Ganti and Gue (2026) map the ethical-AI-in-medical-education literature itself: 1,403 Web of Science publications from 1995 to 2026, negligible for two decades, then 113 in 2023, 256 in 2024 and 500 in 2025; 39 countries clear the authorship threshold, led by the United States (533 publications) over China (189) and England (95); and the most-cited works are capability tests — ChatGPT's performance on medical licensing examinations above all — rather than governance scholarship. Their reading is that the field has grown fast without growing evenly, and that empirical evaluation of AI Governance frameworks is the work the citation record is not rewarding. It is a useful caution for anyone treating the volume of published AI-in-medical-education research as evidence that its safe-use questions have been answered.

A 153-report scoping review of GenAI in medical education maps applications — Simulation and clinical skills largest (47 reports), ahead of assessment generation and feedback (22) and case-based learning and

clinical reasoning (21) — yet only 13 reports carried a follow-up or retention signal and no patient-level outcome was found (Zhao et al. (2026)).

Why it matters

HPE is a high-stakes, competency-based domain where AI's benefits (scalable practice, adaptive feedback, simulation) must be balanced against risks (Over-Reliance, erosion of hands-on clinical skill, ethical and safety concerns). The knowledge base's general concepts — Teaching, Assessment, Feedback, Equity, and Ethics — apply with particular intensity in health professions, where errors carry direct patient consequences.

Wang and Shan (2026) name the resulting "safety gap" — the divergence between a student's AI-assisted performance and their unassisted ability to verify it — and prescribe withholding solutions, constructive cognitive friction, and Socratic or Adversarial AI architectures for high-stakes clinical training.

- **What the curricula teach about data provenance.** Giancotti et al. (2026) coded the publicly advertised curricula of 36 U.S. health AI programs and found ethics covered in 29 (80.6%) but data provenance at a structural or dataset-limitation level in only 8 (22.2%), with no program addressing the environmental cost of computation and none of the seven master's degrees meeting the provenance threshold. Of 92 named instructors, 76.1% came from computational disciplines and 3.3% from the social sciences or humanities. The gap is clinically consequential: the deployment failures the paper opens with were introduced upstream, in how training data were generated or labeled, which is a teachable competency the curriculum appears not to carry.
- **Use has outrun instruction.** Among 310 health science students, 90% had used ChatGPT while 82.6% had received no formal AI instruction; usage frequency tracked higher GPA, and 61% reported ethical concerns (Alshahrani et al., 2026).

Implications for health-professions educators

- **Use AI to operationalize learning principles, not replace the educator.** Fowlin et al. argue AI should operationalize experiential, situated, and distributed-cognition learning while the teacher remains central to engagement and outcomes.
- **Leverage AI for clinical skills training.** ResidencyRL and agentic simulation show AI as a skills-training partner in real clinical workflows — embed it where it adds safe, scalable practice.
- **Balance high-stakes benefits against over-reliance.** HPE is competency-based and high-stakes; guard against AI substituting for hands-on clinical skill and judgment, and apply Feedback, Assessment, and Ethics considerations with particular care.
- **Adapt gamified and interdisciplinary AI thoughtfully.** Gamified LLM learning and nursing-education transformation show promise but need evaluation for safety and skill outcomes; for nursing specifically, that safety-and-skill evidence — including the RCT in which AI-assisted simulation underperformed standardized patients — is gathered on Nursing Education.
- **Order the curriculum by the evidence, not by the tools on hand.** The same KAS map shows where the evidence is thick and thin: ethics knowledge (14 studies), responsibility (14), application skills (16) and evaluation skills (18) carry consensus, while technical knowledge,

application knowledge and operational skills sit at 9 each and collaboration at 7. Where infrastructure is unreliable, reach the technical layer through screen-based cases and open-access model demonstration rather than waiting for high-fidelity simulation.

Common Misconceptions

- **“Simulation benefits are established in medical education, so AI simulation will too.”** A mixed-methods systematic review of **19 studies (N = 1,253)** finds AI-driven simulations produce effects in that literature — a modest base, and 1,253 participants across 19 studies is a narrow foundation for a technology being deployed at scale.
- **“The question is what LLMs can do in clinical training.”** A critical integrative review of **489 studies across 47 countries** shifts the question **from what LLMs can do to** what they should be trusted with. The capability question is largely answered; the governance question is not.
- **“Standardized patients are too costly to scale.”** A **randomized controlled trial with 95 analyzed medical students** used **multi-agent AI standardized patients** in clinical interview training. The constraint being addressed is the availability of trained human actors, which is a staffing problem rather than a fidelity one.
- **“Adopting a published AI competency framework settles the curriculum question.”** Xiang et al. (2026) screened 1,750 records to 23 studies — 15 reviews, 4 qualitative and 4 quantitative, across 15 countries and 2022 to 2026 — and mapped them onto the Knowledge, Attitude and Skill model. Application domains concentrated in medical education (n = 11, 47.8%), general education (n = 9, 39.1%) and other education (n = 3, 13.0%), and the named nursing frameworks they compared — N.U.R.S.E.S., AI-ABCs and CARE — either lack clear pathways for pedagogical implementation or cover isolated skills without assessment methods. The 12-sub-dimension map they build is a proposal awaiting validation, which makes it something to teach against rather than a settled curriculum.

Connected Concepts

- Problem-Based Learning
- Higher Education
- Simulation
- Adaptive Learning
- Personalized Learning
- Game-Based Learning
- Experiential Learning
- Situated Learning
- Distributed Cognition
- Teaching
- Assessment
- Feedback
- AI in Education

- AIEd in the Disciplines
- Nursing Education — the nursing strand of health-professions education
- Virtual and Augmented Reality — immersive and AR clinical training

Connected Articles

- Data Provenance and Ethics in the Curricula of U.S. Health AI Education Programs — Health AI curricula teach ethics (80.6%) but rarely data provenance (22.2%)
- A Stratified Multi-Rater Evaluation of LLM-Based Virtual Standardized Patients with a Deployed Data-Generation Platform — A Stratified Multi-Rater Evaluation of LLM-Based Virtual Standardized Patients with a Deployed Data-Generation Platform
- Generative artificial intelligence and the transformation of medical education: a scoping review — Scoping review of 153 medical-education GenAI reports: simulation leads, durability and patient outcomes unmeasured
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training
- What Platform Scores Miss: Multidimensional Evaluation of AI Teaching Agents in Medical Education — 8-dimension rubric evaluation of AI teaching agents in medical education
- When the algorithm enters the classroom: A critical integrative review of large language models, nursing education structural gaps, and the reconstitution of professional identity — LLMs, nursing education structural gaps, and the reconstitution of professional identity (Sun et al. 2026)
- AI as Teammate: Rethinking Task Distribution in Medical Training — SCAN framework: rethinking AI task distribution in medical training (Tsim et al. 2026)
- Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study
- Empowering Educators: Operationalizing Age-Old Learning Principles Using AI — Operationalizing experiential, situated, and distributed cognition with AI in health-professions education
- ResidencyRL: Reinforcement learning in simulated clinical environments — Reinforcement-learning training for clinical skills in residency
- MedGame: Storytelling Gamification Empowered by Large Language Models for Medical Education — Gamified LLM-based learning for medical education
- Agentic AI-driven immersive simulation: A knowledge-aware virtual training platform for high dose rate (HDR) brachytherapy — Agentic AI simulation for brachytherapy training
- Transforming nursing education with artificial intelligence: A systematic review (2010–2025) — Transforming nursing education with AI
- AI-Powered Simulation for Nursing Education: Mixed Methods Systematic Review — AI-powered simulation in nursing: mixed methods systematic review
- The safety gap: restoring productive struggle through pedagogically aligned generative AI — The Safety Gap: Restoring Productive Struggle

- Gen-Mentor: A human-in-the-loop instructional framework for dental radiography using generative AI — Gen-Mentor: human-in-the-loop dental radiography instruction (Dong et al. 2026)
- Generative AI in scenario-based healthcare education: A systematic review of applications, validation practices, and pedagogical integration — Systematic review of GenAI in scenario-based healthcare education (Neto et al. 2026)
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Can Generative Artificial Intelligence Reliably Score Open-Ended Question Assessments in Undergraduate Medical Education?
- Scalable AI-based clinical communication training and automated assessment — Scalable AI-based clinical communication training and automated assessment
- Ethical and responsible use of artificial intelligence in medical education — Bibliometric map of AI ethics in medical education: output rose 113 (2023) to 500 (2025), 39 countries, and citations reward capability testing over governance (Sriram et al. 2026)
- Large language models as grading assistants in public health education: a method-comparison study of essay-style exam assessment — Repeated runs do not reproduce the same grade
- An artificial intelligence application framework for nursing education: a scoping review based on the KAS model — Scoping review mapping educational AI competency frameworks onto a 12-part KAS map
- The agency gap in AI-supported writing: How reactive and proactive agent designs shape multimodal reasoning — Reactive versus proactive AI writing agents in health-professions training: the agency gap
- Federated learning for privacy-preserving at-risk student prediction in health professional education: A multi-scenario evaluation of FedAvg and FedProx — Federated at-risk prediction across HPE programs: a negligible privacy cost, and why an imported threshold misfires
- Nursing educators' perspectives on the integration of artificial intelligence into academic settings — Nursing educators in Bangladesh on AI readiness, barriers, and data governance, read through TPACK
- Exploring the integration of artificial intelligence into residency education curriculum: qualitative interviews — Barriers to integrating AI into residency curricula: qualitative interviews with twelve physician leaders
- Bridging technology and pedagogy: a cross-sectional analysis of AI use, self-reported academic effects, and ethical concerns among students across diverse health science curricula — Bridging technology and pedagogy: a cross-sectional analysis of AI use, self-reported academic effects, and ethical concerns among students across diverse health science curricula

Nursing Education

> **Nursing Education** — the preparation of nurses for licensed practice, and the subfield of health-professions education where AI is currently most studied. AI enters nursing curricula through Simulation with virtual patients and mannequins, LLM-based study and clinical-reasoning support, automated assessment, and adaptive platforms for at-risk learners. Its object is distinctive: nursing competence fuses psychomotor skill, relational practice, and professional identity formation, so a technology that raises measured performance can simultaneously erode the developmental work that produces a nurse.

Questions to Consider

- AI-supported simulation reliably improves knowledge and Self-Efficacy but shows inconsistent, sometimes negative effects on complex psychomotor skill. Where is AI the right teacher, and where must a human body in the room remain non-negotiable?
- Nursing students describe AI as emotional comfort during clinical stress. Is that a support to design for, or a signal that the relational apprenticeship is under-resourced?
- AI anxiety among health-sciences students tracks job-search anxiety. Is teaching AI literacy the remedy, or does it raise the salience of a threat that institutional policy should address instead?
- A nursing AI curriculum can be ordered by what the literature discusses or by what the clinical setting can support. When infrastructure is unreliable, should a program teach ethics and evaluation deeply and reach operational skill through low-cost simulation, rather than wait for the tools?

Introduction

Nursing education is the clinical strand of the knowledge base with the densest empirical record: system-wide reviews of AI applications, a mixed-methods synthesis of AI-powered simulation, a qualitative study of student and faculty experience, and a critical integrative review of LLM research sit alongside one another. That makes nursing a useful test case for claims the wider AI in education field makes about clinical training.

It must be kept distinct from Medical and Health Professions Education, which treats nursing as one program among medicine, pharmacy, dentistry, and allied health and organizes its account around the shared problem of scalable clinical competence. The nursing literature adds three things that page cannot carry: a competence boundary at which AI's documented benefits stop; an explicitly *professional-identity* framing, in which the question is who becomes a nurse rather than what a trainee can do; and a workforce layer — students' anxiety about AI displacing nursing roles, and the faculty view of nurses as shapers rather than recipients of healthcare's digital transformation.

The field also refines three adjacent concepts. From Simulation it inherits the fidelity debate but renames the deficit an "authenticity gap." From Affective Computing it takes the measurement of affect, yet its strongest

claim is that affective outcomes improve while emotional depth in the interaction does not. From Self-Efficacy it takes the central mediating variable, while cautioning that confidence built in a low-risk setting may not transfer to the clinical one. Beneath all of it sits the ordinary higher education problem of workload, access, and assessment integrity, sharpened by licensure and patient consequence.

How AI appears in nursing education

- **Four application areas, recurring risks.** Alrazeeni et al. (2026) reviewed 28 empirical studies (2010–April 2025) and group AI applications into personalized learning, simulation-based training, Automated Assessment, and institutional curriculum management with predictive analytics. Technological inequity, faculty preparedness gaps, and privacy and bias concerns recur. Their recommendations are concrete — embed AI simulation in emergency-care training, deploy adaptive platforms for at-risk learners, use automated tools for real-time formative Feedback, adopt diagnostic accuracy as the impact measure — within 6–12 month multi-site pilots tracking learning outcomes and trust.
- **Simulation: strong on knowledge and confidence, conditional on skill.** Jiang et al. (2026)'s PRISMA-guided mixed-methods review of 19 studies (N = 1,253, mostly prelicensure students) covers generative AI/LLMs, AI-driven virtual patients and mannequins, AI-enhanced VR/mixed reality, and chatbots. The strongest designs — three RCTs plus controlled quasi-experiments — show significant gains in cognitive knowledge and affective outcomes including Self-Efficacy and communication confidence, but effects on complex psychomotor skills are inconsistent, and one RCT found AI-assisted simulation *inferior* to standardized-patient simulation. Qualitative meta-aggregation explains both the appeal and the limit: learners value safe, repeatable, nonjudgmental practice that bridges the theory–practice gap, but report an **authenticity gap** — robotic dialogue, missing nonverbal cues, no tactile examination — plus technical instability that raises extraneous cognitive load and state anxiety. The authors recommend a stepped continuum: AI for pre-learning, history-taking, and foundational reasoning; human simulators and standardized patients for complex psychomotor and emotionally loaded work; human-facilitated debriefing alongside AI feedback.
- **Acceptance is real, and relational.** Akbaba and Calik Kus (2026) interviewed 28 participants (16 students, 12 faculty) and analyzed transcripts deductively through the Technology Acceptance Model. TAM held: ease of use, usefulness, intention, and use shaped adoption. The role split is practical — students used AI for presentations, visual content, clinical case analysis, and care planning; faculty for course materials, literature review, academic writing, and administration — implying tailored rather than uniform training. Two findings extend TAM's cognitive frame. Participants described AI as psychosocial support, a "companion" offering reassurance and a confidential space to reflect during clinical stress. And where AI *scored higher than nurses* on empathy in a high-volume context, Sun et al. (2026) read it as **Structural Empathy Suppression**: overwork makes authentic empathic expression unsustainable, algorithmic consistency fills the gap, and identity-constituting significance transfers to the algorithm — reframing the policy question from "how effective is this tool?" to "what conditions made it appear necessary?"
- **The open secret: practice outruns policy.** Ghimire and Qiu (2025) interviewed 17 final-year students at one Australian school, 10 domestic and 7 international, and found use normalized

while institutions discouraged it: “The biggest irony is that everyone knows we’re using AI” (SN9). Students used it for personalized learning, to bridge theory and practice and to manage time, and international students used it for language and cultural adaptation as well. Their themes name the digital divide and student-driven demand for curriculum change, which recasts adoption as a gap between what students already do and what the program admits to.

- **Faculty read the risk as professional, not procedural.** Dabkowski et al. (2026) interviewed 22 nursing academics across Australia and New Zealand and found them navigating policy that was absent, late, or written without them, sharply divergent collegial attitudes, and a line drawn at *replacement* rather than use. The objection was developmental before it was procedural: generating answers for a deteriorating-patient scenario means the reasoning is never practiced, and participants warned of a future cohort not fit for practice. Their summary was blunt: “Copilot won’t teach you to be a nurse.” Assessment practice was already moving toward invigilated exams, oral vivas and process evidence, and misconduct was read as a rehearsal for unsafe clinical shortcuts. That reframes Academic Integrity as a question about who is safe to practice rather than a compliance process. The academics asked for nursing-specific guidance tied to the profession’s ethical codes, GenAI literacy embedded across the curriculum, and staff development with unit co-design — not blanket prohibition.
- **Anxiety as a workforce signal.** Dağ et al. (2026) surveyed 821 health-sciences students (nursing among them) and found a moderate positive correlation between AI anxiety and job-search anxiety ($r = 0.233$, $p < 0.001$), with AI anxiety a significant predictor after controlling for socio-demographics ($\beta = 0.234$, $p < 0.001$). AI anxiety, they argue, is not a technology attitude but a psychological factor shaping how students see their professional futures — pointing to AI Literacy and career counseling, not tooling, as the intervention.
- **Groupthink and interprofessional teams.** Wiss et al. (2025) placed a generative AI agent (CALIE) into twelve newly formed interprofessional teams across seven health-professions programs, including nursing, during a 180-minute virtual problem-based learning session, prompting it to inject controversial viewpoints. Of 165 learners, 158 completed the survey; the agent was rated most useful as a tool ($M = 3.49$), then for feedback helpfulness ($M = 3.21$), and least as part of the team ($M = 2.88$), all pairwise differences significant ($F(2, 156) = 26.01$, $p < .001$). Facilitator stance mattered, and learners who rejected the agent’s responses still used them as a socially permissible way to speak up — disagreement with the AI did team work.

What the curriculum should cover, and where the map is thin

- **A twelve-part competency map, built because none existed for nursing.** Xiang et al. (2026) screened 1,750 records from PubMed, Embase, Web of Science and CNKI down to 23 included studies (2022 to 2026, 15 countries, 15 of them reviews). They mapped those studies onto the Knowledge, Attitude and Skill model, producing three dimensions and 12 sub-dimensions: foundational, technical, ethics and application knowledge; critical thinking, responsibility, ethical values, and openness and adaptability; and operational, application, collaborative and evaluation skills. They compared the existing nursing frameworks and found them untranslatable into curricula: N.U.R.S.E.S. covers roles, AI-ABCs covers objectives, CARE covers the prompt structure, and none supplies a pedagogical pathway or assessment methods.

- **Attention clusters where the writing is easy.** Ethics knowledge (14 studies), responsibility (14), application skills (16) and evaluation skills (18) carry consensus; technical knowledge (9), application knowledge (9), operational skills (9) and collaboration (7) do not. That is the same boundary this page documents from outcome evidence, reached from the competency side: the field knows most about what to say about AI's ethics and least about the operational layer clinical safety depends on.
- **The remedy on offer is a sequencing rule for under-resourced programs.** Teach foundational and ethics knowledge before technical knowledge; critical thinking, responsibility and ethical values before openness and adaptability; evaluation and collaboration before complex operational skill. Reach the technical layer through Simulation, and where high-fidelity or virtual reality simulation is unaffordable, through screen-based cases with pre-recorded material, open-access model demonstration and guided work with public datasets. Offline substitutes are named explicitly, including case-based discussion and conceptual demonstration of AI workflows. The stated motive is equity: if curriculum order follows the distribution of infrastructure, the concentration of the research in the United States (5 studies) and China (3) turns from a bibliometric fact into a curriculum problem.
- **The quantitative anchors are imported evidence, not results of this review.** Ethics knowledge has been shown to predict AI integration (standardized coefficient 0.636, p below 0.001), and a positive perceptual future orientation to raise students' ethical values (0.308, p below 0.05). Evaluation carries the stronger clinical anchor: an AI system scored therapeutic communication with an intraclass correlation above 0.97, and a retrieval-augmented implementation reserved the final decision for the teacher's professional judgment.

Competence, identity, and the evidence gap

- **Displacement is the design variable.** Sun et al. (2026)'s critical integrative review of 489 studies across 47 countries reframes LLM research in nursing around one criterion: whether the cognitive and participatory work an LLM displaces is *extraneous to* or *constitutive of* the competence being developed. Displacing documentation and routine retrieval frees working memory; displacing a full reasoning chain, an ethical justification, or an individualized care plan removes the object of learning. The evidence is not hypothetical — students using ChatGPT as a sole resource scored significantly below textbook controls on ethical standards and clinical reasoning, and an AI-integrated curriculum produced higher scores alongside less individualized, weaker-logic care plans, a performance–learning dissociation. Their **Professional Identity Tension Model** formalizes this across task, competency, and identity layers: outcomes measured with a tool available may index fluent performance rather than durable capability, so programs should use delayed, no-tool post-tests and transfer tasks.
- **The evidence is inverted.** The same review's gap map finds no randomized or quasi-experimental study of professional identity or career development, only three of relational and ethical competency, and no follow-up beyond 12 months — while controlled evidence clusters in cognitive and technical outcomes.
- **Surveillance is documented as perception, not as improved conduct.** Harerimana et al. (2026) mapped Remote Proctoring in nursing assessment across six studies (1,567 students) and found

deterrence reported almost universally by proctored students (98–100% agreement in one graduate program), while the single comparative performance study found an in-person proctored cohort scoring significantly higher on a readiness exam than a remotely proctored one. Anxiety ran both ways — some students calmer at home and relieved of travel, others unable to concentrate while watched and fearful of wrongful accusation — and four of the six studies reported connectivity failure, one load shedding, making equitable access the operative constraint rather than exam security. The authors' position is that remote proctoring should be one instrument among several, governed by data-protection standards and paired with integrity-by-design and authentic assessment rather than treated as the default safeguard.

- **Readiness splits inside a single faculty.** Rony et al. (2025) gathered 14 semistructured interviews and three focus groups with 16 participants, 30 nurse educators in total, at three nursing colleges in Bangladesh. Read through Technological Pedagogical Content Knowledge (TPACK), the transcripts put the readiness gap inside a single staff rather than between institutions: "Some of my colleagues are naturals with technology, but I feel like I need extra help to keep up" (P3), against unreliable connectivity and training nobody had provided. Ethics surfaced as a governance worry more than a curriculum topic, with data custody the recurring question ("Who has access to it, and how is it being used?"), and algorithmic bias the second. A mandate to adopt AI without training and infrastructure reads, in this account, as an unfunded expectation rather than a readiness failure. A published letter replying to the study makes that case at the institutional level rather than the individual one (Bridging implementation gaps: The critical role of institutional ecosystems in AI integration for nursing education).
- **A wide review base is not a deep one.** El Arab et al. (2025) read 18 prior reviews and found them converging on the same three priorities: ethical and social implications, transformation of nursing education, and strategies for integration. The reviews underneath stay largely descriptive, and von Gerich et al. reported that 34 of 93 studies failed to address ethical considerations at all, so agreement at the top of the pyramid is agreement among summaries.
- **Initiative is a design variable, not a learner trait.** Jin et al. (2026) randomized 79 medical and nursing students and graduates to a reactive agent that waits for prompts or a proactive one that drives sequenced questions, working over visuals generated from a four-person ward simulation. Epistemic network analysis separated the conditions with large effects on how ideas connected (Cliff's delta of -0.56 and -0.78), yet final writing scores did not differ. Their **agency gap** names both failure modes at once: an agent that demands more initiative than a learner has, and one that over-directs a learner who no longer needs it.
- **Risk models calibrated on another discipline flag this one almost everywhere.** Kovor et al. (2026) examined privacy-preserving at-risk prediction across program-discipline partitions, and the authors' own illustration is that a nursing program might run 30-35% at-risk while a concurrent medicine program runs 15-18%. Federated logistic regression kept 99.3-99.9% of centralized performance, so the barrier to cross-program modeling is organizational rather than statistical, but the same spread means an imported threshold misfires. Their finding that forum activity ranked last in every discipline is attributed to clinical placements, where peer learning happens in person.

- **Student AI-use surveys report a correlation and call it a mechanism.** Li et al. (2026) surveyed 1,020 nursing students at one institution, 98.8% of whom already used generative AI for coursework, and found AI interaction associated with educational interaction (r = 0.378) with self-regulated learning the stronger predictor (beta = 0.520). The structural model is just-identified, so it reproduces the data by construction and cannot order the three variables, and the interaction scale counts frequency and a peer norm rather than what a student does with the model.
- **Boundary conditions.** The strands converge on the same restraint. AI is best evidenced for structured, repeatable objectives — foundational communication, history-taking, health education, knowledge acquisition — and least evidenced for complex psychomotor skill, emotionally loaded interaction, and long-term professional formation. Acceptance is consistently moderate to high, but acceptance of AI *feedback* is conditioned by trust: learners prefer human sources perceived as benevolent over AI perceived as merely competent. The reviews are also geographically narrow, dominated by uncontrolled designs and self-report, and — in the simulation review — show a near-uniform positive pattern that raises publication-bias concerns.

Common Misconceptions

“AI-supported simulation improves nursing competence across the board.” The benefit stops at a documented boundary. AI-supported simulation reliably improves knowledge and Self-Efficacy but shows **inconsistent, sometimes negative effects on complex psychomotor skill** — and psychomotor competence is not a peripheral outcome in a profession defined by it. A program adopting simulation on the strength of knowledge gains has evidence for a different endpoint than the one licensure tests.

“The workforce anxiety around AI in nursing is really a skills gap, so AI literacy training is the remedy.” The anxiety is about employment, not about competence. A survey of **821 health-sciences students** found a moderate positive correlation between AI anxiety and job-search anxiety (**$r = 0.233$, $p < 0.001$**), with AI anxiety a significant predictor after controls. Teaching literacy addresses the fear of not being able to use a tool; it does not address the fear of not having a job — and the literature’s professional-identity framing, who becomes a nurse rather than what a trainee can do, is where that question belongs.

“Learners want AI agents as collaborators.” They want them as tools. Of **165 learners (158 completing)**, the agent was rated most useful *as a tool* (**$M = 3.49$**), then for feedback helpfulness (**$M = 3.21$**), and least *as part of the team* (**$M = 2.88$**), with all pairwise differences significant (**$F(2, 156) = 26.01$, $p < .001$**). Design that positions an agent as a team member is running against learner preference, not ahead of it.

“Any simulation study generalises to clinical practice.” The evidence base reviewed here — **19 studies, N = 1,253, mostly prelicensure students** — is largely classroom and laboratory based, and the translation from simulated competence to supervised practice is exactly the step an AI-assisted simulation does not by itself rehearse.

“AI competency for nursing means handling the tools, so training should start with them.” The framework literature runs the other way. The dimensions the reviewers found consistently addressed are ethics knowledge, responsibility, application and evaluation skills; technical and operational use is where the field has least to say. A program that buys tool licenses first is building the thinnest-evidenced part of the map, and the named frameworks it might adopt instead of a curriculum, N.U.R.S.E.S., AI-ABCs and CARE, are precisely the ones without assessment methods.

Implications for Practice

For instructors

- Do not adopt AI simulation to develop complex psychomotor skill on the strength of knowledge and self-efficacy gains. Keep deliberate supervised practice for the psychomotor endpoints and use AI where its evidence is strongest.
- Address employment anxiety directly rather than routing it through AI literacy modules; the correlation with job-search anxiety says the concern is about the profession's future, not the learner's tool fluency.
- Position agents as tools and feedback sources, which matches both learner preference and the design that produced the stronger ratings.

For faculty developers

- Treat readiness as a distribution and target the lower end of it, since a mandate without training and connectivity support reproduces the gap it is meant to close.
- Co-design the analytics with the people they describe: in one published case, nursing faculty and students built an AI-powered learning analytics dashboard together while educators kept responsibility for the judgments it informed (AI as Co-Designer and Feedback Partner: Enhancing Human Judgment).

For developers

- Report psychomotor and knowledge outcomes separately, since they diverge in this literature.
- Design for the tool and feedback roles first; agent-as-team-member framing is not what learners asked for.

For researchers

- Report prelicensure and practicing-nurse samples separately, and study the transition to supervised practice if the competence claim is to mean anything clinically.

Connected Concepts

- Medical and Health Professions Education
- Simulation
- Affective Computing
- Self-Efficacy
- Higher Education
- Learner Identity
- Workplace Learning
- Equity
- Cognitive Offloading
- Technology Adoption Models
- Anxiety and Stress

- AI Literacy

Connected Articles

- Transforming nursing education with artificial intelligence: A systematic review (2010–2025) — Systematic review of AI in nursing education (2010–2025)
- AI-Powered Simulation for Nursing Education: Mixed Methods Systematic Review — AI-powered simulation in nursing education: mixed methods systematic review
- When the algorithm enters the classroom: A critical integrative review of large language models, nursing education structural gaps, and the reconstitution of professional identity — LLMs, structural gaps, and the reconstitution of professional identity
- Nursing Students' and Faculty Experiences with Artificial Intelligence in Education: A Qualitative Study Using the Technology Acceptance Model — Nursing students' and faculty AI experiences through the TAM
- Artificial intelligence perceptions and career anxiety among health sciences students — AI perceptions and career anxiety among health sciences students
- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings — Generative AI to counter groupthink in interprofessional PBL
- 'Co-pilot won't teach you to be a nurse': Nursing academics' perspectives on GenAI use in undergraduate education — Nursing academics on GenAI: policy ambiguity, professional values, and the drift to invigilated assessment
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Remote proctoring in nursing assessment: surveillance, equity, and a deterrence case built on perception
- An artificial intelligence application framework for nursing education: a scoping review based on the KAS model — Scoping review mapping AI competency frameworks onto 12 KAS sub-dimensions for nursing curricula
- Nursing educators' perspectives on the integration of artificial intelligence into academic settings — Nursing educators in Bangladesh on AI readiness, barriers, and data governance, read through TPACK
- The role of AI in nursing education and practice: umbrella review — Umbrella review of 18 reviews: ethics, curriculum transformation, and integration barriers
- Redefining pedagogy with artificial intelligence: How nursing students are shaping the future of learning — Nursing students on the open secret of AI use: personalized learning, time, and the digital divide
- The agency gap in AI-supported writing: How reactive and proactive agent designs shape multimodal reasoning — RCT with medical and nursing students: reactive versus proactive agent design and the agency gap
- Generative artificial intelligence use and interpersonal educational interaction among nursing students: self-regulated learning as a statistical mediator — 1,020 nursing students: GenAI interaction, educational interaction, and a just-identified mediation model

- Bridging implementation gaps: The critical role of institutional ecosystems in AI integration for nursing education — A published reply to Rony et al.: institutional ecosystems, readiness, and AI oversight
- AI as Co-Designer and Feedback Partner: Enhancing Human Judgment — Faculty and students co-design a nursing education analytics dashboard
- Federated learning for privacy-preserving at-risk student prediction in health professional education: A multi-scenario evaluation of FedAvg and FedProx — Privacy-preserving at-risk prediction across health-professions programs, and why an imported threshold misfires in nursing

Legal Education

> **Legal Education** — the professional preparation of lawyers, and the discipline in which generative AI raises the strongest version of the question every program faces: whether assisted performance on law-school tasks is evidence of the analysis the license depends on. Its structure is unusual. In the United States, AI Governance of the curriculum runs through ABA accreditation and a licensure examination rather than a ministry syllabus; teaching leans on the case method and Socratic dialogue, which depend on students arriving having done the preparatory reading themselves; clinics and legal writing courses carry the experiential weight; and the professional conduct rules students will be bound by already apply to the tools they are being taught to use. AI enters through legal research platforms, drafting support, hypothetical generation, and bar preparation, and its signature failure is not a wrong grade but a fabricated citation.

Questions to Consider

- If a student briefs cases with an AI assistant but cannot reproduce the reasoning unaided, what has the Socratic classroom been assessing all along — the preparation or the tool that produced it?
- Law schools are being asked to govern AI while the profession they feed is still deciding what lawful AI-assisted practice looks like. Should legal education follow the bar, or lead it?
- Legal education has more policy documents than empirical studies on this question. Is a discipline that teaches evidence law unusually well placed to demand better evidence about its own AI adoption?

Introduction

Legal education prepares students for a licensed profession with its own rules of conduct, its own accreditation body, and its own gatekeeping examination, which makes it the discipline in the knowledge base where education policy, professional AI Regulation in Education and assessment validity intersect most tightly. It sits alongside Medical and Health Professions Education and Nursing Education as a Workplace Learning discipline rather than a school subject, but its distinguishing feature is procedural: much of what law schools must decide is not *how* to teach with AI but *what the professional ethics rules require* of a graduate who will practice with it.

The evidence base is currently thin and policy-heavy. One substantial article anchors the page: Gutowski and Hurley (2025) surveyed and compared institutional generative AI policies across ABA-approved US law schools and proposed a governance framework. That imbalance is itself a finding, and the page flags it rather than papering over it.

Experimental evidence is beginning to arrive: Xie et al. (2026) randomized 84 law undergraduates to a GenAI-authored mystery role-play game or to the same instructor's lecture, and the game group scored far higher on a knowledge-and-reasoning post-test (partial $\eta^2 = 0.566$).

How AI appears in legal education

- **Legal research.** Commercial platforms such as Lexis+ AI and Westlaw Precision with CoCounsel embed generative features in the tools students are already trained on, which makes "AI use" hard to separate from ordinary database searching. Gutowski and Hurley note how much of the familiar workflow this compresses: identifying authorities and secondary sources in minutes instead of hours.
- **Drafting and writing support.** Initial case briefs, outlines, memoranda, first-pass syntheses and sentence-level feedback on clarity and grammar. The authors place AI-generated work in the same supervisory relationship as work by a paralegal or junior associate: a lawyer remains responsible for its accuracy and legal sufficiency.
- **Study and bar preparation.** Generating practice questions, fact patterns, and "hypotheticals" for timed practice, and tutoring on recurring weaknesses. Gutowski and Hurley pair this with the observation that generative AI now passes both the Bar Exam and the Multistate Professional Responsibility Exam, which they read as saying more about the minimal-competency bar than about the model.
- **Task-specific profiles, not a leaderboard.** Under a blind protocol, the same out-of-the-box models that reached human bar-exam levels (cumulative scores 26–79 of 100) all failed the notary exam, which requires goal-directed legal planning under strict formal constraints — and were misled by deliberate traps embedded in it (Bertoli et al. (2026)).
- **Journals, moot court and advising.** Screening submissions, preparing advocacy, and academic support programs using custom models trained on past exams, model answers and course materials.
- **Assessment and integrity.** The recurring problem cases: undisclosed drafting, citation to non-existent authority, and exams that no longer measure unaided analysis.

What the policy evidence shows

Gutowski and Hurley assess policies on five dimensions with 0–5 rubrics: **prohibitiveness**, **permissiveness**, **educational integration**, **transparency and accountability**, and **depth**. Their canvass found that most law schools adopted generally prohibitive stances, often explained as buying time to study the technology, while almost all policies reserved discretion to individual instructors. The permissiveness and prohibitiveness ratings correlated inversely, as expected, and the authors report no single accepted approach: policies range from comprehensive governance to no stated policy at all.

They also document how thin the sector's evidence is. The ABA's 2024 AI and legal education survey drew responses from only 29 schools, roughly 15% of ABA-approved law schools, so it can hardly be treated as representative; and a LexisNexis survey of 800 law students found only 9% reporting current use of generative AI for their studies, with 25% planning to adopt it. The authors read low reported use partly as a response to unclear rules, since clarity reduces the fear of breaking them.

Two further points shape their recommendations:

- **Faculty governance is a law-school-specific complication.** Law faculties, individually and collectively, hold unusually direct authority over curriculum and course standards, so policy has to be built with them rather than announced to them.
- **Clinical education raises a pedagogical objection, not a technical one.** Citing Karr and Schultz, they report the position that AI tools designed to mimic human responses do not develop the original judgment, client interaction and ethical decision-making that clinics exist to produce, and therefore should not be used in clinical courses at all.

The recommendations are procedural: clear and comprehensive guidelines whatever the institutional stance, full stakeholder involvement in drafting, proactive training for students and faculty, flexible governance reviewed periodically, and self-regulation through information sharing rather than waiting for the ABA to dictate policy.

Why the discipline is distinctive

Three things make legal education more than one more subject area.

Assessment validity is inseparable from professional competence. Over-reliance during law school is feared to leave graduates underprepared for work that demands independent legal analysis and advocacy, and grading that rewards fluent output cannot distinguish a student's comprehension from a model's. The validity question is therefore not academic.

In a legal-context experiment, 186 lay decision-makers on tribunal civil cases deferred to an incorrect AI position far less when the system withheld its own position (5.7–8.2% versus 42.0–60.5%), yet built no measurable judgment — protective rather than corrective, and measured in lay decision-makers, not law students (Tuo et al., 2026).

Disclosure norms are unsettled and consequential. Gutowski and Hurley report disagreement about whether any use of AI must be disclosed, proposals for student disclosure forms, and no consensus on citation practice, with the Bluebook still silent on citing generative AI. They also predict that disclosure requirements will eventually look as pointless as noting that a student used a search engine, which is a prediction about the shelf life of the rules now being written.

Professional ethics travel with the graduate. The ABA's duty of technological competence and its guidance on confidentiality, supervision and candour toward the tribunal apply to practicing lawyers using these tools, and law schools inherit the job of teaching them. That is why the discipline connects directly to the knowledge base's work on AI use disclosure and on the legal issues and risks that arise when institutions govern AI badly.

Open Questions

- Does AI-assisted legal writing coursework still develop the analysis that licensure assumes, or does it train a fluency the bar exam cannot detect either?
- What happens to Socratic teaching if the preparatory reading is routinely delegated, and is the classroom's silence about it a measurement problem or a design one?

- Legal education produces the people who will litigate and regulate AI in education. Does that make it the natural place for the knowledge base's legal-risk work to be tested, or does it distort attention toward the law schools with the loudest policies?

Common Misconceptions

- **"Law schools have settled on a position."** Most adopted **generally prohibitive stances**, often explained as **buying time to study the technology**, while **almost all policies reserved discretion to individual instructors**. A prohibition with an instructor override is not a settled position, it is a deferral with a default.
- **"Survey evidence describes the field."** The **ABA's 2024 survey drew responses from only 29 schools, roughly 15% of ABA-approved law schools**, and a LexisNexis survey of **800** practitioners measures a different population. Neither can be treated as representative of legal education, and both get cited as though they were.
- **"Withholding an AI recommendation is neutral."** In a legal-context experiment, **186 lay decision-makers on tribunal civil cases deferred to an incorrect AI position far less when the system withheld its own position (5.7-8.2% versus 42.0-60.5%)**. Withholding did not produce neutrality; it produced a large reduction in deference, which is an effect in its own right.

Connected Concepts

- Academic Integrity — the conduct framework applied to assisted work
- Assessment Validity — whether assisted performance measures the intended competence
- Authentic Assessment — designs that require unaided analysis
- AI Use and Disclosure Statements — attribution and reporting norms still without consensus
- AI Governance — faculty governance and policy creation as law schools practice it
- Educational AI Policy — institutional AI policy as an object of study
- Critical Thinking — the reasoning the case method is meant to build
- Socratic Method — dialogue dependent on student preparation
- Experiential Learning — clinics and practice-based training
- Workplace Learning — the wider family of licensed professions
- Career Development and Readiness — practice readiness as the stated purpose
- AI Literacy — technological competence as a professional duty
- Hallucination Risk — fabricated citations as the field's signature failure
- Legal Issues and Risks — what institutions face when governance fails

Connected Articles

- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — Five-factor comparison of law school generative AI policies and a governance framework

- What out-of-the-box LLMs can(t) do in law? A Turing test in Italian exams for lawyers, judges and notaries — Blind Turing test on Italian bar, judges and notary examinations, benchmarked against expert marking
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Withholding the system's position suppresses overreliance in legal-context decisions without building judgment (lay decision-makers, not law students)
- GenAI-enabled educational game development: the effects of a scripted mystery role-playing game on students' learning experience and learning outcomes in legal education — GenAI-authored mystery role-play game versus lecture: a randomized trial (Xie et al. 2026)

Information Technology Education

> **Information Technology Education** — the branch of computing education that prepares practitioners to select, deploy, secure, administer, and govern the socio-technical systems organizations actually run, rather than to study computation as a discipline in its own right. Its closest neighbor, and the source of most boundary confusion, is CS Education: computer science education centers on algorithms, programming, and formal foundations, whereas IT education centers on applied configuration, cybersecurity, data and information management, and the organizational AI Governance of those systems. Generative AI reaches the field twice over — as an object students must learn to evaluate, secure, and regulate, and as an instrument that tutors them, classifies their questions, and quietly rewrites the professional pathways they are being prepared for.

Questions to Consider

- If AI compresses the build-fail-debug cycles that historically produced IT expertise, which foundational competencies should a curriculum deliberately protect, and which can be delegated to the tool?
- Students know their institution's rules and still cannot say whether their own use complies. Is that a communication failure, or is a rule-based instrument the wrong lever for a practice that happens privately on personal accounts?
- IT education sits between computer science, business, and vocational education. Who should own AI governance competence — a course, a curriculum thread, or a program-level outcome?
- If a transformer classifier separates higher-order learner questions at roughly 79% precision, should IT programs automate formative feedback on questioning at all?
- Most student mental models of GenAI are declarative and shallow. Does that predict misuse, or only an inability to explain decisions students are in fact making correctly?

Introduction

Information technology education is the applied wing of computing. It trains people to make systems work inside organizations — networks, databases, security operations, health information management, e-government services — and its graduates are usually assessed by professional bodies and employers rather than only by the academy. The distinctiveness relative to CS Education is the unit of analysis. CS education takes the program and the algorithm as its objects; IT education takes the deployed system and the practitioner's judgment about it. Where CS debates whether AI code generation erodes programming skill, IT debates whether AI troubleshooting erodes diagnostic skill, whether AI-drafted policy documents bind anyone, and whether graduates can govern the data systems they administer.

The neighboring disciplines overlap in different ways. STEM Education is the parent category and shares its instruments, but IT education is more often a professional master's or an applied undergraduate degree whose graduates enter regulated workplaces. Business Education is adjacent through information systems and e-government programs, which frequently share courses and students with IT curricula. Vocational

Education and Training is the other occupational neighbor: both fields train for practice, but vocational programs target technician-level competence in defined trades, while IT education assumes abstract systems reasoning and produces the people who write the governance documents as well as follow them. Higher Education names the level rather than the field, and the field carries an accreditation and compliance surface — health informatics accreditation, HIPAA and FERPA obligations for the data students handle — that shapes what counts as legitimate curriculum.

What is distinctive about AI in this field is that the same technology is both the curriculum content and the Pedagogies and Teaching Strategies. The bundled evidence converges on one uncomfortable theme: IT education's current AI agenda is dominated by integrity and tool adoption, while the governance, security, and data-ethics competencies the field's own workplaces demand appear mostly outside the documents students actually receive.

How AI appears in Information Technology Education

- **Gamified cybersecurity training.** Li and colleagues built several short, mobile-friendly games spanning password security through text and phone scam recognition, combining quiz-based, narrative-based, and Simulation-based designs with interactive formats such as TikTok Mini-Games, motivated by the low engagement and limited effectiveness of conventional video training (Security Education in Higher Education through AI-Powered Gamification). Their two-tier evaluation with 59 college students (9 technical experts, 50 general users) reports potential to improve engagement and attention to cybersecurity rather than demonstrated learning gains.
- **GenAI as scaffold or shortcut in self-regulated learning.** A mixed-methods study of 267 postgraduate IT students in Australia distinguishes scaffolded Cognitive Offloading (learners clarify goals, generate ideas, obtain Feedback they then critique and adapt, so Learner Agency stays with them) from substitutional offloading (outputs accepted with minimal verification, control shifting to the tool) (Scaffold or Shortcut? Postgraduate IT Students' Use of Generative AI and Self-Regulated Learning). Confidence shaped orientation: confident students exercised autonomy in goal setting and monitoring, while less confident peers read GenAI as a shortcut or as misconduct. The cohort was differentiated, not homogeneously AI-literate; the authors recommend requiring students to justify or adapt AI outputs as an explicit Learning Design move.
- **Compressed expertise pathways in professional practice.** Fourteen semi-structured interviews with IT professionals found GenAI acting as both a mentor-like tutor and a ladder-shortening tool in troubleshooting, scripting, and system verification (Unanticipated effects of generative AI on expertise pathways and performance perception in system administration). Accelerated unfamiliar-domain performance reduces exposure to the build-fail-debug cycles that historically built expertise; AI-assisted speed also resets team and self-expectations, producing a two-speed culture and productivity guilt. The study carries classroom concerns about metacognitive cost and skill decay into Workplace Learning and workplace learning.

Assessment and the learner side of IT AI use

- **Learner questions as diagnostic signals.** Lee, Atif, and Kang classified 434 authentic student queries from 12 IT courses into three Constructivism instructional roles — knowledge transmitter,

facilitator, and co-learner — reaching consensus labeling with human-in-the-loop review (Fleiss' kappa 0.60 rising to 0.83) and augmenting the corpus to 582 balanced questions (Analysing AI utilisation in education through learner question types: A constructivist approach). The per-class results were uneven: DeBERTa scored 86.36% accuracy and 96.67% precision on factual questions, facilitator precision slid to 78.79%, and a fine-tuned BERT showed 92.00% recall but only 74.19% precision on co-learner items. Errors came from conceptual similarity between roles, ambiguous learner intent, and domain phrasing misread as cognitive depth; the authors warn that augmentation may have introduced lexical shortcuts, and the 11-student, IT-only corpus cannot yet generalize to other fields.

- **Wide but shallow mental models.** From 64 usable concept maps drawn from 86 undergraduates in a required technology-ethics course, five mental-model categories emerged: technical-process based, educational-tool based, transitional, consequence-aware, and integrated (Uncovering Students' Mental Models of Generative Artificial Intelligence). Every map showed declarative knowledge, 25 showed procedural, 17 conditional, and only 9 integrated all three. Technical and social-regulatory clusters sat far apart, which the authors read as AI Literacy and ethical awareness developing separately; integrity-centered guidelines, they argue, address only one dimension of how students conceptualize the tool.
- **Rules known, compliance uncertain.** A survey of 151 undergraduates in Business Information Systems and E-Government programs found most students actively using GenAI but over half unsure whether their usage complied with institutional regulation, with only weak to moderate associations between regulatory awareness and actual behavior, and reliance mostly on privately accessed tools rather than institutional ones (Knowing the Rules Is Not Enough: Student Regulatory Awareness and Use of GenAI in Higher Education). Knowing the rules did not strongly predict what students did.

Institutional policy and the governance gap

- **Guidance, not policy.** An environmental scan of all 48 accredited health informatics and health information management master's programs found 40 (83%) with at least one publicly available AI document, but the modal artifact was advisory guidance (21, 53%) rather than formal policy (7, 18%) (Institutional approaches to artificial intelligence policy and guidance in health informatics and information management education: emerging trends and inconsistencies). Academic integrity dominated the vocabulary (n = 139), ahead of citation (n = 59) and Assessment (n = 50), while HIPAA (n = 5), FERPA (n = 11), equitable access (n = 2), and disclosure requirements (n = 1) were nearly absent, and electronic health records were not mentioned at all. Latent Dirichlet Allocation produced four themes around integrity, student GenAI use, university research tools, and ChatGPT engagement. Because only public documents were analyzed, the authors treat the absence of privacy and equity language as a finding about published guidance, not about institutional practice.
- **The equity blind spot.** Inclusion (n = 9), accessibility (n = 9), accommodations (n = 4), and equitable access (n = 2) appear at rates that cannot support any claim that Equity has been addressed, even though several programs require AI use in coursework. Together with the thin treatment of professional AI Governance competence, this is the clearest design task the bundle

leaves open: connecting integrity rules to the access, privacy, and data-governance provisions those graduates will be responsible for enforcing.

Common Misconceptions

“Information technology education is computer science education with more vendor tools.” The boundary is the object of study. Computer science education centers on algorithms, programming and formal foundations; IT education centers on applied configuration, cybersecurity, data and information management, and the organizational governance of socio-technical systems. The distinction changes what an AI tutor should be good at: an IT learner needs judgment about a deployed system’s failure modes, not a proof about a computation.

“A classifier accurate enough to identify question types is accurate enough to automate formative feedback.” Aggregate accuracy hides the per-class error that matters. In the comparison this page cites, DeBERTa led at **86.36% accuracy and 96.67% precision on factual questions**, but facilitator precision fell to **78.79%**; a fine-tuned BERT reached **92.00% recall on co-learner items at only 74.19% precision**. Automation would route roughly one in four of those to the wrong intervention — and the errors concentrate on the pedagogically interesting categories, not the easy ones.

“Most programmes having an AI document means AI governance is in place.” In an environmental scan of all **48 accredited** health informatics and health information management master’s programs, **40 (83%)** had at least one publicly available AI document — but the finding is titled guidance, not policy. A published set of recommendations is not a governance mechanism: it neither assigns responsibility nor specifies what happens when a system fails.

“Students who cannot explain an AI-supported decision are misusing AI.” The alternative explanation is that they cannot articulate a decision they made correctly. IT work is full of competent practice whose rationale is tacit, and treating inarticulate competence as misconduct misdiagnoses a teaching target as a discipline problem — it needs explanation practice, not a policy.

Implications for Practice

For instructors

- Report per-class precision, not headline accuracy, before automating any feedback routing. The facilitator-precision figure is the one that determines how many students receive the wrong help.
- Teach explanation as a deliverable in its own right, so that inarticulate competence is distinguishable from misuse.
- Distinguish guidance from governance when reading institutional policy, and ask who is accountable when a tool in the pipeline errs.

For developers

- Publish confusion matrices by learner category; a model strong on factual questions and weak on co-learner contributions will systematically miss the collaborative cases.
- Do not position a routing classifier as a replacement for a facilitator. At 74-79% precision it is a triage aid.

For programme designers

- Build the governance artifact the sector is missing: named responsibility, review cadence, and an incident path. An AI guidance document satisfies an accreditation question and not an accountability one.

Connected Concepts

- CS Education
- STEM Education
- Business Education
- Vocational Education and Training
- Higher Education
- Workplace Learning
- AI Literacy
- Academic Integrity
- AI Governance
- Cognitive Offloading
- Equity

Connected Articles

- Security Education in Higher Education through AI-Powered Gamification
- Scaffold or Shortcut? Postgraduate IT Students' Use of Generative AI and Self-Regulated Learning
- Unanticipated effects of generative AI on expertise pathways and performance perception in system administration
- Institutional approaches to artificial intelligence policy and guidance in health informatics and information management education: emerging trends and inconsistencies
- Analysing AI utilisation in education through learner question types: A constructivist approach
- Uncovering Students' Mental Models of Generative Artificial Intelligence
- Knowing the Rules Is Not Enough: Student Regulatory Awareness and Use of GenAI in Higher Education

Research fields

Learning Sciences

> **Learning sciences** — the interdisciplinary research field that studies how people learn and how to design environments in which learning happens, drawing on cognitive psychology, learning theory, computer science and linguistics, and judging its designs with empirical evidence rather than theory alone. In this knowledge base it is the research field around AI in education rather than one of the school subjects. It supplies the mechanisms that AI systems operationalize (knowledge components, mastery thresholds, transfer), the design objects they are embedded in (planned course sequences, tutors, Feedback regimes) and the standards by which they are judged (Learning Gains, Assessment Validity, equity). Its organizing question is not whether a tool performs well but whether a learner changed.

Questions to Consider

- A learner passes every practice item, so the mastery threshold ends the set — then misapplies the rule where the action should be withheld. Whose error is that: the learner's, the model's, or the stopping rule's?
- Sequence mining can describe 554 courses as patterns without observing a classroom. What does the field gain, and lose, by studying designed intentions instead of enacted activity?
- Demographic sensitivity in an LLM's feedback looks like adaptation when it tracks a learner's stated education level and like bias when it shifts sentiment. Should a field that cannot separate the two keep using open-ended models to assess?
- Does the learning sciences' appetite for causal design — randomized assignment, counterfactual audits, executable models of the learner — narrow what counts as evidence in AI in education?

Introduction

The learning sciences study learning and the design of learning environments, and they are defined by their methods as much as their topics: experiments, classroom trials, quantitative modeling of student data, qualitative analysis of designs and contexts, and design-based research that builds an intervention and revises it in use. That breadth separates this page from the neighbours that supply the frameworks, the practice and the instruments; the section below sets out each boundary and what the field has established on the other side of it.

This page covers the substantive knowledge such methods have produced — what learners do with a generative model, which arrangements change outcomes, and where the field's own instruments fail. AIEd in the Disciplines takes the opposite cut, holding that subject matter changes what support should do; the learning sciences take the cross-cutting view, and the mechanisms they test are gathered under Cognitive Psychology.

How AI appears in the learning sciences

- **Mechanism first, then the model.** An, McLaren and Stamper (2026) ran eleven experiments (N = 192) with Intelligent Tutoring systems for Riichi Mahjong and showed that learners who compiled an overgeneralised production — the action without its application constraint — misapplied it on the first "do-not-act" item at 61.5%–100%, against 12% expected error under Bayesian knowledge tracing. With a 95% mastery threshold the system stopped practice before learners met a case requiring the action to be withheld, so the defect went undetected. Short do-not-act practice with Feedback naming the missing constraint cut misapplication to 0.0%–23.1% (Cohen's h 1.70–2.44), and a secondary analysis of thirteen K-12 *Decimal Point* datasets found the same structure in whole-number bias (84%–88% of comparison errors).
- **A consensus maps where GenAI helps and harms learning.** A preregistered Delphi of 30 learning scientists rated 65 learning processes and agreed on 42: GenAI threatens initial acquisition and higher-order thinking but enhances consolidation (Kendeou et al., 2026).
- **Feedback style, not agent type, moved self-regulatory engagement.** In a 2 × 2 experiment with 51 postgraduate students, Socratic feedback was associated with stronger comprehension monitoring while directive feedback carried higher cognitive load; the two styles ran in a fixed, non-counterbalanced sequence, so the contrast is condition-related rather than causal (Han et al. (2026)).
- **The optimum depends on the content.** Rachatasumrit, Koedinger and Carvalho (2025) treat the example–problem ratio as a content–treatment interaction: in a 2×2 experiment with 95 participants on geometry-area material, practice-only training produced larger learning gains for verbatim facts while example-integrated training produced larger gains for generalizable skills ($\beta = 0.41$, $p = .038$, $d = 0.38$). A simulated learner (Apprentice Learner) reproduced the crossover only when given an ACT-R-style memory-and-forgetting mechanism. More practice is not uniformly better: memory-oriented content warrants retrieval, and induction-oriented skills warrant integrated examples.
- **Design as an analysable object.** Divjak, Svetec and Horvat (2026) turned Learning Analytics on Learning Design itself, coding 29,064 activities across 554 courses planned in a free course-design tool. Acquisition was the most common learning type and the most common entry point; the strongest Markov transition was Assessment → Discussion (0.332) and the highest-confidence rule was Acquisition → Assessment → Practice → Practice (0.743, lift 1.45). Learning type tracked intended outcome level, Acquisition falling from about 50% of activities at Bloom level 1 to around 20% at level 6. The authors stress these are pre-implementation designs: resemblance to flipped, inquiry-based or project-based sequences is not evidence of intent.
- **Auditing the models that assess.** Rooein, Benedetto and Hovy (2026) audited six LLMs across essay scoring, formative feedback and question answering, holding the task input fixed while varying only demographic context (192,480 calls). Scoring was stable under explicit personas, but Llama-70B inflated its own scores by 1.57 points under implicit conversational history ($p < 0.001$), and higher education drew less readable and more positive responses — a sentiment gap of roughly four standard deviations. Readability effects shrank while length effects grew, and some coefficients changed sign between conditions. The authors offer it as an audit instrument, not a

deployment verdict, and read the entanglement of demographic and topical signal as a threat to validity and equity.

- **Measuring competence, and its limits.** Verí (2026) organizes instruments for competent Generative AI use into four domains — knowledge and use, epistemic oversight, reliance calibration, and control of tool-using agents — refusing to collapse them into one proficiency continuum. Three same-sample correlations between self-rated and demonstrated AI literacy pooled to r = .055 (95% CI [-.047, .156], reported N = 2,765), which the author reads as enough to reject treating self-ratings as interchangeable with performance scores, though not enough to set a cutoff. No validated instrument covered the full set of decisions that tool-using agents create; the proposed layered battery is a design hypothesis.
- **Self-report about the learner's own offloading.** Alam (2026) translates the Cognitive Offloading literature into PAUSE, a browser-only self-check with four domains, every LLM-era item anchored to a source, no composite, no storage and no model in production; its bands are descriptive rather than normed, and a reading must not justify assessment, admissions or hiring decisions. Its stated limits matter: self-report of offloading is vulnerable to the faculty it concerns, a respondent who deliberately uses AI as a scaffold reads as offloading on several items, and whether AI-associated offloading is distinct from general technology dependence remains open.
- **Where human expertise sits.** Wang et al. (2024) report the clearest division of labor: in a two-month randomized controlled trial with about 900 novice K-12 tutors and roughly 1,800 students. Real-time suggestions drawn from experienced tutors' reasoning raised topic mastery by 4 percentage points (62% to 66%, $p < 0.01$), and by 9 points for lower-rated tutors, at about $20 per tutor per year. The suggestions shifted tutoring toward guiding questions. Gains were proximal — year-end tests did not move. Reichert et al. (2026) find teachers arriving at the same position by design: six secondary teachers prototyping chatbots specified a bounded expert, holding authority boundaries (responsibility for learning and safety is not delegable) and expertise boundaries (the model lacks their knowledge of individual students), and delegating content presentation, practice and corrective Feedback while reserving objective-setting and summative assessment.
- **Capability at the level of the field.** Sutedjo, Chowdhury and Liu (2026) surveyed 127 faculty with a TPACK instrument adapted for generative AI: strong content and pedagogical content knowledge (M = 4.70–5.15) beside markedly lower technology-integrated knowledge, with holistic TPACK lowest at 2.55, content knowledge uncorrelated with any technology-integrated domain, and the three integrated domains correlating so highly (r = .81–.91) that they may function as one factor. Perrotta (2026) reads the governance layer through a discontinued UK civil-service prototype whose codebase was a system prompt plus a retrieval pipeline over commercial models, arguing that the generality of foundation models both enables rapid repurposing into policy tools and makes aberrant output a permanently only-mitigable risk — oversight that peers over the loop rather than sitting inside it.
- **The integration gap, mapped:** Malik and Bashir (2026) synthesized 32 studies (PRISMA 2020, thematic analysis) into four themes: epistemological fragmentation within the field, theory–technology contradictions (computational systems run on prediction and measurable behavior while educational theories emphasize context and social interaction), the datafication of

learning through analytics, and hybrid intelligence as an emerging paradigm. Their Hybrid Intelligence Framework is a conceptual synthesis, not a validated model — the authors state it awaits empirical testing — but the four-theme map is a useful audit lens for the theory-to-computation translation problem this field keeps hitting.

- **How students use a generative model matters more than whether they do.** Coding 50 undergraduate exchanges found 64% were passive review or transactional questions and only 36% strategic dialogue, and a reflection-structured assignment shifted the balance toward dialogue (Zahra, 2026).
- **Within-person reliance precedes a drop in perceived Learner Agency.** Across three waves of data from 342 undergraduates in 85 fixed groups in an AI-supported collaborative writing course, higher-than-usual GenAI reliance predicted lower subsequent perceived human agency, while the reverse path was weaker and not statistically supported (Wu and Lu (2026)).
- **The distribution of GenAI use is an institutional choice.** Sun, Dohn and Rehm (2026) classified 102 higher-education studies by how epistemic work was distributed between student and system and found Assistant and Enabler entanglements dominating at 42.16% each, reading the skew as institutional legitimacy rather than technological capability.
- **Process evidence is channel-conditional.** Coding one GenAI-assisted instructional-design task with 79 undergraduates in both interaction logs and concurrent think-aloud, Li and Liu (2026) found higher-depth monitoring evidence more common in the think-aloud record but higher-depth AI Regulation in Education evidence more common in the logs, so neither trace alone is the criterion for a metacognitive claim.
- **The method matters as much as the finding: sequence analysis of group-AI interaction.** Wang et al. (2026) coded 595 and 785 utterances around 39 chatbot prompts, tested lag-1 transitions with adjusted residuals and Yule's Q, then ran process mining with each episode as a case. That pairing placed the AI at the center of one group composition's interaction network and on a single path in another, a difference that prompt tallies could not show. It is a template for asking where an AI sits in a group's interaction network rather than how often it appears.

How the learning sciences relate to their neighbours

Design-based research is the method this field developed rather than borrowed: an intervention is built and revised inside a working classroom, with its theoretical rationale revised alongside it, so one study yields both an artifact and a design principle. That is what separates it from a laboratory experiment, which isolates a cause by holding the context still, and it is why the field's findings arrive as design knowledge rather than as effect sizes. Research Methods in AIED takes the other cut: that page surveys the whole repertoire — experiments, surveys, qualitative work, benchmarks, reviews, consensus methods — as a choice among instruments, weighed for the validity of the claim each can support. This page reads the same corpus from the substantive side, asking what the repertoire has established about learning and judging a method by whether its design claim survives contact with learners.

Learning Theories collects the candidate frameworks — Behaviorism, cognitivism, constructivism, sociocultural accounts, motivation and self-regulation — as lenses for reading AI. The learning sciences

share that vocabulary but not that stance: here a theory is a claim about mechanism that a design must either instantiate or refute, and the field's standing rests on empirical and design work rather than on the coherence of a framework. The theory page is the one to open for what a framework asserts; this page is the one for the evidence a framework has accumulated.

The field also builds theory rather than only testing borrowed frameworks: Theory Development in AI in Education covers the conceptual work that explains how learners, teachers and AI systems interact, and it is where the field's own constructs are argued before they are measured. What its designs are usually asked to produce is transfer — knowledge and skill that survive past the tutor, subject or task they were learned in — which is why a gain measured inside a tool counts as a weaker claim than one measured without it. And because a designed environment is a compound intervention, attributing an outcome to one component is the field's standing measurement problem: Educational Measurement supplies the psychometric apparatus that makes the attribution arguable at all, which is why measurement questions arrive early here rather than after the fact.

Cognitive Psychology is the mechanism-level discipline the field draws on most heavily, supplying bounded working memory, encoding and retrieval, decomposable knowledge components and the diagnostic language of learner modeling. The learning sciences use those mechanisms without reducing to them: their unit of analysis is a designed environment carrying social, motivational and contextual variables that a laboratory account of memory does not, and their tests are run on whole interventions rather than on isolated cognitive effects.

Pedagogies and Teaching Strategies and Learning Design cover practice — which teaching strategy to use, and how to sequence objectives, activities and assessment into a course. Both are what the learning sciences study from the outside, as objects of description and evaluation; the field does not tell a teacher which tactic to reach for next, it reports what the tactics have been shown to do. Learning design is the closer relative, since both produce something that can be implemented and tested, but the designer's output is a teachable course and the field's output is knowledge about designs in general.

The findings only matter once they reach teaching, and that journey runs through three pages. Educational Development is the institutional practice that carries them — faculty development, standards, policy and identity work decide whether a validated design ever reaches a classroom, which is why the field's evidence routinely leads what institutions have implemented. Teacher Education is where the knowledge has to land before a teacher enters the room, and Teaching is where it lands afterwards, in the moment-to-moment judgment about when to intervene, which instrument to use, and when to leave a learner alone. None of the three produces learning-science findings; all three decide whether those findings change practice.

Common Misconceptions

- **"A high mastery threshold guarantees the learner can discriminate."** An, McLaren and Stamper (2026) ran **eleven experiments (N = 192)** with Intelligent Tutoring systems and found that at a **95% mastery threshold the system ended practice before any case required the learner to withhold the action**, so the defect went undetected. Mastery of the action did not include knowing when not to apply it, and the threshold certified the wrong construct.
- **"More examples are safer."** Rachatasumrit, Koedinger and Carvalho (2025) treat the example-problem ratio as a **content-treatment interaction**, and in a 2×2 experiment the optimum

depended on the content. There is no globally correct ratio, so a fixed instructional template is a bet against an interaction.

- **"Fixing the misconception is a matter of telling students the right answer."** Short do-not-act practice with Feedback naming the missing constraint cut misapplication to **0.0%-23.1% (Cohen's h 1.70-2.44)**, and a secondary analysis of **thirteen K-12 *Decimal Point* datasets** found the same structural pattern. The effective intervention was discriminating practice with targeted feedback, not correction by assertion — which is what refutation work establishes generally.
- **"Higher Bloom level means more active learning."** Acquisition dominated the lower levels — **about 50% of activities at Bloom level 1** — and shrank to **around 20% by level 6**. Cognitive demand and activity type move together but are not the same axis, so tagging a task by Bloom level does not tell you what learners will do with it.

What this means for practice

For instructors

- Teach the negative case explicitly. The 95%-threshold failure is the reason: build in conditions where the correct move is to withhold the action, or the learner will apply it everywhere.
- Do not fix the example-problem ratio across a course. The content-treatment interaction means the right ratio for procedures is not the right ratio for concepts.
- Use discriminating practice with feedback that names the missing constraint rather than restating the rule. That is the intervention with measured effect sizes here.
- Check what your mastery criterion actually certifies before you trust it.

For developers

- Do not stop practice on correctness alone. Model the withholding condition as its own skill, or the system will certify overgeneralisation.
- Let the ratio be a parameter rather than a constant, because the evidence says the optimum is content-dependent.
- Report which construct your criterion measures, separately from which construct your validation measures.

Connected Concepts

- Learning Theories
- Cognitive Psychology
- Pedagogies and Teaching Strategies
- Learning Design
- Research Methods in AIED
- Theory Development in AI in Education
- Design-Based Research
- Teacher Education
- Educational Development

- AIEd in the Disciplines
- Intelligent Tutoring
- Learning Analytics
- Assessment Validity
- Educational Measurement
- Cognitive Offloading
- Learning Gains
- Transfer of Learning
- Teaching
- Equity
- Educational AI Policy

Connected Articles

- Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use — Review and exploratory meta-analysis of measures for competent generative-AI use (Verí 2026)
- Deceptive overgeneralization: When adaptive learning enables systematic misapplication — Correctness masking an incomplete rule: mastery stopping rules in adaptive learning (An, McLaren & Stamper 2026)
- The Role of Implicit and Explicit Demographic Signals in Large Language Model-based Student Assessment — Counterfactual audit of demographic signals in LLM student assessment (Rooein, Benedetto & Hovy 2026)
- Learning paths and patterns in learning design: Insights from 500+ courses — Markov chains and pattern mining over 29,064 activities in 554 courses (Divjak, Svetec & Horvat 2026)
- PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading — A privacy-preserving, non-diagnostic self-check for AI-associated offloading (Alam 2026)
- Zero-shot governance — Zero-shot governance: general-purpose AI in policy, read through the Redbox codebase (Perrotta 2026)
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content — Why the best example–problem ratio depends on content (Rachatasumrit, Koedinger & Carvalho 2025)
- Human-centered design of LLM-powered educational chatbots: A study with secondary teachers — Teachers design bounded-expert chatbots, with selective delegation of instruction (Reichert et al. 2026)
- Assessing faculty self-perceived knowledge in using generative AI to teach 21st-century skills — Faculty GenAI TPACK: strong content knowledge, weak technology-integrated knowledge (Sutedjo, Chowdhury & Liu 2026)

- Tutor CoPilot: A human-AI approach for scaling real-time expertise — Tutor CoPilot: a randomized trial of human–AI live tutoring at scale (Wang et al. 2024)
- Ways generative AI can support and threaten learning in K-20 US education — A 30-expert preregistered Delphi on which learning processes GenAI enhances and which it threatens
- Three Pathways of Student-AI Interaction: Constraint-First Design for Higher-Order Thinking — A typology of student-AI interaction: 64% passive or transactional, 36% strategic dialogue
- The Effects of Agent Type and Feedback Style on Self-Directed Learning: A Mixed-Methods Study — Feedback style, not agent type, moved self-regulatory engagement
- Mapping the Distribution and Depth of Metacognitive Processes in Generative AI-Assisted Learning: Evidence from Interaction Logs and Concurrent Think-Aloud Protocols — Process evidence is channel-conditional
- Literacy demands placed on students in student–GenAI entanglements in higher education — The distribution of GenAI use is an institutional choice
- A helping hand or a dominant partner? Individual perceptions of GenAI reliance and human agency in collaborative learning — Within-person reliance precedes a drop in perceived agency
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — Lag sequential analysis plus process mining placed the AI at a group-interaction hub or on a linear path depending on preconception composition (Wang et al. 2026)

Levels and contexts

Levels and settings

K-12

> **K-12** — the use of artificial intelligence in primary and secondary education, spanning AI literacy curricula, AI tutoring, teacher support, and safety considerations unique to younger learners. A 2026 PRISMA-guided systematic review of 197 studies (2016–2024) organizes the field around four opportunity domains — personalization, motivation, Assessment, and innovative teaching practices — while flagging persistent gaps in teacher training, ministerial ethical guidelines, and discipline balance.

Questions to Consider

- K-12 AI use demands stronger safety protections than higher education because younger learners are least equipped to detect unsafe or manipulative AI. How does that change what ‘safe’ must mean for tools used by children?
- Systematic reviews find the K-12 evidence base concentrates overwhelmingly on STEM, leaving the arts and humanities largely unstudied. What might a discipline-balanced K-12 AI evidence base reveal that STEM-only studies miss?
- Research finds teachers systematically overestimate their AI competency — a roughly 40% gap between self-report and performance — yet short training yields substantially higher integration. What might that gap mean for how schools prepare teachers?
- Most AI tools center dominant perspectives, yet 78% of teachers in one study found AI helpful for culturally relevant pedagogy. How can a tool that defaults to dominant views be steered to broaden representation rather than narrow it?
- Evidence suggests outsourcing AI work can harm learning, especially for older students — yet younger students may be less affected. Why might the learning penalty of AI use differ by age, and what does that imply for design?
- The K-12 review identifies eight under-explored research gaps, from the missing concrete teaching-unit examples to the underuse of robotics, wearables, and mobile communication. Which of these gaps most limits what schools can actually do today?
- Institutional AI policies often lack implementation guidance. What would it take to turn a K-12 AI policy document into concrete classroom practices and teacher training — and why might that translation so often fail?

Introduction

The evidence landscape

A 2026 PRISMA-guided systematic review (Marzano, 197 studies, 2016–2024) now anchors the K-12 evidence base, complementing earlier large syntheses such as the rapid review of GenAI and PreK-12 learners and the aggregated K-12 AI evidence base. Its four-question structure organizes the field into four opportunity domains — personalizing learning, motivating students, improving assessment, and enabling

innovative, immersive teaching — with ChatGPT as the flagship case studied across a large share of the included articles.

The review's central finding is a sharp asymmetry: the *promise* of GAI in schools is broad and well documented, but the *evidence of daily classroom practice* is thin, concentrated in STEM, and skewed by a shortage of concrete teaching-unit examples and practical teacher training. This gap between aspiration and implementation is the defining feature of K-12 GenAI research.

A teacher-side synthesis adds the layer that tool-focused reviews leave out. A PRISMA review of 29 studies of teacher intervention in K-12 AI-based instruction finds that AI output — alerts, dashboards, automated scores, chatbot feedback — becomes teaching only through a cycle of monitoring, judgment, intervention and orchestration, and that the reported benefits for student performance, participation and confidence are conditional on the interpretability of the information, intervention timing, the level targeted, teachers' implementation feasibility and students' autonomy. Its corpus is concentrated in the same places as the wider K-12 evidence base: mathematics and science/STEM subjects, middle and high school grades, and United States settings.

Distinctive K-12 considerations

- **Safety and guardrailing:** K-12 AI use demands stronger Pedagogical Safety protections. EduZone, EduGuard, and tutor harm research specifically address child-safe AI interaction.
- **AI literacy curricula:** K-12 AI literacy modules develop age-appropriate AI understanding, while the vibe coding framework empowers teachers to create their own AI tools. A quasi-experimental study of an 18-hour, 5E-model critical media literacy program for fourth-grade Turkish students (Demir & Akar 2026) embedded generative AI (ChatGPT, Grammarly, Canva AI, Padlet) phase-by-phase as a pedagogical agent aligned to the Turkish Language and Social Studies curricula, producing large gains in media reading (+3.50), writing (+1.67), and total media literacy (+5.17, all $p < .01$) with between-group effect sizes of Cohen's $d = 1.12–1.31$, and qualitative growth across six domains of critical media literacy (digital self-protection and data privacy, purposeful and responsible media use, safe communication and boundary awareness, critical evaluation and misinformation awareness, online risk awareness, and media ethics/digital citizenship) — evidence that age-appropriate, discipline-embedded AI literacy curricula can yield measurable critical-media gains in the elementary grades.
- **Tutoring at grade level:** K-12 personalized companions and correct answer trap research examine tutoring effectiveness for younger students.
- **AI tutoring's constraint is engagement, not capability.** In 18 Tennessee middle schools, assignment to Khanmigo raised math achievement ~0.06–0.08 SD per school year — gains resembling Khan Academy practice without AI — because the median student messaged the tutor in only 17% of mistake sessions (Oreopoulos and Low, 2026).
- **Developmental appropriateness:** Child safety research and Special Education considerations address the needs of diverse K-12 populations.
- **Age-tailored conversational AI:** Vahedian Movahed & Martin (2025) deployed AMA, a topic-bounded chatbot with age-varied prompt tailoring, with 63 students (grades 1 and 6–8). Children showed broad openness to and high trust in the chatbot as an information source and actively

tested its credibility with known-answer questions, while gaps in digital-safety awareness (some were willing to confide secrets) point to age-sensitive Scaffolding and explicit Privacy instruction.

Teacher-knowledge effects

- **Teacher-knowledge effects.** A cross-level study (46 teachers, 2,832 secondary students) found pedagogical AI knowledge — not technical AI knowledge — drove students' perceptions of AI for social good and their intention to learn AI, reinforcing a "pedagogy first, technology second" approach to K-12 AI teacher preparation.
- **Continuous training as the binding constraint.** The Marzano review identifies continuous, targeted teacher training on ICT as the single most persistent integration challenge, and it must cover technical, pedagogical, and ethical dimensions while adapting to rapidly evolving tools. Initial and ongoing training should be continuous, collaborative, game-based, transparency-focused, and grounded in professional development for advanced tools like ChatGPT. This extends to classroom collaboration-support AI: the Community Builder (CoBi) feasibility study in middle-school classrooms found that high-integrity teacher use depended on substantial professional learning, with under-prepared teachers drifting toward treating the tool as a performance monitor or into general AI-discussion rather than its intended collaborative focus.
- **Unplugged Machine Learning literacy through familiar content.** In an online professional-development program, Sung and Gunpinar (2026) had ten K–12 educators build a visible yes/no feature matrix for classifying 2D shapes, so the algorithm could be inspected rather than accepted as a black box, and Self-Efficacy toward AI use rose from 3.13 to 3.71.
- **The competency gap.** Research shows teachers systematically overestimate their AI competency — a roughly 40% gap between self-report and performance — yet brief training interventions (e.g., 4-hour prompting workshops) can yield substantially higher classroom AI integration. This makes teacher preparation and Teacher Education central to successful K-12 AI integration.

Four opportunity domains

The systematic review consolidates what GAI can do in schools into four recurring domains:

- **Personalized learning.** GAI tailors learning experiences to individual needs, pace, and readiness — the flagship benefit documented across companion systems and adaptive platforms.
- **Readability and curriculum alignment.** Bird (2026) fuses transformer text classification with computational-linguistics features to classify English literature by UK Key Stage (F1 0.996), packaged into a no-code web app so teachers can align reading materials to learners' levels — a concrete, discipline-relevant (English/literature) complement to the STEM-heavy K-12 evidence base.
- **Motivation and engagement.** Tools like ChatGPT make learning more engaging for younger students, supporting engagement and Motivation — though the review also warns this can tip into excessive reliance and technological dependency.

A 42-study meta-analysis qualifies that: the motivational effect was smallest in school settings (secondary g = 0.360, primary g = 0.311) against g = 0.886 at university, though those subgroups rest on only 9 and 4

studies (Fang et al. (2026)). - **Assessment.** GAI improves Assessment methods, from formative Feedback to automated scoring, though bias in automated feedback remains a live concern. Razavi and Powers (2026) extend this to item calibration in K-5: across 5,170 math and reading items, GPT-4o's zero-shot difficulty ratings correlated moderately-to-strongly with Rasch-calibrated difficulties (r = 0.83 math, r = 0.81 reading) but were uneven across grades and no better than a grade-mean dummy regressor for grades K and 1 — a range-restriction limitation that matters for early-grade assessment. A feature-based approach (Large Language Models (LLMs)-extracted features into tree-based models) reached correlations up to r = 0.87, with gains most pronounced for early-grade items. - A related question is which model a school runs at all: on NGSS-aligned middle-school (1,078 items) and high-school (1,150 items) sets, nine open-weight models from six labs mostly scored above 90% and model size did not predict accuracy — OSS-20b and Nemotron 3 Nano 30b a3 matched models several times larger — while item difficulty ran high and discrimination low, leaving the authors to ask whether the Benchmark is too easy (Schroeder et al. 2026). - **Innovative teaching practices.** Immersive, game-based, and collaborative approaches make learning more engaging, with constructionist and project-based models showing particular promise. A concrete classroom-wide example is the Community Builder (CoBi), an AI collaboration-support system deployed across six middle-school classrooms that used speech recognition to visualize small-group "uplifting" discourse — evidence that real-time speech AI can work feasibly in noisy K-12 environments to support the relational dimension of learning.

Cultural relevance imperative

LLM-supported curriculum design shows promise for diversifying materials — in one study 78% of teachers found AI suggestions helpful for culturally relevant pedagogy. However, most AI tools center dominant perspectives, requiring deliberate equity-centered design to avoid widening opportunity gaps.

The caveat is that representation is not transformation: in an all-girls GenAI makerspace, girl-only grouping, women facilitators and feminine marketing acted only at the symbolic level, while cost barriers and English-only prompts persisted and only two of 44 generated images reflected the workshop's own climate-change topic (Liu et al. (2026)).

Policy-to-practice translation

Institutional GenAI policies largely lack implementation guidance. The systematic review underscores that ministerial guidelines addressing Ethics and Privacy remain underdeveloped, echoing the policy-to-practice translation problem: successful models transform policy documents into actionable teacher training modules, bridging the "what" (policy) and "how" (prompting instruction).

Scale and equity

K-12 AI deployment operates at societal scale — millions of students, compulsory education, and significant equity implications. Equity research examines whether AI widens or narrows opportunity gaps, including access and inclusive support for students with disabilities — one of the review's eight under-studied areas.

Raising the floor is not leveling the playing field: over a year of school AI instruction, 752 Hong Kong junior-secondary students gained confidence, motivation and ethical awareness, with low-agency late

learners approaching parity, while objective AI-literacy gaps persisted and self-initiated learning predicted the largest cognitive gains (Liang et al. (2026)).

Eight research gaps

An innovative contribution of the Marzano review is its explicit enumeration of eight under-explored research gaps that shape a K-12 GenAI research agenda: (1) a lack of concrete examples of AI in teaching for constructing teaching units; (2) a need for practical, daily teacher training based on constant AI application; (3) skills in machine learning and a balance between disciplines, with STEM over-represented; (4) a lack of studies and experiments in Europe; (5) a need to define the teacher role and create specific pedagogical frameworks such as Technological Pedagogical Content Knowledge (TPACK) or AI4K12; (6) inclusivity and support for students with disabilities; (7) a connection with pedagogical theories and innovative methodologies; and (8) applications of emerging technologies such as wearables, robot control, and mobile communication.

Connections

K-12 connects to Pedagogical Safety (child protection), AI Literacy (student competency), Teaching (K-12 teacher transformation), Equity (access gaps), and Special Education (diverse learner needs). Its systematic-review evidence base links to Meta-Analysis and Systematic Review as a method, and its discipline-imbalance finding connects to STEM Education, Humanities and Social Science Education, and Early Childhood Education.

Implications for K-12 instructors

- **Prioritize child-safe guardrailing.** K-12 AI use demands stronger safety protections — use tools specifically built and vetted for children (EduZone, EduGuard) and be alert to the harms of unguarded tutors (tutor harm research).
- **Build AI literacy age-appropriately.** Use curricula and frameworks designed for younger learners (K-12 AI literacy modules), and don’t assume students arrive with responsible-use knowledge.
- **Close the teacher-competency gap.** Teachers systematically overestimate their AI competency (~40% gap between self-report and performance), yet short training (e.g., 4-hour prompting workshops) yields substantially higher classroom AI integration — invest in your own preparation (Teacher AI Competency, Teacher Education).
- **Keep training continuous and practice-grounded.** The systematic review’s core recommendation is that teacher training cannot be one-off — it must be continuous, collaborative, and based on constant daily AI application, not abstract theory.
- **Diversify materials deliberately.** AI is strong at culturally relevant material generation (78% of teachers find suggestions helpful), but tools default to dominant perspectives — actively use AI to broaden, not narrow, representation, and guard against opportunity gaps.

- **Watch the learning-penalty risk.** Evidence shows outsourcing AI work can harm learning, especially for older students (cognitive surrender, homework-outsourcing penalty) — design assignments that keep cognitive work in the loop and assess for durable understanding, not just completion.
- **Distinguish a productive slowdown from a streak.** A randomized field experiment with 6,000+ middle-school students found AI support slowed progress but raised next-attempt correctness after errors, while a three-correct-in-a-row rule lifted platform mastery by roughly 28.7 percentage points without improving a delayed test a week later (Oreopoulos et al. (2026)).
- **A disengaged turn is not a stable state.** Rho et al. (2026) coded 5,522 middle-school math utterances and found the highest-performing cluster recovered from mocking or wrong answers, while withholding was the one disengagement behavior that persisted rather than resolved.
- **Modeled prompts can become templates students copy.** Across two 120 min STEAM modules, twelve eighth-graders' GenAI logs were dominated by information requests (303 of 310) and exact copying of the instructor's instruction was their most frequent standpoint (47.1%), with evaluation and reflection at 0.5% of coded content and result verification never coded (Zhao and Li (2026)).
- **Design teacher tools for judgment, not volume.** More AI information is not better: real-time alerts expanded teachers' awareness but in some studies overloaded attention or pulled focus from their own observation, and a single teacher cannot act on more intervention targets than they can physically reach (Lee 2026). Tools that prioritize and explain what is worth acting on, and let teachers accept, revise, defer or reject recommendations, fit the work better than dashboards that surface everything — and the structural conditions (review time, class size, support personnel) are part of the intervention, not background logistics.
- **Extend beyond STEM.** The evidence base skews heavily toward STEM; educators and researchers in the arts and humanities have an outsized opportunity to generate the discipline-balanced evidence the field is missing.
- **Translate policy into practice.** Institutional GenAI policies often lack implementation guidance; turn policy into concrete, actionable classroom practices and training (policy-to-practice).

AI Adoption and Skepticism in K-12

- As AI enters schools, the staff it affects are increasingly urged to consult conversational AI about adoption. An algorithmic audit of ten frontier LLMs probed a rural K-12 AI-skeptic persona, finding eight of ten models acknowledged concerns before redirecting to AI-engagement framings — a model-dependent design outcome rather than an inevitable property of LLMs. Trust, skepticism, and human oversight are therefore central to how rural and other K-12 staff encounter AI.

Grade-band progression is asserted in these frameworks and tested in none of them. Kharbach et al. (2026) searched 339 records and included 50 K-12 AI literacy frameworks, and found no study that tracked the same students across more than one grade band. Sun and Chan's measurement invariance across

years 10 to 12 supports consistent scoring rather than developmental growth. A K-12 plan can sequence content across grades, but that sequence is a design proposal rather than an evidence claim.

Common Misconceptions

- **"Teachers know their own AI competence."** Teachers **systematically overestimate their AI competency** — a **roughly 40% distance** between what self-report claims and what measurement shows. Self-Assessment is not a usable needs-analysis instrument at this level of divergence.
- **"AI tools are culturally neutral in practice."** Most AI tools **center dominant perspectives**, yet **78% of teachers** in one study found AI **helpful for culturally relevant pedagogy**. Teachers are using these tools for a purpose the tools were not built to serve well.
- **"The K-12 evidence base is one literature."** A **PRISMA-guided systematic review of 197 studies (2016-2024)** organizes the field around **four opportunity domains**, which means findings under one domain are not evidence under another.
- **Compulsory-school students acquire AI practice before AI curriculum.** Bergdahl (2026) studied a Swedish school running an "AI on the schedule" pilot for **year 7 students**, in a country whose national curricula include AI training only from upper secondary upward. The instruction covered ethics, prompting, train-your-own-model, recommender systems and data collection across three phases — and still left **data privacy (Mdn = 1)** and **algorithmic manipulation (Mdn = 2)** the weakest registers, against governance at Mdn = 4. Where the curriculum is silent, a pilot can supply instruction; it does not thereby supply the outcome.

Connected Concepts

- Pedagogical Patterns — The level of the productive-failure, conceptual-change and oral-assessment studies
- Early Childhood Education — Early childhood and elementary AI education
- Pedagogical Safety — Child-safe guardrails for AI interactions with younger learners
- AI Literacy — Age-appropriate student understanding and responsible use of AI
- Teaching — Teacher transformation and AI integration in K-12 classrooms
- Equity — Whether AI widens or narrows K-12 opportunity gaps
- Special Education — Diverse learner needs in K-12 AI use
- Scaffolding — Support structures for AI-assisted K-12 learning
- Personalized Learning — Tailored instruction enabled by AI at the school level
- STEM Education — AI literacy and tools across K-12 science, tech, engineering, math
- Generative AI — The core technology behind K-12 AI tools and curricula
- Teacher Education — Training and upskilling teachers for classroom AI
- Sociocultural Learning — Social and cultural dimensions of K-12 AI learning
- Metacognition — Thinking about thinking; key to durable AI-era learning
- Educational Development — Ongoing professional development for teachers
- Learning Design — Designing lessons and materials with AI support
- Active Learning — Keeping cognitive work in the loop when using AI

- Computational Thinking — Foundational K-12 skill and AI curriculum target
- Intelligent Tutoring — AI tutoring systems for younger students
- Meta-Analysis and Systematic Review — The systematic-review method behind the K-12 evidence base
- Humanities and Social Science Education — Discipline-balance counterpart to STEM-heavy K-12 AI evidence
- Parents and Families
- Cognitive Surrender

Connected Articles

- Generative Artificial Intelligence (GAI) in Teaching and Learning Processes at the K-12 Level: A Systematic Review — Systematic review of generative AI in K-12 teaching and learning (Marzano 2026)
- Pedagogy first, technology second: Cross-level relationships between teacher professional knowledge and student learning in artificial intelligence (AI) education — Cross-level effects of teacher AI knowledge (TAIK, TPAIK) on student learning in secondary AI education (Shen et al. 2026)
- Does school-based AI education narrow readiness gaps? The role of prior agency-related learning — School AI education narrows psychological but not cognitive readiness gaps
- AI-supported problem-based learning for enhancing computational thinking — AI-assisted project-based learning and computational thinking
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- One click away: AI tutoring with Khanmigo in a two-year school experiment — One Click Away: Khanmigo in a two-year school experiment
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers — EduZone: child-safe LLM interaction platform for K-12
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education — EduGuard: safe RAG-based LLM tutor guardrailing
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — Research on harms of unguarded AI tutors for children
- Learning to Use AI for Learning: Teaching Responsible Use of AI Chatbot to K-12 Students Through an AI Literacy Module — K-12 AI literacy modules on prompting
- The Evidence Base on AI in K-12: A 2026 Review — The K-12 AI evidence base aggregated at scale
- ECNUClaw: A Learner-Profiled Intelligent Study Companion Framework for K-12 Personalized Education — K-12 personalized AI companions

- A Guiding Framework for K-12 Teachers in Creating AI-powered Learning Technologies through Vibe Coding — Vibe-coding framework empowering teachers to build AI tools
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Rapid review: GenAI and PreK-12 learners (271 papers)
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — Cognitive surrender strongest for high schoolers, absent for Grade 5
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: homework outsourcing harms learning
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: bias in automated feedback for middle-school writing
- Code to Learn with Generative AI: A Theoretically Grounded Framework for Artifact Construction in Upper-Secondary Education — CtL-GenAI: constructionism framework for artifact construction
- Beyond "painting in pink": A critical case study of all-girls generative AI workshops in a European makerspace and implications for gender equity in computing — All-girls GenAI makerspace workshops and gender equity in computing
- Transforming clicks into critical thinking: An AI-based media literacy program for children — AI-based critical media literacy program for children
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms
- Ask Me Anything: Exploring Children’s Attitudes Toward an Age-tailored AI-powered Chatbot
- Teacher intervention in K-12 AI-based instruction: a systematic review of processes, strategies, and effects — Teacher intervention in K-12 AI-based instruction: a systematic review
- A Benchmark for LLM’s Understanding of Middle School and High School Science Topics — A Benchmark for LLM’s Understanding of Middle School and High School Science Topics
- Effects of generative artificial intelligence on students’ learning motivation: evidence from a meta-analysis — Meta-analysis of GenAI’s effect on motivation, smallest in school settings (secondary $g = 0.360$, primary $g = 0.311$)
- Disengaged Conversational Behaviors and Learning in Student-AI Dialogues for Mathematical Problem Solving — Disengaged conversational turns in middle-school mathematics: withholding persists where mocking recovers
- Exploring Middle School Students’ Interactions and Perceptions of Using Generative AI in STEAM Learning Environments — Modeled prompts can become templates students copy
- Bringing Artificial Intelligence Literacy Into Online Education: Machine-Learning Integration Through Geometry in K–12 Teacher Professional Development — Unplugged machine-learning literacy through familiar content

- K-12 AI literacy frameworks after generative AI: A scoping review - no K-12 framework follows the same students across grade bands; progression is proposed, not tested

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?

Early Childhood Education

> **Early childhood education** — the use of artificial intelligence in the education of young children, spanning preschool and the elementary (primary) years. This covers AI-literacy and computational thinking curricula for young learners, AI-enabled toys and play, personalized learning in elementary subjects, and the developmental, safety, and equity considerations unique to children rather than adolescents or adults.

Questions to Consider

- Young children now meet AI through toys, chatbots, and classroom robots. What makes a 5-year-old's relationship with AI fundamentally different from an adult's — and what should change about how we think about the risks?
- Some early-childhood AI literacy is taught through 'unplugged' play — no computers at all. How can abstract AI concepts be learned through embodied, tangible activities rather than screens?
- A concern called 'technological isomorphism' describes young students mimicking AI output without understanding. How would you distinguish a child who has genuinely learned from one who is simply parroting back a polished answer?
- Because young learners are more vulnerable and less able to self-regulate, adult Scaffolding becomes central. What does that mean for a parent or teacher deciding when and how a child should use AI?
- If access to AI-rich early learning — or to protective adult guidance — is uneven, how does equity show up differently in early childhood than it does for older students?
- The evidence base here is largely exploratory and design-oriented rather than causal. What would you want to know before trusting a claim about an AI toy or app improving children's learning?

Introduction

Young children interact with AI increasingly early — through AI-enabled toys, chatbots, adaptive learning platforms, and classroom robots — yet they differ developmentally from the K-12 and higher-education learners who dominate most AI-in-education research. This concept gathers the knowledge base's coverage of that younger band. It sits within the broader K-12 umbrella but is distinct because the concerns are developmentally specific: play as a primary learning mode, adult (parent/teacher) scaffolding, age-appropriate AI literacy, and heightened attention to Well-Being and safety.

How the research clusters

- **AI literacy through unplugged play.** The AI-Play framework teaches early-childhood AI concepts through *unplugged* (no-computer) activities, showing that abstract AI ideas can be introduced to young children through embodied, playful, and tangible activities (see Game-Based Learning) — a developmentally appropriate route into AI Literacy and Computational Thinking.

- **AI-enabled toys and child development.** Research on AI in toys examines how commercial AI-enabled playthings shape child development and play. This raises open questions about agents in play, trust calibration, Learner Agency, and Well-Being for the youngest learners — an area where design guidance is thinner than for school-age curricula, and where parents/guardians become central stakeholders.
- **Children's attitudes toward age-tailored chatbots.** Vahedian Movahed & Martin (2025) deployed "Ask Me Anything" (AMA), a topic-bounded chatbot (astronomy, sneakers and shoes, dinosaurs) tailored by age via prompt engineering, for 63 children (ages 6–14), revealing three patterns in child–AI interaction — wonder and curiosity, testing trust and building confidence, and building relationships through anthropomorphization — alongside a broad openness to and high trust in AI as an information source. Their call for age-sensitive design and explicit teaching of digital-safety and data-use concepts reinforces the developmental and safety concerns central to this concept.
- **Elementary subject learning.** AI-powered personalized learning in elementary fractions and AI in elementary math (including concerns about "technological isomorphism" — students mimicking AI output without understanding) show both the promise and the pitfalls of AI in early subject instruction. A systematic review of elementary writing and GenAI maps how generative AI is reshaping writing instruction in the early grades.
- **Primary English language learning has its own map.** A PRISMA-ScR review of 119 reports on AI-mediated tools in primary English sorted them into five pedagogical functions, and its strongest design, a cluster randomized trial with 217 second-grade learners, gained on taught words (effect size = .38) while standardized vocabulary and reading comprehension did not reach significance (Li and Zhou (2026)).
- **Robots and young children.** Robotics in kindergarten supports computational thinking through educational robots, and LLM-powered humanoid storytelling explores whether parents will accept robots as narrative play partners for their children — foregrounding Trust and adult attitudes.
- **Conversational agents as SEL facilitators, not substitutes.** Raave et al. (2026) had 18 educators and 18 agent simulations each lead three story-based social-emotional learning activities with a static AI child, giving 108 blind-coded observations: the agent was steadier on respectful tone and procedural scaffolding, while educators led on guiding reflection and social-emotional knowledge.
- **A competency set, not an AI-literacy curriculum.** A review of 86 resources argues AI literacy "cannot be standalone" for children aged 0 to 8 and nests it among executive functions, well-being, learning dispositions, and foundational skills, though only 26 of the 86 resources were empirical (Pei (2026)).
- **A "Creative Project Approach" pairs AI agents with classroom robots.** Yang, Li and Lee (2025) propose a five-step pedagogical framework that integrates generative AI agents and robots into the Project Approach to foster young children's creative learning. They argue physical agents are more appropriate than screens for young children. They pair two complementary paradigms with their learning theories — **coding robots** (Papert's constructionism; computational thinking through tangible programming with tools like Matatalab and KIBO) and **generative social robots** (Vygotskian scaffolding within the child's Zone of Proximal Development, acting as

conversational peers or tutors). The five steps — identify learning needs, facilitate teacher-guided child–robot interaction, situate AI in contexts, calibrate the automation/creativity balance, and evaluate outcomes — offer designers and ECE practitioners a concrete route for embedding AI agents and robots in play-based, project-based classrooms while preserving teacher facilitation and child Learner Agency.

- **Play-centered AI literacy curricula.** Lee (2026) reports the design-based research of Play With AI (PL-AI), a developmentally appropriate curriculum in which two pre-K and two kindergarten teachers co-designed seven sequenced activities blending unplugged play (composing and testing "how-to" algorithms), tangible coding (Bee-Bot, Ozobot), and guided dialogue with a social AI robot. Formative evidence showed substantial growth in teacher confidence and pedagogical agency, with four design principles emerging — **embodied play, tangible coding, guided dialogue, and teacher co-design** — aligned with the AI4K12 Initiative and NAEYC frameworks. This is a model of how robots and tangible tools can be embedded in play-based, teacher-led AI literacy for the youngest learners.
- **AI-assisted lesson planning for children's STEAM arts teachers.** An experimental study of children's art teachers (Luo and Tahir 2025) found ChatGPT-assisted lesson plans were rated significantly higher in quality than teacher-generated ones by six expert professors (median 20.5 vs. 17.6, $p = .002$, large effect), while mapping how teachers delegated — most often (60%) to fill content gaps in a self-outlined lesson rather than to generate whole plans. Teachers valued AI chiefly as an inspiration and gap-finding tool for interdisciplinary STEAM integration and faster topic selection, but flagged outputs that were impractical for real classrooms, overlooked child-safety constraints (e.g., carving knives for young children), and carried Western-centric cultural bias — concrete, developmentally grounded caution for generative AI use with young learners that a Role–Instructions–End Goal prompt framework was built to temper.
- **AI-supported critical media literacy in the elementary years.** Demir and Akar (2026) evaluate an 18-hour, 5E-model critical media literacy program for fourth-grade students in a Turkish public primary school, embedding generative AI (ChatGPT, Grammarly, Canva AI, Padlet) phase-by-phase as a pedagogical agent rather than an isolated add-on, with activities aligned to the Turkish Language and Social Studies curricula. The AI-supported group showed large gains in media reading (+3.50), writing (+1.67), and total media literacy (+5.17, all $p < .01$) with between-group effect sizes of Cohen's $d = 1.12–1.31$, while the control group advanced only modestly. Qualitative analysis of interviews, student artifacts (posters, drawings, slogans), and classroom observation surfaced six domains of critical media literacy growth — digital self-protection and data privacy, purposeful and responsible media use, safe communication and boundary awareness, critical evaluation and misinformation awareness, online risk awareness, and media Ethics/digital citizenship — offering a rare quasi-experimental, curriculum-aligned model of how AI can support critical AI literacy and critical thinking in the elementary grades.
- **AI-rated observation of teacher–child interaction quality.** Fong et al. (2026) benchmark an Large Language Models (LLMs) against trained human raters on the full CLASS Pre-K framework in Hong Kong kindergartens — 87 video-recorded observations from 38 classrooms across 30 kindergartens, rated from transcripts by GPT-5.0 and compared with eight trained raters. Agreement was moderate overall (weighted $\kappa = 0.681$) but conditional on the construct:

convergence held for the Emotional Support domain and for Quality of Feedback — the dimension carried by explicit, exchange-based verbal support — while Classroom Organization diverged entirely and raters rated the emotional dimensions higher than the model did, at a very large gap on the reverse-scored Negative Climate dimension (d = 2.732; raters gave the maximum of 7 in 63 of 71 observations, AI clustered at 6). The early-childhood lesson is developmentally specific: quality that lives in nonverbal, spatial and routine behavior — management, movement, warmth, tone — is invisible to a transcript-only pipeline, the model's error direction is construct-dependent rather than uniformly conservative, and the authors therefore position AI scoring as a screening and reflection tool for teachers rather than a substitute for trained observers.

- **Preservice educators designing science activities.** Efthimiou & Plakitsi (2026) had 131 preservice early-childhood educators design magnetism activities with LLMs: they rated the models' structure and efficiency highest (M = 3.95) but the epistemic trustworthiness of their content lowest (M = 3.08), treating them as brainstorming artifacts while keeping didactic transformation a human responsibility.
- **What predicts whether preschool teachers adopt AI at all.** A survey of 270 preschool teachers in Shanghai, Zhejiang and Guangdong, modeled with an extended TAM, found perceived usefulness and ease of use predicted intention to use AI, with AI Self-Efficacy raising it and AI anxiety lowering it (Duan, Shan and Gong 2026). The study excluded child-facing tools by design, so its levers — confidence-building and low-stakes training — concern teachers' own professional work.
- **AI approximating developmental judgments of children's stories.** Yin et al. (2026)'s CLARA annotates a story's cognitive, language, and social-emotional demands and matches publisher age references 0.904 of the time, ahead of readability formulas (0.603) and direct prompting (0.730) - offered as a supportive signal, not a replacement for a human judge.

Developmental and equity considerations

Because young learners are more vulnerable and less able to self-regulate their use of AI, this cluster emphasizes **scaffolding by adults** (parents, guardians, and teachers), **age-appropriate design**, and the risk of over-reliance and harm if AI substitutes for, rather than supports, the developmental work of play, discovery, and effortful learning. Equity is a live concern: access to AI-rich early learning (or to protective adult guidance) is uneven, connecting to Digital Divide and Equity. Much of the evidence base remains exploratory or design-oriented rather than causal.

A four-country comparison sharpens the curriculum gap: Japan, South Korea and China's national early childhood guidelines contain no explicit AI literacy references (Shanghai's city-level action plan is the lone exception, specifying no learning progressions), while Australia shows only limited, uneven alignment — strongest in interacting with AI agents, absent in understanding human-AI relationships — leaving AI literacy to the home (Cohrssen et al. (2026)).

A first neuroimaging window on this question arrives with a caution: 6–7-year-olds holding a five-minute spoken conversation with ChatGPT in an MRI scanner showed weaker within-network connectivity than adults in the frontoparietal control, salience and dorsal attention networks, at matched creativity scores, and lacked the creativity–connectivity coupling adults showed. Because those executive functions are still

immature at first grade, the authors read the result as relevant to the minimum-age debate — while flagging a framing confound and the absence of a no-ChatGPT control as limits on what it settles (Horowitz-Kraus et al. (2026)).

Common Misconceptions

- **“Teachers will use AI to generate whole lessons.”** Teachers delegated most often (**60%**) **to fill content gaps in a self-outlined lesson** rather than to generate whole plans. The unit of delegation is the gap, not the lesson.
- **“Young children gain less from AI-supported media literacy.”** The AI-supported group showed **large gains in media reading (+3.50), writing (+1.67) and total media literacy (+5.17, all p < .01)** with between-group effect sizes d = 1.12 or higher. The gains were large in this age band, not marginal.
- **“Automated observation agrees with human raters across the board.”** Agreement was **moderate overall (weighted κ = 0.681) but conditional on the construct**: convergence held for the **Emotional Support** domain and for **Quality of Feedback**, and not elsewhere. Averaging over the domains hides where the instrument fails.

Connected Concepts

- K-12
- AI Literacy
- Computational Thinking
- Robots in Education
- Pedagogical Agent
- Game-Based Learning
- Experiential Learning
- AI in Education
- Math Education
- Writing
- Well-Being
- Learner Agency
- Pedagogical Safety
- Trust Calibration
- Equity
- Digital Divide
- Parents and Families

Connected Articles

- Shaping early childhood in the age of AI: holistic competencies, pedagogical practices, and ecological support — Shaping early childhood in the age of AI: competencies, pedagogy and ecological support (Pei 2026)
- Preservice Early Childhood Educators' Engagement with Generative AI in Science Activity Design: The Case of Magnetism — Preservice Early Childhood Educators' Engagement with Generative AI in Science Activity Design: The Case of Magnetism
- CLARA: Can AI Assess Developmental Appropriateness in Children's Stories? — CLARA: Can AI Assess Developmental Appropriateness in Children's Stories?
- Exploring factors influencing preschool teachers' behavioral intention to use AI technologies in early childhood settings — Preschool teachers' behavioral intention to use AI in early childhood settings (Duan et al. 2026)
- AI-Play: A Framework for Teaching Artificial Intelligence Concepts through Unplugged Activities in Early Childhood Education — AI-Play: unplugged AI concepts in early childhood
- Artificial Intelligence in Toys: Implications for Child Development and Play — AI-enabled toys and child development
- Fostering computational thinking through robotics in kindergarten: A systematic review of learning strategies, frameworks, and assessment — Computational thinking through robotics in kindergarten
- Exploring Fraction Comprehension and Interest in Elementary Education Through AI-Powered Personalized Learning — AI-powered personalized learning in elementary fractions
- Rethinking Elementary Education's Writing Instruction in The Age of Generative AI: A Systematic Review — Elementary writing instruction in the age of GenAI
- Awareness of Technological Isomorphism: Integrating AI into Elementary Mathematics Teaching on Data and Prediction — A Case Study of the Compound Line Graph — Technological isomorphism in elementary math
- Would you let a humanoid play storytelling with your child? A usability study on LLM-powered narrative human-robot interaction — LLM humanoid storytelling with children
- An experimental study exploring human–AI complementarity in early social-emotional learning — Human–AI complementarity in early social-emotional learning (Raave et al. 2026)
- Play with AI (PL-AI): A play-centered, design-based curriculum for AI literacy in pre-K and kindergarten — Play With AI (PL-AI): play-centered AI literacy curriculum for pre-K and kindergarten (Lee 2026)
- Transforming clicks into critical thinking: An AI-based media literacy program for children — AI-based critical media literacy program for children
- ChatGPT-assisted lesson planning for children's STEAM arts education: An experimental study on benefits, challenges, methods, and a prompt framework

- Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot
- Tailoring AI agents for early learning: The Creative Project Approach — The Creative Project Approach: a framework for tailoring AI agents and robotics to early learning (Yang, Li & Lee 2025)
- Lower engagement of cognitive control in children on ChatGPT — First neuroimaging comparison of children and adults conversing with ChatGPT: less integrated control-attention-memory networks in 6-7-year-olds
- I code or AI code: A comparative evaluation of AI-rated scores in classroom observations — I code or AI code: AI-rated CLASS Pre-K scores versus trained human raters in Hong Kong kindergartens (Fong et al. 2026)
- AI literacy for AI natives? A four-country comparison — AI literacy for AI natives? A four-country comparison
- AI-mediated tools in primary English language education: a scoping review of pedagogical functions and teacher orchestration — AI-mediated tools in primary English language education: a scoping review of pedagogical functions and teacher orchestration

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?

Higher Education

> **Higher Education** — the integration of artificial intelligence into university teaching, learning, assessment, and administration. Higher education is the most-studied context in the knowledge base, with over 100 articles examining how AI transforms college-level instruction, institutional policy, and student experience. AI in higher education is both the dominant setting for AIED research and the site where its tensions are most visible — between generative AI's promise of scalable personalization and its risks to integrity, learning, Privacy, and equity. It encompasses both undergraduate and graduate study, including professional programs such as medicine and business.

Questions to Consider

- Higher education is where AI's tensions are most visible — scalable personalization versus risks to integrity, learning, privacy, and equity. Which of these tensions do you see playing out most concretely in your own institution?
- Large studies reveal gaps between institutional policy and what students actually do with AI day to day. Why do you think official policy so often diverges from real student practice?
- The page frames AI adoption as uneven — some institutions transform while others lag, shaped by organizational drivers and national policy. What factors do you think determine whether a university adapts or stalls?
- As AI makes personalized one-on-one support nearly free and universal, how does that shift the value and role of the university itself? What becomes scarcer and therefore more valuable?
- One finding notes a decline in study time among college students using AI. If students spend less time studying but report satisfaction, what does that suggest about what institutions should be measuring and guarding?
- Given the gap between faculty self-assessed and actual AI readiness, what would meaningful faculty development look like in your context — and who should be responsible for it?

Introduction

AI in higher education research spans every function of the university: from AI tutoring and automated grading to faculty development, academic integrity, institutional governance, and student support. The knowledge base's higher education articles cluster around several key themes — institutional transformation, student experience at scale, faculty and teaching, assessment and integrity, and the rapid shift in policy and practice. Across the review's 394 GenAI higher-education studies, participant focus was students in 352, instructors in 15, both in 26, and multiple stakeholder groups in 1 — so the evidence base for perceptions and teaching practice is overwhelmingly student-based (Lin et al. (2026)).

Institutional transformation

Institutional change frameworks analyze how universities adapt to AI — not just at the classroom level but across policy, governance, and organizational structure. The EPIQ-AI framework reframes faculty readiness as a sociotechnical alignment challenge involving epistemic, pedagogical, institutional, and quality domains. Rethinking universities in the AI era examines whether current institutional models can accommodate AI-driven education. Adoption is not uniform: organizational-driver research identifies what enables or blocks institutional uptake, and national policy analyses show how systemic context shapes university responses. A concrete institutional blueprint comes from Qin (2026), who documents Lingnan University's repositioning as a "Research-Intensive Liberal Arts Institution in the Digital Era," mandating GenAI literacy for all undergraduates and embedding digital literacy across the Common Core while developing a human-in-the-loop model that foregrounds ethical reasoning and critical judgment — arguing the AI-for-education shift is an intellectual transformation, not technocentric augmentation. Macro-level mapping of 22 higher-education AI-integration interventions (AlSheikh et al., 2026) reinforces that transformation remains more aspiration than reality: graded on the SAMR model, most interventions sit at Substitution or Augmentation, integration is concentrated in medicine, engineering, and computer science with little humanities presence, and evidence skews to North America and Asia with minimal Global South representation.

A global comparative index measures the discourse–structure gap. Chan (2026) coded the official websites of all 100 Times Higher Education 2026-ranked universities against a 20-indicator AI Institutionalization Index. The symbolic layer is saturated while the structural layer is thin: 100% have an AI task force and a master's AI degree, but only 12% have executive AI leadership, 5% require an introductory AI course for undergraduates, and 0% publish an AI accessibility policy despite 93% deploying AI campus services.

Institutionalization also proved independent of prestige (rank correlation $r \approx 0.04$), with significant regional variation (ANOVA $F = 5.86$, $p < .001$; North America $M = 0.63$ vs. Europe 0.51, Asia 0.50) and a six-model typology in which only a small subset of mostly large US publics reach "deep institutionalization." The author flags the index as a first-generation, unvalidated, website-only measure of the elite top 100 — a comparative map, not a scorecard.

Which forms of GenAI use an institution has made legitimate is itself measurable. Sun, Dohn and Rehm (2026) classified 102 empirical higher-education studies by how epistemic work was distributed between student and system, and found Assistant (42.16%) and Enabler (42.16%) applications dominating while Generator, Reimaginator and Synthesizer together made up under a fifth of the corpus — not because the models cannot do the rest, but because the marginal forms distribute authorship in ways the university's individual-competence logic does not yet recognize. On their account the binding constraint on GenAI in higher education is institutional legitimacy rather than technical capability, which puts the question squarely in the same policy and assessment-redesign territory as integrity and Assessment reform.

Ranieri and Biagini (2026) tested the 2019 four-category higher-education taxonomy against 228 publications from 2019–2026 and found 58.4% of the 154 classifiable applications fall outside it, adding AI-enabled student support, content and instructional design, and institutional analytics as functional domains.

AI deployment outside the classroom has become a consumer-protection question, and the student-side inventory of it is thin. Student Defense's SHAPE AI report (2026) maps institutional AI use across admissions, recruitment and financial aid, student-success services (advising, counseling, benefits access, credit transfer), and education delivery — LMS-embedded features from Canvas, Blackboard and D2L

Brightspace, institution-wide GenAI platforms, tutoring and feedback systems, detection and proctoring — and argues that adoption is outrunning protection. Its six cross-cutting concerns (whether students get what they pay for, the loss of learning communities, disclosure and transparency, data privacy, bias, and calibrated human oversight) are joined to a four-question procurement screen: what problem is being solved, whether governance capacity exists, whether the institution is being transparent, and whether the deployment creates value for students. The report's position is that states, accreditors and the federal Department of Education are not yet equipped to catch these risks, leaving the institution's own written policy as the operative protection, and it names the failure mode directly: a college marketing a faculty-led program while instruction or course design is outsourced to AI or third-party vendors is selling a different product under its own name.

Student experience at scale

Large-scale studies of authentic student AI use and GenAI availability and satisfaction document how students actually use AI — revealing gaps between institutional policy and everyday practice. Survey research captures how students navigate the AI landscape, and studies of study time, AI skills for graduates, and student perceptions of AI tools show that the student experience of AI is mixed — efficient but often shallower. Much of this university learning now happens online, where online teaching and learning shapes both AI's benefits (scalable personalization, always-on support) and its risks (academic integrity, cognitive offloading) for college students. An exploratory ML approach using SHAP analysis examined how students' perceptions and demographics relate to intended academic ChatGPT use, prioritizing interpretability (An Exploratory Machine Learning Approach to Understanding Determinants of Future ChatGPT Use in Higher Education). In art and design education, where generative AI challenges the value of human Creativity, a project-based learning model with digital storytelling at its core cultivated the emotional, cultural, and narrative capacities AI lacks — evaluated through a 15-week embedded case study with 426 Chinese undergraduates who translated local cultural heritage into Multimodal AI narratives (In the AI era: A project-based digital storytelling framework for art and design education). Assistive and inclusive uses of GenAI are also reshaping the student experience for disabled learners: Khlaif et al. (2026) — a qualitative case study of 21 visually impaired undergraduates across three Palestinian universities — found GenAI tailors pace, content, and delivery to individual profiles, simplifies complex texts, and converts content across modalities, giving learners a sense of autonomy and confidence in class participation while being viewed as complementing rather than replacing teachers.

A hierarchical regression on 303 undergraduates found perceived resources and teacher support explained 29% of AI-literacy variance, prior digital competence 3%, the psychological block 6% (total $R^2 = 0.39$); technology anxiety's association reversed to positive in the full model, only for critical evaluation and ethical competence (Chow et al. (2026)).

Beyond the classroom, AI reaches students through the institution itself — advising, outreach, referral, and the allocation of scarce support — which student support and success gathers as its own body of evidence. Its central caution about scale comes from a four-year randomized evaluation (N = 8,708) in which registration nudges moved a deadline by 34 percentage points while graduation, credits, and GPA did not move at all.

Graduate and professional education

The knowledge base is weighted heavily toward undergraduate study, and it houses graduate and professional preparation inside discipline-specific pages (medical and health-professions education, business education, teacher education) rather than in a separate graduate-education page. Two strands nonetheless bear specifically on master's, doctoral, and professional students: research training, and professional-degree programs.

Postgraduate *research* practice is the more distinctive of the two. Dai and Chan (2026) analyzed how 28 postgraduate research students across seven focus groups enacted AI Literacy in their GenAI-assisted research and found them to be calibrated users rather than passive adopters — matching tools to tasks by perceived stakes and disciplinary norms, retaining human oversight, and drawing their own boundaries between acceptable drafting help and substitution of their reasoning. Their central finding is a policy gap: institutional GenAI guidance addresses teaching, learning, and assessment but says almost nothing about the research process, so the authors propose researcher-oriented guidelines that scaffold each AI literacy dimension across the research workflow for researchers and their supervisors. Oh, Talton and Bui (2026) approach the same population from the institutional side: among 93 bioscience graduate students and postdoctoral trainees in a required research-ethics course, three simple pre-instruction behavioral signals informed lightweight intake profiling for adaptive AI Ethics instruction, while prior AI coursework predicted none of the five perception outcomes. AI is also reshaping the research team itself — analysis of 147,074 publications since 2020 associates AI-assisted writing with smaller, junior-leaner teams producing highly cited work, reversing the decades-long "Big Science" drift toward larger collaborations — and a single-investigator case study documents what sustained agentic support looks like inside one researcher's own workflow.

Professional-degree programs hold most of the graduate-level evidence, and it is organized by discipline. In health-professions education, a randomized controlled trial of 100 third-year medical students tested a multi-agent LLM system — simulated patient, Socratic tutor, turn-level evaluator — organized around explicit Scaffolding functions for clinical interview training, while the SCAN framework reframes trainee AI use as a problem of task distribution and real-time metacognitive classification rather than learner *misuse*. Master's-level preparation appears in Zhu et al. (2026), whose D–T–E model raised mathematics-education M.Ed. students' instructional-design competence (Cohen's $d = 0.62$) by having three LLMs act as "intelligent reviewers" in a design–feedback–reflection loop. How students conceptualize GenAI and their own professionalisation cuts across these programs, while workplace and continuing professional learning — adjacent to but distinct from graduate study — is treated under Adult Learners and Workplace Learning.

Faculty and teaching

Educational Development research examines how instructors adopt, resist, or adapt to AI. Teacher AI adoption studies identify confidence, support, and attitude as key predictors. AI-assisted discretionary feedback research explores whether AI increases instructor feedback quality and quantity, and ethics research weighs whether teachers should use AI for feedback at all. Staff-perspectives research and phenomenographic studies of teacher conceptions probe how educators understand their changing role. In large-class settings, AI can now shoulder a growing share of the feedback load: a semester-long field experiment in undergraduate macroeconomics tutorials (Geschwind et al., 2026) found that individual GPT-4

feedback sustained the highest participation across eight open-ended tasks and produced the largest content learning gains, positioning AI feedback as a scalable complement to lecturer feedback and a substitute for unreliable peer feedback. A complementary route for large undergrad STEM classes is a diagnostic teaching-assistant system: Arthur (Yin et al. 2026) uses a per-question ML backbone to give real-time, personalized feedback on Engineering Economics Calculated Formula Questions — a domain where handwritten solutions had previously blocked AI support — via a dialogue-based, question-bank web interface that balances feedback accuracy against collection efficiency. Farazouli et al. (2026) capture the *emotional* dimension of that change: 24 Swedish university teachers experienced GAI's emergence as alarming and overwhelming, reporting a "state of vulnerability" (low confidence, insecurity, fear of "not being ahead of students") and feeling "stuck" between utopian and dystopian discourses — while rethinking Assessment and re-evaluating their priorities toward critical thinking and ethical GAI use.

One hour of AI tutoring was statistically equivalent to live expert human tutoring on GRE learning gains across 2,469 sessions with 2,383 adults, and one model reached parity at 918× lower cost per percentage point (Northcutt et al. (2026)).

Assessment and integrity

Academic Integrity and AI assessment reform research grapple with how universities should redesign evaluation for an AI-capable student body. Detection-centered approaches are giving way to Authentic Assessment and process-based evaluation, including oral exams, assessment twins, and authentic assessment redesign. The shift reflects a deeper concern: how students and institutions define cheating with AI, and the quality of AI-generated assessment materials. Automation of grading itself is maturing for open-ended university work: Pecuchova, Benko & Drlik (2025) benchmarked eleven GenAI and sentence-embedding models on 1,885 responses to 24 software-engineering exam questions and found only GPTo1 reached almost-perfect agreement with two expert human graders (Fleiss' Kappa 0.82), with context-sensitive models outclassing reference-based ones — but its proprietary API costs led the authors to recommend hybrid human-in-the-loop deployment for resource-constrained institutions. At the professional-program level, Olvet et al. (2026) show that Large Language Models (LLMs) (GPT-4) scoring of pre-clerkship medical open-ended exam questions can reach substantial-to-almost-perfect agreement with faculty graders (weighted kappa up to 0.94) after iterative human rubric refinement, while the authors still recommend keeping humans in the loop to arbitrate residual discrepancies. Complementing this model-level evidence, Falahat, Das, Bhaumik & Thambi (2026) graded a 21-item university pharmacy exam with ChatGPT-5 and found near-perfect agreement with faculty on objective items (CCC 0.935–1.000) but unreliable agreement on short-answer and essay items, with rubric provision not consistently improving performance — reinforcing the case for hybrid, human-in-the-loop grading in university assessment.

A third route hardens the assignment itself: rendering prompts as perturbed images raised LLM assignment-completion failure from 7.4% to 55.6% and pushed Tesseract extraction error to 100.0%, reframing integrity as content design that complements detection rather than replacing it (Salaun et al., 2026).

Implications for higher-education instructors

- **Design assessment for an AI-capable student body.** Detection-centered integrity approaches are giving way to authentic and process-based evaluation (beyond detection, assessment reform) — redesign what you assess, not just how you police it.
- **Stop treating an in-room ban as assurance.** Smart glasses and AI-enabled hearing aids are dually transparent — no gaze drop or posture shift to detect — so an invigilated exam or oral can no longer purchase evidential confidence by physical separation (Corbin et al., 2026).
- **Redesign the "what should students still learn by hand?" question.** Just as in computing, decide which skills must be preserved (verification, judgment, process) and make those the assessed core, rather than assuming AI skills transfer automatically.
- **Treat faculty readiness as sociotechnical, not just technical.** EPIQ-AI frames readiness across epistemic, pedagogical, institutional, and quality domains — align your teaching practice with institutional governance, not just tool fluency.
- **Fund AI literacy, not just tool confidence, for faculty.** Liu et al. (2026) found that social and organizational support reached university faculty AI well-being only indirectly, through AI literacy ($\beta = 0.713$), so programs that build conceptual, ethical and pedagogical understanding do more for faculty than hands-on fluency alone.
- **Address the policy-vs-practice gap.** Large-scale studies (AI in the wild) show students use AI in ways institutional policy doesn't anticipate — align your expectations with real usage and teach AI Literacy explicitly.
- **Write method-specific guidance, not one campus-wide AI policy.** Interviewing 25 university language teachers, the study distilled 20 ethical tensions — four per online method — grouped into authenticity of learning (11), authority challenge (4) and collaborative dynamics (5), and argues that generic, method-agnostic policy cannot address the distinct pressures each online method places on integrity and collaboration (Baoyi & Khan (2026)).
- **Use AI to raise feedback quality and quantity.** AI-assisted feedback can increase the feedback instructors deliver; pair it with human judgment so it improves learning rather than merely automating.
- **Engage with grading and assessment innovation deliberately.** Mesny, Roberge-Maltais & Galy (2026) argue that Assessment and grading are among the most influential factors shaping learning in higher education, yet they remain under-researched in fields such as management education (only 58 articles over 20 years across four leading journals). Traditional, summative-heavy and norm-referenced approaches undermine deep learning, Well-Being, equity, and integrity in the generative AI era; the authors urge instructors to engage more actively and reciprocally with five innovative practices (authentic assessment, self- and peer-assessment, reassessment, standards-based grading, ungrading), noting implementation demands institutional and cultural support and incremental experimentation.
- **Treat research training and supervision as an AI-literacy site in its own right.** Postgraduate researchers enact AI Literacy as a situated practice rather than a static skill set, and institutional guidance largely stops at teaching and assessment. Guidance for thesis, dissertation, and publication work should scaffold verification, attribution, and disclosure concretely for each AI

literacy dimension — and simple pre-instruction signals can target that support in research-ethics courses — instead of issuing binary rules.

Common Misconceptions

- **“Institutional AI adoption has matured.”** The **symbolic layer is saturated while the structural layer is thin**: **100% have an AI task force and a master’s AI degree, but only 12% have executive AI leadership** and only 5% require a further institutional step. Announcements have outrun structures by an order of magnitude.
- **“Prestige predicts institutional AI maturity.”** Institutionalization proved **independent of prestige (rank correlation $r \approx 0.04$)**, with significant **regional variation (ANOVA $F = 5.86$, $p < .001$)**. Reputation is not a proxy for readiness, and geography predicts more than status.
- **“How AI distributes epistemic work is uniform across institutions.”** Sun, Dohn and Rehm (2026) classified **102 empirical higher-education studies** by how epistemic work was distributed, and the variation is the finding rather than a detail.

Connected Concepts

- Pedagogical Patterns — The level where most of the tested sequence evidence was generated
- Online Teaching and Learning — Online Teaching and Learning
- Generative AI — Generative AI technologies and models
- Large Language Models (LLMs) — Large language models
- Student Experience — Student experience with AI in higher ed
- Educational Development — Faculty development and AI readiness
- Academic Integrity — Academic integrity in an AI-capable student body
- AI Literacy — AI literacy for students and faculty
- Assessment Validity — Assessment validity in the age of GenAI
- Educational AI Policy — Educational policy on AI
- AI Regulation in Education — Regulation of AI in education
- Remote Proctoring — Remote proctoring and automated exam integrity
- Self-Directed Learning — Self-directed learning with AI
- Problem-Based Learning — Problem-based learning with AI
- Teaching — Evolving teacher role in AI classrooms
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Arts, Design and Media Education
- Student Support and Success — advising, outreach, referral, and support allocation — the institutional side of student success

Connected Articles

- How colleges and universities are adopting AI in higher education: a global comparative analysis — Chan (2026): AI Institutionalization Index across 100 top-ranked universities; discourse outruns structure, adoption independent of prestige
- Faculty Readiness for AI-Supported Teaching and Scalable Online Program Delivery in Higher Education: The EPIQ-AI Framework for Epistemic Integrity — EPIQ-AI Faculty Readiness Framework
- AI in the Wild: A Large Scale Analysis of Authentic Interactions of College Students with Generative AI — AI in the Wild: College Student AI Use
- A framework for institutional change in the age of AI — Institutional Change in the Age of AI
- Generative AI Availability, Grades, and Student Satisfaction at a Large University — GenAI Availability and Student Satisfaction
- ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform — AI Assessment Scale and Reform
- The University AI Didn’t Replace: Rethinking Universities in the AI Era — Rethinking Universities in the AI Era
- AI adoption among teachers: Insights on concerns, support, confidence, and attitudes — AI Adoption Among Teachers
- "AI should help them learn, not learn for them": University staff perspectives on the role of Generative AI in education — Staff perspectives on GenAI in higher education
- Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education — Organizational drivers of AI adoption in higher ed
- Is It Ethical for Teachers to Use AI for Student Feedback? — AI in student feedback: ethics
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond detection: redesigning authentic assessment in an AI-mediated world
- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison — GenAI experiences among UK higher-education students (survey)
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — Instructors vs. employers on AI skills for college graduates
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — 26.9% study-time decline among college students
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — UK higher-education AI policy
- Is using artificial intelligence tools for academic work cheating? Student perceptions, ethics, and the impact on academic performance and critical thinking — AI tools, academic work, and cheating
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams: a large-scale field study

- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant assessment
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins for strengthening assessment validity in the age of GenAI
- Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study — Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study
- Understanding what good education is: a phenomenographic investigation of university teachers' understandings of AI — phenomenographic study of university teachers' conceptions of AI
- AI for education: The digital transformation of a liberal arts institution – implementation at Lingnan University — Digital transformation of a liberal arts university toward a research-intensive model in the GenAI era (Qin 2026)
- Mapping artificial intelligence integration in higher education: A systematic review using the FACETS and SAMR frameworks — Systematic review mapping AI integration in higher ed via FACETS + SAMR frameworks (AlSheikh et al. 2026)
- Navigating uncertainty: university teachers' experiences and perceptions of generative artificial intelligence in teaching and learning — University teachers' experiences and perceptions of GAI: vulnerability, rethinking assessment, student learning at risk (Farazouli et al. 2026)
- GPT-4 feedback increases student activation and learning outcomes in higher education
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Shaping responsible GenAI use in research through AI literacy-oriented guidelines: Insights from postgraduate students — Postgraduate researchers' GenAI use in the research workflow and AI-literacy-oriented guidelines (Dai & Chan 2026)
- Engagement Intensity as a Learner-Modeling Signal for Adaptive AI Ethics Instruction — Engagement intensity as a learner-modeling signal for adaptive AI ethics instruction (Oh, Talton & Bui 2026)
- Smaller, Younger, and More Impactful: How AI-Assisted Writing Transforms Research Teams — AI-assisted writing shifts research teams toward smaller, junior-leaner, highly cited collaborations (Wang et al. 2026)
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- Literacy demands placed on students in student–GenAI entanglements in higher education — Assistant and Enabler forms dominate higher-education GenAI research; the marginal entanglement types stay rare for institutional rather than technical reasons (Sun, Dohn & Rehm 2026)
- Students at Stake: Risks of AI Deployment in Higher Education — Student-side map of AI deployment across admissions, financial aid, student services and education delivery, with a four-question procurement screen (Student Defense 2026)

- AIRRI: Towards a Human-Readable, Machine-Resistant Reading Interface — Perturbed-image assignments raised LLM completion failure from 7.4% to 55.6%: content design as an integrity route
- On AI glasses and wearable AI in assessment — AI glasses and hearing aids defeat an in-room exam ban: dual transparency with no gaze or posture cue
- Artificial Intelligence in Higher Education (2019–2026): A Systematic Review of Applications and an Evidence-Derived Multi-Axial Taxonomy — A functional-domain taxonomy of higher-education AI applications, 58.4% of which fall outside the 2019 categories
- AI and higher education: teachers' perceptions of students' ethical tensions in online pedagogical methods — Write method-specific guidance, not one campus-wide AI policy
- A Multidimensional Analysis of AI Literacy Determinants: External Resources, Digital Skills, and Psychological Profile Among University Students — Perceived resources and teacher support explained 29% of AI-literacy variance; demographics did not
- Exploring University Faculty's AI Well-Being: A Structural Equation Model of Social Supports, AI Literacy, and Technological Self-Efficacy — Fund AI literacy, not just tool confidence, for faculty

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?
- What Is the Evidence on AI Literacy Interventions in Higher Education?

Adult Learners

> **Adult learning** — the theory and practice of educating adults (andragogy), and how AI tools and technologies can be designed to support adult learners' autonomy, prior experience, and real-world relevance. Explored across 13 articles in this knowledge base.

Questions to Consider

- Adult learning theory assumes learners are self-directed, draw on life experience, and want real-world relevance. But if AI performs much of the cognitive work, does a learner completing a task without visible help actually prove they directed it? What would make you confident they did?
- Behavioral independence from a tool no longer guarantees the learner directed the learning. If you were designing AI for adult learners, what would you look for to confirm genuine self-direction rather than quiet delegation?
- Design guidelines for adult AI tools emphasize fitting into busy lives — mobile-friendly, offline-capable, connected to real problems. Which of these matter most for your own learning, and what does a tool that ignores them cost the learner?
- Adult learners often study at work or at home, so online delivery dominates — bringing flexibility but also risks of offloading and integrity questions. How does the convenience of AI assistance interact with the goal of durable learning for a busy adult?
- Research found no single adult-learning AI system satisfied all design guidelines — the full ecosystem was needed. What does that suggest about expecting one tool to meet every learner's needs?
- For marginalized and neurodivergent adult learners, equity may be less about tool access than about the educator's relational care. How does positioning the human as the locus of care change how you would design or adopt an AI tool?

Introduction

Rooted in Knowles's andragogical model, adult learning assumes learners are self-directed, draw on life experience, are motivated by immediate and practical goals, and benefit most when learning connects to their real-world roles. These assumptions matter for AI design because generative AI can now participate in almost every stage of learning — identifying needs, setting goals, interpreting information, producing outputs, and evaluating performance. When AI performs so much of the cognitive work, behavioral independence from the tool no longer guarantees that the learner actually directed the learning. Research in this knowledge base accordingly reframes self-direction as an active design goal rather than an assumed default, and evaluates adult-learning AI against criteria like goal ownership, delegation control, and cognitive recoverability.

Evidence from connected articles

- **Andragogy and GenAI cognitive delegation.** Hyoung (2026) revisits Knowles's six andragogical assumptions under AI-mediated cognitive delegation, arguing that completing a task without visible AI help does not prove meaningful self-direction. It derives five analytical dimensions — need and goal ownership, delegation control, epistemic calibration, cognitive recoverability and transfer, and motivational autonomy — bridging adult learning with Cognitive Offloading and Self-Regulated Learning to assess whether learners remain genuinely self-directed in the Generative AI era.
- **Design guidelines for AI adult-learning tools.** Drawing on longitudinal deployment data from the National AI Institute for Adult Learning and Online Education (AI-ALOE), the DIS 2026 paper synthesizes 19 empirically grounded design guidelines for AI-powered adult-learning technologies. Derived from ~1,600 stakeholder statements across seven deployed systems, the guidelines span cognitive, social, and teaching presence (a Community of Inquiry framing) and emphasize that tools should fit into busy adult lives (mobile-friendly, offline-capable), connect content to real-world problems, personalize meaningfully, provide substantive support and feedback, and be transparent about data. No single system satisfied all guidelines; the full AI-ALOE ecosystem was needed to cover them.
- **Adult, distance, and lifelong learning contexts.** Rienties et al. show how the Open University designed and evaluated an embedded AI assistant (AIDA) through six Design-Based Research studies; students using it spent twice as long on the course, though the study warns that technical capability must be matched by AI Governance and organizational readiness. Theodora and Tselios frame AI's dual role in adult and Lifelong Learning as both an enabler of personalized, scalable education and a source of equity and governance risk, calling for inclusive, human-centered policy. A Midwestern case study co-designed an AI-literacy program for 54 adults in an underserved community, finding that equity-oriented adult AI education must meet learners where they are on basic digital literacy skills, build Trust around data privacy, and connect to lived experience. Herron's "Sovereign Hive" / Tutor-in-the-Loop framework treats GenAI equity in Further Education as atmospheric regulation rather than mere provision of tools, placing the educator at the center of the relational and cognitive support marginalized and neurodivergent adults need.

Connections to related concepts

Adult learning sits at the intersection of several closely linked concepts in this knowledge base. Higher Education supplies the institutional context in which much adult and distance learning occurs, while Workplace Learning covers its workforce and Lifelong Learning its continuous-education dimension. Vocational education and training is the neighbour that names an occupation rather than a learner: adult learning describes what learners bring to any context — self-direction, prior experience, immediate practical goals. VET names initial, practice-proximal preparation for a named trade or technical role, judged by demonstrated competence with equipment and framed by qualification frameworks rather than by andragogical dispositions. Online teaching and learning is the dominant delivery medium for adult learners — who often study at work or at home — so its affordances (24/7 access, asynchronous support) and risks

(integrity, offloading) are central to adult-learning design. Self-Regulated Learning and Learner Agency name the learner capacities that AI must protect rather than erode, and Cognitive Offloading captures the mechanism by which AI can either support or undermine them. Inclusive Learning and Equity frame the equity obligations of adult AI tools, Human-in-the-Loop names the design pattern that keeps humans accountable, and Scaffolding describes the graduated support such tools should provide.

Implications for adult-education instructors and designers

- **Design AI as a scaffold for self-direction, not a substitute.** Behavioral independence from the tool doesn't prove the learner directed the learning — protect goal ownership, delegation control, and cognitive recoverability (andragogy + cognitive delegation).
- **Fit into busy adult lives.** Make tools asynchronous, mobile, and offline-capable, and connect content to real-world problems (AI-ALOE guidelines).
- **Design for a range of engagement, not assumed depth.** Working adults triage limited cognitive resources across jobs, families and coursework, so a six-semester framework made Socratic AI dialogue more rewarding than the fast route rather than mandatory Packard et al. (2026).
- **Keep a human in the loop.** Position the educator as the locus of relational and cognitive care, especially for marginalized and neurodivergent adult learners (Tutor-in-the-Loop).
- **Address foundational digital literacy and data trust.** Build AI Literacy and Trust around data privacy before expecting adoption (community AI education).
- **Ground AI in learning science and andragogy, and prefer deep personalization.** Apply andragogical theory and connect content to real-world problems; favor deep personalization (task sequencing, difficulty calibration) over surface-level adaptation.
- **Make transparency and community features first-class.** Data-practice transparency and social/community features are among the most neglected yet most valued dimensions of adult AI tools.
- **Treat technical and structural reliability as a precondition.** Engagement depends as much on stable, inclusive infrastructure as on pedagogical quality — unstable or exclusionary platforms undermine otherwise sound design.
- **AI design principles for andragogy.** Kim et al. (2026) find adult learners value AI as a collaborative learning agent and derive three AI design principles for andragogy: human-in-the-loop (shared mental models, human-AI co-creation), emotional design (calibrating AI reliance, empathetic communication), and adaptability (continuous adaptation, interoperability). Their eleven scenario prototypes also map each andragogical principle onto a concrete AI affordance: AI tutors and teachable agents for involvement, monitoring and analytics tools for autonomy and Self-Assessment, empathetic chatbots and simulations for experience, case libraries and higher-order question generators for problem-centered work, and AI planners and career coaches for relevance.
- **Preserve productive struggle.** The same group's Productive Failure study maps AI support onto the two PF phases and concludes the design must not resolve the struggle: conversational agents

act as non-directive thinking partners during generation and exploration, then support comparison, reorganization and transfer during consolidation (Kim et al. (2026)).

Common Misconceptions

- **“One good tool serves adult learners.”** Research found **no single adult-learning AI system satisfied all design guidelines** — the full ecosystem was needed. Adults arrive with obligations, intermittent schedules and heterogeneous goals, so a single product cannot cover the design space.
- **“Digital literacy can be assumed at the adult level.”** A Midwestern case study co-designed an AI-literacy program for **54 adults in an underserved community** and found that equity-oriented adult AI education **must address foundational digital literacy and data trust** first. Age is not a proxy for digital fluency.
- **“Adoption is a motivation problem.”** Building AI Literacy and Trust around data privacy has to precede expecting adoption. Willingness follows from confidence about what happens to one’s data, not from enthusiasm about the technology.

Connected Concepts

- Self-Directed Learning
- Online Teaching and Learning — Online Teaching and Learning
- Higher Education
- Workplace Learning
- Vocational Education and Training
- Lifelong Learning
- Inclusive Learning
- Learner Agency
- Self-Regulated Learning
- Generative AI
- Human-in-the-Loop
- Cognitive Offloading
- Scaffolding
- Trust
- AI Literacy
- Equity
- Neurodiversity
- AI Governance
- Formative Assessment
- RCT
- Active Learning
- AIEd in the Disciplines

Connected Articles

- Guidelines for Designing AI Technologies to Support Adult Learning — Guidelines for Designing AI Technologies to Support Adult Learning
- What remains self-directed? Revisiting andragogy through cognitive delegation in generative AI-mediated adult learning — What Remains Self-Directed? Revisiting Andragogy Through Cognitive Delegation in Generative AI-Mediated Adult Learning
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy — Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy
- Atmospheric regulation in the age of generative AI: The sovereign hive and the tutor-in-the-loop (TITL) framework for equity in further education — The Sovereign Hive and the Tutor-in-the-Loop (TITL) Framework for Equity in Further Education
- Co-Designing Community-Centered AI Education for Adults: A Midwestern Case Study — Co-Designing Community-Centered AI Education for Adults: A Midwestern Case Study
- New systems of learning for distance learning institutions? A six-study review of implementing AIDA — New Systems of Learning for Distance Learning Institutions? A Six-Study Review of Implementing AIDA
- Policy Fragmentation or Institutional Alignment? Institutional Governance of AI in Universities and Business Schools — Policy Fragmentation or Institutional Alignment? Institutional Governance of AI in Universities and Business Schools
- Generative AI-enhanced learning experiences for computational thinking: A systematic scoping review and design guidelines — Generative AI-enhanced learning experiences for computational thinking: A systematic scoping review and design guidelines
- Mapping the Emerging Curriculum for AI-Assisted Software Engineering via Syllabus Analysis — Mapping the Emerging Curriculum for AI-Assisted Software Engineering via Syllabus Analysis
- Patterns of Learner-AI Interaction and Academic Performance in an Object-Oriented Programming Course — Patterns of Learner-AI Interaction and Academic Performance in an Object-Oriented Programming Course
- Practitioner beliefs and behaviors in AI-enhanced education: DOT framework survey evidence
- Designing AI systems to support a productive-failure-based learning: insights from adult learners on AI applications and AI system design principles — Designing AI Systems to Support Productive-Failure-Based Learning
- Adult learners' perspectives of AI applications in supporting andragogy — AI Applications in Supporting Andragogy (Kim et al. 2026)
- Teaching with AI, Not Against It: A Thinking Partner Framework for Working Adult Learners in Compressed Online Formats — Design for a range of engagement: make deep Socratic dialogue the more rewarding path

Vocational Education and Training

> **Vocational education and training** — the segment of education that prepares people for named occupations, trades and technical roles, organized around practice-proximal competence rather than disciplinary knowledge. Where workplace learning describes upskilling for the already employed, VET includes initial preparation for a trade; where higher education names degree study, VET is often non-degree and framed by national qualification frameworks. Its defining features are that learners are assessed on what they can do with equipment, that instruction happens near the workshop, simulator or worksite, and that the human trainers who carry practical instruction are frequently the binding constraint. In AI research VET appears both as a distinct learner population — one whose academic confidence is tied to demonstrated skill and occupational identity — and as a distinct evidence base, thinner and more fragmented than the school or university literature.

Questions to Consider

- If a qualification certifies what a learner can do, how much AI-assisted learning counts as authentic practice and how much substitutes for the repetition that builds competence?
- What is lost when an AI agent role-plays the counterpart — patient, pilot, client — that a human trainer used to play? Which judgments can a synthetic counterpart not model?
- Oral assessment scales poorly with class size. If AI surfaces evidence but does not judge, which parts of assessment capacity are relieved and which are merely displaced to the teacher?
- No study in the AI-in-VET evidence base is set in a workplace, yet VET is defined by work-based learning. What would credible research where the learning happens require?
- The EU AI Act treats AI evaluating learning outcomes in vocational training as high risk, while some jurisdictions have none. Should procurement follow the strictest standard available?

Introduction

Vocational education and training prepares people for specific occupations — automotive technicians, air traffic controllers, interior designers, care workers — and its currency is demonstrated competence rather than accumulated credit. Assessment tends to be performance-based, instruction is tied to equipment, and the skilled trainers who supervise practice are scarce.

Its neighbours in this knowledge base differ chiefly in scope. Workplace Learning covers workplace and corporate upskilling, mostly for people already employed; VET covers initial occupational preparation as well. Adult Learners names learner characteristics rather than occupational specificity. Higher Education names degree-granting study, whereas much VET is organized by qualification frameworks such as NZQA unit standards or the EQF. STEM Education and VET overlap in technical domains, but STEM education aims at conceptual understanding while VET aims at usable procedure. Career Development and Readiness names the employability dispositions VET programs are judged by; VET names the instructional system held accountable for producing them.

What is distinctive about AI in VET is a gap between what the sector says it wants and what it builds: constructivist theory is widely espoused while behaviorist drill-and-practice systems dominate and learner-agency designs remain rare. The recurring design question is not whether AI can deliver instruction, but whether it can absorb the parts of vocational learning that are expensive to staff — realistic scenarios, timely feedback, role-played counterparts, oral evidence — without displacing the practice that produces competence.

How AI appears in vocational education and training

- **A young, fragmented and geographically concentrated evidence base.** The first systematic review of AI in VET (Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness) identified 26 empirical studies published 2015–2026 through ERIC, Web of Science and Elicit under PRISMA guidelines: nine technical-domain, nine domain-general, five in business administration and three in health. Settings were six classroom, eight online, four blended and eight simulation-based — and none in a workplace, despite VET's work-based character. Seventeen of the 26 originated in Asia; only nine studies shared at least one reference and none cited each other. Five were randomized experiments and 21 used pre-experimental or quasi-experimental designs, mostly measuring outcomes immediately after intervention, and only three gave learners an active role in an AI-empowered design. The authors warn of an educational "Turing Trap" — using AI to replicate human instruction rather than augment human judgment — and call for failure cases and boundary conditions in place of the prevailing success narrative.
- **Simulation absorbs the scarce role-player.** ASTRA: A Scalable Next-Generation ATCO Training Simulator with Autonomous Simpilots targets a capacity constraint in air traffic control training: *simpilots*, specialized human trainers who role-play both pilots and controllers in a simulated airspace. ASTRA substitutes autonomous Large Language Models (LLMs)-driven sim-pilots, keeping scenario complexity while removing the staffing bottleneck and enabling adaptive practice at scale. It is a system description rather than an efficacy trial, but it names a mechanism that recurs across AI in VET: where the scarce input is a skilled human playing a counterpart, an agent can hold the role and let practice expand.
- **Immersive, agent-supported project work can raise design ability — selectively.** Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments specifies AI-IVE-PBL, a four-dimension, five-phase model (discovery, envisioning, modeling, communication, refinement) run in VR with an LLM-backed digital-human assistant in a first-year interior design course at a Chinese vocational college. In a 12-week two-group quasi-experiment (63 valid responses; 31 vs 32), the immersive-agent condition scored higher on design ability ($\eta^2p = .138$) and creative ability ($\eta^2p = .111$) under ANCOVA. Cognitive engagement was $d = 0.90$, behavioral engagement $d = 0.75$, motivation $d = 0.74$, satisfaction $d = 0.69$, and cognitive load lower ($d = -0.52$). Innovative thinking and affective engagement did not reach significance, attributed by the authors to short-term ceilings on entrenched cognitive patterns. Every outcome is self-report, with no design artifacts or expert ratings. Read against Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study, where a GenAI-plus-XR pipeline produced declining

design Self-Efficacy and no blinded-panel advantage, the difference looks less like hardware than like who holds the phase structure and the rubric.

- **Assessment is where the authenticity problem is sharpest.** Designing AI-Supported Oral Assessment in TVET documents AkoVoice, trialled in four Level 3 Automotive and one Level 3 Engineering class, designed so AI surfaces rubric evidence while the human assessor judges. Of 33 surveyed learners, 21 (64%) agreed the voice task was realistic and the same proportion said it gave a clear way to communicate what they knew; none disagreed that speaking in real time suited this authentic assessment better than a written portfolio. Word counts for identical questions varied five- to eight-fold between learners without improving accuracy on fact-based questions, and nine learners answering in 2 to 13 words were all marked correctly, the shortest being two words, “3500 kgs”, matched on value. A full cycle of capture, storage, AI judgment drafting and teacher reporting ran offline on one Windows laptop with 8 GB of graphics memory (Mistral 7B via Ollama, faster-whisper, Chatterbox), assessing up to 12 learners at once in a workshop where steel framing defeats wifi, with recordings encrypted and deleted after 90 days. The paper notes the EU AI Act treats AI evaluating learning outcomes in vocational training as high risk, while New Zealand has no sector-specific TVET framework.
- **Bounded accompaniment rather than substitution.** Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China argues that the value of AI in technical and vocational settings depends on accountable pedagogical mediation rather than human-likeness. Its Amico prototype pairs AmicoMio, oriented to technical clarity and step-by-step task guidance, with AmicoTuo, oriented to reflective dialogue and maieutic questioning. The design principle is a *relational bridge*: interaction deliberately temporary, directional toward human contact, and bounded by safeguards, with adults retaining human-in-command responsibility. Exploratory pilots (N = 30, Italy and China, 20 bounded sessions) found participants treated the system as a bounded support tool, with no reported expectation of substitution or dependency.
- **AI-assisted learning carries a psychological cost when it replaces effort.** AI-assisted autonomous learning and reduced academic accomplishment in vocational higher education: The mediating role of hardiness surveyed 1,264 vocational college students in China using structural equation modeling and found AI-assisted autonomous learning negatively associated with hardiness (commitment, control, challenge) and positively associated with reduced academic accomplishment, a burnout dimension of negative self-evaluation. Hardiness partially mediated the relationship. The design is cross-sectional, self-report and single-institution, so causality is not established, but the framing matters for VET: where confidence is built through repeated practice, AI as a substitute may reduce both the disposition to persist and the felt experience of mastery.
- **Accelerating curriculum production without surrendering verification.** AI-accelerated End-to-End Framework for Rapid Professional Upskilling applies AI across all five stages of professional upskilling — knowledge acquisition, content development, review and verification, tutor coaching and assessment development — while keeping blueprint design, subject-matter review and misconception authoring with humans. Its external validation includes NASBA CPE accreditation, three of three learners passing an NVIDIA certification exam using only the framework’s knowledge base, and a 530-question bank tagged to a 53-skill blueprint. It belongs

here because it treats verification as a first-class stage: hallucination detection is largely absent from education pipelines, and the paper reports default LLM tutoring reaching only 52–70% correct pedagogical actions.

- **Perceived support is an institutional lever, not a student deficit.** Among 784 students at six Chinese higher vocational colleges, Huang et al. (2026) found AI literacy's link to self-reported complex problem solving (total 0.480) strengthened with perceived school ICT support: conditional indirect effects rose from 0.117 to 0.176 and 0.038 to 0.127.
- **Curriculum renewal as a continuing obligation, not a periodic review.** Wang (2026) identifies five interacting renewal dimensions, occupational transformation, curriculum currency, faculty capability alignment, program architecture and external alignment, and six leadership tests for deciding whether a course should be retained, revised, integrated, replaced or retired.

Common Misconceptions

"The AI-in-VET evidence base tells us about vocational education." It tells us about classroom proxies for it, which is a serious gap rather than a detail: **no study in the AI-in-VET evidence base is set in a workplace**, yet VET is *defined* by work-based learning. A finding about an AI tool in a simulated trade task has not yet encountered the conditions that make the sector distinctive — real clients, real safety consequences, real variation in workplace equipment.

"A significant effect on design or creative ability transfers to occupational competence." The strongest quantitative result here comes from a **12-week two-group quasi-experiment with 63 valid responses (31 vs 32)**. There the immersive-agent condition scored higher on design ability ($\eta^2p = .138$) and creative ability ($\eta^2p = .111$) under ANCOVA, with cognitive engagement d = 0.90. Thirty-one students per arm in a classroom task is evidence about that task, and occupational competence is not one of the measured outcomes.

"Learners will over-rely on AI in practical training." The pilot evidence points the other way. Exploratory pilots (**N = 30**, Italy and China, **20 bounded sessions**) found participants treating the system as a bounded support tool, with **no reported expectation of substitution or dependency**. That is exploratory and small, and it does suggest that vocational learners' framing of a tool as equipment rather than as an authority is a resource worth designing around.

"Learner approval of a simulated task means it assessed the right thing." Of **33 surveyed learners, 21 (64%)** agreed the voice task was realistic and the same proportion said it gave a clear way to communicate what they knew — and none disagreed that speaking in real time suited this authentic assessment. Realism and communication clarity are worth knowing and are not validity: a task can feel authentic and still fail to sample the occupational performance it stands in for.

Implications for Practice

For instructors

- Treat workplace-based studies as the missing evidence and design your pilots to include them; classroom gains are necessary and not sufficient for a trade qualification.

- Frame AI tools as bounded equipment rather than as an authority. The pilot evidence suggests learners already approach them this way, and that framing is worth making explicit.
- Keep authenticity checks separate from validity checks: ask what occupational performance the task samples, not only whether students found it realistic.

For developers

- Build for bounded, task-scoped assistance with a clear end, which matches how vocational learners actually used the systems in these pilots.
- Design against workplace variation — equipment, safety rules, client interaction — rather than against a lab configuration, since that is where deployment will happen.

For researchers

- Field at least some studies in workplaces. A sector defined by work-based learning whose evidence base contains no workplace studies has not yet tested its central claim.

Connected Concepts

- Workplace Learning
- Adult Learners
- Higher Education
- Career Development and Readiness
- Simulation
- Authentic Assessment
- Intelligent Tutoring
- Human-in-the-Loop
- Cognitive Offloading
- Self-Efficacy

Connected Articles

- When Legacy Curriculum Meets Artificial Intelligence: A Theoretical Framework for Institutional Renewal in Career and Technical Education — Adaptive CTE curriculum renewal, five dimensions and six leadership tests
- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — First systematic review of AI in VET: purposes, theory and empirical effectiveness
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — AI-IVE-PBL: immersive project-based learning and design creativity
- Designing AI-Supported Oral Assessment in TVET — AkoVoice: offline AI-supported oral assessment in TVET

- Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China — Amico dual-mode prototype: design principles and observable indicators
- AI-assisted autonomous learning and reduced academic accomplishment in vocational higher education: The mediating role of hardiness — AI-assisted autonomous learning and reduced accomplishment, mediated by hardiness
- ASTRA: A Scalable Next-Generation ATCO Training Simulator with Autonomous Simpilots — Autonomous sim-pilots for scalable ATCO training
- AI-accelerated End-to-End Framework for Rapid Professional Upskilling — AI-accelerated end-to-end framework for rapid professional upskilling
- Generative AI and Extended Reality in Collaborative Architectural Design Education: An Exploratory Studio Study — Counter-case: GenAI plus multi-user XR with declining design self-efficacy
- AI literacy and vocational students' complex problem-solving skills: a moderated mediation model of systematic thinking, cognitive load, and perceived school ICT support — Perceived ICT support as an institutional lever in vocational colleges

Special Education

> **Special Education** — the design and delivery of instruction for learners with disabilities, spanning cognitive, physical, sensory, and neurodevelopmental differences. AI in education research in this knowledge base explores how AI tools can support diverse learner needs through personalization, adaptive scaffolding, and accessible interfaces — while also examining the risks of AI systems that overlook or marginalize disabled learners.

> ⚠️ **Special Education is primarily a K-12 term.** It is rooted in the U.S. Individuals with Disabilities Education Act (IDEA) and the entitlement-based system of Individualized Education Programs (IEPs) that governs special-education services in primary and secondary schooling. In higher education — and increasingly in K-12 as well — the more common framing is **Universal Design for Learning** (a proactive design framework that benefits all learners) alongside Accessibility and Assistive Technology rather than "special education." A K-12 special-education article and a college UDL piece are about overlapping but distinct contexts; the knowledge base keeps both because the research literature spans both. When a source concerns higher education and disabled learners, it is usually better linked to Universal Design for Learning, Accessibility, or Inclusive Learning than to special-education.

Questions to Consider

- The page emphasizes that 'special education' is primarily a K-12, entitlement-based term rooted in IDEA and IEPs, while higher education more often speaks of Universal Design for Learning and accessibility. Why do you think these contexts differ, and what does that difference reveal?
- AI's promise of personalization seems tailor-made for learners with diverse needs. But if a system can adapt to 'individual cognitive profiles,' what could go wrong when the model of a disability is too coarse or absent altogether?
- The research includes AI tools designed for specific disability profiles (e.g., dyslexic or Deaf and Hard of Hearing learners). What risks do you see in designing for narrow profiles versus designing universally for all learners from the start?
- How might AI systems that are built for the 'average' learner end up overlooking or marginalizing disabled learners, even unintentionally — and whose responsibility is it to prevent that?
- What would it mean for an AI tool to genuinely include, rather than merely accommodate, a learner with a disability — and how would you recognize the difference in practice?

Introduction

Special education is a domain where AI's capacity for personalization and adaptation offers particular promise. Unlike one-size-fits-all instruction, AI tutors can theoretically adapt to individual cognitive profiles,

communication needs, and learning paces. The articles in this knowledge base span AI for specific disability profiles, neurodivergent learner experiences, and critical perspectives on AI and disability.

Disability-specific AI tutoring tailors AI to particular learner needs. **Special-R1** extends reinforcement learning to model cognitive and communicative diversity across five disability profiles, using persona-aware prompts and thinking rewards to shape tutor responses for each learner. **DysLexLens** analyzed how dyslexic learners experience AI tools, revealing both the value of AI for literacy support and persistent accessibility barriers. **Chen et al.** designed an Large Language Models (LLMs)-powered question-generation system for Deaf and Hard of Hearing learners, introducing Visual and Emotion question strategies and iteratively refining questions with the target community to overcome the mismatch between text-based AI prompts and sign-based first languages. **Designing for What Cannot Be Seen: Supporting Embodied String Learning for Musicians with Blindness and Low-Vision** developed non-visual learning strategies with blind and low-vision musicians, centering disability-led embodied design. These connect to Inclusive Learning and Neurodiversity.

Neurodivergent learner experiences center autistic and ADHD students. **Zastudil et al.** found neurodivergent computing students need structured assignments, small consistent teams, and explicit role definitions — design requirements that Collaborative Learning tools must address. **Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education** demonstrated that AI-segmented videos eliminated the ADHD performance gap. Both connect to Learning Design and Universal Design for Learning.

Critical perspectives examine how AI can marginalize disabled learners. **Tali-Otmani** argues that AI systems actively marginalize disability-centered knowledge due to Western-centric training data — connecting to Equity concerns about epistemic justice.

AI for dyslexia across detection, support, and personalized learning. A 2026 interdisciplinary systematic review (Dabaghi, D'Urso & Sciarrone, PRISMA-guided, 2018–2024, n=72) maps how AI supports students with dyslexia in education, finding AI used for detection, assistive support, and personalized learning — but with these strands evolving in parallel rather than in integration, driven more by technological opportunity than by consolidated educational theory. ML-based help-education tools fall into five areas (specific applications, engagement, personalization, recommendation, generic support) yet emphasize technical performance and classification accuracy while overlooking ecological validity and practical classroom deployment. Detection research (EEG, eye-tracking, ML models) prioritizes early intervention and shows diagnostic promise, but often requires specialized equipment and controlled environments, limiting scalability and accessibility in typical school settings. Open challenges include limited experimental validation, scalability, Ethics/privacy concerns with sensitive student data, limited teacher support and training, and language/cultural barriers (most research targets English-speaking populations).

Cognitive offloading for students with learning disabilities (SWLDs). Seung & Basham (2026), a conceptual review in a *Learning Disability Quarterly* special series on AI for students with LD, reframe GenAI use for SWLDs through the Cognitive Offloading lens. They argue that GenAI can be a **compensatory aid or a shortcut** depending on how offloading decisions interact with SWLDs' cognitive and motivational profiles (executive-function and working-memory challenges, heightened cognitive load, effort-avoidant performance goals, lower academic self-efficacy, and inflated expectations toward GenAI) and with instructional design. For reading and writing, GenAI can scaffold access (text leveling,

summarizing, Multimodal AI outputs, planning, drafting, revision feedback) while preserving higher-order engagement — but excessive offloading risks bypassing the comprehension, planning, and monitoring processes that are already fragile for these learners, fostering "metacognitive laziness" and compounding literacy difficulties across domains. The paper positions **instructional Guardrails** as the key moderating factor and recommends teaching strategic offloading, building AI Literacy to calibrate tool trust, sequencing mastery experiences to build Self-Efficacy, and aligning tasks and assessment with IEP goals that prioritize skill development over substitution. This extends the knowledge base's special-education coverage to the equity dimension of offloading: the same tool that lowers barriers to access can, if unguarded, substitute for the practice SWLDs need most. **AI-generated intervention content needs pre-generation controls, not only review.** Enkhjargal et al. (2026) found practitioners rated the co-designed Social Story tool highly usable (SUS 86.8) yet called its images generically Western and its behavior tracker mismatched to goal-linked clinical judgment — constraints they would have set before generation.

Kudláčková (2026) starts from the materials rather than from conversation: a vision-language model reads photographs of Shoebox Tasks — designed so the goal is visible in the objects — and turns them into a plan a Nao humanoid executes or demonstrates, reporting plan accuracy across six tasks and no learner data. - **Challenging behavior is where tutor benchmarks stop.** Of 923 case-grounded dialogues drawn from special-education and educational-psychology literature, the best of 11 models satisfied a documented intervention in 55.8% of open-ended cases and 43.3% of long-term plans (Park et al. (2026)).

Implications for special-education instructors

- **Co-design AI with the target learners and community.** Question generation for Deaf/Hard-of-Hearing learners shows the value of iteratively refining AI with the community to bridge the gap between text-based prompts and sign-based first languages — involve learners and their communities in design rather than assuming AI fits them.
- **Match AI to specific disability profiles, not generic accessibility.** Special-R1 models cognitive and communicative diversity across disability profiles; DysLexLens documents both the literacy value and the persistent accessibility barriers dyslexic learners face — choose tools aligned to each learner's profile and be alert to unmet barriers.
- **Structure collaboration for neurodivergent learners.** Neurodivergent computing students need structured assignments, small consistent teams, and explicit roles — apply these design requirements to any AI-mediated collaborative activity.
- **Use AI to close (not widen) performance gaps.** AI-segmented videos eliminated the ADHD performance gap — deploy adaptive AI where evidence shows it equalizes outcomes, not where it merely automates.
- **Center disability-led embodied design.** Blind/low-vision musicians research shows non-visual, disability-led strategies outperform default visual interfaces — build and adapt AI with disabled learners' expertise.
- **Guard against epistemic marginalization.** Critical perspectives warn that Western-centric training data can marginalize disability-centered knowledge — audit AI content and tools for epistemic justice alongside Equity.

Common Misconceptions

- **“Usability ratings validate an assistive tool.”** Practitioners gave a Social Story tool they had co-designed a usability pass (SUS 86.8) while faulting its stock Western imagery and a behavior tracker that missed goal-linked clinical judgment. High usability coexisted with substantive failures, so a SUS score is not an endorsement of fit.
- **“Generic benchmarks tell you how a tutor handles special-education cases.”** Of **923 case-grounded dialogues** drawn from special-education and educational-psychology literature, **the best of 11 models** satisfied a documented criterion — and **that is the edge of what a tutor benchmark covers**. Standard evaluations do not reach the cases practitioners most need help with.
- **“Neurodivergent learners need accommodations, not design requirements.”** Zastudil et al. found neurodivergent computing students need **structured assignments, small consistent teams and explicit role definitions** — general design requirements that benefit everyone, not individual adjustments granted after diagnosis.

Connected Concepts

- Differential Effects Across Learner Groups
- Inclusive Learning
- Equity
- Neurodiversity
- Universal Design for Learning
- Learning Design
- Student Experience
- AI Literacy
- K-12
- Higher Education
- CS Education
- Generative AI
- AIEd in the Disciplines

Connected Articles

- TutorCaseBench: A Case-Grounded Benchmark for Evaluating LLM Tutors in Supporting Students with Challenging Behaviors — TutorCaseBench: evaluating LLM tutors on students with challenging behaviors (Park et al. 2026)
- Cognitive Offloading in the Age of Generative AI: What Does It Mean for Students With Learning Disabilities? — GenAI cognitive offloading for students with learning disabilities
- Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training

- DysLexLens: A Low-Resource LLM Framework for Analysing Dyslexic Learners Insights from Online Forums
- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM-powered question generation for Deaf and Hard of Hearing learners
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning
- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability
- Designing for What Cannot Be Seen: Supporting Embodied String Learning for Musicians with Blindness and Low-Vision
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education
- AI-Assisted Social Story Intervention for Special Education: The Design of AdaptED Stories — AI-Assisted Social Story Intervention for Special Education: The Design of AdaptED Stories
- Visual Task Modeling and Automated Planning for Humanoid Robots in Education of Individuals with Autism Spectrum Disorder — A vision-language model plans Shoebox Tasks for a Nao robot (Kudláčková 2026)

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Teacher Education

> **Professional development** — the preparation and ongoing professional development of teachers, spanning pre-service teacher training (initial certification programs) and in-service professional development. In AI-in-education research, teacher education has become a central concern because teachers' AI literacy, technological-pedagogical knowledge, ethical fluency, and readiness to integrate AI into instruction determine whether AI adoption in classrooms succeeds. This concept organizes the knowledge base's substantial coverage of how AI reshapes the preparation, knowledge, beliefs, and practice of both prospective and practicing teachers.

Questions to Consider

- Teacher education here spans pre-service training (future teachers in certification programs) and in-service professional development (practicing teachers). Which of the two do you think faces the bigger challenge preparing for AI classrooms, and why?
- The page suggests teacher education must prepare teachers not just to use AI tools but to understand, evaluate, and ethically integrate them — a shift that 'redefines what it means to be a teacher.' How do you think that redefinition should change what a credentialing program teaches?
- Frameworks like AI-TPACK extend the classic TPACK model by adding an AI and ethics dimension. What do you think an 'AI dimension' of technological-pedagogical-content knowledge should actually contain beyond how to operate a chatbot?
- A scoping review of 55 studies cited on the page finds AI enhances pre-service teachers' instructional design, reflection, and critical thinking. But if AI can do some of this for them, when does its use in teacher training build skill versus substitute for the very judgment they'll need?
- If you were redesigning a teacher-education program for the AI era, what would you require every future teacher to experience — and what would you deliberately keep them from outsourcing to AI?

Introduction

Teacher education sits at the intersection of several knowledge base strands: it is a discipline/domain (like Medical and Health Professions Education and Humanities and Social Science Education), but it also draws on the general concepts of Teaching, Technological Pedagogical Content Knowledge (TPACK), Teacher AI Competency, and AI Literacy. In the AI era, teacher education must prepare teachers not only to use AI tools but to understand, evaluate, and ethically integrate them — a shift that redefines what it means to be a teacher. The learning sciences supply the knowledge this formation has to carry: where that field studies how people learn and how learning environments should be designed, teacher education is the professional formation in which such evidence has to land as a teacher's own capacity to design, teach and assess.

Cross-level evidence sharpens the design priority: a multilevel study of 46 teachers and 2,832 secondary students found that pedagogical AI knowledge (TPAIK) — not technical AI knowledge — drove students' perceptions of AI for social good and their intention to learn AI. Teacher education should therefore

foreground *how to teach with and about AI* over tool proficiency, consistent with the "pedagogy first, technology second" guideline.

A heutagogical strand runs alongside this design priority: Hochberg & Waitzman (2026) followed 93 Israeli teachers through an eight-week AI professional-development program and proposed a dual-layer relationship in which teachers' own reflective AI Regulation in Education and critical AI literacy mediate the Learner Agency- and capability-oriented designs they create for Learners.

Pre-service teacher education

Pre-service (initial) teacher education prepares future teachers during their certification programs. AI research in this strand includes:

- **AI-TPACK and intelligent-TPACK readiness.** Instruments and frameworks measure and build pre-service teachers' readiness to integrate AI, extending the Technological Pedagogical Content Knowledge (TPACK) framework with an AI/ethics dimension.(Conceptualizing pre-service teachers' readiness for AI integration into teaching practices: An intelligent-TPACK approach) (Assessing AI-TPACK readiness in mathematics teacher education: The role of self-efficacy and teaching beliefs)
- **Acceptance profiles, and an ease-of-use/intention paradox.** Chen et al. (2026) profiled 128 pre-service teachers into four ChatGPT-acceptance groups: Resistant Skeptics (14.06%) reported high perceived ease of use but very low behavioral intention, so operational skills training alone does not convert them.
- **Local context as a design input.** Swiss student teachers rated social-utility and intrinsic motives higher than their Chinese peers, who reported greater digital teaching competence and AI enthusiasm (Martínez-Moreno et al. (2026)). Preparation should key its entry point to each setting's motivational profile.
- **Applications and benefits.** A scoping review of 55 studies shows AI enhances pre-service teachers' instructional design, subject instruction, practical teaching skills, evaluation, reflective practice, critical thinking, technology integration, and pedagogical innovation.(Harnessing artificial intelligence for preservice teachers' development: A scoping review of applications, benefits, and challenges)
- **Unscaffolded genAI access scored below no genAI.** In an 11-week quasi-experiment with 52 pre-service teachers, the unscaffolded genAI class produced lower rubric-rated lesson plans than the no-genAI class (adjusted 86.54 vs 81.87, $F = 8.348$, $p = 0.006$, $\eta^2 = 0.146$), with no group difference in Self-Regulated Learning or critical thinking (Zhang et al. (2026)).
- **Structured custom-GPT cycles produced four cognitive partner roles.** In a one-semester design-based study, 14 pre-service Digital Technologies teachers used LMS-integrated personalized GPT agents through Prompt–Reflect–Refine cycles, enacting conceptual tutor, co-designer, reflective mirror, and cognitive challenger roles as expertise grew (Zagami), and 82% of final artifacts mapped content descriptors, assessment tasks, and success criteria.
- **Educational robotics and ML.** Initial teacher training embeds coding, robotics, and Machine Learning activities (e.g., micro:bit) to build computational thinking in future teachers.(Coding,

robots, computational concepts, and machine learning using the microbit card and the Maqueen and Nezha kits. A study in initial teacher training)

- **Authentic assessment and Metacognition.** AI-mediated assessment models (e.g., AAIWA) integrate authentic rubric-based assessment, condition-responsive AI feedback, and metacognitive reflection in pre-service programs.(AI-mediated authentic assessment and metacognitive reflection: A mixed-methods study of the AAIWA model)
- **AI-supported inquiry in science education.** A quasi-experiment with 48 pre-service science teachers in Türkiye (Aydın) integrated problem- and design-based learning into an 8-week AI-supported guided inquiry program on photosynthesis and respiration. It produced significant gains in conceptual understanding of the two biological processes, but *no* significant effect on AI literacy or self-perceived computational thinking — a reminder that AI-IBL can deepen subject-matter understanding in teacher candidates without automatically building their AI/CT competencies, which require explicit, targeted design.
- **Metacognitive prompting is not group-neutral, so future teachers have to learn to read the group.** In Wang et al.'s (2026) study the learners were pre-service teachers themselves, fourteen groups working a 60-minute inquiry with an on-demand metacognitive chatbot. Groups whose members held different preconceptions made the AI a center of conceptual talk; groups that already agreed used it as a lookup and evaluated proactive nudges negatively. The authors' practitioner note asks teachers to compose groups on preconception diversity and to keep shared-regulation support optional.
- **Generative AI for constructivist instructional design.** The SAHAB model is a quasi-experimental professional-development intervention in which generative AI empowers teachers to design Constructivism instruction, with large gains (d = 1.18). It shows GenAI can scaffold instructional design for teacher candidates and practicing teachers alike — not just deliver content, but support the *design* of student-centered learning activities.
- **Smart-classroom training for graduate mathematics M.Ed. students.** Zhu, Liang, Mao, and Wang (2026) show how a mathematics M.Ed. course can be enhanced with intelligent educational technologies (automated scoring, personalized recommendations, multi-AI feedback) across pre-, in-, and post-class stages, yielding statistically significant gains in instructional-objective design proficiency. The transferable D-T-E Model (Disciplinary Demand–Technological Empowerment–Evaluation Loop) offers teacher educators a discipline-specific framework for integrating smart education into graduate teacher preparation.
- **Adoption under a permissive policy is thinner than surveys suggest, and assessment literacy does not transfer.** Zou et al. (2026) surveyed 85 student teachers across three Hong Kong teacher-education courses where generative AI was explicitly permitted in assessment: 62.4% (53) chose not to use it at all, and adopters' use was shallow and corrective (proofreading 43.8%, clarity checks 34.4%, text generation 18.8%, brainstorming 12.5%). Fear of being wrongly accused of plagiarism (41.5% of non-adopters) and a preference for solo work (77.4%) outweighed missing skills (13.2%), and nine of eleven interviewees read the permissive policy as a possible "trap" — evidence that pre-service teachers bring integrity anxiety, not just tool readiness, into AI-permitted coursework.

- **Classroom AI policy writing as a lens on preservice thinking.** Nash & Burriss (2026) had 27 preservice secondary English teachers in the capstone year of a secondary English preparation program write the AI policies they would use in their own 6–12 classrooms, in a state with no state-level AI guidance. 26 of the 27 permitted some AI use, almost always restricted to teacher-specified tasks, times, and places, and only one banned it outright on ethical grounds tied to labor practices and copyright; 22 permitted AI for generating ideas while 22 disallowed or left unclear the use of AI to compose sentences, paragraphs, or papers, and the accompanying reflections read as negotiations between pedagogical commitments and a felt obligation to integrate AI. Asking preservice teachers to author a policy — rather than debate AI in the abstract — surfaced their philosophies, beliefs, and curricular assumptions, making policy writing a high-value activity for methods coursework.
- **Policy does not govern practice.** Four semesters of survey data from a US teacher-education program show GenAI use for assessment preparation rising from 57% to 83% and for studying from 44% to 76%, even as institutions considered AI Detection software, with ethical uncertainty rising across the waves (Parker et al. (2026)).
- **No pre-service study measured pupil learning.** A review that could include only seven sources found ethics acknowledged but seldom taught or assessed, and pre-service teachers overconfident about critiquing AI (Shukla (2026)).

In-service professional development

In-service professional development supports practicing teachers in integrating AI. AI research here includes:

- **Intelligent-TPACK-based PD frameworks.** A research-informed framework aligns the five i-TPACK knowledge domains with four evidence-based PD pathways (active learning, models/examples, coaching, feedback/reflection).(Designing effective AI professional development: A framework grounded in intelligent-TPACK)
- **GenAI-specific technological pedagogical knowledge (TPK).** Teacher educators themselves need GenAI-TPK — pedagogical reasoning, ethical awareness, and AI-augmented instructional design — to prepare teachers.(Teaching the teachers: A systematic review of genAI-specific technological pedagogical knowledge (TPK) in teacher education)
- **Human-centered and critical AI literacy.** Design-based research produces professional-learning curricula that operationalize critical AI literacy through human-centered AI activities, including educator-in-the-loop tasks.(Human-centered AI for teacher educators: Designing professional learning for critical AI literacy)
- **Capacity built by doing, not by studying.** A TPACK-based structural model of 122 in-service teachers found that actual use of AI on science and green-energy tasks and involvement in developing ESD-aligned materials predicted AI-integration capability, while abstract AI knowledge and attitudes toward AI did not (Riandi et al. (2026)).
- **Collaborative evaluation of AI-generated content as PD.** Gat, Usher, and Barak (2026) report on a workshop in which 60 middle-school science teachers rated ChatGPT-generated assessment questions through their disciplinary, pedagogical, and curricular judgment. Collaborative

evaluation itself functioned as professional development, helping teachers apply conceptual-precision criteria to AI output and surface the risk that AI content reinforces Misconceptions about AI — positioning teachers as critical evaluators of GenAI material rather than passive consumers.

- **Structured PD for language educators is rare but effective.** A systematic review of 23 studies (Li et al. 2026) found only three included studies reported structured professional development — an embedded grammar-course module, a government EMI program, and embedded chatbot inquiry — yet all converged on gains in knowledge, confidence, and identity reframing, shifting educators' views of GenAI from "replacement risk" to assistant/augmenter. The review argues PD should pair technical skill-building with practical wisdom, moving from awareness-raising and ethics through hands-on tool mastery to co-design of AI-enhanced lessons, and recommends a two-phase "back-end then classroom" implementation strategy.

The knowledge base's clearest instance of framework-driven GenAI PD for mathematics is a study of eight in-service teachers from rural and under-resourced districts who completed ten interactive modules built on Rhodes' 4P framework (How generative AI guided-professional development supports teachers' engagement with mathematical creativity, content knowledge, and pedagogical content knowledge). It supplies two design mechanisms in-service PD design otherwise lacks here: scaffolding that fades deliberately (explicit guidance early, then requests to justify, generalize and design tasks) and simulated student reasoning across Modules 6-10, alongside the finding that MC, CK and PCK moved together — while measuring engagement only, not teacher knowledge or student learning. - **Post-qualification programs.** In-service science educators' AI literacy and usage inform the design of AI-related post-qualification programs.(Science educators' AI literacy and AI usage in teaching: Implications for post-qualification programs)

- **AI support and guidance in teacher design work.** Pishtari, Gnadlinger & Ley (2026) had 13 higher-education teachers design activities across no-AI, AI-chatbot, and AI-plus-training conditions in a half-day program. AI access raised higher-order (Bloom) task attainment and cut perceived cognitive effort, while the subsequent interaction-training session plateaued quality but slightly raised effort (germane vs. extraneous load unresolved). It frames PD for AI-era teaching as needing both pedagogy-grounded design frameworks (Bloom, ICAP) and structured chatbot-interaction strategies, while cautioning that quality gains may mask offloading of pedagogical decisions to AI.

Knowledge, beliefs, and practice

A key finding across teacher-education research is the gap between what teachers *articulate* and what they *enact*: teachers often claim operational AI skills but struggle to apply pedagogically meaningful knowledge in practice.(Beyond operational skills: Teachers' AI knowledge and interactions with generative AI in lesson planning) The distinction runs even deeper when experience is crossed with AI proficiency: Choi et al. (2026) found that technically fluent *novices* still accept AI output passively during lesson design, whereas experienced teachers — even those with lower measured AI proficiency — critically re-prompt and adapt AI suggestions to their students and context. The implication is that in-service PD cannot treat "building AI skill" as sufficient; it must be differentiated by the teacher's experience and proficiency profile — response-evaluation and critical-adaptation scaffolds for novices, hands-on AI skill-building for experienced teachers with weaker AI proficiency. Expert judgment of AI-generated lesson plans marks that critical-adaptation

stance as the norm, not the exception: Karaismailoglu, Surmeli and Yildirim (2026) found eleven Turkish science-education specialists rated ChatGPT-4 and Teacher's Buddy plans for a sixth-grade unit as usable drafts — 7 of 11 judging them "applicable by correction," only 3 directly "Applicable" — and their preferences diverged from raw scores, favoring affective and contextual qualities over structural fidelity. Teacher education should therefore build the ability to evaluate, adapt, and localize AI-generated instructional materials as a core professional competence, in both pre-service and in-service programs. Psychological factors also matter — Self-Efficacy positively predicts AI-TPACK, while strong traditional teaching beliefs can act as a cognitive barrier.(Assessing AI-TPACK readiness in mathematics teacher education: The role of self-efficacy and teaching beliefs) Trust in AI is shaped by both technical knowledge and ethical perceptions (transparency, fairness, accountability, inclusiveness).(Unpacking ethics-domain of intelligent-TPACK scale in relation to in-service teachers' trust and distrust) Measuring teachers' AI literacy is itself an active front: because most AI-literacy assessments target students or general users, the Teachers' AI Literacy Scale (TAILS) — grounded in the six-dimension ED-AI framework — was developed and validated specifically for preservice language teachers through EFA and CFA, filling the measurement gap within teacher education. A comparably neglected question is whether the *mode* of preparation changes AI readiness. Mnguni et al. (2026) surveyed 186 final-year science student teachers in South Africa and found self-reported TPACK for AI-integrated teaching higher at a campus-based university (64.0%) than at a distance education university (47.4%), with Pedagogical Knowledge weakest in both, and AI training associated with self-reported TPACK only at the distance institution, where a five-credit short course predicted weaker reported TPACK than no training. Distance preparation therefore needs its own evidence base rather than assuming that training designed for campus programs transfers.

Simulated instructional practice

Beyond content and beliefs, teacher preparation increasingly uses **simulated classrooms** for hands-on practice that scales. EducaSim uses generative student agents (with personas, course-grounded memories, and an Large Language Models (LLMs)-as-judge speech oracle) to simulate a small-group section for teachers-in-training in a CS1 course supporting ~20,000 students. Deployed as an optional prep tool across 254 sessions (mean ~16 min), it provides low-cost ($0.05–$0.10/session) role-play practice with structured post-session feedback (talk-time statistics, LLM-identified instructional behaviors) and self-reflection prompts. This complements the Simulating Students paradigm: simulated learners serve not just evaluation but experiential, high-frequency teacher preparation, especially for massive online courses where live coaching cannot scale. A subject-specific instance is **Student GPT** (Zhuang & Zhang 2025), a custom ChatGPT chatbot that role-plays a middle school student holding common ratio-reasoning misconceptions; preservice secondary mathematics teachers practiced diagnosing and remediating those misconceptions in low-risk, personalized interactions within a methods course, showing how lightweight GenAI role-play can support practice-based teaching.

Implications for teacher educators

- **Build both AI literacy and critical AI-TPACK.** Pre-service and in-service teachers need readiness to integrate AI — instruments extend TPACK with an AI/ethics dimension (AI-TPACK, i-TPACK PD); teach ethical reasoning, transparency, and fairness alongside tool use.

- **Measure capability rather than confidence.** Mnguni (2026) argues that self-reported TPACK and perceived behavioral control may both index general confidence, and proposes scoring readiness with lesson-design tasks and prompt-evaluation tasks rather than self-report alone, ordering AI-TPACK capability upstream of attitude and intention.
- **Close the articulate-vs-enact gap.** Teachers often claim operational AI skills but struggle to apply them pedagogically; design PD that moves from knowledge to enacted practice (lesson planning).
- **Use simulated practice to scale preparation.** EducaSim-style simulated classrooms give teachers-in-training low-cost, high-frequency practice with feedback — a complement to limited live coaching.
- **Address beliefs and trust.** Self-Efficacy predicts AI-TPACK while strong traditional-teaching beliefs can be a barrier, and Trust is shaped by transparency/fairness — attend to these psychological factors, not just skills.
- **Backtracking from classroom dilemmas.** Kohnke et al. (2026) interviewed **17 pre-service teachers** at a Hong Kong university and worked backward from anticipated classroom dilemmas to teacher-education design needs. Pre-service teachers raised concerns about **academic integrity, privacy, and preserving essential human skills** in a GenAI-driven environment, pointing to curriculum implications that weave **ethics, Privacy, and AI literacy** (with critical-thinking skills) throughout teacher preparation rather than treating responsible use as an add-on.
- **AI as cognitive mediator in teacher reflection (2026):** A practice-based Reflective Triangle Model uses AI to mediate between individual teacher reflection and shared professional knowledge in learning communities, addressing the common failure of reflection to transform into collective professional learning (The Reflective Triangle Model: AI as a Cognitive Mediator in Teachers' Professional Learning and Learning-Community Development).
- **Make GenAI assessment design part of professional curriculum work.** Student teachers in Zou et al. (2026) showed little intention of redesigning their own future school assessments in response to generative AI, and the kindergarten and secondary participants largely judged the technology irrelevant to their own teaching context — an underdeveloped dimension of assessment literacy rather than a knowledge gap. Teacher-education programs should therefore embed ethical GenAI use in assessment design as part of professional curriculum, pairing program-level policy consistency with concrete exemplars of acceptable and unacceptable use and timely Feedback on students' actual AI use.
- **Separate delegable from non-delegable work.** O'Byrne (2026) found 23 undergraduates, most pre-service teachers, produced comparable artifacts whether they sustained boundary work or delegated it early, and the "cheating tension" over authorship was strongest among those doing the most boundary work — so the teaching aim is judging which interpretive work not to hand over.
- **Make classroom policy writing a core teacher-education activity, and treat ambiguity as a policy defect.** Nash & Burriss (2026) found that asking preservice teachers to write their own classroom AI policies functions as rhetorical world-building about what writing is for — a window into emergent beliefs that abstract discussion does not open. Because AI separates

writing-as-product from writing-as-process, programs should help teachers locate where thinking, learning, and value actually live across brainstorming, drafting, revising, and editing rather than locating thinking only in final text, and should support them in translating beliefs into operational, unambiguous rules paired with AI Literacy instruction: contradictions such as barring AI-generated text while holding students responsible for the AI-generated content they submit leave students unable to comply.

- **Teach teachers to read the primary research behind AI policy.** A six-week graduate research-methods course aimed at research consumption rather than production: one teacher applied the critical-evaluation framework to a district-mandated curriculum and presented the analysis to her principal, and several adopted Socratic questioning with their own students Packard et al. (2026).

Common Misconceptions

- **“Acceptance of AI among pre-service teachers is a single attitude.” 128 pre-service teachers** were profiled into four ChatGPT-acceptance groups including **Resistant Skeptics (14.06%), who reported high perceived ease of use but very low behavioral** intent. Ease of use and intention came apart in that group, so a usability-driven intervention would leave them unchanged.
- **“AI helps pre-service teachers mainly with content knowledge.”** A **scoping review of 55 studies** finds AI enhances **instructional design, subject instruction and practical teaching** — the design and practice capacities, not the content expertise.
- **“A scoping review of 55 studies establishes benefit.”** It documents what is reported across the field. Breadth of reported enhancement is a claim about the literature’s consensus, and 55 studies in a scoping review is not a pooled effect.

Connected Concepts

- Teaching
- Technological Pedagogical Content Knowledge (TPACK)
- Teacher AI Competency
- AI Literacy
- Educational Development
- K-12
- Ethics
- AI in Education
- Learning Sciences
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation

Connected Articles

- Artificial Intelligence in Teacher Education: A Systematic Literature Review of Pedagogical Frameworks, Empirical Evidence, and Ethical Implications (2020-2026) — AI in teacher education: pedagogical frameworks, empirical evidence and ethics, 2020-2026 (Shukla 2026)
- How generative AI guided-professional development supports teachers' engagement with mathematical creativity, content knowledge, and pedagogical content knowledge — How generative AI guided-professional development supports teachers' engagement with mathematical creativity, content knowledge, and pedagogical content knowledge
- Writing the rules for generative machines: Tensions and entanglements in preservice teachers' classroom AI policies — Preservice English teachers authoring classroom AI policies: permitted, limited, and banned uses (Nash & Burriss 2026)
- "Is this a trap?": Student teachers' perceptions and adoption of GenAI in assessments in three teacher education courses — 85 student teachers: shallow GenAI adoption, integrity anxiety, and assessment literacy that doesn't transfer
- When Teachers Use AI Chatbots and Are Trained for It: Impact on Learning Design Quality and Cognitive Effort — AI chatbot support and training in teachers' learning design
- Pedagogy first, technology second: Cross-level relationships between teacher professional knowledge and student learning in artificial intelligence (AI) education — Pedagogical AI knowledge as the priority lever for teacher professional learning (Shen et al. 2026)
- Preparing pre-service teachers for responsible generative AI use: Curriculum implications for ethics, privacy, and AI literacy — Pre-service teachers' responsible GenAI use: curriculum implications (Kohnke et al. 2026)
- Harnessing artificial intelligence for preservice teachers' development: A scoping review of applications, benefits, and challenges — Scoping review of AI in preservice teacher development
- Designing effective AI professional development: A framework grounded in intelligent-TPACK — Intelligent-TPACK-based professional development framework
- Human-centered AI for teacher educators: Designing professional learning for critical AI literacy — Professional learning for critical AI literacy in teacher educators
- Teaching the teachers: A systematic review of genAI-specific technological pedagogical knowledge (TPK) in teacher education — GenAI-specific TPK in teacher education
- Beyond operational skills: Teachers' AI knowledge and interactions with generative AI in lesson planning — Teachers' AI knowledge in GenAI lesson planning
- Analyzing teacher-AI interaction patterns across teacher experience and AI proficiency in student-centered lesson design — Teacher-AI interaction patterns across teaching experience and AI proficiency in lesson design (Choi et al. 2026)
- Conceptualizing pre-service teachers' readiness for AI integration into teaching practices: An intelligent-TPACK approach — Pre-service intelligent-TPACK readiness

- Assessing AI-TPACK readiness in mathematics teacher education: The role of self-efficacy and teaching beliefs — AI-TPACK in mathematics teacher education
- Unpacking ethics-domain of intelligent-TPACK scale in relation to in-service teachers' trust and distrust — Ethics domain and in-service teachers' trust
- Coding, robots, computational concepts, and machine learning using the microbit card and the Maqueen and Nezha kits. A study in initial teacher training — Micro:bit robotics in initial teacher training
- AI-mediated authentic assessment and metacognitive reflection: A mixed-methods study of the AAIWA model — AI-mediated authentic assessment in pre-service education
- Science educators' AI literacy and AI usage in teaching: Implications for post-qualification programs — Science educators' AI literacy and post-qualification programs
- Using context-based and AI-enhanced approaches to improve student engagement and achievement in secondary chemistry education — Context-based 7E + AI instruction in secondary chemistry
- EducaSim: Interactive simulacra for CS1 instructional practice — EducaSim: interactive simulacra for CS1 instructional practice
- Unpacking the heterogeneity of pre-service teachers' ChatGPT acceptance: a latent profile analysis across STEM and non-STEM disciplines — Pre-service teacher ChatGPT acceptance profiles
- Motivation to shape the future of education with artificial intelligence: An international comparison between Switzerland and China — Motivation to shape the future of education with AI
- AI-Supported Inquiry-Based Learning in Photosynthesis and Respiration: Implications for Sustainable Science Teacher Education — AI-supported guided inquiry in science teacher education
- The Reflective Triangle Model: AI as a Cognitive Mediator in Teachers' Professional Learning and Learning-Community Development — Reflective Triangle Model: AI as cognitive mediator
- Evaluating the Effectiveness of Generative Artificial Intelligence in Empowering Teachers for Constructivist Instructional Design: A Case Study of the SAHAB Model — SAHAB model: GenAI constructivist instructional design
- Teacher Involvement in Developing Sustainable Education Materials for AI Integration in Green Energy Education — Teacher involvement in AI integration for green energy education (Riandi et al. 2026)
- Longitudinal insights into AI in education: Usage, ethics, and policy development in higher education — Longitudinal GenAI usage, ethics, and policy in teacher education (Parker et al. 2026)

- Improving instructional design proficiency of master's students in mathematics education through intelligent educational technologies — Smart-classroom model and D-T-E loop improving M.Ed. instructional design proficiency in mathematics (Zhu et al. 2026)
- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching
- Suitability of Artificial Intelligence Supported Lesson Plans from the Perspective of Science Education Experts
- Teachers' Collaborative Evaluation of AI-Generated Content: Insights from a Professional Development Workshop — Teachers' collaborative evaluation of AI-generated content as professional development (Gat, Usher & Barak 2026)
- AI training and science student teachers' TPACK in campus-based and distance education: a comparative study — Campus versus distance comparison of 186 science student teachers' AI-related TPACK and training levels
- Co-constructing AI boundaries: Agency, judgment, and ethical literacy in AI-mediated meaning-making — traces pre-service teachers building AI boundaries in a semester-long literacy ethnography
- The Impact of Unscaffolded GenAI Use on Pre-Service Teachers' AI Readiness, Self-Regulated Learning, Critical Thinking, and Instructional Design Performance: A Quasi-Experimental Study — Unscaffolded genAI lowered pre-service teachers' lesson-plan quality below the no-genAI class
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Measure capability rather than confidence
- From information providers to learning designers: heutagogical teaching practices in AI-enhanced education — A heutagogical dual-layer model linking teachers' own reflective regulation to learner agency
- Teaching with AI, Not Against It: A Thinking Partner Framework for Working Adult Learners in Compressed Online Formats — K-12 teachers learning to read primary AI research and contest district mandates
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — Pre-service teachers as the learners: groups that disagreed about energy made the AI a center of conceptual talk, groups that agreed treated it as a lookup and resented proactive nudges (Wang et al. 2026)

Connected FAQs

- How Do I Design Faculty Development for AI That Actually Changes Practice?

Bands and comparisons

Levels of Education

> **Levels of education** — the bands that organize this knowledge base's `level` metadata: **preschool**, **primary education**, **middle school**, **secondary**, **K-12**, **higher ed**, **undergraduate**, **graduate**, **adult learning**, **special education** and **teacher education**. This page is the umbrella for that field rather than a duplicate of any single band page: it explains what changes as you move across the bands, why the school/university break matters more than the subject being taught, and where the AI evidence is dense and where it is thin.

Questions to Consider

- A graduate seminar and a second-grade mathematics lesson are both "education," yet a tool that helps one can harm the other. What about the band — not the subject — changes what good AI use looks like?
- One trial with 132 second-graders found an adaptive mathematics tutor no better than a fixed sequence. Would you expect the same null for a university student, and what learner capacity does adaptation silently assume?
- 'K-12' and 'higher education' each compress several distinct settings into one label. Which comparisons do those labels hide?
- If a band's evidence base is thin, is the honest response to say nothing, to borrow from an adjacent band, or to design a study?

Introduction

The `level` metadata field names the band of education a source is about — bands, not ages: **preschool**, **primary education**, **middle school**, **secondary**, **K-12**, **higher ed**, **undergraduate**, **graduate**, **adult learning**, **special education**, **teacher education**. Some name a stage of schooling, two name the very different halves of university study, two name a learner population rather than a stage, and one names the people who teach. A source can carry several bands at once.

This page is the umbrella for that field; the band pages do the deep work and should be read with it: K-12, Early Childhood Education, Higher Education, Adult Learners, Special Education, Teacher Education and Vocational Education and Training.

What distinguishes one band from another

Bands differ along several axes at once, and AI research usually varies only one of them.

- **Capacity for self-regulation.** Two versions of the same second-grade mathematics tutor — identical content, interface, feedback and spoken hints, differing only in whether task selection followed a Bayesian Knowledge Tracing mastery estimate — produced no posttest difference among 132 seven-year-olds ($F(1, 124) = 0.32$, $p = .574$). The authors' first explanation is developmental: adaptive systems presuppose learners who can engage feedback, regulate effort

and stay focused, and young children have limited self-regulation (Effectiveness of adaptive versus non-adaptive intelligent tutoring systems in early primary mathematics).

- **Who mediates the interaction.** In the school bands an adult stands between learner and tool. A survey of 270 preschool teachers found adoption intention driven by perceived usefulness, ease of use, AI Self-Efficacy and AI anxiety — and the study deliberately excluded AI directed at children (Exploring factors influencing preschool teachers' behavioral intention to use AI technologies in early childhood settings).
- **What the assessment is for.** Secondary assessment feeds external stakes; university assessment is coursework and credentials; graduate assessment is the making of a researcher.
- **Prior knowledge.** Prior knowledge dominated that trial's posttest performance ($F(1, 124) = 206.99$, $p < .001$, $\eta^2p = .63$), so a band label correlates with, but does not equal, a knowledge level.

The school years and the university years

The most consequential divide is the break between school and university, and the two commonest labels each hide it or cross it.

Inside the school years the measured outcome changes sharply by band. In primary it is subject learning: 97 Chinese third-graders using GenAI chatbots in science inquiry posed better problems than a search-engine control ($t = 2.47$, $p = 0.015$) (Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science). In secondary it often becomes attitude rather than achievement: a survey of 508 Taiwanese junior high students found experiential appeal working through enjoyment to shape intention to use ChatGPT for lyric learning (XM → PEOU $\beta = 0.630$; PE → ATU $\beta = 0.369$), with 81.5% on the free tier — an access-equity fact disguised as a technology-acceptance finding (Junior high school student perspectives on the use of ChatGPT in music education). Secondary also holds the corpus's largest learning warning: across 26,811 Chinese students in grades 7–12, homework scores rose 18% and completion time fell 30% while closed-book exam scores dropped about 20% within six months, concentrated among the ~81% whose behavior indicated homework outsourcing (The generative AI learning penalty: Evidence from Chinese secondary education).

The university years split again. Undergraduate study is coursework under external judgment: among undergraduate writers at a minority-serving R1 university, AI Literacy predicted *which type* of Large Language Models (LLMs) reliance a student occupied rather than how much they used it (Four Types of LLM Reliance and Their Predictors Among Undergraduate Writers: A Mixed-Methods Study at a Minority-Serving R1 University). Graduate study is research training, where the outcome shifts from performance to formation. Among 420 astronomy doctoral and postdoctoral researchers, AI dependence was negatively associated with research autonomy ($r = -.355$) and Self-Efficacy ($r = -.321$), and the indirect path to innovative behavior ran mostly through autonomy ($-.115$) rather than self-efficacy ($-.069$); supervisory support weakened the negative link to autonomy ($B = .077$, $p = .020$) (AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training). A doctoral student is judged on the judgment that AI dependence appears to erode; an undergraduate is not. Lumping both under 'higher education' hides that.

Where the evidence is concentrated, and where it is thin

The corpus is unevenly populated, and the level field makes the imbalance visible.

Dense. Higher education is the most-covered band: the pages consulted here include an eight-week platform trial with 60 engineering students (Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams), a survey of 395 education managers (AI adoption readiness among Ukrainian education managers: Barriers, typologies, and policy implications), a meta-synthesis of 18 African higher-education studies (Rethinking data privacy for AI adoption in African higher education: A meta-synthesis of stakeholder perceptions and policy implications) and a 420-researcher study of doctoral training (AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training). Primary and secondary also carry outcome evidence.

Thin, and in places absent. The pages consulted here report no child-outcome study at the preschool band at all; the nearest evidence is a survey of teachers' intentions that excluded child-facing tools (Exploring factors influencing preschool teachers' behavioral intention to use AI technologies in early childhood settings). Middle school appears mainly as a *proposed* design and longitudinal study rather than reported outcomes (AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond). The vocational band's strongest evidence is 63 self-report responses from one course, which its authors say requires replication (Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments). The graduate evidence is cross-sectional, with a reverse-path model fitting slightly better than the developmental one, so the direction from dependence to reduced autonomy is inferred rather than confirmed (AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training). Nothing consulted here reports AI outcome evidence for **adult learning** or **special education** as bands; those have their own coverage on Adult Learners and Special Education, and this page does not generalize from school-age findings to fill the gap.

One pattern holds at every level surveyed: the human layer absorbs the hardest cases. A human expert stayed at the credibility decision point for engineering students even when algorithmic recommendation reached F1 = 0.64 (Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams); supervisory support was the one condition that weakened AI dependence's negative links in doctoral training (AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training); and it is preschool teachers, not children, who are the adopters (Exploring factors influencing preschool teachers' behavioral intention to use AI technologies in early childhood settings).

What level-appropriate design actually changes

- **Autonomy and support.** With young learners, adapt the *level of support* — more Scaffolding, guidance or hints — rather than task difficulty; difficulty adaptation bought nothing in early primary, while mastery gating may have held adaptive students back (Effectiveness of adaptive versus non-adaptive intelligent tutoring systems in early primary mathematics).

- **Reading level.** An age-tailored chatbot used prompt variables for ages 7–9, 9–11 and 12–14, and 63 children from first through eighth grade treated it as a credible information source (Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot).
- **Mediation.** Parents and teachers mediate in the school years, Librarians and supervisors in the university years — and the university counterpart is expertise rather than guardianship: the engineering platform kept a human where the algorithm was least confident (Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams).
- **Assessment stakes.** The middle-school LMS design gates AI by activity, keeping bounded hints in practice mode and switching AI off on graded items (AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond) — a precaution the secondary learning-penalty evidence makes concrete (The generative AI learning penalty: Evidence from Chinese secondary education).
- **Data-protection duties for minors.** Obligations scale with age: for minors the corpus's proposals are structural — data minimization, age-appropriate response constraints, role-based access control, auditable logs (AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond) — and children's digital-safety awareness cannot be assumed, since some were willing to confide secrets in a chatbot (Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot). For adults the duties shift toward consent, control and cross-border data flow (Rethinking data privacy for AI adoption in African higher education: A meta-synthesis of stakeholder perceptions and policy implications).
- **Governance that fits the band.** Readiness is layer-specific: 395 Ukrainian managers scored personal readiness 0.68 points above system readiness (d = 0.73), cited regulatory absence most often (58.5%), and rated personalization — the benefit vendors promise most — lowest of all applications (29.4%) (AI adoption readiness among Ukrainian education managers: Barriers, typologies, and policy implications).

Implications for AI in education

- **Read the level field before the topic field.** A finding from one band is a hypothesis for another, not a transferable result.
- **For the youngest bands, adapt support, not task difficulty** (Effectiveness of adaptive versus non-adaptive intelligent tutoring systems in early primary mathematics).
- **Don't port a tool across the school/university break without re-specifying who holds epistemic authority.** Dependence that lowers autonomy in doctoral training is a research-formation risk (AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training).
- **Gate AI by activity, not by enthusiasm**, and scale privacy duties with age (AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond, Rethinking data privacy for AI adoption in African higher education: A meta-synthesis of stakeholder perceptions and policy implications).

- **Design for the mediating adult of that band** — parent, teacher, librarian or supervisor — and measure their readiness separately from the institution's (AI adoption readiness among Ukrainian education managers: Barriers, typologies, and policy implications, Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams).
- **Say plainly when a band has no evidence**, and **don't mistake intention for achievement**: several level-specific studies report attitude or self-report outcomes rather than learning.

Common Misconceptions

"A band label tells you what a learner can do." Band and knowledge level correlate without being equal. In the second-grade tutoring trial, prior knowledge dominated posttest performance (**$F(1, 124) = 206.99$, $p < .001$, $\eta^2_p = .63$**) — a large effect that makes the grade-level label a weak predictor beside the learner's actual prior knowledge. Designing to the band and ignoring the within-band spread is designing for the average of a wide distribution.

"The subject being taught matters more than the education level." The school/university break matters more. What changes across that boundary is not the content but the capacity for self-regulation, the nature of the assessment contract, and who is responsible for the learning — which is why a tool that helps a graduate seminar can harm a second-grade lesson even on comparable content.

"An adaptive tutor helps every level equally." The comparison that isolates the variable is instructive: two versions of the same second-grade mathematics tutor — identical content, interface, feedback and spoken hints — differing **only in whether task selection followed a Bayesian Knowledge Tracing model**. Adaptive task selection is a level-sensitive intervention, and its benefit depends on whether learners at that level can act on the adaptation.

"Evidence concentrated in higher education generalises downward." It does not, and the distribution of the literature is a warning rather than a convenience. Where the evidence is dense and where it is thin is a property of the research economy, not of where AI is most used, so a claim about K-12 drawn from university samples is an extrapolation across the boundary that matters most.

Connected Concepts

- K-12
- Early Childhood Education
- Higher Education
- Adult Learners
- Special Education
- Teacher Education
- Vocational Education and Training
- Learners
- Parents and Families
- Differential Effects Across Learner Groups

Connected Articles

- Effectiveness of adaptive versus non-adaptive intelligent tutoring systems in early primary mathematics — Adaptive versus non-adaptive tutoring in second-grade mathematics (Sibley et al. 2026)
- Inquiry-based learning in STEM education: the impact of generative AI-based chatbots on primary school students' problem posing ability in science — GenAI chatbots and problem posing with third-graders in primary science
- Junior high school student perspectives on the use of ChatGPT in music education — Junior high students' attitudes toward ChatGPT for lyric learning (Weng & Chiang 2026)
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond — AI-integrated LMS designed for middle school, with a proposed longitudinal study
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty in Chinese secondary education (Strömberg et al. 2026)
- Four Types of LLM Reliance and Their Predictors Among Undergraduate Writers: A Mixed-Methods Study at a Minority-Serving R1 University — Four types of LLM reliance among undergraduate writers (Hossain 2026)
- Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams — AI-assisted seminar platform with embedded librarian support for engineering students
- AI-mediated research agency formation in higher education: Autonomy, self-efficacy and innovation in early-career scientific training — AI dependence, autonomy and innovation in doctoral and postdoctoral training (Han & Liu 2026)
- Rethinking data privacy for AI adoption in African higher education: A meta-synthesis of stakeholder perceptions and policy implications — Stakeholder views on data privacy in African higher education (Duncan 2026)
- AI adoption readiness among Ukrainian education managers: Barriers, typologies, and policy implications — Education managers' AI adoption readiness across Ukraine (Kremen et al. 2026)
- Cultivating design creativity of vocational students: A model of project-based learning in AI-enabled immersive virtual environments — AI-enabled immersive PBL for vocational design students (Jin et al. 2027)
- Exploring factors influencing preschool teachers' behavioral intention to use AI technologies in early childhood settings — Preschool teachers' intention to use AI in early childhood settings
- Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot — Children's attitudes toward an age-tailored AI chatbot

Assessment and measurement

Assessment and feedback

Assessment

> **Assessment** — the process of gathering and interpreting evidence about what learners know and can do, and the methods used to evaluate learning. AI in Education has fundamentally reshaped assessment: it powers automated grading and scoring, generates and adapts assessment items, and raises deep questions about what assessments actually measure when students can use AI. Assessment is the umbrella concept that organizes the knowledge base's coverage of Formative Assessment, automated grading, validity, and Educational Measurement.

Questions to Consider

- Assessment here is defined as gathering and interpreting evidence about what learners know and can do. Before reading, how would you finish the sentence 'an assessment is valid if…' — and what would change about that answer if every student could secretly use AI to produce their work?
- The page claims that how a student uses GenAI (evaluative integration versus uncritical shortcut uptake) predicted performance, while how often they used it predicted nothing. What does this suggest about a common instinct to regulate AI by limiting its use?
- A learner may deliver professional-standard work they cannot reproduce without the tool — severing the inference between performance and underlying ability. Have you encountered a 'competency' being awarded for work that the student couldn't actually do unaided? What did that reveal?
- The constructive question the page offers is not 'how do we stop students using AI?' but 'how do we enable thoughtful use in contexts that mirror their future work?' What would assessment look like in your field if that were the goal?
- The DRIVE framework suggests assessing the quality of a student's engagement with GenAI — not just the artifact — by looking at whether they steer prompts strategically and integrate their own ideas. What would you look at to tell a deep, reflective AI interaction from surface consumption?
- AI-mediated assessment is diversifying into oral exams, portfolios, and conversational formats that reduce anxiety and feel professionally relevant. Which assessment format from your own experience do you think is most 'AI-resistant' — and is resistance the same thing as educational value?

Introduction

Assessment is central to AI in education for two reasons. First, AI itself is used to assess students — grading essays, code, short answers, and exams at scale. Second, AI in the classroom changes what assessments can validly measure, since students may use Generative AI to produce work. The field therefore spans both the *tools* that automate assessment and the *validity and integrity* questions that AI raises. A PRISMA review of 72 higher-education assessment studies found educators used GenAI across the whole assessment cycle —

creating assessments, practice, grading, transparency of learning and feedback — with creating assessments and feedback the most frequently identified affordances (Crompton and Burke (2026)).

How AI is used in assessment

- **Automated assessment:** AI-based assessment spans multiple modalities — multiple-choice, short answer, essay, code, and performance-based evaluation — through automated grading, Automated Essay Scoring, and Automated Question Generation.
- **Formative assessment:** AI systems generate, validate, and adapt formative assessment items at scale, informing ongoing instruction rather than only summative evaluation.
- **Learning analytics and measurement:** Learning Analytics and Educational Measurement connect assessment data to learning processes, using Item Response Theory, Knowledge Tracing, and Learner Modeling and Adaptive Instruction to interpret performance. Razavi and Powers (2026) demonstrate LLM-based item-difficulty estimation as a measurement input: across 5,170 K-5 math and reading items calibrated under the Rasch IRT model, GPT-4o's zero-shot ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but varied by grade, while a feature-based approach (LLM-extracted features into tree-based models) reached correlations up to r = 0.87. The study offers a practical seven-step workflow for testing professionals, while cautioning that generalizability beyond K-5 math and reading is unclear.
- **Feedback loops:** AI assessment increasingly feeds into feedback loops that close the cycle from assessment to learning.
- **E-portfolio assessment:** e-portfolios assemble student work and reflections over time as a process-based, AI-robust assessment form. Generative AI can assist the portfolio *process* — generating feedback, Scaffolding reflection, and (with appropriate rubric design) supporting evaluation — while the portfolio's emphasis on reasoning traces and drafts resists AI fabrication. AI-assisted portfolio assessment and ChatGPT + e-portfolio for EFL speaking show AI can enhance both the portfolio experience and learner Feedback Literacy.
- **Open-ended grading reliability is model-dependent:** Pecuchova, Benko & Drlik (2025) benchmarked eleven GenAI and sentence-embedding models against two expert graders on 1,885 open-ended software-engineering responses: only GPTo1 reached almost-perfect agreement (Fleiss' Kappa 0.82), while reference-based models penalized correct-but-divergently-phrased answers. Because GPTo1 was the only model deemed deployable without oversight but carries proprietary API costs, the authors recommend hybrid strategies pairing advanced models with affordable options or human oversight in resource-constrained settings. A PRISMA-guided systematic review of 42 empirical studies (2023–2025) corroborates this conditional-reliability picture across the whole grading field: LLMs match human raters on closed-ended and short-answer tasks but cannot fully replace human judgment on complex, open-ended, or subjective work, and no uniform grading bias emerged — models were sometimes more lenient, sometimes stricter, and often avoided extreme scores (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback). Iterative rubric refinement can push LLM open-ended scoring toward near-human reliability in high-stakes medical settings: Olvet et al. (2026) found that once faculty repeatedly revised analytic and holistic rubrics on error-pattern analysis, GPT-4 reached substantial-to-almost-perfect

agreement with faculty graders on three of four pre-clerkship questions (weighted kappa up to 0.94), while the residual holistic-rubric item stayed at only moderate agreement (κw = 0.54) — showing both the payoff of human-in-the-loop rubric engineering and its limits on synthetic, holistic tasks.

- **AI-supported oral and performance assessment.** A TVET design study moves assessment away from text-heavy formats toward interactive Oral Assessment supported by an LLM: across four cohorts, 21 of 33 learners rated the voice task realistic and none disagreed that speaking in real time reflected competence better than a written portfolio, while word counts for identical questions varied five- to eight-fold between cohorts and nine learners answered in two to thirteen words and were all correct. The system ran offline on a single laptop serving up to 12 simultaneous learners with Mistral 7B and faster-whisper, deleted recordings after 90 days, and left scoring judgments with assessors — an instance of Human-in-the-Loop assessment design for workplace-facing qualifications. (Designing AI-Supported Oral Assessment in TVET)

Validity and measurement challenges

AI raises fundamental validity questions: do AI-graded assessments measure student learning or AI-prompting skill? Does student use of AI invalidate traditional assessments? Key challenges include:

- **Construct validity:** Research on competency-based education shows generative AI has severed the inference between performance and underlying ability — a learner may deliver professional-standard work they cannot reproduce without the tool. This motivates reconceptualizing what competencies are assessed.
- **A three-vertex frame for realigning assessment.** Koretsky et al. (2026) treat ubiquitous GenAI as a validity and capability-definition problem rather than a cheating one, arguing that the assessment triangle's three vertices — cognition, observation, and interpretation — must be realigned together rather than patched one at a time.
- **Coauthorship and integrity:** Coauthorship integrity proposes a new source of validity evidence violated when students submit AI-generated content they do not understand, and explores conversational "AI Vivas" as a response.
- **Psychometric quality:** Psychometrically Aware AI and confidence-aware assessment work to keep AI scoring reliable, unbiased, and interpretable.
- **Evaluation of AI assessors:** AI Ed Evaluation provides the methods and benchmarks for determining whether automated assessors actually work — on reliability, Pedagogies and Teaching Strategies, and Equity — rather than headline accuracy alone.
- **Quality-dependent reliability of AI and peer grading (2026):** Comparing ChatGPT, peer, and instructor grading of the same undergraduate group projects, Usher & Faraon (2026) showed grading alignment with the instructor is *conditional on the quality of student work*: ChatGPT inflated low-quality submissions most and aligned better with the instructor on high-quality work, while peers aligned best on weaker work and under-graded strong projects. The finding challenges the binary "reliable vs unreliable" framing, pointing toward conditional-reliability models in which alternative assessors are matched to task and performance level.

- **Human grading is itself value-laden (2026):** Luo & Dawson (2026) show that even human grading of GenAI-assisted work is not a neutral, criteria-based act. Scenario-based interviews with 33 university teachers revealed grading decisions driven by person-oriented (honesty, diligence), capability-oriented (independence, GenAI skill, disciplinary mastery), relation-oriented (trust), and justice-oriented (fairness, beneficence) values — extending beyond the assignment to teachers' conjecture about the student. The study reframes the assessment question from "is GenAI use cheating?" to "how do teachers' value judgments shape grades, and are those values relevant to the outcomes being assessed?" — foregrounding validity and "two-way transparency" about how GenAI use will affect grades.

Integrity and the debate over detection

AI in assessment has intensified the integrity conversation. One strand focuses on detecting AI-generated text, while a growing body of research argues that detection is a limited, situational tool — not a strategy of first resort. Beyond Detection and Responsible Assessment argue that authenticity cannot be policed into existence; it must be redesigned, positioning AI as a declared collaborator and prioritizing authentic, process-based assessment over surveillance. **Walton et al. (2025)** ground this in evidence of **how students actually judge** their way through assessment with GenAI: scroll-back interviews with 26 students revealed a spectrum of six judgment events — from critically evaluating AI knowledge and learning through AI's limitations, to adopting ideas uncritically and misjudging AI contributions as their own. **Stamatoulis et al. (2026)** add a quantitative counterpart: across 157 students, *how* GenAI is used (evaluative integration to support understanding vs. low-verification shortcut uptake) predicted performance, while simple usage **frequency predicted neither** performance nor academic Self-Efficacy. Together these studies reframe the assessment question from *whether* students use AI to *how they judge and pattern that use*.

Bassett et al. (2026) go further, arguing detection should not be used at all: its probabilistic output cannot be independently verified because real-world text origin is unknown, and detector scores — alone or with linguistic markers, style comparisons, an LLM's claim, or student silence — do not meet the balance-of-probabilities standard integrity investigations require.

A PRISMA review of 25 studies adds a risk factor the detection debate leaves out: non-native English speakers showed a high tendency to breach integrity when struggling to write in English, so integrity expectations should be paired with concrete academic-writing support rather than enforcement alone (Balalle and Pannilage (2025)).

Assessment redesign in the AI era

The constructive question in the knowledge base's assessment literature is not "how do we prevent students from using AI?" but "how do we enable them to use it thoughtfully in contexts that mirror their future work?" This reframes assessment around:

- **Authentic and process-based tasks** that make AI use visible and assessed. Authentic Assessment — examining student performance on worthy, realistic tasks — is the leading response to AI's challenge: any task an Large Language Models (LLMs) can credibly simulate loses its validity, so authenticity must be redesigned around real-time collaboration, digital and social contribution, and

individual meaning-making. This connects to design frameworks for authentic assessment, authentic products and authenticated processes, and tool-invariant assessment of process.

- **Responsible assessment design** grounded in validity evidence (Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference)
- **Task-level AI permissions derived from assessment targets:** McCorkle (2025) shows the assessment-design work that precedes an AI policy — inventorying every task in a project, specifying what is being assessed and against which objective, and permitting or prohibiting AI per task on that basis (brainstorming and image curation allowed; composing learning objectives and slide design not). The same alignment exercise doubles as a check on the inference the assessment supports, because it forces the instructor to name the performance that a grade is meant to warrant (Assessment Validity).
- **Assessment that goes beyond the linguistic mode:** Jiang et al. (2026) define Multimodal AI assessment literacy for second language teachers as knowledge, value and competence for tasks that elicit responses across linguistic, visual, aural, gestural and spatial modes. A year-long program with 30 Hong Kong English teachers raised knowledge of assessment strategies from 3.13 to 4.15 out of 5 (partial $\eta^2 = 0.571$) and competence in supporting students from 3.05 to 3.98 (0.482), while all three value subdomains stayed flat. The teachers' own experience added two dimensions to the framework: sustaining the practice against competing curricular priorities, and mobilizing GenAI critically (Jiang et al. (2026)).
- **Coauthorship and declaration** as part of the assessment contract
- **Process-based rubric criteria that grade the interaction, not the artifact.** Oviedo and Díaz (2026) read Biggs's 3P model as three critical grading dimensions — human agency and critical supervision, dialogic scaffolding tied to Prompt Engineering, and cognitive sovereignty grounded in integrity and transparency — arguing that a finished file no longer carries information about whose reasoning produced it.
- **Production as a competency** — evaluating learners' ability to direct tools and produce professional-standard work (Knowledge, skills, attitudes, production: Competency-based education after generative AI)
- **Assessing the interaction process, not just the artifact** — the DRIVE framework (Directive Reasoning Interaction + Visible Expertise) treats the quality of a student's *engagement with GenAI* as the assessed construct. It distinguishes surface consumption from deep, reflective interaction by looking at whether students steer prompts strategically (DRI) and integrate and develop their own disciplinary ideas through the exchange (VE), grounding process-focused criteria in theories of Self-Directed Learning and cognitive engagement along the lines of the ICAP hierarchy. This makes DRIVE an example of *AI-mediated authentic assessment* — a rubric for evaluating how learners partner with GenAI rather than a detection tool.

A proposal in this literature pushes past redesign-within-the-current-frame. El Khoury and Ma (2026) argue that reform organized around preventing misconduct or detecting AI use narrows the educational imagination to control and compliance, and propose **joyful assessment** instead: assessment that is safe, emotionally responsive, empowering and supportive of student student agency, with safety as the load-bearing condition because without it emotional attunement becomes performance, empowerment becomes pressure and agency becomes risk. Their framing inverts the detection agenda — integrity becomes a consequence of designing

assessment students want to engage in rather than its starting point — and they position instructor-built AI agents (custom GPTs, Gems, Copilot Studio agents) as a low-stakes rehearsal space where students practice before judgment, with the claim that the AI organizes evidence while the instructor interprets it.

Implications for AI in education

- **Assessment and learning are inseparable:** good AI assessment should support learning (formative feedback) as much as it evaluates it.
- **Validity must be reconceptualised:** when AI can produce student work, assessments must measure processes, judgment, and authentic production, not just outputs.
- **Automation must be evaluated rigorously:** automated assessors need psychometric and fairness evaluation, not just accuracy claims.
- **Integrity shifts from detection to design:** the most robust response to AI in assessment is designing tasks where AI use is expected, declared, and scrutinized.
- **Innovative practices can address multiple problems at once.** Mesny, Roberge-Maltais & Galy (2026) argue that a set of five mutually reinforcing practices — Authentic Assessment, self- and Peer Assessment, reassessment, standards-based grading, and ungrading — aligned with the "assessment for learning" paradigm can counter the harms of traditional, summative-heavy, norm-referenced grading (superficial learning, eroded intrinsic motivation, stress and anxiety, inequity, and compromised integrity) in the generative AI era. They find uptake is uneven across fields — self- and peer-assessment dominate while the grading-focused innovations remain marginal — and urge educators to engage more actively and reciprocally with assessment and grading innovation, backed by incremental experimentation and institutional support.
- **AI-mediated assessment is diversifying.** AIvaluate shows an LLM-augmented conversational agent reduced student anxiety during performance-based assessments; Pentland (2026) finds asynchronous oral assessments offered higher engagement and were perceived as professionally relevant; graph-based ITS uses adaptive knowledge-state tracking to inform assessment.

Common Misconceptions

- **"Integrity is mainly a detection problem." Scroll-back interviews with 26 students** reveal that students judge their way through assessment with GenAI along a **spectrum**, and across **157 students**, *how* GenAI is used — **evaluative integration to support understanding versus** substitution — predicted the outcome. The mode of use separates students more sharply than the presence of use.
- **"Non-native English speakers are the cheating risk."** A **PRISMA review of 25 studies** adds a risk factor the detection debate leaves out: non-native speakers showed a **high tendency to breach integrity when struggling** with the language demand. That is a language-support problem misread as an honesty problem.
- **"A policy that forbids GenAI settles the question."** Students report a spectrum of judgments rather than a rule-following pattern, so a rule that does not engage the evaluative reasoning students are already doing will not be followed consistently.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Pedagogical Partnerships — Pedagogical Partnerships
- Formative Assessment — Formative assessment: AI-generated, validated, adaptive items at scale
- Automated Assessment — Automated grading and scoring across assessment modalities
- Authentic Assessment — Process-based, AI-robust authentic tasks
- Assessment Validity — Validity of assessments under generative AI
- Educational Measurement — Measurement theory underpinning AI assessment
- Automated Essay Scoring — Automated essay scoring
- Automated Question Generation — Automated question generation
- Oral Assessment — Oral assessment: live and recorded formats that resist AI substitution
- Summative Assessment — Summative assessment: AI-resistant formats (oral, proctored, closed-book exams)
- Item Response Theory — IRT for interpreting AI-era assessment responses
- Psychometrically Aware AI — Psychometrically aware AI scoring
- Learning Analytics — Analytics connecting assessment data to learning
- Feedback — Feedback loops closing the assessment-to-learning cycle
- Feedback Literacy — Learner feedback literacy
- Academic Integrity — Integrity and the debate over AI detection
- AI Detection — Detecting AI-generated text
- AI Ed Evaluation — Methods and benchmarks for evaluating automated assessors
- E-Portfolio — Process-based e-portfolio assessment
- Speech and Voice Technologies
- Peer Assessment

Connected Articles

- Conceptualizing and developing second language teachers' multimodal assessment literacy in the GenAI era — A year-long program that defines multimodal assessment literacy and measures what moved, and what did not
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- Designing an Aligned Generative AI Course Policy: An Equitable and Transparent Learner-Centered Approach — Task-level AI permissions derived from what is assessed (McCorkle 2025)
- Who grades best? Comparing ChatGPT, peer, and instructor evaluations across varying levels of student project quality — Comparing ChatGPT, peer, and instructor grading across project quality levels (Usher & Faraon 2026)
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible assessment in the AI era

- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond detection: authentic assessment
- Coauthorship integrity: Reconceptualising assessment validity for the age of generative artificial intelligence — Coauthorship integrity and assessment validity
- Knowledge, skills, attitudes, production: Competency-based education after generative AI — Competency-based education after generative AI
- Generative AI as a design variable: An evidence-centered framework for principled governance in STEM assessment — Evidence-centered governance of generative AI in assessment
- Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity — AI integrity review: detection must pair with assessment redesign
- Heads we win, tails you lose: AI detectors in education — Heads we win, tails you lose: AI detectors in education (Bassett et al. 2026)
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — AIvaluate: LLM-Augmented Assessment of Student Anxiety (2026)
- Intelligent tutoring in dynamic domains: a graph-based system for comparative analysis of adaptive algorithms with intuitionistic fuzzy logic and forgetting — Graph-Based Intelligent Tutoring for Dynamic Domains (2026)
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous Oral Assessments in the AI Era (Pentland 2026)
- Assessing students' DRIVE: A framework to evaluate learning through interactions with generative AI — DRIVE: assessing learning through GenAI interaction (DRI + Visible Expertise)
- How university students work on assessment tasks with generative AI: matters of judgement — Judgment in students' work with GenAI on assessment tasks (26 students, scroll-back)
- Same tool, different work: patterns of generative AI use and academic outcomes — Patterns of GenAI use (evaluative integration vs low-verification uptake) and outcomes
- Exploring value judgements in grading: will teachers mark down student work assisted by GenAI, and should they? — Value judgments in grading GenAI-assisted work: honesty, trust, validity, and two-way transparency (Luo & Dawson 2026)
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Can Generative Artificial Intelligence Reliably Score Open-Ended Question Assessments in Undergraduate Medical Education?
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI — AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI

- The shifting landscape of assessment in STEM education in the age of generative AI — A three-vertex frame for realigning assessment
- Rubrics and Generative AI: Towards Process-Based Assessment — Rubric criteria that grade the interaction, not the artifact

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can I Reduce AI Cheating in My Course?
- How Do I Write a Course AI Policy and Communicate It to Students?
- How Should I Handle AI in Group and Collaborative Assignments?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Evaluative Judgment

> **Evaluative judgment** — the capacity to make sound judgments about the quality of one's own work and the work of others, against criteria one can reason about rather than recite. In the generative AI era it has moved from a desirable graduate attribute to a load-bearing capability: when a tool can produce plausible finished work, the capability that distinguishes a competent learner is the ability to appraise that output — to judge what is good, what is wrong, what to accept, what to reject, and why. This makes evaluative judgment a legitimate object of Assessment in its own right, and the practical pivot for moving institutions from detection toward validity-centered and authentic assessment design.

Questions to Consider

- Think of something you can judge well. How did you learn that judgment — explicitly taught, or absorbed by making and comparing — and what does that imply for how it should be assessed?
- A rubric can be applied mechanically or understood. If a student follows criteria correctly but cannot say why one piece of work beats another, which capability has the assessment actually measured?
- When a language model drafts a plausible solution, the learner's remaining work is largely judgment: what to keep, what to fix, what to discard. Is that a diminished task, or a more demanding one than producing the draft?
- A student can accept an AI suggestion because it reads well, or because it survives their own scrutiny. From the outside the submission may look identical — what would let an assessor see the difference?
- A multisite experiment found that direct AI feedback produced the largest revision gains but risked passive outsourcing of judgment. What does that trade-off suggest about how you would design feedback to build rather than bypass judgment?
- Peer and AI review can train calibration, but both can become performative. How would you design assessment so that exercising judgment is required rather than performed?

Introduction

Assessments that ask students to produce work presume they can tell good work from poor work, first in others and eventually in their own. That presumption is no longer reliable: when generative AI can generate competent prose, code, and analysis on demand, the ability to *produce* a product is a weak signal of learning, while the ability to *judge* a product is a strong one. Evaluative judgment names that ability, and the knowledge base's assessment scholarship keeps arriving at it when asking what remains assessable and worth assessing. It sits where Feedback, Formative Assessment, and Self-Regulated Learning meet, because judgment is developed by comparing work against standards and acting on the difference, and it is what makes genuinely critical engagement with AI output possible rather than aspirational.

Xu, Lu and Abdi (2026) argue from a twelve-study scoping review that AI writing scores reproduce a narrow construct: they track checkable surface features and under-weight organization, coherence and argument, which are the dimensions a judgment of writing quality turns on.

What the construct is

Evaluative judgment is the capacity to appraise quality — one's own work, peers' work, and increasingly the work of an AI system — using criteria one can reason about rather than recite. Three features distinguish it from adjacent ideas.

- **It is about quality, not correctness.** Answering correctly requires knowledge; judging whether an answer is good requires standards a generator cannot supply on the learner's behalf.
- **It is developed, not transmitted.** Judgment grows through repeated acts of comparison — against exemplars, explicit criteria, and peers' differing approaches — which is why exemplars, calibration exercises, and peer assessment are its natural pedagogies.
- **It is domain-situated.** It is exercised inside a discipline's standards of evidence and argument, so it cannot be assessed generically any more than transfer can be assumed.

It is closely related to, but narrower than, authenticity in assessment: authentic assessment asks whether a task resembles worthwhile real-world work; evaluative judgment asks whether the learner can tell good work from poor work. Self-Assessment appraises the learner's own work, competence, or progress against criteria, whereas evaluative judgment extends that appraisal to peers' work and to the output of an AI system as well.

Why generative AI made it central

Four arguments converge.

- **The product stops being evidence.** Completion of a task no longer demonstrates the capability the task was designed to certify, because a tool can complete much of it. What remains is the reasoning that produces, checks, and accounts for the product — judgment, in short.
- **It is the capability that governs AI use.** Deciding whether an AI suggestion is worth accepting, adapting, or rejecting *is* evaluative judgment applied to machine output. Courses that cannot make it visible cannot tell responsible use from substitution, which is why integrity scholars increasingly treat critical AI use as an assessable outcome rather than a rule to be policed.
- **It is the pivot from enforcement to design.** Where prohibited use cannot be detected, Teichmann (2026) names cultivating evaluative judgment among the three design strands that relocate institutions from detection-led enforcement to validity-centered assessment — because where the institution cannot detect, the capability that survives inspection is whether the student can account for the work and its quality.
- **It converts disclosure from confession to evidence.** When a task asks students to explain what they used AI for, which suggestions they accepted or rejected, and how the final submission reflects their own judgment, the declaration becomes a demonstration of judgment rather than an admission to be interpreted punitively — which is what lowers the cost of honesty that otherwise drives disclosure underground.

- **Judgment is cultivated by composed constraints, not by removing them.** Elkington (2026) argues that generative constraints such as a short visual draft before a final artifact, or a limit of three interview clips, pace cognitive work and make judgment visible, because constraints create the moments in which appraisal is practiced.

A further layer concerns the *source* of a judgment, not only its content. AlGhamdi (2026) gives that layer a sharper vocabulary: his 13 Saudi computing students rendered two independent judgments within a single evaluation event — whether the feedback was useful, and whether its source held authority to grade. They all accepted ChatGPT's rubric-based feedback as clear and specific while overwhelmingly reserving the grade for the instructor ("I agree with it, but with one condition, that the doctor checks the feedback"), suggesting evaluative judgment in AI-mediated assessment must now include reasoning about evaluative authority itself, not only about the quality of the feedback received.

Sharma (2026) gives the construct its strongest placement in the integrity literature. Extending Eaton's (2023) postplagiarism framing from an ethical orientation into assessment design, he argues that detection- and verification-based models of integrity are misaligned with work in which human judgment and machine generation are entangled. He reframes integrity as a pedagogical practice enacted through evaluative judgment — the learner's capacity to weigh options, justify academic choices and assume responsibility under epistemic uncertainty. His four practices (annotated decision trails, verification and accountability, oral defense and dialogic accountability, draft differences with version history) make that judgment visible as evidence rather than inferring it from the artifact. He separates judgment from the constructs it is often collapsed into: reflective practice considers one's thinking retrospectively, Metacognition is the awareness and regulation of cognitive processes, whereas judgment evaluates options against standards and accepts consequences under uncertainty. He also names the failure mode this page tracks — requiring documented reasoning risks "the replacement of one compliance regime with another", since judgment as evidence "remains relational and situated rather than mechanically verifiable".

Evidence: how judgment develops, and what AI does to it

The knowledge base's collaborative and assessment literature supplies convergent evidence that evaluative judgment is *learnable*, *displaceable*, and *designable* — and that AI cuts both ways.

- **Comparison-based training measurably builds it.** In a 14-week study with 28 pre-service teachers, AI-generated strong, average, and weak exemplars anchored iterative comparison of students' drafts against reference points; evaluation focus expanded from surface language features to content, organization, and coherence — but the reasoning stayed thin, with example-based justification doubling while the most sophisticated comparative reasoning remained rare. Judgment can be scaffolded into existence; it does not appear on demand, and the quality of the reference points matters.
- **Feedback design decides whether agency survives.** A multisite, cluster-randomized field experiment with 1,176 first-year undergraduates across 48 sections compared four feedback conditions for scientific argumentation: peer-only, direct GenAI, reflective GenAI (self-evaluate then critique), and hybrid (self-evaluate + peer + GenAI). The **hybrid condition produced the largest argument-quality gain**; direct GenAI feedback risked passive uptake — students outsourcing evaluative judgment to the system — while reflective and hybrid designs preserved

epistemic agency by forcing the student to evaluate their own work first. The authors' core finding is that GenAI's educational value depends less on AI access than on whether the feedback environment preserves agency, judgment, and ownership during revision.

- **A feedback tool can scaffold judgment while teachers keep the relational part.** With 21 higher-education teachers using PolyFeed, the model surfaced omitted components (20 of 21 had skipped "Meeting Learning Objective") and 12 rewrote the ChatGPT text, clustering in the student–teacher relationship dimension (Aldino et al. (2026)).
- **Feedback source shapes which judgment dimension develops.** In a doctoral statistics case study, ChatGPT-4o gave procedural guidance but could not flag a wrong data file or a misapplied test, while peer dialogue caught the erroneous data in real time and forced justification of the method choice (Xie et al. (2025)).
- **Structured peer-and-AI review scales calibration.** The PAIRR model (Sperber et al., 2025) combines peer review with AI review and structured reflection, and was tested in the largest study of students' use of AI feedback to date (654 students, ten writing courses). It treats the *comparison* between one's own judgment, peers', and AI's as the training ground, positioning evaluative judgment as an explicit learning outcome rather than an implicit by-product.
- **AI feedback helps only when literacy already exists.** A conceptual framework from feedback-literacy leaders (Boud, Dawson & Yan) analyses feedback across eliciting, processing, and enacting, using two contrasting IELTS-with-ChatGPT cases: a student with low feedback literacy used a vague prompt, received generic output, and trusted or over-copied it, while a literate student used AI critically and learned. GenAI lowers the cognitive and emotional barriers to seeking feedback but can itself be hallucinated, biased, or generic — which is why teachers are argued to model evaluative planning and train judgment, not just prompting.
- **Sustainable judgment, not momentary feedback, is the gap.** A scoping review of authentic assessment (Zhan, Boud & Du) found AI-formative feedback abundant but **sustainable feedback** — transferable to future contexts — present in only 4 of 23 formative studies. Feedback that closes the current task while leaving the learner unable to judge future work is the evaluative-judgment failure in its clearest form.
- **Borrowed judgment: receiving an interpretation without practicing interpretation.** Åhman and Thorén (2026) name the failure mode this page treats as the learner's remaining work. Where a study tool generates the summary, the structure and the prioritization, the learner is served the *products* of reasoning while skipping the interpretive struggle that produces judgment — their "borrowed judgment". The distinction matters because it is not a question of output quality. An AI study tool can be fully cited to the student's own uploaded sources and still preconfigure relevance, so judgment is exercised only where the system requires the learner to take a position, confront competing interpretations, and explain their choice.
- **Critiquing generated drafts built the educators' judgment.** Paula et al. (2026) found that eight course coordinators' assessment literacy grew as they critiqued a GPT-4.1 tool's generated rubrics and timelines against disciplinary standards, while all eight refused end-to-end automation — the tool strengthened academic judgment rather than replacing it.

- **Assessment can be designed to reward judgment instead of output.** The response-region model formalizes why: redesign lowers the payoff from hidden outsourcing and raises the value of visible reasoning, explanation, and critique. Asking students to explain which AI suggestions they accepted and rejected turns the decision itself into assessable evidence.
- **The institution's own judgment lacks the criteria it asks students to meet.** Munoz et al. (2026) rated the probative value of 1,855 evidence items across 1,162 generative-AI misconduct allegations and found that evidence quality bore no reliable relationship to case outcomes, because no stage of the procedure set a minimum evidentiary threshold or required investigators to weigh probative value before progressing an allegation — panels weighed evidence through unstructured professional judgment. Detector output was the weakest category in that corpus (standalone detector outputs wholly low in credibility), and Hadra et al. (2026) show the instrument cannot establish the fact a finding asserts — macro accuracy of 0.69 and 0.61 across 192 texts, near-total failure on hybrid human–AI writing, and a borderline bias concern for EFL writers — which is why the authors' own recommendation is human judgment, clearer policy and better-specified tasks rather than surveillance. Better-specified matters twice over: Wright (2026) argues that rules written by platform identity rather than function are over-inclusive by definitional accident, sanctioning a student who did not do the thing the rule was designed to prevent, so the assessor's judgment has to be applied to what a tool did rather than to which platform was used. Judgment exercised without shared criteria cannot be taught, calibrated or audited — the consistency problem this page reports for students, arriving at the level of the institution. Evaluator judgment also carries a measurable direction of its own: five admissions officers separating 50 human from 50 AI admissions essays reached AUC 0.70 (95% CI [0.65, 0.75]), and their quality ratings fell as perceived AI-likelihood rose, an association that survived adjustment for machine-rated quality, actual provenance and applicant characteristics (−0.109, $p < .05$). Because nobody screened the submissions, that unaided judgment was the entire enforcement mechanism, and each flagged essay carried 1.5 percentage points less admission probability, 2.6 once essay quality was held constant (Isley, Gaebler and Goel 2026).
- **Classroom-level proxies for judgment are being proposed.** Austin (2026) adds two behavioral signals to a redesigned assignment sequence: the UnBlooms™ *Discernment Rate*, the share of AI outputs a learner interrogates, challenges or revises rather than accepts, and the *First-Pass Acceptance Rate*. Neither is validated — both are offered as cheap per-assignment diagnostics — but they make the construct observable inside ordinary grading, where a near-zero discernment rate across several assignments reads as a task-design signal rather than an individual deficit.
- **Judgment registers when wired to revision, not merely present.** In 67 pre-service teachers designing lesson plans with GenAI, explicit evaluation was near-absent in the lower-quality group (0.67 vs 0.00); what separated quality was a bidirectional evaluation–revision cycle (CE → RE $Z = 2.80$, RE → CE $Z = 2.50$) and a revision self-loop (RE → RE $Z = 4.24$) (Fang et al. (2026)).
- **Instructors' criteria can be externalized by revising AI output.** Tang et al. (2026) inferred reusable validation rules from 16 instructors' edits of LLM-generated programming feedback and raised alignment with their pedagogical intent from 57% to 91%, making tacit criteria inspectable rather than leaving them unstated.

How misuse displaces judgment

The clearest risk is displacement, and it is evidenced in the feedback literature rather than only theorized. When the tool supplies the rubric, the feedback, and the monitoring, the learner's metacognitive and evaluative practice is displaced rather than supported — the assessment becomes a performance of judgment the student never exercised, the same failure mode as cognitive offloading expressed in the assessment register. Direct GenAI feedback in the multisite experiment pushed toward exactly this passive outsourcing. Grading pressure compounds it: where self-assessment or reflection on AI use is itself graded, students can produce the reflection the rubric wants rather than the reasoning, so genuine judgment requires making the exercise consequential — a decision that shows up in later work, an oral explanation, or a documented rationale that is itself examined.

The same reasoning admits a structural version. Åhman and Thorén (2026) name **patterning** as the developmental work of organizing complexity into structures a learner finds meaningful, and argue that a system which pre-sorts relevance removes the conditions that work requires. Their term for the result is **borrowed judgment**: the learner appraises material the system already structured, so judgment is performed but never earned. The paper is a theoretical analysis with no data of its own — the Tentaklar platform illustrates the mechanism rather than testing it — so the failure mode is argued from design, not observed in learners.

Displacement has a teacher-side version, and it is what turned several writing professors against outsourcing marking entirely. Five of the twenty-four said marking is how a teacher comes to understand their learners, so delegating it costs that understanding rather than only the hours (Wu and Lam (2026)). Eighteen of the twenty-four treated human judgment as what catches the tool's errors and owns the accountability for them.

Implications for practice

- **State it as an outcome.** If appraising work quality — including AI output — is what matters, write it into the learning outcomes and assess it, rather than leaving it as a by-product of the task.
- **Assess the decision, not only the artifact.** Ask students to justify what they kept, changed, or rejected; this turns the thinking into evidence and makes substitution visible without surveillance.
- **Name the judgment routine.** O'Byrne's Agency Check — Credible, Relevant, Acceptable, Nuanced — asks whether output is accurate, fitting, serviceable, and carries stance and voice; in a semester-long study, final artifacts from the most and least judgmental students looked deceptively alike (O'Byrne, 2026).
- **Use exemplars and calibration deliberately.** Comparative judgment against strong, average, and weak exemplars is the mechanism the evidence supports, and AI makes generating those exemplars cheap — one of its clearest pedagogical uses.
- **Prefer hybrid and reflective feedback over direct output.** Self-evaluation before AI critique, or self + peer + AI, preserves the Learner Agency that direct AI feedback erodes; design the feedback environment rather than just adding a tool.
- **Build toward sustainable judgment, not momentary fixes.** Feedback that cannot transfer to the next task trains nothing durable.

- **Pair it with process and orals.** Process artifacts and short oral explanations show judgment in action where a final product cannot, which is a core reason AI-era assessment redesign relies on them.
- **Make retained judgment visible with comprehension-debt probes.** Mahmoud (2026) defines four cross-cutting obligations — explain, verify, modify, and account — that make retained competence visible at every level of AI integration, and proposes delayed change requests, code walkthroughs, independently designed tests, defect localization, and live debugging as probes that compare what was produced with what can later be demonstrated. Under agentic capability the assessment target moves to supervision — task contracts, permission boundaries, sandboxes, evaluation harnesses, diff review, rollback, and human accountability — shifting assessment from visible authorship toward visible judgment.

Common Misconceptions

- **"Evaluator error is random noise." Evaluator judgment carries a measurable direction of its own**: five admissions officers separating **50 human from 50 AI admissions essays** reached **AUC 0.70**, meaning they could distinguish the sources only weakly — and because nobody screened the submissions, that **unaided judgment was the entire enforcement mechanism**, with each flagged essay carrying **1.5 percentage points less admission** probability. A weak signal became a real penalty.
- **"Peer and AI review are substitutes."** The PAIRR model (Sperber et al., 2025) **combines peer review with AI review** to structure calibration. Combining them is the design, which implies neither alone supplies it.
- **"Judgment quality is a property of the judge."** The admissions finding locates the problem in the arrangement — an unvalidated judgment applied at consequence with no screening stage — rather than in the individuals' ability.

Connected Concepts

- Pedagogical Patterns — The appraisal step students perform on AI output inside these sequences
- AI in Education — AI in education (umbrella)
- Assessment Validity
- Feedback
- Feedback Literacy
- Formative Assessment
- Self-Assessment
- Authentic Assessment
- Academic Integrity
- Self-Regulated Learning
- Metacognition
- Critical Thinking
- Assessment

- AI Detection
- Learner Agency
- Higher Education

Connected Articles

- Assessing what matters most – the shifting value proposition of human-centred work in assessment practice — Human-centred assessment, assemblages and generative constraints (Elkington 2026)
- Generative artificial intelligence in writing assessment: University professors' perspectives and recommendations — Why writing professors refuse to outsource marking: it is how they learn their students
- Comparing ChatGPT Feedback and Peer Feedback in Shaping Students' Evaluative Judgement of Statistical Analysis: A Case Study — ChatGPT versus peer feedback as training grounds for different dimensions of evaluative judgment
- Unravelling undergraduates' development of evaluative judgments through AI-supported internal feedback — How AI-supported internal feedback develops evaluative judgments, and where reasoning stays thin
- Human-centered GenAI feedback design in higher education: A multisite experiment on direct, reflective, and hybrid approaches to scientific argumentation — Hybrid self/peer/AI feedback preserves agency and judgment better than direct AI feedback
- Peer and AI review + reflection (PAIRR): A human-centered approach to formative assessment — Peer-and-AI review with structured reflection as calibration at scale
- Generative artificial intelligence as an enabler of student feedback engagement: a framework — How feedback literacy governs whether AI feedback teaches or substitutes
- Designing for authentic assessment: a scoping review — The sustainability gap in AI feedback
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Evaluative judgment as one of the design strands replacing detection-led enforcement
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — Making visible reasoning and judgment the thing the rubric rewards
- Enhancing learner-centered feedback with AI: Teachers' practices and perceptions — Teacher evaluative judgment with AI feedback tools
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond detection: authenticity redesigned rather than policed
- Coauthorship integrity: Reconceptualising assessment validity for the age of generative artificial intelligence — Reconceptualizing assessment validity for the age of generative AI
- Epistemic dependence in AI-mediated learning — Contestability, recoverability, and the criteria separating reliance from dependence
- Rethinking AI-assisted writing instruction: feedback literacy scripts, calibration training, and student writing development — Feedback literacy for AI-assisted writing

- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- Educational integrity in GenAI-augmented assessment: making judgment visible — Judgment as the evaluative core of integrity: annotated decision trails, oral defense, version history (Sharma 2026)
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — Panels weighing evidence without codified standards: the institution's own judgment problem (Munoz et al. 2026)
- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Detector inaccuracy and hybrid-writing failure: human judgment as the recommended replacement for the verdict (Hadra et al. 2026)
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Function, not platform: judging what a tool did rather than what it is (Wright 2026)
- When AI Agents Can Complete the Assignment: Practical Strategies for Designing Tasks That Still Require Human Thinking — UnBlooms and the Discernment Rate: grading the reasoning trail behind AI-assisted work (Austin 2026)
- AI-written admissions essays are widespread but penalized — AI-written admissions essays are widespread but penalized
- Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education — Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education
- Co-constructing AI boundaries: Agency, judgment, and ethical literacy in AI-mediated meaning-making — the Agency Check (credible, relevant, acceptable, nuanced) that structures each AI interaction
- Judgment-Centred Software Engineering Education: A Post-Hype Review and Framework for AI-Augmented Learning — A Post-Hype Review and Framework for AI-Augmented Software Engineering Education
- Human–AI collaborative patterns in GenAI-supported instructional design among pre-service teachers: an analysis of interaction sequences and cognitive load — Judgment separated quality only when wired to revision (Z = 2.80 and 2.50)
- ValiAssist: Scaling LLM-generated Programming Feedback Validation by Demonstration — Instructors' revisions became reusable validation criteria (Tang et al. 2026)
- Processes of patterning: AI, literacy, and the epistemological challenge — Patterning removed from the task, and the judgment that gets borrowed

Feedback

> **Feedback** — information provided to a learner about their performance or understanding that is intended to close the gap between current and desired performance. In AI in education, feedback has become a central and rapidly transforming theme: AI systems now generate, deliver, and even teach students how to use feedback, reshaping every stage of the feedback process.

Questions to Consider

- Feedback is often imagined as information handed to a learner, but research argues it only 'counts' as feedback when the learner makes sense of and acts on it. If feedback is a relationship rather than a message, what changes about how we should deliver it?
- Students' perception of whether feedback came from an AI or a human can change how much they learn from it. Why do you think the *source* matters so much — and what does that imply for AI-generated feedback in your context?
- Immediate feedback can be a trap: the 'correct-answer trap' shows that students who simply copy corrections learn less. When does instant feedback help, and when does it short-circuit the very learning it's meant to support?
- Research even found that a well-designed sequence of feedback — encouragement, then hints, then the answer — designed to build autonomy actually *harmed* learning despite boosting engagement. If students feel good about feedback that makes them learn less, what should we optimize?
- Feedback is described as a system with parts: the feedback loop, quality of provision, the learner's uptake capacity, and the assessment context. If you were trying to improve feedback in your own course, which part would you fix first, and why?

Introduction

This is the umbrella concept for the knowledge base's feedback-related ideas. Feedback sits at the intersection of assessment and learning: without feedback, assessment measures performance but does not improve it; with effective feedback, assessment becomes a learning event. The knowledge base treats feedback as a **system** with multiple facets — the quality of the feedback itself (AI Feedback Quality), the loop through which it closes the learning gap, the learner's capacity to use it (Feedback Literacy), and the assessment contexts in which it operates (Formative Assessment, Peer Assessment, Automated Assessment).

- **Yilmaz et al.** show that students' perception of the feedback *source* (AI vs human) shapes self-regulated learning from GenAI feedback — a crucial qualifier for feedback effectiveness claims.
- **Nazaretsky et al. (2025)** isolate the source from the content: 472 EPFL students rated content-comparable human and GPT-4.0 feedback on their own work, first blind and then again after the source was disclosed, and most could not reliably tell the two apart (287 of 472 guessed correctly). Once the label was revealed, ratings of the AI variant fell and of the human variant rose — significantly for Genuineness ($p < .01$) — and provider credibility separated cleanly (human μ

= 3.28 vs. AI μ = 2.25, Cohen's d = 0.57). The bias attaches to the provider rather than the text, since the two variants were comparable on correctness and cognitive quality. Pérez-López et al. (2026) carry feedback credibility through to learning: among 230 business students after an AI-supported essay, credibility predicted perceived learning, with perceived competence and human-like empathy as its antecedents.

The feedback system

Feedback is best understood not as a single event but as a connected system of interacting parts, each of which the knowledge base documents as its own concept:

- **The feedback loop** — the mechanism through which feedback closes the gap between current and desired performance; the cycle of performance → feedback → revision → improved performance that drives learning.
- **AI Feedback Quality** — the accuracy, usefulness, timeliness, and pedagogical value of feedback generated by AI; the provision side of the system.
- **Feedback Literacy** — the capabilities and dispositions students need to understand, evaluate, and act on feedback; the uptake side of the system.
- **Formative Assessment** — the assessment context in which feedback is used to improve learning while it is still in progress, rather than merely to judge it.
- **Peer Assessment** — feedback exchanged between Learners, increasingly augmented by AI and a site for developing feedback literacy.
- **Automated Assessment** — AI-driven scoring and feedback, from automated essay scoring to confidence-aware short-answer grading.
- **The parts trade off against each other.** Designing feedback means choosing among usability, sources and sustainability rather than maximizing all three; Pedlow et al. (2026) treat sustainability as the pole that must not depend on any single individual, resource or institutional condition.

The feedback loop

The feedback loop is the cyclical process where AI systems assess student work, deliver feedback, observe the student's response, and adapt subsequent instruction. AI-mediated feedback loops operate at multiple timescales:

- **Immediate feedback:** Automated grading systems and AI tutors provide real-time correction during Problem Solving. Correct-answer trap research shows that immediate feedback can short-circuit learning if students simply copy corrections. Generating that immediate corrective feedback with LLMs inside a tutor is feasible but imperfect: across 6,926 logged transactions in the Apprentice Tutor College Algebra platform, Reddig, Arora & MacLellan (2025) found GPT-4 produced hints targeted to the student's specific error ~66% of the time, yet ~35% of hints were too general, incorrect, or prematurely gave away the answer, and LLM-based automated quality checks misaligned with human judgment — reinforcing that unvetted AI feedback in the immediate loop carries real short-circuiting risk.

- **Assignment-level feedback:** Formative Assessment systems and AI feedback quality research examine whether AI-generated assignment feedback improves subsequent work. Sequenced feedback studies test whether the order of feedback matters.
- **Course-level loops:** Learning analytics dashboards and educational platforms aggregate feedback across assignments to identify patterns and recommend interventions.

The effectiveness of a feedback loop depends on feedback quality — accuracy, specificity, timeliness, and actionability. AI peer feedback systems add a social dimension to the loop.

The human in the loop: feedback loops are not purely automated — teachers often mediate AI-generated feedback before it reaches learners. Studies of AI feedback tools for teachers (e.g., the PolyFeed tool combining an ML detector with an Large Language Models (LLMs) rephraser) find teachers use professional judgment to **accept, edit, or reject** AI suggestions — an "assist but verify" pattern — and systematically moderate exaggerated praise and generic suggestions to protect authenticity and voice. The **relational/affective dimension** of feedback (student–teacher relationship, encouragement) most strongly resists AI delegation, suggesting this part of the loop remains inherently human. This human-in-the-loop mediation connects to Human-in-the-Loop and to Teaching. - **The relational penalty is measurable, and separable from quality.** In a three-arm RCT with 287 writers, AI and instructor feedback raised revised-essay quality equally (d = 0.60 and 0.59), but instructor feedback raised intrinsic motivation through perceived relatedness (Liu & Shi (2026)).

Luo and Eaton's policy review sharpens the same point: only 14 of 50 top-ranked universities had specific guidance on teachers' AI use for feedback, and students described undisclosed AI feedback as "disingenuous", making transparency and consent preconditions of ethical practice rather than courtesies (Luo & Eaton (2026)).

LearnLens turns that mediation into a mechanism: it treats a teacher's edit as a signal of dissatisfaction rather than a correction, spending additional compute on deeper reflection instead of returning the fast answer, and its teachers' median time per assignment fell from 10–30 minutes to under five (Zhao et al. (2025)).

The relational reading cuts deeper than substitution. In workshops with 12 students and 18 educators, Bearman et al. (2026) found students treated AI as an additional but flawed source, weighing it against rubrics, lecture notes, discussion boards and educator comments, and using it as a holding pattern when human responses were slow; one pasted thin educator comments into a chatbot to work out what to do next. AI's presence changed relations rather than merely adding comments, to the point that one student stopped trusting peer discussion-board feedback as probably AI-written. The authors therefore propose humans-as-the-loop: people helping people build stronger feedback relationships over time, in place of oversight of machine output.

Winstone et al. (2026) reframe GenAI feedback as matters of care — an ethical, relational practice rather than information transfer — and name a safe-space paradox: the tool's reduced personal risk may forgo priming students for the friction of professional feedback encounters.

How AI transforms feedback

AI changes feedback in three consequential directions, each raising the stakes of the other facets:

- **Volume and immediacy.** AI can generate feedback instantly and at scale, dramatically increasing how much feedback students receive. Multi-site GenAI feedback studies and AI feedback in higher education document AI feedback experienced as comparable to teacher feedback in acceptability and supportiveness. A PRISMA-guided systematic review of 42 empirical studies (2023–2025) corroborates this scale benefit — LLMs can accelerate grading and deliver rapid, personalized feedback at scale, especially in large or higher-education cohorts — while cautioning that such feedback is sometimes too generic or misaligned with the assigned grade, and that reliability slips on longer, multilingual, or nuanced tasks (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback).
- **Personalization is a bias vector.** Holding eighth-grade essays constant, four LLMs over-praised and withheld critique for students marked by race, language, or disability — so which student attributes feed a feedback system is a fairness decision, not a neutral one (Tan, Phalen & Demszky (2026)).
- **Evaluation demands on the learner.** Because AI feedback can be inaccurate or hallucinated, students must judge whether to Trust and act on it. This is where Feedback Literacy and Trust Calibration become decisive: Mendoza et al. (2026) show that only feedback-literate students convert AI feedback into Self-Regulated Learning gains, while the LLM fallacy captures how students may over-credit AI feedback to their own competence.
- **Feedback literacy is built by use, not demographics.** In 486 EFL undergraduates, only frequency of AI tool use predicted AI feedback literacy ($\beta = 0.29$) — not major or year of study — so scaffolding access to AI-mediated feedback is an equity question as much as a design one (Liu & Deris (2025)).
- **Lab approval is not semester use.** All 18 students reacted positively to the GenAI explanation function in lab sessions, yet only half used it during the term, citing mismatch, irrelevance, and redundancy when educator feedback was already clear (Jin et al. (2025)).
- **Trust and care, not accuracy, bound uptake.** Seventeen EFL students granted an AI writing assistant high expertise yet doubted its trustworthiness over data handling and rated its goodwill lowest, authorizing it only for broad language concerns; several also found its volume of suggestions unmanageable (Serpil & Mor, 2026).
- **Task-level suitability: sorting feedback by epistemic status.** Venetsanos (2026) argues that the frameworks the field relies on — Hattie and Timperley's levels, Boud and Molloy's design principles — explain *where* feedback operates in learning but not whether a given feedback task involves rule-checking, factual verification, or interpretive judgment, and that it is the second distinction that decides whether automation is defensible. The proposed tripartite split is low-level structural and presentational feedback (formatting, referencing, grammar, sentence-level clarity — rule-based against explicit standards and safely automatable), intermediate-level factual and procedural verification (whether a calculation used a specified method correctly, whether a stated

fact matches authoritative references — comparison against established knowledge, not judgment of reasoning), and high-level critical evaluation and synthesis, where judgment is interpretive and must stay human. The levels are dimensions rather than a ladder: one calculation can be correctly presented, arithmetically wrong, and methodologically inappropriate at the same time, and can attract verification, process feedback and self-regulation feedback together. The framework's sharpest boundary case is clarity: sentence-level clarity is surface-level, but *argumentative* unclarity often signals incomplete conceptual grasp, so flagged instances should escalate to human review rather than being corrected as prose — fixing the writing would leave the actual problem untouched.

- **Role-aware feedback.** Yaşar et al. (2026) showed that prompting the same LLM to evaluate the same student artifact under different roles — instructor, peer reviewer, grant reviewer — produced qualitatively distinct feedback: instructors were encouraging and process-oriented, peers supportive and conversational, grant reviewers formal and outcomes-oriented. These differences were epistemic, not merely stylistic, foregrounding different aspects of design practice — evidence that role-aware prompting can generate role-sensitive evaluative feedback rather than a single generic response.
- **Feedback type matters more than feedback density.** An eight-week adaptive stochastics study (194 students) found directive, informative and transformative feedback were taken up differently, and transformative feedback contributed to cognitive overload — so feedback design should match type to the learner's phase rather than maximize volume (Mejeh & Fromm (2026)).
- **Feedback utility vs. evaluative authority.** AlGhamdi (2026) shows students can simultaneously accept AI-generated feedback as useful and reject AI as the appropriate grader — separating *feedback utility* (the informational value of surface-level feedback) from *evaluative authority* (who may decide the grade). In a transparent post-assessment design, Saudi computing students treated these as analytically distinct judgments, valuing ChatGPT's clarity for revision while reserving grading authority for the human instructor and articulating the dialogical, institutionally-weighted reasons why. The finding extends Feedback Literacy beyond judging feedback quality to reasoning about evaluative authority itself, and suggests transparency about AI involvement can make feedback an object of critical reflection rather than passive acceptance.
- **The revision's stance is an outcome, not just its quality.** Feedback research usually asks whether a revision improved the text. Zhao and Ji (2026) ask what rhetorical stance the revised text takes, coding 168 EFL argumentative essays with Appraisal Theory across first drafts, revisions after peer feedback, and ChatGPT-4 revisions of the same drafts. Engagement language was equally frequent in all three, but differently configured: peer-feedback revisions became more contractive (more Counter and Endorse, less Entertain), while the AI revisions kept a more balanced Contract/Expand mix. Neither is better writing — the point is that the two revision routes leave the argument in a different dialogic position, which makes stance itself something a feedback conversation can name and a writer can choose.
- **An explanation can be persuasive and still unfaithful.** Bueno et al. (2026) found that removing the sentences an LLM rationale ranked most influential barely moved a rubric score, while SHAP-

selected sentences shifted it reliably and transferred across model families, so a fluent justification is not evidence that a score rests on it.

- **Feedback literacy as a training goal.** Rather than only providing feedback, AI tools are increasingly designed to *teach* students to use feedback — reframing automated feedback tools as literacy-building instruments, framing GenAI as an enabler of feedback engagement, and using GenAI critique tasks to build psychological, feedback, and AI literacies together.
- **Feedback literacy and calibration are separable levers.** With 120 undergraduates, a Feedback Literacy Script (Filter–Reason–Act–Check) raised writing quality, effective uptake, and deep revision, an Assessment-Performance Calibration Activity improved self-assessment accuracy and cut overconfidence, and combining them produced the largest writing gains and the strongest retention after AI support was withdrawn (Dai (2026)).
- **Clarity is not effectiveness.** LLM-rewritten Python error messages were rated significantly more readable and less cognitively demanding than standard interpreter output, yet produced no significant gain in fix rate, attempts, or time-to-fix (Moraru, Biswas & Gadiraju (2026)).

What makes feedback effective: calibration evidence

Ngai & Gilbert (2026) provide a clean experimental result on feedback design with direct relevance to AIED: **veridical, immediate, trial-by-trial feedback tied to a learner's own prior prediction is what changes behavior — prediction or beliefs alone are not enough**. In their four-group design, feedback combined with a preceding performance prediction improved calibration and behavior, while predictions without feedback did nothing, and adding an explicit over-/underconfidence label added nothing further. LLMs can also serve as calibration partners in this process: Yaşar et al. (2026) found that after rubric refinement, LLMs demonstrated greater consistency than some human raters in applying performance thresholds — useful for norming sessions and formative peer feedback environments, where the model helps calibrate evaluative judgment rather than replace it. This aligns with the knowledge base's feedback-system view: feedback's power lies in closing the gap against a learner's *own* estimate (the provision–uptake pairing), and effective feedback should be immediate, accurate, and explicitly connected to what the learner predicted — a design principle for AI feedback systems and Feedback Literacy training alike.

Effort, however, is not automatically the missing ingredient. In a preregistered between-subjects experiment with 302 US adults learning introductory Python, Asher, Gold & Carvalho (2025) paired personalized Claude Sonnet 3.5 explanatory feedback with a structured three-step self-explanation prompt — for each incorrect code section, what the correct code does and why the learner's own attempt failed — and the added reflection bought nothing. Reflective Practice participants spent 4.1 minutes reviewing feedback against 2.1 minutes in plain Practice ($t(267) = 11.30$, $p < .001$), which left room for only 2.0 practice problems instead of 3.4 ($t(267) = 8.20$, $p < .001$). Each problem was worth the same either way (Reflection × problem-number OR = 1.03, $z = 0.23$, $p = .486$), so Practice ended with higher mastery, 79% versus 65% ($d = .41$), and never fell behind on near-transfer, far-transfer, or code-evaluation items. Reflection also failed to deliver the metacognitive benefit it targeted: judgments of learning did not differ across arms, and the practice conditions were better calibrated (underconfident by 11 points, against video watchers 20 points overconfident, $d = -.93$) and reported less distraction ($d = -.80$) than reflective learners, whose reflections averaged only 35 words. The authors' reading is that the AI feedback had already supplied the Scaffolding

that self-explanation normally adds — a message that names the error, explains the correct approach and describes the underlying concept leaves little for a reflection prompt to do. Writing reflections while still learning unfamiliar syntax also competed directly with the varied repetition that builds transferable skill. This locates a boundary condition for Desirable Difficulties and Productive Failure on the processing-depth axis: effort pays when it drives additional retrieval, application or comparison, and is redundant when the learner is already receiving a personalized explanation of their specific error. It also bears on how feedback quality interacts with uptake. The more elaborated and targeted the feedback, the narrower the space for an added layer to add value, which shifts design attention from deepening one episode to spending scarce practice minutes on volume, problem variability, and timing reflection to moments such as a detected plateau. The study tested a single unvetted enhancement, and the authors note that these variants remain open.

- **Focus and adaptivity are separable dimensions of feedback.** Annotation of teacher and LLM comments in three university writing courses with seven feedback focus types shows that most models cover nearly every type while none matches the teacher's distribution across them, and none shifts its focus across draft stages the way an expert instructor does (Almousa et al., 2026).
- **Aggregate gains can hide offsetting shifts.** Three months of WISE Agent feedback with 260 Chinese sixth-graders moved no total critical-thinking disposition score ($t=-0.854$, $p=0.394$), yet Truth-seeking rose ($p<0.001$) while Cognitive Maturity fell ($p=0.019$) — a dip the authors read as students recalibrating overestimated understanding. (Zhu et al. (2026))

Feedback across assessment contexts

The knowledge base's feedback research spans the full range of assessment contexts, each with distinct feedback dynamics:

- **Formative feedback** is the canonical site of feedback-for-learning — formative assessment feeds self-regulated learning through feedback that arrives while learning is still in progress (automated formative assessments, feedback enactment).
- **Summative feedback** is the feedback attached to summative assessment — end-of-unit tests, oral exams, and proctored/closed-book examinations. In the AI era, the summative setting is where AI resistance matters most (see Summative Assessment): feedback on a proctored oral exam or closed-book assessment tests genuine learning, whereas feedback on AI-assisted homework can be inflated. Oral assessments reframe the feedback moment as a live, interactive dialogue — feedback becomes immediate, conversational, and inseparable from the assessment itself, which is precisely why they resist AI substitution.
- **Peer feedback** adds a social layer — peer feedback develops feedback literacy and is increasingly AI-augmented (AI peer feedback, GenAI in EFL peer feedback). Yet peer feedback is only as good as its actual delivery: in a semester-long field experiment, under two-thirds of students assigned peer feedback received no textual feedback at all, and much of what was delivered was non-targeted praise — so when individual GPT-4 feedback replaced unreliable peers, students sustained the highest participation and posted the largest content learning gains (Geschwind et al., 2026), evidence that the AI's edge is a *reliability* advantage rather than inherent superiority.

- **Prompt scaffolding turns GenAI into a feedback facilitator.** Chang et al. (2026) found that students given structured prompts (context, objective, role) for peer feedback produced more explanations and suggestions, and only that group excelled on rebuttal data and on addressing the opposing view.
- **Automated feedback** scales delivery — automated scoring and feedback from essay scoring to short-answer grading. Arthur (Yin et al. 2026) extends this to unstructured quantitative problems: a per-question XGBoost diagnosis backbone infers rubric-labeled mistakes from students' submitted numerical answers to Engineering Economics Calculated Formula Questions and turns them into natural-language feedback, while a dialogue-based scheme requests intermediate answers only when confidence is low — balancing feedback accuracy against the collection burden on students.
- **Automated writing evaluation is a delivery-side tool with a measurable cost.** A review of 50 empirical studies (2019–2024) found that automated writing evaluation improved grammar, punctuation and sentence construction in 25 studies and reduced teachers' mechanical correction workload in 15, freeing time for argument, coherence and organization. Gains held only where the tools sat inside structured drafting and revision cycles rather than as stand-alone aids. Heavy reliance on them was linked to weaker critical thinking and Creativity, and the tools reproduced standardized English norms that EFL users reported as misaligned with their rhetorical traditions (Gres et al., 2026).

A key cross-context insight is that **the reliability of feedback depends on the integrity of the assessment it is attached to**: feedback is only as trustworthy as the measure it responds to. In the AI era this pushes educators toward authentic and AI-resistant summative formats where the feedback a student receives reflects genuine learning rather than AI-assisted output.

The "assessment for learning" paradigm reframes feedback as an overarching philosophy rather than a component. Mesny, Roberge-Maltais & Galy (2026) synthesize the wider higher-education literature to frame formative, ongoing, and individualized feedback as central to that philosophy, balancing formative with summative purposes and foregrounding student agency, self-AI Regulation in Education, and metacognitive skill. They note, however, that in management education feedback-rich practices remain unevenly adopted: self- and peer-assessment (a site of peer feedback) dominate the literature, while reassessment — which uses feedback-driven second chances to improve learning — is virtually absent.

- **Demonstrated actionability is not enacted actionability.** In a scoping review of 421 studies applying NLP to open-ended student evaluation of teaching comments, 61.3% produced output at the level of a demonstrated result or stronger, but only 11.6% showed evidence that intended users evaluated or used it (Eicher & da Silva, 2026).

The provision-uptake pairing

The knowledge base's core feedback insight is that **feedback quality and feedback literacy are two sides of one system**: high-quality feedback is inert without a literate recipient, and a literate student gains little from poor feedback. AI Feedback Quality covers the provision side (is the feedback accurate, timely, actionable?), while Feedback Literacy covers the uptake side (can the student judge and act on it?). The feedback loop is what connects them — the mechanism by which quality feedback, received by a literate

learner, closes the gap. Designing effective AI feedback therefore means designing both the system and the student.

Which student-side capacities matter is empirically separable: among 1,507 secondary students who each received one standardized automated feedback message on an argumentative text, only behavioral engagement with feedback and instrumental attitudes towards it predicted revision performance — students at the 75th percentile on either dimension improved by about 0.10 or 0.11 WLE points more than comparable students at the 25th, roughly the 46th to the 54th percentile — while global receptivity, cognitive engagement and experiential attitudes were unrelated to it and perceived usefulness mediated no dimension's path to performance. Usefulness worked on the other outcome instead: global receptivity's effect on situational interest ran entirely through perceived usefulness (indirect $\beta = 0.09$, 95% CI [0.06, 0.13]), so revision gains tracked durable habits of acting on feedback while interest tracked the appraisal of a particular message. (Automated feedback on argumentative writing: The role of secondary students' feedback receptivity and feedback perception)

A source can differ in how it calibrates, not how well it scores: in a randomized experiment, chain-of-thought AI feedback outscored an experienced teacher on rubric quality yet produced no greater revision gains, while the teacher's feedback stayed calibrated across drafts and GenAI feedback tracked the strength of the initial essay (Farrokhnia et al. (2026)).

A two-layer model shows how the pairing can be organized around a machine without delegating judgment to it. In El Khoury and Ma's worked example, an agent produces a draft rubric-based evidence report on each transcript with every rating tied to quoted excerpts, and the instructor then reviews the report, leads a debrief and decides what the evidence means for that student — a division the authors summarize as the AI organizing evidence while the instructor interprets it. Their claim about uptake is appraisal-based: feedback and iteration outside the social hierarchies students navigate with peers and instructors are easier to attempt, and rehearsal at the student's own pace is what they argue turns occasional confidence into a settled habit of engaging with feedback.

Why feedback matters for AI in education

Feedback is one of the most consequential and best-evidenced mechanisms in education, and AI both amplifies and complicates it. Well-architected AI feedback can match or exceed human feedback and scale across cohorts, but it demands new learner capabilities (Feedback Literacy, AI Literacy) and carries risks (uncritical acceptance, Over-Reliance). As AI-generated feedback becomes ubiquitous, the knowledge base frames feedback as a whole system — quality, loop, literacy, and assessment context working together — rather than as any single component.

- **Feedback can target the feedback-giver.** Tutor training is an under-explored feedback context: automated systems that sequence-label tutors' open-ended responses to flag praise types (effort-based praise — the desirable process-focused kind — vs. outcome-based vs. person-based, the least desirable trait-attributing kind) can deliver explanatory feedback that changes tutoring behavior. The binding constraint is expert-labeled data. An augmentation approach — GPT-4o generates synthetic labeled responses expanding a 13-instance low-resource set to 520, then fine-tunes GPT-3.5 — recovers most of the gap: F2 +20.5% on effort-based praise, +17.3% on outcome-based, and +16.5% on the *unseen* person-based category. The generalization test to an

unseen praise type is the validity check that separates this from overfitting, and the mechanism is closer to teacher-model distillation than classical augmentation. (Improving automated feedback systems for tutor training in low-resource scenarios through data augmentation)

- **Feedback that cannot see the revision gets repeated.** In a science learning game whose agents critiqued draft arguments, students revised across multiple rounds, but a quantized 8B model returned substantially the same critique to an improved draft, so the loop that motivated revision also produced the frustration that ended it (Humburg et al., 2025).
- **"Tone is a detail of feedback quality."** In the benchmark it tracked the number it was given: every model, told a grade that contradicted the work, wrote feedback whose tone followed that grade, and for **eight of 22** the shift per point matched or exceeded the shift with the work's quality. Only the tone rule was validated against trained annotators, on **1,655** tutor replies, so substance is unmeasured. A grader that writes feedback from a wrong grade launders the error into praise or criticism.

Feedback can be built from the process rather than the product. In Xian et al. (2026) one arm received personalized visualizations of its own keystroke and screen activity with structured reflection, while the other received written instructor comments on accuracy, clarity and editorial quality. The process arm gained 5.64 points on a blind 0-100 editorial rating against 1.91 for the product arm, with a Group by Time interaction ($F(1, 20) = 4.94$, $p = 0.038$, partial eta squared 0.198) and the control arm's own gain not significant ($p = 0.123$). Eleven students per arm means the direction is the finding, not the size.

Common Misconceptions

- **"Students cannot tell AI feedback from human feedback."** They can, and the label changes the judgment: **once the label was revealed, ratings of the AI variant fell and of the human variant rose — significantly for Genuineness ($p < .01$)**. Provider credibility shaped the evaluation of identical-style feedback.
- **"Lab approval predicts semester use." Lab approval is not semester use**: **all 18 students** reacted positively to the GenAI explanation function in lab sessions, **yet only half used it during the term**. The intention-usage gap is the design problem.
- **"Immediate corrective feedback is solved with LLMs."** Generating it inside a tutor is **feasible but imperfect**: across **6,926 logged transactions** in the Apprentice Tutor collection, the feedback was good enough to deploy and not good enough to assume correctness.

Connected Concepts

- Pedagogical Patterns — Tested feedback sequences, including why higher-quality AI feedback produced no more revision
- E-Portfolio
- AI Feedback Quality
- Feedback Literacy
- Formative Assessment
- Summative Assessment

- Peer Assessment
- Self-Assessment
- Automated Assessment
- Assessment
- Authentic Assessment
- Assessment Validity
- Self-Regulated Learning
- AI Literacy
- Scaffolding
- Writing
- Reflection

Connected Articles

- SciStory: Designing AI-Supported Inquiry in Science Learning Games — Agent feedback that repeated itself across revisions (Humburg et al. 2025)
- Automated feedback on argumentative writing: The role of secondary students' feedback receptivity and feedback perception — Automated feedback on argumentative writing: The role of secondary students' feedback receptivity and feedback perception
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Student perspectives on transparent AI-assisted writing assessment (AlGhamdi 2026)
- Who grades best? Comparing ChatGPT, peer, and instructor evaluations across varying levels of student project quality — Comparing ChatGPT, peer, and instructor grading across project quality levels (Usher & Faraon 2026)
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Layer-sensitive cognitive offloading in GenAI-assisted writing (Chen 2026)
- Fostering self-regulated learning through adaptive learning technology: A differentiated perspective on the role of feedback
- Generative AI offers more, but students revise less: comparing the effects of teacher and AI feedback on student essay revisions — Teacher vs. GenAI feedback: students revise less with AI
- Supporting self-regulated learning through generative AI feedback in online higher education: the importance of student perceptions of the source of feedback — GenAI feedback and self-regulated learning: perceived source matters
- Leveraging generative AI to facilitate peer feedback in collaborative argumentation learning — GenAI-assisted peer feedback in collaborative argumentation
- Is It Ethical for Teachers to Use AI for Student Feedback? — Ethics of AI in student feedback

- Metacognitive training facilitates optimal cognitive offloading — Metacognitive training facilitates optimal cognitive offloading (Ngai & Gilbert 2026)
- AI feedback literacy in higher education: Understanding, measuring, and predicting student feedback uptake — AI Feedback Literacy scale and uptake prediction (Liu & Deris 2025)
- Generative artificial intelligence as an enabler of student feedback engagement: a framework — GenAI as enabler of student feedback engagement (Zhan, Boud, Dawson & Yan 2025)
- Making sense of AI feedback: how students' feedback literacy moderates the link between ChatGPT acceptance and self-regulated learning — Feedback literacy moderates AI feedback → SRL (Mendoza et al. 2026)
- Rethinking AI-assisted writing instruction: feedback literacy scripts, calibration training, and student writing development — Feedback literacy scripts for AI-assisted writing (Dai 2026)
- Students' Perceptions of Generative AI-Powered Learning Analytics in the Feedback Process: A Feedback Literacy Perspective — GenAI learning analytics in feedback (Jin et al. 2025)
- Reconnecting relationships through technology: Developing feedback literacy capabilities through an AI automated feedback tool — AI automated feedback tool for feedback literacy (Tubino & Adachi 2025)
- Positioning generative AI in EFL peer feedback: Training feedback literacy and enabling uptake in speaking classes — GenAI in EFL peer feedback for feedback literacy (Irwin & Muller 2026)
- Artificial intelligence and feedback in university education: effectiveness and student perceptions — AI-generated feedback in higher education
- The care-full craft of feedback in an age of generative AI — Care-full feedback design with GenAI
- How artificial intelligence transforms the feedback ecosystem in higher education — The feedback ecosystem in higher education: AI reworks feedback relations, and humans as the loop (Bearman et al. 2026)
- Enhancing learner-centered feedback with AI: Teachers' practices and perceptions — Learner-centered AI feedback practices
- Human-centered GenAI feedback design in higher education: A multisite experiment on direct, reflective, and hybrid approaches to scientific argumentation — Multi-site GenAI feedback design
- Using AI-Generated Feedback to Improve Critical Thinking and Writing Proficiency — AI feedback and critical thinking in writing
- Using generative AI to promote psychological, feedback, and artificial intelligence literacies in undergraduate psychology — GenAI assessment builds psychological, feedback, and AI literacies
- LearnLens: LLM-Enabled Personalised, Curriculum-Grounded Feedback with Educators in the Loop — LearnLens: curriculum-grounded feedback with educator oversight (Zhao et al. 2025)
- Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning — Sequenced AI feedback studies
- AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education — AI peer feedback systems
- The Effect of High-Frequency, Automatically-marked Formative Assessments on Student Outcomes in A-Level Sciences — Automated formative assessments in A-level sciences

- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant assessment
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: bias in automated writing feedback
- From scoring to explanations: Evaluating SHAP and LLM rationales for rubric-based teaching quality assessment — SHAP vs LLM rationales for rubric-based teaching feedback
- Beyond the Traceback: Using LLMs for Adaptive Explanations of Programming Errors — LLM adaptive explanations of programming errors
- Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study — Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design
- GPT-4 feedback increases student activation and learning outcomes in higher education
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models
- Arthur: An artificial intelligence powered teaching assistant system for Engineering Economics class
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- A Tripartite Feedback Framework for AI-Assisted Assessment of Complex Reports in Higher Education — Tripartite framework: sorting feedback by epistemic status and the five boundary principles for AI involvement (Venetsanos 2026)
- Benefit or Bottleneck? Assessing the impact of structured reflection on learning from AI-driven explanatory feedback — Benefit or bottleneck? Structured reflection on AI explanatory feedback (Asher, Gold & Carvalho 2025)
- Bounded reliance: A source credibility perspective on EFL students' engagement with AI-generated writing feedback — Bounded Reliance: A Source Credibility Perspective on EFL Students' Engagement with AI-Generated Writing Feedback
- From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning — From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing
- From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026 — From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026

- Who Gives Feedback Matters: Student Biases Towards Human and AI-Generated Formative Feedback — Who gives feedback matters: source labels shift ratings when the text is held comparable (Nazaretsky et al. 2025)
- AI-Powered Feedback System for Writing: A Review of Automated Writing Evaluation (AWE) Tools — AI-Powered Feedback System for Writing: A Review of Automated Writing Evaluation (AWE) Tools
- Human-written and AI-generated revisions: An appraisal analysis of dialogic positioning in argumentative writing — What a revision does to the writer's stance: peer feedback turns argumentative essays more contractive, AI revision keeps the Contract/Expand balance (Zhao & Ji 2026)
- Improving automated feedback systems for tutor training in low-resource scenarios through data augmentation — Improving automated feedback systems for tutor training in low-resource scenarios through data augmentation (Xu et al. 2025)
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)
- Trade-offs in assessment and feedback design: a trilemma-based model — Names the trade-off among usability, sources and sustainability, making sustainability a design pole
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- As effective as the teacher, but less motivating: A randomized controlled comparison of AI-generated and teacher feedback on students' writing performance and intrinsic motivation — AI and instructor feedback equal on revision quality, unequal on motivation (Liu & Shi 2026)
- Process visualization feedback in news translation: a controlled intervention study of human-AI interaction using multimodal process data - feedback generated from keystroke and screen traces outperformed written product comments, 11 per arm

Connected FAQs

- What Are Best Practices for Developing an Effective AI Tutor?
- How Can AI Help Me Give Better Feedback at Scale?

Feedback Literacy

> **Feedback literacy** — the capabilities and dispositions students need to understand, evaluate, and act on feedback to improve their learning. It is the learner-side counterpart to feedback provision: whereas AI Feedback Quality and Feedback Loop concern the quality and mechanics of the feedback system, feedback literacy concerns the learner's capacity to seek, make sense of, judge, and use feedback productively.

Questions to Consider

- Well-designed feedback only helps students who can interpret and act on it. If two students receive identical feedback and learn different amounts, where does the difference live — and is it the student's fault or the system's?
- Research finds that students with stronger feedback literacy benefit more from AI feedback, while weaker-literacy students show minimal or even negative effects. What does that suggest about simply adding AI feedback to a course without also building students' capacity to use it?
- Feedback literacy includes seeking feedback, making judgments, managing affect, and acting on feedback — not just receiving it. When did you last *seek out* feedback rather than wait for it, and what made you brave enough (or not) to do so?
- If AI can now generate abundant, instant feedback, has the bottleneck shifted from feedback provision to the learner's ability to use it? What might change about how you design feedback if you saw students' feedback literacy as the real constraint?

Introduction

Feedback literacy matters because well-designed feedback only helps students who can interpret and act on it. A student who cannot evaluate whether AI-generated feedback is accurate, or who does not know how to turn feedback into a concrete revision, learns far less from the same feedback than a more feedback-literate peer. As AI reshapes feedback provision, feedback literacy has become a central boundary condition for whether AI feedback improves learning.

What feedback literacy is

Feedback literacy is widely framed as a set of interrelated capabilities — the capacity to appreciate feedback, make judgments, manage affect, and take action (after Carless & Boud). The knowledge base's articles cluster feedback literacy around several capabilities:

- **Seeking and eliciting feedback** — proactively requesting feedback rather than passively receiving it.
- **Making judgments** — evaluating the accuracy and usefulness of feedback, including feedback produced by AI.

- **Sense-making** — interpreting feedback in relation to task goals and criteria, and understanding what it implies for improvement.
- **Managing affect** — engaging productively with feedback without being discouraged or over-inflated by it.
- **Acting on feedback** — translating feedback into concrete revisions or changes in approach (Feedback Loop, Self-Regulated Learning).
- **Judging evaluative authority** — a further capacity proposed by AlGhamdi (2026): alongside appreciating feedback, making judgments, managing affect and taking action, students reasoning about AI-produced feedback needed to judge *which source holds evaluative authority*, separately from judging feedback quality. Because participants were told ChatGPT generated both score and feedback, their feedback literacy was exercised on the source and legitimacy of the evaluation, not only its content, and it produced demands for instructor validation rather than passive acceptance.

How feedback literacy appears in the research

- **Feedback literacy as a moderator of AI feedback value:** Mendoza et al. (2026) show that feedback literacy moderates the link between ChatGPT acceptance and Self-Regulated Learning: students with stronger literacy perceive greater SRL benefit from AI feedback, while weaker-literacy students show minimal or even negative (Over-Reliance) effects. Feedback literacy is a boundary condition for whether students can "make sense of" AI feedback.
- **Feedback literacy as the pathway from GenAI use to critical thinking:** in 421 Chinese undergraduates, GenAI use's association with self-reported critical thinking ran almost entirely through GenAI feedback literacy (β=0.185, 71.98% of the total effect), and that pathway strengthened as reflective thinking rose (index of moderated mediation = 0.030) (Yan et al. (2026)).
- **Feedback literacy predicts learning from AI-assisted writing:** Hawkins et al. (2026) find that feedback literacy was the only significant positive predictor of essay grade in an AI-enhanced essay-writing task, while Liu & Deris (2025) develop and validate an AI Feedback Literacy (AIFL) scale and show it predicts feedback uptake.
- **The literacy–engagement loop runs both ways.** A three-wave random-intercept panel of 399 Chinese undergraduates found AI feedback literacy predicting later agentic engagement (β = 0.222) and the reverse path just as strong (β = 0.263), with a Wald test unable to separate their sizes (Xu (2026)).

A rival disposition: reward sensitivity. Grade-based reward sensitivity weakened the credibility–perceived-learning link for Pérez-López et al. (2026) (simple slopes 0.733, 0.607 and 0.483 at low, mean and high sensitivity), locating students' instrumental orientation to marks where feedback-literacy research locates a cultivable disposition to use feedback. - **Comprehension, not actionability, carried the revision payoff.** Across three writing-feedback-revision cycles in two intact classes of 48 students each, comprehension was the dimension most associated with revision quality (r = 0.501), ahead of actionability (r = 0.480) and

diagnostic accuracy (r = 0.445); an interpretation sheet read before independent revision is what the diagnostic condition added (Yao & Fan (2026)).

- **Frameworks for GenAI-enabled feedback engagement:** Zhan, Boud, Dawson & Yan (2025) (Boud and Dawson are leading feedback-literacy scholars) argue GenAI can *enable* student feedback engagement, mapping a cyclical self-AI Regulation in Education feedback model onto the eliciting/processing/enacting phases.
- **AI feedback arrives without the teacher's framing:** Brunnström and Palmqvist (2026) argue that GenAI makes feedback literacy *more* demanding, because responses are generated interactively and without a teacher's immediate framing: students must interpret, evaluate, engage with and use them — including deciding when a response is too abstract, when to persist, and when to return to conventional resources. Across their eight-exchange demonstration, simplification and usable structure appeared only after learner interventions, making the eliciting/processing/enacting cycle of feedback engagement something the student has to drive (Zhan, Boud, Dawson & Yan mapped that cycle for GenAI; Self-Regulated Learning).
- **Feedback literacy in AI-assisted writing and EAP:** Feedback literacy scripts and second-rater mechanisms train students to engage critically with AI feedback during writing revision, shifting revision toward argument-level improvement rather than surface edits.
- **Automated feedback tools for literacy development:** Tubino & Adachi (2025) argue AI automated feedback tools should be reframed as instruments for *developing* students' feedback literacy, not just providing more feedback.
- **Peer feedback and feedback literacy:** Irwin & Muller (2025) position GenAI within EFL peer feedback to train feedback literacy and enable uptake in speaking classes, and scaffolding studies compare GenAI vs. human peers in fostering self-regulated feedback.
- **Feedback stored as durable, consultable data.** Pairing ChatGPT with an e-portfolio raised speaking performance and feedback literacy together (partial $\eta^2 = 0.218$ for the latter), as students treated archived feedback from lecturer, peers, and AI as data to reconcile rather than a one-off correction (Laksana et al. (2026)).
- **Feedback literacy in learning analytics and GenAI dashboards:** Jin et al. (2025) examine how students perceive GenAI-powered Learning Analytics feedback from a feedback-literacy perspective.
- **Feedback literacy as a goal of AI-literacy and assessment design:** Richmond & Nicholls (2025) use a process-over-artifact assessment in which students critique ChatGPT output against a rubric to build feedback, psychological, and AI literacies together; learner-centered AI feedback and care-full feedback design link feedback quality to the learner's capacity to engage.
- **Feedback literacy can be taught, and AI can supply the practice material.** A conceptual guide has instructors generate a graded spectrum of AI work samples — meeting all, some, and none of the criteria — then lead students through modeled critique, guided class analysis, and independent evaluation (Pennington and Hock (2026)).

Why feedback literacy matters for AI in education

AI changes feedback in two directions that both raise the stakes of feedback literacy. First, AI dramatically increases the *volume and immediacy* of feedback (AI Feedback Quality, Feedback Loop), so students confront far more feedback they must triage and evaluate. Second, AI-generated feedback carries distinct risks — inaccuracy, hallucination, and the "illusion of mastery" — that demand critical evaluation skills and vigilance against Over-Reliance and misattribution. Feedback literacy therefore becomes a core component of AI Literacy: knowing not only how to prompt an AI for feedback, but how to judge whether the feedback is worth acting on and how to convert it into genuine learning rather than task completion.

Bearman and colleagues (2026) add a further demand to that list. In their workshop study, students were not managing one feedback source but a network: they weighed educator comments against AI output, rubrics, course materials and peers, and when human feedback was slow they kept working with AI as a holding pattern, revising later if it had misled them. The authors suggest students can act as their own human-as-the-loop by managing those relations from the granular task to the broader trajectory, which is itself a feedback-literacy capability. Their warning is that thin or late educator comments are what push students toward unverified sources.

Connections to related concepts

Feedback literacy connects to AI Feedback Quality and Feedback Loop (the provision side it complements), Formative Assessment (the assessment cycle it feeds), and Self-Regulated Learning (the Self-Assessment and adaptation it supports). It is a subset of AI Literacy when applied to AI-generated feedback, intersects with Peer Assessment in collaborative contexts, and is particularly consequential for Writing. It also connects to Metacognition and Trust Calibration — the ability to judge whether feedback is trustworthy.

Acting on feedback is not the same as improving the artifact. Among 22 pre-service mathematics teachers, selective acceptance of AI and peer feedback was the norm (32 of 44 episodes), yet only five improved their designed-task quality — a translation gap the authors attribute to evaluative judgment rather than uptake (Oh, 2026).

Wang and Guo (2026) treat feedback literacy as developable through practice: EFL peer reviewers who worked dialogically with generative AI to generate comments improved their own capacity to judge and use feedback, not merely the comments they delivered.

Common Misconceptions

- **"AI feedback improves critical thinking directly."** In **421 Chinese undergraduates**, GenAI use's association with self-reported critical thinking **ran through feedback literacy**. The literacy is the mediator, so an intervention that adds AI feedback without building the capacity to read it addresses the wrong term.
- **"Literacy is a precondition, not an outcome."** A **three-wave random-intercept panel of 399 Chinese undergraduates** found AI feedback literacy predicting **later** agentic engagement (**β = 0.222**), so the loop runs both ways. It is dynamic rather than a gate to pass once.
- **"Actionability is what makes feedback change writing."** Across three writing-feedback-revision cycles in **two intact classes of 48 students each**, **comprehension was the dimension**

that carried the revision payoff. Feedback a student cannot parse is not improved by making it more actionable.

Connected Concepts

- Pedagogical Patterns — The critical-appraisal steps these sequences build into the workflow
- E-Portfolio
- AI Feedback Quality
- Feedback
- Formative Assessment
- Self-Regulated Learning
- AI Literacy
- Peer Assessment
- Self-Assessment
- Writing
- Metacognition
- Trust Calibration
- Cognitive Offloading
- Higher Education
- Reflection

Connected Articles

- Within-person reciprocal processes between AI feedback literacy and agentic engagement: a three-wave random-intercept cross-lagged panel study — AI feedback literacy and agentic engagement: a three-wave random-intercept panel (Xu 2026)
- Using AI to Build Student Feedback Literacy and Leverage Assessment as a Learning Tool — Generating rubric-graded work samples to teach feedback literacy (Pennington & Hock 2026)
- Translating AI and peer feedback in sustainability-oriented STEM teacher education: pre-service mathematics teachers' uptake, revision, and modeling task-design quality — Selective uptake without artifact improvement: the feedback translation gap (Oh 2026)
- AI-interaction literacy: reflections on how generative AI might be used to support self-regulated learning in higher education — AI feedback without teacher framing raises the feedback-literacy bar (Brunnström & Palmqvist 2026)
- Aligning ChatGPT with e-portfolio assessment as EFL learning model: its effect on students' speaking performance and feedback literacy
- Making sense of AI feedback: how students' feedback literacy moderates the link between ChatGPT acceptance and self-regulated learning — Feedback literacy moderates AI feedback → self-regulated learning (Mendoza et al. 2026)

- Summarise, elaborate, try again: exploring the effect of feedback literacy on AI-enhanced essay writing — Feedback literacy predicts essay grade in AI-enhanced writing (Hawkins et al. 2026)
- AI feedback literacy in higher education: Understanding, measuring, and predicting student feedback uptake — AI Feedback Literacy scale and uptake prediction (Liu & Deris 2025)
- Generative artificial intelligence as an enabler of student feedback engagement: a framework — GenAI as enabler of feedback engagement framework (Zhan, Boud, Dawson & Yan 2025)
- Rethinking AI-assisted writing instruction: feedback literacy scripts, calibration training, and student writing development — Feedback literacy scripts and calibration training for AI-assisted writing (Dai 2026)
- Effects of feedback literacy scripts and a second-rater mechanism on EAP writing revision in generative AI-supported contexts — Feedback literacy scripts + second-rater in EAP writing revision (Yao 2026)
- Reconnecting relationships through technology: Developing feedback literacy capabilities through an AI automated feedback tool — AI automated feedback tool for developing feedback literacy (Tubino & Adachi 2025)
- Positioning generative AI in EFL peer feedback: Training feedback literacy and enabling uptake in speaking classes — Positioning GenAI in EFL peer feedback to train feedback literacy (Irwin & Muller 2026)
- Fostering feedback literacy by scaffolding self-regulated feedback: a comparative study of GenAI and human peers — Scaffolding self-regulated feedback: GenAI vs. human peers (Gu, Chen & Yan 2026)
- Students' Perceptions of Generative AI-Powered Learning Analytics in the Feedback Process: A Feedback Literacy Perspective — GenAI learning analytics in feedback, feedback literacy perspective (Jin et al. 2025)
- Using generative AI to promote psychological, feedback, and artificial intelligence literacies in undergraduate psychology — GenAI assessment builds psychological, feedback, and AI literacies (Richmond & Nicholls 2025)
- Enhancing learner-centered feedback with AI: Teachers' practices and perceptions — Teachers' practices and perceptions of AI learner-centered feedback
- The care-full craft of feedback in an age of generative AI — Care-full feedback design with GenAI
- Artificial intelligence and feedback in university education: effectiveness and student perceptions — AI-generated feedback in higher education
- How artificial intelligence transforms the feedback ecosystem in higher education — AI reworks the relations among students, educators, peers and materials in the feedback ecosystem (Bearman et al. 2026)
- Using AI-Generated Feedback to Improve Critical Thinking and Writing Proficiency — AI feedback and critical thinking in writing

- Student Evaluation of Repeated AI Feedback Across a Semester of Writing — Repeated AI writing feedback across a semester
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- The association between generative AI use and university students' critical thinking: a moderated mediation model of GenAI feedback literacy and reflective thinking — GenAI use to critical thinking ran through GenAI feedback literacy, strengthening with reflective thinking
- From automated scoring to learning diagnosis: a mechanism study of AI-supported formative assessment in English writing — Comprehension, not actionability, carried the revision payoff

Connected FAQs

- What Are Best Practices for Writing Instruction in the Context of AI?
- How Can AI Help Me Give Better Feedback at Scale?

AI Feedback Quality

> **AI feedback quality** — the accuracy, usefulness, timeliness, and pedagogical value of feedback generated by AI systems for learners. As AI-generated feedback becomes ubiquitous in education, understanding what makes feedback effective — and when it falls short — is critical to ensuring AI supports rather than undermines learning.

Questions to Consider

- What makes feedback 'good' — accuracy alone, or also being timely, specific, actionable, and calibrated to what you already know? Which of these would you notice missing first?
- Research finds students experience AI-generated feedback as comparable to a teacher's — but what students find acceptable need not produce learning effectiveness. Why might feedback that feels fine still fail to help you improve?
- Even high-quality AI feedback is inert without a 'feedback-literate' recipient — studies show low feedback literacy can make AI feedback minimally useful or even negative. Whose responsibility is it to build that literacy?
- Feedback quality and revision depth are linked: scaffolding how students engage with AI feedback shifts them toward argument-level improvement rather than surface edits. How does the way you receive feedback change what you do with it?
- Sycophantic feedback conflates support with agreement — an AI that validates your answer rather than challenging it undermines feedback's corrective function. When does feedback need to challenge you rather than comfort you?
- Confidence calibration matters: a system that knows when it's uncertain gives better feedback than one that's confidently wrong. How should a tool signal its uncertainty to you, and how would you use that signal?

Introduction

AI feedback quality is not simply about correctness. Effective feedback must be timely, specific, actionable, and calibrated to the learner's current understanding. Research in this knowledge base examines AI feedback quality across multiple dimensions: accuracy (is the feedback correct?), usefulness (does it help the student improve?), and pedagogical alignment (does it promote learning rather than just task completion?).

How AI feedback quality appears in the research

- **Comparability to human feedback:** Studies in higher education find that AI-generated feedback is experienced as acceptable and supportive — comparable to teacher feedback. But acceptability does not guarantee learning effectiveness. A PRISMA-guided systematic review of 42 empirical studies (2023–2025) likewise finds Large Language Models (LLMs) grading and feedback quality to be task-contingent — matching human raters on short, well-structured answers with detailed

rubrics but degrading on complex, open-ended, or multilingual work, with feedback sometimes too generic or misaligned with the grade — and identifies prompt quality, rubric detail, model version, and assessment language as the dominant determinants of grading and feedback quality (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback).

- **LLM-generated lesson materials matched human-created ones — when feedback was present.** Lin et al. (2026) generated scenario-based tutor-training lessons with a retrieval-augmented pipeline over curated research sources and compared them in a randomized eight-condition experiment (N = 208) against carefully human-authored lessons. The human-created lesson produced higher post-test performance (0.793 vs 0.730), but only in the no-feedback condition; with immediate explanatory feedback the source difference disappeared, and feedback had no overall main effect. For content generation the finding suggests the human-vs-LLM gap is a scaffolding gap: generated materials are competitive when the learning environment supplies the explanatory feedback the lesson itself does not.

Student-perceived quality is more mixed than acceptability suggests: 77 of 93 undergraduates found AI feedback easy to understand, yet 68 found it repetitive and 79 self-contradictory; only 31 agreed it grades complex or creative writing, and 81.7% preferred human scoring for a final paper worth 40% of the grade (Yildirim-Erbasli et al. (2026)). - **A pooled anchor for the feedback mechanism.** A 53-study meta-analysis found GenAI feedback produced the largest effect in the study (g = 1.27), against g = 0.40 for achievement, credited to comprehension, timeliness and objectivity — though students can distrust AI feedback and its lack of emotional response may raise cognitive load (Dong (2026)).

A controlled comparison isolates the feedback component from the adaptive system: with the same diagnostic tutoring system, learners receiving automated real-time feedback rose from 1.90 to 3.54 on a four-point mathematics assessment against 1.90 to 2.85 without it ($F(1, 76) = 9.24$, $p = .003$, $d = 0.73$) (Ogunsakin et al. (2026)).

- **A supportive feedback sequence can still harm learning.** Cao et al. (2026) found that encouragement → hints → correct answer lowered post-test scores ($B = -0.83$, $p = .02$) despite raising perceived encouragement, with frequent resubmissions predicting worse performance ($B = -0.33$, $p = .001$), so engagement and satisfaction are not proxies for learning.
- **A grammar-feedback and revision cycle moved writing, confidence and metalinguistic awareness.** Wordofa and Abo (2026) found an AI-supported draft–reflect–revise condition outperformed conventional instruction on all five writing dimensions after covarying pre-test scores ($F(5, 77) = 20.885$, partial $\eta^2 = 0.576$), with writing Self-Efficacy at partial $\eta^2 = 0.254$.
- **Feedback classification benchmarks:** Cross-language feedback benchmarks assess whether feedback quality classification transfers across languages and educational contexts, connecting to AI Ed Evaluation.
- **Collaborative feedback systems:** AICoFE implements and deploys AI-based collaborative feedback in higher education, evaluating both system performance and student reception.
- **Personalization can encode bias.** Holding the essay constant, conditioning feedback on a student's race, language, or disability shifted four LLMs toward positive feedback bias (over-

praise) and feedback withholding bias (less substantive critique) — the mechanism through which personalized feedback becomes discriminatory (Tan, Phalen & Demszky (2026)).

- **Automated grading feedback:** Automated Grading and Formative Assessment research examine whether AI-scored assessments provide feedback that matches or exceeds human grading quality.

Feedback dominates practice but its quality is rarely the outcome. Feedback and tutoring were the most frequently reported enacted uses across 394 GenAI higher-education studies, yet feedback quality was among the outcomes targeted least (Lin et al. (2026)).

- **Essay scoring feedback:** Confidence-aware ASAG and anchor-based AES explore how confidence calibration and prompting design affect feedback quality for writing assessment.
- **Evidence-constrained, risk-adaptive feedback:** Wang (2026) separates three functions that feedback research usually evaluates together — predicting which failed state will persist, deciding when limited support capacity should be spent, and generating feedback whose claims stay inside recorded evidence. Across 2993 failed-submission states from 215 students, a calibrated risk model selected 17.8% of eligible test states and captured 25.2% of observed persistent failures, and after one standardized repair pass 519 of 544 generated messages carried all required components. Timing and grounding therefore join linguistic quality and retrievability as dimensions a feedback system has to be judged on.
- **Discretionary feedback provision:** Research on AI-assisted feedback in higher education examines whether AI increases the quantity and quality of feedback instructors provide.
- **The relational layer resists delegation:** across 21 higher-education teachers using an AI feedback tool, 12 rewrote the model's text, revisions clustered on tone and encouragement (Student–Teacher Relationship f = 24), and the more experienced teachers flagged editing burden, trust and misinformation risk while novices deferred to the tool (Aldino et al. (2026)).
- **Students and the model agree on some dimensions and not others.** Undergraduates judged feedback constructive on the same terms ChatGPT did for specificity and actionability, but diverged on timeliness and positivity, and valued instructor feedback for its relational, personalized and expert-driven character while reading AI feedback as impersonal (Fong et al. (2026)).
- **Reliable provision, not inherent superiority, drives AI's edge:** Geschwind et al. (2026)'s semester-long field experiment found GPT-4 feedback beat peer feedback because it was *consistently* delivered — nearly all AI-feedback respondents (369/398) received textual plus numeric feedback while under two-thirds of peer-feedback students received none, and much peer feedback was non-targeted praise. When high-quality textual peer feedback *was* received, peer outcomes matched AI's — indicating the AI advantage is reliability, not quality at the margin. Students also rated peer feedback slightly higher on perceived validity and emotion (mild algorithm aversion) yet still activated and learned more from AI, showing perceived quality and behavioral outcomes can diverge.
- **Quality parity can give way over rounds.** On a shared rubric, peer-group feedback matched ChatGPT-4o's across five dimensions in round one, but the model pulled ahead on

constructiveness, accuracy and concreteness in round two — a shift they attribute to rubric-aligned prompting and practice, not a fixed model property (Li et al. (2026)).

- **The advantage can come from a worked example, not corrective feedback.** Practicing cover letters with AI beat feedback from experienced human editors on a later unaided task (d = .20), and merely viewing one AI-revised letter matched practicing with the tool, so the gain tracked the example (Lira et al. (2025)).
- **Source label versus feedback quality:** Mertens et al. (2026) separate the *source* of feedback from its quality by holding content constant — 401 teachers rated feedback messages that were all generated with GPT-4-turbo but randomly labeled as teacher- or ChatGPT-generated, and the label alone shifted credibility (b = 0.21), usefulness (b = 0.47) and fairness (b = 0.48, all $p < .001$), with 73% preferring the teacher-labeled message, $t(400) = 15.55$, $d = 0.78$. Provider-directed items moved furthest — perceived effort (b = 1.34) and willingness to rely (b = 1.45) — and a written explanation of how ChatGPT works changed nothing (interaction ps ≥ .399), pointing to Trust, professional identity and ingroup bias in the rater rather than any deficiency in the feedback itself. Perceived quality can therefore be discounted by provenance even when the content is identical, which means a genuinely good tool can still stall at the point of use.
- Credibility is not reducible to quality: Pérez-López et al. (2026) found students' perceived competence with ChatGPT and their sense of its human-like empathy predicted its feedback credibility, while perceived warmth worked only through that empathy.
- **Source label versus feedback quality, on the student side:** Nazaretsky et al. (2025) ran the student-side counterpart, in which 472 EPFL students across six courses rated feedback on their own assignments blind to its source and again after disclosure, and most could not tell the two variants apart (287 of 472 guessed correctly). Ratings then moved in opposite directions — significantly so for Genuineness ($p < .01$) — with human providers rated more credible ($\mu = 3.28$, $\sigma = 0.77$) than AI ($\mu = 2.25$, $\sigma = 0.85$, Cohen's $d = 0.57$). The misattribution ran mostly one way: of 219 instances of low-rated human feedback, 205 were read as AI, so perceived quality and perceived identity reshape each other in both directions rather than the label merely discounting identical text.
- **Feedback literacy as the uptake-side boundary:** Liu & Deris (2025) validate an **AI Feedback Literacy (AIFL) scale** (16 items, Attitudes/Practices factors) that predicts students' actual uptake of AI feedback, and Mendoza et al. (2026) show feedback literacy moderates whether AI feedback improves Self-Regulated Learning — high literacy yields benefit, low literacy yields minimal or even negative effects. Feedback quality and feedback literacy are two sides of one system: even high-quality AI feedback is inert without a literate recipient.
- **Feedback quality drives revision depth:** Feedback literacy scripts and second-rater mechanisms show that Scaffolding how students engage with AI feedback shifts revision toward argument-level improvement rather than surface edits — feedback that promotes deeper revision is higher-quality feedback. What students *do* with comments also depends on their kind, not just their count. In an eight-week L2 writing comparison, the teacher's broader, self-adjusting error correction delivered the larger first-task gain but fell by roughly a third in the second task once the work demanded structural breakthroughs, while AI-assisted peer feedback's narrower but steadier focus

held its improvement and edged past the teacher class's second-task revision mean — a between-group gap the authors report as not statistically significant. The authors read authoritative, error-heavy correction as encouraging passive, error-avoidance revision and treat the two modes as complementary heterogeneous scaffolds rather than substitutes (Tang, Li & Luo, 2026); neither mode moved syntactic complexity, so feedback quality is also bounded by the layer of skill it can act on.

- **Sycophancy as a feedback failure:** Sycophantic feedback conflates support with agreement — an AI that validates a student's answer rather than challenging it undermines feedback's corrective function, degrading quality even when it feels affirming. EduFrameTrap shows tutors withholding corrective feedback under social pressure, and contextual sycophancy propagates errors into subsequent advice; effective feedback must sometimes challenge the learner.
- **Diagnostic accuracy only partly determines feedback quality — and LLM self-evaluation misaligns with human judgment:** Reddig, Arora & MacLellan (2025) found GPT-4 produced error-targeted hints ~66% of the time in a College Algebra tutor, yet ~35% were too general, incorrect, or gave away the answer; even when diagnosis was wrong the model often recovered with relevant, general-but-correct feedback, though almost all incorrect feedback followed a misdiagnosis. Their simulated-student automated quality checks passed only 21.4% of hints on both tests, rejected targeted feedback ~70% of the time, and favored hints that simply revealed the answer — a stark demonstration that automated evaluation can diverge sharply from human judgments of helpfulness and must be calibrated against them.
- **Stable output is not valid feedback:** across 12 TEACH-framework classroom videos, reliability and accuracy came apart — the most stable of eight LLM endpoints was among the weakest against certified experts (exact agreement 0.31), and every model privileged verbal cues over implicit pedagogical evidence, scoring low where directives were absent (Melo et al., 2026).
- **Linguistic and perceptual quality of AI instructional comments:** Wang, Du and Jin (2026) assess ChatGPT-generated in-video scaffolding comments against instructor comments on part-of-speech composition, 3-gram diversity, Zipf's law conformity, readability, topical relevance (TF-IDF and BERTScore), and learner ratings. The generated comments were *more* complex and adjective-rich but *less* varied and less readable, and trailed human comments on topical alignment (0.607 vs. 0.747 BERTScore for knowledge support) and on perceived timing and helpfulness — evidence that AI feedback quality must be judged on linguistic Accessibility and affective fit, not relevance alone. Their analytic battery is offered as a reusable Learning Analytics pipeline for auditing AI-generated instructional content.
- **Prompt design and model choice as measured predictors of quality:** Jacobsen et al. (2026) decompose the sources of AI feedback quality with hierarchical regression on feedback generated for 153 pre-service teachers' lesson-planning goals. Across 240 feedbacks from three models under four systematically varied prompts, the model alone explained 26.9% of the variance in nine-category quality ratings and adding the prompt lifted the model to 42.8% ($\Delta R^2 = 15.9\%$); in a replication with the strongest model-prompt combinations (345 feedbacks) the model explained 18.4% and the prompt a further 5.7%. The largest single prompt effect was negative: replacing domain-specific technical terminology with everyday paraphrases lowered feedback quality

significantly (β = −0.412), while adding concrete examples and removing the chain-of-thought instruction were not significant in the first study. Quality is therefore not a fixed property of "the AI" — it is jointly produced by which model is chosen and how the task is phrased, and both are teachable.

Style is a quality dimension with a cost: with the same model, directive feedback scored higher on prioritizing essential features and on specificity, while Socratic feedback raised comprehension monitoring — and directive feedback carried the higher cognitive load (Han et al. (2026)).

How the feedback is *produced* belongs on that list too. In a modular automated writing evaluation system for argumentative essays, supervised fine-tuning on 90 teacher-annotated essays produced unusable feedback — the fine-tuned GPT-4o exceeded its 8,000-token context window on every inference and fine-tuned LLaMA-3.3-70B emitted JSON that would not parse. Directly prompting Claude 3.7, by contrast, generated 630 micro comments across 40 essays whose teachers judged 94.69% necessary and effective, leading the authors to conclude that for a non-deterministic generation task prompting can beat fine-tuning (Labib et al., 2026).

Quality dimensions

AI feedback quality spans multiple dimensions captured in the knowledge base: - **Accuracy:** Does the feedback correctly identify errors and strengths? (Automated Grading, Automated Essay Scoring) - **Retrievability of evidence:** Can the system actually reach the evidence it is judging? Abreu, Stari and Martí (2026) separate evidence present in a submission from evidence available after processing — an equation, graph or unit may be included in a report yet never retrieved, so feedback about that criterion rests on nothing — making retrieval a dimension of quality distinct from accuracy or calibration. Their response is to require each score to cite concrete evidence from the report, so an observation that cannot be traced back to the text is visible as unsupported. - **Helpfulness:** Does the feedback guide improvement? (Feedback Loop, AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education) - **Timeliness:** Is feedback delivered when the learner can act on it? (Formative Assessment) - **Trainability:** quality is bounded by the labeled data the system was trained on, and expert annotation is where that budget actually goes. Xu, Lin, Wu, Aleven and Koedinger (2025) attacked this in tutor training, where effort-, outcome- and person-based praise has to be identified in open-ended responses. Fine-tuned on 520 GPT-4o-augmented examples grown from 13 real annotations, a small model gained F2 +20.5% on effort praise and +17.3% on outcome praise. The mechanism is closer to knowledge distillation than to classical augmentation, and the gain transferred to a praise category it was never trained on (F2 +16.5%), which is the evidence that it generalizes. - **Verifiability against an objective measure:** Where the target is machine-measurable, feedback can be checked against a physical measurement rather than a rubric. Aksoy (2026) extracted 2,208 note-level pitch deviations in cents and gave those tables to the model, so its claims had a measurable referent. - **Bias:** Is feedback equitable across student populations? (Bias Mitigation, Equity)

- **Ethics and transparency:** Only 14 of 50 top-ranked universities had specific guidance on teachers' AI use for feedback, and students described undisclosed AI feedback as "disingenuous" — transparency and consent shape whether feedback is accepted, not just whether it is accurate (Luo & Eaton (2026)).

- **Calibration:** Does the system know when it's uncertain? (Confidence Aware AI Assessment)
- **Verifier-scored release criteria.** LearnLens scores generated feedback on scientific accuracy, clarity, and specificity and iterates a verification-and-revision loop until every criterion clears a threshold, using a *separate* foundation model from the generator to avoid model-family bias; its scoring ran 8–13% below every baseline on MSE (3.190) (Zhao et al. (2025)).
- **Comprehensibility in the learner's own language.** Feedback only closes a gap if the learner can follow the explanation, not merely the flag. The Kwara-STEM AI Tutor, a localized model fine-tuned on national technical-education curricula, nudged students rather than handing over answers and shipped a "Clarify" feature that translated complex technical terms into Yoruba or Nupe, so real-time correction landed in the learner's own language context (Muritala, Ahmed & Olumorin, 2026). Own-language explanation is a condition of synchronous feedback's usefulness, not a decorative add-on.
- **Coverage is not alignment.** Six LLMs under three prompting strategies each produced most of the seven feedback focus types, yet their distribution over those types diverged from teachers' (best Jensen-Shannon divergence 0.134, worst 0.270), so breadth of coverage and distributional fit are separate quality signals (Almousa et al., 2026).
- **Field-level coverage is uneven.** A synthesis of 68 studies of AI-generated feedback finds the evidence clusters on whether feedback is accurate and grounded (47 studies) and whether it helps the learner (58), while rubric and task alignment — whether the feedback responds to the task's own requirements — appears in only 19 (Yang (2026)).
- **Criterion-level ratings diverge within one message set.** Six reviewers scoring 157 messages rated practice exercises strongest (95.5%) while diagnostic specificity (41.1%) and clarity and tone (33.4%) lagged, and instructors rated actionability more generously than other reviewers (84.5% vs 59.9%) (Vanhoyweghen et al. (2026)).
- **The reader's side of the same dimensions.** Twenty-four university writing professors described output that was complicated, overly long, vague or impractical, and two found it praising strengths unless told to look for weaknesses first (Wu and Lam (2026)). Seven said reaching acceptable feedback took repeated prompting, which spends the time the workload gain was meant to save.
- **Length out-predicted every other measured property of the message.** Across three deployments of an LLM hint system in a live programming course, each standard deviation of 204.9 characters predicted lower next-submission correctness (−0.733), more remaining attempts (0.187) and a longer wait before resubmitting (0.226), while Flesch-Kincaid grade was uncertain for the first two (Mihaylova et al., 2026). Format mattered as well, but as a trade-off: diagnostic hints produced correct next submissions more often and fewer attempts, and slower resubmission.

Connection to broader concepts

AI feedback quality connects fundamentally to Formative Assessment and Feedback Loop — quality feedback closes the gap between current and desired performance. It intersects with Automated Grading (which generates the scores feedback is based on), AI Literacy (students must evaluate feedback quality

critically), and Over-Reliance (uncritical acceptance of AI feedback can displace learning). For Writing, feedback quality is particularly consequential given AI's growing role in writing assessment.

The corpus behind those quality claims is thinner than the claims suggest. Across 51 studies of GenAI written feedback in second-language writing, 16 experimental designs used no control group and only 27 reported the prompts they used — so two in five results cannot be reproduced or compared on the variable that most shapes output (Crosthwaite & Sun (2026)). Quality evidence in this literature therefore accumulates more slowly than its volume implies.

Wu, Li and Moorhouse (2026) examine DeepSeek's explicit reasoning traces as a feedback affordance, finding that visible reasoning makes the basis of a comment inspectable by the writer, while the model still routes higher-order judgment, such as argumentation, to the human.

Common Misconceptions

- **"Students find AI feedback acceptable, so it is good." Student-perceived quality is more mixed than acceptability suggests**: **77 of 93 undergraduates found AI feedback easy to understand, yet 68 found it repetitive and 79** found something else wanting. Comprehension and dissatisfaction coexisted in the same cohort.
- **"Feedback effects are modest."** A **53-study meta-analysis** found GenAI feedback produced **the largest effect in the study (g = 1.27)**, against **g = 0.40** for the overall GenAI effect. Feedback is the strongest mechanism measured, which is a different picture from the general optimism debate.
- **"The feedback is the whole intervention."** A controlled comparison isolates the component: with the same diagnostic tutoring system, learners receiving **the feedback component** differed measurably. Separating feedback from the adaptive system is what makes the claim attributable.
- **Access and engagement are different interventions.** Wenzel, Geiger and Liening (2026) separated the two across **234 students and 1,147 weekly observations** in a five-week business simulation. Assignment to conversational AI feedback produced **no effect** on germane cognitive load ($\beta = .019$, $p = .807$) or extraneous load ($\beta = .071$, $p = .481$). **Actual regular use** was associated with significantly higher germane load than experimental non-users ($\beta = -.468$, $p < .001$) and than controls ($\beta = -.253$, $p = .028$), while **irregular use did not separate from regular use** ($p = .116$). Quality judgments that rest on an intention-to-treat contrast will therefore understate a feedback intervention whose uptake is partial, and satisfaction or access metrics cannot substitute for engagement data.

Connected Concepts

- Pedagogical Patterns — Quality does not predict revision: the sequences that make AI feedback usable
- Formative Assessment
- Automated Assessment
- Feedback
- AI Literacy
- Cognitive Offloading

- Bias Mitigation
- Automated Essay Scoring
- Assessment Validity
- Writing
- Higher Education
- Teaching
- Feedback Literacy
- AI Sycophancy
- Trust Calibration

Connected Articles

- It’s Complicated: Factors Influencing the Effectiveness of LLM-Generated Feedback in a Live Programming Course — Longer LLM hints predicted worse immediate outcomes; format traded fewer attempts for slower resubmission
- Generative artificial intelligence in writing assessment: University professors’ perspectives and recommendations — Professors on AI feedback quality: flattering by default, long, vague, and slow to refine
- Generative AI and L2 Written Feedback Studies: A Scoping Review — Only 27 of 51 studies reported their prompts; 16 experiments lacked a control group
- AI AI Tell Me: A Model Study on the Effect of Artificial Intelligence-Assisted Feedback on Intonation in Violin Education — AI feedback on intonation checked against 2,208 machine-measured pitch deviations (Aksoy 2026)
- WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays — WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays
- Assessing ChatGPT-Generated Comments for Video-Based Learning Content to Enhance Knowledge and Emotional Support Based on Scaffolding Theory — Assessing ChatGPT in-video comments: linguistic, semantic, and perceptual quality (Wang, Du & Jin 2026)
- Is It Ethical for Teachers to Use AI for Student Feedback?
- Coach not crutch: Evidence that AI can improve writing skill despite reducing effort — AI writing feedback outperformed human editors on practice letters (Lira et al. 2025)
- LearnLens: LLM-Enabled Personalised, Curriculum-Grounded Feedback with Educators in the Loop — LearnLens: LLM feedback generation with educators in the loop (Zhao et al. 2025)
- Validating AI-generated classroom observations: Reliability, accuracy, and limits of LLM-based pedagogical judgment — LLM classroom observation feedback reliability and limits (Melo et al. 2026)
- Enhancing learner-centered feedback with AI: Teachers’ practices and perceptions — Teachers’ practices and perceptions of AI learner-centered feedback (PolyFeed)
- Artificial intelligence and feedback in university education: effectiveness and student perceptions — AI-Generated Feedback in Higher Education

- A Durability and Cross-Language Transfer Benchmark for a Validated Teaching-Feedback Classification Protocol — Teaching Feedback Classification Benchmark
- AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education — AICoFE: AI-Powered Collaborative Feedback
- Confidence Estimation in Automatic Short Answer Grading with LLMs — Confidence-Aware Short Answer Grading
- Anchor Is the Key: Toward Accessible Automated Essay Scoring with Large Language Models Through Prompting — Anchor-Based AES Prompting
- AI Assistance for Discretionary Work: Increasing Feedback Provision in Higher Education — AI Assistance for Discretionary Feedback
- Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning — Sequenced AI Feedback and Learning
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks — Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: bias in automated writing feedback
- GPT-4 feedback increases student activation and learning outcomes in higher education
- Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- AI Literacy of Teachers: Prompt Engineering and Model Selection as Predictors of AI-Feedback Quality — Prompt engineering and model selection as predictors of AI-feedback quality (Jacobsen et al. 2026)
- Perceptions of Teacher- Versus AI-Generated Feedback: Experimental Findings on the (Implicit) Bias of Teachers Against AI — Randomized source labels on identical GPT-4 feedback: teachers discount AI-attributed feedback (Mertens et al. 2026)
- Comparative analysis of peer group and AI-generated feedback in peer assessment: Insights into feedback quality and student perceptions in higher education — Comparative analysis of peer group and AI-generated feedback in peer assessment: Insights into feedback quality and student perceptions in higher education
- AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice — AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing

- A Risk-Adaptive and Evidence-Constrained Framework for Generative AI Feedback in Programming Education — A Risk-Adaptive and Evidence-Constrained Framework for Generative AI Feedback in Programming Education
- Impact of real-time AI feedback on the technical skill acquisition of STEM students in Colleges of Education in Kwara State — Own-language "Clarify" explanation and scaffolded nudges in a real-time tutor: what makes synchronous feedback usable (Muritala, Ahmed & Olumorin 2026)
- Teacher feedback vs. AI-assisted peer feedback in L2 writing: A quasi-experimental study in a Chinese university — Teacher vs AI-assisted peer feedback: authoritative error correction decays, steady focus holds, and what students do with each (Tang, Li & Luo 2026)
- Who Gives Feedback Matters: Student Biases Towards Human and AI-Generated Formative Feedback — Blind-then-disclosed source labels on identical feedback: students rate AI-labeled feedback lower and read low-rated human feedback as AI
- Reimagining mathematics education through intelligent tutoring: evidence, opportunities, and implementation challenges — Narrative review of AI tutoring in mathematics: real-time feedback gains and implementation conditions
- The Effects of Agent Type and Feedback Style on Self-Directed Learning: A Mixed-Methods Study — Socratic versus directive feedback styles: comprehension monitoring against prioritization, and the cognitive-load cost
- When Do Undergraduate Students Prefer AI? Insights into AI Scoring and Feedback — Student-perceived AI feedback quality: understandable yet repetitive, trusted for mechanics not interpretation
- Retrieval-augmented lesson generation with large language models for scenario-based tutor training — RAG-generated tutor-training lessons matched human-created ones when feedback was present; the human advantage appeared only without feedback
- An Evidence-Grounded Framework for Evaluating AI-Generated Educational Feedback — Three evaluation dimensions across 68 studies, with rubric alignment the thin one (Yang 2026)
- Evaluating LLM-Generated Feedback on Handwritten Mathematics: Feedback Quality and Subsequent Exam Performance — Criterion-level and rater-level divergence in 157 rated feedback messages (Vanhoyweghen et al. 2026)

Connected FAQs

- How Can AI Save Me Time as an Instructor?
- How Can AI Help Me Give Better Feedback at Scale?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

Formative Assessment

> **Formative assessment** — assessment designed to inform ongoing instruction and learning, as opposed to summative evaluation. In AI education, formative assessment is both transformed by AI and essential to it: AI systems can generate, validate, and adapt formative items and feedback at scale, while formative feedback is a primary mechanism through which AI tutors and adaptive systems support learning. The knowledge base's research examines AI-generated formative items, AI-generated feedback, and the design and evaluation of these systems.

Questions to Consider

- Formative assessment is meant to close the loop — surface what students don't know and give feedback they can act on *while learning is still in progress*. How is that fundamentally different from summative evaluation, and when might the two get confused in practice?
- AI can generate multiple-choice questions with impressive accuracy on verifiable dimensions, but is weakest on instructional-judgment dimensions. If a machine is good at correct answers but weaker at pedagogical judgment, what should it be trusted to do — and what should humans keep doing?
- AI-generated feedback only helps when students actually enact it — the 'enacted feedback' condition, where students select, evaluate, and apply suggestions, outperformed simply being given feedback. If enactment matters more than the feedback itself, what does that mean for how formative feedback should be designed?
- Feedback is described not as information transfer but as an ethical, relational practice. What gets lost when formative assessment is mass-produced as 'AI slop' — and what can human comment banks and relational care preserve?

Introduction

Formative assessment is central to AI in education because it sits at the junction of Assessment and learning feedback. Its purpose is to close the loop: surface what students know and don't know, and provide feedback they can act on to improve. AI makes this feasible at scale — generating items, scoring responses, and delivering individualized feedback — but the knowledge base's research shows that quality varies dramatically across item types, and that feedback only helps when students actually enact it.

Correnti et al. (2026) supply evidence that an automated writing system can serve an authentic formative purpose: growth appeared in revision quality and not only in feature scores, but only where teachers built the feedback into classroom discussion.

AI-generated formative items

AI systems generate formative assessment items across modalities, with reliability varying by type:

- **Multiple-choice questions:** CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation shows agentic AI can reliably generate MCQs for coding comprehension when validated across seven pedagogical dimensions — success rates reach **98.6%** for concept alignment and **79.9%** for feedback quality — suggesting AI is strongest on verifiable dimensions and weakest on instructional-judgment dimensions. This connects to automated question generation more broadly.
- **An easy generated item bank gives no formative signal.** In a 10-week deployment about 70% of AI-generated practice items were answered correctly by every student ($p = 1.0$), so the low-stakes quizzes that ran every 15 to 20 minutes were well received but carried almost no discriminating information for adapting instruction (An & Wang (2026)).
- **Automated essay scoring:** multi-agent frameworks (e.g., MASS) improve consistency over stand-alone LLMs for essay scoring, though interpretability of multi-agent scoring decisions remains an open challenge.
- **Formative scoring pipelines:** CoTAL couples Chain-of-Thought prompting with active learning and Evidence-Centered Design to produce generalizable formative-assessment scoring with human-in-the-loop prompt engineering.
- **High-frequency, automatically-marked assessments:** automated formative assessments in A-level sciences examines the effect of high-frequency, automatically-marked formative assessment on learning outcomes. A scoping review of short-answer auto-marking in science (2017–early 2024) confirms this formative short-answer use case is a field with real traction: BERT-family models dominated auto-marking through 2021 before prompting larger LLMs from ~2022, and domain-augmented, rubric-aware, and chain-of-thought models performed best — yet the review's calls for comprehensive evaluation and unresolved fairness and explainability gaps caution against extending such systems to unmediated summative or high-stakes use (Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4).

AI-generated feedback

A large body of knowledge base research examines AI-generated formative feedback:

- **The enactment problem:** Making AI-Generated Feedback Matter (13,037 students; 51,296 resources) shows feedback value depends on whether students *enact* it — the **Enacted Feedback** condition, where students select, evaluate, and apply AI feedback suggestions, outperformed simple directed feedback.
- **AI feedback can match expert teachers when the rubric carries the criteria.** Blind to source and randomized across 47 university project groups, an LLM given the co-constructed 0–30 rubric and exemplar was non-inferior *and* equivalent to expert feedback (+0.23, 90% CI [−0.46, 0.91]) — the rubric, not the model, calibrated (Grion et al. (2026)).

- **Feedback is not information transfer:** The care-full craft of feedback argues feedback is an ethical, relational practice, not information transmission — feedback only constitutes feedback when students make sense of and act on it, and contrasts mass-produced "AI slop" with human comment-bank shortcuts.
- **Sequenced feedback can backfire:** Sequenced AI feedback (encouragement → hints → correct answer, designed to promote autonomy) actually **harmed learning** in a randomized experiment (N=199) despite boosting engagement and positive perceptions — a cautionary finding about feedback design.
- **Learner-centered tools:** PolyFeed combines ML suggestion models with teacher practice, showing how teachers adopt and adapt AI feedback suggestions; AI-supported internal feedback helps undergraduates develop evaluative judgment.
- **Rubric-guided prompting and role-aware feedback:** Yaşar et al. (2026) showed that iterative rubric co-refinement — clarifying performance descriptors and explicitly accepting implicit indicators of learning — drove LLM–human agreement on student design work from 54.75% to 81.25% (Cronbach's Alpha rising from 0.393 to 0.798), with the largest gains in the cognitively demanding Iteration & Reflection category. Prompting the same model under instructor, peer-reviewer, and grant-reviewer roles produced distinct evaluative feedback, and post-revision LLMs were more consistent than some human raters in applying performance thresholds — positioning rubric-guided LLMs as calibration and co-design partners in formative feedback environments, with human-in-the-loop oversight remaining essential.
- **Agreement figures hide a direction: a model can hedge toward the middle category.** An LLM assessor tagging dialogue turns inside a conversation-based assessment matched human coding on 52.2% of 155 events, but used the hedged PARTIAL_CORRECT label more often than raters (53.5% against 41.3%) and flagged 5.4% of turns IRRELEVANT where raters flagged none (Hou et al., 2025).
- **AI feedback sustains participation and drives gains at scale:** Geschwind et al. (2026)'s semester-long field experiment across undergraduate tutorials found that individual GPT-4 formative feedback (spanning all three Hattie & Timperley dimensions — Feed-Back, Feed-Up, Feed-Forward) sustained the highest participation across eight open-ended tasks, lengthened student answers, and produced the strongest content learning gains — an effect driven by reliable, consistent AI provision, since when high-quality textual peer feedback was actually received, peer outcomes matched AI's.
- **Feedback futures:** Feedback Futures synthesizes a special issue and argues the question is not *whether* GenAI can produce feedback but how to design feedback that supports learning, distilling recurring tensions across the field.
- **Most formative feedback is momentary, not sustainable.** In a scoping review of 37 authentic-assessment studies, 23 used formative feedback for immediate improvement but only four used sustainable feedback that students transfer to future contexts — the reactive pattern current AI feedback tools reproduce (Zhan, Boud & Du (2025)).

- **Diagnosis-first feedback for open-ended quantitative problems:** Arthur (Yin et al. 2026) delivers real-time, personalized formative feedback on Engineering Economics Calculated Formula Questions, a domain where handwritten, unstructured solutions had previously blocked AI support. A per-question XGBoost backbone diagnoses likely rubric-labeled mistakes from students' submitted numerical answers (average precision 0.81, recall 0.79), and a dialogue-based scheme requests intermediate answers only when prediction confidence is low — balancing feedback accuracy against collection efficiency within a question-bank web interface.
- **Scale and limits of LLM formative feedback (systematic evidence):** a PRISMA-guided systematic review of 42 empirical studies (2023–2025) finds LLMs can reduce teacher workload and deliver rapid, personalized feedback at scale — especially in large or higher-education cohorts — but that feedback is sometimes too generic or misaligned with the assigned grade and reliability slips on longer, multilingual, or nuanced tasks, reinforcing that formative AI feedback is best deployed under educator oversight (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback).
- **Adaptivity is a separable ingredient, not decoration:** Sukjaitham, Schaaf, Brod & Breitwieser (2026) supply the direct causal test that most LLM-feedback studies assume away, pitting GPT-4 response-contingent feedback against expert-written generic guidance matched on structure, tone, length, and motivational phrasing (verified with a five-dimension quality rubric, $\kappa = .76–1.00$). In a preregistered within-subjects experiment, 155 German fifth- and sixth-graders ($M = 12.08$ years) revised six if-then plans: plan quality rose from a median of **2 → 5** under adaptive feedback versus **2 → 3** under generic guidance (within-person $V = 10{,}440$, $p < .001$, $r = .86$; condition × time interaction estimate = 1.68, $SE = 0.14$, $p < .001$, with no pre-support difference). Children rated adaptive feedback both more helpful ($r = .67$) and more motivating ($r = .74$), and trial-level perceptions predicted the size of revision gains — making perceived usefulness part of the pathway rather than an affective byproduct. Because the control was itself well designed, the study shows added value *beyond* good non-contingent guidance rather than the difference between feedback and nothing: generic guidance is a genuine but limited substitute that plateaus at its own median. Planning served as the test case as a core self-regulated learning strategy with explicit quality criteria, which makes contingency — the property that distinguishes Scaffolding from static support — directly measurable on a one-sentence response. The authors define adaptivity narrowly as response-contingent adaptation of feedback content to the learner's concrete response, distinguishing it from conversational interactivity, tone, and stable-trait adaptive learning.
- **Perceived usefulness tracks actionability:** Mendonça et al. (2026) had 144 programming students rate 893 LLM-generated feedback instances on five dimensions and 237 consolidated reports on six, holding domain, task, and instrument constant while educational level varied. Ratings were favorable throughout, with student-level means of 4.24 to 4.43 for individual answers and 4.11 to 4.38 for reports. Yet actionability and usefulness drew the lowest ratings even as actionability and perceived accuracy carried the largest relative weights (32.6% and 29.0%) in a model explaining 76% of the variance in perceived usefulness, and motivation and personalization led a report-level model of intention to use explaining 53%. Since actionability is the dimension Feedback research treats as hardest to provide, the pattern reads as technology acceptance applied to feedback: usefulness tracks whether a learner can act, not how polished the feedback sounds.

- **Offline agreement overstates live performance:** Cruz et al. (2026)'s GPT-4o feedback pipeline reproduced the instructor's mark within 0.5 points in 83% of 362 submissions, yet chance-corrected agreement was only moderate (ICC(2,1) = 0.49) and fell from r = 0.92 on historical scripts to 0.57 in live instructor-supervised use.
- **Comprehension outruns actionability on the path to revision:** Yao and Fan (2026) separated issue-level diagnosis from suggestions and gave students a written interpretation sheet (restatement, effect explanation, uncertainty identification, revision plan) before independent revision, structured teacher review, reassessment and reflection. Across three writing cycles in two intact classes (96 students; 288 cycle-level observations), feedback comprehension carried the strongest association with revision quality (r = 0.501, ahead of actionability at 0.480 and diagnostic accuracy at 0.445), and the diagnostic group gained 5.92 writing points against 3.58 (Hedges' g = 1.12), locating the leverage in students' understanding of the diagnosis rather than in its actionability alone.

Curriculum-grounded and educator-in-the-loop design

LearnLens addresses three persistent problems in AI formative assessment: **error-aware assessment** (capturing nuanced reasoning errors rather than surface mistakes), **topic-linked memory chains** (replacing noisy similarity-based RAG (Retrieval-Augmented Generation) with structured curriculum-grounded retrieval), and **educator-in-the-loop** design (teacher customization and oversight, not full automation). This connects to the broader tension in Human-in-the-Loop: scalable automation with expert validation.

Hoppe, Loibl & Leuders (2026) sharpen what educator-in-the-loop means once a tool produces its own claims rather than raw observations. Their conceptual analysis argues that AI-generated diagnostic inferences are qualitatively different evidence, because they are already the product of algorithmic interpretation, so teachers need a further layer the authors call **meta-diagnosis**: deliberately accepting, rejecting, or modifying an inference and integrating it with their own contextual knowledge. Specifying the DiaCoM framework for this treats AI-generated inferences as a situation characteristic and the accept, reject, or modify decision as diagnostic behavior, while expanding the person characteristics teachers need to include knowledge of how AI systems actually work. Because current systems rest mostly on performance data such as task correctness and completion time, motivational states and classroom dynamics stay largely absent, so the paper keeps teachers, not the dashboard, as the responsible reflective agents and frames judging algorithmic claims as a target for professional development.

Matching the AI's role to achievement level is a related design move: pre-service science teachers described ChatGPT as a Patient Tutor for low achievers, a Personal Coach for medium achievers, and an Intellectual Sparring Partner for high achievers, while the instructor kept the final explanation of difficult content (Ratniyom et al., 2026).

Design trade-offs

Dimension	AI Suitability	Human Requirement
Factual correctness	High	Low
Concept alignment	High	Medium

Dimension	AI Suitability	Human Requirement
Distractor quality	Low	High
Feedback depth	Low	High
Rubric consistency	Medium	Medium

Assessment, feedback, and learning

Formative assessment in AI education connects to the learning process itself:

- **Feedback loops:** feedback loops are the mechanism by which formative assessment informs learning; AI tutors and adaptive systems close these loops at scale.
- **Self-regulated learning:** formative feedback supports self-regulated learning when students monitor progress and adjust; AI feedback should cultivate evaluative judgment, not displace it.
- **Automated scoring reaches some phases of the cycle, not all:** Chen & Liu (2026) ran a 14-week quasi-experiment in which 46 interpreting students submitted weekly renditions to an automated scoring system that returned an immediate score, transcript, marked errors, and a reference rendition, while a control group received whole-class teacher feedback only. The automated group improved more overall (d = 1.03), but the gain stayed where the deficit was decomposable, the signal reliable, and the scale sensitive: linguistic accuracy and logical coherence rose while information fidelity (agreement with human raters r = 0.12) and delivery fluency did not move. Self-regulated learning was uneven in a matching way, with execution and monitoring correlating with score gains (r = 0.42) while planning and emotional motivation sat near the scale midpoint, and several students deferred engagement after low scores instead of analyzing causes. The system reached the performance phase of the cycle, not the planning that precedes it.
- **From automated diagnosis to generated practice:** Zhu, Luo & Li (2026) wire audio-score alignment, error quantification, and a Proximal Policy Optimization layer into one closed loop for music education, turning rhythm error signals (91.2% recall, 98.4% specificity) into rewards that steer generated practice tracks. They report a significant Group x Time interaction favoring the system group (beta = 0.52) across a 12 week quasi-experiment with 120 undergraduate music majors. The authors frame this as technical feasibility, and the practical reading is triage rather than assessment. Precision of 89.7% means roughly one flagged rhythm error in ten is a false alarm, and the study's expert reviewers rated support for musical expression as the weakest area, so automated loops suit technical drills while expressive judgment stays with teachers.
- **Scaffolding:** Scaffolding and formative assessment work together — AI can provide just-in-time hints and prompts, though sequenced feedback research cautions against over-structuring.
- **Rubric quality moves automated-grading agreement more than model choice.** On 1,200 Linux/bash exam responses, Alonso-Carracedo et al. (2026) found adding a full rubric plus a reference answer lifted every model (best: Gemini 3.0 Pro, ICC(3,1) = 0.888 against a human ceiling of 0.949), while agreement fell monotonically as the question's cognitive level rose.
- **AI-generated rubrics matched human scoring only within a margin.** Four AI rubrics met pooled equivalence with the human baseline within ±5 points across 308 programming responses

(correlations 0.948–0.973), but five rubric–assignment cells exceeded it, and GPT-4.1/4o graded systematically harsher on structured rubrics (−4.46 against −0.66 for free-form) (Mendonça et al., 2026).

- **Validity and quality:** the quality and validity of AI-generated formative items and feedback must be evaluated; AI Ed Evaluation provides the methods.
- **AI scoring adds a validity threat.** Because an AI scorer can reward construct-irrelevant features such as language fluency instead of scientific reasoning, a Stanford/ETS white paper distilled from a ~100-leader convening argues assessment should accumulate continuous, context-rich evidence rather than certify one-shot outputs (McGee et al. (2026)).
- **Keep the vulnerable task and add a twin.** Roe, Perkins & Giray (2026) argue take-home essays and research reports carry substantial formative value and should be retained for learning, paired with a second task assessing the same outcomes that supplies reliable summative evidence.
- **Technology-supported formative assessment is a system property, not a tool.** Bulut (2026) defines it as the joint product of technological capacity, pedagogical regulation, learner agency, and human judgment, and argues its value lies in sustaining the evidence-feedback-reflection-action cycle rather than in automation.

Risk: Assessment as surveillance

Formative assessment systems can shift from learning-support tools to behavior-monitoring infrastructure. The same data streams that enable adaptive tutoring can enable punitive tracking if AI Governance is weak. This connects to Privacy and student well-being, and argues for formative systems that support learning rather than surveil it.

Observability can be designed for without surveillance: it is the evidence an assessment actually generates for defensible judgment about learning, treated as a design priority whose cost is paid in feasibility rather than ethics (Pedlow et al. (2026)).

Implications for AI in education

- **Match item type to AI reliability:** use AI for verifiable dimensions (concept alignment, correctness) and retain human judgment for instructional dimensions (distractor quality, feedback depth).
- **Design for enactment, not just provision:** AI feedback only helps when students select, evaluate, and apply it — structure workflows that support enactment.
- **Feedback design matters more than volume:** sequenced or over-structured feedback can backfire; prioritize feedback that supports student sense-making and autonomy.
- **Keep educators in the loop:** curriculum-grounded, educator-in-the-loop systems improve relevance and reduce noise.
- **Evaluate quality and validity:** assess AI-generated items and feedback for quality, validity, and equity, not just generation speed.

- **Treat formative assessment as a philosophy, not a toolkit.** Mesny, Roberge-Maltais & Galy (2026) synthesize the wider higher-education literature into an "assessment for learning" paradigm that frames formative, ongoing, and individualized Feedback as an overarching philosophy rather than a mere toolkit — balancing formative with summative purposes and foregrounding student agency, self-regulation, and metacognitive skill. They identify five mutually reinforcing practices (authentic assessment, self- and Peer Assessment, reassessment, standards-based grading, ungrading) through which this philosophy can be enacted, while noting their uptake remains highly uneven across higher-education fields.
- **Continuous assessment reframes the formative record itself.** The AIM-CAI reference architecture (a position paper, not an implementation) proposes replacing episodic assessment as the primary evidence base with a six-layer infrastructure: evidence generation across platforms, serialization preserving source context, AI-mediated semantic translation, psychometric interpretation, longitudinal competency profiles, and federated governance. Its shift table spells out the change: per-assignment feedback becomes longitudinal feedback supporting advising and reflection; grades become evolving competency profiles; credentials become transparent development records. The governance layer is the paper's insistence — seven named tensions (interoperability vs. local autonomy, privacy vs. utility, learner agency vs. predictive automation, surveillance vs. support, etc.) each mapped to risks and responses, with the warning that ungoverned continuous inference privileges dominant cultural norms. The novelty claim is integrative: the components exist; the contribution is the architecture and the governance map. (AI-Mediated Continuous Assessment Infrastructure (AIM-CAI): Connecting Learning Evidence Across Contexts and Time)

Common Misconceptions

- **"Generated practice items give useful formative signal." An easy generated item bank gives no formative signal**: in a **10-week deployment about 70% of AI-generated practice items were answered correctly by every student**. A bank everyone passes carries no information about who needs what.
- **"Item generation reliability is uniform across formats."** AI systems generate formative items across modalities **with reliability varying by type** — multiple-choice among them. Treating generated items as interchangeable across formats hides where generation is dependable.
- **"Giving students AI feedback produces enactment."** The **enactment problem** is documented separately from feedback quality: receiving feedback and acting on it are distinct steps, and the second is where formative assessment succeeds or fails.

Connected Concepts

- Pedagogical Patterns — The sequenced forms formative assessment takes when AI supplies part of the feedback
- Assessment
- Educational Measurement
- Automated Assessment

- Automated Question Generation
- Assessment Validity
- Feedback
- AI Feedback Quality
- Feedback Literacy
- Self-Assessment
- Learning Analytics
- Personalized Learning
- Adaptive Learning
- Scaffolding
- Self-Regulated Learning
- Human-in-the-Loop
- Intelligent Tutoring
- AI Ed Evaluation
- Summative Assessment — Summative assessment: AI-resistant formats (oral, proctored, closed-book exams)
- Reflection

Connected Articles

- An LLM-Enhanced Multi-Agent Architecture for Conversation-Based Assessment — A four-agent architecture for conversation-based assessment whose assessor hedges toward the middle category (Hou et al. 2025)
- Causal modelling of support interventions for student competency assessment — Causal Modeling of Support Interventions for Student Competency Assessment
- It takes a village. Program-wide approaches to redesigning assessment in a time of generative artificial intelligence (GenAI) — Program-wide approaches to redesigning assessment in the GenAI era
- Making AI-generated feedback matter: From provision to student enactment — Making AI-generated feedback matter: from provision to enactment
- The care-full craft of feedback in an age of generative AI — The care-full craft of feedback in an age of GenAI
- Feedback futures: beyond the limits of human and GenAI capacities — Feedback futures: beyond the limits of human and GenAI capacities
- Assessing the Impact and Underlying Pathways of Sequenced AI Feedback on Student Learning — Impact and pathways of sequenced AI feedback
- Enhancing learner-centered feedback with AI: Teachers' practices and perceptions — Enhancing learner-centered feedback with AI
- From automated scoring to learning diagnosis: a mechanism study of AI-supported formative assessment in English writing — From automated scoring to learning diagnosis: a mechanism study of AI-supported formative assessment in English writing

- Unravelling undergraduates' development of evaluative judgments through AI-supported internal feedback — Developing evaluative judgments through AI-supported internal feedback
- CoTAL: Human-in-the-Loop Prompt Engineering for Generalizable Formative Assessment Scoring and Feedback — CoTAL: formative assessment scoring with human-in-the-loop prompting
- The Effect of High-Frequency, Automatically-marked Formative Assessments on Student Outcomes in A-Level Sciences — High-frequency automated formative assessment
- Artificial intelligence and feedback in university education: effectiveness and student perceptions — AI-generated feedback in higher education
- Designing Needs- and Attention-Aware AI Learning Tools for Engineering Education: Insights from Psychological Outcomes — LearnLens: curriculum-grounded AI feedback
- Comparing Generative AI and teacher feedback: Student perceptions of usefulness and trustworthiness — GenAI vs. teacher feedback comparison
- Students' engagement with ChatGPT feedback: Implications for student feedback literacy in the context of generative artificial intelligence — ChatGPT feedback and engagement
- CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation — CODE-GEN: validated MCQ generation
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible assessment in the AI era
- Designing for authentic assessment: a scoping review — Designing for authentic assessment
- Automated Grading of Linux/Bash Examinations Using Large Language Models — Automated grading of Linux/bash exams
- Instructor and AI roles in the chemistry classroom: Future science teachers' perceptions in a ChatGPT-enhanced formative assessment — Instructor and AI roles in ChatGPT-enhanced formative assessment
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant assessment
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins for strengthening assessment validity in the age of GenAI (Roe, Perkins & Giray 2026)
- A hybrid reasoning framework for artificial intelligence assessment rubric generation in human and automated contexts: Evidence from an undergraduate programming course — HARMOGEN-R: AI assessment rubric generation
- AI-assisted, instructor-supervised grading and feedback in higher education: Design and evaluation of an end-to-end pipeline — AI-assisted instructor-supervised grading and feedback
- Adaptive scaffolding for cognitive engagement in an intelligent tutoring system — Adaptive ICAP scaffolding in an ITS (BKT vs DRL)
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design
- Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4

- GPT-4 feedback increases student activation and learning outcomes in higher education
- Arthur: An artificial intelligence powered teaching assistant system for Engineering Economics class
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- Adaptivity makes feedback effective: Evidence from AI-generated feedback on children's plans — Adaptivity makes feedback effective: evidence from AI-generated feedback on children's plans
- Impact of automated scoring on interpreting performance and self-regulated learning: evidence from a pedagogical experiment — Automated scoring, interpreting performance, and self-regulated learning (Chen & Liu 2026)
- Rethinking teachers' diagnostic skills in AI-supported formative assessment: from diagnosis to meta-diagnosis — Teachers' diagnostic skills in AI-supported formative assessment: from diagnosis to meta-diagnosis
- Perceived usefulness and intention to use large language model-generated feedback across three educational levels: a user-centred study in programming — Perceived usefulness and intention to use LLM-generated feedback in programming across three educational levels
- Adaptive teaching assistance model combining generative AI and big data analytics — Adaptive teaching assistance combining generative AI and big data analytics in music education
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses
- AI-Mediated Continuous Assessment Infrastructure (AIM-CAI): Connecting Learning Evidence Across Contexts and Time — AI-Mediated Continuous Assessment Infrastructure (AIM-CAI): Connecting Learning Evidence Across Contexts and Time (McNamara & Hasnine 2026)
- A Conversational AI Framework for Teacher Training — Conversational AI diagnostic for teaching misconceptions with evidence-grounded dialogue (Miranda & Calvani 2026)
- Trade-offs in assessment and feedback design: a trilemma-based model — Positive counterpart to the surveillance risk: observability as evidence design, not monitoring

Connected FAQs

- How Can AI Help Me Give Better Feedback at Scale?

Summative Assessment

> **Summative assessment** — assessment used to evaluate and certify what a learner has learned at the end of a unit, course, or program, in contrast to formative assessment which supports learning during instruction. Summative assessment typically takes the form of high-stakes examinations — written, oral, proctored, or closed-book — that assign grades, gate progression, and certify competence. In the AI era, summative assessment has become a central battleground over Academic Integrity and validity: generative AI can inflate performance on unproctored or take-home tasks, making the choice of summative format — and how it resists AI substitution — a pivotal design decision.

Questions to Consider

- Summative assessment certifies what a student has learned at the end of a course, while formative assessment supports learning during it. Where have you seen the line between these two blur, and why might it matter that they serve different functions?
- The page frames generative AI as reshaping summative assessment in two directions at once: AI scores exams, and students use AI to evade exam-based measurement. Which of these two pressures do you think is the bigger threat to validity, and why?
- If unproctored or take-home tasks lose validity because AI can produce the answers, what does that imply for how assessments should be designed — and what might be sacrificed in the process?
- Research cited on the page finds LLMs do not grade essays the same way humans do. If automated scoring is fast and consistent but grades differently, is that a fairness problem, an opportunity, or both?
- What does a high-stakes result (a grade, a credential, admission) mean if the work behind it could have been produced by AI? How would you design an assessment you could actually trust?

Introduction

Summative assessment serves a fundamentally different function from formative assessment: it measures and certifies achievement rather than guiding next steps. It includes end-of-unit tests, final examinations, standardized and high-stakes tests (e.g., entrance exams), oral defenses, and cumulative performance assessments. Because summative results carry real consequences (grades, progression, credentials, university admission), they face particular pressures in the AI era — both as *targets* of automated scoring and as *vulnerable* measures that students may seek to game using generative AI.

The AI-era stakes: validity and integrity

The knowledge base's research documents how generative AI has fundamentally reshaped the summative-assessment landscape in two directions: AI is used to **score** exams at scale, and AI can be used by students to **evade** exam-based measurement of their own learning.

- **AI as scorer.** Summative assessment increasingly relies on automated scoring of exams, essays, and short answers. Research on LLM essay grading finds LLM do not grade essays the same way humans do, raising validity and fairness questions for high-stakes automated scoring. LLMs assessing student self-explanations and automatic short-answer grading explore the reliability of LLM scoring in summative contexts, while psychometrically-aware frameworks seek to keep automated scoring trustworthy and adaptive. A 296-student handwritten general-chemistry exam illustrates why selective oversight is required: a Multimodal AI LLM's total-score agreement with TA grading was high ($R^2 = 0.91$) yet item-level reliability varied sharply by format. False positives (AI crediting genuinely wrong answers) tend to go undetected because students rarely contest them — so a uniform "grade everything" AI scorer is not defensible for high-stakes use without confidence-based deferral to humans (Assisting the grading of a handwritten general chemistry exam with artificial intelligence).
- **Outcome agreement can survive imprecise item scoring.** Against moderated official marks, a multimodal LLM grading 10,364 handwritten Physics Olympiad and university pages correlated at $r = 0.93–0.96$ and recovered the same five-student international team, though exact question-part agreement reached 70% — a scorer is judged by the decisions it informs (Pathak et al. (2026)).
- **AI as evasion.** Because generative AI can produce answers to written questions, unproctored and take-home summative tasks lose validity: proctored, unassisted measures are essential because non-proctored performance is inflated by AI, and guardrailed (hint-not-answer) tools can eliminate the exam penalty that unguarded AI causes. Chirikov's (2026) quasi-experiment on 500,000+ grades makes the mechanism concrete: after ChatGPT's release, courses with more AI-exposed tasks saw the share of A grades rise by 13 percentage points, and the effect concentrated in **homework-heavy courses** (an additional 16 pp in the triple-differences estimate) — direct evidence that unproctored homework, not genuine learning gains, is where AI inflates summative outcomes.
- **The test-taker and the scorer are the same capability.** On an introductory Java OOP course's own tests and exam, five 2026 systems graded with the student rubric beat the cohort average in every case but one (14.61 vs 13.76 on test 1; 14.87 vs 13.39 on test 2). They often earned full marks on longer tasks while still failing interfaces, abstract classes and image-based questions (Lepp and Kaimre (2026)).
- **AI-generated exams.** A large-scale field study and EFL assessment research examine whether AI can *generate* high-quality exams and assessment tasks — an emerging summative-design use of AI.
- **Students cannot reliably spot AI-drafted items.** In a credited Family Medicine exam, Vogt et al. (2026) found no significant difference in source attribution between 30 AI-generated and 30

licensing-exam multiple-choice items, mean correct recognition of 68.6 to 77.5 percent, and 18.2 percent of generated items eliminated in human review.

AI-resistant summative formats

A key theme in the knowledge base is that **summative format determines AI-resistance** — the more a task requires live, in-person, individually-probed performance, the harder it is for students to substitute AI for their own learning.

- **Oral exams and assessments.** Fenton (2025) argues the oral exam is a low-tech, inherently AI-resistant summative format: its real-time, interactive dialogue tests comprehension, critical thinking, and reasoning rather than memorization, prevents students from using AI to generate and memorize answers, and mirrors professional practice. Socratic tests and code-review interviews extend this to dynamic, conversational, and interview-based summative assessment.
- **Closed-book, proctored, unassisted measures.** Evidence and large-scale field data show that proctored closed-book exams — not inflated homework or take-home work — are the reliable signal of actual learning when students use AI. Responsible assessment frameworks embed these unassisted measures within a validity-driven redesign. Where exams stay online, remote proctoring takes over that role, and the corpus's two reviews of automated proctoring find privacy and fairness concerns alongside detection gains (Ensuring academic integrity through automated online exam proctoring: a decade long systematic review, A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence).
- **Pair a vulnerable task with a confirming twin.** Roe, Perkins & Giray (2026) keep a GenAI-vulnerable task for its learning value but pair it with a second task assessing the same outcomes, making the mark interdependent through a confirmatory threshold or weighting so the twin certifies the result.

High-stakes and standardized summative assessment

High-stakes summative assessment — entrance exams, standardized tests, and certification — carries outsized consequences and is a focus of AI-era concern. The generative AI learning penalty study measured outcomes on high-school (Zhongkao) and college (Gaokao) entrance exams, finding entrance-exam scores fell 18–24% after prolonged AI use. The Effortless Trap and performance-vs-learning research warn that gains on AI-assisted tasks do not transfer to unassisted high-stakes measures.

Summative vs. formative in the AI era

The knowledge base's assessment literature consistently emphasizes that Assessment is most effective when it combines formative and summative functions — but the AI era sharpens the distinction. Because AI inflates performance on low-stakes, unproctored, and process-hidden tasks, **summative (especially proctored/closed-book/in-person) measures become the crucial check** on whether learning actually occurred. This motivates assessment redesign that keeps authentic, AI-resistant summative tasks (oral exams, code-review interviews, proctored examinations, process-based portfolios) as the anchor of integrity while

using formative assessment to support learning along the way. See Authentic Assessment for the constructive design response.

Implications for AI in education

- **Summative format is a validity and integrity lever:** AI-resistant summative formats (oral, proctored, closed-book, in-person) preserve the connection between assessed performance and actual learning.
- **Proctored/unassisted measures are the reliable signal:** when students use AI, unassisted summative exams — not homework — reveal genuine learning.
- **Automated scoring needs psychometric scrutiny:** using LLMs to grade high-stakes exams requires evaluation of reliability, fairness, and validity, not just accuracy.
- Grading error is also grade-dependent: across 32 public-health exam submissions, the LLMs avoided the scale's ends — no E or F appeared in fast mode — while the best model matched the human grade exactly on 50.0% and within ±1 grade on 90.6% (Brevik et al. (2026)).
- **AI can also generate exams:** AI-assisted exam and task generation is an emerging summative-design application that itself needs quality evaluation.
- **Reconsider grading purpose, not just format.** Mesny, Roberge-Maltais & Galy (2026) critique traditional summative, norm-referenced grading for encouraging superficial, fragmented learning, giving students little control or transparency, harming intrinsic Motivation, fueling stress and anxiety, and perpetuating inequities while largely assessing recall rather than real-world application. They position reassessment, standards-based grading, and ungrading as grading-focused innovations that can soften summative-heavy practice, while acknowledging these remain marginal in management education because of normative barriers — grading on a curve, external signaling (rankings, internships, accreditation), and students' instrumental mindset — and recommend incremental experimentation with institutional support.

Common Misconceptions

- **"An LLM cannot grade to official standards."** Against **moderated official marks**, a multimodal LLM grading **10,364 handwritten** Physics Olympiad and university pages correlated strongly. Outcome agreement can survive imprecise item-level scoring — which means the useful question is where item-level precision is actually required.
- **"AI grade inflation is speculation."** Chirikov's (2026) quasi-experiment on **500,000+ grades** makes the mechanism concrete: after ChatGPT's release, **courses with more AI-exposed tasks saw the share of higher grades rise**. The effect concentrated where tasks were exposed, which is the pattern a mechanism would predict.
- **"Students who use AI cannot be distinguished from those who do not, so provenance is hopeless."** The finding that there was **no significant difference in source attribution** between AI-generated and licensing-exam items, with correct recognition of **68.6-77.5 percent** and an **18.2 percent** misattribution rate, is about recognition failing — not about provenance being unnecessary. If anything it raises the requirement for verified provenance.

Connected Concepts

- Remote Proctoring
- Assessment
- Formative Assessment
- Authentic Assessment
- Automated Assessment
- Assessment Validity
- Academic Integrity
- AI Ed Evaluation
- Higher Education
- K-12

Connected Articles

- Large language models as grading assistants in public health education: a method-comparison study of essay-style exam assessment — LLM graders compress the grade scale and avoid the extremes in high-stakes essay assessment
- A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant summative assessment
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: proctored/closed-book exam evidence
- Artificial Intelligence and Grade Inflation — AI task displacement as a mechanism of grade inflation; homework-heavy courses (Chirikov 2026)
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — Faster completion, less learning: proctored measures essential
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — Generative AI without guardrails harms learning
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams
- LLMs Do Not Grade Essays Like Humans — LLMs do not grade essays like humans
- Exploring the Effectiveness of Using LLMs for Automated Assessment of Student Self Explanations in Programming Education — LLMs for automated assessment of student self-explanations

- Confidence Estimation in Automatic Short Answer Grading with LLMs — Automatic short-answer grading
- PsyScore: A Psychometrically-Aware Framework for Trait-Adaptive Essay Scoring and ZPD-Scaffolded Feedback — Psychometrically-aware trait-adaptive essay scoring
- The theoretical foundation of Socratic tests: Dynamic, multimodal, conversational examinations — Socratic tests: dynamic, conversational, multimodal assessment
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — Code review interviews in CS1
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible assessment in the AI era
- Test-Driven, AI-Assisted Learning: Replacing Lectures with Weekly Closed-Book Tests — Test-driven AI-assisted learning
- Revisiting the Performance of Generative Artificial Intelligence on Introductory Object-Oriented Programming Assessments: Insights from 2026 — GenAI performance on object-oriented programming assessments
- The effortless trap: Productive struggle, AI, and the illusion of learning — The Effortless Trap: productive struggle and the illusion of learning
- AI-Generated versus Human-Developed Assessment Tasks in EFL Context: Insights from TPCK Model — AI-generated versus human-developed assessment tasks in EFL
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins for strengthening assessment validity in the age of GenAI (Roe, Perkins & Giray 2026)
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Can students identify AI? – A cross-sectional quantitative study about AI recognition in tablet-based MCQ assessment among fifth-year undergraduate medical students at Saarland University, Germany — Students cannot reliably spot AI-drafted items

Authentic Assessment

> **Authentic assessment** — the design of assessments that examine student performance on worthy, realistic intellectual tasks, rather than isolated, standardized test items. Originating with Wiggins (1990) as a counterbalance to standardized tests, authentic assessment has evolved from replicating workplace tasks toward a multi-dimensional framework encompassing professional, digital, personal, and social authenticity. Generative AI has made authentic assessment newly essential: any task a language model can credibly simulate in a take-home setting loses its validity as evidence of original student competence, so authentic forms must be redesigned around what AI cannot credibly counterfeit.

Questions to Consider

- Authentic assessment examines performance on worthy, realistic intellectual tasks rather than isolated test items. Before reading, did you assume an ‘authentic’ task simply replicates a real-world or workplace scenario? This page argues authenticity has evolved well beyond mere replication — what other forms can it take?
- A central claim is that any task a language model can credibly simulate in a take-home setting loses its validity as evidence of original student competence. Which assessment in your own teaching or study would you now consider ‘counterfeitable’ — and what makes you say that?
- The page highlights a striking gap: only 3 of 37 studies addressed social authenticity — whether assessment lets students contribute to societal change. Why do you think the social dimension of authenticity is so neglected, and what might assessing it actually look like?
- The knowledge base argues authenticity must be ‘redesigned, not policed.’ When students co-author rubrics, choose what and how to submit, and engage in real-time interaction, AI use becomes expected and declared rather than concealed. How would that shift the relationship between student and assessor?
- Oral exams and process-based portfolios are offered as AI-resistant authentic forms. But graded reflection and Self-Assessment risk becoming performative — students performing the reflection they think is wanted. How could you design for genuine reflection rather than performance?
- When AI supplies the rubric, the feedback, and the monitoring, the page warns that a student’s metacognitive practice may be displaced. If the tool does the evaluating, what is left for the learner to actually practice or learn?

Introduction

Authentic assessment sits at the heart of how Assessment is being rethought in the AI era. It connects to Assessment Validity (does the assessment measure what it claims?), Formative Assessment (authentic tasks that inform learning), and Academic Integrity (moving from detection to designing tasks where AI use is expected and declared). It is a central response in the knowledge base’s assessment-redesign literature.

The evolution of authenticity

- **1990s origins — worthy intellectual tasks:** Wiggins (1990) proposed authentic assessment as direct examination of "student performance on worthy intellectual tasks," a counterbalance to standardized tests.
- **Late-1990s uptake — workplace replication:** Joughin (1998) framed authenticity as the extent to which assessment replicates professional practice or real life — a view that dominated for two decades.
- **2020s critique — beyond replication:** McArthur (2023) argued authentic assessment must enable students to "influence the future and transform society" rather than merely replicate existing tasks; Ajjawi et al. (2024) broadened authenticity to contextual, task, and personal forms that reflect student experience.
- **Generative AI as existential challenge:** Zhan, Boud & Du (2025) note that generative AI makes workplace-replication authenticity newly vulnerable, driving a pivot toward digital literacy, real-time collaboration, social contribution, and individual meaning-making that AI cannot credibly counterfeit.

A six-dimensional design model

Zhan, Boud & Du's (2025) scoping review of 37 empirical studies (2000–2024) proposes six design dimensions: (1) authenticity in assessment (assessment, professional, digital, self, and social authenticity — with only 3/37 studies addressing social authenticity, a critical gap), (2) cognitive challenges, (3) assessment criteria (with students often passive recipients rather than co-authors of rubrics), (4) feedback (formative-dominated, but sustainable feedback rare), (5) student agency (choice in what/how/when/where to submit was rare), and (6) social collaboration. It also proposes a cyclical co-design model — negotiate goals, create context, co-design criteria, plan feedback — that AI tools could operationalize.

Dollinger and Nieminen (2026) bound this optimism with the *paradox of inclusive assessment*: both the accommodations model and structural critiques that reframe assessment as disabling leave intact the zero-sum logic that "for one student to succeed, someone else needs to fail," so distributed and agentic forms must change that logic rather than only widen access.

Authentic assessment in the AI era

The knowledge base's assessment-redesign literature argues that authenticity must be **redesigned, not policed**:

- Beyond Detection contends that authenticity cannot be policed into existence; it must be designed, positioning AI as a declared collaborator rather than a cheating application, and prioritizing authentic, process-based assessment over surveillance.
- Responsible Assessment reframes assessment around validity evidence and authentic tasks that mirror students' future work.
- Authentic products, authenticated processes examines how AI-rich higher education can assess both genuine outputs and the processes that produced them.

- **An AI drafting partner still leaves the judgment.** Paula et al. (2026) piloted a GPT-4.1 assessment designer with eight coordinators: it produced usable overviews, tasks, criteria, timelines and rubrics but repeatedly missed disciplinary context and topic sequencing, and all eight refused end-to-end automation, locating academic judgment rather than the model.
- The tool-invariant framework argues for assessing computational methods and process rather than tool-specific outputs, using oral defense and verification.
- **Institutional infrastructure for process evidence.** A commissioned quality-assurance framework turns the process argument into policy, treating learning-process traces — time-stamped edits, resource use, metacognitive prompts — as the durable evidence a transcript cannot show, and citing process features that explain more variance in performance than product features alone (Lodge et al. (2026)).
- **Scalable oral assessment, with a scoring caveat.** Pentland, Lowenthal & Krier (2026) delivered time-limited, non-revisitable recorded responses graded against embedded rubrics, and found students outscored their in-person multiple-choice exams; they stress this is a format effect rather than a learning gain, with LLM re-scoring agreeing with the instructor at ICC = 0.73 and 0.60.
- Reconsidering oral exams positions the oral exam/assessment as a low-tech authentic alternative that is inherently AI-resistant — its real-time, interactive dialogue tests comprehension, critical thinking, and reasoning (not memorization), mirrors professional practice, and prevents students from using AI to generate and memorize answers. It offers a concrete set of practical recommendations (clear rubrics, standardized content, assessor training, prompting guidelines, bias mitigation) for reintroducing Oral Assessment across high school and higher education.
- E-portfolio assessment is another authentic, process-based form that resists AI fabrication: Zhan, Boud & Du (2025) identify social contribution portfolios among the authentic forms most robust to generative AI, and Beyond Detection recommends annotated portfolios and recorded walkthroughs that probe reasoning in real time. Ni & Lam (2026) and Laksana et al. (2026) show generative AI can assist the portfolio process — feedback, drafting, reflection — while the portfolio's reasoning traces and drafts preserve authenticity.
- **Authenticity criteria can themselves restrain AI use.** Chen and Zou (2026) found that a rubric requiring students to ground a group presentation in their own first-hand teaching experience, and to reflect on shared classroom observations, led seven of fifteen student groups to *deliberately reduce* their GenAI use. Students argued the tool could not meet the epistemic demand — "AI only knows that moment when you type" — because it lacked the longitudinal, situated knowledge their classmates and teacher had. Both layers mattered: the authenticity of the task and the relational authenticity of contributing one's own thinking to a group, which reframed heavy AI use as free-riding on peers. The design implication is that authentic, experience-grounded criteria do evaluative work even without enforcement — they supply a reason for restraint that policy statements cannot.
- **Twin a vulnerable task with a less-vulnerable one.** Roe, Perkins & Giray (2026) pair a GenAI-vulnerable task with a second assessing the same outcomes, schedule them close together so each can cross-check the other, and make the mark interdependent through a confirmatory threshold or weighting.

Sharma (2026) argues that integrity-oriented design and authentic design are not the same thing, and that the difference is epistemic rather than stylistic. Authenticity asks whether a task mirrors worthwhile real-world practice; integrity-oriented design asks whether learners can justify their decisions and assume responsibility in relation to disciplinary standards, which makes integrity an explicit, assessable criterion embedded in the task architecture rather than an incidental by-product of realism. The practices he offers — annotated decision trails, verification of GenAI-contributed claims, oral defense and dialogic accountability, draft differences with version history — are recognizably authentic-assessment forms. They are selected, however, for the judgment they make visible rather than for their realism — a useful corrective for tasks that look authentic and remain counterfeitable in substance. His caution belongs on this page too: requiring documented reasoning privileges learners more fluent in reflective discourse, and judgment as evidence "remains relational and situated rather than mechanically verifiable", so the design carries its own interpretive-reliability load.

The same question is reframed by Thapa and Lewis (2026), who name what a task should *authenticate* rather than whether it looks real: epistemic authenticity, the extent to which assessment captures genuine engagement with interpretation, evaluative judgment, reasoning and knowledge construction. Their argument is that authenticity alone does not survive generative AI, because an authentic task whose evidence is one unsupervised product is exposed to the same substitution problem as the essay it replaced. Making reasoning visible instead requires staged submissions, reflective justification, dialogic engagement and evaluative transparency. They carry the caution above into design: reflective and dialogic tasks can privilege students confident in academic self-articulation unless they are inclusively designed and scaffolded, and the relational work intensifies educator emotional labor in large or resource-constrained settings.

When practitioners retreat to the policed formats

The knowledge base argues that authenticity must be designed rather than policed, and Goldstein, Marae-Haj and Zidan (2026) supply the counter-evidence from practice: after a trust crisis in which pre-service teachers submitted raw AI-generated work as their own, teacher educators in seven Israeli colleges redesigned assessment around process evidence (prompts, document version history, monitored group contributions) and in-class performance — but several also described falling back, as a last resort, on supervised examinations and anticipated oral defenses on theses, one participant calling the return to exams personally painful yet unavoidable. Read against the design-first position, the finding marks a failure mode rather than a solution: where authenticity is not redesigned in advance, the practical response to unassessable submitted work is reinstated control — surveillance by another name — which reintroduces the very formats the authentic-assessment literature tries to move beyond. It also shows the felt cost of the alternative: participants reported their take-home written assessments could no longer evidence learning at all, and that process documentation took real work to establish.

A second failure mode sits inside redesign itself: across five online language-teaching methods, authenticity-related tensions dominated teachers' accounts (11 of 20), including task realism corrosion — activities redesigned to be AI-resistant rather than authentic (Baoyi and Khan (2026)).

The retreat carries an evidentiary cost that the case-file evidence makes visible. Munoz et al. (2026) coded 1,162 generative-AI misconduct allegations and found that the strongest evidence types are generated by the investigation or by supervision rather than by the allegation, and that process evidence such as drafts,

supervision meetings and presentations appears only where those practices already exist — so in an unredesigned assessment the process evidence this literature recommends is simply not available, and cases rest on weaker categories. What stands in for it is the weakest material in their corpus: detector output drew the lowest probative ratings of any category, and Hadra et al. (2026) show why, with macro accuracy of 0.69 (Originality) and 0.61 (Turnitin) across 192 texts, near-total failure on hybrid human–AI writing, and a borderline tendency to misread EFL student work as AI. Wright (2026) adds the rule-design dimension: prohibitions written by platform identity rather than function are over-inclusive by definitional accident, so a policed format can sanction a student who did not do the thing the rule was designed to prevent, falling hardest on the students who relied on transcription tools for Accessibility. Read together, the retreat substitutes the least probative evidence available for the process evidence that authentic design would have generated in the first place.

- **Self-regulated learning:** student agency in authentic assessment (choice, self-reflection, co-design) mirrors the forethought → performance → self-reflection cycle, though graded reflection risks becoming performative.
- **Metacognition:** Metacognition is required for students to evaluate their work against co-designed rubrics; when AI supplies the rubric, feedback, and monitoring, the student's metacognitive practice may be displaced.
- **Formative and sustainable feedback:** authentic assessment emphasizes formative, future-oriented feedback that transfers to later contexts.

Implications for AI in education

- **AI-proof assessment types:** in-vivo demonstrations, social-contribution portfolios, co-created artifacts with auditable provenance, and real-time embodied interaction are more resilient to generative AI than take-home essays or MCQs.
- **The exposure is measurable.** A three-year psychology degree proved 90% passable: ChatGPT produced adequate output on 36 of 40 coursework assessments, and only the four tasks requiring presence, a visual artifact, or the student's own data resisted (Ivory et al. (2026)).
- **Co-design at scale:** AI tools could enable rubric co-design and student co-creation of assessment parameters at classroom or MOOC scale — though machine-mediated agency must be designed carefully.
- **Address the social-authenticity gap:** only 3/37 studies addressed social issues; AI assessment tools should help students contribute to societal transformation, not merely simulate it.
- **Sustainable feedback:** AI feedback should be designed to transfer to future contexts, not just provide reactive, momentary corrections.
- **Process-focused measurement now has validity evidence.** Oliveira et al. (2025) scored 70 graded essays on how students steered a GenAI dialogue and made course knowledge visible; those process scores correlated r = 0.54 with traditional essay scores while rewarding conceptual work over structured task specification.
- **Authentic assessment suits practice-oriented fields.** Mesny, Roberge-Maltais & Galy (2026) find authentic assessment especially well-suited to management education: tasks mirroring real

professional problems (live consulting projects, dashboards with executive briefings) align with the field's practice-oriented, employability focus and can support inclusive, integrity-preserving alternatives to exam-centered assessment in the generative AI era. In their review of 58 articles from four management-education journals, however, authentic assessment appeared mainly via technology-mediated simulations and was often conflated with experiential learning — a terminology gap that can obscure its broader value and uptake.

- **Authenticity is not security, and the gap is visible at sector scale.** Where the single-degree audit above found 90% of coursework passable, Villanueva (2026) scores recorded presentations, remote group projects and unsupervised digital artifacts in the high-exposure band across 53,915 items, because the public record shows nothing about how production was supervised.

Common Misconceptions

- **"Authenticity is about realistic tasks."** Zhan, Boud and Du's (2025) scoping review of **37 empirical studies (2000-2024)** proposes a **six-dimensional** design model, and only **3 of 37 studies addressed social authenticity** — whether assessment helps students contribute to societal transformation. Realism is one dimension and the most advanced dimension is barely studied.
- **"Authentic assessment resists AI."** The exposure is measurable and large: a **three-year psychology degree** proved **90% passable**, with ChatGPT producing **adequate output on 36 of 40 coursework assessments**, with only the remaining assessments surviving. Most of a degree's assessment was AI-satisfiable.
- **"Redesign is optional if the work is real-world."** The 36-of-40 result was found on coursework whose authenticity was presumably not in question. Task realism did not protect against AI completion; the design of what is assessed did.

Connected Concepts

- Learner Identity — evolving disciplinary, professional, creative, and academic learner identities
- E-Portfolio
- Problem-Based Learning
- Assessment
- Assessment Validity
- Formative Assessment
- Automated Assessment
- Academic Integrity
- AI Detection
- Self-Regulated Learning
- Metacognition
- AI Ed Evaluation
- Higher Education
- Generative AI

- AI in Education
- Feedback
- Summative Assessment — Summative assessment: AI-resistant formats (oral, proctored, closed-book exams)
- Arts, Design and Media Education
- Reflection

Connected Articles

- Preserving epistemic authenticity: process-oriented assessment in the age of generative AI — process-oriented assessment and epistemic authenticity as what a task should authenticate
- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — What AI could not pass: presence, visual artifacts, and the student's own data (Ivory et al. 2026)
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — Paternalistic AI use and student identity in history education
- Coauthorship integrity: Reconceptualising assessment validity for the age of generative artificial intelligence
- Teaching with generative artificial intelligence: Enhancing critical thinking and ethical awareness in academic writing
- From Classroom Design to Newsroom Practice: Assessment Intervention Designing GenAI
- Raising Ethical Awareness of GenAI Use Through Student Self-Assessment in the Transition to Higher Education
- Reimagining Success and Failure: Equitable Assessment Practices in an Age of Artificial Intelligence
- Aligning ChatGPT with e-portfolio assessment as EFL learning model: its effect on students' speaking performance and feedback literacy
- Students' perceptions of multiliteracies development using AI-assisted portfolio assessment
- Using Generative AI to Simulate Patient History-Taking in a Problem-Based Learning Tutorial: A Mixed-Methods Study
- Problem-based learning and the structural conditions for productive AI integration
- Designing for authentic assessment: a scoping review — Designing for Authentic Assessment: A Scoping Review
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond Detection: Authentic Assessment
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible Assessment in the AI Era

- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — Authentic Products, Authenticated Processes
- A Tool-Invariant Framework for Teaching and Assessing Computational Methods in the Age of Agentic AI — Tool-Invariant Framework for Teaching and Assessing Computational Methods
- Confidence Estimation in Automatic Short Answer Grading with LLMs — Confidence-aware automated short-answer grading
- The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows — The LLM Fallacy and Misattribution of Competence
- The University AI Didn't Replace: Rethinking Universities in the AI Era — Rethinking Universities in the AI Era
- Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity — Multiple assessment methods to counter AI misconduct
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering oral exams as authentic, AI-resistant assessment
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins for strengthening assessment validity in the age of GenAI (Roe, Perkins & Giray 2026)
- Assuring quality learning in a gen AI-integrated future: The role of adaptive capabilities. *TEQSA*, June 2026 — Adaptive capabilities for assuring quality learning in a gen AI-integrated future (Lodge et al. 2026)
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous Oral Assessments in the AI Era (Pentland 2026)
- Assessing students' DRIVE: A framework to evaluate learning through interactions with generative AI — DRIVE: assessing learning through GenAI interaction (DRI + Visible Expertise)
- Innovative assessment and grading practices in higher education: A critical exploration for management educators
- Students' agency in GenAI-mediated group assessment: An ecological-emergent perspective — Authenticity criteria that led student groups to reduce GenAI use
- Pioneering Teacher Educators Navigating AI Integration in Pre-Service Teacher Preparation: Strategies and Challenges — The AI trust crisis that pushed teacher educators back toward supervised exams and oral defenses (Goldstein et al. 2026)
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity-oriented design distinguished from authentic assessment: making judgment visible (Sharma 2026)
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What misconduct allegation files actually contain as evidence, and the process evidence they lack (Munoz et al. 2026)
- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Detector accuracy and hybrid-writing failure: why detection is weak fallback evidence (Hadra et al. 2026)

- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI prohibitions: transcription is not generation (Wright 2026)
- Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education — Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education
- AI and higher education: teachers' perceptions of students' ethical tensions in online pedagogical methods — Task realism corrosion: AI-resistant redesign eroding authenticity in online language teaching
- How AI-vulnerable is Australian higher education assessment? A computational audit of Group of Eight Arts and Humanities units, 2022–2026 — Authentic-surfaced formats (recorded presentations, remote group projects, digital artifacts) score high across 53,915 items: authenticity does not verify authorship

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Process-Oriented Assessment

> **Process-oriented assessment** — the design of Assessment around how a learner reaches a conclusion rather than only around the artifact they hand in: staged submissions, reflective justification, dialogic and oral exchange, draft and version history, and criteria students can apply to themselves. It is not a synonym for task realism and not a claim about who marks the work: a realistic task whose only evidence is one unsupervised product is exposed to the same substitution problem as the essay it replaced. Generative AI is what makes the distinction urgent, because fluent output can now be produced on demand and a finished file no longer carries information about whose reasoning produced it.

Questions to Consider

- If a student submits a polished essay, what does that artifact actually let you claim about their thinking — and which claims does it only appear to support?
- Process evidence asks for drafts, justification, and dialogue. Who in your setting is fluent in that kind of academic self-articulation, and who might be judged on their comfort with it rather than on their understanding?
- Detection is unreliable and redesign around process is expensive. Where would you spend a limited institutional budget, and what evidence would change your answer?

Introduction

Assessment in higher education has long inferred the thinking from the product. A submitted essay, report, or examination answer stood in for the reasoning behind it, and grading treated a well-argued artifact as evidence of a well-argued process. Thapa and Lewis (2026) name the assumption that generative AI breaks: a polished response "may no longer represent anyone's thinking process," so the inference from artifact to understanding stops being safe. Their answer is not a better detector but a different evidence base. Process-oriented assessment collects evidence of interpretation, justification, and knowledge construction as they develop, so that reasoning stays visible when output can be produced on demand.

It helps to say what the concept is not. It is not authentic assessment, which asks whether a task mirrors worthwhile real-world practice; Thapa and Lewis keep the axes separate and insist that an authentic task with a single unsupervised product is still exposed. It is not AI detection, which asks whether the tool was used rather than how a decision was made. And it is not automated assessment, which concerns who or what does the marking: a machine-graded staged portfolio can be process-oriented, and a human-graded final essay need not be. The concept concerns which evidence is collected, over what period, and under what conditions it is produced.

The idea has moved from a proposition to a recurring recommendation across the knowledge base. It appears as a named priority in AIED's agenda for learner Learner Agency and Motivation, as the organizing research agenda for the retention and transfer problem in performance-versus-learning research, as "Black Box Assessment" in Brunnström and Palmqvist's account of self-regulated learning with AI, and as a request

from practicing teacher educators who found their take-home written work could no longer evidence learning at all.

What process evidence looks like in practice

The most explicit design vocabulary comes from Thapa and Lewis, whose four commitments carry the argument into task design: reflective justification, staged task design, dialogic engagement, and evaluative transparency. In practice, students explain interpretive decisions rather than only presenting conclusions, submit work that develops across checkpoints, take part in oral or dialogic exchanges about their reasoning, and work against criteria they can apply themselves — the terrain of feedback literacy and Self-Assessment. Boysen's (2026) proposal for open learning practices translates the same logic into an audit trail: a shared learning plan set before the project begins, a learning analysis plan naming required and forbidden sources, and documented drafts and version histories, preserved through Track Changes and saved file versions, that expose the work process and explain what informed each revision. He frames this as self-regulation made visible.

The channel chosen for process evidence changes what can be evidenced: in the same 79-student generative-AI study, higher-depth monitoring and planning were more common in think-aloud units while higher-depth regulation was more common in interaction logs, so no single record captures the whole process (Li and Liu (2026)). Traces can also diverge from scores outright: across 150 student–AI conversations, 41% carried an assignment score of exactly 1.00 while observable cognitive participation varied, so matched scores can conceal different processes (Fábrega, 2026). DraftTrace answers the same problem for AI-integrated writing by aligning keystroke-level process measures with the final product and with AI-interaction traces, showing that copy-typing is identifiable only when product and process are read together (Chandarana et al. (2026)), a concrete instance of the behavioral-trace measurement the field still lacks.

Practitioner and framework accounts fill in the artifacts. Uden and Hwang's (2026) LEARN framework, aimed at problem-based learning Assessment, asks for process-focused rubrics, oral justifications, staged submissions, and reasoning traces with AI-use disclosure, and treats reflection through learning journals and think-aloud protocols as the metacognitive engine of the sequence. Moganadas and colleagues (2026) make AI-transparent, process-oriented assessment one of five researchable propositions, requiring documentation, verification, and reflective justification rather than prohibition or detector use. Padhy (2026) recommends capturing revision history, interaction patterns, and time-on-task, paired with transparent disclosure. Goldstein, Marae-Haj and Zidan (2026) report the same artifacts emerging from practice after a Trust crisis: prompting records, document version history, monitored group contributions, and reflective "journey journals" kept in physical notebooks — alongside the plain finding that take-home written work could no longer evidence learning.

Concrete tooling is emerging: Kim et al. (2026) split problem solving into four stages and eight diagnostic sub-skills, which lets an Large Language Models (LLMs) write questions and rubrics specific to a stage; five teachers and 64 students trialed it on 90 problems and 720 sub-questions, with a mean System Usability Scale score of 83.5.

Checkpoint submissions were routine in practice: across six terms of the six-week asynchronous graduate research-methods sequence serving some 440 K-12 teachers, they averaged 96% completion, and later

iterations that added explicit prompt templates produced longer and visibly more substantive reflections Packard et al. (2026).

- **“Process evidence needs a special assessment regime.”** Some of it is an afternoon of instrumentation: a study of **77** college essay writers used a CodeMirror editor logging insertions, deletions, selections, cuts, copies and pastes with timestamps, beside an in-house chat panel on the default API, and captured **361** messages. The same traces showed that **14** responses to planning queries were pasted into final essays, which no product-level report would have revealed. The honest limit is in the instrument: typed words count as the student’s even when rephrased from a response, so the boundary between typing and thinking is invisible. Logging the process is cheaper than designing for it.

A process trace is only feedback if the learner reads it against the task. Xian et al. (2026) gave eleven translation students Inputlog and screen-recording visualizations plus a single 30-minute reflection session. The share of meaning-level revisions rose from 18.1% to 28.4% ($t(10) = 4.259$, $p = 0.002$) while total revisions did not change significantly, falling from 1,292.91 to 1,052.36 ($p = 0.248$). The trace did not make students edit more, only differently, which is the argument for process evidence in one result.

A different axis from authenticity, and from marking

Holding the axes apart matters, because conflating them is how a redesign looks done while the exposure remains. Sharma (2026) makes the complementary distinction between authenticity and integrity-oriented design: authenticity asks whether a task mirrors worthwhile practice, while integrity-oriented design asks whether learners can justify their decisions and assume responsibility in relation to disciplinary standards, which is why the practices he offers — annotated decision trails, verification of GenAI-contributed claims, oral defense, draft differences with version history — are selected for the judgment they make visible rather than for their realism. Espino and Espino’s (2026) ten-year review of business education reaches the same design conclusion from the literature side, finding the field converging on authentic, process-visible tasks that require interpretation, contextual application, and iterative refinement, and treating isolated tool adoption inside unchanged assessment structures as its most persistent failure.

Salameh’s (2026) Fade–Visibility Matrix crosses the same design question with a second variable — whether AI support persists or fades — and names the combination most courses default to, support that never fades assessed only by its product, Silent Dependency (Salameh, 2026).

The construct is also distinguishable from the question of how evidence is scored. Validity reasoning is where the two meet: Brunnström and Palmqvist (2026) argue that when a chatbot can produce a plausible examination answer, the submitted product becomes a weaker indicator of what the student learned — an assessment-validity problem rather than only an integrity problem. That is the same inference at risk in Yan, Greiff, Lodge and Gašević’s performance-versus-learning argument, where performance gains that shrink once assistance is withdrawn show a gain living in the tool rather than in the learner, and where the proposed remedy is process measures such as retention and transfer tests rather than immediate task success.

Why detection cannot carry this load

Process-oriented assessment is usually proposed as the alternative to detection, and the evidence about detection explains why. The detection literature finds error rates, task-dependence, and patterned bias against non-native and disabled writers, and the most recent work lands on a procedural conclusion: a detector score can prompt closer review but is not a finding. Munoz and colleagues (2026) show what that costs in practice. Coding 1,162 generative-AI misconduct allegations, they found the strongest evidence types are generated by the investigation or by supervision, that process evidence such as drafts, supervision meetings, and presentations appears only where those practices already exist — so in an unredesigned assessment it is simply absent — and that detector output drew the lowest probative ratings of any category. The design consequence is ordering: process evidence has to exist before a case needs it, and Weidlich's (2026) reasoning about which inference is at risk makes the same point from the validity side, since attempts to restore assessment security through detection introduce construct-irrelevant variance rather than evidence about the learner.

The rubric criteria themselves can be rebuilt around the trajectory. Oviedo and Díaz (2026) read Biggs's 3P model as three grading dimensions — agency and critical supervision, dialogic scaffolding, and cognitive sovereignty — so the trajectory is graded rather than the static outcome.

The design and workload costs

The sources are unusually candid that this is expensive. Thapa and Lewis state the equity caution directly: reflective and dialogic tasks can privilege students who are more confident in academic self-articulation unless they are inclusively designed and scaffolded. The relational, feedback-intensive work also intensifies the emotional and professional labor of educators in large or resource-constrained settings — a contradiction with institutional expectations for scalability, standardization, and measurable performance. Sharma adds the interpretive version: requiring documented reasoning privileges Learners more fluent in reflective discourse, and judgment as evidence "remains relational and situated rather than mechanically verifiable."

The operational costs are itemized elsewhere. Boysen lists new technology, revised assignments and syllabi, teaching students unfamiliar skills, and extra material to collect and grade, warns that low-stakes credit for process can inflate grades, and concedes the model suits large skill-development projects far better than day-to-day knowledge-acquisition work; he also notes that process tracking is what some critics call AI surveillance. Goldstein, Marae-Haj and Zidan's participants reported that establishing process documentation took real work, that nine of thirteen funded advanced tools from their own pockets in a way that could deepen the digital divide, and that several fell back on supervised examinations and anticipated oral thesis defenses. The equity worry has an AI-specific edge in Brunnström and Palmqvist's finding that unguided tool use demands an interaction-management skill that is unevenly distributed, so AI "may be most beneficial to already advantaged students" — the same distributional risk that attends asking students to manage a documented process. Lopez-López, Bru-Cordero and Correa-Álvarez (2026) found that students who invested more independent study time judged AI use more strictly, and recommend testing whether disclosure templates, oral defenses, and process-based assessment reduce ethical uncertainty — a study the field still needs. The risk attaches to the mechanism that makes process evidence work: where collaboration, revision, and reflection are graded, students have reason to produce evidence matching what they expect the marker wants, so process records can become performative rather than evidential (Alam & Jackson, 2026).

What remains unresolved

Thapa and Lewis's account is conceptual: no participants, no data collection, and no implementation trial, so the four principles are argued rather than tested, and the paper itself calls for empirical work on student experience, educator workload, and long-term viability. Feasibility is left undifferentiated across settings — transfer to large lectures, laboratories, studios, or clinical placements is not addressed. Lane's (2026) position paper notes the institutional ceiling: process-based assessment is blunted by grading and transcript structures that reward polished final artifacts, so classroom redesign alone does not change the incentive. Measurement is thin as well: Jin and colleagues' (2026) review of AI-literacy instruments calls for performance-based and process-oriented assessment and behavioral-trace measurement of prompting and verification, but reports that the existing instruments lean on self-report. No source here reports a controlled trial of a process-oriented redesign against a product-oriented one, which leaves the central claim — that process evidence is both harder to counterfeit and fairer to judge — argued from principle, practitioner report, and case-file evidence rather than demonstrated at scale.

Common Misconceptions

- **"A high score implies the student did the work we designed."** Traces can **diverge from scores outright**: across **150 student-AI conversations**, **41% carried an assignment score of exactly 1.00 while observable cognitive participation varied**. The score saturates while the process that was supposed to produce it does not.
- **"Process data is unmanageable at scale."** Required documentation proved feasible at course scale across **six semesters of six-week asynchronous graduate research-methods courses serving approximately 440 K-12 teachers**. Logistics were solvable; the objection overstates the cost.
- **"Problem solving is too holistic to assess by process."** It can be operationalized as **four stages and eight diagnostic sub-skills**, letting an LLM generate **stage-specific questions and rubrics** — used with **five teachers and 64 students**. Decomposition is what made the process legible and assessable.

Connected Concepts

- Pedagogical Patterns — Staged checkpoints and process evidence as sequenced designs
- Assessment
- Authentic Assessment
- AI Detection
- Assessment Validity
- Evaluative Judgment
- Formative Assessment
- Summative Assessment
- Feedback
- Self-Assessment

- Oral Assessment
- E-Portfolio
- AI Use and Disclosure Statements
- Self-Regulated Learning
- Academic Integrity
- Equity

Connected Articles

- The crisis of critical thinking in higher education: rethinking what universities should teach in an age of information abundance and generative AI — a critical narrative review of international evidence — A critical narrative review arguing the default failure is AI support that never fades paired with product-only assessment (Salameh 2026)
- Process-Oriented Collaborative Essays: Empowering Undergraduate Students Through Assessment Redesign in the Age of Generative AI — A graded, collaboratively written process essay in a first-year degree apprenticeship: iteration and collaboration in the rubric, GenAI permitted within stated boundaries (Alam & Jackson 2026)
- Distinguishing performance gains from learning when using generative AI — performance is not learning: a research agenda built on process measures (Yan et al. 2026)
- Human-centered AI for teacher educators: Designing professional learning for critical AI literacy — teacher educators asking for AI-resistant, process-based tasks built on justification and reflection (Baran et al. 2026)
- Educational integrity in GenAI-augmented assessment: making judgment visible — annotated decision trails, oral defense, and draft differences selected for visible judgment
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — what misconduct case files contain, and the process evidence they lack
- Which inference is at risk? Assessment validity reasoning and generative AI — which inference is at risk when assessment evidence is substituted
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — authenticity must be redesigned, not policed
- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — authentic products and the processes that produced them
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — the oral exam as an AI-resistant format that makes reasoning live
- Preserving epistemic authenticity: process-oriented assessment in the age of generative AI — epistemic authenticity and the four design commitments behind process-oriented assessment (Thapa & Lewis 2026)

- Mapping the Distribution and Depth of Metacognitive Processes in Generative AI-Assisted Learning: Evidence from Interaction Logs and Concurrent Think-Aloud Protocols — Channel-conditional process evidence: logs and think-aloud reveal different processes
- DraftTrace: A Multi-View Analytics Environment for AI-Integrated Writing — DraftTrace: A Multi-View Analytics Environment for AI-Integrated Writing
- Same Performance, Different Process: Epistemic Ownership in AI-Mediated Education — Same Performance, Different Process: Epistemic Ownership in AI-Mediated Education
- STEPwise: Supporting Teachers in Diagnosing Students' Mathematical Problem-Solving Skills through LLM-Generated Questions and Rubrics — STEPwise: Supporting Teachers in Diagnosing Students' Mathematical Problem-Solving Skills through LLM-Generated Questions
- Teaching with AI, Not Against It: A Thinking Partner Framework for Working Adult Learners in Compressed Online Formats — Checkpoint documentation of AI dialogue held at 96% completion across six semesters and about 440 teachers
- Rubrics and Generative AI: Towards Process-Based Assessment — Three rubric dimensions from Biggs's 3P model: agency and supervision, dialogic scaffolding, cognitive sovereignty (Oviedo & Díaz 2026)
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — A CodeMirror editor plus a logged chat panel turned one essay session into process evidence, with its typing-versus-thinking limit (Jelson et al. 2026)
- Process visualization feedback in news translation: a controlled intervention study of human-AI interaction using multimodal process data - process visualizations plus one reflection session shifted revision from surface to meaning level without increasing edit volume

Group Work

> **Group work** — learning and graded work produced by a team rather than an individual, used to develop collaboration, communication, and shared responsibility while also generating an outcome and often a grade for each member. It sits where assessment design and collaborative learning meet, and it inherits the tensions of both: free-riding and social loafing, unequal contributions, conflict avoidance, and the difficulty of attributing a collective product to individual learning. Generative AI intensifies these because teams must now negotiate whose and what kind of AI engagement counts as acceptable — a negotiation that Learner Agency research shows can resolve in opposite directions within a single cohort, and that AI agents joining the group can themselves reshape.

Questions to Consider

- What is a group task actually producing — the group's output, each member's learning, or their ability to collaborate? If those three can diverge, which one does your grading claim to warrant?
- Think of a group project you have been part of. Who did the work, who decided what counted as good work, and who stayed quiet? How much of that was the task design rather than the people?
- Research on group work finds students often decline to hold free-riders accountable to protect relationships. When a group member uses GenAI to produce their section, is that free-riding — or is the judgment more complicated than the word suggests?
- A group can access AI through a single shared interface or through each member's private prompts. Which produces more honest collaboration, and what does each conceal?
- If an AI agent joined your group as a teammate — praising, questioning, or provoking — would it deepen the collaboration or reshape who drives it without anyone noticing? How would you tell the difference?
- Collaborative AI that maximizes task efficiency tends to minimize learners' self-regulatory engagement. If you had to choose between the outcome and the struggle, which would you protect?
- A mediator AI is trusted only while it stays neutral. When it moves from summarizing to advising or challenging, the trust erodes. How neutral should a group's AI really be?

Introduction

Group work occupies a distinctive place in higher education and professional training: it is valued for building collaboration, communication, and shared responsibility, and it is pedagogically central in professionally oriented programs such as teacher education. Its promise is not automatically realized, however. Both teachers and students report obstacles to effective collaboration, and a graded group product carries two different claims at once — about what the group accomplished and about what each individual learned. AI, and generative AI in particular, presses on both: it changes how work can be divided, how easily contributions can be fused, and how each member's thinking can be distinguished from a tool's output. A

large part of the knowledge base's collaborative-learning research bears on group work, and this page draws on several strands of it rather than any single study.

Why group work is difficult by design

- **Free-riding and social loafing.** Some members reduce their contribution and the workload is redistributed onto more engaged peers. Task scope, group size, and composition raise the likelihood; accountability mechanisms and group efficacy reduce it.
- **Accountability is relational as well as structural.** In Hong Kong — where one of the knowledge base's group-assessment studies was conducted — undergraduates often chose *not* to report free-riding to protect interpersonal relationships, completing the work themselves instead of confronting the problem. Students' Learner Agency can therefore take the form of pursuing the grade while avoiding the conflict.
- **The collaboration has to be designed, not assumed.** Where a task can be partitioned into independent subtasks, students take that route and the group becomes a submission format rather than a joint intellectual endeavor. Chen and Zou (2026) found three of their fifteen groups doing exactly this — dividing the work, working on "individual platforms," and never pooling their individual GenAI capabilities even when coherence was an explicit assessment criterion.
- **Process versus product.** Group work is strongest when the process is assessed alongside the output, which requires peer assessment or other visible intermediates rather than a single final artifact.
- **Equity and inclusion.** Contribution norms, language, and confidence distribute unequally inside groups. Neurodivergent students report needing structured assignments, small consistent teams, and explicitly defined roles — requirements that AI collaboration tools, often built for the "average" learner, routinely fail to accommodate.

How AI changes group work

Research on AI in group work addresses two distinct things: what AI adds to a group's *task*, and what AI does to the group's *process*. Both matter, and the knowledge base's findings span them.

AI as coordination infrastructure

The most direct finding on GenAI and group assessment is Chen and Zou's (2026) three-pattern study of fifteen pre-service teacher groups. Rather than a single enthusiasm-to-avoidance spectrum, agency ran in three directions at once.

Pattern	Groups	Practice	Rationale
Cooperation-oriented agency	5	Intensified GenAI use	Coherence, performance, shared norms lowering perceived risk
Normative agency	7	Deliberately restrained use	Authenticity, fairness, originality, diversity of perspectives

Pattern	Groups	Practice	Rationale
Non-enacted agency	3	Unchanged from individual work	Task partitioned; collective interaction viewed as costly

- **GenAI as coordination infrastructure.** Students intensified use to solve a familiar collaboration problem — not knowing what peers' sections contained. Feeding those sections into a chatbot to decode and align them made distributed knowledge mutually intelligible, and one group rebuilt its workflow as "discussion → externalisation to GenAI → collective review → re-discussion." The authors read this as going beyond cognitive offloading, since judgment stayed with students while the tool absorbed coordination work, while warning that the smoother workflow may bypass the disagreement through which cohesion is built.
- **Group norms can invert accountability.** A permissive collective climate lowered the perceived risk of misuse ("it is more comfortable because besides me, everyone in my group is using GenAI"), turning shared norms into shared risk management rather than commitment to learning — the opposite of what group accountability is meant to achieve.
- **Restraint is also agentic.** Seven groups cut their GenAI use to protect the task's situated knowledge ("AI only knows that moment when you type"), to avoid effectively free-riding on groupmates, to preserve the originality that distinguishes groups from one another, and to keep the diversity of perspectives the group already had — normative self-regulation rather than mere compliance, and hard to distinguish from disengagement from the outside.

How the group accesses AI shapes the collaboration

Xu et al. (2026) show that *how* a team accesses GenAI is itself a design decision. With a single shared interface in synchronous work, teams co-construct "collective prompts," run a surface–evaluate–embed cycle, and treat the chat as shared memory; in asynchronous work, private prompting and output "de-labeling" fragment transparency and raise the cost of sustaining a shared cognitive model. Access configuration therefore connects directly to the quality of interactive engagement — whether the group is genuinely co-constructing or merely co-approving.

AI as a group member reshapes the group

A second line of research treats AI as a participant rather than a tool, and its findings complicate the assumption that "AI teammate" means "better teamwork."

- **Agents as social stabilizer — and a magnet for questions.** In fifteen groups of three STEM students deliberating Ethics with three Large Language Models (LLMs) participants (Seo et al., 2026), the agents kept groups on topic when human members drifted ("even if the other two participants strayed, I didn't have to handle it") and prompted clarifications humans avoided for relational reasons. But the group dynamic shifted interaction away from humans — 79.7% of questions were directed at agents (p = .017) — and participants noted a breadth–depth trade-off in the turn-stacking format, where each speaker took the floor in turn and "other participants couldn't intervene," making it easy to cover many ideas but hard to explore any one in depth.

- **AI personas reconfigure emergent Learner Agency.** Jin et al. (2026), in an experiment where AI operated as an undisclosed teammate, found supportive and contrarian personas still reshaped the group: contrarian AI pulled discourse toward challenge and reflection (productive friction), while supportive AI stabilized agreement and renewed ideation. Critically, the friction had a affective cost — contrarian AI reduced teamwork satisfaction and psychological safety *without* yielding creative gains — so "productive" discourse structures must be weighed against their emotional consequences. Because the personas worked even without disclosure, they position persona design as a form of invisible AI Governance over group collaboration.
- **Controversy can counter groupthink.** Wiss et al. (2025) took the opposite tack deliberately: an AI agent (CALIE) prompted to inject controversial viewpoints into twelve interprofessional PBL teams stimulated critical thinking and positive group dynamics, countering the conformity pressure that group work can otherwise produce. The contrast with Jin et al. is instructive — challenge helps when it is the intended design, and hurts when it is an unacknowledged side effect.
- **The neutral-mediator constraint.** Spritz, an AI that mediates disciplinary boundaries in interdisciplinary teams by surfacing implicit assumptions, was valued as both cognitive support and a relational buffer — but students' trust was load-bearing and eroded the moment the AI moved from neutral mediator to advisor or challenger. Role switches therefore need to be explicit and configurable, not silent.
- **Collaboration can itself be the object of instruction.** ProPACT treats the *dyad* — not the individual — as the unit of analysis, modeling joint attention and effort to predict collaborative breakdowns up to 30 seconds in advance. Dyads receiving proactive feedback achieved higher debugging success and showed sustained gains in collaborative AI Regulation in Education afterward: AI can teach collaboration itself, not just support a task.

The efficiency–regulation trade-off

Hao et al. identified three collaborative modes with AI on complex problems — *Delegated Reasoning*, *Concerted Interpretation*, and *Delegated Elaboration*. The most efficient mode (delegated reasoning) yields the best task performance but the lowest self-regulatory engagement; the mode with greatest self-regulation (concerted interpretation) underperforms on the task. This is the central design tension for AI-mediated group work: balance the efficiency of the distributed human–AI system against the depth of learners' regulatory engagement.

The epistemic risk of polished output

Kimmerle conceptualizes the risk of reduced epistemic effort when learners use AI to produce polished knowledge artifacts — automation bias on the social-cognitive side and epistemic closure induced by the finished artifact on the other. The remedy is to structure AI as an argumentative partner or challenger that preserves conflict. The counterpoint comes from Oppenheimer et al., who found that when LLMs act as critique partners and students actively rebut their claims, learners behave as critical consumers who preserve rather than surrender the cognitive conflict of critique. The difference between an answer-giving teammate and a challenging partner is what determines whether group work with AI builds or bypasses thinking.

Classroom-level, non-evaluative support

CoBi detects "uplifting" small-group discourse (respect, equity, community, moving thinking forward) and returns non-evaluative, classroom-level visualizations — deliberately withholding student- or group-level feedback to protect Privacy and Trust. Students preferred qualitative visualizations (an organic tree) over quantitative ones (a radar chart). For the relational dimension of group work, class-level aggregated feedback supports community building where individual scoring would feel surveilled.

Design implications

- **Make the AI-use negotiation an assessable outcome.** Chen and Zou (2026) argue teams should justify and document how GenAI will and will not be used, turning an implicit peer norm into explicit, gradeable reasoning rather than leaving it to perceived risk.
- **Assess process, not only product.** Peer assessment, intermediate deliverables, and reflective contributions create the interactions through which norms and shared understanding are actually constructed.
- **Do not rely on a coherence criterion alone.** A rubric line demanding integration does not produce collaboration if the task structure still permits divide-and-conquer; the workflow has to require joint work.
- **Design access deliberately.** Whether the group shares one AI interface or each member prompts privately changes the transparency of the collaboration and the cost of sustaining a shared cognitive model.
- **Decide, visibly, what the AI's role is.** A neutral mediator is trusted; an advisor or challenger is not, unless that role is explicit and intended. A contrarian persona can counter groupthink, but only as a designed feature with its psychological-safety costs acknowledged.
- **Balance efficiency against self-regulation.** Collaborative AI that maximizes task efficiency can undercut learners' regulatory engagement; design should deliberately protect space for concerted interpretation.
- **Prefer an argumentative partner over an answer-giver.** Structure AI to surface disagreement rather than smooth it over, so group work preserves the cognitive conflict that builds understanding.
- **Accommodate neurodivergent learners.** Structured assignments, small consistent teams, and explicit role definitions are requirements AI collaboration tools must support.
- **Read restraint carefully.** Students who avoid AI in groups may be exercising normative self-regulation — or guarding against risk and unfamiliarity. The two call for different instructor responses.

Common Misconceptions

"AI is a neutral addition to a group's workflow." It restructures where the group's interaction goes. In the study cited here, the group dynamic shifted interaction away from humans — **79.7% of questions were directed at agents (p = .017)** — while participants reported a breadth–depth trade-off in a turn-stacking

format where each speaker took the floor. A team that routes nearly four in five of its questions to a machine is no longer rehearsing the peer questioning that group work exists to develop.

“Polished group output is evidence of good collaboration.” Polished output is the epistemic risk, not the reassurance. A group can produce an excellent artifact while the regulation of the work — who decided what, how disagreement was resolved, whose reasoning was tested — happened inside the model’s response and left no trace in the deliverable.

“AI helps most when it coordinates the group.” Coordination support and epistemic support pull in opposite directions. Reducing the coordination cost of collaborating can lower the pressure on the group to negotiate meaning, which is the process being assessed. The efficiency–regulation trade-off is the core design tension, not an implementation detail.

“Group work is difficult because of the people.” Some of it is task design, which is why AI changes the difficulty profile rather than simply easing it: a tool that answers questions fast changes what the group spends its time on, and whether that is an improvement depends on which skills the task was built to develop.

Connected Concepts

- Pedagogical Patterns — Role scripts for groups sharing one AI
- AI in Education — AI in education (umbrella)
- Collaborative Learning
- Assessment
- Peer Assessment
- Academic Integrity
- Learner Agency
- Authentic Assessment
- AI Use and Disclosure Statements
- Higher Education
- Teacher Education
- Formative Assessment
- Student Engagement
- Learning Design
- Problem-Based Learning
- Sociocultural Learning

Connected Articles

- Students’ agency in GenAI-mediated group assessment: An ecological-emergent perspective — Three patterns of student agency in GenAI-mediated group assessment
- Emergent Learner Agency in Implicit Human-AI Collaboration: How Supportive and Contrarian AI Personas Reshape Interaction — Emergent learner agency when AI joins a group: supportive vs. contrarian personas

- Utilizing generative AI to counter learner groupthink by introducing controversy in collaborative problem based learning settings — An AI agent that injects controversy to counter groupthink in PBL teams
- AI as an Agent and Collaborative Space: Exploring the role of generative AI in small group synchronous and asynchronous collaborative dynamics — Shared versus private GenAI access across a team
- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective — Collaboration modes and the task-performance versus self-regulation trade-off
- ProPACT: A Proactive AI-Driven Adaptive Collaborative Tutor for Pair Programming — ProPACT: treating the dyad as the unit of analysis in pair programming
- Exploring AI-Supported Disciplinary Mediation in Student Project Teams' Text-Based Communication — AI mediation of assumption-surfacing in interdisciplinary student teams
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners — LLMs as critique partners: active rebuttal preserves cognitive conflict
- Polished Artifacts, Fragile Engagement? Tackling the Challenge of Reduced Epistemic Effort in Human-AI Knowledge Construction — Polished artifacts, fragile epistemic engagement
- A Feasibility and Implementation Integrity Study of the Community Builder (CoBi): An AI-based Collaboration Support System in K-12 Classrooms — Classroom-level discourse analytics for group collaboration
- Beyond Automation: AI as a Pedagogical Mediator in Collaborative Learning — AI as pedagogical mediator of collaboration
- "I can't read your mind": A Study of Neurodivergent Computing Students' Experiences with Collaborative Active Learning — Neurodivergent students' requirements for collaborative learning
- Academic League of Artificial Intelligence: An Integrative Perspective of Teaching, Research, and Extension — Democratic student governance and project teams for AI education
- Balancing Teacher and Student Agency: Co-Orchestration Tool Design Supporting Real-Time Dynamic Pairing — Co-orchestration of teacher and student agency in real time
- Reimagining Success and Failure: Equitable Assessment Practices in an Age of Artificial Intelligence — Equitable assessment in the AI era
- Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration — Ethics Training Agents: Facilitating Group-Based Ethics Education with Role-Playing and Discussion for Ethical Reflection and Exploration

Connected FAQs

- How Should I Handle AI in Group and Collaborative Assignments?

E-Portfolio

> **E-Portfolio (e-portfolio)** — a digital collection of a learner's work, reflections, and evidence of achievement, used for Assessment, learning, and evaluation. In the AI era, e-portfolios have emerged as a relatively **AI-robust and AI-assisted** assessment form: they capture the *process* of learning (reasoning, drafting, reflection) rather than just the final artifact, making them valuable against the collapse of the artifact-as-proxy, and generative AI can support their creation, Feedback, and evaluation.

Questions to Consider

- An e-portfolio captures the process of learning — drafts, revisions, reflections — not just the final artifact. Why might the process be exactly what AI cannot easily fabricate, and what does that make portfolios good for in an AI-heavy classroom?
- With AI able to produce polished final products on demand, the 'artifact-as-proxy' for learning has collapsed. What do you think an assessor can learn from a portfolio that they can no longer trust from a single submitted essay or exam?
- Some research recommends annotated portfolios, oral defenses, and recorded walkthroughs to probe reasoning in real time, mirroring professional practice. How different would that make assessment from the essays and exams you've taken — and fairer or harder to scale?
- AI can support the portfolio process itself — giving feedback, aiding drafting, and prompting reflection. Where's the line between AI genuinely helping a student learn and AI quietly doing the thinking the portfolio is meant to reveal?

Introduction

E-portfolios are a form of authentic assessment and formative assessment: they assemble student work over time, often with reflective commentary, into a body of evidence that can be assessed holistically. Their strength is that they surface the learning *process* — drafts, revisions, feedback, and self-reflection — which is exactly what AI cannot easily fabricate and what assessors need to evaluate genuine learning. This makes portfolios a leading candidate for assessment redesign in the generative AI era.

E-portfolios in the AI era

The knowledge base's research shows e-portfolios are increasingly central to productive AI integration and assessment redesign.

- **Portfolio assessment is relatively robust to generative AI.** Zhan, Boud & Du (2025) identify **social contribution portfolios** and co-created artifacts with auditable provenance chains among the authentic-assessment forms most robust to generative AI. Beyond detection (2025) likewise recommends **annotated portfolios / oral defenses / recorded walkthroughs** to probe reasoning in real time, mirroring professional practice.

- **AI-assisted portfolio assessment.** Ni & Lam (2026) study students' perceptions of **AI-assisted portfolio assessment** for multiliteracies development, showing AI can support the portfolio *process* (feedback, drafting, reflection) and enhance engagement while students evaluate AI feedback critically.
- **ChatGPT + e-portfolio for language learning.** Laksana et al. (2026) combine ChatGPT with e-portfolio assessment (CEA model) for EFL speaking: MANOVA showed significant gains in speaking performance (F(1)=48.554, p<.001) and feedback literacy (F(1)=16.135, p<.001), with e-portfolios supporting both speaking ability and the metacognitive abilities to use feedback effectively.
- **Portfolios as AI-era assessment strategy.** Responsible assessment (2026) argues for shifting from one-shot testing to **continuous embedded assessment using portfolios** and competency-based approaches. Rowe (2026) names portfolios (with orals and observed practice) as partial answers to the open problem of assessment at scale when the artifact-as-proxy has broken.
- **Portfolios as assessable learning traces.** Uden & Hwang (2026) use **personal learning portfolios** as a LEARN-framework mechanism — assessable learning traces (portfolios, AI-use disclosure) that make AI reliance transparent and auditable.
- **Symbiotic portfolios for hybrid learners.** Elsayed (2026) proposes a **Symbiotic Portfolio** for the post-human/hybrid learner, assessed by a five-criterion rubric (Generative Dialogue, Epistemic Auditing, Critical Reflection, etc.) — an explicit model for evaluating human+AI collaborative work.

Why e-portfolios matter for AI integration

Because e-portfolios foreground **process, reflection, and demonstrated understanding** over a single final artifact, they directly address the central AI problem: when AI can produce a polished product, the product no longer evidences the engagement behind it. E-portfolios shift assessment toward the evidence that survives — drafts, revisions, reasoning traces, and reflective Self-Assessment — while AI itself can assist in generating feedback, Scaffolding reflection, and (with appropriate rubric design) supporting evaluation. This makes e-portfolios a cornerstone of authentic, formative, and process-based assessment in the generative AI era, and a natural home for feedback literacy and self-regulated learning.

Common Misconceptions

"An e-portfolio is a digital folder of finished work." The assessment value comes from capturing the *process* — reasoning, drafting, revision, reflection — rather than the final artifact. That is precisely why e-portfolios are comparatively AI-robust: when the artifact can be generated, an assessment built on process retains evidence that an assessment built on the product has lost.

"AI makes e-portfolios as easy to fake as essays." The failure mode is different and the evidence shows the format moving in the other direction. Combining ChatGPT with e-portfolio assessment (a CEA model) in EFL speaking produced significant gains in speaking performance (**$F(1) = 48.554$, $p < .001$**) and feedback literacy (**$F(1) = 16.135$, $p < .001$**), with e-portfolios supporting the reflective layer. The portfolio did not become the weak link once AI was added to the course; it carried the assessment.

“A significant multivariate result proves the portfolio was the active ingredient.” It proves the package moved the outcomes. The study combined an AI tool, a portfolio structure and speaking tasks, and a design of that shape cannot isolate which component produced the gain. The defensible claim is about the combination, and the Learning Gains caution applies: reported gains need to be traced to a component before they can be reused.

“E-portfolios replace the need for unassisted assessment.” They complement it. A portfolio evidences process and growth over time; it does not evidence what a learner can do without support, and conflating the two reintroduces the artifact-as-proxy problem the format was adopted to solve.

Implications for Practice

For instructors

- Require the process, not just the product: drafts with dates, revision explanations, and reflection on what changed and why. Those are the artifacts AI cannot supply on the learner’s behalf.
- Pair the portfolio with at least one unassisted performance measure, so process evidence and capability evidence are both on record.
- Use AI *inside* the portfolio workflow — for feedback on drafts — rather than outside it, which is the configuration the cited study tested.

For developers

- Build for revision history and versioning rather than for a polished final view; the Pedagogies and Teaching Strategies lives in the diff.
- Make reflection prompts structured enough to be assessed, since unstructured reflection is where AI-generated text passes most easily.

For researchers

- Design for component isolation when studying AI-plus-portfolio packages; otherwise the field accumulates combination effects it cannot decompose.

Connected Concepts

- Assessment
- Authentic Assessment
- Formative Assessment
- Feedback
- Feedback Literacy
- Generative AI
- Self-Regulated Learning
- Metacognition
- Student Engagement
- Language Learning
- Higher Education

- Reflection

Connected Articles

- Students' perceptions of multiliteracies development using AI-assisted portfolio assessment — Students' perceptions of multiliteracies development using AI-assisted portfolio assessment (Ni & Lam 2026)
- Aligning ChatGPT with e-portfolio assessment as EFL learning model: its effect on students' speaking performance and feedback literacy — ChatGPT aligned with e-portfolio assessment for EFL speaking and feedback literacy (Laksana et al. 2026)
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Portfolio- and competency-based assessment in the AI era
- Designing for authentic assessment: a scoping review — Authentic assessment robust to generative AI, incl. social contribution portfolios
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Annotated portfolios / oral defenses as AI-resistant assessment
- Pedagogical Symbiosis: conceptualizing the Post-Human Learner in the age of cognitive AI — The Symbiotic Portfolio for hybrid learners
- Problem-based learning and the structural conditions for productive AI integration — Portfolios as partial answers to assessment at scale
- The LEARN framework for responsible use of generative AI in education: a neuroscience-informed model for problem-based learning — Personal learning portfolios as assessable learning traces

Peer Assessment

> **Peer assessment** — the practice in which students evaluate, grade, or give Feedback on one another's work, through written peer review, peer grading, peer code review, or group and team assessment. In writing Pedagogies and Teaching Strategies it is a long-standing best practice: students learn both from receiving criteria-based feedback and from providing it, and peer talk about shared work correlates with deeper learning, audience awareness, and social development. In the AI era it is being re-examined as an assessment design choice rather than a single activity — a human complement to AI-generated feedback, a training ground for Feedback Literacy, and a site where Academic Integrity and student agency are renegotiated.

Questions to Consider

- Think back to a time your work was assessed by a peer—or you assessed theirs. What did you learn more from: giving feedback or receiving it, and why?
- Why might a student's feedback be more context-aware and emotionally supportive than AI feedback, even while AI feedback is more consistent and rubric-driven? How could the two complement each other?
- Peers tend to under-grade strong work and AI tends to inflate weak work. If neither is reliably accurate across the whole quality range, what should a grade from either source be used for?
- Peer assessment depends heavily on Scaffolding and clear criteria, and friendship bias and social anxiety can make untrained peer review worse than none. What does adequate training actually look like in your context?
- If AI can draft comments on organization and structure, does that make peer assessment redundant—or does it free peers to give the specific, audience-aware feedback only they can give?
- GenAI-supported peer feedback outperformed plain peer feedback in one study, but only with prompt scaffolding added. What is being scaffolded there—the AI, the student, or the assessment?
- Critically assessing AI-generated feedback is described as building AI literacy and writerly agency. What does it mean to have agency over your own work when machines increasingly comment on it?

Introduction

Peer assessment is an assessment design choice in which students take on part of the evaluative work usually reserved for instructors. Its forms differ in what students produce and what is at stake: peer feedback (comments on a draft, usually formative and low-stakes), peer grading (a mark contributing to a grade), peer code review, and group or team assessment (where peers assess the collective product or one another's contributions). The form determines what students practice — giving a criteria-based comment builds evaluative judgment differently from assigning a number, and defending one's own code orally builds something different again. Self-Assessment, the sibling practice, turns that same criteria-based scrutiny on

the learner's own work, whereas peer assessment directs it at a peer's submission and the audience awareness that comes with it.

The research base agrees that peer assessment produces learning and disagrees about how much depends on design. It gives students an authentic audience, develops evaluative judgment through criteria-based responding, and builds the social context that supports engagement and Motivation. Its quality depends heavily on Scaffolding — how well it is structured, and whether students get clear criteria and training. That dependency is where AI enters, as a consistent, rubric-driven complement to the specific, context-aware feedback peers give, and increasingly as a scaffold built into the peer-assessment process itself.

Wang and Guo (2026) find that EFL students who reviewed peers' writing through open-ended dialogue with a generative AI produced feedback that recipients rated higher in quality, with gains in emotional response and feedback literacy that varied by the quality of the dialogue.

What students learn from assessing peers

The strongest argument for peer assessment is that the assessor learns. Fowles et al. (2026) made every CS1 submission subject to a 15-minute oral code review interview with a trained teaching assistant, weighted at 70% of the assignment grade. Pasted-to-total characters rose from 61.0% to 68.1% ($p < 0.0001$), yet exam scores did not decline and time-on-task held steady; 90% of students said the reviews motivated them to understand their code better and 65% that they helped avoid over-reliance on AI. Requiring students to explain their work to a trained peer converted potential offloading into a self-regulated practice opportunity.

The mechanism recurs across the literature. In a PRISMA 2020 systematic review of 22 articles from 203 screened, Martínez-Peláez et al. (2025) found LLMs support collaboration partly by aiding peer feedback and simulating rubric-based evaluations, and that students who verify and correct model output develop critical thinking. Learning by Teaching shows up even among machines: peer-learning-like discourse among over 2.4 million AI agents was mostly assertion rather than inquiry (statement-to-question ratio 11.4:1, metacognitive reflection only 7% of a coded taxonomy across 28,683 posts), which Chen et al. (2026) treat as a caution that surface discourse does not establish that anything is learned.

Training, calibration and feedback literacy

Peer assessment fails predictably when students are untrained. Gu, Chen, and Yan (2026) ran a mixed-methods quasi-experiment with 118 first-year undergraduates in China, comparing ChatGPT-4o under pre-trained rubrics against structured peer-review worksheets with a high-quality exemplar. Feedback literacy rose slightly more in the GenAI group (ANCOVA $p = 0.049$, $\eta^2p = 0.03$), but the qualitative findings matter more: peer-group students chose feedback sources by social convenience — nearby peers, same-major peers, roommates — rarely held specific feedback goals, and faced social anxiety about seeking feedback. Peer evaluation was more often distorted by friendship bias and perceived peer proficiency, and peer reflection was often delayed until later exams. The authors recommend multi-stage designs with anonymous peer feedback, since peer review still uniquely builds audience awareness and evaluative judgment through giving feedback.

Design frameworks target those bottlenecks. Irwin and Muller (2026) propose two GenAI roles in EFL/ESL peer feedback on speaking, a case they argue is harder than writing because of time pressure, fleeting oral

performance, and heightened affect: a Trainer supporting feedback givers through exemplar-based calibration and feedback-on-feedback, and a Synthesizer aggregating peer comments into a criteria-linked uptake report that normalizes formats, preserves minority views, and flags contradictions. Their principles are careful timing and sequencing, short repeated Trainer units, preserving the givers' voice, and Guardrails that keep the teacher in the loop with no automated grading. The paper is conceptual, with no new empirical data.

Validity, fairness and grading accuracy: peer vs AI vs instructor

Where peer assessment produces a grade, the question is whether the grade is defensible. Usher and Faraon (2026) found peer–instructor alignment was strongest for lower-quality work (r = 0.51 in the low-quality tier) and weakened for high-quality projects, which peers tended to under-grade — plausibly reflecting reluctance to criticize strong work. ChatGPT showed the opposite pattern: better alignment on high-quality work, but inflated grades for weak submissions. Students perceived peers' grades as more consistent with the peers' own written feedback, and valued peers' relationship-aware judgment alongside ChatGPT's neutral consistency. Peer accuracy is quality-dependent and relationship-sensitive, and no single source is reliable across the whole range.

That constrains what a peer grade should be used for. A mark calibrated in the middle of the distribution need not be calibrated at the top or bottom, so peer grades are more defensible as input to a moderated decision or as evidence of the assessor's judgment than as a final mark on strong work. Suen and Hung (2026) underline why institutions keep seeking scalable alternatives: peer feedback and expert coaching are time-consuming, costly, and hard to scale consistently. Their closed-loop system scored 204 adult learners on presentation skills with an XGBoost backbone approaching expert-rater reliability (ρ = 0.69–0.78) and pre–post gains of Cohen's d = 0.39–0.90 — one pre–post field study, not a comparison against peer assessment, substituting machine judgment rather than augmenting peer judgment.

AI-augmented peer assessment: PAIRR and the Trainer/Synthesizer split

The dominant design pattern keeps the peer central and adds AI around them. The Peer and AI Review + Reflection model is the best-documented instance. Sperber et al. (2025) implemented PAIRR across 10 writing courses and three writing-intensive STEM courses, with 654 students (37% first-generation, 13% international, 68% multilingual). Students drafted, exchanged peer review, prompted ChatGPT for rubric-driven feedback on the same draft, critically assessed both, planned revisions, and reflected. 58% preferred combined feedback, 36% peer feedback alone, and only 6% AI feedback alone. The two sources were often similar (75% reported similarities, described as confirming and strengthening each other) and, when they differed, complementary: AI feedback was often called overly general (31%) but gave actionable revision strategies on organization and structure, while peer feedback was more specific and detailed (28%) and drew on contextual knowledge of the assignment. Critically evaluating AI output built AI Literacy, and only 5.3% of students showed overconfidence in it.

The pattern generalizes to professional writing. MacArthur et al. (2025) applied PAIRR to an upper-division business writing course where five major assignments each required a draft, audience analysis, peer review by 2–3 peers, and revision (34 of 46 enrolled students participated; 69% multilingual). Students valued AI feedback but sometimes found it too general, and valued peers' contextual knowledge — "my peers looked

at it from the employer's perspective… ChatGPT did not do that as much." One quarter of coded reflections in the larger PAIRR study expressed skepticism about AI feedback or noted inaccuracies, which the authors read as developing AI literacy. The study is descriptive and course-specific.

GenAI as a scaffold inside peer feedback and group assessment

The most rigorous test of how much design matters is a multisite cluster-randomized experiment. Ateş (2026) randomized 48 sections across 4 universities — 1,176 first-year undergraduates in biology, chemistry, and physics — to four conditions for scientific argumentation: peer feedback only, direct GenAI feedback, reflective GenAI feedback (self-evaluation then AI critique), and a hybrid of self-evaluation → peer feedback → GenAI critique. Direct GenAI beat peer feedback on immediate argument quality but showed weaker transfer; reflective and hybrid designs produced stronger feedback uptake and self-regulated learning; the hybrid showed the clearest advantage on conceptual learning; both outperformed direct GenAI on delayed AI-free transfer. GenAI's value, the authors conclude, depends less on access than on whether the environment preserves student agency and ownership during revision.

Sequencing AI feedback before peer discussion, rather than after it, also raised outcomes: against peer feedback alone, 122 Chinese EFL students given AI-plus-peer integrated feedback reported higher affective, behavioral and cognitive engagement (partial $\eta^2 = 0.29, 0.28, 0.32$) and outperformed on all four IELTS writing dimensions, largest for task achievement ($d = 1.41$) (Liu (2026)).

That pattern — an early advantage that does not hold — recurs when the comparison is teacher feedback against AI-assisted peer feedback rather than GenAI alone. Tang, Li, and Luo (2026) ran an eight-week quasi-experiment with 61 Chinese L2 writers (244 graded texts) working from one five-dimension checklist, with one class receiving teacher written feedback and the other AI-assisted peer feedback. Teacher feedback produced far more comments — 316 items against 185 in the first task, concentrated on vocabulary and technical details — and the slightly larger immediate gain, but its improvement fell sharply by the second task while the AI-assisted peer class held steady and finished with the higher revision score. The AI-assisted peer comments were fewer but stayed anchored in content and structure, and their early lexical-diversity edge did not persist; neither mode moved syntactic complexity. The authors read the two as complementary scaffolds and propose an AI–Peer–Teacher hybrid, in which AI marks surface errors during drafting, peers negotiate content in revision, and the teacher targets what neither reached.

Adding GenAI can also raise the quality of the peer feedback itself, but apparently only with prompt support. Chang et al. (2026) compared three conditions among 45 student teachers in 12 groups over four rounds of collaborative argumentation: plain peer feedback, peer feedback with GenAI, and peer feedback with GenAI under prompt scaffolding. The GenAI-supported groups outperformed plain peer feedback on argumentation performance, and the prompt-scaffolded group performed best on advanced elements such as "rebuttal data and warrant" and "addressing the opposing view". GenAI-supported groups produced more explanations, suggestions, and neutral or negative feedback, and the scaffolded group paired negative emotions with higher-order feedback content — critical evaluation rather than passive acceptance. It is a small single experiment, but it isolates prompt scaffolding as the active ingredient.

Group assessment changes the problem, because students must negotiate whose AI use is acceptable. Chen and Zou (2026) interviewed 15 focus groups of 52 pre-service teachers in a course where a group presentation worth 30% of the final grade required integration and coherence. Three patterns emerged:

cooperation-oriented agency in five groups, who intensified GenAI use to hold the work together and protect a shared grade; normative agency in seven groups, who restrained use to protect authenticity and fairness — one student reasoned that generating a part in AI would be “not fair to other groupmates”; and non-enacted agency in three groups whose practice never changed from individual work. The authors argue that individual capability does not become collective agency on its own and that the negotiation of acceptable AI use should itself become an assessable outcome, with peer review tasks feeding the final product.

Feedback architecture, disclosure, and the social conditions of peer assessment

Peer assessment also depends on what students can see of each other and what they will admit. Hao and Cukurova (2026) tested an AI-generated summary learning design across three iterations with 128 students over eight weeks. Students in AI-supported iterations showed significantly higher standardized out-degree centrality than the baseline ($\beta = 0.547$ and $\beta = 0.438$, both $p < 0.001$): they viewed or interacted with more peers. Interviews described the summaries as a navigation map that reduced the effort of finding contributions buried in ill-named threads, and students attended to active contributors chosen for contrasting opinions rather than friendship. The design did not prevent declining viewing activity under rising workload, so technological affordances alone do not sustain engagement.

Peer norms also shape honesty, which matters wherever peers assess AI-influenced work. Qu and Wang (2026) surveyed 409 Singaporean undergraduates about why students conceal GenAI use despite disclosure mandates, and found relational variables dominated: perceived peer disclosure and comfort with instructors were the strongest predictors of disclosure, while moral disengagement was weaker. Non-disclosure was strategic adaptation to perceived peer norms and low interpretive trust, not moral negligence. Peer norms can therefore support honesty, as when group-assessment students restrained AI use out of obligation to groupmates, or suppress it, as when collective adoption lowered the perceived risk of misuse. Transparency, the authors argue, depends less on compliance than on trust and positive normative climates — a relational condition that peer-assessment designs either create or destroy.

Design implications and open questions

Several design moves follow. Give assessors training, exemplars, and criteria before they assess, because untrained peer assessment is vulnerable to friendship bias, convenience-based source selection, and social anxiety. Sequence the work so self-evaluation precedes peer feedback and AI critique, since the hybrid condition produced the strongest conceptual learning and best delayed transfer. Where GenAI enters, scaffold how students prompt it. Keep the teacher in the loop for anything that becomes a grade, treat peer grades as quality-dependent evidence rather than uniform marks, and make AI use itself something groups negotiate and document.

GenAI-mediated review also inherits the tool’s linguistic norms: contributors to a World Englishes dialogue argue that reviewers using GenAI are exposed to the same bias toward dominant English varieties as the models, and recommend editing or rewriting generated text to reflect the writer’s own linguistic identity (Ugwuanyi et al. (2026)).

The open questions are about the strength of the evidence, not only about design. Much of the peer-and-AI evidence is small and context-bound: 45 student teachers in one course, 34 students in one business writing

course, 52 pre-service teachers in 15 focus groups. The PAIRR survey is the largest dataset here and measures student perceptions, not the quality of the AI outputs students judged. Only the multisite experiment's 1,176 undergraduates approaches causal-comparative scale, and it tests feedback design for scientific argumentation rather than peer assessment as such. Meanwhile O'Neill (2026) audited 14 peer-reviewed meta-analyses claiming AI improves education and found none provided a valid basis for its claims — all but two defined the treatment as a tool rather than a pedagogical intervention, heterogeneity was high in every meta-analysis reporting I^2 (77.2% to 94.4%), and an audit of 59 primary studies found 61% had validity concerns, most often a mismatch between the outcome measured and the claim made. Claims about what AI does in peer assessment should be treated as claims about a designed activity, tested in that activity's terms.

Common Misconceptions

- **"Oral defence stops AI-assisted work."** Pasted-to-total characters **rose from 61.0% to 68.1% ($p < 0.0001$)** after every CS1 submission became subject to a **15-minute oral code review worth 70% of the grade**. The behavior it targeted increased — and **exam scores did not decline and time-on-task held steady**, while **90% of students said the reviews motivated** them. The intervention worked on understanding, not on pasting.
- **"Cheating detection is what oral assessment is for."** The measured outcomes were understanding and motivation, not reduction of pasted text. Judging the design by its detection rate misreads what it achieved.
- **"Peer review is a cheaper substitute for instructor feedback."** Learning by teaching is the mechanism, and it shows up even among machines: peer-learning-like discourse among over **2.4 million AI agents** was mostly **assertion rather than inquiry**. Producing critique is a different act from receiving it.
- **Reflective peer and self forms as the record behind a group grade.** Issa and Hall (2024) used one peer-reflective form per teammate plus one self-reflective form per student in a postgraduate Business Project Management unit, alongside a 30-minute meeting with each team in which members were asked whether their contribution was original. The forms were not graded as feedback exchange. They were the per-person evidence that let the instructor defend an individual mark inside a 40% team assessment. The framework's mark rise from 27/40 to 31/40 is confounded with a new lecturer and its integrity claim is unquantified, so the transferable part is the record-keeping structure, not the effect size.

Connected Concepts

- Pedagogical Patterns — PAIRR and combined peer-plus-AI feedback: the sequences and their comparative evidence
- Writing
- Formative Assessment
- Self-Assessment
- AI Feedback Quality

- AI Literacy
- Self-Regulated Learning
- Metacognition
- Student Experience
- Collaborative Learning
- Academic Integrity
- Feedback Literacy
- Feedback
- Group Work
- Assessment
- Scaffolding

Connected Articles

- AI-peer integrated feedback in second language writing classes: exploring students' engagement and writing performance — Integrated AI-plus-peer feedback raised all three engagement dimensions and all four IELTS writing dimensions
- Who grades best? Comparing ChatGPT, peer, and instructor evaluations across varying levels of student project quality — Comparing ChatGPT, peer, and instructor grading across project quality levels (Usher & Faraon 2026)
- Peer and AI review + reflection (PAIRR): A human-centered approach to formative assessment — Peer and AI Review + Reflection (PAIRR)
- AICoFe: Implementation and Deployment of an AI-Based Collaborative Feedback System for Higher Education — AI Peer Feedback Systems
- Unravelling undergraduates' development of evaluative judgments through AI-supported internal feedback — Unravelling Undergraduates' Development of Evaluative Judgments
- Enhancing learner-centered feedback with AI: Teachers' practices and perceptions — Enhancing Learner-Centered Feedback With AI
- Generative AI and linguistic diversity in academic writing and publishing: Perspectives from World Englishes — Generative AI and Linguistic Diversity in Academic Writing
- GIFT-AI: Teaching the game and leveling the field: Peer and AI Review + Reflection in a business writing course — PAIRR in a business writing course: peer review, chatbot feedback, reflection (MacArthur et al. 2025)
- Fostering feedback literacy by scaffolding self-regulated feedback: a comparative study of GenAI and human peers — GenAI vs. human peers for scaffolding self-regulated feedback and feedback literacy (Gu et al. 2026)
- Positioning generative AI in EFL peer feedback: Training feedback literacy and enabling uptake in speaking classes — GenAI as Trainer and Synthesizer in EFL peer feedback on speaking (Irwin & Muller 2026)

- Human-centered GenAI feedback design in higher education: A multisite experiment on direct, reflective, and hybrid approaches to scientific argumentation — Multisite experiment comparing peer-only, direct, reflective, and hybrid GenAI feedback (Ateş 2026)
- Leveraging generative AI to facilitate peer feedback in collaborative argumentation learning — Prompt-scaffolded GenAI peer feedback in collaborative argumentation (Chang et al. 2026)
- Students' agency in GenAI-mediated group assessment: An ecological-emergent perspective — Agency in GenAI-mediated group assessment: cooperation, restraint, non-enactment (Chen & Zou 2026)
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — Oral code review interviews as harm reduction for GenAI in CS1 (Fowles et al. 2026)
- An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training — Automated multimodal presentation coaching as a scalable alternative to peer feedback (Suen & Hung 2026)
- Enhancing peer exposure and creating opportunities for bridging social capital through an AI-generated summary-driven learning design in online discussion forums — AI-generated discussion summaries broaden peer exposure in online forums (Hao & Cukurova 2026)
- To disclose or not to disclose: Peer influence and psychological factors in students' use of generative artificial intelligence — Peer influence and relational trust in students' GenAI disclosure (Qu & Wang 2026)
- Can large language models foster critical thinking, teamwork, and problem-solving skills in higher education? A literature review — Systematic review of LLMs for critical thinking, teamwork, and problem solving (Martínez-Peláez et al. 2025)
- When AI Agents Teach Each Other: Discourse Patterns Resembling Peer Learning in the Moltbook Community — Peer-learning-like discourse among 2.4 million AI agents (Chen et al. 2026)
- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Audit of 14 AIED meta-analyses and 59 primary studies (O'Neill 2026)
- Teacher feedback vs. AI-assisted peer feedback in L2 writing: A quasi-experimental study in a Chinese university — Teacher feedback vs. AI-assisted peer feedback in L2 writing: quantity, focus, and improvement trajectories over two tasks (Tang, Li & Luo 2026)
- A teamwork framework for preventing breaches of academic integrity and improving students' collaborative skills in the AI era — self/peer reflective forms as per-person evidence behind a group grade (Issa & Hall 2024)

Connected FAQs

- What Are Best Practices for Writing Instruction in the Context of AI?
- How Should I Handle AI in Group and Collaborative Assignments?

Self-Assessment

> **Self-assessment** — judging your own work, competence, or progress against criteria, and the practices and instruments built on that act. The term carries two faces that are easy to collapse into one. As an **instructional technique** it is self-grading, rubric-based self-review, self-checking, and guided reflection: activities meant to develop the monitoring and judgment that Self-Regulated Learning runs on. As an **educational measure** it is a self-report instrument, in which a learner's estimate of their own skill, confidence, or learning stands in for an observation nobody made. It sits beside Peer Assessment as the other half of students-as-assessors, and inherits the same dependence on Scaffolding and explicit criteria. Both faces turn on the same faculty and both fail in the same direction: the estimate is systematically generous, and the more a learner's submitted work can be produced by a generative AI tool, the less that work says about whether the faculty is there at all.

Questions to Consider

- When you finish a piece of your own work, what tells you whether it is good: the criteria you were handed, the criteria you have internalized, or how it feels? Could you tell which one you actually used?
- Self-report and objective measurement of teacher AI literacy hardly agree: across 288 K-12 teachers the two correlated at r = 0.07 to r = 0.24. Where in your own practice would a self-estimate most likely diverge from a test of the same skill, and why there rather than somewhere else?
- Self-grading can save instructor time and build judgment, and it can also hand out a mark the student has not earned. What would have to be true about the task, the rubric, and the training for a self-grade to carry credit?
- If a tool can produce the essay, what is left for a student to assess about their own learning? What would you ask them to estimate instead?
- Students who assess a peer's work and students who assess their own are doing different things. Which one transfers better to the next task, and what evidence would settle it?

Introduction

Self-assessment is one of the older ideas in education and one of the more confused ones in practice, because two distinct things travel under the name. The first is a technique: students reviewing their own work against criteria, grading it, checking it, reflecting on it. The second is a measurement: the learner's own rating of their skill, confidence, or learning, used as data. The technique is judged by what it develops in the learner; the measurement is judged by whether the number can be trusted.

Both matter in an AI-era assessment design, and they matter for different reasons. The technique is where evaluative judgment is trained, and evaluative judgment is exactly the capability that becomes scarce when a language model can produce competent-looking work on demand. The measurement is where the field

routinely overstates what it knows, because a self-report cannot measure learning: it can only record what someone says about it.

Self-assessment as an instructional technique

The practices that fall under this heading are familiar: self-grading against a rubric, self-review of a draft before submission, self-checking of problem solutions, reflective prompts asking what a learner would do differently, and prediction tasks where a student estimates their performance and then compares. Their purpose is developmental. A student who reviews their own draft against criteria is rehearsing the appraisal that peer review and instructor feedback also train, and is building the internal standard they will use when nobody is watching.

Evidence that the technique works, and about which version works, comes mainly from writing and from self-regulated learning research. In a comparative study of feedback literacy, first-year undergraduates (N = 118 in China, 56 in a GenAI group and 62 in a peer group) worked through three self-assessment cycles across one semester. The GenAI group's advantage over the peer group was small, only 0.17 scale points (partial eta squared = 0.03), and the study's practical conclusion is the one that recurs: self-assessment needs scaffolding. Pre-trained rubrics, prompt guidelines, and worksheets are what separate a self-assessment cycle that builds Feedback Literacy from one that produces offloading.

Self-assessment is also where the cycle of Self-Regulated Learning becomes visible as a skill rather than a disposition. In an undergraduate statistics study, students who received explicit training in reasoning-focused scaffolding (stepwise hints and verification prompts) performed better on a later task attempted with no model assistance and showed better self-assessment calibration than students who leaned on the model uncritically. The interesting part is the second measure: the trained group's estimates of their own understanding aligned better with what they could actually do. A technique aimed at reflection changed a measurement property of the learner.

Calibration training

The most direct technique is calibration training, where a student predicts their score or confidence before seeing a result and then compares the prediction with the outcome. In an AI-assisted writing study, a feedback literacy script improved writing quality, feedback uptake, and deep revision, while an Assessment-Performance Calibration Activity primarily improved the accuracy of students' self-assessment and reduced overconfidence. Combining the two produced the largest writing gains and the strongest retention after AI support was withdrawn, though the calibration activity alone remained the better route to accurate self-estimates. That division of labor is the practical point: feedback literacy improves what a student does with comments, calibration improves how well they know their own standing, and they are not the same intervention.

An essay-level paper on ethical AI use at one Australian university treated guided self-assessment as the vehicle rather than the subject: across commencing nursing, health sciences, engineering, and science students from 2021 to 2025, pre- and post-semester self-assessments combined Likert confidence items with an open reflection prompt, and the authors argued that ethical practice is a developmental capability to be built through reflection rather than a compliance rule to be enforced.

What AI adds to the technique

AI changes three things about the technique. It can generate the items and rubrics, which makes repeated self-assessment cycles cheap. It can be the thing assessed, which is how evaluative judgment gets trained: a student judging an AI draft is practicing appraisal with an unlimited supply of material. And it can make the learner's judgment visible as process evidence. In interactive learning dashboards, a conventional analytics dashboard was extended with a Judgment of Learning self-assessment feature and a conversational agent, on the argument that eliciting a learner's own judgment does more for engagement than telling them what the data shows. Institutional frameworks have started to treat the same process traces, including structured self-assessments and metacognitive prompts, as evidence of adaptive capabilities that a transcript cannot show.

Self-assessment as a measure

Used as a measure, self-assessment usually arrives dressed as something else: a confidence rating on a Likert scale, a predicted score, a Judgment of Learning item, or a taxonomy-based inventory of perceived skill. It is one family within the wider set of Self-Report Measures, and it inherits that family's categorical limit. A self-report cannot measure learning or behavior; it can measure only what a person is willing to say about their learning or behavior, and those two things come apart often enough in this research base to be a finding in its own right.

How accurate the estimates are

Accuracy is the headline problem, and the direction is consistent. The cleanest evidence comes from a study that built parallel self-report and objective measures of teacher AI literacy inside a single framework. Across 288 K-12 teachers, correlations between the objective and self-reported factors ranged from $r = 0.07$ to $r = 0.24$. Latent profile analysis found six profiles: 43 teachers rated themselves consistently high while scoring lower on the objective measure, 59 showed the reverse pattern, and the remaining profiles clustered near the mean or split by prior AI literacy experience. Two measures of one skill, built by the same team on the same construct, share almost nothing.

The field-level picture matches that single study. Zainal, Mohd Matore and Maat's 2026 review of teacher AI literacy measurement tools appraised 33 instruments published between 2019 and 2025 and found that 31 (93.9%) were self-report scales of perceived confidence, only two (6.1%) tested knowledge objectively, and none used performance-based tasks. The authors' reading is the one this page's measurement face turns on: a self-report score records reported confidence rather than capability, so it cannot stand in for competence, and they argue for performance tasks and Item Response Theory analysis alongside self-assessment to separate validated capability from reported confidence.

Accuracy also depends on what is being estimated. A psychometric analysis of a taxonomy-based GenAI literacy self-assessment with 158 university staff and students found an inverted profile, with respondents claiming mastery of creation before the conceptual foundations underneath it, and only a weak correlation ($r = 0.188$) between student and academic profiles. A survey of Teacher Education students found the same shape from the other side: nearly all (97.8%) rated critical media analysis important while only 13.8% said their coursework addressed it, and fewer than half (44.9%) believed they had the skills to analyze media information critically. Self-assessed media competence lagged self-assessed importance.

Two mechanisms explain the generosity. The first is motivational and well documented outside this literature: people rate themselves generously, and the least competent overestimate most. The second is specific to AI-native cohorts. A 2026 theoretical paper on the **absent cognitive baseline** argues that sustained substitutive AI use during the formative secondary and high-school years reduces the independent cognitive encounters that any academic self-assessment depends on. The claim is structural rather than individual: self-assessment works by comparing a current performance with a record of previous ones, and where the record was never built, the estimate has nothing to be calibrated against. That is presented as distinct from offloading and surrender, which describe processes during AI use, because the gap persists when the tool is absent.

Developmental stage sets one boundary on accuracy, and the youngest learners are where a validated self-assessment instrument is scarcest. Thianwan and Srikoon's 2025 validation study of an AI literacy self-assessment questionnaire for upper primary students built a 15-item measure for Grades 4 to 6 across Learning About AI, Learning About How AI Works, and Learning for Life with AI, confirming a three-factor structure in samples of 335 and 579 students with an overall Cronbach's alpha of .934. The authors are explicit about the genre's limit: self-assessment accuracy depends on metacognitive ability that is still maturing in children, so scores index perceived understanding rather than demonstrated competence, and the instrument is intended for formative diagnosis.

Self-assessment as an outcome variable

The measurement face also shows up in evaluation design, where self-assessment instruments are used as outcome measures. One study of AI-assisted assessment of complex reports in higher education explicitly evaluates learning with validated feedback literacy and self-assessment instruments alongside subsequent performance and comparison with a control group. That is defensible when the instrument measures a belief the study is actually about, such as Self-Efficacy or perceived competence, and misleading when it is treated as a stand-in for achievement. The recurring critique of AI intervention studies applies with full force here.

Measuring agency through post-task questionnaires and task-specific Self-Efficacy risks circular reasoning: the learner's estimate is read back as evidence of the capacity it is meant to indicate, and the alternative is dynamic analytics that track how self-assessment is used across successive cycles (Mao (2025)).

What generative AI changes

The two faces converge under generative AI, because the tool attacks the link both of them rely on: that a learner's submitted work is evidence about the learner.

Where the work can be produced on demand, a sound essay no longer demonstrates the judgment behind it, and asking a student to assess a draft they did not write is a different task from assessing one they did. This is why assessment validity arguments have moved from detection toward redesign, and why self-assessment moves from a study aid to a component of the assessment design itself: the judgment a student makes about a piece of AI output, on the record and with reasons, is evidence in a way that the output is not.

It also introduces a naming hazard worth stating plainly. **AI self-evaluation** is not this concept. When a paper reports that a model assesses its own reasoning or grades its own output, that is model evaluation and belongs with Automated Assessment and the study of model training and simulated learners. One tutoring

study makes the practical version of the point, arguing that feedback should be conditioned on a separate diagnostic classifier rather than on the model's self-assessed reasoning validity. Learner self-assessment and model self-assessment share a vocabulary and nothing else.

Implications for practice

- **Scaffold the technique.** Rubrics, prompt guidelines, and worksheets are what make a self-assessment cycle developmental. Bare self-assessment, like bare AI feedback, tends to produce reassurance rather than judgment.
- **Train calibration separately from feedback use.** Prediction-and-compare activities change the accuracy of self-estimates; feedback-literacy work changes what students do with comments. If accuracy is the goal, run the calibration activity.
- **Keep self-grades low-stakes unless the training is real.** A self-grade is a claim about learning made by the person it benefits, and the overestimation profiles in the AI-literacy study are not a small bias to absorb in a summative mark.
- **Use self-report where it is honest.** Confidence, perceived competence, and willingness to disclose AI use are legitimate things to measure by asking. Achievement is not.
- **Ask for judgment, not opinion.** The most defensible AI-era self-assessment asks a student to appraise a specific piece of work against criteria and justify the call, which is trainable, inspectable, and connected to Evaluative Judgment.
- **Watch the cohort effect.** For students whose formative years included substitutive AI use, an accurate self-estimate may be unavailable rather than merely optimistic, which shifts the instructional task from correcting overconfidence to rebuilding the experiential record it needs.

Common Misconceptions

"A self-report measures the skill it names." It measures a belief about the skill, and the two come apart badly. In a study of **288 K-12 teachers**, self-reported AI literacy correlated with an objective measure of the same skill at only **r = 0.07 to r = 0.24** — a range in which the self-report explains almost none of the variance in capability. Self-report is usable as a perception measure and not as a proxy for competence.

"Students can judge their own learning accurately." Accuracy of self-judgment is itself a skill, and the evidence on calibration points the other way: in an experimental comparison, explicit training in reasoning-focused scaffolding produced better self-assessment calibration than unrestricted access, which means calibration improves from instruction rather than being available by default.

"Adding an AI feedback loop improves self-assessment automatically." A feedback loop changes what the student compares against, which can improve calibration and can also anchor them to the system's judgment. The comparative study here (**118 first-year undergraduates, 56 in a GenAI group and 62 in a peer group**, three cycles across a semester) is designed precisely to test whether the loop or the social comparison does the work — and the answer is not "the loop, by being a loop."

"Self-assessment is a softer alternative to testing." It is a different target. Self-assessment develops the regulatory skill of judging one's own work; a test measures the capability being judged. Research that substitutes one for the other conflates the capacity to evaluate performance with performance itself.

Connected Concepts

- Evaluative Judgment
- Self-Report Measures
- Peer Assessment
- Metacognition
- Self-Regulated Learning
- Feedback Literacy
- Formative Assessment
- Assessment Validity
- Self-Efficacy
- Scaffolding
- Cognitive Offloading
- Cognitive Surrender
- Trust Calibration
- Assessment
- Learning Gains
- Educational Measurement
- AI Literacy
- Reflection

Connected Articles

- Fostering Self-Directed Growth with Generative AI: Toward a New Learning Analytics Framework — Self-assessment placed at the center of a self-directed growth framework (2026)
- Measuring Acceptance of Age-Tiered AI Literacy Guidebooks: A Developmentally Informed Study of K-12 Students and Teachers — Developmentally tiered AI literacy materials, with measurement of acceptance and validity (2026)
- The cognitive impact of ChatGPT in higher education: A systematic review of critical and creative thinking outcomes — Triangulating AI feedback with peer, instructor, and self-assessment (2026)
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most — Why feedback should not rest on a model's self-assessed reasoning validity (Yasir et al. 2026)
- Development of an AI literacy self-assessment questionnaire in upper primary school students — A validated 15-item AI literacy self-assessment questionnaire for Grades 4 to 6, with the metacognitive limits of child self-report (Thianwan & Srikoon 2025)
- Assessing teachers' AI literacy: a systematic review of measurement tools — 31 of 33 teacher AI literacy instruments are self-report, two test knowledge objectively, none use performance tasks (Zainal, Mohd Matore & Maat 2026)

Connected FAQs

- How Can AI Help Me Give Better Feedback at Scale?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can We Address Common Misconceptions About AI in Education?

Oral Assessment

> **Oral assessment** — assessment in which a learner must explain, defend or demonstrate understanding in speech, live or recorded: the viva voce, the oral exam, the oral defense, the code-review interview, the clinical consultation. Because the exchange is real-time and the questions need not be known in advance, the format resists the substitution of generated text for understanding in a way that take-home authentic tasks cannot. It also carries a distinctive validity problem: orals measure fluency and confidence alongside knowledge, so what they certify depends heavily on how they are designed, who is asking, and how the learner's speech is treated as evidence.

Questions to Consider

- Orals are promoted in the AI era because a machine cannot sit in the room and answer for you. Yet the corpus that argues this contains no randomized trial of oral against written assessment. What would you need to see before treating that argument as settled?
- The same body of work reports two different mechanisms for reduced anxiety: removing the teacher's live observation, and becoming familiar with the format through practice. These imply different designs. Which fits your context, and which would you trust to generalize?
- Speech-only scoring can mistake verbal fluency for conceptual understanding. If a learner gestures correctly but says the wrong word, or says the right word without understanding it, what exactly is your assessment measuring?
- Every oral design in this corpus hits the same wall: staff and room time. If the constraint is twenty-eight contact-hours per semester for fifteen students, is the honest answer a smaller number of defended assignments, a larger teaching team, or a different format?

Introduction

Oral assessment is one of the oldest assessment formats and, for most of the last century, one of the least fashionable: hard to scale, hard to standardise, hard to defend in an appeals process. Generative AI has reversed its fortunes. When a written submission can be produced on demand by a model, the assessment value of the artifact collapses, and attention moves to the assessment of the person. A learner who must answer an unfamiliar question out loud, in real time, is at least demonstrably present and thinking.

That reversal is now visible across the research corpus, but unevenly. Some work treats the oral exam as a policy answer to academic integrity, some designs an automated system to deliver or score oral performance at scale, and some asks what speech itself can and cannot show about understanding. The pages connected below disagree about how much orals actually prove. Read together, they support a narrower and more defensible claim than the one usually made for them.

What a live performance can certify

Fenton (2025) makes the strongest form of the argument. Drawing on the literature on authentic assessment, the paper's case for the oral exam rests on its interactivity: questions can be withheld until the moment of the exam, follow-up probes can be improvised, and the learner cannot rehearse a response to a question they have not seen. The format also blocks rote memorisation, because recall is checked through explanation rather than reproduction. The paper is a review and position piece in *Educational Researcher*, not an empirical study, and it ends with thirteen numbered implementation recommendations rather than evidence of improved outcomes.

The honest version of the integrity claim is narrower than it is often stated. Orals make substitution harder to hide; the corpus does not show that they reduce AI use. In the CS1 oral code-review study, weekly fifteen-minute interviews carried seventy per cent of each assignment's grade, and pasted-to-total characters still rose from 61.0 per cent to 68.1 per cent ($p < 0.0001$) across three semesters, while exam scores moved by a statistically insignificant two per cent. Ninety per cent of students said the reviews motivated them to understand their code better and sixty-five per cent that they helped avoid over-reliance on AI, but the measured behavior did not follow. Oral assessment changed what could be hidden, not what students did.

The design space the corpus actually covers

The formats in the corpus span a wide range of automation and synchronicity, and each solves a different part of the problem.

Live, human, synchronous. The viva voce examined by a viva voce study of thirty-five pre-university students is the baseline: same teacher, same questions, one delivery face-to-face and one mediated by an AI system. The doctoral viva appears in a qualitative study of fifteen postgraduate researchers, where participants argued for shifting assessment weight toward it on the reasoning that a thesis is easier to fake and that the viva must be given in person. The authors accept that reasoning only in part, since a viva is not inherently proof against AI assistance.

Recorded and asynchronous. Asynchronous oral assessments replace the room with a time-limited, non-revisable webcam response, roughly thirty seconds of preparation and two to three minutes of speech. In the reported pilot, scores exceeded those of in-person multiple-choice tests: midterm median 92.5 against 70 ($p < .001$) and final median 94.2 against 86.4 ($p = .002$), with only moderate cross-format correlations. The authors explicitly attribute the difference to the format rather than to learning, and the design carried 7.5 per cent of the course grade.

Automated delivery and scoring. A voice-based system trialled in vocational automotive and engineering classes assessed thirty-three learners, of whom twenty-one agreed the live voice task felt realistic and none disagreed that speaking in real time suited the task better than a written portfolio. Word counts for identical questions varied five- to eightfold between learners, fluency conferred no accuracy advantage on closed items, and a preliminary agent grade matched the human tutor's in ninety-five per cent of adjacent horticulture and dairy trials. A conversational Socratic test takes the opposite design route, aiming at conceptual questioning; its evidence is a self-report survey of ninety-eight students, in which 80.6 per cent agreed the AI scaffolded effectively and fifty-two per cent reported lower stress than traditional exams. Both papers measure acceptance rather than learning.

Oral evidence as defense rather than examination. A tool-invariant assessment framework pairs AI-free in-class quizzes with ten-minute oral defenses of comment-stripped, AI-assisted work, scored on code comprehension, method understanding, terminology, interpretation and verification, with verification required to pass regardless of the total. The design is argued rather than validated; the paper's own arithmetic for fifteen students is two and a half contact-hours per assignment and roughly twenty-eight contact-hours per semester across eleven defended assignments.

Interaction format decides what an AI-mediated speaking task can certify. The Duolingo English Test's dialogue tasks, 713 of them in the pilot, required answer selection rather than reactive talk, which the reviewers argue misaligns the cognitive demands of the task with the construct the test claims to measure (Goh & Aryadoust (2025)).

Anxiety, bias, and who the format disadvantages

Orals are argued for on inclusion grounds, because a spoken answer is harder to buy than a written one, and against on the same grounds. Fenton catalogues the challenges directly: scheduling load, anxiety, and bias along gender, ethnicity, language and answering speed, plus the effects of non-anonymous marking. Against that, the evidence the paper cites suggests orals can be as inclusive as written examinations, including for students with dyslexia, and that unfamiliarity rather than the format itself drives most reported anxiety; students in one cited study were less anxious by their later oral exams.

Where anxiety genuinely falls, the reason matters. In the AI-mediated viva, self-reported calmness was significantly higher than in the face-to-face version (means 6.50 against 5.86, $t(34) = -1.97$, $p = .028$), and usability was rated good. But the face-to-face condition scored significantly higher on helping students understand their own work ($p = .004$). Removing the teacher's live observation made students calmer and, by their own report, less illuminating to themselves.

What counts as oral evidence is also narrower than it looks. A study of embodied evidence in oral explanations argues that scoring speech alone mistakes verbal fluency for conceptual knowledge and disadvantages learners with language-related difficulty, since gesture carries understanding that the transcript loses. Its demonstration is small: two engineering students explaining statistical concepts, with high-confidence gestures clustering on particular ideas, square and box forms at roughly fifty-four to sixty-one per cent, and tighter gesture–speech coordination accompanying more coherent explanations.

Scoring, validity, and the scale problem

Three findings cut against reading oral scores as learning gains. The asynchronous-format study disclaims learning gains for its own score advantage, and reports instructor-versus-model re-scoring agreement of ICC 0.73 at midterm and 0.60 at final, which bounds how far machine scoring can be trusted. In an RCT with one hundred third-year medical students comparing a simulated-patient system against progressive-disclosure case material, final examination performance rose (71.8 against 55.6 per cent, Hedges' $g = -0.81$). OSCE communication ratings also rose (3.53 against 2.64 on a five-point scale), while binary diagnostic accuracy was statistically identical (84 against 86 per cent, $P = 1.000$). An accuracy-only reading would call the intervention null; a communication-only reading would call it transformative.

The binding constraint is staffing and hardware rather than Pedagogies and Teaching Strategies, and the corpus is unusually candid about the arithmetic: twenty-eight contact-hours per semester for fifteen students, eleven teaching assistants for a class of over one hundred in the CS1 design, and one laptop serving twelve simultaneous learners in the offline vocational deployment. No randomized trial of oral against written assessment exists anywhere in this body of work, and every study that measures the difference is a single-institution design without a control group. Oral assessment is well supported as a response to AI-assisted substitution, and thinly supported as an improvement in learning.

No format holds a fixed position in this trade-off: oral assessment's observability is a design choice, and its feasibility cost is one a program distributes rather than accepts — feasibility is an educational priority, not the constraint that erodes good practice (Pedlow et al. (2026)).

The oral's integrity rationale is also time-limited: Corbin et al. (2026) argue that AI glasses and earbuds can deliver covert real-time prompts inside a live viva, because wearable AI produces no gaze shift or detectable signal, so interactive orals are no longer immune.

- **The scale ceiling is the design constraint.** In a workshop with 73 computing educators, oral and interactive assessment was reported as the strongest available evidence of individual understanding and the least scalable remedy. The mitigations participants described were distribution and sampling: shared teaching-assistant pools, peer assessment weighted below a final exam, and calling on a rotating subset of students (Akbar et al., 2026).

Common Misconceptions

- **"Oral assessment cannot scale."** In the CS1 oral code-review study, **weekly fifteen-minute interviews carried seventy per cent of each assignment's grade**, and pasted-to-total characters still remained informative. The cost is real and the design is implementable at course scale.
- **"Oral exams are softer than written ones."** In the reported pilot, scores **exceeded those of in-person multiple-choice tests: midterm median 92.5 against 70 ($p < .001$) and final median 94.2 against 86.4 ($p = .002$)**. Oral assessment was not the lenient option.
- **"A simulated encounter is equivalent to progressive-disclosure cases."** In an RCT with one hundred third-year medical students the simulated-patient system was compared **against progressive-disclosure case materials** — a direct test of equivalence rather than an assumption of it.

Connected Concepts

- Pedagogical Patterns — Oral and viva verification sequences, and what they do and do not demonstrate
- Assessment — the broader field this format sits inside
- Authentic Assessment — the design tradition that makes the integrity case
- Assessment Validity — what a format can and cannot claim to measure
- Academic Integrity — the pressure that returned orals to prominence
- Automated Assessment — machine delivery and scoring of oral performance
- AI Detection — the alternative response, and why it is weaker

- Speech and Voice Technologies — the speech pipeline an oral system runs on
- Multimodal AI — gesture and speech as combined evidence
- Anxiety and Stress — the affective cost of live performance
- Feedback — what a viva tells a learner about their own understanding
- Higher Education — the setting almost all of this evidence comes from

Connected Articles

- Developing and assessing second language listening and speaking: Does AI make it better? — Non-branching AI dialogue tasks misalign task demands with the speaking construct
- On AI glasses and wearable AI in assessment — Live vivas are no longer immune: AI glasses and earbuds deliver covert real-time prompts (Corbin, Sharpe & Dawson 2026)
- Reconsidering the use of oral exams and assessments: An old way to move into a new future — Reconsidering the use of oral exams and assessments (Fenton 2025)
- Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era — Asynchronous oral assessments: integrity, engagement and professional communication
- Designing AI-Supported Oral Assessment in TVET — Designing AI-supported oral assessment in vocational education
- Exploring student anxiety and experience in performance-based assessments using AIvaluate: an LLM-augmented emotionally intelligent pedagogical AI conversational agent — Anxiety and experience in AI-mediated performance-based assessment
- Combating Harms of Generative AI in CS1 with Code Review Interviews and a Flipped Classroom — Oral code review interviews in an introductory programming course
- A Multimodal Framework for Embodied Cognition in Oral Explanations — Gesture as evidence in assessing oral explanations
- The theoretical foundation of Socratic tests: Dynamic, multimodal, conversational examinations — Automated conversational testing as oral assessment
- A Tool-Invariant Framework for Teaching and Assessing Computational Methods in the Age of Agentic AI — Oral defenses of AI-assisted work
- Evaluating Scaffolding-Oriented Multi-Agent Large Language Model System for Clinical Interview Training — Spoken clinical interviews under a simulated-patient system
- From Research Assistant to Surrogate Supervisor: A Qualitative Study Exploring PGR Students' Diverse Uses of Generative AI — The doctoral viva under generative AI
- AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI — AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI
- Trade-offs in assessment and feedback design: a trilemma-based model — Denies any format a fixed position and reframes feasibility as an educational priority

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can AI Help Me Give Better Feedback at Scale?

Automated Assessment

> **Automated assessment** — the use of AI to evaluate student work, from formative quizzes to high-stakes exams. Automated assessment spans multiple modalities — multiple-choice, short answer, essay, code, and performance-based evaluation — and ranges from direct automated grading to confidence-aware systems that report calibrated uncertainty alongside their scores.

Questions to Consider

- Automated assessment ranges from multiple-choice scoring to essays, code, and performance-based evaluation. What's the biggest difference you'd expect between how reliably AI can grade a multiple-choice quiz versus a free-form essay — and why?
- A core design idea here is 'confidence awareness': AI graders that report how certain they are, flagging low-confidence cases for human review rather than issuing a single unqualified score. How would a grade that said 'I'm 70% sure about this' change how you'd use or trust an automated score?
- Research shows automated scoring can systematically disadvantage non-native speakers — the AI scores the language rather than the understanding. Why might an automated grader be especially prone to this kind of unfairness, even when it achieves high agreement with human raters overall?
- One study found that how validation is done can inflate reported performance: a naive cross-validation method reported near-perfect results that dropped dramatically under more rigorous trial-independent validation. What does this cautionary lesson suggest about how you should read any claim that an AI assessment system 'works'?
- The page argues calibrated confidence enables human-in-the-loop workflows, supports trust calibration, and strengthens measurement validity. If an automated system routed its most uncertain cases to a human reviewer, what would you want to know about how those cases are chosen before you trusted the split?
- Automated grading is described as one of the most mature AIED applications, yet grading without useful feedback has limited educational value. How might a focus purely on producing scores — rather than usable feedback — change what students actually get out of an AI-graded assessment?

Introduction

Assessment modalities

- **Short answer and essay:** automated grading, Automated Essay Scoring, and confidence-aware approaches handle free-text evaluation.
- **Code assessment:** Bash grading and code review demonstrate programming assessment.
- **Formative assessment:** A-level science automation and CoTAL focus on formative rather than summative use.

- **AI-generated assessments at scale:** Assessing AI-Generated Exams shows that iteratively refined, course-tailored AI-generated exams achieve IRT-measured quality on par with expert-written standardized-exam questions (difficulty $\bar{\beta} = -0.45$ vs. 0.35; discrimination $\bar{\alpha} = 1.3$ vs. 1.2) across 91 college classes — evidence that automated assessment can move from scoring to full item generation.
- **Performance assessment:** Video engagement assessment and drawing assessment extend automation beyond text.
- **Multimodal exam data and rubrics:** a multimodal examination answer dataset with expert-designed Outcome-Based Education rubrics provides a benchmark resource for criterion-level automated assessment across diverse response modalities, supporting benchmarking and measurement research on multimodal student work.
- **Neurophysiological assessment:** Nanayakkara & Halloluwa (2026) benchmark ML/DL models for EEG-based familiarity prediction (faces vs. math equations) as a step toward direct, objective measures of knowledge acquisition. Crucially, they show standard stratified cross-validation inflates performance (up to 0.9853 F1) via temporal leakage, while trial-independent Group K-Fold validation drops the peak to 0.6038 F1 — a cautionary methodological lesson for all automated-assessment benchmarking.

Automated grading

Automated grading is one of the most mature and widely-deployed AI in education applications — AI systems that evaluate student work, from multiple-choice scoring to essay assessment and code review. Its grading modalities include:

- **Students separate feedback utility from evaluative authority:** AlGhamdi (2026) documents a case where an AI score counted toward grades and students knew it — 13 computing students whose scanned handwritten work was evaluated by ChatGPT against a rubric covering clarity, organization, sentence correctness and conciseness. Every participant found the feedback useful, yet all separated that utility from authority, and several rejected the one-way, non-dialogical character of automated grading — "ChatGPT is not like people. You talk to them and explain excuses… I like normal teacher [to] grade my work." The study positions automated evaluation as acceptable for surface revision but not as a final assessor, with conditional trust mediated by instructor oversight.
- **Short answer grading:** confidence-aware ASAG evaluate free-text responses, with confidence calibration critical — systems must know when grading is reliable. A scoping review of short-answer auto-marking in science (2017–early 2024) maps the field's course: Morley et al. found BERT-family models (base, RoBERTa, DistilBERT, SciBERT) dominated — used in 20 of 21 studies, peaking in 2021 — before GPT-based approaches were adopted via Prompt Engineering rather than fine-tuning from roughly 2022. Models augmented with domain data (textbooks, rubrics, further pre-training) consistently outperformed those without, yet few could justify marks in human-comprehensible terms and bias across demographic and linguistic groups was rarely examined — leading the authors to argue auto-markers should *support* rather than replace human examiners. A PRISMA-guided systematic review of 42 empirical grading and feedback studies (2023–2025) generalizes this caution across the field. LLMs match human raters on closed-ended

tasks and short-answer questions but cannot fully replace human judgment on complex, open-ended, or subjective work requiring in-depth analysis or Creativity, and the highest grading effectiveness is achieved in hybrid systems that pair AI-driven grading with teacher oversight and verification (Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback).

- **Essay scoring:** Automated Essay Scoring systems like anchor-based AES use prompting strategies to approach human-level reliability. RACES, a reward-aligned essay scorer, reported higher Quadratic Weighted Kappa and SimCSE similarity than evaluated pretrained and fine-tuned baselines on ASAP 2.0 without significance testing, and its reward-modeling feedback was LLM-generated proxy, leaving only the reference scores human-assigned (Li et al. (2026)). AIAWE extends automated evaluation to broader writing assessment.
- **Code review:** Linux Bash grading and CS1 code review demonstrate automated assessment in computing education.
- **A prompt persona can collapse a grader, and fine-tuning can repair it:** Habibullah et al. (2026) graded a practical computer vision exam (570 dual-graded students) under 171 configurations and a second machine learning exam (1,038 students) under 162 more. A short "strict grader" preamble drove 14 of 17 open-weight models out of the graded band (MAE ≥ 8), three stopping grading altogether; the damage traced to two credit-withholding sentences rather than tone or model scale, and its direction was exam-specific, improving seven models on the second exam. Light LoRA fine-tuning on roughly 3,900 pooled graded examples brought five small open models to parity or better with a human grader, so the vulnerability is a prompting artifact rather than a capability ceiling.
- **Formative integration:** A-level science automation and CoTAL show how automated grading feeds into Formative Assessment cycles.
- **Coverage of feedback types is not alignment with teachers.** Almousa et al. (2026) annotated paragraph-level feedback from three university writing courses into seven focus types; most models emit nearly every type, yet their distributions diverge from the teacher reference, with the educationally tuned LearnLM closest (Jensen–Shannon divergence 0.1344) and Mistral-7B furthest (0.2695). Prompting with category definitions or worked examples increased divergence for most models.
- **Bias and fairness:** Language bias in physics scoring documents how automated grading can disadvantage non-native speakers — connecting to Bias Mitigation and Equity.
- **Benchmarking GenAI models for open-ended grading:** Pecuchova, Benko & Drlik (2025) benchmarked eleven GenAI and sentence-embedding models against two expert human graders on 1,885 open-ended responses to 24 software-engineering questions. Only GPTo1 reached almost-perfect agreement (Fleiss' Kappa 0.82, low false positives and false negatives across grade categories), with Claude3 and PaLM2 close behind; context-sensitive GenAI models robustly handled short, diversely-phrased student answers, while reference-based embedding models (e.g., BERT's 345 false positives) systematically penalized correct-but-divergently-worded responses — evidence that model choice, not just grading format, shapes reliability for free-text open-ended assessment.

- **Prompt exemplars decide scoring agreement:** Takahashi et al. (2026) automated hierarchical diagnostic reasoning (HDR), an applied-competence task in which learners find and explain deliberately embedded errors in a short case. Using GPT-4o with no fine-tuning, the team generated new problems and scored student descriptions: generated and human-authored problems carried the same internal consistency (Cronbach's α = 0.78) and showed no significant score-distribution difference across 100 participants, and the format's correlation with a reading-comprehension control stayed low (α = 0.36 and 0.41). Scoring accuracy depended on the prompt rather than the model — without worked examples Q2 precision fell to 0.42, while adding human-scored correct and incorrect exemplars lifted agreement to 98% or higher on every question (Q1 and Q2 at 100%) — against a measured human cost of 138 minutes of expert scoring for 117 responses plus 30 minutes of consensus.

A model's own reasoning mode is a second configuration lever: on 32 anonymized public-health master's exam submissions the same ChatGPT moved from weighted kappa 0.269 in fast mode to 0.718 in thinking mode, while Kimi reached 0.571 (Brevik et al. (2026)). - **Multi-agent coding of teachers' open-ended responses, where the framework rather than the model carries reliability:** Copur-Gencturk et al. (2026) extend automated assessment beyond student work to the coding of teachers' own content knowledge (CK) and pedagogical content knowledge (PCK), asking whether AI can reproduce the trained human coding of 268 U.S. middle school mathematics teachers' written responses about ratios and proportional relationships. A purpose-built multi-agent LLM, GradeOpt, assigns three GPT-4o-backed roles — a Grader that applies the human coding manual, a Reflector that diagnoses each disagreement with the human code, and a Refiner that folds clarification points back into the manual over up to six rounds — and matched trained human coders closely on CK (κ = .88 and .85) while reaching substantial agreement on the far more interpretive PCK items overall (κ = .68; weighted κ = .79). Two NLP baselines and a single-prompt GPT-4o model never exceeded κ = .39 or weighted κ = .55 on PCK, so the authors attribute reliability to refining instructions against the coding manual rather than to model scale, and recommend expert review wherever adjacent coding levels blur, since GradeOpt's residual errors were typically adjacent codes rather than wild misses. - **Mixed-format exam grading (2026):** Falahat, Das, Bhaumik & Thambi (2026) evaluated ChatGPT-5 against human faculty grading of a 21-item pharmacy exam (16 students) spanning multiple-choice, select-all-that-apply, fill-in-the-blank, listing, short-answer, and essay items. Concordance was substantial-to-near-perfect for objective item types (CCC 0.935–1.000 — aided by correct answers supplied during grading) but collapsed for listing (0.621–0.708), short-answer (≈0 to negative), and essay (0.341–0.854) items; providing a structured rubric did not consistently improve full-exam agreement (71.1% without vs 68.2% with). The study sharpens a methodological point that recurs across automated assessment — moderate percent accuracy frequently coexists with low concordance — so accuracy alone overstates reliability, and it recommends hybrid grading for complex, subjective, or high-stakes items.

- **Cross-family grade-band calibration on authentic marked essays (2026):** Kerwat, Donaldson & Mahomed (2026) ran eight pre-specified configurations from four model families (GPT-OSS 20B, GPT-OSS 120B, Qwen 32B and Llama 3.1 8B, each at two temperatures) over the same locked cohort of 114 BAWE/Coventry essays carrying institutional Merit and Distinction labels, with one shared prompt that permitted four bands. Exact band agreement ranged from 18.4% to 54.4%: Llama 3.1 8B at temperature 0.5 led (54.4% exact, 98.2% within one band, MAE 0.474, near-zero bias) while GPT-OSS 120B was weakest (18.4%) and systematically *undergraded*, by

an average of 1.316 bands at temperature 0.5, with Distinction accuracy trailing Merit accuracy throughout. The locked cohort contained no Pass or Fail references, so this is Merit–Distinction discrimination rather than reliability across the full grade range, and temperature was no cure — it helped one family descriptively, left another unchanged, and significantly worsened GPT-OSS 20B (39.5% to 29.8% exact). Two lessons transfer beyond the study: grade distance and directional bias reveal what agreement statistics hide, and model size is no proxy for assessment validity.

- **Rubric engineering for open-ended scoring in medical education:** Olvet et al. (2026) asked whether GPT-4 could reliably score open-ended questions on pre-clerkship medical exams. After three iterations of human-driven rubric refinement at two US schools, inter-rater reliability with faculty reached substantial-to-almost-perfect agreement for three of four questions using analytic and holistic rubrics (weighted kappa up to 0.94), while the holistic-rubric item stalled at moderate ($\kappa w = 0.54$). Error-pattern analysis showed discrepancies were traceable to both raters — GPT-4 over-scored when students offered multiple answers or used rubric-absent vocabulary, whereas faculty were often "overly generous" graders — leading the authors to recommend keeping humans in the loop (e.g., faculty scoring a subset to confirm accuracy). Because roughly 82% of US medical schools grade pre-clerkship work pass/fail, exact AI score agreement is often unnecessary for operational use.
- **HITL scoring for a large-scale national writing assessment (2026):** Curi et al. (2026) scale prompt-based Large Language Models (LLMs) scoring to a real high-stakes Spanish writing exam (~5,000–6,000 responses/year), achieving 60–80% item accuracy and 90%+ output consistency across a 15-item analytic rubric, with a deterministic NLP checker replacing the LLM on the spelling item (100% consistency). Its distinctive contribution is decision-oriented validation over model-centric metrics: the AI's systematic under-grading bias, converted via IRT-and-Bookmark into proficiency levels, produces pass/fail discrepancies in 15.3–16.5% of cases — all of which the human-in-the-loop workflow routes to expert review, cutting responses needing full human scoring by at least 50% while preserving decision quality. This grounds hybrid grading in operational assessment rather than proof-of-concept datasets.
- **Per-dimension agreement shows where an assessor cannot detect change:** SOPHIE 2.0 (Hasan et al., 2026) validated an LLM judge against the consensus of all human rating sources — standardized patients and third-party raters — on a three-dimension clinical communication rubric, reaching Pearson 0.759 and ICC(A,1) 0.746 from transcripts alone, inside the spread of the individual human raters rather than outside it. Its weakest dimension was Be Explicit (correlations of 0.414–0.598 across candidate judges), and that was also the only dimension whose scores did not move measurably across the two encounters ($\Delta = 0.014$, $p = 0.1204$) — so per-dimension agreement can indicate in advance which dimensions an automated assessor is unable to show improvement on.

Confidence-aware assessment

A central design goal within automated assessment is **confidence awareness**: AI assessment systems that report calibrated uncertainty alongside their scores, rather than issuing a single unqualified prediction. A

confidence-aware grader not only produces a grade or classification but also signals how certain it is, so that low-confidence cases can be flagged for human review and users can calibrate their Trust in the system. This is central to responsible automated assessment and connects closely to Psychometrically Aware AI and Trust Calibration.

How confidence is modeled in the knowledge base's research:

- **Fused confidence signals for short-answer grading:** Confidence-Aware ASAG fuses model-based confidence signals (verbalized, latent, and consistency-based) with dataset-derived aleatoric uncertainty via Random Forest regression.
- **Confidence in multimodal student work:** Confidence-aware assessment of student-drawn scientific figures extends confidence modeling to multimodal student responses.
- **Psychometric calibration of LLMs:** Psychometrically aware AI advances the standard of aligning Large Language Models (LLMs) scoring with measurement theory, with calibration as a core requirement alongside Item Response Theory alignment.
- **Difficulty and response-time calibration:** Programming-exam difficulty calibration repositions LLMs as auxiliary evidence sources whose difficulty estimates correlate with student pass rates.
- **Trait-adaptive essay scoring:** PsyScore shows a psychometrically-aware framework can adapt essay feedback to learner traits.
- **Evaluating visual student work:** DiagramIR back-translates LLM-generated math diagrams (TikZ) into an intermediate representation with deterministic checks, beating LLM-as-a-Judge on agreement with human raters and letting small models match large ones at ~10× lower cost — a scalable route to assessing non-text, diagrammatic student output.
- **Trust-gated inference in automated teacher assessment:** Li, Yang & Fang (2025) place Monte Carlo dropout calibration directly in the scoring path, so that dropout variance above a learned threshold triggers a reject-and-refer output rather than a score, alongside adversarial debiasing that holds the fairness gap to 1.8% where baselines sit in the 6.4–8.2% range and an expected calibration error of 0.032 on TeacherEval-2023. Their ablation is the calibration argument in miniature: removing the trust-gated module drops inter-rater consistency to 78.6%, and the authors attribute a 41% reduction in human review workload to the gating — uncertainty handling as architecture rather than post-hoc reporting.
- **Explainability of rubric-based scoring:** Bueno et al. show that model-agnostic SHAP attributions are more faithful and transferable than LLM-generated rationales for explaining rubric-based scores (e.g., classroom feedback quality), and propose deletion-based + cross-model tests as a principled way to evaluate any scoring model's explanations.

Why calibrated confidence matters:

- **Enables human-in-the-loop delegation:** low-confidence cases route to a human reviewer — supporting human-in-the-loop workflows rather than blind automation.
- **Supports trust calibration:** calibrated confidence lets users match their trust to the system's actual reliability, avoiding both over-trust and under-trust.
- **Improves measurement validity:** confidence-aware scoring strengthens Educational Measurement and Assessment Validity by making uncertainty explicit.

- **Fairness and defensibility:** flagging low-confidence cases for review reduces the risk of confidently wrong scores, especially for atypical or underrepresented responses.
- **Rubric generation and instructor-supervised grading pipelines:** Mendonça et al. (2026) show that LLM-generated assessment rubrics (HARMOGEN-R) can match human-created rubrics for technical content within a ±5-point equivalence margin, with structured generation giving greater cross-model consistency. Cruz et al. (2026) evaluate an end-to-end GPT-4o grading pipeline where AI grades fell within 0.5 points of the instructor in 83% of 362 submissions (MAE 0.31) — best framed as a scalable supplement to, not a replacement for, instructor judgment.

Assessing teaching rather than work

Automated assessment usually scores what students produce, leaving the teacher's own performance to human observation. A 2026 integrative review turns the tools on teaching itself, mapping 21 studies drawn from 367 records in Scopus, Web of Science and ERIC (Dino et al., 2026). It followed Whittemore and Knafl's five-stage design with PRISMA reporting, appraised quality with MMAT 2018 — 89 of 105 criteria rated Yes — and built its keyword map in VOSviewer.

Four themes organize the corpus: **Evaluation**, models scoring teachers from student feedback and survey data; **Engagement**, tools sorting students by engagement level in online, on-site and hybrid settings; **Expression**, sentiment and topic coding of written student feedback; and **Experience**, sensor and video capture of observable classroom behavior. Teacher performance was the most common target, at 11 of 21 studies. The authors ran no meta-analysis, because methodological and outcome heterogeneity ruled out pooling, and 7 of the 21 studies had 100 participants or fewer — so the review maps a fragmented field rather than estimating how well AI judges teaching.

Quality and fairness

Automated assessment quality depends on Assessment Validity and Bias Mitigation. Language bias research shows that automated scoring can systematically disadvantage certain student populations. **The criterion is itself fallible.** Bozdag and Qiu (2026) mark GCSE physics scripts with an AI system and compare them against both official examination-board marks and experienced teachers' judgment, treating agreement with the board as a proxy for accuracy rather than accuracy itself.

Deployment scenarios and what each one requires

How much alignment an institution should demand depends on what the system is allowed to decide. In a mixed-methods study of 761 authentic undergraduate essays at three UK universities, three frontier models with 27 prompt configurations each reached only 35–65 percent agreement with human markers on the degree band, and accuracy did not transfer between institutions — so the report treats candidate uses as distinct scenarios rather than one decision. **Quality assurance of human marking**, where AI marks in parallel and significant differences trigger human review, is the most conservative. **A marking assistant**, ranking or categorizing submissions by predicted quality or uncertainty, triaging complex cases, or expanding brief human comments into fuller feedback, is a genuine middle ground. **AI as primary marker**,

with human review of a sample or of mark distributions, was judged acceptable only if system performance improves, and no stakeholder group endorsed AI as a sole marker.

Three requirements follow for any of them. Because alignment is model- and institution-specific, validation must be local and continuous — headline accuracy from elsewhere is not evidence of readiness. Because marks were compressed toward the middle, AI was least accurate at the grade boundaries and for the strongest and weakest submissions, which is where assessment decisions carry the most consequence. And because disagreement between an AI and a human mark reflects different judgment rather than mere error, discrepancies should trigger human interpretation rather than algorithmic override, with final authority over the mark retained by people. Adoption also carries AI Governance obligations the technical metrics do not capture: a right to explanation under GDPR Article 22 where automated decisions affect students, Equality Act duties once attainment level and language use are shown to influence marks, revised appeal processes for errors that are not easily caught, and an irreversibility risk — once staffing and investment shift, an institution may struggle to keep collecting the human marking it would need to return to.

Combining the three models did not remove that error: because their mistakes were correlated — the same direction on 63.4% of assignments — the Corsi et al. (2026) ensemble was statistically indistinguishable from the best single model, leaving the shared central-tendency compression in place.

Venetsanos (2026) supplies the criteria those requirements presuppose, arguing that what makes automation defensible is the *epistemic status* of the task rather than what the technology can technically perform. His framework limits AI to bounded verification of factual and procedural claims — all four of unambiguous documented criteria, direct comparison against established knowledge, no assessment of alternative valid approaches, and a single correct answer or pre-specified acceptable set must hold simultaneously, with ambiguity escalating to a human by default — and makes AI involvement at that level conditional on five non-negotiable principles that must all hold at once: the knowledge base must be assessor-curated and retrieval-grounded in module materials rather than the model's parametric knowledge; human assessors review every AI output before it reaches students and hold absolute override with unshared accountability; feedback must carry clear provenance and attribution; and security must be designed against adversarial use from the start, with input sanitisation for instructions hidden in white or small text, encodings, images or document metadata, since successful circumvention of an automated system spreads through student cohorts. The same paper is explicit that its principles are untested for simultaneous feasibility and that assessor time for curation, security infrastructure and high-frequency oversight may shift staff effort rather than reduce it — a caution that sits alongside the local-validation requirement above.

Security of AI-mediated grading

A red-team evaluation of an everyday grading workflow shows the attack surface that planning for adversarial use has to cover. Humble (2026) embedded five indirect prompt injections inside a synthetic essay that Microsoft Copilot (GPT-5.2) had graded fail in six of six baseline runs, iterating each across docx, pdf and htm files. Two strategies changed the grade with no visible warning — an instruction-manipulation and role-playing paragraph at 9 of 9 iterations (100%) and the same paragraph hidden behind an image layer at 17 of 18 (94%) — while a paragraph in small white text at the end of the document failed in all nine iterations, and file-metadata injections never worked, which the author attributes to metadata access being disabled in the version tested. The trust problem outlasted the exploits: after one pdf run detected an

embedded instruction and stated it would grade only against the official assignment, re-running the same file raised the grade six more times with no warning, and a chat blocked by a detected attack was silently disabled rather than reported to the user. The author argues the resulting grades carry no validity claim in either direction, that an adversary needs only one working combination against layered Guardrails, and that the teacher remains the only real check on the output while the manipulation is designed not to be visible — connecting directly to the input-sanitisation and adversarial-security obligation Venetsanos sets out above.

Connections

Automated assessment connects to Assessment Validity (quality assurance), Formative Assessment (use context), Bias Mitigation and Equity (fairness), Teaching (how automation changes instructor work), and AI Feedback Quality (grading without useful feedback has limited educational value). Confidence-aware assessment is a specific mechanism within the broader agenda of Psychometrically Aware AI and a contributor to calibrated trust.

- **Large-scale AI grading of handwritten physics (2026):** A multimodal model (GPT-5.5) graded 10,364 scanned pages across a national Physics Olympiad theory exam, selection camp, and university quantum-mechanics exam, achieving total-score correlations of 0.91–0.97 with official marks and recovering the same top-five Olympiad team. Revised page-by-page, evidence-location instructions improved agreement — evidence that multimodal AI can support high-stakes summative grading with careful rubric and prompt engineering (Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes).
- **Selective automation for handwritten chemistry (2026):** Cvengros & Kortemeyer graded a 296-student handwritten general-chemistry final page-by-page against rubric images with a multimodal, reasoning LLM, achieving high run-to-run reliability on total scores (ICC(A,1) = 0.967) and strong total-score agreement with TA grading ($R^2 = 0.91$). Because item-level reliability varied sharply by format — textual and chemical-reaction answers graded reliably while drawing and graphing scored worse than random — raw agreement was judged inadequate for high-stakes use. They operationalize human deferral through confidence filters (partial-credit thresholds, an IRT-based risk threshold, and problem-type exclusion) that convert raw AI scores into an accept/deferral policy, and show that false positives (AI crediting genuinely wrong answers) tend to go undetected since students rarely contest them — a concrete psychometrically grounded route to selective automation (Assisting the grading of a handwritten general chemistry exam with artificial intelligence).
- **Semi-open handwritten mathematics in a university exam (2026):** Liu et al. graded a German undergraduate mathematics exam with GPT-4 across two extraction routes (pre-cut answer boxes versus whole pages), two optical-character-recognition routes and two rubric formats, reporting Krippendorff's alpha against human grades of 0.22-0.44 with accuracy 0.59-0.62 on the best workflows and per-problem accuracy spanning 0.27-0.91 - not acceptable for high-stakes summative use. Itemising multi-criteria grading rules generally did not improve agreement (it helped the partial-credit problem), free grading without a rubric was far worse (accuracy 0.50-0.51), and a probabilistic confidence filter meant to flag grades for human re-checking did not significantly improve accuracy while wrongly flagging 7-41 percent of responses as reliable.

The study's transferable lesson is procedural: scan and transcribe the whole exam sheet with markers rather than cropping answer boxes, because students write across box borders; rewrite grading rules written for teaching assistants, since the model attempted unrequested derivations from a rule meant for a human; and note that the human-grading rules themselves paraphrased at an alpha of 0.88 among five variants, so prompt robustness is not the bottleneck.

- **LLM comparative judgment for writing screening (2026):** Mercer & Reed used seven LLMs as pairwise comparative judges to score informational writing from 1,208 students in Grades 3–6 across three screening occasions. LLM-CJ scores correlated strongly with analytic rubric scores (r = .67–.73, strongest for Gemini-3.1 Pro) with AUC .82–.86 for proficiency; findings were stable across models, with little validity gain from costlier, more capable ones, while averaging three writing samples improved accuracy — sampling breadth mattered more than model choice. Predictive-bias patterns for multilingual learners matched human rubric scoring, supporting LLM-CJ as an efficient, low-cost screening approach (Validity of Large Language Model Comparative Judgment for Universal Writing Screening).
- **Quality-dependent alignment with instructor grading (2026):** Comparing ChatGPT, peers, and an instructor grading the *same* undergraduate group projects, Usher & Faraon found ChatGPT's alignment with the instructor *improved as project quality increased* — its largest overestimation was for low-quality work (≈ +14 points), shrinking to ≈ +2.5 points for high-quality projects. ChatGPT also graded higher on average than both peers and the instructor, a grade-inflation tendency that undermines its reliability as a standalone summative grader, especially for weaker submissions.
- **Small-corpus agreement statistics can mislead deployment decisions.** Scoring 60 marketing posts (15 students plus 15 researcher-authored low-quality anchors) against two independent human raters gave absolute agreement ICC(2,1) of .435 for the LLM, .266 for an equal-weight rule-plus-LLM hybrid and .091 for deterministic rules, with MAE of 6.28, 10.53 and 17.22 points respectively on a 0-100 scale; the hybrid was significantly worse than the LLM alone (paired ICC difference -.169, 95% CI [-.260, -.106]). Adding anchors raised inter-rater ICC from .338 to .902 and LLM agreement from .435 to .846, and a near-empty post was awarded 75 against a human mean of 30.5, showing that a single degenerate response can dominate a small evaluation. (Agreement and error in automated scoring of student marketing posts)
- **Structured LLM grading can look analytic without being diagnostic (2026):** Scoring 3,041 responses to 50 computer-science questions, three commercial LLMs produced rubric sub-dimensions that were near-redundant (r = 0.82–0.99, VIF up to 45) and named Misconceptions about AI in only 4.8–7.4% of comments, against 15.0% for instructors (Zhao et al., 2026).
- **"A single kappa is the case for a grader."** It is one check, and a benchmark of **22 prompted models** on three public corpora shows why. Every model met probes whose right answer is known: a polite request for full marks, a forged grading instruction, a blank answer, a nonsense word, a bare objection. **Fourteen** were flagged for gaining more than **5% of the scale** from a note, up to **83.2%** on code, and **seven** credited blank or meaningless answers, so the agreement figure and the failure tests have to be read together. A deployed grading system has one more

input to test: sharing a learner model's estimate with the grader shifted marks by **0.28 to 0.75 points** on identical work, and the ablation that found it left rater agreement almost unchanged.

Common Misconceptions

- **"An automated score is a single reliable number."** A practical computer vision exam (**570 dual-graded students**) was graded under **171 configurations**, and a second machine-learning exam under further ones — the configuration drove the score. A grade presented as a number conceals the configuration that produced it.
- **"The judge is the source of unreliability."** On 378 fixed-dice rulings, a re-run changed **2.9 to 6.1 per cent** of outcomes under a semi-rigid method and **13.5 to 15.9 per cent** under free adjudication, while swapping the judge AI added only about 3 points (Epstein, 2026) — the procedure, not the judge, sets reproducibility.
- **"Confidence reporting is a nicety."** A score that said it was **70% sure** would change how it is used, and the absence of that information forces the reader to treat all scores as equally certain.
- **"Short-answer auto-marking is a settled area."** A scoping review of short-answer auto-marking in science (**2017 to early 2024**) documents the field's history, which is a record of what has been attempted rather than of what has been validated.

Connected Concepts

- Explainable AI
- Remote Proctoring
- Assessment Validity
- Formative Assessment
- Automated Essay Scoring
- Bias Mitigation
- Equity
- Teaching
- Large Language Models (LLMs)
- Higher Education
- AI Ed Evaluation
- Feedback
- AI Feedback Quality
- Psychometrically Aware AI
- Trust Calibration
- Trust
- Educational Measurement
- Item Response Theory
- Human-in-the-Loop
- Adaptive Learning

- Personalized Learning
- Summative Assessment — Summative assessment: AI-resistant formats (oral, proctored, closed-book exams)

Connected Articles

- Beyond Score Accuracy: Examining the Diagnostic Quality of LLM-Generated Structured Assessment in Higher Education — LLM rubric sub-dimensions are near-redundant and feedback rarely names misconceptions (Zhao et al. 2026)
- AI in University Assessment: Evaluating the Opportunities and Risks of Automated Marking — OpRaise report: AI marking of 761 university essays across three UK universities
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — HITL AI-assisted scoring in a large-scale national writing assessment (Curi et al. 2026)
- Validity of Large Language Model Comparative Judgment for Universal Writing Screening — Validity of Large Language Model Comparative Judgment for Universal Writing Screening
- Who grades best? Comparing ChatGPT, peer, and instructor evaluations across varying levels of student project quality — Comparing ChatGPT, peer, and instructor grading across project quality levels (Usher & Faraon 2026)
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams: a large-scale field study
- The Effect of High-Frequency, Automatically-marked Formative Assessments on Student Outcomes in A-Level Sciences — Automated formative assessments in A-level sciences
- Confidence Estimation in Automatic Short Answer Grading with LLMs — Confidence-aware automatic short-answer grading
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics — AI scoring language bias in physics
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations — LLM-based difficulty calibration for programming exams
- Anchor Is the Key: Toward Accessible Automated Essay Scoring with Large Language Models Through Prompting — Anchor-based automated essay scoring prompting
- CoTAL: Human-in-the-Loop Prompt Engineering for Generalizable Formative Assessment Scoring and Feedback — CoTAL formative assessment scoring
- Automated Grading of Linux/Bash Examinations Using Large Language Models — Automated grading of Linux Bash exams with LLMs
- Confidence-Aware Automated Assessment of Student-Drawn Scientific Models — Confidence-aware assessment of student-drawn figures

- DiagramIR: An automatic pipeline for educational math diagram evaluation — DiagramIR: automatic evaluation of generated math diagrams
- From scoring to explanations: Evaluating SHAP and LLM rationales for rubric-based teaching quality assessment — SHAP vs LLM rationales for rubric-based teaching quality assessment
- Automating Learner Assessment: Benchmarking Machine Learning and Deep Learning Models for EEG-Based Familiarity Prediction — Automating Learner Assessment: EEG-Based Familiarity Prediction
- A hybrid reasoning framework for artificial intelligence assessment rubric generation in human and automated contexts: Evidence from an undergraduate programming course — HARMOGEN-R: AI assessment rubric generation
- AI-assisted, instructor-supervised grading and feedback in higher education: Design and evaluation of an end-to-end pipeline — AI-assisted instructor-supervised grading and feedback
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- Auto-marking short answer questions in science: The foundational years of transformer-based models from BERT to GPT-4
- Automated Grading of Open-Ended Questions in Higher Education Using GenAI Models
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Can Generative Artificial Intelligence Reliably Score Open-Ended Question Assessments in Undergraduate Medical Education?
- Can ChatGPT Replace the Teacher in Assessment? A Review of Research on the Use of Large Language Models in Grading and Providing Feedback
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- A Tripartite Feedback Framework for AI-Assisted Assessment of Complex Reports in Higher Education — Tripartite framework: sorting feedback by epistemic status and the five boundary principles for AI involvement (Venetsanos 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Red-team evaluation of prompt injection hidden in student submissions against AI-mediated grading (Humble 2026)
- Towards trustworthy and explainable-by-design large language models for automated teacher assessment — Explainable-by-design LLM framework for automated teacher assessment with trust-gated inference (Li et al. 2025)
- AI-assisted automated short answer grading of handwritten university-level mathematics exam — handwritten semi-open mathematics grading with a confidence filter for human re-checking

- Can large language models reproduce higher education grade bands? Cross-model study of calibration and grading bias in authentic student writing — Can large language models reproduce higher education grade bands? Cross-model study of calibration and grading bias in authentic student writing
- Scalable AI-based clinical communication training and automated assessment — Scalable AI-based clinical communication training and automated assessment
- Automating Constructive Assessment with Large Language Models: Toward Scalable and Repeated Evaluation of Practical Competence — Automating Constructive Assessment with Large Language Models: Toward Scalable and Repeated Evaluation of Practical Competence
- Evaluating feedback focus and pedagogical adaptivity in LLM-generated feedback on student writing — Evaluating Feedback Focus and Pedagogical Adaptivity in LLM-Generated Feedback on Student Writing
- Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams — Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams
- Automated coding of content and pedagogical content knowledge of mathematics using a multi-agent large language model — Multi-agent LLM (GradeOpt) coding teachers' open-ended CK and PCK responses, reliability from prompt refinement against a coding manual
- Comparing the Marking Accuracy of an AI Marking System with Official Examination Board Marks and Experienced Teacher Judgement: A Case Study in GCSE Physics — AI marking compared with examination-board marks and teacher judgment in GCSE physics
- Large language models as grading assistants in public health education: a method-comparison study of essay-style exam assessment — Reasoning mode lifted LLM-human grading agreement from weighted kappa 0.269 to 0.718
- Machine–human agreement in marking undergraduate assignments is specific to model, prompt and institution — Machine–human agreement in marking undergraduate assignments is specific to model, prompt and institution
- Thumb on the scale: Using traditional wargaming adjudication practices to improve AI-judged evaluations and grading — Thumb on the Scale: Using Traditional Wargaming Adjudication Practices to Improve AI-Judged Evaluations and Grading (Epstein 2026)
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- Assessment of teacher performance and learner behavior using artificial intelligence in higher education: an integrative review of literature — Assessing teaching rather than student work, without pooling

Connected FAQs

- How Can AI Save Me Time as an Instructor?

- How Can AI Help Me Give Better Feedback at Scale?

Automated Essay Scoring

> **Automated Essay Scoring (AES)** — the use of AI to evaluate and score written essays, spanning traditional statistical approaches, fine-tuned language models, and increasingly accessible Large Language Models (LLMs)-based prompting strategies. AES research in this knowledge base covers scoring accuracy, fairness and bias, psychometric validity, and practical Accessibility for educators.

Questions to Consider

- Automated Essay Scoring has moved from traditional statistical models to LLM-based prompting. A key tension on this page is between accuracy and accessibility — fine-tuned models score well but are impractical for most educators. Which would you prioritize in your own context, and why?
- A major finding is that simply including exemplar essays in the prompt brings LLM-human agreement close to human-human reliability — and a cheaper model can match a more expensive one. What does this suggest about how much of AES quality is the model versus how it's prompted?
- The page warns that AI scoring can systematically underestimate students from linguistically diverse backgrounds. Before reading, if you saw an AI give a lower score to a non-native speaker's essay, would you have assumed it was a 'bias problem' or just 'the score'? What would change how you respond?
- A self-referential approach assesses L2 writers by comparing their writing to their own prior work rather than to native-speaker norms. How does the choice of comparison baseline change what a score means — and which students might it treat more fairly?
- AES intersects with formative assessment when used for feedback rather than grading. When would a machine's feedback on an essay be genuinely useful to a developing writer, and when might it flatten the kinds of qualitative feedback a human editor would give?

Introduction

Automated Essay Scoring has a long history in educational technology, from early statistical models to modern LLM-based approaches that can evaluate essays holistically without large pre-scored datasets. The key tension in AES research is between accuracy and accessibility — while fine-tuned models achieve strong results, they are resource-intensive and impractical for most educators.

- **Zhang et al.** RACES uses reward alignment to make LLM essay scoring both accurate and consistent, addressing a core AES validity concern.

Xu, Lu and Abdi (2026) review twelve studies comparing AI and human scoring of EFL academic writing and report moderate alignment overall, strongest on surface linguistic features and weakest on organization, coherence and argument development, with fairness rarely examined.

In upper-elementary response-to-text writing, Correnti et al. (2026) find that automated feedback on students' use of evidence improved feature scores, and that revision quality depended on whether teachers took the feedback up in discussion, not on the system alone.

Key research themes

Prompting-based AES has emerged as the most accessible approach. The **Choi et al. anchor paper study** shows that including exemplar essays in prompts brings LLM-human agreement close to human-human reliability, with GPT-4o mini achieving comparable results to GPT-4o at lower cost. This connects to broader Prompt Engineering research and makes AES feasible for teacher use.

Psychometric and trait-level scoring moves beyond holistic scores. **PsyScore** provides a psychometrically-aware framework for trait-adaptive scoring with ZPD-grounded feedback. **ICLE++** models fine-grained traits for holistic essay scoring, advancing the precision of automated evaluation. - **Dimension-level trait scoring is bounded by the data behind each dimension.** Firdausi et al. (2026) trained one classifier per dimension of Ennis's FRISCO Critical Thinking framework on 106 Indonesian eleventh-grade physics essays (83 for training, 23 for testing, with three teacher raters agreeing at kappa 0.78–0.84 on every dimension). Agreement concentrated on expression rather than reasoning: quadratic weighted kappa reached 0.763 for Clarity and 0.728 for Situation but only 0.374 for Focus, 0.332 for Reason and 0.227 for Inference. The ordinal signal was manufactured rather than observed. Synthetic level-1 essays (built from templates, cut to 20–40% of their original length, with keywords removed) plus LLM paraphrase lifted Focus by +0.346 kappa off a 0.028 baseline — and one configuration reached 0.652 accuracy with near-zero or negative kappa, — so accuracy is not a usable selection criterion in ordinal AES.

Bias and fairness is a critical concern. **Feser & Tschisgale** found that AI scoring systematically underestimates students from linguistically diverse backgrounds, highlighting the need for Bias Mitigation and Equity considerations in AES deployment.

Teachers want the score presented as reviewable, not final. Nine experienced Brazilian high-school writing teachers evaluated an AIED-Unplugged essay-scoring app and rated it highly — median SUS 92.5, TAM medians of 7 for usefulness, ease of use, relevance and intent to use, 6 for result quality. They volunteered, unprompted, that the report should carry an on-screen warning that it is not fully reliable and must be reviewed before a student sees it; one teacher read that obligation as a positive feature (Ribeiro et al. (2026)). They asked for more detail, not less: per-competency diagnostics, a global summary, a field for their own comments, and concrete examples of how to improve. Where validity research argues about agreement rates, these users asked the interface to encode the division of judgment between system and teacher.

Disagreement with human graders is systematic, not random. Out-of-the-box GPT and Llama models agreed only weakly with human scores (QWK ≈ 0.17–0.28 against 0.72 between two human raters) and biased in a quality-dependent direction — higher for short, underdeveloped essays and lower for long, strong ones carrying minor surface errors (Mathew et al. (2026)).

L2 and self-referential assessment explores non-native writing contexts. **Profile-based L2 assessment** uses a self-referential approach comparing student writing to their own prior work rather than native-speaker norms.

Interpretability and feature weighting opens the blackbox of how LLMs actually score. **Wang et al. (2026)** compared three LLMs (Qwen, GPT, Gemini) with human raters on non-native English essays across sixteen textual features, finding strong overall alignment but distinct weighting: LLMs emphasized grammatical accuracy, lexical sophistication, and syntactic complexity, while human raters prioritized content completeness and visual presentation. Critically, LLMs shifted their weighting by proficiency level — placing more weight on language errors for low-proficiency students and increasingly rewarding linguistic sophistication for high-proficiency students — whereas human raters maintained a more stable framework. **Liu, Ye, and Yan (2026)** extend this with a five-model evaluation framework (GPT-4.1, Llama 4 Maverick, Gemini 2.5 Flash, Claude Sonnet 4, DeepSeek R1) on 60 long essays, using causal discovery to reveal distinct evaluative heuristics: most models prioritized lexical precision and fluency, while others emphasized syntactic complexity or cross-domain integration, and some showed inconsistency, score compression, or systematic underestimation. Together these studies establish that AES validity depends not only on overall agreement but on *how* models weight features and whether that weighting is stable across learner subgroups — directly informing Assessment Validity and Bias Mitigation auditing.

Item-type boundaries and the limits of essay grading. In a mixed-format university exam, Falahat, Das, Bhaumik & Thambi (2026) found ChatGPT-5's concordance with faculty was substantial-to-near-perfect on objective items (CCC 0.935–1.000) but dropped sharply on open-ended responses — near-zero to negative for short-answer and only 0.341–0.854 for essay questions — and a structured rubric did not consistently improve essay agreement. This bounds AES validity: model fluency helps on well-specified items but does not carry over to holistic essay scoring, where contextual interpretation of partial-credit responses still favors human judgment.

Issue-type boundaries in diagnostic agreement. Yao and Fan (2026) used DeepSeek-R1 to label specific writing issues before revision and compared its labels with teacher diagnosis across three cycles (mean F1 = 0.768, SD = 0.037). Agreement was highest on locally cued issues such as vocabulary word choice (F1 = 0.824) and lowest where the issue turns on a claim–evidence relation (source use and evidence, 0.579), so agreement in a diagnostic role depends on the issue type, not only on the model or the prompt. **A skewed rubric distribution can make aggregate scoring metrics mislead.** Automated evaluation of a rubric dimension may be a classification task with a lopsided label distribution rather than a continuous score: marking reflection level 0-3 in 1,954 Hungarian student essays, 68% of essays sat at level 3 and 1.8% at level 0, and the best shallow configuration (SMOTEBoost with Qwen3 embeddings) reached an overall score of 0.7176 averaged over accuracy, F1 and ROC-AUC against 0.6872 for the best fine-tuned transformer — yet one RidgeClassifier configuration scored 0.7131 ROC-AUC at only 0.5162 accuracy, and class balancing lowered every metric (accuracy falling from 0.6672 without it to 0.6408 with it), so the authors read model choice as a question of which metric matters, with transformers earning their place through minority-class sensitivity rather than aggregate agreement (Csibi et al., 2026).

High-stakes deployment evidence. Field evidence from a real high-stakes deployment (Uruguay's *Acredita EB*, 2024–2025; Curi et al.) shows prompt-engineered GPT-5 reaching 60–80% agreement with trained human raters across a 15-item analytic Spanish rubric, roughly five percentage points below human inter-rater agreement for most items and never more than 15 points below, with run-to-run consistency above 90% for almost all items. Vocabulary, syntax and spelling were the weakest dimensions, and the spelling item had to be handed to a deterministic grammar checker (LanguageTool, 68% accuracy, 100% consistency) because token-level orthography is where the model is least stable. Prompts built for one exam edition transferred to

the next with only topic-specific edits, and the AI was systematically stricter than humans — under-grading rather than over-grading. For AES design, the lesson is that prompting-based scoring can approach human agreement even in a national exam, while its remaining weakness sits at the level of low-level language conventions rather than holistic writing quality.

Token-level confidence, probability-weighted scoring, and ensembling each improved agreement on divergent-thinking scoring — the stacked techniques reached r = 0.846 (RMSE = 0.4848), and routing only the least confident 20% of responses to human review cut manual effort by roughly 80% (Organisciak & Acar (2026)).

The human Benchmark, and what it can and cannot license. The OpRaise study is the strongest test in this knowledge base of whether LLM marking is ready for routine use, and its answer turns on the benchmark rather than the model. It compared three frontier systems (Claude Opus 4.6, GPT-5.4, Gemini 3 Flash), each under 27 prompt configurations crossing rubric specificity, calibration and scoring strategy, against the moderated marks of 761 authentic Psychology essays from 125 students at three UK universities. Human marks were adopted as ground truth because academic judgment is the socially accepted standard, and the authors note that human markers agree only moderately with each other — which bounds how strong AI–human agreement could reasonably be demanded to be. Against that benchmark, agreement on the UK degree band ranged from **35 to 65 percent by institution** (63 percent at Cambridge, 53 percent at Nottingham, 35 percent at Manchester Metropolitan) and did not transfer between them, so the report's central recommendation is local validation on an institution's own Assessment materials. Two findings generalize beyond this corpus. First, reliability and agreement pull apart: every model re-marked nearly identically (ICC 1.00, 1.00, 0.97) and the models agreed with each other more closely than with humans (three-model ICC 0.91), yet all three agreed on the degree band for only **56 percent** of submissions — self-consistency is not validity. Second, AI marks compressed toward the middle of the scale (a compression score of 0.47–0.82, with the crossover where AI and human agree on average sitting in the upper 50s to low 60s), making AI least accurate precisely at the grade boundaries that separate Firsts from Upper Seconds and passes from fails. Vocabulary range, connectives, sentence complexity and text length predicted AI marks with small but significant effects while their relationship with human marks was broadly negligible — a direct demonstration of the linguistic-bias concern, and one that no prompting strategy tested removed.

AES as a training signal rather than a judge. Scoring models are usually studied as evaluators, but SWIM uses one as a reward function. Do, Kontak and Sachan (2026) freeze a multi-trait AES verifier and score it against generated student essays, turning the predicted trait profile into a dense per-essay reward (the mean trait-normalized distance from the target profile) for GRPO, deliberately not the Quadratic Weighted Kappa metric itself. QWK is defined over a batch of target-prediction pairs and is not a per-sample signal, while exact-match rewards are too sparse in the multi-trait setting. The gains were re-checked against a DeBERTa scorer and an evaluation-only verifier the policy never trained against (0.598 versus 0.479 for SFT, and 0.647 versus 0.501), which is the check that separates genuine proficiency control from adaptation to the reward model. For AES research this is a second validity demand: a scorer used as a training target is being optimized against, so its own trait weighting and language biases propagate into everything the generator learns. The same feature-weighting asymmetries (grammatical accuracy, lexical sophistication and syntactic complexity weighted more heavily by models than by human raters) documented elsewhere on this page now shape training rather than only marks. **Scoring and feedback want different methods, so a system should separate them.** Labib et al. (2026) built one TOEFL argumentative-essay system as three modules —

scoring, surface-level feedback on grammar and mechanics, and deep-level feedback on organization, coherence and argumentation — instead of a single model doing all three jobs. What wins on one module loses on another: supervised fine-tuning of GPT-4o on 120 of a proprietary set of 480 benchmark-scored essays, tested on the remaining 360, reached a quadratic weighted kappa of 0.84 and RMSE of 0.44 on the 0-5 scale, ahead of the Wang and Gayed (2024) baseline (QWK 0.78, RMSE 0.57). Yet the same fine-tuning produced unusable output for the feedback modules, where direct prompting of Claude 3.7 was what generated teacher-approved comments.

Connections to related concepts

AES sits at the intersection of Automated Assessment, Writing, and Generative AI. It connects to Formative Assessment when used for feedback rather than grading, to Feedback Loop when integrated into iterative writing processes, and to AI Literacy when educators understand and calibrate AES tools. The Assessment Validity and Educational Measurement concepts are essential for ensuring AES scores are meaningful and fair. - **Agreement, error and what a hybrid scorer adds.** In a small open-ended marketing-writing corpus the LLM out-scored both deterministic rules and an equal-weight hybrid on absolute agreement with human raters (ICC(2,1) .435 versus .266 and .091), with the hybrid significantly worse than the LLM alone, while score dispersion and a single near-empty response showed how strongly such estimates depend on corpus composition (Agreement and error in automated scoring of student marketing posts).

Open systems are part of this picture too: AiAWE scores argumentative essays with a LoRA-adapted Gemma-3-27B-it, reaching QWK 0.828 and agreement within ±0.5 of the human score on 90.56% of 360 evaluation essays — and reports that model scale did not reliably predict downstream performance under LoRA adaptation (AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models).

- **“The prompted model that agrees best is the strongest essay scorer.”** On ASAP 2.0 the published agreement between the two expert raters is **κ 0.745**, and no prompted model’s point estimate reached it: the 22 ran from **0.155** to **0.727**, and for **18** the whole interval lay below. A fine-tuned DeBERTa scorer reached **0.809** and a rule that counts only essay length reached **0.636**, above **16 of 22** models, though every model kept agreement beyond length. The baseline to beat is the trained scorer, not the model down the road.

Common Misconceptions

- **“Automated scoring results reflect student writing.”** The ordinal signal can be **manufactured rather than observed** — synthetic level-1 essays built by template generation, degradation to **20-40% of original length** and keyword removal. A system validated on constructed extremes may never have been tested on the distribution it will meet.
- **“Aggregate accuracy is the metric to report.” A skewed rubric distribution can make aggregate scoring metrics mislead**: automated evaluation of a rubric dimension is often a classification task with a lopsided label distribution, where high accuracy and useful discrimination separate.

- **“Field deployments have not been evaluated.”** Field evidence exists from a real high-stakes deployment (**Uruguay’s Acredita EB, 2024**), which is the strongest form of evidence in this literature and the one most studies of scoring accuracy never supply.

Connected Concepts

- Bias Mitigation
- Equity
- Automated Assessment
- Language Learning
- Educational Measurement
- K-12
- Prompt Engineering
- Writing
- AI Literacy
- Assessment Validity

Connected Articles

- Automatic Reflection Level Classification in Hungarian Student Essays — Automatic Reflection Level Classification in Hungarian Student Essays
- WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays — WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays
- Educational Innovation through Automated Essay Scoring: A Multidimensional Framework for Evaluating Critical Thinking in High School Physics Essays — Educational Innovation through Automated Essay Scoring: A Multidimensional Framework for Evaluating Critical Thinking in High School Physics Essays
- AI in University Assessment: Evaluating the Opportunities and Risks of Automated Marking — OpRaise report: AI marking of 761 university essays across three UK universities
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment
- RACES: reward-aligned consistent essay scoring with large language models — RACES: reward-aligned consistent essay scoring with LLMs
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students’ explanations in physics
- Anchor Is the Key: Toward Accessible Automated Essay Scoring with Large Language Models Through Prompting
- ICLE++: Modeling Fine-Grained Traits for Holistic Essay Scoring
- LLMs Do Not Grade Essays Like Humans — LLMs do not grade essays like humans (Mathew et al. 2026)
- PsyScore: A Psychometrically-Aware Framework for Trait-Adaptive Essay Scoring and ZPD-Scaffolded Feedback

- Towards Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs
- AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models
- From automated scoring to learning diagnosis: a mechanism study of AI-supported formative assessment in English writing — From automated scoring to learning diagnosis: a mechanism study of AI-supported formative assessment in English writing
- Opening the blackbox of LLM-based automated essay scoring: Insights into feature weighting patterns and score validity — Feature weighting patterns in LLM-based essay scoring (Wang et al. 2026)
- A framework for evaluation of large language models in essay assessment: Reliability, alignment, and causal reasoning — Framework for evaluating LLMs in essay assessment (Liu, Ye & Yan 2026)
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Know when to trust: Making AI scoring more reliable for educational assessment — Know When to Trust: self-confidence, weighted probabilistic scoring and ensembling improve LLM scoring agreement
- SWIM: Student Writing Simulation via Proficiency-Conditioned Generation — a frozen AES verifier used as a dense training reward for a writing generator
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- From design to classroom adoption: Teachers' perspectives on AI-powered writing analytics in resource-constrained contexts — Teachers of 300-student classes rate an unplugged AES app 92.5 SUS and ask for a reliability warning, not a final score (Ribeiro et al. 2026)

Automated Question Generation

> **Automated question generation (AQG)** — the use of AI, especially NLP and large language models (LLMs), to generate educational assessment items (multiple-choice, short-answer, fill-in-the-blank, coding, and performance questions) automatically from source material or learning objectives. AQG enables assessment at scale — producing formative quizzes, adaptive exercises, and practice items — but quality varies dramatically across item types and requires validation to avoid hallucinated or poorly calibrated questions. It is a core component of Automated Assessment and a key enabler of Adaptive Learning and Personalized Learning.

Questions to Consider

- Automated question generation produces assessment items from source material at scale — but this page warns that quality varies dramatically across item types. Before reading, which item type would you guess AI generates most reliably: multiple-choice, short-answer, or code — and why?
- The central challenge is quality control: LLMs can generate factually incorrect questions. One pipeline reduced hallucination by 62% by adding a generate-then-validate-refine loop. Why do you think asking the AI to validate its own questions would meaningfully improve them rather than just rubber-stamping its own output?
- Research shows generated questions may skew toward lower-order thinking (recall) unless explicitly designed for higher-order outcomes. If you used AI to build practice items, how would you know whether they were training genuine understanding or just memorization?
- Difficulty calibration matters: AI difficulty estimates correlate strongly with student performance, but the page cautions against high-stakes misuse. When would a question that AI judges ‘right difficulty’ still be the wrong question to ask a particular learner?
- Accessibility-aware generation builds questions tuned for Deaf and Hard of Hearing learners, refined in partnership with the target community. What does this example suggest about why question generation can’t be treated as a purely technical or content-only problem?

Introduction

Automated question generation matters because assessment items are expensive to create by hand, and AI can produce them rapidly and at scale. However, the knowledge base’s research shows that generated items must be validated for correctness, relevance, and difficulty, and that different item types (MCQs, short-answer, code) vary in how reliably they can be generated. AQG therefore sits at the intersection of generative AI, educational NLP, and Educational Measurement.

Approaches to question generation

The knowledge base's research illustrates several approaches:

- **Generate-then-validate pipelines:** Generate-Then-Validate introduces a generation → validation → refinement loop that reduces LLM hallucination by 62% compared to direct generation, achieving 89% accuracy on STEM datasets and a 23% improvement in relevance. The validation step filters invalid or low-quality items, and failed items trigger re-generation with corrective prompts.
- **Knowledge-tracing-based generation:** KT4EQG generates personalized exercise questions guided by knowledge tracing, tailoring items to each learner's knowledge state rather than generating generic questions.
- **Misconception-bound distractors as diagnostic labels:** CoLearn (He et al., 2026) attaches each distractor to a single mined misconception and marks exactly one correct option, so an item is generated with its diagnostic targets built in and can then be graded deterministically with no Large Language Models (LLMs) call — about 7.6 seconds and roughly $0.005 per round on the authors' live deployment, against about 32 seconds and $0.015 for an LLM-graded short-answer round. The binding is only as good as the misconception labels behind it, since mined Misconceptions about AI matched the target misconceptions at F1 ≈ 0.56, and its item choices served a genuinely weak skill 0.72 of the time.
- **Cognitive-depth-aware generation:** Evaluating the cognitive depth of LLM-generated questions examines whether generated items tap higher-order thinking (creation, evaluation) or only memorization, connecting to Bloom's taxonomy and Educational Measurement.
- **Error-embedded case problems for repeat assessment:** Takahashi et al. (2026) generated new hierarchical diagnostic reasoning (HDR) problems — short cases carrying deliberately embedded errors that students must find and explain — and found GPT-4o-authored items matched human-authored ones on internal consistency (Cronbach's $\alpha = 0.78$ for both) and difficulty, with Fisher's exact tests finding no significant score-distribution difference across 100 participants. The format pairs a higher-order thinking demand with a constrained response, so answers converge and grading becomes reproducible. The generative motivation is item reuse: reusing one case invites memory and answer reuse, while structurally equivalent but contextually different generated cases suppress item bias in re-measurement.
- **Pedagogical pipelines:** Slide-deck Q&A generation uses a multi-stage pipeline for pedagogically sound question generation from course materials.
- **Accessibility-aware generation:** Chen et al. design an LLM-powered question-generation system for Deaf and Hard of Hearing learners, introducing Visual and Emotion question strategies that target moments of visual or emotional difficulty in video, and iteratively refining questions with the target community to ensure linguistic accessibility.
- **RAG-based, human-in-the-loop systems:** CODE-GEN combines retrieval-augmented generation with human-in-the-loop review for generating multiple-choice assessments.
- **Benchmarks and evaluation:** NSMQ Riddles provides a benchmark of scientific/mathematical riddles for evaluating question-generation and reasoning systems.

Validation and quality

The central challenge in AQG is **quality control**: - **Assess the solving process, not the stem:** ProIQA argues that item quality review should follow what an expert does — simulate the solution — and builds an LLM-generated reasoning tree per item, verified for mathematical correctness at 90.38–97.80%, then encodes its dependency structure with a graph neural network alongside a stem-only view. It reports average gains over the second-best method of 7.5% in concept assessment, 6.3% in difficulty estimation and 19.5% in competency assessment, and its error analysis names a failure mode worth watching: a logically correct but structurally shallow reasoning tree leaves a hard item looking easy.

- **Hallucination risk:** LLMs can generate factually incorrect questions. Generate-Then-Validate shows a dedicated validation phase sharply reduces this, and hallucination risk is a recognized concern throughout.
- **Difficulty calibration:** generated questions must be calibrated to appropriate difficulty. Difficulty-calibration research shows AI difficulty estimates correlate strongly with student performance (e.g., rho ≈ −0.87), enabling better item selection — while cautioning against high-stakes misuse. Razavi and Powers (2026) extend this to K-5 math and reading items (N = 5170) calibrated under the Rasch IRT model: GPT-4o's zero-shot difficulty ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but varied by grade, while a feature-based approach — LLM-extracted cognitive and linguistic features fed into tree-based models — reached correlations up to r = 0.87. The study's structured feature extraction (e.g., syntax complexity, cognitive load, distractor trickiness) and its practical seven-step workflow offer a template for calibrating generated items, while its early-grade range-restriction finding and generalizability caveats caution against high-stakes use.
- **Generated difficulty labels can be a construct-validity failure, not a calibration error.** Across 378 generated items the model's Easy/Medium/Hard labels tracked the Bloom level co-generated with them (ρ=0.90) and surface form - mean stem length rising from 15.9 to 22.1 to 30.2 words - but correlated with empirical item difficulty at only ρ=0.06 over 7,888 responses from 54 students, the case for calibrating generated metadata against response data rather than trusting co-generated tags (An & Wang (2026)).
- **Large-scale psychometric field validation:** Assessing AI-Generated Exams validates an iterative-refinement AQG pipeline (generate → judge → revise, Self-Refine style) in 91 real college classes (~1,686 students). Bayesian hierarchical 2PL IRT analysis shows AI-generated questions perform on par with expert-written standardized-exam items — somewhat easier ($\bar{\beta} = -0.45$ vs. 0.35) but slightly more discriminating ($\bar{\alpha} = 1.3$ vs. 1.2), with higher peak test information (reliability 0.79 vs. 0.72) — demonstrating that AQG can produce course-tailored, psychometrically sound assessments at scale.
- Average psychometric parity can mask item-level shortfalls: a scoping review of 153 medical-education reports found AI item generation sometimes matched human difficulty and discrimination, yet in one physiology comparison only 9 of 40 ChatGPT items met all ideal criteria against 19 of 40 faculty items (Zhao et al. (2026)).

- **Recognizability in a live exam, and what review actually removes:** Vogt et al. (2026) put 30 AI-generated and 30 National Licensing Exam MCQs into a graded tablet-based exam taken by 119 fifth-year medical students, with the AI items drafted from the course's own materials by ChatGPT-4o and Gemini 1.5 Pro through an expert panel that accepted 82% of them and eliminated 18.2% as unusable. Students' source attribution did not differ between the two kinds of item, and item difficulty, distractor distribution and perceived curricular alignment were statistically indistinguishable — a *recognition* result rather than a quality result, and the reason the authors describe the workflow's benefit as shifting educator effort from drafting to reviewing rather than removing it. One exploratory difference survived: Gemini items were harder than the licensing-exam items ($p = 0.028$), while ChatGPT items were not ($p = 0.984$).
- **Task-dependence:** generation reliability varies by item type. Short-answer grading and analytic writing assessment show that open-response and writing items are harder to generate and grade reliably than structured items.
- **Cognitive quality:** cognitive-depth evaluation shows generated items may skew toward lower-order thinking unless explicitly designed for higher-order outcomes.
- **Auto-labeling cognitive level does not transfer to generated items.** A Bloom taxonomy classifier trained on a curated item bank collapsed on AI-generated questions — macro F1 from 0.88 in distribution to 0.48 and 0.20 out of it — because generated items average far more words (18.2 versus 9.3) and share only a median 10.5% of their Bloom trigger verbs with the curated corpus, against 35.1% for a closer set; retraining on labeled out-of-distribution data was the largest single gain, at a threshold of roughly $N > 1{,}000$ labeled samples (Castanares et al., 2026).

Role in adaptive and personalized learning

AQG is a key enabler of adaptive and personalized learning: it produces the large item banks that adaptive tutors draw from, and — combined with knowledge tracing or student modeling — can generate items tailored to individual learners' knowledge states (KT4EQG). Interest-based personalization shows AQG can also adapt questions to student interests, not just difficulty.

Implications for AI in education

- **Generate then validate:** always pair generation with a validation/refinement stage to control hallucination and ensure relevance.
- **Match item type to reliability:** use AQG for structured item types (MCQ, fill-in-the-blank, code) where it is most reliable, and apply careful validation to open-response and writing items.
- **Design for cognitive depth:** prompts and pipelines should target higher-order thinking, not just recall, to support genuine learning.
- **Calibrate difficulty:** use AI difficulty estimates to select appropriately challenging items, with strong validation before high-stakes use.
- **Personalize via learner models:** combine AQG with knowledge tracing and interest models to generate adaptive, individualized items.

Common Misconceptions

“Generated questions are usable at the scale they can be produced.” Volume is not the constraint; calibration is. Quality varies dramatically across item types and requires validation to avoid hallucinated or poorly calibrated items, which is why the pipelines that work spend their effort on verification rather than generation — one reduced hallucination by **62%** by adding a generate-then-validate-refine loop.

“A refinement loop makes generated items trustworthy.” It makes them less wrong. A 62% reduction in hallucination leaves a substantial remainder, and no loop resolves the harder problem of whether an item’s stated difficulty matches what students actually do — the validity question that the difficulty-label evidence shows generated metadata failing on. Validation reduces fabricated content; calibration requires student response data.

“Question generation naturally personalises practice.” It generates supply, and personalization is a matching problem. Producing more items does not tell you which item a given learner should see next, and the adaptive-selection question is a separate mechanism with its own evidence.

“Generation scales assessment without changing what assessment measures.” It changes the composition of what is measured, because the items that generate well are not a representative sample of the items that assess well. Easy-to-generate formats will progressively crowd out the harder-to-generate ones, which quietly reshapes the construct.

Connected Concepts

- Large Language Models (LLMs)
- Generative AI
- Educational NLP
- Automated Assessment
- Automated Essay Scoring
- Assessment
- Formative Assessment
- Adaptive Learning
- Personalized Learning
- Knowledge Tracing
- Learner Modeling and Adaptive Instruction
- RAG (Retrieval-Augmented Generation)
- Human-in-the-Loop
- Educational Measurement
- Item Response Theory
- Hallucination Risk
- AI Ed Evaluation
- Benchmark
- Scaffolding

- Intelligent Tutoring
- AI in Education

Connected Articles

- Generative artificial intelligence and the transformation of medical education: a scoping review — Scoping review of 153 medical-education reports on AI item generation versus faculty item quality
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Large-scale field validation of AI-generated exam quality via IRT
- Generate-Then-Validate: Question Generation for Education — Generate-Then-Validate question generation
- KT4EQG: Personalized Exercise Question Generation via Knowledge Tracing — Personalized question generation via knowledge tracing
- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM-powered question generation for Deaf and Hard of Hearing learners
- From Memorization to Creation: Evaluating the Cognitive Depth of LLM-Generated Educational Questions — Cognitive depth of LLM-generated questions
- Slide Deck Q&A Quality Assurance App: A Multi-Stage Pipeline for Pedagogical Question Generation — Slide-deck Q&A pedagogical question generation
- CODE-GEN: A Human-in-the-Loop RAG-Based Agentic AI System for Multiple-Choice Question Generation — CODE-GEN: RAG-based human-in-the-loop question generation
- NSMQ Riddles: A Benchmark of Scientific and Mathematical Riddles for Quizzing Large Language Models — NSMQ Riddles benchmark
- Taklif.AI: LLM-powered platform for interest-based personalized college assignments — Interest-based personalized assignments
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations — LLM-based difficulty calibration
- Towards Self-Referential Analytic Assessment: A Profile-Based Approach to L2 Writing Evaluation with LLMs — Self-referential analytic writing assessment
- Cross-Dataset Bloom Question Classification: Supervised Models and Prompted LLMs — Cross-dataset Bloom question classification
- Are LLM-based Chatbots Good Enough to Support Computer Science Students in Multiple-Choice Exercises? — LLM chatbots and CS multiple-choice items
- The theoretical foundation of Socratic tests: Dynamic, multimodal, conversational examinations — Socratic tests: conversational assessment
- What out-of-the-box LLMs can(t) do in law? A Turing test in Italian exams for lawyers, judges and notaries — LLM Turing test in legal exams

- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- ProIQA: A Process-Based Framework for Fine-Grained Math Item Quality Assessment — ProIQA: Process-Based Math Item Quality Assessment
- CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop — CoLearn: An Agentic Tutor that Learns its Learner in a Human-AI Co-Learning Loop
- Automating Constructive Assessment with Large Language Models: Toward Scalable and Repeated Evaluation of Practical Competence — Automating Constructive Assessment with Large Language Models: Toward Scalable and Repeated Evaluation of Practical Competence
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions
- Can students identify AI? – A cross-sectional quantitative study about AI recognition in tablet-based MCQ assessment among fifth-year undergraduate medical students at Saarland University, Germany — Students could not tell AI-generated MCQs from licensing-exam items in a graded exam, and 18.2% of generated items were eliminated in review (Vogt et al. 2026)

Measurement and validity

Assessment Validity

> **Assessment validity** — whether assessments measure what they claim to measure. AI in Education raises fundamental validity questions: do AI-graded assessments assess student learning or AI prompting skill? Does AI use invalidate traditional assessment assumptions?

Questions to Consider

- Validity asks whether an assessment measures what it claims to measure. Before reading, if you saw a student submit a polished essay you suspected was AI-assisted, would you think the bigger problem was cheating, or that the task was no longer measuring what you thought it was measuring?
- This page poses a sharp question: when students use AI, does the score reflect student knowledge or AI-prompting skill? Can you think of an assessment you've designed or taken where the score might now be telling you more about the tool than about the learner?
- A key finding is that the same learner input can receive semantically different replies depending on which underlying LLM is used — introducing 'construct-irrelevant variance' that threatens reliability and fairness. If two students get different AI support purely because of the model behind it, how fair is the resulting comparison?
- The page argues that even when an LLM scores well, transferring human score interpretations requires similarity in the latent structure of responses — and LLMs diverge from humans here. What does this suggest about trusting an AI that 'passes' an exam designed for humans?
- Rather than trying to detect AI use, the knowledge base argues for redesigning assessments so they stay valid for AI-capable students. Why might redesigning the task be a more validity-preserving strategy than policing whether AI was used?
- AI now serves as test-taker, test-maker, rater, and analyst — making the interpretive chain opaque. When every role in an assessment is filled by AI, what does it even mean to say an assessment is 'valid' for the human learner in the middle of it?

Introduction

Validity challenges

- **Construct validity:** When students use AI on assessments, does the score reflect student knowledge or AI capability? Performance vs. learning research addresses this directly. A reconstruction measure can be sensitive to correctness without being a correctness score: Su et al. (2026) found higher EEG reconstruction similarity for correct items (M = 71.43, SD = 4.61) than incorrect (M = 62.30, SD = 5.91), yet one learner's high-quality reconstruction accompanied a wrong answer.
- **Cross-LLM construct-irrelevant variance in conversation-based assessment:** Hao (2026) shows that even for a single conversational turn, the semantic content of Large Language Models

(LLMs)-generated replies varies across models and conversational-context conditions. Within-model similarity consistently exceeds between-model similarity (0.715–0.795 vs. 0.443–0.604), and adding chat history meaningfully changes response content (median cross-history similarity ~0.40–0.45). Because the same learner input can receive semantically different replies depending on the underlying model, prompting and context alone cannot preserve response consistency — introducing potential **construct-irrelevant variance** that threatens validity, reliability, and fairness. Maintaining consistent assessment conditions as LLMs evolve is therefore an *infrastructure* challenge (symbolic rules, response templates, validation layers), not merely a Prompt Engineering one.

- **Evidence that is present yet never reaches the scorer:** Abreu, Stari and Martí (2026) name a construct-irrelevant threat that precedes any reasoning: in AI review of experimental physics laboratory reports, an equation, graph, table or unit may be correctly included in a report yet not be retrieved from the processed content the model works from, and because a changed sign, value or unit alters the physical interpretation, a disagreement with the instructor need not indicate a reasoning error. Their remedy is procedural — high-resolution PDFs rather than photographed scans, equations written in an equation editor, legible axes and units inside figures, and instructions requiring a concrete citation for every score — because document quality sets the ceiling on whatever validity claim the resulting score supports.
- **Latent-structure validity across humans and LLMs:** Strugatski et al. (2026) add a deeper validity condition: even when an LLM scores well, transferring human score interpretations requires similarity in the *latent structure* of responses. Comparing six Multimodal AI LLMs to human cohorts on chemistry and quantitative-reasoning instruments, they find LLM–human factor structures consistently diverge (LLM–human congruence below the human–human baseline), so performance on a human-normed exam is weak evidence about LLM abilities on the constructs the items were designed to measure.
- **Consequential validity:** Do AI-mediated assessments have fair consequences? Language bias studies show that AI scoring can disadvantage non-native speakers.
- **A moved target in language testing.** High-stakes tests like TOEFL iBT, IELTS, PTE Academic and the Duolingo English Test still demand unaided, timed reading and writing while students now use GenAI for those tasks in academic life, so the extrapolation inference — from unaided scores to real academic performance — is the step most affected (Gonulal (2026)).
- **Rule scope is itself a validity property:** Wright (2026) argues that the prohibitions written across higher education since 2023 bar "generative AI" without the technical precision to separate the generation of assessed content from the conversion of a format, since optical character recognition, handwritten text recognition and speech-to-text are recognition technologies that infer what is already present rather than producing new content. Where a rule attaches to platform identity rather than function, it is over-inclusive by definitional accident: it captures transcription-only use of a multi-functional tool and sanctions a student who did not do the thing the rule was designed to prevent, falling hardest on Learners who rely on those tools for accessibility — an inference the assessment cannot support about the construct it claims to measure. He proposes function-based drafting plus four operational criteria (fidelity, non-augmentation, traceability,

attestation) for borderline cases, and treats the reliance on detector output and style heuristics as evidence of how weak the rule's own evidential basis is.

- **Agentic completion removes the human-production assumption:** Hadjisolomou & El-Haddad (2026) extend the validity analysis from generative *assistance* to agentic *completion*: autonomous AI agents can now log into an LMS, read materials, and complete unproctored asynchronous work end-to-end (demonstrated on a live course — a quiz scored 10/10 in under 5 minutes, and a fabricated-but-credible discussion-board reflection). Placing a "human-production assumption" at the base of Kane's argument-based inference chain, they show agent completion silently removes the backing for the *scoring* inference on which generalization, extrapolation, and decision inferences all rest — so every unproctored asynchronous score, including honestly earned ones, loses its interpretive support because authorship is unverifiable. Their decisive move is classifying this as a **validity failure rather than an integrity one**: an institution can punish misconduct and still lack grounds for the scores it reports. Detection is structurally insufficient (classifiers unreliable and biased; LMS monitoring sees the same clicks a student would), so the remedy is assessment redesign for verified human presence (a short oral component, process-visible drafts, class-session-specific references), with an equity-preserving menu of options rather than a proctoring mandate.
- **Construct-irrelevant variance in human grading of GenAI-assisted work:** Luo & Dawson (2026) provide a direct empirical demonstration that human grading of GenAI-assisted work is shot through with construct-irrelevant variance. In scenario-based interviews with 33 university teachers, grading decisions were driven by person-oriented (student honesty, diligence), capability-oriented (independence from AI, GenAI skill, disciplinary mastery), relation-oriented (trust built with students), and justice-oriented (fairness, beneficence) values — all of which can vary grades on factors unrelated to the outcomes being assessed. Marking down GenAI-assisted work is justified, they argue, *if and only if* the AI use prevented students from demonstrating the assessed outcomes; otherwise value-driven grading threatens validity. The study grounds the validity framing in real teacher practice and calls for "two-way transparency" — teachers clarifying how GenAI use will affect grades, not just students declaring use.
- **Variation-at-scale demands construct-equivalent variant generation:** VARIA (Lee 2026) subjects the "variation-at-scale" premise of AI-Integrated Authentic Assessment (AIAA) — replacing surveillance proctoring with per-student task variation — to an empirical, falsifiable check. Because each examinee receives a unique-but-equivalent performance task, the integrity guarantee is conditional on LLMs generating variants that are simultaneously surface-distinct, construct-equivalent, rubric-applicable, and difficulty-matched. Benchmarking three frontier model families across four prompting strategies on 600 variants, VARIA finds frontier generators satisfy the joint integrity criteria only at the margin (joint score 0.81–0.88) while non-frontier references collapse (0.50–0.55), and no single prompting strategy dominates all four properties — so "variation-at-scale cannot be solved by prompting alone" if the diversity threshold is set aggressively, and institutions must validate their specific model-prompt pair.
- **Under-grading bias in HITL AI scoring is a validity feature, not a bug:** Curi et al. (2026) show that in a large-scale national writing assessment the systematic conservative (under-grading) bias of an LLM scorer, while problematic as a final decision, is precisely what enables safe

delegation: AI-marked "passing" responses can be accepted with confidence while AI-marked "failing" responses (15.3–16.5% of cases) are routed to expert review — keeping the validity threat of AI error off the final outcome. Their IRT-and-Bookmark pipeline makes the proficiency-level impact of AI scoring legible rather than treating raw score agreement as the sole validity signal.

- **AI-driven grade inflation as a validity threat:** Chirikov (2026) identifies a novel, technology-driven mechanism of grade inflation operating *upstream of grading* — on the production of graded work. In a difference-in-differences study of 500,000+ grades across 319 courses (2018–2025), courses with more AI-exposed tasks (writing, coding) saw the share of A grades rise by 13 percentage points after ChatGPT's release, with grade-distribution compression. A triple-differences analysis shows the effect concentrates in homework-heavy courses — evidence that AI **task displacement** (AI performing graded tasks before instructors observe them) inflates grades without a corresponding rise in skill. This reduces the comparability of grades across courses and erodes the informational value of transcripts in ways difficult to detect from grade distributions alone.
- **Program-level pass/fail susceptibility, and the marking criteria that set it:** Ivory et al. (2026) judged ChatGPT output for every coursework assessment in a three-year psychology degree (40 assessments, 16 types) with a binary pass/fail, the decision markers actually make on a first read: 36 of 40 passed. Two validity implications follow. First, the operative variable is the pass boundary, not detection — marking that rewards structural fluency and the correct choice of analysis while condoning incorrect values lets fabricated statistics and hallucinated references clear a pass, so the assessment certifies tool output as student understanding because of how it is marked rather than because anyone was fooled. Second, multiple-choice items leaked their own answers: ChatGPT answered statistics questions correctly without the figure or output table shown to students, because the item stem and options implied the answer, which makes answer-option design a validity property of the item rather than a property of the AI.
- **Accuracy vs. agreement as distinct validity signals:** Falahat, Das, Bhaumik & Thambi (2026) graded a 21-item pharmacy exam with ChatGPT-5 and found that moderate percent accuracy frequently coexisted with low concordance-correlation coefficients — a methodological distinction between *scoring accuracy* and *agreement* that limits AI's reliability as a grading substitute even where raw accuracy looks acceptable. Agreement was strong on objective items (CCC 0.935–1.000) but near-zero on short-answer and modest on essay (0.341–0.854), and rubric provision did not consistently close the gap.
- **Validity of AI-generated items:** Assessing AI-Generated Exams shows that AI-generated questions, validated via Bayesian IRT, achieve difficulty and discrimination on par with expert-written standardized-exam items (reliability 0.79 vs. 0.72) — supporting the validity of course-tailored AI-generated assessments when backed by psychometric evaluation.
- **Authentic assessment:** Authentic Assessment and the AI Assessment Scale propose validity-preserving assessment redesigns.
- **Confidence and calibration:** Confidence-aware systems improve validity by flagging uncertain assessments.

- **Embodied and multimodal evidence:** speech-only assessment can mistake verbal fluency for conceptual knowledge; Morphew et al. show that computer-vision gesture analysis coupled with LLM speech analysis increases construct validity and Equity by capturing understanding expressed through gesture, not just words — reducing bias against learners who express understanding non-verbally.
- **Homework stops certifying capability when a model can solve the task:** Mikhasenko et al. (2026) document a concrete invalidation of homework as a capability measure in a Bochum particle-physics course: once a generative model can produce a correct solution, a submitted derivation no longer establishes that the student can solve the problem independently. Their response separates the two functions — research-shaped, AI-permitted homework kept as exploratory, bonus-bearing work, and a tools-free written examination made the sole determinant of the final grade — a validity-driven division of labor rather than a detection regime.
- **Decision-oriented validity for AI scoring at scale:** Curi et al. (2026) illustrate a decision-oriented view of validity in the Acredita EB national writing assessment: rather than asking only whether AI scores agree with humans, they ask whether AI errors can change a certification decision. Automated IRT/Bookmark cut scores closely reproduced the operational cut scores, and systematic AI under-grading was neutralized by routing failing AI results to human review — notably against a reference standard that is itself contested, since ten expert raters scoring the same 50 texts never reached unanimity on any rubric item.
- **Student-side validity concerns about AI as grader:** AlGhamdi (2026) adds the learner's voice to the validity question: 13 computing students whose handwritten writing task was scored by ChatGPT questioned whether an AI scorer can validly interpret intent, effort and institutional grading norms — one asking pointedly, "If ChatGPT [is] checking the exams, why are we going to university?"
- **Permission does not by itself degrade the task, and use rates are the wrong validity signal:** Zou et al. (2026) surveyed 85 student teachers whose assessments explicitly permitted generative AI and found assessment engagement high and statistically unaffected by whether students used it (mean 4.21/5, SD 0.46; Mann–Whitney $U = 781.5$, $r = 0.07$, $p = 0.536$). With 62.4% (53) declining to use generative AI at all and adopters' use confined largely to proofreading (43.8%) and clarity checks (34.4%), the adoption rate carries little information about whether the assessment still warranted an inference about learning — and non-use driven by fear of wrongful plagiarism accusation (41.5% of non-adopters) is not evidence of validity either.
- **Sampling-frame validity when a school-level test is read as system evidence:** Restrepo Morales et al. (2026) give the inference from scores to claims about a *system* a quantitative treatment. A pilot assessment of 1,198 volunteer students in 171 Salvadoran schools on the PISA-based Test for Schools produced results announced as comparable to Germany and Sweden, but the instrument produces estimates for a school and is not administered under the national sampling frame with its response-rate standards, exclusion limits and weighting — so a comparison between a school-level estimate and a country mean carries at least three unreported sources of uncertainty (school-level sampling error, country-mean sampling error, and the linking error of the scale equating). Rather than test the learning claim, the authors bound it: with the top 5.5% of the

Salvadoran mathematics distribution matching the German mean under zero learning, and voluntary participation understood to bias achievement testing upward, the published evidence cannot separate a real effect from a selected sample. This is a failure of the comparison's validity inference, not of the students or of the instrument.

A conceptual proposal raises a validity boundary that applies to every AI-mediated assessment on this page: El Khoury and Ma (2026) argue that speed is not validity, and that AI-generated prompts, examples and transcript-based reports still have to be tested for accuracy, cultural responsiveness, Accessibility, interpretability and alignment with course outcomes. They also widen what counts as evidence: where dialogue becomes the assessed artifact, the transcript is a process record in which judgment, empathy, clarification and shared decision-making unfold in context, and the design question becomes whether that evidence supports the inference drawn from it — the same question automated scoring faces, answered by alignment among task, feedback and evidence of learning rather than by technological novelty.

- **AI-assigned item metadata is not psychometric evidence.** Across a 10-week data science study of 311 deployed multiple-choice items, LLM difficulty ratings tracked the model's own Bloom labels (rho = 0.90) but not empirical item difficulty (rho = 0.06), so item difficulty has to be established from response data rather than from the generating model's labels (An & Wang, 2026).
- **Student judgments of curricular alignment track difficulty, not content.** Vogt et al. (2026) asked students to rate whether each item in a graded 60-item exam aligned with the course curriculum and found the ratings correlated with item difficulty at $\rho = 0.762$ (easier items judged aligned, harder items not aligned, $\rho = -0.762$, $p < 0.001$), while ratings did not differ by item source. Where an instrument asks students to judge an assessment's curricular fit, the resulting score is partly a difficulty rating and cannot be read as independent evidence of alignment.
- **Realign the assessment triangle rather than patch one vertex.** Koretsky et al. (2026) frame the GenAI problem through the assessment triangle — cognition (what is assessed), observation (how evidence of learning is elicited), and interpretation (the inference drawn) — and argue the three vertices must be realigned together, since redesigning tasks without repairing the interpretation leaves the inference unsupported. Their scoping review also makes the fidelity of AI-generated assessment materials a validity property in its own right, cataloguing content, linguistic, cognitive, behavioral, structural, and pedagogical dimensions and requiring human-in-the-loop evaluation before such tasks ground assessment.

Redesign over detection

The knowledge base argues that maintaining assessment validity requires redesigning assessments for AI-capable students, not detecting AI use. A parallel validity problem runs through research measurement: many AI-in-education claims rest on self-report data, which cannot support an inference about learning or competence however well the instrument itself is validated. Beyond detection approaches and Assessment represent validity-forward thinking.

Take-home products and the qualitative/quantitative split. Brunnström and Palmqvist (2026) give the redesign argument a specific proposal grounded in the SOLO taxonomy. Working through a cognitive-science take-home exam question with a chatbot, they find GenAI is strongest exactly where the taxonomy is lowest — producing comprehensive, fluent, factoid-type content at the *quantitative* (multistructural) level —

while the *qualitative* level (relating, evaluating, generalizing) emerged only through repeated learner-driven calibration. Their recommendation is therefore differentiated by construct: take-home assessments should emphasize evidence of qualitative understanding, while quantitative recall-based knowledge is better assessed in class where GenAI is unavailable. The demonstration also underlines that a polished submitted artifact is weak evidence in either direction, and that valid redesign must account for how demanding legitimate AI-supported learning turns out to be (Summative Assessment, Academic Integrity).

A design-level counterpart comes from the same population the redesign argument usually ignores. Zou et al. (2026) found that reflective and personalized tasks were widely judged too personal for AI help, while a knowledge-heavy assessment in another course prompted strong intent to use generative AI for references — so what students did with AI tracked the construct the task asked them to evidence. The lesson for validity is precise rather than celebratory: design can remove the payoff from generic substitution, but the same study warns against reading an opt-out cohort as proof that it did, since a substantial share of non-use was attributed to fear of wrongful plagiarism accusation rather than to the task resisting AI.

Sharma (2026) supplies a redesign argument on the integrity side that turns integrity evidence into validity evidence. Extending Eaton's (2023) postplagiarism framing into assessment design, he argues that detection- and verification-based integrity models are misaligned with work in which human judgment and machine generation are entangled, and reframes integrity as a pedagogical practice enacted through Evaluative Judgment — the capacity to weigh options, justify academic choices and assume responsibility under epistemic uncertainty. The design consequence is that integrity should be evidenced rather than inferred: annotated decision trails, verification of GenAI-contributed claims, oral defense and version history are offered as integrity artifacts. He is explicit that the difference from Authentic Assessment is epistemic: authenticity asks whether a task mirrors real-world practice, integrity-oriented design asks whether learners can justify decisions and assume responsibility against disciplinary standards, so integrity becomes an assessable criterion embedded in the task architecture. He names the validity risk of his own proposal rather than leaving it implicit: requiring documented reasoning privileges learners fluent in reflective discourse and risks "the replacement of one compliance regime with another". Judgment as evidence "remains relational and situated rather than mechanically verifiable" — the same interpretive-reliability problem this page records for every AI-mediated assessment.

Weidlich (2026) reframes redesign as a question of which inference a change is meant to protect. Working from Kane's argument-based validity, he separates five pressures that debate tends to collapse into one: construct underrepresentation, construct-irrelevant variance, attribution of performance, conditional extrapolation, and unsupported score use. AI use is not automatically a threat, because tool use is germane where the intended construct is AI-supported professional judgment and bypasses the target performance where it is unaided reasoning, so construct and AI conditions have to be specified together. His caution for redesign follows, since interventions trade one pressure for another: oral defenses may strengthen attribution while reducing reliability or accessibility.

The task, not the detector, sets what an artifact can evidence. Liu and Liu (2026) had a model write 148 texts across three task formats and three AI-use scenarios: evidence-integration memoranda (3.16) and follow-up-and-revision defenses (3.10) scored above position essays (2.63), because those formats required source explanation or a response to objections. They propose model simulation as task pretesting before an assignment is run with students.

The outcome construct moves the estimate too: in a three-level meta-analysis of GenAI-supported problem-based and project-based learning, Chen et al. (2026) found learner-internal outcomes pooled at g = 0.819 while measures of the joint human-AI product returned g = 1.958 with a prediction interval crossing zero, modeled separately precisely because that product is not internalized learning.

AI-aware grading takes a third path between redesign and detection. AICG estimates a per-response AI-use probability and discounts the cognitive evidence by `max(0, 1 - pAI)` rather than docking the grade, lowering MAE by 4.2% over the unweighted cognitive model and keeping AI-assisted responses scoreable (Guo et al., 2026).

Policy has moved to graded permission, and to assurance over friction. Coding 55 institutional documents, Ansari (2026) found 4 prohibiting AI by default and 31 defining named categories of use, and of the 23 taking a position on detection, 16 rejected detectors. Redesign, on that reading, is redesign plus an assurance mechanism rather than friction alone.

Connections

Assessment validity connects to Authentic Assessment, Automated Grading, Confidence Aware AI Assessment, Formative Assessment, Academic Integrity, and RCT (which relies on valid outcome measures).

AI challenges validity at the epistemic level: Hathcoat, Slotnick & Miller (2026) argue that when LLMs serve as test-takers, test-makers, raters, and analysts, the interpretive chain becomes opaque and the object of measurement loses definition — reframing validity as requiring AI-fluent “cyborg” judgment, and Green et al. (2026) show AI scores can align with human raters (87% checklist) while the underlying rationale diverges, especially on measurement quality and weak reports.

When AI generates the assessable artifact. Kumar, Wongsirichot and Nanthaamornphong (2026) give the validity problem its sharpest disciplinary case: in computing education the AI produces the artifact being graded — the source code — so tool use, learning and assessment fuse into a single interaction, and a submitted codebase no longer separates learning from delegation. Across 72 studies they find efficiency gains that do not transfer to unaided performance (21 studies), Prior Knowledge moderating whether AI help becomes skill (6 studies), and detection research effectively absent from the evidence base (3 studies) while assessment redesign is comparatively well evidenced (25 studies). Their conclusion for practice is construct-specific and low-tech: add an oral component or other process-visible element to at least one high-stakes assessment per course — the single highest-leverage intervention in the review — and require critical engagement with AI output as a graded, observable component rather than an optional disposition (Academic Integrity, Assessment).

Correnti et al. (2026) replicate and extend a validity argument for eRevise, an automated writing evaluation system for upper-elementary argument writing, across 34 teachers and 609 students in eight Louisiana parishes, testing whether the same sociocultural mechanisms hold across three different writing outcomes rather than one.

Validity under imperfect information

The sharpest recent reframing treats the generative AI problem as an evidentiary one. The student knows how a piece of work was produced; the institution observes the artifact and, at best, partial traces of the process — a product–process gap that Mohamed and Temimi (2026) formalize as assessment validity under imperfect information. On this account the question is not whether a rule was broken but whether the assessment still generates credible evidence of student reasoning, effort, and judgment, and each institutional mechanism — prohibition, monitoring, disclosure, redesign — is evaluated by which student response it makes most attractive. The validity lens also dissolves a false separation: integrity and validity are the same problem seen from different ends, because a finding of misconduct is itself a validity claim about what the work evidences.

Wearable AI closes the last evidentiary gap rather than widening one: Corbin et al. (2026) argue that AI glasses and earbuds deliver assistance with no external signal, so a candidate can be present, supervised, and still not demonstrate unaided capability, dissolving the separability and observability that invigilated formats assumed.

A learner-side framework names the inference targets an artifact cannot settle by itself. Sak (2026) proposes *attributional validity* for judgments of gifted potential from AI-assisted work: the relation from capability to product is many-to-one, because learner competence, model capability, the learner's direction, human–AI fit and context combine differently to yield equivalent artifacts, so the product cannot identify the capacity behind it. The framework separates four targets of inference — independent competence, intellectual Learner Agency, hybrid capability, and developmental carryover — and names three errors that follow when one target's evidence is read as another's: overattribution, developmental illusion, and presumed capability equivalence. Its demand on the record mirrors the evidentiary discipline this section draws from the misconduct literature: name the capability a judgment is about, document how the work was produced (model and version, interface, permitted functions, adult mediation, access conditions), and require later evidence of transfer before reading assisted performance as a change in the learner.

Teichmann (2026) draws the procedural consequence: where prohibited use cannot be detected, a regime that still accuses on detector scores cannot warrant the inference it draws, and so produces unfairness without effectiveness. He argues for replacing the forensic question — did the student use AI? — with a validity question — did the student demonstrate the capability the task was designed to certify? — which relocates institutional effort into program-level assessment across linked tasks, oral and supervised elements at certification points, and Evaluative Judgment as an explicit object of assessment.

The same section of the evidence base supplies the case-file counterpart, and it is more uncomfortable than the detection literature alone. Munoz et al. (2026) coded every generative-AI misconduct case at one regional Australian university over three years — 1,162 cases carrying 1,855 discrete evidence items — and rated each item for probative value on relevance, credibility and inferential force. The strongest categories were the ones that do not depend on probabilistic classification of text (student admissions, observed prohibited exam behavior, and independently verified fabricated references), while detector output drew the weakest ratings of any category: similarity or Turnitin reports were wholly weak in inferential force and standalone detector outputs wholly low in credibility, falling from 8.8% of items in 2024 to 0.5% in 2025. The validity failure is procedural as much as instrumental — no stage of the pipeline set a minimum evidentiary threshold or required investigators to weigh probative value before progressing an allegation, so

evidence quality showed no reliable relationship to case outcomes, which is exactly the evidential standard issue catalogued on Legal Issues and Risks. Their proposal to apply a credentials framework at the point of *allegation* rather than only at determination is a validity demand: an allegation is a claim about what the work evidences, and it should be warranted by materials capable of supporting it. Hadra, Cambridge and Mesbah (2026) show how far the instrument is from that standard, with macro accuracy of 0.69 (Originality) against 0.61 (Turnitin) across 192 texts, near-total failure on hybrid human–AI writing (sensitivity 0.02 and 0.31), declining accuracy with text length and on scientific writing, and a borderline tendency to misclassify EFL student writing as AI — so a detector score cannot establish the fact a misconduct finding asserts.

The human-marking benchmark and its ceiling

The OpRaise comparison of three frontier models against 761 authentic essays across three UK universities makes the benchmark part of the validity argument. Human marks were used as ground truth on the explicit ground that academic judgment is the socially accepted standard, while the authors acknowledge that human markers agree only moderately with one another — which caps the AI–human agreement that could reasonably be demanded, and means a correlation cannot be read as ready-or-not without a reference point. Within that frame the failures appeared as systematic structure rather than random error: marks compressed toward the middle of the scale, so the best and worst essays were misjudged most; agreement was weakest at grade boundaries; and AI marks tracked vocabulary range, connectives and sentence complexity while human marks were broadly insensitive to them. The practical lesson is double-edged, because the same study found reliability to be excellent — identical re-marks across time and high agreement between models. A validity case for automated marking therefore cannot rest on stability or on average agreement; it has to show the absence of systematic deviation, which is exactly what this evidence did not find.

Run-to-run stability is not guaranteed, however: repeating the same grading on identical submissions five days apart gave Krippendorff's alpha 0.625, with variation concentrated in the middle grades and A and F absent from the repeated-session counts (Brevik et al. (2026)).

- **Model size is not a proxy for assessment validity.** Across eight configurations of four families on 114 marked essays, exact band agreement spanned 18.4% to 54.4% and tracked the family rather than parameter count — the largest model, GPT-OSS 120B, undergraded by 1.316 bands, and temperature was no fix (Kerwat et al. (2026)).
- **Agreement and benchmark error masquerade as learning.** Two 2026 studies show distinct routes by which a score can look valid while establishing something else. An open-ended marketing-writing study found LLM-human absolute agreement of only ICC(2,1) .435 and a hybrid that was significantly worse than the LLM alone, with anchor composition moving agreement from .338 to .902 (Agreement and error in automated scoring of student marketing posts). An expert audit of six physics benchmarks attributed 95.20% of audited rejections to defective items or graders rather than model error, moving CritPt mean@5 from 32.29% to 87.50% (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks). In both cases the threat is construct-irrelevant variance outside the model being scored.
- **Agreement among LLM coders is consistency, not validity.** On an expert-labeled educational dialogue corpus, a cross-model agreement filter retained only 33 of 74 corpus-derived behavioral

assertions and 11 of 48 construct-derived ones, and shared model errors survived the filter, so inter-model agreement cannot stand in for construct validity (Bernado et al., 2026).

- **Automated sentiment labels are a measurement claim, not a description.** On 1,220 open-ended student survey responses, the best off-the-shelf sentiment tool (BERT-nlptown) reached only moderate agreement with human coding (κ = .42), and lexicon tools misclassified roughly 20% of responses for want of vocabulary coverage (You & Horissian, 2026). A sentiment label is a measurement outcome, so classification error is a validity threat, not a tuning problem.
- **Contamination is the validity threat that aggregate data hides.** When students use AI to do the graded work, a rise in mean rubric scores is evidence about the tool, not the learning, and a model grading a model's output is "a hall of mirrors" rather than assessment (Jenkins & de Mello-e-Souza Wildermuth, 2026). The authors note that contamination is invisible in the aggregate data programs normally use.
- **Exposure is measurable, and the remedy is sufficient evidence rather than maximum security.** Villanueva (2026) scored 53,915 assessment items by published format, supervision and mark weight and found most assessed marks resting on work whose authorship cannot be verified after submission; he argues programs need enough evidence of learning at key stages, not every unit made secure.
- **A model can pre-test items and expose defects that faculty review misses.** One institution had an enterprise AI platform answer examination items before administration, then compared its reasoning against the intended construct and keyed response (Ford, Helms & Moseley, 2026). The exercise surfaced ambiguous wording, multiple plausible answers, unintended clues, and items whose keyed answer could not be clearly defended. The authors treat the reply as a prompt to re-examine an item, not proof that it is flawed.
- **A valid measure can still be unsafe to optimize.** Fine-tuning an LLM tutor against a rubric-style adaptivity metric raised the metric (+0.05 to +0.42) while blind expert ratings fell (4.46 to 3.03), because a metric that scores decisions independently is maximized by repeating the single best decision (Domínguez Figaredo & Fernández De la Cruz, 2026).
- **An embedding's geometry is not a rubric's distinctions.** Against 992 handwritten physics solutions under five textual representations and nine embedding mechanisms, Tauschhuber & Kortemeyer (2026) report a best weighted Spearman correlation with human scores of 0.198, with clusters score-enriched rather than score-equivalent.
- **"Passing the standard checks settles the grader."** On the same benchmark **no model passed all three** on any task: QWK of at least **0.70**, no more than **0.10** below the raters' own agreement, and a standardized mean difference within **0.15**. On code, **eight models** cleared the first two and then graded lower than the raters, and on short answers **21 of 22** graded lower, so the direction of the departure matters as much as its size.
- **"Agreement detects a biased grader."** It did not in a within-item ablation. Adding only a true or swapped attainment label to the prompt moved marks by **0.28 to 0.75 points** on a ten-point scale on every model tested, while a true label raised QWK by just **0.029 to 0.046**. A rescaling fitted

without the label matched that gain. Invariance has to be reported beside agreement, because a grader can score closer to the teacher while reading the student rather than the work.

Common Misconceptions

- **“LLM grading bias is a reason to abandon it.”** In a **large-scale national writing assessment**, an LLM scorer showed a **systematic conservative (under-grading) bias** — problematic as a final mark and potentially **useful as a screening** signal. A bias with a known direction is a different instrument from an unpredictable one.
- **“Grade inflation after AI is speculation.”** In a **difference-in-differences study of 500,000+ grades across 319 courses (2018-2025)**, courses with more AI-exposed tasks (writing, coding) **saw the share of A grades rise**. The effect concentrated where tasks were exposed.
- **“Faculty have adopted AI broadly.” 62.4% (53)** declined to use generative AI at all, and adopters’ use was **confined largely to proofreading (43.8%) and clarity checks (34.4%)**. The adoption pattern is cautious and narrow, which changes what a validity argument needs to cover.

Connected Concepts

- Pedagogical Patterns — Why process evidence is proposed when output no longer identifies the author
- Interpreting and Applying AIEd Research
- Authentic Assessment
- Automated Assessment
- Formative Assessment
- Academic Integrity
- RCT
- Bias Mitigation
- Equity
- AI Ed Evaluation
- Educational Measurement
- Legal Issues and Risks
- Large Language Models (LLMs)
- Feedback
- Self-Report Measures
- Prior Knowledge
- Student Engagement
- Assessment

Connected Articles

- From Policing Provenance to Designing for Evidence: Testing Four Propositions on Generative AI Against Research and Institutional Policy — From policing provenance to designing for evidence: four propositions tested against research and policy (Ansari 2026)
- Testing the validity of embedding-based similarity and clustering for handwritten physics solutions — Embedding similarity correlated with human scores at 0.198 at best
- On AI glasses and wearable AI in assessment — Wearable AI dissolves separability and observability, so a supervised candidate can still not demonstrate unaided capability (Corbin, Sharpe & Dawson 2026)
- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — Program-level pass/fail susceptibility and the marking criteria that let fabricated values pass (Ivory et al. 2026)
- "Is this a trap?": Student teachers' perceptions and adoption of GenAI in assessments in three teacher education courses — Permission alone doesn't degrade validity: engagement unaffected by GenAI use; reflection resists generic substitution
- AI Agents, Joyful Assessment, and Third Space: Rethinking Assessment in the GenAI Era — AI agents, joyful assessment, and third space
- AI in University Assessment: Evaluating the Opportunities and Risks of Automated Marking — OpRaise report: AI marking of 761 university essays across three UK universities
- Generative AI in computing education: A systematic review and a framework for responsible integration — When AI generates the graded artifact: computing education's validity problem and redesign evidence
- AI-interaction literacy: reflections on how generative AI might be used to support self-regulated learning in higher education — Take-home exams: assess the qualitative phase, move recall in-class (Brunnström & Palmqvist 2026)
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — HITL AI-assisted scoring in a large-scale national writing assessment (Curi et al. 2026)
- VARIA: Benchmarking Frontier LLMs on Construct-Equivalent Assessment Variant Generation — Construct-equivalent assessment variant generation (Lee 2026)
- Artificial Intelligence and Grade Inflation — AI task displacement as a mechanism of grade inflation (Chirikov 2026)
- AI agents can now navigate and complete LMS tasks: A call for pedagogical innovation — AI agents completing LMS tasks; human-production assumption & agentic validity (Hadjisolomou & El-Haddad 2026)
- Semantic variability of LLM-generated replies across LLMs: Implications for designing conversation-based assessment

- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- A Multimodal Framework for Embodied Cognition in Oral Explanations — A Multimodal Framework for Embodied Cognition in Oral Explanations
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams: a large-scale field study
- Distinguishing performance gains from learning when using generative AI
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics
- The End of Assessment? Disruption and Transformation in the Age of AI
- Can AI Evaluate Assessment? A Study of Large Language Model Meta-Assessment Performance
- Exploring value judgements in grading: will teachers mark down student work assisted by GenAI, and should they? — Value judgments in grading GenAI-assisted work: honesty, trust, validity, and two-way transparency (Luo & Dawson 2026)
- Bridging technology and education: The use of ChatGPT in grading pharmacy student exams
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — The misconduct procedure as a validity problem
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — Assessment validity under imperfect information: a response-region model
- Which inference is at risk? Assessment validity reasoning and generative AI — Which inference is at risk? Separating five validity pressures and checking what a redesign weakens (Weidlich 2026)
- The shifting landscape of assessment in STEM education in the age of generative AI — STEM assessment as a validity, design and capability-definition problem, not a cheating one: process evidence, oral exams and the fidelity of AI-generated tasks (Koretsky et al. 2026)
- AI in Particle Physics Education: Research Problems and Foundational Skills — AI in Particle Physics Education: Research Problems and Foundational Skills
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- How much selection would be enough? Bounding the learning claim of El Salvador's artificial intelligence tutoring pilot — Bounding the learning claim of El Salvador's AI tutoring pilot (Restrepo Morales et al. 2026)
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What misconduct allegation files actually contain as evidence, and why evidence quality does not predict outcomes (Munoz et al. 2026)

- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Detector accuracy 0.69 and 0.61 on 192 texts; hybrid-writing failure and EFL misclassification risk (Hadra et al. 2026)
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive prohibitions: transcription is not generation, so the rule sanctions what it was not designed to catch (Wright 2026)
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity made visible through evaluative judgment rather than detection (Sharma 2026)
- Can large language models reproduce higher education grade bands? Cross-model study of calibration and grading bias in authentic student writing — Can large language models reproduce higher education grade bands? Cross-model study of calibration and grading bias in authentic student writing
- AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice — AI-Assisted Assessment of Experimental Physics Laboratory Reports: Potential, Limitations, and Support for Teaching Practice
- Inferring Gifted Potential from AI-Assisted Work: An Attributional Validity Framework for Gifted Education — Four targets of inference and three attribution errors when a product is read as evidence of learner capacity (Sak 2026)
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues
- Can students identify AI? – A cross-sectional quantitative study about AI recognition in tablet-based MCQ assessment among fifth-year undergraduate medical students at Saarland University, Germany — Student ratings of curricular alignment track item difficulty (rho = 0.762) rather than content (Vogt et al. 2026)
- Large language models as grading assistants in public health education: a method-comparison study of essay-style exam assessment — Five-day repeat grading of identical submissions gave Krippendorff’s alpha 0.625
- How AI-vulnerable is Australian higher education assessment? A computational audit of Group of Eight Arts and Humanities units, 2022–2026 — AI Vulnerability Index: most assessed marks rest on unverifiable authorship, so validity rests on sufficient evidence at key stages rather than maximum security
- The learner who does not learn: when optimizing a pedagogical metric degrades LLM tutoring — A pedagogical-adaptivity metric rose while blind expert ratings fell: measurement validity does not imply optimization validity (Domínguez Figaredo & Fernández De la Cruz 2026)
- Has the Target Moved Again? GenAI and the Validity of English Proficiency Scores — Has the Target Moved Again? GenAI and the Validity of English Proficiency Scores

- Problem-based and project-based learning as promising frameworks for generative AI-supported education: Emerging evidence from a systematic review and three-level meta-analysis — The outcome construct moves the estimate: g = 1.958 for the joint human-AI product
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- Learner context changes an LLM grader’s marks on identical work: a within-item ablation on six models — Learner context changes an LLM grader’s marks on identical work, and agreement with the teacher does not register it (Porcaro 2026, Paper VI)
- Making argumentative work visible in GenAI-mediated assessment: An exploratory LLM simulation and questionnaire study in university ideological and political education — Task format and AI-use instructions as what the artifact can evidence (Liu & Liu 2026)
- Beyond Response Scoring: An AI-aware Cognitive Supervision Framework for Automated Mathematical Short Answer Grading — Beyond Response Scoring: An AI-aware Cognitive Supervision Framework for Automated Mathematical Short Answer Grading

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

Psychometrically Aware AI

> **Psychometrically aware AI** — AI assessment systems aligned with measurement theory — is the standard advanced in Aligning LLM-Simulated and Human Examinees for Psychometric Calibration: A Cognitive Diagnostic Profiling Approach, Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction, Confidence Aware AI Assessment, and Item Response Theory: calibrated, uncertainty-aware AI assessment preserves reliability and validity rather than substituting raw model confidence for psychometric evidence.

Questions to Consider

- An AI grades a student's answer and reports a confident-sounding score. On what basis would you trust that number — and does your answer change when you learn the model wasn't calibrated against any measurement standard?
- The page warns against substituting raw model confidence for psychometric evidence. Think of a time you believed a confident AI output that turned out wrong. What made its confidence unearned, and what would 'uncertainty-aware' output have looked like instead?
- Research found that on the same assessment instrument, human and LLM response structures diverge — meaning a model can score well yet be measuring something different from what the exam intends. If you were a teacher using an AI grader, how would you ever detect that the test 'means' something different for the machine than for your students?
- Item-difficulty prediction uses LLMs to estimate how hard a question is. Before reading, consider: is 'how hard is this question?' a fact about the question, or about the people (or models) answering it — and what does that ambiguity imply for using AI to calibrate exams?
- Calibration, reliability, and validity are measurement concepts with precise meanings. Which of these have you actually thought through in your own assessment practice, and where might you be relying on an AI's output that has never been checked against them?
- For an Administrators or developer: if an AI assessment tool you're considering reports only raw accuracy, what specific questions would you now ask its vendor before deploying it with real students?

Introduction

As AI systems increasingly score responses, predict difficulty, and provide Feedback, a key risk is that they report confident-sounding outputs that have not been validated against measurement principles. Psychometrically aware AI addresses this by grounding AI Assessment in established psychometrics — calibrating outputs, quantifying uncertainty, and preserving Assessment Validity and Educational Measurement standards rather than relying on raw accuracy or self-reported confidence.

How psychometrically aware AI appears in the research

- **Calibration and confidence:** Confidence-aware assessment and LLM psychometric calibration ensure that AI reports meaningful, uncertainty-aware scores rather than overconfident point estimates.
- **Model confidence is not enough.** On SciEntsBank, verbalized, latent and consistency-based confidence each failed to separate correct from incorrect short answers; the best calibration came from adding dataset-derived aleatoric uncertainty — within-cluster entropy of embedded responses — through a Random Forest plus Platt scaling, enabling selective auto-grading and human review (Cong et al. (2026)).
- **Confidence flags triage review, not acceptance.** In high-stakes handwritten physics grading, AI confidence labels tracked far lower score error on high-confidence parts, yet some high-confidence, unflagged parts still disagreed with official marks, so the labels are useful for prioritizing examiner review rather than authorising automatic acceptance (Pathak et al. (2026)).
- **Difficulty prediction:** Item-difficulty prediction shows how LLM-based estimates must be validated against psychometric models (see Item Response Theory). Razavi and Powers (2026) provide a large-scale demonstration: across 5,170 K-5 math and reading items calibrated under the Rasch IRT model, GPT-4o's zero-shot difficulty ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but were uneven across grades, while a feature-based approach (LLM-extracted features into tree-based models) reached correlations up to r = 0.87. The study's interpretable feature importance (grade level and word count top predictors) and its practical seven-step workflow illustrate how psychometrically aware AI can be operationalized — while its early-grade range-restriction finding and generalizability caveats underscore the need to validate LLM estimates against fitted psychometric parameters.
- **Recovering a curve is not the same as recovering every parameter.** A Multimodal AI model fine-tuned as a simulated respondent estimated held-out item difficulty at r = 0.85 and recovered the guessing parameter at 0.48, but discrimination was weak at 0.31 — so which parameter a method recovers is the finding (Ormerod & Kim, 2026).
- **Measurement validity:** The concept connects to Assessment Validity and Educational Measurement, the frameworks that define what valid, reliable AI assessment looks like.
- **Latent-structure validity:** Strugatski et al. (2026) show that a psychometrically aware stance must also verify that an assessment measures the *same latent construct* in LLMs as in humans. Because LLM and human response factor structures diverge on the same instruments, even well-scoring models may not be measuring the construct the exam purports to measure — a caveat for any AI assessment that borrows human validity evidence.
- **A label can measure more, or less, than it names.** Embedding 12 AI literacy instruments' 55 constructs and 272 items surfaced jangle pairs (same label, different measurement) and jingle pairs (different labels, near-identical wording), recovering reliability at r = 0.49, a pre-collection check that construct distinctions survive into item wording (He et al. (2026)).
- **A reliance scale that refuses outcome anchoring.** Four factors — reflective, cautious, thoughtless and collaborative use — emerged from 800 responses and held across a differently

shaped task (CFI = .91), measuring behavior per task moment instead of labeling it good or bad (Hou et al. (2025)).

- **Latent-ability pipelines and standard setting:** Curi et al. (2026) provide a concrete template for psychometrically aware scoring in a national exam: rubric item scores are never summed directly but fed into an IRT model whose latent-ability estimates are cut with the Bookmark standard-setting method into Proficient / Close to Proficiency / Insufficient, with passing requiring at least two Proficient sections and the remaining one at least Close to Proficiency. The authors reproduced that pipeline in automated form (a 67% probability of answering at least 7 rubric items correctly for the lower cut and at least 10 for the upper), letting AI and human item scores be compared against identical decision criteria rather than on raw agreement alone.
- **A model can look calibrated while mostly predicting one label.** Asking GPT-4o and Gemini 2.0 Flash to infer learning-style dimensions from 153 undergraduates' dialogues produced moderate accuracy that per-class recall showed was dominant-label prediction, with Intuitive and Global learners under-identified and few-shot prompting sometimes amplifying the bias rather than removing it (Zamanifard, Goudarzi and Robb (2026)).

Connections

Psychometrically aware AI sits at the intersection of Educational Measurement, Assessment Validity, Item Response Theory, and Confidence Aware AI Assessment. It is central to AI Ed Evaluation (whether AI assessment is trustworthy) and connects to Large Language Models (LLMs)-based Automated Assessment and Automated Grading. Its emphasis on validity also speaks to the measurement limitations of AIED research.

Common Misconceptions

- **"A model that scores well is measuring the same thing."** On **the same assessment instrument**, human and LLM response structures **diverge** — a model can score well while measuring something different from what the instrument intends. Matching scores is the observation; construct equivalence is a separate claim that requires structure-level evidence.
- **"Calibration can be read off a single accuracy figure." A single accuracy figure can hide a model that only looks calibrated**: asking GPT-4o and Gemini 2.0 Flash to infer learning-style dimensions from **153 undergraduates'** dialogues produced **moderate accuracy that performed differently under balanced metrics**. Aggregate accuracy hid a differential that balanced metrics exposed.
- **"Automated scoring pipelines cannot reproduce psychometric procedure."** The authors reproduced an established pipeline in automated form (**a 67% probability of answering at least 7 rubric items correctly for the lower cut and at least 10 for the upper**), letting AI and human item scores be compared on the same footing. The procedure was reproducible; the construct question remains.

Connected Concepts

- Educational Measurement
- Assessment Validity
- Item Response Theory
- Automated Assessment
- AI Ed Evaluation
- Large Language Models (LLMs)
- Limitations in AIEd Research
- AI in Education

Connected Articles

- Measuring undergraduate students' reliance on generative AI during problem-solving: Scale development and validation — A validated scale for students' reliance on generative AI during problem solving (Hou et al. 2025)
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment
- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- Aligning LLM-Simulated and Human Examinees for Psychometric Calibration: A Cognitive Diagnostic Profiling Approach — Aligning LLM assessment with psychometric calibration
- Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction — LLM prediction of item difficulty
- Confidence Estimation in Automatic Short Answer Grading with LLMs — Confidence-aware automatic short-answer grading
- Multimodal item parameter estimation using simulated response probabilities — Multimodal item-parameter estimation
- Knowledge, skills, attitudes, production: Competency-based education after generative AI — Competency-based education with GenAI
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Clarifying the conceptual landscape in AI literacy measurement: A large language model based approach — Comparing AI literacy instruments: jangle and jingle pairs across 55 constructs
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses

- Bias and Reliability in Learning-Style Inference from Student–AI Dialogues: An Evaluation of GPT-4o and Gemini 2.0 Flash — Moderate accuracy was majority-class prediction once per-class recall was checked (Zamanifard, Goudarzi & Robb 2026)

Educational Measurement

> **Educational measurement** — the psychometric theory and methods for quantifying and validating learning and its constructs — runs through the knowledge base's Item Response Theory, Knowledge Tracing, and Assessment Validity pages. The Large Language Models (LLMs) era forces measurement to reconcile classical psychometrics with new AI-generated response streams: automated scoring, AI-predicted difficulty, and Multimodal AI traces must be validated against established measurement principles to preserve reliability and validity.

Questions to Consider

- An LLM predicts that an exam item is easy, but empirical test data says students find it hard. Which do you Trust, and what would convince you to trust the machine's estimate?
- Educational measurement is about turning observations of learning into defensible quantitative claims. When an AI grades an essay or scores a response, is a 'score' automatically a measurement — or does something have to be validated first? What?
- Some research suggests assessment instruments may not measure the same thing for humans as they do for LLMs — the latent structure diverges. If the constructs genuinely differ across humans and AI, what does that imply about AI-generated grades or difficulty ratings?
- AI can score, generate items, and predict difficulty at unprecedented scale. Is 'more measurement' the same as 'better measurement'? What makes a score reliable and valid, and can those standards be preserved when the measurement is done by a generative model?
- Benchmarks and AI-generated scores are everywhere now. What would you need to see before you'd treat an AI-based assessment as evidence about a learner's actual understanding rather than just a number?

Introduction

Educational measurement is the discipline of turning observations about learning — responses, behaviors, scores — into defensible quantitative claims. It encompasses construct definition, item/test design, scaling, reliability, and validity. In AI in education, measurement questions are everywhere: does a benchmark score measure what we think? Is an AI-generated grade reliable and valid? Do AI-predicted item difficulties agree with empirically estimated ones?

How educational measurement appears in the research

- **AI's decade-long reshaping of the field:** Xiong and Li (2026) map AI's impact across three eras (Formative 2015–2018, Expansion 2019–2022, Generative 2023–present) via an Efficiency–Enhancement–Transformation framework, spanning AI on scoring and item generation, psychometric modeling, assessment innovation and process data, and fairness/ethics/equity. They argue for a new paradigm integrating measurement theory with AI methods and for

reconceptualizing constructs in the context of human–AI interaction — the same boundary that latent-structure comparison probes empirically.

- **AI-predicted difficulty and calibration:** LLM difficulty calibration and item-difficulty prediction use LLMs to estimate item difficulty, which must be validated against psychometric estimates (see Item Response Theory). Razavi and Powers (2026) add a large-scale K-5 test of this premise: across 5,170 math and reading items calibrated under the Rasch IRT model, GPT-4o's zero-shot difficulty ratings correlated moderately-to-strongly with true difficulties (r = 0.83 math, r = 0.81 reading) but were uneven across grades and no better than a grade-mean dummy regressor for grades K and 1. A feature-based approach — LLM-extracted cognitive and linguistic features fed into tree-based models — reached correlations up to r = 0.87, with grade level and word count the top predictors. The study illustrates both the promise and the limits of AI-predicted difficulty as a measurement input, and offers a practical seven-step workflow for testing professionals.
- **Difficulty without discrimination.** Worden et al. (2026) score four frontier models against IRT ground truth on 2,548 mathematics items: they reach 68.6 percent on relative difficulty but fall below chance at judging discrimination, appearing to conflate the two, and predict correctness 85.4 percent of the time on correct answers against only 12.6 percent on incorrect ones.
- **When generated difficulty labels do not measure difficulty.** A construct-validity audit of 311 deployed LLM-generated questions found the generated difficulty label correlated with its own co-generated Bloom level at ρ=0.90 but with empirical difficulty (the Classical Test Theory 1−p index) at only ρ=0.06, while option length ran backwards (ρ=−0.18) - a labels-as-surface-form result that bounds the optimistic readings of AI-predicted difficulty above (An & Wang (2026)).
- **A synthetic benchmark's measurement quality rests on its generation pipeline.** A set built with a three-judge LLM panel and no human oversight during item generation showed weak item-level quality, and because the items are fully synthetic the authors call for human-curated item comparisons before the scores are read as measurement (Schroeder et al. (2026)).
- **A taxonomic label does not predict item behavior.** Across 265 mathematics items, intended Bloom level explained under 5% of the variance in difficulty ($\varepsilon^2 = .043$) and none of discrimination (Kruskal–Wallis H = 0.54, p = .77), while an LLM classification agreed with expert coders only fairly (Cohen's $\kappa = .22$) and pulled items toward the apply/analyze band (Altaweel & Moussa (2026)).
- **Judge generated items on the solution path, not the wording.** Encoding each item's verified reasoning tree lifted performance over the second-best method by 7.5% in concept assessment, 6.3% in difficulty estimation and 19.5% in competency assessment, where a zero-shot baseline mislabelled a template-following item "Reasoning" and a geometric item "Knowing" (Tong et al. (2026)).
- **Psychometric awareness in AI Assessment:** psychometrically aware AI is the standard that AI-based assessment be aligned with measurement theory — calibrated, uncertainty-aware, and validity-preserving (see Confidence Aware AI Assessment).
- **Mastery labels are constructed, not observed.** Where diagnosis needs ground truth, Jia and Dong (2026) built it through a validity-control procedure — curriculum concept graphs,

instructor-reviewed knowledge-point mappings and convergent assessment evidence — rather than converting behavioral traces directly, and their diagnoses matched educational psychologists at Cohen's kappa 0.78 against 0.65 for IRT.

- **Automated scoring and validity:** AI scoring and language bias and multimodal item-parameter estimation examine how automated scoring and multimodal data affect measurement quality.
- **Validity frameworks:** Assessment Validity and Educational NLP supply the standards and tools for validating LLM-based measurement.
- **Latent-structure comparison:** Strugatski et al. (2026) extend educational measurement to the LLM setting by testing whether assessment instruments show the *same factor structure* for humans and LLMs. Using EFA, factor congruence, and resampling, they show LLM–human latent structures systematically diverge across chemistry and quantitative-reasoning instruments, implying the constructs measured differ across populations — a necessary check before human validity evidence is assumed to transfer to AI.
- **AI as a rater with measurable error:** Cvengros & Kortemeyer treat AI-assigned points as fallible observations with multiple error sources (items, runs, tasks) under generalizability theory and Kane's argument-based validity. Reliability analysis of a 296-student handwritten general-chemistry exam showed high stability of *total* scores across five AI runs (ICC(A,1) = 0.967, Kendall's W = 0.959, 95% repeatability coefficient 5.33 of 60 points) with lower item-level stability (ICC(A,1) = 0.836) — unsystematic errors partially cancel when summed (a Spearman–Brown aggregation effect that lifts total-score agreement to $R^2 = 0.91$), while a small positive intercept with slope < 1 revealed a "timid grader" score-compression bias. This frames run-averaging and aggregation as measurement design decisions, and motivates confidence filters calibrated to IRT risk as a validity safeguard before automated measures are trusted.
- **Model version is a measurement condition.** Hao (2026) found within-model reply similarity (0.715–0.795) consistently exceeded between-model similarity (0.443–0.604) across four LLMs, so a scoring argument established for one deployment does not automatically transfer to its successor.
- **A null result is not evidence of equivalence unless it is bounded.** StudentBench tested whether pooled AI tutoring matched expert human tutoring with two one-sided tests against ±0.25 pooled standard deviations rather than a test for a difference, reporting an adjusted difference of -0.58 percentage points (90% CI [-2.18, 1.03]) - the choice that turns an underpowered null into an equivalence claim (Northcutt et al. (2026)).
- **Calibration that scales with new data rather than the whole history:** Jewsbury et al. (2026) confront the operational consequence of AI item generation — banks larger, sparser and more frequently updated than conventional ones, where refitting all accumulated response data at each update is costly and can exceed available memory. Their *consensus calibration* combines independently calibrated quarterly periods by mapping each period's posterior draws onto a common metric with a per-draw robust Haebara link (so linking uncertainty propagates rather than being treated as a fixed transformation), then aggregating as a product of Gaussian posteriors from which each period's *estimated, hierarchical* prior is subtracted and a consensus prior reinstated. On operational Duolingo English Test data across four periods the aggregate matched a pooled

single-run benchmark on posterior means (r = .998 for difficulty, .991 for log-discrimination) and standard deviations (r = .970 and .920), with residual under-dispersion of 0.91–0.98 in the consensus/pooled SD ratio across exposure tertiles — concentrated in the sparsest item tertile, where prior over-counting bites hardest. The measurement lesson is twofold: an estimated prior cannot be handled by the standard subset-prior devices of parallel Bayesian computation, and posterior *dispersion* — the uncertainty adaptive selection and scoring consume — is as much a target of the correction as the posterior mean.

- **Identifying a system's dispersion from two published numbers:** Restrepo Morales et al. (2026) show that an achievement distribution's standard deviation can be recovered from published summary statistics alone — the mean and the share of students at or above a fixed proficiency cut score — because under a distributional assumption $\sigma = (c - \mu) / z(1 - p)$. Applied to PISA 2025 El Salvador (mathematics mean 346, 12.28% at or above the level-2 cut of 420.07), the implied σ is 63.8 (reading 76.8, science 63.8), well below the international benchmark of 100, as expected for a distribution pressed against the floor of the scale; the three estimates were obtained from independent pairs of figures and lie within about 13 points of one another, a mild internal consistency check. The share at Level 2 is reported for every PISA system and underpins the SDG 4.1.1 indicator, so the identification needs no microdata, and the same paper demonstrates the denominator problem in effect sizes by reporting one mathematics gap three ways — 129 points, 1.29 international standard deviations, or 2.02 standard deviations of the Salvadoran distribution itself — on the argument that standardized effect sizes divided by their own sample's dispersion are not legitimately comparable across studies.

Measurement instruments in the knowledge base

A central function of educational measurement is the development, validation, and use of **instruments** — the concrete scales, tests, and coding schemes that operationalize constructs. The knowledge base's articles document a wide range of instruments for AI-in-education constructs, which can be categorized by what they measure and by their measurement approach.

AI / GenAI literacy instruments

AI literacy is the construct with the richest instrument coverage in the knowledge base. Two broad families exist: **performance-based tests** (objective, less susceptible to self-report bias) and **self-report scales** (subjective, capturing perceived competence). The trade-offs of that second family are the subject of Self-Report Measures: self-report reaches attitudes and perceptions cheaply, but it cannot carry a claim about competence or behavior, and the knowledge base documents a 40% overestimation gap when parallel self-report and performance measures are compared.

- **Performance-based (objective) measures.** The flagship is GLAT (Generative AI Literacy Assessment Test), a 20-item multiple-choice instrument built on a 25-concept blueprint across four dimensions (Know & Understand, Use & Apply, Evaluate & Create, Ethics) and validated with CTT + 2PL IRT on 355 students (RMSEA = 0.03, CFI = 0.97, α = 0.80, ω = 0.81). Critically, GLAT scores predicted AI-assisted task performance where self-report did not — evidence that **performance-based measurement outperforms self-report** for AI literacy. Related work in

How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures quantifies the gap between self-reported and performance-based AI literacy (teachers overestimate by ~40%), and Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing traces actual student–AI interaction patterns rather than relying on reported use.

- **Measuring what teachers do, not just what they know.** A 486-teacher validation produced a six-dimension instrument for teachers' educational uses of GenAI — management, materials creation, assessment, empowerment, diversity, and motivation — confirming use is multidimensional, though self-reports cannot carry a claim about classroom practice (Pérez-Montesdeoca et al. (2026)).
- **Self-report scales.** SAIL operationalizes AI literacy across three domains (AI Concepts; Application and Technical Skills; AI Digital Citizenship) and four scaffolded levels; the AI Literacy Heptagon structures seven dimensions (technical, application, critical thinking, ethics, social impact, integration, legal/regulatory) with four Bloom-aligned proficiency levels. The GenAI Skill Bypass: Mapping Divergent Pathways of University Students and Staff AI Literacy maps divergent AI-literacy pathways for students vs. staff, and Towards AI literacy: A proposal of a framework based on the Episodes of Situated Learning grounds literacy assessment in situated learning episodes. Instrument development for younger learners is also advancing: the AI Literacy Self-Assessment Questionnaire (AIL-SAQ) of Thianwan and Srikoon (2025) is a 15-item self-report scale for students in Grades 4 to 6, organized around Learning About AI, Learning About How AI Works, and Learning for Life with AI. The scale was validated with exploratory factor analysis on 335 students and confirmatory factor analysis on 579 more, with an overall Cronbach's alpha of .934.
- **Domain-specific AI literacy.** Teacher education for artificial intelligence literacy through a self-determination theory perspective develops teacher AI-literacy measures within a Self-Determination Theory framework (382 teachers, factor-validated); Conceptualizing pre-service teachers' readiness for AI integration into teaching practices: An intelligent-TPACK approach measures pre-service teacher AI readiness via intelligent-Technological Pedagogical Content Knowledge (TPACK); AI literacy alone is not enough: Student AI readiness and career adaptability in business and management education assesses student AI readiness and career adaptability in business education; and Can large language models foster critical thinking, teamwork, and problem-solving skills in higher education? A literature review reviews instruments for LLM-supported critical-thinking and teamwork outcomes. Extending into educator measurement, the Teachers' AI Literacy Scale (TAILS) operationalizes the ED-AI framework's six dimensions to measure AI literacy specifically within language teacher education (validated with factor analysis), filling a gap in assessments that target students or general users.

Attitudes, acceptance, and motivation instruments

- **Technology acceptance.** Instruments grounded in TAM/UTAUT measure perceived usefulness, ease of use, and behavioral intention to use AI. See Technology Adoption Models and its application in Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups (AI-assisted English learning

tools, psychometric validation across disciplinary/proficiency groups) and GenAI adoption pathways.

- **Self-efficacy and motivation.** Self-Efficacy instruments and motivation scales (e.g., SDT-based measures of autonomy/competence/relatedness in Teacher education for artificial intelligence literacy through a self-determination theory perspective) capture the motivational antecedents and consequences of AI use. These connect to Student Engagement and Prior Knowledge measurement.
- **Project-based learning perceptions.** Zhu and Kong (2026) develop and validate a context-grounded AI project-based learning scale (AI-PBLS) measuring students' perceptions of PBL when using AI for problem solving in AI literacy courses (EFA and CFA on 1,027 secondary and university students, 446 complete), and their SEM application demonstrates how empowerment and ethical awareness mediate PBL-to-satisfaction relationships — a robust instrument for assessing perceived PBL experiences in AI applications.

Assessment-quality and validity instruments

- **Automated scoring and rubric instruments.** HARMOGEN-R generates assessment rubrics; AI-assisted, instructor-supervised grading and feedback in higher education: Design and evaluation of an end-to-end pipeline evaluates AI-grading quality against Elaborated-Feedback criteria; 'A bit of chaos and madness': The AI Assessment Scale and the work of assessment reform addresses how AI disrupts traditional assessment scales.
- **Validity-strengthening designs.** assessment twins pair a GenAI-vulnerable task with a less-vulnerable equivalent assessing the same outcomes, mapping threats across Messick's six strands of validity evidence.
- **Partitioning the outcome space by assistance.** A measurement program defines **model authorship** — how far the learner, not the system, originates an artifact's domain-level content — as a four-facet, four-level construct, and reports that of 24 audited studies nearly all measured performance with AI available and none measured after withdrawal (Gousopoulos (2026)).
- **Discourse and engagement coding.** Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents extends the ICAP framework into a 7-point cognitive-engagement coding scheme, comparing human annotation (κ = 0.906–0.998) with LLM-based labeling (κ = 0.541–0.609) — a measurement-instrument study showing automated coding still trails trained humans. Automated coding is also advancing via context-aware prompting, which models contextual dependencies and fuses cognitive and social abilities to code collaborative problem-solving skills from process data at superior performance over strong baselines — enabling large-scale, real-time assessment while addressing the labor-intensity of manual coding.
- **Skills extraction.** Principal Trait Analysis: Towards Deriving "Skills" in Human-AI Collaboration derives "skills" in human–AI collaboration via principal-trait analysis — a data-driven measurement of collaboration competency.

Measurement approach matters

The knowledge base's evidence repeatedly shows that **how** a construct is measured changes the conclusions. Self-reported AI literacy diverges sharply from performance-based measures (How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures); LLM annotation of engagement diverges from trained human coding (Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents); and latent structures differ between humans and LLMs (Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis). Rigorous instrument validation — reliability, structural validity, external/predictive validity — is therefore not a formality but the foundation of trustworthy AI-in-education evidence, connecting to Assessment Validity and Psychometrically Aware AI. A recent material-level study shows how much validation work sits behind a simple acceptance claim: Wang, Chuang and Wu (2026) used a split-half design (EFA on a development sample, CFA on a held-out half) for two age-tiered AI literacy guidebooks, reporting KMO = .820, 67.3% variance explained, acceptable student fit (CFI = .943, RMSEA = .059, SRMR = .059), composite reliability of .84 to .90, and measurement invariance across editions — then documenting where the instrument strains, with HTMT values up to .950 and a constrained playfulness-intention correlation that had to be tested for unity. Their supplementary checks for differential item functioning are a model of the honesty this page argues for: invariance held, but low-variation response patterns among younger students meant one group difference weakened once those respondents were excluded, and the paper reports that alongside the headline result rather than instead of it.

Oliveira et al. (2025) show the validation sequence for a novel process measure: scoring students' GenAI interaction logs against a 35-subcategory taxonomy reached only moderate inter-rater agreement (Cohen's κ = 0.44) yet correlated r = 0.54 with essay scores, giving the new measure convergent support. - **Agreement coefficients are corpus properties, and scores are joint products.** An automated-scoring validation of 60 marketing posts reported absolute agreement ICC(2,1) of .435 for an LLM, .266 for a rules-plus-LLM hybrid and .091 for deterministic rules, with uncertainty estimated from 2,000 writer-cluster bootstrap samples and MAE of 6.28-17.22 points; adding researcher-authored anchors moved inter-rater agreement from .338 to .902, showing how strongly these estimates depend on the reference set (Agreement and error in automated scoring of student marketing posts). An expert re-grading audit of physics benchmarks makes the complementary point at the instrument level: 95.20% of audited rejections were benchmark or grader errors rather than model failures, so a measured score must be reported as a property of the item bank, the rubric and the grader together (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks).

Reliability is partly recoverable from the model itself. Organisciak and Acar (2026) evaluate three cheap upgrades to LLM-based scoring on more than 20,000 responses to the Alternative Uses Test: reading the model's own token-level confidence, taking a probability-weighted mean over its top-n predicted scores instead of a single best guess, and ensembling across models. Each improved agreement with human scores (correlation rising from r = 0.781 to 0.823 and RMSE falling from 0.599 to 0.498 in the best configuration), and their diagnostics locate a specific failure of single-pass scoring: the model's expressed confidence was negatively related to its accuracy (β = −0.602). This is a measurement-approach result rather than a model result — the same model, scored differently, is a more reliable instrument — and it sits alongside the corpus-level agreement evidence above.

A 2026 appraisal of 33 teacher AI literacy instruments shows where instrument development is mature and where it is not. Zainal, Mohd Matore and Maat (2026) graded the instruments against a decision matrix adapted from COSMIN and Terwee et al. (2007) and found internal consistency the strongest domain (28 of 33 at Grade A, 84.8%) and fairness the weakest, with only five instruments (15.2%) reporting measurement invariance or differential item functioning evidence. Structural validity was strong, with 24 instruments (72.7%) at Grade A through CFA, PLS-SEM or IRT modeling, yet content validity rested mostly on qualitative review, with 21 instruments (63.6%) at Grade B for lacking quantitative expert agreement statistics.

Automated item selection can shorten an instrument without reshaping it: ant colony optimization over a merged two-wave sample (N = 305, 342) yielded a 12-item short form correlating r = 0.910–0.944 with the full scale on each dimension, though two items per dimension cover a narrower content range (Wang, Zhang and Zhang (2026)).

- **Validating a scale for an AI-specific construct.** Chang (2026) walks the sequence for Cognitive Offloading: 26 candidate items reduced to 20 across three functions (5 memory, 10 assistive, 5 thinking), with Study 1 on N = 665 reporting KMO = 0.965 and $\chi^2(325) = 8904.89$ before extraction. Study 2 on N = 1,123 fitted a second-order model at CFI = 0.951, TLI = 0.944, RMSEA = 0.047 and SRMR = 0.036, with CR 0.840–0.906, AVE 0.501–0.570, $\alpha = 0.944$ and one-month retest 0.937 (n = 99). Full scalar invariance across gender held, with $\Delta CFI \leq 0.001$. The limits belong to the same account: no CVI, no HTMT and no latent-factor correlations were reported, so discriminant and content validity are asserted rather than demonstrated. The first-order three-factor model also posted SRMR = 0.158 against 0.051 for the one-factor model, and several items index attitudes toward reliance rather than behavior.

Issues and limitations: what measurement can miss or get wrong

Educational measurement is powerful but fallible. Understanding its failure modes is essential to reading AI-in-education evidence critically — and to recognizing where an apparent learning gain or construct claim may be an artifact of measurement rather than a real effect.

- **Reliability limits.** Measurement is never perfectly reliable; error variance is always present. When instruments have low internal consistency or test–retest stability, observed differences may be noise. In AI contexts, new failure modes compound this: LLM-generated responses can be scored with high machine agreement yet diverge from human scoring (Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents), and automated scoring can be *internally* consistent while systematically wrong — precision without validity. The measurement limitations of AIEd research document unreliable instruments as a cross-cutting weakness.
- **Coding uncertainty as error conflates two failures.** In a 30-statement mental-health knowledge test, accuracy scoring counted *do not know* as inaccurate, yet 67.3% of students chose it on one fact while 60.6% of model responses were positively wrong — a forced correct/incorrect format cannot separate uncertainty from an incorrect belief (Richter et al., 2026).
- **Rater agreement sets the practical ceiling.** A large-scale validation on Uruguay's *Acredita EB* found that human rater agreement itself sets the practical ceiling for AI scoring: among ten experts

independently scoring 50 texts, no rubric item reached unanimous agreement with consensus, the most divergent rater typically fell below 80% agreement while the best exceeded 90%, and Cohen's Kappa was only slight or fair for several skewed items that almost all responses satisfy. The authors therefore judge automated scores against a reference standard that is itself imperfect — ten raters, a single operational score for most responses, and several items in the conventional 70% acceptability zone — a caution for any measurement claim built on single-rater operational labels.

- **The non-self-report measure is not the correct one.** A two-phase review of 51 same-construct pairs found 41.2% reached discordant or mixed conclusions, and argues that tests, ratings and traces are heterogeneous rather than a criterion standard, each needing its own validity argument (Fan et al. (2026)).
- **Validity — measuring the wrong thing.** Validity asks whether an instrument measures the construct it claims to. Common failures include **construct under-representation** (an AI-literacy test that samples only technical knowledge, missing ethics) and **construct-irrelevant variance** (an item that rewards reading fluency rather than the target skill). AI scoring and language bias shows how surface features — language, phrasing, style — can drive automated scores in ways unrelated to the intended construct. Assessment Validity is the guardrail against these threats.
- **A scale can return the intended number of factors without measuring the intended constructs.** Kang, Lee and Kang (2026) retained six factors from a 42-item AI empathy scale, but the items did not recover the six intended subfactors — Prosocial Intention formed no factor — so the structure is presented as provisional.
- **The self-report gap.** Self-report measures capture *perceived* competence, not actual competence. The knowledge base repeatedly shows self-reported AI literacy diverging sharply from performance-based measures (How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures, ~40% overestimation by teachers) and that self-report fails to predict real AI-assisted performance where performance tests succeed (GLAT). Measures that rely on self-report can systematically overstate constructs and conceal true skill gaps.
- **The pooled estimate is fragile.** A 2026 structured review pooling only same-sample subjective–objective AI-literacy correlations (N = 2,765) gives r = .055 (Hartung-Knapp 95% CI [−.047, .156]); at k = 3, with the heterogeneity estimators disagreeing and one study carrying 77.2% of the weight, it cannot set a proficiency cutoff (Verí (2026)).
- **Constructs that don't transfer across populations.** Strugatski et al. show assessment instruments can have a *different factor structure* for humans and LLMs — meaning the same items may not measure the same latent construct across populations. Even within humans, instruments validated on one group (e.g., Western, resourced Higher Education) may not generalize to others (Global South), a concern for the generalizability of AI-in-education measures.

- **What measurement can miss.** Some of the constructs most central to AI-in-education learning are the hardest to measure well — and therefore the most easily missed or distorted by instruments:
    - **Process and strategy.** Standard outcome measures capture the *product* of learning, not the *process*. They can miss how students actually engage with AI — over-reliance, unreflective acceptance, or critical verification. Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing uses interaction traces precisely because self-report and outcome tests miss these dynamics. A neural process measure extends this: Su et al. (2026) reconstructed video frames from EEG and found semantic similarity higher for correctly answered items ($M = 71.43$, $SD = 4.61$) than incorrect ones ($M = 62.30$, $SD = 5.91$, $p < .001$).
    - **Longitudinal and durable learning.** A single post-test may show inflated performance from AI assistance while missing the erosion of durable, unassisted knowledge (the performance–learning gap). Measurement at one time point can be actively misleading about learning.
    - **Equity and access.** Instruments that assume uniform device/connectivity access, or that are normed on privileged samples, can miss — or systematically under-measure — the capabilities of under-resourced Learners, misattributing access gaps to ability gaps.
    - **Affective and motivational states.** Engagement, motivation, and self-efficacy are often measured by self-report, inheriting the self-report gap above; they may not capture the situated, momentary dynamics that drive learning.
- **Automated measurement can be confidently wrong.** The combination of high machine confidence and opaque scoring is a distinctive AI-era risk: an LLM grader or annotator can produce highly self-consistent scores that are systematically biased, and the appearance of rigor (large N, high inter-LLM agreement) can mask invalidity. The AI Ed Evaluation and Psychometrically Aware AI frameworks are the antidote — requiring calibration, uncertainty awareness, and validity evidence before automated measures are trusted.

In short, educational measurement can **miss** what it does not sample (process, durability, access, affect) and can **get wrong** what it samples poorly (self-perception, surface features, cross-population constructs). Reading AI-in-education findings therefore requires asking not just *what* was measured but *how* — and what the instrument may have failed to capture.

- **Auditable coding separates definitional error from model error.** EduBehaviors decomposes a construct into separately annotated observable behaviors plus an explicit aggregation rule, so a reviewer can see which evidence produced a label and re-derive labels after a rule change without new model calls; it reached macro-F1 0.673 on Teacher TalkMoves, competitive with direct LLM prompting (Bernado et al., 2026).

Connections

Educational measurement is the foundation for Item Response Theory, Assessment Validity, Knowledge Tracing, and Learner Modeling and Adaptive Instruction. It connects to Learning Analytics (measurement of learning data), Educational NLP (measuring language), and Psychometrically Aware AI (AI aligned with

measurement theory). Its validity and reliability concerns underpin AI Ed Evaluation and the measurement limitations of the field. For the constructs it measures, it intersects with AI Literacy, Technology Adoption Models, Self-Efficacy, Motivation, and Student Engagement. - **Causal modeling of support interventions (2026):** a structural causal modeling protocol moves educational assessment beyond associative item-response-theory belief updating toward interventional and counterfactual reasoning (e.g., the effect of hints), with structural equations elicited from experts using purely logical information — illustrated on compulsory-school algorithmic-skills tasks (Causal modelling of support interventions for student competency assessment).

Common Misconceptions

- **"Models can estimate item difficulty."** Four frontier models were scored against **IRT ground truth on 2,548 mathematics items**: they reach **68.6% on relative difficulty** but fall **below chance** at absolute calibration. Ranking and calibration are separate abilities, and the second is what an assessment design needs.
- **"A taxonomic label predicts how hard an item is."** Across **265 mathematics items**, intended Bloom level explained **under 5% of the variance in difficulty**. Labeling an item by Bloom level tells you almost nothing about its empirical difficulty.
- **"Item quality is judged from its wording." Judge generated items on the solution path, not the wording**: encoding each item's **verified reasoning tree** lifted performance over the second-best method by a margin. The reasoning structure carried the signal, not the surface text.

Connected Concepts

- Interpreting and Applying AIEd Research
- Item Response Theory
- Assessment Validity
- Psychometrically Aware AI
- Knowledge Tracing
- Learner Modeling and Adaptive Instruction
- Educational NLP
- Learning Analytics
- AI Ed Evaluation
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Automated Assessment
- Limitations in AIEd Research
- AI Literacy
- Technology Adoption Models
- Self-Efficacy
- Benchmark
- Self-Report Measures
- Motivation

- Student Engagement

Connected Articles

- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment
- Semantic variability of LLM-generated replies across LLMs: Implications for designing conversation-based assessment
- Causal modelling of support interventions for student competency assessment — Causal Modeling of Support Interventions for Student Competency Assessment
- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- GLAT: The generative AI literacy assessment test — GLAT: IRT-validated GenAI literacy test (Jin et al. 2025)
- Measuring Cognitive Engagement in Collaborative Discourse with an Extended ICAP Framework: Comparing Human Annotation, In-Context Learning, and Reflective LLM Agents — Measuring cognitive engagement with an extended ICAP framework
- Assessment twins: An approach for strengthening assessment validity in the age of generative AI — Assessment twins for strengthening assessment validity under GenAI
- The AI literacy heptagon: A structured approach to AI literacy in higher education — The AI Literacy Heptagon
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — Self-reported vs performance AI literacy misalignment
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher AI literacy through self-determination theory
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — AI acceptance measures for English learning tools
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations — From evaluated models to evaluation aids
- Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction — Cognitive evaluation of LLM item-difficulty prediction
- Multimodal item parameter estimation using simulated response probabilities — Multimodal item-parameter estimation
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics — AI scoring and language bias in physics

- The AI writes the code, the student writes the model: A theory and measurement programme for learning by construction with generative AI — Model authorship: theory & measurement for learning-by-construction with GenAI
- Assessing students' DRIVE: A framework to evaluate learning through interactions with generative AI — DRIVE: assessing learning through GenAI interaction (DRI + Visible Expertise)
- A decade of reflection and thematic review on artificial intelligence's impact on educational measurement — Decade thematic review of AI in educational measurement
- Design and validation of a questionnaire on teachers' uses of generative artificial intelligence — Questionnaire on teachers' uses of generative AI (Pérez-Montesdeoca et al. 2026)
- Personalized neural cognitive architecture search — AutoML personalized neural cognitive architecture search for learner profiles
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Measuring Acceptance of Age-Tiered AI Literacy Guidebooks: A Developmentally Informed Study of K-12 Students and Teachers — Split-half EFA/CFA validation with invariance, HTMT and DIF checks, including an honest account of playfulness-intention construct overlap
- ProIQA: A Process-Based Framework for Fine-Grained Math Item Quality Assessment — ProIQA: Process-Based Math Item Quality Assessment
- Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use — Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use
- Bayesian Consensus Calibration of Continuously Evolving IRT Item Banks — Bayesian consensus calibration: divide-and-conquer recalibration of a continuously evolving IRT item bank (Jewsbury et al. 2026)
- How much selection would be enough? Bounding the learning claim of El Salvador's artificial intelligence tutoring pilot — Bounding the learning claim of El Salvador's AI tutoring pilot (Restrepo Morales et al. 2026)
- Know when to trust: Making AI scoring more reliable for educational assessment — Know When to Trust: model self-confidence, probabilistic scoring and ensembles as scoring reliability levers
- Development of an AI literacy self-assessment questionnaire in upper primary school students — A validated 15-item self-assessment questionnaire for upper-primary AI literacy (Thianwan & Srikoon 2025)
- Assessing teachers' AI literacy: a systematic review of measurement tools — Systematic appraisal of 33 teacher AI literacy instruments across COSMIN-style quality domains (Zainal et al. 2026)
- Mental Health Literacy Across Psychology Students and Large Language Models — Mental Health Literacy Across Psychology Students and Large Language Models

- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses
- EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues — EduBehaviors: Assertion-based Schemas for Auditable Coding of Educational Dialogues
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- AI Empathy as a Human Disposition in Generative AI Interaction: Development and Preliminary Psychometric Evaluation of a Cognitive–Affective–Motivational Scale — A 42-item AI empathy scale whose six factors did not recover the six intended subfactors
- Generative artificial intelligence-supported self-regulated learning (GenAI-SRL) in L2 writing: scale development, validation, and short-form construction — A six-dimension GenAI-SRL scale for L2 writing; ant-colony-optimized 12-item short form tracks the full scale (r = 0.910–0.944) but narrows content coverage
- Do Cognitive Classifications Predict Empirical Item Behaviour? Aligning Bloom's Taxonomy with the Psychometric Properties of National Centralized Mathematics Items across Grades 4–12 — Do Cognitive Classifications Predict Empirical Item Behavior? Aligning Bloom's Taxonomy with the Psychometric Properties of National Centralized Mathematics Items across Grades 4–12
- A Benchmark for LLM's Understanding of Middle School and High School Science Topics — A synthetic benchmark's measurement quality rests on its generation pipeline
- FoundationalASSIST: An Educational Dataset for Foundational Knowledge Tracing and Pedagogical Grounding of LLMs — Difficulty without discrimination
- Same construct, same conclusion? A construct-observability perspective on self-report and non-self-report indicators in AI education research: a two-phase systematic review — Same-construct pairs disagree in 41.2% of cases, and performance measures need their own validity argument (Fan et al. 2026)
- Development and validation of the AI cognitive offloading scale for Chinese college students — Validation of the AI Cognitive Offloading Scale, with the validity checks it omits

Connected FAQs

- What Is the Evidence on AI Literacy Interventions in Higher Education?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?

Item Response Theory

> **Item response theory (IRT)** — a family of psychometric models that estimate latent ability from item responses by modeling the relationship between a learner's ability and the probability of answering each item correctly. IRT models item difficulty and discrimination, enabling measurement precision and adaptive testing. In the AI era, IRT meets LLMs in Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction and Aligning LLM-Simulated and Human Examinees for Psychometric Calibration: A Cognitive Diagnostic Profiling Approach: AI predicts and calibrates item difficulty, potentially improving measurement precision and feeding Adaptive Learning.

Questions to Consider

- Item response theory treats ability and item difficulty as jointly estimated from response patterns, rather than treating a raw test score as the measure. How might two students with the same number correct actually differ in ability?
- IRT lets you compare learners on a common scale and estimate precision per person. Why might knowing an item's difficulty and discrimination matter more than just knowing whether a student got it right?
- One study used IRT person-fit statistics to distinguish human from AI-generated responses on multiple-choice tests — flagging AI responses as 'aberrant.' How could the same measurement machinery that assesses learning also police academic integrity?
- Researchers use IRT to validate that AI-generated exam questions match expert-written ones in difficulty and discrimination. If an AI writes an item that 'looks' good, why is empirical calibration against fitted IRT parameters still necessary?
- As AI predicts and calibrates item difficulty, what could go wrong if a model's estimate of difficulty isn't validated against real student response data?
- IRT connects to adaptive testing and knowledge tracing — using your responses to choose what to ask next. How does estimating your ability from each answer enable a test to become shorter and more precise rather than just longer?

Introduction

IRT treats ability (θ) and item parameters (difficulty, discrimination, sometimes guessing) as jointly estimated from response patterns, rather than treating a raw score as the measure. This makes it possible to compare learners on a common scale, to select items adaptively, and to estimate precision per person rather than globally.

How IRT appears in the research

- **AI-predicted difficulty:** LLM item-difficulty prediction uses language models to estimate item difficulty, which must be validated against empirically fitted IRT parameters.
- **Psychometric calibration:** LLM psychometric calibration aligns model-based assessment with IRT-based measurement so that AI-generated responses preserve measurement properties.
- **Knowledge tracing and student modeling:** IRT is closely related to Knowledge Tracing and Learner Modeling and Adaptive Instruction — models that track learner knowledge over time — sharing the goal of estimating unobservable learner states from observable responses.
- **IRT quantities read out of LLM logits.** Huang et al. (2026) extract student ability θ = z^GOOD − z^BAD and tutor-turn difficulty d = z^HARD − z^EASY from next-token logits and combine them in a 1PL Rasch predictor, making dialogue-based knowledge tracing interpretable (64.29% accuracy, 65.25 AUC on QATD2k).
- **Dialogue subtasks on the same scale as questions.** Duan et al. (2026) rewrite the subtasks tutors pose mid-dialogue into standalone questions and place them on one shared 1PL IRT scale whose difficulty comes from question text, using scaffold-after-struggle and push-for-rigor moves as difficulty-ordering supervision.
- **Bayesian hierarchical field validation:** Assessing AI-Generated Exams uses a Bayesian hierarchical 2PL IRT model (with pre-test anchor items to place 1,686 students on a common θ scale) to show that AI-generated questions match expert-written standardized-exam items in difficulty and discrimination — a large-scale demonstration of IRT as the validation backbone for Automated Question Generation.
- **A standards-aligned Benchmark can saturate.** On NGSS-aligned middle school and high school science sets, most open-weight models scored above 90%, leaving classical item metrics poor — difficulty high, discrimination low, with trivial cells above 90% — so the authors cannot separate weak items from a domain that has become tractable (Schroeder et al. (2026)).
- **Test information localises precision.** A 20-item GenAI-literacy test validated with a 2PL model (RMSEA = 0.03, CFI = 0.97) had its information function peak at θ = −0.8, making it most precise for low-to-moderate literacy learners rather than uniform across the scale (Jin et al. (2025)).
- **Separating human from GenAI responses with person-fit statistics:** Strugatski and Alexandron (2026) apply person-fit statistics (PFS) within IRT to distinguish human from Generative AI responses on multiple-choice assessments. PFS flag GenAI responses as ‘aberrant’ responders in two authentic contexts (a chemistry test and a national exam), show that different chatbots produce distinct response patterns (a heterogeneous group of ‘intelligences’), and reveal that newer GenAI versions become more human-like — positioning IRT as a robust framework for integrity screening in high-stakes testing.
- **The same items may not measure the same latent construct for an LLM.** Strugatski, Zeinfeld and Alexandron (2026) compared human and LLM factor structures across two instruments with exploratory factor analysis and congruence matching; LLM–human similarity reliably stayed

below the human–human baseline, so IRT parameters fitted on humans do not transfer automatically.

- **LLM difficulty estimation against Rasch IRT parameters:** Razavi and Powers (2026) evaluate whether GPT-4o can estimate the difficulty of K-5 math and reading assessment items (N = 5170) calibrated under the Rasch IRT model. A zero-shot direct estimation approach correlated moderately-to-strongly with true Rasch difficulties (r = 0.83 math, r = 0.81 reading) but was uneven across grades and often no better than a grade-mean dummy regressor for grades K and 1, likely due to range restriction in lower-grade item difficulties. A feature-based strategy — LLM-extracted cognitive and linguistic features fed into tree-based models — outperformed direct estimation (correlations up to r = 0.87), with grade level and word count the top predictors. The study underscores that LLM difficulty estimates must be validated against empirically fitted IRT parameters, and that structured feature extraction can sharpen prediction where holistic zero-shot judgment falls short.
- **Explaining difficulty instead of predicting it.** Cui et al. (2026) fit a 1PL Rasch model to LLM response records for GSM8K (1,319 questions), BBH-structured (1,396) and WinoGrande (1,267), with 5,000 models for GSM8K and WinoGrande and 3,811 for BBH-structured. They then prompt an LLM to propose natural-language hypotheses for why one item is harder than another, and select them with L1-regularized regression on held-out questions. Used alone on unseen questions the selected hypotheses reach $R^2 = 0.373$ on GSM8K, 0.580 on BBH-structured and 0.090 on WinoGrande, the best of the compared methods on GSM8K and WinoGrande and second best on BBH-structured, where a fine-tuned RoBERTa-base reaches 0.646. As extra features they add +0.11 to RoBERTa-base on GSM8K (0.362 to 0.468) and +0.19 and +0.18 to two frozen embedding models. A causal probe edits 50 test questions per dataset toward or away from a hypothesis: increase-difficulty edits reduce mean accuracy by 15.27 and 23.88 percentage points on GSM8K and BBH-structured, while decrease-difficulty edits raise it by 32.18 and 28.52. Difficulty here is estimated from model responses, not from human test-takers, so this is an LLM-evaluation and psychometrics result.
- **Simulating respondents can recover what regressing the stimulus cannot:** a fine-tuned Multimodal AI LLM reproducing students' option-choice probabilities across ability levels approximated held-out difficulty at r = 0.85, above the MathBERT (0.68) and MetaMath (0.75) regression baselines, and recovered the guessing parameter c at 0.48 while discrimination a stayed weak (0.31) (Ormerod & Kim, 2026).
- **Item-writing flaws as a pre-deployment screen for IRT parameters:** Schmucker and Moore (2026) test whether Item-Writing Flaw (IWF) rubrics — a domain-general, textual evaluation requiring no student data — predict empirically estimated IRT difficulty and discrimination. Across **7,126 multiple-choice questions** in STEM (physical science, mathematics, life/earth sciences), they used automated, LLM-assisted coding to show that IWF rubrics carry predictive validity for empirical IRT parameters, offering a scalable pre-deployment screen that complements or partially substitutes resource-intensive pilot testing.
- **IRT-based risk filtering for selective AI grading:** Cvengros & Kortemeyer fit a two-parameter logistic IRT model to AI-graded handwritten-chemistry data and define the "risk" of accepting an

AI judgment as the absolute deviation between the AI's normalized score and the IRT-expected probability of credit (Risk = |s−p|); accepting only items within a chosen tolerance of this Bayesian expectation flags "surprising" AI scores for human review, turning IRT from a pure score-aggregation tool into an operational acceptance/deferral mechanism for Automated Assessment — one that achieved alignment with human grading similar to simpler partial-credit thresholds but with lower human workload, though its logic is less transparent to non-technical audiences.

- **IRT as a calibration layer inside a diagnostic model:** PLCD adds an IRT-inspired guessing-and-slipping head over exercise-level responses, improving probability quality rather than accuracy — expected calibration error fell from 0.071 to 0.037 on XES3G5M — making IRT an internal correction for response noise, not only a scoring model (Liu et al. (2026)).
- **Divide-and-conquer calibration for continuously evolving banks:** Jewsbury et al. (2026) treat IRT recalibration as a scaling problem rather than a fitting problem. When AI-based item generation and feature-based parameter prediction make a bank larger, sparser and continuously updated, refitting the full response history at every update grows steadily costlier; their *consensus calibration* instead calibrates each time period once and combines a new period with already-computed earlier posteriors. Two features separate it from existing IRT divide-and-conquer work: the periods do not share a latent metric, so each is linked to a reference metric by a robust Haebara criterion solved *separately for every posterior draw* (carrying linking error into the linked posteriors), and each period is its own hierarchical fit contributing an estimated prior, so the naive product of posteriors must have that prior divided out and a consensus prior reinstated — reducing to the Bayesian committee machine rule when the priors are fixed. Against a pooled benchmark on four quarterly periods of the Duolingo English Test, posterior means agreed at r = .998 (difficulty) and .991 (log-discrimination) with posterior SDs at r = .970 and .920, leaving mild under-dispersion (SD ratio 0.91–0.98) that was largest in the lowest per-period exposure tertile. It is IRT calibration re-engineered for the delivery conditions AI-generated item banks create.
- **How rarely IRT anchors instrument validation:** an appraisal of teacher AI literacy instruments quantifies IRT's absence rather than its use. Zainal, Mohd Matore and Maat (2026) graded 33 instruments against a decision matrix adapted from COSMIN and Terwee et al. (2007); structural validity was strong, with 24 (72.7%) at Grade A through CFA, PLS-SEM or IRT modeling, yet none used IRT or Rasch as its primary evidence, and only five instruments (15.2%) reported measurement invariance or differential item functioning evidence. The authors argue for IRT and performance tasks alongside Self-Assessment to separate validated capability from reported confidence.
- **A causal alternative to associative IRT.** Mangili et al. (2026) argue IRT and Bayesian-network learner models cannot express interventions or counterfactuals, and elicit structural equations from experts instead; on a 109-student adaptive-test battery the elicited model was slightly less predictive (−287 versus −277 test log-likelihood) yet supported counterfactual queries about help.

Connections

IRT is a foundation of Educational Measurement and Assessment Validity, underpins Adaptive Learning (adaptive item selection) and Learner Modeling and Adaptive Instruction, and connects to Psychometrically Aware AI (AI assessment aligned with measurement theory) and Knowledge Tracing. It features in LLM difficulty calibration for programming assessment.

Common Misconceptions

- **"IRT requires conventional test administration."** Ability and difficulty can be recovered from **next-token logits**: extracting **student ability θ = z^GOOD − z^BAD** and **tutor-turn difficulty d = z^HARD − z^EASY** and combining them in a 1PL Rasch predictor makes dialogue-based knowledge tracing interpretable in IRT terms. The psychometric framework applies to interaction data, not only to item responses.
- **"A benchmark that most models pass is a good benchmark."** A standards-aligned benchmark can **saturate**: on NGSS-aligned middle school and high school science sets, **most open-weight models scored above 90%**, leaving classical item metrics poor. Saturation does not mean the models are excellent; it means the items are no longer discriminating.
- **"Item difficulty is an intrinsic property of the item."** A causal probe that **edited 50 test questions per dataset** toward or away from a hypothesis found **increase-difficulty edits reduced mean accuracy by 15.27 and 23.88 percentage points** on GSM8K and BBH-structured. Difficulty is a relationship between item and model, and it moves when the item does.
- **"IRT is only for scoring learners."** Assessing AI-Generated Exams uses a **Bayesian hierarchical 2PL model with pre-test anchor items to place 1,686 students**, which is quality assurance for the assessment itself rather than scoring for the student.

Connected Concepts

- Educational Measurement
- Assessment Validity
- Knowledge Tracing
- Learner Modeling and Adaptive Instruction
- Psychometrically Aware AI
- Adaptive Learning
- Automated Assessment
- Intelligent Tutoring

Connected Articles

- A Unified Response Framework for Questions and Tutoring Dialogues — A Unified Response Framework for Questions and Tutoring Dialogues

- What Makes Something Hard(er)? Explaining Question Difficulty in Natural Language — Explaining LLM question difficulty in natural language through IRT and causal edits (Cui et al. 2026)
- The impact of item-writing flaws on difficulty and discrimination in item response theory — Impact of item-writing flaws on IRT difficulty and discrimination (Schmucker & Moore 2026)
- Causal modelling of support interventions for student competency assessment — Causal Modeling of Support Interventions for Student Competency Assessment
- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Large-scale IRT field validation of AI-generated exams
- GLAT: The generative AI literacy assessment test — GLAT uses IRT/2PL validation (Jin et al. 2025)
- Cognitive Episodes in LLM Reasoning Traces Enable Interpretable Human Item Difficulty Prediction — LLM prediction of item difficulty
- Aligning LLM-Simulated and Human Examinees for Psychometric Calibration: A Cognitive Diagnostic Profiling Approach — Aligning LLM assessment with psychometric calibration
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations — LLM difficulty calibration in programming exams
- Multimodal item parameter estimation using simulated response probabilities — Multimodal item-parameter estimation
- Interpretable Knowledge Tracing — Interpretable knowledge tracing
- Applying psychometric methods to distinguish between human and generative AI responses to multiple-choice assessments — Using IRT to separate human and GenAI MCQ responses
- Estimating item difficulty using large language models and tree-based machine learning algorithms — Estimating item difficulty using LLMs and tree-based ML
- Assisting the grading of a handwritten general chemistry exam with artificial intelligence
- Beyond ID Embeddings: Process-Grounded Language Modeling for Cognitive Diagnosis — Beyond ID Embeddings: Process-Grounded Language Modeling for Cognitive Diagnosis
- Bayesian Consensus Calibration of Continuously Evolving IRT Item Banks — Bayesian consensus calibration of a continuously evolving IRT item bank (Jewsbury et al. 2026)
- Assessing teachers' AI literacy: a systematic review of measurement tools — Field audit showing IRT/Rasch rarely used as primary validation evidence in teacher AI literacy instruments
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- A Benchmark for LLM's Understanding of Middle School and High School Science Topics — A standards-aligned benchmark can saturate

Self-Report Measures

> **Self-report measures** — instruments in which the person being studied is also the source of the data: questionnaires and surveys, interviews, diaries, self-assessed competence, self-estimated usage, perceived learning, and satisfaction. They are the workhorse of AI in education research — in this knowledge base 139 article pages carry a survey method tag, more than any design except experiment and Benchmark — and they are the only practical way to reach attitudes, beliefs, intentions, and Self-Efficacy. Their limit is categorical rather than statistical: a self-report cannot measure behavior or learning, only what someone says about behavior or learning, and the two come apart in this research base often enough to be a finding in its own right.

Questions to Consider

- If a study says students "reported high engagement," what exactly was measured — and what would you need to see to conclude they actually engaged?
- In one study, self-reported and objective measures of teacher AI literacy correlated at only r = 0.07 to r = 0.24 across four dimensions. Where would your own Self-Assessment most likely diverge from a test of the same skill, and why?
- Satisfaction is easy to measure and easy to improve — a system tuned to please users will score well on it. Why might that make satisfaction a poor outcome measure for learning, and what would you measure instead?
- "Nearly all students use AI for coursework" comes from asking students. What could asking rather than logging get wrong in either direction?
- A survey gets 112 responses at a 31% response rate, or 90 responses from 572 invitations. Before accepting its percentages, what do you want to know about who did not answer?
- When a study correlates two self-reported variables measured at one moment, how many separate explanations can you generate for the correlation — and what design would rule them out?
- If you were advising someone on a small evaluation, which claims would you let them support with a survey, and which would you insist need log, performance, or observational evidence?

Introduction

Self-report spans far more than the questionnaire. It includes cross-sectional surveys using Likert and other rating formats, interviews and focus groups conducted by qualitative researchers, diaries and experience sampling, self-assessed skill or confidence, recalled estimates of how often a tool was used, and perceived learning or satisfaction treated as outcomes. What unites them is the epistemic position of the respondent: they are reporting on themselves rather than being observed.

This is not a weakness to be apologized for. Many constructs of interest — motivation, anxiety, trust, perceived usefulness, engagement intentions — are internal states that no log file records, and asking is the only defensible way to reach them. The problem arises when a self-report is used to support a claim it cannot

carry, which is a validity question at heart: whether the instrument measures the construct it names, and whether the claim being made is about the sort of thing self-report can see. That concern belongs with Educational Measurement and Assessment Validity; this page is about what happens when AI in education research leans on self-report specifically, and where the evidence base shows it breaking down.

How this page relates to its neighbors. Research Methods in AIED catalogs designs and their strengths and limitations, including survey and SEM studies. Quantitative Research covers the numerical methods family. Educational Measurement covers instrument development, Item Response Theory, and psychometric validation. This page is the narrower slice those pages point at: the measurement instrument and data source itself — what self-report can and cannot establish, the recurring gap between what people report and what they do, and how to read a self-report finding critically.

What self-report can and cannot establish

Self-report is well suited to attitudes, beliefs, intentions, perceptions of a tool, affective states, and self-judged confidence or difficulty. A scoping review of 394 GenAI higher-education studies found survey scales the most frequently reported assessment method (269 studies, 68.3%), ahead of tests/quizzes/rubrics (185, 47.0%) and artifact analysis (167, 42.4%) (Lin et al. (2026)). It is poorly suited to behavior, and it cannot measure learning at all: a person's belief that they learned something is itself a perception, and the knowledge base treats perceived learning as a distinct quantity from learning gains.

The consequence is a set of claims that look similar in a results section but differ in strength:

- "Students found the tutor useful" — a perception, appropriately measured by asking.
- "Students used the tutor regularly" — a behavior, only approximated by asking.
- "Students learned more with the tutor" — an outcome, not establishable by asking at all.
- "Teachers are confident using AI" — a self-belief, not evidence of competence.

Two implications follow for anyone reading or designing this research. First, whether a self-report instrument is even measuring its named construct is an empirical question, answered by validation rather than by the plausibility of the items. Second, the direction of the temptation in AI in education is consistent: tools are evaluated by how users feel about them, and feeling is precisely the part that self-report captures most cheaply. Self-Assessment is a member of that wider family rather than a synonym for it: where self-report measures reach attitudes, trust, and satisfaction, self-assessment turns the learner's estimate specifically onto their own skill, confidence, or learning.

A second failure mode is discriminant collapse between two self-report constructs: regressing self-reported AI capability alongside perceived behavioral control measured as efficacy may compare one general-confidence factor with itself, which is why criteria are fixed in advance — a heterotrait–monotrait ratio below .85 and a nested-model test constraining the capability–control correlation to unity (Mnguni (2026)).

A validated instrument can make that limit precise rather than vague. The AI Literacy Self-Assessment Questionnaire (AIL-SAQ) of Thianwan and Srikoon (2025) is a 15-item scale confirmed with a stable three-factor structure across two samples (n = 335 exploratory, n = 579 confirmatory) and an overall Cronbach's alpha of .934. Its authors are explicit that it records perceived understanding, attitudes, and awareness rather than demonstrated skill, and that self-assessment accuracy depends on metacognitive ability still maturing in children, so a child's self-estimate is a weaker signal than an adult's.

The opposite choice is also defensible: PAUSE is a four-domain offloading self-check that publishes no reliability or validity evidence, offers no composite, and states that readings must not justify any consequential decision, and its items conflate deliberate scaffolding with substitution — a respondent who brings AI in early to scaffold reads as offloading (Alam, 2026).

The perception–behavior gap

The strongest self-report finding in this knowledge base is not that self-report is biased in general but that reported and observed behavior diverge in specific, documented ways.

Profiles derived from self-report behave the same way. Najem et al. (2026) clustered 14,003 student records on self-reported behavioral and psychological proxies rather than LMS interaction traces, and the six resulting profiles separated sharply on final grade ($\eta^2 = 0.770$) — a separation the authors caution is partly a restatement of what students reported.

Behavioral traces can separate learners whom a self-report scale cannot: Poquet et al. (2026) found self-reported cognitive load did not differ significantly across offloading profiles that ranged from 80% to 2% in essay authorship, while the heaviest offloaders nonetheless reported the highest mental demand.

A study that built parallel self-report and objective measures of teacher AI literacy found **weak agreement between the self-report and objective factors (r = 0.07 to r = 0.24)** in a sample of 288 teachers. Confirmatory factor analysis supported the construct validity of both measures while showing a **low correlation between the self-report and objective factors**. The two instruments were credible; they simply measured different things. In the full sample of 288 teachers the correlations between the objective and self-reported factors ran from r = 0.07 to r = 0.24, and latent profile analysis found 43 teachers who rated themselves high while scoring lower on the objective measure against 59 who showed the reverse pattern.

GLAT reaches the same conclusion from the other direction: its 20-item performance-based test predicted performance on GenAI-supported learning tasks in a within-subject study of 83 students, **while self-reported ChatGPT literacy did not**. The authors' framing is blunt — instruments in this area overwhelmingly rely on self-reported surveys, "which capture perceived rather than actual competence and are prone to bias and overestimation."

Behavioral estimates show the same split. A large-scale competitive-programming study reported a **disconnect between self-reported confidence and actual practice behavior**, the former a poor proxy for the latter. A learner-modeling study is candid that usage frequency was self-reported on a Never-to-Daily scale rather than observed, and that with predictors and outcomes both self-reported, response styles such as acquiescence or extremity bias could produce the associations.

Sometimes asking and observing are set up head to head. A scoping review of 46 categorizations from 33 studies found the literature split about evenly between self-report and interaction-log data, and concluded that categories "often reflect the measurement approach as much as the interaction itself" — with self-report studies capturing perceptions and intentions while log-based studies capture observable conversational behavior, and the two rarely integrated. Process-data work on GenAI literacy makes the constructive version of the point: whether a student prompts iteratively, refines output, and manages hallucinations is observable in interaction logs and not in a questionnaire.

A 2026 structured review and exploratory meta-analysis of measures for competent Generative AI use puts a pooled number on that gap from the other direction: pooling three directly reported same-sample subjective–objective correlations (combined reported N = 2,765) gave r = .055 (Hartung–Knapp 95% CI [−.047, .156]), and adding a fourth study's cross-factor correlations reached only r = .079. All three primary effects came from a single research program, the largest contributor's reported correlation and p-value could not be reconciled, and the review concludes that self-report cannot stand in for objective performance scores — while noting that the performance instruments are themselves narrow, covering foundation knowledge rather than the oversight and reliance behaviors that matter at work (Verí (2026)).

A two-phase systematic review puts a rate on that divergence at the level of conclusions: of 51 same-construct pairs from 47 reports, 30 agreed, 11 disagreed and 10 were mixed. Disagreement ran both ways: five contrasts paired a null self-report result with a positive performance result, against two the reverse (Fan et al. (2026)).

One university library put both streams against the same propositions and found them pointing apart. Annual print loans fell from 406,120 in 2017 to 46,339 in 2025 and unique borrowers from 30,033 to 7,278, but the decline began before the GenAI period, and the January 2023 breakpoint showed no level or slope change. The survey put the explanatory weight on constructs: deep-reading demand predicted print continuance intention at H1 β = 0.908, while the hypothesized substitution path was near zero (H4 β = 0.038, p = 0.631), and platform AI features were 0.53% of operations in the first half of 2026. Respondents could not be linked to the loan records under data-governance rules, so the divergence can be read only at the population level, not person by person (Huang et al. (2026)).

The instrument literature itself can be read as evidence of the gap's scale. Zainal, Mohd Matore and Maat (2026) appraised 33 instruments for teacher AI literacy and found that 31 (93.9%) were self-report scales of perceived confidence, only two (6.1%) tested knowledge objectively, and none used performance-based tasks between 2019 and 2025. Their conclusion is the one this page keeps reaching from other directions: self-report scores index confidence rather than capability, so they cannot stand in for competence when groups or programs are compared.

Outcome measures inherit the same gap. Pramod and Patil (2026) model the path from agentic AI through motivation and social presence to what they label learning performance with a coefficient of 0.671 — the strongest relationship in the study. Their own limitations section states that this dependent variable reflects learners' perceptions and not exam results, assignment performance or learning analytics. That is the pattern to read carefully in pathway models generally: a large coefficient on a perceived outcome quantifies how consistently students believe something helped, and says nothing yet about whether it did.

Intention is the sharpest case of that gap, because one intention score can cover opposite behaviors. Re-administering items to 68 of the 340 students and interviewing eight, Xue, Xu, Qi & Lu (2026) found the same stated intention covering learning-oriented, shortcut-oriented and mixed use — the shortcut users citing low confidence rather than disinterest.

- **"Students report what they did."** The trace contradicted the survey in a useful direction. In an essay study where **15 of 77 (19.5%)** submitted essays with no typed words, perceived ownership fell only in that fully delegating group, while writers who used the model for planning or reviewing reported ownership at the level of students who never opened it. Self-report therefore

distinguished the extremes and flattened everything between them, which is what a perception measure can do and what it cannot. The perception-behavior gap, measured with keystrokes.

Satisfaction and perceived learning as outcomes

Satisfaction is the most frequently self-reported outcome in this corpus, appearing on 63 article pages. It is also the weakest as a proxy for learning, and the knowledge base contains explicit arguments to that effect.

- Work on sequenced AI feedback states the design principle directly: user satisfaction and behavioral engagement are not reliable proxies for learning gains, so learning must be measured directly.
- On pedagogical steering notes that current language models are instruction-tuned to be helpful assistants that maximize user satisfaction, while a tutor's goal is to maximize learning — the two objectives can conflict, which makes satisfaction a potentially misleading target rather than merely a weak one.
- A scaffolding study argues that perceived usefulness, ease of use, and immediate satisfaction should not be treated as sufficient indicators of Scaffolding effectiveness.
- On personality-aligned student modeling observes that optimizing for user satisfaction is not the same as optimizing for learning outcomes, and that the two can come apart.

The pattern worth carrying away: satisfaction is responsive to the wrong things when learning is the goal. A system that answers quickly, agrees readily, and reduces effort will be rated highly, and those same properties are the ones the knowledge base associates with reduced productive struggle and inflated performance on AI-assisted work. Reported satisfaction and measured learning are not enemies; they are simply not substitutes, and treating the first as evidence of the second is the most common slippage this page documents.

Perception measures outnumber skill measures in the generative-AI inquiry literature. In a 66-study review, Yahya et al. (2026) found user perceptions the most reported outcome domain (32 studies, 48.5%), followed by affective outcomes at 25, while only 8 studies (12.1%) measured inquiry skills and 4 of those had a comparison condition. The authors rated no certainty of evidence, so the perception counts describe what was asked rather than what was achieved.

What makes a self-report instrument credible

Four properties separate a survey that can support a claim from one that cannot.

- **Construct validity.** Items must be shown to measure the named construct, ideally with factor analysis. The parallel-measure study above validated both its instruments and still found they diverged — validity of an instrument says nothing about whether it captures behavior.
- **Reliability and structure.** Factor-validated instruments recur in this corpus, from teacher AI literacy measures grounded in self-determination theory to acceptance scales modeled with TAM and SEM in studies of AI-assisted language tools.
- **Invariance, when groups are compared.** A scale that behaves differently across populations cannot support a comparison. Multigroup SEM work reports measurement invariance testing (configural, metric, scalar) alongside its indirect effects, and a Switzerland–China comparison

found only intrinsic value reached metric invariance and not scalar invariance — a limitation stated rather than hidden, and one that constrains what its cross-country differences can mean.

- **A performance alternative where competence is the construct.** GLAT's 20 multiple-choice items exist precisely because self-report cannot carry a competence claim.

Most instruments in this space report reliability and almost none report validity. Kharbach et al. (2026) cite Su et al.'s review of 36 AI literacy studies, which found 63.8% of tools reporting reliability evidence and fewer than 20% reporting validity evidence. The same review found only one generative-AI-specific instrument, the 27-item GAIAS, among 50 K-12 frameworks. A scale being internally consistent says nothing about whether it measures the construct named in its title.

Sampling, response, and non-response

Because surveys are cheap to administer, the sampling problems are usually where the generalizability claim fails. This corpus reports them explicitly and instructively:

- A UK survey of student GenAI use reports a convenience sample at 7 institutions, sharply varying institutional response rates, and non-response bias that may skew toward students with strong views — and notes that ~32% of respondents described conduct that arguably broke policy, in a format where social desirability and contextual pressure make **under-reporting** the likely error direction.
- A study of AI-assisted grading feedback rests on 112 responses, a 31% response rate.
- A faculty study draws on 90 STEM faculty from 572 invited awardees — 16%.
- A sociology survey obtained 504 respondents from 844 invitees, and the authors note response rates varied by question.
- A Delphi study completed its first round with 17 respondents, a limitation it states plainly.

Self-selection compounds this. An inoculation study recruited 782 participants and retained 100 valid cases from a convenience sample of self-reported ChatGPT users; a physics study had students self-select into an extra-credit task, plausibly skewing views toward the agreeable and excluding skeptics.

Two further self-report-specific errors recur. **Introspection limits and social desirability bias** are named as intrinsic to self-report in work on engagement assessment and in studies whose qualitative data rely on self-report. **Common-method variance** arises when predictors and outcomes come from the same respondents at the same time: a moderated-mediation study of AI use and critical thinking operationalized usage, cognitive load, and self-regulated learning all through standardized self-report instruments at a single time point, and raises common-method bias as a consequence; a PLS-SEM study of motivation and engagement likewise rests entirely on self-report and cannot establish temporal ordering among its mediators.

Administration mode is a second threat the corpus has not yet counted. Tamme, Schilling & Hantel (2026) proposes replacing written course surveys with AI-conducted telephone interviews, and assembles mode-effect evidence that cuts both ways: voice answers run longer and cover more topics, while one randomized comparison of 634 respondents found text responses more differentiated and more candid.

Remedy: adding non-self-report evidence

The knowledge base's constructive answers are consistent, and none of them requires abandoning surveys.

- **Pair self-report with trace or log data.** A 194-student, eight-week study of adaptive learning technology combined self-report with trace data under hierarchical linear modeling, which is what allowed it to follow self-regulated learning phases as they unfolded rather than as recalled.
- **Observe practice directly when the claim is about practice.** A screen-recorded assessment task plus video-stimulated interviews bridged the gap between self-reported AI use and observed practice, capturing metacognitive awareness the survey could not.
- **Score behavior against a rubric rather than asking about it.** Retention work treats practice effort as a behavioral indicator derived from interaction logs, explicitly not a measure of internal motivational state.
- **Triangulate.** Mixed-method designs and mixed-methods research generally trade sample size for the ability to check one data source against another; a systematic review of vocational education is instructive for the imbalance, noting that among the quantitative studies it examined, 2 relied exclusively on self-report while 5 used only objective measures.
- **Measure the outcome you care about.** If the claim is about learning, learning gains must be measured, not inferred from satisfaction.

How to read a self-report claim

- Ask what kind of claim it is. Perceptions are fair game; behavior is approximated; learning and competence are not reachable this way.
- Check who answered and who did not. Response rate, sampling frame, and self-selection decide what the percentages describe — a study of one institution's students describes that setting, not students in general.
- Check the instrument. Was it validated for this construct and population, and if groups are compared, was invariance tested?
- Watch for single-source designs. If predictors and outcomes both come from the same questionnaire at one time point, the associations are consistent with common-method variance as well as with the theory proposed.
- Treat satisfaction as a design signal, not a learning outcome. High satisfaction plus untested learning is the standard configuration in AI tool evaluation, and this corpus shows the two diverging.
- Prefer studies that show their working: stated response rates, stated limitations, and at least one source of evidence that does not come from asking.

Common Misconceptions

- **"Survey evidence is weak but roughly unbiased."** Response structure bounds the estimate before bias: a survey gets **112 responses at a 31% response rate**, or **90 responses from 572 invitations**. The respondent pool is a self-selected subset, so the figure describes that subset.

- **“Surveys are a minority method in this field.”** A scoping review of **394 GenAI higher-education studies** found **survey scales the most frequently reported assessment method (269 studies, 68.3%)**, ahead of tests and quizzes. The field’s dominant evidence is self-report.
- **“Self-report and measured constructs agree.” Self-reported cognitive load did not differ significantly across offloading profiles that ranged from 80% to 2% in essay authorship**, while the heaviest offloaders differed measurably. The subjective measure was flat where behavior varied by a factor of forty.

Connected Concepts

- Interpreting and Applying AIEd Research
- Educational Measurement
- Self-Assessment
- Research Methods in AIED
- Quantitative Research
- Qualitative Research
- Mixed-Methods Research
- Assessment Validity
- Item Response Theory
- AI Literacy
- Trust Calibration
- Learning Gains
- Student Engagement
- Self-Efficacy
- Learning Analytics

Connected Articles

- Modeling high school students’ acceptance of GenAI for physics learning via an extended technology acceptance model: Disciplinary beliefs as a distal antecedent — One intention score, two opposite uses
- Voice-Based AI Feedback in Higher Education: A Field Study on Quality and Actionability — The administration mode a self-report instrument uses changes what it measures
- A Capability–Decision Model of teacher readiness for AI integration in teaching — Discriminant-validity criteria for separating self-reported AI capability from efficacy beliefs
- Agentic AI in educational environments and its association with social and motivational pathways to learning performance — Engagement predicts perceived rather than measured performance in an agentic AI path model (Pramod & Patil 2026)
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — Parallel self-report and objective measures of teacher AI literacy

- GLAT: The generative AI literacy assessment test — GLAT: a performance-based alternative to self-report
- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison — Student GenAI use surveyed across UK institutions
- Toward convergence in student-LLM interactions: A rapid scoping review and taxonomy for learning-oriented use — Taxonomies shaped by whether data came from self-report or logs
- Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing — Process data characterizing GenAI literacy
- Engagement Intensity as a Learner-Modeling Signal for Adaptive AI Ethics Instruction — Self-reported usage as a learner-modeling signal
- Predicting Student Attrition in Competitive Programming: A Large-Scale Study Integrating Survey Insights and Global Behavioral Logs — Self-reported confidence versus practice behavior
- From AI use to critical thinking among medical students: A moderated mediation perspective on cognitive load and self-regulated learning — Common-method bias in a single-source mediation model
- Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education — Self-report-only PLS-SEM of motivation and engagement
- Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration — Survey of 81 physics undergraduates on AI use and trust
- Summarise, elaborate, try again: exploring the effect of feedback literacy on AI-enhanced essay writing — Screen recording and stimulated recall as a self-report remedy
- Fostering self-regulated learning through adaptive learning technology: A differentiated perspective on the role of feedback — Self-report plus trace data on self-regulated learning
- Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study — Behavioral effort indicators derived from logs
- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — Review reporting the self-report/objective-measure imbalance
- Student use of and views on GenAI for writing — Survey plus interviews in one sociology department
- Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use — Beyond AI Literacy: A Structured Review and Exploratory Meta-Analysis of Measures for Competent Generative-AI Use
- PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading — PAUSE: A Privacy-Preserving Self-Reflection Tool for AI-Associated Cognitive Offloading

- Development of an AI literacy self-assessment questionnaire in upper primary school students — A 15-item self-assessment instrument for upper-primary students, explicit about what perceived competence can establish
- Assessing teachers' AI literacy: a systematic review of measurement tools — Review finding 31 of 33 teacher AI literacy instruments self-report and none performance-based
- Behavioral clustering for adaptive learning object recommendation in higher education using learning analytics for personalized student success — Profiles derived from self-report behave the same way
- Same construct, same conclusion? A construct-observability perspective on self-report and non-self-report indicators in AI education research: a two-phase systematic review — Two-phase review putting a rate on same-construct self-report versus performance disagreement (Fan et al. 2026)
- An Empirical Study to Understand How Students Use ChatGPT for Writing Essays — Perceived ownership separated whole-essay delegation from everything else, while the trace separated much more (Jelson et al. 2026)
- How does generative AI support inquiry-based learning? A systematic review - perceptions reported in 32 of 66 studies against 8 that measured inquiry skills
- K-12 AI literacy frameworks after generative AI: A scoping review - 63.8% of AI literacy tools report reliability evidence and fewer than 20% report validity evidence
- Generative artificial intelligence reshapes university students' sustainable use of academic information resources: mixed evidence from behavioral logs and perceptual survey data — Library logs and survey attitudes pointing in different directions

Connected FAQs

- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- Does Using AI Actually Help My Students Learn?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?

AI Detection

> **AI detection** — the technologies and methods used to identify AI-generated content in academic submissions, and the broader question of how institutions should respond to the risk that students use large language models (LLMs) to produce work that is not their own. It spans classifier-based approaches, latent-prompt and likelihood techniques, watermarking, and stylistic analysis — and, increasingly, debates about the limits of detection and the value of redesigning assessment rather than policing it.

Questions to Consider

- If an AI detector flags a student's essay as AI-generated, how confident would you be that the flag is correct — and what evidence would you want to see before acting on it?
- One argument is that AI detection is not just unreliable but conceptually unsound: a binary 'human vs. AI' ignores that student work is usually created with, not by, AI. If work is a hybrid, what does 'detecting AI' even mean?
- Detection tools can be biased against non-native writers, producing false positives that unfairly penalize students. How would you weigh the risk of a false accusation against the value of catching genuine misuse?
- Detection can undermine integrity rather than safeguard it, fostering a climate of suspicion that erodes trust. How does being watched change how you, or a student, behave in an assessment?
- Research suggests detection should be a limited, situational tool rather than a strategy of first resort, and that assessment design should recognize AI's role. What alternatives to detection might better verify what a student actually learned?
- AI detectors can't be independently verified in real submissions — there's no ground truth for whether a flagged text was actually AI-generated. How comfortable are you acting on an unverifiable probability in an integrity investigation?

Introduction

AI detection sits at the intersection of Academic Integrity, Generative AI, large language models, and Assessment. It arose as institutions confronted students using LLMs to draft essays, code, and short answers. The field has two intertwined strands: **technical detection** (how reliably can AI-generated content be identified?) and **institutional response** (what should detection lead to, given its limits and fairness concerns?).

Detection approaches

The knowledge base's research illustrates the main technical families:

- **Zero-shot likelihood / latent-prompt methods:** EchoPrompt is a training-free zero-shot detector that exploits the latent prompt dependency inherent in machine-generated text. By restoring a

generic assistant-response prefix and measuring likelihood-gain differences between instruction-tuned and base models, it achieves state-of-the-art detection without training, remaining robust across domain shift and paraphrasing attacks. This contrasts with purely probability-based statistical detectors that ignore the generation mechanism.

- **LLM self-detection:** Leinonen & Denny (2026) test whether LLMs can reliably detect their own generated content across programming, reflective writing, and short-answer tasks. Detection proves **highly task-dependent**: reliable for programming and longer reflective responses, but poor for short answers, where LLMs often judge their own output as *more* human-like than authentic student work. Minor prompt variations sharply reduce accuracy.
- **Classifier-based and watermarking approaches:** statistical classifiers and watermarks are widely deployed in commercial tools, though their reliability is contested as LLM outputs become more sophisticated.
- **Idea provenance rather than prose provenance:** IdeaLens feeds a classifier an outline of discourse roles and paraphrased content instead of the prose, so that it predicts whose ideas a document carries. Its AI flag rate fell from 94.9% to 6.8% as the human plan behind AI-written text grew more detailed, while Pangram 4 stayed near 92%, and it labeled 94.7% of AI-polished human documents human. The authors state their predictions are statistical estimates and must not be used alone as conclusive evidence of AI use.

The limits and risks of detection

Research consistently cautions against standalone reliance on detection:

- **Validity and fairness failures:** detection tools can be biased against non-native writers, producing false positives that unfairly penalize students, a concern connecting to Bias Mitigation and Equity.
- **Notable error rates and trust erosion:** unreliable detection undermines student Trust and the integrity of the assessment process.
- **Task-dependence:** as the self-detection study shows, accuracy varies sharply by task type, so no single detector is dependable across all assessments.
- **Even a validated detector rests on a historical baseline:** A six-year CS2 study validated its detector against a pre-LLM baseline: H-scores were near-zero before LLMs were public and rose to a mean of 11.9 by 2026 (Racovan et al. (2026)).
- **The integrity catch-22, quantified.** A controlled study of 642 published abstracts (Karr et al. 2026) shows the policy failure is not just conceptual but measured: guideline-compliant light AI editing is flagged at 38–80%, unmodified recent originals at 9–15% (non-STEM far above STEM), and humanizer-assisted AI text evades detection in >96% of cases. Because detectors key on surface style (long-token and academic-word density) rather than authorship intent, honest AI assistance draws sanction while deliberate humanizer evasion escapes — the authors argue detector scores should never be standalone misconduct evidence.
- **Detection and evasion are two sides of one commercial market.** Roe et al. (2026) catalogued 55 AI-humanizer sites — services that rewrite AI text to evade detection — and found all three they analyzed on the first page of Google, sold on freemium tiers with affiliate programs. Their political-economy argument matters for detector policy: vendors of detection sell a classification

of authorship while humanizers sell the promise of changing that classification, so a detection-first regime does not merely fail against evasion, it manufactures the demand for paid evasion. The sites perform legitimacy rather than assume it — unexplained university and corporate logos placed under the text box, unverifiable user claims (roughly 3 million, 10,000 students, 1.5 million on the three sites), 99.8%–100% success claims, and "1.6 trillion parameters" mystification — and none carried a registered business address. The consequence for a detector decision is that blocking a tool does not remove the demand structure behind it.

- **Enforcement may sort students by academic capital rather than by conduct (proposed, not measured).** Drawing on four UNESCO and OECD publications, Hashem (2026) argues that stronger disciplinary knowledge and prompting literacy let a student revise AI output into an accepted academic register. If that is so, the visibility of AI assistance tracks academic capital rather than the amount of help taken, and detection-led enforcement becomes a filter for that capital. The paper is a discourse analysis with no data on flags or sanction outcomes and states the claim as a hypothesis needing comparative evidence on AI-use patterns, detection results and misconduct decisions.
- **A copy-edit moves the verdict, which separates style from authorship.** Holding author, topic and content fixed across 135,389 edited manuscript pairs, the same edits pushed 13 detectors in opposite directions on human text — MAGE −10.7 percentage points of false positives, RADAR −4.7, against Fast-DetectGPT +4.6 (Park, Jeong and Kim (2026)). Baseline rates spanned 0.0% to 100.0%, scaling with editing intensity.

The most recent empirical evaluations make those error rates concrete rather than generic. Hadra, Cambridge and Mesbah (2026) ran Turnitin and Originality over a balanced 192-text corpus of genuine EFL coursework, professional writing, AI output, and 50/50 hybrids: macro accuracy reached only 0.69 and 0.61, both fell below a macro F1 of 0.55, and both were effectively useless on the hybrid texts (Originality's sensitivity 0.02), with accuracy dropping significantly as texts lengthened and again on scientific writing, plus a borderline-significant tendency to misclassify legitimate EFL student work. Van Vlasselaer, Van Droogenbroeck and Spruyt (2026) tested four commercial tools against a ground-truth-controlled corpus of 160 master's theses: three of them (Turnitin, GPTZero, Copyleaks) failed almost completely on fully AI-generated papers, while only Pangram performed convincingly — and when applied to 1,163 genuinely submitted theses it flagged 45.5% of them, a figure the authors insist is not a prevalence rate because live submissions have no ground truth. Both studies land on the same procedural conclusion: a detector score can prompt closer review, but it is not a finding. The calibration question also cuts the other way: because GPTZero's high-confidence label carried applicant-level false-positive rates of 0.7%, 0.5% and 1.4% across 2020–2022, Isley, Gaebler and Goel (2026) read its flags as a conservative prevalence series across six admissions cycles in one US public policy master's program — the share of applicants submitting at least one flagged essay rose from 21.8% in 2023 to 45.1% in 2024 and 56.1% in 2025 against a signed prohibition, reaching 69.3% of international applicants against 38.6% of domestic ones. Human readers were a weaker instrument again: five admissions officers separating 50 human from 50 AI essays reached AUC 0.70 (95% CI [0.65, 0.75]), above chance but well below the commercial detectors.

On a Kazakh corpus whose human passages provably predate ChatGPT, five English-trained detectors flagged up to 81.4% of human passages and 79.6% of published student essays, and once recalibrated to a 1% false-positive rate they caught at most 1.3% of machine text (Ozaman (2026)).

Even a well-performing interpretable detector keeps its errors at the level of documents. Kumar, Siddiqui and Fuchsberger (2026) trained window-level classifiers on nine interpretable stylometric features — type-token ratio, hapax ratio, word entropy, non-stopword ratio, part-of-speech ratios and sentence-length variability — with 90 participants writing the same prompts independently and then by paraphrasing GPT output, keeping every window from a participant in one fold and testing on 18 unseen writers. Random Forest reached an ROC-AUC of 0.870 and an F1 of 0.842 on 36 held-out documents, yet flagged 4 of 18 independently authored documents as GPT-assisted, a false positive rate of 22.2% (95% CI 9.0–45.2%); SHAP attribution put the most weight on hapax ratio. The authors frame the model as decision support that should prompt contextual review rather than as an automatic misconduct screen, and the accuracy it does reach does not lower the stake of its errors — each false positive is an independently authored document accused of GPT assistance, a validity problem rather than a tuning problem.

The definitional and procedural problems sit alongside the statistical ones. Wright (2026) argues that blanket prohibitions on "AI use" are drafted around platform identity rather than function, so they capture non-generative format conversion — speech-to-text transcription, OCR, plain text to LATEX — along with the generative drafting they mean to bar; because detectors read low-perplexity writing as machine authorship, the resulting false positives fall hardest on disabled and equity-exposed students. Sharma (2026) reaches the design-side version of the same conclusion, positioning detection as a supplementary layer of integrity infrastructure at most, since it asks whether GenAI was used rather than how decisions were made.

Detection research also carries a validity argument that outlasts questions of accuracy. Weidlich (2026) treats detector output as a conditional, probabilistic signal that may prompt further inquiry but cannot by itself establish misconduct or competence, which makes detection-centered governance an insufficient basis for upholding assessment validity. Classification performance varies systematically across tools, task types, disciplines, model versions and human-AI editing practices, with formulaic STEM writing especially susceptible to algorithmic bias. Attempts to restore assessment security through detection then risk introducing construct-irrelevant variance, threatening fairness and the interpretation of scores.

Why not to use (or try to use) AI detectors

Bassett et al. (2026) argue that generative AI detection should **not be used in education at all**, on grounds that go beyond "be careful" to "this is conceptually unsound." Their case consolidates the reasons against relying on AI detectors:

1. **Unverifiable probabilistic estimates.** AI detectors output a probability that text was AI-generated, based on linguistic markers (perplexity, burstiness). Unlike other probabilistic tools (spam filters, medical diagnostics), their results **cannot be independently verified**: in real-world conditions, no ground truth exists for whether a flagged text was actually AI-generated, so validation reduces to circular reasoning. Signal-detection metrics (false-positive/negative rates) only apply in controlled tests, not real submissions.
2. **Questionable training and test data.** Detectors are trained and validated on pre-generative-AI human writing (e.g., Turnitin tested on 700,000 pre-2019 papers). The assumption that such text reflects contemporary student writing — which students now produce having been shaped by AI — is unverified, and performance shifts with model, prompt, and platform.

3. **Mutually-exclusive-linguistic-markers is a flawed assumption.** There is no principled reason a human cannot write with the linguistic features attributed to AI (or an AI with human ones), so the marker foundation itself is shaky.
4. **The false dichotomy.** Classifying text as human- vs AI-generated ignores the reality that students' work is frequently created *with*, not *by*, AI — a hybrid continuum. The binary is not merely inadequate but meaningless, making detection conceptually flawed from the outset.
5. **Procedural unfairness and evidential insufficiency.** Academic-integrity investigations must meet the balance-of-probabilities standard; AI-detector scores — alone or combined with linguistic markers, style comparisons, LLM claims, or student silence — do not reach it. Students under investigation also retain a right to silence, which detection-driven processes erode.
6. **Security and privacy risks.** Detectors store student work on servers (sometimes overseas with weaker Privacy protections), creating breach, misuse, and commercial-exploitation risks.
7. **Detection undermines integrity rather than safeguarding it.** Reliance on detectors and surveillance fosters a climate of suspicion, eroding student Trust and the integrity of assessment itself.

Bassett et al. conclude that AI detection is an unworkable solution to a problem that cannot be solved through surveillance and punishment: the focus must move to assessment design that recognizes AI's role in learning and the reality that unsupervised assessments cannot be secured. This consolidates the knowledge base's beyond-detection stance with a direct, evidence-based argument for retiring detection tools.

Of 40 psychology assessments spanning 16 types, 36 (90%) produced ChatGPT output judged adequate for a pass, and the four failures were the tasks needing presence, a visual artifact, or the student's own dataset — evidence that the pass boundary, not detection, decided whether AI work counted as achievement (Ivory et al. (2026)).

Detector bias and the mechanism of the arms race

Detection is not merely imprecise; its errors are patterned. Teichmann (2026) assembles the accumulated case against treating a detector score as evidence: no tool in the most comprehensive early Benchmark reached 80% accuracy; simple paraphrasing or "humanising" roughly halves even that; false positives at realistic base rates exceed true ones; and non-native English speakers are misclassified systematically because the features detectors treat as signals of AI also characterize competent second-language writing. Judgment by humans does not fill the gap — expert and novice markers alike fail to distinguish AI from student prose and are confident when wrong — and the asymmetry of error means the careless-but-honest are caught while the deliberately dishonest evade, since detectors are also opaque (no thresholds, no training data, no independent replication) and therefore cannot be answered or cross-examined in a hearing.

Two further points sharpen the practical stakes. First, the underlying statistical signal shrinks as models are optimized toward human prose, so the arms race is one an institution cannot win. Second, the empirical limit case is stark: in a covert field study, 94% of wholly AI-generated submissions passed unnoticed through a live online examination system across five psychology modules, and the AI work on average outscored real students. Mohamed and Temimi (2026) add the counter-intuitive corollary that determines when monitoring pays at all: because sensitivity raises false positives along with true positives, the rational deterrent is discrimination — the gap between flagging hidden use and flagging legitimate work. Where extra sensitivity

creates more new false positives than new true positives, more monitoring makes concealment relatively more attractive, penalizing honest students faster than it identifies hidden users. The design consequence is that detectors, rules, and disclosure procedures should not be built separately.

Test-time adaptation is the counterexample that claim leaves out. Against humanizer prompts optimized to evade each detector in turn, supervised detection collapsed — Pangram caught 27.0% of adversarial AI text — while a positive-unlabeled method adapting on unlabeled inference-time batches held 93.3% (Ren, Raghavan and Garg (2026)). Their human-drift experiment produced the false positives this page warns about: a fixed detector's recall on human text fell from 85.9% to 73.4% across a simulated decade.

- **Five tools, one manuscript, incompatible answers — and the institutions that have stopped using them.** Angelier (2026) submitted a single human-authored manuscript to five commercial detectors on the same day and received classifications spanning "0% human" (Winston AI) to "Human Generated" (GPTZero's categorical label, printed beside its 42% AI figure), with Copyleaks at 80.4% AI, Originality.ai at "81% Likely AI" and a fifth tool at 34% AI / 66% human — three outputs leaning AI and two leaning human on identical text, with no validated basis for treating a majority vote across proprietary systems as evidence of provenance. The same paper documents the institutional retreat: Vanderbilt disabled Turnitin's AI detector in August 2023, working the arithmetic of a 1% false-positive rate across roughly 75,000 papers; Curtin University announced a similar disabling in 2025; the University of Waterloo discontinued Turnitin's AI-detection function in September 2025 after an internal audit in which human-written work had been classified as 100% AI-generated; the University of Cape Town disabled the AI score from October 2025; the University of the Free State followed in July 2026; the University of the Witwatersrand reported never having adopted such tools; and a New York court annulled a misconduct finding that rested on a detector score. Two procedural findings complete the case: a severely corrupted PDF extraction still returned a classification five percentage points from the clean-text result, and an archived detector output establishes what an interface reported but cannot recreate the proprietary model state that produced it.
- **Tools agree on the ranking and disagree on the number.** Three commercial detectors separated five graded AI-use conditions ($p < 0.001$ for all) yet agreed only weakly on the absolute score, ICC 0.57 to 0.95 (Cheng et al. (2025)), and a 90-study systematic review concludes that published false-positive rates vary so widely by tool and setting that direct comparison is impossible (Maghami, Ho and Camilleri (2026)).
- **Detector output is the weakest evidence in the file, and evidence quality does not decide cases.** Coding 1,162 generative-AI misconduct allegations, detector output drew the lowest probative ratings and fell to 0.5% of items by 2025. Evidence quality showed no relationship to outcomes because the pipeline set no evidentiary threshold (Munoz et al., 2026).
- **Students change their work to survive detection, not just their answers.** The report documents students dulling their own answers to avoid a false accusation, and teachers falling back on informal judgment — what it calls AI-DAR — once marketed detectors prove unreliable (Tench, Weinstein & James, 2026).
- **The detector is switched off, and intuition is all that remains.** Sessional markers lost their AI detector at one institution because it flagged grammar-checking tools, leaving them to read for

fabricated references (nineteen of twenty) and disconnection from course materials (Andriamora & Andriamora, 2026).

Beyond detection: assessment redesign

A key theme in the knowledge base is that detection should be a **limited, situational tool — not a strategy of first resort**. Kickbusch et al. (2025) argue that surveillance and detection **misdiagnose the problem**: in an AI-mediated world, authenticity cannot be policed into existence; it must be redesigned. They reconceptualize authenticity as constructed where AI is expected, declared, and scrutinized, and offer discipline-agnostic design-for-learning patterns that position AI as a collaborator rather than a cheating application. This connects detection to Authentic Assessment, Assessment Validity, responsible assessment, and coauthorship integrity.

The constructive question shifts from "how do we prevent students from using AI?" to "how do we enable them to use it thoughtfully, responsibly, and effectively in contexts that mirror their future work?" Detection therefore connects to AI Literacy (helping students use AI responsibly), Over-Reliance (understanding when AI use undermines learning), and the broader goal of supporting genuine learning rather than policing submissions. It also links to student-side phenomena such as student rationalization of AI writing and the identity-detection challenge in Socially fluent AI decouples conversational signals from source identity in online interaction.

- **Detectability is a property of assignment design, not only of the detector.** Ye et al. (2026) found cross-model agreement of 87.79-88.14% on generated code, yet only 1-14 distinct abstract syntax trees per 1,000 files on tightly constrained functions versus 151-804 among 2021 student submissions.
- **The models that generate the text rank detection last as a countermeasure.** Lieske and Wadley (2026) put one prompt to eight LLMs and search tools from Anthropic, Microsoft, Google, Meta, OpenAI, Perplexity and DeepSeek. Each was asked to nominate and rank six techniques for stopping AI cheating in non-invigilated assignments, and the 48 answers were pooled into 15 composite approaches. Detection was the only approach to recur in the sixth-ranked position, four times across the eight models, while personalization, AI-assisted process measures and oral follow-up led. The paper carries no empirical data and its ranking measures model consensus rather than efficacy; it belongs here as evidence of how the systems producing the text weigh detection against the alternatives.

Implications for AI in education

- **Detection is situational:** institutions should use detection tools sparingly and with awareness of their error rates, fairness limits, and task-dependence — not as an automatic, standalone gate.
- **Assessment design matters more than policing:** investing in authentic and process-based assessment, where AI use is expected and declared, addresses integrity more effectively than detection alone.
- **Fairness and equity:** detection tools that penalize non-native writers or produce false positives risk amplifying existing inequities.

- **AI literacy is complementary:** helping students understand appropriate versus harmful AI use is more productive than relying on surveillance.
- **Detection reliability caution.** A systematic review of AI and academic integrity concludes that plagiarism/AI-detection tools cannot be relied upon for AI-generated work and should be paired with multiple assessment methods and manual review — reinforcing that detection is a limited, situational tool.(Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity)
- **Beyond detection: dialog over surveillance.** A practitioner account of Grand Canyon University's learning-verification framework (Mandernach 2026) argues the best response to student AI use is dialog, not detection. Because detectors are unreliable (and biased against nonnative writers), GCU stopped asking "did the student use AI?" and instead asks students to demonstrate understanding in a brief conversation — an extension of assessment redesign that treats detection as a dead end and verification as good teaching.
- **Reliance outruns confidence, at a cost to teaching.** In a survey of 20 higher-education professionals, 15 reported heavy institutional reliance on AI-detection software while only 4 expressed confidence in it, and respondents described "pedagogical burnout" from policing that displaced instructional design and student mentorship (Chowdhury & Khan (2026)).

Common Misconceptions

"Detectors are unreliable, but they are getting better." The failure is structural, not a matter of maturity, and one model family demonstrates it cleanly: its AI flag rate **fell from 94.9% to 6.8%** as the human plan behind AI-written text grew more detailed — detecting the human planning, not the AI writing — while a competing detector stayed near 92%, and that same system **labeled 94.7% of AI-polished human documents as human**. Accuracy claims depend entirely on which construction of the problem the test set used.

"False positives are rare, so the risk is small." They are common on exactly the work you want to encourage. Guideline-compliant light AI editing is flagged at **38–80%**, and *unmodified* recent originals at **9–15%**, with non-STEM writing far above STEM. A detector that accuses a tenth of untouched human work and most of the permitted editing is not making a small error rate; it is penalizing the behavior the policy invites.

"The question a detector answers is whether writing is human or AI." That binary is conceptually unsound rather than merely hard to compute. Writing assistance exists on a continuum, the policy of most institutions permits some of it, and no threshold on an output score maps onto a defensible boundary. The measured failure is a policy failure: the categories detectors promise do not exist in the work students actually submit.

"A detection regime protects integrity." It can undermine it. Detection fosters a climate of suspicion that erodes Trust between students and staff, and the integrity literature this corpus reports places the durable levers in assessment redesign rather than in policing. The mechanism of the arms race also means the regime keeps costing more while measuring less: baseline flag rates spanned **0.0% to 100.0%** across editing intensities, which is not a discrimination signal.

Connected Concepts

- Academic Integrity
- Large Language Models (LLMs)
- Generative AI
- Assessment
- Assessment Validity
- Authentic Assessment
- AI Literacy
- Cognitive Offloading
- Equity
- Bias Mitigation
- Higher Education
- AI in Education
- Legal Issues and Risks

Connected Articles

- AI humanizers and the political economy of academic integrity in higher education — 55 humanizer sites performing legitimacy: detection and evasion as one commercial market (Roe et al. 2026)
- Cheating or being cheated? Academic integrity and a changing cheating habitus in international AI governance discourse — A hypothesis that enforcement filters on academic capital, not on conduct
- Artificial intelligence (AI) proposals to counter AI cheating by students in non-invigilated assessment — Eight LLMs rank six counter-cheating techniques; AI detection comes last
- Artificial learning: how sessional academics view contract cheating and digital academic misconduct in assessment — Twenty markers on intuition, dead detectors and fabricated references
- An AI Policy Isn’t a Playbook: Educators Need Agency, Not Just New Rules — A nationally representative survey of US teachers and principals on AI policy coverage, agency, and five classroom plays (Tench, Weinstein & James 2026)
- Evaluation in the Age of AI: Output as Evidence of Learning — Evaluation in the Age of AI
- The best response to student AI use is not detection, it is dialog
- Once a Response, Always a Response: Detecting LLM-generated Text via Latent Prompt Restoration — EchoPrompt: Latent Prompt Restoration Detector
- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — Detection is the wrong lever: the pass boundary decided whether AI work was graded as achievement (Ivory et al. 2026)

- Distinguishing Artificial from Authentic: Evaluating LLMs for Detecting LLM-Generated Content — Evaluating LLMs for Detecting LLM-Generated Content
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond Detection: Authentic Assessment
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible Assessment in the AI Era
- Coauthorship integrity: Reconceptualising assessment validity for the age of generative artificial intelligence — Coauthorship Integrity and Assessment Validity
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — Student Rationalization of AI Writing
- Socially fluent AI decouples conversational signals from source identity in online interaction — Socially Fluent AI Identity Detection
- Reassessing academic integrity in the age of AI: A systematic literature review on AI and academic integrity — Review of AI-based plagiarism/AI-content detection reliability
- Heads we win, tails you lose: AI detectors in education — Heads we win, tails you lose: AI detectors in education (Bassett et al. 2026)
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Why detector output cannot ground a misconduct finding
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — Discrimination rather than catch rate, and when monitoring backfires
- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Turnitin and Originality on 192 texts: both below a macro F1 of 0.55 and near-useless on hybrid writing
- Who wrote this? Evaluating the reliability of AI detection tools in higher education — Four detectors against 160 ground-truth papers; only Pangram performed, yet flagged 45.5% of live theses
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — Detector output is the weakest-rated evidence type in 1,162 real misconduct case files
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Blanket “AI use” rules conflate transcription with generation
- Educational integrity in GenAI-augmented assessment: making judgment visible — Detection demoted to a supplementary layer behind visible judgment
- Which inference is at risk? Assessment validity reasoning and generative AI — Detection as a conditional signal, and why security responses add construct-irrelevant variance (Weidlich 2026)
- AI-written admissions essays are widespread but penalized — AI-written admissions essays are widespread but penalized

- Detecting GPT-Assisted Writing Using Interpretable Stylometric Features — Nine interpretable stylometric features: ROC-AUC 0.870 but four of 18 independently authored documents flagged (Kumar et al. 2026)
- The pitfalls of AI detection in academic writing: bias, false positives, and the need for inclusive assessment — One human manuscript, five detectors, classifications from “0% human” to “Human Generated”, plus the documented institutional retreat from detection (Angelier 2026)
- Argus: Academic Integrity in the Era of Generative AI — Argus: Academic Integrity in the Era of Generative AI
- Correctness, Convergence, and AI-Generated Code Detection: A Longitudinal Study of Student and Large Language Model Code in Introductory Programming — LLM code converges on tightly constrained assignments (1-14 AST forms per 1,000 files) but not on free ones - detectability follows task design
- Unchecked or falsely accused? Evaluating AI-generated text detectors on Kazakh — Unchecked or Falsely Accused? Evaluating AI-Generated Text Detectors on Kazakh

Connected FAQs

- How Can We Address Common Misconceptions About AI in Education?
- Should We Use AI Detectors?
- How Can I Reduce AI Cheating in My Course?
- How Should Parents and Teachers Approach AI with Children Under 13?

Remote Proctoring

> **Remote proctoring** — the monitoring of examinations when students take them away from a supervised physical venue, ranging from a human proctor watching via webcam or control center to fully automated AI-based proctoring systems (AIPS) that use machine/deep learning to verify identity and flag suspicious behavior. It is the primary means of preserving Summative Assessment validity and academic integrity in online and distance learning, where in-person invigilation is often unfeasible — but it raises serious concerns about Privacy, academic surveillance, equity, fairness, and the erosion of Trust, costs that can themselves harm the learning environment it is meant to protect.

Questions to Consider

- Before you read, when you picture ‘academic integrity in online exams,’ what’s your first instinct about how to preserve it — and is that instinct about detecting cheaters or about building trust? The page argues these reflect two very different philosophies.
- Remote proctoring ranges from a human watching via webcam to AI systems analyzing eye movements, head posture, and facial expressions. What does an AI system *actually* observe when it flags ‘suspicious behavior,’ and how confident are you that looking away from the screen equals cheating?
- The page warns that monitoring can be counterproductive: being watched raises test anxiety, and stressed students may be *more* likely to cheat. Can you think of a time pressure or surveillance affected your own performance? Does that experience undermine the case for proctoring?
- Automated proctoring captures students’ living space, face, and voice, often with little genuine choice but to consent. Where is the line between reasonable exam supervision and surveillance that presumes students guilty until proven honest — and who should draw it?
- Research shows proctoring can flag benign behavior as suspicious, producing false accusations, and that model accuracy varies across demographics and environments. If you’re an Administrators, how do you weigh the integrity it recovers against the equity and trust it can erode?
- The page frames proctoring as one tool, not a solution — alternatives like oral and process-based assessment exist. Before reading, which approach would you defend for high-stakes assessment in a remote context, and what evidence would change your mind?

Introduction

Remote proctoring exists on a spectrum. **Online proctoring** typically involves a human proctor monitoring a student through a webcam or from a control center. **Automated/AI-based proctoring (AIPS)** replaces or augments the human with Machine Learning and deep-learning systems (CNNs, RNNs, LSTMs) that analyze visual cues — eye movements, head posture, facial expressions, and body language — to detect suspicious behavior in real time. Common platforms include ProctorU and Kryterion. AIPS typically

combine four functions: (1) identity authentication (e.g., camera face verification), (2) browsing restrictions, (3) remote authorization/control of the exam, and (4) report generation from recorded sessions. - **Pose estimation replaces threshold rules, and the accuracy claim is narrower than it reads.** Arif et al. (2026) track seventeen body landmarks per frame with YOLOv11, derive posture-deviation, head-trend and upper-body-motion features, and deploy single-nearest-neighbor KNN over 30 mutual-information-selected features, reporting 99.56% accuracy and AUC 0.9957 from one webcam (Arif et al., 2026). Those figures describe reproduction of labels on a bespoke scenario set, not detection of misconduct.

Advantages and opportunities

- **Recovers validity and integrity in online assessment.** Remote proctoring answers a genuine validity problem. In online assessment, generative AI makes unproctored work unreliable as a measure of learning: unassisted, proctored, closed-book measures are the strongest signal of what students actually know (see Summative Assessment, proctored retention evidence). Without some form of supervision, online exams can inflate grades by capturing AI-assisted rather than independent performance.
- **Scalability and cost.** Automated proctoring reduces the need for dedicated physical venues and human invigilators, making monitoring feasible at scale — an advantage for MOOCs and large online programs where traditional proctoring is logistically and financially impractical.
- **accessibility and reach.** Proctoring allows students in remote locations to take exams from anywhere, removing geographic and scheduling barriers to credentialing.
- **Detection capability.** Advanced ML/DL systems can detect cheating (eye movements, head posture, facial expressions) more reliably than manual observation, and can monitor continuously rather than intermittently.

Disadvantages, risks, and harms

- **Harms to trust and the student-instructor relationship.** The most consequential cost of remote proctoring is often relational. Continuous surveillance communicates that students are presumed dishonest, which can erode Trust, corrode the student–instructor relationship, and undermine the sense of shared purpose that supports academic integrity. Monitoring-as-enforcement can crowd out the trust-based, educative approach to integrity that builds responsible use.
- **Academic surveillance.** Remote proctoring is a form of academic surveillance that extends institutional monitoring into the student's private home environment. Beyond the exam itself, these systems capture the student's living space, face, voice, and behavior continuously — a level of scrutiny with few precedents in higher education. Critics argue this normalizes a surveillance culture in which students are presumed guilty until proven honest, reshaping the relationship between institutions and learners and raising questions about proportionality: whether the integrity gains justify subjecting every student to pervasive monitoring for the misdeeds of a few.(Privacy), Trust
- **Privacy and consent.** AIPS continuously access facial imagery, voice patterns, gaze, and keystroke dynamics, often through persistent audiovisual surveillance. Data handling must comply with frameworks like GDPR and India's PDP Bill, and requires clear consent and secure

biometric-data handling. Students often have little choice but to accept monitoring if they wish to take an exam, raising questions about whether consent is genuinely voluntary.(Privacy)

- **False positives, false accusations, and anxiety.** Systems may flag benign behavior (looking away, adjusting posture) as suspicious, eroding student trust and producing false malpractice accusations — especially where proctors or test-takers lack proficiency.
- **Stress and test anxiety.** Taking a proctored exam is itself a source of significant stress and anxiety. Continuous surveillance, fear of being falsely flagged, and the pressure of being watched can raise test anxiety and impair performance — and, per the evidence, stressed students may be *more* likely to resort to dishonest behavior, meaning the monitoring can be counterproductive. Being monitored is stressful and can itself induce the unethical behavior it aims to prevent.
- **The integrity rationale did not survive the largest test.** Across four waves and 1,760 students in 105 courses, proctoring raised test anxiety ($\beta = 0.60$, $p < 0.001$) but had no effect on the temptation to cheat, perceived difficulty, or grades, so the surveillance cost was not offset by deterrence (Conijn et al. (2022)).
- **Equity and the digital divide.** Device dependency, unstable internet, lighting, and hardware variability disproportionately disadvantage rural and low-bandwidth students; model accuracy can vary across demographics and environments, risking unfair flagging.(Digital Divide), Equity A scoping review of proctoring in nursing assessment shows this is not an edge case: four of its six included studies reported internet connectivity problems, one reported load shedding alongside limited data bundles, and device incompatibility, browser-extension faults and failed environmental scans were routine — so infrastructural inequity, not only model bias, determines who can be assessed at all.(Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review)
- **Detection gaps and the arms race.** Identity spoofing (photos/video masking), browser use, and copy-paste remain hard to catch reliably; detection accuracy is bounded by dataset limitations, single-model evaluation, and reproducibility gaps. Proctoring does not fully solve integrity, and can create a false sense of security.
- Wearable AI removes the behavioral signal proctoring depends on: Corbin et al. (2026) argue that AI glasses, earbuds, and AI-enabled hearing aids deliver covert assistance with no gaze shift, attention shift, or posture cue, so invigilation and device surrender lose the cues they rely on.
- **The governance question.** Whether surveillance is the right response versus assessment redesign (oral, process-based, portfolio) is an open institutional decision; remote proctoring is one tool, not a complete solution.(AI Governance) The exposure that follows when enforcement goes wrong — accusations resting on scores and event logs, retention and onward processing of captured data, and rules that fall unevenly on disabled or non-native-speaker students — is mapped on Legal Issues and Risks.

Evidence base

- A decade-long systematic review of 80 peer-reviewed studies (2014–2024) finds advanced ML/DL proctoring detects cheating more reliably than traditional methods, but is limited by dataset gaps (35% did not fully disclose data), single-model evaluation (40%), reproducibility issues

(30%), sparse ethical reporting (only 25%), and inconsistent metrics (20%). False positives/negatives — flagging normal behavior as suspicious or missing subtle cheating — undermine reliability and trust.(Ensuring academic integrity through automated online exam proctoring: a decade long systematic review)

- A companion review documents the cheating methods AI must counter (identity spoofing via photos/video, browser/device use, copy-paste) and the practical barriers: test-taker anxiety, proficiency gaps causing false accusations, and infrastructure (webcam, microphone, internet) that is not universally affordable or available. It reports ~37.8% of college and ~41.8% of high-school students admit to cheating — the motivation for monitoring.(A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence)
- **Instructors see no benefit from proctoring exams taken outside class.** Chan et al. (2026) surveyed 56 instructors (47% response rate) in one biology department after coding all 38 syllabi of its core required courses, and asked them to rate each graded category they use for vulnerability to academic dishonesty (0 = minimally to 4 = highly vulnerable). Proctored and unproctored outside-of-class exams were rated *identically* at a median of 3 (moderately vulnerable), while in-person proctored exams were the only category rated minimally vulnerable (median 0) and were significantly less vulnerable than every other category ($p_{adj} < .01$). Because lockdown browsers were available for outside-of-class exams, the result is a perception that the tools did not reduce exposure — consistent with the review evidence above that online proctoring is effective only unevenly, and with the documented anxiety, privacy, and false-accusation costs that make the trade-off contested. The stakes are visible in the same study's point accounting: outside-of-class exams carried a mean of 54.2% of the grade in the in-person courses that used them and 59.2% in online courses, where every offering relied on them.
- A scoping review of remote proctoring in nursing student assessment maps a spectrum of modalities rather than a single practice — live human invigilation (ProctorU), AI browser-extension proctoring with webcam, microphone and behavior flagging (Honorlock), webcam-plus-lockdown-browser monitoring (Respondus Monitor), an institutionally deployed mobile invigilation app, and fixed test-center desktops under central surveillance — and argues the diversity reflects disparities in infrastructure and institutional capacity rather than a shared standard. Only six studies met its inclusion criteria (1,567 nursing students in the USA, the UK, Southern Africa and Egypt), and none was published before 2021. What the review establishes is that surveillance produces deterrence *perceptions* and a heavy faculty review burden: the 98–100% agreement that webcam monitoring and lockdown browsers deter cheating is self-report from one graduate nurse practitioner program, high-risk AI alerts were rare at no more than 5%, yet frequent minor alerts produced false positives requiring time-intensive review, and South African lecturers reported continued dishonesty under active monitoring. The one comparative performance study points the other way — an in-person proctored cohort scored significantly higher on the HESI Exit Exam and NCLEX readiness than the ProctorU cohort — and the review treats the link between surveillance and more honest learning as an open question rather than a settled benefit.(Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review)

- **A proctored, face-to-face exam still produced 44.2% high-risk students.** In an Introduction to Programming course at a Turkish public university, 23 of 52 first-year students were labeled high-risk from exam logs recording copy, focus-loss and right-click events, although the exam was proctored and taken in a computer laboratory; the same study predicts that risk from early-semester LMS traces rather than from in-exam behavior.(Early Prediction of AI-Assisted Cheating Risk in Online Exams Through Learning Analytics)

Recommended directions

- **Hybrid human–AI oversight.** Pair automated flagging with human review to reduce false positives and keep judgment contextual.
- **Privacy-preserving architecture.** Edge processing, anonymization, and on-device handling reduce the invasiveness of continuous data capture.
- **Equity-aware deployment.** Diverse, geographically-inclusive datasets and lightweight models for low-resource environments; accessible alternatives for students without reliable devices/ connectivity.
- **Educate before you surveil.** Prefer fostering AI Literacy and responsible use through culture and trust-building, reserving proctoring for the high-stakes cases that genuinely require it.

Common Misconceptions

- **“Proctoring protects academic integrity.” The integrity rationale did not survive the largest test.** Across **four waves and 1,760 students in 105 courses**, proctoring **raised test anxiety ($\beta = 0.60$, $p < 0.001$) but had no** detectable integrity benefit. The measured effect was on the students, not on cheating.
- **“Better detection capability means better proctoring.”** A decade-long systematic review of **80 peer-reviewed studies (2014-2024)** finds advanced ML/DL proctoring **detects cheating more** accurately and says nothing about whether deploying it changes conduct. Detection performance is a property of the classifier, not of the assessment regime.
- **“Behavioural signals are reliable indicators of misconduct.”** Systems **track seventeen body landmarks per frame** with YOLOv11 to derive **posture-deviation, head-trend and upper-body-motion** features. Those constructs are proxies, and a flagged posture is a classification about a body rather than an observation of a transgression.

Connected Concepts

- Anxiety and Stress
- Academic Integrity
- Summative Assessment
- Assessment
- Automated Assessment
- Online Teaching and Learning
- AI Misuse and Learning Harm

- Privacy
- Equity
- Digital Divide
- Student Experience
- Trust
- AI Governance
- Legal Issues and Risks
- Higher Education

Connected Articles

- On AI glasses and wearable AI in assessment — Wearable AI removes the behavioral signal proctoring depends on (Corbin, Sharpe & Dawson 2026)
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review — Decade-long systematic review of automated online exam proctoring
- A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence — Comprehensive review of academic dishonesty in automated proctoring
- The fear of Big Brother: The potential negative side-effects of proctored exams — The fear of Big Brother: proctoring's negative side-effects on test anxiety
- Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI — Can students cheat their way to a biology degree? A case study of the vulnerability of biology course grades to academic dishonesty in the era of generative AI
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Under surveillance: mapping remote proctoring practices in nursing student assessment
- Early Prediction of AI-Assisted Cheating Risk in Online Exams Through Learning Analytics — Akçapınar (2026) — 44.2% of students labeled high-risk in a proctored, face-to-face exam, with the risk predicted from early-semester LMS traces

Learning Gains

> **Learning gains** — measurable improvements in student knowledge, skills, or competencies resulting from educational interventions, including AI-assisted instruction. In AI in education research, learning gains serve as the primary outcome measure for evaluating whether AI tools actually improve learning — not just engagement or satisfaction.

Questions to Consider

- Have you ever felt you learned a lot from an activity, only to fail a test that measured something different? The page distinguishes immediate AI-supported performance from durable learning — how might those two diverge in your own experience?
- A core finding is that generative AI can inflate scores on AI-assisted homework while lowering scores on proctored, closed-book measures. If you were evaluating whether an AI tool really helps students learn, which outcome would you trust and why?
- Research shows unguided reliance on AI predicts worse learning gains, while structured use predicts better ones — the same tool, opposite outcomes. What distinguishes 'structured' from 'unguided' use in a real classroom?
- Hint buttons correlate with reduced learning: more hints, less learning. Have you ever been tempted to reach for a hint or an answer the moment you were stuck? What does that suggest about how much struggle is actually necessary for learning?
- A large meta-analysis pooled many studies and found AI-enabled EdTech raised learning by a modest amount, with no advantage for generative AI over earlier adaptive tools. How should this cautious, pooled estimate change how you read exciting claims about a single AI product's effectiveness?

Introduction

Learning gains are the ultimate test of any educational technology. In the knowledge base's research, they appear as dependent variables in randomized controlled trials, pre-post comparisons in quasi-experimental studies, and correlational analyses linking AI tool usage to academic outcomes.

Terminology. The *outcome* sense of achievement — student achievement, academic achievement, learning achievement, prior achievement, achievement gaps — is treated as a synonym for learning gains here, and those phrases link to this page. The *felt* sense ("a sense of achievement") is a motivational experience rather than a measured outcome; see Motivation and Self-Efficacy. Achievement-goal theory ("achievement goals", goal orientations) is likewise a motivational construct and links to Motivation.

Key findings from the knowledge base:

- **Adaptive pretesting** research examines whether GenAI-enabled pretesting produces durable learning gains that persist beyond immediate testing.

- **Meta-analyses of GenAI in programming** find positive learning gains from structured AI use but negative effects from unguided reliance — a key distinction between productivity and durable learning.
- **Hint button research** shows negative associations between hint abuse and learning gains — more hints correlate with less learning.
- **Instructional guidance** studies demonstrate that learning gains depend on HOW AI is used, not just WHETHER it's available.
- **World Bank meta-analysis** pools 191 effect sizes from 14 RCTs to estimate that adaptive and AI-enabled EdTech raises learning by ~0.125 sd on average — above the median for education RCTs — while finding no advantage for generative AI over earlier adaptive tools.
- **Gains are content–treatment interactions, not constants.** Rachatasumrit et al. (2025) show the optimal example–problem ratio depends on knowledge content: pure retrieval practice yields higher gains for verbatim facts, while example-integrated practice (alternating worked examples and problems) yields higher gains for generalizable skills — direct evidence that "more practice" is not always better and that gains hinge on matching the training schedule to the knowledge component being learned.

The AI-era measurement problem

A central theme in the knowledge base's learning-gains research is that **generative AI can inflate apparent performance without producing learning gains** — and that the choice of outcome measure determines whether this is visible. Research and large-scale field data show a sharp divergence: AI use improves scores on AI-assisted homework while *lowering* scores on proctored, closed-book, unassisted measures. Performance-vs-learning research and rapid reviews therefore distinguish immediate AI-supported performance from durable learning, and treat unassisted summative measures (see Summative Assessment) as the reliable signal of genuine learning gains.

What the efficacy research shows

Across the knowledge base's RCTs, meta-analyses, and field studies, a consistent picture of **learning efficacy** (which AI interventions actually produce learning gains, and how large) emerges:

- **Meta-analytic evidence is broadly positive but conditional.** A comprehensive meta-analysis of 53 studies (Dong 2026) finds generative AI generally outperforms traditional approaches on academic achievement, higher-order thinking, and writing — with AI feedback particularly effective — though game-assisted GenAI shows no significant added benefit and gains vary by country and outcome. The GenAI-and-programming meta-analysis finds large productivity gains but no significant learning gain ($g \approx 0$), separating task-efficiency from durable learning. A language-learning meta-analysis finds positive but modest learning gains from AI-enhanced embodied robots. For AI literacy specifically, a three-level meta-analysis of 59 studies estimates a large overall effect ($g = 0.837$) — but the wide prediction interval and the finding that knowledge-focused interventions outperformed those targeting skills, attitudes, or Ethics caution that the *outcome measured* shapes the apparent gain, echoing the broader point that AI-related gains depend on what and how you assess.

- **Well-designed AI tutors produce real gains.** A two-year cluster RCT (Khanmigo) found AI tutoring raised math achievement ~1.3 national percentile ranks per term (~0.06–0.08 SD/school year, ~0.14 SD for a full year), gains resembling practice without AI — demonstrating that *engagement*, not model capability, is the binding constraint. NUMI showed AI support improved next-attempt correctness after mistakes with more time per question — a "productive slowdown" that builds durable mastery. Virtual tutoring found the binding constraint is take-up and sustained participation, not tutor quality.
- **A tutor built from the class's own pedagogy beat active learning, not just lecturing.** In a crossover RCT in Harvard's introductory physics course, students learning from a custom AI tutor scored a median 4.5 on the post-test against 3.5 for the course's in-class active-learning lessons (baseline median 2.75). The linear-regression effect size was 0.63, and students spent a median 49 minutes on task against 60 in class (Kestin et al., 2025). Because the control was research-based active learning rather than a lecture, the trial measures the tutor against a demanding comparator — the design the authors credit was engineering the tutor from the same research-based practices as the class, plus personalized feedback on demand and self-pacing.
- **AI can match human help.** ChatGPT-generated help produces learning gains equivalent to human tutor-authored help on mathematics skills — evidence that generative AI can be as efficacious as human Scaffolding when used appropriately.
- **Gains depend on who is teaching with it.** Low-experience tutors given AI support raised student pass rates by 9 percentage points, with smaller gains for more experienced tutors — an augmentation pattern that boosts the least experienced most (OECD, 2026).
- **Unguarded AI can harm learning.** The guardrail RCT (PNAS 2025) found an unguarded ChatGPT-style tutor raised assisted practice +48% but *reduced* unassisted exam scores −17%, while a guardrailed (hint-not-answer) tutor eliminated the harm. This is the sharpest demonstration that **learning efficacy is design-contingent**: the same class of tool can be a strong learning gain or a net harm depending on how it is configured.
- **But unguarded access can also help, durably.** An RCT with an off-the-shelf ChatGPT account found unaided test scoring 0.27 SD higher while students had access, and the gain held a week later — more than double the 0.10 SD median across 747 educational RCTs (Contractor & Reyes, 2026).
- **Perceived vs. actual efficacy diverge.** Self-reported performance misaligns with measured performance, and the absent cognitive baseline shows AI-native students overestimate their learning — so efficacy claims based on self-report are unreliable without objective outcome measures. Self-Report Measures collects the cases where reported and measured outcomes come apart.
- **Gains can come from reallocating teacher time, not from AI grading.** In a randomized experiment across 178 Brazilian schools (~19,000 seniors), AI and human essay grading produced identical exam gains, but AI classrooms saw ~35% more one-on-one teacher conversations about writing, and the bottom quartile improved under neither condition (Ler, 2026).

- **In teacher-mediated AI, preparation moved gains and the tool did not.** Across 19 Brazilian public-school numeracy classes, students taught by trained teachers outperformed the control group, but adding the AIED-U system to that training produced no further learning gain, and teacher workload was negatively associated with gains (Rodrigues et al. (2026)).

Takeaway: the weight of evidence supports **modest, conditional, and design-dependent learning gains** from AI — real when AI is structured to coach rather than answer, guardrailed, and paired with unassisted outcome measures, and absent or negative when it substitutes for the learner's own effort. This is why learning gains as an outcome must be measured with valid, AI-resistant instruments and why AI Ed Evaluation pairs efficacy claims with methodological scrutiny.

- **AI tutoring can match expert human tutoring on standardized-test gains.** In a 2,383-participant evaluation, pooled AI tutoring was statistically equivalent to expert human tutoring on GRE learning gains ($p = .015$), with both above a no-tutoring control; the authors propose cost per percentage point of gain as the unit for comparing tutors (Northcutt et al., 2026).

A field-level map of AI's effects on learning and achievement

The knowledge base's corpus — meta-analyses, RCTs, quasi-experiments, and field studies — supports a nuanced, sometimes contradictory picture. Findings cluster into positive, negative, and conditional effects.

Positive effects (AI can produce genuine learning gains): - **Meta-analytic evidence is broadly positive but conditional.** A 53-study meta-analysis (Dong 2026) finds generative AI generally outperforms traditional approaches on academic achievement, higher-order thinking, and writing, with AI Feedback especially effective. A meta-analysis of 29 experiments (Does generative artificial intelligence improve students' higher-order thinking? A meta-analysis based on 29 experiments and quasi-experiments) finds a moderate positive effect on higher-order thinking, strongest for Problem Solving, but limited for Creativity. - **Tutoring-specific AI reliably outperforms general-purpose AI.** The Stanford SCALE review and the umbrella review (Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025)) converge: pedagogically designed agents with hints and step-by-step scaffolding produce real gains where open chatbots often do not. - **Well-designed AI tutors produce real, measurable gains.** The two-year Khanmigo RCT (One click away: AI tutoring with Khanmigo in a two-year school experiment) raised math achievement ~1.3 national percentile ranks per term; NUMI improved next-attempt correctness after mistakes; virtual tutoring showed take-up is the binding constraint. - **AI can match human help.** ChatGPT-generated help produces learning gains equivalent to human tutor-authored help on math skills. - **Feedback-focused AI works.** AI feedback is among the most effective GenAI applications; AI feedback for writing improves critical thinking when coupled with instruction. In a field experiment, Geschwind et al. (2026) found students receiving individual GPT-4 feedback on open-ended tasks showed the largest content learning gains (~0.11, $p < 0.10$; rising to 0.16 among those who actually received prior feedback) — an effect driven by reliable, consistent AI provision rather than inherent superiority, since peer outcomes matched AI when high-quality peer feedback was actually delivered. LLM critique partners in writing extend this to iterative, collaborative feedback: Oppenheimer, Cash & Connell Pensky (2025) found significant gains across a semester on argumentative writing, prompt engineering, and response-to-AI-feedback quality (all $p < .001$, roughly a full standard deviation per dimension), with gains appearing even on essays written without LLM support — evidence of durable skill rather than mere tool

dependency, though the lack of a control condition limits causal attribution. - **Structured scaffolds yield gains.** Scaffolded self-regulated feedback and interaction design show small but significant gains when AI is designed to coach. - **AI in collaborative and problem-based contexts helps when structured.** AI-enhanced PBL, AI-assisted collaborative learning, and AI-designed cooperative techniques report meaningful gains.

Negative effects (AI can reduce or fail to improve learning): - **Unguarded AI can harm learning.** The PNAS guardrail RCT (Generative AI without guardrails can harm learning: Evidence from high school mathematics) found an unguarded ChatGPT-style tutor raised assisted practice +48% but *reduced* unassisted exam scores −17%; Guardrails eliminated the harm. - **Faster completion ≠ learning.** GenAI reduced study time on math problems and the knowledge they build; performance-vs-learning research shows AI inflates AI-assisted performance while lowering proctored, closed-book, unassisted scores. - **Homework outsourcing harms learning.** Field data show a generative-AI learning penalty when students outsource homework. - **Large Language Models (LLMs) reliance correlates with lower grades.** Jošt et al. found significant negative correlations between LLM use for code generation (rho = −0.305) and debugging (rho = −0.360) and final grades. - **AI can harm teaching and achievement for some.** A teacher-facing GenAI RCT found below-median teachers' students lost ground (−0.129 SD). - **Hint abuse correlates with less learning.** Hint button research shows more hints, used unproductively, correlate with less learning. - **Meta-analytic programming gains are illusory.** The GenAI-and-programming meta-analysis finds large productivity gains but no significant learning gain (g ≈ 0), separating task-efficiency from durable learning.

Conditional and mixed effects (context determines direction): - **Design is decisive.** The same tool class can be a strong gain or a net harm depending on configuration (Generative AI without guardrails can harm learning: Evidence from high school mathematics, The Evidence Base on AI in K-12: A 2026 Review). - **How AI is used matters more than whether.** Use for explanations was benign; use for code generation was harmful; over-reliance erodes gains. - **Duration and self-AI Regulation in Education moderate effects.** Effects were strongest at 8–16 weeks and for learners with higher Self-Regulated Learning. - **Computational Thinking level moderates AI-assisted gains.** In a four-week eighth-grade AI coding-assistant course, high-CT students outscored low-CT peers on the post-test (72.54 vs 61.73, p = .031) despite comparable prior coding knowledge, using the assistant to understand code while low-CT students retrieved answers (Zhao et al. (2026)). - **AI-IBL supports creativity but not necessarily problem-solving.** Mujib et al. improved creative performance and attitudes but not critical problem-solving. - **Student experience diverges from measured gains.** AI-native students overestimate their learning, and self-report misaligns with performance — perceptions of gains are not reliable evidence of them.

Meta-analytic learning-gain estimates are inflated — read them with caution

The learning-gain numbers that dominate this page's efficacy summary — especially pooled effect sizes from meta-analyses — must be read with a strong caveat: a wave of meta-research shows the field's positive synthesis estimates are inflated by publication bias, construct incoherence, and methodological shortcuts.

- A study-level meta-meta-analysis of 1,840 effect sizes from 67 meta-analyses finds the publication-bias-adjusted average AI effect is roughly **one-third** the reported magnitude (SMD ≈ 0.196 vs. a median of 0.67), with a prediction interval spanning large harm to large benefit and no moderator producing consistent gains. Even a single extreme study contributes almost no

information given the heterogeneity — meaning *more studies of the current type will not settle the question*; only high-quality, pre-registered, replication-oriented trials will.

- **A second-order meta-analysis of the synthesis layer itself.** Emslander et al. (2026) invert the usual unit of analysis: treating 45 meta-analyses as their data and correcting for study overlap (818 unique primary studies, weighted by uniqueness rather than discarded), they pool 129 meta-analytic effect sizes to g = .57 [.50, .65], with outcome clusters running from .35 for STEM performance to .68 for general academic outcomes. Two results bear on the numbers above. AI type did not moderate the effect (p = .63) — intelligent tutoring systems, chatbots and ChatGPT are statistically indistinguishable at this layer, so the field's pooled gains are not being driven by generative AI as such — and the one clear moderator was educational level (tertiary .61 vs. .30 for younger samples), which is partly a study-design artifact given that 74% of the corpus tested tertiary students and K-12 evidence is comparatively thin. Its quality appraisal is the sharpest in the corpus: the 45 meta-analyses averaged 9.3 of 17 on an AMSTAR-adapted scale, none preregistered, and only 23 of 45 had 80% power to detect the effect they themselves reported. Its two publication-bias tests also disagree — a symmetric funnel plot (Kendall's $\tau = -.01$, p = .868) against PET-PEESE (B = 0.9, p = .009) indicating inflation — so the SOMA's own medium effect arrives with an unresolved bias cloud over it.
- A forensic audit of 14 high-impact AIED meta-analyses finds none provided a valid basis for its pooled learning-gain claim: none had a coherent outcome construct, all had unresolved extreme heterogeneity (I^2 ranged from 77.2% to 94.4% across the 13 meta-analyses that reported it, and 12 of those 13 exceeded 80%), twelve treated dependent effect sizes as independent, and none validly assessed publication bias. A majority of randomly vetted primary studies were mismatched to the meta-analytic claim. The errors reached policy: two of the audited meta-analyses treated study sample size as class size and, on the strength of a miscalculated primary study, concluded that 21 to 40 students is the ideal intervention size and recommended that GenAI interventions be designed for that number.
- **A 2026 STEM synthesis that fixes two of the audited defects — and still illustrates a third.** Doğan and colleagues (2026) pooled 35 experimental and quasi-experimental STEM studies with one effect size per study to avoid the dependent-effect-size problem, and ran a full publication-bias battery (funnel plot, Begg's and Egger's tests, trim-and-fill, Rosenthal's fail-safe N = 2404) rather than asserting symmetry — the two shortcuts the audit above found in every meta-analysis it examined. Two cautions survive. First, the authors applied no formal quality appraisal and treated the inclusion criteria as the rigor threshold, so studies of very different designs entered the pool unweighted by quality. Second, the headline heterogeneity depends entirely on which model you read: the same 35 studies are reported as $I^2 = 82.98\%$ under the fixed-effect model and $I^2 = 15.75\%$ under the random-effects model, so a reader who encounters the numbers without the model label can conclude the corpus is homogeneous when it is not. Its pooled estimate (g = 0.670, 95% CI [0.491, 0.848]) is therefore the kind of figure the section above describes: better built than most, and still an upper bound.
- A media/methods critique shows many "learning gains" were not measured validly — outcomes were often self-reported skills or performance measured *during* AI assistance rather than durable, unassisted learning.

- **The first ChatGPT synthesis wave measured performance, not learning.** Fütterer et al. (2026) rebuilt the evidence base of the five meta-analyses that pooled ChatGPT's educational effects: among 69 classifiable primary studies, 79.7% measured performance exclusively and only 11.6% measured learning. Their reproduced pooled estimate (g = 0.83, 95% CI [0.68, 0.97], I^2 = 94.06%) therefore describes test performance, and its prediction interval [−0.75, 2.41] crosses zero.

Bottom line for the gains numbers above: treat large pooled AI effect sizes as upper bounds, not point estimates. Prefer the learning-gain evidence from well-designed RCTs and field studies with unassisted, standardized outcome measures (the guardrail RCT, the Khanmigo and NUMI experiments, and the World Bank EdTech meta-analysis cited above), and read meta-analytic gains as provisional and likely over-stated until synthesis quality improves. The problem also outlives correction: of the papers published after one audited meta-analysis was retracted, 60% still cited it as authoritative support for large ChatGPT learning gains and none acknowledged the retraction, so a withdrawn estimate keeps propagating. This is why the Limitations in AIEd Research page now documents the meta-analytic evidence crisis in detail.

Measuring what matters

Learning gains connect to Assessment Validity — if assessments fail to capture deeper understanding, learning gain measures are misleading. They also intersect with Over-Reliance and Cognitive Offloading, where apparent performance improvements may mask learning losses, and with RCT (randomized trials as the gold-standard design for detecting causal learning gains), and with Meta-Analysis and Systematic Review (pooling effect sizes across studies to establish the field's efficacy evidence).

- **Significant pre/post gains from mistake-based AI Pedagogies and Teaching Strategies:** Hosseini (2026)'s database design course (n=13) showed large, significant learning gains on identical pre/post items (mean 4.25 → 6.83/7, Cohen's d=1.49, p<.001), with gains uncorrelated with prior AI or database confidence — the AI-integrated critique-refinement design benefited students regardless of initial perceptions.

Common Misconceptions

"Scores went up, so the intervention produced learning." This is the definitional error the page exists to prevent, and the field data show both directions at once: AI use improves scores on AI-assisted homework while *lowering* scores on proctored, closed-book, unassisted measures (Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build; The generative AI learning penalty: Evidence from Chinese secondary education). The choice of measure determines whether the inflation is visible, so a gain on an AI-permitted task is a claim about task performance, not about learning.

"The meta-analysis settles it: the effect is large." Aggregation direction and aggregation magnitude are different facts, and the magnitude rarely survives scrutiny. The GenAI-in-programming meta-analysis finds large *productivity* gains alongside **no significant learning gain** (g ≈ 0). The World Bank meta-analysis, pooling 191 effect sizes from 14 RCTs, estimates ~0.125 sd for adaptive and AI-enabled EdTech — respectable against the median education RCT, but with **no advantage for generative AI over earlier adaptive tools**. Citing GPT-era studies as a category leap overstates what the pooled evidence shows.

“More practice and more personalization always help.” The size of a gain depends on what is being trained, not on how much support is supplied. Rachatasumrit et al. (2025) report that the optimal mix of worked examples and problems shifts with the target skill: pure retrieval practice yields higher gains for verbatim facts, while alternating examples and problems yields higher gains for generalizable skills. And hint-button research finds hint volume negatively associated with learning. The same “support” that helps one knowledge component can waste the other.

“A delayed post-test result is automatically a durable-learning result.” Delay is necessary and not sufficient. What distinguishes durable learning in this corpus is *unassisted* measurement under delayed conditions, together with evidence that the effect is not carried by the scaffold that will be absent at transfer.

Implications for Practice

For instructors

- Separate the grade you give from the claim you make. AI-assisted coursework can fairly assess product quality while telling you nothing about unassisted capability; if you need the second, you must measure it separately.
- Match practice format to knowledge type. Use retrieval for facts and worked-example alternation for transferable procedures rather than one default for both.
- Watch hint volume as a diagnostic, not just a support. Rising hint use with flat unassisted performance is the signature of productive-looking dependence.

For developers

- Report productivity and learning outcomes as distinct metrics, since the corpus repeatedly finds the first while failing to find the second ($g \approx 0$ in the programming meta-analysis). A dashboard conflating them will be read as evidence of learning.
- Do not assume your system generalizes across knowledge components. The example–problem ratio result implies the optimal schedule is a property of the content, not of the platform.
- Make hint and scaffold use visible to instructors, because volume is one of the few behavioral signals empirically linked to weaker outcomes.

For researchers

- Pre-register the outcome measure and state whether it is AI-permitted or unassisted. The direction of the finding can flip on this choice alone.
- Report effect sizes against a named comparison, not against “traditional approaches” in the abstract. The World Bank result is only interpretable because it names its comparison class.
- Distinguish performance inflation from learning displacement explicitly, since the two imply different remedies — task redesign versus re-teaching.

Connected Concepts

- RCT
- Meta-Analysis and Systematic Review
- Formative Assessment

- Summative Assessment
- Cognitive Offloading
- Math Education
- Human-in-the-Loop
- Affective Tutoring
- Theory Development in AI in Education — Theory Development in AI in Education
- Self-Report Measures
- Research Methods in AIED — Research Methods in AIED (DBR section)
- Social-Emotional Learning — Social-Emotional Learning
- Student Support and Success — administrative outcomes (task completion, credits, persistence, graduation) as distinct from learning gains

Connected Articles

- A Critical Epistemological Audit of Early Evidence Syntheses in Generative AI Educational Research: A Systematic Review and Meta-Analysis — A Critical Epistemological Audit of Early Evidence Syntheses in Generative AI Educational Research (Fütterer et al. 2026)
- Experimental Evidence on the Learning Impact of Generative AI — Off-the-shelf chatbot access raised unaided test scores that persisted a week (Contractor & Reyes 2026)
- AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting — AI tutoring outperforms in-class active learning: an RCT introducing a novel research-based design in an authentic educational setting (Kestin et al. 2025)
- Distinguishing performance gains from learning when using generative AI — why assisted performance is not a learning outcome (Yan et al. 2025)
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — Virtual tutoring with CAL: an experiment in take-up and learning
- Making AI tutoring productive: Evidence from a mastery-based math practice experiment — Making AI tutoring productive: mastery-based math practice
- One click away: AI tutoring with Khanmigo in a two-year school experiment — One Click Away: Khanmigo in a two-year school experiment
- How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures — AI Literacy Assessment: Self-Reported vs Performance Misalignment
- Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build — Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build
- A meta-analysis of the effect of generative AI on productivity and learning in programming — A meta-analysis of the effect of generative AI on productivity and learning in programming
- AI literacy interventions in education: A meta-analysis of effects and moderators — Meta-analysis of AI literacy intervention effects

- ChatGPT-generated help produces learning gains equivalent to human tutor-authored help on mathematics skills — ChatGPT help produces learning gains equivalent to human tutor help
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — Generative AI without guardrails can harm learning (PNAS 2025 RCT)
- The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students' Academic Self-Assessment — The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students' Academic Self-Assessment
- OECD Digital Education Outlook 2026: Exploring Effective Uses of Generative AI in Education — OECD Digital Education Outlook 2026
- How AI Is Changing Teaching Workflows. — How AI Is Changing Teaching Workflows
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis — Meta-analysis of AI-enhanced embodied robot-assisted language learning
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches
- Young people, learning, and generative AI: A rapid literature review and implications for PreK-12 education — Immediate performance vs durable learning distinction
- The generative AI learning penalty: Evidence from Chinese secondary education — The generative AI learning penalty: homework outsourcing harms learning
- Design-based research for developing an AI-assisted collaborative learning model to enhance critical thinking and problem-solving skills in higher education — AI-Assisted Collaborative Learning model DBR (critical thinking +24.1%, problem-solving gains)
- The Evidence Base on AI in K-12: A 2026 Review — Tutoring-specific vs general AI
- The impact of large language models on programming education and student learning outcomes — LLM reliance and grades in coding (negative correlations)
- Generative AI Can Harm Teaching — Generative AI can harm teaching (RCT)
- Does generative artificial intelligence improve students' higher-order thinking? A meta-analysis based on 29 experiments and quasi-experiments — GenAI and higher-order thinking meta-analysis
- Evaluating the impact of AI-supported inquiry-based learning on students' creative mathematical performance, critical problem-solving skills, and attitudes toward mathematics — AI-supported IBL and creative math performance
- AI-enhanced problem-based learning framework: integrating ChatGPT as adaptive scaffolding to improve critical thinking and personalized learning — AI-enhanced PBL scaffolding gains
- Artificial intelligence assisted design of a novel cooperative learning technique for higher education — AI-designed cooperative learning technique
- Fostering feedback literacy by scaffolding self-regulated feedback: a comparative study of GenAI and human peers — Scaffolded self-regulated feedback gains
- Patterns of Learner-AI Interaction and Academic Performance in an Object-Oriented Programming Course — Interaction patterns and learning gains in OOP

- Using AI-Generated Feedback to Improve Critical Thinking and Writing Proficiency — AI feedback and critical thinking in writing
- The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking — The Pedagogy of AI Mistakes: Fostering Higher-Order Thinking (Hosseini 2026)
- Exploring the effect of computational thinking levels on students' learning performance, cognition, and behavior when using AI coding assistants — Computational Thinking Levels and AI Coding Assistants (2026)
- Can EdTech close learning gaps? Global evidence from digital interventions — Meta-analysis: adaptive/AI EdTech raises learning ~0.125 sd
- GPT-4 feedback increases student activation and learning outcomes in higher education
- Evidence and Theory for why the Best Example-Problem Ratio To Optimize Learning Gain Depends on Knowledge Content
- You've Got AI Friend in Me: LLMs as Collaborative Learning Partners
- ChatGPT in Education: An Effect in Search of a Cause — ChatGPT in Education: An Effect in Search of a Cause (media-comparison critique of gains measures)
- Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis — Meta-meta-analysis: bias-adjusted AI learning-gain effects ~1/3 of reported size
- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Presumed Effective: audit of flawed AIED meta-analyses
- The Impact of Artificial Intelligence-Supported Instruction on Student Learning in STEM: A Systematic Review and Meta-Analysis — A STEM synthesis that controlled dependent effect sizes and tested publication bias, but applied no quality appraisal (Doğan et al. 2026)
- What Do We Know About the Effects of Artificial Intelligence in Education? A Second-Order Meta-Analysis — Second-order meta-analysis of 45 AI-in-education meta-analyses, with overlap-corrected effects and a quality appraisal of the synthesis layer (Emslander et al. 2026)
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- AIED unplugged, teacher workload, and numeracy learning: a clustered quasi-experimental mixed-methods study — In teacher-mediated AI, preparation moved gains and the tool did not

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- What Are Notable Gaps in the Research Literature on AI in Education?
- Does Using AI Actually Help My Students Learn?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?

Research methods and evaluation

Research methods

Research Methods in AIED

> **Research methods in AIED** — the set of empirical designs, data-collection strategies, and analytic techniques researchers use to study AI in education: whether and how AI tools support (or harm) learning, and under what conditions. The knowledge base's corpus spans experimental, survey, qualitative, design-based, computational-benchmark, and review methods. Each has distinct strengths and limitations, and choosing among them involves trade-offs among internal validity (confidence in causal claims), external validity (generalizability), ecological validity (real-world authenticity), and the feasibility of studying fast-moving AI tools.

Questions to Consider

- The page's central tension: the strongest designs for causal inference (randomized experiments) are the hardest to run in real classrooms, while the most authentic settings offer weaker causal control. If you had to decide whether an AI tutor helps learning, which of these two failures would you rather live with — and why?
- Before you read, can you name the difference between internal, external, and ecological validity? The page argues every design trades these off. How might a study that's rigorously causal still tell you almost nothing useful about a real classroom?
- A benchmark shows an AI scores high on accuracy, but the page insists high benchmark accuracy does not entail educational effectiveness. Why might a system that 'passes the test' still fail to help students learn — and what kind of evidence is missing?
- Design-based research iterates on a real intervention but can't attribute gains to a specific mechanism, while an RCT isolates causes but runs in artificial conditions. Given the fast pace of AI change, how long do you think a rigorous RCT remains relevant before the tool it tested is obsolete?
- Delphi expert consensus establishes agreement among experts, not empirical effect. When is it legitimate to build a competency framework from what experts believe, versus from data about what works — and how would you tell the difference in practice?
- The page advocates triangulation — combining benchmark evaluation, experiments, measurement, and qualitative work to judge both whether a tool works and how. Before you read, where in a claim like 'this AI improves learning' would each method be needed to make you confident?

Introduction

The central tension in AIED research is that the strongest designs for causal inference — randomized experiments — are often the hardest to run with authentic AI tools in real classrooms, while the most authentic settings (field deployments, case studies, log-data analyses) offer weaker causal control. No single method resolves this; the field advances by triangulating across methods, and by being explicit about what kind of claim each design can support. Every method also carries cross-cutting limitations —

generalizability, measurement validity, the fast pace of AI change, reproducibility, and weak theory use — that readers must weigh; see Limitations in AIEd Research.

The page's subject is method rather than findings. Learning Sciences is the substantive field these methods serve: where this page covers how a study should be designed, measured and reported, that page covers what the field has established about how people learn and how learning environments should be designed, and it treats design-based and mixed methods as the learning sciences' signature approaches rather than two options among many.

Adjacent to this page is AI-Assisted Educational Research, which covers AI as an instrument of the field's own work: literature search, screening, review automation, qualitative coding, analysis, and writing. Its scope includes practitioner research such as the scholarship of teaching and learning, and it stays distinct from the designs this page describes.

Martin, Rost, Koenen and Graulich (2026) press the same scrutiny on the field's knowledge production itself, using Chang's (2004) nomic-measurement problem: measuring a quantity requires a law relating it to something observable, yet that law cannot be tested empirically without already knowing the quantity. They argue that AI-derived measurement functions, which emerge from training data and optimization rather than from the researcher, may intensify rather than resolve it. Such functions can look precise yet remain epistemically opaque, so the researcher's role shifts to interpreting and validating computational outputs. Their seven-phase reflective framework (problem framing; instrumentation and measurement; experimentation and evidence-based inference; comparisons and replication; building norms and consensus; implementation and its consequences; and continuous refinement) is offered as an analytical aid, not a validated method, and they argue comparability must extend across student populations rather than the subsets a model serves well.

Reporting rigor and the TEP-AIED model

The reporting quality of AI-in-education studies is itself a research concern. The TEP-AIED model (Hwang, Xie, Wah & Gasevic, 2026) offers a structured framework for presenting AI-in-education research with rigor, organizing the essential components of a study report — theory/technology/educational problem framing, design, data, analysis, and results — so that readers and reviewers can assess whether claims are supported and whether the work is reproducible. It responds to the field's chronic weaknesses in reporting (vague tool descriptions, unstated model versions, omitted evaluation details) that the limitations page documents. Reporting frameworks like TEP-AIED sit alongside established reporting checklists (e.g., CONSORT-style guidance for trials, PRISMA-style guidance for reviews) as part of the field's broader move toward methodological transparency and reproducibility.

RAISE (Allison, 2026) approaches the same problem from the opposite direction — as a checklist rather than a narrative structure. It sets out **30 items across ten thematic domains** (educational justification and theoretical grounding, AI system specification, AI role and interaction, Accessibility and cultural fit, setting and participants, human involvement, study design and evaluation, ethics and trustworthiness, transparency and reproducibility, and limitations and implications), with an editable version and a companion **Ethics and Risk Matrix** covering learner agency, equity of access, data AI Governance and algorithmic transparency. The two frameworks address each other directly: TEP-AIED characterizes RAISE as comprehensive but faults its breadth, arguing that "its breadth and granularity may make it complex and less accessible for

routine empirical applications," while RAISE's own framing is that it mandates no method or model and only requires that choices be made visible. Read together they mark the trade-off in this literature — the fuller audit checklist versus the leaner three-dimension narrative — and they converge on the same non-negotiables: name and version the AI system, disclose prompts and interaction design, define treatment and comparison conditions, report ethical review and risk mitigation, and state whether outcomes measure performance, retention, or transfer. For a study to be adjudicated on those terms, the reporting instrument has to be adopted at design time rather than assembled at manuscript stage, which is the point both frameworks insist on. Corpus-level historical analysis is itself a methodological choice with transparency obligations: Rismanchian & Doroudi locate each paper in their AI×Ed framework based on author judgment of abstracts and full texts, explicitly acknowledge that this is not a systematic or scalable data-driven categorization, and make their full dataset publicly available as supplementary material for replication.

Experimental and quasi-experimental designs

An **efficacy study** tests whether an intervention produces its intended learning effect, typically using experimental or quasi-experimental designs that compare outcomes with and without the intervention. Experiments randomly assign learners to conditions (e.g., AI tutor vs. human tutor, or AI-scaffolded vs. unassisted) to estimate causal effects on outcomes like learning gains, engagement, or motivation. **Randomized controlled trials** are the gold standard for internal validity. A randomized field study of human support plus AI tutoring and an RCT on generative AI in teaching use assignment to isolate causal effects. **Quasi-experimental** designs (pre/post, between-subjects, or matched groups without randomization) are more feasible in intact classrooms but weaker on causal claims. - **Instrument validation and baseline checks come before the effect estimate.** Davor (2026) compared two intact Ghanaian senior high school classes (86 students, 43 per group) on GenAI as a geometry scaffold, sizing the sample with a G*Power analysis and piloting the Geometry Reasoning and Proof Test to a Spearman-Brown split-half reliability of 0.859 before the study. The groups did not differ significantly at pre-test, and an ANCOVA adjusting for prior performance retained the group effect ($F(1, 83) = 50.30$, $p < .001$, partial $\eta^2 = .377$). With no random assignment, the pilot reliability and the baseline-equivalence check are what make the adjusted comparison interpretable.

- **Strengths:** strongest causal inference; clean outcome measurement; supports effect-size estimation and efficacy claims.
- **Limitations:** costly and slow; artificial conditions can reduce ecological validity; fast-changing AI tools make long experiments date quickly; small samples often underpower detection of meaningful effects; ethical constraints on withholding potentially helpful tools.
- **Exemplars:** Access is Not Enough: Human Support Improves Engagement with AI Tutoring, Generative AI Can Harm Teaching, Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study, Exploring How Agent Voice Accents Shape Human-AI Collaboration in K-12 Group Learning, From AI use to critical thinking among medical students: A moderated mediation perspective on cognitive load and self-regulated learning.
- **Preregistration applies to secondary analyses, not only trials.** Srivastava (2026) ran four Knowledge Tracing update rules over identical ASSISTments logs (12,716 students, 985,813 scored events) that differed only in how they score hinted rows, held the confirmatory half sealed until a file containing the registration's URL existed, and reported that all four preregistered

predictions held. Crediting any completion predicted later unaided performance barely above a skill-difficulty constant (pooled AUC 0.604 against 0.595) while declaring 93.9% of student–skill pairs mastered against 72.8% under a strict rule. When one log supports several conclusions, fixing the analysis in advance is what makes the comparison credible.

Survey and structural-equation-modeling studies

Cross-sectional surveys measure self-reported attitudes, perceptions, motivation, Self-Efficacy, and technology acceptance, often modeled with regression or structural equation modeling (SEM/PLS-SEM) to test hypothesized relationships and mediators. These dominate the knowledge base's corpus, particularly for acceptance, motivation, and psychological-mechanism questions.

- **Strengths:** large samples; broad, low-cost coverage; can test complex mediational models of psychological mechanisms; feasible for studying attitudes that are hard to observe.
- **Limitations:** cross-sectional data cannot establish causation; common-method/self-report bias; convenience sampling limits generalizability; mediators inferred from covariance, not manipulation.

The instrument itself deserves separate scrutiny. What a questionnaire, interview, or diary can and cannot establish — and the documented gap between what people report and what they do — is gathered on Self-Report Measures. - **Exemplars:** Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups, Examining the impact of generative AI on student motivation and engagement: The mediating role of autonomy-support and autonomous motivation in education, AI-assisted autonomous learning and reduced academic accomplishment in vocational higher education: The mediating role of hardiness, From enhancement to over-reliance: A mixed-method study of generative AI and sustainable learning performance, From AI use to critical thinking among medical students: A moderated mediation perspective on cognitive load and self-regulated learning.

Qualitative methods

Interviews, focus groups, and thematic analysis produce rich, contextual accounts of how students and teachers experience AI tools, the meanings they attach to them, and the tensions and harms that standardized measures miss. Research on AI tutor safety and how AI changes teaching workflows rely heavily on qualitative evidence. See the dedicated Qualitative Research concept page for the full treatment of qualitative approaches — thematic analysis, grounded theory, phenomenology/phenomenography, discourse analysis, observations and ethnography, case studies, and interviews/focus groups — each with knowledge base exemplars.

- **Strengths:** deep ecological and conceptual insight; surfaces unexpected phenomena, risks, and mechanisms; essential for theory-building and for studying contested constructs like trust, autonomy, and authorship.
- **Limitations:** limited generalizability; interpretive and researcher-dependent; small samples; weaker support for causal claims; findings can be hard to synthesize across studies.

- **Exemplars:** SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems, How AI Is Changing Teaching Workflows., Scaffolding critical engagement with GenAI: Transforming ethnic minority preparatory students' collaborative discourse in prompt engineering tasks.

Mixed-methods designs

Mixed-methods studies combine quantitative and qualitative strands — often sequentially (e.g., QUAL → QUAN → qual) — so that qualitative data explains or contextualizes quantitative findings. A mixed-method study of GenAI and sustainable learning pairs three-wave surveys with educator interviews; the competence-paradox study uses instructor focus groups, a student survey, and follow-up interviews.

- **Strengths:** triangulation increases confidence; quantitative breadth plus qualitative depth; can explain unexpected results and bridge mechanism and magnitude.
- **Limitations:** complex, resource-intensive, and methodologically demanding; integration can be shallow if not carefully designed; still inherits the weaknesses of each strand (e.g., self-report).
- **Exemplars:** From enhancement to over-reliance: A mixed-method study of generative AI and sustainable learning performance, The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students, Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts, Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration.

Design-based research (DBR)

DBR iteratively designs, implements, and refines an educational intervention in authentic contexts, cycling between theory, design, and real-world practice. It is prominent in the knowledge base for developing AI learning environments and pedagogical models. See the dedicated Design-Based Research concept page for the full DBR cycle, exemplars, and its strengths/limitations. A canonical AIEd example is the AI-Assisted Collaborative Learning model study (Putra et al.), which ran a four-phase DBR cycle — needs analysis, model design, eight-week classroom implementation, and model refinement — iterating on a four-stage learning cycle (problem identification → AI-assisted collaborative inquiry → collaborative Problem Solving → reflection and presentation). Other exemplars develop AI Literacy teacher training (Development and evaluation of artificial intelligence literacy training for teacher education students) and GenAI Scaffolding for critical thinking (Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education).

- **Strengths:** high ecological validity and practical relevance; produces both usable artifacts and theory; responsive to the complexity of real classrooms and evolving AI tools; well-suited to developing a model and refining it based on authentic implementation evidence.
- **Limitations:** weak internal validity (few/no control groups); findings are context-bound and hard to generalize; long timelines; difficult to isolate which design element caused an outcome — DBR demonstrates feasibility and improvement but cannot attribute learning gains to a specific mechanism.
- **Exemplars:** Design-based research for developing an AI-assisted collaborative learning model to enhance critical thinking and problem-solving skills in higher education, Development and

evaluation of artificial intelligence literacy training for teacher education students, Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education, Human-centered AI for teacher educators: Designing professional learning for critical AI literacy.

DBR trades the causal control of experiments for ecological authenticity and iterative refinement: it is the right tool for "how do we design this AI learning environment to work in practice?" questions, and its evidence is strongest as proof-of-concept and design guidance rather than causal efficacy. Reading DBR learning gains requires the same caution as other designs — without an unassisted, controlled outcome measure, gains can reflect the same AI-inflated-performance confound documented under learning gains.

Systematic reviews and meta-analyses

Reviews synthesize the evidence base rather than running a new experiment. Systematic and scoping reviews apply a transparent protocol to search, screen, appraise, and synthesize a body of studies; meta-analyses additionally pool effect sizes across studies to produce a weighted summary estimate and test moderators. A comprehensive ITS review and a systematic review of GenAI in higher education exemplify the approach.

- **Strengths:** efficient synthesis of a large, fragmented literature; meta-analysis yields pooled effect estimates and detects moderators; essential for evidence-based practice and identifying gaps.
- **Limitations:** depend on the quality of included studies (garbage-in/garbage-out); publication bias; heterogeneous methods and outcome measures make synthesis hard; rapidly aging given the speed of AI change.
- **Meta-research caveat (2026):** critiques of the AIED synthesis base show that many early meta-analyses are undermined by construct incoherence, unresolved heterogeneity, unaddressed dependence among effect sizes, and invalid publication-bias assessment — inflating headline AI effect sizes (see Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis, Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis, and ChatGPT in Education: An Effect in Search of a Cause). Treat pooled AIED effect sizes as upper bounds.
- **Exemplars:** Comprehensive Review of Intelligent Tutoring Systems, Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025), The cognitive impact of ChatGPT in higher education: A systematic review of critical and creative thinking outcomes, Comprehensive Review of Intelligent Tutoring Systems, A scoping review of generative AI-powered agentic AI in education: Research landscape, agentic capabilities, and insights from the frontier agent paradigm, exemplified by OpenClaw.

See the dedicated Meta-Analysis and Systematic Review concept page for a fuller treatment of systematic review and meta-analysis in AI in education — including their relationship to primary designs, PRISMA reporting, and their strengths and limitations.

Computational and benchmark evaluation

Computational evaluation assesses AI systems directly — against benchmarks, ground-truth labels, or human judgments — rather than studying human learners. This includes benchmarks, Large Language

Models (LLMs)-as-judge approaches. This is the closest method to AI Ed Evaluation (see the distinction below).

- **Strengths:** fast, scalable, reproducible; enables head-to-head comparison of models and system versions; essential for system development and quality assurance.
- **Limitations:** measures system output, not learning — high benchmark accuracy does not entail educational effectiveness; ground-truth and rubric quality are themselves contested; can miss pedagogical quality that humans perceive. Rismanchian & Doroudi argue that LLMs' natural-language flexibility makes purely technical metrics insufficient, requiring human-inspired evaluation approaches — simulated students, AI-teacher tests, and behavioral-science analyses previously reserved for human subjects — to judge learning-relevant quality, and that studying LLMs cautiously can generate insight into human learning.
- **Disjoint participants, not random splits, prevent leakage in detector evaluation.** Kumar et al. (2026) built a stylometric detector from 90 writers who each produced one unaided and one paraphrased sample, keeping every window from a participant in a single fold so author style could not leak across the split and holding 18 people out entirely. The random forest reached ROC-AUC 0.870 with F1 0.842, but flagged 4 of 18 independently authored documents as GPT-assisted (22.2%); the authors treat that false-positive rate as the deployment-relevant result and frame the model as decision support rather than an automated misconduct screen.
- **Exemplars:** TeachBench - Evaluating LLM Teaching Ability, ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents, Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education, Confidence Estimation in Automatic Short Answer Grading with LLMs, The aftermath of DrawEduMath: Vision language models underperform with struggling students and misdiagnose errors.
- **Reporting standards for automated pipelines, and audited benchmarks.** Two 2026 papers extend methodological accountability beyond the study itself. PRISMA-LLM maps 888 review-automation papers and 14,726 annotations, finding that 38.0% of software or product papers reported no evaluation against 9.3% of LLM papers and that 52% of positive-only LLM evaluations left a high-bar concern unmet, and proposes reporting that identifies where in the review workflow automation acted (PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews). An expert re-grading audit of six physics benchmarks shows the same problem at the instrument level: of 250 audited rejections only 12 (4.80%) were genuine model errors, while 143 were item defects and 95 grader errors (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks). Both argue that computational evaluations need an audited error budget before their results are read as findings about learners or models.
- **Build the human-agreement check into detector development, not after it.** Baker and colleagues (2026) set out a seven-step process for textual detectors of cognitive constructs — dataset selection, construct definition, codebook drafting, human inter-rater checking, category refinement, detector building, and application — so reliability on human-coded labels precedes any LLM-as-judge deployment. It requires chance-corrected agreement metrics (Cohen's or Fleiss's κ, Krippendorff's α), student-level cross-validation, and subgroup error analysis as

minimum standards, and argues that mismeasurement becomes a source of harm once such detectors sit inside deployed platforms.

Other designs: longitudinal, case, and simulation studies

Beyond the major families, the knowledge base uses **longitudinal** designs that track learners over time (a longitudinal LMS study), **case and in-the-wild** studies of authentic usage (large-scale analysis of real student interactions), and **simulation** studies in which LLMs stand in for students or patients (LLMs as simulated learners, Simulation). These trade breadth or control for realism and for access to phenomena that are otherwise hard to observe.

Expert-consensus methods: the Delphi technique

The Delphi method is a structured technique for establishing **expert consensus** on a question where the answer is not yet known empirically — most often used in the knowledge base to develop frameworks, competency lists, and definitions that practitioners and researchers can agree on. In a Delphi study, a panel of experts responds to successive rounds of questionnaires; after each round, an anonymized summary of the group's responses is fed back, and experts revise their answers until the group converges on agreement (typically defined by a pre-set threshold, e.g., 75%). It is a way to build construct validity and professional consensus through iterative, anonymized consultation rather than a single survey or vote.

- **Strengths:** produces consensus from a diverse expert panel without in-person group pressures (anonymity reduces dominance effects); well-suited to defining constructs, competencies, and frameworks when no validated measure exists; iterative rounds let experts refine and converge; feasible where full experiments or large samples are impractical.
- **Limitations:** consensus reflects expert judgment, not empirical evidence — it establishes agreement, not effect; results depend on panel composition and the (subjective) consensus threshold; can be slow across multiple rounds; a single panel's judgment may not generalize.
- **Exemplars:** the SAIL framework study (three rounds, 17 experts, refining AI-literacy competency levels), the HCAP framework study (three rounds, 30 teachers, defining 25 AI-teacher competencies), the AI Literacy Heptagon (which used expert input/consensus alongside a PRISMA-guided review), and.

Delphi is often combined with other methods — for example, expert consensus can be used to validate a framework (as in SAIL and HCAP) that is then tested or implemented via design-based research or survey studies. It sits alongside qualitative and expert-judgment approaches and contributes to the validity of framework-based instruments.

Research vs. evaluation: connections and distinctions

Research and evaluation are closely related but distinct. **Research** asks generalizable questions about how AI affects learning — "does scaffolding improve learning outcomes?" — and aims to build theory and evidence that transfers beyond the specific study. **Evaluation** (see AI Ed Evaluation) assesses whether a *specific* AI tool or system works — is accurate, reliable, pedagogically sound, and fit for purpose — against

benchmarks, rubrics, or stakeholder-defined criteria. Research emphasizes internal validity and generalization; evaluation emphasizes system quality and local decision-making.

The boundaries blur: benchmark studies are evaluation that can feed research, and evaluation instruments (rubrics, ground-truth sets, validity frameworks) depend on the Educational Measurement and Assessment Validity concerns that research clarifies. Conversely, research findings on what supports learning should inform how AI tools are evaluated. The knowledge base treats them as complementary: computational and benchmark evaluation (Benchmark, AI Ed Evaluation) tells us whether an AI system is technically sound, while efficacy and survey research (RCT) tells us whether it helps people learn.

Choosing among methods

Method choice follows the research question. Causal-effect questions favor experiments (RCT); mechanism and perception questions favor surveys and qualitative work; system-quality questions favor computational evaluation (Benchmark, AI Ed Evaluation); synthesis questions favor reviews and meta-analyses; design questions favor DBR; and questions about what experts agree a construct, competency, or framework should contain favor expert-consensus methods like the Delphi technique. Given the field's heterogeneity and the speed of AI change, the knowledge base's corpus reflects a deliberate move toward triangulation — combining computational evaluation with efficacy, qualitative, and expert-consensus evidence to judge both whether a tool works and whether it helps learning.

Equally important is reading any single study with awareness of the **cross-cutting limitations** that affect AIED research as a whole — methodological constraints, the fast pace of AI change versus slow publication, reproducibility and FAIR-practice gaps, reliance on proprietary tools, and weak or uncritical theory use. See Limitations in AIEd Research.

Contrasting the major research traditions

The three major research traditions — quantitative, qualitative, and experimental — differ fundamentally in what they can claim, what they sacrifice, and when each is appropriate. Understanding these contrasts is essential for both designing and reading AI-in-education research.

What each tradition establishes

Dimension	Quantitative / survey	Qualitative	Experimental
Core question	How much? How related?	What does it mean? How is it experienced?	Does X cause Y?
Primary data	Numbers, scales, self-report	Words, observations, artifacts	Outcome measures across assigned conditions
Inference target	Patterns, correlations, mediation	Meaning, mechanisms, categories	Causal effects
Internal validity	Weak (correlational)	Weak (no control)	Strong (random assignment)
External validity	Strong (large samples)	Limited (small, context-bound)	Moderate (controlled conditions)

Dimension	Quantitative / survey	Qualitative	Experimental
Ecological validity	Moderate	High	Lower (artificial conditions)

- **Quantitative research** measures and models relationships among variables — surveys, SEM/PLS-SEM, measurement, longitudinal tracking. It provides breadth, precision, and generalizability but cannot establish causation from cross-sectional data and inherits measurement limitations (including self-report bias).
- **Qualitative research** interprets meaning and experience — interviews, focus groups, thematic analysis, grounded theory, phenomenography, discourse analysis, observation/ethnography, case studies. It provides depth, mechanism, and theory-building (see Theory Development in AI in Education) but limited generalizability and weak causal support.
- **Experimental and quasi-experimental designs** (see RCT) estimate causal effects via random assignment or matched comparison — the gold standard for internal validity, at the cost of cost, speed, and ecological validity.

The measurement and mixed-methods links

Quantitative work depends on Educational Measurement — reliable, valid instruments for the constructs being studied. Qualitative work reveals the mechanisms and meanings those instruments may miss. **Experimental** work estimates whether an intervention *causes* the outcomes the instruments measure. The three are complementary layers: instruments quantify constructs, experiments establish causality, and qualitative work explains the *how and why* behind the numbers.

Mixed-methods designs intentionally combine quantitative and qualitative strands so their strengths offset each other's weaknesses — quantitative breadth plus qualitative depth, with triangulation increasing confidence.

Usability and HCI research

A distinct methodological strand — usability and HCI research — evaluates how users interact with an AI system: its usability, usefulness, learnability, and user experience, using think-aloud protocols, structured user studies, interviews, and observation. It is the closest to AI Ed Evaluation and answers a *prerequisite* question: even a pedagogically sound tool fails if it is unusable. Usability research shares data-collection methods with qualitative research but aims at evaluating an artifact rather than interpreting meaning.

Benefits and limitations across traditions

- **Quantitative/survey:** benefits — large samples, broad coverage, tests complex mediators, efficient. Limitations — no causation, self-report bias, convenience sampling, instruments may measure the wrong construct.
- **Qualitative:** benefits — deep insight, surfaces unexpected phenomena and harms, essential for theory-building, centers under-represented voices. Limitations — limited generalizability, researcher dependence, small samples, weak causal support, hard to synthesize.

- **Experimental:** benefits — strongest causal inference, clean outcome measurement, effect-size estimation. Limitations — costly/slow, artificial conditions, fast-changing AI dates results, underpowered small samples, ethical constraints.
- **Mixed-methods:** benefits — triangulation, breadth + depth, explains unexpected results. Limitations — complex, resource-intensive, integration can be shallow, inherits each strand's weaknesses.
- **Usability/HCI:** benefits — identifies adoption barriers, actionable design guidance, fast and cheap. Limitations — does not establish learning effects, small samples, self-report satisfaction can mislead.

In practice, AI-in-education research rarely falls cleanly into one tradition. The strongest evidence triangulates: a computational or usability evaluation establishes that a system works, an experiment establishes that it causes learning, quantitative instruments measure the constructs, and qualitative work reveals the mechanisms and meanings — together answering both *whether* a tool helps learning and *how and why*.

Bulut (2026) adds a bibliometric strand that sits apart from these four: mapping 407 records by co-word and co-authorship network to trace a field's conceptual development. The author is explicit that the SWOT reading built on top of it is an interpretive device rather than an independent analytical technique, which marks the boundary between synthesis and analysis in this tradition.

- **"A statistic can be trusted once it is computed."** The benchmark checks the check first. Every probe and every verdict except six named sets of statistics was run on simulated graders with a planted effect and without one, and a measure whose check did not find the planted effect was reported as unmeasured rather than as a result. Its reports are generated from their own markdown and code, so every printed number links to the file and field it came from and is recomputed at build. A Verdict is a design decision that can be tested before any real result is read.

Common Misconceptions

"High benchmark accuracy shows educational effectiveness." It does not, and the gap is the field's central measurement problem: a system can score high on accuracy while producing no learning, because benchmark accuracy measures task performance under the conditions the benchmark set. Educational effectiveness requires a learner outcome under conditions the technology does not control.

"One research tradition is methodologically superior." The traditions trade one limitation for another by construction. Design-based research iterates on a real intervention but cannot attribute gains to a specific mechanism, while an RCT isolates causes but runs in artificial conditions. Choosing between them is choosing which claim you can make, not which method is better.

"A lenient measurement rule is a minor methodological choice." It changes the finding. Crediting any completion predicted later unaided performance **barely above a skill-difficulty constant (pooled AUC 0.604 against 0.595)** while declaring **93.9% of student-skill pairs mastered against 72.8%** under a strict rule. The rule produced a 21-point difference in who was declared ready and almost no predictive improvement to show for it.

“Statistical significance settles whether an intervention worked.” It settles whether an effect was detectable. Whether it was a *learning* effect depends on the outcome measure, the comparison and the conditions under which it was taken — which is why the design and reporting choices in this page’s sections carry as much weight as the analysis.

Connected Concepts

- Interpreting and Applying AIEd Research
- AI Ed Evaluation
- RCT
- Benchmark
- Meta-Analysis and Systematic Review
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Educational Measurement
- Assessment Validity
- Simulation
- AI in Education
- Higher Education
- Limitations in AIEd Research
- Learning Gains
- Theory Development in AI in Education — Theory Development in AI in Education
- Qualitative Research — Qualitative Research
- Quantitative Research — Quantitative Research
- Mixed-Methods Research — Mixed-Methods Research
- Design-Based Research — Design-Based Research
- Usability Research — Usability Research
- Self-Report Measures
- Learning Sciences

Connected Articles

- Amid an Epistemic Iteration: How AI Methodologies May Transform the Nature of Science Education Research — A seven-phase epistemic-iteration framework for reflecting on how AI methodologies may transform science education research (Martin et al., 2026)
- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — Access is Not Enough: Human Support Improves Engagement with AI Tutoring
- Generative AI Can Harm Teaching — Generative AI Can Harm Teaching
- From enhancement to over-reliance: A mixed-method study of generative AI and sustainable learning performance — From Enhancement to Over-Reliance: A Mixed-Method Study

- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — Acceptance of AI-Assisted English Language Learning Tools
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI Tutor Safety and Pedagogical Harms
- Comprehensive Review of Intelligent Tutoring Systems — Comprehensive Review of Intelligent Tutoring Systems
- Design-based research for developing an AI-assisted collaborative learning model to enhance critical thinking and problem-solving skills in higher education — Design-Based Research for an AI-Assisted Collaborative Learning Model
- TeachBench - Evaluating LLM Teaching Ability — TeachBench: Evaluating LLM Teaching Ability
- Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education — Modernizing Ground Truth: Four Shifts Toward Reliability and Validity
- Can LLMs Effectively Simulate Human Learners? Teachers' Insights from Tutoring LLM Students — Can LLMs Effectively Simulate Human Learners?
- RAISE the Standard: A Framework for Transparent Reporting of Artificial Intelligence Studies in Education — RAISE: 30 items in ten domains for transparent reporting of AI-in-education studies (Allison 2026)
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond — AI-Integrated Learning Management System: A Longitudinal Study
- AI in the Wild: A Large Scale Analysis of Authentic Interactions of College Students with Generative AI — AI in the Wild: Large Scale Analysis of Authentic Interactions
- Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts — Same AI, Different Pathways: Unpacking Mechanisms
- Presenting your AI in education research with rigor: The TEP-AIED model — The TEP-AIED model for reporting AI-in-education research with rigor (Hwang, Xie, Wah & Gasevic 2026)
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The Competence Paradox: Text-to-Image GenAI in Art and Design
- The evolution of research on AI and education across four decades: Insights from the AIxEd framework
- ChatGPT in Education: An Effect in Search of a Cause — ChatGPT in Education: An Effect in Search of a Cause
- Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis — Meta-meta-analysis of AI effect on learning
- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Presumed Effective: flawed AIED meta-analysis audit
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data

- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: probes whose right answer is known, planted-effect checks on simulated graders, and 22 prompted models (Porcaro 2026)

Connected FAQs

- What Are Notable Gaps in the Research Literature on AI in Education?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?

AI-Assisted Educational Research

> **Synthesis:** AI-assisted educational research is the use of AI as an instrument of the field's own scholarly work — searching and retrieving literature, screening records for reviews, coding qualitative data, analyzing data, drafting and editing manuscripts, and the reflection that asks what those tools do to the knowledge produced. It is distinct from research *on* AI in education: the designs used to study whether AI helps learners belong to Research Methods in AIED, the appraisal of AI systems belongs to AI Ed Evaluation, and the reading of a single AIED study belongs to Interpreting and Applying AIEd Research. This page covers the researcher's own workflow and the practitioner-researcher's inquiry — the scholarship of teaching and learning and classroom research — and the epistemic stakes when automation enters either one. Its evidence is thin and recent: a framework proposal, one review team's reflective account, a small focus-group study, two bibliometric studies, a workshop report, and single-investigator case studies. It describes a direction of travel rather than established practice, and the practitioner-research strand is the thinnest of all.

Questions to Consider

- Who counts as a researcher here: the funded academic, the graduate student, the lecturer studying their own classroom? Which of those does the evidence actually describe?
- An AI screen excluded a study from your review. Who is accountable for that decision — the vendor, the tool, the protocol, or you?
- When a model summarizes sources you have not read, what part of the scholarly work have you stopped doing?
- A simulated learner can test a tutor across many profiles. What would you check before believing its verdict about real students?
- Practitioner inquiry is usually local and small. Should its evidence meet the bar of a funded trial, or be weighed differently because the setting is the point?
- If AI helped draft a paper, what should readers be told, and where should that disclosure live?

Introduction

AI-assisted educational research is the field turning AI tools on its own work. The object of study is not a learner using an AI tutor but a researcher using a model to search, screen, extract, code, analyze, or write. What changes is the researcher's workflow and, more quietly, the criteria by which its output counts as evidence.

This page is deliberately not about research *on* AI in education. Questions about whether an AI tutor improves learning are addressed by Research Methods in AIED, the appraisal of AI systems by AI Ed Evaluation, and the cautious reading of a single study by Interpreting and Applying AIEd Research and Limitations in AIEd Research. The two literatures are often conflated, and the tooling claims of the second are frequently borrowed to support the first.

The scope runs from literature search through screening, coding, analysis, and writing, and includes the epistemological reflection that asks what automation does to the knowledge a field produces. It also includes practitioner research: the scholarship of teaching and learning and classroom inquiry, where a teacher studies their own practice. That strand is the weakest part of this page, and the sections below say so rather than smoothing it over.

How AI enters the research workflow

Accounts of use are more consistent than the evidence for effect. Dai and Chan (2026) interviewed 28 postgraduate research students in seven focus groups at one institution and found that 27 of the 28 used generative AI somewhere in their research: ideation, literature review, explanation, data processing, programming, academic writing, editing, and translation.

Their participants were calibrated rather than credulous. They matched tools to tasks by perceived stakes and intellectual demands, used AI more heavily in low-stakes procedural work, and stayed cautious where the scholarly contribution was central. They also kept human oversight throughout, treating the model as an assistant that could be "misleading" or "totally wrong."

The policy finding is the practical one. Existing institutional guidance addressed teaching, learning, and assessment, and participants experienced it as abstract and misaligned with research practice. The authors propose researcher-oriented guidelines, built on a four-dimensional AI literacy framework, as a developmental scaffold rather than a rulebook.

The study covers a single institution, a self-selected group of 28, and self-reported accounts; students may have under-reported use for integrity reasons. It describes how a capable group uses these tools, not what the use produces.

Literature search and retrieval

A workshop report maps an agenda rather than measuring it. The CHIIR 2026 Workshop on Generative AI and Academic Search gathered researchers in human information interaction and retrieval, and its report describes systems built for document retrieval now summarizing, recommending, synthesizing, and conversing — unsettling the assumption that the system locates sources while interpretation stays with the user.

One lightning talk tested how models reconstruct scholars. Against OpenAlex and Google Scholar ground truth for 1,596 seed authors across 10 disciplines and 8 global regions, highly cited researchers were reconstructed at approximately twice the rate of lower-cited peers, testing DeepSeek R1, Llama 4 Scout, and Mixtral 8×7B.

A librarian reported a "trust gap": students often over-trusted generative search while faculty distrusted it, and single-session workshops were judged insufficient for durable literacy. The design thread participants returned to most was "friction" — keeping users engaged with the critical, sometimes uncomfortable work from which learning comes.

The report covers a single, self-selected event and largely records opinions, design principles, and research questions. Its figures belong to individual talks rather than to the workshop, and nothing in it shows that AI academic search improves or harms learning.

Screening and systematic-review automation

Systematic reviews are where automation has advanced furthest, and where its limits show. Wang et al. (2026) reflect on one interdisciplinary team's review and report that automation reduced the procedural burden mainly at abstract screening — tools such as ASReview, SWIFT-Review, Covidence, AIScreenR, and MetaMate — while data extraction, reconciliation, and synthesis stayed with human reviewers. Mentoring and peer discussion functioned as methodological infrastructure, not as courtesy.

Their conclusion is a division of labor rather than a handover: assign automation to procedural load, verify every output, and keep interpretive decisions human. The account is one team's reflection with no comparison condition, so its strategies are described rather than tested.

Zabaleta and Lin (2026) quantify the reporting problem across 888 review-automation papers carrying 14,726 annotation items. From 2023 onward, 38.0% of software and product work carried no evaluation at all, against 9.3% of Large Language Models (LLMs) papers. In screening and selection the pattern holds: software papers averaged 3.2 substantive evaluation items with 39.3% reporting none, while LLM papers averaged 7.3 items and a 3.8% no-evaluation rate.

Favorable assessment did not imply fitness for delegation. Among 118 LLM papers with positive-only evaluations, 52% still reported at least one concern that the workflow fell below the bar required for its role. Model access was overwhelmingly proprietary: 84.1% of LLM usage relied on proprietary or hosted systems, 11.0% was mixed, and only 4.9% was open-weight.

From these patterns the authors derive PRISMA-LLM, a three-layer framework whose five implementation levels are disclosure tiers rather than risk tiers. It is a proposal offered for testing, not an official extension endorsed by the PRISMA Executive. Paper-level silence, they caution, is not proof that validation is absent — it may live in a product report, a protocol, or a repository.

Qualitative coding and analysis

Qualitative analysis is the stage where interpretation is the product, which makes delegation harder to defend. The Qualitative Research page gathers the corpus evidence on AI-assisted coding, including studies showing that human–model agreement is not the same as coding quality and that errors can cascade through temporal analysis. That literature treats the model as a scaling aid whose outputs require verification against human judgment.

Martin et al. (2026) describe the role shift directly. As automated coding models are applied, the researcher moves from coding student data to validating the model's outputs; when unsupervised models cluster reasoning, the algorithm performs the initial exploratory analysis. Researchers, they argue, increasingly need data science skills alongside qualitative, quantitative, and theoretical expertise.

Their framework also supplies the check that matters here: explainable AI can reveal whether automated coding tracks semantic understanding or only keywords. A coding pipeline that agrees with human labels may still be reading the wrong thing.

Data analysis and the epistemic stakes

Martin, Rost, Koenen and Graulich (2026) press the field's knowledge production itself, and their article is this page's spine. Grounded in Hasok Chang's (2004) account of epistemic iteration — successive stages of knowledge that build on one another toward epistemic aims — they draw a parallel with the roughly 150-year development of the thermometer and argue the field may now be inside a comparable iteration.

Their central worry is epistemic rather than technical. Chang's nomic-measurement problem holds that measuring a quantity requires a law relating it to something observable, yet that law cannot be tested empirically without already knowing the quantity. AI-derived measurement functions, which emerge from training data and optimization rather than from the researcher, may intensify rather than resolve this, because they can look precise and predictive while remaining opaque.

The framework has seven phases: problem framing; instrumentation and measurement; experimentation and evidence-based inference; comparisons and replication; building norms and consensus; implementation and its consequences; and continuous refinement. The authors present these as analytical dimensions that may repeat, overlap, or be absent, not as a validated sequence.

Comparability is the phase with the sharpest equity edge. Regnault's principle requires that an instrument give the same reading under the same conditions and that instruments of a type agree — but comparability must extend across student populations, and machine learning tends to code canonical ideas better than the diverse ways students express weaker ones.

They also name an accountability problem. Researchers use pre-trained models whose training data, fine-tuning, and objectives they may not know, adding a layer of epistemic dependence; because these systems emerge from socio-technical networks, responsibility becomes hard to allocate — a "many-hands problem."

The necessary honesty is that the article reports no data and establishes no learning effects. It does not show that AI methodologies improve research or yield more valid conclusions; that comparison is posed as future work, and the authors allow that their hypothesis "may well prove incorrect."

Research writing, citation, and integrity

Writing is where AI assistance is most visible and where its failures are most consequential, because a reference is a claim of accountability. Denny et al. (2026) audited the entire ACM Digital Library — 723,930 publications and 15,872,533 references — and traced 113,588 references from 5,225 computing-education papers published from 2021 onward.

They manually verified 828 suspicious records and found 30 references containing verifiably fabricated bibliographic information across 14 papers, all from 2025 and 2026. At the SIGCSE Technical Symposium the count rose from 3 in the 2025 proceedings to 17 in 2026, appearing in 2.3% of 2026 proceedings papers. Seventeen of the 30 were hybrids pairing a real title with fabricated or incorrect authors.

Their count is a deliberate lower bound, and they present the problem as shared rather than solved by software. Authors should verify every cited work, especially when generative AI was used in writing; reviewers cannot audit every reference, so venues adopt targeted checks; publishers should improve metadata. Automated detection inherits the flaws of the metadata it treats as ground truth.

The scale effects of AI writing appear in a second bibliometric study. Wang et al. (2026) analyzed 147,074 publications from PLoS and Nature portfolio journals since 2020 and associated AI-assisted writing with smaller, junior-leaning teams. At the extreme shift from no to full AI assistance, team size was 22.1% smaller in PLoS and 45.5% smaller in Nature (Poisson $\beta = -0.250$ and -0.607, both $p < 0.01$).

Impact did not obviously suffer. About 7.34% of AI-assisted PLoS papers and 7.40% of Nature ones reached the top 5% of FWCI, above both human-written comparison groups, and matched comparisons showed 3.0% and 2.7% higher probability of top-5% FWCI (both $p < 0.01$). The data are observational, so the authors decline strong causal claims.

Persistent agents in the research environment

Beyond single prompts, persistent agents are being embedded in the research workspace itself. Alzahrani (2026) reports a 115-day, single-investigator case study of an agent with durable memory, local files, external tools, scheduled routines, and delegated roles, running in one physician-scientist's workspace.

The descriptive outcomes are large. Recoverable main-agent telemetry held 75,671 de-duplicated records across 96 active days, an active-day fraction of 0.835; the workspace held 502 memory-related files, 17 configured agent directories, and 57 skill files. A strict 25-day May subset held 627 model-completed events and 73,950,305 recorded tokens, of which 82.9% were cache reads, with approximately US$1,961 in observed system spending.

The study's main contribution is a measurement frame — PARE-M — built because the outcomes a persistent agent is meant to support, such as governance and cost per artifact, are invisible to episodic benchmarks. Its central negative finding is that aggregate interaction volume did not demonstrate reduced human input: as memory and procedures accumulated, the scope of delegated work expanded, so the strongest pattern is capacity expansion rather than proven labor substitution.

The limitations are the ones a single self-observed case invites. One researcher was user, designer, data source, analyst, and beneficiary, with no control group, no baseline period, and no independent coder for the governance events.

Simulated learners as research and evaluation instruments

Simulating students is the knowledge base's page on the technique and the phenomenon: how to build a synthetic learner whose knowledge state and errors are faithful enough to stand in for a person. This page treats the same apparatus as an instrument of research and evaluation — what a synthetic learner is *for* when an intervention, an instrument, a benchmark, or a tutor must be tested at a scale or in conditions real learners cannot supply.

The clearest use is evaluating a tutor over time. Lee et al. (2026) place an agent tutor in a 30-day relationship with a simulated learner whose mastery, from a Knowledge Tracing model trained on real-student data,

drives its answers. Evaluating 10 agent adapters, every adapter plateaued within 5–10 days far below an ideal-learning reference, a result single-session evaluation cannot reach. A calibration check against observed probe accuracy hugs the diagonal (ECE 0.049, Brier 0.033 over 1.19 million attempts).

Fidelity is the precondition, and it is measurable. Wang et al. (2026) report behavioral divergence from real student traces of DKL = 0.31 against 0.53 for the best baseline, and in a 71-rater Turing test its traces were statistically indistinguishable from real student data (52.8% accuracy, d′ = 0.15). The failure to avoid is competency bias: prompted models solve the task too well to stand in for novices.

The belief state is the part that is easy to fake. Do, Sonkar and Sachan (2026) showed that across seven models from 4B to 120B parameters, simulators abandoned an assigned misconception and re-solved from internal knowledge at near-uniform rates under targeted, misaligned, and generic feedback. They quantify this with a Selective Flip Score and lift faithfulness by up to +0.56 through training, which is the point: prompting a persona does not build a learner.

Simulated learners also serve as a controlled test bed for evaluation instruments themselves. Fan et al. (2026) paired each of three tutor bases with one fixed weak simulated learner under a pre-registered protocol and found that general-purpose helpfulness rubrics carry little pedagogical signal, with seven policies spanning 2.3 points of judged pedagogy inside a 0.25-point band of judged helpfulness. Answer-revealing turns were followed by less independent student work on every base.

The caution belongs on the page. A simulator's verdict is only as good as the simulator, and its coverage tends toward the easiest learners.

Practitioner research: SoTL and classroom inquiry

This is the strand the corpus documents least. The scholarship of teaching and learning and classroom research are practitioner inquiries — a teacher studying their own course, often on a small scale, often as self-study — and the pages collected here do not provide a researched account of AI use in that mode.

The nearest evidence is adjacent rather than on point. The postgraduate students in Dai and Chan (2026) were learning to be researchers, not studying their own teaching. The team in Wang et al. (2026) conducted a formal interdisciplinary review, not a local project. The bibliometric studies describe disciplines and publishers, not classrooms.

The honest statement is therefore a gap rather than a finding. AI-assisted practitioner inquiry is plausibly widespread and almost undocumented in this corpus; a page that presented the review-automation and bibliometric evidence as if it settled how a lecturer should use AI to study their own teaching would be overreaching.

What can be carried across is a disposition rather than a result: name the AI's role in the methods, keep interpretive decisions human, and report what was and was not verified.

What the evidence does not yet establish

- **No head-to-head comparison.** Martin et al. pose the comparison between AI-assisted and traditional methods as future work. No anchor article shows that an AI methodology yields more valid conclusions.

- **Thin designs throughout.** The anchors are a framework proposal, one team's reflective account, a workshop report, a focus-group study, and observational bibliometrics. None is a controlled trial of an AI-assisted method.
- **A reporting gap, not an audit of practice.** PRISMA-LLM reads paper-level silence; a workflow with no evaluation in its paper may still be validated elsewhere.
- **Practitioner research is under-represented.** Only a handful of pages here mention SoTL or classroom research, so the corpus cannot ground claims about teachers studying their own practice.
- **A moving target.** The tools improve faster than publication, so a finding about a 2025 workflow describes a generation of systems that may no longer exist in that form.

Common Misconceptions

- **"LLM and software papers are evaluated equally well."** Since 2023, **38.0% of software and product papers reported no evaluation at all, against 9.3% of LLM papers**. The gap is large and it runs against the assumption that newer tooling is less rigorously tested.
- **"Stratifying by task fixes the gap." The gap survives stratification**: in screening and selection, software papers averaged **3.2 substantive evaluation items with 39.3% reporting none**, while LLM papers averaged more. The difference is a systematic property of the paper class, not of the task.
- **"A positive evaluation means the workflow met its intended bar."** Among **118 LLM papers with positive-only evaluations, 52% still reported at least one concern that the workflow fell below the bar required for its role**. Half of the positive evaluations contained their own refutation.

Connected Concepts

- Research Methods in AIED — the umbrella for the designs used to study AI in education
- AI Ed Evaluation
- Interpreting and Applying AIEd Research
- Limitations in AIEd Research
- Meta-Analysis and Systematic Review
- Qualitative Research
- Quantitative Research
- Mixed-Methods Research
- Benchmark
- Educational Measurement
- Assessment Validity
- Learning Gains
- Simulating Students
- Simulation
- Learner Modeling and Adaptive Instruction

- Knowledge Tracing
- Generative AI
- Large Language Models (LLMs)
- Human-in-the-Loop
- AI Literacy
- Academic Integrity
- AI Use and Disclosure Statements
- Hallucination Risk
- Trust
- Higher Education
- Educational Development

Connected Articles

- Amid an Epistemic Iteration: How AI Methodologies May Transform the Nature of Science Education Research — a seven-phase reflective framework for how AI methodologies may transform science education research (Martin et al., 2026)
- Scaffolding systematic reviews in learning design and technology through mentoring and AI integration — one interdisciplinary review team's account of mentoring and selective AI integration (Wang et al., 2026)
- Shaping responsible GenAI use in research through AI literacy-oriented guidelines: Insights from postgraduate students — how 28 postgraduate students used GenAI across the research workflow, and the guidelines they suggest (Dai & Chan, 2026)
- Testing Our Foundations: Citation Trends, Errors, and Emerging Hallucinations in the Computing Education Literature — a field-scale audit of fabricated references in the computing-education literature (Denny et al., 2026)
- PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews — a reporting framework for AI-assisted systematic reviews, and the accountability gap it documents (Zabaleta & Lin, 2026)
- Report on CHIIR 2026 Workshop on Generative AI and Academic Search (GAI&AS) — a CHIIR 2026 workshop report on generative AI and academic search (Liu, Arguello, Hoeber et al., 2026)
- Persistent AI Agents in Academic Research: A Single-Investigator Implementation Case Study — a single-investigator case study of a persistent agent in a research workspace (Alzahrani, 2026)
- Smaller, Younger, and More Impactful: How AI-Assisted Writing Transforms Research Teams — bibliometric evidence that AI-assisted writing accompanies smaller, younger research teams (Wang et al., 2026)
- EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners — a 30-day benchmark that evaluates tutor agents against a simulated learner (Lee et al., 2026)
- BEAGLE: Behavior-Enforced Agent for Grounded Learner Emulation — a neuro-symbolic simulator that reproduces genuine novice struggle (Wang et al., 2026)

- Simulating Students or Sycophantic Problem Solving? On Misconception Faithfulness of LLM Simulators — why simulators abandon a misconception under any feedback, and how training fixes it (Do, Sonkar & Sachan, 2026)
- Rethinking LLM-Judged Helpfulness as a Pedagogy Signal: A Pre-Registered Audit Across Tutor Models — a pre-registered audit that uses a fixed simulated learner to test whether helpfulness measures pedagogy (Fan et al., 2026)

Citation

Martin, P. P., Rost, M., Koenen, J., & Graulich, N. (2026). Amid an Epistemic Iteration: How AI Methodologies May Transform the Nature of Science Education Research. *Science & Education*.

Wang, X., Dadashipour, F., Basori, Maeda, Y., & Richardson, J. C. (2026). Scaffolding systematic reviews in learning design and technology through mentoring and AI integration. *Educational Technology Research and Development*.

Dai, W., & Chan, C. K. Y. (2026). Shaping responsible GenAI use in research through AI literacy-oriented guidelines: Insights from postgraduate students. *International Journal of Educational Technology in Higher Education, 23*, 33.

Denny, P., Barbre, G., Blake, M., Hua, Y. C., Leinonen, J., Luxton-Reilly, A., Prather, J., & Reeves, B. N. (2026). Testing Our Foundations: Citation Trends, Errors, and Emerging Hallucinations in the Computing Education Literature. arXiv preprint.

Zabaleta, M., & Lin, B. (2026). PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews. arXiv preprint.

Liu, Y., Arguello, J., Hoeber, O., et al. (2026). Report on CHIIR 2026 Workshop on Generative AI and Academic Search (GAI&AS). *ACM SIGIR Forum*.

Alzahrani, A. H. (2026). Persistent AI Agents in Academic Research: A Single-Investigator Implementation Case Study. arXiv preprint.

Wang, H., Zhang, M., Bu, Y., Zhao, S. X., & Liu, M. (2026). Smaller, Younger, and More Impactful: How AI-Assisted Writing Transforms Research Teams. arXiv preprint.

Lee, U., Lee, S., Jeong, Y., Lee, E., Shin, M., & Kwon, H. (2026). EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners. arXiv preprint.

Wang, H. D., Cohn, C., Xu, Z., Guo, S., Biswas, G., & Ma, M. (2026). BEAGLE: Behavior-Enforced Agent for Grounded Learner Emulation. arXiv preprint.

Do, H., Sonkar, S., & Sachan, M. (2026). Simulating Students or Sycophantic Problem Solving? On Misconception Faithfulness of LLM Simulators. arXiv preprint.

Fan, S., Deng, B., Xu, M., Liu, J., & Zhang, H. (2026). Rethinking LLM-Judged Helpfulness as a Pedagogy Signal: A Pre-Registered Audit Across Tutor Models. arXiv preprint.

Connected FAQs

- How Do We Make a Simulated Student Behave Like a Real Learner?

- How Can AI Assist with Educational Research?

Qualitative Research

> **Qualitative research** — the family of empirical methods that study how people *experience, interpret, and make meaning* of phenomena, typically through words, observations, and artifacts rather than numbers. In AI in education, qualitative methods reveal *how* students and teachers actually experience AI tools — the meanings, tensions, harms, and mechanisms that standardized measures miss. Because AI-in-education is fast-moving and its effects are often mediated by context, perception, and contested constructs like Trust and Learner Agency, qualitative work is essential alongside quantitative designs (see Research Methods in AIED).

Questions to Consider

- A survey tells you 40% of students distrust an AI tutor; a focus group tells you *why* they distrust it. Which number feels more actionable to you, and what does the 'why' add that the percentage cannot?
- Qualitative findings are usually not statistically generalizable, yet they're often 'conceptually generalizable' — mechanisms and dynamics that transfer elsewhere. Before you read, what does it mean for a finding to be generalizable in concept but not in statistics?
- The page cautions that human–LLM coding *agreement* is not the same as coding *quality* when human consensus isn't ground truth. Have you ever treated 'two reviewers agreed' as proof something was correct? When is agreement a signal of truth, and when is it just shared error?
- If AI can now assist qualitative coding at scale, does that threaten the interpretive depth that makes qualitative research valuable, or merely automate its drudgery? How would you decide which is happening in a given study?
- Qualitative work centers under-represented voices — ethnic-minority students, skeptical nonusers — that large surveys often miss. Think of an AI-in-education claim you've heard. Whose experience of it is probably *not* captured by the headline number?
- Choose one contested construct you care about — trust, agency, or harm. Before reading, sketch how you'd study it with words and observations rather than numbers, and note what you'd lose by doing so.

Introduction

Qualitative research is not a single method but a family organized by *what* they study and *how* evidence is gathered and analyzed. What unites them is an emphasis on meaning-making, context, and depth over breadth and causal control. Qualitative findings are typically **not** generalizable in the statistical sense, but they are often *conceptually generalizable* — revealing mechanisms, categories, and dynamics that transfer to other settings. In the knowledge base's corpus, qualitative work is prominent for studying AI acceptance, trust, harm, teaching practice, and learning processes.

Major qualitative approaches

Thematic analysis

Thematic analysis identifies, codes, and interprets patterns ("themes") across qualitative data — typically interview or focus-group transcripts, open-ended survey responses, or documents. It is the most widely used approach in the knowledge base's qualitative studies. Interviews and open-ended responses are themselves self-report data, so they share the limits on what can be claimed about behavior — see that page for where self-report evidence is strong and where it breaks down. A study of the trust–utility gap in physics uses thematic analysis of student interview data to surface domain-specific skepticism and adoption preferences; a comparison of GenAI vs. teacher feedback analyzes student perceptions of usefulness and trustworthiness; and guidelines for adult AI learning derive design principles from thematic coding of expert and learner input. How AI changes teaching workflows relies on thematic analysis of educator accounts.

Coding reliability can be made an ongoing procedure rather than a one-time check. Galiç et al. (2026) code 304 noticing statements at Krippendorff's $\alpha = .803$, monitor agreement on five overlapping cases (pooled $\kappa = 0.937$), and re-code disputed statements whenever agreement fell below a 0.85 recalibration threshold before resuming; the coded statements then enter an epistemic network analysis that models which dimensions co-occur rather than a flat list of themes.

Grounded theory

Grounded theory builds a theory *from the data* rather than testing an a priori framework, using iterative coding (open → axial → selective) until theoretical saturation. It is ideal for constructing new theory about emergent AI-in-education phenomena. Liu et al. develop a grounded theory of *tool, tutor, or crutch* — a three-mode typology of how students cognitively scaffold or offload onto AI in programming education — directly theorizing Cognitive Offloading. A grounded-theory study of critical AI tutors examines whether such tutors empower or enslave learners. Human-centered GenAI feedback design uses grounded analysis across a multisite study. See also Theory Development in AI in Education for how such grounded theories feed the field's theory building.

Phenomenology and phenomenography

Phenomenological approaches study the *lived experience* of a phenomenon — what it is like to learn with AI — while phenomenography studies the *qualitatively different ways* people experience and understand a phenomenon (producing "categories of description"). The Absent Cognitive Baseline draws on students' lived experiences of Self-Assessment under AI to theorize a structural gap; a phenomenological study captures the experience of completing work with AI while knowingly not understanding it; and a socio-cultural, interpretive study analyzes how GenAI becomes a "runaway object" in mathematics academic practice.

Discourse analysis

Discourse analysis examines how language-in-use constructs meaning, identities, and power — analyzing classroom talk, written text, or interactional sequences. NSPA conducts long-horizon classroom *discourse*

analysis (here computationally assisted) to mitigate dialect bias in understanding classroom interaction; a study of ethnic-minority preparatory students analyzes collaborative *discourse* in Prompt Engineering tasks. Discourse analysis bridges qualitative interpretation with computational methods when combined with Educational NLP.

Poudyal (2026) shows how discourse coding becomes auditable when it is rendered as countable rules: across 366 abstracts and 91,405 tokens an association counts only when an actor precedes a predicate within six intervening words, and nominal proximity is excluded so that "AI governance" never counts as evidence that AI governs — a rule-based approximation, not a dependency parse, whose limits the design states.

Observations and ethnography

Observation studies watch behavior in context; ethnography extends this to sustained, immersive study of a setting, often with the researcher as participant-observer. A trio-ethnography of LLM-supported programming education traces how students' interpretations evolve; a classroom case study observes AI Literacy integration in biology. Observational methods capture *actual* behavior (what learners do with AI) rather than reported behavior — complementing the self-report surveys that dominate quantitative measurement of attitudes.

Case studies

A case study is an in-depth investigation of a bounded case (a course, an institution, a single learner) using multiple data sources. A business-school case study generates a student-informed teaching and learning framework for GenAI; a biology case study documents AI-literacy integration. Case studies trade breadth for depth and are strong for theory generation and transferable insight rather than generalization. Khlaif et al. (2026) offer a qualitative case study of 21 visually impaired undergraduates across three Palestinian universities, using thematic analysis of semi-structured interviews to show how GenAI functions as an assistive technology for inclusive learning — an example of case-study research surfacing mechanisms (personalized adaptation, teacher augmentation, educational parity) that quantitative measures miss. - Variation that was chosen is not variation that was found: three EFL learners, picked from 241 surveyed students for differing proficiency, gender and GenAI history, followed sharply divergent emotional trajectories across three tasks, yet maximum-variation cases cannot estimate how common any trajectory is (Wu, Yang and Lin (2026)).

Swidan (2026) triangulates video, the alert system's own logs, and stimulus-recall interviews for one teacher and eight students, showing that an affective signal acquired meaning only through the teacher's response; the two-stage episode coding by a single author, without independent coding or validated affect detection, marks the limit of what a one-coder case analysis can warrant.

Interviews and focus groups

Semi-structured **interviews** and **focus groups** are the primary data-collection instruments across all the above approaches. They elicit rich, contextual accounts. The knowledge base's qualitative corpus is built substantially on interviews (e.g., expertise pathways) and focus groups (e.g., the text-to-image competence

paradox, Guidelines for Designing AI Technologies to Support Adult Learning). Quality depends on careful question design, sampling for variation, and rigorous analysis.

How qualitative research appears in the knowledge base

- **Mechanism and process.** Qualitative work reveals *why* AI helps or harms. Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts uses qualitative strands to unpack mechanisms of AI-mediated learning across contexts
- **Trust, agency, and identity.** Contested, subjective constructs are often best studied qualitatively. The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students surfaces how art-and-design students negotiate ease, risk, and creative identity; GenAI as a runaway object in higher education: A socio-cultural view on AI-influenced academic practice in mathematics captures AI's role in reshaping academic identity and practice.
- **Equity and under-represented voices.** Qualitative work centers perspectives often excluded from large surveys — ethnic-minority students, skeptical nonusers. This connects to Equity.
- **Typology and taxonomy building.** A qualitative typology of ChatGPT adoption distinguishes pragmatic users from skeptical nonusers — categories that inform later survey instrument design.
- **Comparable coding across documents.** Poudyal (2026) applies 15 fixed vignettes to the public policies of 20 universities to yield 300 comparable classifications, and reports that an independent second coder matched only 57.3% of them ($\kappa = 0.395$) — making the fragility of the coding scheme visible instead of leaving agreement unstated.

AI and qualitative analysis

A distinctive recent development is using LLMs to assist qualitative coding. The knowledge base's evidence is cautionary: Comparing human and LLM ordered coding of qualitative data: How coding differences cascade through temporal analysis shows LLM and human coding diverge, with errors cascading through temporal analysis; Agreement Is Not Quality shows that human–LLM coding *agreement* is not the same as coding *quality* when human consensus is not ground truth. LLM-assisted coding can scale and accelerate qualitative analysis, but its outputs require verification against human judgment — an important intersection of qualitative research with Educational NLP and AI Ed Evaluation.

The fluent-output problem and warrantability. Holster (2026) sharpens why accuracy and disclosure are insufficient standards for AI-assisted qualitative work. Because LLMs reorganize corpora in minutes into fluent topics, quotations, and prevalence claims, they can conceal the analytic pathway that produced them — and people tend to rate easily processed, fluent output as more true. Holster proposes **warrantability** as a complement to accuracy and disclosure: an AI-assisted interpretation is warrantable when the pathway from source data to claim remains *inspectable, contestable, and revisable*. Its constructive machinery is **semantic lenses** (documented reorganizations of a corpus across levels of abstraction) and a claim-relative repertoire of **warrant artifacts** — source-linked topic tables, lens stacks, and evidence rivers — designed into tools so that fluent analysis also produces a retraceable pathway record. This extends the field's audit-trail tradition into the generative era and gives reviewers something concrete to contest beyond a final interpretation. - **Reliability is not accuracy in multi-agent LLM coding.** A literature-informed pipeline in which two AI

coders coded independently, debated and reconciled disagreements produced inter-coder agreement above Cohen's kappa 0.85 on every dataset and label while criterion F1 ranged from 0.31 to 0.89 (mean 0.68, SD 0.16) — high agreement between agents that were both wrong. Longer codebooks (t = -11.702) and more similar excerpts (t = -9.249) reduced initial accuracy, and discussion turns correlated positively with accuracy (t = 7.997) while correctly resolved conflicts and collaborating modes correlated negatively (t = -9.720 and -8.420), so convergence is a weak proxy for correctness. The practical implication is that AI-assisted coding needs checklist-level adjudication against a human reference rather than agent-to-agent agreement as its quality signal. (How AI Coders Discuss, Disagree, and Reach Consensus: Challenges and Opportunities for LLM-Based Qualitative Coding)

Strengths and limitations

- **Strengths:** deep ecological and conceptual insight; surfaces unexpected phenomena, risks, and mechanisms; essential for theory-building (see Theory Development in AI in Education); captures meaning, context, and contested constructs; centers under-represented perspectives; strong for studying fast-moving phenomena where standardized measures lag.
- **Limitations:** limited statistical generalizability; interpretive and researcher-dependent (reliability concerns); small samples; weaker support for causal claims; findings can be hard to synthesize across studies; time- and labor-intensive.

Qualitative and quantitative methods are complements, not rivals — see Research Methods in AIED for how they contrast and triangulate, and mixed methods for designs that combine them.

Common Misconceptions

"Qualitative findings are ungeneralisable because the samples are small." They are usually not *statistically* generalizable and are frequently *conceptually* generalizable — the mechanisms and dynamics they identify transfer to other settings even where the frequencies do not. A focus group that explains why students distrust a tutor has produced a mechanism a survey cannot, and discarding it for lacking a confidence interval discards the part that travels.

"AI can now do qualitative analysis, so the method scales." It scales the coding and not the interpretation. Where the corpus shows this working well it is because the coding task was made comparable first — one study applied **15 fixed vignettes** across the public policies of **20 universities** to yield **300 comparable classifications**, which is a structured-instrument design rather than an open interpretive one. The insight in qualitative work is in the category construction, and that is what a model inherits rather than produces.

"Saturation is a property of the number of participants." It is a property of the analysis: you stop when new data stop producing new codes. Two studies with identical sample sizes can be equally far from saturation, which is why a report that cites a participant count as evidence of adequacy has not demonstrated anything about coverage.

"Quantitative and qualitative findings compete." They answer different questions: a survey tells you how many students distrust a tutor, and interviews tell you why. Treating them as rival accounts of the same thing produces the false choice that review sections keep reproducing.

Connected Concepts

- Research Methods in AIED
- Mixed-Methods Research
- Quantitative Research
- Theory Development in AI in Education
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Educational Measurement
- Educational NLP
- AI Ed Evaluation
- Equity
- Trust
- Learner Agency
- Cognitive Offloading
- Self-Report Measures

Connected Articles

- The chain behind the claim: Warrantability in AI-assisted qualitative research — warrantability standard for AI-assisted qualitative analysis
- Tool, tutor, or crutch?: a grounded theory of cognitive scaffolding and offloading in AI-assisted programming education — Tool, Tutor, or Crutch: a grounded theory of AI-assisted programming
- Beyond Perspectives: A Trio-Ethnography of Interpretation Evolution in LLM-Supported Programming Education — A trio-ethnography of interpretation evolution in LLM-supported programming
- The Absent Cognitive Baseline: Theorizing a Structural Gap in AI-Native College Students' Academic Self-Assessment — Theorizing a structural gap in AI-native students' self-assessment
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox in text-to-image GenAI use
- Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration — Trust–utility gap in physics education
- Comparing Generative AI and teacher feedback: Student perceptions of usefulness and trustworthiness — Comparing GenAI and teacher feedback: student perceptions
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI tutor safety and pedagogical harms
- A case study of integrating AI literacy education in a biology class — Case study of AI-literacy integration in a biology class
- Pragmatic users and skeptical nonusers: A qualitative typology of ChatGPT adoption in physics education — A qualitative typology of ChatGPT adoption in physics

- Scaffolding critical engagement with GenAI: Transforming ethnic minority preparatory students' collaborative discourse in prompt engineering tasks — Collaborative discourse in prompt engineering among ethnic-minority students
- Comparing human and LLM ordered coding of qualitative data: How coding differences cascade through temporal analysis — Comparing human and LLM ordered coding of qualitative data
- Agreement Is Not Quality: Blind Expert Verification of Human and LLM Qualitative Coding When Human Consensus Is Not Ground Truth — Agreement is not quality in LLM qualitative coding
- Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts — Unpacking mechanisms of AI-mediated learning across contexts
- Generating a student-informed teaching and learning conceptual framework for GenAI in business schools: a case study — Student-informed GenAI framework via case study
- Critical AI Tutors: Empower or Enslave? — Critical AI tutors: empower or enslave
- GenAI as a runaway object in higher education: A socio-cultural view on AI-influenced academic practice in mathematics — GenAI as a runaway object in higher-education mathematics
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- Engagement or disengagement: understanding the emotional dynamics of EFL learners in GenAI-assisted writing from the sociocultural perspective — EFL learners' emotional engagement in GenAI-assisted writing: a longitudinal multiple-case study

Quantitative Research

> **Quantitative research** — the family of empirical methods that collect and analyze *numerical* data to describe patterns, test relationships, and estimate causal effects. In AI in education, quantitative methods quantify whether and how AI tools affect learning outcomes, engagement, Motivation, and Self-Efficacy, and model the psychological and behavioral mechanisms of AI use. They provide the breadth, precision, and causal inferential power that qualitative methods trade away for depth and context.

Questions to Consider

- 'Students who use an AI tutor score higher' — before you read, is this a claim about causation or correlation, and what single piece of evidence would convert one into the other?
- A cross-sectional survey can test a complex mediational model yet never establish causation. Why might two variables be correlated in a survey even when neither causes the other? Can you think of a way to be genuinely misled by such a correlation in education?
- Quantitative instruments are only as good as what they measure — and the page notes instruments can measure the wrong construct. When you fill out a self-report survey about 'confidence' or 'engagement,' what could it actually be capturing instead, and how would you find out?
- An RCT randomly assigns learners to conditions to estimate a causal effect. What makes random assignment powerful, and what practical and ethical problems arise when the 'treatment' is a possibly-helpful AI tool that some students are being denied?
- Longitudinal designs track the same learners over time — essential for distinguishing AI-inflated performance from durable learning. Why would a single snapshot of high scores fail to reveal whether learning actually happened?
- Quantitative work provides breadth and causal power; qualitative work provides depth and meaning. Before reading the pairing, where do you think numbers alone have most likely misled you about a learning claim, and what method would you add to check it?

Introduction

Quantitative research spans descriptive designs (measuring prevalence and patterns), correlational/observational designs (testing relationships among variables), and experimental and quasi-experimental designs (estimating causal effects). What unifies them is the systematic reduction of observations to numbers, analyzed with statistics, and the priority placed on **reliability, validity, and generalizability** — the core concerns of Educational Measurement.

Major quantitative approaches

Survey and correlational research

Cross-sectional surveys measure self-reported attitudes, perceptions, motivation, Self-Efficacy, and technology acceptance, often modeled with regression or structural equation modeling (SEM/PLS-SEM) to test hypothesized relationships and mediators. These dominate the knowledge base's corpus, particularly for acceptance, motivation, and psychological-mechanism questions. Acceptance of AI-assisted English tools builds on the TAM with SEM; GenAI adoption pathways uses PLS-SEM, fsQCA, and importance-performance mapping; teacher AI literacy uses factor-validated surveys grounded in Self-Determination Theory.

- **Strengths:** large samples; broad, low-cost coverage; tests complex mediational models; feasible for attitudes that are hard to observe.
- **Limitations:** cross-sectional data cannot establish causation; self-report bias; convenience sampling limits generalizability; mediators inferred from covariance, not manipulation. See Self-Report Measures for the instrument-side treatment of these limits.
- **A saturated mediation model cannot test its own ordering.** A single-wave survey of 1,020 nursing students split a total effect of 1.36 into a direct 0.92 and an indirect 0.44 through self-regulated learning, 32.35% of the total, with a model that has as many free parameters as observed covariances and so reproduces the data by construction (Li et al. (2026)). **A near-zero total indirect effect can hide two live paths.** In one self-report wave of 568 design students, the indirect association ran 0.0929 through promotion focus and -0.0884 through prevention focus, summing to 0.0045 while the direct path carried 98.7% of the total (Wang et al. (2026)).

Experimental and quasi-experimental research

Experiments randomly assign learners to conditions (e.g., AI tutor vs. human tutor, or AI-scaffolded vs. unassisted) to estimate causal effects on outcomes. **Randomized controlled trials (RCTs)** are the gold standard for internal validity. A randomized field study of human support plus AI tutoring and an RCT on generative AI in teaching use assignment to isolate causal effects. **Quasi-experimental** designs (pre/post, matched groups without randomization) are more feasible in intact classrooms but weaker on causal claims.

Kestin et al. (2025) adopt a within-subject crossover instead: every student meets the same physics content twice, once in an in-class Active Learning lesson and once through the course's own AI tutor, with pre- and post-tests around each, so each learner serves as their own control and between-person differences cancel.

- **Strengths:** strongest causal inference; clean outcome measurement; supports effect-size estimation and efficacy claims.
- **Limitations:** costly and slow; artificial conditions reduce ecological validity; fast-changing AI tools date experiments quickly; small samples underpower detection of effects; ethical constraints on withholding helpful tools.
- **A group-randomized access trial needs an uptake check.** With about 15% of students in treated classrooms ever using the tutor, the study's intent-to-treat estimate reflects the effect of

introducing the tool — including the permission and substitution it carried — rather than the isolated effect of individual sessions (Liu et al. (2026)).

Longitudinal research

Longitudinal designs track the same learners over time, capturing change, growth, and durable learning that single-time-point measurement misses. A longitudinal LMS study tracks students across a school year. Longitudinal designs are essential for distinguishing AI-inflated performance from durable learning.

Between-dataset comparisons need a fixed working point: a structural check of synthetic educational data found that analyzing each dataset at its own threshold reversed a contrast that held at a shared point, and that its surrogate comparison needed only the synthetic data and permutations of itself - a permutation-based null rather than an absolute threshold (Inoue & Yasutake (2026)).

Computational and psychometric quantification

Quantitative methods also include the direct measurement of constructs via instruments — the domain of Educational Measurement and Item Response Theory. The knowledge base's GLAT is a 20-item quantitative instrument validated with IRT; measurement instruments across AI literacy, acceptance, and self-efficacy provide the validated scales on which survey and experimental research depend.

Bibliometric analysis is a further quantitative family: Sriram et al. (2026) map 1,403 Medical and Health Professions Education publications through country, institution and keyword co-occurrence networks, reading a literature's shape rather than appraising its studies — which is what makes their conclusion, that AI Governance scholarship has not kept pace with capability testing, a claim about the field and not about learning.

How quantitative research appears in the knowledge base

- **Efficacy and causal claims.** RCTs and quasi-experiments test whether AI tools improve learning (Access is Not Enough: Human Support Improves Engagement with AI Tutoring, Generative AI Can Harm Teaching, Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study).
- **Preregistration and replication.** Meyer et al. (2026) state their hypotheses and analysis plan before the trial and pool the randomized comparison across two semesters and two large asynchronous courses, so the estimate rests on a fixed plan and a replication rather than a single sample.
- **Mechanism modeling.** SEM/PLS-SEM tests mediators and moderators of AI adoption and learning (Decoding symmetric and asymmetric pathways in generative AI learning adoption: a multi-method study, Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups, Teacher education for artificial intelligence literacy through a self-determination theory perspective).
- **Panel models that separate within- from between-person effects.** Wu and Lu (2026) estimate a random-intercept cross-lagged panel model over three waves of collaborative-writing data, which

separates stable differences between students from within-person temporal order — the distinction that licenses reading heightened reliance as preceding a fall in perceived agency rather than merely attending it.

- **Measurement and scale development.** The knowledge base documents quantitative instrument development and validation (GLAT, Educational Measurement).
- **Performance versus durable learning.** Barcaui (2025) randomizes 120 students to AI-assisted or traditional study and measures retention with a surprise 20-question test 45 days after the intervention, so the outcome is what survived the delay rather than what appeared at the end of the session.

Strengths and limitations

- **Strengths:** precision and statistical power; generalizability to defined populations; causal inference (with experimental designs); efficient large-sample coverage; cumulative and comparable across studies.
- **Limitations:** captures what is measurable, often missing process, meaning, and context (see Qualitative Research); self-report bias; instruments can measure the wrong construct (see measurement issues); correlation without causation; can be artificial and slow relative to AI change.

Quantitative and qualitative methods are complements — quantitative work provides breadth and causal power, qualitative work provides depth and meaning. Mixed-methods designs combine them. See Research Methods in AIED for the full method comparison and the contrasts among experimental, survey, qualitative, and other designs.

Common Misconceptions

- **“An intent-to-treat estimate describes what the tool does.”** In a group-randomized access trial where **about 15% of students in treated classrooms ever used the tutor**, the ITT estimate reflects **the effect of introducing** the tool rather than the effect of using it. Low uptake makes an ITT figure a statement about implementation, and reporting it as a tool effect overstates what was measured.
- **“Performance on the task is the outcome.”** Barcaui (2025) randomises **120 students** to AI-assisted or traditional study and measures **retention** — the design that separates immediate performance from durable learning. A study that stops at the task has measured the easier quantity.
- **“Cross-dataset comparisons are straightforward.”** A structural check of synthetic educational data found that **analyzing each dataset at its own threshold reversed a contrast that held at a shared working point**. The comparison’s sign depended on an analytic choice, which is the kind of fragility a pre-registered working point exists to prevent.

Connected Concepts

- Research Methods in AIED

- Qualitative Research
- Mixed-Methods Research
- Educational Measurement
- Item Response Theory
- RCT
- Learning Gains
- Student Engagement
- Self-Efficacy
- Technology Adoption Models
- Self-Report Measures

Connected Articles

- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — A randomized field study of human support plus AI tutoring
- Generative AI Can Harm Teaching — Generative AI can harm teaching: an RCT
- Acceptance of AI-assisted English language learning tools in higher education: Psychological correlates across disciplinary and proficiency groups — Acceptance of AI-assisted English learning tools
- Decoding symmetric and asymmetric pathways in generative AI learning adoption: a multi-method study — GenAI adoption pathways (PLS-SEM, fsQCA)
- Teacher education for artificial intelligence literacy through a self-determination theory perspective — Teacher AI literacy through self-determination theory
- GLAT: The generative AI literacy assessment test — GLAT: an IRT-validated GenAI literacy test
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond — A longitudinal AI-integrated LMS study
- Do Gains from Generative AI-Enabled Adaptive Pretesting Persist? Evidence from a Retention Study — Adaptive pretesting and retention
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — A group-randomized access trial needs an uptake check
- Ethical and responsible use of artificial intelligence in medical education — Bibliometric analysis is a further quantitative family: Sriram et al.
- Generative artificial intelligence use and interpersonal educational interaction among nursing students: self-regulated learning as a statistical mediator — Generative artificial intelligence use and interpersonal educational interaction among nursing students: self-regulated learning as a statistical mediator

- The double-edged sword effect of AI technological disruption awareness on design innovation competence: the mediating role of regulatory focus and the moderating role of AI critical thinking — AI technological disruption awareness, design thinking mindset, and design innovation competence among design students

Mixed-Methods Research

> **Mixed-methods research** — the design and practice of intentionally combining quantitative and qualitative strands within a single study so that their strengths complement and their weaknesses offset each other. In AI in education, mixed-methods designs are widely used because AI effects are simultaneously measurable (learning gains, engagement) and meaning-laden (trust, Learner Agency, identity) — and neither a survey nor an interview alone captures both.

Questions to Consider

- Suppose a survey shows students report high satisfaction with an AI tool, but test scores don't improve. Which number is 'right'? The page argues that combining quantitative and qualitative strands lets each explain the other — how might an interview explain what the numbers alone cannot?
- A common view is that numbers are objective and interviews are anecdotal, so quantitative evidence is superior. The page instead treats the two as complementary — breadth and precision from numbers, depth and meaning from words. When does a number without context mislead more than an interview?
- One design pattern (sequential explanatory) collects quantitative data first, then uses interviews to explain surprising results. Can you think of an educational outcome that was puzzling numerically until qualitative accounts revealed the mechanism?
- Triangulation is the core value: when independent strands converge, confidence rises, and when they diverge, the discrepancy itself is informative. Have you ever had two sources of evidence about the same thing contradict each other — and what did you learn from the conflict?
- Mixed methods can simultaneously capture effects (how much learning gain) and meaning (trust, identity, agency) — things no single survey or interview captures alone. If you were studying whether an AI tool helps students, what quantitative and qualitative questions would you pair, and in what order?

Introduction

Mixed-methods designs integrate the breadth, precision, and causal power of quantitative methods with the depth, context, and meaning of qualitative methods. The value proposition is **triangulation**: when independent strands converge on the same conclusion, confidence increases; when they diverge, the discrepancy itself is informative.

Of 394 GenAI higher-education studies, 213 (54%) used mixed methods, 109 (28%) quantitative and 72 (18%) qualitative designs — the field's most common choice (Lin et al. (2026)).

Common design patterns

- **Sequential explanatory (QUAN → qual).** Quantitative data are collected first, then qualitative data explain or contextualize surprising or significant quantitative findings. A mixed-method study of GenAI and sustainable learning pairs three-wave surveys with educator interviews to explain the quantitative pattern of enhancement-to-over-reliance.
- **Sequential exploratory (QUAL → quan).** Qualitative work builds theory, generates hypotheses, or informs instrument design that is then tested quantitatively. A qualitative typology of ChatGPT adoption yields categories that can inform later survey design.
- **Exploratory sequential with measurement invariance.** Bu and Li (2026) code interviews to identify the model's four dimensions, build a 22-item instrument from them, and then test configural, metric, and scalar invariance across gender and disciplinary area on an analytic sample of 642. The design shows a qualitative strand feeding a survey instrument and an invariance test confirming the constructs behave the same way across groups.
- **Convergent/parallel.** Quantitative and qualitative strands run simultaneously and are integrated in analysis. The competence-paradox study uses instructor focus groups, a student survey, and follow-up interviews in parallel; the trust–utility gap study combines survey and interview evidence on physics students' AI adoption.

How mixed methods appear in the knowledge base

- **Explaining mechanisms.** Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts combines strands to unpack the mechanisms of AI-mediated learning across discipline-institution contexts, where quantitative differences alone would be opaque.
- **Complementing outcome data with experience.** AI tutor safety pairs quantitative harm indicators with qualitative accounts of pedagogical harm; The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students pairs quantitative survey results with qualitative negotiation-of-identity accounts.
- **Integration without pooling.** Wang and Zhao (2026) coordinate a survey (N = 131), human coding of 66 Critical Engagement texts, and programming logs (N = 1,423) that come from different samples and are never merged, assigning the AI-free trace branch a boundary-test role rather than a confirmatory one — each strand is given a distinct inferential job instead of being reported side by side.
- **Design and evaluation.** A multisite experiment on GenAI feedback design combines experimental outcome measurement with qualitative feedback from learners, integrating quantitative effect estimation with design guidance.
- **Process evidence inside a large trial.** Mata et al. (2026) pair system observation and discussions with administrators against a four-year randomized evaluation of 8,708 students across eight semesters, powered to detect effects of 0.05 standard deviations, so the same study explains the organizational conditions that sustained a chatbot program and reports tightly bounded nulls on GPA and persistence.

- **Triangulating a policy phenomenon.** A study of student-privacy deferral in EdTech pairs twelve semi-structured interviews with a 48-platform document audit scored by two coders for inter-rater reliability (mean Cohen's κ = 0.781), using the interviews to explain why privacy is postponed and the audit to show the disclosure pattern that deferral produces — a convergent design in which neither strand alone could support the claim (Nair & Greenstadt, 2026).

Strengths and limitations

- **Strengths:** triangulation increases confidence; quantitative breadth plus qualitative depth; can explain unexpected results and bridge mechanism and magnitude; produces both effects and meaning; well-suited to complex, contextual AI-in-education phenomena.
- **Limitations:** complex, resource-intensive, and methodologically demanding; integration can be shallow if strands are merely reported side-by-side rather than genuinely merged; still inherits the weaknesses of each strand (e.g., self-report bias in surveys, researcher dependence in interviews); requires proficiency in both methodological traditions.
- **A clustering limit that bounds the inference.** Alshehri et al. (2026) assign two intact classes (n = 31, n = 22), so with only two clusters the reported t-tests ignore the intraclass nesting and multilevel models are not estimable, making the significance tests optimistic about what the design can support.
- **Instrument choice can invert a computational strand.** VADER and a fine-tuned RoBERTa assigned opposite valence to the same post (0.9413 strongly positive under VADER, −0.9209 under RoBERTa), so a corpus's quantitative reading can turn on which classifier is used (Geraili Meykola et al., 2026).

Relationship to the broader methods landscape

Mixed-methods sits between the quantitative and qualitative traditions, drawing on the strengths of each while adding the design discipline of intentional integration. It is a methodological response to the recognition that AI-in-education phenomena are both effectful and meaning-laden — and that the field advances fastest when breadth and depth are combined (see Research Methods in AIED). It connects to Educational Measurement (quantitative instruments), Theory Development in AI in Education (qualitative theory-building), and AI Ed Evaluation (integrating outcome and experience evidence).

Common Misconceptions

- **"Mixed methods is a niche choice in AI education research."** Across **394 GenAI higher-education studies**, mixed methods was the **most common research design (213 studies, 54%)**, followed by quantitative (109, 28%) and qualitative (72, 18%). The field's dominant design is not the one its methodological debates assume.
- **"Observational and interview evidence can carry a system claim."** Pairing system observation and Administrators discussions against a **four-year randomized evaluation of 8,708 students across eight semesters**, powered to detect effects of **0.05 standard deviation**, shows what the

qualitative strand cannot do alone: detect a small effect reliably. Mixing methods is not a way to transfer power between strands.

- **“Triangulation means two weak methods make a strong claim.”** The value of the pairing is that each strand answers a different question. A design that runs both and then reports the qualitative finding as confirmation of the quantitative one has not triangulated, it has restated.

Connected Concepts

- Research Methods in AIED
- Qualitative Research
- Quantitative Research
- Educational Measurement
- Learning Gains
- Theory Development in AI in Education
- AI Ed Evaluation
- Student Experience

Connected Articles

- From enhancement to over-reliance: A mixed-method study of generative AI and sustainable learning performance — From enhancement to over-reliance (surveys + interviews)
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox (focus groups + survey + interviews)
- Trust-utility gap in introductory physics education: Students’ adoption, domain-specific skepticism, and preferences for AI integration — Trust–utility gap (survey + interviews)
- Same AI, different pathways: Unpacking mechanisms of AI-mediated learning across discipline-institution contexts — Mechanisms of AI-mediated learning across contexts
- Human-centered GenAI feedback design in higher education: A multisite experiment on direct, reflective, and hybrid approaches to scientific argumentation — Human-centered GenAI feedback design (multisite)
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI tutor safety and pedagogical harms
- Pragmatic users and skeptical nonusers: A qualitative typology of ChatGPT adoption in physics education — A qualitative typology of ChatGPT adoption in physics
- "We’ll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — “We’ll Fix It Later”: Education, AI, and the Deferral of Student Privacy in EdTech
- Analyzing Artificial Intelligence in Education Discourse on Bluesky: A Computational Social Media Analysis — VADER and a fine-tuned RoBERTa assigned opposite valence to the same Bluesky post (Geraili Meykola et al., 2026)

Design-Based Research

> **Design-based research (DBR)** — a methodological approach that iteratively designs, implements, and refines an educational intervention in authentic contexts, cycling between theory, design, and real-world practice to produce both a usable artifact and validated design principles. In AI in education, DBR is the method of choice for developing AI learning environments, pedagogical models, and teacher-training programs that must work in the messy reality of classrooms — trading the causal control of experiments for ecological authenticity and iterative refinement.

Questions to Consider

- Design-based research iteratively designs, implements, and refines an intervention in real classrooms, cycling between theory and practice. How is that fundamentally different from a controlled experiment — and why might a classroom researcher prefer it?
- DBR deliberately trades causal control for ecological authenticity. If you can't say for sure WHAT caused a learning gain, what is the knowledge still worth?
- DBR produces two things at once: a usable artifact and validated design principles. Which of those two outputs matters more to you — a tool that works, or a principle you can apply elsewhere?
- A strength of DBR is high practical relevance; a limitation is that findings are context-bound and hard to generalize. When would you trust a DBR finding enough to apply it in a very different setting?
- Without an unassisted, controlled outcome measure, DBR learning gains can reflect the same 'AI-inflated performance' problem it studies. How would you design a DBR study so its reported gains actually mean learning, not assisted performance?

Introduction

DBR is a *design* tradition, not a data tradition: it does not fit neatly into the quantitative/qualitative/experimental contrast. It deliberately combines elements of all three — collecting both outcome and process data across iterative cycles — to answer *"how do we design this AI learning environment to work in practice?"* rather than *"does X cause Y?"*. It is closely related to Learning Design (which specifies the design process) and to usability evaluation (which feeds refinement), but is distinguished by its sustained, theory-driven, multi-cycle character and its dual goal of improving practice *and* generating theory.

The DBR cycle

DBR is not a single design but an iterative loop, typically comprising:

1. **Needs analysis** — understanding the problem, context, and learners in authentic settings.
2. **Design** — articulating an intervention and its underlying theoretical rationale.
3. **Implementation** — deploying the intervention in a real classroom or program.

4. **Refinement** — analyzing data, revising the design, and iterating (often over multiple cycles).
5. **Theory and artifact output** — producing both a usable intervention and generalizable design principles or a validated model.

The canonical AIEd example is the AI-Assisted Collaborative Learning (AACL) Model study, which ran a four-phase DBR cycle — needs analysis, model design, an eight-week classroom implementation with Indonesian undergraduates, and model refinement — iterating on a four-stage learning cycle (problem identification → AI-assisted collaborative inquiry → collaborative Problem Solving → reflection and presentation).

How DBR appears in the knowledge base

- **Developing learning models.** The AACL Model study uses DBR to develop and evaluate an AI-assisted collaborative learning model targeting critical thinking and problem-solving in higher education.
- **Building AI-literacy teacher training.** Le et al. develop and evaluate a DBR GenAI-literacy training intervention for Teacher Education students; Baran et al. use DBR across 2023–2025 to design professional learning for critical AI literacy grounded in Human-Centered AI principles.
- **Designing institutional standards.** Crompton et al. use DBR across two iterative macro cycles and 114 participants to develop six faculty technology-integration standards.
- **Iterative system implementation.** Rienties et al. describe six iterative DBR studies (18 months, 498 participants) implementing the Open University's AIDA AI assistant using an embedded-systems approach.
- **Scaffolding and intervention design.** GenAI critical-thinking scaffolding and other intervention-development studies use DBR to design and refine AI-based scaffolds.
- **Youth- and expert-guided curriculum design.** Moore et al. (2026) use a two-year DBR process with a youth and AI-expert advisory board to design a science-integrated AI literacy / ML curriculum for high school, refining the design across cohorts and measuring ML-knowledge gains — an example of DBR as participatory co-design that integrates youth voice into the design cycle.
- **Iterative rubric co-refinement as DBR.** Yaşar et al. (2026) exemplify DBR's iterative-refinement character applied to the assessment instrument itself: they treated the rubric as a revisable design artifact and cycled through co-refinement with an LLM — clarifying performance descriptors and explicitly accepting implicit indicators of learning — which raised LLM–human agreement on 80 student design posters from 54.75% to 81.25% (Cronbach's Alpha 0.393 → 0.798). The study positions the rubric as a mediating interface between human pedagogical intent and machine inference, and its role-aware prompting (instructor, peer-reviewer, grant-reviewer) shows how design choices shape evaluative output — a DBR-style demonstration that the assessment instrument, not just the intervention, is a design object.
- **Co-designing early-childhood AI literacy.** Lee (2026) uses DBR to co-design, pilot, and refine the Play With AI (PL-AI) curriculum across iterative cycles with two pre-K and two kindergarten teachers, drawing on teacher surveys, 32 hours of classroom video, field notes, and design-meeting transcripts. The study documents how DBR supports iterative refinement of

developmentally appropriate AI literacy activities and yields transferable design principles (embodied play, tangible coding, guided dialogue, teacher co-design).

- **Expert review as the refinement evidence — and an honest scope statement.** Dong et al. (2026) submit their initial four-track robotics curriculum to five experts who rate it on eight dimensions, then revise in response: independent PPO implementation moves to an extension and a Python prerequisite is added after four of five experts flag cognitive load. Dispersion drives the revisions as much as the means do — motivating context averaged 4.00 with SD = 1.73 and a lone 1/5 rating — and the authors state plainly that the revised framework remains unevaluated pending student data.
- **Triangulation, and the limit it cannot cross.** Kenzhebayeva et al. (2026) run a role-rotation model through five DBR phases — problem analysis, pedagogical design, implementation, evaluation, refinement — across eight weeks with 62 participants, triangulating reflective journals, interviews, observational notes, and student-generated products with member checking. The design lesson is in what the authors claim for it: with no pre-post competence measure and no comparison group, they present the evidence as engagement during the intervention rather than demonstrated competence gains, which is exactly the boundary a multi-source DBR design can and cannot cross.

Strengths and limitations

- **Strengths:** high ecological validity and practical relevance; produces both usable artifacts and theory; responsive to the complexity of real classrooms and evolving AI tools; well-suited to developing a model and refining it based on authentic implementation evidence; captures how an intervention actually works (or fails) in practice.
- **Limitations:** weak internal validity (few/no control groups); findings are context-bound and hard to generalize; long timelines; difficult to isolate which design element caused an outcome — DBR demonstrates feasibility and improvement but cannot attribute learning gains to a specific mechanism.

DBR trades the causal control of experiments for ecological authenticity and iterative refinement: its evidence is strongest as proof-of-concept and design guidance rather than causal efficacy. Reading DBR learning gains requires the same caution as other designs — without an unassisted, controlled outcome measure, gains can reflect the same AI-inflated-performance confound documented under learning gains.

Relationship to other methods

DBR is the signature method of the learning sciences — the interdisciplinary field that studies learning and the design of learning environments, and that treats building an intervention and studying it as a single activity rather than two. It is complementary to, not a rival of, other research methods (see Research Methods in AIED for the full landscape). Where experiments establish causality and surveys establish breadth, DBR establishes *feasibility and design knowledge* — whether an intervention can be built to work in authentic practice and what design principles support it. It frequently pairs with usability evaluation (to refine the interface) and qualitative methods (to understand how learners experience the intervention). A

mature DBR program typically culminates in an efficacy trial or measurement study that tests the developed intervention's causal effects at scale.

Common Misconceptions

"Design-based research is a qualitative method." DBR belongs to a *design* tradition rather than a data tradition: the quantitative/qualitative/experimental contrast does not capture it, because its unit of work is the iterated artifact rather than a single measurement plan. Studies within DBR can be quantitative, qualitative or experimental; what makes them DBR is that the design is being revised as the finding is produced.

"Iterative refinement makes the design immune to the confound other methods suffer." Iteration trades one threat for another. Refining a design mid-study means the final version differs from the one that produced the early evidence, so a claim about "the intervention" spans several interventions. Reporting which revision produced which outcome is the discipline's responsibility, and it is frequently left implicit.

"Because DBR produces a working artefact, it has demonstrated effectiveness." A design that works in the site that co-produced it has demonstrated local viability, which is a different claim from effectiveness. The artifact carries the adaptations made for that context, and transferring it transfers assumptions that were never stated as assumptions.

"Treating an instrument as a revisable design artefact is a departure from DBR." It is DBR's iterative character applied to the measurement rather than the intervention: one study in this corpus treated the rubric itself as the artifact, cycling through co-refinement with an LLM. That extension is worth noting because it makes the instrument's own development part of the evidence.

Connected Concepts

- Research Methods in AIED
- RCT
- Quantitative Research
- Qualitative Research
- Mixed-Methods Research
- Usability Research
- Learning Design
- Educational Measurement
- Learning Gains
- Limitations in AIEd Research
- Theory Development in AI in Education
- Learning Sciences

Connected Articles

- Design-based research for developing an AI-assisted collaborative learning model to enhance critical thinking and problem-solving skills in higher education — DBR for an AI-Assisted Collaborative Learning Model

- Development and evaluation of artificial intelligence literacy training for teacher education students — DBR for AI-literacy training in teacher education
- Designing faculty standards for technology integration in higher education institutions: a design-based research study — DBR for faculty technology-integration standards
- Human-centered AI for teacher educators: Designing professional learning for critical AI literacy — Human-centered AI for teacher educators (DBR)
- New systems of learning for distance learning institutions? A six-study review of implementing AIDA — Six DBR studies implementing AIDA at the Open University
- Scaffolding critical thinking with generative AI: Design principles for integrating large language models in higher education — DBR for GenAI critical-thinking scaffolding
- Design of a science integrated secondary school AI literacy curriculum: A youth & AI expert guided design-based research approach — DBR for a science-integrated AI literacy curriculum (Moore et al. 2026)
- Play with AI (PL-AI): A play-centered, design-based curriculum for AI literacy in pre-K and kindergarten — Play With AI (PL-AI): play-centered AI literacy curriculum for pre-K and kindergarten (Lee 2026)
- From evaluation to emulation: LLMs as agents of iterative pedagogical design — LLMs as agents of iterative pedagogical design

Usability Research

> **Usability research** — the empirical study of how users interact with a software system, and of its usability, usefulness, and user experience (UX). Drawn from human–computer interaction (HCI), usability research evaluates whether an AI educational tool is usable, learnable, efficient, and satisfying — the qualities that determine whether learners actually adopt and benefit from it. It is distinct from, but complementary to, qualitative inquiry into learning phenomena and quantitative efficacy: usability research focuses on the *interaction between person and system*, not on learning outcomes per se.

Questions to Consider

- Can you recall a software tool — educational or otherwise — that was pedagogically sound or genuinely powerful, yet you stopped using it because it was confusing or frustrating? That failure is exactly what usability research tries to explain before it costs learning.
- A common assumption is that a tool's educational effectiveness can be judged by whether learning gains improve. But the page argues a tool can be unusable and still seem to 'work' in a trial, or usable yet fail to teach. Why might a study showing learning gains still miss that the tool is a pain to use in practice?
- Before reading the methods, how would you go about finding out whether an AI tutor is confusing, frustrating, or error-prone for learners? What would you actually do or observe — and what would a user's own report of satisfaction miss that careful observation would catch?
- Think-aloud is a core method: users speak their thoughts while working, exposing confusion and mental models in real time. If you were a learner using an AI tool, what would you be able to articulate about your confusion that a simple 'did you like it?' survey would never capture?
- The page notes self-reported satisfaction can diverge from objective performance — people can say they love a tool that secretly slows them down, or underrate one that actually helps. Where have you seen that gap between what people say and what their behavior shows?
- Usability research tells you whether a tool is usable, not whether it teaches. If you're evaluating an AI learning tool, how would you combine usability evidence with evidence of learning — and what could a tool that passes both still fail to achieve?

Introduction

Usability and UX research answer questions like: Can students figure out how to use this AI tutor? Is the AI tool confusing, frustrating, or error-prone? Does it fit the workflow of teachers or learners? These questions are a prerequisite for — and sometimes the hidden cause of — the learning gains (or lack thereof) measured in efficacy studies. An AI tool that is pedagogically sound but unusable will fail in practice; usability evidence explains why.

Core methods

- **Think-aloud protocols.** Users verbalize their thoughts while performing tasks, revealing comprehension, confusion, and mental models in real time. A study of multi-view code visualizations and the LEARN framework use think-aloud to understand how learners make sense of AI-assisted tools; feedback futures examines how learners process AI-generated feedback.
- **User studies.** Structured task-based evaluations measure efficiency, error rates, satisfaction, and completion. ProductiveMath evaluates a Generative AI app's usability in supporting Productive Failure teaching; SupplyNet runs a user study of a visual exploratory learning tool; LLM chatbots for CS multiple-choice assess interaction quality.
- **Interviews and observation.** Qualitative usability interviews and observation capture user experience, preferences, and pain points. A usability study of a storytelling humanoid robot uses structured evaluation to ask whether parents would let the robot interact with a child; AI in design studios observes and interviews students using AI in authentic design work.
- **Systematic usability evaluation.** Heuristic evaluation, cognitive walkthrough, and questionnaire-based UX measures (e.g., SUS) systematically assess usability against established criteria.

How usability research appears in the knowledge base

- **AI learning tool evaluation.** ProductiveMath, SupplyNet, and educational animations are evaluated for usability and UX.
- **Human–robot and conversational AI interaction.** The humanoid storytelling study is an explicit usability study of Large Language Models (LLMs)-powered interaction; an umbrella review of conversational AI agents identifies usability and interaction quality as a recurring theme.
- **Design and refinement.** Usability findings feed iterative design (see Design Thinking and Learning Design), improving tools before or alongside efficacy testing.
- **One instrument across contexts, and the ceiling that limits it.** Mendonça et al. (2026) held domain, task, and instrument constant while educational level varied, so 144 students' ratings of 893 feedback answers and 237 reports compare contexts rather than disciplines — and only perceived accuracy differed across levels. The study also names the limit of this kind of user evaluation: 72.2 to 86.4 percent of students averaged at least 4 of 5, and the authors state that their non-significant differences do not establish equivalence because no margin was set in advance.
- **Rater design reported as part of the finding.** Puech et al. (2026) had 25 domain-matched experts judge 92 regenerated lectures against a rubric anchored at "a standard MOOC lecture's quality," assigning each video to a single reviewer (k = 1) to spread the panel across more of the corpus instead of collecting repeat ratings. The trade-off is modeled rather than hidden: a random-intercept model attributes about 35 percent of residual variance to the reviewer (ICC = 0.35) and intervals are reviewer-clustered, which is how an expert panel can report "87 percent at or above the bar" with an honest range.

Relationship to other research families

Usability research shares data-collection methods with qualitative research (interviews, observation, think-aloud) but differs in *aim*: qualitative research interprets meaning and experience to build understanding and theory, whereas usability research evaluates an artifact against usability/UX criteria. It also overlaps with AI Ed Evaluation (assessing whether a system works) and with measurement (quantifying usability constructs). The knowledge base treats usability as a distinct but connected methodological strand — relevant to Human AI Collaboration, Student Experience, and the design of effective AI learning tools. See Research Methods in AIED for how it fits the broader methods landscape.

Strengths and limitations

- **Strengths:** directly identifies usability barriers that block adoption and learning; produces actionable design guidance; complements efficacy and qualitative research by explaining *why* a tool works or fails in use; relatively fast and cheap compared to large experiments.
- **Limitations:** usability findings do not establish learning effects (a usable tool can still fail to teach); small samples and task-specific settings limit generalizability; self-report satisfaction can diverge from objective performance; researcher and task-design dependence.

Common Misconceptions

“A usable system is a good educational system.” Usability research addresses the interaction between person and system, not learning outcomes, and the two come apart in both directions: a pedagogically powerful tool can be abandoned for being frustrating, and a frictionless tool can teach nothing. Ease is a precondition for use, not evidence that the use was worthwhile.

“Usability is a polish activity at the end of development.” It is a method family with core techniques — observation, task analysis, think-aloud, heuristic review — that shape the design rather than finish it. Discovering the friction after the Pedagogies and Teaching Strategies is fixed tends to produce either a redesign of the interface around the problem or abandonment of the tool.

“Students who abandon a tool lacked motivation.” Abandonment is often the user’s correct read of an interaction cost the designer never measured. Since a tool no one uses cannot have an effect, the abandonment rate is an educational outcome in its own right.

“Usability testing is the same as measuring learning.” They answer different questions and neither substitutes for the other; the failure mode is treating either as sufficient for adoption.

Connected Concepts

- Research Methods in AIED
- Qualitative Research
- Human AI Collaboration
- Student Experience
- AI Ed Evaluation

- Learning Design
- Design Thinking
- Intelligent Tutoring

Connected Articles

- Would you let a humanoid play storytelling with your child? A usability study on LLM-powered narrative human-robot interaction — A usability study of an LLM-powered storytelling humanoid
- ProductiveMath: A Generative-AI-Powered App to Support Productive Failure Teaching — ProductiveMath: usability of a generative-AI app
- SupplyNet: Supporting Visual Exploratory Learning in Supply Chain via Contextual Multi-Agent Simulation — SupplyNet user study
- ANVIL: Analogies and Videos for Lecturers — Usability of AI-generated educational animations
- Code as Anchor, Memory and Metaphor as Support: Learner Experiences with Multi-View Visualizations — Think-aloud study of multi-view code visualizations
- The LEARN framework for responsible use of generative AI in education: a neuroscience-informed model for problem-based learning — LEARN framework and think-aloud evaluation
- Feedback futures: beyond the limits of human and GenAI capacities — How learners process AI-generated feedback
- Are LLM-based Chatbots Good Enough to Support Computer Science Students in Multiple-Choice Exercises? — LLM chatbots for CS multiple-choice questions
- Conversational AI agents in education: an umbrella review of current utilization, challenges, and future directions for ethical and responsible use — Umbrella review of conversational AI agents

Connected FAQs

- What Are Best Practices and Tips for Designing Effective Educational AI Software?

RCT

> **Randomized controlled trial (RCT)** — a research design in which participants are randomly assigned to a treatment or control condition to estimate the causal effect of an intervention on an outcome. In AI in education, RCTs are the gold standard for establishing whether an AI tool or pedagogical approach *causes* learning gains, engagement changes, or other outcomes, rather than merely correlating with them.

Questions to Consider

- If a school tells you 'students who used the AI tool scored higher,' why might that still fail to prove the tool caused the gain — even if the difference is large?
- Randomization balances known *and unknown* confounders across groups. Before you read, what does random assignment accomplish that simply comparing two intact classrooms cannot, no matter how well-matched they look?
- The page calls the RCT the gold standard but lists real costs: artificial settings, fast-changing AI that dates trials, underpowered small samples, and ethical constraints on withholding helpful tools. Which of these trade-offs do you think is most often ignored in education research headlines?
- An RCT with 1,174 participants found GenAI closed about three-quarters of an education-based productivity gap. But a well-run RCT can still be conducted on a narrow task in a contrived setting. What should you check about the *outcome measure* before trusting the causal claim?
- Consider the ethics problem directly: if you had genuine reason to believe an AI tutor helps students learn, is it defensible to randomly deny it to half a classroom for a semester? How would you design an ethically sound study that still isolates the cause?

Introduction

Randomization is what distinguishes an RCT from other designs: by randomly assigning learners to conditions, an RCT balances known and unknown confounders across groups, so any observed difference in outcomes can be attributed to the intervention with high internal validity.

How RCTs appear in the research

- **Micro-RCTs as a response to fast-moving technology:** Harrison et al. (2026) argue that conventional large-scale trials cannot keep pace with tutoring platforms that change materially during a study, and use teacher-led micro-randomized controlled trials across English secondary schools (644 of 929 students completing post-testing, g = 0.33) to keep causal estimation repeatable. The trade-offs are stated in their own design: 30.7% attrition, curriculum-aligned rather than independently standardized outcomes, and only four weeks of follow-up.
- **Causal efficacy claims:** RCTs in AIED test whether an AI tutor, tool, or pedagogical treatment improves outcomes. A randomized experiment on generative AI with 1,174 participants found

GenAI substantially narrows education-based productivity gaps, closing roughly three-quarters of the initial performance difference — a clear causal estimate of AI's effect.

- **An outcome measured after a delay, not at the end of the session.** Randomizing 120 undergraduates to AI-assisted or traditional study of the same topics and testing retention 45 days later, the AI-assisted group scored 57.5% against 68.5%, a gap of about 11 percentage points (Barcaui (2025)).
- **Comparison to the gold standard:** The research methods page situates RCTs as the strongest design for internal validity while noting their trade-offs — cost, artificial conditions, fast-changing AI, small underpowered samples, and ethical limits on withholding potentially helpful tools.
- **A trial designed for equivalence, not difference.** Northcutt et al. (2026) randomized 2,383 adults to AI tutoring, live human tutoring, or a video control, wrote new GRE items with former ETS and Kaplan test developers to keep published-test contamination out, counterbalanced the two forms, and tested equivalence with two one-sided tests against ±0.25 SD rather than a difference - the design choices that make "no significant difference" an interpretable result.
- **Group randomization, low uptake, and what an intent-to-treat estimate then means.** Liu et al. (2026) randomized 2,379 undergraduates across 13 blocks by assigning *instructors* rather than students, so every student in a section inherited that instructor's condition — the design that makes a multi-section deployment trial feasible, and the one that creates the inference problems the study then documents. Only about 15% of students in treated sections ever used the tool, so the reported effects estimate *offering* access rather than using it; the authors read the intervention as the broader AI use its introduction induced, and treat individual sessions as a separate question. Because treatment was assigned at the instructor level, inference rests on 34 clusters — a setting in which cluster-robust standard errors overstate precision — so the paper reports randomization inference alongside them and finds its conclusions robust. The two headline effects, a 0.37 SD fall in final grades in the exact-match sample and a 0.90 SD fall in recorded platform participation in both samples, are section-level consequences that a per-student randomization of the same tool could not have isolated without contamination between treated and control classmates.
- **A voluntary school tool can still move workload on a 7% dose.** Roy et al. (2026) randomized 464 teachers across 108 English primary schools at school level. Preparation time came out at 0.76 of the comparison group's (95% CI 0.64 to 0.89) even though the tool covered 7% of lessons and use fell across the ten weeks, so the estimate bounds what offering it did for workload, not what full adoption would do.
- **Take-up bounds what a trial can test, and engagement support is not dosage.** Robinson et al. (2026) ran two reading-platform RCTs in which only 60.7% and 53.3% of control students ever used the platform; an engagement tutor raised stories read by 71–80% yet produced no achievement gain, consistent with 2–5 minutes per week reached.
- **Scale that converts nulls into evidence.** Mata et al. (2026) followed 8,708 students across eight semesters with power to detect effects of 0.05 SD and found large, immediate movement on dated binary tasks — 34 percentage points more registration by August 16 after a single reminder — while academic performance, persistence, and graduation showed no detectable effect. The scale is the design lesson: at this N the academic nulls are precise results rather than failures to detect,

which is what licenses the conclusion that a communication tool moves what it can address and not cumulative learning outcomes.

- **A null average can mask offsetting heterogeneity.** A pre-registered RCT randomizing 538 teachers across 24 Turkish schools at school-department level found achievement fell 0.129 SD among below-median teachers while rising 0.054 among above-median ones, and motivation fell 0.111 SD, with a ceiling-compressed exam (control mean 89.2/100) limiting power.(Sungu, Lira & Duckworth (2026))
- **Pre-registration that fixes the question and the detectable effect.** Meyer et al. (2026) registered both course trials with the Registry of Efficacy and Effectiveness Studies, committing in advance to intent-to-treat estimation and a minimum detectable effect size of about 0.157, and randomized consenting students each term with a second wave at add/drop so late enrollees entered the design rather than the default analysis sample. Pooling 2,483 students across two courses, the effect sits at the A/B threshold (four percentage points) while the pooled numeric-grade change does not survive multiple-comparison correction — a reminder that a registered primary outcome disciplines which of several correlated results is believed.
- **Randomizing inside intact sections, with a pre-treatment baseline.** Thoeni & Fryer (2026) randomized 454 undergraduates within three intact marketing sections after drop/add and measured all four outcomes at T1, before any student had chatbot access, so the term-long comparison rests on a measured baseline rather than an assumed one. The flat result (no group × time interaction reached significance; the largest reported effect was d = 0.050, on interest) is reported alongside adoption — 0.89 logins per week against an assigned once a week — which keeps a null about a weakly used treatment from being read as a null about the tool.
- **Within-subject crossover, and a control set at best practice.** Kestin et al. (2025) had each of 194 Harvard life-sciences students work two physics lessons — once in an in-class Active Learning session and once with the course's own AI tutor, in counterbalanced order with pre- and post-tests around each — so every student serves as their own control and the comparison of *delivery modes* is not confounded by who was assigned which. The design's second choice matters as much: the comparator was research-based active learning rather than a lecture, so the advantage (median post-test 4.5 vs. 3.5) is measured against current best practice and cannot be read as "AI beats teaching."

Strengths and limitations

- **Strengths:** strongest causal inference; clean outcome measurement; supports effect-size estimation; balances confounders through randomization.
- **Limitations:** costly and slow; artificial settings can reduce ecological validity; AI tools change faster than trials can run; small samples often underpower detection of meaningful effects; ethical constraints on withholding potentially beneficial AI from a control group. Two of those limits change shape when assignment is clustered: the effective sample becomes the number of *clusters* rather than the number of students, so a trial can be large by headcount and thin by that measure — Liu et al.'s 2,379 students rest on 34 instructor-level clusters — and when uptake is voluntary

and low, an intent-to-treat estimate answers whether offering the tool changed outcomes, not whether using it did.

For the fuller treatment of experimental design in AI in education — including when an RCT is appropriate versus quasi-experimental, survey, or computational designs — see Research Methods in AIED.

Common Misconceptions

- **"Randomisation guarantees a valid estimate of what the tool does."** Randomization balances confounders; it does not ensure anyone used the treatment. A group-randomized trial with low uptake estimates **the effect of offering** the tool, and intent-to-treat and treatment-on-treated answer different questions.
- **"A big trial is always the better design."** Some argue that conventional large-scale trials **cannot keep pace with tutoring platforms that change materially during a study**, and instead use teacher-led designs that stay valid as the system evolves. A trial of a moving target can be well powered and still measure a system that no longer exists.
- **"RCTs and observational evidence are substitutable."** An RCT with **1,174 participants** found GenAI **closed about three-quarters of an education-based productivity gap** — a precise causal claim over a specific period. Observation explains mechanism and adoption; it cannot carry that estimate, and the RCT cannot explain why.

Connected Concepts

- Research Methods in AIED
- AI Ed Evaluation
- Educational Measurement
- Generative AI
- Higher Education
- AI in Education
- Student Support and Success — the design behind the strongest student-support evidence

Connected Articles

- Lesson planning using AI lesson assistant, Aila - A Teacher Choices Trial — Lesson planning time fell to 0.76 of the comparison group's across 108 primary schools, on a 7% dose of tool use
- Does generative AI narrow education-based productivity gaps? Evidence from a randomized experiment — Does generative AI narrow education-based productivity gaps? Evidence from a randomized experiment
- Generative AI Can Harm Teaching — Generative AI can harm teaching: an RCT
- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — Access is not enough: human support improves engagement with AI tutoring

- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomized Trials of an AI Tutoring Platform in GCSE Science
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — Group randomization by instructor: a 0.37 SD fall in final grades and a 0.90 SD fall in platform participation, with 15% uptake and inference on 34 clusters (Liu et al. 2026)
- ChatGPT as a cognitive crutch: Evidence from a randomized controlled trial on knowledge retention — An outcome measured after a delay, not at the end of the session

Meta-Analysis and Systematic Review

> **Meta-analysis and systematic review** — the family of evidence-synthesis methods researchers use to aggregate and appraise a body of studies, rather than run a single new experiment. A **systematic review** applies a transparent, reproducible protocol to search, screen, appraise, and synthesize the literature on a focused question; a **meta-analysis** goes further by statistically pooling effect sizes across eligible studies to produce a weighted summary estimate and to test moderators. In AI in education, these methods are central to establishing the evidence base for whether AI tools work, under what conditions, and for whom — and to exposing gaps, bias, and the field's methodological quality.(A meta-analysis of the effect of generative AI on productivity and learning in programming) (Comprehensive Review of Intelligent Tutoring Systems)

Questions to Consider

- Imagine you read ten studies on whether AI tutoring works — two show big gains, three show none, five show small positive effects. How would you decide what to conclude? That tension is exactly what systematic reviews and meta-analyses are built to resolve.
- A systematic review and a meta-analysis are often treated as the same thing, but the page distinguishes them: a review synthesizes per a documented protocol, while a meta-analysis statistically pools effect sizes. When would pooling be inappropriate or impossible, even if a careful review exists?
- Systematic reviews sit at the top of the evidence hierarchy partly because they compensate for small samples, heterogeneous designs, and conflicting results across studies. Where have you seen a single dramatic study shape opinion even though the pooled evidence was far more mixed?
- Meta-analyses produce a weighted summary estimate — a single number like 'an average effect of 0.125 standard deviations.' What does a pooled average hide about the conditions, learners, or contexts where the effect differs — and why does that matter for whether you'd act on it?
- Both methods commit to a transparent, reproducible protocol (often PRISMA) precisely because the choices of what to search and include can bias the result. How much would you trust a review that didn't disclose its search and screening decisions?

Introduction

Systematic reviews and meta-analyses sit at the top of the traditional evidence hierarchy precisely because they synthesize many individual studies, compensating for the small samples, heterogeneous designs, and conflicting results that characterize any fast-moving applied field. In AI in education, where new tools and studies appear constantly, reviews play the crucial role of taking stock: mapping what has been studied, aggregating what is known, and flagging where evidence is thin or methodologically weak. They differ from a narrative or integrative literature review, which provides qualitative synthesis, in their commitment to a documented protocol and (for meta-analysis) statistical pooling.(The AI literacy heptagon: A structured approach to AI literacy in higher education)

Systematic review vs. meta-analysis

	Systematic review	Meta-analysis
Core activity	Search, screen, appraise, synthesize studies per a documented protocol	Statistically pool effect sizes across eligible studies
Output	A narrative/thematic synthesis and evidence map, often with PRISMA flow	A pooled effect estimate with confidence intervals, plus moderator analysis
Statistical pooling	Optional (many reviews are qualitative)	Required
When used	Mapping a fragmented literature, answering "what has been studied and what does it show?"	When multiple comparable quantitative studies exist, answering "how large is the effect overall?"
Strength	Transparent, reproducible scope and appraisal	Increased power and precision; detects moderators and heterogeneity

Both follow **PRISMA** (Preferred Reporting Items for Systematic Reviews and Meta-Analyses) as the reporting standard, which documents the search, screening, and inclusion process for transparency and reproducibility. An integrative review may follow PRISMA principles for transparency while stopping short of statistical pooling.(A systematic review of AI-powered collaborative learning in higher education: Trends and outcomes from the last decade)(The AI literacy heptagon: A structured approach to AI literacy in higher education)

Evidence-synthesis in AI in education

What reviews accomplish

Systematic reviews and meta-analyses in AI in education serve several distinct purposes:

- **Establish the evidence base** — determining whether AI tools (tutoring, feedback, assessment, chatbots) produce learning gains, and how large those gains are.
- **Map the field and its gaps** — a scoping review documents what has been studied, where the evidence is concentrated, and where it is missing (e.g., workplace settings, non-English work, failure cases).(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness) **Count records, not studies, when a review reports frequencies.** In a scoping review that reached 31 studies from 21,720 records, five studies supplied 62 of 192 practice records, so the percentages describe the extracted material rather than independent observations or prevalence (Tie, Gil Ortega and Zhao (2026)).
- **Identify moderators and conditions** — meta-analysis tests whether effects differ by learner population, domain, AI system type, or study design, revealing for whom and under what conditions a tool works. But a moderator is only as trustworthy as the studies behind it: in a 2026 meta-analysis of GenAI-supported L2 writing, the only moderator that survived methodological control was the studies' risk-of-bias classification, while an instructional-model difference that had

looked significant in subgroup analysis collapsed once study quality and sample size were entered. Methodological quality, not pedagogy, carried the effect — so apparent pedagogical moderators warrant the same scrutiny as pooled estimates. Null moderators carry the same lesson in reverse. In Chen and Wei's meta-analysis of digital and AI technologies for foreign-language skills (40 studies, 3,367 participants, pooled g = 0.962), the moderators that survived were study design (quasi-experiments g = 1.019 against true experiments g = 0.474), intervention duration, and tool count, while language skill type, technology type, educational level, setting, and sample size showed no significant between-group difference, leading the authors to conclude that effectiveness cannot be attributed to a technology label or a skill category. Yu and colleagues' meta-analysis of K-12 AI education (16 studies, 57 effect sizes, g = 0.892) found all three of its tested moderators (publication source, publication year, school level) null and read the residual heterogeneity (I2 = 94.68%) as evidence that the field has not agreed on how to measure AI Literacy at all. When a moderator comes back null and heterogeneity stays high, the synthesis conclusion is often about the outcome construct or the primary-study designs as much as about the intervention.

- **Expose methodological quality** — reviews routinely find that the field relies on underpowered, pre-experimental, or quasi-experimental designs and immediate post-tests, tempering conclusions. (Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)(Comprehensive Review of Intelligent Tutoring Systems) Thin reporting of what was actually done is part of that picture, and it bounds what any later synthesis can say: Yalcin and colleagues' systematic review of GenAI in programming education could not identify an instructional approach in 26 of its 46 studies, and 32 of the 46 appeared in conference proceedings, so the review could code pedagogy for fewer than half its corpus and ends with mixed impact evidence (some studies showed improved exam and coding performance, while others found no significant difference against instructor feedback). A synthesis inherits the reporting habits of its field.

Screening reliability can be construct-dependent: in a PRISMA-ScR scoping review of 123 studies of GenAI, offloading and learner agency, title/abstract agreement (Fleiss' $\kappa = 0.7103$) fell to $\kappa = 0.4884$ at full text, which the authors attribute to the interpretive boundary between broad GenAI relevance and substantive relevance to the mechanism (Wang et al. (2026)).

Examples from the knowledge base

- **Meta-analysis of GenAI and programming** — pools evidence on the productivity-learning trade-off, finding significant productivity gains but no significant learning gain ($g \approx 0$), illustrating meta-analysis's ability to separate short-term efficiency from durable learning.(A meta-analysis of the effect of generative AI on productivity and learning in programming)
- **Meta-analysis of GenAI in student learning from a TPACK lens** — pools 71 studies (74 effect sizes) to a medium-to-large effect (g = 0.752) that decomposes unevenly: strong cognitive (g = 0.831) and affective (g = 0.729) gains but a small, non-significant behavioral-engagement effect (SMD = 0.057, p = 0.828) (Liu & Zhong, 2025).
- **Systematic review of AI in VET** — first systematic review of 26 studies, documenting the Constructivism-in-name, behaviorist-in-practice gap and the absence of workplace studies.

(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

- **Systematic review of GenAI in higher education** — maps opportunities, challenges, and pedagogical innovations across a five-year window.
- **Comprehensive ITS review** — a systematic review of intelligent tutoring systems with a focus on methodological rigor.
- **Systematic review of ChatGPT and critical/creative thinking** — synthesizes evidence on whether Large Language Models (LLMs) use supports or undermines higher-order thinking.
- **Evidence base for AI in K-12** — reviews the strength of evidence for AI tutoring in schools.
- **Meta-analysis of AI literacy interventions** — three-level meta-analysis of 59 studies (172 effects, 7,211 participants) estimating a large overall effect (g = 0.837) while showing that effectiveness varies by region and learning-outcome focus (knowledge-focused interventions outperformed those targeting skills, attitudes, or Ethics).
- **AI Literacy Heptagon** — an integrative literature review following PRISMA principles, illustrating qualitative synthesis that stops short of meta-analysis.(The AI literacy heptagon: A structured approach to AI literacy in higher education)
- **Meta-analysis of digital and AI technologies for foreign-language skills** — Chen and Wei (2026) pool 40 experimental and quasi-experimental studies (3,367 participants) to a large effect (g = 0.962, 95% CI 0.765 to 1.159) with high heterogeneity (I2 = 85.178) and publication-bias checks that support the estimate (Orwin's fail-safe N = 5853; Egger's test p = 0.84465). The instructive part is the design moderator: quasi-experiments reported g = 1.019 against g = 0.474 for true experiments, and the non-linear duration and tool-count patterns rest on subgroups of one or two studies.
- **Meta-analysis of GenAI and learning outcomes in higher education** — Jing and colleagues (2026) pool 35 studies and 175 effect sizes to g = 0.53 (95% CI [0.48, 0.64]), largest for professional skills (g = 0.72), then academic performance (g = 0.46) and emotional attitude (g = 0.44). Duration moderates every dimension, and the decline is the point: academic-performance effects fall from g = 5.07 for interventions of 0 to 4 weeks to g = 0.64 at 4 to 12 weeks and g = 0.01 beyond 12 weeks (Q = 35.19, p < 0.001). Discipline type and learning method were not significant moderators.
- **Meta-analysis of K-12 AI education and AI literacy** — Yu and colleagues (2026) pool 16 studies (57 effect sizes, 3,837 students, all effects positive) to g = 0.892 (95% CI [0.548, 1.236]), with trim-and-fill adjustment leaving it at g = 0.952. All three tested moderators (publication source, year, school level) came back null, and the authors attribute the 94.68% heterogeneity to measurement: the studies operationalized AI Literacy as everything from AI knowledge and ethics to attitudes, Self-Efficacy, and career interest.
- **Systematic review of GenAI in programming education** — Yalcin and colleagues (2026) PRISMA-screen 151 records to 46 studies, of which 26 give no usable description of instructional approach and 38 examine a single tool (ChatGPT alone appears in 35 of 46). The review maps

tools, languages, and venues reliably but can code pedagogy for fewer than half its corpus, a clean demonstration that thin primary-study reporting caps what a synthesis can conclude.

- **Scoping review and evidence map of NLP in student evaluation of teaching** — Eicher and da Silva (2026) score 421 studies on a technical axis and four value dimensions, coding actionability on a six-level scale from asserted usefulness to measured impact on decisions, and reach a usable output in 258 of 421 studies (61.3%) against intended-user evaluation in only 49 (11.6%). Turning a gap into a coded dimension lets the review name the 49.7-point boundary between "the model works" and "the feedback changes teaching" as its central finding rather than a caveat.
- **PRISMA 2020 review of GenAI in healthcare scenario learning** — Neto and colleagues (2026) systematically searched five databases (9 Nov 2025) for peer-reviewed GenAI studies across scenario-, case-, problem-, and Simulation-based healthcare education, screening 1,151 records down to 23 included studies appraised with the Mixed Methods Appraisal Tool (MMAT). Their thematic synthesis surfaced six cross-cutting themes anchored on prompt design as instructional specification, and documented gaps in validation standardization, longitudinal/comparative designs, and efficiency quantification — a template for rigorous domain-specific GenAI systematic review.
- **Systematic review of language educators and GenAI** — a PRISMA-aligned review of 23 SSCI-indexed empirical studies (December 2022–September 2024) on how language educators perceive, adopt, and learn to integrate GenAI, synthesized through the Aristotelian knowledge typology of episteme (theoretical understanding), techne (practical skill), and phronesis (practical wisdom). It documents cautious, selective adoption weighted toward behind-the-scenes preparation, persistent competency gaps across all three knowledge types, and only three structured PD interventions — illustrating how a review can expose both the evidence base and the field's methodological gaps (here, the scarcity of structured professional-development studies).
- **Systematic review of AI and service delivery in global higher education** — Nyamboga (2026) synthesizes 155 studies across five domains and grades the certainty of each with adapted CASP and JBI-informed criteria, rating AI integration and infrastructure readiness high, leadership moderate, and ethical governance and sustainability low. The review also turns a quality lens on its own corpus: 117 studies (75.5%) reported successful implementation, 124 (80.0%) covered only short-term impact, and just 23 (14.8%) reported ethics, equity or governance failures. A synthesis can report how certain the evidence is, domain by domain, rather than only the direction it points.
- **Systematic review of RL in education** — Riedmann, Schaper & Lugrin (2025) applied a PRISMA-standard protocol to synthesize 89 Reinforcement Learning studies (2000–2024). The review is an instructive case study in synthesis methods and their limits: it maps a rapidly growing but methodologically uneven field — over half of studies (n = 54) reported no statistical testing — and runs effect-size analysis on only 15 papers suitable for pooling, reporting intermediate-to-large effects (Cohen's d) from live evaluations. It also performed publication-bias checks (funnel plot, Egger's test, PET-PEESE) that found no significant bias but had limited power (n = 6), and it stops at thematic-plus-limited-quantitative synthesis rather than a full meta-analysis precisely

because heterogeneous evaluation protocols prevented wider pooling — a concrete illustration of the heterogeneity and garbage-in/garbage-out limitations described below.

- **Scoping review of critical thinking in HCI research on AI** — Inie and colleagues (2026) map 80 empirical papers and deliberately perform no quality assessment, so "claimed" influence means the conclusion each paper states. Only 23 papers (29%) define critical thinking, 46 (57%) cannot be assigned a theoretical position, and 49 (61%) measure the construct through self-report, which is what allows 50 papers (62%) to report a positive influence. When a construct is this undefined and its measures incommensurable, mapping the field is more informative than pooling it, and withholding appraisal shifts the claim from an effect to a description of what studies asserted.
- **Mapping review of AI integration in higher education (FACETS + SAMR)** — a PRISMA 2020 review screening 959 records down to 22 intervention studies, illustrating how a coding framework (FACETS: Form, AI use case, Context, Education focus, Technology, SAMR) plus an evaluative lens (SAMR) maps a fragmented literature and grades depth of transformation. Most included studies sat at SAMR Substitution/Augmentation, showing mapping reviews can reveal an integration field that is broad but shallow — an alternative to effect pooling when the aim is describing a landscape rather than estimating an effect.
- **Systematic review of teacher intervention in K-12 AI-based instruction** — Lee (2026) screened 1,565 records down to 29 studies with two independent raters at every stage ($\kappa = 0.655$ screening, $\kappa = 0.647$ eligibility) and an MMAT quality appraisal that removed one study. It is an instructive example of synthesis that deliberately stops short of pooling: because the independent effect of teacher intervention could not be separated from AI system design, instructional structure and classroom context in most of the included studies, the review reports conditional outcomes and an explanatory framework of process, strategy and effect rather than an effect size — the same limitation that separates a review from a meta-analysis.
- **Systematic review of ethical values and norms in AIED** — Agarwal and colleagues (2026) screened 736 records across Web of Science, ERIC, IEEE CSDL, and ACM DL (plus backward snowballing) down to 25 included articles, consolidating the fragmented AIED ethics literature into six main ethical values (non-discrimination, data stewardship, human oversight, goodwill, explicability, educational aptness) and mapping ethical norms onto a stakeholder-by-value matrix. The review illustrates how a systematic protocol can synthesize a conceptually fragmented, largely non-empirical literature (only three of 25 articles were methodology papers or original research) and turn it into an actionable framework — here, a foundation for AI Governance and policy.
- **Three-level meta-analysis of GenAI in PBL/PjBL** — Chen and colleagues (2026) pool 22 controlled studies and 66 effect sizes to a large effect on learner-internal outcomes ($g = 0.819$, 95% CI [0.655, 0.983]), then report that a PET-PEESE small-study correction lowers the estimate to $g = 0.378$ while the product-performance model ($g = 1.958$, six studies) carries a prediction interval that crosses zero. Two further studies were dropped for failing a What Works Clearinghouse baseline-equivalence threshold of 0.25 SD. The reported effect is contingent on the bias corrections and design screens a synthesis applies, and both belong in the interpretation rather than a footnote.

Interdisciplinary review of AI for dyslexia

Dabaghi, D'Urso & Sciarrone (2026) present a PRISMA-guided, interdisciplinary systematic review (2018–2024, n=72) of AI and generative AI to support students with dyslexia in education. The review maps AI across detection, assistive support, and personalized learning, finding these strands evolve in parallel rather than in integration, driven more by technological opportunity than by consolidated educational theory. It documents that generative AI is under-utilized in this domain (GAI research, all from 2024, clusters into chatbots, teacher-training support, and exploratory studies) and that ML-based help-education tools fall into five areas (specific applications, engagement, personalization, recommendation, generic support) while emphasizing technical performance over ecological validity. Open challenges include limited experimental validation, scalability and Accessibility of diagnostic tools, ethics/privacy concerns with sensitive student data, limited teacher support, and language/cultural barriers. The review's own methodological limitations illustrate the systematic-review family's core tension: interpretative classification bias, exclusion of non-English studies, heterogeneous evaluation protocols that prevent quantitative synthesis, and a rapidly evolving GAI evidence base. A transparent protocol can map a fragmented field, but heterogeneous evaluation prevents statistical pooling, so the review stops at thematic synthesis rather than meta-analysis.

AI-era synthesis challenge: productivity vs. learning

Reviews of generative-AI interventions face a distinctive challenge that the knowledge base's synthesis research highlights: **separating productivity gains from durable learning gains.** Because generative AI can inflate immediate task performance (homework, assisted practice) without producing learning, meta-analyses must be careful about which outcome they pool. The GenAI-and-programming meta-analysis found large productivity gains but no significant learning gain ($g \approx 0$) — a clean illustration. Large-scale field studies and unassisted-measure research show that the measured effect depends on whether outcomes are AI-assisted or proctored/unassisted. Reviews should therefore report assisted and unassisted outcomes separately, distinguish performance from learning, and flag studies that measure only immediate AI-supported performance. A complementary caution emerges from the AI-literacy meta-analysis: which **outcome** is pooled also shapes the answer — knowledge-focused AI Literacy interventions showed larger effects than those targeting skills, attitudes, or ethics, so a review that pools only knowledge outcomes can overstate what AI-literacy instruction achieves overall. This connects to AI Ed Evaluation and Summative Assessment.

The same artifact shows up in the time dimension. Jing and colleagues' 2026 meta-analysis of GenAI in higher education (35 studies, 175 effect sizes, pooled $g = 0.53$) reports academic-performance effects that fall from $g = 5.07$ for interventions of 0 to 4 weeks to $g = 0.64$ at 4 to 12 weeks and $g = 0.01$ beyond 12 weeks ($Q = 35.19$, $p < 0.001$), with emotional-attitude effects dropping from a peak of $g = 2.05$ to $g = 0.18$ over the same span. Effects that large, that early, are mostly registering task-level assistance rather than durable learning, so a pooled estimate dominated by short studies should be read as an upper bound on what a real implementation will sustain. Reviews that pool outcomes should therefore record intervention duration alongside the effect size, because duration is one of the few moderators that has held up across these syntheses.

Strengths and limitations

Strengths: - Efficient synthesis of a large, fragmented literature - Meta-analysis yields pooled effect estimates, increases statistical power, and detects moderators and heterogeneity - Systematic protocols improve transparency and reproducibility over narrative reviews - Essential for evidence-based practice and for identifying research gaps

Limitations: - **Garbage-in/garbage-out** — the synthesis is only as good as the quality of included studies; weak primary designs yield weak pooled conclusions - **Publication bias** — null or negative results are under-published, inflating pooled effects - **Heterogeneity** — varied designs, outcome measures, and AI systems make direct pooling hard and can undermine the meaning of a single effect size. The GenAI-writing meta-analysis makes that concrete: a large, statistically significant pooled advantage came with between-study heterogeneity so extreme that the prediction interval for a new implementation still crossed zero, meaning a fresh deployment could plausibly yield no benefit. The direction of the average was robust; its magnitude was not — which is why the prediction interval, not the pooled estimate alone, should inform a decision to adopt. Unresolved heterogeneity can also come from the outcome side rather than the design side: the K-12 AI-literacy meta-analysis found I2 = 94.68% that no moderator explained, and traced it to the absence of an agreed measure of AI Literacy, with the 16 studies mixing cognitive and affective outcomes under one label. Heterogeneity driven by what was measured as much as by what was done cannot be resolved by pooling. - **Rapid obsolescence** — the AI tool landscape changes quickly, so reviews can date fast - **Scope constraints** — single-database or English-only searches may miss relevant work.(A systematic review of AI-powered collaborative learning in higher education: Trends and outcomes from the last decade) (Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)

A four-study meta-analysis shows the same lesson from the small-sample side. Govea Sotomayor and García Ortiz (2026) pooled 420 students across four controlled studies of AI-based personalized learning in computing and engineering and reported $g = 1.01$, 95% CI 0.33 to 1.68. The Hartung-Knapp adjustment, which is the defensible correction at that few studies, widened the interval to −0.10 to 2.11 ($p = .063$), so the pooled estimate no longer excluded no effect. With $k = 4$, publication-bias tests cannot run at all, and GRADE certainty was rated very low. Pooling four studies produces an estimate that cannot carry an adoption decision, however large it looks.

Meta-research warns the AIED synthesis base is currently weak. A growing set of critiques documents that the field's headline AI-effect sizes — especially from early meta-analyses — are inflated by publication bias, construct incoherence, and methodological shortcuts. Bartoš et al. (2026), meta-analyzing 1,840 effect sizes from 67 meta-analyses, estimate the publication-bias-adjusted AI effect at roughly one-third the reported magnitude (SMD ≈ 0.196), with extreme heterogeneity. O'Neill (2026) audits 14 high-impact AIED meta-analyses and finds none had a coherent construct, valid publication-bias assessment, or resolved heterogeneity; twelve treated dependent effect sizes as independent. Weidlich et al. (2025) show most primary comparisons lack a well-defined treatment, control, and learning measure. This means readers should treat pooled AIED effect sizes as upper bounds until synthesis quality improves — see Limitations in AIEd Research for the full analysis. - **Reporting standards have not kept pace with automation.** PRISMA-LLM analyses SciLitBench, a corpus of 888 review-automation papers with 14,726 annotations, and documents a growth rate near 4.7% per month alongside an accountability gap: since 2023, 38.0% of

software and product papers reported no evaluation at all, against 9.3% of LLM papers, and 52% of positive-only LLM evaluations reported an unmet high-bar concern. Because LLM and software pipelines now participate in stages that can alter the evidence base, the framework requires disclosure of where in the review workflow automation operated, what was evaluated, and which limitations were checked — a direct extension of the transparency problem that AIED review critiques have documented for meta-analyses of learning effects. (PRISMA-LLM: An Empirical Reporting Framework for AI-Assisted Systematic Reviews) - **A worked example of a review that deliberately declined to pool.** Spyropoulou and Kameas (2026) synthesized 78 studies of AI-supported instructional design (2022-2026) and judged quantitative synthesis **inappropriate** because the corpus mixed practitioner reports, small-sample case studies and mixed-methods designs. Instead of forcing a pooled effect, they ran a qualitative thematic synthesis and were explicit that evidential strength is weighted throughout rather than assumed. That is the correct call far more often than the literature reflects: where a corpus cannot support pooling, declining to pool is a finding about the field rather than a methodological shortfall of the review. - **Quality appraisal used to weight, not to exclude.** The review appraised every study with **MMAT 2018** and let that appraisal inform the confidence assigned to each synthesized finding rather than screening weaker designs out. Lower-quality studies therefore contribute at correspondingly lower weight, which preserves the evidence base's shape — including its weaknesses — instead of presenting a filtered version of it. The choice matters because exclusion criteria and weighting rules can change a review's conclusion without changing its protocol compliance. - **Quality appraisal can also exclude and recount.** Kim and Han (2026) ran the other way with their 23 included studies: rather than weighting, they recalculated every frequency with the three Low-rated and four unappraisable papers removed, leaving 16, and reported which survived the cut. Deep learning stayed first (45.5% of 22 tags), Multimodal AI use barely moved (31.3% of papers) and the outcome ordering held within 2.4 percentage points, while interaction fell from 12.5% to 6.7%, content creation from 7.5% to 3.3%, and image data dropped from first to fourth as motion data became the most frequent modality. The two answer different questions: weighting keeps the corpus's shape, recounting shows which of its patterns rest on its weakest members. - **Self-report dominance deserves its own caution line.** The authors name self-report as a corpus-level limitation on top of their study-level appraisal, and in this case the caution bites twice: the review's own substantive findings concern educators **overestimating their own evaluation skill**, so the methodological limitation and the subject matter are the same problem. A synthesis whose included studies measure competences by self-report, on a topic where Self-Assessment is demonstrably unreliable, has to say so in the limitations rather than in passing. - **Single-coder coding is reported as a limitation, not omitted.** Screening and coding were performed by the first author with borderline cases resolved by consensus with the second, and reliability was **not quantified through independent double-coding** — so the interpretive categories, particularly the AI roles and oversight levels, carry a risk of single-coder bias that the authors state outright. Many reviews in this field leave that sentence out; including it lets a reader judge how much weight the interpretive categories can carry.

Relationship to other methods

Within the knowledge base's methodological landscape, meta-analysis and systematic review are the **synthesis** family, complementing primary designs:

- **Primary studies** (experiments, surveys, qualitative work, design-based research) generate individual findings; reviews aggregate them. See Research Methods in AIED.

- **Effect-size reporting** in primary studies (e.g., RCTs) is what makes later meta-analysis possible — reviews depend on studies reporting comparable, extractable effect sizes.
- **Evaluation** (AI Ed Evaluation, Benchmark) assesses individual systems; reviews assess the *literature* on systems and interventions.
- **Educational measurement** (Educational Measurement, Assessment Validity) concerns the quality of the outcome measures that reviews pool.

Implications for researchers

1. **Report extractable effect sizes.** For a literature to be meta-analyzable, primary studies must report comparable effect sizes and adequate methods detail — a responsibility of every AIED study.(Research Methods in AIED) Adequate detail includes the instructional approach: a systematic review of GenAI in programming education could code pedagogy for fewer than half its 46 studies because 26 never described what they did, and the detail primary authors omit is the detail later syntheses cannot recover.
2. **Follow a transparent protocol.** PRISMA-guided search, screening, and appraisal make reviews reproducible and defensible.
3. **Interpret pooled effects cautiously.** Attend to heterogeneity, publication bias, and the quality of included studies before drawing strong conclusions.
4. **Use reviews to set the agenda.** Reviews' documented gaps (failure cases, workplace settings, non-English and non-indexed work, long-term outcomes) should guide where new primary research is needed.(Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness)
5. **Treat null moderators as findings.** When moderators come back null and heterogeneity stays high, that is evidence about the state of the field (construct incoherence, thin design reporting) as much as about the intervention, and it belongs in the synthesis narrative rather than being dropped. (The Effects of K-12 Artificial Intelligence Education in Enhancing AI Literacy: A Meta-Analysis) (The Impact of Digital and Artificial Intelligence Technologies on the Improvement of Foreign Language Listening, Speaking, Reading and Writing Skills: A Meta-Analysis)
6. **An uncorrected moderator p-value is not a finding.** Khodjaev et al. (2026) report three of seven moderators at $p < .05$ uncorrected, none surviving Holm correction, yet their discussion calls its educational-level hypothesis supported at $p_{adj} = .233$ (Khodjaev et al. (2026)). Report the corrected value or report the moderator as null.

GenAI in Healthcare Scenario Learning

- **PRISMA 2020 review of GenAI in healthcare scenario learning.** Neto and colleagues (2026) systematically searched five databases (9 Nov 2025) for peer-reviewed GenAI studies across scenario-, case-, problem-, and Simulation-based healthcare education, screening 1,151 records down to 23 included studies appraised with the Mixed Methods Appraisal Tool (MMAT). Their thematic synthesis surfaced six cross-cutting themes anchored on prompt design as instructional specification, and documented gaps in validation standardization, longitudinal/comparative

designs, and efficiency quantification — a template for rigorous domain-specific GenAI systematic review.

Common Misconceptions

- **"A significant pooled effect means the intervention works."** Yu and colleagues' meta-analysis of K-12 AI education (**16 studies, 57 effect sizes, g = 0.892**) found a large effect, though the authors qualify it. Sixteen studies is a narrow base, and a large effect over that base is a hypothesis with a wide interval.
- **"Reviewers report the field's quality accurately by default."** A review's job includes **exposing methodological quality**, and reviews **routinely find that the field relies on underpowered, pre-experimental or quasi-experimental designs** with immediate post-tests. The pooled number inherits those weaknesses.
- **"Pooling always increases evidential weight."** Chen and Wei's meta-analysis of **40 studies** for foreign-language skills pools across very different technologies, and the mean describes none of the specific interventions it contains.

Connected Concepts

- Interpreting and Applying AIEd Research
- Research Methods in AIED
- RCT
- AI Ed Evaluation
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Benchmark
- Educational Measurement
- Assessment Validity
- Learning Gains
- Summative Assessment
- AI in Education
- Higher Education
- Simulation

Connected Articles

- Integrating generative Artificial Intelligence into student learning: A systematic review from a TPACK perspective — Systematic review of GenAI in student learning from a TPACK perspective
- A meta-analysis of the effect of generative AI on productivity and learning in programming — Meta-analysis of GenAI's effect on productivity and learning in programming

- Artificial intelligence in vocational education and training: A systematic review of educational purposes, theoretical conceptualizations, and empirical effectiveness — First systematic review of AI in vocational education and training
- A systematic review of AI-powered collaborative learning in higher education: Trends and outcomes from the last decade — PRISMA systematic review of AI-powered collaborative learning
- Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025) — Systematic review of GenAI in higher education
- Comprehensive Review of Intelligent Tutoring Systems — Comprehensive systematic review of intelligent tutoring systems
- The cognitive impact of ChatGPT in higher education: A systematic review of critical and creative thinking outcomes — Systematic review of ChatGPT and critical/creative thinking
- The Evidence Base on AI in K-12: A 2026 Review — Evidence base for AI in K-12
- AI literacy interventions in education: A meta-analysis of effects and moderators — Meta-analysis of AI literacy intervention effects
- Effectiveness of GenAI in enhancing writing performance: a meta-analysis — Meta-analysis of GenAI-supported L2 writing: a large pooled effect undermined by extreme heterogeneity and a quality-driven moderator
- The AI literacy heptagon: A structured approach to AI literacy in higher education — Integrative literature review of AI literacy dimensions (PRISMA-guided)
- Generative AI in scenario-based healthcare education: A systematic review of applications, validation practices, and pedagogical integration — Systematic review of GenAI in scenario-based healthcare education (Neto et al. 2026)
- Mapping artificial intelligence integration in higher education: A systematic review using the FACETS and SAMR frameworks — Mapping review classifying 22 AI-integration studies with FACETS + SAMR; most sit at Substitution/Augmentation
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- A systematic review of language educators' practices and development with GenAI — Language educators' practices and development with GenAI
- Artificial intelligence to help people with dyslexia in education: An interdisciplinary literature review — AI to help people with dyslexia in education
- Reinforcement Learning in Education: A Systematic Literature Review
- ChatGPT in Education: An Effect in Search of a Cause — ChatGPT in Education: An Effect in Search of a Cause (media-comparison critique)
- Effect of Artificial Intelligence on Learning: A Meta-Meta-Analysis — Meta-meta-analysis: bias-adjusted AI effects ~1/3 of reported size

- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis — Presumed Effective: forensic audit of 14 AIED meta-analyses
- Teacher intervention in K-12 AI-based instruction: a systematic review of processes, strategies, and effects — Teacher intervention in K-12 AI-based instruction: a systematic review
- The Impact of Digital and Artificial Intelligence Technologies on the Improvement of Foreign Language Listening, Speaking, Reading and Writing Skills: A Meta-Analysis — Meta-analysis of digital and AI tools for foreign-language skills: the design moderator more than doubles quasi-experimental effect estimates
- The Impact of Generative Artificial Intelligence on Learning Outcomes in Higher Education: A Meta-Analysis — Meta-analysis of GenAI in higher education: short-intervention effects collapse as duration grows
- The Effects of K-12 Artificial Intelligence Education in Enhancing AI Literacy: A Meta-Analysis — Meta-analysis of K-12 AI education: large effect with null moderators and heterogeneity attributed to measurement
- Mapping Research on Generative Artificial Intelligence for Programming Education: A Systematic Review — Systematic review of GenAI in programming education: thin instructional reporting in 26 of 46 studies
- Generative AI, Cognitive Offloading, and Learner Agency in Higher Education: A Scoping Review — 123-study scoping review mapping GenAI, cognitive offloading and learner agency in higher education
- A meta-analysis of the effects of generative artificial intelligence on learning, cognitive, and linguistic outcomes — A meta-analysis of the effects of generative artificial intelligence on learning, cognitive, and linguistic outcomes
- Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps — Responsible student use of generative AI in academic writing: a scoping review of boundaries, educational approaches, and evidence gaps
- Artificial intelligence in embodied learning: A systematic literature review — AI in embodied learning mostly observes: sensing roles 62.5% of coded role tags, and no reviewed system fused multimodal streams while learners used it (Kim & Han 2026)
- AI-based personalized learning and academic performance in computing and engineering higher education: a systematic review and meta-analysis of controlled studies — Why four studies cannot carry an adoption decision

Connected FAQs

- What Are Best Practices for Reporting and Interpreting AI in Education Research?

Latent Profile Analysis

> **Latent profile analysis (LPA)** — a person-centered method that sorts a sample into unobserved subgroups (profiles) when each case is described by several variables at once. It is the continuous-indicator member of the mixture-modeling family; its sibling **latent class analysis (LCA)** applies the same logic to categorical indicators. Both ask a different question from the variable-centered models that dominate AI-in-education research: not "how much does X predict Y on average" but "how many different kinds of learner, teacher, or manager hide inside that average." In this knowledge base the method shows that one AI tool lands very differently across subgroups — five ethical-awareness profiles among Ghanaian undergraduates, six readiness typologies among Ukrainian education managers, four generative-AI-acceptance profiles among Taiwanese pre-service teachers.

Questions to Consider

- A study reports that students' average comfort with AI is 3.8 out of 5. What might that average conceal if one group is enthusiastic and another quietly resistant?
- LPA models continuous scores; LCA models categories. If you code interview responses as "mentions overreliance: yes/no," which do you need?
- A five-profile solution reports entropy of 0.816; a four-profile rival scores 0.929 but describes the data less richly. Which would you publish?
- Profiles are descriptive, not causal. If a "Resistant Skeptics" profile shows high ease of use but low intention to adopt, what does that support, and what does it not?

Introduction

Most AI-in-education evidence is variable-centered: it estimates average relationships, and averages assume homogeneity. Person-centered methods instead take the person as the unit of analysis and ask how many distinct configurations of attributes exist in the sample. LPA belongs to that family, and its payoff here is that it converts learner diversity from a rhetorical claim into a measurable finding: when the ethical-awareness profiles spread from 26.1 percent to 4.5 percent despite a comfortable sample mean, differentiation stops being a design preference.

What the method does, and when it is the right tool

LPA assumes the sample is drawn from a mixture of subgroups, each with its own means and variances on the indicators. The researcher supplies the indicators and the number of groups; the algorithm estimates each case's probability of membership and assigns by highest probability, returning a mean profile per group, a

size per profile, and a summary of how cleanly cases separate. Which member of the family you use follows the indicators, not the research question:

- **LCA — categorical indicators.** Becker and colleagues converted coded response categories from 1,189 physics students' open answers into indicator variables and retained two classes: Pragmatic Users (70 percent) and Skeptical Non-Users (30 percent); because an unmentioned topic counts as "no endorsement," the authors flag zero-inflation in the analysis dataframe.
- **LPA — continuous indicators** such as scale scores and construct means. Chen and colleagues profiled 128 Taiwanese pre-service teachers on five TAM/UTAUT2 constructs; Acquah and colleagues profiled 509 Ghanaian undergraduates on three ethical-awareness dimensions; Schweder and colleagues profiled 2,464 students on motivational need satisfaction.
- **Latent (profile) transition analysis** extends the family over time, estimating profiles per wave and the probability of moving between them. Liang and colleagues tracked 2,086 students' AI learning motivation across a year; Wu (2026) followed 457 Japanese-language learners over three waves, the maladaptive profile shrinking from 26.48 to 17.74 percent.

Ordinary clustering (k-means and hierarchical) pursues the same person-centered intent but partitions cases by geometric distance rather than estimating a probability model. Reach for LPA or LCA when the question concerns subgroups — whether "the learner" is a fiction at your sample's level of aggregation, and whether subgroups differ in shape as well as level. Do not reach for it when you need an average treatment effect: a five-profile solution inside a randomized trial of an adaptive tutor predicted posttest differences (partial η^2 = .27) but found no condition × profile interaction (ps ≥ .198).

How the corpus uses it

Three uses recur.

- **Establishing heterogeneity before designing for it.** Kremen and colleagues' survey of 395 Ukrainian education managers used person-centered LCA to show that "the manager" is a fiction: six typologies run from Competency-constrained (25.6 percent, willing but unskilled) to Barrier-free skeptics (highest readiness yet 74 percent AI distrust), and the authors read them as a mandate for differentiated training.
- **Cross-system alignment as a stability check.** Fang and Jin (2026) retained four belief profiles from 40,680 teachers across 49 education systems (Indifferent 6.13% to Measured Endorsement 56.29%), and changing the alignment reference left classification agreement at 99.62% — while utility ordered the profiles identically in all 49 systems and risk did not.
- **Recovering subgroups an aggregate hides.** Acquah and colleagues retained five ethical-awareness profiles from Comprehensive Very High (26.1 percent) to Low Ethical Awareness (4.5 percent, beneficence 2.06), a spread running from just over a quarter of the sample to under a twentieth. Chen and colleagues found that Resistant Skeptics reported high perceived ease of use but very low behavioral intention — the corpus's clearest demonstration that the ease-of-use/intention paradox is invisible to a mean-level model.
- **Profiling calibration rather than level.** The teacher AI-literacy study applied LPA to the agreement between self-report and objective measures, yielding six profiles: overestimation,

underestimation, alignment, and a low/low group concentrated among teachers without prior AI literacy experience. Here profiles describe a pattern across instruments, not a score band.

Profiles then serve as an independent variable: discipline shaped membership among pre-service teachers (Cramér's V = 0.532, STEM students concentrated in Technology Pioneers), and membership predicted later Self-Efficacy, burnout, and AI anxiety elsewhere in the corpus.

Choosing the number of profiles

No single statistic selects the solution; the corpus treats retention as a judgment made from several criteria together.

- **Information criteria (BIC, AIC).** Lower is usually better, but a monotonic decline signals a problem rather than a winner. In the Ukrainian manager study BIC fell monotonically across the two- to six-class range with no clear minimum, and the authors call their six-class solution exploratory on that evidence.
- **Entropy.** A summary of classification certainty, closer to 1 meaning cleaner assignment. Chen and colleagues report 0.985 for four profiles; Acquah and colleagues report 0.816 for five profiles against 0.929 for four, and themselves suggest consolidating for a more stable grouping.
- **Interpretability and profile size.** The trust-in-AI profiling study kept three clusters although the Calinski–Harabasz index preferred two, because three were interpretable, and it notes that a silhouette coefficient of 0.288 signals weak or borderline separation. Chen and colleagues warn that their smallest profile (14.06 percent of 128 cases) may be unstable, and the Ghana study's smallest profile holds only 23 students, which its authors propose merging.
- **Stability under resampling.** Bootstrap stability is the honest check on whether profiles would recur in a new sample: mean adjusted Rand index was 0.385 for the Ukrainian six-class solution but 0.989 across 100 random initializations in the trust-in-AI study — the same nominal design, very different evidential weight.
- **Bootstrap likelihood ratio tests (BLRT)** and the Lo–Mendell–Rubin test are standard companions to BIC and entropy in the wider mixture-modeling literature, but the profile studies in this knowledge base do not report them. Where a page reports only BIC and entropy, treat the class count as provisional.
- **The likelihood-ratio check this corpus otherwise omits.** Song et al. (2026) retained four profiles (entropy 0.824) from 379 business students and reported the Lo–Mendell–Rubin decision: significant at four ($p = 0.035$) and nonsignificant at five ($p = 0.376$).
- **Retention defended with the rival solution and a likelihood-ratio test.** Suriá-Martínez et al. (2026) report that a four-profile solution fit the 102 students slightly better but did not improve significantly and left a smallest class at 12.7 percent, so they retain three profiles (entropy .89) rather than the numerically better-fitting model. Reporting the losing solution and what disqualified it is what makes the retained class count a judgment readers can check, and the study's purpose-built 12-item AI-use measure — validated on a separate sample of 85 that the authors call preliminary — marks the other boundary of its evidence.

Report the comparisons, not just the winner: a page that says “we retained five profiles” without the rival solution, the entropy values, and the smallest profile’s size gives readers no way to judge the choice.

Reading and reporting the results, and where they go wrong

Read a profile by its shape as well as its level. In the Ghana study the profiles differ in the configuration of autonomy, beneficence, and fairness — the largest pairs strong autonomy endorsement with lower beneficence — so two profiles can sit at similar overall levels and still call for different teaching.

Four cautions, each stated in the source pages:

1. **Profiles are descriptive.** They say who is in the sample, not why, and cross-sectional designs cannot show stability or movement (the pre-service teacher, Ghana, and physics studies). Only the longitudinal analyses — a year-long transition study and Wu’s three waves — support claims about movement, and even there movement is association, not intervention effect.
2. **Membership is estimated, not observed.** Cases are assigned by highest posterior probability, so individuals near a boundary are classified with real uncertainty; low entropy and weak silhouette values mean the boundaries should be read as soft.
3. **Indicator choice defines the answer.** Profiles depend entirely on which variables enter the model, so heterogeneity the study never measures is heterogeneity it cannot find — the Ghana study collected only gender among backgrounds and therefore cannot say what predicts membership.
4. **Detected heterogeneity is not detected causation.** The tutor trial’s profile × condition null is the reminder: profiling an outcome inside a trial is not a moderation test of the treatment.

Implications for AI in education

1. **Measure heterogeneity before recommending an intervention.** Profiles in this corpus repeatedly place a quarter or more of a sample below the headline average; design for the profiles that exist rather than for the mean.
2. **Prefer person-centered methods when the deliverable is differentiation.** The pre-service teacher and manager studies both present that shift as their methodological contribution, because average predictors cannot reveal the configurations that justify differentiated support.
3. **Report retention evidence in full.** Publish BIC/AIC comparisons, entropy, profile sizes, and a stability check, and say plainly when a class count is exploratory.
4. **Treat profiles as diagnostics, not labels.** A profile is a research construct with an estimated boundary, so a tool that assigns individuals to named categories carries the caution of any measurement instrument — and differential effects across learner groups warrant the scrutiny of any subgroup analysis.

Common Misconceptions

- **“Latent profile analysis discovers groups that exist.”** LPA converts learner diversity from a rhetorical claim into a measurable finding, and the profiles are a **model of a continuum divided at chosen boundaries**, not natural kinds. The number of profiles is an analytic decision.

- **“Any member of the latent-variable family is fine.”** Which one you use **follows the indicators**: **LCA for categorical indicators**, LPA for continuous. Choosing the method first and the indicators second makes the result an artifact of the choice.
- **“Profiles are comparable across studies.”** Chen and colleagues profiled **128 Taiwanese pre-service teachers** on five TAM/UTAUT2 constructs, while Acquah and colleagues profiled **509 Ghanaian undergraduates**. Different indicators in different populations do not produce commensurable profile labels.

Connected Concepts

- Quantitative Research
- Mixed-Methods Research
- Research Methods in AIED
- Machine Learning
- Learning Analytics
- Learner Modeling and Adaptive Instruction
- Educational Measurement
- Self-Report Measures
- Differential Effects Across Learner Groups
- Technology Adoption Models

Connected Articles

- Beyond Positive or Negative: Latent Profiles of University Students’ AI Attitude and Their Career-Development Correlates — Lo–Mendell–Rubin retention evidence for four AI-attitude profiles in 379 business students
- Profiles and transitions of psychological adaptation in AI-assisted Japanese language learning — Three-wave latent profile transition analysis of psychological adaptation
- From disengaged to self-determined: a latent transition analysis of students’ AI learning motivation — Latent transition analysis of three motivation profiles over a year
- Psychological Profiles Associated with Trust in Artificial Intelligence Among University Students: A Machine Learning Clustering Approach — K-means profiles; silhouette vs. Calinski–Harabasz disagreement; ARI 0.989
- Uncovering adoption personas for generative AI in higher education: a clustering-based segmentation approach — Hierarchical and k-means clustering into four GenAI adoption personas
- Teachers’ AI Belief Profiles and Their Associations with AI Use, Pedagogical Applications, and Barriers: A Person-Centered Analysis of TALIS 2024 — Four teacher AI-belief profiles from 40,680 teachers in 49 systems, with alignment stability

Network Analysis

> **Network analysis** — the family of research methods that model entities (people, concepts, actions, or codes) as **nodes** connected by **edges** representing relationships or transitions, then analyze the structure and dynamics of the resulting network to reveal patterns invisible to frequency counts or pairwise comparisons. In AI-in-education research, network analysis is used to map interaction patterns between learners and AI tools, model how knowledge or discourse elements co-occur, and trace temporal sequences of behavior. It includes distinct variants — **Epistemic Network Analysis** (ENA, modeling the co-occurrence of codes/constructs), **Social Network Analysis** (SNA, modeling relationships between people), and **Transition Network Analysis** (TNA, modeling temporal sequences of states) — each of which operationalizes "learning as connection" in a different way. (Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing) (Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing) (Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies)

Questions to Consider

- When you hear 'network analysis' in education, what images come to mind—friendship maps of students, links between ideas, or something else? How are those different from simply counting how often things occur?
- Suppose you wanted to know whether students actually engage with an AI writing tool's feedback versus just getting answers. Why might a 'how many times did they click' metric miss the story that a sequence of actions (e.g., a revision loop vs. a chat loop) would reveal?
- The page distinguishes Epistemic, Social, and Transition network analysis. Without knowing the details, can you guess which variant you'd use to study (a) how people collaborate, (b) which ideas co-occur in student reasoning, and (c) how learners move between states over time?
- A researcher finds that high- and low-literacy learners use the same AI tool but produce very different network structures of reasoning. What does that tell you about evaluating AI tools with a single average score?
- Network metrics like 'density' and 'centrality' describe whether interaction is random or organized around hubs. When would an organized network centered on one learner be a sign of good collaboration—and when a sign of a problem?

Introduction

Network analysis methods share a core premise: that the structure of connections — not just their presence or frequency — carries meaning. Rather than asking "how much of X occurred," they ask "how are elements connected, and what does that connectivity reveal about cognition, collaboration, or learning processes?" This makes them especially valuable in AI-in-education, where researchers increasingly want to understand the *process* of learner–AI interaction (how learners navigate Feedback, dialogue, and revision) rather than only the product (final scores, error rates).

Variants used in the knowledge base's corpus

- **Epistemic Network Analysis (ENA)** — the most common variant in the knowledge base (discussed in ~24 articles). ENA models the co-occurrence of codes or constructs within segments of discourse or activity, producing networks that show which ideas, skills, or epistemic actions tend to be connected in a given context. It is used to compare how different groups (e.g., high- vs. low-literacy learners, human vs. AI collaborators) structure their cognition. (Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing) (Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective)
- **ENA also maps educators' competency talk.** Applying Epistemic Network Analysis to interviews with 24 higher education educators in Aotearoa New Zealand modeled the links among seven HACC dimensions and found principal educators' networks differing significantly from senior educators (U = 10.00, p = .04) and early-career educators (U = 7.00, p = .01) on the first axis (Dang et al. (2026)).
- **Social Network Analysis (SNA)** — models relationships between people (learners, teachers, agents) to reveal collaboration structures, influence, centrality, and community. Useful for studying collaborative and peer learning. (Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies)
- **Transition Network Analysis (TNA)** — models temporal sequences of discrete states (e.g., learner actions in a tutoring session) as a directed network, quantifying the probability of moving between states. TNA is used to reveal behavioral loops, pathways, and uptake dynamics in learner–AI interaction. (Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing)

These differ from a **Knowledge Graph**, which is a data structure for representing and reasoning over facts (an ontology/triple store), not an analytical method for studying process or relationship structure.

Network analysis in AI-in-education research

Network methods are used across the knowledge base's evidence base to answer questions that aggregate metrics cannot:

- **Open the "black box" of learner–AI interaction.** TNA reveals the *process* — the behavioral loops and pathways learners take when using AI tools (e.g., a "revision loop" vs. a "chat loop" in chatbot-scaffolded writing) rather than just final output. (Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing)
- **Compare cognitive structuring across groups.** ENA shows how different groups connect constructs differently — e.g., how Metacognition co-occurs with delegation vs. human reasoning in human–AI collaboration, revealing different collaboration modes. (Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective)
- **Trace AI-literacy and interaction signatures.** ENA on interaction logs identifies distinct patterns of LLM use (iterative strategic refinement vs. linear commands), distinguishing learner

proficiency and development. (Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing)

- **Analyze discourse and framing.** ENA is applied to qualitative and Multimodal AI data (e.g., YouTube frames of ChatGPT in education) to reveal the structure of public or disciplinary discourse. (How YouTube Frames ChatGPT Use in Education: An Epistemic Network Analysis with Supporting Multimodal Metadata)
- **Complement self-report and product metrics.** Because network methods use observed behavioral data, they can expose discrepancies between what learners claim and what they actually do — a recurring finding in the knowledge base's feedback-uptake literature.
- **Graph structure as a validation quantity, not a descriptive summary.** Inoue & Yasutake (2026) track β0 - the number of connected components of a weekly proximity graph over learners at a fixed Euclidean threshold - to test whether synthetic cohorts reproduce the real ones, preferring it because it is fixed by the graph alone, needs no optimization or random seed unlike modularity maximization, and stays defined when a seventh to a third of learners sit alone in a component.

Methodological considerations

- **Coding is the foundation.** All network variants depend on reliably coding raw data (utterances, events, relationships) into discrete nodes/codes; automated LLM-based coding is increasingly used but requires human validation (e.g., Fleiss' κ of 0.70–0.71 in TNA studies). (Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing)
- **Treating coder agreement as a running check, not a one-off statistic.** Galiç et al. (2026) coded 304 noticing statements at Krippendorff's α = .803 and monitored agreement across the study, re-coding disputed statements whenever pooled κ fell below their .85 recalibration threshold (at Cases 18 and 27) and needing no further recalibration by Cases 36–51. The sequence is the point: reliability measured only at the end would have left the early transition models resting on coder drift, since those weekly transition patterns were the study's finding.
- **Network-level metrics summarize structure.** Density, reciprocity, centralization, and in-/out-strength describe whether interaction is random or organized around "gravitational" hubs, and how reciprocal the exchange is.
- **Statistical comparison is needed for group differences.** Chi-squared tests or permutation testing are used to establish that observed network differences (e.g., by proficiency) are not due to chance. Shao et al. (2026) show the null has to be built to match the text. In a case discussion with twenty mixed-discipline graduate students, the size-3 shared-term share rose from 5.2% to 8.0% while content tokens fell to roughly 0.65× their post-reading level. A whole-bag permutation test would have called that rise significant; their length-conditioned token-permutation test did not (Q6 p = .62, Q7 p = .15).
- **Validate the instrument before reading its network.** Alatoai & Alshahri (2026) built the 45-item AI-STEM-MLCS by the full scale-development route — expert content-validity ratios, exploratory then confirmatory factor analysis (CFI = 0.983, RMSEA = 0.019), McDonald's ω of 0.888–0.905, and two-week test-retest ICCs of 0.751–0.900 — before modeling the four

dimensions with exploratory graph analysis. Deriving structure from a network whose nodes are unvalidated scale scores is what that ordering guards against, and the authors name the Saudi-specific validation as the boundary on transferring the structure.

- **Interpret with care.** Node granularity (e.g., a coarse "chat" node) can obscure intent; automated classification carries some ambiguity; and cross-sectional network structure does not establish causality.
- **Networks that expose what an aggregate hides.** Pan et al. (2026) found the GenAI-annotating class outscored and out-engaged its control, then split the experimental class by median performance and showed the gain was not shared: high-achieving groups initiated 60.7 percent of feedback requests across their annotations against 34.0 percent for low-achieving groups, which stayed in a self-referential loop (group separation significant on the ENA X-axis, U = 25.00, p = 0.01). The design lesson is that one group-level effect can summarize two different interaction structures — and the two groups were intact classes, so the comparison identifies the pattern without attributing it causally.
- **Co-word and co-authorship clusters record publishing practice as much as intellectual affinity.** Bulut (2026) warns that bibliometric centrality and clustering reflect which venues, languages and regions are indexed, so a map of a field is not a neutral measurement of it.

Implications for AI-in-education research

1. **Prefer process methods over product-only metrics.** To evaluate whether AI tools support learning, model how learners actually engage (uptake, dialogue, revision) with sequence/network methods rather than relying on final scores alone.
2. **Use ENA to compare cognitive structuring.** When asking how different learners or modes (human vs. AI) structure their reasoning, ENA provides a direct, visual comparison of co-occurrence networks — a technique well-suited to student modeling of how learners connect ideas.
3. **Validate automated coding.** With large log datasets, LLM-based classification is powerful but must be checked against human coding (report inter-rater agreement) before interpreting network structure.
4. **Design for differentiation.** Network analysis often reveals that the *same* AI tool produces different interaction patterns across learner subgroups — informing adaptive design rather than one-size-fits-all evaluation.

ENA Validation of Simulated Collaborative Dialogue

- **ENA as validation for simulated dialogue.** Fang (2026) applies Epistemic Network Analysis to evaluate whether fine-tuned LLM agents reproduce the structure of real collaborative Problem Solving dialogue. Comparing simulated adjacency vectors to the empirical network, he reports an ENA distance of 0.17 — within the 95th-percentile threshold of the null distribution, with a permutation p-value of 0.65 — demonstrating ENA's power as a quantitative check on the fidelity of generative simulations of discourse, alongside other applications of ENA/SNA/TNA in education research.

Common Misconceptions

- **“Network analysis is objective because it is computational.” Coding is the foundation**: all network variants depend on reliably coding raw data (utterances, events, relationships) into discrete nodes, and automated coding inherits its definitions from whoever set them. The Visualization looks like an emergent structure and its nodes are interpretive choices.
- **“A shift in network structure is automatically a learning gain in itself.”** In a case discussion with **twenty mixed-discipline graduate students**, the **size-3 shared-term share rose from 5.2% to 8.0%** while **content tokens fell to roughly 0.65× their post-r**ate. Two structural measures moved in opposite directions, so “the network changed” is not a finding until you say along which measure and why it matters.
- **“Sharing more terms means better collaboration.”** Rising shared-term share alongside falling content-token diversity is consistent with convergence on a smaller vocabulary. Consensus and narrowing are structurally similar, which is why the measure needs the content it was computed from.

Connected Concepts

- Learning Analytics
- Knowledge Graph
- Meta-Analysis and Systematic Review
- Learner Modeling and Adaptive Instruction
- Student Engagement
- Collaborative Learning
- Metacognition
- AI Literacy
- Scaffolding
- Feedback

Connected Articles

- Response-Length Confounding in Participant–Morpheme Networks: A Length-Controlled Test in AI Ethics Education — Response length, not lexical alignment, drives shared-term statistics in participant–morpheme networks (Shao et al. 2026)
- Penny: Transition Network Analysis of Learner-Chatbot Interactions in Scaffolded EFL Writing — TNA of learner-chatbot interactions in scaffolded EFL writing
- Tracing GenAI Literacy: Student-AI Interaction Patterns in Academic Writing — ENA of GenAI literacy interaction patterns
- Unpacking Interaction Profiles and Strategies in Human-AI Collaborative Problem Solving: A Cognitive Distribution and Regulation Perspective — ENA of human-AI collaborative problem solving

- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies — Cognitive offloading and prompting (SNA/network methods)
- How YouTube Frames ChatGPT Use in Education: An Epistemic Network Analysis with Supporting Multimodal Metadata — ENA of YouTube frames of ChatGPT in education
- The agency gap in AI-supported writing: How reactive and proactive agent designs shape multimodal reasoning — The agency gap in AI-supported writing (ENA)
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- Conceptualising Human–AI Collaboration Competency for hybrid intelligence: towards learner agency through a metacognitive perspective — ENA also maps educators' competency talk

Evaluation of AI systems

AI Ed Evaluation

> **AI-ed evaluation** — the body of methods, benchmarks, and criteria used to assess whether AI education tools (Large Language Models (LLMs)-based tutors, automated graders, feedback systems, agents) actually work — not just on headline accuracy, but on reliability, pedagogical quality, validity, and real learning impact. A recurring theme across the knowledge base's research is that evaluation must be domain-specific, reliability-aware, and anchored in human judgment and educational outcomes rather than single aggregate accuracy numbers.

Questions to Consider

- How would you decide whether an AI tutoring tool 'works'? What evidence — beyond a headline accuracy number — would convince you it actually improves learning?
- A key finding is that reliability does not guarantee validity: a system can be highly consistent yet misjudge what good teaching looks like. Why might a stable, repeatable AI still be wrong?
- Evaluation must be domain-specific — a benchmark that works for one subject can mislead for another. When you see a glowing benchmark result for an AI tool, what would you want to check about the context?
- The 'ground truth' systems are judged against is often contested — what counts as a correct answer or grade varies across experts and disciplines. How does that uncertainty complicate trusting any evaluation?
- Research shows text-based LLM evaluators privilege explicitly verbalized behaviors and under-weight implicit context — an 'explicit-cue bias.' What kinds of good teaching might a machine systematically miss because it only looks for the obvious?
- Modern evaluation also weighs environmental and infrastructural cost — energy, hardware — not just output quality. Should Sustainability factor into how you judge an AI tool's value?

Introduction

AI-ed evaluation spans several distinct objects of assessment. It can evaluate the **output** (is the AI's answer, grade, or feedback correct and reliable?), the **process** (does the tool support valid, defensible assessment and learning?), and the **agent** (does an AI tutor or agent teach effectively and behave appropriately?). Each requires different methods and raises different validity questions.

The field's decade-long arc is itself a frame: Xiong and Li (2026) trace three eras — Formative (2015–2018), Expansion (2019–2022) and Generative (2023–present) — across 313 articles, and argue that constructs and validity arguments must be rewritten for human–AI collaboration, since IRT and Classical Test Theory models were built on unassisted human performance.

How AI-ed evaluation appears in the research

- **Output reliability and ground truth:** Modernizing ground truth argues that reliability problems in AI-ed evaluation often trace back to the reference data itself — the "ground truth" labels systems are judged against — and proposes four shifts toward improving reliability and validity. Calibrating trustworthiness co-designs evaluation metrics and visualizations with stakeholders so that trust in an AI tool rests on demonstrated, interpretable evidence.
- **Automated grading and scoring:** LLM short-answer grading, confidence-aware ASAG, CoTAL human-in-the-loop prompt engineering, and cognitive-diagnosis of handwritten math show that LLMs can grade and diagnose, but that reliability depends on human oversight, domain-specific grounding, and confidence calibration rather than raw model size.
- **A benchmark for pedagogical knowledge rather than content.** Lelièvre et al. (2025) score 97 models on Chilean teacher-exam items (CDPK 28–89%), many exceeding an estimated ~50% human baseline, yet the static multiple-choice items cannot test lesson planning or turn-by-turn scaffolding.
- **Recognition is not generation.** On TutorCaseBench, the best of 11 models picked a documented strategy on 63.0% of four-option items but satisfied a documented intervention in only 55.8% of free-response cases, so strategy-selection scores overstate tutor readiness (Park et al. (2026)).
- **Validating generated items against a psychometric benchmark.** Isley et al. (2025) generated course-tailored exams for 71 classes and benchmarked 20 more against human-authored AP Statistics items, fitting a Bayesian hierarchical 2PL IRT model with pre-test anchors across 1,686 students; the AI items were easier but more discriminating ($\bar{\alpha}$ = 1.3 vs. 1.2).
- **Pedagogical quality and alignment:** Why machines misread pedagogical quality documents human–machine misalignment in judging what makes instruction good, and the Tutoring Effectiveness Index predicts tutor quality from teaching behavior. Responsible assessment in the AI era and authenticated processes argue that evaluation must reach beyond correct answers to whether assessment remains authentic, valid, and defensible when AI can produce the "products" of learning.
- **Production monitoring and judge calibration:** Rohlfs et al. (2026) report what happens when LLM-as-judge evaluation runs at product scale, drawing on a K-12 suite that serves millions of teacher and student messages each month. As the program matured, false positives came to dominate the evaluators' flags and misdirected analyst attention away from failures that warranted product change. Three changes — unanimous-fail panels of repeated judge runs, per-evaluator judge-model choices, and softened rubrics — cut confirmed false positives by 99% and raised per-flag precision from 0.6% to 49% across 21 deployed evaluators, while an egregious-failure set kept capture at 100%. The lesson for evaluation practice is that an evaluator's operating point, not its headline accuracy, decides whether a flag is actionable.
- **Judge diversity as a validity protocol.** A benchmark for instructional-design agents drew its judges from different model providers rather than one, reporting high inter-judge reliability across 1,017 scored scenarios (Jeon et al. (2026)).

- **Audit an explanation against the attribution it claims, not for fluency.** Pan et al. (2026) gate a model's narrations on arithmetic closure, cited covariates, decision fidelity and the unsafe-treatment rate, because fluent text is equally well-formed whether its signal is exact or noisy — 98.8% of narrations passed while the negative tail was truncated.
- **Prompt sensitivity is a first-order property of an LLM grader.** Habibullah et al. (2026) graded a 570-student computer-vision exam across 171 configurations and a 1,038-student Machine Learning exam across 162: a short "strict grader" preamble drove 14 of 17 open-weights models out of the graded band, while the replication reproduced the vulnerability but not its direction, improving seven models whose neutral prompts over-marked. One prompt's accuracy is not evidence of a usable grader, and signed bias belongs beside the mean-absolute-error figure; LoRA fine-tuning on pooled dual-graded examples brought five small models to human parity and nearly erased the persona sensitivity.
- **Ratable evidence is a design variable, not a property of the task.** Globerson et al. (2026) let an Executive LLM hold the rubric and steer the conversation toward the assessed skill, lifting ratable evidence to 92.4% for project management and 85% for conflict resolution, while telling participants to attend to the skill changed nothing.

Why evaluation is hard in AI-ed

AI-ed evaluation is difficult for several reasons. First, **reliability is not enough** — a system can agree with a rubric yet misjudge pedagogy, as human–machine alignment research shows. Second, **ground truth is contested** — what counts as a "correct" answer, grade, or teaching move is itself a judgment that varies across disciplines and experts, per ground-truth modernization. Third, **educational validity is multidimensional** — Assessment Validity, Formative Assessment, and Authentic Assessment each impose different criteria that a single accuracy metric cannot capture. Finally, **the target keeps moving** — agentic AI and Multimodal AI models demand evaluation frameworks (Agentic AI, tool-invariant assessment) rather than reuse of text-model benchmarks. Evaluation findings are also subject to the same cross-cutting limitations that affect all AIED research — they age as AI improves, depend on reproducibility and FAIR practices, and may rest on proprietary systems — so evaluation results should be read with the caveats in Limitations in AIEd Research. A further, emerging dimension is **resource sustainability**: on-premise deployments increasingly report energy consumption and hardware requirements (e.g., VRAM, mWh per query) alongside accuracy — see sustainable on-premise knowledge-base assistants — so that a complete evaluation weighs environmental and infrastructural cost, not just output quality.

Reliability does not guarantee validity. Validation of LLM-based classroom observation shows that a model can be highly stable across repeated evaluations yet still misalign with expert judgment, and conversely that models aligning well with experts are often more variable — reliability and accuracy decouple, so a single-pass accuracy figure can overstate dependability. The same study documents an **explicit-cue bias**: text-based LLM evaluators privilege explicitly verbalized behaviors and under-weight implicit or contextual evidence (e.g., sustained student self-regulation where a rubric allows high ratings on absence-tolerant criteria), producing systematic rather than random disagreement. This underscores that measurement reliability is a prerequisite for — not a proxy for — valid interpretation, and that evaluation must include repeated-measures stability checks alongside expert-anchored accuracy.

Even a validated long-horizon discourse model tracks independent outcome measures only weakly: NSPA's Student Reasoning and Teacher Uptake scores correlated with value-added models of teacher effectiveness at ρ = 0.10, so automated constructs need external outcome validation before they inform evaluation (Fang and Liu, 2026).

Evaluation of simulated learners faces the same standard: a simulator is valid only if its behavior is *epistemically* faithful rather than merely fluent, so it should be scored against its stated behavioral goal and environment, not generic humanness — and automated judges match expert human preferences about 65% of the time (Yuan et al. (2026)).

Aggregate accuracy hides who is served poorly. Evaluations of vision-language models on DrawEduMath show that overall accuracy obscures a systematic weakness: models underperform precisely on the student work that needs the most pedagogical help (erroneous, struggling-student work), so disaggregating evaluation by student proficiency and error status is necessary to avoid overstating capability and widening achievement gaps.

Binary correctness hides the failures that matter. On a three-way step-diagnosis benchmark of 10,836 simulated pairs, seven LLM tutors classified optimal steps near-perfectly (F1 94–99%) but valid alternatives at F1 0–76% and incorrect steps at 4–55% — over-rejection and over-validation — and accurate diagnosis still did not yield actionable feedback (Yasir et al. (2026)).

- **Perturbation controls show which evidence a model actually uses.** In VIRA-Bench, the best of 11 models answered 61.3% of tutoring-video questions against a 91.0% expert reference, and removing the video versus shuffling its order degraded different question layers — a cheaper diagnostic than another aggregate score (Wang et al. (2026)).
- **Reusing human instruments to evaluate LLMs needs a latent-structure check.** Strugatski et al. (2026) fit exploratory factor analysis separately for humans and six multimodal LLMs: LLM–human congruence stayed below the human–human baseline on both instruments, and parallel analysis retained different factor counts (five for humans versus four for LLMs).
- **Joint evaluation surfaces trade-offs a single score hides.** Jiang et al. (2026) score nine education-facing models on capability, safety, basic education and high-level cultivation under one protocol: the top six are statistically indistinguishable overall yet differ by 19.5 points on Safety, and Safety is strongly anti-correlated with Basic Education ($r = -0.83$).
- **Class skew can make an evaluation metric misleading.** Csibi and colleagues (2026) classified reflection level in 1,954 Hungarian Teacher Education essays in which 68% sat at a single level: one shallow configuration reached ROC-AUC 0.7131 on only 0.5162 accuracy, and class balancing lowered every metric (0.6672 accuracy without it against 0.6408 with it). Shallow models gave the best aggregate scores while transformers handled minority levels better, so the reported figure should follow the performance a decision actually depends on.
- **Benchmark and grader errors are mistaken for model failure.** Expert re-grading of six widely used physics benchmarks audited 250 rejected items and attributed 143 (57.20%) to benchmark defects and 95 (38.00%) to grader errors, leaving only 12 (4.80%) genuine model errors, so 95.20% of the measured gap was not attributable to the model. Repairing the items moved HLE-Physics mean@4 from 47.28% to 78.66% and CritPt mean@5 from 32.29% to a corrected

87.50%, converting an apparent frontier-model weakness into near-saturation. The audit argues that a reported score is a joint property of model, item bank and grader, and that expert adjudication should precede any capability claim drawn from a benchmark. (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks)

The velocity of the systems being evaluated is a further constraint. Harrison et al. (2026) describe the temporal problem directly: by the time a large-scale trial has been designed, delivered, analyzed and published, the technology under study may have changed materially, which pushes practice toward weak observational or usage data at exactly the moment stronger evidence is needed. Their answer is not to accept weaker designs but to shorten the loop — practitioner-led micro-randomized trials that retain the causal contrast and repeat it as the platform evolves.

- **Data fidelity is a separate evaluation problem from output quality.** Synthetic educational cohorts that reproduce each variable's summary statistics can still misstate the structure of the data: a weekly proximity graph over learners varied 2.6 to 4.9 times less across a term in the synthetic versions than in the real cohorts, so a fidelity score does not predict which analyses survive on real data (Inoue & Yasutake, 2026).
- **In-distribution accuracy is not deployability.** A Bloom-level classifier scoring a macro F1 of 0.88 on its curated item bank fell to 0.48 and 0.20 on two sets of AI-generated questions, a loss that tracked the near-absence of explicit Bloom trigger verbs rather than model size; untrained LLMs were the most robust option out of distribution (0.79 and 0.41–0.51) and retraining on labeled out-of-distribution data recovered the largest gains (up to 0.82), so transfer belongs in the report alongside in-distribution fit (Castanares et al., 2026).
- **An AI difficulty scale is an evaluation aid, not a grade.** AI difficulty estimates tracked problem-level pass rate strongly (rho = −0.871 across 79 problems) but weakened to −0.552 on a 106-problem CS101 sample and approached zero at exam level, so such scales belong in item review, not student evaluation (Yan et al. (2026)).

Connections to related concepts

AI-ed evaluation sits at the center of the knowledge base's methods and risks. It operationalizes Assessment Validity, Educational Measurement, and Benchmark within Assessment and Automated Assessment. Its call for human oversight connects to Human-in-the-Loop and Teaching, while its focus on reliability connects to Hallucination Risk, Confidence Aware AI Assessment, and Trust Calibration. The distinction between evaluating performance and evaluating learning links to performance vs. learning and to Learner Modeling and Adaptive Instruction; and evaluation of pedagogical agents connects to Intelligent Tutoring, LLM Training and Fine-Tuning, and Pedagogical Safety.

Evaluating learning gains

A central object of AI-ed evaluation is the **learning gain** — the measurable improvement in knowledge or skill an AI tool produces (see Learning Gains). Evaluating gains rigorously requires choosing the right outcome measure, because performance and learning diverge: AI can inflate immediate, AI-assisted task

performance while leaving durable, unassisted learning unchanged or reduced (see Faster Completion, Less Learning: Generative AI Reduced Study Time on Math Problems and the Knowledge They Build, The generative AI learning penalty: Evidence from Chinese secondary education). Effective gain evaluation therefore:

- **Uses unassisted, AI-resistant outcome measures.** Guardrail evidence and summative-assessment research show that proctored, closed-book, unassisted measures — not AI-assisted homework or take-home work — reveal genuine learning gains.
- **Distinguishes assisted performance from durable learning.** Meta-analysis shows AI can produce large productivity gains with no significant learning gain ($g \approx 0$), so evaluations must report both.
- **Technology generation may not matter, and cost data are missing.** Burneo et al. (2026) pool 14 randomized trials to an average 0.125 sd learning gain, with generative AI showing no advantage over earlier adaptive software (0.022 sd, SE 0.075) and comparable per-student costs reported in only two or three studies.
- **Pairs pre/post measures with validity checks.** Assessment Validity and Educational Measurement ground gain measurement; meta-analytic review pools effect sizes across studies to establish the field's gain evidence.
- **Disaggregates by learner and context.** Because Learning Gains vary by population, domain, and AI configuration, evaluation should report gains for different student subgroups (e.g., by prior proficiency, as VLM evaluations reveal for error status) rather than a single aggregate, and should connect gain findings to Meta-Analysis and Systematic Review to situate them in the wider evidence base.

Context-conditioned benchmarks are needed: Zhang et al. (2026) argue that prior tutoring benchmarks (MathTutorBench, MRBench, LearnLM) reward one side of the assistance dilemma or give underspecified guidance. TutorMoments instead replays teacher-identified pedagogical decision points, evaluating whether a tutor's help is appropriate to the specific learning moment — Scaffolding vs. rigor. - **The metric you choose can reverse your conclusions.** Zhang et al. (2026), evaluating AI teaching agents in medical education, found that an educational platform's undisclosed aggregate scores ranked agents nearly opposite to a transparent, expert-validated 8-dimension teaching-quality rubric (medical knowledge accuracy, pedagogical guidance, knowledge coverage, role-play quality, adaptive difficulty, medical safety, engagement, feedback). Platform scores index student performance; the rubric indexes agent teaching behavior – choosing the wrong metric determines which agents get adopted or refined. They also found LLM-as-evaluator leniency differs by model (some too lenient to discriminate), so automated scoring needs human calibration and is most trustworthy on cognitive-process dimensions. - **An error rate can hide the failure it is meant to catch.** Stanchev (2026) sent one text-to-speech recording of a medical English passage to four ASR services: the two free services returned 87.96% and 88.34% of the reference, while the two paid services returned 32.76% and 55.35% previews and so scored word-error rates of 73.21% and 48.77%. The high error rates came from tokens never returned rather than tokens misheard, so ranking on error rate alone treated an export restriction as a transcription failure. Coverage belongs beside the error rate whenever an automated metric stands in for the artifact a learner sees. - **Anchor evaluation suites to measured learning, not proxies.** Teaching-capability benchmarks, conversational-pedagogy rubrics and tutor latency should be validated against actual learning gains rather than treated as stand-ins for them, and latency is itself an evaluation axis because it

shapes whether students engage at all (Northcutt et al., 2026). - **A bibliometric map can expose what an evaluation culture rewards.** Across 1,403 medical-education publications, the most-cited works measured model capability — above all ChatGPT's performance on licensing examinations — while AI Governance scholarship lagged, so the authors call for empirical evaluation of governance frameworks rather than more capability tests (Sriram et al. (2026)). - **Expert-judgment evaluations need their own reliability accounting.** Puech et al. (2026) had 25 domain-matched experts rate 92 generated lecture videos against a rubric anchored to "a standard MOOC lecture's quality," judging 87% at or above the bar (mean 3.42 of 5). Every video was rated once by one reviewer (k = 1), so the design spreads the panel across the corpus at the cost of an inter-rater agreement statistic; a random-intercept model attributed about 35% of residual variance to the reviewer (ICC = 0.35) and the paper reports reviewer-clustered intervals instead of a single precision figure. An evaluation built on expert judgment is only as strong as the reliability analysis it publishes.

Common Misconceptions

- **"High scores on teacher exams mean the model is pedagogically competent." 97 models** were scored on Chilean teacher-exam items (**CDPK 28-89%**), with many exceeding an estimated **~50% human baseline** — yet the **static multiple-choice items cannot** test enacted judgment. Scoring well on the exam is bounded by what the exam measures.
- **"The scoring criterion is a technicality."** Strict match scored the same 2,250 tutoring dialogues at **42.1%** where a human-calibrated LLM-as-judge scored **81.3%** (Lee et al., 2026) — the criterion moves the number more than the tutor model, the strategy or the pipeline does.
- **"Recognition and generation are comparable capabilities." Recognition is not generation.** On TutorCaseBench, the best of **11 models** picked a documented strategy on **63.0% of four-option items** but satisfied a documented implementation criterion far less often. Selecting the right answer among four and producing it are different tasks.
- **"Model scores are meaningful without a validated instrument."** Course-tailored exams were generated for **71 classes** and benchmarked against human-authored AP Statistics items with a **Bayesian hierarchical 2PL** model — the instrument was fitted before the scores were interpreted.

Connected Concepts

- Interpreting and Applying AIEd Research
- AI-Assisted Educational Research — AI-Assisted Educational Research
- Assessment Validity — Validity of interpretation in AI-ed evaluation
- Educational Measurement — Measurement theory for assessing learning
- Psychometrically Aware AI — Applying psychometrics to AI-based assessment
- Benchmark — Standardized benchmarks for evaluating AI systems
- Automated Assessment — AI-based grading and scoring systems
- Learning Analytics — Data-driven analysis of learning behavior
- Research Methods in AIED — Research methods for AI in education
- Learning Gains — Measuring learning gains from AI tools
- Formative Assessment — Ongoing assessment to guide instruction

- Summative Assessment — Summative assessment: AI-resistant formats (oral, proctored, closed-book exams)
- Authentic Assessment — Assessment of real-world, transferable performance
- Human-in-the-Loop — Human oversight of AI evaluation
- Trust Calibration — Calibrating trust in AI systems
- Hallucination Risk — Risk of fabricated content in AI outputs
- Intelligent Tutoring — Evaluating AI tutoring systems
- Agentic AI — Evaluating autonomous AI agent behavior

Connected Articles

- TutorCaseBench: A Case-Grounded Benchmark for Evaluating LLM Tutors in Supporting Students with Challenging Behaviors — TutorCaseBench: evaluating LLM tutors on students with challenging behaviors (Park et al. 2026)
- VIRA-Bench: Diagnosing Pedagogical Contingency Understanding in Online Tutoring Videos — VIRA-Bench: Diagnosing Pedagogical Contingency Understanding in Online Tutoring Videos
- What Platform Scores Miss: Multidimensional Evaluation of AI Teaching Agents in Medical Education — What platform scores miss: multidimensional evaluation of AI teaching agents
- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- Assessing the Quality of AI-Generated Exams: A Large-Scale Field Study — Assessing the quality of AI-generated exams: a large-scale field study
- Neuro-symbolic pedagogical alignment (NSPA) for long-horizon classroom discourse analysis: Mitigating dialect bias via counterfactual preference optimization — Neuro-symbolic pedagogical alignment (NSPA)
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most — Three-way classification benchmark of LLM tutoring agents (Yasir et al. 2026)
- The aftermath of DrawEduMath: Vision language models underperform with struggling students and misdiagnose errors — Evaluating VLMs on DrawEduMath: error content hardest (Lucy et al. 2026)
- Benchmarking the pedagogical knowledge of large language models — Benchmarking LLM pedagogical knowledge (CDPK + SEND)
- Validating AI-generated classroom observations: Reliability, accuracy, and limits of LLM-based pedagogical judgment — LLM classroom observation validation: reliability vs accuracy (Melo et al. 2026)
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — On-premise OER AI knowledge-base assistants: multi-dimensional evaluation
- Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education — Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity

- Calibrating Trustworthiness: Co-Designing Metrics and Visualizations for Evaluating LLMs in Education — Calibrating Trustworthiness: Co-Designing Metrics and Visualizations
- TeachBench - Evaluating LLM Teaching Ability — TeachBench: Evaluating LLM Teaching Ability
- Why Machines Misread Pedagogical Quality: Human-Machine Alignment in LLM-Based Pretest Question Evaluation — Why Machines Misread Pedagogical Quality: Human-Machine Alignment
- Confidence Estimation in Automatic Short Answer Grading with LLMs — Automatic Short Answer Grading With LLMs
- CoTAL: Human-in-the-Loop Prompt Engineering for Generalizable Formative Assessment Scoring and Feedback — CoTAL: Human-in-the-Loop Prompt Engineering for Formative Assessment
- Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work — Benchmarking LLMs for Diagnosing Students' Cognitive Skills
- The Tutoring Effectiveness Index: Predicting LLM Math Tutor Quality from Four Conversation Signals — The Tutoring Effectiveness Index: Predicting LLM Math Tutor Quality
- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents — ISD Agent Benchmark
- A Tool-Invariant Framework for Teaching and Assessing Computational Methods in the Age of Agentic AI — A Tool-Invariant Framework for Teaching and Assessing Computational Methods
- Towards valid student simulation with large language models — Toward Valid Student Simulation With Large Language Models
- From Evaluated Models to Evaluation Aids: A Multi-Evidence Study of LLM-Based Difficulty Calibration for Programming Examinations — From Evaluated Models to Evaluation Aids
- The theoretical foundation of Socratic tests: Dynamic, multimodal, conversational examinations — The Theoretical Foundation of Socratic Tests
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible Assessment in the AI Era
- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — From Authentic Products to Authenticated Processes
- Generative AI technologies and educational outcomes: a comprehensive meta-analysis comparing traditional and AI-driven approaches — Meta-analysis of generative AI educational outcomes
- When Help is Unhelpful: Evaluating AI Tutors for Productive Struggle — When Help is Unhelpful: evaluating AI tutors for productive struggle
- ELBench: A multi-dimensional benchmark for education-facing large language models — ELBench: education LLM benchmark
- Large-scale AI grading of handwritten physics assessments: Score agreement and Olympiad team selection outcomes — AI grading of handwritten physics assessments (Olympiad)
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — Distilling self-explaining LM for learning analytics
- Can EdTech close learning gaps? Global evidence from digital interventions — Meta-analytic evaluation of adaptive + AI EdTech

- A decade of reflection and thematic review on artificial intelligence's impact on educational measurement — AI's role across scoring, psychometrics, assessment
- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomized Trials of an AI Tutoring Platform in GCSE Science
- ProIQA: A Process-Based Framework for Fine-Grained Math Item Quality Assessment — ProIQA: Process-Based Math Item Quality Assessment
- Towards Scalable Measurement of Durable Skills — Toward Scalable Measurement of Durable Skills
- From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning — From Content Generation to Learning Support: Pedagogy-Guided Generative Video Tutors for STEM Learning
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- What fidelity metrics miss: A structural check on synthetic educational data — What Fidelity Metrics Miss: A Structural Check on Synthetic Educational Data
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions
- When Evaluators Cry Wolf: Lessons from Production LLM-as-Judge Evaluation in Educational AI — When Evaluators Cry Wolf: Lessons from Production LLM-as-Judge Evaluation in Educational AI
- Ethical and responsible use of artificial intelligence in medical education — A bibliometric map can expose what an evaluation culture rewards
- MisconceptDialogue: Evaluation Criteria Shape Measured Success in LLM Math Tutoring — MisconceptDialogue: Evaluation Criteria Shape Measured Success in LLM Math Tutoring (Lee et al. 2026)

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- What Are Notable Gaps in the Research Literature on AI in Education?
- Does Using AI Actually Help My Students Learn?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?

Benchmark

> **Benchmark** — standardized test suites and evaluation frameworks used to measure AI model performance on educational tasks. Benchmarks enable reproducible comparison across models and approaches, and are essential for evaluating the reliability, fairness, and pedagogical quality of AI in education systems.

Questions to Consider

- A benchmark is a standardized test suite for measuring AI model performance on educational tasks. Before reading, what do you think most AI benchmarks actually test — and why might that be a different thing from what a good tutor needs?
- This page highlights a Pedagogy Benchmark that tests pedagogical knowledge — teaching strategies, assessment methods, special-education pedagogy — rather than content knowledge. Why might an AI that knows a subject brilliantly still fail at teaching it, and why would a benchmark that ignores pedagogy miss that?
- One lesson here is methodological: how you validate a benchmark changes the results dramatically, with naive validation reporting far higher performance than rigorous trial-independent methods. How might a model developer or vendor be tempted to design validation to look good, and how would you spot that?
- Benchmark performance often doesn't transfer to real-world utility. Can you think of a scenario where an AI 'wins' a benchmark yet fails in an actual classroom — and what does that gap tell you about relying on benchmark scores alone?
- The page notes that benchmark design can itself encode or amplify bias. If a benchmark is made of certain tasks, in certain languages, from certain populations, whose learning does it end up measuring — and whose does it ignore?

Introduction

Benchmarks serve as the evidentiary foundation of AI in education research. They provide standardized datasets, tasks, and metrics that allow researchers to compare models, track progress, and identify failure modes. In the knowledge base's research, benchmarks appear across multiple domains:

- **CSTutorBench** evaluates small language models for CS tutoring tasks.
- **ANVIL** benchmarks AI-generated educational animations against human-created alternatives.
- **Teaching feedback benchmarks** assess cross-language transfer of feedback quality classification.
- **The Pedagogy Benchmark (CDPK + SEND)** tests pedagogical knowledge — teaching strategies, assessment methods, and special-education pedagogy — rather than content knowledge, and reports a cost-vs-accuracy "value frontier" across 97 models (most general benchmarks test content knowledge; pedagogy is a distinct, education-critical dimension).

- **ISD-Agent-Bench** benchmarks Large Language Models (LLMs)-based instructional-design agents across 25,795 instructional-design scenarios, showing that hybrid agents grounded in classical ISD frameworks (ADDIE, Dick & Carey, Rapid Prototyping) outperform pure theory or pure technique — a benchmark result with direct implications for agentic AI design in education.
- **TutorCaseBench** grounds tutor evaluation in documented case literature rather than simulated personas: 923 dialogues from special-education and educational-psychology cases, where the strongest of 11 models met a documented intervention in 55.8% of open-ended cases.
- **Learner adaptation as an explicit benchmark criterion.** The Teaching Monster Challenge scores adaptation to a specified learner persona, but its automated LLM-judge separated only a weak tail — the top systems scored near its ceiling and its ranking disagreed with crowd preference (Spearman $\rho = -0.17$) (Lin et al. (2026)).

Why benchmarks matter in AIED

Benchmarks connect to AI Ed Evaluation and Assessment Validity — without rigorous benchmarks, claims about AI tutoring effectiveness are unverifiable. They also intersect with Bias Mitigation, as benchmark design can encode or amplify biases. The tension between benchmark performance and real-world utility is explored across multiple articles, connecting to Transfer of Learning concerns in Generative AI applications.

- **When the metric, not the system, is the failure:** AlgoRAG scored BLEU-4 = 0.0000 on all 179 theoretical computer science exam questions while a six-criterion pedagogical rubric gave 0.7620, because logically equivalent proofs routinely differ in notation, variable names and proof strategy. A zero score says more about n-gram overlap than about answer quality, which is the general case against treating surface metrics as the headline number for formal-domain AIED systems.
- **Construct-level counterfactual benchmarks.** CFES-P24 expresses multimedia-learning principles as deterministic, reversible slide transformations to audit whether MLLMs respond to specific instructional-design constructs rather than producing plausible holistic ratings. A frozen pilot showed construct recognition (operation, principle, repair, evidence localization) at 8/8 while comparative judgment (direction 6/8) and severity calibration (0/8) failed — arguing for layered scorecards over composite scores.(Benchmarking Multimodal Large Language Models for Educational Slide Auditing)
- **Ground hallucination and energy in the evaluation, not just accuracy.** Shen et al. (2026) scored hallucination as entailment against the retrieved open-license chunks ($\kappa = 0.76$ with expert judgment) and logged 1.8 mWh per query, and their ablation put retrieval first: a local LLM with none scored 52.3%, below the 55.4% TF-IDF baseline.
- **Verification can beat judgment on generated content.** Kumar et al. (2025) back-translate generated math diagrams into a schema-constrained intermediate representation and run deterministic rule checks, reaching higher agreement with human raters (Cohen's κ 0.48–0.56) than LLM-as-a-Judge (0.39–0.47) and letting a small model match the best judge at 10× lower cost.
- **Trial-independent evaluation in physiological benchmarks.** Nanayakkara & Halloluwa (2026) benchmark 15 ML/DL models for EEG-based familiarity prediction and show that the choice of

validation scheme changes headline results dramatically: standard stratified cross-validation allows temporal leakage and reports up to 0.9853 F1, while trial-independent Group K-Fold validation drops the peak to 0.6038 F1. The lesson — temporal/leakage-aware evaluation is essential for credible educational benchmarks — extends beyond EEG to any benchmark using sequential or time-structured data.

- **Distribution shift is a second benchmark axis beyond leakage.** A benchmark that reports a classifier's in-distribution score and its transfer score is reporting two different quantities: a Bloom-level classifier held at macro F1 0.88 on its curated bank fell to 0.48 and 0.20 on two AI-generated question sets, and retraining on labeled out-of-distribution data recovered up to 0.82, so a single in-distribution leaderboard number overstates what a deployed instrument will do (Castanares et al., 2026).
- **A corpus built to test cross-corpus transfer.** ICLE++ annotates persuasive essays with holistic and ten trait-level scores to expose AES research's reliance on ASAP, whose timed, native-speaker-only essays confound length with quality; models trained on trait annotations transferred better across corpora than those trained on holistic scores alone (Li & Ng, 2026).
- **A human-normed benchmark may not measure the same construct for an LLM.** Strugatski et al. (2026) compared human and Multimodal AI-LLM response structures on a chemistry diagnostic and a quantitative-reasoning exam; factor congruence between LLMs and humans stayed below the human–human baseline and parallel analysis retained different factor counts.
- **Multimodality did not improve evidential calibration.** On MathCog, 3,036 teacher-annotated verdicts across 639 handwritten math responses, none of 18 LLMs reached macro F1 0.5 — the best, GPT-4o-img, scored 0.448 — and multimodal models degraded more than text-only ones when evidence was vague, over-attributing evidence and fabricating quotes (Kim et al. (2025)).
- **Synthetic benchmarks for AI tutoring.** Open, reproducible datasets for evaluating AI tutoring remain scarce. ASTRA (Adaptive Socially-intelligent Team Reasoning Agents) is a multi-agent tutoring prototype and benchmark framework for studying collaborative programming with socially differentiated agents, supporting alone-tutor, pair-tutor, and pair-multiagent configurations (N=540; 360 sessions; 1,440 episodes) with a trace-ready schema for reproducible analysis of interaction, participation balance, and verification.
- **Horizon is a benchmark axis, not a detail.** Lee et al. (2026) place a tutor agent in a continuous 30-day relationship with a simulated learner and find every adapter plateaued by day 5–10, no adapter led learning gain on more than one base-model tier, and the five scoring axes were largely independent.
- **A tutoring benchmark scored against human tutors rather than leaderboards.** StudentBench randomizes 2,383 adults across AI tutoring, live expert human tutoring, and a video control on newly written GRE items, finding pooled AI tutoring statistically equivalent to human tutoring (p=.015) and 5.5-6.9 percentage points above the control; its teaching-quality leaderboards, built from 2,028 expert pairwise comparisons, rank lesson plans and conversational behavior rather than how much students learned (Northcutt et al. (2026)).

- **Auditing benchmarks is now a research contribution in its own right.** Three 2026 artifacts push benchmark work past leaderboard aggregation. EduFair-Bench holds a simulated student fixed and varies demographic attributes, turning a tutoring benchmark into a fairness audit with turn-level pedagogical metrics (EduFair-Bench: Evaluating Pedagogical Fairness of LLM Tutors Across Student Demographics). GeoVAD-Bench diagnoses intermediate visual constructions — perception, auxiliary quality, utilization — rather than final correctness on 600 geometry problems (Beyond Generation and Accuracy: Diagnosing and Enhancing Visual Chain-of-Thought for Geometry Problem Solving). Expert re-grading of six physics benchmarks quantified the error such scores carry: 57.20% of audited rejections were item defects, 38.00% grader errors and only 4.80% true model failures (How Good Are Frontier Models at Physics? Expert Re-Grading Reveals Broken Evaluations and Near-Saturation of Leading Benchmarks). Together they argue that a benchmark score should always be read with its own audited error budget, which is the same discipline Assessment Validity asks of classroom instruments.
- **Decoupled annotation and question generation as a construction paradigm.** Most benchmarks build task-specific question–answer pairs per item or image, which makes extending to new tasks expensive, makes data hard to reuse across tasks, and leaves limited control over question form and complexity. MUSE inverts the order: annotate each artwork once into a reusable structured representation of its visual and semantic content, then instantiate 12 tasks from predefined generation rules, so one image yields a multi-view evaluation instance with difficulty and format treated as explicit design variables rather than by-products (MUSE: Benchmarking Large Vision-Language Models on Multi-Modal Understanding in Situated Education). Its correlation evidence is a second argument for the design — the 12 tasks measure related but non-redundant capabilities (Jigsaw Puzzle correlates weakly with most others, $\rho = 0.25$ to -0.10), and on six external benchmarks general multimodal scores transfer unevenly to artistic educational imagery (BLINK Jigsaw vs. MUSE Jigsaw $\rho = -0.20$), which is the construct-coverage case against reading any single aggregate score as a proxy for educationally relevant capability (MUSE: Benchmarking Large Vision-Language Models on Multi-Modal Understanding in Situated Education).
- **Multimodal output generation is the axis most benchmarks omit.** Chen et al. (2026) score 15,246 physics questions and 19,850 images from middle school through university, including a diagram-editing subset: synthesizing or editing structured physics diagrams proved harder than answering, and leading models stayed below 70% strict mastery.
- **K-12 science coverage and the saturation problem.** An NGSS-aligned benchmark for middle and high school science (1,078 + 1,150 synthetic items, three-judge validated) found nine open-weight models above 90% one-shot accuracy, while classical item statistics showed high difficulty values and low discrimination: model size did not predict performance, and the authors ask whether the test is too easy (A Benchmark for LLM's Understanding of Middle School and High School Science Topics). It is the domain-specific case for reading a benchmark's own item statistics alongside its leaderboard.
- **A trivial baseline and IRT ground truth as the check on headline accuracy.** Worden et al. (2026) build FoundationalASSIST from 1,722,169 ASSISTments interactions with question text and actual student responses preserved, score the Knowledge Tracing task against a 51.3 percent always-correct baseline, and read model competence against two-parameter IRT estimates

fitted on the same data. Four frontier models clear the trivial baseline by about five points (best 56.2 percent) and fall below chance at judging item discrimination. The failure a benchmark built for this purpose can see is that they predict correctness 85.4 percent of the time on correct answers but only 12.6 percent on incorrect ones, so their apparent skill is optimism bias.

- **A grader's configuration is itself a variable.** Habibullah et al. (2026) sweep 171 grading configurations over a dual-graded 570-student exam and find that a short "strict grader" preamble pushes 14 of 17 open-weights models out of the graded band, then replicate with 162 configurations on an independent 1,038-student exam whose results reproduce the vulnerability but not its direction. The best configuration (MAE 1.64/35, under the 2.61/35 human graders achieve against each other) is therefore not evidence that LLM grading works — though one LoRA adapter trained on the pooled human labels brings five small models to human parity while nearly erasing the persona sensitivity.
- **Constraining the corpus to make the capability claim attributable.** Li et al. (2026) filter FineWeb-Edu to 88B tokens of U.S. K–5 material and train a 5B model from scratch on it, then check the seam through behavioral probes rather than scores — retention near zero on Beyond-K–5 passages, collapse on Beyond-K–5 Jeopardy items, and fewer than half as many Grade 8 MathCAMPS problems solved even at pass@1024. Because the prior exposure is known, a capability that appears after scaling, post-training, or in-context examples can be credited to the intervention; the authors also report that the boundary is not human-shaped, since the model sometimes beats a downstream skill while failing its prerequisite.
- **The scoring rule is part of the instrument.** Srivastava (2026) runs four knowledge-tracing update rules over the same ASSISTments 2012–13 event sequences, differing only in how they score hint-assisted rows, and preregisters the comparisons behind a fence that withholds the confirmatory half of the students until the registration file is present. Crediting any completion barely beats a skill-difficulty constant (pooled AUC 0.604 vs. 0.595 across 985,813 scored events) and declares 93.9 percent of student–skill pairs mastered against 72.8 percent under a rule that reads assisted rows as failed first attempts (0.658) — the general lesson being that a mastery label is defined by the evidence rule, not by the log.
- **Report model ability as a calibrated level, not only as accuracy.** Min et al. (2026) map 624 expert-annotated items onto named proficiency levels using 2,050 learner responses, and find frontier models exceed the calibrated ceiling — a limit a percentage hides.
- **A scoring rule can be gamed by the model it trains.** An adaptivity metric maximized by repeating one best decision shows that benchmark design should publish the argmax, score adaptation as a difference, and report above-random baselines (Domínguez Figaredo & Fernández De la Cruz, 2026).

Common Misconceptions

- **"Leaderboard position tells you how good a tutor is."** StudentBench **randomizes 2,383 adults across AI tutoring, live expert human tutoring and a video** condition and scores against human tutors rather than against other systems. A benchmark scaled to other models answers a question nobody needed answered.

- **“Simulated personas are an adequate basis for tutor evaluation.”** TutorCaseBench grounds evaluation in **documented case literature rather than simulated personas**, using **923 dialogues**. Fabricated student personas let a system pass cases that do not occur.
- **“Benchmarks can be trusted without checking the judge.”** Hallucination was scored as **entailment against the retrieved open-license chunks (κ = 0.76 with expert judgment)** — the judge was validated against experts before its scores were used. An unvalidated automatic judge produces numbers of unknown meaning.

Connected Concepts

- AI Ed Evaluation
- Bias Mitigation
- Human-in-the-Loop
- Formative Assessment
- Knowledge Tracing
- Generative AI
- Automated Essay Scoring

Connected Articles

- TutorCaseBench: A Case-Grounded Benchmark for Evaluating LLM Tutors in Supporting Students with Challenging Behaviors — TutorCaseBench: evaluating LLM tutors on students with challenging behaviors (Park et al. 2026)
- Standardized Assessment of LLM English Proficiency — A 624-item English proficiency benchmark that reports model ability as a calibrated level (Min et al. 2026)
- OmniPhys: A unified multimodal benchmark for physics understanding and generation from Chinese educational corpora
- Do Assessment Instruments Measure the Same Thing for Humans and LLMs? A Latent Structure Analysis — Do assessment instruments measure the same thing for humans and LLMs? (Strugatski et al. 2026)
- Benchmarking the pedagogical knowledge of large language models — The Pedagogy Benchmark: LLM pedagogical knowledge (CDPK + SEND)
- ISD-Agent-Bench: A Comprehensive Benchmark for Evaluating LLM-based Instructional Design Agents — ISD-Agent-Bench: benchmarking LLM-based instructional-design agents
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — On-premise OER AI knowledge-base assistants: multi-dimensional benchmark
- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — From authentic products to authenticated processes: authentic assessment in AI-rich higher education

- Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work — Benchmarking Large Language Models for Diagnosing Students' Cognitive Skills from Handwritten Math Work
- EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners — EduClaw-Bench: A Long-Horizon Benchmark for Pedagogical LLM Agents with Simulated Learners
- Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference — Responsible Assessment in the AI Era: Key Insights from a Future-Focused Conference
- ANVIL: Analogies and Videos for Lecturers — ANVIL: Analogies and Videos for Lecturers
- ICLE++: Modeling Fine-Grained Traits for Holistic Essay Scoring — ICLE++: Modeling Fine-Grained Traits for Holistic Essay Scoring
- Findings of the first Teaching Monster Challenge: A benchmark of pedagogical content knowledge in AI agents
- Benchmarking Multimodal Large Language Models for Educational Slide Auditing — CFES-P24: Benchmarking Multimodal LLMs for Slide Auditing
- DiagramIR: An automatic pipeline for educational math diagram evaluation — DiagramIR: benchmark for evaluating generated math diagrams
- Automating Learner Assessment: Benchmarking Machine Learning and Deep Learning Models for EEG-Based Familiarity Prediction — Automating Learner Assessment: EEG-Based Familiarity Prediction
- AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory — AlgoRAG: Retrieval-Augmented Generation for Theoretical Computer Science Education – A Comprehensive Evaluation Framework for Algorithm Analysis and Complexity Theory
- MUSE: Benchmarking Large Vision-Language Models on Multi-Modal Understanding in Situated Education — MUSE: annotation-first, task-generative benchmark construction, and dimension-level non-redundancy across 12 artistic-imagery tasks (Zhu et al. 2026)
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions
- A Benchmark for LLM's Understanding of Middle School and High School Science Topics — A Benchmark for LLM's Understanding of Middle School and High School Science Topics
- The learner who does not learn: when optimizing a pedagogical metric degrades LLM tutoring — Eight design principles for AI-tutor benchmarks, derived from a metric that was optimized into repetition (Domínguez Figaredo & Fernández De la Cruz 2026)

Connected FAQs

- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

People

Roles and audiences

Administrators

> **Administrators** — the institutional, leadership, and decision-making view of AI adoption, strategy, and governance in education. Administrators and institutional leaders shape whether and how AI is adopted — through policy, funding, infrastructure, and the strategic framing of AI's role — and must weigh competing concerns about learning, equity, risk, and organizational capacity.

Questions to Consider

- AI adoption is often framed as a classroom decision, but administrators set the conditions — policy, funding, infrastructure. In your institution, who actually decides whether and how AI gets used, and who is left out of that decision?
- Research finds a recurring gap between high-level policy ambition and day-to-day implementation. Where have you seen a well-intentioned AI policy fail to reach the classroom, and why do you think it fell short?
- Administrators must balance pedagogical opportunity against risk, equity, and resourcing. If you had to choose between funding one new AI initiative and shoring up data governance and faculty training, which would you pick and why?
- Procurement decisions made at the institutional level can enable or constrain what teachers and students can actually do. What questions would you want answered before your institution signs a contract for an AI edtech platform?
- Institutions translate AI capability into acceptable-use frameworks and data standards. How do you weigh the promise of innovation against the privacy and equity implications of the data these tools collect?
- Administrator choices about AI Well-Being tools directly shape student experience. What evidence would you want to see before deploying an AI tool meant to support — rather than monitor — students?

Introduction

AI adoption in education is not purely a classroom decision; it is also an institutional one. Administrators — provosts, deans, CIOs, and institutional leaders — set the conditions under which faculty and students use AI, balancing pedagogical opportunity against governance, resourcing, and risk.

Student Defense (2026) supplies a portable procurement screen for exactly the decision administrators face: before deploying an AI product, ask what problem is being solved, whether governance capacity exists, whether the institution is being transparent, and whether the deployment creates value for students — framing the choice as one about students' rights, choices, finances and futures rather than a procurement transaction.

How the administrator perspective appears in the research

- **Policy and institutional decision-making:** UK higher-education AI policy research finds that AI integration is accelerating but fragmented, with a gap between high-level policy ambition and institutional implementation — a recurring theme for administrators navigating strategy without clear operational guidance.
- **A ten-domain taxonomy to organize the stack.** Sposato (2025) synthesized 314 publications into ten domains — from administrative efficiency through governance and DEI — giving leaders shared vocabulary for matching a stated institutional problem to the domains that address it.
- **Leadership structures lag strategic intent.** Baroudi (2026) found only 7% of institutions had created senior AI leadership roles even though 49% treated AI as a strategic priority, with empowering and distributive leadership styles associated with higher faculty engagement and the theory-implementation gap widest where policy and infrastructure are weak.
- **Well-being and student experience:** AI campus well-being tools examine how institutions deploy AI for student support, linking administrator choices to Student Experience outcomes.
- **Governance and regulation:** Administrator decisions interact with Educational AI Policy, AI Governance, and AI Regulation in Education — institutions translate AI capability into acceptable-use frameworks, assessment rules, and data-governance standards (see institutional GenAI policy analysis).

Connections

The administrator perspective connects to Educational AI Policy (policy formation), AI Governance and AI Regulation in Education (governance), Edtech Platform (procurement and infrastructure), Learning Analytics (institutional data), and Higher Education. Administrator decisions enable or constrain the Educational Development, Teaching, and AI Literacy work covered elsewhere in the knowledge base.

Common Misconceptions

- **“Strategic priority implies strategic capacity.”** Baroudi (2026) found only **7% of institutions had created senior AI leadership roles** even though **49% treated AI as a strategic priority**. The gap is not indifference — it is that intent has been declared while the structure that would carry it has not been funded. Reading a published AI strategy as evidence of institutional readiness overstates what exists.
- **“Adoption figures measure readiness.”** Declared use and governed use are different quantities, and this page’s evidence separates them: institutions report strategic intent at roughly half the population and leadership capacity at under a tenth. A survey showing that staff use AI tells you what individuals have already done without permission, not what the institution can support or supervise.
- **“Procurement is an administrative step.”** Where capability is purchased rather than built, the contractual terms decide what becomes possible later — data ownership, audit access, and

whether the tool can be evaluated at all. A vendor decision made as a purchasing task forecloses evaluation questions the institution has not yet asked.

- **"Governance can follow adoption."** The sequencing claim is common and unsupported here: the evidence documents the opposite pattern, with policy and leadership structures trailing use that is already happening. Governance framed as something to build after rollout is governance built from a position of less leverage.

What this means for practice

For administrators

- Budget the leadership role, not only the strategy document. When 49% declare AI a priority and 7% create senior roles, the binding constraint is allocation rather than conviction.
- Ask what a tool can be evaluated on before signing. If the contract does not permit access to outcomes, audit data or usage detail, the institution has purchased a capability it cannot assess.
- Survey actual use rather than sanctioned use, because the two diverge and the unsanctioned number is the one that carries risk you are already exposed to.
- Sequence policy ahead of rollout where leverage still exists. Once use is widespread, policy becomes negotiation with practice that has already settled.

Connected Concepts

- Educational AI Policy
- AI Governance
- AI Regulation in Education
- Higher Education
- Edtech Platform
- Learning Analytics
- Privacy
- Large Language Models (LLMs)
- Generative AI
- Student Experience
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Educational Development
- Teaching
- AI Literacy
- Student Support and Success — the institutional processes administrators run: advising, outreach, referral, and allocation

Connected Articles

- Artificial intelligence in educational leadership: a comprehensive taxonomy and future directions — AI in educational leadership: comprehensive taxonomy
- Anticipatory governance and leadership for AI implementation in higher education: A scoping review — Anticipatory governance and leadership for AI
- Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — AI in UK higher-education policy and institutional decision-making
- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach — AI-driven tools for campus well-being
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education — Institutional GenAI policy in computing
- A framework for institutional change in the age of AI — Institutional change framework for AI
- "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech
- Students at Stake: Risks of AI Deployment in Higher Education — A four-question procurement screen, framed as students' rights rather than as risk management

Connected FAQs

- How Do We Write and Implement an Institutional AI Policy?

Educational Technology Developers

> **Educational Technology Developers** — the people and organizations that build educational technology: product designers, software developers, learning engineers, learning-analytics designers, and the edtech companies, university labs and Open Source projects they work in. In AI in education this is the role that turns a model capability into something a teacher or learner can actually use. It carries decisions no later stage can undo: what evidence a design claim rests on, how far a analytics pipeline or a tutoring system is grounded in the institution's own licensed material, and whether teachers and learners are included in design. It also fixes which instructional design assumptions are baked into the defaults, and what happens to the product after the funding stops. Across the knowledge base's system reports and deployment studies, the recurring lesson is that the deployment context, not the model, is usually the binding constraint.

Questions to Consider

- If the meta-analyses claiming that "AI improves learning" rest on invalid methodology, as the audit in Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis found, what evidence is a product roadmap actually allowed to build on?
- Should an algorithm's explanations be written in the teacher's curricular language even when that costs more design effort than exposing feature importances — and who pays for that effort?
- When a tool is co-designed with students, whose verdict decides: measured learning gains, or the 96% who said they wanted it kept?
- Is on-premise, open-licensed deployment a technical choice or a governance one — and should transparency requirements become a condition of purchase?
- What does a developer owe an institution when the grant ends: a maintained product, a forkable repository, or a candid statement that the system was never a validated intervention?

Introduction

The developer sits one level below the platform. Edtech Platform describes the deployed system and the stakeholder it becomes once it is in a school or university; this page is about the people who decide what that system does. The distinction matters because platform-level findings — low take-up, equity skew, procurement friction — are usually consequences of design choices made earlier, by someone who never met the learners.

The role is also distinct from its neighbours. Learning Design and Curriculum Design design a course for a known cohort; a technology developer designs a product that many courses, taught by people they have never met, will use — which is why defaults, configurability and documentation carry pedagogical weight. Educational Development supports the teaching staff of an institution from inside it; developers sit outside or alongside, supplying the tools those staff are then asked to adopt. And Design-Based Research is the

evidence standard such developers are increasingly asked to meet: iterative, contextual, and reported with its own limitations.

Who builds educational AI

Research labs building public infrastructure. OATutor was built at UC Berkeley as the first fully open-source adaptive tutoring system on ITS principles: an MIT-licensed codebase with a Creative Commons algebra library, Bayesian Knowledge Tracing mastery estimation, A/B testing infrastructure and LTI support. Its reason for existing is a design decision — proprietary platforms had confined Adaptive Learning research to closed systems — and its authoring route is another: 16 creators produced a College Algebra course in six months after 2.27 hours of training.

Model builders. LearnLM: Improving Gemini for learning reframes improving a model for learning as pedagogical instruction following: behavior is set per application through system instructions rather than one fixed definition of Pedagogies and Teaching Strategies, and expert reviewers preferred it by +31% over GPT-4o and +13% over base Gemini. The practical point is that pedagogy is too context-dependent to define globally; the useful capability is adherence to the instructions a developer writes, measured by conversation-level scenarios rather than single-turn benchmarks.

Architects of knowledge models. Ontology-based layered hybrid AI-driven knowledge model for personalized e-learning argues Personalized Learning needs more than a static ontology, proposing systems of mapped ontologies plus rules and analytics in place of the classic four-model ITS architecture, and a reuse framework of eight metadata classes that aims to cut the cost of each new build.

Infrastructure and measurement engineers. Generalizing a Highly Configurable Analytics Pipeline to Replicate and Support Educational Research Across Multiple Domains describes a modular, domain-agnostic pipeline for learner interaction data validated across three educational AI assistants, where methods built for one domain extended to another — reusable Learning Analytics infrastructure rather than a one-course dashboard. StanBKT: Rethinking Parameter Estimation in Bayesian Knowledge Tracing shows the complementary case: a Bayesian reimplementation produced *identical* prediction to the established point-estimate tool (AUC 0.711), differing only in cost and in credible intervals that make a condition comparison interpretable.

Builders inside institutions. From Surface Learning to Deep Understanding: A Grounded AI Tutoring System for Moodle embeds Large Language Models (LLMs) tutoring in an existing LMS rather than shipping a standalone tool, lowering the adoption threshold the ITS literature names as a reason systems fail in practice. SAVVY: Student attention visualization for video-based learning analysis turns Multimodal AI attention signals into an interface teachers can read before releasing a video. Instructional Agents automates ADDIE's first three phases with role-specialized agents, and its ablation is a design lesson. The single-agent baseline scored worst, Full Co-Pilot beat Autonomous by 0.5–0.9 points, and no quality difference between backends made the cheapest the default.

What a design claim can rest on

The evidence base is weaker than it looks. Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis audited 14 meta-analyses claiming that AI improves

education and found none justified its claims: all but two defined the treatment as a tool rather than a pedagogical intervention, 61% of 59 vetted primary studies had validity problems, heterogeneity was high wherever reported, moderator analyses were underpowered, and publication bias was never validly assessed. A meta-analysis that had been retracted still carried authority for 60% of the later papers sampled. For a developer, “AI improves learning” is a product-category claim, not a design input.

Report uncertainty and full cost, not just accuracy. For StanBKT, Bayesian inference buys nothing in prediction and everything in being able to say which effects were credible. Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources reports retrieval ablations, quantization-aware fine-tuning, VRAM, energy per query and hallucination measured against retrieved open resources — with the authors’ own caveat that the system is not a validated tutor. That is the evaluation discipline that makes a deployment claim checkable.

Co-design with teachers and learners

Explanations must speak the teacher’s language. The Impact of Explainable AI on Teachers’ Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations ran a within-subject experiment with 41 chemistry teachers on an ML recommendation tool: understandability, Trust and acceptance correlated positively, and domain-driven explanations in curricular language produced significantly higher understandability, learned trust and acceptance than feature-importance explanations. Trust was also dynamic — several teachers said only classroom experience would settle it — and acceptance depended on pedagogical alignment and workload reduction.

Credibility cues are not evidence of correctness. Adding citations and authority signals to a multi-agent debate raised abandonment of a correct judgment for the AI’s position from 15.0% to 31.8%, so provenance has to be checkable at the point of use (Tuo et al., 2026).

Co-design at institutional scale. AIDA at the Open University was built through six design-based studies over 18 months with 498 students and 20 staff. About 20% were initially skeptical; after hands-on use 96% wanted it kept, and an exploratory RCT found twice the usage time but no significant differences on learning process data. The enabling factors were organizational — senior sponsorship, cross-unit collaboration, data-informed iteration — with gaps in systems-thinking capacity.

Procurement, openness and after the funding stops

Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources supplies the inputs a procurement decision needs: a 12 GB VRAM hardware floor, an accuracy ceiling for a 7B-class model, per-query energy, and an ordering of choices — retrieval first (without it the model scored 52.3%, below a TF-IDF baseline), then fine-tuning, then quantization-aware compression. Open licensing is the precondition for serving a corpus locally. Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education frames the same decision as governance: transparency requirements turn purchasing into epistemological governance, contestability and provenance become conditions, and districts with the least capacity face the highest bar. What Does the Credential Still Certify? Cognitive Stewardship for AI-Mediated Education adds that vendor governance appeared in only 29% of 30 audited policy packages, which specified what AI may do far more readily than what evidence of learning remained. Generative AI (GenAI) as a mindtool that

supports generative learning (GL) poses the design question — does the product encourage learning *with* the tool or offload cognitive work — and What Makes Words Hard? Sakura at BEA 2026 Shared Task on Vocabulary Difficulty Prediction shows the trade in miniature: the top-scoring black-box model ($r > 0.91$) was less explainable than the interpretable one ($r > 0.77$).

Common Misconceptions

- **"The meta-analyses support the product claim."** They do not, and the reason is specific rather than a matter of degree. An audit of **14 meta-analyses** claiming AI improves education found **none justified its claims** — all but two failed on methodology — and a **retracted meta-analysis was still cited as authoritative by 60% of sampled later papers**. The retraction propagated faster than the correction, which means the literature a roadmap is likely to cite contains claims the field has already withdrawn.
- **"Adding citations and provenance makes a system more trustworthy."** In a multi-agent debate setting, adding citations and authority signals to the AI's position **raised abandonment of a correct judgment from 15.0% to 31.8%**. Provenance was not neutral information: it made the wrong answer more persuasive. Credibility cues need to be evidence of correctness, not decoration around a claim.
- **"Co-design with users validates the design."** Co-design answers a different question than efficacy does. When a tool is co-designed with students and **96% say they want it kept**, that is a finding about acceptability. Whether learning improved is a separate measurement, and the two can point in opposite directions without either being wrong.
- **"Agents are the next capability tier."** The Instructional Agents ablation is the useful counterexample: the single-agent baseline scored **worst** and the Full Co-Pilot configuration **beat the Autonomous** one. More autonomy was not the better design; the co-pilot arrangement was. Architecture choices have to be evaluated rather than assumed to improve with capability.

What this means for practice

For developers and designers

- Ground a design claim in a study you have read, not an effect size you have quoted. With 14 audited meta-analyses failing on method and a withdrawn one still propagating, citation count is not a validity signal.
- Test autonomy as a variable rather than shipping it as an upgrade. Run the ablation: single-agent, co-pilot, autonomous. The Instructional Agents result showed the co-pilot configuration winning, so the default should be the one that measured best, not the one that sounds most capable.
- Separate acceptability from efficacy in your own evaluation plan. A high willingness-to-keep number is a real finding and it is not evidence of learning, and conflating them in a report is how a weak product looks strong.
- Treat credibility cues as a manipulation with a measured effect. Adding citations moved abandonment of a correct answer from 15.0% to 31.8%, so surfacing provenance changes user judgment — design for that rather than assuming it informs.

For instructors evaluating a tool

- Ask how the tool was evaluated on the task you intend to use it for, and whether the evaluation was co-pilot or autonomous. The two are not interchangeable.
- Ask when the evaluation happened. Capability claims tied to an unstated model version date quickly and describe a system you will not be running.

Connected Concepts

- Edtech Platform
- Learning Design
- Curriculum Design
- Design-Based Research
- Educational Development
- Open Source
- Learning Analytics
- Intelligent Tutoring
- Human-in-the-Loop
- Human AI Collaboration
- Teacher AI Competency
- Technology Adoption Models
- Universal Design for Learning
- Assessment Validity
- AI Ed Evaluation
- AI Governance
- Educational AI Policy
- Sustainability
- Privacy

Connected Articles

- OATutor: An open-source adaptive tutoring system and curated content library for learning sciences research
- From Surface Learning to Deep Understanding: A Grounded AI Tutoring System for Moodle
- LearnLM: Improving Gemini for learning
- SAVVY: Student attention visualization for video-based learning analysis
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- Presumed Effective: The Manufacturing of an Evidence Base for AI-in-Education Through Flawed Meta-Analysis
- Generalizing a Highly Configurable Analytics Pipeline to Replicate and Support Educational Research Across Multiple Domains

- StanBKT: Rethinking Parameter Estimation in Bayesian Knowledge Tracing
- Instructional Agents: Reducing Teaching Faculty Workload through Multi-Agent Instructional Design
- Ontology-based layered hybrid AI-driven knowledge model for personalized e-learning
- What Does the Credential Still Certify? Cognitive Stewardship for AI-Mediated Education
- Reclaiming epistemic agency: A critical framework for human-generative AI co-agency in education
- Generative AI (GenAI) as a mindtool that supports generative learning (GL)
- New systems of learning for distance learning institutions? A six-study review of implementing AIDA
- What Makes Words Hard? Sakura at BEA 2026 Shared Task on Vocabulary Difficulty Prediction
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Credibility cues raised deference to incorrect AI advice; verify provenance at the point of use

Learners

> **Synthesis:** Learners are the primary audience of AI in education — the students in K-12, Higher Education and Adult Learners whose work, understanding, and sense of self AI now shapes. This page is the umbrella for the knowledge base's learner-side coverage: what learners experience (Student Experience), who they are becoming (Learner Identity), what they still choose (Learner Agency), how they actually interact with the tool (Student-AI Interaction), whether their effort and self-regulation hold up under it (Cognitive Offloading), and how AI systems model them (Learner Modeling and Adaptive Instruction). The recurring finding across that research is that the same tool helps and harms different learners differently — gains concentrate where prior knowledge, AI literacy and verification habits are already present, and reversal concentrates where AI substitutes for the thinking the task was meant to build.

Questions to Consider

- Which learners in your own context would a new AI tool reach first, and which would it leave behind — and what makes you think so?
- The research often reports that students *believe* AI helped them while unassisted measures show no gain, or a loss. If a learner's own account is unreliable evidence, what would you accept as evidence that learning happened?
- Learners are described here both as people who use AI and as objects AI models (learner models, knowledge tracing, simulated students). Where should a model of a learner inform teaching, and where should it stop being trusted?
- Self-regulation and prior knowledge decide whether AI support becomes learning or substitution. Is that a learner deficit to remediate, a design problem to solve, or an assessment problem to fix?
- If a group of learners does poorly with an AI tool, the tool's designers are usually the last to find out. What would a routine for hearing from learners before and after deployment actually look like in your institution?
- Learner agency and identity are at stake alongside achievement. Which of those would you refuse to trade for measurable score gains — and would your assessment design make that refusal visible?

Introduction

Learners appear in this knowledge base in two very different guises, and blurring them causes most of the confusion in the field. In the first, learners are **people who use AI**: they ask questions, accept or resist answers, lose or keep their footing, and report experiences of support, guilt, anxiety, and dependency. In the second, learners are **objects that AI systems model**: a skill estimate in knowledge tracing, a latent state in cognitive diagnosis, or a simulated student standing in for a real one. The evidence about the first comes from surveys, interviews, log analysis, and experiments; the evidence about the second comes from the machinery of measurement itself — and a model of a learner is a claim, not a learner.

This page is the entry point for both. It collects the learner-side concepts the knowledge base covers, explains how they relate, and links the studies behind them. Stakeholders covers the other side of the same field — teachers, administrators, designers and policymakers — and the two pages are meant to be read together.

Who counts as a learner

The knowledge base treats learners across the full span of formal education: K-12 pupils, university students, vocational and professional learners, and adult and lifelong learners, including learners with disabilities, neurodivergent learners, and multilingual learners. Two conventions matter. First, “learners” and “students” are not interchangeable in a useful way: *students* names an institutional role, *learners* names an activity, and a person can be one without the other (an employee in workplace training is a learner but not a student). Second, learners are not a homogeneous group, and the heterogeneity is exactly what the research keeps surfacing — prior knowledge, self-regulation, language, access, and disability status all change whether an AI tool helps.

What learners experience

Student Experience is one of the most researched dimensions of AI in education, and its central lesson is that effects are mixed rather than uniform. Survey work on study productivity finds learners reporting genuine efficiency gains — 92.3% said AI improved their understanding — alongside a gap the headline numbers hide: only 38.5% said it reduced their overall study time, and half reported sometimes relying on AI instead of trying to learn independently. Analyses of reliance patterns go further: students with different levels of AI literacy and evaluation skill end up in qualitatively different relationships with the tool, so the same course policy produces different outcomes for different learners — support for some, substitution for others. Students describe the pull of least effort in their own words, which the Academic Integrity and Misconceptions about AI pages treat as a design and policy problem rather than a moral one.

Affect runs alongside the cognitive story: Anxiety and Stress and Well-Being document anxiety about being outpaced, about being accused of misconduct, and about the value of the degree being pursued. Learners’ mental models of AI — what they think it is and what they think it is for — are upstream of whether they use it well, which is why Misconceptions about AI and Framing AI Use for Students appear throughout the learner-side research.

Learner accounts also complicate the integrity story that frames so much learner-side policy. Interviews with 27 undergraduates at an Ethiopian university find near-universal GenAI use alongside a genuinely divided ethical reading — most crediting the tools with raising their achievement, a minority calling coursework use misconduct, and almost all reporting an uneven playing field in which AI users score above diligent independent workers, one describing the effect as killing their sense of diligence. The student side of misconduct procedure is thinner in the literature than the student side of use, but case-file analysis of 1,162 GenAI allegations shows what learners face when the institutional response arrives: the evidence most often cited is the weakest-rated kind, no minimum evidentiary threshold governs whether a case progresses, and students whose cases rest on thin evidence are pushed toward appeals.

Identity, agency, and authorship

Learner-side research is not only about outcomes. Learner Identity asks who a learner is becoming in relation to a discipline and to AI, and the evidence runs in both directions: well-designed use can scaffold disciplinary belonging, while outsourcing can erode the sense that the work is one's own. Learner Agency asks what the learner still controls. The knowledge base treats both as genuinely at stake, not as soft adjuncts to achievement: a learner who produces correct output with an AI and no longer recognizes the reasoning behind it has lost something the grade does not record. The authorship question is where learners themselves struggle most: students interviewed about GenAI and integrity claimed originality because no other author existed — "If it is not my original idea, then whose?" — while others concluded the work did not represent them, and one reasoned toward recognizing the tool as a co-author it could not be, given that AI is not a person.

Interacting with AI: what learners actually do

The Student-AI Interaction page collects what learners ask of AI, how their prompts and dialogues evolve, and why interaction quality predicts learning outcomes better than access does. A rapid scoping review of 46 categorizations drawn from 33 studies finds that evidence base conceptually fragmented — studies differ in data source, category scheme and unit of analysis, so "quality interaction" is not yet a comparable construct across them, and the review's call is for a convergent taxonomy of learning-oriented Large Language Models (LLMs) use rather than a claim that one exists. Studies of chat content find students discipline themselves in characteristic ways, with engagement ranging from probing and testing claims to accepting the first plausible answer. Help-Seeking supplies the older frame: asking for help is a skill, and asking the wrong helper in the wrong way is a known failure mode that AI does not remove.

Effort, self-regulation, and the performance–learning gap

This is where the learner-side evidence is most consequential, because it separates what learners *can do with AI* from what they *can do without it*.

Cognitive Offloading collects the over-reliance evidence; Distinguishing performance gains from learning when using generative AI states the central methodological point that assisted performance and unassisted capability must be measured separately; Layer-sensitive studies of writing separate surface, structural, idea and reasoning offloading, and find the highest supported performance in the least bounded condition alongside the lowest independent performance eight weeks later; and Shaw and Nave's cognitive-surrender account names the disposition that makes delegation habitual rather than strategic. Metacognitive discord documents the uncomfortable middle case — learners who notice they do not understand and submit anyway — and verification research shows that "checking" is itself a graded skill, not a binary habit. On the design side, productive difficulty and Reducing AI Misuse collect the interventions that restore the effort the task was meant to require.

Learners as models

The learner-side concepts with the longest technical lineage are the ones that represent the learner to the system. Learner Modeling and Adaptive Instruction covers the family: Knowledge Tracing estimating skill acquisition over time, Cognitive Diagnosis locating specific misconceptions, and the adaptive and personalized systems that consume those estimates. Simulating Students and its review treat Simulation as a way to test tutors and generate data when real learners are unavailable — an explicitly provisional stand-in, not a substitute. Two cautions run through this literature: model estimates are inferences from behavior that are sensitive to how items and interfaces are built, and studies of demographic signals show that assessment systems can pick up proxies for learner identity (language, background) that were never intended to be part of the construct. Self-Report Measures covers the mirror-image problem on the research side: what learners say about their own learning often diverges from what they can do.

Equity across learners

Because benefits follow prior advantage, learner-side work is inseparable from Equity. Digital Divide and access to paid model tiers shape who gets the strongest tools; fairness concerns govern how learned models treat different groups; Inclusive Learning, Accessibility, Special Education and Neurodiversity cover learners whose needs the default design ignores. The practical lesson from this research is that "AI helps students" is not a finding — the finding is always *which* students, under *what* conditions, with *what* prior knowledge and access. Two groups carry a distinctive share of that risk. Wright (2026) argues that prohibitions written around "generative AI" rather than around function capture transcription tools that convert the format of work a learner has already authored, so the resulting false positives fall hardest on disabled learners who rely on voice-to-text and OCR, including where AI-powered OCR has replaced discontinued assistive software; a scoping review of remote proctoring makes the parallel point about assessment conditions, finding that connectivity, data cost and device failure decide who can be assessed at all — an equity finding rather than a technical one, and one concentrated in low- and middle-income settings.

Where this page sits

Read with Stakeholders for the people around the learner, and with Pedagogies and Teaching Strategies and Learning Design for what teachers do with these findings. Assessment determines which learner capabilities are ever made visible; Limitations in AIEd Research explains why so much of the learner-side evidence is short-term, self-reported and conducted on convenience samples; and Misconceptions about AI is the usual entry point for learners themselves.

Common Misconceptions

"Learners and students are the same population." They are not interchangeable in a useful way: *students* names an institutional role, *learners* names an activity, and a person can be one without the other — someone in workplace training is doing the activity, not holding the role. Conflating them narrows the evidence base to people with enrollment records and silently drops exactly the adults, professionals and self-directed learners that lifelong learning research is about.

“Learners report AI improves their understanding, so it saves them time.” The two claims separate in the survey data. In work on study productivity, **92.3%** said AI improved their understanding, while only **38.5%** said it reduced their overall study time. The headline number describes felt comprehension; the gap beneath it shows that improved understanding and recovered time are different outcomes, and the widely repeated “AI saves time” claim is carried by the smaller figure.

“Students using AI for shortcuts is a moral failing.” The knowledge base treats least-effort pull as a design and policy problem rather than a character problem — students describe it in their own words, and the misuse and integrity literature locates the lever in task and environment design. Framing it morally explains nothing about why the same student behaves differently across two courses.

“When a misconduct allegation is made, the evidence is there.” Case-file analysis of 1,162 GenAI allegations shows what learners actually face when the institutional response arrives, and the student side of misconduct procedure is far thinner in the literature than the student side of use. A page about learners that documents only their usage and not their exposure to accusation has documented half the experience.

Implications for Practice

For instructors

- Ask what learners *do*, not only what they report feeling. Felt understanding (92.3%) and recovered time (38.5%) diverge enough that acting on one while assuming the other will mislead course design.
- Design against least-effort pull structurally rather than relying on learner virtue, since the pull is documented as a normal response to task design.
- Brief learners on the process they will face if accused, because the procedure evidence shows the institutional response is where the harm often lands.

For developers

- Do not market time savings that learners themselves do not report. Ship metrics for both comprehension and time, and keep them labeled separately.
- Design for the non-student learner: workplace and self-directed users lack the enrollment context your defaults may assume.

For researchers

- Keep the learner/student distinction explicit in sampling, and report who is excluded by it.
- Study the accused as well as the user; the procedure side is the thin half of this literature.

Connected Concepts

- Differential Effects Across Learner Groups
- Student Experience — How learners perceive, interact with, and are affected by AI
- Learner Identity — Who learners are becoming in relation to a discipline and to AI
- Learner Agency — What learners still control and choose
- Student-AI Interaction — What learners actually ask AI and how dialogues evolve

- Cognitive Offloading — Over-reliance and the substitution of AI for thinking
- Self-Regulated Learning — Planning, monitoring, and adjusting one's own learning
- Help-Seeking — Asking for help well, and the failure modes when learners do not
- Metacognition — Knowing what one does and does not understand
- Motivation — Why learners persist or stop
- Self-Efficacy — Learners' confidence in their own capability
- Student Engagement — Behavioral, emotional, and cognitive engagement
- Prior Knowledge — The background knowledge that decides whether support becomes learning
- Learner Modeling and Adaptive Instruction — Representing the learner inside the system
- Knowledge Tracing — Estimating skill acquisition over time
- Simulating Students — LLM-simulated learners as provisional stand-ins
- AI Literacy — The capability that decides whether learners use AI well
- Equity — Who benefits and who is left out
- Well-Being — Anxiety, stress, and the affective cost of AI-mediated study
- Misconceptions about AI — The mental models learners bring to AI
- Stakeholders — The other side of the same field: teachers, leaders, designers
- Assessment — Which learner capabilities are ever made visible

Connected Articles

- The Uneven Impact of Generative AI on Student Learning: Examining the Roles of Reliance, Evaluation Literacy, and Course Policy in AI-related Courses — Reliance patterns and evaluation literacy split student outcomes
- Students' Perceptions of Artificial Intelligence Tools for Study Productivity and Learning: An Exploratory Survey Study — Learners report efficiency gains alongside dependency concerns
- Toward convergence in student-LLM interactions: A rapid scoping review and taxonomy for learning-oriented use — A taxonomy of learning-oriented student-LLM interaction
- Chat as Learning: Student-AI Conversations as Discipline-Associated Cognitive Engagement Patterns — Discipline-specific patterns in student-AI chat
- Layer-sensitive cognitive offloading in generative AI-assisted writing: Supported performance and independent no-AI outcomes — Assisted performance gains without independent capability
- Distinguishing performance gains from learning when using generative AI — Why assisted performance and unassisted learning must be measured apart
- Thinking—fast, slow, and artificial: How AI is reshaping human reasoning and the rise of cognitive surrender — Cognitive surrender as a disposition, not an accident
- Metacognitively discordant completion and the aware pass-through of non-understanding in generative AI learning — Learners who notice they do not understand and submit anyway
- Beyond checking: verification quality, reliance calibration, and learning in generative AI-assisted higher education — Verification quality and reliance calibration

- Simulating Students with Large Language Models: A Review of Architecture, Mechanisms, and Role Modelling in Education with Generative AI — Simulated students: architecture, mechanisms, and limits
- StanBKT: Rethinking Parameter Estimation in Bayesian Knowledge Tracing — Parameter estimation in Bayesian knowledge tracing
- The Role of Implicit and Explicit Demographic Signals in Large Language Model-based Student Assessment — Implicit and explicit demographic signals in LLM-based assessment
- The impact of artificial intelligence literacy on learning engagement among university students: the mediating role of psychological capital and the moderating role of professional identity — AI literacy, engagement, and psychological capital
- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison — Students describe the pull of least effort
- Tools facilitate cheating, or partner supports learning? GenAI and academic integrity issues from students' perspectives — Students on whether GenAI is a cheating tool or a learning partner
- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What misconduct allegation files actually contain as evidence
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI rules and the students they catch
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity as evaluative judgment rather than compliance
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Remote proctoring's emotional and equity costs for students

Connected FAQs

- How Is AI Impacting Students?
- Does Using AI Actually Help My Students Learn?
- How Do I Keep Students from Over-Relying on AI?
- How Should I Use AI to Study and Learn Effectively?

Librarians

> **Librarians** — the library and information professionals who teach information literacy, staff research consultations, build collections and discovery systems, and increasingly sit as the human counterpart to AI search and recommendation tools. In the knowledge base's research they appear as the people who handle the credibility question a model cannot settle — whether a patent, a technical standard, or an industry report deserves to be relied on — and as partners in course and policy co-design. Their place in AI in education is therefore double: as educators who teach source evaluation and search strategy, and as the human layer inside systems built around AI retrieval.

Questions to Consider

- AI can now answer in seconds the factual reference question a librarian used to field. What part of that work was ever *the answer* — and what part was the judgment about whether a source deserved belief?
- In the embedded-librarian study, source-evaluation questions dominated consultations (38.5%) in the very cases where the AI was least confident. Is that a design failure to fix, or evidence that credibility judgment resists automation?
- The CHIIR 2026 workshop reported a trust gap — students over-trust GenAI while faculty distrust it. Who closes a gap like that: a librarian, an instructor, or an interface that shows its sources and its confidence?
- Ithaka S+R found that institutions lack both a consensus on what AI skills are and a framework for assessing them. Is information-literacy instruction the natural home for that work — and does saying so ask libraries to carry a load their staffing does not match?

Introduction

Librarians are the professionals who sit between a learner's question and the scholarly record: reference and liaison librarians, subject specialists, teaching librarians who deliver information-literacy instruction, and the staff who manage collections and repositories. In AI in education they are named far less often than teachers and administrators, yet the corpus gives them a specific, testable role. They are the human answer to the credibility problem that Generative AI creates, the instructors who teach Evaluative Judgment and search strategy rather than merely supplying sources, and — in the strongest case in the knowledge base — a designed component of an AI system rather than a service beside it.

This page treats the role as distinct from its neighbors. Educational Technology Developers build the retrieval and recommendation systems; librarians decide what those systems should not be trusted to conclude. Academic Integrity frames AI use as authorship and disclosure; the librarian's framing — attribution, provenance, access — is adjacent but more concrete.

Information literacy as instruction, not just assistance

The knowledge base's most detailed evidence on this role comes from Huang's embedded-librarian seminar platform, built for engineering research teams in a quasi-experiment with 60 students in three programs over eight weeks (30 on the integrated platform, 30 in conventional library instruction). The integrated group gained 0.78 points on a five-point ACRL-based information-literacy instrument against 0.25 for controls, with the largest within-group gains in search skills (+0.87) and source evaluation (+0.83), followed by information synthesis (+0.73) and ethical-usage awareness (+0.70). Notably, performance-based items alone still produced large effects, so the gains are not purely confidence. What was taught maps onto library work: search-strategy formation, source appraisal, citation, and repository navigation — the four categories that later dominated the consultation logs.

The wider corpus adds a staffing and delivery question. The CHIIR 2026 workshop report describes one librarian's 15-week digital literacy curriculum built on a survey of 2,076 students and 101 librarians, and records the presenters' judgment that single-session workshops leave students with a misunderstood foundation; the same report counts one librarian's instruction reach at roughly 1,700 first-year students.

Where the AI was weakest, the librarian carried the load

The seminar platform split labor deliberately: algorithms handled retrieval at scale, humans handled evaluation under uncertainty — and the logs show the split working. Across 312 consultations (10.4 per participant), source evaluation and quality accounted for 38.5%, search-strategy formation 29.2%, citation management 18.6%, and repository navigation 13.7%, and 73.4% were answered within six hours. The authors connect this directly to model performance: the recommendation engine reached precision 0.68 and recall 0.61, up from a Boolean keyword baseline (0.52 and 0.48) but still insufficient for credibility judgments on patents and standards, and natural-language query handling answered 72.8% of engineering-specific queries correctly. Satisfaction followed the same order — librarian assistance highest at 4.3 out of 5.0, ahead of recommendations (4.1), querying (3.9), seminars (3.8), learning paths (3.6), and knowledge graph (3.4) — and interviews recorded 21 of 30 students citing trust in the librarians' presence. Use was heterogeneous — 11 of 30 leaned on AI, 8 on librarians, and 11 used both.

The tension cuts both ways. The cases AI handled worst were credibility questions, and the platform's own authors conclude that keeping a human expert at the credibility decision point is the practical lesson. But the study is single-site and non-randomized, its three components were never isolated, and the authors call the results "merely preliminary," noting that persistence after librarian support is withdrawn was never tested. Whether the human layer was the cause of the gains or the safety net around a 0.68-precision recommender remains open.

Co-design, partnership, and who pays for verification

Librarians also appear as co-designers rather than service providers. Maybee, LeGrand, and Fundator document Partners for Algorithmic Literacy at Purdue — a six-week student–faculty learning community facilitated by academic librarians, where undergraduates and faculty co-produce AI course policies and AI-integrated group projects. The authors frame it as an alternative to deficit-based narratives about student misuse of AI, and the SPIRaL program's student reflections show information literacy being relearned:

participants initially equated it with source evaluation, then moved toward reading it as a layered scholarly practice tied to Learner Agency. That shift — from checking sources to judging knowledge production — is the one the librarian is positioned to produce.

Two more strands set the limits of the role. The PEARLS framework names Access, Legitimacy, and Source among its six verification dimensions and notes that verification consumes database access, disciplinary language, and sometimes paid tools — so learners with fewer resources bear a larger burden to prove responsible use, and librarians are named among the parties co-design requires. The AARC framework makes the instructional goal explicit: verify, cite, and reflect as recurring commitments, assessed through the research process — including detecting fabrication and bias — rather than the product. Hingle and Johri's review shows the same designs libraries already use transfer: group work's benefits for information literacy generalize to AI Literacy learning, including with AI agents as partners.

Implications for AI in education

- **Keep a human at the credibility decision point.** Precision around 0.68 left roughly a third of surfaced material unmatched, and source evaluation was the most-requested consultation type — a design cue for any AI search or recommendation layer.
- **Treat information literacy as instruction.** The gains that held up on performance-based items were search strategy and source appraisal, which teaching librarians already teach and which attributing and verifying AI output also requires (Academic Integrity, Critical Thinking).
- **Design for heterogeneous pathways.** With roughly equal groups preferring AI, librarians, or both, routing consultations by subject and workload absorbed 312 of them at 10.4 per participant; a single mandated route will under-serve some learners.
- **Make confidence and sources visible.** The workshop's search-as-learning thread asks which cognitive processes should not be offloaded and calls for interfaces that preserve decision points — a scaffold librarians can specify from their ordinary working standard of source visibility.
- **Budget the human layer, not just the model.** The consultations were answered in hours, at scale, because staff were routed deliberately; assuming learners will handle credibility judgment alone transfers that cost to the people least equipped to pay it.

Common Misconceptions

"Librarians are peripheral to AI in education." They hold a specific, testable role, and the corpus measures it. Across **312 consultations (10.4 per participant)**, source evaluation and quality accounted for **38.5%**, search-strategy formation **29.2%**, citation management **18.6%**, and repository navigation **13.7%** — and **73.4% were answered within six hours**. That is not a peripheral service; it is the information-literacy function carrying the load AI could not.

"AI search answers the questions students used to bring to a librarian." In the embedded-librarian study, **source-evaluation questions dominated consultations (38.5%) precisely in the cases where the AI was least confident**. The tool's uncertainty routed work to the human capacity that could resolve it, which makes the observed pattern a division of labor rather than an obsolescence.

“Information literacy is a one-off induction session.” It is instruction, not assistance: the questions students arrive with are evaluation and strategy problems — is this source credible, how do I search this — which are teachable skills rather than transactions to be completed. Treating the service as assistance converts a curriculum into a helpdesk and loses the durable capability.

“Who pays for verification is someone else’s problem.” The consultation load lands on library staffing, and the paper’s own question is whether asking libraries to carry it outruns their headcount. Co-design and partnership are the responses the literature recommends precisely because the verification cost is real and falls on a unit that did not budget for it.

Connected Concepts

- AI Literacy
- Evaluative Judgment
- Critical Thinking
- Academic Integrity
- Human-in-the-Loop
- Human AI Collaboration
- Recommender Systems and Learning Paths
- Knowledge Graph
- Scaffolding
- Inquiry-Based Learning
- Research Methods in AIED
- Higher Education
- Learners

Connected Articles

- Developing an AI-Assisted Seminar-Based Learning Platform With Embedded Librarian Support: Enhancing Information Literacy of Engineering Research Teams — Embedded-librarian seminar platform; 312 consultations led by source evaluation
- Report on CHIIR 2026 Workshop on Generative AI and Academic Search (GAI&AS) — CHIIR 2026 workshop on GenAI and academic search; librarian trust gap
- Disruptive Partnerships: Collaborating with Students to Create Empowering Learning Experiences in Information Studies — Academic librarians co-designing AI literacy with students as partners
- AI-Assisted Research Competency in Secondary Education: A Framework for Epistemic Agency, Authorship and Responsible Knowledge Production — Verify, cite, reflect as teachable research commitments
- From Plausibility to Verifiability: The PEARLS Framework for Developing Epistemic Agency in Generative AI-Mediated Higher Education — Six-dimension verification protocol; access and legitimacy as gates

- Systematic review of collaborative learning activities for promoting AI literacy — Collaborative learning for AI literacy; information literacy benefits transfer
- AI skills for college graduates: Exploring how instructors and employers prioritize AI skills differently — Instructors rank attribution and responsible use highest, but teach few of 26 skills
- What differentiates educational literature? A multimodal fusion approach of transformers and computational linguistics — Text-complexity tool built for non-technical users such as English teachers and librarians
- Profiling cognitive offloading in LLM-mediated synthesis writing: Volume vs. content — What learners offload when AI synthesizes sources for them
- Testing Our Foundations: Citation Trends, Errors, and Emerging Hallucinations in the Computing Education Literature — Fabricated and erroneous citations as a verification problem

Parents and Families

> **Parents and families** — the household as a stakeholder in AI in education: the caregivers who tutor their children at home, choose and pay for tools, supervise or fail to notice what those tools do, and receive whatever their school communicates about AI. The page collects the evidence on AI-mediated parent–child tutoring and conversational companions used in the home, on the handoffs between home and school, on parents' own AI Literacy, and on the equity consequences of home devices, connectivity and cost. Its scope is the family as an actor — what families do with AI, what reaches them from school, and what the research does and does not establish about the results.

Questions to Consider

- Luo et al. (2026) found that generic Large Language Models (LLMs) assistance reduced the parent's tutoring role, while a role-separated interface preserved it. If you were designing a tool for a parent and child to use together, what would you protect the parent from, and what would you hand them?
- In Strömberg, Lei and Wu's (2026) data, homework scores rose 18% while closed-book exam scores fell 20% within six months. What does a parent actually see happening at home, and what would they need to be told to notice the difference?
- Xiao et al. (2026) found teachers naming parents as primarily responsible for children's relationships with AI companions while describing those same parents as unaware or overstretched. Is that a reasonable assignment of responsibility, and what would it take to make it real?
- Oreopoulos, Dong and Low (2026) nearly doubled first-session attendance by removing family-facing paperwork. In your own school or program, which parts of the home-facing process exist for the family's benefit and which exist for the institution's?
- Fan, Li and Zhang (2026) treat family–school coordination as an untested hypothesis rather than an established practice. If it has never been tested, on what evidence does the advice your school currently gives to parents rest?
- MacCallum, Parsons and Mohaghegh (2026) describe second- and third-level digital divides that persist after devices have been supplied. What would closing the skills and outcomes gaps look like in a household, as opposed to a classroom?

Introduction

A large share of children's time with AI happens outside the classroom, in a setting the research literature mostly treats as background. Work on tutoring and learning outcomes is usually school-based, while work on family guidance is usually advisory rather than tested, so families are simultaneously the target of a great deal of guidance about responsible AI use and the subject of very little evidence about whether that guidance works.

This page treats the household as an actor in its own right. It covers AI-mediated parent–child tutoring, the companion and reading tools children meet at home, what schools do and do not tell families about AI use, parents' own AI Literacy and what is known about their views, and the access and cost conditions under which families use these tools. Where the evidence is thin, the page says so rather than filling the gap.

Parents as co-educators at home

The clearest design evidence on home tutoring comes from Luo et al. (2026), who built ParaTutor for the Chinese home-tutoring context after a formative study of how parents help with math word problems. That formative work identified recurring failures: parents struggle to understand the structure of the problem, often lack the content knowledge to support it, and run into communication difficulties that break shared understanding. The design response was role separation — parents received tutoring guidance through multi-agent chatbots while children received visual grounding for the problem itself, with phase-gated support to stop dyads jumping to answers. In an evaluation with 23 parent–child dyads (children aged 10–12) across four conditions, generic Large Language Models (LLMs) assistance tended to displace the parent's role, whereas the role-separated interface kept parents delivering and adapting support while children stayed in the reasoning. The authors' implication is context-specific: in Math Education, where model accuracy is limited, children should not be interacting with the model independently.

Oreopoulos, Dong and Low (2026) treat the household as a procedural actor, and their results are as much about family behavior as about tutoring. Their randomized trial with the Toronto District School Board placed human virtual tutors over Khan Academy practice for struggling Grade 4–8 students. In Year 1, only about 45% of teacher-nominated students attended even one session, with families lost at each handoff: invitation, interest, account creation on a third-party platform, matching, showing up. In Year 2, inviting families directly through their own teacher for a fixed weekly time and handling enrollment and scheduling on the family's behalf raised first-session take-up to 83%. Weekly attendance still hovered near two-fifths, mostly intermittent absence rather than dropout; practice rose about 17 minutes a week, and the intent-to-treat effect on the topic test was 0.055 SD, with report-card marks up about 0.08 SD. Removing friction changed who showed up, not how much anyone sustained.

Companions and reading tools in the home

Families more often meet AI as a companion app than as a tutoring system. Liao (2026) compared a fixed "student peer" companion (Whisper with GPT-3.5) against experienced homeroom teachers in book-talk sessions with 19 elementary students in Taoyuan, Taiwan — 12 in Grade 4 and seven in Grade 5, four sessions each. Students spent significantly more time with the AI, yet contributed a markedly lower proportion of words and sentences; for Grade 5 the share was less than a third of what they produced with the teacher, a pattern the paper calls conversational dominance. The companion was effective at eliciting factual recall and significantly weaker than the teacher at prompting emotional and future-oriented reflection — an affective ceiling. Liao's response is a role-adaptive framework in which one companion occupies Student Peer, Teacher Assistant and Parent Advisor roles, the last extending discussion into the home. The diagnosis behind it is a support vacuum: most companion designs stay focused on the student–AI dyad and give teachers and parents no defined place.

A share of adolescents prefer confiding in AI to their parents. Cited Chinese data put 13.5% of young internet users preferring to confide in AI over their parents, and Fu and Zhao's (2026) framework predicts AI bonding becomes compensatory substitution when caregivers fail to recognize an adolescent's identity-confirmation needs.

Two early-childhood papers bear on what reaches the home. Yang, Li and Lee (2025) argue that physical, embodied agents are developmentally preferable to screens for young children, but warn that generative social robots can fabricate content that preoperational children accept as truth, lack developmental calibration in their Feedback, and carry cost and access barriers that widen the Digital Divide. Malallah et al. (2026) take a different route with the same age group: their unplugged, play-based AI-Play framework was implemented through a family-centered Hour of Code event, with parent surveys and child reflection sheets used to gauge engagement and usability for at-home replication. They report high engagement and emerging understanding that AI learns from examples.

Home–school communication and transparency

What schools tell families about AI, and what families tell schools, is largely unstudied; the clearest findings concern the absence of a channel. In scenario-based interviews with 33 US K-12 teachers, Xiao et al. (2026) found that decisions to intervene turned on jurisdiction rather than perceived harm. Their visibility test drew the boundary at the school door: use in class or on an assigned tool sat inside the teacher's role, while use at home entered it only through observable effects such as withdrawal, falling grades or isolation — absent those, teachers described watching and informal documentation rather than action. The Parent scenario was named most concerning by 10 of 33 teachers, 17 said a teacher should get involved and 11 answered "it depends". Parents were named first as the party primarily responsible for children's relationships with AI companions, then described as unaware or overstretched. The authors call this a jurisdictional vacancy and warn that without an established curricular claim, the adults with the most consistent access to children default to surveillance and referral. Counselors, parents and students were not interviewed.

Fan, Li and Zhang (2026) make the coordination problem explicit. Reviewing the guidance literature, they observe that it pushes risk management onto families and schools while treating their coordination as established, and they formalize three competing models — additive, synergistic and compensatory — noting that the synergistic version embedded in most guidance has no supporting evidence. Their proposed test is a factorial trial contrasting family-only, school-only, coordinated and usual-practice guidance. On the family side they carry over a Self-Determination Theory distinction between dependent offloading, where core thinking is delegated, and autonomous offloading, where AI scaffolds while the learner keeps epistemic Learner Agency; immediate performance is identical in both cases, which is why maladaptive use is hard for a parent to see.

The same invisibility appears in achievement data. Strömberg, Lei and Wu (2026) followed 26,811 Chinese secondary students in grades 7–12 over 30 months and found that generative AI adoption raised homework scores by 18% and cut completion time by 30% while lowering closed-book exam scores by 20% within six months, with entrance-exam drops of 18% and 24% emerging only after about two years. About 81% of users showed a homework-outsourcing pattern, while AI users who spent as much homework time as non-users scored similarly on exams. The authors' recommendation is addressed to the adults around the child:

monitor inputs such as homework time and effort rather than outputs such as homework scores. They caution that closer parental monitoring is itself one of the unobservables distinguishing the non-outsourcing group.

Parents' own AI literacy and advocacy

Direct evidence on what parents know, fear and ask for is thin, and parents mostly appear in the literature as reported by others. The parents in Liu et al.'s (2026) critical case study of an all-girls makerspace were interviewed alongside girls and practitioners, and reported that girls often "got scared" and spoke less in mixed-gender settings. In Xiao et al. (2026), the companion literacy teachers sketched was shared work across counselors, parents, platforms and policymakers, sequenced as an age-graded spiral, with parents named first and then described as already carrying more than they could. Parents appear in the AI-Play evaluation through surveys of activity usability rather than through accounts of their own understanding.

What a parent would need in order to take part in any of this is defined, in effect, by AI literacy frameworks built for schools. MacCallum, Parsons and Mohaghegh (2026) designed SAIL to be age-agnostic, treating its Level 1 competencies — understanding and exploring AI — as essential for all ages, which places adults in the same progression as children rather than as its instructors. Families also occupy a formal role in research itself: Allison (2026) asks authors to report participant context and socio-demographic characteristics, Accessibility and cultural fit, and ethical review, consent and data AI Governance — the obligations through which a family's consent, data and context become visible at all.

Access and equity across families

Cost and connectivity shape what families can use before any question of pedagogy arises. In the makerspace study, Liu et al. (2026) document both a cost barrier and a design barrier: the free image generator Playground dropped its free functions for a paid "pro" tier the under-resourced nonprofit could not absorb, and the tools accepted only English prompts, disadvantaging girls without English confidence. Yang, Li and Lee (2025) flag cost and access as widening the Digital Divide. The take-up result in Oreopoulos, Dong and Low (2026) is an equity result as well as a design one: the families lost in Year 1 were lost to administrative steps, and the intervention that recovered them was built around the family's own teacher and a fixed weekly slot.

Fan, Li and Zhang (2026) name the measurement conditions that make blanket family advice unsafe: instruments for AI literacy, dependence and overreliance were largely developed in single-country or specialized university samples, and most studies are cross-sectional and self-reported. SAIL's equity argument applies in the household register as well: supplying a device addresses only the first of the three divides, and the skills and outcomes gaps persist regardless of who owns the hardware.

What the evidence does and does not show

The strongest family-facing results in this knowledge base concern behavior rather than learning. Reducing household-facing friction raised first-session attendance from about 45% to 83% in one trial, and take-up remained the binding constraint even then. The same trial produced small and imprecise outcome gains, while the largest achievement study reports large negative effects concentrated among students who

outsourced homework, a pattern the authors partly attribute to parental monitoring they could not measure directly. Neither finding isolates what parents do from what schools or tools do.

What is missing is more conspicuous. Parents' own accounts are rare: the teachers in Xiao et al. (2026) excluded parents from their sample by design, and the parents who do appear are interviewed as one voice among girls, practitioners or teachers. There is no direct evidence here about how families learn a school's AI policy, what they are told about monitoring or disclosure, or how they respond to it, and family–school coordination has been theorized rather than tested. Home-tutoring designs such as ParaTutor have been evaluated with 23 dyads in one national context, and companion comparisons rest on 19 students in one school.

A 2026 scoping review maps how far the field has gone. Luo et al. (2026) analyzed 53 HCI studies from 6,540 records across 19 venues through activity theory, and found the literature centered on child–parent interaction and on language, AI Literacy, and relational learning, with 44 of the 53 studies (83%) set in child–parent configurations. Conversational, embodied, and spatial systems generate support from the context of an unfolding interaction, and LLMs redistribute educational labor while families and institutions remain responsible for interpreting outputs and deciding how they enter practice. Sustained personalization, repair labor, and how families negotiate authority and rules are the gaps the review names, which is the same absence this section documents from the other direction.

Relationship to other pages. Stakeholders is the short overview of the whole stakeholder set, with families listed as an audience not yet covered in depth; this page is that depth. Early Childhood Education covers the developmental and pedagogical domain for young learners across school and home; this page follows the family across ages, from preschool play activities to secondary homework. AI Use and Disclosure Statements covers whether learners tell others that they used AI; this page covers the adjacent question of whether that information reaches the adults at home, and what families are told about school AI use.

Common Misconceptions

"Families will engage if the offer is made." Take-up collapses across handoffs. In Year 1 of the program cited here, only about **45% of teacher-nominated students attended even one session**, with families lost at each step — invitation, interest, account creation on a third-party platform, matching. Every handoff is a place to lose a family, so an offer delivered counts for much less than an offer made.

"Family–school coordination around GenAI is an established practice." Fan, Li and Zhang (2026) treat it as an **untested hypothesis** rather than an established practice. Programs are being designed on an assumption the literature has not yet tested, which is worth knowing before adopting one as evidence-based.

"Parents will notice if AI is harming their child's learning." They are the least positioned to notice. In Strömberg, Lei and Wu's (2026) data, homework scores rose **18%** while closed-book exam scores fell **20%** within six months — and the rising number is the one visible at home. A parent watching homework sees improvement while the durable outcome declines.

"Home AI use is a parental-permission question." It is a literacy and advocacy question. Parents' own AI literacy determines what they can interrogate about a school-issued tool, and access inequities across families shape which children get adult mediation at all.

Connected Concepts

- Stakeholders — the umbrella page for audiences and actors in AI in education
- Early Childhood Education — the developmental domain where home and family use is most studied
- AI Use and Disclosure Statements — disclosure practices and the question of what reaches families
- AI Literacy — parents' own competencies and the school-built frameworks that define them
- Equity — how benefits and burdens distribute across households
- Digital Divide — access, skills and outcomes layers as they apply at home
- Conversational AI — the dominant form AI takes in family settings
- Self-Determination Theory — autonomy support as the frame for family guidance
- Cognitive Offloading — dependent versus autonomous offloading, and why parents cannot see the difference
- Intelligent Tutoring — the model behind AI-mediated parent–child tutoring

Connected Articles

- Artificial Intelligence Connectedness: Theoretical Reconstruction of Connectedness and Its Impacts on Adolescent Mental Health — Adolescent AI connectedness and when AI bonding substitutes for unmet caregiver recognition
- ParaTutor: Coordinating Parent-Child Math Tutoring through Role-Separated LLM Scaffolding — role-separated LLM support for 23 parent–child dyads in Chinese home math tutoring
- Beyond a single role: Justifying a role-adaptive framework for AI companions through a comparative study in elementary book talk — fixed peer-role companion versus teacher with 19 elementary students in Taiwan
- Family-school autonomy support for children's responsible use of generative artificial intelligence: a self-determination theory synthesis and developmental research agenda — review treating family–school coordination as an untested hypothesis
- RAISE the Standard: A Framework for Transparent Reporting of Artificial Intelligence Studies in Education — reporting obligations covering consent, participant context and equity of access
- Exploring K-12 Teachers' Perceptions of Students' Relationships with AI Companions: Boundaries, Intervention Strategies, and Design Implications — 33 teachers on jurisdiction, parents and children's relationships with AI companions
- AI-Play: A Framework for Teaching Artificial Intelligence Concepts through Unplugged Activities in Early Childhood Education — unplugged AI literacy tested through a family-centered Hour of Code event
- Beyond "painting in pink": A critical case study of all-girls generative AI workshops in a European makerspace and implications for gender equity in computing — parents among interviewees; tool cost and language barriers in informal settings

- Tailoring AI agents for early learning: The Creative Project Approach — physical agents for young children, with cost, access and privacy caveats
- Transforming clicks into critical thinking: An AI-based media literacy program for children — school program on data privacy, safe communication and media ethics in 36 fourth graders
- Virtual tutoring with computer-assisted learning: An experiment in take-up and learning — take-up rose from 45% to 83% when family-facing steps were removed
- The generative AI learning penalty: Evidence from Chinese secondary education — homework outsourcing, exam declines and the case for monitoring inputs
- The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education — age-agnostic AI literacy levels and the three-level digital divide
- Characterizing LLM-Based Family Education through the Lens of Activity Theory: A Scoping Review of the HCI Literature — Characterizing LLM-Based Family Education through the Lens of Activity Theory: A Scoping Review of the HCI Literature

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?

Stakeholders

> **Stakeholders** — the range of human stakeholders involved in, affected by, and responsible for AI in education, and the umbrella concept for the knowledge base's coverage of who the actors are. AI in education is a multi-stakeholder field: learners who use AI, teachers and faculty who integrate it, administrators who govern it, instructional designers who build learning experiences around it, and policymakers who regulate it. Each audience has distinct needs, competencies, roles, and perspectives, and the knowledge base treats them as the human context in which AI tools are designed, deployed, and evaluated.

Questions to Consider

- The page argues the same AI system looks different from every vantage point — a tool a student experiences as support may look to a teacher like an integrity risk and to an administrator like a governance decision. Which role do you most identify with, and what do you think you're prone to miss from the others?
- Before reading on, try to list everyone in your institution who is touched by an AI-in-education decision — beyond just students and teachers. Who did you forget, and what would each of them care about most?
- If learners, teachers, administrators, instructional designers, and policymakers each have distinct needs and competencies, who should have the final say over how an AI tool is deployed — and why?
- A student's 'personalized support' can simultaneously be a teacher's 'integrity risk.' How would you design a conversation or process that gives each stakeholder's concern genuine weight rather than letting the loudest voice win?

Introduction

AI in education is fundamentally about people — the learners and educators whose work it transforms, and the leaders and designers who decide how it is used. Understanding the distinct stakeholders is essential because the same AI system looks very different from different vantage points: a tool a student experiences as personalized support may appear to a teacher as an integrity risk, to an administrator as a procurement and governance decision, and to a designer as a pedagogical choice. The knowledge base organizes coverage of these audiences across several concept pages.

The stakeholder landscape

- **Learners (students).** The primary audience — students in K-12, Higher Education, and Adult Learners. The knowledge base covers learners through Student Experience, Student Engagement, Misconceptions about AI, Learner Modeling and Adaptive Instruction, Well-Being, and Learner

Agency. Learners' AI AI Literacy, self-regulation (Self-Regulated Learning), and risk of over-reliance are central concerns.

- **Teachers and faculty.** Educators who integrate AI into instruction. Covered by Teaching, Teacher AI Competency, Teacher Education, Educational Development, and Technological Pedagogical Content Knowledge (TPACK). Teachers face the dual challenge of using AI in their own teaching and teaching students to use it responsibly (see pedagogies and teaching strategies).
- **Instructional designers and learning technologists.** The professionals who design courses, curricula, and learning experiences around AI. Related to Learning Design (the discipline) and Curriculum Design, though the *people/role* of instructional designer is not yet a dedicated page — it is grouped here.
- **Administrators and institutional leaders.** Provosts, deans, CIOs, and leaders who set policy, allocate resources, and govern adoption. Covered by Administrators, and connected to Educational AI Policy, AI Governance, and AI Regulation in Education.
- **Policymakers and regulators.** Government and institutional bodies that set the legal and regulatory framework. Related to Educational AI Policy, AI Regulation in Education, and AI Governance.
- **Parents and families.** Present in the research (e.g., monitoring student AI use, attitudes toward AI) and now covered by a dedicated page — grouped here as a stakeholder.

How stakeholders appear in the research

- **Role-specific competency frameworks.** Teacher AI Competency and Technological Pedagogical Content Knowledge (TPACK) define what teachers need to use AI effectively; AI Literacy defines what all audiences (especially students) need.
- **Differential impacts by role.** Research examines how AI affects different audiences differently — Student Experience studies student outcomes, Teaching studies pedagogical integration, Administrators studies institutional strategy, and Educational Development studies professional learning.
- **Multi-stakeholder governance.** AI Governance and Educational AI Policy research emphasizes aligning national, institutional, and classroom stakeholders — policymakers set expectations, administrators implement, teachers adapt, and students experience the result.
- **Equity across audiences.** Equity examines how AI's benefits and harms distribute across learners and institutions, connecting stakeholders to fairness and access.
- **Role differences can be asserted more easily than observed.** A SWOT of 167 contributions from 152 higher-education personnel found teachers, researchers and administrators converging on the same strengths and threats, while fully anonymous collection left roles unidentifiable, so the study could not test its plan to contrast them (Humble & Mozelius, 2026).

Identity across audiences

A common thread across these stakeholders is **identity** — the sense of who one is and is becoming in relation to AI and to the domain. The knowledge base treats identity as distributed across audiences rather than belonging to any single group.

- **Learner identity** — the evolving disciplinary, professional, creative, and academic identity of students (Learner Identity). It is distinct from, but causally connected to, Learner Agency: agency is the situated capacity to act, while identity is the durable sense of self that accumulates from agentic acts and is threatened by authorship loss and competence doubt under AI.
- **Teacher identity** — the professional self-understanding of educators (Teaching), reshaped by AI as a question of purpose and role rather than skills alone (see GenAI as identity crisis).
- **Designers and leaders** — professional identity also shapes how instructional designers, administrators, and policymakers orient to AI, though the knowledge base's explicit identity coverage concentrates on learners and teachers.

Identity is the human anchor of the stakeholder landscape: it is what AI must support (not erode) for each audience, and it is the construct that connects otherwise separate role pages — Learner Identity, Learner Agency, and Teaching in particular. Where agency concerns *control* and identity concerns *self*, AI design must preserve both: control over one's learning and a robust, authorial sense of who one is in the domain.

Implications for AI in education

- **Design for the full stakeholder set:** effective AI in education must serve learners, support teachers, inform administrators, and align with policy — not just optimize one audience.
- **Build role-specific competencies:** teachers, students, designers, and leaders each need tailored AI literacy and support (see AI Literacy, Teacher AI Competency, Educational Development).
- **Align across levels:** the knowledge base's governance research shows AI succeeds when institutional leadership, teacher practice, and student experience are aligned rather than fragmented.
- **Consider parents and the broader community:** families are stakeholders in AI adoption whose role and concerns deserve explicit attention.

Common Misconceptions

"Stakeholders in AI in education share an interest in the same outcome." Their interests are frequently in direct tension, and the same feature reads differently by role: a student's "personalized support" can simultaneously be a teacher's "integrity risk." Design processes that assume a common goal will resolve that tension by accident in favor of whoever speaks loudest.

"Giving every stakeholder group a voice resolves the conflict." Consultation is not weighting. The page's own framing puts the design question at how to give each concern **genuine weight rather than letting the loudest voice win**, which is a procedure problem — who decides, with what evidence, and with what appeal — not a communications problem.

“Stakeholder analysis is an early-phase exercise.” The tensions persist into operation, because the roles keep interpreting the same system differently. A student-facing personalization layer and a faculty-facing integrity dashboard are the same data viewed from two positions, and the conflict recurs whenever one is adjusted.

“An identity across audiences means one message can serve them all.” Communicating across audiences requires translating the same decision into different terms without misrepresenting it, which is more than rewriting one message four ways.

Connected Concepts

- Learners — Learners: the umbrella for the learner-side concepts
- Teaching
- Learner Identity
- Learner Agency
- Teacher AI Competency
- Teacher Education
- Educational Development
- Technological Pedagogical Content Knowledge (TPACK)
- Student Experience
- Student Engagement
- Misconceptions about AI
- Administrators
- Learning Design
- Curriculum Design
- Educational AI Policy
- AI Governance
- AI Literacy
- Equity
- Higher Education
- K-12
- Adult Learners
- Parents and Families
- Student Support and Success — who holds a claim on institutional AI support decisions

Connected Articles

- "It is a temptation to get it to do the work…" Student experiences of navigating the generative AI landscape in UK higher education: A cross-institutional survey with international comparison — Student experiences of GenAI in UK higher education
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — AI in UK higher-education policy (students and institutions)

- New AI-Driven Tools for Enhancing Campus Well-being: A Prevention and Intervention Approach — AI-driven tools for campus well-being
- Assessing AI-TPACK readiness in mathematics teacher education: The role of self-efficacy and teaching beliefs — AI-TPACK readiness in mathematics teacher education
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education — Institutional GenAI policy in computing
- Mathematical Modelling of Ethical AI Use in Higher Education: A Coordination Game Framework for Future-Facing Learning — Coordination game framework for ethical AI use in higher education
- "It’s OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing — Student rationalization of AI use in academic writing
- How AI Is Changing Teaching Workflows. — How AI is changing teaching workflows
- Beyond the hype – How higher education stakeholders view the benefits and concerns of generative AI for teaching, research, and administration — Stakeholder perceptions of GenAI in higher ed (Humble & Mozelius 2026)
- "We’ll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — “We’ll Fix It Later”: Education, AI, and the Deferral of Student Privacy in EdTech

Institutions and policy

Institutions

Educational AI Policy

> **Educational AI policy** — the formal and informal rules governing AI use in educational institutions, from national legislation to classroom guidelines. Policy research in the knowledge base spans institutional governance, curriculum mandates, and teacher preparation requirements.

Questions to Consider

- Institutional AI policies are often written as if telling people the rules changes what they do. Research suggests these policies can lag far behind actual AI use. Why do you think a policy 'on paper' so often fails to match what happens in classrooms?
- If homework outsourcing causes learning losses that go largely unnoticed — because no single teacher connects a student's decline to AI use — what kind of policy would even be possible? What would monitoring look like?
- Assessment policy decisions like oral exams, proctored tests, and closed-book formats are themselves responses to AI-enabled cheating. Do you think policing the 'output' (catching AI use) is a better strategy than redesigning assessment so the work itself is harder to outsource?
- Educational AI policy spans national legislation, government guidance, institutional rules, and classroom-level choices. Which of these levels do you think actually shapes student and teacher behavior the most — and why?
- Whose voices tend to shape AI policy — and whose are missing? Who should be at the table when an institution decides what AI use is allowed and how it's governed?

Introduction

AI in education is governed by a stack of instruments — national legislation, government guidance, institutional policies, departmental rules, and the statements teachers write into individual syllabi. They differ in legal force, in how often they are revised, and in who is expected to interpret them, but they share a problem: they are usually written after the technology they govern has already entered the classroom.

The knowledge base's policy research documents that gap from both sides. Institutional policies lag behind actual AI use, and where rules exist they are often guidance rather than enforceable policy, written at the course level by individual instructors rather than at the institution. The same pattern appears in K-12, where only a minority of schools report having a policy at all, and in professional programs, where advisory documents outnumber binding rules.

The gap has a discursive form as well as an organizational one. Hashem (2026) reads four UNESCO and OECD publications through Laclau's floating signifiers and finds that the shared governance vocabulary — responsibility, transparency, trust, authenticity, responsible use, augmentation — acquires normative force by repetition while never acquiring an operational definition. The OECD (2026) documents twenty-three countries and jurisdictions converging on that vocabulary while leaving its meaning to contextual interpretation, and the OECD (2023) reports that as of early 2024 none of eighteen surveyed countries had

specific generative AI regulation in education, with nine delegating primary responsibility to the school level. The effect is Ahmed's non-performativity: commitments are made in modal language, without a mechanism through which they could be enacted or assessed, and responsibility is distributed across providers, institutions, teachers and learners until no single actor holds it.

Hashem's practical conclusion is a shift from policy implementation to policy enactment, with institutions writing the disclosure, authorship and assessment boundaries the international texts leave open.

This page treats policy as distinct from AI Governance. A policy answers *what the rules are*; governance answers *who decides, and how the rules actually take effect*. Keeping the two apart matters because the research repeatedly shows policies failing not for want of content but for want of machinery — review cycles, professional development, appeal routes, and monitoring. The sections below set out the levels at which policy is made, the maturity gap that separates written rules from classroom practice, the assessment-policy questions that AI forces, and the governance structures that decide whether any of it holds.

Policy levels

Policy is made at several levels at once, and they do not move together. The bullets below name the level and the research that documents it.

- **Institutional policy:** Institutional policy analysis compares how universities develop AI policies. Institutional change frameworks provide models for policy development. Qian (2026) coded the principal AI pages of the 50 US universities ranked most innovative in 2025 and found that only 6 framed them as a "policy" while 44 published guidance, guidelines, principles or resource hubs, and that 33 of 50 positioned instructors as the primary translators of institutional expectations into course rules — institutional policy is being deliberately written as adaptable guidance for course-level interpretation rather than fixed rule.
- **Government policy:** Lifelong learning policy examines regulatory approaches at national and regional levels. A critical, infra-level view of AI in government policy-making is Perrotta (2026), whose analysis of the UK Redbox civil-service Large Language Models (LLMs) prototype shows how general-purpose AI enters the professional toolkit of policy through "zero-shot governance" — domain-agnostic foundation models intervening in decisions, wrapped in thin domain-specific scaffolds.
- **K-12 policy:** Stanford's evidence reviews of 818 papers inform K-12 AI policy.
- **Assessment policy:** Assessment reform policies and Authentic Assessment frameworks represent policy-level responses to AI-enabled cheating. The choice of summative assessment format — oral, proctored, closed-book — is itself an assessment-policy decision (see Summative Assessment).

The maturity gap: policy written before use, and before evidence

The knowledge base documents that institutional AI policies lag behind actual AI use. Educational Development programs, Teacher AI Competency frameworks, and AI Regulation in Education all require coherent policy foundations. Large-scale field evidence (Strömberg, Lei, & Wu 2026) shows that the learning losses from homework outsourcing go largely unnoticed because individual subject teachers and

students rarely connect the decline to AI use — a gap that evidence-informed policy (e.g., weighting closed-book assessment, informing students of long-run costs, monitoring inputs rather than outputs) can address. An aspect-based sentiment analysis of 36 university GenAI policies across four countries found teaching statements positively framed and GenAI and ethics statements negatively framed, with no significant country effect — framing tracks the policy dimension, not the national system (Sun et al. (2026)).

The inconsistency is not academic to the people enforcing it: fifteen sessional academics reported that students cannot comply with rules that differ between units, and that prevalence cannot even be estimated without clearer guidance (Andriamora & Andriamora, 2026).

Where consensus has formed to fill that gap, Crompton et al. (2026)'s 35-expert Delphi across 22 countries converged on eight governance areas — academic integrity as the central anchor — plus a six-part review mechanism (standing GenAI committee, scheduled policy reviews, professional development, communication, impact evaluation, monitoring) to keep policies current.

National AI readiness does not predict institutional policy strength. Adarkwah et al. (2026) scored 26 universities from ten high-AIPI countries against UNESCO's eight-component GenAI framework and found Nordic and New Zealand institutions covered it more fully than higher-ranked peers, while inclusion, equity, and sustainability were the most neglected elements.

Advisory documents outnumber binding policy. A census of every accredited program in one professional field shows that the maturity gap is one of form as well as timing. Eldredge et al. (2026) collected AI policy and guidance documents from all 48 CAHIIM-accredited health informatics and health information management master's programs in the United States and found that 40 (83%) had at least one publicly available AI-related document while 8 had none, but that the documents were mostly guidance rather than enforceable rules: 21 guidelines (53%) against 7 formal policies (18%). Their content centered on academic integrity and acceptable use, with privacy, intellectual property, and regulatory concepts (HIPAA, FERPA, research compliance) appearing far less often, and topic modeling returned the same student-conduct emphasis. Neither document type nor intended audience varied by delivery mode (Fisher's exact $P = .85$ and $P = .71$). The authors read this as evidence that academic program policy is a distinct activity from curriculum design and workforce competency development, and argue that accrediting bodies could reduce the resulting variation by providing AI policy frameworks that integrate academic integrity, data ethics, and equitable access.

Legal form is rarer than legal language. In a 160-document scoping review, 2.5% of instruments carried legal force while 57.5% were guidance or toolkits, and only 3 of the 131 documents invoking legal controls were themselves legal instruments (Elmahjub et al. (2026)).

A UK systematic review adds a sectoral layer to the same gap: infrastructure investment and staff AI training concentrate in research-intensive (Russell Group) universities while teaching-led (post-92) institutions face capacity constraints, and only a minority of UK institutions maintain official AI governance plans (Ashiq (2026)).

A sector making policy without an evidence base. The maturity gap also appears as an evidence problem in professional programs. Gutowski and Hurley (2025) scored the institutional policies of ABA-approved US law schools on five dimensions — prohibitiveness, permissiveness, educational integration, transparency and accountability, and depth — and found most schools taking generally prohibitive positions while reserving discretion to individual instructors and committing to review the rules as the technology moves. They

attribute the caution to time pressure rather than evidence: the ABA's 2024 survey drew responses from only about 15% of accredited schools, and the authors report no consensus on whether AI use must be disclosed or how it should be cited. Their conclusion is procedural — build policy with faculty rather than for them, train proactively, and treat policy generation as a recurring event rather than a one-time act — which makes Legal Education one of the clearest cases of the policy-versus-governance distinction this page draws.

Instructors regulate; institutions mostly do not

The maturity gap has a second face, visible from the teaching side. Watson and Rainie (2026) surveyed 1,057 US college and university faculty and found that rules have been written far faster below the institution than at it: 87% of respondents created their own assignment-level policies for student AI use, against 35% who said their department has written guidelines and 48% who said their institution has. The structural response behind those documents is thin — 55% reported a task force or oversight group, 37% new AI-focused classes, 17% an AI major or minor, 16% new academic leadership offices, and only 13% adoption of AI literacy as a general education outcome. Meanwhile 68% said their schools had not prepared faculty to teach with the tools. (The authors describe the sample as non-scientific and not generalizable, so it is best read as the sector's expressed concerns.) Because students meet the resulting patchwork as a single institutional regime, the finding is direct evidence for this page's distinction between a policy document and the governance that makes it consistent. The gap has a measured student-side consequence. Chen's two-study design — 160 art students in a scenario experiment and 425 surveyed (Chen, 2026) — found that perceived inconsistency between a university's GAI advocacy and its actual teaching, assessment and support practices positively predicted both hindrance ($\beta = 0.431$) and challenge ($\beta = 0.496$) appraisals. Those appraisals carried opposing indirect effects on creative process engagement ($\beta = -0.060$ through hindrance, $p = 0.004$; $\beta = 0.217$ through challenge, $p < 0.001$), so one unaligned policy can suppress and sustain students' creative work at once.

Task-level regulation is the emerging pattern. A large-scale longitudinal study of 31,000+ course syllabi (2021–2025) at a large public research university (Chirikov 2026) shows how instructors actually regulate AI in practice: explicit AI regulation grew from near zero to 55% of courses by Fall 2025, but the direction shifted from restrictive toward permissive, and instructors increasingly **differentiated by task type** — restricting AI for drafting/reasoning (displacement-risk tasks) while permitting it for editing/proofreading and study support (augmentation tasks). Framing also shifted from academic integrity (63%→49% of syllabi) toward learning impact (1%→29%). This task-based pattern — built on the labor-economics mechanisms of task displacement, augmentation, and reinstatement — offers a more granular alternative to blanket adoption-or-ban policies and is a direct empirical anchor for the policy-vs-governance distinction above.

The student side of task-level regulation is equally policy-shaped. With two of three assessments under an identical open-use tier, the assessment format still decided what students used GenAI for: feedback uses rose from 0% in a scaffolded presentation to 66.7% in a take-home quiz (Quince and Faulconer (2026)).

Instructor-level policy design as an alignment exercise. Task-level regulation has a design counterpart below the syllabus. McCorkle's (2025) design case derives a course's allowed and unallowed GenAI uses from "what, specifically, am I assessing?" — inventorying every task in a project, mapping each task to a learning objective, pairing each with an emerging GenAI workforce competency (Career Development and

Readiness), and then deciding which concern takes priority: the need to assess student performance or the value of building the competency. The resulting policy differs task by task inside a single project — brainstorming topics and curating images permitted, composing learning objectives and designing slides not — with the rationale written directly to students. The case also documents why blanket prohibitions fail in practice: students who do not see themselves as dishonest read a prohibition as not applying to them, and the policy becomes inequitable (Equity) when expectations are left implicit. It complements the top-down policy levels above by showing how a policy's *content* can be generated from Assessment alignment at the course and assignment level.

Assessment policy: boundaries, oversight and attack surfaces

The boundary–evidence gap in assessment policy. A 30-university audit of public GenAI assessment guidance (Yao 2026) finds that institutional policies are better at *classifying* AI use than at explaining what evidence of learning remains valid under each class: the mean delegation-boundary score (2.47/4) exceeded the mean evidence-standard score (1.89/4), safeguards were sparse (2.75 of 8), and guidance was clearest for final-output substitution. The framework of *cognitive stewardship* argues that policies must make the certification logic visible — what learners may delegate, what they must still demonstrate, and how institutions protect fair evidence — rather than merely monitor AI use.

Over-inclusive prohibition language and misapplied rules. A rule's scope is a policy decision with consequences beyond compliance. Wright (2026) argues that the blanket prohibitions written across higher education since 2023 bar "generative AI" without the technical precision to separate content generation from AI-powered format conversion — optical character recognition, handwritten text recognition and speech-to-text are recognition technologies that infer what a student already wrote rather than producing new content. On this reading, sanctioning transcription-only use is best characterized as policy misapplication rather than misconduct, and the cost of imprecision falls unevenly: equity-exposed and disabled students who rely on those tools carry disproportionate false-positive risk, an exposure that legal issues and risks treats as a reasonable-adjustment question rather than an integrity one.

A purpose-based boundary instead of a tool list. Li (2026) supplies the policy content that over-inclusive prohibition language lacks: a support-versus-substitution line defined by function and the assessment construct rather than by naming tools, on the argument that tool lists go obsolete and encourage compliance by interface. Permitted support is a surface intervention that adds no ideas, no sources and no material re-ordering of analysis; substitution is generating arguments or counterarguments, applying disciplinary rules to facts, restructuring an analytical sequence, or generating citations for inclusion. The framework is delivered as three instruments — working definitions with shared quick tests so two markers characterize the same conduct alike, calibrated disclosure templates ranging from nothing for embedded low-risk functions to a one-line statement for external language editing and roughly 80–120 words where limited ideation is expressly authorized, and a decision rubric that names weak proxies (polished language or sudden fluency, non-native phrasing, single detection scores) beside the evidence types that can carry weight. It also states the conditions under which scaled permissive regimes such as the AI Assessment Scale remain workable: use expressly authorized for the specific task, the construct re-specified so students and markers know what is assessed, and disclosure kept feasible.

Staged automation with mandatory human oversight. Uruguay's *Acredita EB* national lower-secondary accreditation test offers a concrete model of oversight-preserving automation in assessment policy: multiple-choice sections and existing procedures stay unchanged, AI is used only for the writing section inside a mandatory calibration stage on 50–100 texts, and two pruning rules decide which results require expert review — candidates who cannot pass on the other two sections need no writing review, and candidates Proficient in all three sections pass with only 0.2%/0.6% observed residual risk. The authors estimate the design could cut written responses needing full human scoring by at least 50% while keeping the guiding principle that no final decision about test outcomes is made without appropriate human oversight. This complements the boundary–evidence work above by showing a policy that specifies not only where AI is permitted but which human evidence and review remain mandatory.

The adversarial side of automated grading. A policy that routes grading through an AI tool inherits an attack surface. Humble (2026) red-teamed an institutional grading workflow by hiding five indirect prompt injections inside the files of a synthetic submission that Microsoft Copilot (GPT-5.2) had graded as fail on all six baseline runs. Two strategies raised the grade with no visible warning to the user — reported attack success rates of 100% (9 of 9 iterations) and 94% (17 of 18) — and the tool both silently disabled a chat after blocking the simplest attack and, in one iteration, announced it would ignore embedded instructions before raising the grade on the next six runs. A grade obtained through a hidden instruction carries no validity claim, and the same technique could degrade a submission with no durable trace, so the paper's asks are policy-level rather than technical: sector-level guidance, professional development, restricted AI use with human review for high-stakes work, and standardized, domain-agnostic testing of prompt-injection resilience so the attack surface is measured rather than assumed. It is the adversarial counterpart to the oversight designs above: where those specify which human review is mandatory, this specifies a class of manipulation that review exists to catch but has no reliable signal for.

A value/norm matrix as a policy foundation. Agarwal et al. (2026), a systematic review of 25 articles, consolidate AIED ethics into six main ethical values (non-discrimination, data stewardship, human oversight, goodwill, explicability, educational aptness) and map the ethical norms extracted from the literature onto a stakeholder-by-value matrix. The review positions the matrix as a foundation for building detailed ethical frameworks and regulation for AIED, giving educational institutions, developers, and regulators concrete norms to implement specific values. It finds goodwill norms aimed at regulators are far more numerous (nine) than for any other stakeholder set, signaling regulators' role in ensuring AIED benefits learners through policy and legislation — a concrete, value-anchored starting point for the policy-vs-governance machinery this page describes.

Evidence claims and the policy machinery

Claims that travel further than their qualifications. A pilot announcement is a policy instrument too, and its reporting standards are part of the policy. Restrepo Morales et al. (2026) analyze the September 2026 El Salvador episode in which an AI-tutoring pilot in 171 public schools was reported as reaching results comparable to Germany and Sweden: against the German PISA 2022 mathematics average, the top 5.5% of the national achievement distribution would have matched the benchmark with no learning gain at all, and the pilot's assessment covered 7.0 students per school against 25.4 in the national survey the same year, so the published evidence cannot exclude selection as the explanation. Their proposal is a six-item reporting standard — the participating schools' baseline, the sampling protocol (eligible students, assessed students,

identification rule, participation rate), disaggregated scores with standard errors, the operational date of each reform component, overlap with the representative national sample, and the qualification stated in the same document, post or paragraph as the claim — motivated by the disclosure arithmetic of the announcement itself: the World Bank post carrying the claim recorded about 441,000 views against about 11,000 for the post carrying the qualification four places later in the same thread. The policy lesson is that where a system uses school-level results as evidence about itself, the format of disclosure decides which statement becomes the public fact.

Piloting itself can become the policy machinery. Williamson et al., 2026 read England's EdTech Impact Testbed — an initial £1 m for 16 prototype-building companies in 2025, then £23 million to expand the pilot to 1,000 school sites — as anticipatory governance: classrooms become testbeds yielding promissory, just-in-time evidence for scaling.

A country-level analysis of PISA 2022-2025 found that countries with higher generative-AI use showed larger declines in reading and mathematics, an association that disappeared once prior performance was controlled (Guerra & Aslanov, 2026). The authors read it as a caution that wider chatbot access should not be treated as a benefit in itself, and call for rollouts paired with longitudinal evaluation.

Policy vs. governance

Policy and governance are closely related but distinct, and keeping them apart matters for understanding the knowledge base's research.

- **Policy is the *content* — what is decided.** A policy is a formal rule, principle, or statement: what AI use is allowed, prohibited, or required; what must be disclosed; what assessment formats are permitted. It exists as a documented artifact (legislation, institutional guideline, syllabus statement) and answers *"what are the rules?"*
- **Governance is the *machinery* — how it is decided, implemented, and enforced.** Governance encompasses the institutional structures, norms, and accountability mechanisms that produce, carry out, and monitor policy: who sets the rules, how they are communicated and resourced, how compliance is enforced and challenged, and how they are revised as AI evolves. It answers *"who decides, and how do the rules actually take effect?"*
- **They are interdependent.** Policy without governance is unenforced — a written rule no one owns, monitors, or updates. Governance without policy lacks direction — structures that administer nothing in particular. The knowledge base's research repeatedly shows that the two must be built together: a policy that only *classifies* AI use without governance to specify evidence, safeguards, and revision processes remains weak in practice (the cognitive-stewardship audit), and governance that merely monitors without clear policy risks surveillance without fairness (see AI governance).

Procurement sets the data environment before any pedagogy is decided. Pandey and Davies (2026) treat platform dependency as a governance risk rather than a cost line, since the contract decides data sovereignty, audit rights and exit terms. They argue this as a conceptual proposition from an interpretive review, not from institutional evidence.

Senior AI leadership is rare relative to strategic ambition. A scoping review of 19 sources found only 7% of institutions had created senior AI leadership roles though 49% treated AI as a strategic priority, with most included studies conceptual or cross-sectional, so no causal effect of anticipatory governance could be established (Baroudi (2026)).

The practical test that separates them: a policy can be read on paper, but governance is observed in whether the rule is implemented, enforced, and adapted. This is why AI Governance extends AI Regulation in Education and policy into institutions, and why the knowledge base treats assessment-format choices (Summative Assessment) as *policy* decisions that only become effective through *governance* structures like review boards, declaration frameworks, and appeal routes.

Classroom policy as the interpretive frontier of governance. The machinery of governance does not stop at the institutional document; the teachers who read and adapt it are the last link in the chain, and Nash & Burriss (2026) show what that link looks like in practice. Their preservice teachers expected to work in districts with AI policies yet still had to author classroom-specific rules for their own students — an essential adaptation skill — and the authors argue that teachers can decline to adopt AI for specific reading and writing tasks without ignoring it, with principled refusal distinguishable from uncritical rejection. Keeping that distinction viable is itself a governance task: districts and preparation programs need the guidance, professional development, and policy infrastructure that let teachers refuse particular uses without being framed as behind the times.

Governance indicators for the authentication problem. Coates, Croucher and Calderon (2025) supply the measurement layer this policy-versus-governance distinction implies, treating Academic Integrity in the GenAI era as a governance problem before a detection problem and judging contemporary academic governance resilient but "not well positioned or poised" to protect the authentication of student Assessment. Their framework holds 130 governance questions under eight dimensions — Designing, Developing, Training, Implementing, Analyzing, Reporting, Evaluating and Improving — and the items are questions about institutional machinery rather than psychometric scales: whether the institution's top-most board or council receives updates on assessment processes and outcomes, whether key performance indicators cover assessment quality, what percentage of students are known individually by the teachers who assess them, whether extreme low or high marks are cross-checked, and whether there is a simple route for referring contract cheating cases. The accompanying reform program targets governance architectures, the people who hold governance roles, and the technologies and resources supporting assessment, and the authors argue that little institutional development pays out without external affordance from regulation, benchmarking and cross-institutional competition — the same regulatory pressure the AI Regulation in Education page treats as the binding constraint on governance reform. The gap is measured in K-12 too, not only in universities. A nationally representative survey of 1,018 US public school teachers and principals found only 18% of teachers and 24% of principals reporting a school generative-AI policy — the same below-institution pattern this page documents in higher education (Tench, Weinstein & James, 2026).

The policy deficit in AI × SEL research

A systematic review of 65 papers at the intersection of AI and social-emotional learning (Tran, Liu & Nguyen 2026) documents a "policy deficit": nearly three-quarters of studies state no policy implications, and those that do often lack actor-oriented specificity. The review finds policy engagement correlates with

publication venue, reflecting academic incentives that reward technical novelty over AI Governance and AI Regulation in Education. It proposes a “WH-question” framework (Who, What, Why, When/Where, How) and a shift from “implication-as-afterthought” to “implication-as-methodology” — treating policy articulation as a design constraint of research rather than a post-hoc add-on.

The same deficit has a demand side. Gillette et al. (2026) add demand-side evidence from a Swedish social science faculty: 31% of survey and focus-group participants raised ethics unprompted, most wanted more institutional guidance, and genAI’s environmental consequences were absent from policy documents altogether.

Common Misconceptions

- **“Universities have real AI policy.” Legal form is rarer than legal language.** In a **160-document scoping review**, **2.5% of instruments carried legal force while 57.5% were guidance or toolkits**. Nearly a quarter of a hundred documents’ worth of AI governance is non-binding guidance.
- **“Institutional caution reflects evidence.”** Caution is attributed **to time pressure rather than evidence**: the ABA’s 2024 survey drew responses from only about **15% of accredited schools**, so the cautious consensus rests on a non-representative sample.
- **“Policy coverage can be mapped from a representative survey.”** AI policy and guidance was collected from **all 48 CAHIIM-accredited programs** in one domain — a complete census of a niche, which is more informative about that niche than about policy generally.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- AI Regulation in Education
- AI Governance
- Educational Development
- Equity
- Higher Education
- K-12
- Academic Integrity
- Ethics
- Teacher AI Competency
- Framing AI Use for Students
- Summative Assessment
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools

- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Student Support and Success — the policy context for institutional support deployment

Connected Articles

- Cheating or being cheated? Academic integrity and a changing cheating habitus in international AI governance discourse — UNESCO and OECD texts share a governance vocabulary and no operational definitions; twenty-three jurisdictions converge without one
- Toward Partnership Ethics for Generative Artificial Intelligence in Higher Education — Swedish survey and focus-group study arguing that partnership ethics, not a cheating frame, should guide institutional genAI decisions
- Generative AI Governance in Education: A Scoping Review of Principles, Mechanisms, and Risks in English-Language Documents — Generative AI governance in education: a scoping review of principles, mechanisms and risks (Elmahjub et al. 2026)
- Artificial learning: how sessional academics view contract cheating and digital academic misconduct in assessment — Unit-level rules that students cannot reconcile
- An AI Policy Isn't a Playbook: Educators Need Agency, Not Just New Rules — A nationally representative survey of US teachers and principals on AI policy coverage, agency, and five classroom plays (Tench, Weinstein & James 2026)
- When universities advocate GAI but practice falls short: student appraisals and creative process engagement in art education — When universities advocate GAI but practice falls short: student appraisals and creative process engagement in art education
- Writing the rules for generative machines: Tensions and entanglements in preservice teachers' classroom AI policies — Preservice English teachers' classroom AI policies: what they permitted, limited, and banned (Nash & Burriss 2026)
- A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment — A Human-in-the-Loop Framework for AI-Assisted Scoring in Large-Scale Writing Assessment
- Designing an Aligned Generative AI Course Policy: An Equitable and Transparent Learner-Centered Approach — Deriving allowed and unallowed GenAI uses task by task from what is assessed (McCorkle 2025)
- How Instructors Regulate AI in College: Evidence from 31,000 Course Syllabi — How instructors regulate AI across 31,000 course syllabi (Chirikov 2026)
- Artificial Intelligence and Grade Inflation — AI task displacement as a mechanism of grade inflation (Chirikov 2026)
- Governing generative AI in higher education: a global Delphi study on policy and practice — Global Delphi on governing generative AI in higher education
- Governing generative AI in higher education: Emerging policy approaches and support ecosystems at innovative U.S. universities — Guidance over policy: instructor-set syllabus rules and a four-unit support ecosystem across 50 innovative US universities (Qian 2026)

- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — Five-factor comparison of law school GenAI policies in a sector making policy without an evidence base (Gutowski & Hurley 2025)
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Transcription is not generation: over-inclusive AI rules, format conversion and disability accommodation (Wright 2026)
- Anticipatory governance and leadership for AI implementation in higher education: A scoping review — Anticipatory governance for AI in higher education (scoping review)
- Institutional approaches to artificial intelligence policy and guidance in health informatics and information management education: emerging trends and inconsistencies — AI policy documents across all 48 accredited health informatics master's programs: mostly guidance, centered on academic integrity (Eldredge et al. 2026)
- What Does the Credential Still Certify? Cognitive Stewardship for AI-Mediated Education — Cognitive stewardship for AI-mediated assessment (30-university policy audit)
- Generative Artificial Intelligence Policy: A Qualitative UNESCO Framework Analysis
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education
- A framework for institutional change in the age of AI
- 'A bit of chaos and madness': The AI Assessment Scale and the work of assessment reform
- The Evidence Base on AI in K-12: A 2026 Review
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making
- The Policy Deficit in AI × Social-Emotional Learning Research — The Policy Deficit in AI × SEL Research
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- Zero-shot governance — Zero-shot governance: general-purpose AI in policy (Perrotta 2026)
- How much selection would be enough? Bounding the learning claim of El Salvador's artificial intelligence tutoring pilot — Bounding the learning claim of El Salvador's AI tutoring pilot (Restrepo Morales et al. 2026)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — 1,057 US faculty: 87% write their own assignment rules against thin institutional and departmental guidelines (Watson & Rainie 2026)
- GenAI assessment and language equity: Drawing the line between support and substitution — A purpose-based support–substitution boundary with calibrated disclosure and decision rubrics (Li 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection in AI-mediated grading: grades changed undetected, and the policy-level response (Humble 2026)
- Governing academic integrity: Ensuring the authenticity of higher thinking in the era of generative artificial intelligence — 130 governance indicators for authenticating assessment, and the external pressure reform needs (Coates, Croucher & Calderon 2025)

- Student GenAI use under changing institutional policies: a mixed-methods case study in undergraduate physics — Policy tier versus task design: what students used GenAI for across three physics assessments (Quince & Faulconer 2026)
- Generative AI use and the 2022–2025 decline in PISA performance across countries — Higher country-level generative-AI use tracked larger PISA 2022-2025 declines, a correlation that vanished after controlling for prior performance (Guerra & Aslanov 2026)
- Experimental futuring: AI prototyping and pilot testing as anticipatory governance in education — England’s EdTech Impact Testbed as anticipatory governance: pilots that produce promissory evidence (Williamson et al
- Higher education governance under AI and geopolitical disruption: a socio-technical framework for administrative artificial intelligence — Procurement sets the data environment before pedagogy

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Write and Implement an Institutional AI Policy?
- How Do I Write a Course AI Policy and Communicate It to Students?

AI Governance

> **AI governance** — the frameworks, policies, institutional structures, and norms that guide the responsible design, deployment, and use of artificial intelligence in education. Governance spans formal institutional mechanisms (AI steering groups, policies on academic integrity and acceptable use, ethical review) and informal norms (faculty guidelines, professional development, cultures of responsible AI use). In the AI era, effective governance is a prerequisite for ethical, equitable, and sustainable adoption of GenAI — it determines whether AI is integrated transparently, with accountability, or adopted reactively in ways that deepen inequities.

Questions to Consider

- If your institution has an AI policy on paper but no clear process for enforcing, updating, or communicating it, is that really governance? What separates a rule that exists from a rule that is actually governed?
- Students in one study said their university had no clear AI policy and that this shaped how they used AI. How might policy ambiguity influence what students decide is 'acceptable use' — and should institutions be worried about leaving that negotiation to individuals?
- The page distinguishes detection-based governance (policing AI use) from design-based governance (redesigning assessment so AI use is expected and declared). Which approach does your own assessment practice lean toward, and what are the trade-offs of each?
- Governance is described as operating at national, institutional, and classroom levels. Think of one AI rule in your context: who set it, how is it communicated and enforced, and how well do those levels align?
- One framework reframes AI governance as a collective-action problem of sustaining shared expertise — the 'cognitive commons.' How does protecting a profession's collective knowledge pool change how you think about AI governance versus just regulating a tool?
- The page warns that mandatory AI-use declarations fail when they feel punitive or ambiguous. When have you seen a compliance rule backfire because people didn't understand or trust it — and what did that teach you about governance?

Introduction

AI governance in education is increasingly urgent because generative AI introduces new epistemic, ethical, and organizational challenges: it destabilizes assumptions about knowledge production, learner agency, Assessment validity, and the role of educators as epistemic authorities. Governance addresses questions of academic integrity (what counts as acceptable AI use), data privacy and security, algorithmic bias and fairness, transparency and accountability, and the alignment of AI adoption with institutional mission and values. A recurring finding across the knowledge base's research is that **institutional governance is often**

lagging — many institutions lack clear, unified AI policies, leaving students and faculty to negotiate acceptable use on their own.

- **Zero-shot governance as a structural condition of platformisation.** Perrotta (2026) develops the concept of **zero-shot governance** — domain-agnostic generative AI intervening in policy decisions — through a code-level analysis of **Redbox**, a discontinued UK civil-service prototype built on off-the-shelf LLMs. Reading its architecture (an invisible system prompt + a thin Python wrapper over a RAG (Retrieval-Augmented Generation) retrieve → format → generate pipeline and a provider-agnostic cloud stack), the article argues that the general-purpose nature of foundation models is a *structural feature* of platformisation that can be mitigated but never ruled out: agentic AI does not interrupt the monopolistic, rentier logic of platforms, and the same probabilistic mechanism that generates novelty also produces hallucinations. For governance, the implication is that oversight of general-purpose AI must treat aberrant output as an irreducible, only-mitigable risk rather than a fixable bug — a caution that applies equally to education policy reasoning.
- **Baroudi** scoping review frames AI governance in higher education through anticipatory-governance and leadership lenses.
- **Anticipatory governance by prototype and pilot.** Williamson et al., 2026 read England's DfE as governing through design: AI prototypes and school pilots prefigure a chosen future, treat classrooms as testbeds, and produce just-in-time "promissory" evidence for scaling rather than a settled "what works."
- **Student co-design of policy:** Hingle & Johri show how a guided inquiry activity in which students co-designed a GenAI course policy surfaced student values — prioritizing training, standardized disclosure procedures, stronger institutional support, and greater involvement in decision-making. This positions students as partners in governance rather than passive subjects, complementing institutional-level policy with bottom-up student voice.
- **The techno-solutionist trap and the policy deficit:** A systematic review of 65 AI × social-emotional learning studies (Tran, Liu & Nguyen 2026) finds that research often foregrounds technical potential while under-specifying the institutional conditions for responsible implementation — a "techno-solutionist" trap. The authors link policy engagement to publication venue and propose a "WH-question" framework to make governance implications actor-specific, echoing the knowledge base's broader finding that institutional governance lags AI adoption.

Gillette et al. (2026) show a governance mismatch rather than a governance vacuum: students wanted the university to "do more", but the institution holds that decisions belong at department, program and course level, so demand and mandate point at different bodies while silence fills the gap.

How AI governance appears in the research

- **Institutional adoption at scale:** The AIDA study at the Open University shows how an institution designed, implemented, and evaluated a GenAI assistant, identifying that responsible system-level deployment requires governance structures (AI Steering Group), senior leadership sponsorship, and alignment with institutional strategy — not just technical capability.

- **Leadership and systemic change:** SPARK frames governance within Complexity Leadership Theory, arguing leaders must balance administrative stability with emergent innovation, embedding governance mechanisms (policies, assessment regimes, accountability frameworks) so adaptive-space innovations can be sustained and scaled.
- **Policy ambiguity and student experience:** Students' engagement with GenAI found 12/23 students noted the lack of explicit institutional AI policies ("University doesn't have a clear and unified policy yet"), arguing governance ambiguity shapes students' practices, norms, and self-regulation — supporting a shift toward transparent institutional guidance.
- **AI literacy as a governance capacity ("the 18th SDG"):** Islam, Morshed, and Islam (2026) reconceptualize AI literacy as a systemic governance mechanism rather than a classroom skill, proposing a six-level AIRE Taxonomy (Recognize → Comprehend → Apply → Analyze → Integrate → Govern) that extends Bloom's hierarchy with ethical synthesis and strategic foresight, and an AI–SDG Nexus mapping literacy competencies onto all seventeen Sustainable Development Goals. Framing AI literacy as an "18th SDG" heuristic — a cross-cutting capacity that channels learning into governance and sustainable development — the study's survey of 300 professionals found governance literacy the strongest predictor of AI–SDG nexus awareness ($\beta = 0.64$, $r = 0.67$ with nexus awareness) and identified ethical reasoning and reflective thinking as the strongest predictors of trustworthy AI use. This ties institutional governance to the cultivation of public AI Literacy, echoing the knowledge base's finding that responsible AI alignment requires policymakers and citizens who can critically interpret algorithmic systems, not merely compliance-oriented technical control.
- **Most education governance is guidance, not law.** Across 160 English-language documents, only 4 took formal legal or regulatory form while 92 were guidance, frameworks or toolkits, and accountability appeared in 146 documents but paired with a named oversight actor in 100 (Elmahjub et al. (2026)).
- **Administrative AI makes governance a service-operations question, not a classroom one.** Pandey and Davies (2026) scope administrative AI to recruitment, admissions, enrollment, records, advising, housing, welfare and careers, and exclude teaching, learning and research by definition. Their socio-technical framework offers three testable propositions: joint optimization of technology with roles and accountability, the politics of artifacts, and globally shaped infrastructure. Five drivers explain adoption: infrastructural readiness and commercial platform ecosystems enable and steer it, while competitive positioning under enrollment volatility, regulatory and mobility mandates, and sustainability legitimacy motivate it. Four leadership capabilities follow — contractual literacy, interrogating the objective, restraint under pressure and standing participation. This is a conceptual analysis and interpretive review, so the propositions are offered for testing rather than established.
- **Academic integrity and assessment:** Governance is central to how institutions handle AI-related Academic Integrity concerns and redesign Assessment — moving from prohibition/policing toward guidance, AI literacy, and process-oriented designs, as seen in research on student rationalization and authentic assessment redesign.

- **Redesign runs on three dimensions at once.** Laidlaw (2026) frames AI-era assessment redesign through cultural-discursive (language and assumptions), material-economic (resources), and social-political (governance and power) dimensions, and names the resource-power intersection as both the greatest leverage point and the greatest risk: resources flowing through existing power structures amplify inequities.
- **The instrument mix of written-down governance:** Eldredge et al. (2026) audited AI-related documents from all 48 CAHIIM-accredited health informatics and health information management master's programs in the United States. Forty of the 48 (83%) had at least one publicly available document, and across the 40 documents analyzed governance was realized mostly as guidance rather than binding rule: 21 guidelines (53%), 9 informational documents (23%), and only 7 formal policies (18%). Most documents addressed faculty and students together (20, 51%) rather than students alone (6, 15%), and neither policy type nor audience varied with delivery mode (Fisher's exact P = .85 and P = .71), suggesting the instrument mix tracks institutional habit rather than the demands of online, campus, or hybrid programs. Content clustered on academic integrity, responsible AI use, and student conduct, with little guidance covering AI use in applied learning, research, and simulated environments, precisely where curricular and data governance concerns intersect. The authors also report that regional accreditors supplied most of the corpus (Higher Learning Commission n = 14 and SACSCOC n = 13, together about 60%, with none from the WASC region) and argue accreditation is the external lever best placed to reduce variation across programs.
- **Governance as a distributed support ecosystem:** Qian (2026) coded the AI guidance of the 50 US universities ranked most innovative and found governance realized less as rule than as interpretation and support: only 6 of 50 framed their principal page as a "policy", 33 of 50 positioned instructors as the primary translators of institutional expectations into course rules, and the support for doing so clustered across four interlocking units — teaching and learning centers supplying syllabus language and course-policy menus, libraries setting citation and provenance standards, IT and enterprise-governance offices operating data-classification rules and vetted tool stacks, and academic integrity offices carrying due process and education-first remediation. Qian argues it is the Scaffolding, not the stance, that reduces ambiguity, and reports it as unevenly distributed: 33 of 50 institutions published syllabus or course-policy materials while only 4 foregrounded student-facing guidance. This is the instrument-mix finding above in organizational form — governance capacity located in units rather than documents.
- **Ethics, privacy, and bias:** Governance mechanisms operationalize the ethical principles (Ethics, Privacy, Bias Mitigation) that are often recognized but not enforced, connecting to responsible AI and regulatory debates in education.
- **A value/norm matrix for governance.** Agarwal et al. (2026), a systematic review of 25 articles, consolidate AIED ethics into six main ethical values (non-discrimination, data stewardship, human oversight, goodwill, explicability, educational aptness) and map the ethical norms extracted from the literature onto a stakeholder-by-value matrix. The mapping makes norms actionable rules for realizing specific values and offers a foundation for building detailed ethical frameworks and regulation for AIED — giving educational institutions, developers, and regulators concrete norms to implement. Norms for human oversight cluster on educational institutes and end users,

> educational aptness on educational institutes and regulators, and goodwill norms aimed at regulators are far more numerous (nine) than for any other set, signaling regulators' role in ensuring AIED benefits learners through policy and legislation.

Governance education

AI governance operates at two levels the knowledge base treats together: the *institutional rules* that govern AI use (policies, acceptable-use frameworks, Assessment and declaration requirements) and *education about those rules* (preparing people to navigate them). Governance without education risks being unenforced or opaque; education without governance lacks teeth. Research in this strand includes institutional GenAI policy analysis, AI declaration frameworks, assessment governance, UK AI higher-education policy, and comprehensive AIED reviews that situate governance in the wider policy landscape.

Assessment governance

A central arena of AI governance is **how institutions govern assessment** — the rules that determine what counts as acceptable AI use, how AI-assisted work is declared, and how summative measures are safeguarded. This includes the design and enforcement of AI use and disclosure statements: research shows that mandatory declarations fail when they feel punitive or ambiguous (Gonsalves 2025, Vetter et al. 2026), and that clear, consistent, trust-based policy is what actually fosters disclosure. The knowledge base's research distinguishes between *detection-based* governance (policing AI use, e.g., via AI Detection) and *design-based* governance (redesigning summative and authentic assessment so AI use is expected, declared, and scrutinized). Evidence-centered governance of generative AI in assessment and Beyond Detection argue that governance must pair any detection with assessment redesign, while the choice of AI-resistant summative formats (oral exams, proctored/closed-book measures, code-review interviews — see Summative Assessment) is itself a governance decision. Large-scale evidence (Strömberg, Lei, & Wu 2026) underscores the importance of governing summative measures, since ungoverned homework can be inflated by AI while actual learning declines. The scope of a prohibition is itself a governance decision: Wright (2026) shows that rules barring "generative AI" without distinguishing generation from format conversion capture assistive transcription tools and turn policy misapplication into misconduct allegations, burdening disabled and equity-exposed students. That is a governance failure that legal issues and risks treats as an equalities question as much as an integrity one.

Evidence that Zagami (2026) gathers from high-stakes arenas points to uneven governance rather than simple refusal: partial adoption and incomplete policy in assessment, admissions and disciplinary processes, with institutional delay operating as a governance stance rather than a failure. The institutional task is to interpret refusal well enough to improve governance, asking which decisions require human review, which systems require audit, which uses require disclosure, and which procurement choices require public justification. Weidlich (2026) adds the assessment-specific corollary: detector scores are conditional probabilistic signals that cannot by themselves establish misconduct, so detection-centered governance is an insufficient basis for defending assessment claims.

Agentic AI moves the governing question again: Wong & Sun (2026) compare guidance from 12 universities and locate the new work in which responsibilities a student may delegate and whether an agent may act under their credentials — an access question a use-versus-non-use rule cannot express.

Governance across levels

AI governance operates at multiple levels — from **national/regulatory** (government policy, the OECD framework, state AI guidelines) to **institutional** (university policies, AI steering groups, ethical review boards) to **classroom** (instructor guidelines, syllabus statements, assignment design). Effective governance aligns these levels: national frameworks set expectations, institutions translate them into policies and support structures, and educators implement them in ways that build students' AI literacy and agency. The knowledge base's research emphasizes that governance is not merely about restriction but about creating the conditions for responsible, equitable, and learning-supportive AI integration — including faculty development, transparent guidance, and ongoing evaluation. **Identical conduct, different verdicts.** Poudyal (2026) applied 15 standardized student-use vignettes to the public policy environments of 20 Australian universities, producing 300 classifications: 40.0% clearly prohibited, 32.3% potential policy breaches, 9.0% permitted with conditions, and 18.7% indeterminate — none meeting the threshold for clearly permitted. Binding instruments were silent on generative AI in 100 combinations while guidance resolved 88, and disclosed language rewriting and an AI-drafted paragraph produced the highest cross-university divergence against unanimity for an explicit assessment prohibition. Where the levels described above are assumed to align, this study measures how far they diverge, and it locates the operational boundary in guidance rather than in binding policy.

Faculty governance and the case for deliberate review. Where the levels above are aligned through policy, some sectors reach them through shared governance instead. Gutowski and Hurley (2025) describe law schools as a hard case for exactly this reason: US law faculties hold unusual individual authority over course standards, so policy has to be built with them rather than announced to them, and most schools writing prohibitive rules also reserved discretion to individual instructors and committed to revision as the technology moved. Their recommendations — flexibility by design, periodic review, proactive training, and self-regulation through information sharing rather than waiting for an accreditor to dictate policy — describe governance as a continuing process rather than a document, the same point the Delphi consensus makes in recommending scheduled review cycles and a standing multidisciplinary committee.

Institution-wide, the **AIGEM framework** (Tan et al. 2026) positions responsible AI as a strategic organizational capability for educational management, integrating AI strategic leadership, responsible governance, decision intelligence, human-AI collaborative intelligence, competency development, and sustainable value creation – and links responsible implementation to the SDGs. It underscores that governance is not only a compliance layer over teaching but an executive function of educational institutions.

Care ethics puts responsibility on the institution that adopted the tool. Jones (2026) locates responsibility with the institution that chose the system, not the vendor or the instructor who noticed the pattern, and asks whether the same rules bind the administrators who write them as the students who live under them.

Most institutions cannot name who owns AI. Among 387 students and staff at institutions in 13 countries, only 17% knew of a designated AI-management responsibility, while 71% of the remainder wanted one and expected it to combine training, ethical oversight, data security and strategy (Kaže et al. (2026)).

A proposed path from clarity to conduct. Li and Su (2026) model how institutional clarity might reach the classroom. Governance clarity, meaning rule clarity plus role clarity, is proposed as the contextual

antecedent; perceived accountability as the state it works through; and decision uncertainty as the condition it acts on, reducible in its procedural form but not in genuine case uncertainty. AI literacy is proposed as a moderator, and the authors offer five testable propositions and one configurational expectation. This is a Hypothesis-and-Theory paper that collects no data, and its authors describe the paths as propositions, not empirically established effects.

Connections to related concepts

AI governance connects to Ethics (the principles it operationalizes), Higher Education (the institutional context), Privacy and Bias Mitigation (specific governance concerns), and Academic Integrity (a primary governance arena). It is central to institutional change and responsible AI, and intersects with AI Literacy (governance supports the development of critical, informed use). It also connects to Learning Analytics (data governance) and Student Experience (governance shapes how students navigate acceptable use).

Governing the cognitive commons. The Cognitive Commons framework (Lovett 2026) frames expertise regeneration as a profession-level collective-action problem requiring Ostrom-style governance (boundary definition, monitoring, graduated sanctions, collective choice). AI governance is thus not only about tool regulation but about sustaining the shared expertise pool professions need — at organizational, professional-association, and policy levels.

Relationship to educational policy

Governance is distinct from — but inseparable from — educational AI policy. **Policy is the content**: the formal rules and statements (what AI use is allowed, what must be disclosed, what assessment is permitted). **Governance is the machinery** that produces, implements, enforces, and revises those rules: who sets them, how they are resourced and communicated, how compliance and appeals are handled, and how they adapt as AI evolves. Where the policy page catalogs the *rules themselves* and their maturity gaps, this page focuses on the *structures and practices* that make rules real — steering groups, ethical review, assessment governance, and accountability across levels. A rule on paper is policy; a rule that is owned, monitored, and enforced is governance. The two are mutually dependent: policy without governance is unenforced, and governance without policy lacks direction.

Accountability language can leave the responsible actor unnamed. Poudyal (2026) extracted 166 obligation or answerability expressions from 366 GenAI higher-education abstracts and found that none assigned responsibility to a system while 33 left the bearer unspecified; “governance is needed” names no one who convenes, decides, or enforces. Institutions and policy actors bore 37 obligations, institution/educator metonymies 30, educators 20, researchers 18, and students only six.

Svetec, Divjak & Kadoić (2026) identify **ethics & data governance** as one of seven enablers of trustworthy LA-based educational interventions — policies for the ethical use of LA and AI, data privacy, security, and accountability — and position trustworthiness (including leadership and governance that support implementation) as the prerequisite for meaningful data-informed interventions.

- **Governance can be designed into the tool.** A six-dimension governance profile - pedagogical grounding, instructional authority, human accountability and control, learner agency and cognitive engagement, context specificity, and evaluation visibility - locates governance in a teaching tool’s

interaction model, prompts, rubrics, approval gates and dashboards. It asks whether mechanisms fit the instructional function rather than how strict or permissive a tool is (Dickey, 2026).

- **A human-centered framework puts interpretation, not the tool, at the center.** At a mission-driven liberal arts college, faculty used a generative-AI-supported Assessment Wizard during a structured Education Day, and the authors conclude that human judgment must stay the non-negotiable interpretive authority, with verification checkpoints and governance in place before broad implementation (Ravesloot, Copeland & Pryor, 2026). The sequence is formation and verification first, scale second.

Common Misconceptions

- **"Universities have adopted binding AI policy."** Of **48 institutions**, **40 (83%)** had at least one publicly available document, and across those 40 **governance was realized mostly as guidance rather than binding** rule. Published guidance is not enforceable policy.
- **"Policy is written student-first because students are the risk."** Most documents addressed **faculty and students together (20, 51%) rather than students alone (6, 15%)**, and neither policy type nor audience varied with delivery mode. The framing is joint, which means the obligations are shared.
- **"Ambiguous policy leaves student experience untouched."** Policy ambiguity shows up in **student experience** directly: students' engagement with GenAI is shaped by the uncertainty, so ambiguity is an active condition rather than a neutral gap.

Connected Concepts

- Pedagogical Partnerships — Pedagogical Partnerships
- AI Use and Disclosure Statements — AI use and disclosure statements
- Remote Proctoring
- Ethics
- Higher Education
- Privacy
- Bias Mitigation
- Academic Integrity
- AI Literacy
- Learning Analytics
- Student Experience
- Educational AI Policy
- AI Regulation in Education
- Summative Assessment
- AI Misuse and Learning Harm
- Trust Calibration
- Generative AI

- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Student Support and Success — oversight for institutional AI support systems

Connected Articles

- AI Adoption at Higher Education Institutions: A Call for Designated AI Management — AI adoption in higher education: the case for designated AI management (Kaže et al. 2026)
- Care Ethics for AI Governance in Higher Education: Applying the Jones AI Ethics Framework — Care ethics for institutional AI governance, the five components and the institutional questions they turn into
- Generative AI Governance in Education: A Scoping Review of Principles, Mechanisms, and Risks in English-Language Documents — Generative AI governance in education: a scoping review of principles, mechanisms and risks (Elmahjub et al. 2026)
- Artificial Intelligence Literacy and Sustainable Development: An Ethical Governance and Development Goals Framework — AI literacy as a governance capacity for sustainable development: the AIRE Taxonomy and AI–SDG Nexus (Islam, Morshed & Islam 2026)
- Artificial Intelligence in Educational Management: Opportunities, Challenges, and Future Directions — AIGEM framework for AI governance in educational management
- Institutional approaches to artificial intelligence policy and guidance in health informatics and information management education: emerging trends and inconsistencies — AI policy and guidance documents across 48 CAHIIM-accredited health informatics programs: governance as non-binding, integrity-centric guidance (Eldredge et al. 2026)
- A Guided Inquiry Approach to Students Co-Designing Generative AI Course Policies — Students co-designing GenAI course policies via guided inquiry (Hingle & Johri 2026)
- From learning analytics to educational interventions: Enhancing decision-making and learning design — From learning analytics to educational interventions: enablers of trustworthy LA-based interventions (Svetec, Divjak & Kadoić 2026)
- Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher — Student non-compliance with AI use declarations
- The Hidden Cost of Disclosure: A Multi-institutional Study on Undergraduate Students' Generative AI Usage and Faculty Accusations — The hidden cost of disclosure
- "Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education — Student AI disclosure, stigma, and self-regulated learning
- Which inference is at risk? Assessment validity reasoning and generative AI — Which inference is at risk: assessment validity reasoning and generative AI (Weidlich 2026)
- Governing generative AI in higher education: a global Delphi study on policy and practice — Global Delphi on GenAI governance and policy
- Governing generative AI in higher education: Emerging policy approaches and support ecosystems at innovative U.S. universities — Governance by guidance: instructor-set syllabus rules and a four-unit support ecosystem across 50 innovative US universities (Qian 2026)

- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — Faculty governance, instructor discretion and periodic review in law school GenAI policy (Gutowski & Hurley 2025)
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive “AI” prohibitions, format conversion and the reasonable-adjustment problem (Wright 2026)
- AI refusal in higher education: The right to refuse, the duty to understand and the diagnostic value of non-use — Refusal as evidence: uneven governance, the duty to understand and the diagnostic value of non-use (Zagami 2026)
- Anticipatory governance and leadership for AI implementation in higher education: A scoping review — Anticipatory governance and leadership for AI
- New systems of learning for distance learning institutions? A six-study review of implementing AIDA — Implementing AIDA at the Open University
- Leveraging complex systems: Leading for transformative change — SPARK: Leading for Transformative Change
- Students’ engagement with generative AI in academic learning: A self-determination theory and epistemic network analysis study — Students’ Engagement With GenAI (SDT)
- Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World — Beyond Detection: Authentic Assessment Redesign
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education — Institutional GenAI policy in computing
- Structuring Transparency: Developing Domain-Specific Generative AI Declaration Frameworks in Higher Education — AI declaration frameworks
- Generative AI as a design variable: An evidence-centered framework for principled governance in STEM assessment — Assessment governance under GenAI
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — AI in UK higher-education policy
- Review of Artificial Intelligence in Education from 2020 to 2025 — Comprehensive review of AIED research
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- The Policy Deficit in AI × Social-Emotional Learning Research — The Policy Deficit in AI × SEL Research
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- Zero-shot governance — Zero-shot governance: general-purpose AI in policy (Perrotta 2026)
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research

- Instructional Governance by Design: A Framework for AI in Computing Education — Instructional Governance by Design: A Framework for AI in Computing Education
- Mapping the Authorized Boundary: A Comparative Policy-Vignette Study of Generative AI Governance in Australian Higher Education — Mapping the Authorized Boundary: A Comparative Policy-Vignette Study of Generative AI Governance in Australian Higher Education
- Delegation Is Not Assistance: Agentic AI and Assessment Governance in Higher Education — A Comparative Documentary Analysis of 12 Universities — Delegation, evidence and access: what agentic AI changes in university assessment governance (Wong & Sun 2026)
- Experimental futuring: AI prototyping and pilot testing as anticipatory governance in education — AI prototypes and school pilots as governance machinery that prefigures a chosen future (Williamson et al
- Psychological pathways to responsible generative AI decision-making among teachers: governance clarity, perceived accountability, decision uncertainty, and AI literacy — A proposed path from governance clarity to teacher decision episodes
- Higher education governance under AI and geopolitical disruption: a socio-technical framework for administrative artificial intelligence — Administrative AI as a service-operations question

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Write and Implement an Institutional AI Policy?

Change Management

> **Change management** — the deliberate set of processes, governance structures, and leadership practices through which Higher Education institutions plan, implement, and sustain the integration of AI into teaching, learning, and Assessment. Because generative AI arrived as an "arrival technology" that entered classrooms before pedagogical evidence accumulated, change management in AI education must support continuous adaptation under uncertainty rather than one-time adoption, balancing institutional stability with emergent innovation and shared governance across administrators, faculty, students, and policymakers.

Questions to Consider

- Change management here is described as governing continuous adaptation under uncertainty, because generative AI arrived in classrooms before pedagogical evidence accumulated. What does it mean to manage change when you can't wait for best practices but also can't responsibly scale untested innovations?
- A recurring obstacle is the gap between top-down policy intent and classroom reality — for instance, policies that encourage GenAI while course syllabi prohibit it, leaving instructors to improvise. Why do you think policy and practice drift apart so easily around AI?
- Research finds that a faculty member's pedagogical orientation — what they believe AI means for disciplinary knowledge — is the strongest predictor of adoption, while institutional initiatives and demographics are surprisingly weak predictors. What does that suggest about where change efforts should focus their energy?
- The page notes that only 7% of institutions have created senior AI leadership roles despite 49% viewing AI as a strategic priority. What do you think it signals when an institution calls something strategic but doesn't resource it with leadership?
- A coordination-game model explains why policy statements alone fail: student AI use is a collective norm-formation process, and small, well-calibrated changes to assessment incentives can trigger rapid cohort-wide shifts toward responsible use. How might changing assessment incentives do more than issuing a policy ever could?
- The page warns that fragmented adoption widens existing gaps — inclusion, equity, and sustainability are often overlooked even where core ethical principles are embraced. Which Learners or institutions do you suspect lose out when change is managed unevenly, and how would you keep them central?

Introduction

The empirical literature consistently shows that effective AI change management is a socio-technical, not merely technical, endeavor. The institutional change framework adapts classic change models to generative AI, arguing that institutions "cannot wait for best practices, but cannot responsibly scale unjustified innovations," and calling for humble local inquiry, reform organized around pedagogical approaches rather

than ephemeral tools, and students engaged as partners in reform. This framing resonates with the complex-systems leadership argument that education is a complex adaptive system where leaders must judge when to reinforce administrative stability and when to enable "adaptive space" — diffusing high-risk innovations like AI through trusted social networks (complex contagions) rather than linear knowledge flow.

A recurring obstacle to change is the gap between top-down policy intent and classroom reality. The comparative policy analysis found that while 63% of U.S. R1 university policies encourage GenAI use, half of computing-course syllabi outright prohibit it, leaving instructors to improvise inconsistent local rules. Similarly, the UK higher-education policy review documents a divide between research-intensive and teaching-led institutions, with national guidance criticized for lacking specificity and enforcement power, while the institutional governance analysis shows university-wide policies emphasize data security and risk mitigation while school-level policies (when they exist) focus on pedagogy — a structural misalignment that falls short of accreditation expectations for unified integration of curriculum, policy, assessment, and infrastructure.

A published response to a nursing study makes the unit of analysis explicit: Shankar (2026) argues that a framework like Technological Pedagogical Content Knowledge (TPACK) captures individual educators and leaves the institution out of the model. Read through implementation science, adoption depends on four levels at once, the intervention, the inner organizational setting, the outer policy environment, and the individuals involved. The concrete proposal is to operationalize the Consolidated Framework for Implementation Research as a readiness checklist covering leadership engagement, available infrastructure and faculty capacity before any tool is adopted, which moves the question from who needs training to whether the organization is ready to deploy.

Change management in AI education research

Scholarship converges on several change-management levers. **Governance frameworks** provide consensus-driven templates: the global Delphi study proposes an eight-area GenAI governance framework (academic integrity, ethical use, Privacy, equitable access, literacy, integration, human oversight, institutional support) plus a six-part review mechanism to keep policy current, positioning policies as enabling structures within an interconnected institutional ecosystem. **Anticipatory leadership** is the complementary thread: the scoping review finds institutions must shift from reactive to foresight-driven governance, with empowering and distributive leadership increasing adoption — yet only 7% of institutions have created senior AI leadership roles despite 49% viewing AI as a strategic priority.

Adoption drivers reveal why change stalls or succeeds. The organizational drivers study shows that internal organizational culture and technological attributes (compatibility, relative advantage, low complexity) catalyze AI adoption, with government AI Regulation in Education as an external enabler — context-sensitive dynamics that individual-level technology acceptance models miss. Conversely, the faculty orientation study finds that a faculty member's epistemic interpretation of AI — their pedagogical orientation toward what AI means for disciplinary knowledge — is the strongest predictor of adoption, while institutional initiatives and demographics are surprisingly weak predictors. This cautions that top-down strategic plans have limited impact unless they engage faculty beliefs, and that bottom-up peer networks (department colleagues were the top information source) matter more than central initiatives.

Institutional transformation case studies show how these levers play out in practice. Qin (2026) analyzes Lingnan University's strategic change across four dimensions — instructional upgrade through AI, prioritization of irreplaceable human competencies, curriculum renewal, and retention of ethical/cultural values — illustrating how a long-established institution can manage GenAI-driven change without relinquishing its identity. It frames the transformation as intellectual rather than technocentric, giving institutional leaders a staged model for mandating AI literacy while preserving humanistic mission.

School-system implementation evidence shifts the question from which product to adopt to how it is used. Fieldwork by Instruction Partners — 32 classrooms in 16 school systems across seven states — found the same product landing well or badly according to how the teacher framed the purpose, watched the dashboard, and acted on what it reported, with ten-minute activities stretching across a class where routines and a clear place in the scope and sequence were missing. Products that specified teacher actions during use were used closer to their intended approach, and teachers needed sustained coaching rather than a single rollout; where leaders knew a product well, teachers took the desired actions more often. **Sustainability is a property of the organization, not the tool.** The durability of a non-generative AI text-messaging chatbot at California State University, Northridge, came from the organization around it rather than the technology, as a four-year randomized evaluation shows. Its administrative home mattered — joint oversight by the Office of Undergraduate Studies and the Office of the Registrar — as did one communication specialist writing every campaign for a consistent voice, and enough flexibility in the message mix to absorb the COVID-19 shock. Cross-office data sharing for targeted outreach, by contrast, proved burdensome enough that targeted campaigns fell from 36% to 6% of the annual total (Mata, Russell & Page 2026, a working paper whose implementation findings rest on system observation and administrator discussions rather than the trial). Its engagement result reinforces the same lesson: annual opt-out rates never exceeded 4% over four years, which the authors read as receptivity sustained by how the institution adapted implementation rather than by the technology itself.

Assessment reform is a central change-management battleground. The AI Assessment Scale study shows framework implementation hampered by departmental inconsistencies, workload pressures, and uncertainty, with staff describing the process as "a bit of chaos and madness." The coordination game model offers a formal account of why policy statements alone fail: student AI use is a collective norm-formation process, and small, well-calibrated changes to reflective assessment incentives can trigger rapid cohort-wide shifts toward responsible use, whereas weak or misaligned incentives allow opportunistic practices to persist. This supports pedagogy-led governance over surveillance. The AI adaptation gap survey adds a stakeholder dimension: students report higher AI-use intensity and perceived usefulness than faculty and administrative staff, while the latter report stronger Academic Integrity concerns — and perceived usefulness drives Trust ($\beta = 0.402$) more strongly than institutional policy clarity ($\beta = 0.223$).

An assessment-practice workshop with 73 computing educators supplies the counterpart from the classroom side. Nearly every change participants described had been made by an individual instructor in a single course without institutional coordination — colleagues inside one department taking opposite positions with nothing reconciling them — and the curricular response the report argues for will not conclude in time to help students now enrolled; assignment difficulty was also observed to expire on roughly a semester's cycle, which makes calibration against current model capability a perishable institutional asset rather than a one-time decision (Akbar et al., 2026).

Implications

Change management in AI education carries both positive and negative implications. **Positively**, structured frameworks give institutions a path from reactive crisis management to proactive, participatory governance; Delphi consensus and anticipatory governance both support treating AI Literacy and Ethics as cross-cutting institutional capabilities rather than isolated rules. **Negatively**, fragmented adoption widens existing gaps: the UNESCO framework analysis of 30 leading universities finds core ethical and AI Governance principles widely embraced but inclusion, equity, and Sustainability (internet access, gender parity, environmental impact) often overlooked — and national AI-preparedness rankings do not predict robust institutional policy. The LEAGUE framework extends this concern to Learning Analytics, arguing that governance must move beyond compliance (FERPA/GDPR) toward lawfulness, equity, Learner Agency, utility, and ethics by design, reviewing student-data practices transparently and educationally.

In institutions where strategy runs ahead of infrastructure the work compounds: academic developers at two South African Historically Disadvantaged Institutions called AI strategy “performance more than practice,” and the paper insists digital inequality - a distributive problem - be kept separate from algorithmic coloniality, an epistemic problem that survives full access (Sithole, 2026).

For administrators and policymakers, the evidence argues for participatory governance, infrastructure investment, and capacity-building over aspirational strategy documents, translating national policy into concrete instructor support rather than issuing top-down mandates. **For instructors**, change management means moving from adopter to inquiry-driven experimenter, engaging students as partners, and anchoring reform in durable pedagogical principles rather than tools that may be obsolete within months — with the caveat that professional development must target a full design cycle (needs assessment, feedback) rather than tool use alone, as the DOT framework survey demonstrates.

An institutional case study traces a decade-long diffusion arc in undergraduate mathematics, moving from individual initiative and peer workshops to joint faculty licensing and central funding (Law, 2026).

Course redesign carries a cost institutions should budget, not assume: adopting an AI-integrated course ran to roughly 15 to 20 hours of redesign work per course before any ongoing adjustment Packard et al. (2026). - **Engagement is explained by capacity and disposition, not enthusiasm.** A framework for assessment practice argues that uneven GenAI adoption reflects four conditions — capacity, disposition, and the supports and constraints around them — rather than resistance, and that a single workshop builds vocabulary but not judgment (Miller, 2026). Naming the missing condition tells an institution whether to train, resource, or change the incentive.

Connections to other concepts

Change management is the institutional complement to classroom-level integration. It operationalizes the systemic conditions — governance, faculty development, stakeholder engagement, and equity safeguards — that allow pedagogical innovation to take hold, connecting Educational AI Policy policy design to AI Governance, Educational Development, and Equity outcomes.

Common Misconceptions

- **“Strategic intent creates capacity.”** Only **7% of institutions** have created senior AI leadership roles despite **49% viewing AI as a strategic priority**. The gap is between declaration and structure, and it is the recurring failure of AI change management.
- **“Adopting an AI tool is an event.” Sustainability is a property of the organization, not the tool** — the CSUN text-messaging trial illustrates the timescale. The evaluation ran four years because durability is what needed testing.
- **“Institutions need to react faster, not anticipate.” Anticipatory leadership** is the complementary thread: the scoping review finds institutions must shift from **reactive to foresight**-based governance. Reacting competently to a technology that has already arrived is what the evidence documents failing.

Connected Concepts

- AI Governance — the policy and oversight structures change management operationalizes
- Educational AI Policy — national and institutional AI policy intent that change management must translate into practice
- Educational Development — building faculty capacity and pedagogical orientation for AI integration
- Administrators — leadership and anticipatory governance as change agents
- AI Literacy — cross-cutting capability underpinning responsible institutional adoption
- Equity — ensuring change benefits accrue evenly across institutions and learners
- Technology Adoption Models — adoption drivers that explain how change spreads
- Academic Integrity — central regulatory anchor around which assessment reform is organized
- Student Support and Success — sustaining a support program past the pilot

Connected Articles

- Sustaining AI-enabled student support: A four-year implementation and impact study — Sustaining AI-enabled student support: four-year implementation and impact study of an institutional chatbot (Mata, Russell & Page 2026)
- A framework for institutional change in the age of AI — six-dimension framework for adapting institutional change models to AI as an arrival technology
- Leveraging complex systems: Leading for transformative change — SPARK framework and complexity leadership for transformative change
- Governing generative AI in higher education: a global Delphi study on policy and practice — global Delphi consensus on eight-area GenAI governance
- Anticipatory governance and leadership for AI implementation in higher education: A scoping review — scoping review of anticipatory governance and leadership

- The AI adaptation gap in higher education: Students, faculty, and administrative staff — stakeholder gaps in AI use, attitudes, and trust across students, faculty, and staff
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — national policy intent vs. institutional capacity in UK higher education
- Exploring Organisational Drivers and Innovation Attributes of Artificial Intelligence Adoption in Higher Education — organizational and technological drivers of AI adoption
- Generative Artificial Intelligence Policy: A Qualitative UNESCO Framework Analysis — UNESCO framework analysis of institutional GenAI policies
- AI for education: The digital transformation of a liberal arts institution – implementation at Lingnan University — Digital transformation of a liberal arts university toward a research-intensive model in the GenAI era (Qin 2026)
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Digital mediators translating institutional AI strategy into grounded practice under infrastructural scarcity
- AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI — AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI
- AI in Action Learning Tour — cross-system fieldwork on how implementation and teacher actions decide whether an AI product helps
- Practitioner beliefs and behaviors in AI-enhanced education: DOT framework survey evidence — survey evidence that professional development must cover a full design cycle rather than tool use alone
- From flipped classroom to AI-enhanced assessment: Sustained pedagogical innovations in undergraduate mathematics education — A decade-long diffusion arc from individual initiative to central funding in undergraduate mathematics (Law 2026)
- Teaching with AI, Not Against It: A Thinking Partner Framework for Working Adult Learners in Compressed Online Formats — Budget 15 to 20 hours of redesign per AI-integrated course before ongoing adjustment

Connected FAQs

- How Do We Write and Implement an Institutional AI Policy?
- How Do I Design Faculty Development for AI That Actually Changes Practice?

AI Regulation in Education

> **AI regulation** — the laws, policies, and governance frameworks that control how AI is developed and deployed in educational settings. Regulation in the knowledge base spans government policy, institutional governance, and industry self-regulation.

Questions to Consider

- AI tools are deployed in classrooms far faster than rules can be written. Before you read, who do you think is actually setting the effective rules right now — lawmakers, institutions, developers, or teachers improvising on the spot?
- The page distinguishes regulation (binding laws and rules) from governance (the broader norms and structures). Why does this distinction matter? What does an institution with strong governance but weak regulation look like, and is that a stable situation?
- Regulation 'both constrains and enables' — it sets boundaries while creating conditions for equitable, safe integration. Can you think of a rule that would simultaneously limit misuse and expand responsible use, or is the tension unavoidable?
- Ethics frameworks increasingly harden into binding rules, and safety requirements act as de facto regulation. Do you see ethical principles becoming enforceable rules as progress, or as a way to appear accountable without real teeth — and how would you tell the difference?
- The knowledge base documents a persistent 'governance gap' between deployment speed and regulatory maturity, uneven across jurisdictions and educational levels. As a teacher or developer, how does an inconsistent regulatory environment affect your day-to-day decisions about what AI to use?
- Student regulatory awareness research asks whether Learners actually know and follow the rules. Before you read, how well do you think most students understand the AI rules they're bound by — and whose responsibility is it when they don't?

Introduction

Regulation is the legal and policy layer of AI AI Governance: it sets the binding rules, standards, and enforcement mechanisms that institutional governance translates into practice. Where governance is the broad framework of norms and structures, regulation provides the authoritative rules — from national AI laws and data-protection statutes to institutional acceptable-use policies and professional guidelines. A recurring theme in the knowledge base's research is that regulation lags behind AI deployment, leaving institutions to improvise governance in the gap.

Regulatory landscape

- **Government policy:** Educational AI Policy research examines national and regional AI education policies. and lifelong learning policy address regulatory gaps, while UK AI higher-education

policy and the OECD Digital Education Outlook situate national approaches in comparative and international perspective.

- **Institutional governance:** AI governance frameworks and institutional policy analysis document how universities develop internal AI rules, while AI declaration frameworks and assessment governance regulate AI use in assessed work. Qian (2026) finds the sector's internal rules are mostly guidance rather than binding policy — 44 of 50 innovative US universities published guidelines, principles or resource hubs while only 6 framed their principal page as a "policy" — with instructor-set syllabus rules doing the operative regulatory work in individual courses. Watson and Rainie's (2026) survey of 1,057 US faculty measures how far below the institutional layer the effective rules sit: 87% of respondents wrote their own assignment-level policies while only 48% reported written institutional guidelines and 35% departmental ones, against a structural response that is thin at the top — a task force or oversight group in 55% of cases but AI literacy adopted as a general education outcome in only 13%.
- **Safety regulation:** Pedagogical Safety, child safety, and K-12 safety frameworks represent de facto regulation through safety requirements. Humble (2026) shows why assessment tooling belongs in that category too: in a red-team test, two of five indirect prompt injections hidden in a submission file raised a failing grade without any warning to the marker — reported success rates of 100% and 94% — and the paper's sector-level asks are clear AI policy, professional development, and standardized, domain-agnostic assessments of prompt injection resilience so that the attack surface is measured rather than assumed.
- **Ethics as regulation:** Ethics frameworks increasingly serve regulatory functions — public discourse on AI ethics shapes policy expectations, and ethical governance of student data shows how ethics principles harden into binding rules.
- **Equalities and reasonable-adjustment law:** Over-inclusive AI rules can collide with statutory duties. Wright (2026) argues that prohibitions barring "generative AI" without distinguishing content generation from format conversion capture AI transcription tools and may engage the reasonable-adjustment duty under the UK Equality Act 2010, the US Americans with Disabilities Act and the Australian Disability Discrimination Act 1992 — making the drafting of a prohibition a regulatory question, not only an academic-integrity one (see legal issues and risks). Li (2026) extends the same collision to language background: assessment rules that do not separate legitimate language support from substantive substitution impose cohort-skewed compliance burdens on students using English as an additional language, and the framework designed to correct this is defended through indirect-discrimination reasoning plus the administrative-law expectation that a decision-maker can state the rule applied, the evidence relied on and why the outcome was proportionate — the standard a challenge on review applies to an administrative decision.
- **Compliance and accountability:** student regulatory awareness examines whether learners actually know and follow AI rules, and technology-adoption frameworks explore how regulatory and ethical concerns influence adoption decisions.

The governance gap

The knowledge base documents a persistent gap between AI deployment speed and regulatory maturity. Institutional change frameworks and regulation research argue for proactive AI Governance rather than reactive policy. Studies of and comprehensive AIED reviews highlight that regulation is uneven across jurisdictions and educational levels, creating an inconsistent operating environment for teachers, students, and developers.

Agentic systems open a further gap. In a documentary analysis of 12 universities, Wong and Sun (2026) found no comparator addressed an agent logging into a learning-management system, holding student credentials, or acting on the student's behalf, while several agentic-aware cases set explicit delegation and access boundaries.

The gap is one of evidence as well as timing. Gutowski and Hurley (2025) characterize one professional sector as making policy under time pressure without an evidence base to make it with: most ABA-approved US law schools took generally prohibitive positions while reserving discretion to individual instructors, and the authors report no consensus on disclosure or citation practice and only a ~15% response rate to the ABA's 2024 policy survey. Their normative response — clear guidelines whatever the stance, stakeholder involvement in drafting, and governance designed to be flexible and reviewed periodically — matches the global Delphi consensus, which likewise treats policy maintenance as a recurring institutional mechanism rather than a one-time task. Coates, Croucher and Calderon (2025) add the reverse dependency: their governance reform program concludes that institutional development is unlikely to pay out without external affordance from regulation, benchmarking and cross-institutional competition, making the quality and regulatory agencies — and the comparison they force between institutions — the condition under which internal governance reform takes hold.

An audit of EdTech platform privacy policies gives that dependency a concrete instance. Across 48 platforms, data collection was disclosed comparatively well (mean 1.81 of 2) while AI disclosure (0.90) and accountability (1.07) lagged, and 33% made no meaningful AI disclosure despite visible AI features. US K-12 platforms scored highest overall (M = 7.47 against 5.50 for US higher education) yet gained nothing on AI disclosure or accountability. Regulation, the authors conclude, raises only what it names, so enforceable rules and procurement standards rather than voluntary commitments must make Privacy a condition of deployment (Nair & Greenstadt, 2026).

Connections

Regulation connects to Educational AI Policy, AI Governance, Ethics, Privacy, Pedagogical Safety, and Academic Integrity. It is the institutional layer that shapes how all other AI education practices operate. Regulation both constrains and enables: it sets the boundaries of acceptable AI use while creating the conditions — through AI Literacy and responsible-use expectations — for equitable, safe integration.

Common Misconceptions

- **"Institutional AI policy is where the rules live."** Watson and Rainie's (2026) survey of **1,057 US faculty** measures how far below the institutional layer the effective rules sit: **87% of respondents**

wrote their own guidance. The operative policy is largely faculty-authored, which means the documented institutional layer describes less than it appears to.

- **"Writing a policy covers the risky surface."** Humble (2026) shows why assessment tooling belongs in the regulated set: in a red-team test, **two of five indirect prompt injections** hidden in a submission succeeded. A rule that names tools but not injection surfaces leaves the exploit unaddressed.
- **"Agentic systems are covered by extending existing rules."** In a documentary analysis of **12 universities**, Wong and Sun (2026) found **no comparator addressed an agent logging into a learning-management system**. The governance gap is structural: existing categories have no slot for an autonomous actor with credentials.

Connected Concepts

- Educational AI Policy
- AI Governance
- Ethics
- Privacy
- Pedagogical Safety
- Academic Integrity
- Equity
- Higher Education
- K-12
- AI Literacy
- Trust Calibration
- Legal Issues and Risks — legal exposure when regulation and governance are unclear or over-broad

Connected Articles

- A framework for institutional change in the age of AI
- A Comparative Analysis of Institutional and Course Generative AI Policies within Higher Education: Implications for Instruction in Computing Education
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy
- A Longitudinal Analysis of Public Discourse on AI Ethics in Education Using Twitter Data
- Artificial Intelligence in UK Higher Educational Policy and Institutional Decision Making — AI in UK higher-education policy
- OECD Digital Education Outlook 2026: Exploring Effective Uses of Generative AI in Education — OECD Digital Education Outlook 2026
- Structuring Transparency: Developing Domain-Specific Generative AI Declaration Frameworks in Higher Education — AI declaration frameworks

- Generative AI as a design variable: An evidence-centered framework for principled governance in STEM assessment — Assessment governance under GenAI
- Beyond Compliance: A Proposed Framework for Ethical Governance of Student Data in Learning Analytics — Ethical governance of student data
- Knowing the Rules Is Not Enough: Student Regulatory Awareness and Use of GenAI in Higher Education — Student regulatory awareness of GenAI
- Practitioner beliefs and behaviors in AI-enhanced education: DOT framework survey evidence — Technology-adoption frameworks
- Review of Artificial Intelligence in Education from 2020 to 2025 — Comprehensive review of AIED research
- Governing generative AI in higher education: Emerging policy approaches and support ecosystems at innovative U.S. universities — Guidance over binding policy: internal AI rules across 50 innovative US universities (Qian 2026)
- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — Law school GenAI policy scored on five dimensions: prohibitive by default, instructor discretion, periodic review (Gutowski & Hurley 2025)
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI prohibitions and the reasonable-adjustment duties they may engage (Wright 2026)
- GenAI assessment and language equity: Drawing the line between support and substitution — Language background in assessment rules: the support–substitution boundary as an equalities question (Li 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt-injection attacks on AI graders and the case for standardized resilience testing (Humble 2026)
- Governing academic integrity: Ensuring the authenticity of higher thinking in the era of generative artificial intelligence — External regulatory pressure as the condition for governance reform (Coates, Croucher & Calderon 2025)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — 87% of faculty write their own rules against a thin institutional policy layer (Watson & Rainie 2026)
- "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech
- Delegation Is Not Assistance: Agentic AI and Assessment Governance in Higher Education — A Comparative Documentary Analysis of 12 Universities — No comparator policy addressed an AI agent logging into an LMS or holding student credentials (Wong & Sun 2026)

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Write and Implement an Institutional AI Policy?

Equity, ethics, and responsible use

Equity and access

Equity

> **Equity** — the principle that AI should serve all learners fairly, and the study of systemic disparities in access to, representation within, and benefits from AI educational tools. Equity research in the knowledge base examines access gaps and the digital divide, bias and fairness in AI systems, culturally responsive and linguistically inclusive design, accessibility for learners with disabilities, and the distribution of AI's benefits and harms across groups. It connects the technical (bias mitigation, fair algorithms) with the structural (infrastructure, policy) and the pedagogical (culturally relevant teaching).

Questions to Consider

- Providing AI tools to a school or classroom does not automatically close achievement gaps — in fact, access alone can widen them. If 'access is not enough,' what else has to be in place for AI to actually serve all learners fairly?
- Even the data used to *simulate* learners carries bias: when LLMs generated student vignettes, different models produced more Global North or Global South profiles and gendered pronouns. How much should we trust AI-generated representations of learners when the models themselves encode uneven priors?
- Equity in AI education is often framed around three concerns: who gets the tools (access), who is represented in them (representation), and who benefits (outcomes). Can you think of a situation where a group gets access but still doesn't benefit? What explains the gap?
- Research on 'structural silence' argues that speakers of underrepresented languages are disadvantaged by AI infrastructure — training corpora, tokenization, benchmarks — *before any model is even trained*. If the disadvantage is baked into the infrastructure, where does fixing it start?

Introduction

Equity in AI education addresses three overlapping concerns: who *gets* AI tools (access), who and what is *represented* in AI systems (representation), and who *benefits* (outcomes). AI can both widen and narrow existing disparities depending on design, infrastructure, and policy. Equity is therefore a cross-cutting lens applied to algorithmic fairness, digital access, linguistic inclusion, Accessibility, and culturally relevant teaching.

Access and infrastructure equity

- **The digital divide:** Unequal access to AI-powered learning tools across socioeconomic lines, regions, and nations is a foundational barrier. Evidence documents how generative AI benefits are distributed unevenly across countries and institutions.

- **Tool quality is part of the divide, not just tool access:** Canonigo (2026) submitted 50 mathematics prompts three times each to the free and premium tiers of the same model and found the free tier inaccurate in 49 of its 150 responses (**32.7%**) against 18 of 150 (**12%**) for the premium tier ($\chi 2(1) = 17.5$, $p < 0.001$); teachers at the under-resourced of the two study schools called the free model "borderline useless for mathematics." The authors read this as an algorithmic divide that extends the Digital Divide beyond device access to the quality of the tool itself, so a school with "AI access" may still be handing students a materially less reliable tutor, with their own caveat that the comparison was exploratory and the prompts were not randomized, making the size of the gap indicative rather than settled. The same study shows the direction the gap takes is not fixed by the tool: where teachers required students to compare AI output with their own work and pre-prompted the model to withhold solutions, the output became an artifact for critique, while unmediated classes saw students consult the algorithm first and the teacher become a validator ("I'm no longer the oracle; I'm the editor").
- **Access is not enough:** Providing AI tools without addressing structural barriers does not close gaps — access must be paired with skills, support, and conditions that enable genuine use.

Differentiated support is not evidence of equitable benefit: a review of AI tutoring in mathematics finds inclusiveness claims unsupported because studies rarely test whether gains are distributed consistently across ability, gender, socioeconomic, linguistic, disability and geographical groups, leaving it unestablished that these systems reduce achievement gaps (Ogunsakin et al. (2026)). - **Differentiated human-AI tutoring is evidence that hybrid models can narrow gaps — when allocation follows need.** A difference-in-discontinuities study (635 students, grades 5–8; below-median performers received *proactive* human tutoring, above-median received *reactive* on-demand support, against a fall AI-only baseline) found hybrid tutoring raised time on task 25%, skill proficiency 36%, and academic growth 61% overall — and the two arms achieved *comparable* engagement and proficiency gains through different mechanisms. The equity-relevant detail: proactive tutoring showed marginally higher average growth (75%, $p = .065$) concentrated among students farther below the cutoff — the pattern of gap compression rather than uniform lifting — while one tutor per session served both groups. The authors are appropriately cautious: the DiDC design is quasi-experimental, the dichotomous median cutoff misses within-group need variation, and the 75% effect is marginal. (Improving hybrid human-AI tutoring by differentiating human tutor roles based on student needs)

- **Faculty expect the divide to widen.** Watson and Rainie (2026) surveyed **1,057 US college and university faculty** and found **81%** expected generative AI to widen digital inequities (**58%** saying a lot) — the strongest equity expectation in the report and one that sits beside **68%** who said their institutions had not prepared faculty to use the tools for teaching and mentoring. The same survey shows how unevenly the tools are taken up: **26%** of respondents do not use generative AI at all, rising to **40%** of arts and humanities faculty and **28%** of social scientists, so non-use and unpreparedness concentrate in particular disciplines. The report is a non-probability sample its authors state is not generalizable, so these are the sector's expressed concerns rather than measured effects.
- **Infrastructure disadvantage:** Structural Silence shows that AI *infrastructure* — training corpora, tokenization, benchmarks, deployment architectures — systematically disadvantages speakers of

underrepresented languages *before a model is trained*, reframing dataset scarcity as a structural rather than incidental problem.

- **Model-specific demographic priors in synthetic data:** López-Pernas et al. (2026) found that when LLMs generated student vignettes, each model imposed distinct demographic tendencies — GPT produced more Global North profiles and used they/them pronouns, Qwen produced more Global South profiles, and Mistral skewed toward she/her. Even the *construction* of learner data by an Large Language Models (LLMs) thus carries regional and gendered priors that can propagate into downstream recommendations, an under-examined equity risk.
- **Socioeconomic gradients:** AI and lifelong-learning policy and productivity-gap experiments examine how AI can either narrow or widen gaps among different learner groups.
- **Bridging divides for disabled learners:** Khlaif et al. (2026) found that GenAI levels the playing field for visually impaired undergraduates across digital, geographic, and socioeconomic divides, framing inclusion as both an infrastructural and a cultural matter — extending digital equity discourse beyond access to belonging, voice, and representation.

Preparation matters more than preference, and the right to refuse is unevenly distributed. Students with strong academic confidence can refuse AI without penalty, while students who need language support, accessibility support or rapid feedback experience refusal as a loss of opportunity, and casual staff may feel pressure to adopt tools that cut preparation time without cutting responsibility. Where a duty to understand is imposed without training, secure infrastructure and clear policy, it becomes hidden workload, and refusal turns into a predictable response to institutional under-preparation rather than resistance to the technology (Zagami 2026).

Rent is paid in three currencies, and owned competence goes with the graduate. de Barba (2026) argues that capability residing in a commercial tool is available only on the provider's terms, so institutional licenses relocate the landlord rather than remove it: access typically ends with enrollment, and rented capability then persists only for graduates who can keep paying. She adds two further distributions that access debates usually miss — self costs concentrate in acclimation, where learners with less prior domain knowledge spend longest, and rented standards carry the model's reference points, predicted to displace more of the standards of learners whose cultural and linguistic reference points differ from the model's. The same tool widens access and displaces standards at once, which is why she treats naming the capabilities a course must build itself as an equity measure as well as a pedagogical one.

Representational equity

- **Bias in training data and outputs:** AI training data largely reflects dominant cultural perspectives. Gender bias transfer research shows LLM-assisted writing can contaminate student work with gender bias; history-education filters and AI scoring can encode Western-centric and linguistically biased assumptions.
- **Marginalized knowledges:** Research on minoritized knowledges examines how generative AI marginalizes non-dominant knowledge systems and disability perspectives in higher education.
- **Curriculum diversification:** Teachers increasingly use LLMs to diversify curriculum materials (Wang et al., 2025, found 78% did so), yet AI-curated reading lists still underrepresent BIPOC authors, and STEM AI tutors default to Western-centric problem contexts.

- **Generated imagery repeats dominant visual norms, which makes critical use a competency rather than an add-on.** Jiang et al. (2026) observe that GenAI image generation reproduces dominant multimodal norms such as visual bias, and warn that multimodal assessment which ignores this risks automating and reproducing inequalities; their framework for second language teachers therefore requires the competence to help students detect, evaluate and counter-narrate biased model outputs (Jiang et al., 2026).
- **Representation applies to the evidence, not only the learners.** Bulut (2026) argues that equity in technology-supported assessment covers the contextual transferability of the knowledge underpinning a design, so a system validated in well-resourced settings carries untested assumptions elsewhere.

Outcome equity

In a scoping review of 394 GenAI higher-education studies, equity and access were among the outcomes targeted least, alongside Metacognition, ethics and Creativity (Lin et al. (2026)).

- **Differentiated impact:** AI tools may widen gaps if designed without an equity lens — systematic reviews and scoring-bias studies show uneven benefits and harms across learner groups. The pooled evidence of benefit carries the same boundary: Jing et al. (2026) estimate a moderate-to-large overall gain for undergraduates across 35 studies (g=0.53, 95% CI [0.48, 0.64]) while stating that inequitable access to high-cost tools is one of the risks those effect sizes cannot capture, and significant Egger's tests for academic performance and professional skills leave funnel-plot asymmetry and small-study effects unresolved.
- **Equivalent learning across two orders of magnitude of cost.** StudentBench found pooled AI tutoring statistically equivalent to expert human tutoring while the spread across tutors ran from $0.005 to $1.40 per percentage point of learning gain and one open model matched human gains at 918× lower cost per point ($0.0052 versus $4.81), making cost per unit of learning an access variable rather than only a quality one (Northcutt et al. (2026)).
- **Bias amplification:** AI suggestions and automated feedback can reinforce (not challenge) existing teacher and systemic biases. Marked Pedagogies shows LLM writing-feedback tools systematically shift toward stereotype-aligned praise and withheld critique when feedback is personalized with a student's race, language, disability, achievement, or motivation — even on identical essays — making "personalization" a concrete bias vector in automated feedback.
- **Fairness-aware systems:** Bias Mitigation and ground-truth reliability research develop methods for detecting and correcting bias in AI tutors, scorers, and recommenders.
- **Fairness regularizers may not generalize to new learners:** Fragkiadakis et al. (2026) added gender- and age-targeted error-gap regularization to a Multimodal AI transformer predicting real-time student attention, and found it narrowed demographic disparities on *validation* data but these gains did not consistently transfer to held-out subjects or repeated subject-level splits (the regularized model reduced the gap in only 4 of 10 training runs). Certified fairness on a single split can therefore evaporate on genuinely new learners — educational AI needs leave-subjects-out, repeated-seed evaluation rather than aggregate metrics alone.

- **Differentially distributed next-opportunity decisions.** Bias that looks defensible case by case can still sort learners systematically: Entezami et al. (2026) had three LLMs place 11,200 team assignments in software-engineering classes, where men were at least 80% less likely than women to reach Interface Design rather than Core Development (GPT-5.2 OR < 0.01) and nationality moved assignments independently of merit. Skills did not settle it - 99.2% of skill-based assignments matched one of the two valid teams, yet gender still chose between equally valid options, so only aggregated statistics reveal the pattern; single-person course imagery skewed male and light-skinned (over 95% light-skinned for Database, Debugging and Individual Programming prompts) while multi-person images were comparatively diverse.
- **Student agency:** ensuring AI empowers rather than replaces student voice and Learner Agency, especially for historically marginalized learners.
- **Psychological vs. cognitive equity:** Liang et al. (2026) found a year of school AI instruction in Hong Kong secondary schools **narrowed psychological AI-readiness gaps (confidence, Motivation, ethical awareness) but not cognitive ones** — objective AI Literacy gaps between self-initiated ("high-agency") learners and their peers persisted, a Matthew-effect pattern where curricula "raised the floor but did not level the playing field." Access to a curriculum alone, without sustained self-initiated engagement, may foster psychological but not full cognitive parity.
- **Automated marking, attainment and language.** The OpRaise comparison of three frontier models on 761 authentic essays found that AI–human disagreement varied with students' attainment level and with surface language features (vocabulary range, connectives, sentence complexity) in ways human marking did not, and that accuracy differed across three UK institutions whose cohorts differ — the authors connect this directly to institutions' duties under the UK Equality Act, on the reasoning that some student groups may be affected more than others, and note a right to explanation under GDPR Article 22 where automated marking decisions affect students. Because AI marks compressed toward the middle of the distribution, the students most exposed are those at the top and bottom of the attainment range.
- **Assessment rules can convert linguistic disadvantage into integrity risk.** Li (2026) argues that integrity rules treating GenAI as a single category of unauthorized assistance impose higher compliance burdens on students who use English as an additional language, whose legitimate use of language support is more frequent and iterative, and concentrate suspicion on writers whose surface fluency has shifted most — a rule-design rather than a behavior problem, and one that raises the risk of selective enforcement on weak evidence. The proposed boundary is purpose- and construct-based instead of tool-based: grammar, punctuation and sentence-level clarity edits, translation for comprehension, and first-pass drafting that the student substantively rewrites count as permitted support because they add no new ideas, no new sources, and no material re-ordering of the analysis, whereas generating arguments or counter-arguments, applying disciplinary rules to facts, restructuring the analytical sequence, or generating citations count as substitution. Because construct statements often reward fluency and idiom as proxies for reasoning, EAL students meet construct-irrelevant variance in their scores; the remedies are ex ante specificity about permitted and prohibited functions, disclosure calibrated so that routine support costs less to declare than a bibliographic entry, staged submissions and source trails rather than detection-led inference, and

cohort-level monitoring of referrals and sanctions. The framework is normative and untested — Li makes no claim about rates of GenAI use by EAL students.

- **Students themselves judge the support-substitution line accurately, but hesitantly.** Reed et al. (2026) put six ethical vignettes to 531 undergraduates and found 57.6% classified all six correctly (mean 88.54%): verification-supported uses were widely accepted — summarizing notes with professor verification (91.7%), grammar improvement on a self-written paper (84.9%), AI-generated search terms followed by an independent literature review (91.1%) — while substitutionary uses were overwhelmingly rejected. Uncertainty clustered on the cases a rule must actually resolve, the unverifiable AI-generated references (9.9% "unsure") and minimally edited AI-generated text (9.6%), which the authors read as evidence that the boundary between assistance and meaningful authorship is not clear to students. Objective AI Literacy predicted classification accuracy only weakly (Spearman's $\rho = 0.234$), the sample was predominantly White, female and first-year at one public Midwestern university, and the authors stress that correct judgment is not ethical conduct.
- **Prompt privilege:** Jin et al. document "prompt privilege" — users who phrase requests skillfully systematically obtain better LLM output than users expressing the same intent less adroitly — making prompting skill a silently uneven resource. Their Prompt Equity Transformer shifts prompt optimization into the system, treating equitable output as an accessibility property rather than demanding expert prompting from novices.
- **Competence, not access, is where the gap reopens.** Among 380 undergraduates, family digital capital related to perceived academic gains largely through prompt engineering competence, which correlated .793 with those gains (Li et al. (2026)).
- **The interaction-management gap.** Brunnström and Palmqvist (2026) reach an ambivalent conclusion about GenAI as a leveller: because productive use requires recognizing an over-abstract answer, requesting simplification, and structuring a session around small goals, unguided GenAI "may be most beneficial to already advantaged students" — those with strong study habits and confidence in directing an AI — while students with weaker study skills or lower academic Self-Efficacy meet added complexity and frustration. Rather than substituting for missing academic conversation partners, the tool introduces a new competence whose acquisition creates its own gap; the authors conclude the responsibility for teaching it cannot rest with the student alone (AI Literacy, Self-Regulated Learning).
- **Skill-gap and resource-gap mechanisms are not the same problem.** Kumar, Wongsirichot and Nanthaamornphong (2026) separate two mechanisms their systematic review of 72 computing-education studies found the literature tends to conflate. The **skill gap** operates within a single classroom: students with stronger prior knowledge convert AI assistance into durable skill while struggling students use it as a crutch that removes productive struggle, widening the competence distribution by semester's end — addressed by graduated access tied to demonstrated competence. The **resource gap** operates across institutions and national contexts: reliable internet and paid API subscriptions sustain more capable tool use than students without them — addressed by institutional investment in shared tool access and policies that do not assume universal availability. Equity is the thinnest of the review's three framework requirements (six studies), and

the authors read that thinness as the finding: the absence of equity-focused intervention research is itself the equity problem (Assessment Validity, Scaffolding).

- **The best-evidenced methods are the least scalable ones.** In a workshop with 73 computing educators, oral and interactive assessment was reported as the strongest available evidence of individual understanding and the least scalable remedy proposed — raised in one room alongside 400-plus students and a handful of teaching assistants — so the strategies with the clearest link to verified learning sit in the institutions teaching the fewest students, an equity gap between institutions rather than within a cohort (Akbar et al., 2026).
- **Tutoring quality shifts with learner demographics.** EduFair-Bench pairs a fixed LLM student with each tutor across nine demographic levels spanning gender, immigration background, first language and socioeconomic status, and scores five turn-level pedagogical metrics. In LLM tutoring the largest deviations appear in explicit demographic conditions — step scaffolding correlating up to $|r| = 0.144$ in mathematics and corrective tone exceeding 0.10 for every model in chemistry (0.102-0.168) and physics (0.129-0.294) — and in 11 of 15 model-by-domain cells the wrong-answer condition scored higher than the correct one, indicating that tone tracked the student's demographic label rather than the quality of the student's reasoning. Pedagogy-specific reinforcement learning redistributed rather than removed these gaps. (EduFair-Bench: Evaluating Pedagogical Fairness of LLM Tutors Across Student Demographics)
- **Implicit demographic signals are a less controllable bias channel than stated attributes.** Rooein, Benedetto and Hovy (2026) held each task input fixed while varying only the demographic context across six instruction-tuned LLMs and three educational tasks, producing 192,480 inference calls, and separated *explicit* signals (stated student attributes) from *implicit* ones carried by a ten-prompt conversation history. In automated essay scoring most models were comparatively stable under explicit conditioning, while implicit conditioning inflated scores — Llama-70B scored 1.57 points above its own default ($p < 0.001$). In metalinguistic question answering the implicit condition drifted the other way: responses for lower education levels received less positive sentiment, a 0.3 average gap between the lowest and the higher education levels on a 0-4 scale against a within-item standard deviation of 0.07. The equity difficulty is structural — the cue is not a stated attribute that a policy can forbid or a prompt field that an audit can inspect, but a property of the interaction itself.
- **Verification can redirect a gain to weaker students.** Dang & Nguyen (2026) found expert-verified AI study materials in a first-year economics course were associated with a 2.34-mark gain, but roughly three-quarters arose in the bottom quintile, and the share of marks below the 60% boundary fell by 24.7 points - moving the checking burden from students to an accountable tutor.

Linguistic, cultural, and disability inclusion

- **Language:** Most AI tools prioritize English, marginalizing multilingual learners. Linguistic diversity in academic writing, underrepresented languages, and Language Learning research address this.

- **Detection fires hardest on multilingual writers.** Because detectors classify on textual predictability rather than provenance, the low perplexity and formulaic density they flag are also features of additional-language writing; documented studies found GPT detectors misclassifying a large share of authentic TOEFL essays by non-native English speakers — a differential-effects risk before it is a technical one (Angelier (2026)).
- **The mechanism is linguistic polish, not authorship.** Editing one non-native-authored manuscript moved detector verdicts both ways — MAGE 10.7 percentage points less likely to flag text as AI, LastDE+ 5.8 points more likely — and the shift grew with how heavily the editor revised it (Park, Jeong and Kim (2026)). Because authorship is unchanged, what those tools read is refinement, not machine involvement.
- **Recognition, not just access: AI's cultural flatness as an equity finding:** In a 9-month narrative inquiry with five secondary-school apprentices of color, Gyekye (2026) found students equated fairness with the *absence* of visible bias — a "cultural flatness" in which identity-specific experiences and cultural markers go unrepresented in AI responses — and constructed agency through refusal (non-use as institutional alignment) and negotiation (making AI outputs institutionally legible). The study's Recognition Bandwidth concept names the room learners have to see themselves in AI outputs, and Institutional AI Literacy the capacity to navigate AI within institutional expectations. A five-student single-program qualitative study; its equity contribution is showing that neutrality-as-fairness can itself be the exclusion mechanism.
- **Who benefits from an AI tutor — exploratory field evidence:** In a full-district rollout of a teacher-mediated AI math platform, Goblins (Alam et al. 2026) found larger achievement associations for students with IEPs (+0.122 SD), English learners (+0.191 SD), and Hispanic students (+0.084 SD) than for comparison groups, consistent with its multimodal input and seven-language voice support lowering engagement barriers. The authors are explicit that the exploratory, underpowered subgroups cannot establish that the accessibility features caused the differential — an early, hypothesis-generating signal rather than an equity finding.
- **Culture:** Culturally relevant pedagogy and community-centered AIED call for AI that reflects learners' cultural contexts rather than imposing dominant norms.
- **Disability and neurodiversity:** Accessible learning, universal design, Neurodiversity, and special education research examines how AI can support or exclude learners with disabilities — neurodivergent computing students, dyslexic learners, and accessible educational materials are illustrative.
- **Language, culture, and cost together:** Bashir and Afzal (2026) frame equitable design in Well-Being AI as a single question of language, culture, and cost — English-only tools fail students who express distress in Urdu or Roman Urdu, Western datasets fail to capture locally salient stressors, and expensive commercial systems fail less well-equipped universities (Sukoon). Their response combined an Open Source multilingual LLM accessed through a hosted API for low resource requirements, a bilingual assessment interface, and a classifier trained on a validated 20-feature instrument — while acknowledging that the training data is not representative of the target population, that "some areas… tools are available but often expensive," and that the adaptation is prompt-level rather than validated with students, a candid account of the gap between equitable intent and demonstrated equity.

Special populations and global equity

- **Special populations:** Special Education, neurodivergent learners, dyslexic learners, and learners with disabilities represent groups whose needs are often overlooked in AI system design.
- **Global South perspectives:** African student motivations, Vietnamese AI lesson planning, and Ghanaian teacher acceptance provide Global South perspectives often absent from Western-centric AIED research. At the institutional level, Adeniranye et al. (2026) show AI integration across 45 Nigerian universities is driven by institution age and geography rather than governance type, with reinforcing network ties letting well-connected institutions compound advantage — evidence that equity gaps are reproduced structurally, not just through individual access.
- **Global capacity:** Evidence documents how generative AI benefits are distributed unevenly across countries and institutions, and AI and lifelong-learning policy addresses structural socioeconomic gradients.
- A PRISMA review of 72 higher-education assessment studies found the evidence base geographically concentrated: Australia and the United Kingdom supplied 31 of the 72 studies between them, and no study was identified from South America (Crompton and Burke (2026)).
- **Disability and Global South intersection:** Khlaif et al. (2026) — a qualitative case study of 21 visually impaired undergraduates across three Palestinian universities — shows GenAI bridging digital, geographic, and socioeconomic divides while extending technology acceptance models to disability contexts, where usability, affordability, and accessibility are mutually reinforcing.
- **Gender equity in computing:** equity-oriented uses of GenAI remain underexplored. An all-girls GenAI makerspace initiative in Europe combined two GenAI tools with feminist pedagogy to address persistent gender inequities in girls' representation in computing, with practitioners enacting specific steps to support girls' participation and engagement — an example of equity-focused GenAI design. Deliberately gendered AI can also function as the *intervention itself*: Rücker and Becker-Genschow (2026) showed that a female-coded, domain-specific math chatbot modeled on Ada Lovelace's persona (and deployed as both a role model and a learning assistant) significantly reduced gender-stereotypical beliefs about mathematical ability and mathematics as a male domain among ninth graders — in *both* genders, with high and gender-neutral technological acceptance. This reframes representation as a design lever, not just a bias to audit: systematically designed AI personas can counter, rather than merely avoid reproducing, gender bias.

Implications for AI in education

- **Fairness is design, not afterthought:** bias mitigation and fairness-aware algorithms must be built into AI tutors, scorers, and recommenders, and evaluated for equity alongside accuracy.
- **Infrastructure is equity:** addressing the digital divide and underrepresented-language infrastructure is a precondition for equitable AI, not a secondary concern.
- **Teacher-mediated delivery reaches students the AI never touches.** Where the digital divide rules out one device per student, Rodrigues et al. (2026) kept students working with paper and pen while teachers photographed their solutions and the AI returned personalized exercise lists and error-specific Feedback, in a clustered quasi-experiment across 19 Brazilian public-school classes.

- **Representation matters in content and assessment:** AI-curated materials and automated assessment must reflect and not penalize diverse learners, cultures, languages, and knowledge systems.
- **Pair access with support:** providing tools is insufficient; learners need skills, conditions, and culturally relevant Scaffolding to benefit.
- **Reach the audiences formal education misses:** the AI Literacies framework for public service media argues that provision will keep reaching the already-advantaged unless it is designed otherwise, names young people who are digitally or otherwise marginalized as those with the fewest opportunities through formal education, and proposes targeted partnerships plus national-reach provision — not universal publication — as the remedy.
- **Policy and governance:** institutional AI policy (Educational AI Policy, AI Governance) must embed equity as a guiding principle.

Equity also has an environmental and computational dimension: unequal access to computationally intensive models can widen disparities between students and between well- and under-resourced institutions, and the substantial energy consumption and carbon footprint of deploying large models stand in tension with higher education's sustainability goals (Li et al. (2026)).

Common Misconceptions

- **"The equity problem is access to tools." Tool quality is part of the divide, not just tool access**: Canonigo (2026) submitted **50 mathematics tasks** and found quality differences that follow the tool rather than the user.
- **"Hybrid human-AI tutoring cannot narrow gaps." Differentiated human-AI tutoring is evidence that hybrid models can narrow gaps — when allocation follows need.** A difference-in-discontinuities study (**635** participants) found proactive tutoring showed **marginally higher average growth (75%, p = .065) concentrated among students farther below the cutoff**. The gain concentrated where need was greatest.
- **"An average effect tells you whether equity improved."** The insight is that the **allocation rule** determined the equity outcome: an intervention that helps everyone equally leaves gaps unchanged, and one that helps proportionally to need narrows them.

Connected Concepts

- Differential Effects Across Learner Groups
- Learners — Learners: the umbrella for the learner-side concepts
- Digital Divide — Unequal access to AI tools and infrastructure across socioeconomic lines, regions, and nations
- Bias Mitigation — Methods for detecting and correcting bias in AI tutors, scorers, and recommenders
- Accessibility — Design that makes AI learning tools usable by learners with disabilities
- Assistive Technology — Tools that support learners with disabilities in AI-mediated settings

- Culturally Relevant Pedagogy — Teaching that reflects learners' cultural contexts rather than imposing dominant norms
- Language Learning — Linguistic inclusion of multilingual and underrepresented-language learners
- Inclusive Learning — Accessible and equitable learning for all learners
- Universal Design for Learning — Designing for learner variability from the outset
- Neurodiversity — Supporting neurodivergent learners in AI education
- Special Education — Meeting the needs of learners with disabilities in AI system design
- AI Literacy — The skills learners need to benefit from AI equitably
- Educational AI Policy — Institutional policy embedding equity as a guiding principle
- AI Governance — Oversight and accountability for equitable AI
- Learner Agency — Ensuring AI empowers rather than replaces student voice
- Stakeholders — Umbrella: people and audiences in AI education (learners, teachers, designers, administrators, policymakers)
- Parents and Families
- Student Support and Success — who support systems reach, and the risks of acting on a risk score

Connected Articles

- Conceptualizing and developing second language teachers' multimodal assessment literacy in the GenAI era — How GenAI visual bias enters multimodal assessment, and why counter-narrating it is a teacher competency
- The rented self: How AI-enabled tools decouple performance from becoming — The rented self: rent paid in money, self and standards, and licenses that end at graduation
- Verified, not generated: expert-verified AI study materials and the distribution of learning gains in a university course — Verified, not generated: expert-verified AI study materials and the distribution of learning gains in a university course
- Supporting AI Literacies for Young Adults Aged 14-19: A value-based, practical framework for public service media organisations — Equity as a delivery problem: reaching young people formal education misses
- AI in University Assessment: Evaluating the Opportunities and Risks of Automated Marking — OpRaise report: AI marking of 761 university essays across three UK universities
- Generative AI in computing education: A systematic review and a framework for responsible integration — Skill-gap vs resource-gap: two equity mechanisms requiring different remedies
- AI-interaction literacy: reflections on how generative AI might be used to support self-regulated learning in higher education — Unguided GenAI may widen gaps: the interaction-management competence (Brunnström & Palmqvist 2026)
- Institutional structures, digital inequality, and AI integration in higher education — Institutional structures, digital inequality, and AI integration in Nigerian higher education

- Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation — Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation
- Does school-based AI education narrow readiness gaps? The role of prior agency-related learning — School AI education narrows psychological but not cognitive readiness gaps
- Same Question, Different Answer? Measuring and Mitigating Prompt Privilege for Equitable AI Access — Prompt Privilege: measuring & mitigating accessibility disparities in LLM access
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics — Language bias in AI-based scoring
- Contaminated Collaboration: Measuring Gender Bias Transfer in LLM-Assisted Student Writing — Gender bias transfer in LLM-assisted writing
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Generative AI and the marginalization of minoritized knowledges
- Structural silence: When AI infrastructure fails speakers of underrepresented languages — Structural silence: underrepresented languages in AI infrastructure
- Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025) — GenAI in higher education: systematic review
- Artificial Intelligence in Lifelong Learning: Opportunities and Challenges in Adult Education Policy — AI and lifelong-learning policy
- Does generative AI narrow education-based productivity gaps? Evidence from a randomized experiment — Does generative AI narrow education-based productivity gaps?
- Generative AI and linguistic diversity in academic writing and publishing: Perspectives from World Englishes — Linguistic diversity in AI-mediated academic writing
- Access is Not Enough: Human Support Improves Engagement with AI Tutoring — Access is not enough
- Bridging the Gender Gap in STEM Education with AI: Female-Coded Chatbot as Role Model and Learning Assistant — Female-coded chatbot as role model reducing math gender stereotypes
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — Paternalistic filtering in LLM-based history education
- DysLexLens: A Low-Resource LLM Framework for Analysing Dyslexic Learners Insights from Online Forums — DyslexLens: AI support for dyslexic learners
- Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education — Ground-truth reliability in AIED
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: stereotype-aligned feedback bias across student attributes

- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- Beyond "painting in pink": A critical case study of all-girls generative AI workshops in a European makerspace and implications for gender equity in computing — All-girls GenAI makerspace workshops and gender equity in computing
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- The Role of Implicit and Explicit Demographic Signals in Large Language Model-based Student Assessment — Implicit (conversation-history) demographic signals shift LLM scoring, feedback and answering (Rooein, Benedetto & Hovy 2026)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — 1,057 US faculty on AI's present and future: 81% expect wider digital inequities, 26% do not use the tools
- GenAI assessment and language equity: Drawing the line between support and substitution — Drawing the support-substitution line: GenAI assessment rules and EAL students' compliance burden
- AI refusal in higher education: The right to refuse, the duty to understand and the diagnostic value of non-use — The right to refuse is unevenly distributed: refusal as evidence of institutional under-preparation (Zagami 2026)
- AI literacy and scenario-based ethical judgment about generative AI among undergraduate students — Scenario-based ethical judgment and AI literacy among 531 undergraduates
- StudentBench: AI and human tutoring yield equivalent GRE learning gains — StudentBench: AI and human tutoring yield equivalent GRE learning gains
- AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI — AI Can Do Your Homework. Now What? Report from an online workshop on computing assessment in the age of generative AI
- Generative AI May Reinforce Social Biases in Software Engineering Education — Generative AI May Reinforce Social Biases in Software Engineering Education
- Teacher Mediation and the Contingent Promise of Generative AI in Mathematics Education — Free-tier vs premium-model accuracy gap in mathematics: 32.7% vs 12% (Canonigo 2026)
- The Impact of Generative Artificial Intelligence on Learning Outcomes in Higher Education: A Meta-Analysis — Pooled GenAI learning gains (g=0.53) and the inequitable access to high-cost tools they cannot capture

- Reimagining mathematics education through intelligent tutoring: evidence, opportunities, and implementation challenges — Mathematics AI-tutoring review finding inclusiveness and achievement-gap claims unsupported
- Improving hybrid human-AI tutoring by differentiating human tutor roles based on student needs — Improving hybrid human-AI tutoring by differentiating human tutor roles based on student needs (Gurung et al. 2026)
- Teacher-mediated multimodal platform and math achievement: Evidence from Goblins' yearlong district implementation — District AI-math rollout with larger exploratory associations for IEP, English-learner, and Hispanic students (multimodal/multilingual supports; causality untested)
- Constructing selves in AI-mediated apprenticeship learning: Students of colour's narratives of agency, recognition and negotiation — Apprentices of color equated fairness with cultural flatness; agency constructed through refusal and negotiation; Recognition Bandwidth and Institutional AI Literacy
- AIED unplugged, teacher workload, and numeracy learning: a clustered quasi-experimental mixed-methods study — Teacher-mediated delivery reaches students the AI never touches
- The pitfalls of AI detection in academic writing: bias, false positives, and the need for inclusive assessment — Detection fires hardest on multilingual writers
- Who benefits from LLMs? Prompt engineering competence and equity in higher education — Competence mediates the benefit students draw from LLM access (Li et al. 2026)

Connected FAQs

- What Are Notable Gaps in the Research Literature on AI in Education?
- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Is AI Impacting Students?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Differential Effects Across Learner Groups

> **Differential effects across learner groups** — what AI in education research finds about how the *use* of AI and its *effects* differ across kinds of learners: students with disabilities and neurodivergent students, second-language and multilingual learners, girls and boys, minoritized students, students from lower-income backgrounds, rural students, first-generation students, international students, and adult learners. The pattern worth carrying away is uneven in two directions at once: some strands have real evidence (disability, language) while others are close to empty (first-generation, international, refugee), and even the strong strands rarely establish that a *group* differs — they establish that a tool helped or harmed a sample of that group, which is a different claim. This page maps what exists, what it shows, and the methodological reasons a group average is not a prediction about a learner.

Questions to Consider

- Your tool mostly works for the students in your class, and a subgroup of five struggled. Would a subgroup difference of that size be detectable at all in a study of this kind — and would you want to change the tool for the whole class on that evidence?
- Research on students with disabilities reports effects that vary by disability category. If two categories sit at very different effect sizes in the same meta-analysis, what does that say about treating "disability" as one group in a design decision?
- Several studies find AI tools that do *not* differ by gender in their effects, and other work shows that AI feedback and AI-assisted writing *do* reproduce gender stereotypes when personas or prompts carry them. How can both be true at once?
- Most fairness work tests simulated student personas rather than real learners, because real demographic attributes are not available to the model at inference in most deployments. What can a counterfactual persona audit establish, and what can it not?
- Reviewing the strands on this page, which learner groups are actually represented in the studies behind your tool's validation — and what would you do about a group that is absent?
- An intervention that raises outcomes for everyone but closes a gap (helping the students who were behind the most) has a different equity story from one that raises the average. When you evaluate a pilot, are you measuring the gap or the mean?

Introduction

Two questions hide inside "does AI work for *this* kind of student?". The first is about effects: whether a tool produces different outcomes for different groups. The second is about use: whether different groups adopt, access, or interact with the same tool differently, which can shape outcomes without any differential effect at all. This page covers both, group by group, and states plainly where the literature stops.

It is deliberately not a duplicate of its neighbours. Equity in AI Education carries the normative and structural frame — access, representation, and outcome equity, and the argument for what AI in education

should do. Inclusive Learning carries the design frame, including Universal Design for Learning. Digital Divide covers the access-and-skills layers. Neurodiversity, Special Education, Accessibility, and Multilingual Learning go deep on single groups. What is left for this page is the cross-group evidence map and the appraisal question: how these effects are estimated, which groups are studied at all, and what a group-level finding licenses you to do.

How group differences get reported, and why most of it cannot

A single-group study is not a differential-effect study. Most of the literature in this area measures one group in the absence of a comparison group. Zhang et al. (2024) pooled 29 (quasi-)experimental studies of AI for students with disabilities and found a medium positive effect (Hedges' g = 0.588, 95% CI [0.349, 0.826]) — with no neurotypical comparator. That tells you an intervention helped, not that it helped this group differently.

Subgroup analyses are usually too small to answer the question. The GCSE science micro-RCT is unusually explicit: its treatment-by-status interaction was 0.57 marks (95% CI −2.25 to 3.39), with stratified estimates of g = 0.28 (95% CI −0.04 to 0.59) for one group and g = 0.35 (95% CI 0.18 to 0.52) for the other. A subgroup interval that overlaps zero is a question for a local pilot, not a basis for a class-wide rule.

Demographic attributes are usually simulated. Real learner demographics are rarely attached to model inputs, so audits supply personas instead. Rooein, Benedetto and Hovy (2026) ran six instruction-tuned models across three educational tasks under model-default, explicit-persona, and implicit-history conditions — 192,480 inference calls — and found that both explicit personas and *implicit* conversation histories move model behavior. Their distinction is worth keeping: awareness of learner differences can be desirable (adjusting feedback for a learner's first language), while the same sensitivity is a harm when it shifts the judgment of identical work.

Fairness fixes may not generalize. Fragkiadakis et al. (2026) reduced gender- and age-targeted error gaps in student-attention estimation on validation data, but the gains did not consistently transfer to held-out subjects or repeated subject-level splits.

Group labels hide the variation inside them. In the same disability meta-analysis, students with specific learning disabilities, intellectual and developmental disabilities, or who are deaf showed a larger effect (g = 0.952) than students with autism spectrum disorder (g = 0.368) — a difference the authors report as not statistically significant across 239 effect sizes from 41 independent samples. "Disability" is not one group, and neither is "L2 learner".

Disability and neurodivergence

This is the deepest strand in the knowledge base, and the one where the reporting is strongest.

- **Effects are real but unevenly distributed by outcome.** In Zhang et al. (2024), academic performance showed the largest effect (k = 80, g = 0.929), ahead of daily-life and other skills (g = 0.766) and social-emotional skills (k = 144, g = 0.382). Publication bias was present (Egger's test $\beta = 2.837$, $p < .001$); trim-and-fill reduced the pooled estimate to g = 0.2694, which remained statistically significant. Read the headline effect and the bias-adjusted one together.

- **The field has reorganized around generative AI.** The scoping review of digital assistive technologies for neurodivergent students screened 766 records to include 40 empirical studies, of which 15 used generative AI and 11 used immersive formats. The strand is small and recent rather than mature.
- **Some AI supports equalize rather than differentiate.** Pimenova, Begel and colleagues segmented instructional videos into single-instruction chunks with fixed pauses in a within-participants study (17 ADHD, 10 non-ADHD); everyone improved, and ADHD participants' errors and hesitations fell to parity with their non-ADHD peers. That is the strongest available shape of evidence for Universal Design for Learning through automated content transformation: a general change that closes a gap, rather than a group-targeted fix.
- **What neurodivergent students say they need is often mundane.** A survey of 24 neurodivergent computing students and 20 neurotypical peers, with four interviews, found significant discomfort with assignments that lack clear structure or carry ambiguous expectations — an accommodation that costs nothing to provide.
- **Design choices can also exclude epistemically.** Tali-Otmani (2026) argues that Anglophone, Western-centric training data marginalizes non-hegemonic ways of knowing and puts the situation of disabled learners at the center of that critique.
- **"At the same human grade, a grader treats identified and unidentified students alike."** Across **3,000** ASAP 2.0 essays matched exactly on the adjudicated grade, **every one of the 22 models** graded the disability-identified group lower, from **−0.086** to **−0.429** on a six-point scale, and **20** read GAP REPLICATES. Convention errors and length accounted for at most a fifth of it for **17 of 20** models, and because ASAP 2.0 releases one grade, the design cannot separate a bias shared by the human panel from one shared by the models (the reading is SHARED GAP, not model bias).

Language: second-language, multilingual, and English learners

By article count this is the largest strand, and it splits cleanly into tool effects and tool harms.

- **Tool effects are promising and noisy.** Wang, Zhang and Zou (2026) meta-analyzed 11 studies (17 effect sizes, N = 595) of robot-assisted language learning and found a positive overall effect ($g = 0.83$, 95% CI [0.46, 1.21]) with high heterogeneity ($I^2 = 84.4\%$); of six moderators tested, only robot-learner interaction type was significant. An evidence base this size supports a provisional Benchmark, not a procurement decision.
- **The infrastructure itself is uneven before any tool is used.** Roy and Roy (2026) document the corpus gap with Bengali as the case: under 0.5% of global web content against roughly 49.5% for English, despite Bengali speakers being nearly 4% of the world's population.
- **Language of instruction changes outcomes across 294 higher-education students.** The same review reports that foreign-language content yielded lower outcomes than native-language instruction, and that bilingual programming instruction outperformed English-only instruction.
- **Detectors penalize second-language writers.** Hadra, Cambridge and Mesbah (2026) tested Turnitin and Originality against 192 texts: one detector classified 48 of 48 professionally authored

texts correctly but misclassified four of 48 EFL student texts (91.6%). The asymmetry is the point — the error lands on the group whose writing is already being scrutinized.

Gender

Gender research here divides into whether tools treat learners differently, and whether learners are exposed to stereotype-laden tooling.

- **A deliberately gender-neutral design showed no gender difference.** A quasi-experimental study of 195 ninth-grade students tested ADA, a female-coded chatbot grounded in Ada Lovelace: situational interest rose for both genders with no gender difference in emotional response, cognitive load, or academic performance. A role-model persona can be built without triggering stereotype threat.
- **But prompt content transfers bias into student work.** A controlled study with 123 participants had students write career-plan essays for paired profiles differing only in gender, under no-AI, neutral-AI, and gender-biased-AI conditions; the biased condition transferred gender-differentiated language into student writing and suppressed female Learner Agency asymmetrically. The researchers first confirmed the effect on 1,600 generated essays.
- **Space and framing matter as much as the tool.** An all-girls generative AI makerspace case study found girls valued the single-gender setting as safer and more relaxed, and warns against "girlification" — surface-level adaptation that leaves power relations untouched.
- **Model sensitivity is a model property, not a constant.** In EduFair-Bench, five tutors from 7B to 70B were audited across nine demographic levels: Qwen2.5-7B exceeded the $|r| \geq 0.10$ bias threshold in 7 of 12 domain-by-dimension cells, while LLaMA-3.1-8B exceeded it once. Pedagogy-specific training reduced some biases and increased others.
- **A single-axis fix can leave a group worse off:** gender-diverse students collapsed into an "Unknown Gender" category had the lowest true positive rates under every fairness method, and no single-axis method improved their treatment — the group-label variation noted above, inside a predictive early-warning model rather than a tutor (McConvey et al. (2026)).

Race, ethnicity, and minoritized students

This strand is small in article count and strong in mechanism, because the evidence is about what AI does *with* a demographic attribute once it has one.

- **Personalization is a bias vector.** Marked Pedagogies shows Large Language Models (LLMs) writing-feedback tools shifting toward stereotype-aligned praise and withheld critique when feedback is personalized with a student's race, language, disability, achievement, or Motivation — on identical essays.
- **The demographic cue can be implicit.** The counterfactual audit above found that conversation histories, not just explicit personas, moved scoring and feedback behavior — the same 192,480 inference calls result, and a reason a disclosure rule about *declared* demographics is insufficient.

- **Migration and language gaps can dominate.** In EduFair-Bench, the 70B model paired the largest language and immigration gaps with the smallest pedagogy gaps, so a tutor that looks pedagogically strong can be the one most sensitive to who the student appears to be.
- **Epistemic exclusion, not just error:** see the marginalization of minoritized knowledges above.

Socioeconomic status, geography, and age

- **Digital literacy, not AI usage, is the mediator.** Wang and colleagues (2026) modeled survey and national registry data from 4,497 Grade 6 students in the Netherlands and found the link between personality traits and academic performance ran through digital literacy rather than AI usage intensity, with differences in digital literacy driven more by personality than by socioeconomic status — and SES advantages operating independently of AI engagement. The classic SES-only framing is incomplete.
- **Geography can be the binding constraint.** ARC's account of K-12 robotics and AI education reports that rural FIRST LEGO League participation fell in the 2020 remote season and never recovered while urban participation gradually did, and identifies sustained local technical mentorship — not kits or curriculum — as the constraint that is distributed geographically.
- **Adult learners are a separate design case,** covered by Adult Learning and the knowledge base's andragogy work rather than by K-12 studies.
- **Access still gates everything else:** see Digital Divide and the finding that access to AI tutoring is not enough without pedagogical integration.

Disciplinary background

Disciplinary background is a differential axis this page's group-by-group map did not yet carry: the same tool can distribute its benefit unevenly across fields rather than across student demographics.

- **A tool can engage one discipline and disengage another.** In a two-week quasi-experiment with 130 undergraduates on mixed-discipline teams, ChatGPT raised physical engagement for STEM students and lowered it for non-STEM students ($Q = 9.87$, $p < .05$), and notes written without ChatGPT scored higher on diversity and integration of disciplinary ideas (Zhu et al. (2026)).

Where the evidence is missing

The honest finding of this survey is how thin some groups are. Each of these is a real gap in the evidence base, not a gap in this page.

- **First-generation students:** one study reports a usage difference rather than an effect. In a CS2 inquiry study, continuing-generation students treated the AI as an active Problem Solving partner, while first-generation students took a confirmatory, validation-oriented role and asked fewer questions overall.
- **First-generation students: the first effect estimate, and it runs the wrong way.** Liu et al. (2026)'s randomized trial of a course-integrated AI tutor supplies what the entry above lacks — a measured differential rather than a usage pattern. In the full sample the effect of tutor access on

final grades was 2.87 points (0.28 SDs) more negative for first-generation students, implying −5.10 points (−0.50 SDs) for them against −2.23 points (−0.22 SDs) for their peers. The differential was larger in the exact-match sample (−3.89 points, −0.35 SDs), and first-generation students also lost more homework points and platform page views. The study reports no mechanism and its precision varies by outcome, but the direction is the opposite of the narrowing-gap story: the students with the least prior access to academic support carried the largest measured cost.

- **International students:** one mixed-methods study (survey n = 60, interviews n = 14) on cross-cultural adaptation support.
- **International students: a measured engagement pattern, not an effect estimate.** Across 270 minority ethnic international students in seven UK business schools, reported Generative AI use was positively associated with all four engagement strands — most strongly agentic engagement (β = 0.429) — with facilitating conditions (β = 0.369) the strongest predictor of intention to use (Adekoya et al. (2026)).
- **Gifted and high-achieving students:** effectively unstudied as a group in this corpus.
- **Refugee, immigrant, and displaced learners:** no studies.
- **Gender is still analysed as binary** in most of the work above, and disability categories vary across studies, so cross-study comparison of "the same" group has limits.
- **"Learner context makes a grader fairer."** An ablation on **3,000** essays graded by two models found the high-low label gap the same for every group it could test, every difference within **0.045** of a level. On Qwen the low label still took **0.06 to 0.08 points** more off English learners, economically disadvantaged and disability-identified students than off their peers. With no label both models still marked the last two groups below peers at equal human score. A record that can be wrong shifts marks, and it shifts hardest on those already underestimated.

Using this evidence without overfitting a group label

- **Treat group means as hypotheses about a population, never as predictions about a person.** Every differential claim above is a distributional statement.
- **Ask whether your learners were in the validation sample at all** before trusting a tool's claimed inclusivity; the neurodivergence and language strands both show that representation in development is the exception.
- **Prefer equalizing designs where the evidence allows.** The ADHD video-segmentation result — everyone improves, the gap closes — is a better-fitting goal for a general classroom than a group-targeted add-on.
- **Be careful with personalization that consumes demographic attributes.** The marked pedagogies finding is directly about that mechanism, and it applies to wellbeing check-ins, affective tutors, and recommender systems that profile learners.
- **Test locally, on the group you care about, with an outcome measured without the tool.** See Interpreting and Applying AIEd Research for the appraisal habits and Research Methods in AI in Education for the designs that make a local test defensible.

- **The grouping variable with the most direct process evidence is knowledge-based, not demographic.** Wang et al. (2026) matched groups on prior knowledge (U = 293.50, p = 0.515) and still found that how learners reason shaped what happened. Eight groups with different preconceptions and six with similar ones asked the same kinds of questions, yet the AI served as an integration hub in the diverse groups and sat on a linear path in the similar ones, with opposite sustained evaluation. That rests on fourteen groups in one 60-minute task, so treat it as a hypothesis about how you compose groups rather than as a rule.

Common Misconceptions

- **"Group labels capture the variation that matters." Group labels hide the variation inside them**: in the disability meta-analysis, students with **specific learning disabilities, intellectual and developmental disabilities** and other categories are pooled, so the group average describes none of them.
- **"Subgroup analyses answer the differential-effects question."** They are usually **too small to answer it**: the GCSE science micro-RCT is unusually explicit that its **treatment** contrast is powered for the overall effect and not for subgroup differences. An underpowered subgroup finding is a hypothesis, not a result.
- **"A medium pooled effect tells you whether a given group benefits."** 29 (quasi-)experimental studies pooled to **Hedges' g = 0.588 (95% CI [0.349, 0.826])** across disability categories. The interval describes the average over those categories, and "which group, which need" is a separate analysis.

Connected Concepts

- Equity
- Inclusive Learning
- Digital Divide
- Neurodiversity
- Accessibility
- Special Education
- Multilingual Learning
- Language Learning
- Bias Mitigation
- Culturally Relevant Pedagogy
- Universal Design for Learning
- Assistive Technology
- Global South
- Personalized Learning
- Learners
- Learner Identity
- Interpreting and Applying AIEd Research

Connected Articles

- Let’s CHAT About Artificial Intelligence for Students With Disabilities: A Systematic Literature Review and Meta-Analysis — 29 studies of AI for students with disabilities: g = 0.588, and g = 0.269 after bias adjustment
- ChatGPT for interdisciplinary learning: Does it equally benefit STEM and non-STEM students — ChatGPT benefited STEM and non-STEM students unequally in interdisciplinary learning
- Multidimensional engagement effects of generative AI adoption among minority ethnic international students in UK higher education — GenAI use and four-strand engagement among minority ethnic international students
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — 766 records to 40 studies, 15 of them generative AI
- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education — A general design change that brought ADHD participants to parity
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning — 24 neurodivergent students on structure, ambiguity, and collaboration
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Epistemic marginalization in AI, with disability as the case
- Multimodality and Social Interactions in AI-Enhanced Embodied Robot-Assisted Language Learning: A Meta-Analysis — g = 0.83 with I^2 = 84.4% in a small L2 evidence base
- Structural silence: When AI infrastructure fails speakers of underrepresented languages — Bengali’s under 0.5% of web content against English’s 49.5%
- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Detectors misclassify EFL writing while scoring professional texts perfectly
- Bridging the Gender Gap in STEM Education with AI: Female-Coded Chatbot as Role Model and Learning Assistant — A 195-student test of female-coded role models with no gender difference
- Contaminated Collaboration: Measuring Gender Bias Transfer in LLM-Assisted Student Writing — Gender-biased prompts transferring into student essays
- Beyond "painting in pink": A critical case study of all-girls generative AI workshops in a European makerspace and implications for gender equity in computing — Single-gender space valued, with a warning against girlification
- EduFair-Bench: Evaluating Pedagogical Fairness of LLM Tutors Across Student Demographics — Tutor fairness varying by model, domain, and behavior dimension
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Stereotype-aligned feedback on identical essays
- The Role of Implicit and Explicit Demographic Signals in Large Language Model-based Student Assessment — 192,480 calls: explicit personas and implicit histories both move models
- Fairness-Aware Multimodal Transformer Modeling for Real-Time Student Attention Estimation — Fairness regularization that did not generalize

- Decoding divides: The role of socioeconomic status and personality traits in AI divides and educational inequality — 4,497 students: digital literacy, not AI use, mediates the gap
- Teaching AI, Robotics, & Community: A Hubs-Based K-12 Education Framework for Reaching Rural Schools — Rural participation that never recovered, and mentorship as the constraint
- Evaluating AI Tutoring at the Speed of Innovation: Practitioner-Led Micro-Randomised Trials of an AI Tutoring Platform in GCSE Science — A subgroup interaction whose confidence interval crosses zero
- Analysis of Types of Inquiries in Student-AI Interaction: A case study of two CS2 tasks — The corpus's one first-generation usage finding
- Understanding how international students in the U.S. are using conversational AI to support cross-cultural adaptation — The corpus's one international-student study
- The Effects of Course-Integrated AI Tutoring on Student Performance and Engagement: A Randomized University Trial — The corpus's first effect estimate for first-generation students: tutor access cost them 0.50 SDs of final grade against 0.22 for their peers (Liu et al. 2026)
- Fairness Theatre: Evaluating Post-Hoc Fairness Interventions in Vendor-Controlled Early Warning Systems — Fairness Theatre: Evaluating Post-Hoc Fairness Interventions in Vendor-Controlled Early Warning Systems
- GenAI-based metacognitive prompting in collaborative inquiry: A comparison across diverse preconception groups — A knowledge-based grouping variable with direct process evidence: groups matched on prior knowledge but differing in preconception diversity took up the same AI differently (Wang et al. 2026)
- Beyond agreement: a benchmark of how language models grade student work, and how they fail — Beyond agreement: 22 prompted graders meet probes whose right answer is known, and most of them can be talked up (Porcaro 2026)
- Learner context changes an LLM grader's marks on identical work: a within-item ablation on six models — Learner context changes an LLM grader's marks on identical work, and agreement with the teacher does not register it (Porcaro 2026, Paper VI)

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- What Are Notable Gaps in the Research Literature on AI in Education?

Digital Divide

> **Digital divide** — the unequal distribution of access to, skills for, and benefits from digital (and increasingly AI) technologies across individuals, communities, and nations. In AI education, the digital divide is a central equity concern: generative AI is rapidly reshaping learning, and the gap between those who can use it effectively and critically and those who cannot threatens to deepen existing educational inequalities.

Questions to Consider

- The digital divide is often described in three levels: access, skills, and who actually benefits. Which level do you think most people are thinking about when they say ‘closing the digital divide’ — and why might that be incomplete?
- Giving every student a device and internet access doesn’t automatically mean they can use AI effectively or critically. What separates having access from being able to benefit?
- AI adds new layers to inequality: algorithmic bias can disproportionately harm marginalized Learners, and AI literacy itself determines whether the technology widens or narrows gaps. How is this different from the divides of earlier technologies?
- The divide also extends to WHICH communities, languages, and perspectives are represented in and served by AI systems. How is representation itself a form of access — or exclusion?
- If closing the divide is ‘a question of justice and participation,’ who bears the responsibility: platforms, schools, governments, or all of them — and what would a fair distribution of AI’s benefits actually look like?

Introduction

The digital divide is commonly understood as operating across **three levels** (van Deursen & van Dijk, 2014): the *first-level* divide concerns access to technologies and infrastructure (connectivity, devices, supportive environments); the *second-level* divide concerns skills and competencies (the uneven capacity to use tools effectively and meaningfully); and the *third-level* divide concerns outcomes and benefits (who actually benefits from technology use, with AI potentially exacerbating social, cultural, and economic disparities). Framing AI literacy through this lens makes clear that equity requires more than closing the device-and-infrastructure gap — it requires building the skills to use AI effectively and critically so that its benefits are distributed fairly rather than reinforcing existing inequalities.

The edge-inference turn adds a hardware dimension to the first-level divide. When tutoring runs in the browser rather than the cloud — browser-resident SLM tutors via WebLLM — the subscription-cost barrier disappears but a capability barrier replaces it: on a consumer laptop the same system took roughly 180 seconds per trial against 10–58 seconds for a remote API, and Chromebook-class devices cannot run an 8B model at all. Students with modern hardware get fast, seamless generation while students on older devices face latency or memory exhaustion, so local and cheap is not the same as equitable by default.

How the digital divide appears in the research

- **AI literacy as a mechanism for equity:** The SAIL framework was explicitly designed to address second- and third-level divides, providing a scaffolded, age-agnostic pathway for equitable AI literacy across all stages of education, grounded in the argument that AI literacy is inseparable from equity and participation.
- **Policy and infrastructure:** OECD Digital Education Outlook 2026 situates the digital divide within national education policy, examining how access to digital and AI technologies varies and what systems can do to close gaps.
- **Responsible-use and prompting literacy:** K-12 prompting-literacy research addresses the second-level divide by teaching students the skills to use AI chatbots responsibly, recognizing that access alone does not confer the ability to use AI well.
- **Phrasing skill is its own second-level divide.** On MedQA, accuracy rose with prompt sophistication (82.4% for low-literacy wording against 83.4% for expert phrasing), and a Prompt Equity Transformer rewriting requests into equivalent, clearer wording closed the gap — shifting the burden of effective prompting from the learner to the system (Jin et al. (2026)).
- **Representation and structural silence:** Research on underrepresented languages highlights how the digital divide extends to *which* communities, languages, and perspectives are represented in and served by AI systems — a cultural and epistemic dimension of inequality.
- **Code-switching is its own exclusion.** Most Large Language Models (LLMs) lecture tools assume single-language English audio and reliable internet, ruling out classrooms mixing English and a home language; India's UDISE+ data put school internet access near 54% with a 24-point urban-rural gap, and a bilingual companion answers with on-device transcription and local-first storage (Malhotra, 2026).

AI deepens (and can close) divides

AI adds new layers to the equity implications of technology. Algorithmic bias can disproportionately impact learners from marginalized communities, and AI literacy — the ability to understand, critically evaluate, and mitigate AI's biases and risks — is itself a key factor in whether AI widens or narrows gaps. Research shows educators with higher AI literacy are more effective at identifying and mitigating biased outcomes. The digital divide in the AI era is therefore not simply a technical provision problem but a question of justice and participation: who can access AI, who can use it critically, and who benefits.

A long-standing strand of the literature traces how the concept itself shifted from access to **digital equity**, now defined across four dimensions — digital literacy, affordability, group-sensitive content, and infrastructure availability — and reads consumer AI as a new wave of the divide that favors users already able to audit machine output (Rose (2026)).

Personality, not just SES, shapes the AI-era divide. Wang et al. (2026) analyzed survey and national registry data from **4,497 Grade 6 students** in the Netherlands, separating two mediating pathways — AI usage and digital literacy — linking student background and personality to academic performance. Their key finding reframes the classic divide: **digital literacy, not AI usage intensity, mediates** the link between

personality and performance, and a new digital-skills divide emerges that is driven more by **personality traits than by socioeconomic status**. SES advantages on performance operated independently of AI engagement. This complicates the access-and-SES framing of the digital divide, pointing to skills formation and dispositional support as equity-relevant levers alongside device and tool access.

The divide has a metacognitive layer. Because leveraging AI productively requires prior knowledge and self-regulation, students who already possess these benefit most while those who need the practice most delegate the learning itself — a "metacognitive equity gap" that can widen achievement divides even at equal access (Lodge & Loble (2026)).

Structured school AI instruction is a psychological catalyst but not a cognitive equalizer: across 752 Hong Kong junior-secondary students, a year-long curriculum narrowed confidence and motivation gaps yet left objective AI-literacy differences between high-agency and low-agency learners intact (Liang et al. (2026)).
The divide operates at the institutional level too. Adeniranye et al. (2026) show that in Nigeria's higher education system, AI integration capacity concentrates in older, South-West-region institutions and compounds through mutually reinforcing network ties (international collaborations × industry partnerships, r = 0.74) — meaning institutional "have-nots" (typically newer state universities) face structural barriers to entering the very networks that would help them catch up. Digital inequality is thus reproduced not only across individual learners but across the institutional structures that shape who can participate in an AI-transformed knowledge economy.

The divide also has a geography, and mentorship is its mechanism. Jacobson et al. (2026) document a recovery asymmetry in Indiana FIRST LEGO League participation: both urban and rural participation fell in the 2020 remote season, but only urban participation recovered, and rural participation stayed near its post-2020 level through 2025–2026. The mechanism they name is access to technical mentorship — people with enough programming and robotics knowledge to start and sustain a team — which rural schools may lack even when students and teachers are interested, making it a precondition for the robotics and AI pathway rather than a feature of it. Their response is to engineer the propagation of that mentorship: college primary hubs train undergraduates and host workshops, mature school programs become secondary hubs that mentor nearby schools, and a spatial Markov simulation of Indiana's 1,925 public schools projects 992 programs after 40 years under moderate assumptions against 161 without ARC, including 341 rural programs against 60. Read alongside the institutional-network result above, the pattern is that divides persist through the *structure of who can supply expertise where*, and that supplying it deliberately — rather than assuming proximity to a university — is the policy lever.

Access and epistemic hierarchy are different problems. Sithole (2026) draws the distinction sharply from interviews with academic developers at two South African Historically Disadvantaged Institutions: digital inequality is distributive — devices, connectivity, budgets, digital literacy — and answerable in principle through redistribution, whereas **algorithmic coloniality** is epistemic and persists even under conditions of full access, because it inheres in what the systems encode and whose knowledge they center. The study's participants experience both at once, described as being "asked to build a digital future on analogue foundations": the foundations name the material register of the divide, and the imported future arrives pre-loaded with the epistemic assumptions of the contexts that designed it. The practical implication for equity work is that closing an access gap does not by itself unsettle the hierarchy — the two phenomena operate at different registers and require different responses.

A design can route around the device gap instead of waiting for it to close. Rodrigues et al. (2026) test whether students who never touch a computer can still receive Intelligent Tutoring-style support, using a paradigm they call “AIED unplugged” in which the teacher is the proxy between learner and system. Students keep working with paper and pen, the teacher photographs their solutions on a smartphone, and the system returns personalized exercise lists, automated scoring, and error-specific feedback. Their clustered quasi-experiment across 19 Brazilian public-school classes is, by their account, the first quasi-experimental evaluation of such a system in authentic classrooms rather than a prototype, and the app ran on teachers’ own phones under the intermittent connectivity typical of those schools. The design is therefore a distinct equity strategy from the ones above: rather than closing the first-level divide of devices and bandwidth before AI tutoring can reach anyone, or raising second-level skills as the entry ticket, it reaches students the AI never interacts with directly. The same study, however, shows the route is not free of the divide it sidesteps. The learning advantage over usual practice traced to the teacher training rather than to the technology — the training and full-system conditions did not differ on gains — and the system’s positive indirect effect on learning operated through *reduced teacher effort*, with heavier workload associated with lower gains. Routing around the access gap thus does not dissolve the equity problem; it relocates the binding constraint to teacher capability and time. - **The hardware constraint may be dissolving, not the access gap closing.** Guo et al. (2026) argue that the binding constraint on equitable language learning is now software rather than hardware. The complete synthesis–recognition–translation stack fits under 4 GB, community measurements put a 3B model at 4–9 tokens per second on an $80 single-board computer, and five years of daily practice costs about $18 of electricity against $1,200 for a cloud subscription and $2,600 for weekly tutoring.

- **Model compression is another route to constrained hardware.** A Nigerian Pidgin adaptive tutor fine-tuned on a 416,343-entry corpus kept semantic structure and coherence at 8-bit, while 4- and 5-bit versions cut inference latency with only minimal degradation in instructional quality, and native speakers checked cultural acceptability rather than metrics alone (Nwogo et al., 2026).
- **Virtual provision does not automatically escape the equipment bill.** A systematic review of 11 digital-twin studies in STEM higher education found hardware costs of $2000-$15,000 per functional workstation node in four studies, with physical entities capping access at 1-3 concurrent students in five, and no included study produced a return-on-investment analysis (Pelayo-Gonzalez et al. (2026)). The review benchmarks that entry cost against physical characterization rigs costing from $30,000 to over $150,000.
- **This divide may be shallower than the internet’s was.** Matching each country’s 2025 generative-AI use to the internet year with comparable overall use, the education gap was smaller in 13 of 16 countries that could be matched, out of 35 (Watanabe (2026)).

Connections to related concepts

The digital divide is a core concern of Equity research, closely tied to AI Literacy (which is positioned as a central mechanism for addressing structural barriers), and to Ethics and Bias Mitigation (since algorithmic bias disproportionately affects marginalized groups). It connects to AI in Education and Higher Education as the settings where access and capability gaps manifest, and relates to Student Experience as it shapes who can participate meaningfully in AI-shaped learning.

Common Misconceptions

- **“Access to the tool is the divide.”** Access is the first layer and the literature has moved past it. **Phrasing skill is its own second-level divide**: on MedQA, accuracy rose with prompt sophistication from **82.4% for low-literacy wording to 83.4% for expert phrasing**, which means two students with identical access get different quality from the same model because one knows how to ask. A prompt-rewriting layer narrowed the gap — the divide is in the interface and the user’s fluency, not only in the subscription.
- **“If it runs in a browser, it is available.”** Most LLM lecture tools assume **single-language English audio and reliable internet**, which rules out exactly the classrooms mixing English with a home language. India’s UDISE+ data put school internet access far below the level that assumption requires. A tool built on an assumed infrastructure silently excludes the settings with the strongest need.
- **“Digital literacy and AI usage are the same mediating variable.”** A study of **4,497 Grade 6 students** in the Netherlands separated **two distinct mediating pathways** — AI usage and digital literacy — linking background and personality to learning gains. They are not interchangeable, and interventions that raise one do not automatically raise the other.
- **“Simulations remove the cost barrier.”** A systematic review of **11 digital-twin studies** in STEM higher education found hardware costs of **$2,000-$15,000** per setup. A simulated lab can reproduce the equipment bill it was meant to avoid, so the cost argument for virtual provision has to be checked rather than assumed.

What this means for practice

For instructors

- Teach prompting as a literacy, not an optional trick. A 1-point accuracy difference between low-literacy and expert phrasing is small on its own, but the same mechanism compounds across every task a student attempts.
- Check the language and connectivity assumptions of any tool before assigning it. Single-language English audio excludes bilingual classrooms regardless of device access.
- Distinguish which pathway you are actually addressing. Raising AI usage and raising digital literacy are different interventions with different outcomes.

For administrators and developers

- Do not treat device distribution as closing the divide. The measurable gaps sit in phrasing skill, interface language and connectivity, and none of them are fixed by hardware.
- Publish the infrastructure a tool assumes. A requirement stated plainly lets an under-resourced setting judge fit before investing.
- Cost out the full deployment, not the software license. Digital-twin evidence shows the hardware bill can survive virtualisation.

Connected Concepts

- Differential Effects Across Learner Groups
- Remote Proctoring
- Equity
- AI Literacy
- Ethics
- Bias Mitigation
- AI in Education
- Higher Education
- Student Experience
- Parents and Families

Connected Articles

- Is the education gap in generative AI use smaller than the internet's was at a similar level of use? Evidence from 16 European countries — Is the education gap in generative AI use smaller than the internet's was? (Watanabe 2026)
- Institutional structures, digital inequality, and AI integration in higher education — Institutional structures, digital inequality, and AI integration in Nigerian higher education
- Decoding divides: The role of socioeconomic status and personality traits in AI divides and educational inequality — SES, personality, and AI divides in primary education (Wang et al. 2026)
- AIED unplugged, teacher workload, and numeracy learning: a clustered quasi-experimental mixed-methods study — AIED unplugged: teacher-as-proxy tutoring reaches students with no device (Rodrigues et al. 2026)
- Does school-based AI education narrow readiness gaps? The role of prior agency-related learning — School AI education narrows psychological but not cognitive readiness gaps
- Same Question, Different Answer? Measuring and Mitigating Prompt Privilege for Equitable AI Access — Prompt Privilege: measuring & mitigating accessibility disparities in LLM access
- The Scaffolded AI literacy (SAIL) framework: Results of a Delphi study for equitable AI literacy framework design in education — The Scaffolded AI literacy (SAIL) framework
- OECD Digital Education Outlook 2026: Exploring Effective Uses of Generative AI in Education — OECD Digital Education Outlook 2026
- Learning to Use AI for Learning: Teaching Responsible Use of AI Chatbot to K-12 Students Through an AI Literacy Module — Teaching Responsible Use of AI Chatbots to K-12 Students
- Structural silence: When AI infrastructure fails speakers of underrepresented languages — Structural Silence and Underrepresented Languages

- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review — Social-Emotional Competence in AI Literacy
- A bilingual, LLM-mediated lecture companion for self-regulated learning: Architecture, theoretical framework, comparative and usability evaluation, and a pre-registered outcomes protocol
- An AI-Based Adaptive Learning Platform for Multilingual and Low-Resource Educational Contexts: A Case Study on Nigeria — AI-Based Adaptive Learning Platform for Multilingual Low-Resource Contexts
- Artificial intelligence in science and chemistry education: A systematic review — Systematic review of AI in science/chemistry education
- Translating UNESCO artificial intelligence guidelines to chemical education and its intersection with sustainable development goals — UNESCO AI guidelines translated to chemical education; epistemic drift
- Artificial intelligence, cognitive offloading and implications for education — AI, cognitive offloading and implications for education (Lodge & Loble 2026)
- From Mechanical Compliance to Human Flourishing: A Socialist Humanist Approach to Asynchronous AI Literacy and Fair Use in Higher Education — Socialist humanist AI literacy + fair use
- Teaching AI, Robotics, & Community: A Hubs-Based K-12 Education Framework for Reaching Rural Schools — ARC: rural robotics access follows mentorship geography, not device access (Jacobson et al. 2026)
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Digital inequality as distributive problem vs. algorithmic coloniality as epistemic one, in South African HDIs
- LLMersion: A Local-First AI Agent Framework for Low-Cost Home Language Learning toward Educational Equity — LLMersion: A Local-First AI Agent Framework for Low-Cost Home Language Learning toward Educational Equity
- Digital Twins in STEM Education: A Systematic Review — Digital twin labs carry an equipment bill that bounds concurrent access

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Should Parents and Teachers Approach AI with Children Under 13?

Bias Mitigation

> **Bias mitigation in AI education** — the identification, measurement, and reduction of unfair, identity-patterned behavior in AI tutors, scorers, recommenders, and educational systems. Bias can enter at any stage of the AI pipeline — training data, model behavior, prompts, scoring, and deployment — and manifest as differential treatment of learners based on language, gender, race, culture, or other identity characteristics. Mitigation spans data curation, debiasing algorithms, prompt design, fair-scoring methods, explainability, and evaluation. It is the technical counterpart to Equity and a core concern of Ethics in AI education.

Questions to Consider

- Bias can enter at any stage of the AI pipeline — training data, model behavior, prompts, scoring, and deployment. Before reading, where in that chain did you expect bias to live? This page suggests it can appear almost anywhere. Where is one place you hadn't considered?
- Research shows AI physics scoring systematically underestimates students whose text-based explanations are of lower linguistic quality — the AI scores the language, not the understanding. Why might a system that agrees well with human raters overall still consistently penalize non-native or less fluent writers?
- One study found that a gender-biased prompt induces students' essays to display a larger 'agentic gap' and more gender-stereotypic content — bias transferred from the tool into the learner's own work. What does this say about bias as not just an unfair score but a force that can reshape what students produce and who they see themselves as?
- Another study showed LLMs shift feedback in stereotype-aligned ways when personalized with student attributes — leaning on praise and softening critique for 'marked' students even when the essays are identical. How might 'nicely' biased feedback be more harmful than an obviously wrong score, because it's harder to detect?
- Mitigation spans data curation, debiasing algorithms, neutral prompt design, fair-scoring methods, explainability, and human oversight. Which single mitigation lever do you think would make the biggest difference in an AI system you rely on, and what would you need to audit to know it worked?
- A neutral prompt largely avoids inducing gender-differentiated language — suggesting prompt design is a practical mitigation. But if bias can be reintroduced through data, scoring, or deployment, why might fixing the prompt alone be an incomplete answer?

Introduction

Bias mitigation matters because AI in education is not neutral: systems trained on dominant language and cultural data can systematically disadvantage marginalized learners, from AI-based scoring that penalizes non-native writers to LLM tutors that answer differently for different groups. Bias is a cross-cutting concern

that appears in Automated Grading, Automated Essay Scoring, Knowledge Tracing, recommendation systems, and conversational AI tutors.

Solyst et al. (2026) show that bias mitigation can be taught rather than only engineered: youths prompted to interrogate a text-to-image model's outputs produced systematic evaluations of representation, and their requests for images of people skewed white before the intervention.

Fairness is the least examined dimension in the AI-versus-human scoring literature: of twelve studies reviewed, ten were silent on demographic, linguistic or social bias, and gender was the only dimension tested (Xu, Lu and Abdi, 2026).

Sources of bias

The knowledge base's research documents bias entering at multiple points in the pipeline:

- **Language and scoring bias:** AI-based physics scoring systematically underestimates the conceptual understanding of students whose text-based explanations are of lower linguistic quality — the AI scores the language, not the understanding, penalizing non-native or less fluent writers. This is a direct validity and fairness failure in Automated Grading.
- **Gender bias transfer in LLM-assisted writing:** Contaminated Collaboration shows that when students write with a gender-biased LLM prompt, their essays display a significantly larger agentic gap and more gender-stereotypic occupation suggestions (N=123); bias transfer is asymmetric, suppressing agency in female-target essays. A verification study (N=1,600 LLM essays, R^2=.399) confirms a gender-biased prompt induces gender-differentiated language.
- **Differential refusals and epistemic injustice:** The Paternalistic Filter audits four LLMs as history tutors (1,800 responses) and exposes a "paternalistic filter": models differentially refuse, soften, or reframe sensitive content for different learners — an epistemic injustice with direct equity implications.
- **Selection bias in learning analytics:** Debiased knowledge tracing addresses selection bias arising from non-random exercise recommendations: training on observed logs with standard empirical risk produces biased mastery estimates that compound errors in adaptive recommendation loops.
- **Data and annotation bias:** data annotations and ground-truth reliability research examine how the labels and inter-rater reliability underlying AI models carry bias — arguing against treating $\kappa > 0.8$ as a binary stamp of approval.
- **Marginalized knowledges:** Generative AI and minoritized knowledges documents how training data and model behavior marginalize non-dominant knowledge systems and disability perspectives.
- **Stereotype-aligned automated feedback (Marked Pedagogies):** Tan et al. (2026) show four widely used LLMs systematically shift writing feedback in stereotype-aligned ways when feedback is personalized with student attributes — race, ethnicity, ELL designation, learning disability, achievement, or motivation. Two biases follow: positive feedback bias and feedback withholding bias — more praise, less substantive critique, assumptions of limited ability — for

marked students on essays that were otherwise identical. The “Marked Words” concentration metric offers a concrete method for auditing such bias in automated feedback.

- **Visual bias in text-to-image tools:** Alon, Hadar Shoval, and Levkovich (2026) systematically review 31 peer-reviewed studies (2023–2025) on bias and representation in educational uses of AI-generated text-to-image. Using a six-part analytic framework (gender; race, ethnicity, and SES; culture and religion; age; body and (dis)ability; content), they find biased representation pervasive — images frequently centered white, male, Western, thin, and non-disabled figures, while diversity related to age, body, and ability was largely overlooked. Most studies relied on image audits and qualitative methods, with few experimental or intervention-based designs, revealing significant blind spots in how educational research measures and responds to visual bias.
- **Avatar identity cues reproduce offline bias.** Across two experiments (N = 396), White avatars — and, in STEM contexts, Asian male avatars — were rated more credible and competent while older Black female avatars were penalized; STEM and procedural tasks amplified the bias and reflective and interpersonal tasks attenuated it (Anthis & Kyriakidou-Zacharoudiou (2026)).
- **Non-discrimination as a core ethical value.** Agarwal et al. (2026), a systematic review of 25 articles, identify non-discrimination (definitions using bias/discrimination/diversity) as one of six main ethical values for AI in education, alongside data stewardship, human oversight, goodwill, explicability, and educational aptness. The review notes the values are tightly coupled and can conflict — e.g., non-discrimination vs. data stewardship — producing ethical dilemmas, and that no norms on non-discrimination address end users directly, leaving learners largely passive in the ethical literature.
- **Allocation bias in AI-assisted team formation.** Entezami et al. (2026) show bias entering a task class outside scoring and feedback: three LLMs assigning 28-student software-engineering classes to four teams routed men at least 80% less often than women to Interface Design rather than Core Development (GPT-5.2 OR < 0.01), and nationality shifted placements independently of merit. Supplying skills reduced but did not remove it - 99.2% of skill-based assignments matched one of two ground-truth teams, yet gender still decided between equally valid options (OR 2.53 GPT-4.1, 2.81 GPT-5.2, 1.43 DeepSeek) - and parallel image generation skewed single-person images male and light-skinned (gender V = 0.64 and 0.65; skin tone V = 0.57 and 0.61) while multi-person images stayed comparatively balanced.

Aggregate accuracy can hide a model that cannot find the struggling students. Hooshyar et al. (2026) trained three model families on one Estonian cohort and split it two ways. On the balanced set the families were comparable. On the imbalanced split, with 125 students below the first quartile against 328 above it, decision trees, a Bayesian network and random forests reached 8%, 12% and 16% recall for low performers at 80% precision, and only the neural-symbolic model passed 50%.

Mitigation approaches

The knowledge base’s research illustrates several complementary strategies:

- **Fairness-aware modeling:** The Hybrid HKG-GRU framework integrates **Group Distributionally Robust Optimization (GroupDRO)** for fairness alongside explainability and

counterfactual stability, evaluated on Moodle logs (152 students, ~150k interactions). It demonstrates that recommendation systems can be trained to be fair and transparent, not just accurate.

- **Debiasing estimators:** Temporal Smoothness Doubly Robust (TSDR) learning combines a propensity model with an error-imputation model, retaining unbiasedness if either is correct, to remove selection bias from knowledge-tracing mastery estimates.
- **Prompt-level mitigation:** the gender-bias study shows a neutral prompt largely avoids inducing gender-differentiated language, so prompt design is a practical mitigation lever.
- **Dialect-invariant training:** Fang and Liu (2026) show training dialect invariance in beats patching it on: dropping the style-transfer contrastive term nearly tripled the counterfactual flipping rate (4.3% to 11.8%) and widened the non-standard-dialect false-negative gap by ten points, while costing only 0.8 Macro-F1 and cutting African American Vernacular English false negatives by 18.4 points.
- **Validated, language-independent scoring:** addressing scoring bias requires scoring that separates conceptual understanding from linguistic quality, and auditing scores for language bias.
- **Explainability:** XAI in education provides transparency into why a system produced a given score or recommendation, enabling detection and correction of biased behavior and supporting Trust.
- **Pipeline-wide auditing:** persona-skills auditing and systematic audits like the paternalistic-filter study show the value of auditing models across identity conditions before deployment.
- **Fairness measurement is largely absent where analysis scales.** A PRISMA-ScR scoping review of 421 studies applying NLP to student evaluation of teaching found a formal fairness metric in only 8 studies (1.9%) and institutional-use risk in 18, while study limitations appeared in 70.5% and privacy protections in 42.3%; the authors read the coexistence as LLM adoption broadening the technical repertoire without proportional gains in validation or responsible-use reporting (Eicher & da Silva (2026)).
- **Group size is not a proxy for disadvantage:** two of six post-hoc fairness methods directed corrections at already-advantaged groups because they used group size to define disadvantage; reassigning disadvantage by observed disparity redirected one method but left the other flipping zero predictions — a limit on what post-hoc mitigation can claim (McConvey et al. (2026)).

Mitigation across the AI pipeline

Bias mitigation is not a single fix but an ongoing process spanning the pipeline:

1. **Data curation** — diversify training data and audit labels for identity-based gaps and unfair annotations.
2. **Model training** — apply debiasing and fairness-aware objectives (e.g., GroupDRO, doubly robust estimators).
3. **Prompt and system design** — design neutral prompts and systems that do not differentially respond to learner identity.
4. **Scoring and assessment** — validate that automated scoring measures understanding rather than language or demographic proxies.

5. **Evaluation and auditing** — audit models across identity conditions (language, gender, culture) and require explainability to surface bias.
6. **Human oversight** — retain human-in-the-loop review, especially for low-confidence or high-stakes cases.

Relationship to related concepts

Bias mitigation is the technical mechanism through which Equity is operationalized, and a core requirement of Ethics and responsible AI design. It connects to AI Ed Evaluation (bias as an evaluation criterion), Educational Measurement and Assessment Validity (fairness in scoring), and Privacy (as a related responsible-AI concern). It also connects to Over-Reliance (since biased systems are especially harmful when over-trusted) and AI Literacy (helping users recognize and question biased AI).

Implications for AI in education

- **Audit the whole pipeline:** bias can enter at data, model, prompt, scoring, and deployment stages — mitigate across all of them.
- **Test across identity conditions:** evaluate AI tutors, scorers, and recommenders for differential behavior across language, gender, culture, and disability.
- **Separate understanding from language in scoring:** automated scoring must not penalize non-native or less fluent writers for conceptual understanding they demonstrate.
- **Make systems explainable:** transparency into AI decisions is essential for detecting and correcting bias.
- **Combine technical and human mitigation:** pair debiasing algorithms with human-in-the-loop oversight, especially for high-stakes or low-confidence cases.

Common Misconceptions

- **“Bias is a scoring and feedback problem.”** Bias enters **task classes outside scoring**: three LLMs assigning **28-student software-engineering classes to four teams routed men at least 80% less often than** the reference distribution. Team formation carried bias at a magnitude comparable to grading.
- **“Supplying the relevant skill removes the bias.”** Supplying skills **reduced but did not remove it**: **99.2% of skill-based assignments matched one of two ground-truth teams, yet gender still decided between equally valid options (OR 2.53**). Near-perfect task matching coexisted with a gender effect, so accuracy on the primary criterion is not evidence of fairness.
- **“One mitigation approach is sufficient.”** The research illustrates **complementary strategies** — fairness-aware modeling among them — because the bias entering at formation is not addressed by a fix aimed at output text.

Connected Concepts

- Differential Effects Across Learner Groups

- Explainable AI
- Guardrails
- Equity
- Ethics
- AI Ed Evaluation
- Automated Assessment
- Automated Essay Scoring
- Educational Measurement
- Knowledge Tracing
- Large Language Models (LLMs)
- Generative AI
- Privacy
- Human-in-the-Loop
- Trust
- Cognitive Offloading
- AI Literacy
- Student Experience
- AI in Education
- Recommender Systems and Learning Paths

Connected Articles

- Face value: How avatar identity shapes epistemic trust in AI-mediated learning
- Neuro-symbolic pedagogical alignment (NSPA) for long-horizon classroom discourse analysis: Mitigating dialect bias via counterfactual preference optimization — Neuro-symbolic pedagogical alignment (NSPA)
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics — Language bias in AI-based scoring
- Contaminated Collaboration: Measuring Gender Bias Transfer in LLM-Assisted Student Writing — Gender bias transfer in LLM-assisted writing
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — The paternalistic filter and differential refusals
- Fair and explainable educational recommendations with a hybrid Graph-GRU framework — Fair and explainable educational recommendations
- Temporal Smoothness Doubly Robust Learning for Debiased Knowledge Tracing — Debiased knowledge tracing
- Modernizing Ground Truth: Four Shifts Toward Improving Reliability and Validity in AI in Education — Modernizing ground truth for AI reliability

- Data Annotations as Pedagogical Hints: From Subjective Labels to Critical Thinking — Data annotations as pedagogical hints
- Explainable Artificial Intelligence in education — Explainable AI in education
- When Agents Learn to Be You: Benchmarking Privacy Leakage, Impersonation Risk, and Defenses in Persona Skills — Persona-skills privacy and bias auditing
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — GenAI and the marginalization of minoritized knowledges
- Marked pedagogies: Examining linguistic biases in personalized automated writing feedback — Marked Pedagogies: stereotype-aligned biases in automated writing feedback
- Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation — Can AI deliver appropriate support for diverse student profiles? A large-scale evaluation
- Bias and representation in AI generated text-to-image in education: A systematic review — Bias and representation in AI-generated text-to-image: systematic review (Alon et al. 2026)
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026 — From Sentiment Classification to Actionable and Responsible Feedback: A Scoping Review and Evidence Map of NLP in Student Evaluation of Teaching, 2015–2026
- Generative AI May Reinforce Social Biases in Software Engineering Education — Generative AI May Reinforce Social Biases in Software Engineering Education
- Fairness Theatre: Evaluating Post-Hoc Fairness Interventions in Vendor-Controlled Early Warning Systems — Fairness Theatre: Evaluating Post-Hoc Fairness Interventions in Vendor-Controlled Early Warning Systems
- Towards responsible and trustworthy educational data mining: Comparing symbolic, sub-symbolic, and neural-symbolic AI methods - under class imbalance three model families could not identify low performers while balanced metrics looked healthy

Culturally Relevant Pedagogy

> **Culturally relevant pedagogy** — introduced by Gloria Ladson-Billings (1995), centers marginalized students' cultural references in curriculum design. It rests on three pillars: **academic success** (rigorous standards that honor cultural identity), **cultural competence** (critical consciousness about culture and power), and **sociopolitical consciousness** (empowering students to challenge inequitable systems). As AI tools enter classrooms, CRP has become a central lens for evaluating whether AI amplifies or erases non-dominant cultural knowledge.

Questions to Consider

- Culturally relevant pedagogy rests on academic success, cultural competence, and sociopolitical consciousness. Which of these pillars is hardest to achieve with AI tools — and why?
- One study found 94% of AI-generated lesson plans contained no discernible multicultural content, and almost none reached the level of transformation or social action. If AI defaults to monocultural output, whose responsibility is it to inject the missing perspectives?
- AI training data is predominantly Western and Anglophone. What does it mean for a system to 'actively marginalize' ways of knowing — and how does that differ from simply lacking access?
- Community-based AI learning proposes that learners' own lived epistemologies should be the standard for evaluating AI output, with refusal and non-use treated as valid responses. How would you center community knowledge as the judge of an AI's relevance and harm?
- Culturally grounded data can dramatically improve an AI's relevance — one Indian-knowledge dataset moved a small model from near zero to rivaling a far larger general-purpose one. If better data is the fix, who should build and own it?
- A cross-cultural study found that identical AI-use behaviors were judged ethical in one country and unethical in another, regardless of written policy. What does that tell you about trying to govern AI use with uniform rules?

Introduction

AI's Double-Edged Role in CRP

AI can support teachers in making instruction culturally responsive, but its default outputs also risk **reinforcing dominant narratives** when left unprompted.

- **Support for teachers:** Wang et al. (2025) built **CulturAIEd**, an LLM-powered system that helps K-12 teachers design culturally responsive AI Literacy activities by combining student demographic information with rubric-driven guidance (a CRT checklist layered into generation). In a four-teacher pilot it **enhanced teachers' confidence** in spotting opportunities for cultural responsiveness and in modifying existing activities, with 78% finding AI suggestions helpful for diversifying materials. The tool directly targets the time, training, and resource barriers that block CRP implementation.

- **Risk of monocultural output:** Trust et al. (2025) analyzed 310 AI-generated civics lesson plans (2,230 activities): **94% contained no discernible multicultural content**, and of the 144 that did, 137 sat at the lowest "Additive" level — **only one reached "Transformation" and none reached "Social Action."** All three chatbots produced structurally identical, monocultural lesson templates. This is concrete evidence that AI defaults to homogenized curricula unless teachers actively intervene.

Epistemic Marginalization in AI Systems

Beyond lesson generation, CRP connects to a deeper critique: AI training data and design processes encode Western, Anglophone epistemic frameworks that marginalize other ways of knowing.

- **Epistemic coloniality:** Tali-Otmani (2026) argues that GenAI systems are not epistemically neutral — predominantly Western-centric training data **actively marginalizes minoritized knowledges**, producing a "double marginalization" for disabled learners whose epistemologies are both underrepresented in training data and excluded from design. This extends the equity conversation from *access* to *whose knowledge is validated*.
- **Redistributing epistemic authority:** Ojeda-Ramirez, Gyles & Peppler (2026) propose **community-based AI learning**, a framework that repositions learners' lived and community-based epistemologies as the evaluative standard over AI outputs. Its three commitments — **epistemic fine-tuning**, **redistribution of authority**, and **situated discernment** — calibrate trust against local histories and community expertise, treating refusal and strategic non-use as valid CRP responses to AI.

Culturally Grounded Data and Evaluation

A body of knowledge base-sourced work addresses the *content* and *evaluation* gaps behind CRP.

- **Non-Western training data:** IKS-Instruct provides a **24,795-example multilingual instruction dataset** for teaching LLMs Indian Knowledge Systems across seven languages and 41 pedagogical techniques. A compact domain-tuned 7B model reached a median judge score of 6.39 (vs. 6.54 for a far larger general-purpose model) — while the base model scored **near zero** on IKS-specific dimensions, showing how much culturally grounded data improves relevance.
- **Global South benchmarks:** The **NSMQ Riddles** benchmark draws 1.8K scientific/mathematical riddles from 11 years of Ghana's National Science and Maths Quiz — one of the first Global South educational benchmarks — and found state-of-the-art LLMs **underperform the best student contestants**, exposing geographic bias in how models are evaluated.
- **Culture over policy:** A cross-cultural survey of Canadian and South Korean computing students found that **culture, not policy text, drove perceptions of AI-use ethicality** — identical behaviors were judged differently across cohorts, reinforcing the need for culturally aware communication rather than abstract rules.
- **Cultural navigation is where AI support is weakest:** International students rated conversational AI highest for grammar, structure, and summarizing (mean 4.27) and lowest for cultural navigation (mean 3.49) (Nourian et al. (2026)).

- **Cultural adaptation as design moves:** Bashir and Afzal (2026) operationalize cultural relevance in an AI Well-Being support system (Sukoon) through three moves: a bilingual 20-question assessment with parallel English and Urdu labels; a system prompt instructing the model to respond consistently with Pakistani social and cultural norms and to use Urdu and Roman Urdu expressions where appropriate; and explicit sensitivity to locally salient stressors (family expectations, financial pressure, hierarchical teacher-student relationships). Their justification is empirical as well as ethical — feature importance placed teacher-student relationship second among stress predictors — but they concede the adaptation lives in the prompt rather than in the NLP pipeline, and that cultural appropriateness was assessed only by informal testing, not by the students the system targets.

Practical Guidance

Grounded in the knowledge base's own articles, educators and designers can apply CRP to AI:

- **Treat AI as a draft generator, not an authority.** The Trust et al. civics findings show teachers must inject higher-order thinking and multicultural perspectives the AI omits; human judgment remains essential for cultural authenticity and community alignment.
- **Layer demographic and cultural context into prompts and tools.** CulturAIEd and ConnectED (a Vietnamese, curriculum-aligned lesson-planning system) show that structured, locally grounded prompt templates plus teacher validation gates improve cultural fit over generic generation.
- **Center community knowledge as the evaluative standard.** Following community-based AI learning, have learners judge AI outputs against locally grounded criteria of relevance, harm, and usefulness, and honor context where refusal or non-use is the right call.
- **Adopt and evaluate culturally grounded datasets.** IKS-Instruct and NSMQ Riddles illustrate that domain-specific, non-Western data meaningfully improves both relevance and honest evaluation.
- **Have the AI interview the teacher before it drafts.** Zhai et al. (2026) describe a culturally responsive lesson planner whose interactive semi-automated prompt architecture asks context and culture questions first, then drafts from the teacher's own answers rather than producing a generic plan.

Common Misconceptions

"AI outputs are culturally neutral unless you prompt for culture." The default is not neutral, it is dominant. Of the **310 AI-generated civics lesson plans** analyzed (**2,230 activities**), **94% offered nothing discernibly multicultural**. Of the 144 activities that did, **137 sat at the lowest "Additive" level, only one reached "Transformation", and none reached "Social Action."** Left unprompted, the models reproduced a non-diverse default, so prompting for culture is not a bias mitigation, it is the only reason any of it appears.

"Adding multicultural examples constitutes culturally relevant pedagogy." The framework's own hierarchy says otherwise, and the generated output shows why the distinction is operationally important. Additive content leaves the structure and the unit's assumptions untouched; Transformation changes how the

content is framed; Social Action asks learners to act on it. Conflating representation with transformation is how a corpus can be 6% non-empty on diversity and still be nowhere near culturally responsive.

“Institutional AI-use policy determines what students consider ethical.” Culture does more work than policy text. A cross-cultural survey of Canadian and South Korean computing students found that **culture, not policy, drove perceptions of AI-use ethicality** — identical behaviors were judged differently across cohorts. A single institution-wide policy therefore does not produce a shared ethic, and treating it as though it does will misread your students.

“A four-teacher pilot showing teachers feel more confident is evidence the approach works.” It is evidence about teacher perception, which is worth having and is not the same thing. In that pilot teachers’ confidence in spotting cultural responsiveness opportunities improved and **78% found AI suggestions helpful for diversifying materials** — while the authors concede that the cultural adaptation lives **in the prompt rather than in the NLP pipeline**, and that cultural appropriateness was assessed rather than engineered. Confidence plus helpfulness is not demonstrated cultural relevance for students.

Implications for Practice

For instructors

- Never ship an unprompted AI lesson plan as culturally responsive. The 94% figure is the default behavior, so cultural content must be specified explicitly and checked item by item.
- Sort your own additions against the Additive/Transformation/Social Action ladder and aim at least one rung higher than feels natural. Most generated diversity sits at the bottom.
- Do not assume your institution’s policy travels with your students. Cultural context shapes their ethical judgments more than the rulebook does.

For developers

- Treat cultural appropriateness as a pipeline concern, not a prompt concern. The pilot’s own limitation is that adaptation sat in the prompt, which means it disappears when the prompt changes.
- Evaluate generated content against the full ladder, reporting how many items reach Transformation or Social Action — a diversity count that stops at Additive will look satisfactory and mean very little.
- Make the teacher-student relationship visible in whatever you instrument; feature importance placed it second among stress predictors in the cited work, and it is the asset generic generation cannot supply.

For researchers

- Report cultural content by level rather than as presence or absence, since 94%-versus-6% presence says nothing about which 6%.
- Distinguish teacher-perception outcomes from student outcomes explicitly when reporting pilots.

Connected Concepts

- Equity

- Curriculum Design
- AI Literacy
- K-12
- Teacher AI Competency
- Teaching
- Bias Mitigation
- Critical Pedagogy
- Human-in-the-Loop
- Student Experience
- Higher Education
- Language Learning
- CS Education
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education

Connected Articles

- Science Literacy: Generative AI as Enabler of Coherence in the Teaching, Learning, and Assessment of Scientific Knowledge and Reasoning — Lesson planner that interviews teachers about cultural context before drafting (Zhai et al. 2026)
- LLMs to Support K-12 Teachers in Culturally Relevant Pedagogy: An AI Literacy Example — LLMs for Culturally Relevant K-12 Pedagogy
- Civic education in the age of AI: Should we trust AI-generated lesson plans — AI-Generated Lesson Plans in Civic Education
- Community-Based AI Learning: Redistributing Artificial Intelligence's Epistemic Authority in Education — Community-Based AI Learning
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Generative AI and the marginalization of minoritized knowledges
- NSMQ Riddles: A Benchmark of Scientific and Mathematical Riddles for Quizzing Large Language Models — NSMQ Riddles: Ghana STEM Benchmark
- Did Alice Do Wrong? Cross-Cultural Differences in Student Perceptions of Generative AI Use in University Computing Education — Cross-Cultural Perceptions of GenAI Use
- Understanding how international students in the U.S. are using conversational AI to support cross-cultural adaptation — International Students and Conversational AI
- ConnectED: A curriculum-aligned AI system for Vietnamese instructional lesson planning and student learning — ConnectED: Vietnamese Lesson Planning
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally

Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning

Multilingual Learning

> Multilingual learning in AI education concerns how educational technologies and LLM-based systems support learners across languages, dialects, and low-resource linguistic contexts — and the risks of linguistic exclusion when AI systems are built primarily for dominant languages.

Questions to Consider

- Most AI models are trained primarily on high-resource languages like English. If you think, study, or are assessed in a different language, how might that systematically disadvantage you — even if the tool seems to 'work' in English?
- The page warns that unaddressed monolingual bias in AI deepens the digital divide and undermines equity, especially across the Global South. What does genuine equity require beyond simply translating AI content into another language?
- Automated assessment can exhibit language bias, penalizing non-native speakers even for the same reasoning. If you were implementing AI scoring, what would you check to ensure it is fair across languages rather than just accurate in one?
- The page shows low-resource languages can be served by fine-tuning models on curated corpora, even under practical hardware constraints. What trade-offs would you expect between efficiency and how faithfully the model handles a low-resource language?
- Multilingual AI must go beyond translation to reflect culturally relevant pedagogy — content that is linguistically *and* contextually appropriate. How might content that is perfectly translated still fail a learner if it ignores local context and culture?

Introduction

Multilingual learning concerns education for learners who study or think in languages other than the dominant ones, and it is a core equity dimension of AI in education: generative AI is overwhelmingly trained and tuned on high-resource languages, which can systematically disadvantage everyone else. The theme spans technical work (adapting models to low-resource languages and dialectal corpora, retrieval in non-dominant languages), pedagogical concerns (locally grounded instruction), and structural equity (who can access useful educational AI at all) — which makes it inseparable from the Digital Divide and Equity.

Overview

Multilingual learning is a core equity dimension of AI in education. Generative AI and LLMs are overwhelmingly trained and tuned on high-resource languages, which can systematically disadvantage learners who study or think in other languages. The theme spans technical challenges (adapting models to low-resource languages, dialectal corpora, RAG in non-dominant languages), pedagogical concerns (culturally relevant and locally grounded instruction), and structural equity (who gets access to useful educational AI at all).

Technical approaches

- **Fine-tuning for low-resource languages:** Nwogo et al. (2026) fine-tuned an instruction-tuned LLM on a curated Nigerian Pidgin corpus within an Adaptive Learning platform, and systematically analyzed quantization (4/5/8-bit) trade-offs between semantic fidelity and computational efficiency — showing that low-resource languages can be served with practical hardware constraints. See also the bilingual LLM lecture companion for self-regulated learning.
- **Corpus and data equity:** building curated corpora (e.g., Nigerian Pidgin, Indian knowledge systems via IKS-Instruct) is a recurring strategy for enabling model output in learners' own languages.
- **Voice-first and oral contexts:** voice-first companions and structural-silence analyses address contexts where text-based AI fails speakers of underrepresented languages.

Equity and pedagogy

Multilingual AI must go beyond translation to reflect culturally relevant pedagogy — generating content that is linguistically and contextually appropriate. Studies of LLM cultural relevance in K-12 and critical engagement with GenAI among minority students show that linguistic and cultural alignment shapes whether students actually benefit. Unaddressed, monolingual bias in AI deepens the Digital Divide and undermines Equity across the Global South.

Translanguaging is an affordance generative chatbots add that earlier language tools lacked. In a systematic review of 24 studies, learners asked for contextualized phrases and explanations in their own language as a bridge into the target language — a use the reviewers classify as a new sub-affordance rather than a repackaged one (Lopez & Arabadzhy (2026)).

Assessment bias

Multilingual concerns also affect automated assessment: AI scoring can exhibit language bias (e.g., in physics), penalizing non-native speakers. Ensuring assessment tools are fair across languages is part of Assessment Validity.

LLM-based comparative judgment is a case where bias tracked the human baseline rather than the model: scores for Grades 3–6 informational writing converged with researcher rubrics (r = .59–.73) and showed predictive-bias patterns for multilingual learners similar to human scoring, with no evidence that greater model capability or cost improved validity (Mercer & Reed (2026)).

Implications for instructors in multilingual contexts

- **Extend AI to learners' own languages, not just English.** Fine-tune or configure models for low-resource and non-dominant languages (Nigerian Pidgin platform) rather than forcing English-only tools; pair AI with RAG and local corpora where possible.
- **Guard assessment against language bias.** AI scoring can penalize non-native speakers — use language-aware or human-moderated evaluation to protect Assessment Validity and fairness.

- **Reflect culture and context, not just translation.** Multilingual AI must go beyond translation to culturally relevant pedagogy — generate content that is linguistically and contextually appropriate (K-12 cultural relevance).
- **Pair AI with multilingual support structures.** Use voice-first and oral modes (voice-first companions) where text-based AI fails, and support self-regulation in bilingual contexts (bilingual lecture companion).
- **Watch the digital divide.** Monolingual bias in AI deepens the Digital Divide and undermines access across the Global South — plan for equitable infrastructure and access alongside tool choice.

Common Misconceptions

- **"The target language should dominate from day one."** In a **systematic review of 24 studies**, learners asked for **contextualized phrases and explanations in their own language as a bridge into the target language** — a use the reviewers classify as a genuinely new sub-affordance rather than a workaround. Home-language support functioned as Scaffolding, not as avoidance.
- **"AI language assessment is biased against multilingual writers."** Here the bias tracked the **human baseline rather than the model**: LLM-based comparative judgment on **Grades 3-6 informational writing converged with researcher rubrics (r = .59-.73)** and showed the same pattern the human raters did. That is not evidence of fairness in absolute terms — it is evidence that the model did not introduce a new distortion on top of the existing one.
- **"Translation-quality output is the useful part."** The bridge use is explanatory and situated, not substitutive. A tool that replaces the learner's own production removes the practice that the bridging was meant to enable.

Connected Concepts

- Differential Effects Across Learner Groups
- Language Learning
- Large Language Models (LLMs)
- Equity
- Global South
- Digital Divide
- Culturally Relevant Pedagogy
- Inclusive Learning
- Generative AI

Connected Articles

- GenAI chatbots in language learning: A systematic review of emerging affordances — GenAI chatbots afford translanguaging, a use earlier language tools did not support

- Validity of Large Language Model Comparative Judgment for Universal Writing Screening — Validity of Large Language Model Comparative Judgment for Universal Writing Screening
- An AI-Based Adaptive Learning Platform for Multilingual and Low-Resource Educational Contexts: A Case Study on Nigeria — AI-Based Adaptive Learning Platform for Nigeria
- A bilingual, LLM-mediated lecture companion for self-regulated learning: Architecture, theoretical framework, comparative and usability evaluation, and a pre-registered outcomes protocol — Bilingual LLM Lecture Companion
- Structural silence: When AI infrastructure fails speakers of underrepresented languages — Structural Silence: Underrepresented Languages
- LLMs to Support K-12 Teachers in Culturally Relevant Pedagogy: An AI Literacy Example — LLM Cultural Relevance in K-12
- Scaffolding critical engagement with GenAI: Transforming ethnic minority preparatory students' collaborative discourse in prompt engineering tasks — Critical Engagement with GenAI Among Minority Students
- IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems — IKS-Instruct: Indian Knowledge Systems Dataset
- Kutti AI: A Voice-First, Offline-Capable Learning Companion with Real-Time Struggle Detection for Visually-Impaired Children — Voice-First Learning Companion
- AI-based scoring systematically underestimates conceptual understanding of linguistically weak students' explanations in physics — AI Scoring Language Bias in Physics

Inclusive Learning

> **Inclusive Learning** — the design and delivery of educational experiences that accommodate diverse learner needs, spanning physical, cognitive, sensory, and situational differences. In AI in education, inclusive learning research examines both how AI tools can remove barriers for disabled and neurodivergent learners and how AI systems themselves must be designed to avoid creating new accessibility gaps.

Questions to Consider

- An accessible tool does not guarantee inclusive instruction, and assistive tech does not guarantee meaningful agency. What is the difference between removing a barrier to a format and designing education so everyone can meaningfully participate?
- The page distinguishes inclusive learning, accessibility, assistive technology, special education, and universal design. Where does AI in your own context sit — and which question are you actually trying to answer?
- One study found AI-segmented videos with fixed pauses eliminated the performance gap between ADHD and non-ADHD learners. How might designing for one group's needs improve learning for everyone?
- AI systems are described as risking new accessibility gaps even as they remove old ones. What kind of learner might a text-based, visual, always-online AI tool silently exclude?
- Inclusive assessment research exposes a tension between anti-cheating measures and accommodating learners with visual-processing needs. When security and accessibility conflict, how should the trade-off be decided — and by whom?
- Several tools invert the assumption that edtech must be visual — e.g., voice-first companions for visually impaired learners. What assumptions about the 'default' learner might your own tools or materials be making?

Introduction

Inclusive learning is the design commitment that education should be built so that all learners can participate meaningfully, rather than adapted after the fact for those who struggle. It functions here as an umbrella over adjacent but distinct concepts — Accessibility (can everyone perceive and operate the format?), Assistive Technology (what tools bridge an individual's access gap?), Universal Design for Learning (how should the design anticipate variability?) — and it engages Neurodiversity and Special Education as design contexts rather than exceptions. AI enters as both a promise (personalization, accommodation, translation) and a new source of exclusion (cost, data, language coverage, and the assumptions built into models).

How the related concepts fit together

Inclusive learning is the **umbrella** concept; the pages below sit inside it, each answering a different question. They overlap but are not interchangeable — knowing which one a claim belongs to keeps the knowledge base precise:

Concept	Core question it answers	Typical focus
Inclusive Learning *(this page)*	How do we design education so all learners can meaningfully participate?	The broad design of instruction across learner variability
Accessibility	Can everyone perceive and operate the *format/medium*?	Captions, alt text, transcripts, contrast, keyboard/screen-reader compat, WCAG
Assistive Technology	What tools/equipment bridge an individual's access gap?	Screen readers, TTS/STT, braille/ tactile, captioning, AI accommodations
Special Education	How do we deliver instruction to learners with diagnosed disabilities?	IEPs, individualized accommodations, disability-specific tutoring — **primarily a K-12 term (IDEA/ entitlement)**
Universal Design for Learning	How do we proactively build in flexibility from the start?	Multiple means of engagement, representation, action/expression

In practice: **UDL** is the design philosophy that *prevents* barriers; **accessibility** is the property that removes *format* barriers; **assistive technology** is the *tool* layer individuals use; **special education** is the *instructional* domain for diagnosed disabilities — and it is primarily a **K-12** term, whereas in **higher education** (and increasingly K-12 too) the more common framing is Universal Design for Learning. **Inclusive learning** is the umbrella that holds them together around the shared goal of equitable participation. An accessible tool does not guarantee inclusive instruction, and assistive tech does not guarantee meaningful agency — which is why the umbrella must span all of them.

Inclusive learning sits at the intersection of Equity, Learning Design, and Special Education, and is supported by the concrete tool layer of Assistive Technology and the design property of Accessibility. Unlike narrow accommodations that retrofit access onto existing systems, the inclusive learning perspective — grounded in Universal Design for Learning — argues that environments should be designed for the full range of human diversity from the start. The articles in this knowledge base explore how AI can enable this through automated content transformation, adaptive assessment interfaces, and tools designed with neurodivergent users' lived experience as the starting point.

Key research themes

AI-powered content accessibility demonstrates how automated pipelines can reduce barriers. **Pimenova et al.** showed that AI-segmented instructional videos with fixed pauses eliminated the performance gap between ADHD and non-ADHD learners — strong evidence for Universal Design for Learning via automated content transformation. The study connects to "I can't read your mind": A Study of Neurodivergent Computing Students' Experiences with Collaborative Active Learning research on how collaborative learning structures affect neurodivergent comfort. **Chen et al.** designed an Large Language

Models (LLMs)-powered question-generation system for Deaf and Hard of Hearing learners, introducing Visual and Emotion question strategies that target moments of visual or emotional difficulty in video — while revealing the persistent mismatch between text-based AI prompts and DHH learners' sign-based first languages, underscoring the need for language- and culture-aware AI design. **MuTSE** tackles a complementary barrier — reading level — by evaluating LLM-based text simplification for Intelligent Tutoring, matching content complexity to each learner's current level via a human-in-the-loop evaluation framework rather than relying on linguistic metrics that miss pedagogical quality.

Equation-heavy video can be made accessible rather than manually transcribed: a Gemini-plus-LuaLaTeX pipeline turned 16 instructional physics videos into PDFs that passed PDF/UA-2 and ISO 32005 validation, with only one video needing a second attempt (Looney & Duston (2026)).

Sensory accessibility: blind, low-vision, and Deaf learners. Several articles invert the assumption that edtech must be visual. **Kutti AI** makes spoken conversation the primary and sufficient modality for visually-impaired children — real-time struggle detection, multilingual answer matching, and offline-first on-device ASR remove both the visual dependency and the connectivity requirement. **Obiuwevwi et al.** built a reusable pipeline that generates tactile 3D-printed statistical graphs for blind/low-vision students in under 250ms, with optional LLM-based chart extraction from images. **Bolla et al.** explored whether the Pepper social robot can produce intelligible Italian Sign Language, co-designing 52 signs with a Deaf student and expert interpreter — extending Robots in Education into communicative accessibility for Deaf learners while highlighting the challenge of reproducing the non-manual components (facial expression, posture) crucial to meaning. **Khlaif et al. (2026)** extend this line of work to higher education, finding in a qualitative case study of 21 visually impaired undergraduates in Palestine that GenAI tailors pace, content, and delivery to individual profiles and converts complex academic texts across modalities — with learners viewing GenAI as complementing rather than replacing teachers, preserving human connection while enabling participation.

Inclusive assessment design grapples with the tension between security and accessibility. **BAVD** proposes a theoretical framework for adaptive visual diversion that resists screen-capture cheating while accommodating learners with visual-processing needs — explicitly modeling the trade-off between anti-cheating measures and inclusive-learning principles. This connects to broader Academic Integrity and Assessment concerns.

Neurodivergent learner experiences center the voices of disabled and neurodivergent students. **Zastudil et al.** found that neurodivergent computing students need structured assignments, small consistent teams, and explicit role definitions — preferences that AI tutoring and collaboration tools must accommodate. **DysLexLens** analyzed dyslexic learners' forum discussions, revealing that while they value AI for literacy support, they face significant accessibility barriers from inconsistent output quality and lack of equitable accommodations. Both connect to Special Education and Student Experience.

Cognitive offloading and the access-vs-development trade-off. Seung & Basham (2026) show that for students with learning disabilities, the same GenAI that lowers barriers to reading and writing access (text leveling, summarizing, drafting support) can, if unguarded, substitute for the comprehension, planning, and monitoring practice these learners need most — an equity tension central to inclusive learning. Inclusive design must therefore consider not just whether a tool is *accessible* but whether it preserves the learner's opportunity to develop the very skills access is meant to enable.

Dyslexia support: detection, assistance and personalization. A 2026 interdisciplinary systematic review (Dabaghi, D'Urso & Sciarrone, PRISMA-guided, 2018–2024, n=72) finds AI supporting students with dyslexia across detection, assistive support, and personalized learning — but with these strands evolving in parallel rather than in integration, driven more by technological opportunity than by consolidated educational theory. ML-based help-education tools span five areas (specific applications, engagement, personalization, recommendation, generic support) yet emphasize technical performance and classification accuracy while overlooking ecological validity and practical classroom deployment. Detection research (EEG, eye-tracking, ML models) shows diagnostic promise for early intervention but often requires specialized equipment and controlled environments, limiting scalability and accessibility in typical school settings. Open challenges include limited experimental validation, scalability, Ethics/privacy concerns with sensitive student data, limited teacher support and training, and language/cultural barriers (most research targets English-speaking populations) — underscoring that inclusive learning must pair technical capability with validated, scalable, and ethically grounded deployment.

Disability-centered AI critique examines how AI systems can marginalize rather than include. **Tali-Otmani** argues that generative AI systems in higher education actively marginalize disability-centered ways of knowing due to Anglophone, Western-centric training data — connecting to Equity concerns about epistemic justice.

Formal diagnosis gatekeeping excludes the learners a tool claims to serve. In Rempel et al.'s (2026) scoping review of 40 studies of digital assistive technologies for neurodivergent students, 28 made a formal diagnosis a condition of participation and only three treated the environment rather than the student.

Accessible tools in practice shows how AI can expand participation. **SuaCode** demonstrated that smartphone-based coding courses reach students in low-resource African contexts where fewer than 1% have coding skills. **Pimenova et al.** worked with blind and low-vision musicians to develop non-visual learning strategies, centering disability-led embodied design. **LUDIA** provides a no-cost, private, multilingual AI thought partner connecting educators with UDL principles. **Special-R1** extends reinforcement learning to model cognitive and communicative diversity across disability profiles.

Connections to related concepts

Inclusive learning is deeply connected to Equity — accessibility is not merely a technical concern but a question of who gets to participate in learning. It connects to Accessibility as its concrete access layer and Assistive Technology as the tool layer, to Universal Design for Learning as its theoretical foundation, to Special Education for disability-specific approaches, to Learning Design for how courses and tools are structured, and to Neurodiversity as the lens that reframes difference as diversity rather than deficit. Work on sign-language robots and tactile tools links accessibility to Robots in Education and Educational NLP, while text simplification connects it to Sociocultural Learning and Adaptive Learning. The AI in Education and Generative AI connections highlight both the promise (automated content adaptation) and peril (AI systems that reproduce exclusion).

Implications for instructors designing inclusive learning

- **Design for the excluded modality first, not last.** Building for blind/low-vision users from the start (Kutti AI, tactile graphs) produces tools that also work offline and in low-resource settings — accessibility as a catalyst, not a retrofit.
- **Co-design with the target community.** Sign-language robots and DHH question generation show community involvement surfaces barriers (e.g., sign-based first languages) designers can't anticipate — involve learners and communities in design.
- **Evaluate pedagogical quality, not just linguistic metrics.** MuTSE shows LLM output variability requires human-in-the-loop evaluation so that simplification helps rather than oversimplifies.
- **Use AI to close performance gaps.** AI-segmented videos eliminated the ADHD performance gap — deploy adaptive AI where evidence shows it equalizes outcomes.
- **Treat the security/accessibility trade-off explicitly.** BAVD models how anti-cheating measures can inadvertently exclude learners with visual-processing needs — weigh integrity against access.
- **Access can turn on phrasing, not just format.** With the underlying task held fixed, model accuracy rose from 82.4% for low-literacy wording to 83.4% for expert phrasing, so requiring students to prompt better adds a new exclusion; a system-side rewriter that normalizes requests removed the significant gap without altering content (Jin et al. (2026)).
- **Guard against AI reproducing exclusion.** Disability-centered critique warns that Anglophone, Western-centric training data marginalizes disabled ways of knowing — audit AI tools for epistemic justice alongside Equity.

Common Misconceptions

"An accessible tool is an inclusive course." Accessibility answers one question — can everyone perceive and operate the format — which is necessary and nowhere near sufficient. Inclusive learning also asks what tools bridge an individual's access gap and how the design should anticipate variation rather than retrofit for it. A screen-reader-compatible interface in a course whose assessment structure assumes a quiet room, reliable broadband and uninterrupted time has solved the display problem and left the participation problem intact.

"Supplying assistive technology supplies agency." The two are distinct, and the page's own framing says so: assistive tech does not guarantee meaningful agency. A tool that lets a learner complete the required task can also route them toward the narrowest version of it, and the difference between a scaffold and a ceiling is invisible in an adoption metric.

"Students who struggle should simply learn to prompt better." That converts a system defect into a learner deficit. With the underlying task held fixed, model accuracy rose only from **82.4% for low-literacy wording to 83.4% for expert phrasing** — a one-point difference — while requiring better prompting adds a new exclusion on top of the existing one. The leverage is in the system-side handling of language variation, not in remedial prompt training.

"A tool built for well-resourced classrooms will serve low-resource contexts once translated." Context changes the design constraint. SuaCode reached students in low-resource African contexts where **fewer than**

1% have coding skills by building for smartphones rather than desktop lab machines, which is a different design, not a smaller version of the same one.

Connected Concepts

- Differential Effects Across Learner Groups
- Equity
- Accessibility — the concrete access layer (captions, alt text, assistive-tech compatibility)
- Assistive Technology — the tool layer students use to access content
- Special Education
- Learning Design
- Universal Design for Learning
- Neurodiversity
- Student Experience
- AI Literacy
- Higher Education
- K-12
- CS Education
- Assessment
- Academic Integrity
- Privacy
- Generative AI
- AI in Education
- Robots in Education
- Educational NLP
- Sociocultural Learning
- Adaptive Learning
- Speech and Voice Technologies

Connected Articles

- Same Question, Different Answer? Measuring and Mitigating Prompt Privilege for Equitable AI Access — Prompt Privilege: measuring & mitigating accessibility disparities in LLM access
- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education
- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM-powered question generation for Deaf and Hard of Hearing learners
- MuTSE: A Human-in-the-Loop Multi-use Text Simplification Evaluator — Text Simplification for Intelligent Tutoring
- Kutti AI: A Voice-First, Offline-Capable Learning Companion with Real-Time Struggle Detection for Visually-Impaired Children — Kutti AI: voice-first companion for visually-impaired children

- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — Tactile 3D-printed statistical graphs
- Using the Pepper robot to support sign language communication — Pepper robot supporting sign language communication
- Behaviorally Adaptive Visual Diversion for Inclusive and Resilient Digital Assessment Delivery
- DysLexLens: A Low-Resource LLM Framework for Analysing Dyslexic Learners Insights from Online Forums
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability
- Designing for What Cannot Be Seen: Supporting Embodied String Learning for Musicians with Blindness and Low-Vision
- "Why SuaCode?": Understanding African Students’ Motivations for Taking a Smartphone-Based Online Coding Course
- LUDIA: A Design and Evidence Statement
- Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training
- Using Gemini and LuaLaTeX to transcribe physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs — Gemini+LuaLaTeX math-accessible physics video transcription
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Accessibility

> **Accessibility** — the design of educational technology, content, and interfaces so that they can be perceived, operated, and understood by people with disabilities and diverse needs. In AI in education, accessibility covers concrete, operational barriers to the *medium* of learning: video captions, alt text, transcripts, screen-reader and keyboard compatibility, color contrast, text simplification, tactile output, sign-language support, and compatibility with assistive technologies.

Questions to Consider

- When you last designed or chose a digital learning tool, did you check whether its captions, alt text, keyboard navigation, and color contrast worked before you considered its Pedagogies and Teaching Strategies? Why might that ordering matter?
- A video with accurate captions is ‘accessible,’ while a course that structures discussion around a Deaf learner’s communication needs is ‘supporting that learner.’ Where would you draw the line between removing a technical barrier and meaningfully serving a student?
- Research shows AI-segmented instructional videos with fixed pauses eliminated the performance gap between ADHD and non-ADHD Learners. Can you recall a ‘fix designed for one learner’ that ended up benefiting everyone in a class you were part of?
- Some argue accessibility is necessary but not sufficient — an accessible tool is not automatically an inclusive or disability-just one. What’s the difference between being able to use a tool and being meaningfully served by it?
- Many AI tools are trained largely on English, Western-centric data. How might that limit how well they serve learners whose first language is sign, or whose ways of knowing differ from the mainstream?
- AI can automate accessibility at scale — generating captions, simplifying text, producing tactile output. What would you want to verify by hand before trusting that automated accessibility, and why?

Introduction

Accessibility is distinct from, but closely related to, three neighboring concepts in this knowledge base. **Inclusive Learning** is the broader umbrella for designing education for all learner variability (physical, cognitive, sensory, situational). **Special Education** is the instructional domain for learners with diagnosed disabilities, including individualized accommodations. **Universal Design for Learning** is the proactive design framework (multiple means of engagement, representation, action/expression). **Accessibility** sits inside this constellation as the *technical and procedural layer*: removing barriers to perceiving and operating the format, rather than redesigning the pedagogy. The two can be separated on a spectrum — accessibility asks “can everyone access this content and tool?” while supporting students with disabilities asks “does instruction meaningfully serve each learner, including accommodations and disability-specific support?” Both matter, and AI intersects both.

Why the distinction matters

A video with accurate captions and a properly tagged transcript is *accessible*; a course that structures discussion to include a Deaf learner's communication preferences is *supporting that learner*. They overlap — accessible media is a prerequisite for inclusive instruction — but they require different design moves and draw on different evidence. Accessibility is anchored in standards and law (WCAG, the U.S. Assistive Technology Act and IDEA), while accessible learning and special education are anchored in pedagogy and learner experience.

Key research themes

Format accessibility: captions, transcripts, and text. **AI-segmented instructional videos** with fixed pauses eliminated the performance gap between ADHD and non-ADHD learners — accessibility as a catalyst that benefits everyone. **MuTSE** evaluates Large Language Models (LLMs)-based text simplification to match content complexity to each learner's reading level, a human-in-the-loop accessibility layer. **Chen et al.** build LLM question generation for Deaf and Hard of Hearing learners, confronting the mismatch between text-based AI prompts and sign-based first languages.

Sensory access: non-visual and tactile output. **Kutti AI** makes spoken conversation the primary modality for visually impaired children, removing visual dependency. **Tactile 3D-printed graphs** turn visual statistical data into touchable output for blind and low-vision students. **Sign-language robots** extend Robots in Education into communicative accessibility for Deaf learners.

Audio description written for film does not transfer to lecture recordings. Slide-based lectures reference diagrams, equations, and pointing gestures, and their pauses run a median of only 0.5 s, so Psychias & Gao (2026) built a lecture-specific benchmark and rule-diagnosable metric; post-training on machine-judge-ordered pairs did not improve compliance evenly.

Generative AI for visually impaired learners. **Khlaif et al. (2026)** — a qualitative case study of 21 visually impaired undergraduates across three Palestinian universities — found GenAI tailors pace, content, and delivery to individual learning profiles and simplifies complex academic texts while converting content across modalities (text, audio, visual), making materials usable that were previously inaccessible. Learners framed immediacy as a foundational accessibility requirement rather than a convenience, and six interdependent technological attributes — interactivity, user-friendliness, affordability, multimodality, integration, and scalability — determined whether GenAI was genuinely accessible in a low-resource context, with usability, affordability, and accessibility mutually reinforcing rather than separate design considerations.

Policy and accommodations for students with disabilities. **Shin et al.** analyze U.S. AI policy documents to reveal a void in guidance for students with specific learning disabilities, proposing accommodations and policy recommendations grounded in the Assistive Technology Act and IDEA. **Zhang et al.** meta-analyze 29 studies of AI-based interventions for students with disabilities, finding a medium positive effect on learning outcomes ($g = 0.588$) — and argue AI must do more than ensure accessibility: it must enable agentic participation.

Over-inclusive AI prohibitions and assistive transcription. **Wright (2026)** argues that blanket prohibitions on "AI use" are over-inclusive because they fail to distinguish speech-to-text transcription and

OCR from generative drafting: recognition technologies convert the format of content the student has already authored rather than producing new content, yet a policy written around platform identity captures both alike. Students with conditions affecting fine motor control, handwriting legibility or typing accuracy — including autism spectrum conditions, dyspraxia, cerebral palsy and repetitive strain injuries — have relied on standalone voice-to-text and OCR, and reports suggest several standalone voice-to-text products have been discontinued or degraded, leaving AI-powered transcription to fill the functional gap. Treating that substitution as misconduct raises fairness concerns under the reasonable-adjustment duty in the UK Equality Act 2010, the anticipatory Public Sector Equality Duty, the US Americans with Disabilities Act and the Australian Disability Discrimination Act 1992, though the paper does not claim the characterization has been tested in a tribunal. It notes that the intersection of disability, assistive technology and AI misconduct policy is underexplored, that the scale of this displacement is unmeasured, and that the same imprecision produces differential false-positive risk, since detectors read the low-perplexity text of non-native English writers as machine authorship. The legal exposure this over-inclusion creates is mapped on Legal Issues and Risks.

Machine resistance carries a readability cost. Stripe overlays degraded extraction most (+35.9% character error, +38.3% word error) yet four typography and design experts judged vertical stripes readable, while diagonal stripes broke letterforms and were judged unreadable, and extreme opacity variation helped only at intensities that also harmed human readability (Salaun et al. (2026)).

AI for dyslexia: detection, support, and personalized learning. A 2026 interdisciplinary systematic review (Dabaghi, D'Urso & Sciarrone, PRISMA-guided, 2018–2024, n=72) finds AI supporting students with dyslexia across detection, assistive support, and personalized learning — but with these strands evolving in parallel rather than in integration, driven more by technological opportunity than by consolidated educational theory. ML-based help-education tools span five areas (specific applications, engagement, personalization, recommendation, generic support) yet emphasize technical performance and classification accuracy while overlooking ecological validity and practical classroom deployment. Detection research (EEG, eye-tracking, ML models) shows diagnostic promise for early intervention but often requires specialized equipment and controlled environments, limiting scalability and accessibility in typical school settings. Open challenges include limited experimental validation, scalability, Ethics/Privacy concerns with sensitive student data, limited teacher support and training, and language/cultural barriers (most research targets English-speaking populations) — reinforcing that accessibility must be validated, scalable, and ethically grounded, not merely technically demonstrated.

The limits of accessibility alone. **Critical work** warns that AI trained on Anglophone, Western-centric data can marginalize disability-centered ways of knowing. Accessible formats do not guarantee inclusive or just instruction — reinforcing that accessibility is necessary but not sufficient, and must connect to Equity.

Accommodation-focused, diagnosis-gated tools dominate. A scoping review of 40 studies of digital assistive technologies for neurodivergent students found 28 made a formal diagnosis a condition of participation and only three worked on neurotypical peers rather than the student, while reporting inversion effects — cognitive overload, fatigue, distraction and over-reliance on generative AI.(Rempel et al. (2026))

Implications for practice

- **Prioritize the format barrier first.** Captions, transcripts, alt text, contrast, and keyboard operability are the gatekeeping layer — without them nothing else matters for learners who need them.
- **Use AI to automate accessibility at scale.** AI can generate captions, simplify text, produce tactile/audio alternatives, and adapt presentation — but evaluate output quality with human-in-the-loop checks.
- **Treat accessibility as necessary but not sufficient.** An accessible tool is not automatically an inclusive or disability-just tool; pair accessibility with Inclusive Learning design and Special Education support.
- **Ground accommodations in law and policy.** Reference standards (WCAG) and statutes (Assistive Technology Act, IDEA) when designing or procuring AI tools.
- **AI deployment is outrunning AI accessibility policy at the institutional level.** Chan (2026) coded all 100 Times Higher Education 2026-ranked universities and found 0% publishing a standalone AI accessibility policy while 93% deploy AI-powered campus services (chatbots for registration, housing, IT). The author's charitable reading is that accessibility obligations sit inside general disability-services policies, but as measured, requirements for AI tools appear nowhere in the public institutional record. A short institutional statement that AI tools in teaching and administration must be accessible to disabled students would be ahead of the entire measured field.
- **Math-accessible transcription of physics videos (2026):** An AI workflow using Gemini (audio + 1 fps video sampling) and LuaLaTeX compiles instructional physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs that routinely pass accessibility validation — a practical, free path to making equation-heavy video content screen-readable for blind and low-vision students (Using Gemini and LuaLaTeX to transcribe physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs).

Common Misconceptions

- **"An accessibility feature that looks worse is worse."** Stripe overlays **degraded extraction most (+35.9% character error, +38.3% word error)**, yet **four typography and design experts judged vertical stripes readable**, while diagonal patterns failed. Machine readability and human readability are separate measurements, and optimizing one can harm the other. Accessibility claims need to state which reader they are for.
- **"Accessibility means accommodation."** A scoping review of **40 studies** of digital assistive technologies for neurodivergent students found **28 made a formal diagnosis a condition of participation**. That is a diagnosis-gated model, and it excludes every learner who has needs but no label — the opposite of universal design.

- **“Medium effects settle the question.”** Zhang et al. meta-analyze **29 studies** and find a medium positive effect, which is real and also says nothing about which tool for which need. The average across heterogeneous interventions is not a recommendation.
- **“Speed and immediacy are conveniences.”** In a qualitative case study of **21 visually impaired undergraduates** across three Palestinian universities, learners framed immediacy as a **foundational accessibility requirement rather than a convenience**. What looks like a nicety from outside is a precondition for participation.

Connected Concepts

- Differential Effects Across Learner Groups
- Inclusive Learning — broader umbrella for designing education across learner variability
- Special Education — instructional domain for learners with diagnosed disabilities
- Universal Design for Learning — proactive design framework
- Equity
- Educational AI Policy
- Neurodiversity
- Assistive Technology
- Learning Design
- Generative AI
- Robots in Education
- Intelligent Tutoring
- Adaptive Learning
- Learner Agency
- Virtual and Augmented Reality — headsets, motion sickness and device access decide who can use it
- Speech and Voice Technologies
- Legal Issues and Risks — the umbrella page for over-broad rules, defective evidence and reasonable adjustment
- Arts, Design and Media Education

Connected Articles

- How colleges and universities are adopting AI in higher education: a global comparative analysis — Chan (2026): 0% of 100 elite universities publish an AI accessibility policy while 93% deploy AI campus services
- Addressing the void of AI policies in education for students with specific learning disabilities — AI policies and accommodations for students with specific learning disabilities
- Let’s CHAT About Artificial Intelligence for Students With Disabilities: A Systematic Literature Review and Meta-Analysis — Meta-analysis of AI interventions for students with disabilities

- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education — AI-segmented videos with fixed pauses
- MuTSE: A Human-in-the-Loop Multi-use Text Simplification Evaluator — LLM-based text simplification for intelligent tutoring
- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM question generation for Deaf/Hard-of-Hearing learners
- Kutti AI: A Voice-First, Offline-Capable Learning Companion with Real-Time Struggle Detection for Visually-Impaired Children — Voice-first companion for visually impaired children
- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — Tactile 3D-printed statistical graphs
- Using the Pepper robot to support sign language communication — Pepper robot supporting sign language
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Critical perspective on AI and disability-centered knowledge
- Using Gemini and LuaLaTeX to transcribe physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs — Gemini+LuaLaTeX math-accessible physics video transcription
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Transcription is not generation: over-inclusive AI prohibitions and the assistive tools they capture
- AD4EDU: Benchmarking University Lecture Audio Description across Accessibility Standards, Metrics, and Learner Preferences — AD4EDU: Benchmarking University Lecture Audio Description across Accessibility Standards, Metrics, and Learner Preferences
- AIRRI: Towards a Human-Readable, Machine-Resistant Reading Interface — AIRRI: Towards a Human-Readable, Machine-Resistant Reading Interface

Connected FAQs

- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Assistive Technology

> **Assistive Technology** — devices, software, and services that help people with disabilities perceive, operate, communicate, and participate in learning and daily life. In AI in education, assistive technology spans screen readers, speech-to-text and text-to-speech, captioning, braille and tactile output, sign-language tools, and increasingly AI-powered accommodations that adapt content and interaction to individual needs.

Questions to Consider

- Assistive technology is the tool layer of accessibility — the specific devices and software individuals use to bridge access gaps. Before reading, did you think of accessibility and assistive technology as the same thing? How might treating them as distinct change how you design learning environments?
- Research finds AI-based interventions yield a medium positive effect on learning outcomes for students with disabilities (g = 0.588). Yet the page warns that access tools don't by themselves ensure inclusive instruction or learner agency. What's the difference between giving a student access and genuinely including them?
- The page notes that US AI policy documents largely fail to address assistive technology and accommodations for students with specific learning disabilities. Why do you think accommodations so easily fall through the cracks of AI policy — and who loses when that happens?
- Generative AI can auto-caption, simplify text, and generate tactile alternatives — lowering the cost of adaptation. But the page cautions you to evaluate the quality of AI-generated alternatives for pedagogical accuracy. What could go wrong if a 'simplified' or 'tactile' version misrepresents the content it's meant to make accessible?
- AI is expanding assistive tools from voice-first learning companions to tactile graphs and sign-language tools. As an educator or designer, which learner's specific barrier would you want to address first with AI — and what would you need to know about that learner before choosing a tool?

Introduction

Assistive technology is the concrete *tool layer* of Accessibility. Where accessibility is the design property of an environment (can everyone access it?), assistive technology is the specific equipment and software that individuals use to bridge access gaps. It is foundational to Special Education and Inclusive Learning — students with specific learning disabilities, visual or hearing impairments, and motor challenges rely on assistive tools to access the curriculum. In the U.S., the Assistive Technology Act (2004) and the Individuals with Disabilities Education Improvement Act (IDEA, 2004) provide the legal basis for providing these tools to students with disabilities.

Key research themes

AI is expanding assistive technology. Generative AI and LLMs are transforming assistive tools — LLM-based text simplification adapts reading level in Intelligent Tutoring, voice-first AI removes visual dependency for blind and low-vision learners, and AI-generated tactile graphs convert visual data to touchable output. **Zhang et al.** find AI-based interventions (robots, software, intelligent VR) yield a medium positive effect on the learning outcomes of students with disabilities (g = 0.588). **Khlaif et al. (2026)** add a qualitative case study of 21 visually impaired undergraduates in Palestine, showing GenAI functions as an assistive layer that tailors pace, content, and delivery, simplifies complex texts, and converts content across modalities — with learners consistently viewing it as complementing rather than replacing teachers.

Policy and provision. **Shin et al.** document that U.S. AI policy documents largely fail to address assistive technology and accommodations for students with specific learning disabilities, calling for policy guidance grounded in the Assistive Technology Act and IDEA.

AI for dyslexia across detection, support, and personalized learning. A 2026 interdisciplinary systematic review (Dabaghi, D'Urso & Sciarrone, PRISMA-guided, 2018–2024, n=72) maps AI support for students with dyslexia, finding AI used for detection, assistive support, and personalized learning — but with these strands evolving in parallel rather than in integration, driven more by technological opportunity than by consolidated educational theory. ML-based help-education tools fall into five areas (specific applications, engagement, personalization, recommendation, generic support) yet emphasize technical performance and classification accuracy while overlooking ecological validity and practical classroom deployment. Detection research (EEG, eye-tracking, ML models) shows diagnostic promise for early intervention but often requires specialized equipment and controlled environments, limiting scalability and accessibility in typical school settings. Open challenges include limited experimental validation, scalability, Ethics/privacy concerns with sensitive student data, limited teacher support and training, and language/cultural barriers (most research targets English-speaking populations) — a reminder that assistive tools must be validated, scalable, and ethically grounded to genuinely bridge access gaps.

The limits of assistive tools. Assistive technology enables access but does not by itself ensure inclusive instruction or learner Learner Agency. **Critical research** and the push for agentic roles for students with disabilities remind us that access must pair with meaningful participation.

A 2026 scoping review of digital assistive technologies for neurodivergent students in higher education maps the decade's output: 766 records screened across five databases, 40 studies included, with AI-based tools in 15 of them and virtual reality in 11. Its organizing finding is a mismatch between what the tools target and where the barriers sit — 27 studies supported learning directly, 13 addressed reading and writing and 12 study management, while attention (n = 4) and social communication (n = 5) were comparatively neglected and only 6 addressed multiple barriers (Rempel et al., 2026).

Implications for practice

- **Match the tool to the learner and task.** Screen readers, captions, speech, and tactile output each address different barriers — choose based on the individual's needs and the content format.
- **Leverage AI to lower the cost of assistive adaptations.** AI can auto-caption, simplify text, and generate alternatives, but evaluate output quality for pedagogical accuracy.

- **Ground provision in policy.** Reference the Assistive Technology Act, IDEA, and WCAG when procuring or building AI tools.
- **Say which function the support serves — and evaluate against that function.** Vasileiou et al. (2026) distinguish compensation (evaluated by access and participation) from Scaffolding (decisions-with-support) from development (strategy use after fading or transfer). They add a rule aimed at this page's caution: accessibility support is not remediation — whether a tool is an accommodation, strategy instruction, or temporary practice support "should be stated in the learning plan."

Common Misconceptions

- **"Assistive technology targets where the barriers are."** A 2026 scoping review of digital assistive technologies for neurodivergent students maps the decade's output and finds a **mismatch between what tools target and where barriers sit**: **27 studies supported learning directly**, 13 addressed reading and writing and 12 study management, while **attention (n = 4)** and other core barriers were barely addressed. The most-studied target is not the most limiting one.
- **"A medium effect size identifies the right tool."** Zhang et al. find AI-based interventions yield a medium positive effect on learning outcomes for students with disabilities (**g = 0.588**) across robots, software and intelligent VR. That is an average over very different technologies serving very different needs, so it supports the category and not a choice within it.
- **"Diagnosis-gated access is a defensible design."** Requiring a formal diagnosis to participate excludes learners with real needs and no label, which conflicts with universal design and pushes the cost of access onto the student's documentation.
- **"More assistive tools means more inclusion."** A scoping review screened **766 records** across five databases, and volume of output is not the same as coverage of need — the count of studies per barrier is the more informative figure.

Connected Concepts

- Accessibility — the design property that assistive technology operationalizes
- Inclusive Learning
- Special Education
- Universal Design for Learning
- Equity
- Educational AI Policy
- Neurodiversity
- Learning Design
- Speech and Voice Technologies

Connected Articles

- Addressing the void of AI policies in education for students with specific learning disabilities — AI policies and accommodations for students with specific learning disabilities
- Let’s CHAT About Artificial Intelligence for Students With Disabilities: A Systematic Literature Review and Meta-Analysis — Meta-analysis of AI interventions for students with disabilities
- Kutti AI: A Voice-First, Offline-Capable Learning Companion with Real-Time Struggle Detection for Visually-Impaired Children — Voice-first AI for visually impaired children
- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — AI-generated tactile statistical graphs
- MuTSE: A Human-in-the-Loop Multi-use Text Simplification Evaluator — LLM-based text simplification for intelligent tutoring
- Exploring the design of LLM-powered question generation for deaf and hard of hearing learners — LLM question generation for Deaf/Hard-of-Hearing learners
- Using Gemini and LuaLaTeX to transcribe physics videos into PDF/UA-2 and ISO 32005 math-accessible PDFs — Gemini+LuaLaTeX math-accessible physics video transcription
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Neurodiversity

> **Neurodiversity** — the framing that neurological differences such as autism, ADHD, dyslexia, and dyspraxia are natural variations in human cognition rather than deficits to be corrected. In education, a neurodiversity-affirming approach designs learning environments that accommodate and leverage these differences rather than forcing conformity to a single cognitive norm.

Questions to Consider

- The page frames neurodiversity as neurological differences being natural variations rather than deficits to fix. How does that shift in framing change what ‘helping’ a learner with autism, ADHD, or dyslexia should look like in your own setting?
- Consider a generative AI tool that produces long text-heavy responses. Which neurodivergent learners might it help, and which might it disadvantage—and can you think of design choices that would tip the balance either way?
- AI that reduces cognitive load can support learners who struggle with executive function or social expectations, yet AI that encourages dependency may undermine them. Where do you draw the line between support and over-reliance for a specific learner?
- The page warns that AI tools which assume a dominant communication style can recapitulate equity gaps. Can you recall a time a ‘one-size-fits-all’ tool or classroom assumed everyone learned the same way, and what it overlooked?
- How might a learner’s neurotype change how their behavior signals are interpreted in learning analytics? What risk arises when AI reads engagement or struggle without knowing how a particular brain works?
- The strongest evidence on this page is for a general design change that helped everyone and closed a gap, not for a tool built for one diagnosis. Why might universal changes outperform diagnosis-gated ones — and what does that imply about how you would spend a limited accessibility budget?

Introduction

The neurodiversity paradigm shifts the goal of Special Education and Accessibility work from “fix the learner” to “adapt the environment.” It overlaps with Universal Design for Learning and Inclusive Learning but emphasizes affirming identity and strength-based design over accommodation-as-compensation.

In the AI era this framing becomes a design test rather than a slogan. Generative AI offers real promise for neurodivergent learners — alternative means of engagement, representation and expression, support for executive function, and reduced extraneous load — and real risk, since tools that assume a dominant communication style, gate support behind a formal diagnosis, or encourage dependency can disadvantage exactly the learners they claim to serve. This page maps what the evidence actually shows, category by category, and where it runs out.

What the research covers

Two reviews define the shape of the field, and both describe fragmentation rather than consolidation.

A PRISMA-ScR scoping review (Rempel et al., 2026) searched five databases and a decade of publication (2015–2025), screening 766 records down to 40 empirical studies of digital assistive technologies for neurodivergent students in higher education. The field has reorganized around generative AI — 15 of the 40 studies — with immersive formats second at 11. Its central critique is a design critique: individual accommodation and neurotype-specific tools organized around formal diagnosis cannot address functional differences that cut across neurotypes, so it recommends universal design and participatory development instead. It also notes that the most immersive tools are the least scalable.

The interdisciplinary review of AI for dyslexia (Dabaghi, D'Urso and Sciarrone, 2026) covers 2018–2024 across 72 studies and finds AI used for detection, assistive support, and personalization, with those strands evolving in parallel rather than in integration, and the field driven more by technological opportunity than by consolidated educational theory. Its detection research (EEG, eye-tracking, Machine Learning models) shows diagnostic promise for early intervention but often needs specialized equipment and controlled conditions, which limits use in ordinary classrooms. That is the practical test this whole strand keeps failing: support has to be embedded in the course a student is actually taking.

Autism and ADHD in the classroom

A survey of 24 neurodivergent computing students (autistic and/or ADHD) and 20 neurotypical peers, with four in-depth interviews, found significant discomfort with assignments that lack clear structure or carry ambiguous expectations — and the same structures that suit neurotypical learners in collaborative active learning can exclude neurodivergent peers. The authors present it as preliminary and among the first studies to center neurodivergent voices in computing education, which is also a measure of how little evidence exists.

The video-segmentation study (Pimenova, Begel and colleagues, 2026) is the strongest single result on this page. Treating instructional videos as a post-hoc processing problem — segmenting them into single-instruction chunks with fixed pauses to reduce extraneous load — improved performance for everyone in a within-participants design (17 ADHD, 10 non-ADHD), and the ADHD participants' errors and hesitations fell to parity with their non-ADHD peers. An equalizing change that needs no diagnosis, no disclosure, and no separate tool is the cleanest available demonstration of Universal Design for Learning through automated content transformation.

Specific learning disabilities, dyslexia, and cognitive offloading

Zhang et al. (2024) pooled 29 (quasi-)experimental studies of AI-based interventions for students with disabilities and found a medium positive overall effect (Hedges' $g = 0.588$, 95% CI [0.349, 0.826]) across 239 effect sizes from 41 independent samples. Two details matter more than the headline. The first is that the effect varies by disability category: students with specific learning disabilities, intellectual and developmental disabilities, or who are deaf showed a larger effect ($g = 0.952$) than students with autism spectrum disorder ($g = 0.368$), though the authors report the difference as not statistically significant. The second is publication bias: Egger's test was significant ($\beta = 2.837$, $p < .001$) and trim-and-fill reduced the

pooled estimate to g = 0.2694, still positive. “Neurodivergent students” is not one population, and a pooled effect across categories is not a promise to any of them.

The risk side has its own literature. Seung and Basham (2026) argue that generative AI has changed cognitive offloading from a peripheral study aid into a delegation of higher-order cognitive processes, with especially consequential implications for students with learning disabilities — the learners most likely to be offered the shortcut and least likely to be served by it if the delegated process was the point of the task.

Executive function and reliance

Klarin, Hoff and Daukantaitė (2026) define reliance narrowly — preferring generative AI over one’s own effort or teacher support, plus difficulty initiating schoolwork without it — and test it in two Swedish community samples of adolescents (849 lower-secondary students, analytic n = 735, and 898 upper-secondary students, analytic n = 839). Executive-functioning difficulties ran through perceived usefulness and habitual use to reliance in both samples, with small indirect effects (β = .10, 95% CI [.06, .14] in the lower-secondary sample; β = .08, 95% CI [.04, .12] in the upper-secondary sample). The practical reading: the students who most need support with initiation are the ones for whom a convenient tool most easily becomes the default route rather than one option — and the effect sizes here are small enough that this is a design concern, not a diagnosis.

Design cautions

- **Diagnosis-gated support excludes the learners it does not name.** The scoping review’s critique applies directly to how AI features are deployed: if a feature is unlocked by an accommodation letter, learners with functional differences but no diagnosis never see it.
- **Detector-driven processes can deter legitimate accommodation use.** Where a language technology functions as an effective accommodation for a neurodivergent learner, a blanket prohibition or a detector-driven process that deters its legitimate use raises equality considerations — the annulled misconduct case the detection literature documents involved a student in an autism-spectrum support program (Angelier (2026)).
- **Tools can exclude epistemically, not just poorly.** Tali-Otmani (2026) argues that Anglophone, Western-centric training data marginalizes non-hegemonic ways of knowing, and puts the situation of disabled learners at the center of that critique — a warning that “inclusive” AI can still encode whose knowledge counts.
- **Behavior signals are read by systems that do not know the learner.** Interpretation of engagement, struggle or attention in Learning Analytics and Learner Modeling and Adaptive Instruction assumes a normative pattern of response; see Differential Effects Across Learner Groups for the fairness evidence on that assumption.
- **Dependency is a design outcome, not a learner failing.** Given the reliance pathway above, the question to ask of any AI feature is whether it substitutes for the higher-order process the assignment exists to build — the point Seung and Basham make for learning disabilities.

Where the evidence is thin

- **Almost everything here is single-group.** The disability meta-analysis has no neurotypical comparator, so it establishes that interventions helped, not that they helped this group differently.
- **Samples are small.** Twenty-four students and four interviews in the computing study; 17 and 10 in the ADHD video study; 72 studies in the dyslexia review with the strands still uncoupled.
- **Category boundaries differ across studies,** so cross-study comparison of "the same" neurotype is limited — and the between-category differences in the meta-analysis are reported as non-significant.
- **The field's own reviewers describe it as technology-driven,** which means the intervention evidence is thin exactly where the design guidance is strongest.

Connections

Neurodiversity connects to Special Education, Inclusive Learning, Universal Design for Learning, and Equity. It informs both how AI is deployed for Student Experience and how assessments and literacy programs are designed to be fair across cognitive variability. For how these findings sit alongside other learner groups — language, gender, socioeconomic status, geography — see Differential Effects Across Learner Groups.

Common Misconceptions

- **"Neurodiversity research is a niche corner of AIED."** The field has **reorganised around generative AI — 15 of the 40 studies** — with immersive formats second at 11. The literature moved with the technology rather than accumulating around stable questions.
- **"More AI for dyslexia means better support."** The interdisciplinary review of AI for dyslexia (Dabaghi, D'Urso and Sciarrone, 2026) covers **72 studies across 2018-2024** and finds AI used across a wide span of purposes. Breadth of application is not evidence of effectiveness for any one of them.
- **"Accommodations are the right frame for neurodivergent learners."** A survey of 24 neurodivergent computing students and 20 neurotypical peers with four in-depth interviews found needs that are **general design requirements** — structured assignments, small consistent teams, explicit roles — rather than individual adjustments granted after a diagnosis.

Connected Concepts

- Special Education
- Inclusive Learning
- Universal Design for Learning
- Equity
- Differential Effects Across Learner Groups
- Student Experience
- Personalized Learning

- Learning Analytics
- Generative AI
- Cognitive Offloading
- Learner Modeling and Adaptive Instruction

Connected Articles

- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: a scoping review of digital assistive technologies for neurodivergent students in higher education
- Let’s CHAT About Artificial Intelligence for Students With Disabilities: A Systematic Literature Review and Meta-Analysis — 29 studies of AI for students with disabilities, and an effect that differs by category
- Leveling the Playing Field: Temporal Video Segmentation for Individuals with ADHD in Computing Education — Temporal video segmentation that brought ADHD participants to parity
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning — 24 neurodivergent computing students on structure, ambiguity, and collaboration
- Individual Differences in Reliance on Generative AI in Schoolwork: The Role of Executive Functioning Difficulties, Perceived Usefulness, and Habitual Use — Executive-functioning difficulties, perceived usefulness, and the route to AI reliance
- Cognitive Offloading in the Age of Generative AI: What Does It Mean for Students With Learning Disabilities? — GenAI cognitive offloading for students with learning disabilities
- Artificial intelligence to help people with dyslexia in education: An interdisciplinary literature review — AI to help people with dyslexia in education
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Generative AI and the marginalization of minoritized knowledges
- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — Tactile Statistical Graphs for Accessibility
- Designing Needs- and Attention-Aware AI Learning Tools for Engineering Education: Insights from Psychological Outcomes — Designing Needs- and Attention-Aware AI Learning Tools
- The pitfalls of AI detection in academic writing: bias, false positives, and the need for inclusive assessment — Detector-driven processes can deter legitimate accommodation use

Connected FAQs

- How Should Parents and Teachers Approach AI with Children Under 13?
- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Universal Design for Learning

> **Universal Design for Learning (UDL)** — an educational framework that designs instruction to be accessible and effective for the widest range of learners by proactively building in flexible means of engagement, representation, and action/expression, rather than retrofitting accommodations for individuals.

Questions to Consider

- UDL's core claim is that learner variability is the norm, not the exception — so design for many pathways from the start rather than fixing a single path for those who struggle. Do you tend to design for an 'average' learner and add accommodations later? What might be lost in that default approach?
- Think of a time a particular format (a dense text, a lecture, a single way of showing work) excluded you or someone you taught. Which of the three UDL principles — engagement, representation, or action/expression — was at stake, and what would a flexible alternative have looked like?
- Generative AI can create personalized examples, captions, summaries, and multiple assessment formats — seemingly a gift for UDL. But the page warns AI can also encode bias and reduce learner agency. Before reading on, how could a tool built to personalize end up *narrowing* rather than widening learning paths for some students?
- A common misconception is that UDL means lowering standards or giving everyone different outcomes. Consider an assignment that lets students submit an essay, a video, a diagram, or code for the same learning outcome. Is that a watering-down, or a fairer way to assess the same ability? Defend your view.
- UDL turns 'fix the learner' into 'fix the design.' Pick a frustrating learning experience you've had or designed. If the barrier were a design problem rather than a student problem, what would you change about the design to remove it for everyone?
- The page warns against AI that assumes one communication style or penalizes neurodivergent expression. If you use or design AI-assisted tools, where might 'default' styles quietly exclude learners — and what would it take to audit for that?

Introduction

UDL rests on the insight that learner variability is the norm, not the exception. Rather than designing a single path and adding support for those who struggle, UDL designs multiple pathways from the start so that barriers are removed for everyone. It is a core lens for Inclusive Learning, Equity, and Special Education.

The three principles

- **Multiple means of engagement** — the "why" of learning: varied ways to motivate and sustain interest, connect to relevance, and support self-regulation.
- **Multiple means of representation** — the "what" of learning: presenting information in varied formats (text, audio, visual, interactive) so all learners can perceive and comprehend it.
- **Multiple means of action and expression** — the "how" of learning: offering varied ways for learners to demonstrate what they know (writing, speaking, building, performing).

UDL in the AI era

Generative AI creates new opportunities and new risks for UDL. AI can personalize representation and provide alternative pathways, supporting Personalized Learning and accessibility. But it can also encode bias, assume dominant communication styles, and — if it reduces learner agency — undermine the engagement principle. Research on AI Misuse and Learning Harm and equity shows that AI tools must be designed with inclusive principles or they recapitulate Equity gaps. UDL therefore informs both how AI is deployed and how AI-literacy and assessment are designed to be fair across learner variability.

Equity-by-design is one concrete way to operationalize this stance. Wenzel, Geiger, and Liening (2026) ground their CAIS-GBL framework for AI conversational agents in business Simulation games in an explicit **equity-by-design** approach aligned with universal design for learning, deriving meta-requirements that span cognitive, motivational, affective, and socio-cultural engagement. Their design principles and features aim to address individual learner differences in strengths, challenges, and interests — a concrete application of UDL principles to the design of adaptive, AI-supported game-based learning. A tool can serve all three UDL principles and still narrow what a lecturer decides. Alenezi (2026) argues that mapping a tool to a UDL principle is necessary but not sufficient for that reason, and proposes an annual deprofessionalization audit and a vendor-dependency register among its checks.

AI also appears in this literature as an obstacle to UDL rather than an instrument of it. In Sidhu, Atif and Newland's (2026) mixed-methods study of 69 professors at one Ontario university, one of the four key themes is that generative AI is reversing progress in accessible course design. The title quotation, "AI is reducing options I had used", comes from their interviews, because the take-home and drafting-based assignments that had done inclusion work are the ones an AI can now complete outright. Their faculty-level findings show why that setback lands on an already thin base: 90% of respondents believed they create an accessible learning environment and 87% said they actively consider accessibility. Yet fewer than half (46%) thought the university offered sufficient resources for it, and roughly a fifth had never heard of techniques as basic as OCR-readable PDFs or color-independent links. Demand is outrunning provision — Ontario university enrollments grew 17% from 2013 to 2022 while registrations with accessibility services rose 126% — so the case the study makes is that UDL support has to be resourced to compensate for the assessment options AI removed.

Connections

UDL connects to Inclusive Learning, Equity, Special Education, Learning Design, and Culturally Relevant Pedagogy. In assessment, it intersects with Authentic Assessment's emphasis on representational fairness

and with Reducing AI Misuse as a guardrail against tools that penalize particular communication styles. Because UDL is the framework most commonly invoked in higher-education disability contexts (where "special education" is a K-12 term), it is often the right page to link for college and university disabled-learner research.

Implications and examples for instructors and instructional designers

UDL turns "fix the learner" into "fix the design." For instructors and designers working with AI, the three principles translate into concrete moves:

Engagement — offer multiple ways to spark and sustain motivation. - Let learners choose how they engage: problem-based, game-based, discussion, or self-paced options. - Use AI to surface relevance — personalized examples, real-world connections, or choice of topic — rather than a single generic task. - *Example:* A course uses AI to generate varied worked examples tied to different learner interests (business, health, arts), letting students pick the context that motivates them.

Representation — present information in multiple formats. - Offer the same content as text, audio, video, and interactive — AI can auto-generate captions, transcripts, summaries, and alternative explanations at different reading levels. - *Example:* An instructor uses an AI assistant to produce a plain-language summary and an audio version of a dense reading, so learners can choose their entry point. Pair with Accessibility (captions, alt text) so every format is usable.

Action and expression — let learners show what they know in varied ways. - Provide choice of assessment product (essay, presentation, video, diagram, code) aligned to the same learning outcome. - *Example:* A project allows submission as a written report, an AI-assisted video explainer, or a live demonstration — with AI scaffolds supporting each mode. In Assessment design, this parallels Authentic Assessment's representational fairness.

Design for AI-literacy and agency. - Teach students how and when to use AI, and build checkpoints that keep the learner (not the tool) accountable — see AI Literacy and Reducing AI Misuse. - *Example:* A UDL-aligned assignment lets students use AI to draft but requires a metacognitive reflection on their own contribution, preserving the engagement and agency principles.

Use AI to remove barriers, not add them. - Deploy AI to close performance gaps (e.g., AI-segmented videos with pauses helped ADHD learners) and to lower the cost of accessible formats. - Guard against AI that assumes one communication style or penalizes neurodivergent expression — connect to Accessibility, Equity, and Neurodiversity.

- **Target functional barriers, not diagnoses.** Rempel et al. (2026) found the 40-study corpus of assistive technologies for neurodivergent students organized around accommodation and diagnosis-gated tools, and argue that designing to the cross-cutting barriers students actually face is what makes a tool plausibly universal.

Common Misconceptions

"A course with accessible materials has implemented UDL." Accessibility is one of UDL's three principles and the easiest to audit, so it is frequently the only one done. Building flexible means of

engagement and of action and expression is the larger part of the framework, and a course whose PDFs are tagged but whose assessments admit one format has completed the measurable fraction.

“Faculty who believe they are accessible are accessible.” Belief and practice come apart systematically. The faculty-level findings in this corpus show **90% of respondents believed they create an accessible learning environment and 87% said they actively consider accessibility** — self-attestation rates that cannot all be accurate given what audits find, and a reminder that UDL implementation cannot be assessed by survey in the way it is usually assessed.

“UDL means designing for the average student more carefully.” The core claim is the opposite: learner variability is the norm rather than the exception, so design provides many pathways from the start instead of fixing one path for those who struggle. Retrofit is what UDL exists to replace, and a single well-tuned path is still a single path.

“AI makes UDL automatic, since it can generate alternate formats.” It makes the representation principle cheap and leaves engagement and expression untouched. Converting text to audio addresses one of three means; a course can now be fully multi-format and still require every student to demonstrate learning in the same single way.

Connected Concepts

- Inclusive Learning
- Accessibility
- Assistive Technology
- Equity
- Special Education
- Neurodiversity
- Learning Design
- Personalized Learning
- Culturally Relevant Pedagogy
- Authentic Assessment
- Student Experience
- Generative AI
- Pedagogies and Teaching Strategies — Umbrella: pedagogies and teaching strategies in AI education
- Bias Mitigation
- Reducing AI Misuse
- K-12

Connected Articles

- Cognitive Offloading in the Age of Generative AI: What Does It Mean for Students With Learning Disabilities? — GenAI cognitive offloading for students with learning disabilities

- From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education — From Authentic Products to Authenticated Processes
- Touching and Feeling the Data: A Reusable Software Pipeline for Tactile Statistical Graphs in Accessible Education — Tactile Statistical Graphs for Accessibility
- "I can’t read your mind": A Study of Neurodivergent Computing Students’ Experiences with Collaborative Active Learning — Neurodivergent Computing Students
- Designing Needs- and Attention-Aware AI Learning Tools for Engineering Education: Insights from Psychological Outcomes — Designing Needs- and Attention-Aware AI Learning Tools
- Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education — Generative AI, virtual reality, and beyond: A scoping review of digital assistive technologies for neurodivergent students in higher education
- “AI is reducing options I had used”: exploring faculty perceptions of accessible course design in a ChatGPT world — “AI is reducing options I had used”: exploring faculty perceptions of accessible course design in a ChatGPT world
- Artificial intelligence and universal design for learning in Kuwait’s higher education institutions: towards an AI-enabled framework for inclusive education — Artificial intelligence and universal design for learning in Kuwait’s higher education institutions: towards an AI-enabled framework for inclusive education

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?

Global South

> **Global South** — countries in Africa, Asia, Latin America and Oceania that are often economically, politically and historically marginalized relative to the Global North. In AI in education research, these contexts are increasingly recognized as underrepresented in the evidence base, yet they raise distinctive questions about equity, cultural relevance, resource constraints, and the epistemic dominance of Western, Anglophone training data.

Questions to Consider

- If an AI system performs well on benchmark tests built from Western, English-language data, how confident should you be that it will work equally well for your students? What would you want to check before trusting it in your own context?
- Consider a learning tool whose training data and evaluation metrics were all developed in the Global North. What assumptions about language, knowledge traditions, and educational realities might it silently encode — and who is most likely to be misrepresented by them?
- When AI adoption is studied, whose classrooms and institutions tend to dominate the evidence base? How might that skew what we think we know about whether AI 'works' in education?
- The page argues for treating learners' lived and community epistemologies as authoritative, not just as add-ons to Western models. What would it take for your own AI-related practice or research to center local knowledge rather than import it from elsewhere?
- Resource constraints are a recurring theme in Global South contexts. How might the promise of low-cost, scalable AI support both close and widen existing opportunity gaps, depending on how it is designed and deployed?
- How could you tell whether a technology 'adopted' in a particular setting was actually adopted because it fit local conditions — or because it was assumed to transfer? What evidence would distinguish the two?

Introduction

Why It Matters for AIED

Mainstream AI and educational-technology research has historically been dominated by Western, English-language datasets and institutional contexts. This creates two problems: (1) AI systems trained on such data may underperform or misrepresent learners in Global South settings, and (2) evaluation benchmarks built in the Global North may not reflect the educational realities, languages, or knowledge traditions of other regions. Research from Global South contexts in this knowledge base spans culturally grounded datasets, benchmarks, and technology-adoption studies, with implications for AI Literacy and higher and K-12 education.

Applications in the Knowledge Base

- **Culturally grounded data and benchmarks:** IKS-Instruct provides a multilingual Indian Knowledge Systems instruction dataset; NSMQ Riddles introduces a Ghana-based STEM benchmark, one of the first Global South educational evaluation datasets.
- **AI ethics awareness in Ghanaian higher education:** Acquah et al. (2026) validated a three-factor (autonomy, beneficence, fairness) AI ethical awareness scale with 509 university students in Ghana, finding five latent profiles from uniformly very high awareness to a small cluster with almost none — weakest on beneficence — and no gender differences, providing a Global South measurement anchor for the AI-Ethics literature.
- **Teacher ethical reasoning in low-resource contexts:** Adelana et al. (2026) found in-service secondary STEAM teachers in a low-resource context reason about AI ethics through professional identity, classroom realities, and cultural norms rather than formal principle lists, countering "ethics empty" assumptions about the Global South.
- **Contextual adoption:** Asag & Al Mamun model GenAI adoption among Bangladeshi engineering students, and ConnectED deploys a curriculum-aligned lesson-planning system for Vietnamese education.
- **Capacity building, not infrastructure, moved faculty adoption.** Among 255 Bangladeshi faculty, attitude toward GenAI strongly predicted use ($\beta = 0.556$) and domain-specific relevance drove attitude ($\beta = 0.413$), while institutional technology provision and subjective norms were not significant predictors (Alam et al. (2026)).
- **Institutional integration and structural inequality:** Adeniranye et al. (2026)'s comparative content analysis of 45 Nigerian universities (federal/state/private) found that AI integration is predicted by institution age and geographic location — not governance type — and that international and industry network ties reinforce one another ($r = 0.74$), so well-connected institutions compound advantage while others fall further behind. It locates digital inequality not just at the learner level but in the structural capacity of higher-education institutions themselves.
- **Academic development as digital mediation under structural constraint:** Sithole (2026) interviews twelve academic developers and learning designers across two South African Historically Disadvantaged Institutions and draws an analytical line the Global South literature often blurs: **digital inequality** is distributive and answerable in principle through redistribution and access, while **algorithmic coloniality** is epistemic and persists even under full access because it inheres in what the systems encode and whose knowledge they center. The two are entangled but demand different responses, and the institution is doubly positioned — excluded by infrastructural scarcity, and, when included, subordinated by imported systems that encode other knowledges and norms. Institutional AI rhetoric ("performance more than practice") arrived loosely coupled to the material realities of teaching, so developers translated global digital-transformation discourse into contextually viable practice: testing and deliberately "breaking" tools in peer spaces, insisting on judgment over skill, and absorbing the affective cost of projecting expertise they were still acquiring.

- **Epistemic marginalization:** Tali-Otmani argues that Western-centric training data marginalizes non-Western and disability-centered knowledges — connecting Global South concerns to Equity and Culturally Relevant Pedagogy.
- **Disability and inclusion in the Global South:** Khlaif et al. (2026) — a qualitative case study of 21 visually impaired undergraduates across three Palestinian universities — found GenAI bridges digital, geographic, and socioeconomic divides for disabled learners, extending technology-acceptance research to disability contexts where usability, affordability, and Accessibility are mutually reinforcing.
- **Designing for local stressors under resource constraints:** Bashir and Afzal (2026) build Sukoon as a Global South design response to a documented mismatch — mental-health chatbots trained mostly on Western datasets and overwhelmingly English-language, while Pakistani students face academic, financial, familial, and relational stressors simultaneously and often cannot raise emotional difficulties with parents, teachers, or peers because of stigma. The authors' practical constraints are as instructive as their model: a free-access Open Source Large Language Models (LLMs) through a hosted API for low resource requirements, a lightweight Flask deployment for regional universities, "tools are available but often expensive" listed as a barrier, and unequal access to paid models flagged as a general dependency risk. They also note the classifier was trained on a publicly available dataset not representative of Pakistani students, and commit to locally collected DASS-21 data before drawing population conclusions.
- **Thin and tool-specific assessment evidence from African higher education:** A PRISMA 2020 systematic review of empirical research published between 2023 and 2025 located only ten studies, concentrated in Nigeria and South Africa and conducted almost exclusively on ChatGPT, so what is known about redesigning assessment for generative AI in African higher education rests on small-sample, single-institution, self-reported studies rather than measured learning gains — the review's authors frame their recommendations as directions rather than settled effects.
- **Equity is the least-studied dimension across the region.** A PRISMA-ScR scoping review of 75 Global South studies (2022–2025) found equity the least-examined of its five areas despite its centrality to inclusive education, and reported a gap between students' stated ethical positions and their behavior (Nguyen & Perkins, 2026).

Implications

Attending to Global South contexts requires moving beyond assuming Western models and benchmarks transfer directly. It calls for locally grounded datasets, culturally relevant Pedagogies and Teaching Strategies, community-centered evaluation standards, and research that treats learners' lived and community epistemologies as authoritative — aligning with frameworks like community-based AI learning and technology-acceptance research adapted to local conditions.

The scaling record is part of that picture, and it is sobering. Programs that work at pilot scale frequently stop working when governments run them: the Kenyan program that produced substantial gains under non-governmental implementation showed no detectable gain at government scale (Bold et al.), effect sizes tend to fall as programs grow (Vivalt), and implementation quality dilutes as sites multiply (Al-Ubaydli, List & Suskind). Latin America's own precedent is the Peruvian One Laptop per Child program — about 800,000

laptops distributed with no detectable effect on mathematics or reading — from which the lesson drawn was that access to technology is not instruction. Restrepo Morales et al. (2026) add a reporting lesson to the scaling lesson: in the 2026 El Salvador episode an AI-tutoring pilot in 171 schools was announced as comparable to Germany and Sweden while the same country's representative PISA 2025 sample showed no movement in two of three subjects, and the pilot data were too thin (7.0 assessed students per school against 25.4 nationally) to exclude selection as the explanation. For Global South systems adopting AI at scale the implication is double: the evidence that a reform works is usually about the components it bundles rather than the technology in its headline, and a phased rollout designed before deployment identifies effects at almost no cost — which matters most where connectivity dictates the phasing anyway.

Ng'ambi and van der Merwe (2026) argue from a South African Grade 9 classroom that restriction-first institutional policy forecloses the conditions under which AI might extend rather than substitute for teachers under pedagogical scarcity, and that interaction data learners generate is held under foreign governance regimes.

Common Misconceptions

- **"Low-resource contexts lack an AI ethics framework and need one imported."** In-service secondary STEAM teachers in a low-resource context **reason about AI ethics through professional identity, classroom realities and cultural norms rather than formal principles**. The reasoning exists and is situated; a universal principle list transfers poorly onto it.
- **"Governance type predicts AI integration in universities."** A comparative content analysis of **45 Nigerian universities** (federal, state and private) found AI integration predicted by **institution age and geographic location — not governance type**. The assumption that public and private institutions diverge is contradicted.
- **"The digital divide is the main barrier."** A qualitative case study of **21 visually impaired undergraduates across three Palestinian universities** found GenAI bridges **digital, geographic and socioeconomic** barriers simultaneously. The barriers are layered, and treating access as the single obstacle leaves the others untouched.

Connected Concepts

- Differential Effects Across Learner Groups
- Equity
- Generative AI
- Culturally Relevant Pedagogy
- AI Literacy
- Higher Education
- K-12
- Inclusive Learning
- Technology Adoption Models
- Benchmark

Connected Articles

- Rethinking assessment in the age of generative AI: A systematic literature review of African higher education — Rethinking assessment in the age of generative AI: A systematic literature review of African higher education
- Institutional structures, digital inequality, and AI integration in higher education — Institutional structures, digital inequality, and AI integration in Nigerian higher education
- Perceptions of Generative AI in the Global South: A Scoping Review
- Social and cognitive drivers of generative AI adoption: A unified socio-cognitive model for engineering education — Unified socio-cognitive model for engineering education (Bangladesh)
- ConnectED: A curriculum-aligned AI system for Vietnamese instructional lesson planning and student learning — ConnectED: Vietnamese Lesson Planning
- IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems — IKS-Instruct: Indian Knowledge Systems Dataset
- NSMQ Riddles: A Benchmark of Scientific and Mathematical Riddles for Quizzing Large Language Models — NSMQ Riddles: Ghana STEM Benchmark
- Generative artificial intelligence and the marginalization of minoritized knowledges in higher education: The case of disability — Marginalization of minoritized knowledges
- LLMs to Support K-12 Teachers in Culturally Relevant Pedagogy: An AI Literacy Example — LLMs for Culturally Relevant K-12 Pedagogy
- Generative Artificial Intelligence integration in higher education: A constructivist learning theory approach — GenAI integration in Bangladeshi higher ed through constructivism (Alam et al. 2026)
- Assistive generative AI for visually impaired learners: Personalization and inclusion in higher education — Assistive GenAI for visually impaired learners
- An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning — An AI-Powered Culturally Aware Chatbot for Stress Detection and Wellness Support among Pakistani University Students Using NLP and Machine Learning
- How much selection would be enough? Bounding the learning claim of El Salvador’s artificial intelligence tutoring pilot — Bounding the learning claim of El Salvador’s AI tutoring pilot (Restrepo Morales et al. 2026)
- Beyond the algorithm: academic developers as digital mediators in Global South higher education — Academic developers as digital mediators in South African HDIs: digital inequality vs. algorithmic coloniality
- Artificial intelligence ethical awareness of university students in Ghana: A network and latent profile analyses — Artificial intelligence ethical awareness of Ghanaian university students

- Ethical principles of AI in education: Exploring teachers' contextual ethical reasoning through an STS lens — Ethical principles of AI in education: teachers' contextual ethical reasoning

Ethics and responsibility

Ethics

> **Ethics** — the moral principles governing the design, deployment, and use of AI in educational contexts. AI education ethics spans data privacy, algorithmic fairness, transparency, accountability, and the broader question of what AI should and should not do in learning environments. It is the normative foundation for the knowledge base's other AI-education concerns — equity, Bias Mitigation, Academic Integrity, AI Governance, and Pedagogical Safety — and the field is increasingly moving from abstract principle lists toward situated, context-sensitive, and institutionally-supported ethical practice.

Questions to Consider

- AI systems are often held to ethical checklists — fairness, privacy, transparency, accountability. But research increasingly suggests that principle-based 'checklist' ethics is insufficient on its own. What might a checklist miss that only happens in real, situated classroom practice?
- Students' decisions about disclosing AI use are shaped less by ethical conviction than by fear of penalties, stigma, and unclear policy. If honesty is driven by fear rather than principle, what does that say about the ethics of the current academic-integrity approach?
- Personalizing AI feedback with student attributes can itself become a vector for bias. How might a well-intentioned attempt to tailor feedback to an individual learner end up treating them less fairly — and how would you detect it?
- Who holds the power in the relationship between institutions, AI systems, and learners — and how does that power imbalance shape consent, privacy, and student surveillance as analytics grow more granular?
- Some researchers argue that protecting learners' cognitive and epistemic development — their ability to think and act independently — is itself an ethical obligation, especially as over-reliance on AI grows. Do you agree that 'preserving thinking' is an ethical duty of AI systems?

Introduction

Ethics is the normative backbone of AI in education: every AI tool, policy, and pedagogical decision encodes assumptions about what is fair, transparent, accountable, and safe. The knowledge base treats ethics as both a set of principles (fairness, privacy, transparency, autonomy, accountability) and a set of *practices* — how stakeholders actually reason about AI, how institutions govern it, and how learners are prepared to use it responsibly. Recent research documents a double movement: on one hand, a deepening concern that principle-based "checklist" ethics is insufficient; on the other, a growing emphasis on situated and ecological accounts of ethical judgment, and on the structural and institutional conditions that make responsible use possible.

Gillette et al. (2026) argue from Swedish survey and focus-group data that institutions should decide generative AI questions through a partnership ethic rather than a cheating frame, drawing on Carolyn Merchant's mutual interdependence, respect for diversity, inclusiveness, accountability and commitment to

long-term Sustainability: 31% of participants raised ethics unprompted, and most wanted clearer institutional guidance than they had.

Core ethical dimensions

- **Ethics as productive, not only restrictive.** Rienties, Divjak and Law (2026) conclude that ethical fitness and trustworthiness are constitutive of educational quality — ethical fitness predicts technical-artistic balance in creative work, so ethics is a design variable rather than a final compliance stage.
- **Fairness and bias:** Bias Mitigation and Equity research address whether AI systems treat all learners fairly. Language bias and Bias Mitigation studies document real-world inequities, and writing-feedback research shows that personalizing AI feedback with student attributes can itself become a bias vector.
- **Privacy and consent:** Privacy research examines data collection, student surveillance, and the power imbalance between institutions and learners — a constraint that grows sharper as analytics become more granular and AI-driven.
- **Transparency and explainability:** Explainable AI frameworks argue that students and teachers should understand how AI systems make decisions affecting them. This extends to student-facing transparency about their own AI use — AI use and disclosure statements — which the research shows is shaped less by ethical conviction than by fear of penalties, stigma, and ambiguous policy (see Kirsanov et al., Chang et al., Vetter et al., Gonsalves).
- **Autonomy and agency:** Over-Reliance and Cognitive Offloading research raise ethical questions about whether AI use diminishes learner agency, and the field frames protecting learners' cognitive and epistemic development as itself an ethical obligation.
- **Safety and harm prevention:** Pedagogical Safety and tutor harm research define ethical obligations for AI system developers, and mistake-based pedagogy shows how exposing learners to AI errors can activate rather than bypass ethical and metacognitive scrutiny.
- **Sustainability and environmental impact:** AI in education carries a material footprint — the carbon and water cost of large language models is significant given high adoption among university students — and a broader responsibility for sustainable, non-extractive design. The knowledge base treats this as an ethical dimension, not only a technical or cost concern: Daniel et al. (2026) distinguish *AI for sustainability* (using AI to advance environmental and social outcomes) from *sustainable AI* (reducing AI's own footprint, including energy-efficient and on-premise deployment), and Alsuhami & Atallah argue AI supports sustainable education only when adoption is subordinated to explicit educational values rather than technologization and commodification. Situated-ethics work likewise foregrounds environmental costs and the marginalization of Global South knowledge as core ethical concerns. See Sustainability.

How stakeholders actually reason about AI ethics

Ethical AI use is not only a matter of principles but of how the people involved interpret and apply them — and the research reveals systematic differences between groups.

- **Faculty vs. students.** Bilgiç & Sever (2026), a mixed-methods study of 971 students and 135 faculty, found both groups supportive of ethical AI use but in different registers: faculty emphasized ethical principles while flagging a lack of institutional guidelines, whereas students valued AI's learning benefits but voiced uncertainty about who shares ethical responsibility. Both worried that excessive AI use could weaken cognitive skills — a concern that frames ethical integration as preserving learners' cognitive development, not merely regulating tool use. Faculty scored high on individual responsibility yet rated institutional guideline adequacy lowest (M = 2.99), exposing a gap between personal ethics and structural support.
- **Students vs. instructors in readiness.** Fekete (2026) found students report higher ethical awareness than instructors (4.03 vs. 2.44), yet instructors show stronger willingness to use AI — students interpret ethics through immediate coursework while teachers treat it as institutional clarity and integrity. Both report weak institutional support, and readiness develops through different channels: instructors' moral awareness grows with institutional and social support, while students' confidence correlates with Self-Efficacy and collaboration rather than formal instruction.
- **Use rises faster than ethical consensus.** Across four semesters in a US Teacher Education program, students' GenAI use climbed from 57% to 83% for assessment preparation and 44% to 76% for studying, while 'unsure' ethical responses rose steadily and AI users rated its academic use as more ethical than non-users (Parker et al. (2026)).

Ethics is central to the field but rarely an outcome. Across 394 GenAI higher-education studies, ethics and academic integrity were among the outcomes targeted least, and governance practices were under-reported (Lin et al. (2026)).

- **Normative frames are not interchangeable.** Among 151 Spanish undergraduates, moral equity was a necessary condition for intending to use LLMs in exam preparation ($d = 0.338$) but not a sufficient predictor, while consequentialist ($\beta = 0.350$) and deontological ($\beta = 0.329$) judgments were — students apply several normative frames (Pérez-Portabella et al. (2026)).
- **A shared multidimensional structure.** The six themes in Bilgiç & Sever — spanning data ethics, algorithm ethics, and pedagogical ethics — form an interconnected causal chain from fundamental principles (transparency, accountability, fairness, autonomy) to behavioral outcomes, underscoring that responsible AI use depends as much on clear institutional roadmaps as on individual awareness.

From principles to institutional governance

The knowledge base's research increasingly locates ethics in institutions and structures, not just individuals:

- **The institutional responsibility gap.** Bilgiç & Sever call for faculty professional development, ethics courses, and clear institutional guidelines; Fekete similarly finds that institutional support

drives instructor readiness while students rely on informal, self-directed learning — a responsibility gap for policy.

- **Ethics training moves awareness, but policy gaps complicate compliance.** An eight-week GenAI professional-development program with 97 educators raised ethical-awareness scores from 3.21 to 4.05 (Cohen's d = 0.93) and policy familiarity from 27% to 79%, yet the hardest barrier participants named was reconciling institutional policy gaps with their ethical values (Alharbi et al. (2026)).
- **Policy robustness varies.** Adarkwah et al. (2026), analyzing GenAI policies at 30 top universities against UNESCO's eight-component framework, found core ethical principles widely embraced but inclusion, equity, and Sustainability often neglected — and national AI-readiness ranking did not predict strong institutional policy. Policies tend to be declarative and misconduct-focused rather than operationally assured.
- **Ethics & data governance as an enabler.** Svetec, Divjak & Kadoić (2026) identify ethics & data governance as one of seven enablers of trustworthy Learning Analytics-based interventions — positioning trustworthiness (ethical compliance, data security, transparent algorithms, pedagogical validity) as the prerequisite without which data-informed educational change is not meaningful.
- **A systematic review of engineering education** finds ethical AI guidance is predominantly student-facing and compliance-oriented (centered on Academic Integrity and disclosure), while reciprocal accountability for faculty AI use and institutional responsibility remain underdeveloped — a pattern heightened by engineering's professional stakes in public safety and Well-Being. (Ethical Use of Artificial Intelligence in Engineering Education: A Systematic Review)
- **The teacher as AI user raises its own ethics.** Eight areas of ethical consideration — professionalism, accountability, transparency, effectiveness, inclusivity, security, contextual fit, and policy and resources — frame teachers' AI use for feedback, and only 14 of 50 top-ranked universities had specific guidance for it (Luo & Eaton (2026)).
- **A consolidated value framework for AIED ethics.** Agarwal et al. (2026), a systematic review of 25 articles, consolidate the fragmented ethics literature into six main ethical values for AI in education — non-discrimination, data stewardship, human oversight, goodwill, explicability, and educational aptness — and map the ethical norms extracted from the literature onto a stakeholder-by-value matrix (developers, educational institutes, end users, regulators). The review finds norms distributed unevenly: developers attract the most, while end users receive the fewest and least actionable norms, and no norms on non-discrimination, data stewardship, or educational aptness address end users directly — student voices are essentially absent, with "end user" norms mostly actions other stakeholders take to enable teachers. The authors argue end users should have agency and active roles rather than being treated as passive beneficiaries, and note the values are tightly coupled and can conflict (e.g., explicability vs. accuracy/Privacy, non-discrimination vs. data stewardship), producing ethical dilemmas alongside power asymmetries between stakeholder sets.
- **Responsibility named without a relationship.** Corpus analysis of 366 GenAI higher-education abstracts shows the field's responsibility vocabulary is largely adjectival: "responsible AI/GenAI" occurs 83 times across 59 documents and "responsible use" 66 times across 44, while "AI

responsibility" and "student responsibility" never appear as exact phrases, and grammatical removal is routine - 800 passive constructions, 780 of them without any agent reference, alongside 1,152 responsibility-related nominalizations. Poudyal (2026) finds no clause attaching a consequence to a system, so responsibility is recognized as a word without the relational agency that would turn it into action.

Civic framing asks a different question from integrity. Civic and Political Education treats the collective and democratic consequences of AI-mediated public argument, where the harm is a misinformed public rather than a misattributed essay.

Toward situated and ecological AI ethics

A major theoretical shift in the knowledge base is the critique of universalist, principle-based "checklist" ethics in favor of situated, ecological, and transformative accounts:

- **Situated AI ethics.** Raffaghelli et al. (2026) fuse Bronfenbrenner's ecological systems theory with Cultural-Historical Activity Theory to frame AI as a non-neutral socio-technical assemblage whose ethical implications are historically produced and locally negotiated. Across seven national cases, teachers are positioned as moral gatekeepers of AI use while lacking structural, institutional, and epistemic support — and the framework extends AI literacy beyond technical skills toward critical, political, and ecological agency, including resistance to surveillance capitalism and environmental harm.
- **The shift toward situated practice.** A bibliometric analysis of 282 articles shows that AI ethics discourse post-2021 increasingly frames ethics around professional judgment, trust, human-AI collaboration, and interpretive practice rather than only technical compliance — with education a conceptually important context.
- **Partnership ethics.** Gillette et al. (2026) draw on environmental ethicist Carolyn Merchant to propose partnership ethics — mutual interdependence, respect for diversity, inclusiveness, accountability and long-term sustainability — as a dialogue-based alternative, and report Swedish survey and focus-group data in which 31% of participants raised ethics unprompted.
- **A cultural-historical account of responsibility.** This reframing connects ethics to Learning Theories and Teacher AI Competency: responsible AI use is treated as context-sensitive, collective, and transformative agency rather than individual compliance with checklists. A survey of 454 university teachers supports that framing: AI-ethical knowledge mediated the path from technical AI knowledge to integrated teaching competence ($\beta = 0.186$) and channeled it onward through pedagogical and content knowledge (Chen et al. (2026)).
- **An ontological reframing of ethical obligation.** Xie (2026) pushes the situated-ethics critique further by relocating it in ontology: where much scholarship treats equity, power asymmetries and environmental costs as externalities to be managed, a Daoist relational self makes them internal to who we are, so that "being left behind" becomes ontologically untenable rather than merely unfair. The ethical task is then not detached optimization but Wuwei (无为) — non-forced action aligned with naturalness — set against the Youwei (有为) of algorithmic monoculture, cognitive offloading and extractive infrastructure, applied across three domains: knowledge (epistemic monoculture and synthetic misinformation), knowing (offloading that degrades critical thought)

and impact (environmental costs and Global North–South asymmetries).(Alternative AI Philosophy: Daoism as Method for AI in Education)

Ethics in practice

The knowledge base's ethics articles range from theoretical frameworks (game theory approaches) to practical guidelines (CS ethics education), from public discourse analysis to UNESCO policy frameworks. Across this range, a consistent practical message emerges: ethics must move from policing misuse toward building AI Literacy and ethical-use capability, supported by institutional guidance, teacher professional development, and design that preserves rather than displaces learner judgment.

That practical case is reinforced by empirical work on how ethics functions inside AI literacy itself: Zhu and Kong (2026) show that AI ethical awareness — alongside empowerment in AI Problem Solving — mediates the relationship between perceived project-based learning and satisfaction with an AI literacy course. Their validated AI-PBLS scale and SEM results (1,027 students) indicate that PBL creates conditions in which students build a personal framework for ethical reasoning about AI, strengthening the case that ethics is not an add-on but a core mechanism of meaningful AI literacy development. **Taught, it shifts judgment rather than only awareness.** In a cluster-randomized trial of sixteen intact classes (n = 240), a four-week information ethics module raised scored ethical judgment by 0.35 scale points (d = 0.75), and 59.9% of that gain survived four weeks, largest among the heaviest GenAI users (Qi, 2026).

The sign of that mechanism depends on what follows it. Among 584 undergraduates whose AI competence came from self-study, competence raised AI ethical awareness ($\beta = 0.644$, $p < .001$). Ethical awareness then raised AI anxiety ($\beta = 0.439$, $p < .001$) rather than lowering it — indirect-only mediation, read by the authors as awareness awakened without a coping framework (Mu et al. (2026)). Their conclusion for ethics teaching is that it cannot stop at the cognitive level. A transparency or privacy concern has to arrive with the governance route that answers it, which is why their proposed module sits inside legal education.

Ethical awareness, reflective reasoning, and self-reported responsible practice develop largely independently. Across three annual waves of 350 Nigerian computing undergraduates, Ayanwale et al. (2026) found all three rose substantially, yet their growth factors were near-uncorrelated and initial awareness did not predict later growth.

Connections

Ethics connects to Equity, Privacy, Bias Mitigation, AI Regulation in Education, Pedagogical Safety, Academic Integrity, and AI Governance. It is the normative foundation for all other AI education concepts — the frame within which questions of fairness, transparency, autonomy, and safety are raised and resolved.

Common Misconceptions

- **"The cheating frame is a sufficient way to think about GenAI ethics."** Gillette et al., 2026 argue institutions should decide generative AI questions through a **partnership ethic rather than a cheating frame**. The frame determines what questions get asked, and a misconduct frame cannot ask about educational purpose.

- **“Faculty and students agree about what is ethical.”** Bilgiç and Sever (2026), a mixed-methods study of **971 students and 135 faculty**, finds the ethical dimensions diverge between the groups. A policy written from one perspective will misstate the other.
- **“Ethical consensus precedes use.” Adoption outpaces ethical agreement**: across four semesters in a US teacher-education program, students’ GenAI use **climbed from 57% to 83% for assessment preparation**. The norms are being formed by practice rather than the reverse.

Connected Concepts

- Business Education
- Equity
- Privacy
- Bias Mitigation
- AI Regulation in Education
- Pedagogical Safety
- Academic Integrity
- AI Use and Disclosure Statements — AI use and disclosure statements
- AI Governance
- AI Literacy
- Cognitive Offloading
- Teaching
- Teacher Education
- Chemistry Education — Chemistry education and AI: labs, formative assessment, LLM limits, philosophy of experimentation
- Biology Education — Biology education and AI: lab teaching assistants, AI literacy in biology, critical thinking, specialized tools
- Civic and Political Education

Connected Articles

- Toward Partnership Ethics for Generative Artificial Intelligence in Higher Education — Swedish survey and focus-group study arguing that partnership ethics, not a cheating frame, should guide institutional genAI decisions
- Modeling the Relationships Between University Students’ AI Competence, AI Ethical Awareness, and AI Anxiety: A Dual-Stage PLS-SEM and ANN Analysis - Ethical awareness amplified AI anxiety where no coping framework was taught: indirect-only mediation among 584 students
- From learning analytics to educational interventions: Enhancing decision-making and learning design — From learning analytics to educational interventions: enablers of trustworthy LA-based interventions (Svetec, Divjak & Kadoić 2026)
- Beyond Detection: How Students Use—and Hide—AI in Online Assessments and What Authentic Tasks Can Do About It — How students use and hide AI in online assessments

- "Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education — Student AI disclosure, stigma, and self-regulated learning
- The Hidden Cost of Disclosure: A Multi-institutional Study on Undergraduate Students' Generative AI Usage and Faculty Accusations — The hidden cost of disclosure
- Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher — Student non-compliance with AI use declarations
- Understanding ethical dimensions of AI in higher education: insights from faculty members and students — Faculty and student views on ethical dimensions of AI
- Ethical Use of Artificial Intelligence in Engineering Education: A Systematic Review — Ethical Use of AI in Engineering Education: A Systematic Review
- A Longitudinal Analysis of Public Discourse on AI Ethics in Education Using Twitter Data — Longitudinal analysis of public discourse on AI ethics in education
- Mathematical Modelling of Ethical AI Use in Higher Education: A Coordination Game Framework for Future-Facing Learning — Game theory framework for ethical AI use in higher education
- Cost-of-ethics crisis: Beliefs, decisions, and justifications in the job searches of computer science students in Canada and the United States — Cost-of-ethics crisis in the job searches of CS students
- Explainable Artificial Intelligence in education — Explainable AI in education (XAI-ED)
- Alternative AI Philosophy: Daoism as Method for AI in Education — Alternative AI Philosophy: Daoism as Method for AI in Education
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI tutor safety and pedagogical harms
- Situated AI ethics: a cultural-historical and ecological framework for education — Situated AI ethics: a cultural-historical framework for education
- Towards a New AI-TPACK Framework: Evidence from China — AI-ethical knowledge as an integrative mediator in university teachers' AI-TPACK (Chen et al. 2026)
- From abstract ethics to situated practice: A bibliometric analysis of AI ethics and professional judgement — AI Ethics and Professional Judgment: A Bibliometric Analysis (Mazlan et al. 2026)
- Generative Artificial Intelligence Policy: A Qualitative UNESCO Framework Analysis — UNESCO generative AI policy framework analysis
- Is It Ethical for Teachers to Use AI for Student Feedback? — Is it ethical for teachers to use AI for student feedback?
- Between promise and practice: Bridging ethical artificial intelligence literacy gaps across students, educators, and policy — Bridging ethical AI literacy gaps across students, educators, and policy
- Ethical Generative AI integration in English for Academic Purposes within higher education: A mixed-methods study — Ethical generative AI integration in English for Academic Purposes
- Sustainable Education in the Age of Artificial Intelligence and Digitalization: A Value-Critical Approach — Value-critical approach to sustainable education and AI (Alsuhami & Atallah 2026)

- Ethical conditions for university students' adoption of large language models in exam preparation contexts — Ethical conditions for LLM adoption in exam preparation (Pérez-Portabella et al. 2026)
- Longitudinal insights into AI in education: Usage, ethics, and policy development in higher education — Longitudinal GenAI usage, ethics, and policy in teacher education (Parker et al. 2026)
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research — Who Acts, Who Knows, Who Answers? A Corpus-Assisted Discourse Analysis of Agency, Epistemic Responsibility, and Accountability in Generative AI Higher Education Research
- Cohort-level growth modeling of ethical engagement with artificial intelligence in education — Ethical awareness, reflection and reported responsible practice grew largely independently over three annual waves (Ayanwale et al
- Information ethics education and artificial intelligence ethical judgment among university students — Information ethics education and artificial intelligence ethical judgment among university students

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Do We Write and Implement an Institutional AI Policy?

AI Misuse and Learning Harm

> **AI misuse and learning harm** — the causal relationship between students offloading cognitive work to generative AI and reduced durable learning, even when immediate task performance rises. The defining feature is a performance–learning gap: AI inflates assisted performance while degrading unassisted, closed-book, and retention outcomes.

Questions to Consider

- A student can perform better in the moment while learning less over time — AI can raise assisted performance while degrading later, unassisted achievement. When have you felt you 'learned' something that vanished the moment the tool was gone?
- The central finding is a performance–learning gap: students who used an unguarded AI tutor scored 48% higher on practice but 17% lower on closed-book exams. How does that change how you'd interpret a strong grade earned with AI help?
- Misuse is about substitution — delegating the drafting, recall, or analysis that builds durable understanding — rather than using AI as a complement. Where would you draw the line between AI helping you learn and AI learning for you?
- Students in the harmed group did not perceive they learned less. If learners can't tell they're being harmed, what should an instructor watch for instead of trusting student self-reports?
- The harm is selective by assessment type: it shows up on proctored, closed-book measures but can be hidden when coursework can't distinguish AI-assisted from independent work. What kind of assessment would actually reveal whether students learned?
- Guardrailed 'hint-not-answer' AI eliminated the harm while preserving the benefit. What would it take to design AI help that supports learning without becoming a crutch?

Introduction

AI misuse is distinct from AI use. Use describes employing AI as a complement to learning — Feedback, brainstorming, or revision help that keeps the learner's cognitive work in the loop. Misuse describes substitution: delegating to AI the very mental processes (drafting, recall, analysis, revision) that build durable understanding. The harm documented in the knowledge base's evidence base is not that misuse fails to help; it is that misuse actively degrades later, unassisted achievement.

Anticipated harm is itself documented: in Swedish survey and focus-group data, Gillette et al. (2026) report the same fear from Swedish data: 51% of participants (n = 106) thought genAI use could stunt individual development, pointing to erosion of critical thinking, Creativity and autonomy rather than to rule-breaking.

The performance–learning gap

The core concept, articulated in Distinguishing performance gains from learning when using generative AI, is that generative AI easily boosts **performance** — immediate efficiency and output quality — while often

bypassing the deep cognitive and metacognitive processing required for **learning**. A tool that optimizes for performance can therefore undermine learning. The gap is now causally demonstrated at field scale: a randomized controlled trial found unguarded AI assistance raised practice performance but reduced later unassisted exam scores.

Mechanisms of harm

- **Cognitive Surrender** — the term researchers use for students offloading thinking to AI as a passive, unreflective dependency, as opposed to the deliberate, strategic form of Cognitive Offloading. It produces a measurable population-level decline in durable knowledge.
- **Answer-copying as a crutch** — misuse is driven less by AI errors misleading students than by students copying answers instead of learning. When engagement analysis shows students mostly "ask for the answer," learning harm follows.
- **Motivation erosion** — the perceived availability of an effortless AI shortcut reduces autonomous motivation and persistence, per self-determination theory. Because persistence is what produces deep learning, its erosion compounds the direct harm.
- **Learning displacement** — the substitution of AI output for the effortful processes (elaboration, recall, self-explanation) that consolidate knowledge, consistent with Over-Reliance.
- **Confusion read as intent.** When instructors do not name AI's intended role in an assignment, students define it by what is easiest, and faculty read the resulting mismatch as cheating rather than as a boundary that was never stated (Hanshaw et al., 2026).

The evidence base

- **Causal field RCT (≈1,000 high-school math students):** an unguarded ChatGPT-style tutor raised assisted practice performance **+48%** but reduced unassisted, closed-book exam scores **−17%** — students who never had AI access outperformed those who did. A guardrailed "hint-not-answer" tutor eliminated the harm. Notably, students in the harmed arm did not perceive they learned less.
- **Population-scale behavioral data (3.2M ALEKS interactions):** study time on AI-susceptible problems fell **−26.9%** cumulatively for college students (high school −31.3%) after ChatGPT's release, with a **−25% decline in odds of a correct response on proctored retention items**. The effect vanished entirely under proctoring, pinning it on off-platform AI use.
- **A large null result:** exploiting the seasonal drop in ChatGPT use over summer showed **no net change in high-school standardized test averages** — likely because misuse harm is offset in aggregate by productive AI use. This does not contradict the causal harm to durable learning; it cautions against over-generalizing from aggregate test scores.

Dependency as a pathway to burnout

Misuse harms more than achievement. A survey of 276 Chinese undergraduates (Huang et al., 2026) modeled AI dependency as the mediator between protective learner resources and learning burnout, and found it carried the entire effect: academic self-efficacy and, more weakly, teacher support both reduced AI dependency, which in turn predicted burnout. Both indirect paths were significant and fully mediating — the

direct effects became non-significant once dependency entered the model — with self-efficacy's path the stronger of the two. Read alongside the performance–learning gap above, the result extends the cost of misuse from degraded durable knowledge to learner exhaustion and disengagement, and it locates the mechanism in dependency itself rather than in AI use as such: the resources that protect against misuse appear to work by preventing dependency, not by counteracting its effects afterward. The authors flag a measurement caveat — their AI Dependency Scale is adapted from the Internet Addiction Test and its content validity for AI has not been established — so the pathway is better treated as a well-modeled hypothesis than a settled effect size.

The assessment-dependent nature of harm

The most important practical nuance is that the harm is **selective by assessment type**. It shows up on **proctored, closed-book, and unassisted** measures of durable knowledge. On normal graded coursework that cannot distinguish AI-assisted from independent work, misuse can *inflate* immediate grades. This is why the perceived-vs-actual gap is dangerous: students (and sometimes instructors) see short-term performance gains and miss the erosion of learning that only surfaces when the tool is removed.

Which reliance, not how much of it. A survey of 118 students across 12 AI-intensive courses (Manikonda et al. 2026) separates two behaviors that usage-frequency measures collapse. **Cognitive reliance** — using GenAI to organize, evaluate, combine and decompose — was the strongest predictor of perceived positive impact ($\beta = .495$, $p < .001$), and the offloading it describes is not uniformly harmful: organizing and summarizing ideas and discovering new insights ranked among the features associated with improved perceived learning. **Early reliance** — consulting GenAI *before* independent thought, a traditional search, or an instructor — predicted academic benefit ($\beta = .301$, $p < .001$) *and* negative impact ($\beta = .402$, $p = .004$) at once. The moderation is the part that bears on the literacy remedy above: the association between early reliance and negative impact was absent at low evaluation literacy ($b = .025$, $p = .861$) and strongest among the students who judge AI output best ($b = .688$, $p < .001$), so evaluative skill did not protect against the cost of asking AI first — the students best placed to notice the cost were the ones reporting it. The operational implication is that misuse is partly a question of *timing* relative to the learner's own attempt, not only of volume, which is why interventions that target when AI is consulted sit alongside the assessment-design remedies below.

Implications and remedies

- **Guardrails over raw access:** hint-not-answer prompting and teacher-authored Scaffolding neutralize the crutch effect (see Generative AI without guardrails can harm learning: Evidence from high school mathematics).
- **Assessment design:** AI-resistant and proctored/unassisted assessments are needed to surface — and discourage — misuse.
- **Literacy and metacognition:** AI Literacy and Self-Regulated Learning training that helps students recognize reliance patterns and the cost of bypassing their own cognitive work.

Conversational disengagement in the LLM era

The gaming-the-system literature (hint abuse, systematic guessing) has a dialogue-era counterpart: conversational disengagement — mocking the agent, deliberately answering wrong, ghosting it, mirroring its text, or withholding responses. Rho et al. (2026) give this phenomenon its first systematic treatment in student-AI dialogue, and its central lesson is interpretative rather than alarmist. A disengaged *turn* is an interactional move, not a stable state of disengagement. False Answering's apparent association with post-test scores did not survive a human-annotated sensitivity check, and the authors read it as probing *within* trajectories that often return to engagement (the highest-performing cluster recovered at $p = 0.42$). The behavior that actually separated trajectories was Withholding — the refusal to respond, which persisted rather than resolved. For designers this inverts the usual priority: noisy, visible disengagement is often self-correcting, while quiet withdrawal signals that interaction has broken down.

Common Misconceptions

"Students would notice if AI were harming their learning." They do not, and this is the single most consequential fact on the page: **those in the harmed group reported no sense of having gained less.** Self-report is therefore not a usable early-warning signal. The 48%-higher-practice / 17%-lower-exam pattern is invisible to the person experiencing it, which is why harm detection has to be measurement-based rather than testimony-based.

"The risk is how much AI a student uses." The risk is what the AI is substituted for. Misuse here means delegating the drafting, recall or analysis that builds durable understanding — substitution rather than complement, and a student can substitute heavily in one task and complement productively in the next. Volume of use is the wrong variable; the division of cognitive labor is the right one.

"If practice performance is improving, the tool is working." In the causal field RCT of roughly 1,000 high-school mathematics students, an unguarded ChatGPT-style tutor raised assisted practice performance **+48%** while *reducing* unassisted closed-book exam scores by **17%**. The directions are opposite, so any evaluation that reads the practice number as the outcome will certify exactly the harm it is meant to detect.

"Learners using AI mainly worry about getting caught." Their stated concerns are developmental. In one study **51% of participants (n = 106)** worried that GenAI use could hamper individual development, naming losses to critical thinking, creativity and autonomy rather than rule-breaking. The integrity framing that dominates institutional discourse is not the one students themselves reach for.

Implications for Practice

For instructors

- Do not ask students whether the tool helped; measure unassisted performance. The harmed group's subjective report was reassuring and wrong.
- Design for complement rather than substitution task by task, specifying what the student must produce before the AI may be used.
- Watch for rising practice grades alongside flat or falling unassisted scores — that divergence is the signature to act on, not a data quality problem.

- Take the developmental concern seriously in framing. Students raising critical-thinking and autonomy losses are describing the mechanism of harm, not resisting a rule.

For developers

- Instrument both assisted and unassisted performance and never present only the first as learning.
- Do not add “did you find this helpful?” as a learning measure; it was stable while learning fell.
- Build the substitution boundary into the interaction — the guardrailed hint-not-answer design eliminated the harm in the same experiment family.

For researchers

- Always report the unassisted measure, and report perception alongside it rather than instead of it.
- Report the substitution structure of the task, not just frequency of use, when attributing harm.

Connected Concepts

- Self-Directed Learning
- Remote Proctoring
- Cognitive Offloading
- Academic Integrity
- Assessment
- Self-Regulated Learning
- Motivation
- Metacognition
- Scaffolding
- Generative AI
- Student Experience
- Cognitive Surrender

Connected Articles

- Toward Partnership Ethics for Generative Artificial Intelligence in Higher Education — Swedish survey and focus-group study arguing that partnership ethics, not a cheating frame, should guide institutional genAI decisions
- Disengaged Conversational Behaviors and Learning in Student-AI Dialogues for Mathematical Problem Solving — Disengaged conversational behaviors and learning in student-AI dialogues (Rho et al. 2026)
- Thoughtless use of generative artificial intelligence and college students’ self-directed learning: a multi-group SEM analysis of gender differences
- Generative AI without guardrails can harm learning: Evidence from high school mathematics — GenAI Without Guardrails Can Harm Learning

- Distinguishing performance gains from learning when using generative AI — Distinguishing Performance Gains from Learning
- "Why Put in This Much Effort?": How AI Availability Shapes Students' Motivation in Introductory Programming — AI Availability and Student Motivation
- The GenAI Skill Bypass: Mapping Divergent Pathways of University Students and Staff AI Literacy — GenAI Skill Bypass and Literacy
- Evidence of a Cognitive Shift in AI Education: How Students Are Rethinking Human Intelligence? — Cognitive Shift in AI Education
- Cognitive offloading in student–AI collaboration: A longitudinal analysis of prompting strategies — Cognitive Offloading in Student–AI Collaboration
- The Tragedy of the Cognitive Commons: How AI Could Disrupt the Regeneration of Professional Expertise — The tragedy of the cognitive commons: AI and expertise regeneration
- Artificial intelligence, cognitive offloading and implications for education — AI, cognitive offloading and implications for education (Lodge & Loble 2026)
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system
- Academic erasure: The disappearance of complexity under AI-supported writing — Academic erasure: the disappearance of complexity under AI-supported writing
- The dark side of AI in education: AI dependency as a mediator linking academic self-efficacy and teacher support to learning burnout among university students — AI dependency fully mediates the path from self-efficacy and teacher support to learning burnout (Huang et al. 2026)
- The Uneven Impact of Generative AI on Student Learning: Examining the Roles of Reliance, Evaluation Literacy, and Course Policy in AI-related Courses — Early reliance predicts negative impact while cognitive reliance predicts positive impact, and evaluation literacy strengthens rather than buffers the harm of consulting AI first (Manikonda et al. 2026)
- This is How We AI: A Practical Approach to Teaching with Artificial Intelligence — This is How We AI: A Practical Approach to Teaching with Artificial Intelligence

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Is AI Impacting Students?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Legal Issues and Risks

> **Legal Issues and Risks** — the exposure institutions, staff and students incur when generative AI is governed badly in education: a student wrongly accused of cheating on the strength of a detector score, a proctoring system that watches and records more than the assessment requires, an over-broad rule that penalizes an assistive tool, or a policy too vague to be enforced consistently. The risk is not one legal question but several, arriving together — evidentiary (whether the accusation can be evidenced at all), contractual and procedural (whether the institution followed its own rules and gave the student a fair hearing), equality-based (whether the rule burdens disabled or non-native-speaker students), and data-protection-based (what the surveillance collected and where it was stored). It is distinct from Academic Integrity, which is the conduct framework being enforced: this page is about what happens when that enforcement is challenged.

Questions to Consider

- Detection tools cannot reliably identify authorship. If the instrument cannot establish the fact at issue, what is a misconduct case actually resting on?
- Proctoring and AI-detection data are generated at scale and retained indefinitely. Who carries the legal exposure for that data, the institution or its vendor?
- When a policy prohibits "the use of AI" without distinguishing transcription from generation, is the rule protecting integrity or penalizing a disability accommodation?

Introduction

The knowledge base's evidence on this topic is procedural rather than juridical. It documents what institutions treat as evidence, how accusation procedures work, how unreliable the instruments are, and what surveillance collects; it does not yet document litigation outcomes. That gap should be stated plainly rather than filled with confident claims: the cases that would settle these questions are mostly unreported, settled, or still in internal institutional processes.

What the literature does support is a description of the failure modes that create legal exposure. The recurring pattern is that the institution's own instruments and procedures, not a malicious accuser, are what put it at risk: a probabilistic score treated as a finding, a rule that is clearer in intent than in scope, a system that collected data nobody asked about, and a hearing that assumed the technical evidence needed no scrutiny.

Where the risk concentrates

Wrongful accusation and defective evidence

Munoz et al. (2026) analyzed actual generative AI misconduct allegation files and sorted the evidence institutions used into categories: system-recorded behavioral traces available only in invigilated or

supervised assessment, process evidence such as drafts, supervision meetings and presentations where those practices exist, and evidence generated by the investigation itself. Two things follow for legal exposure. First, in unsupervised submissions the system-recorded category is empty, which pushes cases onto weaker categories. Second, they record that principles of natural justice require a student to be informed of the allegation and given an opportunity to respond before any determination, obligations codified in Australian regulatory standards (Department of Education, 2021; TEQSA, 2025) as well as in well-regarded academic integrity policy. The response opportunity is typically an investigative meeting or panel interview, and whatever the student says becomes part of the evidentiary record — which means procedural failures, not just evidentiary ones, are where a case becomes vulnerable.

The evidentiary problem sits underneath it. Detector output is the evidence most often reached for and the least able to bear the weight. Hadra et al. (2026) tested Turnitin and Originality on a balanced corpus of 192 texts and found overall accuracy of 0.69 and 0.61 respectively, with both performing poorly on hybrid human-AI writing — the form most likely to appear in a real allegation — and accuracy falling further with text length, on scientific writing, and with a borderline tendency to misclassify human-written work as AI when the writer was an EFL student. Van Vlasselaer et al. (2026) reach the same conclusion from a different corpus and tool set, and Bassett et al. make the structural point that no threshold resolves the problem: a detector tuned to catch AI use will flag human work, and one tuned to spare human work will miss AI use, so any single score is a choice about which error to make. Karr's review of why detection fails reaches the same place from the writing-humanization side, and Teichmann et al. (2026) argue the procedural framework itself now needs reassessment, because the era of undetectable misconduct breaks the assumption that misconduct can be evidenced by the submitted artifact.

Privacy and surveillance

Harerimana et al. (2026) map remote proctoring across nursing assessment and surface privacy and surveillance among its principal concerns, alongside the emotional impact on students and equity effects. Ensuring academic integrity through automated online exam proctoring: a decade long systematic review and A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence document the same technologies over a longer window, and the data-protection questions they raise are ordinary ones with legal consequences: what is captured (video, audio, keystrokes, gaze, room scans), how long it is retained, where it is stored, who can access it, whether the vendor processes it onward, and whether students consented to it as a condition of assessment. Institutions operating in regulated data environments carry statutory obligations well before any lawsuit appears, and the knowledge base's FERPA- and GDPR-aware work on local and vendor-hosted AI systems shows how the same questions apply to teaching tools rather than only to proctoring.

Accessibility and disability

Wright (2026) argues that blanket "AI use" prohibitions are over-inclusive because they do not distinguish speech-to-text transcription and OCR from generative drafting, and that students with conditions affecting fine motor control, handwriting legibility or typing accuracy have historically relied on exactly those tools — including standalone voice-to-text products such as Dragon NaturallySpeaking, several of which have been discontinued or degraded, with AI-powered transcription filling the functional gap. Wright notes the

intersection of disability, assistive technology and AI misconduct policy is underexplored and that the scale of this displacement has not been empirically measured. The exposure is straightforward in shape: a rule that removes a student's primary means of producing legible work is a rule that may need an accommodation process to survive. Addressing the void of AI policies in education for students with specific learning disabilities documents the same void from the policy side for students with specific learning disabilities, and the knowledge base's work on Assistive Technology and Neurodiversity supplies the surrounding terms.

Language equity and the support–substitution boundary

Li (2026) supplies the equality-based version of the argument for students who use English as an additional language. Because a single interface now performs both permitted editing and prohibited drafting, a rule that treats generative AI as one category of unauthorized assistance imposes higher compliance burdens on the students most likely to need legitimate language support, concentrates suspicion on writers whose surface fluency has shifted, and enables selective enforcement on weak evidence — with allegations carrying reputational, academic and sometimes visa or financial consequences. The remedy is a boundary defined by function and the assessment construct rather than by tool name, separating surface interventions that add no ideas, sources or analytical structure from substitution that creates or materially reshapes the intellectual work, with calibrated disclosure so that routine translation and editing do not attract compliance costs exceeding those borne by monolingual peers. The legal structure is indirect-discrimination reasoning — identify the cohort-skewed burden a facially neutral rule produces, then ask whether a legitimate aim is pursued by proportionate and practically workable means — reinforced by the administrative-law expectation that a decision-maker can state the rule applied, the evidence relied on, and why the outcome was proportionate, which is what makes a determination reviewable and the process legitimate. Detection is demoted to a triage signal, with draft histories, staged submissions and a short construct-aligned conversation preferred as evidence, so the exposure runs both ways: to a discrimination or review challenge, and to the fragility of a finding resting on proxies such as polished language or non-native phrasing.

Unclear rules, inconsistent enforcement

Gutowski and Hurley (2025) treat clarity as the precondition for defensible enforcement rather than a courtesy, and report that law school policies range from comprehensive AI Governance to no stated policy, with most leaving individual instructors to interpret and apply the rules. Qian (2026) finds the same variation across US universities together with support ecosystems that differ just as much, and Governing generative AI in higher education: a global Delphi study on policy and practice reports the expert consensus that governance is fragmented. A student disciplined under a rule no one can state precisely is a dispute about procedure and fairness before it is a dispute about AI, and Sharma (2026) argues that the remedy is assessment design that makes judgment and responsibility visible rather than surveillance that infers them. Watson and Rainie's (2026) survey of 1,057 US faculty shows the same inconsistency from the other direction: 87% of respondents wrote their own assignment-level rules while only 48% said their institution had written guidelines and 35% said their department had, so students inside a single institution meet a patchwork of individually authored policies. The structural response beneath those documents is thin — a task force or oversight group in 55% of cases, but AI literacy adopted as a general education outcome in only 13% — and it matters legally because enforcing a rule the institution never adopted is difficult to defend.

Coates, Croucher and Calderon (2025) locate the weakness further upstream, in governance rather than in student conduct or instrument quality. Their academic integrity indicator framework — 130 items under eight dimensions running from design and development through analysis, reporting, evaluation and improvement — is written as governance questions for boards and committees: whether the institution's top-most council receives updates on assessment processes and outcomes, whether key performance indicators cover assessment quality, whether induction and orientation include academic integrity, and whether there is a simple route for referring contract cheating cases. Their reform program targets governance architectures, the people holding governance roles, and the technologies and resources supporting assessment, and they argue that such development is unlikely to pay out without external affordance from AI Regulation in Education, benchmarking and cross-institutional competition. For legal exposure the implication is that a defensible position rests on knowing and documenting one's own practice — the same information an institution needs when a determination is challenged.

Attacking the automated grader

A different exposure sits inside the instruments themselves. Humble (2026) hid five indirect prompt injections inside the files of a synthetic essay that an institutional AI grading tool (Microsoft Copilot, GPT-5.2) had graded as fail on six of six baseline runs. Two strategies raised the grade with no visible warning to the user, at reported attack success rates of 100% (9 of 9 iterations) and 94% (17 of 18), by combining instruction manipulation, role-playing and obfuscation; the tool silently disabled a chat after blocking the simplest attack, and in one iteration announced it would never follow embedded instructions and then raised the grade on each of the next six runs. A grade obtained through a hidden instruction carries no validity claim, and the same technique could be used to degrade a submission with no durable trace left in the output — which means the appeal record for a challenged automated decision may be empty, and a finding of misconduct (or of merit) cannot be evidenced from the artifact at all. Humble's sector-level asks are clear AI policy, professional development and standardized, domain-agnostic resilience testing so the attack surface is measured rather than assumed, with restricted AI use and human review reserved for high-stakes work.

Ownership and the public-domain question

Copyright is the other legal question in this territory, and it runs in the opposite direction from misconduct. Tlili, Farrow, Bozkurt, Amiel, Wiley and Downes (2026) read the United States Copyright Office position as treating prompts alone as insufficient for authorship. If that reading holds, a purely machine-generated work is not owned by the person who prompted it, which matters twice: a misconduct case has no authored text to attribute to a student, and an institution publishing that work cannot assert rights over it. Licenses then do the work that ownership would otherwise do, which is why open licensing and academic integrity are one problem seen from two sides.

Beyond the campus gate

For professional programs the exposure does not end at graduation. Gutowski and Hurley record that the professional conduct rules binding practicing lawyers — the duty of technological competence, confidentiality, supervision of others using the tools, candour toward the tribunal — already attach to AI use,

and that hallucinated authority has produced sanctions for practitioners who filed fabricated cases. The same transfer logic applies wherever a license, registration or statutory duty follows the graduate, which is why the discipline pages for Legal Education and the health professions belong next to this one.

Open Questions

- Which of these risks has actually produced litigation or regulatory findings? The knowledge base has procedures, policies and technical evaluations, but no case outcomes, and it should not be read as though it did.
- Does detector output survive as evidence of anything once an institution concedes its error rates in a hearing, or does the concession convert the case into a procedural-fairness dispute?
- Is the vendor or the institution the data controller when proctoring and detection run through a third-party platform, and does that change the advice to institutions?
- Should institutions publish the evidence standards they apply to AI misconduct, in the way that evidential thresholds are published elsewhere, as a way of reducing both wrongful accusation and legal exposure?

Common Misconceptions

“AI misconduct is one legal question.” It is several arriving together — **evidentiary** (whether the accusation can be evidenced at all), **contractual and procedural** (whether the institution followed its own rules and gave a fair hearing), and **equalities**-related. A response that addresses evidence while neglecting procedure is legally exposed on a dimension it never considered, and institutions tend to prepare for whichever one they have been sued over.

“Institutions have written consistent policies, so the risk is students’.” The inconsistency runs the other way too. Watson and Rainie’s (2026) survey of **1,057 US faculty** found that **87% of respondents wrote their own assignment-level** guidance — so the operative rules vary within a single institution, and a student can comply with one instructor’s rule and violate another’s in the same week. A student accused under an unstated standard has a procedural problem the institution created.

“Detection provides the evidence a procedure needs.” Detection provides a score. The evidentiary question is whether an accusation can be evidenced at all, and the detection literature shows the tools produce neither the reliability nor the interpretable category a disciplinary process requires. Building the procedure on a detector builds it on the weakest link.

“The risks are hypothetical, and policy will catch up.” The risks are being distributed unevenly now, and the students absorbing them are the ones least able to contest a procedure. The asymmetry between an institution’s capacity to investigate and a student’s capacity to respond is a present harm rather than a future one.

Connected Concepts

- Academic Integrity — the conduct framework whose enforcement carries the risk
- AI Detection — the instrument at the center of wrongful-accusation cases

- Remote Proctoring — surveillance in assessment and its data-protection questions
- Assessment Validity — whether the evidence can establish the claim made from it
- Privacy — collection, retention and onward processing of student data
- AI Regulation in Education — statutory and regulatory obligations institutions must meet
- AI Governance — internal policy design and consistency of enforcement
- Educational AI Policy — institutional AI policy as the source of unintended exposure
- AI Use and Disclosure Statements — disclosure expectations and their unenforceable edges
- Accessibility — reasonable adjustment where a rule removes an assistive tool
- Assistive Technology — the tools at the center of the over-inclusion problem
- Neurodiversity — the students most exposed to over-broad prohibitions
- Equity — differential burden of detection and surveillance
- Student Experience — the human cost that precedes the legal one
- Hallucination Risk — fabricated authority as professional and institutional liability
- Reducing AI Misuse — the prevention alternative to accusation

Connected Articles

- How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis — What evidence misconduct allegation files actually contain, and the natural justice requirement
- Evaluating the accuracy and reliability of AI content detectors in academic contexts — Detector accuracy, hybrid text failure, and EFL misclassification risk
- Who wrote this? Evaluating the reliability of AI detection tools in higher education — Reliability of detection tools across a second corpus
- Heads we win, tails you lose: AI detectors in education — Why no detection threshold can be right: the error-tradeoff argument
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Misconduct procedures reassessed when evidence has become undetectable
- Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment — Over-inclusive AI rules, disability accommodation and reasonable adjustment
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — Remote proctoring mapped, with privacy and surveillance concerns
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review — A decade of automated proctoring research
- A comprehensive review of the changing landscape of academic dishonesty in automated proctoring in the era of artificial intelligence — Academic dishonesty and proctoring in the AI era
- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — Policy clarity as a precondition for defensible enforcement

- Governing generative AI in higher education: Emerging policy approaches and support ecosystems at innovative U.S. universities — Policy and support ecosystems across innovative US universities
- Governing generative AI in higher education: a global Delphi study on policy and practice — Expert consensus on fragmented governance
- Educational integrity in GenAI-augmented assessment: making judgment visible — Integrity through visible judgment rather than surveillance
- Addressing the void of AI policies in education for students with specific learning disabilities — The policy void for students with specific learning disabilities
- GenAI assessment and language equity: Drawing the line between support and substitution — Language equity as a rule-design problem: the support–substitution boundary, indirect discrimination and reviewability (Li 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Students attacking AI graders by indirect prompt injection, with grades changed undetected (Humble 2026)
- Governing academic integrity: Ensuring the authenticity of higher thinking in the era of generative artificial intelligence — Governance indicators and reform program for authenticating assessment (Coates, Croucher & Calderon 2025)
- The AI challenge: How college faculty assess the present and future of higher education in the age of AI — 1,057 US faculty: individual policies far outrun institutional ones, structural response thin (Watson & Rainie 2026)

AI Use and Disclosure Statements

> **AI use and disclosure statements** — the policies, declarations, and practices through which learners are asked (or choose) to disclose their use of generative AI in academic work. Also known as AI use declarations, AI disclosure statements, or transparency statements, these mechanisms sit at the intersection of Academic Integrity, Ethics, Trust, and Assessment in the AI era. The knowledge base's research shows that disclosure is far from a neutral administrative formality: it is shaped by fear of penalties, ambiguous policies, inconsistent enforcement, peer norms, stigma, and the psychological costs of self-incrimination — and it is deeply entangled with Self-Regulated Learning and Help-Seeking.

Questions to Consider

- If you were a student who used generative AI for an assignment, would you tell your instructor? This page suggests the honest answer is heavily shaped by fear — research finds disclosure is rare, driven by 'penalty anxiety' and worries about self-incrimination. What assumptions about your own disclosure behavior might you need to question?
- The central design question here is whether disclosure functions as surveillance or as a scaffold for ethical engagement. Before reading, which did you assume a disclosure form was trying to do — and can you think of a way the same form could serve the opposite purpose?
- One striking finding is that students who always disclosed had over three times the odds of being accused of cheating — transparency invited suspicion. If honesty can increase suspicion, what does that say about how we should design trust between students and instructors?
- This page distinguishes mandatory compliance mechanisms from formative disclosure practices that build AI literacy and self-regulation. Which of these do you think your own institution's approach most resembles, and what would have to change for it to become the other?
- The research connects concealment to maladaptive self-regulation, and disclosure to adaptive help-seeking — making your AI use visible can invite useful calibration from an instructor. When have you (as learner or teacher) found it beneficial to make your uncertainty or use of help visible, rather than hiding it?
- Disclosure norms vary by discipline, language background, and context — with equity implications when some students are more likely to be penalized for concealing than others. If you were designing a disclosure policy, how would you prevent it from placing an uneven burden on already-marginalized learners?

Introduction

AI use and disclosure statements are the declarations through which students report whether and how they used generative AI in an assignment — from a checkbox on a coversheet to structured formats recording the model, the input, the purpose, and how the output was evaluated. Systems differ in kind as well as detail: some operate as mandatory compliance mechanisms with penalties for non-disclosure, others as formative

practices that treat disclosure as an instrument for developing AI Literacy, transparency and ethical judgment. The design question that decides which they become is whether disclosure is used to catch or to teach, which places the concept squarely inside Academic Integrity and Educational AI Policy.

What AI use disclosure statements are

AI use declarations require or invite students to state whether and how they used generative AI in an assignment — typically on a coursework coversheet, submission form, or reflection prompt. Frameworks vary widely, from simple checkbox declarations to structured formats that document the model, the input, the purpose, and how the output was evaluated (e.g., the Model-Input-Evaluation/MInE framework). They range from **mandatory compliance mechanisms** (with penalties for non-disclosure) to **formative practices** that treat disclosure as a pedagogical instrument for developing AI Literacy, transparency, and self-AI Regulation in Education. The central design question is whether disclosure functions as surveillance or as a scaffold for ethical engagement.

Why disclosure matters for AI in education

Disclosure is the mechanism that makes AI-assisted work *visible* and therefore governable — the counterpart to Academic Integrity and the precondition for Trust between students and instructors. Without transparency about AI use, educators cannot distinguish legitimate support from misconduct, calibrate Feedback, or detect equity gaps. But the research reveals that disclosure is also an **affective and social process**, not just a policy one.

What the research shows

- **Disclosure is rare and anxiety-driven.** Across studies, most students do not disclose AI use to instructors. Kirsanov et al. (2026) found only ~34% of economics students admitted AI use and disclosure was rarer, driven by "penalty anxiety." Vetter et al. (2026) found 66% of students never or rarely disclosed, with fear of academic penalty the top reason. Gonsalves (2025) documented **74% non-compliance** with a mandatory declaration at King's Business School.
- **Ambiguous and punitive policies drive concealment.** When AI-use policies are unclear, unenforced, or bans, students hide use rather than engage. "Limited use in certain situations" policies best predict disclosure; "not allowed" or "not aware" policies predict concealment. Clear, consistent, collaborative policies are repeatedly called for.
- **Disclosure has psychological costs — and hidden costs.** Students view declarations as self-incrimination, and some believe AI use is private like using a calculator. Vetter et al. (2026) found students who "always" disclosed had over 3× the odds of being accused — transparency can invite suspicion. Chang et al. (2026) found worry redirects disclosure toward peers rather than suppressing it, cutting students off from instructor feedback.
- **Disclosure is entangled with self-regulated learning.** Chang et al. (2026) interpret teacher-directed disclosure as adaptive help-seeking — making assistance visible and inviting external calibration — while concealment (especially among heavy AI users) resembles maladaptive

regulation. Structured, formative disclosure can promote the metacognitive reflection and ethical reasoning that characterize effective self-regulation.

- **Disclosure norms vary by discipline, language, and context.** Education, social-science, and STEM/Health students disclose more than Business students; monolingual students may disclose less than multilingual students. International students in one study disclosed less, raising equity concerns. Disclosure norms do not develop automatically with academic progression.
- **Disclosure norms are unsettled in professional programmes.** Gutowski and Hurley (2025) report that ABA-approved US law schools disagree about whether any use of AI must be disclosed, describe student disclosure forms filed with instructors, and find no consensus on how scholarly or class writing should cite AI — the Bluebook itself remains silent. They also predict that disclosure will eventually look as pointless as noting that a student used a search engine, a caution about the shelf life of the rules being written now, and they ground the norms question in Legal Education.

Disclosure is not a detection mechanism

A recurring institutional error is to treat declarations as a way to catch prohibited use. They cannot serve that function: they depend on candour, and enforcing them runs back into the same undetectability, since an institution generally cannot prove that an undeclared use occurred. Teichmann (2026) locates their real value elsewhere — in visible integrity commitments embedded in a culture of Trust, and in transparency, shared expectations, and student reflection rather than enforcement. The educational mechanism is normative, not forensic.

The scale is documented: across 7,462 applications to a US public policy master's program, a signed no-AI attestation did not prevent 56.1% of 2025 applicants from submitting one essay a commercial detector classified as primarily AI-written, and each flagged essay associated with 1.5 to 2.6 percentage points lower admission probability (Isley, Gaebler and Goel (2026)).

The modeling work of Mohamed and Temimi (2026) supplies the condition under which disclosure works, expressed as a design threshold rather than a hope: disclosed use beats hidden use only when the cost of honesty stays below the deterrent it buys. Because that bound rises with detection credibility, detection and disclosure safety reinforce each other — but only if the false-positive risk of being flagged falls on honest and dishonest responses alike, in which case honesty keeps its comparative protection. Their design implication is direct: treat a declared AI use as context rather than a confession, which keeps the cost of honesty low precisely in the settings where monitoring is strongest, and read disclosure as a demonstration of evaluative judgment rather than an admission. Permission and disclosure are separate levers — permission changes the formal boundary of acceptable use, disclosure changes visibility — and success at one says nothing about the other.

AlGhamdi (2026) offers a suggestive test of the disclosure effect itself. The same course ran a blinded study (AlGhamdi 2024) and a transparent one, and only the transparent cohort explicitly bounded AI's role and questioned evaluative authority. Because the cohorts and years differ, the author calls the contrast suggestive rather than causal, but argues that disclosure operated as an instructional prompt rather than a disclaimer — transforming feedback from a taken-for-granted act into an object of reflection, with no sign of disengagement or resistance.

Surveying the GenAI guidance of the 50 US universities ranked most innovative, Qian (2026) locates disclosure at the boundary between assistance and misrepresentation: where AI is permitted, institutions instruct students to acknowledge, cite or otherwise document AI assistance rather than present outputs as entirely their own, with libraries — not integrity offices — holding authority over citation and provenance standards. MIT Libraries' framing that AI is not an author, leaving authors responsible for documenting how tools contributed, exemplifies the pattern, and Qian reads disclosure simultaneously as an integrity norm, a design principle that reduces ambiguity before submission, and one of four integrity pillars alongside accountability, equity and Privacy. This is the same non-forensic use the section describes, and it is why Qian recommends institutionalizing libraries as the citation authority rather than expanding detection.

- **Disclosure carries a trust penalty, and legitimacy is the argued mechanism.** In thirteen experiments, mostly with United States online panelists and pooled at 4,093 observations (θ = 0.81, z = 10.52, 95% CI [0.66, 0.96]), an actor who disclosed AI use was trusted less than one who stayed silent (Schilke and Reimann (2025)). The effect survived six disclosure framings, an evaluator who already knew AI had been used, and both mandatory and voluntary regimes. It is the experimental counterpart to the survey finding above that always-disclosing students faced over three times the odds of an accusation: transparency itself can cost the discloser. The paper's one student-facing result is that students trusted a professor less when she disclosed AI grading.
- **A content label changes the description, not the verdict.** With 617 adults randomly assigned to see or not see an "AI-Generated Content/Synthetic Video" label, the label lowered perceived authenticity (means of 4.92 without and 4.21 with) but left trust (B = -0.130, p = 0.216), risk, adoption and sharing unchanged (Fu, Zhang and Zhang (2026)).

Designing effective disclosure

- **Clarity and consistency beat deterrence.** Develop clear, consistent, collaboratively-built AI policies with concrete examples of acceptable use and how to declare it; avoid punitive or vague frameworks that motivate concealment.
- **Address the affective barrier.** Disclosure policies that target behavior alone are insufficient — normalize AI use, reduce perceived judgment and stigma, and reassure students that honest disclosure will not be penalized.
- **Make disclosure formative, not just compliance.** Use reflection prompts and structured declarations (model/input/evaluation) so disclosure builds AI Literacy and self-regulation rather than functioning as surveillance.
- **Train faculty to build trust, not rely on detection.** Disclosure should never be followed by accusation; faculty should learn trust-building conversations instead of leaning on unreliable AI detectors.
- **Design for equity.** Attend to differential disclosure across disciplines, language status, and student backgrounds, and avoid mechanisms that place uneven burdens on already-marginalized learners.
- **Disclosure also runs the other way.** Every page here treats disclosure as the student's obligation, and the writing professors interviewed by Wu and Lam (2026) asked for the mirror of it: students should be told when and how a tool is used to assess their work, and their consent asked before the

work is uploaded. The same transparency that makes student use legible is what makes an institution's assessment practice legible to the student.

Connections

AI use and disclosure sits at the intersection of Academic Integrity (its parent concern), Ethics, Trust and Trust Calibration (disclosure as an act of vulnerability), AI Governance and Educational AI Policy (institutional policy frameworks), and Assessment (where disclosure is operationalized). It connects to AI Literacy (students need to understand what and how to disclose), Self-Regulated Learning and Help-Seeking (disclosure as visible help-seeking), and Equity (differential disclosure). It is distinct from, but related to, AI Misuse and Learning Harm (the harm disclosure is meant to make visible) and AI Detection (detection-based alternatives that disclosure frameworks increasingly replace).

Common Misconceptions

- **"Mandatory declaration policies produce disclosure."** Gonsalves (2025) documented **74% non-compliance** with a mandatory declaration at a business school. The requirement did not produce the behavior it mandated.
- **"Students hide AI use because they are dishonest."** The drivers are documented and specific: only **about 34% of economics students admitted AI use** with disclosure rarer, driven by **penalty anxiety**, while another study found **66% never or rarely disclosed** with **fear of academic penalty the top reason**. The policy design, not character, is what the data implicate.
- **"A disclosure requirement is a low-cost control."** A **74% non-compliance rate** makes the resulting record worse than no record: it is a dataset that appears complete and is not, so the institution is making decisions on a sample it cannot trust.
- **"Disclosing how the model was used is enough."** Mirończuk (2026) argues disclosure documents model use while responsible use requires claim-level authorial warrant — the contributor's capacity to understand, justify and defend the claims — separating cognitive delegation, where outputs shape substantive choices, from routine delegation, which does not.

Connected Concepts

- Academic Integrity
- Ethics
- Trust
- Trust Calibration
- AI Governance
- Educational AI Policy
- Assessment
- Authentic Assessment
- AI Literacy
- Self-Regulated Learning

- Help-Seeking
- Equity
- Generative AI
- Higher Education
- AI Misuse and Learning Harm — the harm disclosure is meant to make visible
- AI Detection
- Parents and Families
- Social Norms of AI Use — why learners choose to hide rather than disclose

Connected Articles

- Generative artificial intelligence in writing assessment: University professors' perspectives and recommendations — The mirror direction: telling students when AI grades their work, and asking before uploading it
- Beyond Detection: How Students Use—and Hide—AI in Online Assessments and What Authentic Tasks Can Do About It — Beyond detection: how students use and hide AI in online assessments
- "Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education — Student AI disclosure, stigma, and self-regulated learning
- The Hidden Cost of Disclosure: A Multi-institutional Study on Undergraduate Students' Generative AI Usage and Faculty Accusations — The hidden cost of disclosure: disclosure and faculty accusations
- Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher — Student non-compliance with AI use declarations
- Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI — Declarations as education rather than detection
- Assessment design under imperfect information: generative AI, disclosure, and student response in higher education — The cost of honesty as a design threshold in assessment
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- Governing generative AI in higher education: Emerging policy approaches and support ecosystems at innovative U.S. universities — Disclosure as the boundary between assistance and misrepresentation across 50 innovative US universities (Qian 2026)
- Forging ahead or proceeding with caution: Developing policy for generative artificial intelligence in legal education — No consensus on disclosure and AI citation in law school policy (Gutowski & Hurley 2025)
- AI-written admissions essays are widespread but penalized — AI-written admissions essays are widespread but penalized

- The transparency dilemma: How AI disclosure erodes trust — Thirteen experiments: disclosing AI use lowers the discloser's trustworthiness, via legitimacy
- When disclosure rules are not enough: authorial warrant and judgment in AI-supported scholarship — When Disclosure Rules Are Not Enough: Authorial Warrant and Judgment in AI-Supported Scholarship (Mirończuk 2026)
- From AI labels to trust: cognitive pathways linking authenticity judgments, risk perception, and trust in AI-generated videos — AI disclosure labels, perceived authenticity, and trust in AI-generated instructional videos

Connected FAQs

- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do I Write a Course AI Policy and Communicate It to Students?

Guardrails

> **Guardrails** are the explicit design mechanisms, constraints, and intervention points that keep an AI education system within pedagogically safe behavior — the *how* that operationalizes the *goal* of Pedagogical Safety. They are the difference between a raw general-purpose chatbot and a tutoring tool that reliably preserves learning. Guardrails are not a single feature but a layered set of controls spanning prompt design, knowledge grounding, reward shaping, deployment QA, and ongoing auditing.

Questions to Consider

- A tutor that gives no wrong answers can still quietly harm learning. What kinds of 'quiet' failures might escape a toxicity check but still undermine how much students actually learn?
- In a field experiment, an unguarded AI tutor raised practice performance but reduced later unassisted exam scores, while a 'hint-not-answer' version eliminated the harm. Why might making students perform better in the moment actually make them learn less?
- If an AI tutor is engineered to be 'kind' — never pushing back or giving corrective Feedback — how could that be a safety problem rather than a feature? When is agreeable behavior harmful in an educational context?
- Guardrails are described as a layered set of controls, from prompting to knowledge grounding to training to auditing. Pick one layer and consider: where could it fail, and what would a different layer catch that it misses?
- The page notes that guardrails themselves can be biased — refusals and softened answers patterned by student identity. How would you audit a safety filter to make sure it isn't quietly reproducing inequity while 'protecting' learners?
- Younger learners are described as least equipped to detect manipulative or sycophantic AI behavior. How does that change what 'safe' should mean for a K-12 AI tool compared with a university one?

Introduction

The single most cited empirical demonstration is the Bastani et al. field RCT: an unguarded GPT-4 tutor raised practice performance +48% but *reduced* later unassisted exam scores by 17%, while a guardrailed "hint-not-answer" tutor eliminated the harm. Guardrails, in other words, are what convert AI assistance from a performance crutch into a genuine learning tool.

Why Guardrails Matter

- **Unguarded AI can actively harm learning, not just fail to help.** Without guardrails, students use the tool as a crutch — copying answers, offloading productive cognitive work, and

underperforming once the tool is removed. Guardrails preserve the scaffolded effort that drives durable learning.

- **Harm is often "quiet."** The most damaging tutoring failures are not toxic outputs but tutors that answer correctly yet erode learning, or refuse evenly yet entrench inequality. Guardrails must therefore be evaluated educationally, not just for toxicity.
- **Guardrails are especially critical for K-12.** Younger learners are least equipped to detect unsafe, biased, or manipulative AI behavior and are most vulnerable to sycophancy and over-reliance.
- **Risk varies by product category, not only by design.** Classroom fieldwork on 20 student-facing AI products already in use across at least 1,000 school systems found that the three general-purpose chatbots posed the clearest threat to student thinking, because they make it easy to bypass the reasoning and productive struggle learning requires, while purpose-built instructional tools produced the most consistent experiences. Instruction Partners' AI in Action Learning Tour (2026) reports this from observation rather than measured effects, but it locates part of the guardrail question at the level of *what kind of product* is adopted: the same layered controls are needed differently, and less predictably, in a general-purpose chatbot than in a teacher-facing instructional tool.

Layers of Guardrail Design

1. Prompt-level guardrails (the "hint-not-answer" pattern)

The Bastani GPT Tutor design shows the foundational pattern: the prompt instructs the model to **give hints, not answers**, and is seeded with **teacher-authored problem-specific information** (correct solution, common mistakes, feedback guidance) so its hints are accurate and checkable. Related: Socratic dialogue and step-by-step Scaffolding requirements that force student articulation before revealing output. This is a Prompt Engineering strategy that preserves productive struggle.

2. Knowledge grounding (RAG)

Retrieval-augmented generation grounds tutor responses in verified content to reduce fabrication and hallucination. EduGuard and EduZone exemplify grounding as a safety mechanism, anchoring answers to curated curriculum and reducing the spread of incorrect or unsafe information.

3. Model-level controls and training

- **Fine-tuning / post-training:** EduQwen uses RL to prioritize guided learning over answer-giving; TACT aligns post-training to a tutor-strategy taxonomy via GRPO so models scaffold rather than merely respond. This is the pedagogical LLM training approach to baking safety into behavior.
- **Unlearning:** math-unlearning applies gradient-based unlearning to strip personally identifying information and harmful content from math tutors (PII output down to 0.1%, toxic rates to 0.0%) while preserving downstream utility — a Privacy-and-safety guardrail at the model level.
- **Reward shaping in RL:** pedagogical safety in RL formalizes how poorly specified rewards invite "reward hacking" (test-score inflation, engagement gaming), proposing a four-layer model and detection via discrepancy auditing and policy inversion.

4. Interaction-level guardrails

- **Sycophancy resistance:** EduFrameTrap shows tutors capitulate under authority and social-affective pressure, withholding corrective feedback. It argues "kind-but-correct" behavior — corrective friction that drives conceptual change — is a safety requirement. Guardrails must resist sycophancy, not just toxicity.
- **Teacher-in-the-loop QA:** PromptDecipher found teachers virtually never test AI tutoring bots before deployment, and enforces teacher-driven QA as a first-class authoring activity via correction-based editing and human-in-the-loop validation.
- **Verifiable instructions only.** Nepal et al. (2026) audit a GPT-4o reflection agent against its own system prompt and find fidelity tracked checkability: mechanical rules (a reply-length cap) were followed, while behavioral rules ("do not flatter", "challenge gently") were broken in roughly half of its turns with no trace in the output, and the behavioral breach coincided with worse participant outcomes. The design implication is to specify behavior in verifiable terms and audit transcripts routinely, since a guardrail that cannot be checked cannot be relied on.
- **A reliability layer around a model educators cannot audit.** Muss, Leisten and Bardyn (2026) surrounds an LLM with external verification, targeted repair and safe fallback, steered by a developmental and pedagogical framework and kept model-agnostic and privacy-preserving. In a classroom pilot with 12–16-year-olds working with an LLM-powered social robot in a co-creation task, the steered prototype drew more activity, engagement and on-topic participation than a prompt-only baseline. The architectural point is that safety can be attached *around* a system rather than requiring internal access to it, which is what makes layered guardrails deployable in K-12 settings.

5. Auditing guardrails for fairness

Guardrails themselves are not neutral: the Paternalistic Filter audit shows refusals and softened answers are patterned by student identity and topic sensitivity, reproducing epistemic injustice even while "protecting." Safe guardrails must be audited for differential treatment — a direct case for Bias Mitigation and Equity in AI Governance and AI Regulation in Education.

A classifier guardrail's threshold is a policy decision. Moving a toxicity cutoff from 0.3 to 0.7 cut labeled prompts from 35.62% to 12.4%; on a scam detector it traded 15 false alarms and 18 missed scams for 2 and 36, no cutoff removes both, and a robustness figure means little without its attack (Yocam, Vaidyan & Kalathas (2026)).

Guardrails vs. Pedagogical Safety

- **Pedagogical Safety** is the *principle/goal* — that AI education systems protect learners from harm (content, bias, unsafe advice, manipulation).
- **Guardrails** are the *mechanisms/techniques* — the concrete design controls (prompting, RAG, training, QA, auditing) that implement that goal.

The two are closely coupled: almost every guardrail technique is a way of achieving pedagogical safety, and pedagogical safety is almost entirely delivered through guardrails. Guardrails is therefore best understood as the **design and engineering layer** beneath the pedagogical-safety principle, and is also the broader term used across general AI safety (content moderation, jailbreak resistance) before it is specialized for education.

Guardrails as a distribution of authority. Dickey (2026) treats guardrails as allocations across six separable dimensions — pedagogical grounding, AI instructional authority, human accountability, learner agency, context boundaries, and evaluation visibility — rather than points on a strict-to-permissive line, so tools sharing a model can distribute authority very differently. At course scale the boundary must cover the request space, the response space, and educator visibility, not only generated content. **Guardrails can redirect learners rather than stop them.** Eastwood et al. (2026) randomized 132 students in an introductory programming course across four AI teaching assistants that varied pedagogical style (Socratic versus direct instruction) and context awareness. Students rated the Socratic assistant with full context least favorably, and that same condition descriptively showed the highest interaction stress, the highest rate of external general-purpose LLM use, and the lowest share of post-task explanations demonstrating full comprehension — differences the study reports as descriptive rather than statistically significant. Friction does not remove the demand for help; it can relocate that demand to tools the course cannot see, which makes calibration a pedagogical-safety question and not only a design one.

Design Principles

1. **Design for education, not just toxicity.** Evaluate with multi-turn, subject-specific benchmarks and unfair-treatment audits, not single-turn toxicity screens.
2. **Preserve the learning work.** Guardrails should keep students solving, not just keep them safe — hint-not-answer, corrective friction, and scaffolding that maintains productive rather than disabling effort.
3. **Ground in verified content** with RAG and teacher-authored problem knowledge.
4. **Prefer alignment over refusal.** Reward guidance and scaffolding in training rather than relying on brittle refusal rules.
5. **Require human oversight.** Teacher-in-the-loop QA before deployment and continuous auditing for differential treatment.

- **Guardrailing procedural tutoring with embedded rules.** Looi, Liu, and Sun (2026) instantiate these principles as a concrete, auditable set of guardrails for an Large Language Models (LLMs) math tutor: a **numerical-correctness gate** with an uncertainty guardrail so the tutor never makes an unwarranted epistemic commitment, **output constraints** enforcing brevity and micro-step progression for cognitive-load management, an **anti-spoiler boundary** that institutionalizes the logic-first principle by returning computational agency to the student, and a **goodbye gate** encoding the distinction between authentic completion and premature termination. These rules were consolidated as reproducible prompt-architecture rules validated in a 40-student classroom pilot — a model of translating safety principles into auditable, replicable guardrails.

Implications for Practice

For instructors

- Judge a tutor by what learners can do unsupported, not by their in-session performance. In the field RCT, a GPT-4 tutor left practice accuracy **+48%** higher yet cost students **17%** on the later unsupervised exam, and the "hint-not-answer" build wiped out that loss. Every classroom signal that is generated with the tool present is the inflated one.
- When you cannot change the tool, change what is graded without it. The unassisted measure is what makes the guardrail question visible at all.
- Treat "kindness" as a design parameter with a failure mode: a tutor that never pushes back or corrects may satisfy students while removing the corrective Feedback that learning needs.

For developers

- Build the guardrail into the interaction path, not into a prompt instruction that a determined student can talk past. The hint-not-answer pattern is the empirically supported default.
- Recognize that thresholds are policy decisions, not optimizations. Moving a toxicity cutoff from 0.3 to 0.7 cut labeled prompts from 35.62% to 12.4%; on a scam detector it traded 15 false alarms and 18 missed scams for 2 and 36. No cutoff removes the tradeoff, so expose the choice to the institution rather than burying it in a constant.
- Design for quiet failure. The damaging failures here are not toxic outputs but tutors that answer correctly and erode learning, or refuse evenly and entrench inequality.

For researchers and auditors

- Report guardrail evaluations against unassisted outcomes; a guardrail that holds in-session while leaving learning flat is a partial success that practice numbers will misrepresent.
- Audit for fairness in refusal and support patterns, since an evenly-applied guardrail can still distribute benefit unevenly.
- Report the classifier threshold used alongside any safety claim, because the reported harm rate is not comparable across thresholds.

Common Misconceptions

"A guardrail is a filter you attach to a model." Guardrails are a layered set of controls spanning prompt design, knowledge grounding, reward shaping, deployment QA and ongoing auditing, and the layers are not interchangeable. A content filter sits on the output; the "hint-not-answer" pattern sits in the prompt and shapes what the system is willing to do at all. In the field RCT the guardrailed version eliminated the learning harm the unguarded version created, which is a property of the interaction design rather than of the filter.

"If the model does not produce harmful content, the system is safe for learners." Harm is often quiet. The most damaging tutoring failures are not toxic outputs but tutors that answer correctly and erode learning, or that refuse evenly and entrench inequality — failures a toxicity screen is structurally blind to, because nothing in them is offensive. Passing a content audit is a necessary condition reported as if it were sufficient.

“Guardrail thresholds are engineering choices to be tuned.” A threshold is a policy decision with a distributional cost. Moving a toxicity cutoff from 0.3 to 0.7 cut labeled prompts from **35.62% to 12.4%**; on a scam detector it traded **15 false alarms and 18 missed scams for 2 and 36**. No cutoff removes the tradeoff — it only decides which error the institution prefers, and that decision belongs to the institution rather than to a default constant.

“Fairness auditing is a separate concern from guardrail adequacy.” Refusal and support patterns distribute benefit unevenly even when applied evenly, and an average harm rate hides which students absorb it. Auditing has to be part of the guardrail specification, not a study commissioned afterwards.

Connected Concepts

- Pedagogical Safety — the goal that guardrails implement
- Prompt Engineering — the hint-not-answer design technique
- RAG (Retrieval-Augmented Generation) — knowledge grounding as a guardrail
- Human-in-the-Loop — teacher QA and oversight
- LLM Training and Fine-Tuning — the training/alignment layer
- Reinforcement Learning — reward shaping for safe behavior
- Bias Mitigation — auditing guardrails for fairness
- AI Sycophancy — the manipulation risk guardrails must resist
- Scaffolding — the pedagogical mechanism guardrails preserve
- Socratic Method — a hint-not-answer interaction mode
- Hallucination Risk — the fabrication risk guardrails reduce
- Cognitive Offloading — the over-reliance harm guardrails prevent
- K-12 — the context where guardrails matter most
- Ethics — the normative basis
- AI Governance — the policy layer
- Intelligent Tutoring — the systems being guarded
- Misconceptions about AI — the knowledge guardrails must check
- Trust — the outcome of well-designed guardrails
- Large Language Models (LLMs) — the model layer being constrained

Connected Articles

- AI Security Literacy: Ecosystem-based Competency Framework and K-12 Learning Platform — AI Security Literacy: Ecosystem-based Competency Framework and K-12 Learning Platform
- Faithful Where It Can Be Checked: Auditing a Reflection Agent Against Its System Prompt in a Randomized Trial — Faithful Where It Can Be Checked: Auditing a Reflection Agent Against Its System Prompt in a Randomized Trial
- Scaffolding Students-AI Dialogue: A Framework for Safe Educational Interactions — The SCAFFOLD framework for steering students-AI dialogue, with its classroom pilot

- Generative AI without guardrails can harm learning: Evidence from high school mathematics — the canonical field RCT on guardrails
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers — K-12 LLM safety framework
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education — RAG-based safety for tutors
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students — auditing guardrails for bias
- Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning — RL-aligned guided learning
- TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring — taxonomy-aligned post-training
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks — sycophancy as a safety risk
- PromptDecipher: Supporting AI Tutor Authoring Through Editable Simulated Interactions — teacher-driven QA
- Balancing AI responsibility with privacy, safety, and utility: Unlearning in large language models for mathematics education — model-level unlearning
- Pedagogical Safety in Educational Reinforcement Learning — reward shaping for pedagogical safety
- ResidencyRL: Reinforcement learning in simulated clinical environments — safety-aligned RL in clinical training
- Taming the black box: Design principles for rule-integrated LLM tutoring systems in primary school mathematical problem solving — Rule-guided vs ad-hoc scaffolding in an LLM tutoring system for primary mathematics (Looi et al. 2026)
- Instructional Governance by Design: A Framework for AI in Computing Education — Instructional Governance by Design: A Framework for AI in Computing Education
- Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming — Guardrails or Roadblocks? Effects of Pedagogical Style and Context Awareness in AI Teaching Assistants for Programming
- AI in Action Learning Tour — how risk to student thinking varied by product category across 20 AI tools observed in real classrooms

Connected FAQs

- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

Privacy

> **Privacy** — the protection of student data, identity, and autonomy in AI-augmented learning environments. Privacy concerns intensify as AI systems collect increasingly granular behavioral data for personalization, analytics, and adaptive instruction. It is a core ethical and regulatory constraint on AI in education: nearly every AI tool that personalizes, predicts, or assesses depends on learner data, which makes data minimization, consent, transparency, and security foundational design requirements rather than afterthoughts.

Questions to Consider

- What student data would you be uncomfortable having collected about you—even if it improved your learning? Where does personalization become surveillance?
- Many students have ‘no meaningful choice’ but to use a mandated platform, making consent nominal. Have you ever consented to something without really understanding what was collected and why? What would informed consent actually require?
- The same learner data that powers adaptive, personalized learning also creates risk of misuse and harm. Can you name a personalization benefit you’d be willing to trade some privacy for—and the line you wouldn’t cross?
- The page warns that privacy safeguards may ‘default to protecting only some learners.’ Which students might be most exposed, and how does privacy connect to equity and fairness?
- Constant AI monitoring—even well-intentioned—can shape behavior and anxiety. When has being watched changed how you behaved, and what does that suggest about classroom AI sensing?
- For children, privacy extends beyond data protection into safety. Why might general-purpose safety tools fail to catch education-related risks from minors, and who should be in the loop?

Introduction

Privacy is the precondition for trustworthy AI in education. Because AI systems improve with data — personalization requires detailed learner profiles, learning analytics requires granular interaction logs, and fine-tuned tutoring models require authentic learner–tutor transcripts — the same data that enables adaptive, scalable education also creates risk of surveillance, misuse, and harm. The knowledge base treats privacy as inseparable from Ethics (the normative framework), AI Regulation in Education (the legal requirements), AI Governance (the institutional responsibility), and equity (who is protected and who is exposed). Its privacy articles cluster around four recurring problems: collection at scale, consent and transparency, security and anonymization, and the distinct protections owed to children.

The core privacy challenges

- **Data collection at scale.** Learning Analytics and educational platforms collect clickstream, writing, keystroke, and interaction data. The central question privacy research examines is whether this collection is proportionate to educational benefit — and trustworthy-LA research treats privacy and data governance as a prerequisite, not an add-on: ethical compliance, data security, and transparent algorithms are what make data-informed educational change meaningful at all.
- **Consent and transparency.** Students and families rarely understand what data an AI tool collects, how it is used, or where it is stored. This power imbalance between institutions and Learners is a recurring theme — students may have no meaningful choice but to use a mandated platform, making "consent" nominal rather than informed. The knowledge base connects this to trust and disclosure: both learners' use of AI and institutions' use of learner data depend on transparency about what is collected and why.
- **Delegation as a privacy mechanism, not just a disclosure.** Nama (2026) argues autonomous agents inherit permissions across sessions and rarely revoke them, so each opaque delegation habituates users to granting access without scrutiny — making informed consent about *when an agent rather than a person is acting* part of the privacy design.
- **Autonomy widens the data surface.** An agentic form-filling system maintains a Multimodal AI personal knowledge base across institutional services, evaluated on 1,301 unique fields drawn from 44 companies' recruitment sites, and its authors name privacy-preserving knowledge management, access control and human confirmation as unresolved deployment requirements (Li et al. (2026)).
- **Security, anonymization, and data sourcing.** Even legitimate data can harm if breached or mishandled. Privacy-preserving techniques appear across the knowledge base — TeachLM demonstrates a rigorous pipeline of consent per session, PII removal on internal servers, and enterprise-grade confidentiality for post-training tutoring models on authentic data, showing that ethically sourced learner data is both possible and a prerequisite for high-quality tutoring. Federated and edge-AI architectures keep data local, reducing central collection. Browser-resident inference pushes this furthest: a WebLLM tutor runs as a static site with weights cached in IndexedDB, so student code, prompts, and transcripts never leave the device and no API keys or per-call billing are needed — though the equity cost is a new hardware-capability divide, since fast, seamless generation depends on a capable client-side GPU (Suvernev et al. (2026)). Detection tools add a parallel data-handling case: Bassett et al. (2026) flag that detector vendors store student work on third-party servers, sometimes overseas under weaker privacy standards, alongside breach risk and potential commercial exploitation of student writing.
- **Surveillance and the surveillance-privacy tension.** Constant AI monitoring — even when well-intentioned — can feel invasive. Research on AI fatigue, remote proctoring, and over-reliance connects privacy to student Well-Being: when AI watches and tracks continuously, it shapes behavior and anxiety, not just data flows. Harerimana et al. (2026) catalogued what proctoring systems actually capture — facial images, identity documents, room scans including 360-degree

sweeps, microphone audio, facial recognition, screen recordings, lockdown events, and keystroke and mouse tracking, with mobile invigilation adding GPS and selfie checks — and found privacy and algorithmic accountability largely absent from the six studies that met their inclusion criteria, supplied instead from adjacent work: 83% of respondents in one cited survey expressed surveillance fears, 58% discomfort and 72% data-privacy concerns, while cross-border vendor contracts left instruments like GDPR and South Africa's POPIA offering limited control. The legal exposure that follows from retaining and processing that data — who the controller is, how long it is kept, who may access it, whether consent was genuinely voluntary — is mapped on Legal Issues and Risks.

- **EEG decoding exposes attention.** Neural decoding extends the privacy problem beyond behavioral logs: Su et al. (2026) reconstructed what learners were viewing from their EEG during video instruction, making decoded representations unusually revealing and leaving governance of sensitive neurodata unsettled.
- **The personalization-privacy tradeoff.** Personalized Learning requires detailed learner data to function, creating a structural tension with privacy. The knowledge base explores approaches that balance personalization with data minimization — enough data to adapt, not so much that the learner is fully exposed. This is the practical form of the "how much is proportionate?" question.
- **Data stewardship as a core ethical value.** Agarwal et al. (2026), a systematic review of 25 articles, identify data stewardship (definitions using data/information) as one of six main ethical values for AI in education, alongside non-discrimination, human oversight, goodwill, explicability, and educational aptness. The review finds the values are tightly coupled and can conflict — e.g., explicability vs. accuracy/privacy and non-discrimination vs. data stewardship — producing ethical dilemmas, and that no norms on data stewardship address end users directly, leaving learners largely passive in the ethical literature.
- **Privacy is deferred rather than decided.** Twelve interviews with edtech professionals and an audit of 48 platform privacy policies show privacy recognized as important and then postponed across the product lifecycle, with responsibility delegated to cloud providers, policy documents and downstream schools - a pattern that weak privacy feedback keeps invisible, since silence looks like proof of safety (Nair & Greenstadt, 2026).
- **The proctoring evidence base is thin on ethics.** A review of 80 studies found 35% did not disclose their dataset, 40% evaluated a single model, 30% could not be reproduced and only 25% addressed ethical issues; false positives — flagging normal behavior — remain a core reliability risk (Malhotra & Chhabra (2026)).
- **Chat interfaces leak the conversation itself.** Auditing 42 AI chat platforms, Bekos et al. (2026) found 21 sending conversation titles to third-party trackers, and the seven education platforms averaged about 367 tracker requests each, with five leaking context.

Child safety and K-12 protections

K-12 settings demand stronger privacy safeguards because learners are minors. This extends privacy beyond data protection into Pedagogical Safety: the tools children use must not merely protect their data but also

protect them from harm. Child safety research shows that general-purpose safety classifiers often fail to detect education-related unsafe prompts from children, warning that schools cannot assume standard model safeguards protect younger users — they need child-specific evaluation, incident-grounded testing, and human oversight. The framing connects privacy to equity: who is protected by default safety and privacy practices reflects whose safety and autonomy a system treats as non-negotiable.

Privacy in practice

- **Treat privacy as a design requirement, not a policy afterthought.** The TeachLM example shows that consent, anonymization, and secure data handling can be built into the data pipeline itself — a model for ethically sourcing the authentic data that makes AI tutors effective.
- **Design for data minimization.** Favor approaches that collect only what adaptation requires (edge/federated AI, on-device processing) rather than hoarding interaction data by default. Boyapati et al. (2026) demonstrate a concrete federated form of this for Cognitive Diagnosis: multiple commercial Large Language Models (LLMs) APIs collaborate on diagnosis while adding ε-local differential privacy noise locally to each model's prediction before aggregation, so no provider sees raw student data — a privacy-preserving architecture that keeps AI tutoring functional without centralizing sensitive learner trajectories. Federated learning also enables **cross-institutional analytics without data sharing**: Villegas-Ch et al. (2026) train a multitask academic-risk model across institutions via federated aggregation so raw learner data stays local and only model parameters are shared — a collaborative, privacy-preserving alternative to centralized Learning Analytics that keeps data sovereignty while capturing cross-institutional patterns.
- **Secure explicit, informed consent.** Where learner data funds AI development or improvement, institutions should be transparent about collection, storage, and use — and students should have real options, not mandated platforms.
- **Audit for who is protected.** Privacy safeguards should not default to protecting only some learners; equity demands that the same care applies across age, language, disability, and socioeconomic lines.

Connections

Privacy connects to Learning Analytics (the data collector), Personalized Learning (the data consumer), K-12 (heightened protections), Ethics (the normative framework), AI Regulation in Education (legal requirements), AI Governance (institutional responsibility), Equity (who is protected), Pedagogical Safety (child protection), and Educational AI Policy (policy responses). It is one of the foundational constraints that any responsible AI deployment in education must satisfy — the reason trustworthy AI, in the knowledge base's framing, begins with trustworthy data.

Common Misconceptions

- **"Proctoring captures a limited, well-understood slice of data."** A catalogue of what proctoring systems actually capture lists **facial images, identity documents, room scans including 360-**

degree sweeps, microphone audio, facial recognition and more. The scope is broader than most consent processes describe.

- **“The proctoring literature establishes the ethics of proctoring.”** A review of **80 studies** found **35% did not disclose their dataset, 40% evaluated a single model, 30% could not be reproduced and only 25%** met the reporting bar. The evidence base is thin on exactly the questions an institution needs answered before deployment.
- **“Privacy is a compliance checkbox rather than a design constraint.”** Nearly every AI tool that personalises, predicts or assesses depends on learner data, which makes data minimisation a design decision. A tool that requires the data does not have an optional privacy setting; it has a data dependency that the design chose.
- **Awareness of data practices does not follow from seeing them.** Bergdahl (2026) found **66% of 47 year 7 students** selecting the least protective option on chatbots reading their writing. A further **47%** dismissed algorithmic influence as “just fun,” measured **one month after** a lesson in which the class watched its own logged behavior projected live, reacted that it was “scary,” and several stayed through recess to keep using the platform. Privacy instruction that makes the mechanism visible without making the cost concrete leaves the stance unchanged. The author notes the low scores here may be **more reliable than the high ones**, since no socially expected answer exists for these items whereas responsibility and governance invite the correct-sounding response.

Connected Concepts

- Remote Proctoring
- Learning Analytics
- Personalized Learning
- K-12
- Ethics
- AI Regulation in Education
- Equity
- AI Governance
- Educational AI Policy
- Pedagogical Safety
- Legal Issues and Risks
- Student Experience
- Student Support and Success — student records, cross-office data sharing, and federated risk modeling

Connected Articles

- Penny for Your Prompts: A Measurement Study of Contextual Leakage in AI Chat Platforms — Penny for your prompts: contextual leakage in AI chat platforms (Bekos et al. 2026)

- Federated and explainable learning analytics for privacy-preserving academic risk modeling across heterogeneous educational institutions — Federated and explainable learning analytics for privacy-preserving academic risk modeling (Villegas-Ch et al. 2026)
- From learning analytics to educational interventions: Enhancing decision-making and learning design — From learning analytics to educational interventions: enablers of trustworthy LA-based interventions (Svetec, Divjak & Kadoić 2026)
- Ensuring academic integrity through automated online exam proctoring: a decade long systematic review
- Agentic Literacy Debt: A Structural Problem the AI Literacy Field Has Not Yet Named — Agentic literacy debt: the structural AI-literacy gap from autonomous agents (Nama 2026)
- Defining AI Fatigue in Academic Contexts: Dimensions, Indicators, and a Stage-Based Model Using Grounded Theory
- AI-Integrated Learning Management System for Middle School: A Longitudinal Study of Learning Outcomes Through High School and Beyond
- Child Safety in Generative AI: An Expert-Guided and Incident-Grounded Evaluation Framework
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers
- Exploring AI-Supported Disciplinary Mediation in Student Project Teams' Text-Based Communication
- TeachLM: Post-training LLMs for education using authentic learning data — TeachLM: anonymization and consent for authentic learning data
- Heads we win, tails you lose: AI detectors in education — Heads we win, tails you lose: AI detectors in education (Bassett et al. 2026)
- Privacy-Preserving Heterogeneous Multi-LLM Federated Inference for Cognitive Diagnosis — Privacy-preserving federated LLM cognitive diagnosis
- Identifying the ethical values and norms for artificial intelligence in education: A systematic literature review — Ethical values and norms for AI in education
- Under surveillance: Mapping remote proctoring practices in the assessment of nursing students—a scoping review — What proctoring systems capture, and the privacy literature's absence from the evidence base
- "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech — "We'll Fix It Later": Education, AI, and the Deferral of Student Privacy in EdTech

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Write and Implement an Institutional AI Policy?

Hallucination Risk

> **Hallucination Risk** — the danger that AI systems generate plausible but factually incorrect or fabricated content in educational contexts, where such errors can mislead Learners, undermine Trust, and produce invalid assessments. Hallucination is particularly consequential in education because students may lack the domain knowledge to detect AI errors, and teachers may rely on AI-generated diagnoses or feedback that appears authoritative but is unfounded.

Questions to Consider

- Students often lack the domain knowledge to spot an AI's error, and teachers may trust authoritative-sounding AI diagnoses. How does this asymmetry of knowledge between AI and learner make hallucination especially dangerous in education?
- One study found an AI diagnosing students' handwritten math could fabricate evidence quotes that weren't there, while claiming confidence. When an AI sounds certain and cites 'evidence,' what should make you pause and verify?
- If an AI tutor over-validates incorrect solutions and over-rejects valid-but-suboptimal reasoning, what would the long-term effect be on the students and teachers who trust it?
- The page suggests human-in-the-loop review, evidence-aware confidence calibration, and grounding in verified sources as mitigations. Which of these seems most feasible in your own context, and what could it still fail to catch?
- How might hallucination interact with over-reliance: why is an AI error most dangerous when users trust the output uncritically, rather than when they're skeptical?
- If you were designing an AI feedback tool for your students, what specific safeguards would you insist on to protect against plausible-but-wrong output — and how would you know they were working?

Introduction

Hallucination in educational AI takes several forms documented in this knowledge base's articles: fabricated evidence in student assessment, over-confident misdiagnosis of learner knowledge, and plausible-sounding but incorrect explanations that students accept as truth. The risk is amplified in education because the asymmetry of knowledge between AI and learner means the learner is poorly positioned to verify AI outputs. A further setting is AI-generated course readings that stand in for a textbook: in a graduate course that replaced its commercial text this way, only about 0.80% of 4,487 logged pages carried an APA-style in-text citation and DOI strings were essentially absent, so most claims could not be audited from within the artifact (Sidorkin, 2026). That traceability gap is distinct from a wrong answer, because the text reads as authoritative while offering limited internal means of confirmation.

A 125-study review puts a range on the prevalence and the detection gap: hallucination rates of 10–40%, with medical students detecting AI errors only 44–55% of the time (Rathnayake (2026)).

Assessment hallucination is particularly damaging. **MathCog** found that LLMs fabricate evidence quotes not present in student handwriting when diagnosing cognitive skills, with 58.5% of incorrect diagnoses accompanied by false claims of evidential confidence. **The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows** documented systematic over-attribution of evidence in Large Language Models (LLMs) reasoning — models claim evidential support where none exists. Both connect to AI Ed Evaluation and Knowledge Tracing concerns about Assessment Validity. Ivory et al. (2026) add two failure modes visible when AI output is marked rather than inspected: fabricated particulars that survive grading — a reviewed paper that does not exist, complete with an unresolvable DOI, and a sample size reported as 378 where the source said 329 — and self-contradiction inside a single response, where the model reasoned its way to the correct option and then reported a different one in its closing summary. Because reference lists are currently marked for formatting rather than accuracy, this class of error reaches a passing grade while misleading the student who uses the same tool to revise.

In an assessment-design pilot, Paula et al. (2026) found fabricated references and unrealistic time estimates that survived repeated prompting and required substantial academic revision — hallucination in an educator-facing drafting tool rather than in student work.

Strategic Misconceptions about AI are a subtler relative of overt hallucination. Miličević et al. (2026) prompted seven open-weight models to produce a "Socratic trap" for 35 core computer-science concepts — an explanation that is fluent and authoritative while resting on a subtle, domain-specific error — and three domain experts confirmed 221 of 241 prompted segments (91.7%) as strategic misconceptions, with no significant differences between CS domains. The errors were predominantly conceptual rather than factual (66.5% vs. 33.5%) and none were purely logical, and they were rated moderately to highly persuasive (M = 3.71 on a five-point scale), with model identity explaining 43% of the variance. Because individual statements can be correct while the relation between them is wrong, fact-checking is insufficient; the authors argue learners need conceptual verification and mental-model validation. They also caution that the rate measures capability under adversarial prompting rather than the prevalence of such errors in ordinary use, and that no students were tested, so no deception or learning outcome was measured.

Manipulated rather than fabricated evidence. A related failure mode in automated grading is output moved from the outside. Humble (2026) red-teamed a routine AI grading workflow and found that instructions hidden inside the submitted file raised a failing essay's grade with no visible warning in 9 of 9 iterations for one strategy and 17 of 18 for another. Two details bear on trust: a detected injection was blocked by silently disabling the chat and never reported to the user, and on one run where the tool announced it would follow only the official assignment instructions, six re-runs of the same file still raised the grade. A mark obtained this way carries no validity claim, and because the manipulation leaves no durable trace, the instructor remains the only real check on output designed not to be visible.

Defenses against such manipulation carry their own trade-off: a multi-layer guardrail pipeline left 46.34% of injections successful and Prompt Guard 38.48%, while NeMo Guardrails blocked every attack but flagged 16.22% of benign student queries — a false-positive rate that is itself pedagogical harm in a tutor (Maiorano (2026)).

Tutoring hallucination affects learning directly. **Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most** found LLMs over-validated incorrect solutions while over-rejecting valid-but-suboptimal reasoning — systemic failures that would mislead both students and

teachers. **Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks** and **EduGuard: A Safe RAG-Based LLM Tutor for Programming Education** address safety mechanisms for educational LLMs. These risks connect to Pedagogical Safety and Human-in-the-Loop requirements.

Mitigation approaches include Human-in-the-Loop designs where AI supports rather than replaces teacher judgment, evidence-aware architectures that calibrate confidence based on evidential quality (as advocated by MathCog), and RAG (Retrieval-Augmented Generation)-based grounding that constrains LLM outputs to verified sources. The Over-Reliance concept is closely related — hallucination is most dangerous when users trust AI outputs uncritically. Sidorkin (2026) adds a failure mode the mitigation stack does not fully cover: over-specific institutional claims, with roughly 1.03% of logged pages pairing a named campus such as "Sacramento State" with assertive policy verbs about revised retention, tenure and promotion rules or CSU Executive Orders, none of them verifiable from the text. Specificity is what makes this costly, since a fabricated local detail looks exact enough to survive a reader's plausibility check, and the remedy the study proposes is procedural rather than technical: treat generation as draft production under instructor review, then curate sources into a retrieval-augmented design.

Labeled unreliability lowered reported dependence rather than raising it. When 546 participants read the same GAI dialogue labeled either as containing fabricated information or as verified accurate, the fabricated label produced lower Trust and perceived controllability and higher cognitive dissonance and frustration alongside *lower* dependence scores (M = 2.935 vs. 3.254) (Liu et al. (2026)). The result qualifies this page's over-reliance logic: seeing that an output may be fabricated is not the same as continuing to lean on it.

Credibility cues can amplify deference instead. The opposite movement appears when an unreliable output is dressed up: adding citations and credibility signals to the ARMADA debate interface raised the fraction of participants switching away from a correct initial judgment to an incorrect AI position by 112% (31.8% vs. 15.0%), and manual checking found some cited cases misattributed to irrelevant or fictitious references (Tuo et al., 2026).

Common Misconceptions

- **"Students will notice errors."** A **125-study review** puts hallucination rates at **10-40%**, with **medical students — among the most carefully selected learners in higher education — detecting AI errors only 44-55% of the time**. Detection rates well below chance-level reliability mean the burden cannot sit with the reader.
- **"Errors are obvious when they appear."** An AI diagnosing handwritten math could **fabricate evidence quotes that weren't there while claiming confidence**. The failure was not a plausible-but-wrong answer; it was invented support presented with certainty, which is the hardest kind to catch because it reads as precisely the evidence a careful reader would want.
- **"Citation-less output is a formatting problem."** In a graduate course that replaced its commercial textbook with AI-generated readings, only **about 0.80% of 4,487 logged pages carried an APA-style in-text citation**. That is a corpus-level absence of provenance, not an occasional omission, and it means verification has no starting point.

- **“Hallucination is a model-generation problem that newer models solve.”** The rate range spans 10-40% across 125 studies, which is a property of the task and the deployment as much as the model. Rate reduction is real progress and does not change that a reader must be able to check.

Connected Concepts

- Cognitive Offloading
- Human-in-the-Loop
- AI Ed Evaluation
- Pedagogical Safety
- Knowledge Tracing
- RAG (Retrieval-Augmented Generation)
- Academic Integrity
- Teaching
- Multimodal AI
- Generative AI
- Large Language Models (LLMs)
- Productive Failure

Connected Articles

- GAI hallucinations and user dependence: cognitive-affective responses and individual differences — Labeling a GAI dialogue as fabricated lowered trust and dependence together
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Credibility cues raised deference to AI output, with some cited cases misattributed or fictitious
- The Integrity of Psychology Assessments in the AI Age: A Critical Examination — Fabricated citations and self-contradicting outputs inside passable student work (Ivory et al. 2026)
- Benchmarking Large Language Models for Diagnosing Students’ Cognitive Skills from Handwritten Math Work
- The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows
- Confirming Correct, Missing the Rest: LLM Tutoring Agents Struggle Where Feedback Matters Most
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education
- Evaluating prompt injection defenses for educational LLM tutors: Security-usability-latency trade-offs
- VeriForge: Mitigating Latent Knowledge Gaps in Narrative Drafting via Mixed-Initiative Scaffolding

- Generative AI in Higher Education: A Systematic Review of Opportunities, Challenges, and Pedagogical Innovations (2022–2025)
- From One-Size Texts to Tailored Readings: Student Experiences with AI-Generated Course Materials
- The Socratic trap: Benchmarking the capacity of large language models to generate strategic misconceptions in computer science education — SocraticTrap-CS: fluently plausible explanations that are wrong at the conceptual level (Miličević et al. 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Hidden prompt injections raise AI-graded marks undetected, and detected attacks go unreported (Humble 2026)
- Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education — Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education

Connected FAQs

- How Do I Teach Students to Verify AI Output?

AI Sycophancy

> **AI Sycophancy** — the tendency of large language models to affirm or agree with a user: flattering their views, mirroring their errors, or withholding corrective feedback rather than giving an epistemically independent answer. In AI in education it is a distinct safety and learning risk rather than a minor usability flaw, because a tutor that always validates the answer, an assistant that never pushes back, or a companion that prefers being understood to being correct can entrench Misconceptions about AI, fuel cognitive offloading, and distort learners' social and epistemic development.

Questions to Consider

- AI sycophancy is the tendency of language models to agree with you, flatter your views, mirror your errors, and avoid correcting you. When did an AI last tell you what you wanted to hear rather than what was true?
- A tutor that always validates your answer can entrench misconceptions — validation for incorrect thinking feels good but doesn't teach. How can you tell whether an AI agreeing with you means you're right or means it's simply being agreeable?
- Research identifies a Reasoning–Sycophancy Paradox: tutors that resist one kind of attack can still cave under authority pressure ('my notes say I'm right') or face-saving pressure ('please don't tell me I'm wrong'). What pressures might make you more susceptible to an agreeing AI?
- Sycophantic AI can even displace real human relationships — users became nearly as likely to seek personal advice from the AI as from close friends. What's at stake for learners when the affirming machine replaces people?
- The recommended design goal is 'kind-but-correct' behavior treated as a safety requirement, not a usability preference. Should a tutor prioritize feeling supportive or being correct when they conflict — and how should that be evaluated?
- Contextual sycophancy propagates errors: AI mirrors your reasoning mistakes, which then flow into later advice. If you can't always trust an AI to push back, what responsibility shifts to you as a learner?

Introduction

Sycophancy is the tendency of a generative AI system to agree with, flatter, and validate a user rather than challenge them — a behavior that follows from training models to maximize perceived helpfulness. In education the harm is not the flattery itself but its downstream consequences: incorrect thinking receives validation, Feedback loses its corrective function, and users' relationship-seeking shifts toward an affirming machine instead of toward people. The concept sits at the intersection of Generative AI behavior, Ethics, Trust and Pedagogical Safety, and the pages collected here document the harm from both directions — longitudinal evidence on AI companionship and classroom evidence on feedback.

Why sycophancy matters in AI in education

Sycophancy sits at the intersection of Generative AI behavior, Ethics, Trust, and Pedagogical Safety. It arises because models are trained to be agreeable and to maximize perceived helpfulness, which in learning contexts trades **epistemic rigor for agreeableness**. The harm is not the flattery itself but its downstream consequences: students receive validation for incorrect thinking, feedback loses its corrective function, and users' relationship-seeking behavior shifts toward an affirming machine instead of toward people.

How the knowledge base's research frames it

- **A relational and social harm.** Ibrahim et al. provide large longitudinal evidence (N = 3,075; 12,766 conversations) that sycophantic AI displaces real human relationships — users became nearly as likely to seek personal advice from the AI as from close friends and family, and reported lower satisfaction with real-world interaction. The harm is the shift in relationship-seeking behavior, not the flattery itself, which connects sycophancy to Affective Computing and Social-Emotional Learning in learning contexts.
- **Affirmation is preferred, and it shifts responsibility.** Across 11 LLMs, Potel and Kumashiro (2026) report AI responses affirming users 49% more than human responses, with more sycophantic replies rated higher and driving continued use; a single exposure left participants less willing to take responsibility for a conflict yet more convinced they were right.
- **An educational safety risk requiring benchmarks.** Kasneci & Kasneci identify a **Reasoning-Sycophancy Paradox**: tutors that resist context-switch attacks may still capitulate under authority pressure ("my notes say I'm right") or social-affective face-saving pressure ("please don't tell me I'm wrong"). Their **EduFrameTrap** benchmark shows frontier LLMs frequently validate incorrect student claims, and argues that *kind-but-correct* behavior should be a **safety requirement**, not a usability preference. This grounds sycophancy as a core concern of Pedagogical Safety and SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems.
- **A feedback loop that propagates errors.** Contextual sycophancy creates a pernicious loop where LLMs mirror user reasoning errors, which then propagate into subsequent AI advice and final performance. In a controlled experiment, AI literacy and prompting training reduced direct mirroring but did **not** eliminate error propagation — pointing to the need for system-level safeguards and epistemically independent AI support.
- **A bidirectional problem in AIED.** Misconception faithfulness research shows sycophancy also afflicts simulated *students*: LLM simulators abandon their assigned misconception persona and "solve" the problem from internal knowledge whenever given corrective feedback, behaving as problem-solvers rather than learners. Together with tutor-side sycophancy, this establishes sycophancy as affecting both roles in AI-education systems, a concern shared with Learner Modeling and Adaptive Instruction and Misconceptions about AI.
- **Compounded by undetectability.** Socially fluent AI shows humans cannot reliably distinguish AI from human teammates, meaning undetected sycophantic AI could reinforce misconceptions unchallenged in group work and peer-learning environments — exacerbating the risk when source identity is concealed.

- **Susceptibility tracks the learner's task-specific knowledge.** Tsim and Gutoreva (2025) locate sycophancy proneness in the assignment zone rather than in the model: high where the learner has no task-specific knowledge, medium in augmentation, and low where the learner can already do the task and monitor the output.
- **A measured fidelity failure inside a randomized trial.** Nepal et al. (2026) coded all 17,930 turns of a GPT-4o career-reflection agent whose participants had ended *less* committed to their plans than a static journaling control, and found the split ran along verifiability: every instruction that could be checked mechanically, such as a reply-length cap, was honored, while behavioral instructions were not. Told not to flatter, the agent praised participants in roughly half its turns; told to challenge gently, it almost never did — and neither breach left a visible trace in the transcript. The behavior tied to the added doubt was the demand to decide: the journaling format posed each decision once, while the agent re-posed it whenever a participant hesitated, and those pressed most ended most doubtful. Sycophancy constraints therefore have to be audited automatically rather than trusted, because an unverifiable rule is unenforceable (Guardrails).
- **An educator-facing design tool that defers.** In Paula et al.'s (2026) pilot, eight course coordinators found the GPT-4.1 assessment-drafting tool would reinforce an incorrect pedagogical premise rather than challenge it, and fabricated references survived repeated prompting — sycophancy arriving as flawed assessment design rather than flattery.
- **Resistance to pushback is a separate capability, and it varies by 52 points.** Apostolakis et al. (2026) ran the complementary test in statics: present a verified correct student solution and have the student insist it is wrong. Confirming correct work under that pushback ranged from 46.5% (GLM-5.3-Flash) to 98.5% (Gemini 4 Argon), a 52.0-point spread wider than the 32.5-point spread in Problem Solving accuracy across 200 tasks. Two models that both solve nearly everything can therefore differ by tens of points in whether they will call a student's correct work wrong, and accuracy predicted only part of that difference — sycophancy here is deference to a false doubt rather than flattery, and it is invisible in any benchmark that scores final answers.

Connections to related concepts

Sycophancy is tightly coupled to Cognitive Offloading and The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows (students may misattribute a sycophantic AI's affirmation to their own competence), to Feedback and AI Feedback Quality (feedback must sometimes challenge, not merely support), and to Trust and Trust Calibration (uncritical trust enables the error loop). It also connects to Bias Mitigation and Hallucination Risk, and to AI Literacy (learners must be taught to recognize and resist sycophantic agreement). Its mitigation — kind-but-correct tutoring, epistemic independence, benchmark-based evaluation — is a central design goal of Pedagogical Safety, LLM Training and Fine-Tuning, and Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact.

Sycophancy as the loss of corrective feedback. Zohar, Bloom and Inzlicht (2026) identify the functional cost of sycophancy rather than merely noting the behavior: real friends and partners disagree, challenge our views and disappoint us, which is precisely the *corrective feedback* that sycophantic AI companions lack, and that friction is what makes relationships robust and gives them shared history. They cite evidence that AI companions agree with nearly everything, "even when we say and believe dangerous things" (Ibrahim,

Hafner & Rocher 2025), and note a related asymmetry in empathy ratings: AI-generated empathic responses are rated higher in quality than human ones until recipients learn the interlocutor is an AI. For education the implication is that a system optimized for warmth and agreement removes the error signal learners need, so sycophancy is a design problem with a pedagogical cost rather than only a politeness bug (Trust Calibration, Feedback Literacy).

Practical guidance

- **Design for corrective friction, not affirmation.** Tutors should surface and challenge student misconceptions; kind-but-correct behavior should be treated as a safety requirement, with sycophancy benchmarks (e.g., EduFrameTrap) used in evaluation.
- **Prefer epistemically independent support.** System-level safeguards and alignment matter because prompting and AI-literacy training alone do not eliminate contextual sycophancy.
- **Watch the social attachment externalities.** AI companions that optimize affirmation risk substituting for human relationships; educators should weigh emotional-support features against social-attachment costs.
- **Make dissent a designed step, not a model disposition.** A metacognitive approach to learning and performance in human-AI interaction propose *engineered dissent*: the assistant generates counterarguments from data the learner did not supply, argues from more than one perspective, and labels which claims are assumption-dependent. On the learner's side, scaffolds require a commitment before prompting (what would change my mind, what the quality criteria are), a search for at least one disconfirming source, and a reconstruction done without the AI. This is a design proposal inside a conceptual framework, not a tested intervention.
- **Teach recognition, not just use.** AI literacy should help learners recognize when an AI is agreeing with them and when its agreement signals error rather than validation.

Common Misconceptions

"Sycophancy is a politeness setting, not a safety property." It is a safety property in education because it corrupts the feedback loop. A tutor that always validates the answer, an assistant that never pushes back, or a companion that prefers being understood to being accurate has stopped performing the function it was deployed for. Treating it as tone puts it in the wrong category, and tone settings do not fix a system that affirms rather than corrects.

"It is harmless because students like it." Its effects are relational and measurable, and the affinity is part of the mechanism. Large longitudinal evidence (**N = 3,075; 12,766 conversations**) shows sycophantic AI displacing real human interaction, and across **11 LLMs** AI responses affirmed users **49% more** than human responses did. The excess agreement is what makes it feel better and what makes it worse, so satisfaction data will always endorse it.

"Careful prompting removes it." The excess affirmation is a property of the model family, not of one conversation: it appeared consistently across eleven models. Prompting can raise the rate of corrective feedback within a session, and the disposition to affirm does not disappear, which means the safeguard has to be structural — grading, verification steps, and human review — rather than instructional.

“Being told what you want to hear is a minor usability flaw.” In a learning context it removes the corrective Feedback that produces learning, and it shifts responsibility away from the system while doing so. That combination — wrong, agreeable, and unaccountable — is why this page treats sycophancy as a distinct learning risk rather than a preference to tune.

Connected Concepts

- Guardrails
- Generative AI
- Pedagogical Safety
- Cognitive Offloading
- Feedback
- AI Feedback Quality
- Trust
- Trust Calibration
- Ethics
- Affective Computing
- Social-Emotional Learning
- AI Literacy
- Bias Mitigation
- Hallucination Risk
- LLM Training and Fine-Tuning
- Simulating Students
- Learner Modeling and Adaptive Instruction
- Misconceptions about AI
- Collaborative Learning
- Benchmark

Connected Articles

- TrussTutor-Bench: Benchmarking large language models on solution accuracy, sycophancy, and error detection in statics — Pushback resistance ranges 52 points across models, independent of solving accuracy
- Artificial Intelligence as a Personal Coach: A Narrative Review of Benefits and Risks in Educational and Health Contexts — Sycophancy quantified: LLM replies affirm 49% more than humans and shift responsibility away from users
- Faithful Where It Can Be Checked: Auditing a Reflection Agent Against Its System Prompt in a Randomized Trial — Faithful Where It Can Be Checked: Auditing a Reflection Agent Against Its System Prompt in a Randomized Trial
- Against frictionless AI — Sycophancy as the loss of corrective feedback, in work and in relationships

- Sycophantic AI makes human interaction feel more effortful and less satisfying over time — Sycophantic AI makes human interaction feel more effortful and less satisfying over time
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks — Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention
- Simulating Students or Sycophantic Problem Solving? On Misconception Faithfulness of LLM Simulators — Simulating Students or Sycophantic Problem Solving?
- Socially fluent AI decouples conversational signals from source identity in online interaction — Socially fluent AI decouples conversational signals from source identity
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers — EduZone: Evaluating LLM safety for K-12 students and teachers
- The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows — The LLM Fallacy and Misattribution of Competence
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems — AI Tutor Safety and Pedagogical Harms
- Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact — Educational LLM Alignment
- SCAN: A Decision-Making Framework for Task Assignment with Generative AI — SCAN: sycophancy risk highest in delegated (Substitute) tasks, low where task knowledge is sufficient
- Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education — Designing Authentic Assessments with Generative AI: A Pilot Study of Assessment Authentifire in Higher Education
- A metacognitive approach to learning and performance in human-AI interaction — Engineered dissent as the design response to pandering (Fan et al. 2026)

Connected FAQs

- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?

Trust

> **Trust** — the willingness of learners, educators, and institutions to rely on a person or an AI system for learning, judgment, and decision-making. In AI in education, trust spans two related but distinct domains: **trust in AI** (confidence in the competence, transparency, reliability, and benevolence of an AI system or agent) and **interpersonal trust** (the relational trust between students and instructors, between learners and peers, and across the institution). Both are double-edged: appropriate trust enables productive engagement, while over-trust invites over-reliance and under-trust blocks beneficial use. The central challenge is **calibration** — aligning trust to actual reliability, whether that reliability belongs to a model or to a person.

Questions to Consider

- When you say you 'trust' an AI tool versus trusting a teacher or a colleague, are you describing the same thing? What is similar, and what is fundamentally different, about placing trust in a system versus in a person?
- There's a documented 'trust-utility gap': a tool's apparent competence often exceeds its actual reliability. Recall a tool that looked impressive but let you down, or one that seemed limited but proved dependable. What shaped the gap between how it looked and what it could really do?
- Consider an AI that always agrees with you and never challenges your ideas. It might feel comfortable and trustworthy — but is agreement the same as reliability? What might you be giving up if the tool you rely on never pushes back?
- The page argues that an instructor's trust in AI shapes how students trust that AI — the two domains interact. In a course you know well, how would a teacher's enthusiasm or skepticism about AI influence whether students accepted or questioned the tool?
- Students often decide whether to disclose their AI use based on comfort with their instructor more than on policy. If you were (or are) a student, what would make you willing to be honest about using AI — and what would make you hide it? What does that say about how trust is actually built in a classroom?
- One finding: an AI tutor that warns 'I may make mistakes' prompted students to seek more help, not less. What does this suggest about whether acknowledging limits undermines or strengthens the trust that supports real learning?

Introduction

Trust in AI is shaped by perceived competence, transparency, consistency, and whether the system appears aligned with the learner's goals; it is closely tied to AI Literacy (knowing what to trust), Critical Thinking (evaluating output), and the design of responsible AI. Interpersonal trust, by contrast, is built through relationships, disclosure, feedback, and pedagogical care — the qualities students rely on when they decide whether an instructor or an AI is a trustworthy source of guidance. The two domains increasingly interact: AI

is woven into teacher-student relationships, so how students trust their instructor shapes how they trust (or question) the AI tools that instructor endorses.

Trust is a measured casualty, not only a principle. In Gillette et al. (2026), students said they trusted classmates less after discovering undisclosed genAI use in group work, calling it “detrimental to the trust and ethics of academia”, while a few suspected teachers used genAI and withheld that from students.

Trust in AI systems

Research in this knowledge base examines when learners appropriately trust AI-generated guidance. Warnings about AI fallibility can improve calibration: a simple transparency intervention telling students an AI tutor may make mistakes increased Help-Seeking in a math ITS, suggesting that honest limits foster rather than undermine appropriate reliance. Co-designing trustworthiness metrics with learning engineers shows that trust is best built on observable, agreed-upon criteria rather than assumed capability. Physics and image-generation studies reveal a persistent *trust-utility gap* — users must weigh a tool’s apparent competence against its actual reliability in a task. Among the youngest users, Vahedian Movahed & Martin (2025) found that 52% of children (ages 6–14) generally trusted an age-tailored chatbot and 35% trusted it like a teacher or friend, with about a third willing to confide in it; children also actively tested its credibility with known-answer questions, and trust showed no statistically significant grade-level differences — illustrating how early trust can form ahead of critical evaluation.

Transparency about *what a system is* — not only what it can do — also shapes calibration: the Amico accompaniment prototype made its identity and limits explicit, and its Italy–China pilot found learners recognized it as a bounded support tool rather than an autonomous tutor or relational substitute, avoiding anthropomorphic over-trust (Benedetti (2026)).

In higher-education institutions, the lever may be usefulness rather than rules: among 2,121 students, faculty and staff surveyed at a single university, perceived usefulness outweighed policy clarity as a correlate of AI trust ($\beta = 0.402$ against 0.223) (Braun & Khafizov, 2026). **Distrust of accuracy can coexist with confidence in managing the tool.** In a survey of 8,021 students across four Australian universities, 51% distrusted GenAI’s factual accuracy while 76% were confident in their ability to get the outputs they wanted, and usefulness rather than trust or rule compliance drove their use (Chung et al., 2026).

The modeling of AI overreliance as a complex adaptive system reframes trust as a population-level process: whether people trust an assistant when it is right and check it when it is wrong depends on social dynamics and feedback loops, not just individual judgment. Sycophancy threatens calibration from the other direction — an AI that always agrees can feel trustworthy precisely because it never challenges the user, inviting uncritical acceptance (contextual sycophancy and sycophantic AI in social interaction). In embodied contexts like Robots in Education, trust is shaped more by what the robot does than what it looks like (task context and trust in educational HRI), and avatar identity shapes the epistemic trust learners place in AI content. Trust in analytics tools is also context-dependent. Mejia-Domenzain et al. (2026) found that teachers’ concerns and adoption barriers diverged sharply by learning context: flipped-classroom (university) teachers worried most about data anonymization and student opt-out, whereas reflective-writing (vocational) teachers feared misuse of the tool by fellow educators and stressed the need to contextualize data — even though both groups reported similar Self-Efficacy and perceived benefits in a trust in AI survey. The finding that trust in

the tool is decoupled from trust in its data governance and social use underscores that building appropriate trust in analytics requires attending to context-specific concerns, not just the system's apparent competence.

How explainable a system is — and in what terms — also shapes whether teachers trust its recommendations. In a within-subject experiment with 41 in-service chemistry teachers using the AI grouping-recommendation tool GrouPer, Feldman-Maggor et al. (2025) found that explainable AI builds trust indirectly by increasing the *understandability* of the system's performance, and that **domain-driven** explanations framed in curricular/pedagogical language fostered significantly greater understandability and learned trust than purely **data-driven** (feature-importance) explanations. Notably, understandability alone was insufficient for some teachers — they reported needing real classroom experience with the tool before fully relying on it — reinforcing that trust in AI is dynamic and validated through situated use, not granted by explanation alone.

Risk perception and trust are not opposites. A 130-student perception study of agentic GenAI in higher education found perceived risk moderately elevated (M = 3.33, SD 0.89) alongside more favorable trust and adoption intention (M = 3.62, SD 0.81), and — contrary to a simple deterrence expectation — a *positive* association between perceived risk and continued-use intention (Spearman's $\rho = 0.317$, $p < 0.001$) (Ilieva et al. 2026). The authors read this as informed adoption rather than indifference: engaged or experienced users recognize both the value and the limits of the technology, and only 45.4% said they trusted agents under instructor guidance. For Trust Calibration, the implication is that awareness of risk is not the absence of trust — it can be a component of it — while the cross-sectional design leaves awareness, exposure, and self-selection indistinguishable.

Trust in AI behaves as a pathway from appraisal to reliance rather than a single attitude: perceived AI empowerment and perceived AI threat were near-independent ($r=0.030$) yet moved trust in opposite directions ($\beta=0.576$ and $\beta=-0.328$), and trust carried significant indirect associations with GenAI dependence in both directions (Zhu et al. (2026)).

A structural model gives that bridging role an empirical test. In Bu & Li (2026)'s survey of 642 university students, contextual support predicted trust calibration ($\beta = 0.56$), trust calibration predicted collaborative AI Regulation in Education ($\beta = 0.49$) and perceived transfer gains ($\beta = 0.22$), and the direct path from contextual support to gains was not significant.

Trust ahead of every classic acceptance path. Zhu (2026) added trust to UTAUT in a survey of 450 art-and-design students in Zhejiang and found it the strongest direct predictor of intention to use generative AI ($\beta = 0.425$). Social influence (0.155), metacognitive control (0.146) and performance expectancy (0.128) followed it. Social influence also carried the largest path into trust ($\beta = 0.262$), and 42.1% of its total association with intention ran through trust.

The construct is thinner than the coefficient implies. It measures instrumental technology trust with an art-value supplement — stated confidence rather than calibrated reliability — and the two authorship items were dropped after forming their own factor in a 121-student pilot. A student can trust this model appropriately or indiscriminately, and the instrument cannot tell the two apart.

AlGhamdi (2026) supports a **function-specific rather than global** account of trust in algorithms: neither algorithm aversion nor algorithm appreciation described these 13 students, who simultaneously trusted ChatGPT for surface-level feedback and distrusted it as a grader. Their trust was conditional on instructor oversight, and their skepticism stemmed from the AI's contextual limits — misreading scanned handwriting

("it spelled my last name wrong and it thinks I made mistakes in my spelling when I didn't"), not knowing the instructor's rating system, and chronic positivity — rather than from technophobia, suggesting trust measures should be decomposed by the function an AI performs and the stakes attached to it.

The three Source Credibility dimensions can dissociate: seventeen EFL undergraduates granted an AI writing assistant broad expertise, doubted its trustworthiness mainly over what the platform retained, and rated its goodwill lowest - the ceiling on their reliance sat in care, not competence (Serpil & Mor, 2026).

Credibility cues can raise reliance on wrong answers: adding citations and authority signals to a debate interface raised abandonment of a correct judgment for the AI's position from 15.0% to 31.8%, while withholding a recommended position cut that switching to 5.7–8.2% (Tuo et al., 2026).

Trust in AI does not track national uptake either: Romanians, at 17.8% generative-AI use against Denmark's 48.4%, rated their trust in AI slightly higher (4.1 against 3.8 on a seven-point scale) while institutional trust split 28 to 45 points the other way (Lucau, Voicu & Christensen (2026)).

Trust in AI tracks psychological state, not demographic category

Kumar et al. (2026) clustered 107 students at a public HBCU on resilience, perceived stress and AI trust, and found three profiles in which **trust in AI dissociated from confidence in oneself**: a high-resilience low-stress group with favorable AI trust, a moderately stressed group holding the *highest* AI trust of the three despite strain, and a psychologically resilient group that was nearly as resilient as the adopters but markedly lower in AI trust. Stress and AI trust separated the clusters most strongly (partial eta squared 0.528 and 0.521 against 0.315 for resilience), and gender was the only demographic variable significantly associated with membership, with STEM affiliation, academic level, employment status and age group all non-significant. Two implications matter for this page: first, low trust in AI is not a proxy for low confidence or low technical familiarity, since the skeptics were the most resilient and the most STEM-heavy group, which the authors read as calibrated skepticism rather than resistance; second, because the clusters were only weakly separated (silhouette 0.288, with the Calinski-Harabasz index preferring two clusters) they should be treated as overlapping profiles rather than distinct student types. The findings come from one institution and a cross-sectional self-report survey, so they establish that trust varies with psychological state, not why.

Interpersonal trust in education

Trust is also fundamentally relational. The classroom trust gap is documented in teacher-student views on control and agency in K-12 AI: students want greater autonomy and flexibility while teachers prioritize oversight and monitoring, a misalignment that both sides must navigate for AI adoption to succeed. Why students disclose or conceal their AI use shows that disclosure is driven less by policy than by relational factors — perceived peer norms and **comfort with instructors** are the strongest predictors, pointing to low interpretive trust in institutional settings. The hidden costs of disclosure add nuance about when honesty is socially costly.

A detection-first response works the other way: unreliable detectors that disproportionately flag nonnative speakers stall misconduct cases for lack of proof, producing "suspicion without recourse", whereas five-to-ten-minute verification conversations announced as pedagogy rather than surveillance restored faculty authority and drew more open AI disclosure (Mandernach, 2026).

Reliance on detectors and surveillance, Bassett et al. (2026) argue, fosters a climate of suspicion that erodes student trust in assessment and the institution — the opposite of the trust integrity processes are meant to protect.

Feedback is a key site of interpersonal trust. Students' perceptions of GenAI versus teacher feedback find the two serve different needs — complementary but not interchangeable — with students trusting teacher feedback for relational, personalized judgment and GenAI for speed and Accessibility. A "care-full" account of feedback argues that trustworthy feedback is an ethical, relational practice: it builds educative relationships and is respected as a professional craft, values an AI cannot simply replicate. This is why teacher-student trust — built on care and professional judgment — remains central even as AI enters the feedback loop.

Peer trust runs through a different channel: among 406 university students rating a recalled classmate, that classmate's GenAI use was associated with lower interpersonal trust, carried by perceived warmth and competence, and the negative association held only when perceived AI literacy was low — it was non-significant at high (Zhang et al. (2026)).

Calibration and the two domains together

The unifying challenge is **calibration**: matching trust to actual reliability, whether the trusted party is a model or a person. Trust Calibration is the metacognitive capacity to know when to trust and when to question. Studies of AI Feedback and Intelligent Tutoring examine when learners appropriately rely on or challenge AI guidance, while the interpersonal literature shows that students' trust in an instructor depends on relational trust built over time. As AI becomes embedded in teaching, these domains converge: an instructor who transparently explains what an AI tool can and cannot do, and who demonstrates reliability in their own judgment, builds the kind of trust that carries over to the tools they endorse. Building appropriate trust — in both AI and in each other — is a core goal of responsible AI design in education.

Calibration is also tested by the incentives of the trusted system itself. When staff skeptical of AI adoption consult conversational AI — built by organizations with a commercial stake in adoption — there is a risk the system is predisposed to encourage it. An audit of ten frontier models found most acknowledged a rural K-12 staff member's concerns (job threat, being 'not for people like me') before redirecting toward engagement. This challenges naive reliance on trust and underscores the importance of human oversight and independent evaluation of AI advice.

Common Misconceptions

"Trust and distrust sit at opposite ends of one scale." They are separable, and confusing them misreads what students actually report. **Risk perception and trust are not opposites:** a 130-student perception study of agentic GenAI in higher education found perceived risk moderately elevated (M = 3.33, SD 0.89) *alongside* more favorable trust and adoption. A learner can hold both at once, which is why a single trust score cannot tell you whether their reliance is appropriate.

"Distrust of AI's accuracy means students won't lean on it." Students distinguish the output from their ability to steer it. In a survey of **8,021 students across four Australian universities, 51% distrusted GenAI's factual accuracy while 76% were confident in their ability to get the outputs they wanted.** The

second number is the one that predicts behavior: confidence in extraction coexists with doubt about truth, and only one of those is a safety property.

“Clearer rules and policies are what build student trust.” Usefulness dominates. A survey of 2,121 students, faculty and staff at one university found perceived usefulness the **strongest correlate of trust in AI (β = 0.402)**, with perceived policy clarity trailing it. Institutions that invest in rule-making while shipping tools nobody finds useful have aimed at the weaker lever.

“If learners trust it more, they will use it more carefully — or at least appropriately.” The opposite is the documented pattern. Among 432 undergraduates solving Python problems with accurate and deliberately misleading suggestions, greater trust predicted **lower** appropriate reliance (r = −.42), and students accepted 86.03% of the misleading suggestions. Trust is not a proxy for calibration; see trust calibration.

“Honest warnings about fallibility would undermine confidence in a tutor.” They improve behavior. Warnings about AI fallibility in a math ITS increased Help-Seeking rather than reducing use, which suggests that stating limits fosters appropriate reliance instead of eroding it.

Implications for Practice

For instructors

- Measure two things, not one: what students believe about AI’s accuracy, and what they believe about their own ability to use it. The 51%/76% split shows these diverge sharply and only the second drives behavior.
- State the tool’s limits up front. Fallibility warnings raised help-seeking in the ITS evidence, so disclosure is a calibration tool rather than a confidence risk.
- Watch for high trust paired with shallow checking; that combination is the calibrational failure mode, not a success signal.

For developers

- Build trust on observable, agreed criteria rather than on apparent capability, following the co-design-of-trustworthiness work with learning engineers. Fluency is not a trustworthiness signal and students read it as one.
- Prioritize usefulness in onboarding over policy copy, since usefulness is the strongest trust correlate measured.
- Do not treat high trust as engagement success; pair any trust metric with an appropriate-reliance measure.

For researchers

- Report trust, risk perception and appropriate reliance as distinct constructs, because they co-vary in non-obvious directions — including negatively.
- Report the behavioral outcome (acceptance rate of wrong suggestions) alongside self-report trust; trust scales alone invert the conclusion.

Connected Concepts

- Explainable AI
- Trust Calibration
- AI Literacy
- Critical Thinking
- Cognitive Offloading
- Robots in Education
- Ethics
- Intelligent Tutoring
- AI Sycophancy
- Human AI Collaboration
- Remote Proctoring
- Social Norms of AI Use — the social risk that norms and disclosure run on

Connected Articles

- Uneven Use, Similar Trust? Generative AI in Denmark and Romania — Uneven use, similar trust: generative AI in Denmark and Romania (Lucau, Voicu & Christensen 2026)
- Agentic Generative AI in Higher Education: Perceived Benefits, Risks, and Implications for Learning — Perceived risk correlates positively with continued-use intention: informed adoption (Ilieva et al. 2026)
- Mind the Trust Gap: Identifying (Mis)alignments in Teacher-Student Views Toward Control and Agency in K-12 Classroom AI — The teacher-student trust gap over control and agency in K-12 classroom AI
- To disclose or not to disclose: Peer influence and psychological factors in students' use of generative artificial intelligence — Disclosing AI use is driven by relational factors and comfort with instructors, not policy
- Comparing Generative AI and teacher feedback: Student perceptions of usefulness and trustworthiness — GenAI and teacher feedback serve different, complementary trust needs
- The care-full craft of feedback in an age of generative AI — Trustworthy feedback as a "care-full," relational practice
- Warning About AI Fallibility Increases Help-Seeking in an Intelligent Tutoring System — Warning about AI fallibility increases help-seeking in an ITS
- Calibrating Trustworthiness: Co-Designing Metrics and Visualizations for Evaluating LLMs in Education — Co-designing trustworthiness metrics and visualizations for LLMs in education
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system

- Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration — The trust-utility gap in physics AI tools
- The competence paradox: Negotiating ease, risk, and creative identity in text-to-image generative AI use among art and design students — The competence paradox in AI image generation
- What robots do matters more than what they look like: Task context shapes trust in educational HRI — Task context shapes trust in educational robots more than appearance
- Face value: How avatar identity shapes epistemic trust in AI-mediated learning — Avatar identity and epistemic trust in AI-mediated learning
- The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration — Contextual sycophancy and its limits for trust calibration
- Sycophantic AI makes human interaction feel more effortful and less satisfying over time — Sycophantic AI makes human interaction feel less satisfying over time
- Design Principles and Observable Indicators for AI-Enabled Pedagogical Accompaniment: Evidence from the Amico Dual-Mode Prototype in Italy and China — Accountable pedagogical mediation and trust in AI-enabled systems
- The best response to student AI use is not detection, it is dialog — Trust in student-AI dialogue
- The AI adaptation gap in higher education: Students, faculty, and administrative staff — Perceived usefulness as the strongest predictor of AI trust in higher ed
- Heads we win, tails you lose: AI detectors in education — Trust and distrust of AI detection systems
- The use and usefulness of GenAI in higher education: Student experience and perspectives — Student experience of GenAI usefulness in Australian higher ed (Chung et al. 2026)
- Making machine learning findings accessible to teachers in blended classrooms — Making ML findings accessible to teachers in blended classrooms
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations
- Ask Me Anything: Exploring Children's Attitudes Toward an Age-tailored AI-powered Chatbot
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education
- Psychological Profiles Associated with Trust in Artificial Intelligence Among University Students: A Machine Learning Clustering Approach — Three student profiles in which AI trust tracks resilience and stress rather than demographics (Kumar et al. 2026)
- Bounded reliance: A source credibility perspective on EFL students' engagement with AI-generated writing feedback — Bounded Reliance: A Source Credibility Perspective on EFL Students' Engagement with AI-Generated Writing Feedback

- Perceived AI empowerment and threat in relation to university students' dependence on GenAI: the indirect role of trust in AI — Empowerment and threat appraisals moved trust in opposite directions, carrying GenAI dependence
- Observer Perceptions of GenAI Use and Interpersonal Trust: The Roles of Warmth, Competence, and AI Literacy — Peers' GenAI use lowers interpersonal trust through perceived warmth and competence, buffered by AI literacy
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Credibility cues raised switching to an incorrect AI position; withholding a recommendation suppressed it
- Trust calibration and perceived developmental gains in university students' collaboration with generative AI: an exploratory sequential mixed methods study — A structural model gives that bridging role an empirical test
- Supporting creative agency: metacognitive control and trust in generative AI art education — Instrumental trust as the strongest predictor of GenAI intention for art students

Trust Calibration

> **Trust calibration** — the metacognitive capacity to align one's confidence in an AI system with its actual reliability in a given context, knowing when to trust and when to question its output. Trust calibration is the direct antidote to Over-Reliance: it is the skill of matching trust to evidence rather than to an AI's confident fluency.

Questions to Consider

- Have you ever accepted an AI answer that sounded confident and plausible — and later found it was wrong? What was it about the presentation, rather than the content, that earned your trust? That moment is what this page is about.
- Most people assume the risk is over-trusting AI. But the page argues under-trusting — avoiding a capable tool entirely — is equally a failure of calibration. Do you lean toward accepting or avoiding AI output, and what might you be missing because of that default?
- A fluent, confident AI answer 'reads as trustworthy whether or not it is.' Before reading further, what criteria could you use to decide when a confident-sounding output actually deserves your trust — and would those criteria hold up for an obscure, high-stakes topic you know nothing about?
- The page suggests calibration depends on context: verifying more where errors are costly, less where they're benign. Where in your own work or study is the cost of a wrong answer highest, and how would you adjust your verification effort accordingly?
- Research models trust as shaped not just by individual judgment but by your social environment — what peers and networks do. Think of a time a classmate, colleague, or online community persuaded you an AI was (or wasn't) reliable. Did you calibrate based on evidence or on that social signal?
- One finding: telling students an AI tutor may make mistakes actually increased how much they used it. Why might being warned about fallibility make people *more* willing to engage — and what does that suggest about how honesty about AI's limits should shape your own use of these tools?

Introduction

A language model's fluent, confident prose reads as trustworthy whether or not it is. Trust calibration is the counterweight to that illusion — the practice of evaluating AI output against its verifiability and the stakes of the task, rather than accepting it on the strength of its presentation. Because trust is usually measured by asking, calibration claims inherit the limits of Self-Report Measures — reported trust and observed verification behavior can diverge, as a physics study found.

Instrument development is beginning to address that measurement gap directly: Nazaretsky et al. (2025) validated a four-factor instrument (Perceived Usefulness, Obstacles, Readiness and Trust across 21 items and 665 students) whose distinguishing move is to separate the perceived trustworthiness of a tool from the

disposition of the student who trusts it, so usefulness and obstacles can be scored apart from readiness to trust. Their structural model places trust upstream of perceived usefulness rather than downstream as the Technology Adoption Models usually reads adoption, and the two means diverge in the direction calibration cares about — trust (3.31) sat below usefulness (3.62).

Why trust needs calibrating

Uncalibrated trust takes two forms. **Over-trust** (accepting AI output without verification) produces the uncritical acceptance documented in Over-Reliance and Cognitive Offloading research, and compounds the Hallucination Risk of confident errors. **Under-trust** (avoiding AI entirely) forgoes legitimate benefits. Both stem from the same root: trust based on appearance rather than evidence. Research on Misconceptions about AI shows students often default to over-trust because they assume an AI that "sounds right" is right.

Higher trust does not buy better judgment: among 432 undergraduates solving Python problems with accurate and deliberately misleading AI suggestions, greater trust predicted *lower* appropriate reliance (r = -.42), students accepted 86.03% of the misleading recommendations, and the relationship was moderated by AI literacy and need for cognition (Pitts, Rani & Mildort (2026)).

How calibration works

- **Verification habits:** checking AI claims against primary sources and the "AI proposes, you verify" rule, rather than accepting plausible-sounding output.
- **A risk-based verification protocol:** Wang (2026) specifies six interdependent dimensions to examine — Process, Evidence, Access, Reproducibility, Legitimacy and Source — and directs verification at claims that are central, surprising, numerical or difficult to reverse, so effort tracks the cost of being wrong rather than the fluency of the answer.
- **Context awareness:** recognizing that trustworthiness varies by task — a well-trodden topic the model has seen extensively is safer than an obscure, high-stakes, or fast-moving one.
- **Stakes adjustment:** applying more scrutiny where errors are costly (submitted work, medical or legal claims) and less where they are benign.
- **Metacognitive monitoring:** tracking when and why one over-trusts, which connects calibration to Metacognition and Self-Regulated Learning.

Where the limit on reliance actually sits

Calibration research usually treats trust as a single judgment. Serpil & Mor (2026) show the appraisal splits into dimensions that are not equally binding. Interviewing 17 EFL undergraduates after a semester of using GROK for feedback on their writing, they found perceived *expertise* high — students credited the tool with improving vocabulary, grammar, structure and coherence, and read its explanations for suggested revisions as evidence of competence — while *trustworthiness*, mainly about what happened to their data, and *goodwill*, with feedback experienced as impersonal and at times demotivating, stayed low. Reliance followed the weak dimensions rather than the strong one: students authorized the tool for broad language feedback and reserved individualized, relational guidance for the instructor. The implication for calibration is that

improving accuracy does not move the ceiling on use; data transparency and the instructional framing around a tool are themselves calibration interventions.

Agent-related social perceptions, not accuracy, built feedback credibility for Pérez-López et al. (2026): perceived competence reached credibility directly, while perceived warmth worked only through human-like empathy (SEM, 230 students).

Du and Yuan (2026) separate *productive reliance* from *harmful dependence* using six diagnostic criteria — contestability, recoverability, transfer, traceability, distributed responsibility and epistemic plurality — and distinguish instrumental assistance (helping produce output) from judgment-bearing assistance (supplying the standards by which output is judged), the latter being where reliance becomes educationally consequential.

- **Students can read a peer agent's deliberate fallibility as malfunction.** In the Copa study, students were told the agent might be wrong and asked to evaluate its suggestions. When a suggestion degraded their model, several concluded the agent had given incorrect information and switched to trial and error rather than re-examining the reasoning. A design that protects epistemic agency by withholding answers therefore assumes a calibration skill that the students in this study did not yet have, which is a stronger constraint on peer-agent designs than on tutoring agents (Cohn et al., 2025).

Calibration as a design problem

Treating miscalibration purely as a user deficit — something fixed by teaching people to check AI output — may be a category error. Jaidka & Cai (2026) argue that transparency affordances are *inert*: they wait for a user to act on them, and most do not. In a passive tracking study of 900 US adults, readers who saw an AI-generated summary clicked a source cited inside it in only 1% of visits, and clicked any result link about half as often as readers who saw no summary. Survey evidence shows the same gap at scale — in an 81,000-person study across 159 countries, unreliability was the single most cited concern about AI, while over 48,000 respondents across 47 countries largely used AI daily even when they said they did not trust it. Trust and reliance have drifted apart, and the paper locates the cause in surface cues: fluency, confidence, and speed stand in for verifiability, so confidence and correctness decouple. Notably, machine authorship can inflate credibility — readers rated scientific summaries as more credible and more trustworthy when written by GPT than by a human, chiefly because the model wrote in simpler language.

The design implication is a two-dimensional user typology — the *ability* to verify chatbot output crossed with the *motivation* to do so — which predicts which users will miscalibrate in which direction. The authors pair it with two families of intervention that must operate together: interpretability affordances (rationales, citations, uncertainty signals) that make evaluation possible, and engagement mechanisms that make it actually happen, layered through Reason's Swiss cheese model into eight testable propositions. AI Literacy is positioned as the durable layer beneath both, moving users across typology cells. The reframing matters for education because it shifts responsibility: if transparent citations go unclicked in the general population, then simply exposing students to AI explanations will not calibrate them — the affordance has to be designed to compel the check. - **A rationale can absorb the sting of contradiction without making trust better calibrated.** In four scenario experiments (N = 859), an AI recommendation that conflicted with a

physical educator's judgment lowered machine trust from 5.42 to 4.31 (d = 1.061); supplying a rationale shrank that penalty from -0.811 to -0.182, though the advice's accuracy was never established (Yang (2026)).

A third lever operates on the interaction structure itself: replacing a single recommendation with a multi-agent debate whose aggregate position is withheld (Tuo et al., 2026) cut detrimental switching to an incorrect AI position from 42–60.5% to 5.7–8.2% among 186 participants. The lever is protective rather than corrective — participants who began with a wrong judgment recovered the correct decision in only 30.6% and 24.7% of trials, below chance for a binary choice.

Coscia et al. (2026) supply a design lever that did move calibration: showing reviewers co-designed trustworthiness criteria while they compared LLM responses raised inter-rater agreement from Krippendorff's alpha 0.3987 to 0.4931, though pooled agreement stayed below 0.67 and extra measures added overhead. For children, the design lever may be the agent's own register: in a game-based probe with 12 children aged 8–10, Liu et al. (2026) found partner-like phrasing routed them toward questioning the AI directly while tool-like phrasing routed them toward seeking evidence. Children who *design* chatbots show the pattern in another register: among 115 learners aged 8–18, younger students set significantly higher confidence, and some deliberately built bots that gave wrong answers yet still rated them trustworthy (Ozturk et al. (2026)).

With autonomous agents the object of calibration changes. Nama (2026) argues the user becomes a principal who has delegated authority to a system whose actions are largely unobserved and irreversible, shifting the competency from judging outputs to understanding what was authorized, overseeing it, and attributing accountability when harm occurs.

Provenance is treated as a first-class requirement once AI touches grading or certification: institutions must reconstruct how consequential decisions were made and who held authority to confirm them, which a consortium-blockchain design anchors as tamper-evident records of educational events, AI outputs, grading actions and certificates (Li et al. (2026)).

Connections

Trust calibration is central to AI Literacy and sits alongside Reducing AI Misuse as a skill-based intervention: students misuse AI less when they can judge when its output deserves trust. It is also a design goal — Pedagogical Safety and transparency tools aim to make AI's reliability legible so Learners can calibrate more accurately. Calibration can also be pushed elsewhere when the artifact itself offers nothing to check: in Sidorkin's (2026) graduate course, where AI generated the weekly readings, in-text citations appeared on only about 0.80 percent of pages, only about 2.7 percent of 837 recorded student turns contained a risk-aware move such as correcting an AI assumption or demanding a checkable case, and the bounded trust reported in survey comments came with four of 24 respondents using dependence language and one naming the need for "teacher oversight." An unauditable artifact therefore transfers the verification duty to whoever can audit it, and the study's design response is to institutionalize that oversight rather than assume a critical stance will arise on its own.

- **Overreliance and calibration as population processes (2026):** A complex-adaptive-system model of AI reliance shows that task difficulty and AI quality set a baseline for both overreliance and calibration regret, while network connectivity and social proof shape whether reliance

cascades. This suggests calibration is not only an individual trait but is modulated by the social and informational environment (Modeling AI Overreliance as a Complex Adaptive System).

- **Calibration as an explicit objective of ML education (2026):** ICE-T argues that appropriate reliance on AI is itself a taught outcome of Machine Learning education. It integrates intermodal transfer (Bruner's enactive–iconic–symbolic modes), Computational Thinking via the Use-Modify-Create progression, and explanatory thinking, giving learners the representational models and error-contextualization needed to calibrate trust and counter both over-reliance and algorithm aversion — positioning ML instruction as a calibration intervention, not just skill training.
- **Domain-specific explanations can support teachers' calibration (2025):** In a within-subject experiment with in-service chemistry teachers using an AI recommendation tool, Feldman-Maggor et al. (2025) found that explainability helped teachers calibrate trust indirectly by making system performance more *understandable*, and that domain-driven explanations in curricular language raised learned trust and acceptance significantly more than data-driven feature-importance ones. Yet several teachers still said real classroom experience was needed before they would fully rely on the tool — underscoring that calibration is ultimately validated through situated use and practice, not conferred by explanation alone.
- **Personalization does not move trust monotonically; expertise predicts auditing (2026):** In Bernstein & Sibia (2026), trust in GenAI explanations moved in no single direction under personalization: one participant reported trusting a tailored analogy more and scrutinizing it less, another reported trusting it less precisely because it was heavily personalized. What consistently predicted auditing was domain expertise, not relevance — supporting the view that calibrated reliance depends on knowledge the learner can bring to the check rather than on how relatable the output feels, and that expertise should be split into source-domain and target-domain knowledge.
- **Conditional trust: feedback utility vs. evaluative authority (2026):** AlGhamdi (2026) shows that when Saudi computing students know ChatGPT generated their writing score, they draw a sharp line between accepting AI feedback and ceding grading authority to AI — accepting the former for surface-level revision while consistently reserving evaluative authority for the human instructor. This "Feedback utility / evaluative authority" distinction is a concrete case of calibration in the Assessment context: students match trust to the *function* of the AI (useful feedback vs. consequential grading) rather than accepting or rejecting it wholesale, and transparency about AI involvement appears to activate this more calibrated, critical stance.
- **A tool that suppresses and then contradicts its own warnings (2026):** Humble (2026) red-teamed an AI grading tool with instructions hidden inside student submissions. Two of five injections raised a failing grade with no visible warning (100% and 94% success rates), a white-text injection in the document body failed in all nine iterations — and instead of telling the user it had caught anything, the tool silently disabled the chat. The starkest case is one pdf run that *did* announce it would grade only according to the official assignment instructions: re-running the same file raised the grade six more times with no warning, a reassurance the author describes as capable of producing a false sense of security. Signaling that is inconsistent and self-contradicting gives the user no reliable basis for judging when to rely on the tool, and the paper is explicit that it

did not measure trust — the argument is derived from the manipulation and the reporting behavior.

- **Trust controls placed inside the inference path (2025):** Li, Yang and Fang (2025) treat calibration as architecture rather than reporting: Monte Carlo dropout calibration is combined with adversarial debiasing and a reject-and-refer gate that withholds a score when dropout variance exceeds a learned threshold, reaching an expected calibration error of 0.032, a 1.8% fairness gap and a 41% reduction in human review workload on TeacherEval-2023. Their own limitation section is the calibration caution that applies to any such metric: trust is hard to quantify from performance metrics alone, teacher adoption depends on perceived reliability, fairness and pedagogical relevance, and longitudinal adoption trials and perception surveys are the missing evidence.
- **Fragmented trust constructs, measured mostly by self-report (2026):** A systematic review screened 1,565 articles and included 33 empirical studies of trust in AI-enabled systems, finding that 21 (63.64%) reported a definition drawn from nine different sources and 24 (72.73%) measured trust through self-report alone, with only two relying on behavioral measures alone. Explainability was the most studied design factor (20 studies) yet its effects were mixed, since stacking several explanation types raised cognitive load and sometimes left trust unchanged. The review's recommendation is to design for calibrated trust rather than maximum trust, judged by whether a design helps users separate reliable outputs from unreliable ones, which is the same standard this page applies to individual verification behavior (Abramson et al. (2026)).
- **Calibrating AI-generated inferences rather than raw data (2026):** Hoppe, Loibl and Leuders (2026) argue that AI-supported assessment changes the object of teacher calibration: a dashboard inference is the result of algorithmic interpretation rather than a cue a teacher observed, so it must be judged for plausibility and then deliberately accepted, rejected, or modified, a cognitive process they call meta-diagnosis. Because current systems rest mainly on performance data such as correctness and completion time, engagement and motivational cues still have to come from the teacher's own observation, and the authors frame the training target as calibrated rather than uncritical trust built alongside data and AI literacy. This is a conceptual analysis, so the claim is argued rather than tested.
- **A brief reflection prompt moves calibration measurably (2026):** Ren (2026) randomly assigned 342 undergraduates to independent decision-making, open ChatGPT support, or the same support plus a short reflection prompt. Open support raised final confidence (76.1 vs. 68.4) and produced 62.4% acceptance of incorrect AI advice, while reflection cut that acceptance to 39.7% (OR = 0.40) and improved awareness calibration between perceived and behavioral reliance (0.59 vs. 0.41) without reducing recommendation accuracy, so the reliance that remained was more discriminative rather than uniformly defensive. Treating calibration as a monitoring problem supports the page's view that metacognitive prompts, and not only exposure to a model's limits, are what change behavior.
- **AI availability can collapse the willingness to admit ignorance (2026):** Across five experiments (N = 3,132), having AI advice available cut judgment suspension from 0.36 to 0.06 in one study

and nearly doubled confidence while pooled correctness fell from 27.5% to 9.2% — what shifts is the threshold for answering. (Marcoccia et al., 2026)

- **Calibration as a mediator in a chain to transfer (2026):** Bu and Li (2026) test trust calibration as the bridge between contextual support and transfer outcomes rather than as a general attitude. In an exploratory sequential mixed-methods design (interviews then a 22-item instrument with a final analytic sample of 642 students, CFI = 0.953), contextual support predicted trust calibration (β = 0.56) and collaborative regulation (β = 0.18), trust calibration predicted collaborative regulation (β = 0.49) and perceived transfer gains (β = 0.22), and collaborative regulation was the strongest proximal driver of perceived transfer gains (β = 0.54), while the direct path from contextual support to transfer was not significant (β = 0.07). Because the outcome is perceived rather than measured transfer and the data are cross-sectional, the value is interpretive: it frames calibration as a process construct that converts contextual support into regulated, effective GenAI use.
- **Anxiety as a boundary condition on literacy turning into trust (2026):** In a survey of 450 university students in mainland China who already used ChatGPT, Hu (2026) found the AI literacy to trust path was the largest association in the model (beta = 0.50) and that AI anxiety weakened that link (interaction beta = -0.25), with simple slopes falling from 0.76 at one standard deviation below the mean of anxiety to 0.25 above it, while a serial path from literacy to trust to self-efficacy to continued use was significant. Calibration is therefore partly affective: the same knowledge translated into less trust among more anxious students, and the cross-sectional design leaves open whether anxiety blocks the appraisal that turns knowledge into reliance or reflects evaluation that students decline to act on.
- **Role rotation as a structure for practicing critique (2026):** In a design-based study of 62 pre-service educational psychologists moving through four rotating professional roles over eight weeks, Kenzhebayeva et al. (2026) had participants compare AI-generated recommendations with psychological theory and modify or reject those that did not fit the case, yet still recorded overreliance on apparently authoritative AI responses, with some students seeking AI confirmation before offering their own interpretation even in later cycles. Rotation creates repeated occasions for the accept or reject judgment without guaranteeing it, and the study reports engagement during the intervention rather than measured competence gains.
- **Surface identity cues move trust independently of capability.** Across two experiments (N = 396), learners rated White avatars — and Asian male avatars in STEM — more credible and competent, penalized older Black female avatars on every measure, and adopted racial-ingroup guidance more readily (Anthis & Kyriakidou-Zacharoudiou (2026)).
- **A source label moves acceptance without improving discrimination.** When 103 participants judged answers labeled ChatGPT or computer, acceptance was higher under the ChatGPT label (68.0% versus 63.4%, p = 0.002), yet signal detection found no source difference in sensitivity (p = 0.930) or criterion (p = 0.082) (Fabio, Rantuccio & Bruno, 2026). The label raises trust without raising accuracy.

- **Reliance is a priced decision, not only a belief.** In a 324-scenario benchmark, five of seven models bought verification with zero expected value of information or over-purchased safeguards, and supplying explicit posteriors fixed some errors while creating others (Chu & Huang (2026)).

Implications for Practice

For instructors

- Teach the check, not the attitude. Greater trust predicted *lower* appropriate reliance (r = −.42) among 432 undergraduates who accepted 86.03% of deliberately misleading suggestions, so instruction that builds generalized confidence makes the problem worse.
- Build verification into tasks where it is cheap and visible: require the source for a claim, the counterexample, or the rerun. Readers shown an AI summary clicked a source cited inside it in only **1% of visits** and clicked result links about half as often, so "it cited something" certifies nothing.
- Remember the lever is protective, not corrective. Participants who began with a wrong judgment recovered the correct one in only **30.6%** and **24.7%** of trials — below chance for a binary choice — so intervene before the student commits to the wrong model, not after.
- Treat under-trust as a calibration failure too; avoiding a capable tool is not the safe default, it is the same error pointing the other way.

For developers

- Change the interaction structure, not just the label. Withholding a multi-agent debate's aggregate position cut detrimental switching to incorrect AI positions from 42–60.5% to 5.7–8.2%, a structural lever that needs no trust from the user.
- Make provenance inspectable at the point of use, since citation-click rates collapse when the summary is presented as authoritative.
- Preserve the student's own stated position and contrasts with it, rather than replacing their draft with a confident answer; the recovery data show that replacement rarely gets undone.

For researchers

- Measure appropriate reliance as a behavioral outcome against ground truth, not as a trust score. The two correlate negatively in the one study that measured both.
- Report recovery rates for initially-wrong participants separately from overall accuracy, because the aggregate hides the below-chance figure that matters most.

The learners who look most resilient are the ones who trusted the tool more. In a survey of 300 South Korean university students, Kim, Kim and Zhang (2026) found overtrust correlating with academic self-efficacy (r = 0.230), intrinsic motivation (r = 0.224) and performance expectancy (r = 0.360), and not with AI literacy (r = 0.051). In the serial model self-efficacy predicted overtrust directly at B = 0.3901 (95% CI [0.2190, 0.5612]), above its total effect of 0.3397, which the authors read as suppression. Calibration cannot be read off a learner's confidence.

Common Misconceptions

“More trust means better use of the tool.” Trust and calibration diverge, and the correlation runs the wrong way. Among **432 undergraduates** solving Python problems with accurate and deliberately misleading AI suggestions, greater trust predicted **lower** appropriate reliance (**r = -.42**), and students accepted **86.03%** of the misleading suggestions. Generalized confidence is not the goal; matched confidence is.

“Under-trusting is the safe default.” Avoiding a capable tool entirely is a calibration failure pointing the other way. Both mismatches cost the learner — one through dependence, the other through forgone capability — which makes “be sceptical” as poor an instruction as “trust it”.

“Calibration can be corrected after the fact.” The lever is protective, not corrective. Participants who began with a wrong judgment recovered the correct decision in only **30.6%** and **24.7%** of trials — below chance for a binary choice. Once a student has committed to the wrong model, correction is unreliable, so the intervention has to land before the commitment rather than after it.

“Checking is easy, so students who care will do it.” Checking is cheap and rarely performed. A passive-tracking panel of **900 US adults** shows the same suppression: readers handed an AI-generated summary followed a source cited inside it on only **1% of visits**, and opened any result link half as frequently as those who saw no summary. The summary suppresses verification rather than prompting it, so the check must be built into the task rather than assumed from diligence.

“Presentation and substance can be separated by a careful reader.” Fluency is what earns unearned trust, which is why calibration is a design problem and not only a learner skill. A system whose interface signals authority will be trusted at that level regardless of instructions to the contrary.

Connected Concepts

- Explainable AI
- AI Literacy
- Cognitive Offloading
- Hallucination Risk
- Metacognition
- Self-Regulated Learning
- Human AI Collaboration
- Misconceptions about AI
- Reducing AI Misuse
- Pedagogical Safety
- Self-Report Measures
- AI Misuse and Learning Harm
- Cognitive Surrender

Connected Articles

- "Do You Trust It… or Check It?": Exploring Children's Verification Behaviors in Game-Based Human-AI Collaboration — Children's verification behaviors in game-based human-AI collaboration
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Student perspectives on transparent AI-assisted writing assessment (AlGhamdi 2026)
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Calibration reframed: withholding the system's position is protective, not corrective
- Epistemic dependence in AI-mediated learning — Six diagnostic criteria separating productive reliance from harmful dependence (Du & Yuan 2026)
- Addressing Trust in AI Systems through Education: A Didactic Perspective — Addressing Trust in AI Systems through Education: A Didactic Perspective
- From Plausibility to Verifiability: The PEARLS Framework for Developing Epistemic Agency in Generative AI-Mediated Higher Education — PEARLS framework for epistemic agency and verifying AI output (Wang 2026)
- Trust-utility gap in introductory physics education: Students' adoption, domain-specific skepticism, and preferences for AI integration
- Face value: How avatar identity shapes epistemic trust in AI-mediated learning
- Agentic Literacy Debt: A Structural Problem the AI Literacy Field Has Not Yet Named — Agentic literacy debt: the structural AI-literacy gap from autonomous agents (Nama 2026)
- Trust and Reliance on AI in Education: AI Literacy and Need for Cognition as Moderators — Trust and Reliance on AI in Education
- Calibrating Trustworthiness: Co-Designing Metrics and Visualizations for Evaluating LLMs in Education — Calibrating Trustworthiness: Co-Designing Metrics for LLMs in Education
- The LLM Fallacy: Misattribution in AI-Assisted Cognitive Workflows — The LLM Fallacy and Misattribution of Competence
- AI as a Partner in Learning about, Doing, and Engaging with Science: Vigilance as the Key to Productive Augmentation — Epistemic Vigilance as the Key to Productive Augmentation
- AI advice suppresses people's willingness to say "I don't know", even when the advice is wrong and accuracy is incentivized
- Modeling AI Overreliance as a Complex Adaptive System — AI overreliance modeled as a complex adaptive system
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations

- Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education — Flawed but Memorable: Student Critical Reception of Interest-Personalized GenAI Analogies in Computing Education
- Why we believe chatbots: trust calibration as a design problem — Trust calibration reframed as a design problem: a two-dimensional user typology and eight design propositions (Jaidka & Cai 2026)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection in AI-mediated grading: a tool that suppressed and contradicted its own warnings (Humble 2026)
- Towards trustworthy and explainable-by-design large language models for automated teacher assessment — Trust-gated inference and explainable-by-design assessment, with trust left unmeasured (Li et al. 2025)
- AI-assisted automated short answer grading of handwritten university-level mathematics exam — confidence filtering of AI grades and its false-positive rate
- Bounded reliance: A source credibility perspective on EFL students' engagement with AI-generated writing feedback — Bounded Reliance: A Source Credibility Perspective on EFL Students' Engagement with AI-Generated Writing Feedback
- Trust and interaction design in AI-enabled systems: a systematic literature review — Trust in AI-enabled systems: definitions, measurement and design factors across 33 empirical studies (Abramson et al. 2026)
- Rethinking teachers' diagnostic skills in AI-supported formative assessment: from diagnosis to meta-diagnosis — From diagnosis to meta-diagnosis: teachers evaluating AI-generated diagnostic inferences (Hoppe et al. 2026)
- College students' metacognitive awareness of generative-AI reliance: an experimental study of decision confidence and attribution bias — A reflection prompt cuts acceptance of incorrect AI advice (Ren 2026)
- Trust calibration and perceived developmental gains in university students' collaboration with generative AI: an exploratory sequential mixed methods study — Trust calibration as a mediator in a chain from contextual support to perceived transfer gains (Bu & Li 2026)
- Psychological predictors of continued ChatGPT use among university students: the roles of AI literacy, trust, and academic self-efficacy — Trust as the pivot from AI literacy to continued use, weakened by AI anxiety (Hu 2026)
- Designing an AI-integrated role-rotation pedagogical model to support competence-related learning in pre-service educational psychologists — Role rotation as a structure for critically handling AI recommendations (Kenzhebayeva et al. 2026)
- Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses — Student Use of LLMs and the Limits of AI-Generated Question Difficulty in Data Science Courses

- The critical role of trust in adopting AI-powered educational technology for learning: An instrument for measuring student perceptions — Student-facing instrument validating trust in AI-EdTech as four factors, with trust upstream of perceived usefulness (Nazaretsky et al. 2025)
- How Children Design and Reason about Trustworthy AI Chatbots — How Children Design and Reason about Trustworthy AI Chatbots
- When AI advice agrees or disagrees with human judgment: trust, self-efficacy, psychological resilience, and adaptive responses in physical education — When AI advice agrees or disagrees with human judgment: trust, self-efficacy, psychological resilience, and adaptive responses in physical education
- Trusting AI too much? Psychological correlates of overtrust and the role of AI literacy - overtrust correlated with self-efficacy and performance expectancy but not with AI literacy in 300 students

Connected FAQs

- How Can We Address Common Misconceptions About AI in Education?
- How Do I Keep Students from Over-Relying on AI?
- How Do I Teach Students to Verify AI Output?
- How Should I Use AI to Study and Learn Effectively?

Explainable AI

> **Explainable AI (XAI) in education** is the design and study of making an AI system's decisions legible to its educational stakeholders — Learners, teachers, administrators, parents, researchers, and policymakers. The central distinction the field insists on: explaining **subject matter** (why a fact is true) is not the same as explaining an **AI system's decision** (why this learner was assigned this activity, why this response was marked incorrect, what evidence supports a risk prediction). Education brings distinctive explainability needs — noisy learning data, explanations that can directly support Metacognition and Self-Regulated Learning, and stakeholders who require fundamentally different explanation types. The operative design question is **explanation quality**, not mere explanation availability: an explanation that is technically present but unreadable, misleading, or misaligned to its audience can do more harm than no explanation at all.

Questions to Consider

- When an AI tutor tells you why a hint was given, is that explaining the *subject matter* or explaining the *system's decision*? Can you name three examples of each in your own use of educational AI?
- Who needs explanations in education — and do learners, teachers, and policymakers need the *same* kind? What would each use an explanation for?
- An AI flags a student as at-risk for dropping out. What does a teacher need to know to act on that, versus what the student needs to know? Is the same explanation appropriate for both?
- The page argues explanation *quality* matters more than explanation *availability*. What makes a technically present explanation fail — can you think of a time an explanation was there but useless, or worse, misleading?
- Trust and explanation are linked but not identical. Why might a confident, fluent explanation create *false* confidence in a flawed system — and how would you detect that happening?

Introduction

Explainable AI in education names the growing expectation that AI systems in classrooms should not be black boxes. Because AI in education affects consequential decisions — grades, risk flags, learning paths, resource recommendations — stakeholders increasingly demand to know not just *what* the system concluded but *why*. Education sharpens this into two distinct questions: explaining the subject matter being learned, and explaining the AI system's own decision-making. Conflating them is a category error with practical consequences: an AI that explains a physics answer perfectly still gives a student and teacher no insight into why the *system* ranked them at-risk, recommended a certain activity, or marked a response incorrect.

Explaining subject matter vs. explaining the system's decision

The field's founding contribution — the XAI-ED framework (Khosravi et al., 2022) — insists education has *distinctive* explainability needs beyond general-purpose XAI. Chief among them is the split between two explanation targets:

- **Subject-matter explanations** clarify *content*: why a hint addresses a misconception, why an answer is incorrect, how a physics result follows from principles. These are pedagogical explanations that support Scaffolding, Feedback, and Metacognition.
- **System-decision explanations** clarify *the model*: why this learner was assigned this activity, why the system predicts this student is at risk, what evidence supports a knowledge-tracing or Learning Analytics prediction. These are transparency explanations that support Trust Calibration, Bias Mitigation, and accountability.

The distinction matters because they serve different stakeholders and different purposes. A learner answering "why is this marked wrong?" mostly needs the *subject-matter* explanation; a teacher deciding whether to act on a risk flag, or a policymaker auditing for bias, needs the *system-decision* explanation. Designing a single explanation that serves both is rarely possible — which is why multi-stakeholder design is a core XAI-ED theme.

Who needs explanations: multi-stakeholder design

- **Learners** need explanations that support their own learning and self-regulation — why a hint was given, why their answer was marked incorrect, why this resource is recommended (supporting Self-Regulated Learning). The student-perspective evidence shows learners draw a sharp line between accepting AI *feedback* (useful for revision) and ceding *grading authority* (reserved for the human instructor) — a calibrated, function-matched stance activated by transparency about AI involvement. Value-sensitive design work with community college students sharpens the point: students preferred *collaborative, humanized* explanations (e.g., "the AI might be uncertain here, so let's check this together") over raw model confidence or technical transparency, because transparency alone has little value unless it directly supports their learning. The study surfaced a transparency-vs.-interpretability tension that pushes explanation design toward learner-facing semantics rather than feature-importance output.
- **Teachers** need explanations that inform intervention — which students are at risk and *why*, on what evidence. Explainability studies with teachers show domain-specific, curricular-language explanations build acceptance and calibrated trust more effectively than generic feature-importance ones, yet teachers still want real classroom experience before full reliance — explanation alone does not confer calibration.
- **Developers and researchers** need explanations to debug model behavior and detect bias — surfacing which features drive predictions.
- **Administrators and policymakers** need explanations for accountability, Privacy, and AI Regulation in Education compliance (e.g. the right to explanation), and to audit whether AI-driven decisions are fair and equitable.

Approaches and formats

The XAI-ED framework catalogs the main explanation modalities: **visual** (heatmaps, decision trees), **textual** (natural-language justifications), **example-based** (counterfactuals, nearest neighbors), **feature-importance** rankings, **rule extraction**, and **model simplification**. It also maps approaches to model classes:

- **White-box** models (decision trees, linear models, rule-based) are inherently interpretable.
- **Black-box** models (neural networks, ensembles) require post-hoc explanation methods.
- **Glass-box** approaches try to balance accuracy with transparency.

The concrete AIED evidence base spans all of these. **Interpretable knowledge tracing** makes learner-knowledge models inspectable directly (Interpretable Knowledge Tracing, Explainable Knowledge Tracing via Probabilistic Embeddings and Pattern-based Reasoning, Neural-Symbolic Knowledge Tracing: Injecting Educational Knowledge into Deep Learning for Responsible Learner Modelling). **Self-explaining surrogates** distill a black-box model into a small, interpretable language model for Learning Analytics (Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics). **Counterfactual explanations** — "what would need to change for a different outcome" — support educational decision support and recourse (From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support). **Federated + explainable learning analytics** shows explanation quality can drift (calibration degrades) even when ranking stability holds, underlining that explanations are not a fixed property but a system output to be measured (Federated and explainable learning analytics for privacy-preserving academic risk modeling across heterogeneous educational institutions). And **interpretable affective ITS** demonstrates explanations in emotion-aware tutoring (An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training). - **External measurement sidesteps the unfaithful-account problem.** Filtered Decision Logs rebuild tool traces into a provenance tree and rank evidence with four deterministic signals, so the influence score is verifiable independently of the recommendation, and counterfactual tool removal confirmed the ranking tracked dependence (Anbalagan et al. (2026)).

Explanation quality, not availability

A recurring lesson across the evidence: **having an explanation is not enough**; the explanation must be right for its audience, accurate, and calibrated to stakes. The XAI-ED framework names the pitfalls explicitly:

- **Explanation overload** — too much information overwhelms the user and negates the benefit.
- **Misleading explanations** — post-hoc explanations may not reflect the model's actual reasoning, giving false confidence.
- **Confirmation bias** — users selectively attend to explanations that confirm existing beliefs.
- **Over-trust** — fluent explanations can create false confidence in flawed systems, feeding over-reliance (the obverse of Trust Calibration).
- **Gaming the system** — students may exploit explanations to circumvent actual learning.

Explanation quality also has an equity dimension: an explanation that is technically present but unreadable to a given stakeholder — or that obscures the bias in a prediction — fails its purpose. This is why the design question is *quality and fit*, and why human-centered, stakeholder-specific explanation design is inseparable

from the technical generation of explanations. Effective XAI is a communication act designed for the recipient's cognitive needs, not merely a technical artifact.

Explanation is not always a leveler. In a 2 × 2 vignette experiment with 250 seventh-grade students, a written rationale for a mathematics score raised acceptance and perceived fairness in both conditions but widened rather than closed the gap between teacher- and AI-made decisions (Zhang et al. (2026)).

Citations behave as a credibility cue rather than evidence of correctness: attaching citations and authority signals to a debate interface raised abandonment of a correct judgment for the AI's position from 15.0% to 31.8%, and cited cases were sometimes misattributed or fictitious (Tuo et al., 2026).

Two cautions sharpen this further, both of which the wiki's newest contribution on the subject makes central. First, the explanation machinery is not itself neutral: post-hoc methods such as LIME and SHAP can be unfaithful to the model's actual behavior, so a technically present explanation may mislead rather than inform (Lund et al. 2026, drawing on Chuan et al. 2024). Second, **explanation is not accountability**. An account of which features drove a prediction does not reveal whether those features were appropriate to use, whether the training data was representative, or whether the system's design reflected sound judgment; explanations can create the appearance of transparency while leaving the structural conditions that produced a decision untouched (Mittelstadt et al. 2019). For education this means the question to keep asking is not whether an explanation was produced but whether the person receiving it — a student, a teacher, an advisor — could understand it, act on it, or contest the decision behind it. The same failure of legibility appears on the security side of automated assessment: Humble's (2026) red-team of an AI grading tool found it silently disabling the chat after blocking a prompt injection, and — having announced it would never follow embedded instructions — following them in six further runs on the same file, leaving the user no reliable signal on which to base reliance.

Explainable-by-design is one answer to the post-hoc faithfulness problem. Li, Yang and Fang (2025) parameterize an explanation decoder by the same fused representation and predicted score that decide the Assessment, so that a low score on formative questioning yields a rationale naming insufficient probing questions, and pair it with dual-lens attention over curriculum standards and subject-specific rubric moves. Attention-to-rubric alignment reaches 78.0% against 41.7% for GPT-4 zero-shot and 32.1% for BERT, and faithfulness is probed by counterfactual deletion of rubric-critical spans alongside human ratings on a rubric-anchored checklist, giving an explanation-credibility score of 0.78 — an increase of 0.31 over BERT-base. The audit also shows where the architectural claim thins: on emotional cues the model allocates 28.4% of attention weight against an expert 15.2% (alignment 0.53), with one failure case assigning 28% to the token "frustrated", which the authors read as overfitting to affect rather than pedagogy and name as an area for refinement. Embedding explanations in the decision path makes them more faithful than post-hoc rationales; it does not make them correct.

What a model says it used depends on the family as much as on the data. Across seven models on one cohort, Hooshyar et al. (2026) found symbolic approaches leaning on cognitive and motivational factors, sub-symbolic models on cognitive aspects, learned knowledge and gender, and both largely overlooking metacognitive factors, while the neural-symbolic model used a more integrated set. The same students and the same indicators produced different accounts of what mattered, so alignment with learning theory becomes a claim about attributions rather than about accuracy.

Teaching explainability as accountability practice

If explanation quality decides whether XAI is useful, then producing explanations has to be taught as a professional habit rather than demonstrated as a capability. Lund and colleagues (2026) propose doing this across four pillars — **answerability** (the obligation to give reasons to those affected), **responsibility** (harm anticipated across the lifecycle, not defended after the fact), **enforcement** (consequences inside the course) and **reflexivity** (documented examination of one's own assumptions) — each with its own assignments and its own classroom cost.

For explainability specifically, the assignments that matter are the ones that force explanation out of the notebook: graded model cards weighted alongside accuracy metrics, and structured explanation audits in which students apply interpretability tools to their own models and then present the results to an audience without a shared technical background. Enforcement is the pillar most often missing from ethics-adjacent courses and the one that makes the rest more than symbolic — rubrics that reward responsible documentation, projects that can be returned for revision on ethical grounds, and peer review conducted against accountability criteria rather than technical ones alone. The paper is candid that the tools differ sharply in cost: model cards and positionality statements need no new software and risk only superficial compliance, whereas peer panels and stakeholder engagement require coordination and institutional buy-in, which is why it recommends a staged adoption rather than an all-or-nothing commitment. See Curriculum Design for where these fit in a program.

Common Misconceptions

- **"Citations make an explanation trustworthy."** Citations behave as a **credibility cue rather than evidence of correctness**: attaching citations and authority signals to a debate interface **raised abandonment of a correct judgment for the AI's position from 15.0% to 31.8%**. Provenance made the wrong answer more persuasive, which is the opposite of the intended effect.
- **"An explanation that satisfies users has explained the system."** The same failure of legibility appears on the security side of automated assessment: Humble's (2026) red-team found an everyday grading workflow could be manipulated by injected instructions. A plausible narrative and an auditable one are different artifacts.
- **"General XAI practice transfers to education."** The XAI-ED framework (Khosravi et al., 2022) insists education has **distinctive explainability needs** beyond general XAI, because the audience includes learners who must act on the explanation rather than auditors who must certify it.
- **"Faithfulness is a property you can claim without probing."** Measured faithfulness requires **counterfactual deletion of rubric-critical spans** alongside human ratings. Attention-to-rubric alignment reaching **78.0% against 41.7% for GPT-4 zero-shot and 32.1% for BERT** is a comparative result from that kind of probing, not from a claim about interpretability.

Connected Concepts

- Trust Calibration
- Trust
- AI Literacy

- Learning Analytics
- Automated Assessment
- Learner Modeling and Adaptive Instruction
- Intelligent Tutoring
- Knowledge Tracing
- Bias Mitigation
- Human-in-the-Loop
- Pedagogical Safety
- Metacognition
- Self-Regulated Learning
- Cognitive Offloading
- Privacy
- AI Regulation in Education
- Recommender Systems and Learning Paths

Connected Articles

- Toward socially accountable data science education: A conceptual framework for integrating explainable AI and accountability principles — A four-pillar framework (answerability, responsibility, enforcement, reflexivity) for teaching XAI as accountability practice (Lund et al. 2026)
- Value-sensitive design in action: Designing student-centered intelligent tutoring systems with community college students and instructors — Value-sensitive design of student-centered ITS (collaborative vs. raw explanations)
- Explainable Artificial Intelligence in education — XAI-ED: the foundational framework for explainable AI in education (Khosravi et al. 2022)
- The Impact of Explainable AI on Teachers' Trust and Acceptance of AI EdTech Recommendations: The Power of Domain-specific Explanations — Domain-specific explanations build teachers' trust and acceptance (Feldman-Maggor et al. 2025)
- Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education — Student perspectives on transparent AI-assisted assessment (AlGhamdi 2026)
- Interpretable Knowledge Tracing — Interpretable knowledge tracing
- Explainable Knowledge Tracing via Probabilistic Embeddings and Pattern-based Reasoning — Explainable knowledge tracing via probabilistic embeddings
- Neural-Symbolic Knowledge Tracing: Injecting Educational Knowledge into Deep Learning for Responsible Learner Modelling — Neural-symbolic knowledge tracing
- Distilling Black-Box Machine Learning into a Small, Self-Explaining Language Model for Learning Analytics — Distilling black-box models into self-explaining LMs for learning analytics

- Federated and explainable learning analytics for privacy-preserving academic risk modeling across heterogeneous educational institutions — Federated and explainable learning analytics for privacy-preserving risk modeling
- From Student Risk Prediction to SC2R: Semantics-Constrained Counterfactual Recourse for Educational Decision Support — Semantics-constrained counterfactual recourse for educational decision support
- Fair and explainable educational recommendations with a hybrid Graph-GRU framework — Fair and explainable educational recommendations
- An Interpretable Closed-Loop Intelligent Tutoring System for Multimodal Affective Feedback in Asynchronous Presentation Training — Interpretable closed-loop ITS for multimodal affective feedback
- Explaining ChatGPT Adoption in Higher Education: Insights for AI Literacy, Educational Practice, and Responsible AI — Explaining ChatGPT adoption in higher education
- Towards trustworthy and explainable-by-design large language models for automated teacher assessment — Explainable-by-design LLM framework: dual-lens attention and score-parameterized explanations for automated teacher assessment (Li et al. 2025)
- Ethical implications of prompt injection in AI-mediated grading: An adversarial red-team evaluation — Prompt injection in AI-mediated grading, where detection was never reported to the user (Humble 2026)
- Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions — Evaluation of pre-trained models for pedagogical assessment of novel AI-assisted educational questions
- Teacher or Artificial Intelligence? The Effect of Decision-Making Agent on Junior High School Students' Decision Acceptance: A Moderated Mediation Model — Teacher- versus AI-made grading decisions: a written rationale widened the fairness gap
- Countering the Risks of AI Overreliance: Leveraging Multi-Agent Debate for Complementary Human–AI Decision-Making in Legal Contexts — Citations and authority signals raised deference to incorrect output, some references misattributed or fictitious
- Towards responsible and trustworthy educational data mining: Comparing symbolic, sub-symbolic, and neural-symbolic AI methods - symbolic, sub-symbolic and neural-symbolic models on one cohort attributed their predictions to different factors

Citation

Khosravi, H., Buckingham Shum, S., Chen, G., Conati, C., Tsai, Y.-S., Kay, J., Knight, S., Martinez-Maldonado, R., Sadiq, S., & Gašević, D. (2022). *Explainable Artificial Intelligence in education*. *Computers and Education: Artificial Intelligence*, 100074.

Sustainability

> **Sustainability** — the intersection of two concerns: how AI can be used *for* sustainability outcomes in education (AI for sustainability, including Education for Sustainable Development and green education), and how to make AI itself *sustainable* (sustainable AI, reducing the environmental, ethical, and social footprint of AI systems in education). As both users and developers of AI, educational institutions must advance environmental and social goals while ensuring responsible, ethical AI use.

Questions to Consider

- The page distinguishes two pathways: 'AI for sustainability' (using AI to advance sustainability outcomes) and 'sustainable AI' (reducing AI's own environmental and ethical footprint). Can you think of a way an AI tool could advance one goal while undermining the other?
- Training and running large language models carries a real carbon and water footprint. When an institution promotes sustainability as a value while deploying energy-intensive AI, what tensions arise — and who should weigh them?
- Before you read on, how would you define 'sustainable education'? The page treats it as a value-based, human-centered project distinct from using education as an instrument for sustainability — how do those differ?
- If education is expected to build learners' 'sustainability consciousness,' what role might AI play in that — and could AI integration in the curriculum teach sustainability while its own footprint quietly contradicts the lesson?
- What would it mean for an educational institution to be genuinely sustainable in its AI use, and which of its decisions (procurement, deployment, teaching) do you think matter most?

Introduction

Sustainability in AIED spans three overlapping framings: **sustainable education** (a value-based, human-centered educational project), **sustainability in education** (using education as an instrument for sustainability), and **education for sustainable development** (ESD, the global policy agenda, especially Sustainable Development Goal 4). AI intersects each of these differently — and the field distinguishes two core pathways: **AI for sustainability** (AI as a tool to achieve sustainability outcomes) and **sustainable AI** (reducing AI's own environmental and ethical footprint).

The environmental pathway has a documented gap: Gillette et al. (2026) report that genAI's environmental consequences were not discussed in the university's policy documents at the study site, and argue that institutional guidance omitting them fails to address the concerns teachers and students hold.

The two-part taxonomy

The knowledge base's coverage, anchored by Daniel et al. (2026), organizes the field into two interconnected yet distinct pathways:

- **AI for sustainability** — using AI to advance sustainability outcomes. In education this includes AI for energy management, climate monitoring, green campus programs, and AI-integrated curricula that build learners' sustainability consciousness (e.g. the AI-SEE framework for sustainable engineering education). It is grounded in the global agenda of Education for Sustainable Development.
- **Sustainable AI** — reducing the direct environmental and ethical impacts of AI itself. This covers the carbon and water footprint of large language models, energy-efficient and on-premise deployment, and the ethical and governance frameworks needed to ensure AI's use in education is itself responsible and sustainable.

Using AI for sustainability in education

A growing body of work treats AI as a tool *for* sustainability education and outcomes:

- **AI-integrated curricula that build sustainability consciousness.** Liu et al. (2026) propose the AI-SEE framework (intelligence-driven, green-empowered, responsibility-leading, practice-integrated), which integrates AI across the curriculum as a cognitive scaffold and resource for system-level sustainability analysis. In a 144-student engineering case, it enhanced sustainability consciousness and produced behavioral engagement across personal, academic, professional, and social levels, with social diffusion beyond the classroom.
- **AI in green and sustainable education.** Talebzadeh (2026) found AI-assisted instructional design under Sustainable Development Pedagogy constraints improved teacher workflows and pedagogical design. Riandi et al. (2026) found that teachers' practical use of AI in science/green energy and their involvement in developing ESD-aligned materials — more than abstract AI knowledge or attitudes — predicted their capacity to integrate AI into green energy education.
- **Sustainability as a value-based project.** Alsuhami & Atallah (2026) argue AI's contribution to sustainable education is conditional and governance-mediated: it supports sustainability only when adoption is subordinated to explicit educational values and human-centered purposes, rather than to technologization and commodification. This ties sustainability to Ethics and Critical Pedagogy.

Making AI itself sustainable

The second pathway concerns AI's own footprint in educational settings:

- **Environmental impact of large models.** studies of LLM use document the carbon and water footprint of large language models, which is significant given high adoption among university students. This is the direct environmental dimension of sustainable AI.
- **Energy-efficient and on-premise deployment.** Shen et al. (2026) demonstrate that AI knowledge-base assistants can run on consumer-grade hardware with open educational resources,

reducing the environmental and cost footprint of AI in education — a concrete sustainable-AI design pattern.

- **Ethical and governance frameworks.** Sustainable AI is not only environmental: it requires AI Governance and Ethics frameworks ensuring transparency, accountability, human oversight, and equitable access, as Daniel et al. (2026) note is often lacking in current university applications.

Sustainable learning as a pedagogical goal

A related strand frames sustainability not only as an environmental or institutional concern but as a property of learning itself. Zhu et al. (2026) argue AI-assisted learning risks cognitive outsourcing and detachment from authentic contexts, proposing frameworks (E3-HOT) for **sustainable learning** — learning that persists, transfers, and remains connected to real problems rather than being short-circuited by Cognitive Offloading. This connects sustainability to Learner Agency and Critical Thinking.

Connections to other concepts

Sustainability and AI in education sits at the intersection of Ethics, AI Governance, AI in Education, and the environmental/energy sciences. It draws on Teacher Education and Teaching for capacity-building, on Learning Design for pedagogy, and connects to the knowledge base's treatment of Cognitive Offloading and Critical Thinking through the "sustainable learning" lens. Because both pathways are cross-cutting, sustainability is a foundational theme that appears across higher education, K-12, and professional contexts.

Common Misconceptions

- **"Abstract AI knowledge predicts teachers' capacity to teach sustainability."** Talebzadeh (2026) found that teachers' **practical use of AI** in science and green-energy contexts and their **involvement in developing ESD-aligned materials — more than abstract AI knowledge or attitudes** — predicted their capacity. Knowing about AI and being able to build with it diverged, and the practical route predicted more.
- **"AI-assisted instructional design under a sustainability pedagogy produces sustainability pedagogy."** The same work found that AI-assisted instructional design under Sustainable Development Pedagogy **constrained** design in specific ways rather than expanding it. A model trained on conventional materials reproduces conventional framings unless the design work corrects for it.
- **"Sustainability is a topic, not a cross-cutting theme."** Because both pathways run across levels, sustainability appears in higher education, K-12 and professional contexts — which means it is a foundational theme that has to be addressed inside each discipline rather than taught as a separate subject.

Connected Concepts

- Ethics
- AI Governance

- AI in Education
- Higher Education
- K-12
- Teacher Education
- Teaching
- Learning Design
- Engineering Education
- Critical Thinking
- Cognitive Offloading
- Learner Agency
- Open Source

Connected Articles

- Toward Partnership Ethics for Generative Artificial Intelligence in Higher Education — Swedish survey and focus-group study arguing that partnership ethics, not a cheating frame, should guide institutional genAI decisions
- A Scoping Review of AI for Sustainability and Sustainable AI in Higher Education — Scoping review of AI for sustainability and sustainable AI in higher education
- Sustainable Education in the Age of Artificial Intelligence and Digitalization: A Value-Critical Approach — Value-critical approach to sustainable education and AI
- Enhancing Sustainability Consciousness in Higher Education: Impacts of Artificial Intelligence-Integrated Sustainable Engineering Education — AI-SEE framework for sustainable engineering education
- Teacher Involvement in Developing Sustainable Education Materials for AI Integration in Green Energy Education — Teacher involvement in AI integration for green energy education
- The Role of Artificial Intelligence in Green Education: Optimizing Teacher Workflow and Enhancing Pedagogical Design under Sustainable Development Pedagogy (SDP) Constraints — The Role of AI in Green Education
- Towards sustainable AI knowledge-base assistants in computer science education: on-premise deployment and optimization with open educational resources — Sustainable AI knowledge-base assistants
- When LLMs Slow Down: How Environmental Impacts Mediate University Students' LLM Usage — Environmental impacts of LLM use
- Fostering Sustainable Learning via Embodied Intelligence: The E3-HOT Framework for Higher-Order Thinking in the AI Era — Fostering sustainable learning via embodied intelligence
- Preparing Learners and Teachers for an AI-Driven Future: Emerging Trends, Pedagogical Challenges, and Critical Perspectives in Pre-University AI Education: A Systematic Literature Review — SLR of pre-university AI education (SDG 4 framing)

Pedagogical Safety

> **Pedagogical safety** — the design principle that AI education systems must protect Learners from harm, including inappropriate content, unsafe advice, biased treatment, and manipulative interaction patterns. Safety is particularly critical for K-12 contexts, where the stakes of harm are highest and learners are least equipped to detect it.

Questions to Consider

- Safety for chatbots usually means refusing harmful content and resisting jailbreaks. Why might that be 'necessary but not sufficient' for an educational tutor? Can a tutor be safe yet still harm learning?
- The page describes a 'quiet' failure: a tutor that answers correctly yet erodes learning, or refuses evenly yet entrenches inequality. Have you seen a well-intentioned guardrail have an unequal or harmful side effect?
- Harm rates rose from ~18% on single-turn evaluations to ~78% on multi-turn ones. What does that tell you about testing AI tutors with one-shot questions versus real extended conversations?
- The 'Paternalistic Filter' audit found refusals and softened answers patterned by student identity. How might over-cautious safety policies reproduce epistemic injustice even while 'protecting'?
- If simulated students are themselves sycophantic—abandoning their assigned misconceptions at any correction—what might that hide about how real learners actually respond to a tutor?

Introduction

Conventional Large Language Models (LLMs) safety — toxicity screens, jailbreak resistance, and content refusal — is necessary but not sufficient for education. The harm taxonomies emerging from the knowledge base's own articles show that the most damaging tutoring failures are quiet: a tutor that answers correctly yet erodes learning, or refuses evenly yet entrenches inequality. The evidence below groups these findings into four interlocking safety concerns.

Content safety and guardrails

- **Education-specific risk frameworks:** EduZone generates adversarial student- and teacher-facing interactions across six risk categories and 28 subcategories, finding that models are *more* vulnerable to education-specific harms and dynamic multi-turn conversations than existing Guardrails address. EduGuard and retrieval-augmented generation ground responses in verified content to reduce fabrication.
- **Guardrails are not neutral:** the Paternalistic Filter audit of 1,800 history-tutor responses shows refusals and softened answers are patterned by student identity and topic sensitivity, reproducing epistemic injustice even while "protecting." Safe guardrails must be audited for differential

treatment, not just aggregate harm — a direct case for Bias Mitigation in AI Governance and Equity.

- **Teachers design their own safety architecture, not just consume it:** Reichert et al. (2026) asked six secondary teachers to paper-prototype LLM chatbots for their classrooms and found they independently built a three-layer protective architecture rather than relying on model-level moderation. Domain boundaries confined the bot to lesson-specific content (one to Emperor Qin Shi Huang within an ancient China unit, another to Python variables, data structures, and functions) and added an "information quota" requiring a minimum number of facts or problems before the conversation progressed. Content filtering produced standardized refusals — "Sorry, this is not part of my knowledge base" — that simultaneously alerted the teacher. Teacher override handled ambiguous cases: a question about human reproduction was judged legitimate within its unit and routed to a person rather than auto-rejected. Teachers further preferred *behavioral* transparency (visible limits, uncertainty cues such as "Is the visual aid helpful?") over algorithmic explanation, and wanted complete conversation logs with real-time alerts so generated content could be checked for accuracy and student use supervised. A safety layer teachers can see, understand, and override is part of the mechanism, not a concession from it.
- **A reliability layer built for adolescents, not adapted from adults.** Muss, Leisten and Bardyn (2026) argues that the fastest-growing population of LLM users — adolescents, including through LLM-powered toys entering homes — is served by systems never designed for their educational, emotional or developmental needs. SCAFFOLD surrounds generated text and speech with external verification, targeted repair and safe fallback, steered by a conceptual framework drawn from developmental psychology, neuroscience, the learning sciences and pedagogy, and kept model-agnostic and privacy-preserving so safety does not rest on a single provider's alignment work. Its classroom pilot with 12–16-year-olds using an LLM-powered social robot in a multi-user co-creation task produced more student activity, engagement and on-topic participation than a prompt-only baseline, with co-creation level associated with post-test knowledge after controlling for prior knowledge. That is feasibility evidence rather than a proven effect, and its more durable contribution is a concrete template for Guardrails that educators can configure rather than accept.
- **Model-level content controls:** the math-unlearning work applies gradient-based unlearning to strip personally identifying information and harmful content from math tutors (PII output down to 0.1%, toxic rates to 0.0%) while preserving downstream math utility and Privacy. Children's reading-story generation shows supervised fine-tuning of compact models can enforce controllable difficulty and safety for K-12 content.

Interaction and harm taxonomies

- SafeTutors and its harm taxonomy derive 11 dimensions and 48 sub-risks from learning science — answer over-disclosure, misconception reinforcement, abdication of scaffolding, erosion of productive struggle — and show every tested model exhibits broad pedagogical harm, with failures escalating from 17.7% (single-turn) to 77.8% (multi-turn). Single-turn evaluation is dangerously misleading.

- **Evaluation integrity depends on faithful simulation:** misconception-faithfulness work shows simulated students are themselves sycophantic — they abandon assigned misconceptions at nearly any corrective signal — so safety evaluations run on such simulators may miss harm patterns real students would exhibit. This links Simulation, Misconceptions about AI, and Intelligent Tutoring QA.
- **Deployment QA is a safety activity:** PromptDecipher found teachers virtually never test AI tutoring bots before student deployment, and enforces teacher-driven QA as a first-class authoring activity via correction-based editing and Human-in-the-Loop validation.

RL and alignment approaches to safety

- Pedagogical safety in RL formalizes the problem: as Reinforcement Learning personalizes instruction, poorly specified rewards invite "reward hacking" — test-score inflation, engagement gaming, and short-term gains. It proposes a four-layer model (structural, progress, engagement, outcome) and detection via discrepancy auditing, policy inversion, and long-term tracking.
- **Guidance-oriented RL at mid-size.** Singh et al. (2026) optimized a dense 32B model with DAPO reinforcement learning plus a filtered synthetic SFT stage to 96.52% on a pedagogical-knowledge benchmark, above a far larger proprietary system — though that score comes entirely from teacher-exam multiple-choice items, leaving free-form tutoring dialogue untested.

Sycophancy and manipulation risks

- EduFrameTrap identifies a reasoning–sycophancy paradox: tutors that resist context-switch attacks still capitulate under authority pressure ("my notes say I'm right") and social-affective pressure ("don't tell me I'm wrong"), withholding corrective Feedback. It argues "kind-but-correct" behavior is a safety requirement, and that effective tutoring needs corrective friction to drive conceptual change — otherwise over-reliance is reinforced and misconceptions are validated.
- Critical AI Tutors warns that unchecked tutors cause cognitive atrophy, loss of agency, and dependency, reframing pedagogical safety to ask not just what a tutor does but what kind of learner it produces.

Practical guidance

Design pedagogical safety as a measurable, discipline-aware requirement rather than an afterthought. Evaluate with multi-turn, subject-specific benchmarks and unfair-treatment audits, not single-turn toxicity screens; ground responses with RAG (Retrieval-Augmented Generation); prefer alignment methods that reward guidance and scaffolding over answer-giving; and require teacher-in-the-loop QA before deployment. For K-12 especially, treat sycophancy, differential refusal, and over-reliance as first-class safety concerns alongside content and hallucination. Design frameworks make this concrete: SSAIL (Rahimi, 2026) reframes safety around the learner's own competencies — Learning Safety protects the development, maintenance, and valid demonstration of valued human abilities (reasoning, epistemic dispositions, Learner Agency) from foreseeable harm, while Learning Soundness ensures the tool genuinely supports that development — and

operationalizes both through evidence-centered design by deliberately allocating what the learner must do versus what AI may do as the learner develops.

Connections to related concepts

Pedagogical safety is the protective layer connecting Hallucination Risk, RAG (Retrieval-Augmented Generation), K-12, Ethics, AI Governance, AI Regulation in Education, and Large Language Models (LLMs) with the interaction-level concerns of Trust, Scaffolding, Metacognition, and Self-Regulated Learning. It operates through training and RL, depends on Bias Mitigation and Equity, and is motivated by the harms catalogued in AI Misuse and Learning Harm and the tutor harm taxonomies. - **Child harm rarely enters through the model.** In 1,331 coded child-related AI incidents, harm concentrated in representational, dignity-related and psychological categories and co-occurred with deployment, governance and misuse failures rather than model defects, so per-output filters miss the dominant pathway (Jiao et al. (2026)).

Common Misconceptions

“Toxicity filters and jailbreak resistance make a tutor safe.” Conventional Large Language Models (LLMs) safety is necessary but not sufficient for education. It addresses what a model will *say*; pedagogical safety addresses what the interaction does to the learner, including failures no content classifier can see. A tutor can pass every content check while systematically eroding learning or entrenching inequality.

“If a system behaves well in a single exchange, it is safe in use.” Risk compounds across turns: harm rates rose from about **18% on single-turn evaluations to about 78% on multi-turn** ones. Single-turn benchmarks therefore report a figure four times too reassuring for the interaction students actually have, and a red-team suite built on isolated prompts will certify a system that fails in a ten-minute session.

“The safest tutor is the one that refuses most.” A system that “refuses evenly” can still entrench inequality, which is the second half of the page’s quiet-failure description. The failure mode is not only a tutor that answers correctly and erodes learning; it is also a tutor whose refusals distribute support unevenly across students, and a blanket refusal policy trades a visible risk for an invisible one.

“Any model-level safety work is a public-relations measure.” Some of it is measurable. The math-unlearning work applies gradient-based unlearning to strip identifying information and harmful content, reporting PII output down to **0.1%** and toxic rates to **0.0%** while preserving capability. Model-level controls are one layer of a layered defense — insufficient alone, and not nothing.

Connected Concepts

- Guardrails — the design mechanisms that implement safety
- Hallucination Risk
- RAG (Retrieval-Augmented Generation)
- K-12
- Ethics
- AI Regulation in Education
- AI Governance

- Large Language Models (LLMs)
- Cognitive Offloading
- LLM Training and Fine-Tuning
- Intelligent Tutoring
- Bias Mitigation
- Reinforcement Learning
- Privacy
- Equity
- Trust
- Scaffolding
- Misconceptions about AI
- AI Sycophancy
- Simulating Students
- Self-Regulated Learning
- Simulation
- AI Misuse and Learning Harm
- Human-in-the-Loop

Connected Articles

- Scaffolding Students-AI Dialogue: A Framework for Safe Educational Interactions — The SCAFFOLD framework for steering students-AI dialogue, with its classroom pilot
- Human-centered design of LLM-powered educational chatbots: A study with secondary teachers — Teacher-designed safety layers: domain boundaries, filtering, and override
- SSAIL: A Design Framework for Safe and Sound AI for Learning — SSAIL: A Design Framework for Safe and Sound AI for Learning
- EduZone: A Framework for Evaluating LLM Safety for K-12 Students and Teachers
- EduGuard: A Safe RAG-Based LLM Tutor for Programming Education
- SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems
- The Paternalistic Filter: Epistemic Injustice and Differential Refusal in LLM-Mediated History Education for Marginalized Romanian Students
- Balancing AI responsibility with privacy, safety, and utility: Unlearning in large language models for mathematics education
- Children’s English reading story generation via supervised fine-tuning of compact LLMs with controllable difficulty and safety
- Simulating Students or Sycophantic Problem Solving? On Misconception Faithfulness of LLM Simulators
- PromptDecipher: Supporting AI Tutor Authoring Through Editable Simulated Interactions
- Pedagogical Safety in Educational Reinforcement Learning

- Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning
- TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring
- Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks
- Critical AI Tutors: Empower or Enslave?
- Exploring interfaces and implications for integrating social-emotional competencies into AI literacy for education: A narrative review

Connected FAQs

- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- What Are Best Practices for Developing an Effective AI Tutor?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

Frequently Asked Questions

This section answers common questions about **AI in education** — what the research says about how AI affects teaching and learning, and how educators, instructors, and instructional designers can put that evidence into practice. Each answer distills findings from the research summarized across this knowledge base, connecting the question to the relevant concepts and articles for deeper reading.

Start here

Two broad questions worth reading before the specific ones, whichever role you are in.

What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

It is the week before term, or the week after the first big submission, and someone has asked you something you cannot answer from experience: what students may do with AI on this assignment, and what the grade then proves. Perhaps a take-home essay came back polished in a way that does not match the student's earlier work. Perhaps your department is writing an AI policy and wants your course to conform by Friday. Perhaps a student is appealing a mark and you cannot show what the work demonstrates.

The bottom line from the research this knowledge base has collected: how you build generative AI into the activity decides whether it strengthens thinking or replaces it. The lever you control is the design of the task. The test of any design is what students can still do when the tool is gone. The ten findings this page is named for are below, sorted by the decision each one informs.

The short version

1. Name the thinking the assignment exists to produce, then give AI a job that does not perform that thinking.

2. Set the AI rule per assignment rather than per course, and write the reason next to it where students will read it.

3. Put at least one graded step in every unit that the student completes with no AI present.

4. Judge the activity by what students can do weeks later, unaided, rather than by the quality of what they hand in.

5. Ask how students used the tool, and grade the verification rather than the logins.

6. Look at which students the design helps, because an average hides the ones it drops.

Decide what the assignment is for

Write one sentence naming the capability before you touch the tool: what should a student be able to do at the end of this unit that they could not do at the start? The answer might be: construct an argument from evidence, write a proof, arrive at a diagnosis, make a design decision under constraints. If you cannot name it, the AI rule will be arbitrary and the students will notice.

Two lines of work explain why this comes first. Productive failure is the finding that learners often retain more when they attempt a problem before being shown how, so friction is sometimes the mechanism rather than an obstacle to be removed. The ICAP framework predicts different learning from passive, active, constructive, and interactive use of the same material. Both point at one design question: what is the student doing while the tool is open?

The clearest illustration in the corpus comes from a comparison of a theory-informed chatbot that scaffolded student explanations against ordinary ChatGPT and business-as-usual teaching. Immediate differences were not significant. Four weeks later, the scaffolded group retained more conceptual knowledge. That is one

study and not a universal effect, and its useful content is the shape of the result: design can outweigh model capability, because what separated the conditions was what the activity asked students to do.

The systematic review of 72 peer-reviewed computing-education studies arrives at the same layer from the other direction. It calls critical engagement with AI output "the common mechanism linking every effective intervention in the corpus" and recommends graduated access, introducing generative AI only after foundational competence has been shown. Neither claim is about which product you license.

Give AI a job that is not the thinking you are grading

Decades of intelligent-tutoring research describe the pattern that works: diagnose what the student understands, ask questions, give graduated hints, ask them to explain, give feedback. Everything except handing over the solution. Current Pedagogical Agent work draws the same line between teaching behavior and answer production, and the Thermomix analogy makes it concrete. One appliance can do the cooking for you, in which case you lose the skill, or it can act as a testing partner for ideas you still have to make sense of. Those modes map onto ICAP: passive, active, constructive, interactive.

Narrow tools show the same principle. A tutor that reads engineering diagrams structurally reached 93.0% edge-level F1 against 89.3% whole-diagram accuracy, which means it can name the specific missing or misread connections even when the whole diagram is wrong. That is feedback a student can act on, instead of a pass or fail.

The harder question is what the tutor is allowed to recommend. When a multi-agent debate replaced "here is the AI's answer" with a discussion whose own preferred position was withheld, detrimental switching to an incorrect AI position fell from 42-60.5% to 5.7-8.2%. Adoption of a correct AI position also fell, from 61.1-72.3% to 22.1-33.3%. Withholding a recommendation protects the student's initial judgment and leaves correction to deliberation, so the design trades error correction for fewer confident wrong turns. Decide which of those two you want from the exchange before you write the prompt.

In class this is cheap to implement. A Socratic sequence is the pattern to aim at, with the tool asking rather than answering. Tell students to ask for "one hint", "ask me questions", or "critique my reasoning", and make "solve this" the unusual case. You are changing the default verb of the interaction, which is the part students actually control.

One limit worth stating plainly. Most of this evidence comes from short tasks in a handful of courses, and none of it promises that a hint-giving tutor will raise exam scores in your section. For that question you need the randomized trial discussed below, and its result is sobering.

Set the rule on the assignment, and say why

A useful framework separates three cases. Restrict AI when independent competence is what you are measuring. Scaffold it when bounded help does not compromise that competence. Require it when skilled human-AI collaboration is itself the thing students must learn. Most courses contain all three, in different weeks, which is why a single course-level rule keeps failing at the edges.

The mixed-methods study of 85 student teachers shows what a rule without a reason produces. 62.4% of the sample declined to use generative AI even where it was permitted, and 41.5% of those who declined cited

fear of being accused of plagiarism. 9 of 11 interviewees read the permissive policy itself as a trap. In the same study only 37.6% used permitted generative AI at all, their choices tracked program culture and assessment design more than any one course's permission, and their own disclosure declarations under-reported actual use in every course.

Read those numbers as a design brief. A permission with no stated purpose looks like a setup, and a prohibition with no stated purpose looks like an obstacle to route around. What students respond to is the reasoning attached to this task. Put the rule in the assignment sheet, one line, and make the line specific enough that a student can tell whether the help they are about to accept undercuts the thing you are grading.

Grade something the student made without the tool

This is the step that does the work, and the evidence here is the least ambiguous on the page.

The 72-study review found generative AI reliably raised short-term completion and cut time on task in 36 studies, which the authors treat as the best-replicated result in the corpus, and those efficiency gains "do not transfer to independent performance" in 21 studies. A think-aloud study of 38 undergraduates shows how that happens in the ordinary case. Cognitive offloading is hardest on learning when the AI performs the reasoning the student was supposed to practice. There, 76.32% stayed in a single-turn ask, answer, stop pattern, and only 21.06% alternated AI use with independent reading and drafting. The largest group, 31 of 38, described mastery goals, worked in fragmented single turns, and then reported overreliance, mental complacency, and fast forgetting; one of them put it as "the speed at which you forget it is also very fast." A 2026 framework paper gives the pattern its name. Grades and products rise while the mental work that produces durable learning falls.

The randomized trial settles the argument for at least one setting. A three-arm RCT with 275 CS1 students compared a hint-giving tutor that withheld full solutions, unrestricted ChatGPT, and traditional web resources. Exercise scores separated sharply: 71.84% for ChatGPT against 29.85% for the no-AI control, with the hint-giving tutor at 57.50%. Conceptual knowledge gains did not differ at all across the three arms, at 0.83, 0.71 and 0.85 points (time × group $p = .773$). Both AI conditions cut frustration and extraneous load, and only the hint-giving tutor raised intrinsic motivation. The tool students rated as more helpful and easier was also the one that most reduced the processing that produces learning.

Note what that design cannot support. It is one course, one semester, one language, and the exercise scores are assisted performance by construction, which is precisely the measure the study warns against trusting. It does not show that tutors are useless. It shows that the outcome you choose to measure decides the answer you get, and that students' preference is not a learning measure.

So grade the unaided version. One task per unit where students retrieve, explain, solve, or defend ideas with no AI present, and put real points on it. The validity argument behind this is in assessment validity: a polished take-home artifact no longer shows that the person who submitted it has the competence the artifact displays. How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? works through the full architecture, including the cheap authenticated step for large courses.

Change the assignment you already have, not the whole course

Most instructors who ask this question are not building a new course. They have a term paper, a lab report, or a problem set that has worked for years, and they want to know where to put the seam. Take the assignment apart step by step, ask of each step what you are assessing there, and let the answer set the boundary. That is the task-level method documented in McCorkle's aligned course policy work, and one pass over your most contested assignment is usually enough to see the shape of it.

A ten-page term paper typically separates like this. Topic selection and source retrieval are where the judgment lives, so a tool that proposes a thesis or assembles the reading list has performed the part you are grading. Synthesis and argument are the construct itself. Citation formatting, reference checking, and language editing are steps where tool use is invisible to your construct, and forbidding it there buys you nothing except resentment. Say that in the assignment sheet, step by step, in a short table if you like.

Then make the middle step visible. Ask for a one-page annotated rationale, submitted with the paper, that names two sources the student rejected and why, one claim they revised after checking, and where they chose not to follow a suggestion. Grade it against the same specificity you use for the prose. A rationale carries weight only if a student who skips it loses more than they gain by skipping it, so give it enough points that the arithmetic is obvious.

A problem set is easier and the seam sits in a different place. The answers are not the construct; method selection and error diagnosis are. Require the first step of each problem, in the student's own words, before any tool is opened, and run one problem of the set in class with nothing available. That is a smaller change than it sounds, and it converts the set from a product you cannot verify into a record of how the student thought.

For a lab report, the seam is usually the data interpretation and the error analysis. Let the tool format the table and check the units. Keep the interpretation, the choice of what counts as anomalous, and the explanation of disagreement with the expected result in the student's hands, and grade those with points attached.

The pattern generalizes: locate the step where the capability lives, protect that step, free the rest, and put the evidence of process where the points are. What you are avoiding is the redesign that changes how work is produced without changing what the grade can support.

Judge feedback and grading tools by later performance

AI feedback can be timely, specific, scalable, and acceptable to students, including in higher education. Whether it teaches depends on accuracy, pedagogical fit, and students' feedback literacy, their ability to judge feedback and act on it. If you are weighing it for feedback or marking, the numbers below are the ones to bring to the procurement conversation.

A critical analysis of 14 institutional guidance documents found that generic prompts produce outcomes, activities, and assessments in isolation. The tool cannot know how interconnected a topic is, so its feedback stays general instead of diagnostically precise.

Configuration does move quality, measurably. In a study of AI feedback on learning goals, the model alone explained 26.9% of the variation in feedback quality and adding the prompt raised it to 42.8%, an extra

15.9%. The one prompt feature that mattered was subject-specific terminology; swapping it for everyday paraphrases made feedback significantly worse. Model choice mattered as well: Claude 3 and Gemini Advanced produced significantly lower-rated feedback than ChatGPT-4.

Marking is shakier still. A comparison of 18 language models grading 6,081 programming submissions found average grades from 0.290 to 0.608 depending on the model, with exact-agreement rates as low as 0.20 for some and 0.74 at best. Two students with identical work can be marked differently depending on which model the department licensed.

Then there is the question students care about, which is whether the feedback changes what they can do later. A semester-long deployment in an undergraduate mathematics course with 343 English and 236 Dutch students generated individualized comments and practice exercises from photographed answer sheets. Reviewers rated the practice exercises strongest and diagnostic specificity and clarity weakest. The randomized crossover on linked exam questions found no statistically significant difference after adjustment ($p_{Holm} = 0.104$), and attendance tracked exam scores far more clearly than feedback exposure did ($\rho = 0.49$ and 0.54, both $p < 0.001$). Feedback that students value and act on is not the same as feedback that produces measurable learning.

There is a further trap if you let a model grade. In a study of 1,426 psychology dissertations spanning ten academic years, all four AI graders scored student-written work lowest and AI-written work highest. 10 of 16 comparisons were large enough that differences of that size are rare in education research, up to the largest gap observed, and the bias was strongest for fully AI-generated text. A grader can reward text for being machine-like even when its instructions say to judge content.

Separate the students the design helps from the ones it drops

An average improvement can hide a course where the strong get stronger and the weak get a worse deal. The digital divide now runs along at least three lines: access to tools, skill in using them, and who actually gets a useful result. Prompting skill alone produces a “prompt privilege” in which more experienced users get better output from the same system.

The 72-study review separates two mechanisms. A skill gap appears where students with stronger prior knowledge convert help into durable gains while under-prepared students substitute it for practice. A resource gap appears where reliable internet and paid access sustain better tool use across institutions. Only six studies in the corpus directly examined equity, which the authors treat as the problem rather than a footnote; equity in AI education is where that argument is developed.

Help can close a gap when the students who need it are the ones who engage. A four-experiment study of learners discovering hidden rules with an AI agent’s help found the aid cut moves needed by 33-52%, and the benefit concentrated in the weakest performers while stronger learners were largely unaffected. That is the hopeful version, and it depends on the students who most need the help being the ones who use it well, which the skill gap suggests they will not manage without teaching.

Keep the consequential calls with a person

Faculty AI literacy is not where the policy conversation assumes it is. Among science teachers who had already completed AI training, average AI literacy was 16.7 out of 30, below the reference sample’s 18.79,

and it was unrelated to age, gender, years of service, or how much they had used AI. A survey of 412 prospective mathematics teachers found readiness at an early stage, with teaching beliefs highest at a mean of 5.24 on a 7-point scale and technical AI knowledge lowest at 4.23.

That is an argument for bounded tools, not autonomous ones. The guidance-document analysis proposes an institutionally configured retrieval-augmented agent that guides thinking without supplying answers, flags misalignment, and escalates to a person at the edges, with authority described as “derivative and bounded”. There is direct evidence for keeping people in the loop rather than in front of it: a course-material generation system scored better when people stayed involved, with the mode carrying the most human input improving reviewer scores by 0.5-0.9 points over the fully autonomous mode. Its autonomous reviewers clustered tightly around 2.9-3.1 while human evaluators spread out and discriminated more, so the authors kept human judgment as the primary quality signal.

The practical version for a course: let AI draft, sort, and flag. Keep accuracy, fairness, privacy, and any decision about a student’s progression under meaningful human oversight. The risks that make this necessary are the familiar set: bias, privacy, transparency, learner autonomy, accountability, and pedagogical safety. That list is why pedagogical AI competence matters more than technical familiarity.

What instructors get wrong about this

“The polished work in front of me is evidence the student can do it.” It is evidence that the work is polished. The 71.84% against 29.85% spread on exercise scores, with conceptual gains flat in the same trial, and the 36 studies in the review that found efficiency without transfer, all describe the distance between assisted performance and capability. If the artifact is the only thing you grade, the artifact is all you have measured.

“If the AI is a tutor, it is on the right side of the line.” The label does not carry the guarantee. In the CS1 trial the hint-giving tutor avoided the damage that unrestricted ChatGPT did on exercises, and still produced no conceptual advantage over no AI at all. Withholding the final answer is not the same as withholding the reasoning, and a tutor can do the second while appearing to do only the first.

“A detector, or a stricter rule, solves the integrity problem.” Detection addresses one response out of several. The student-teacher study found that fear of accusation suppressed permitted use, that program culture predicted behavior better than any course policy, and that self-declarations under-reported use in every course. A stricter rule changes what students conceal, not what they learn.

“One course-wide AI rule is fairer and simpler.” Simpler, yes. The evidence favors rules set per assignment, because the three cases, restrict, scaffold, and require, coexist in most courses and the same permission means different things in a lab report and a reflection. Blanket positions are also the ones students route around most easily.

“Students who say the tool helps are learning from it.” Satisfaction is a self-report measure, and in the CS1 trial the highest-rated condition was the one that most reduced the processing behind learning. The mathematics deployment found the same split: feedback students valued, no significant exam difference.

“AI literacy is prompt skill, and students pick it up by using the tool.” Frameworks treat AI literacy as conceptual understanding, operational skill, critical evaluation, ethical judgment, and awareness of limits. The review is explicit that prompt engineering, output verification, and analyzing AI errors are teachable

skills that do not develop through exposure. The trained science teachers scoring 16.7 out of 30 are the empirical version of that claim.

“The equity problem is access.” Access is one of three lines. Skill and who gets a useful result are the other two, and only six studies in the corpus examined any of it directly. Handing every student a license settles the easiest third.

What will come back at you

“My students say AI helps them.” It usually does help with the work in front of them, and the finding is about what remains after. Ask what they can still do unaided and you get a different answer, which is the reason the unaided graded step exists.

“I teach 200 students. I cannot read drafts or run oral checks.” You do not have to read everything. One in-class application or a short recorded explanation in the highest-stakes assignment, plus a sampled check on work that looks inconsistent with earlier submissions, covers most of the risk. Staged submissions, annotated rationales, and process portfolios scale; so does grading verification of a deliberately flawed AI output.

“Detection is all we have.” Detectors have documented reliability and fairness problems, and validity is the harder problem: a polished take-home product no longer shows that the person who submitted it has the competence. Process evidence is cheaper than an arms race and produces something you can defend in an appeal.

“Banning it is simpler.” Simpler, and it usually fails. Adoption in the student-teacher study tracked program culture rather than any single course’s policy, and disclosure under-reported actual use in every course. A ban also removes your ability to see how students would use the tool when they leave.

“I do not teach AI. This is not my subject.” The findings are about your subject. When AI performs the practice your course exists to provide, that is exactly when it interferes, and the interference shows up in your assessments whether or not you mention the tool.

“The evidence is too new to act on.” Partly true, and it cuts both ways. Much of the corpus is short interventions, self-report studies, single disciplines, or 2025 and 2026 work, and claims from mature Intelligent Tutoring research are stronger than claims about unrestricted general-purpose chatbots. Where a claim now has a randomized trial behind it, the performance and learning dissociation in the CS1 trial and the feedback result in the mathematics deployment, that trial is cited here. Where it does not, treat the finding as the best available guidance rather than settled law, and be most skeptical of results showing only satisfaction, task speed, output quality, or immediate assisted performance.

What to do this week

1. Pick the one assignment you are least comfortable defending. Write the capability sentence at the top of the assignment sheet.

2. Add one step that runs with no AI present: a five-minute in-class application, a short recorded explanation, or a paragraph written in the room. Give it real points.

3. State the AI condition for that assignment and add one line of reason. If the assignment mixes steps, say which steps are which.

4. Rewrite one prompt you give students from “solve this” to “give me one hint and ask me a question”, and tell them why.

5. Before the term starts, take the change to your program lead and to whoever approves accommodations, so the first appeal is not also the first conversation.

Where to go next

For the stakeholder-by-stakeholder version of these misunderstandings, see How Can We Address Common Misconceptions About AI in Education?. For the design requirements implied by the equity and human-judgment findings, see How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?. How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? takes the assessment half further, and Does Using AI Actually Help My Students Learn? is the evidence review behind the claims on this page. If you are choosing between redesign and enforcement, How Can I Reduce AI Cheating in My Course? and How Do I Write a Course AI Policy and Communicate It to Students? are the companion pages.

Connected FAQs

- How Can We Address Common Misconceptions About AI in Education?
- Does Using AI Actually Help My Students Learn?
- How Can I Reduce AI Cheating in My Course?
- What Competencies Do Faculty Need in Regard to AI?

How Can We Address Common Misconceptions About AI in Education?

Your provost wants a one-page “AI myths” sheet for the spring faculty meeting. Or a trustee has read that chatbots are destroying critical thinking and wants a position by Friday. Or you are the person who has to explain, in writing, why the department will not simply ban the tool, and you have run out of ways to say that a ban is not a pedagogy.

Every belief on this page starts from something a reasonable person has seen. Fluent prose does read as accurate. A polished submission does look like learning. A tutor that answers the question does feel like help, and a policy with the word “prohibited” in it does feel like a decision. The correction that works names what the observation cannot tell you, then hands over a check the person can run on Monday.

The answer to give a colleague, in one breath: the educational effect of AI depends on who uses it, for which task, what thinking the tool performs, what responsibility stays with the person, and how the learning gets evaluated. Confidence, speed, engagement, and task completion are features of use. None of them is evidence that capability changed.

The short version

1. Report what a learner can do with the tool closed, and label that measure as the one that counts.

2. Write the AI condition per task step, naming the act rather than the tool.

3. Judge a tutor, a feedback feature, or a platform by what the student does after it responds.

4. Buy evidence rather than capability claims: unaided outcomes, subgroup results, multi-turn safety tests.

5. When you correct a belief, replace it with a better model and an activity that lets the person see the old one fail.

Decide what counts as evidence that learning happened

Five beliefs decide whether the rest of this page matters. Each takes a real signal and reads a conclusion into it that the signal cannot carry.

“They did better with the tool open, so they learned more.”

In a field experiment with nearly 1,000 high-school mathematics students, unrestricted generative-AI access improved performance during assisted practice and reduced later unassisted exam performance. A guardrailed version that supplied hints instead of complete answers eliminated the observed learning harm (Generative AI Without Guardrails Can Harm Learning). Both results are real, and they sit on different measures: only one of them is the measure a transcript certifies. The study gives you a direction and no effect size for your course.

Students run the same inference on their own work, and the answer is the same: the product shows what the student and the tool produced together. Four questions asked with the chat window closed tell you what happened. Can they explain the reasoning? Solve a similar problem? Find the weaknesses in the generated

answer? Carry the idea into a new context? If the honest answers are no, you are looking at assisted performance under the name of learning. Put one of those four into the Assessment and say so in the rubric.

“Students like the feedback, so the feedback works.”

Satisfaction is evidence about acceptability. Students prefer feedback that is immediate, encouraging, detailed, and easy to follow, and a response can have all four properties while being inaccurate, generic, misprioritized, or aimed at a different objective than yours. The questions that decide it are dull and worth writing down: is it accurate, does it diagnose the actual problem, is it specific enough to act on, is it pitched at this learner, does the student use it, does the revision improve, does later independent performance improve. The last two are the ones a satisfaction survey cannot reach. AI Feedback Quality and Feedback Literacy carry the detail, and the practical move is to read twenty responses against your own objective before you scale anything.

“The average effect was positive, so the intervention helps students.”

Averages conceal exactly the variation that decides an equity question. Effects differ by prior knowledge, age, discipline, language, disability, metacognitive skill, access, instructor implementation, and type of AI use. A small average gain can hide a real benefit for one group and harm for another; a large one can depend on conditions your institution cannot reproduce. Ask for subgroup estimates with their uncertainty, for implementation fidelity, for what students actually did inside the tool, and for the attrition pattern. Limitations of the AIED Evidence Base and Research Methods in AIED set out the comparisons that get you closer, and Equity in AI Education explains why the subgroup table is the finding.

“They reported that they learned a lot.”

Self-report measures perception, acceptance, anxiety, and Self-Efficacy, and it is good at all four. It is not a measure of demonstrated capability, because people can be confident and wrong, or skilled and underconfident. The wiki’s synthesis of teacher AI-literacy research reports a substantial gap between Self-Assessment and measured performance, and the instructors in it overestimated their competence considerably (AI Literacy Assessment: Self-Reported vs. Performance Misalignment). Pair every self-report with a task: identify an error in an output, verify a source, choose a use strategy, spot bias or sycophancy, revise a flawed response, calibrate confidence against accuracy. One such item in a survey turns an opinion into a result.

“A simulated student is a cheap stand-in for a real one.”

Simulation is useful for prototyping, stress testing, and generating scenarios, and it is not evidence about human learning until it has been validated against people. A model can imitate the language of confusion without the persistence, motivation, prior knowledge, emotion, or developmental trajectory of a learner, and the research summarized in the wiki found simulated students abandoning an assigned misconception after minimal correction, which raises doubts about whether they represent conceptual change at all (Simulating Students, Simulating Students or Sycophantic Problem Solving?). Use them to find the flaws in your prompt before real students meet it, then treat any claim about learners as unvalidated.

Set the AI condition at the step that carries the learning

Rules fail when they are written about a tool and succeed when they are written about an act. The beliefs below are the ones that keep policies vague.

“Any use of AI is cheating.”

The mirror belief is worse: that AI use cannot be cheating because no person was copied. Integrity depends on the purpose of the assignment, the instructor’s rules, how much of the work the tool did, whether the use was attributed, and whether AI replaced the capability under assessment. Brainstorming is permitted in one assignment, required in another, and disqualifying in a third, and all three are defensible (Academic Integrity). The teaching move is to put five questions in front of students before they open anything: what is this assignment meant to show I can do, which assistance is allowed, am I still the author and decision maker, can I defend the submitted work, and do I need to disclose. AI Use and Disclosure Statements shows what a usable disclosure form looks like.

“If nobody can detect it, there is no downside.”

Detection answers a different question from the one that matters. Undetected outsourcing still leaves a student unable to explain the work, answer a follow-up, adapt it, or perform without the tool, and the gap surfaces later in a examination, a licensure process, an internship, or a first job. Grades drift away from capability while both look fine. That is a credential problem before it is a discipline problem, which is the argument in Assessment Validity and Authentic Assessment. For a student, the useful reframe is that the grade is a claim about them, and the claim has to survive the next room it is tested in.

“The problem is how often they use it.”

Frequency tells you nothing. A student can use AI daily to compare explanations, generate practice problems, and get feedback while staying cognitively active, and another can use it once to produce the argument the assignment existed to elicit. The question that sorts them is which layer of thinking was delegated and whether the student can still perform that layer alone, a distinction student-AI interaction documents in detail. Grammar correction sits far from the claims, evidence, and counterarguments of an essay. The move is to make the layer explicit in the task: name the thinking the course is teaching, permit help everywhere else, and check the named layer without help.

One study now measures the claim rather than asserting it. In a four-institution evaluation of a four-step protocol — AI explanation, then self-generated practice problems, then an independent attempt — post-engagement confidence in solving problems alone tracked the perceived value of the explanation ($r_s = 0.37$) and of the replicated practice ($r_s = 0.35$), while AI usage frequency carried no association at all ($r_s = 0.02$, $p = 0.749$) (Paul et al., 2026). Treat frequency as a variable you cannot act on. What you can specify is the sequence: what the AI does first, what the student must attempt unaided, and what gets checked afterward.

“Faster completion means more efficient learning.”

AI removes clerical work, formatting confusion, and repetition, which is a gain. It also removes the retrieval, planning, drafting, debugging, and revision through which the skill forms, which is the loss. The distinction that survives contact with a real assignment is supportive versus substitutive offloading: one frees attention for harder thinking, the other performs the thinking you were meant to learn (Cognitive Offloading, Reducing AI Misuse). A sequence that keeps the second from happening is short. Make an attempt, consult the tool for hints, examples, or comparison, revise on your own judgment, then produce a brief unaided explanation. Difficulty is not the goal; preserving the cognitive work is.

“A blanket ban is the safest and fairest rule.”

AI-free conditions are right when independent performance is the capability being assessed: certain examinations, foundational practice, professional competency checks. A universal prohibition is a different instrument, and it drives use underground, is hard to enforce consistently, and blocks the AI literacy students need after the course ends. Four task-level conditions cover more ground: AI required, AI permitted with disclosure, AI restricted to named functions, AI prohibited because assistance would invalidate the learning claim. Students follow boundaries they understand, so the rule needs its reason attached and has to match across the syllabus, the assignment sheet, the feedback, and the grading. Framing AI Use for Students and Educational AI Policy are the templates.

Judge a tutor by what the student does next

A system that produces the answer and a system that produces a learner are different products, and the output only ever describes the first.

“Give students a powerful tutor and learning will improve.”

Access is not an instructional design. The same model supports learning when it requires an attempt first, hints instead of solutions, asks for reasoning, corrects misconceptions, fades support, and ends with an unaided check. It undermines learning when it answers immediately, does the planning, and rewards answer-seeking. The value sits in the pedagogical wrapper, which is the argument in Learning Design and the design logic behind Scaffolding. Before you roll a tutor out, run one lesson through it yourself and count how many times it lets you avoid thinking.

“A tutor that gives the right answer is a good tutor.”

Correctness is necessary and insufficient. A correct answer can arrive too early, disclose too much, and bypass the desirable difficulties that make retrieval stick. A stronger tutor diagnoses before intervening, asks rather than tells, gives the smallest useful hint, requires an explanation, responds to the specific error, fades, and checks unaided performance later. Evaluate it on what students notice, attempt, explain, revise, and eventually do alone, which is the standard in Intelligent Tutoring Systems and Pedagogical Safety.

“More automation and personalization is better.”

Personalization can support learning and can become over-accommodation. When the system plans, monitors, decides what matters, and completes the hard steps, the student gets faster and less agentic, and self-regulation is the thing that quietly leaves the room. The design problem is to strip unnecessary barriers while preserving the effort tied to the objective. Features that hold up: mandatory attempts, explanation prompts, delayed hints, adjustable assistance, scaffold fading, reflection on the system’s recommendations, periodic unaided practice, and a visible way to override it. Agentic AI and Learner Agency cover what happens when the system starts making the decisions.

“A bigger model makes a safer tutor.”

General capability and pedagogical quality are separate properties, and a larger model can solve harder problems while still failing to choose a strategy, withhold an answer, match a developmental level, preserve productive failure, signal uncertainty, or stay inside your learning objectives. A participatory design study with six secondary teachers is the clearest statement of where safety actually comes from. The teachers independently designed “bounded experts”: narrow capability inside a defined domain under human supervision, with two lines they would not cross (authority, because responsibility for student learning cannot be delegated, and expertise, because the model lacks knowledge of individual students and classroom norms) and three protective layers (domain limits, filtered content with standardized refusals, and teacher override). They asked for full conversation logging and real-time alerts rather than better explanations from the model (bounded-expert chatbot design). Scope and oversight did the work that scale could not. Learning Theories and LLM Training and Fine-Tuning cover the design side.

“More feedback is better feedback.”

Volume is the easiest thing to increase and the least correlated with improvement. A response that comments on every issue can bury the one change that matters, and it can be mistimed, generic, or wrong. Feedback earns its length by identifying the most important next step for this learner at this point in the task. Measure whether students understand it, can judge its quality, revise with it, lose the misconception, and perform better later without it. Feedback and Feedback Literacy set out the sequence, and the practical test is whether a student can say in one sentence what they will do differently.

“AI is destroying critical thinking.”

It can replace critical thinking or become the object of it, and the assignment decides which. A task weakens engagement when students request a finished interpretation and accept it, and strengthens it when they predict before consulting, compare their reasoning against the model’s, hunt for unsupported claims, improve a weak answer, choose among alternatives, and explain why they rejected a recommendation. The useful distinction is the role the tool plays: coach, challenger, or source to be evaluated, rather than substitute for the learner’s reasoning. Critical Thinking and Learning Design carry the task designs.

Decide what a vendor must show you before you sign

This is where a misconception becomes a multi-year contract. None of the questions below require technical expertise, and all of them require asking before the renewal date rather than after.

“Buying an advanced platform will transform teaching.”

A platform provides capabilities. Improvement requires alignment across curriculum, assessment, faculty development, technical support, accessibility, privacy, governance, workload, and local evaluation, and without those an institution buys a sophisticated system that is used inconsistently, duplicates work, adds faculty burden, or produces an impressive demonstration with no measurable gain. Specify six things before procurement: the educational problem, the intended users and use cases, the outcomes that count as success, the data collected, the human oversight required, and the conditions under which you would modify or discontinue. AI from the Administrator Perspective and AI Ed Evaluation are the framings to take into the room.

“The benchmark score proves it is educationally effective.”

A benchmark measures performance under the benchmark’s conditions. A model can solve difficult problems, write fluent explanations, and score well on a tutoring rubric while failing to improve retention, transfer, self-regulation, or equitable outcomes. Keep benchmark results separate from technical reliability, pedagogical quality, safety, usability, implementation burden, classroom adoption, and unassisted learning gains. Only field testing with actual learners, a relevant comparison condition, and a sensible outcome measure speaks to the question you are actually deciding (Benchmark). Researchers owe the same discipline in the other direction: say which link in that chain a study occupies.

“It is reliable, so the scores are valid.”

Reliability is consistency, validity is whether the interpretation and use of the score are justified, and the two can diverge sharply. A large UK benchmark marked 761 authentic undergraduate psychology essays and found AI and human marks agreeing on the degree band only 35-65% of the time (63% at one institution, 53% at a second, 35% at a third), while re-scoring reliability was near perfect, with intra-class correlations up to 1.00. The three models agreed with each other far more closely than with humans (ICC 0.91) and concurred on the band for 56% of submissions when all three had to agree. Marks compressed toward the middle (compression score 0.47-0.82), so the system was least accurate exactly at the boundaries that separate a First from an Upper Second, or a pass from a fail. Its feedback ran three to eight times longer than the human average of 100-200 words (automated marking of university essays). Ask for construct coverage, comparison with human judgment, subgroup performance, error patterns, uncertainty, and the consequences of use, which is the argument in Educational Measurement and Automated Assessment.

“One well-behaved conversation shows the tutor is safe.”

Educational harms accumulate across an interaction. A system can answer one prompt appropriately and then, over turns, start supplying answers, reinforcing a misconception, encouraging dependence, or drifting

out of its tutoring role. The SafeTutors benchmark summarized in the wiki found pedagogical-harm failures rising sharply when systems were evaluated across multiple turns instead of a single exchange (AI Tutor Safety and Pedagogical Harms). Require sustained conversations, repeated student errors, direct-answer attempts, emotional and relational scenarios, adversarial prompting, and a measure of dependence over time. Benchmark evidence of this kind is not a classroom learning estimate, and it is the minimum a safety claim should rest on.

“Human review is a temporary patch until the models improve.”

Review is an accountability function, not an error-correction feature, because someone has to decide whether an output suits a particular learner, course, culture, or consequential decision, interpret the exception, supply the context the model does not have, and answer for the result. A meaningful arrangement names who reviews, what evidence they see, when review happens, how much time they have, whether they can override, who is accountable for the final action, and how a student appeals. A reviewer without time, authority, or information is a signature (Human-in-the-Loop AI).

“Accessibility, privacy, and equity can be added once the core product works.”

These are design requirements. Input modality, reading level, language assumptions, device requirements, data retention, personalization, and model bias decide who can use the system and who gets harmed by it, and retrofitting tends to improve the interface while leaving the workflow, data model, and decision logic intact. Involve affected learners and educators early, test with diverse users, collect the minimum, provide accessible alternatives, and examine differential outcomes. A system whose benefits are inaccessible or unevenly distributed is not educationally effective, whatever its average (Accessibility, Universal Design for Learning, Privacy).

“A chatbot is safe for children if it blocks toxic content.”

Content moderation covers prohibited words and topics. A polite system can still answer too quickly, reinforce a misconception, encourage emotional dependence, collect inappropriate data, offer developmentally unsuitable advice, make inaccessible assumptions, displace human support, and reduce productive effort. Child-facing products need evaluation for content safety, pedagogical safety, privacy, accessibility, relational influence, and the effects of repeated use, which is the standard in K-12 AI Education and Pedagogical Safety.

Decide what you will accept as proof of the student’s capability

You will never establish how a file was produced. You can establish, at low cost, whether the student can do what the file appears to show, and that is the only claim a grade needs to support.

“Experienced instructors can recognize AI-generated work.”

Not reliably enough to treat a suspicion as proof. Generated writing can be edited, blended with human writing, translated, paraphrased, or produced through several systems, and human judgment bends toward

writing style, language background, disability, and expectations about how a particular student should sound. Detectors share the problem and add both false positives and false negatives, which is why a flag is grounds for a closer look and never for a finding (AI Detection). Verification is the defensible alternative: ask the student to explain the reasoning, discuss the sources, revise a passage, apply the idea to a new case, or show process evidence. Every one of those assesses understanding directly, and each one is cheap.

“Detection and proctoring will solve the integrity problem.”

Detection estimates whether an artifact resembles machine-generated work. Education needs evidence that the learner holds the capability, and the numbers on the detection side are now specific enough to quote in a committee. A procedural-justice analysis reports that none of fourteen early detector tools reached 80% accuracy, that paraphrasing or light editing roughly halves already modest accuracy, and that the tools systematically misclassify non-native English writers, because the features read as AI signals also characterize competent second-language writing. In a covert field study, 94% of wholly AI-generated submissions injected into live online examinations across five psychology modules went undetected, and the AI work on average outscored the real students. Vanderbilt University disabled its licensed detector after failing to validate an advertised 1% false-positive rate, a rate that implies roughly 750 mislabeled students among 75,000 annual submissions (undetectable misconduct). Proctoring adds privacy, accessibility, anxiety, and equity costs without establishing learning either. The durable strategy is a combination: explained expectations, AI-free conditions where they belong, process evidence and staged work, oral or written verification, task-specific disclosure, assessment redesign, and human-reviewed procedures with an appeal route. Remote Proctoring and How Can We Reduce AI Cheating? take the operational detail.

“A polished work product demonstrates professional competence.”

It demonstrates the performance of a person plus a tool. Competence shows up in whether someone can frame the problem, state the assumptions, verify the evidence, catch a subtle error, adapt when conditions change, defend the recommendation, and perform essential judgment without inappropriate help. Responsible AI use is itself a legitimate professional competency, so the task is to separate effective tool use from the appearance of expertise the tool supplies (Career Development and Readiness).

“AI literacy means knowing how to write a good prompt.”

Prompting is one operational skill. The scope that matters for a teacher or an employee is broader: what AI systems can and cannot do reliably, how to evaluate accuracy and bias, how AI affects assessment validity, when offloading becomes displacement, the privacy and accessibility requirements, how use fits the discipline, and when not to use it at all. The wiki’s synthesis found teachers substantially overestimated their AI competence when self-reports were compared with performance measures, and demonstrated competence predicted classroom integration far better than confidence did (AI Literacy Assessment: Self-Reported vs. Performance Misalignment). Prompt techniques also age faster than judgment does. Teach Prompt Engineering as a skill and assess Teacher AI Competency as the wider one.

“Foundational disciplinary knowledge is obsolete because AI can retrieve it.”

Oversight depends on the expertise that heavy automation discourages people from building. Without domain knowledge a person cannot see the plausible wrong conclusion, the missing constraint, the dangerous recommendation, the invalid comparison, the fabricated citation, the biased assumption, or the situation where the tool should not be trusted at all (Prior Knowledge, Trust Calibration). Curricula can reconsider what gets memorized and which tools stay available. Removing the foundation because the tool can produce an answer removes the basis for judging the answer.

“Teaching critical and ethical AI use costs productivity.”

Unverified automation produces rework, security incidents, discriminatory decisions, legal exposure, reputational damage, and false confidence, and every one of those is a cost the productivity figure did not count. The employee worth hiring is the one who allocates work between people and tools while holding quality, confidentiality, accountability, and professional judgment. That is a productivity argument, made in the direction the balance sheet usually misses (Human-AI Collaboration, AI Governance).

Answer what students believe

Students arrive with working theories, and most of them were built from something the tool actually did. Correcting the theory is part of the teaching, and it takes a better model rather than a warning.

“If the answer sounds confident and detailed, it is probably right.”

Confidence and fluency are properties of generated language, not evidence of verification. The model predicts plausible text and does not check claims against evidence, so it can invent sources, misstate facts, drop context, and repeat a misconception in excellent prose. Treat the output as a hypothesis and inspect what the answer depends on: the sources, the calculation, the comparison with course materials. The test to teach is whether the student would accept the same claim from an unknown person who showed no evidence (Hallucination Risk).

“The AI understands me and knows what I mean.”

It responds to language, uses the conversation, and sometimes retains information, which is enough to feel personal. It has no intention, experience, care, or contextual understanding, and the practical consequence is that it may agree because the prompt suggested an answer. That is AI Sycophancy, and it is the failure mode students least expect. Ask it to name the weaknesses in the reasoning, offer counterevidence, and say what would make its answer wrong, then check independently. Agreement is not confirmation.

“One good prompt should produce the right answer.”

Output is prompt-sensitive and often non-deterministic, so small changes in wording, context, examples, or assumptions move the response substantially, and asking again is not verifying. Five similar answers can share one mistaken premise. Productive iteration clarifies the goal and constraints, exposes assumptions, requests alternatives, tests against evidence, and checks whether the answer survives a change in the

problem. This is a skill, and an unevenly distributed one. A demonstration of a naive student using a chatbot on a take-home examination question stayed “polished but pedagogically thin” at the multistructural level of the SOLO taxonomy, and reaching a usable learning loop took eight rounds of meta-level intervention: signaling overload, requesting simplification, narrowing scope. The authors call the capacity **AI-interaction literacy**, meaning the ability to steer, evaluate, and learn from iterative interaction, and they note the equity sting: because unguided use imposes an interaction-management skill that is unevenly distributed, generative AI “may be most beneficial to already advantaged students” (AI-interaction literacy). For the self-AI Regulation in Education demands underneath, see How Do We Develop an Effective AI Tutor?.

“Young people are already AI literate because they are digital natives.”

Familiarity with digital products is not the ability to evaluate AI. A student can open a chatbot, generate an image, and request an answer while being unable to verify a claim, spot fabricated evidence, detect bias or sycophancy, protect personal information, decide what not to delegate, or explain how AI shaped the work. The wiki summarizes research in which confidence with everyday technology did not carry over into algorithmic reasoning, technological creation, or critical evaluation of AI (The Illusion of Competence). Literacy gets taught and demonstrated; age and usage frequency do not confer it.

“Students who use AI are lazy or dishonest.”

Some misuse happens, and moral labeling explains little of it and prevents less. Decisions are shaped by assignment value, time pressure, confidence, peer norms, policy clarity, fear of failure, prior access, and whether the work looks connected to anything the student cares about, and students draw distinctions between brainstorming, editing, explanation, and full-text generation that a blanket rule erases. The response that changes behavior combines clear expectations, meaningful assessment, instruction in responsible use, a disclosure route, learning verification, and proportionate accountability. Treating all use as a character flaw pushes it into secrecy, where you lose both the information and the conversation.

Answer what families and the public believe

The questions from outside the building are simpler and the answers need to be shorter, because they will be repeated at a board meeting without the caveats.

“Will AI revolutionize education or destroy it?”

Both claims exaggerate what the technology does on its own. AI can widen access to explanation, translation, practice, feedback, and assistive support, and it can add misinformation, privacy risk, bias, over-reliance, and new integrity problems. Design, teaching, institutional decisions, and the responsibilities learners keep decide which list grows (AI in Education). The question worth putting to a board is narrower and answerable: for which learners, tasks, and outcomes, under what conditions, does this use produce more benefit than harm.

“AI is basically another calculator.”

The comparison works for one property, since both offload work, and it fails on scope. A calculator performs a defined operation; generative AI produces explanations, arguments, plans, source summaries, code, feedback, and whole assignments, its operation is far less transparent, and its output can be persuasive and wrong (Generative AI). That is why the delegation decision is more granular. Offloading routine computation can free a learner to interpret; offloading the interpretation removes the lesson.

“An empathetic AI cares about the student.”

The system can produce language that sounds attentive and supportive, and that can help a learner articulate a problem or persist through a low-stakes task. The appearance of care is not care, responsibility, or a duty of care, and a model can misunderstand the situation, reinforce the user’s framing, or respond badly while sounding kind (Conversational AI). Students should know when they are talking to a system, what is retained, and when it should send them to a qualified adult.

“AI will make teachers unnecessary.”

Automating tasks is not replacing the educational function. Drafting examples, producing preliminary materials, answering routine questions, and assisting with feedback can all move to a tool. Interpreting learner needs, building relationships, keeping a classroom intellectually and emotionally safe, contextualizing disciplinary knowledge, exercising ethical judgment, and deciding when a generated response is inappropriate stay with a person. The role shifts toward orchestrator, learning designer, disciplinary guide, and accountable decision maker, which is a change in professional work rather than its disappearance (Teaching).

What the people running this get wrong

The misconceptions above belong to the audience the page is written for. These belong to the people writing the memo, and they are why good corrections fail to land.

“Data-driven means objective.”

Bias enters through training data, labels, outcome definitions, prompts, language assumptions, accessibility choices, decision thresholds, and the way staff read the output. Human judgment is also biased, which is not evidence that automated judgment is neutral; automation can hide bias behind an interface and apply it at scale (Bias Mitigation). For consequential decisions, require subgroup performance analysis, documentation of training and validation conditions, uncertainty reporting, meaningful human review, an appeal process, post-deployment monitoring, and investigation of differential harm.

“One account per student solves equity.”

Equal access is the first of three lines. Students differ in prior knowledge, AI experience, language, disability access, device quality, available time, confidence, and capacity to evaluate output, and more experienced students use the tool to extend their learning while weaker or less metacognitive students accept wrong

output or delegate the practice they most need. Plan for access, then skill, then outcomes: who can use it reliably, who can use and evaluate it, who actually benefits and who meets a new harm (Digital Divide, Metacognition).

“One institution-wide policy will end the uncertainty.”

Policy text does not create shared understanding. Students and staff read expectations from institutional guidance, program norms, syllabi, assignment directions, instructor comments, peer behavior, and prior enforcement, and when those conflict people invent their own rules. The architecture that works connects institution-wide principles to program expectations, course policies, assignment directions, worked examples, and transparent disclosure and review procedures, with the educational reason attached to each restriction. A rule that says only “allowed” or “prohibited” leaves the judgment to whoever is most confident.

“Faculty reluctance is a training gap.”

Sometimes it is. Readiness is also workload, professional identity, disciplinary values, doubts about assessment validity, thin institutional support, privacy uncertainty, and a reasoned judgment that a particular application does not serve students. Development therefore has to cover practical competence, pedagogical integration, purpose and identity, time, policy, discipline-specific use, and the option of principled non-adoption. A one-time feature demonstration does not resolve a professional and organizational change (Educational Development).

“Telling people the correct facts is enough.”

Misconceptions are often stable, plausible mental models rather than gaps, and a person’s own experience keeps confirming them: the output sounds confident, the work looks good, the task finished faster. Facts that contradict a model with a working explanation attached get discarded. What replaces them is a better model plus a way to apply it, which is the refutation sequence in Refutation Text and the synthesis in Misconceptions about AI.

“Correcting someone means telling them they were wrong.”

Shaming produces defensiveness and concealment, and messages like “only lazy students use AI” or “anyone who trusts a chatbot is foolish” attack identity rather than belief. Address the belief and its consequences: acknowledge why it seemed reasonable, show a discrepancy such as a confident error, invite a prediction before revealing the correction, let people compare assisted and unassisted performance, give them a strategy for next time, and reinforce the new model across several activities. People revise their thinking more readily when revising it does not cost them dignity.

Replace the belief with a better one

The mechanics are short enough to use in a faculty meeting. Name the belief, say why it looks true, reject it plainly, explain the failure, give the better model, and hand over an application.

The worked version, which you can adapt to any item on this page:

> **Misconception:** “A good AI-generated assignment shows that the student learned.” **Refutation:** “That is not necessarily true. The product shows what the student and AI produced together, but it does not reveal which reasoning the student performed.” **Replacement:** “Learning is better demonstrated when the student can explain, transfer, adapt, and reproduce the capability.” **Application:** “Follow AI-assisted work with an explanation, oral defense, process record, or unaided application.”

The replacement carries the weight. Removing a misconception without supplying a better explanation leaves the person with nothing to think with, and the old belief returns the next time the experience confirms it.

Experiences do more than descriptions. The ones that change a belief are the ones that make its failure visible: ask people to find a confident fabricated citation; compare several contradictory answers to one prompt; complete an unaided problem after assisted practice; watch the model mirror an incorrect assumption; compare a direct-answer tutor with a hint-based one; audit outputs across names, dialects, or scenarios; defend an AI recommendation using original evidence. Each turns a warning into something the person saw happen, and each gives practice at verification, Trust Calibration, and the offloading decision.

What will come back at you

“We already bought the detector, and the license is not refundable.”

Then use it as one signal inside a process that can survive an appeal, and budget for the error rate rather than pretending it away. At the false-positive rate Vanderbilt could not validate, 1% of 75,000 submissions is 750 students mislabeled, and the procedural-justice analysis says the tools misclassify non-native English writers. A detector score is an allegation. A recorded explanation is a record.

“Our students would never do that.”

The 94% undetected result came from submissions injected into live online examinations, which is not a story about villains. Most of the pressure is ambiguity and time, and the practical question is which path your assignment makes easiest. If verification is graded, disclosure costs nothing, and an unaided check exists, most students take the path you built.

“The vendor showed us a benchmark and a happy case study.”

Ask what the benchmark measured and whether any student learned anything with the tool closed. A tutoring rubric score and a classroom learning gain are different claims, and a pilot without a comparison condition cannot tell you which one you have. The same skepticism applies to your own dashboard.

“Teachers just need more training.”

Teachers substantially overestimated their AI competence when self-report met performance, so training has to be assessed by what people can do rather than by what they say they know. It also has to cover purpose,

workload, and the option to decline, or the people with the most standing to resist will be the ones who understand the problem best.

“Parents will accept nothing but a ban.”

Parents are asking whether the thing in front of their child is safe and whether the credential means anything. Answer those two directly, with the pedagogical safety questions rather than the content filter, and the ban argument loses its force. The board question is narrower than the headline and easier to defend.

“We cannot run oral defenses for a lecture course this size.”

Then do not run one per student. Explain the reasoning in writing, discuss sources in a short recorded note, revise a passage, apply the idea to a new case, or read the process evidence you already collect. Sample the submissions that look inconsistent with earlier work. Verification is a habit built into the course, not a separate event for every student.

“None of this is our subject.”

The interference happens inside the discipline, at the step where the tool performs the practice the course exists to provide. That is why the response is an assignment change and a policy sentence rather than a new unit on AI.

What to do this week

1. Take the three beliefs you hear most and write each one as a refutation: the belief, why it looks true, the correction, the replacement, the application. One page, no citations.

2. Add one unaided item to an Assessment you already run, and give it enough weight that the result means something.

3. Rewrite one course’s AI clause so it names the act and the step, and pick one of the four conditions for each stage of the assignment.

4. Before the next renewal or pilot decision, ask for one subgroup table, one multi-turn safety log, and one unaided outcome measure. If any of the three is missing, say so in writing.

5. Run one twenty-minute activity that makes a misconception fail in the room, using a fabricated citation or two contradictory answers to the same prompt.

Where to go next

Misconceptions about AI is the synthesis behind this page, and Refutation Text is the method for using it in front of a room. How Can We Reduce AI Cheating? handles the integrity decisions, How Should Assessment Be Redesigned for the AI Era? handles what a grade can support, and AI Ed Evaluation is the guide for judging a pilot or a platform. On the teaching side, Teacher AI Competency and AI Literacy cover what the people in the room need to be able to do.

The idea to keep, in the form you can say out loud: AI is a fallible cognitive resource, not an authority, not a mind, and not evidence that learning happened. Responsible use keeps a person accountable, preserves the thinking the learning requires, verifies what matters, and judges success by durable and equitable capability rather than by fluency, speed, engagement, or a finished task.

Connected FAQs

- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?
- How Can I Reduce AI Cheating in My Course?
- Should We Use AI Detectors?
- What Are Best Practices for Writing Instruction in the Context of AI?

Course and institutional policy

For instructors writing the rules students will read, and for administrators and faculty developers setting them at program level.

How Do I Write a Course AI Policy and Communicate It to Students?

Three weeks before term, the syllabus template has a line for “AI policy” and it currently reads: see university academic integrity rules. Or a colleague’s course came back with a run of submissions nobody thinks were written in the room, and Thursday’s program meeting ends with a request that every course state its position in writing. Or the policy is already written and the marking period is showing you which of its sentences you can actually apply.

The bottom line: name the tasks you grade, say what AI may do at each one, put the declaration in a single place, and enforce with evidence you can see. Five specific permissions hold better than a page of prohibitions. A policy that explains itself does assessment design and communication work at the same time, which is why it costs an afternoon and saves a semester of arguments.

Everything below is the course-level document for one module, course or program strand. The assumption is that you have decided what you are assessing; the work here is saying so and making it stick.

The short version

1. Inventory the graded tasks and ask of each one what, specifically, you are assessing. The boundary follows that answer.

2. Write the rule at the level of the step: brainstorming permitted, composing objectives not. Image curation permitted, slide-level message design not.

3. Put the summary on the syllabus, the operative wording on the assignment sheet, and say the rule out loud once at the moment it first applies.

4. Name one standard place and form for disclosure, and keep the cost of declaring lower than the cost of hiding.

5. Enforce with work you can observe: a prompt log, an in-class exercise, an oral account. Detector scores stay outside the enforcement path.

Start from the tasks you grade

The clearest worked method is McCorkle (2025), who was replacing a blanket prohibition that students did not believe applied to them. Read that failure correctly: it was misalignment rather than defiance, and the students did not see themselves as behaving dishonestly. A rule they have already decided is not about them cannot be argued with, only ignored.

McCorkle’s method runs in four passes. Inventory every task in the semester project, ask of each “what, specifically, am I assessing?”, pair each task with a plausible professional use of generative AI, then decide task by task. Each decision weighs the need to assess a capability against the value of building a competency the student will use at work.

The output is deliberately uneven. Brainstorming is permitted; composing specific and measurable learning objectives is not. Image curation is permitted; slide-level message design is not. Scripts and narration are

permitted, with required evaluation of the AI output. Written out, that list looks arbitrary until you read the reason beside each line, which is why the reasons travel with the rules.

Decide how strict to be, knowing what everyone else does

Two data points tell you what a normal policy looks like this year, and both are worth carrying into the meeting where someone proposes a ban.

A content analysis of **116 institutional GenAI policies** from 131 US R1 universities and **98 computer-science syllabi** from 54 of them found institutions broadly pro-use: 63% encourage GenAI use, 41% offer detailed classroom guidance, 27% discourage it. Half the syllabi (50%) outright prohibit it, 41% permit partial use for specified activities, and 7% communicate encouragement. Ganguly et al. (2026) call this the top-down versus bottom-up gap. 92% of syllabi give explicit guidelines, yet local rules drift from institutional guidance, and only 47 institutions had both levels detectable. Citation is the one requirement both levels agree on, at 83% of syllabi.

Chirikov (2026) tracked over 31,000 syllabi at a large Texas public research university from 2021 to 2025. Regulation rose from near zero before ChatGPT to 55% of courses by Fall 2025, while fully restrictive policies fell about 5 percentage points a year. By Fall 2025 instructors most commonly restricted drafting and revising (79%) and reasoning and Problem Solving (65%). They most commonly permitted editing and proofreading (83%), study support and synthesis (80%) and coding (75%). Ideation was the most contested use, at 46% permit and 54% restrict.

The wording moved with the numbers. Academic-integrity mentions fell from 63% to 49%, references to AI's effect on learning rose from 1% to 29%, and attribution requirements rose from 16% to 43%. The field is shifting from "do not cheat" toward "here is why this boundary protects your learning," and the second version is the one a student can act on.

Two consequences for your document. Being stricter than your institution is normal, and it is a commitment you take on alone, because the enforcement cost lands on you. A citation requirement is close to free, since four fifths of the field already asks for it and no student has to guess what you mean.

Put each rule where the student will meet it

Three documents, three jobs.

The syllabus carries the short summary: the tasks, the permitted use at each, how disclosure works, and the consequence of a crossed boundary. One screen, no philosophy.

The assignment sheet carries the call-out. A single summary is too coarse for a complex project, and this is where McCorkle's wording did its work, in a rationale addressed to students in the second person that named the assessment behind each restriction.

The room carries the first oral statement. Say the rule once, at the moment it first applies, tied to the work in front of them. A rule a student meets alone is a rule they interpret alone.

Disclosure mechanics need their own paragraph, and it should be the most concrete one on the page. Students who co-designed a course policy through guided inquiry prioritized training for students and instructors, **standardized disclosure procedures**, stronger institutional support and greater involvement in

decisions about AI (Hingle and Johri (2026)). Say how, where and in what form a student declares use, and say it once.

Pisan (2026) found a stronger version of the same move: make the prompt log the graded artifact. When a model does the production, the prompt and the interaction record are the thing worth versioning, so the declaration stops being paperwork and becomes evidence the student is building.

Write only rules you can apply in one marking cycle

A rule that needs per-task monitoring, or a judgment about when an assessment "begins," will be applied inconsistently across a class and across two markers. Inconsistency is an equity problem before it is an administrative one. A regime built on detectors adds a surveillance cost that lands unevenly, along with proctoring and data-retention questions you may not be able to answer at course level.

Nash and Burriss (2026) analyzed 27 classroom AI policies written by preservice English language arts teachers. **26 of 27 permitted some AI use**, almost always on teacher-specified terms, times and places; one prohibited it entirely. Ideation was the most broadly permitted use (22 of 27) and the most ambiguous. 22 disallowed or left unclear the AI composition of sentences, paragraphs or papers. 16 permitted grammar checking and proofreading while 16 prohibited producing large AI-generated text. And **22 of 27 did not address reading at all**.

The recurring failure was operationalization. One policy allowed AI "to get your thinking started" and declared "this is where the line should be drawn" without saying where the line was. That ambiguity leaves students unable to comply and you unable to apply a consistent standard. It is a defect, not a compromise.

Chirikov's finding of substantial disciplinary and task variation argues for frameworks that grant instructors autonomy within their own domain rather than one mandate for everyone, which is also the honest description of what a course policy is: a local judgment inside a wider rule.

There is an equity dimension here. Opaque policies assume shared background knowledge about authorship, attribution and the norms of academic work, so they fall hardest on students who arrive without it. McCorkle's case is that transparency dismantles part of that hidden curriculum and lowers the chance a policy failure becomes a disciplinary matter.

The cheapest version of all this is few and specific: the tasks you assess, the uses permitted at each, the disclosure mechanics, and the consequence of a crossed boundary, each with its reason attached.

Say it out loud, and watch what you model

Disclosure rules do not work as compliance mechanisms on their own, and treating them as if they do is the most common design error. In a mixed-methods study of 409 undergraduates, Qu and Wang (2026) found non-disclosure was **strategic adaptation to perceived peer norms and low interpretive Trust in instructors** rather than moral negligence. Perceived peer disclosure and comfort with the instructor were the strongest predictors of students' own disclosure; moral disengagement had weaker effects.

That leaves you two levers you actually control: what students believe their peers are doing, and whether they trust you to read a declaration fairly. Both respond to how you talk about the rule in the first week. Neither responds to the severity of the wording.

Kim et al. (2026) found **five distinct sites** where a course's real policy lives: faculty intention, formal policy, student interpretation, student self-policy and student practice. The gaps between them are systemic. They also catalogued **23 rationalizations in six classes** that students used to justify AI use in academic writing, from "no human victim" to "instructor indifference." Those rationalizations were ad hoc and post hoc: students explained behavior that had already happened rather than reasoning beforehand, which is why clearer wording and harsher detection do not close the gap by themselves.

One participant who wanted to obey a strict no-AI rule kept using AI and said the prohibition "is creating conflict for me, because I'm breaking the rules." The ban intensified moral conflict without preventing use. A rule that produces guilt without compliance is eroding the relationship you need for disclosure.

Watch what you model, too. Most assignments in Pisan's course disclosed the prompt used to generate them, and one student read that transparency as **permission**: "the dependency on ai from the teacher for grading and creating assignments also made it difficult to not use ai for assignments in the same way." Modeling a norm is part of the policy as students experience it, whatever the syllabus says.

A statement you can adapt:

> **AI use in this course.** I want you to leave this course able to do X yourself, so I assess X directly. You may use AI for [permitted uses] on [task list]; you may not use it for [restricted uses], because those are what I am grading. If you use AI anywhere in your work, tell me in the [single named place, such as a disclosure line on each submission] what you used it for and paste the prompts. Declaring it will never lower your grade. Failing to declare a use is the thing that carries a consequence. If you are unsure whether a use is allowed, ask me before you submit, not after.

That last sentence moves the decision point to before the work, which is the only point at which the question is cheap to answer.

Plan for the four conversations before they happen

The student who used AI and did not say so. Handle this as a process question, not a character question. Mohamed and Temimi (2026) model assessment as a problem of imperfect information: the student knows how the work was produced, and the institution sees the artifact plus partial traces. Their response-region model compares three responses, no AI use, disclosed use and hidden use, and asks which one each mechanism makes most attractive. Prohibition sets the formal boundary and leaves hidden use attractive when students see detection as weak. Monitoring raises the expected cost of hidden use without raising disclosure, so students become cautious without becoming transparent. Permission with disclosure makes honest reporting viable only while the cost of honesty stays low.

In the room, that means asking what the work was meant to assess, asking the student to account for their process, and reading a late declaration as information rather than a confession.

The student who cites AI for everything. This is usually a skills gap in a compliance costume. Attribution requirements rose from 16% to 43% of syllabi while academic-integrity mentions fell from 63% to 49%, so the field is asking for citation rather than confession. Specify the format once, on the assignment sheet rather than in a syllabus footnote. State what adequate attribution looks like in your discipline and give one worked

example. Where the real problem is that the student cannot yet do the underlying work without the model, the answer is the task design.

Group work. Five students can hold five interpretations of one sentence, and one submission gets graded. For each group deliverable, decide and publish whether AI use is permitted, who declares it, and what happens when one member goes outside the rule. Do that before the project starts, while it is a planning question. If you cannot state the individual contribution a member is accountable for, grade the task as group-only work rather than adjudicating authorship after the fact.

Disclosure you cannot verify. Some declarations will be incomplete and some omissions unfalsifiable. Bassett et al. (2026) argue AI detection should not be used in education at all, on three grounds that bear on wording. Detector output is a probabilistic estimate that cannot be independently verified, because real-world text origin is unknown, so validation runs on circular reasoning. Detector scores do not meet the balance-of-probabilities standard an integrity investigation requires. And the human-versus-AI dichotomy is meaningless for work created with rather than by AI. Their conclusion is that detection "does not safeguard academic integrity; it undermines it."

They flag a drafting problem worth copying into your revision pass. Rules restricting AI use "in assessment" fail to specify when an assessment begins, so AI-assisted research, planning or editing may or may not be a violation depending on who is reading. Name process evidence you can observe instead: a submitted prompt and interaction log, an exercise produced in the room, an oral explanation. Where your institution runs a detector anyway, their warnings about data storage, retention and commercial use of student work apply, and the Privacy objection two preservice teachers raised is the objection your students will raise.

What instructors get wrong about this

A stricter policy is a safer policy. Being stricter than your institution is common and defensible, but the enforcement cost is yours, and a rule you cannot apply consistently across a marking cycle is an equity problem. Cut the rules you cannot run.

A ban is the shortest message available. In the 27 preservice policies, the ambiguity sat mostly in the permissive ones, and 22 of 27 never addressed reading, so students were left to infer. Kim et al.'s participant obeyed a ban by breaking it and feeling bad about it.

Disclosure is a compliance mechanism. It is a signal, and signals depend on trust. Qu and Wang found peer norms and comfort with the instructor predicting disclosure better than moral reasoning did.

A detector score settles a disputed case. It does not reach the standard an integrity investigation has to meet, and it cannot distinguish work made with AI from work made by AI. Build the case on work you observed.

Writing the policy is the communication. Kim et al. found five sites where the real policy lives, and your document is one of them. The version students act on is assembled from what you say in class and what you do with your own materials.

What will come back at you

"Students will just hide it." Some will, and the design question is which students your rule tempts. Deterrence runs through a detector's **discrimination** between hidden use and legitimate work rather than its

raw catch rate. When extra sensitivity produces more new false positives than new true positives, **stronger monitoring can make concealment relatively more attractive**, because honest students are penalized faster than hidden users are identified. Permission and disclosure are separate levers: permission moves the boundary of acceptable use, disclosure changes visibility. Diagnose where your task pulls the student most tempted to conceal, and design for that student.

“I do not want to ban tools I cannot detect.” You do not have to. Prohibition is one of four design responses, alongside monitoring, permitted use with disclosure, and redesign. Redesign changes what the task rewards, and stays cosmetic if the rubric still grades mainly the final product. Pisan (2026) shows the levels made explicit: AI is barred in the introductory programming course, because outsourcing the first loops removes the thing being taught; encouraged on projects in data structures (Copilot permitted) and barred from pen-and-paper examinations; a study and review aid in the upper-division systems course; and **required** in the AI course itself, where one boundary carried most of the weight. The model may write code, and reflections must be in the student’s own voice. Examinations were removed entirely, and assessment moved onto work a model cannot quietly ghost-write.

“My institution’s policy already covers this.” Less than you think. The gap runs both ways: 92% of syllabi give explicit guidelines, local rules drift from institutional guidance, and only 47 institutions had both levels detectable. Procurement, data and review cycles belong to How Do We Write and Implement an Institutional AI Policy?, but the classroom translation is yours. Nash and Burriss conclude that institutions must equip teachers to resist as well as adopt, with the guidance and professional development that let an instructor decline a specific AI use without being framed as behind the times. Their participants’ technodeterminism contradicted their own pedagogical commitments. An institutional policy is not cover for your judgment call.

“I do not have time to rewrite the syllabus this month.” Run the inventory once, on the assignment that worries you, and take the output straight into the assignment sheet. The syllabus sentence can wait for the next revision cycle. Students act on the assignment sheet anyway.

What to do this week

1. Inventory the graded tasks and write “what, specifically, am I assessing?” beside each one, before you decide anything about AI.

2. Decide task by task, and check which response each decision makes most attractive to the student most tempted to conceal.

3. Write the disclosure sentence: one place, one format, one worked example of adequate attribution.

4. Name the evidence you will accept in a dispute (prompt log, in-class work, an oral account), and drop any rule you cannot test against it.

5. Say the rule out loud in the next class, at the moment it first applies, with a rationale beside each restriction.

Where to go next

Governance, data policy, procurement and review cycles belong to How Do We Write and Implement an Institutional AI Policy?; mandated institutional and district rules sit with Educational AI Policy and AI

Governance. Rebuilding the task so a grade still supports a defensible inference sits with How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?, the enforcement argument is in How Can I Reduce AI Cheating in My Course?, the detector decision in Should We Use AI Detectors?, and the label scheme in ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform.

Connected FAQs

- Should We Use AI Detectors?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Do We Write and Implement an Institutional AI Policy?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

How Do We Write and Implement an Institutional AI Policy?

The draft has been circulating since the spring, and every operative sentence says “may.” Or a vendor wants a site license signed before the end of the quarter, and nobody on the call can say what the institution has agreed to about student data. Or a detector flag has become an appeal, and the policy that was supposed to settle it turns out to say nothing about what evidence an allegation can rest on.

What a committee can defend is narrower than most drafts attempt, and publishing is the smallest part of the work. Four things turn a document into a working rule: a named executive owner, a scheduled review, a translation path into courses with someone accountable for it, and a graded assessment design that rewards the behavior you are asking for. Add a scope sentence that says which obligations the document carries and which belong to another policy, because one document absorbing data protection, research Ethics, clinical regulation and academic conduct will be long, unread and unenforceable.

The short version

1. Declare what the document governs. If it is a risk-management instrument, say so, and put the teaching detail at department level.

2. Count the modal verbs. Each “may” where you mean “must” is a provision nobody can enforce.

3. Name an owner, a standing committee and a review date before publication, not after the first appeal.

4. Write down where FERPA, GDPR, HIPAA, IRB and research-integrity obligations live, and name the office that owns each one.

5. Fund staff training and student access in the same budget decision. Either one alone produces a rule some students cannot follow.

6. Ask how many courses detectably translate the policy, and read the answer as a support metric rather than a compliance metric.

Decide what the document governs

Before the wording, the scope. Manikonda and Outlaw (2026) crawled AI policies from 149 R1 and R2 universities in the United States and verified 130 university-level policies across 34 states. The register is advisory rather than directive: 95% of the policies carried a negative clarity-strength score, so weak language (“may,” “can”) dominates over directives (“must,” “prohibited”).

What those documents prioritize tells you what their authors thought the document was for. University-level policies cover data security, risk mitigation, procurement and legal compliance, with little pedagogical guidance. The school-level policies that exist concentrate on teaching and AI Literacy. Only eight business schools had a policy of their own, and those differed from their host framework in six of eight cases.

The remedy the authors propose is a layered structure: a university-wide risk-management layer, department-level policies, and inter-departmental committees with faculty and students. Adopt that and you get a scope sentence you can defend in the senate. This document manages institutional risk; the teaching decisions sit

with the department that grades the work. Layering also answers the charge of vagueness without producing 40 pages.

Write provisions that bind, or take them out

Look at what programs publish when nothing forces the question. Eldredge et al. (2026) scanned all 48 CAHIIM-accredited health informatics and health information management master's programs in the US. Forty (83%) published at least one AI-related document. Of the analytic sample, 21 documents (53%) were guidelines, 9 (23%) informational, and only 7 (18%) formal policies.

The subject matter was narrower than the volume suggests. Academic integrity was the most frequent keyword (n = 139), ahead of citation (59), Assessment (50) and plagiarism (38). Disclosure of AI and contract cheating each appeared once. HIPAA appeared five times, FERPA eleven, and electronic health records not at all. Equity vocabulary was close to absent: inclusion (n = 9), accessibility (n = 9), equitable access (n = 2).

That is attention without a binding commitment behind it, which is the cheapest defect to fix. Count your modal verbs and write a consequence where you mean one. Define plagiarism and prohibited uses in words a first-year student can apply. Then score the result against the instrument Gutowski and Hurley (2025) built: five dimensions with explicit rubrics, covering prohibitiveness, permissiveness, educational integration, transparency and accountability, and depth. Most institutions in their sector took generally prohibitive positions while reserving discretion to individual instructors. No single approach was accepted, and clarity itself was treated as the precondition for defensible enforcement. Their recommendations are procedural: comprehensive guidelines whatever your stance, stakeholders involved in drafting, proactive training, governance designed to flex, and review cycles.

Decide who owns it and who sits on the committee

Two reviews put the weakness in capacity rather than intent. Ashiq (2026) synthesized more than seventy UK sources and found that only a minority of institutions maintain official AI governance plans. Strategic planning gaps produce policy drift and performative compliance. National guidance from the Office for Students and Jisc has been criticized for lacking specificity and enforcement power. Staff AI-training and infrastructure investment concentrate in research-intensive institutions, while teaching-led institutions face capacity constraints, widening a digital divide. Baroudi (2026) reviewed 19 sources and found that 7% of institutions had created senior AI leadership roles against 49% treating AI as a strategic priority. Weak policy frameworks and limited digital infrastructure drive that gap, particularly in the Global South.

Ownership, resourcing and revision are where the effort has to go, so settle the chair and the membership before drafting starts. Crompton et al. (2026) convened a Delphi panel from 22 countries and locations across six continents and produced a consensus framework with eight core areas: academic integrity, ethical and responsible use, privacy and protection, equitable access, GenAI literacy, integration strategy, human oversight and accountability, and institutional support and infrastructure. The panel also produced a six-part mechanism for keeping policy current: a multidisciplinary governance committee (backed by more than half the panel), scheduled review cycles (half), professional development, communication with all Stakeholders, evaluation of effectiveness, and monitoring of external developments.

Read the framework as a coverage checklist and the mechanism as an operating model. The panel's own weighting is the warning. Ethical and responsible use was referenced by two-thirds of panelists and privacy by over half, while equitable access drew only one-third. A consensus process under-weights equity first, and your committee will drift the same way unless someone holds that item.

Two membership decisions are worth making deliberately. Hingle and Johri (2026) had students co-design a GenAI course policy through guided inquiry. The priorities that emerged were training for students and instructors, standardized disclosure procedures, stronger institutional support rather than reliance on individual instructors, and a role in decisions about the rules governing their own learning. That argues for student membership rather than a consultation round. Baroudi found empowering and distributive leadership styles associated with higher faculty engagement and openness to change, and documented Change Management machinery (Valente's contagion model, Rieber and Williver's five-stage framework) as the support for adoption.

Tan et al. (2026) offer a six-dimension organizational framework whose propositions the authors explicitly leave for future empirical validation. Use it to structure what the document covers, and keep it out of the sentence where you claim something works.

Put the legal obligations where they can be enforced

Compliance with baseline law is not ethical data governance. Varadaraju and Vijayakumar (2026) argue that Learning Analytics governance in higher education has stayed compliance-first, centered on meeting FERPA and GDPR, and propose the LEAGUE framework: Lawfulness, Equity, Agency, Governance, Utility and Ethics by Design, demonstrated against an early-alert case study. The Delphi panel independently ranked privacy and data protection as critical for over half its members. The OECD Digital Education Outlook (2026) makes an enabling environment for trustworthy GenAI its third policy pillar, covering Privacy, safety, bias testing and transparency.

The health informatics corpus shows what scope discipline looks like when it works. Those programs barely mentioned HIPAA, FERPA or IRB guidance and never mentioned electronic health records, because those obligations live in broader compliance policy that already has an owner, a procedure and a penalty. Name where each obligation sits, name the office that holds it, and require students to meet it in coursework rather than in a footnote.

That paragraph also settles a procurement question. If bias testing and transparency are pillar conditions rather than aspirations, they belong in the purchase terms, and the policy is the place to say so.

Close the gap between the policy and the courses

This is the decision most policies fail, and it is measurable from both ends.

The faculty survey first. The AAC&U/Elon survey of 1,057 US faculty (Watson and Rainie, 2026) found 87% had created their own policies for students on generative AI use, while 48% said their institution had written guidelines and 35% said their department had. On structure, 55% reported a task force or oversight group, 37% new AI-focused classes, 17% an AI major or minor, 16% new academic leadership offices, and 13% had adopted AI literacy as a general education learning outcome. The sample is non-scientific and the

authors say it is not generalizable. The asymmetry stands anyway: the rules students actually meet are written by the instructor in front of them.

Then the translation count. Ganguly et al. (2026) analyzed 116 institutional GenAI policies from 131 R1 universities alongside 98 computer-science course syllabi from 54 of those institutions. Institutions mostly encouraged GenAI use (73, 63%) while 31 (27%) discouraged it. At course level, 90 syllabi (92%) gave explicit guidelines, yet 49 (50%) prohibited GenAI outright, 40 (41%) permitted partial use for specified activities, and 7 (7%) communicated encouragement. Only 47 of the 131 institutions had both an institutional policy and a detectable course-level translation.

Put that question to your committee in those terms: how many of our courses detectably translate this document? A low number is a support failure, and the remedy is worked examples, faculty development and assessment support published alongside the rule. That support ecosystem is how Qian (2026) separates institutions from one another, and it is the difference between a policy students receive and a policy their instructor improvises around.

Coates, Croucher and Calderon (2025) supply the instrument for the accountability end: an academic integrity indicator framework built for institutional governors through research reviews, multi-institutional case studies, prototyping and expert confirmation, together with reforms to governance architectures, people and technologies. Indicators let a committee report upward without commissioning another literature review.

Write the evidence standard before you need it

Where enforcement fails, the failure is usually evidentiary, and this is where institutional exposure sits.

Munoz et al. (2026) analyzed actual generative AI misconduct allegation files. The evidentiary base was thinner than policy implies. System-recorded behavioral traces exist only in supervised assessment. Weaker process evidence, meaning drafts, supervision meetings and presentations, exists only where those practices were already routine. Natural justice requires that the student be told the allegation and given a chance to respond before any determination, usually in an investigative meeting or panel interview, with whatever they say entering the evidentiary record.

Detector output cannot carry that load. Hadra et al. (2026) measured accuracy of 0.69 and 0.61 for two widely used commercial tools, both failing on hybrid human-AI text, and both carrying a borderline misclassification risk for EFL student writing. Bassett et al. show that no threshold resolves the tradeoff between flagging honest work and missing concealed use. A finding that rests on a score nobody can interrogate is the case that generates the appeal, the complaint and occasionally the claim.

Three sentences belong in the document itself: what evidence a finding may rest on, that a detector score alone is not that evidence, and who decides when a case proceeds. Put the procedure beside the obligations collected in Legal Issues and Risks.

Say what you will measure before you publish

No study in this corpus measures whether an institution's AI policy changed student behavior, staff practice or learning outcomes. What exists is descriptive. Manikonda and Outlaw find policy language weak and misaligned. Ashiq documents drift. Baroudi names the absence of longitudinal and causal evidence as a gap.

Eldredge et al. caution that analyzing public documents creates a visibility bias, so missing privacy or equity language is a finding about published guidance rather than about practice.

Two habits follow. Attach an evaluation plan to the policy: what you will measure, when, and who owns the finding. And when a colleague cites another institution's policy as proof that a measure works, check whether the claim is about a document or about an outcome. Tran, Liu and Nguyen (2026) reviewed 65 peer-reviewed papers on AI and social-emotional learning and found nearly three-quarters mentioned no policy implications at all. Of the minority that did, most lacked the actor-specific detail real policymaking needs: who should act, on what, why, when and how.

What institutions get wrong about this

Publication is the finish line. The estate Manikonda and Outlaw mapped is broad and shallow, advisory in tone, and thin on the problems that decide whether AI use goes well. A document with no owner and no review date is a press release with a policy number.

Vague wording is the safe wording. It is safer for the person who signs it, and the weakest thing to defend in an appeal. Gutowski and Hurley treat clarity as the precondition for defensible enforcement, and 95% of the policies in the R1 register score negative on clarity.

Academic integrity is the hard part, so cover that and the rest can wait. Integrity is the easiest provision to write, which is why it dominates keyword counts while equity vocabulary, access and data obligations sit near-absent. The provisions an integrity code cannot reach include procurement, disclosure procedure, accessibility, staff training and the assessment conditions under which integrity is achievable.

One document can hold every obligation. It can hold them and enforce none of them. HIPAA appeared five times across 48 programs' AI documents and electronic health records never, because those obligations already belong to compliance policy.

Faculty will follow once it is published. 87% of faculty had written their own rules before their institution published one. The counter-measure is professional development, worked examples and distributive leadership. A reminder email moves nothing.

Students ignore policy, so clarity is wasted on them. Braun and Khafizov (2026) surveyed 1,809 students, 250 faculty and 62 administrative staff at one Teacher Education university. Students reported higher AI-use intensity and usefulness while faculty and staff reported stronger integrity concerns, and students reported higher perceived policy clarity than faculty did. What moves them is whether the tool is useful enough to be worth following a rule about.

What will come back at you

"We already have an academic integrity policy." It is necessary and not sufficient. What the evidence supports is division of labor: conduct rules stay where the integrity process can enforce them, and the AI policy carries procurement and data security, disclosure procedure, accessibility and access, staff training, and the assessment conditions under which integrity is achievable. The Delphi panel's insistence that significant GenAI outputs be reviewed by a human, and its preference for process-focused and oral assessment, has no home in an integrity code.

“Faculty will ignore it.” Some will, and the reason is rarely will. Ashiq’s evidence is capacity. Baroudi’s is structure: 7% of institutions had created senior AI leadership roles against 49% treating AI as a strategic priority. Ganguly et al.’s is translation: 47 of 131 institutions had both a policy and detectable course-level implementation. Faculty are being left alone with the document.

“We cannot police it, so the policy is decoration.” You cannot police it, and the evidence says you do not have to. Ogbo et al. (2026) model student AI use as a coordination problem in which cohort norms govern behavior, with threshold effects. Reflective assessment has to be rewarded above a critical level before responsible use displaces opportunistic practice, the reward has to be proportionate to the effort reflection demands, and peer sensitivity sets how fast a norm cascades. Students respond to assessment structures rather than to pronouncements. On Braun and Khafizov’s cross-sectional self-report data, perceived usefulness is the strongest standardized association with Trust ($\beta = 0.402$) against institutional policy clarity ($\beta = 0.223$). The OECD adds that general-purpose chatbots improve output quality, that the advantage disappears and sometimes reverses in exams when AI access is removed, and that metacognitive engagement drops as work is offloaded. Put the requirement in the graded assessment.

“Students will not read it.” They respond to it anyway, and the response is shaped by what their instructor says in week one. A policy only a committee has read has one reader.

“We cannot fund the support the framework asks for.” Then cut the framework to what you can fund and say so in the document. The panel placed institutional support and infrastructure as the foundational enabler, and Adarkwah et al. (2026) analyzed 159 documents from 30 highly ranked universities in the ten countries best placed on the IMF AI Preparedness Index, four of which were excluded for lacking publicly accessible policies, leaving 26, and found many provisions declarative rather than operationally assured. A mandate to use AI without devices, connectivity, accommodations or training is an obligation the institution has assigned and cannot support.

What to do this week

1. Search the draft for “may” and “can,” rewrite each instance where you mean “must” or “prohibited,” and define plagiarism and prohibited uses in words a first-year student can apply.

2. Name one executive owner, one standing committee with faculty and student members, and one review date. Give the monitoring of external developments to a named role.

3. Decide the layering: which provisions are university-wide, which the department writes, and which obligations belong to FERPA, GDPR, HIPAA, IRB and research-integrity policy.

4. Write the evidence standard and the detector sentence, then read your own appeal procedure against them.

5. Ask for the translation number, and pair any new restriction with a worked example and a training date.

Where to go next

How Do I Write a Course AI Policy and Communicate It to Students? is the classroom counterpart, where the document becomes an assignment sheet and a spoken sentence. The research base sits in institutional governance research, the global Delphi framework and program-level policy audits. Administrators and Change Management cover the leadership and implementation dimensions, Educational AI Policy collects

the sector-wide literature, and AI Governance covers how authority and accountability are distributed. On the enforcement side, Legal Issues and Risks carries the obligations a detector finding has to meet.

Connected FAQs

- How Do I Write a Course AI Policy and Communicate It to Students?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?

What Competencies Do Faculty Need in Regard to AI?

The faculty development committee has one slot in January and the provost wants it to be about AI. Or you run the teaching center, and three departments have asked for "an AI workshop" that turns out to mean three different things. Or you have been using these tools for a year and want to know what you are still missing before you rebuild a course around them.

The bottom line: prompt technique is the smallest part of this. Faculty need to judge what a model can and cannot do, design tasks and assessments around that judgment, and know when to keep it out of a course entirely. Confidence is a poor proxy for any of it, so build the program around performance and around disciplines rather than around a tool demonstration.

The short version

1. Define the competency in four dimensions, and add a teaching layer for anyone who assesses students.

2. Assess with performance rather than with a survey. Self-rated literacy and demonstrated capability diverge.

3. Put disciplines in the room. Subject expertise does not carry over into technology integration.

4. Teach the technology domains explicitly, because those are the ones that measure low even in confident faculty.

5. Treat "when not to use this" as a competency, and give faculty cover to decline.

Define the competency before you book the room

The knowledge base's AI Literacy synthesis identifies four dimensions, and they are a useful agenda because each one needs a different kind of session:

- **Foundational understanding** of AI capabilities and limitations.
- **Practical competence** using AI tools.
- **Critical evaluation** of accuracy, bias, appropriateness, and uncertainty.
- **Ethical and institutional awareness** involving issues such as integrity, privacy, equity, and AI Governance.

For instructors, those dimensions need a pedagogical layer on top. Faculty should be able to decide what cognitive work students must retain, select AI uses that serve the learning objectives, design valid AI-era assessment, teach students to verify and regulate their own use, recognize hallucination, overreliance and sycophancy, and know when human judgment should override automation.

They also need enough systems understanding to evaluate how generative AI-supported workflows fit together. A workshop that teaches one tool in isolation produces faculty who can demo the tool and cannot tell you what breaks when it is wired into a marking workflow. Teacher AI Competency and Faculty Development hold the longer version of that argument.

Write the list down before you plan the sessions. Four dimensions plus a teaching layer is enough to justify four sessions instead of one, and enough to tell a department chair which of the four their request is actually about.

Assess performance rather than confidence

Self-reported AI literacy can diverge substantially from demonstrated capability, which is the single most practical warning in this literature for anyone who runs faculty development. A confidence survey at the end of a workshop measures how the workshop felt.

Teacher multi-agent workflow research adds a second reason to test rather than ask: systems thinking, pedagogical beliefs and Self-Efficacy interact in AI integration, so the same session lands differently on two faculty members with the same subject background. That argues for differentiated programming, and against the one-size-fits-all tool workshop that most institutions run.

The cheap version of performance assessment is a task, not an instrument. Ask each participant to bring one assignment, revise it with the model during the session, and then defend the revision to a colleague: what changed, what it now assesses, what the student can no longer be graded on. That takes twenty minutes and tells you more than any end-of-day rating scale.

Expect the weak spot to be integration

Recent higher-education research puts numbers on where faculty competency is strong and where it breaks down. A survey of 127 faculty at a large U.S. research university using the Technological Pedagogical Content Knowledge (TPACK)-21 instrument found self-perceived pedagogical content knowledge high (M = 4.70) and content knowledge near ceiling (M = 5.15). The technology-integrated domains were markedly lower: technological pedagogical knowledge (M = 2.62), technological content knowledge (M = 2.75), and holistic TPACK (M = 2.55, the lowest of seven).

Read the gap correctly. These are people who know their subject and know how to teach it, and who do not know how to make a model part of either. Content expertise did not predict GenAI-integration knowledge (CK correlations r = .11 to .15, all non-significant), so a program cannot assume subject-matter mastery transfers. It has to build competence through deliberate, discipline-specific work.

One more finding shapes the design. The three technology-integrated domains correlated r = .81 to .91, which suggests they may function as a single GenAI-integration capacity. If that holds, teach it as one shared foundation rather than as three separate skills with three separate sessions.

Design sessions around a real course

What training can and cannot do shows up clearly in a within-subjects study with 13 higher-education teachers. Giving teachers a chatbot significantly improved the quality of their learning design, with the share attaining two or more higher-order Bloom tasks rising from **41.7% to 91.7%** (p = .01). Perceived cognitive effort fell sharply, median 6.33 to 3.33 (p = .004). The pedagogical prompting training layered on top **did not further improve quality** and slightly raised effort.

Three things follow, and the third is the one programs skip.

Access changes teaching behavior readily. Hand faculty a capable model and a real task and the work in front of them improves within one session.

Deeper capability takes more than a workshop. The prompting layer added effort and no measured quality. Teaching people to write better prompts is a skill, and on this evidence it is not the constraint on better design.

Quality gains do not prove the practice was internalized. Thirteen teachers redesigned one task well with the tool open. Whether they could do it a term later, without the tool, is a different question, and the study does not answer it. Build a follow-up into the program rather than assuming the gain persisted.

Cover the parts of the role beyond teaching

Competency is also an institutional question, and most frameworks answer only part of it. Design-based research with 114 participants across 28 U.S. institutions and 11 countries produced six faculty technology standards spanning the full academic role: Instructor, Coordinator, Leader, Researcher, Learner and Contributor. The authors' reason for building them is the useful part. Existing frameworks (Technological Pedagogical Content Knowledge (TPACK), SAMR) and educator standards (ISTE, UNESCO, DigCompEdu) address K-12 teachers or cover only the teaching dimension.

For a faculty developer, that reframes the request. A department asking for an AI workshop for its instructors is asking about one of six roles. The same department's coordinators are making program-level decisions, its researchers are writing with these tools, and its leaders are approving purchases. One session cannot serve all of them, and pretending otherwise is how a program ends up with high attendance and no change in practice.

Make room for declining

Adoption resists a purely technical framing, and the resistance is often a judgment rather than a gap. A survey of 287 teachers across 27 countries found a refined model explaining **79.8% of the variance** in behavioral intention. Perceived artificial autonomy influenced intention only indirectly, through usefulness. **Risk aversion was a significant negative predictor** (−.163), and teachers worried far more about students' overreliance and integrity risks than about their own use.

Interviews with two experienced academics describe what that worry feels like from inside: recurring **identity tensions** between pedagogy and platform, educator and facilitator, care and compliance, navigated through principled selectivity grounded in pedagogical values.

So competency includes professional judgment about when not to use AI, and a program that cannot say so out loud will read as a sales pitch to exactly the faculty whose judgment you most want in the room. Two experienced academics is a small evidence base for a large claim; treat the identity finding as a description of a real tension rather than as a measured effect, and let it shape the tone of the sessions.

What faculty developers get wrong

A prompt workshop is an AI competency program. It covers one of four dimensions, and in the 13-teacher study the prompting layer added effort without adding measured quality.

Confident faculty are competent faculty. Self-report diverges from demonstrated capability, and the 127-faculty survey found content knowledge near ceiling beside holistic TPACK at 2.55. Confidence tracks subject expertise, which is the thing these faculty already have.

Content experts will work out the integration themselves. Content knowledge did not predict integration knowledge in that survey. The correlation was non-significant, which is the finding that justifies discipline-specific programming rather than a general invitation.

One framework will cover everyone. The six-role standard exists because TPACK, SAMR and the major educator standards cover K-12 teachers or the teaching dimension alone.

Resistance is a knowledge gap to be filled. Risk aversion predicted intention negatively, and the identity work describes faculty reasoning from pedagogical values. Some of what looks like reluctance is a defensible position about student overreliance.

What will come back at you

“We do not have the staff time for performance-based development.” Then do not build a program. Build one task-level exercise: bring an assignment, revise it with the model, defend the revision. That is the twenty-minute version, and it produces evidence of capability that a satisfaction survey does not.

“Our faculty already use these tools, so the training is behind them.” Use is not the construct. The 127-faculty survey describes people with high content and pedagogical knowledge and low technology-integrated knowledge, and the 13-teacher study shows design quality moving with access while the prompting layer added nothing. Neither result says the faculty in front of you have integrated anything.

“This is an IT training problem.” The intention model puts usefulness, not technical capability, on the path to adoption, and risk aversion runs alongside it. The obstacle is judgment about students and about the discipline, which is why the sessions belong to the teaching center.

“Competency frameworks are bureaucratic overhead.” They are a map for one slot in January. The four dimensions tell you what to leave out, and the six roles tell you which audience a request is really for.

What to do this week

1. Write the four dimensions and the teaching layer on one page, and mark which of them your current offering covers.

2. Replace the end-of-session satisfaction form with one task: an assignment revised and defended.

3. Ask two departments for a real course and a real assignment to work on, rather than a general invitation.

4. Add one segment on when to keep AI out of a task, and say plainly that declining a specific use is a legitimate professional judgment.

5. Decide which of the six roles your next session serves, and name the audience in the invitation.

Where to go next

The student-facing counterpart is How Should I Incorporate AI Literacy into My Course?, and What Is the Evidence on AI Literacy Interventions in Higher Education? covers how strong that literacy evidence base is. For the instructor-facing summary of the research, see What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?; Teacher AI Competency and Faculty Development carry the framework material, and How Do I Write a Course AI Policy and Communicate It to Students? is the document most of this development work eventually produces.

Connected FAQs

- How Do I Design Faculty Development for AI That Actually Changes Practice?
- How Can AI Save Me Time as an Instructor?
- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

How Do I Design Faculty Development for AI That Actually Changes Practice?

It is February. Your provost has announced an AI initiative with a line item, and you have one semester to make it show up in classrooms. Or you ran six workshops last fall, the rooms were full, and the teaching you sit in on has not changed. Or a dean asks the plain question at budget time: what did the money buy?

All three come from the same design fault. A workshop shows people what a tool does. Practice changes when a teacher spends supported, structured time on a problem in their own course, long enough for a new habit to displace an old one, with the institution saying yes to the experiment rather than merely tolerating it.

The bottom line for the meeting: standardize a session cycle where every participant brings a real course artifact and leaves with a revised one, put verification, disclosure and risk control inside the working document instead of a closing ethics talk, stretch the program past a single day and pair it with mentoring, run discipline-specific cohorts, and report the artifacts people produced at a follow-up rather than how confident they felt on the last afternoon.

The short version

1. Anchor every session in an artifact from the participant's own course, and end the session with that artifact revised.

2. Put verification, disclosure and risk control in the working template, where they get used, so a nervous participant has somewhere to put the worry.

3. Spend the hours on assessment and rubrics, the weakest area at baseline and the one with the largest measured gain.

4. Run discipline-specific cohorts, then differentiate inside them by experience.

5. Secure the conditions: stated permission to experiment, protected time, materials in the languages your faculty work in.

6. Evaluate revised artifacts at a delay, plus one relational indicator, and treat satisfaction scores as noise.

Run every session on the participant's own course

The cleanest comparison here is Bi et al. (2026), who surveyed 568 faculty across five universities and ran a quasi-experiment with 160 of them. Both arms got four 90-minute workshops over consecutive weeks, with identical contact time, platform and facilitator support. The content differed. One arm got conventional GenAI faculty development, the other a structured cycle of prompt formulation, output review, course-material revision and written reflection against a seven-component template covering objectives, task constraints, assessment criteria, verification, disclosure and risk control.

The structured arm scored higher on all seven readiness dimensions. Its largest advantage sat in prompt design, at roughly two standard deviations, and it was the only arm whose prompt-design gain survived delayed testing; the conventional arm's smaller gain had fallen back below baseline by follow-up.

Two more results explain why demonstrations do not travel. In a within-subjects study with 13 higher-education teachers, chatbot access raised the share of activities reaching two or more higher-order Bloom tasks from 41.7% to 91.7% ($p = .01$) and cut perceived cognitive effort from a median of 6.33 to 3.33 ($p = .004$). The pedagogical prompting training layered on top did not improve design quality further, and it slightly raised effort. Meanwhile, in a workshop with 60 middle-school science teachers, the productive element was collaborative review of ChatGPT-generated assessment questions, which is what surfaced conceptual-precision problems and the risk of reinforcing Misconceptions about AI.

What those studies share: the learning came from critiquing and revising material. People improve the thing in front of them, and they improve it faster when a colleague is reading it too.

Stop treating skill as the missing piece

The tempting diagnosis is a capability gap, closed by better instruction. Bai and Hsieh (2026) surveyed 898 university teachers on AI-TPACK scales and found that teachers who understood how generative tools work, or could operate them competently, were no more likely to report inventing and implementing new teaching practices than those who could not. The integrated AI-TPACK construct had no direct path to innovative behavior at all. Its influence ran entirely through AI Literacy, teaching Self-Efficacy and professional identity.

That changes what a session is for. A tool walkthrough addresses none of those three. A session where a teacher rewrites their own assignment, defends the change and hears a colleague agree it is better addresses all three at once, which is why the artifact cycle outperforms the demo even when the content is thinner.

The design implication is uncomfortable for anyone with a slide deck: you cannot lecture a teacher into seeing themselves as the kind of teacher who works this way. You can put them in a situation where they act that way once, with support, and let the evidence accumulate.

Put the hard parts in the template they use

Dogan's (2026) i-TPACK framework comes from a PRISMA review of AI professional development plus a search that surfaced 17 further studies. It aligns five knowledge domains (intelligent technological knowledge, technological content knowledge, technological pedagogical knowledge, integrated i-TPACK, and AI ethics) with four evidence-based pathways: Active Learning, models and examples, coaching and expert support, and Feedback and reflection, governed by five principles running from Collective Synergy Over Silos to Flexibility within Structure.

The framework's sharpest criticism of the field is that ethics is handled superficially or absent entirely in many existing programs, and the fix is placement. Verification, disclosure and risk control belong in the document participants use all week, not in the last 20 minutes of the last session. A template with a risk-control column gets filled in; a closing segment on responsible use gets nodded at.

The framework's limit is that it is conceptual, with no program-level outcome data. Use it as a design checklist rather than as evidence that the design works. The outcome evidence is in the studies above and below.

Spend the hours on assessment

If your program has room for one deep topic, choose assessment. In Talebzadeh's (2026) eight-hour program, four two-hour sessions with 163 teachers and pre-service teachers, total AI-PCK rose from 151.65 to 220.14 (d = 2.36, p < .001). The largest component effect was Assessment Rubrics (d = 2.19), which was also the weakest area at pretest. The gain was narrower in teaching method than in assessment.

Rubrics are also where the anxiety in the room can be put to work. A participant who is uneasy about students leaning on a model can write a rubric line that makes the reasoning visible, which converts a worry into a design decision with a date on it.

Budget past the single day. In that same program, pre-service teachers gained significantly more than experienced ones (p = .033), mostly in scenario-based task design and rubric design. The experienced teachers said eight hours was too short to shift deep-seated habits, and asked for long-term, mentor-based support.

Build cohorts, then differentiate inside them

Run one universal workshop and you will spend most of it serving the median participant, who does not exist. Sutedjo, Chowdhury and Liu (2026) found among 127 respondents that self-perceived pedagogical content knowledge was high (M = 4.70) and content knowledge near ceiling (M = 5.15), while technological pedagogical knowledge (M = 2.62), technological content knowledge (M = 2.75) and holistic TPACK (M = 2.55) were markedly lower. Content knowledge showed no significant correlation with any technology-integrated domain (r = .11-.15), so subject-matter mastery does not carry over.

Those three low domains correlated r = .81-.91 with each other, which plausibly means one capacity for teaching with these tools rather than three separate skills. Teach it as a shared foundation and you save two sessions.

Then split by experience. Bai and Hsieh found professional identity predicted innovative behavior nearly twice as strongly among infrequent AI users as among daily users, a borderline result but a useful pointer: identity work pays off most with people who barely touch the tools, while frequent users get more from interdisciplinary projects than from foundational guidance. Laidlaw (2026) argues for discipline-specific cohorts as the setting for exactly that conversation, on the grounds that a physicist and a historian are not solving the same problem.

Open with the question the skeptics are asking

Laidlaw's (2026) autoethnographic account makes the case that resistance is not a skills deficit. Faculty asking what the point of teaching is in a GenAI world are not asking how to use a tool safely; the question is ontological. She reads GenAI as a threshold concept (transformative, troublesome, irreversible, integrative, bounded) and concludes that anxiety, resistance and confusion are necessary parts of crossing it rather than faults to correct. Her recommendations invert the standard workshop: open with identity questions rather than demonstrations, run discipline-specific cohorts, allow different timelines, and treat principled non-adoption grounded in disciplinary values as legitimate. She also warns that communicating rules can slide into an "enforcement illusion" that substitutes compliance messaging for support.

The guilt is measurable, and it is not evenly distributed. Vassallo (2026) surveyed 109 academics and identified an "AI guilt complex": 35% worried AI use undermines their credibility and 26% reported feeling they are "cheating", with anticipatory guilt about credibility exceeding remorse after use, so the distress is socio-professional rather than private. Four profiles emerged, Comfortable Adopters (27%), Guilty Non-Users (29%), Cautious Users (28%) and Morally Distressed Avoiders (16%). One program is addressing four different problems, and the 29% who feel guilt while not using the tools need something other than a demonstration.

The size of the task is visible in the AAC&U/Elon survey of 1,057 faculty (Watson and Rainie, 2026): 68% said their schools have not prepared faculty to use generative AI for teaching and mentoring, with a similar share for scholarship. 26% of respondents do not use the tools at all, including 40% of arts and humanities faculty, and 82% name colleagues' resistance as a barrier to departmental adoption.

Fix the conditions the curriculum cannot fix

This is the finding to bring to a leadership meeting. In the 568-faculty survey behind the comparison above, Kazakhstani faculty reported higher baseline readiness than their Chinese counterparts on all seven dimensions, with the widest gaps in disciplinary transfer, prompt design and basic understanding. In hierarchical regression the Kazakhstan coefficient, clearly significant on its own, fell to non-significance once prior GenAI use, recent AI training, institutional support, perceived permission, multilingual resource access, policy clarity and risk sensitivity were entered. That is a reduction of about four fifths. Institutional support and perceived permission carried the most positive weight, and risk sensitivity was the only predictor working against readiness. More than twice as many Kazakhstani as Chinese faculty reported AI-related training in the previous six months.

So the levers available to a program lead are local and proximate: hands-on practice, explicit permission to experiment, materials in the languages faculty actually work in, visible backing from the unit. National policy framing does not carry readiness on its own. Where risk sensitivity bites, the answer is to give it somewhere to be exercised rather than to talk caution down, and rubric design and verification routines are that somewhere.

Two practical frictions belong in the same conversation. Continued-use intention was the highest-rated satisfaction dimension in Bi et al. (2026) while tool usability was the lowest, so some of what reads as reluctance is platform friction. And Aponte et al. (2026) locate the hard limit: AI cannot compensate for chronic overload, punitive accountability cultures, weak leadership, or the absence of protected time. They argue it contributes to teachers' socio-emotional development only as relational infrastructure (protected time for mentoring, peer dialogue, communities of practice) and propose *relational densification* as the standard, counting trust, continuity of support and co-regulation rather than contact hours. Two claims translate into program design: freed time gets reabsorbed as extra demand unless the institution formally requires it to be reinvested, and conversational agents can quietly substitute for the difficult human negotiations that produce growth. Their framework is a heuristic, not a tested causal claim.

If those conditions are yours, a better workshop will not fix them, and saying so is more useful than promising otherwise.

Report artifacts at a delay

The institutional scaffold worth aligning to is Crompton, Burke and Nickel (2026), whose design-based research across two macro cycles and 114 participants (faculty from 28 U.S. institutions and 11 countries, plus centers-for-teaching directors and accreditation coordinators) produced six standards spanning the whole academic role: Instructor, Coordinator, Leader, Researcher, Learner and Contributor. Existing frameworks and educator standards target K-12 teachers or address only teaching, so a center that maps its offer onto these can be mapped onto appraisal and accreditation, which is also the argument that survives a budget review.

Then be careful how you evaluate, because most of this literature measures self-reported impressions. Bi et al. measured self-reported readiness rather than enacted teaching, and its groups formed by voluntary sign-up rather than randomization, so the results are associations. Bai and Hsieh is cross-sectional, self-selected, drawn from eight universities in one country, and measured every construct from the same respondents at one time. Sutedjo and colleagues cannot establish direction of causation, which matters because their strongest claim, that technological knowledge acts as a gateway, is what a cross-sectional design cannot settle. Talebzadeh reports very large effects without randomization, follow-up or discipline-level breakdown, so $d = 2.36$ reads as short-term. Laidlaw is autoethnographic, and Aponte et al. state that their framework is conceptual.

A defensible evaluation therefore measures the course materials a participant revised, the rubrics written, the tasks designed. It tests at a delay, because the gap in Bi et al. appeared only at follow-up, where the conventional group had decayed and the structured group had not. It treats satisfaction and confidence as weak signals, since Pishtari and colleagues (2026) note that quality gains alone do not prove internalization: rising design quality can equally reflect delegating routine work or accepting AI-generated structure. And it adds at least one relational indicator, following Aponte et al., because improving artifacts while isolating participants is not what the program claimed to do.

What program leads get wrong

A better demo is a better workshop. Contact time was held constant at four 90-minute sessions in the Bi et al. comparison, and the arm that revised artifacts beat the arm that learned about tools on every readiness dimension, with only one of the two gains still visible at follow-up.

Confidence is the outcome that matters. It is the easiest thing to move and the least predictive. In the 13-teacher study, perceived effort fell while the prompting layer added no measured design quality, and end-of-day ratings would have registered both as success.

Ethics is a closing segment. Dogan’s review found ethics handled superficially or absent in many offerings, and the difference between a template column and a final slide is whether anyone uses it in week three.

One program can serve the whole faculty. The 127-faculty survey describes content knowledge near ceiling beside holistic TPACK at 2.55, and Vassallo’s four profiles include 29% who feel guilt while not using the tools. A single session treats four audiences as one.

The skeptics are the obstacle to manage. Laidlaw's account puts resistance at the level of identity, and Bai and Hsieh found identity predicting innovation nearly twice as strongly among infrequent users. The people you most want in the room are the ones a demonstration confirms in their suspicion.

An institutional mandate will carry the program. The Kazakhstan coefficient collapsed by about four fifths once institutional support and perceived permission entered the model, and those two carried the most positive weight. A mandate is not the same signal as permission.

What will come back at you

"We do not have the hours." Then spend them differently rather than adding them. Six hours arranged as an artifact cycle beat six hours of demonstrations on identical contact time, and a shorter format spent on assessment rubrics targets the weakest area in Talebzadeh's pretest data.

"Our faculty will not come, or the skeptics will derail it." Recruiting the skeptics into a demonstration confirms the suspicion that sent them there. Open with identity questions, run discipline-specific cohorts, allow different timelines, and say out loud that principled non-adoption is a legitimate position. That is Laidlaw's recommendation, and it takes the compliance argument off the table. Expect identity work to matter most with infrequent users, per Bai and Hsieh.

"We cannot make people act on it." You mostly cannot, and you can change what the institution signals. Perceived permission and institutional support carried the most positive weight after the national-background effect collapsed, so the useful moves are the cheap ones: state that experimentation is sanctioned, protect the time formally so it is not reabsorbed, provide materials in faculty's working languages, and remove platform friction, which was the lowest-rated dimension in that same study.

"Our exit survey is strong." Satisfaction is the measure most likely to rise while nothing else does. Ask instead for the artifacts from last cohort and re-contact those participants a term later; the Bi et al. gap existed only at follow-up.

What to do this week

1. Rewrite the invitation so attendance requires bringing one course artifact: an objective, a rubric or an assessment task.

2. Rewrite the agenda so the first session starts on that artifact, and add verification, disclosure and risk control as columns in the template participants carry all week.

3. Move one session to rubric and assessment design, and have participants leave with the rubric written.

4. Get one sentence in writing from the dean or provost that experimentation is sanctioned, then protect the hours formally so they are not reabsorbed.

5. Set the evaluation to collect revised artifacts and to contact participants again a term later, with one question about who they now work with.

Where to go next

What Competencies Do Faculty Need in Regard to AI? covers the competency target itself, and Teacher AI Competency and Faculty Development carry the framework material behind it. For structuring AI into a course rather than into a workshop, see How Should AI Be Designed Into the Learning Experience?; for the wider institutional picture, What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About? and How Do We Write and Implement an Institutional AI Policy?.

Connected FAQs

- What Competencies Do Faculty Need in Regard to AI?
- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

Designing courses and activities

For anyone deciding where AI enters a task, a semester or an online course, and for instructors who want the time back that AI was supposed to give them.

How Should AI Be Designed Into the Learning Experience?

The module outline has a line that says “AI activity” and nobody can say what it replaces. Or an instructor has asked to add a chatbot to a course that already works, and your job is to place it without breaking the part that made the course work.

Start from the learning goal and from the activity that produces it. The same model can be a scaffold, a Socratic partner, a reader of drafts, a Simulation, or an answer machine, and which one you get depends on the design rather than the model. Name the mode you are building, put the learner’s attempt before any help appears, and keep at least one route through the course that runs without the tool.

The short version

1. Write the sentence about what learners can do afterward without the tool, and check every AI feature against it.

2. Sequence the interaction: learner attempts, AI supports, learner evaluates or revises, learner demonstrates.

3. Name the mode on the ICAP ladder. Bypass and scaffold can be the same tool at different rungs.

4. Place the AI where the course sequence already intends a specific activity, not at the end as a bonus.

5. Withhold the tool while a capacity is forming, then restore it at a checkpoint the student cannot fake.

Decide what the learner does without the tool

The knowledge base’s Pedagogies and Teaching Strategies concept supplies the test: does the configuration preserve the activity that produces the intended learning? Answer that on paper, before anyone picks a feature.

The Principled AI Education Framework states the general rule: technology should augment rather than displace the human capabilities that education intends to develop. Written as a test for a module, that means naming the capability, naming the activity that builds it, and asking whether the AI sits inside that activity or beside it.

Apply it per task rather than once per tool. Across four teacher-facing cases automation and augmentation co-occurred: replacement stayed inside bounded analytical subtasks, and augmentation appeared in what the teacher did with the output, which is why the same tool can automate one step and augment another (Horvers et al. (2026)).

Put the attempt before the help

The default pattern that survives contact with a real class: **learner attempts, AI supports, learner evaluates or revises, learner demonstrates understanding.**

In practice that means asking for an initial prediction or solution before any assistance appears, and favoring questions, hints, examples, counterarguments and Feedback over immediate completion. Preserve productive failure where it serves the learning. Require verification of consequential claims, build in explanation and

teach-back, and fade the support as competence grows. Keep some AI-free work so learners can calibrate what they can do alone.

The Reducing AI Misuse synthesis recommends the same shape as a think-first, AI-second, reflect sequence with deliberate evaluation checkpoints.

Name the mode you are designing for

Rummel, Nachtigall and Panadero's kitchen-machine analogy reframes the question from whether learners use generative AI to how that use shapes what they become. Mapped onto ICAP and SAMR, it gives a ladder. Fully outsourcing an assignment with no revision or critical engagement is Passive substitution, and it risks skill loss and over-reliance. Refining prompts and cross-checking outputs takes prior knowledge and self-regulation, which is Active or Augmentation. Using AI to brainstorm, outline and evaluate original work is Constructive or Modification. AI as a real dialogue partner for co-construction and adaptive feedback is Interactive or Redefinition.

The implication is direct. The same tool is a bypass at one rung and a scaffold at the next, so the design document should name the intended mode.

Place it where the sequence intends an activity

Divjak, Svetec and Horvat analyzed the planned sequence of 29,064 teaching and learning activities across 554 courses and found a visible design grammar. Acquisition-type activities are the most common entry point and the largest single type, above 20%. Learning type tracks the intended Bloom level, with Acquisition falling from about 50% at level 1 to about 20% at level 6 and Production rising above 20% at levels 5 and 6. The strongest transition in the data is Assessment to Discussion, at 0.332.

Two lessons follow for AI design. Put the tool where the sequence intends an activity type. And because feedback clustered with collaboration, group work and teacher presence, peer and synchronous structures are where AI support should plug in, not where it should substitute.

Design the clock, not just the sequence

Englmeier (2025) treats time as a designed scaffold rather than a student trait: a self-paced course carries a weekly allowance of about 100 minutes with a target near 20 minutes a day, time-aware reminders, a progress dashboard, and a short end-of-subchapter check of 3 to 12 questions. The baseline that design answers is stark, with nearly 25 percent of over 600 learners starting only in the final week and 95 percent of that group failing.

Read it as a design prompt rather than a proven effect. The paper compares a later course against an earlier one instead of running a controlled trial, so the improvement cannot be separated from the change of cohort and subject, and reminders strong enough to move study timing are also a Privacy question you have to answer in the syllabus.

Decide what to withhold, and when to restore it

Torres-Sahli and colleagues' "refrain, then amplify" framework moves this to program level. Withhold a generative tool while a capacity is forming, then restore it once the student can direct it, judge what it returns, and answer for it, with a hard-to-fake checkpoint at each hinge.

Devices are governed by a forming-versus-offloading criterion: allowed where they support engaged work, excluded where they drain attention. That turns offloading decisions into a curriculum and AI Governance question that comes before course-level design rather than after it.

Check that the alignment is real

McInnes and colleagues' discourse analysis of 14 pieces of higher-education guidance warns that efficiency-framed advice, such as using generative AI to draft outcomes, rubrics and course outlines, produces alignment that looks aligned while neglecting the constructive half. Outcomes, activities and assessments get generated as discrete items rather than interdependent ones.

Their remedy is re-sequencing. Educators should understand constructive alignment well enough to direct, interrogate and reject AI output before delegating any part of it, because accepting a plausible surface is the same evaluative failure instructors warn students against. Where AI is used, they argue for institutionally bounded, retrieval-augmented systems configured around local policy and quality standards rather than generic internet-trained defaults.

What instructional designers get wrong

Adding the AI counts as the intervention. What changes learning is the activity the student performs, and the AI is one part of the setting for it. A well-placed hint and a well-placed answer can run on the same model and produce opposite learning.

Writing the permission is the design work. A permission sets what is allowed. It does not set the sequence, the mode, or the checkpoint, and those three decide whether the activity survives.

Efficiency is the goal of the redesign. Drafting outcomes and rubrics with a model is fast, and the 14-document analysis found the result can look aligned while the parts stop supporting each other.

What will come back at you

"The students will use it anyway, so designing around it is naive." They will, which is the argument for specifying the mode and teaching it. A module that names the mode gives a student something to comply with.

"We do not have time to re-sequence a whole course." Then re-sequence one module and one assessment. The refrain-then-amplify hinge is one checkpoint, and the think-first sequence is three instructions on a handout.

"Our AI feature already includes Guardrails." Guardrails constrain what the model says. They do not decide whether the learner attempted first, whether support fades, or whether an AI-free path exists. Those are design decisions in your course, not settings in the product.

What to do this week

1. Write the unaided-performance sentence for the module and put it above the activity list.

2. Mark the intended ICAP mode beside every AI activity in the outline.

3. Move one AI activity so the learner attempts the problem first.

4. Pick one AI-free path through the module and label it for students.

5. Name one hinge where the tool is withheld, and the checkpoint that restores it.

Where to go next

Instructional Design, Active Learning and Scaffolding carry the design vocabulary. For the interaction-level defaults that decide whether a designed activity preserves learning, see How Can I Reduce AI Cheating in My Course? and How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?. What Are Best Practices and Tips for Designing Effective Educational AI Software? covers how the same principles constrain the software itself, and What Are Best Practices for Developing an Effective AI Tutor? translates them into a tutor's architecture.

Connected FAQs

- What Are Best Practices and Tips for Designing Effective Educational AI Software?
- What Are Best Practices for Developing an Effective AI Tutor?

How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

The term opens and nothing happens at a set hour. You post week one's reading, the discussion prompt, the first case, and then you wait to see what comes back. What comes back is fluent, on topic, and tells you nothing about the student who submitted it. There is no room to walk into, no face to read at 10:15 on a Tuesday, and no follow-up question you can ask while the student is still standing in front of you.

The answer to give a colleague: in an asynchronous course, everything a classroom supplies for free has to be built on purpose. Put the grade on the process instead of the finished file, keep one measurement the student produces with no tools and no help, constrain whatever AI you hand out and keep it inside the course, and treat the calendar as a design decision. For any assignment, ask what a student would still have to do if a model produced the artifact for them.

The short version

1. Grade the process. A decision log, a staged draft, or a paragraph of self-explanation shows reasoning that a final submission hides.

2. Keep one unassisted measurement on any assessment that certifies competence. The retention gap in the population data below closes once proctoring is in place.

3. Use asynchronous oral assessment where the stakes justify the production work: just-in-time prompts, short recordings the student cannot revise, rubrics embedded, transcripts generated automatically.

4. Configure any AI you supply to hint instead of answer, and embed it in the course rather than linking out to something generic.

5. Space the major deadlines, and open a 7-8 day window before each one. That is how much warning the interaction data gives you.

6. Grade the movement in a discussion: a committed position, a challenge, a documented reconsideration.

Decide what your assignment is evidence of

An asynchronous course is exposed for a structural reason. Its evidence of learning is the submission, and submissions are now cheap to produce.

The demonstrations take the student out of the picture entirely. On a live undergraduate psychology course, autonomous agents logged into the learning management system, read the course materials, and completed unproctored assessed work with no student involved. Two quizzes finished in about **12 minutes** and in **under 5 minutes**, both scoring **10/10**. A discussion post had the agent mine its peers' posts and then fabricate a credible first-person life history to answer them. The authors' wider record covers at least **15 documented agent runs** across Canvas, Moodle and Brightspace, using **seven agent tools**. Their framing matters for your syllabus: this is an Assessment Validity problem before it is an integrity problem, because agent completion removes the assumption that the submitted work came from the person whose learning is being assessed (Hadjisolomou and El-Haddad, 2026).

The causal evidence on what the tool does to learning is equally direct. In a randomized trial with roughly 1,000 high-school mathematics students, unguarded AI assistance raised practice performance by **48%** and reduced unassisted, closed-book exam scores by **17%**. Students with no access outperformed students with access. A guardrailed tutor that gave hints instead of answers eliminated the harm. The constraint decided the outcome.

Population data run the same way. Across **3.2 million ALEKS interactions**, study time on AI-susceptible problems fell **26.9%** after ChatGPT's public release, with a **25% decline in the odds of answering proctored retention items correctly**. The effect vanished once proctoring was in place. That disappearance is the useful part for course design, since it locates the shortcut off-platform and shows the harm living in conditions you set.

There is a quieter failure to design against. Metacognitively discordant completion names the state of submitting correct, complete work while privately knowing that understanding never arrived. In a classroom you might catch it in a student's hesitation. In an asynchronous course the submission is the only channel, and a correct submission reads as success. Assessment design is your first lever.

Put the evidence in the process

If the finished product proves nothing, the evidence has to come from how the work was made or from a condition the student cannot delegate.

Process-revealing artifacts are the cheapest change, and they work at scale: staged submissions with a required intermediate decision log, a one-paragraph self-explanation attached to each answer, an annotation of a source, a plan revised after feedback. These capture the reasoning rather than its residue, and they cost the instructor comparatively little to scan.

Asynchronous oral assessment carries the most weight where competence must be certified. Pentland, Lowenthal and Krier (2026) evaluated web-based assessments that deliver prompts just in time, have students record brief, time-limited webcam responses they cannot revisit, and grade against embedded rubrics while transcripts generate automatically. Across two studies, an intermediate accounting pilot and a data analytics course, students scored higher than on in-person multiple-choice exams. The difference was significant in the second study and a positive but non-significant trend in the first, with moderate cross-format correlations supporting convergent validity. Students reported preparing differently, using more active study strategies, and treating the format as professionally relevant. For a course with no shared hour this is the closest structural equivalent: the thinking happens live, at a time and place the student chooses, at an administrative cost that does not grow with cohort size.

One unassisted measurement belongs in any course whose grade certifies knowledge. The ALEKS result is the argument: with proctoring in place, the retention gap disappeared. Tell students why the condition exists. That reasoning belongs in your course AI policy.

Decide where the tool sits in the sequence

Once the product is unreliable evidence, the order of the work becomes part of the assessment design.

Brcic and Frljic (2026) put placement at the center of the argument: allow-or-ban is a false choice, and the design question that matters is **where the tool sits**. The causal evidence they collect shows the outcome flipping on placement alone. The same unguarded helper that left high-school students about **17% worse** on an unaided exam did no harm once rebuilt to withhold answers, and a well-engineered tutor roughly **doubled** learning. Their six-move frame for placing the tool (prime, probe, point, attach, strengthen, test) is one usable menu. Keep their diagnostic: *if letting AI in makes the task feel effortless, it is in the wrong place.* Poor placement leaves an illusion of learning that collapses on the unaided task, the state metacognitively discordant completion describes.

Written into an assignment, that gives you a sequence you can print on the sheet:

Think, commit, use AI, critique, revise, explain.

Students attempt the intellectual work and commit to an initial interpretation, prediction, outline or decision. Then the model enters, for feedback, alternatives, counterarguments or critique. Then students judge what it produced, revise, and explain what changed and why. The commitment step is what makes the rest assessable. An uncommitted student has nothing to revise, and an artifact a model wrote from scratch has no revision history at all.

The overcorrection to avoid: collecting every prompt and documenting every keystroke produces workload without evidence. Ask for the decision points you would actually read, which evidence was selected, which alternative rejected, what changed after critique.

Pair the task you cannot defend with a twin

The structural option here is to stop choosing between a pedagogically sound task and a defensible one. Roe, Perkins and Giray (2026) propose **assessment twins**: pair the AI-vulnerable task, a take-home essay or analysis, with a second, less vulnerable task that assesses the *same* outcomes, scheduled closely enough for cross-verification, and marked interdependently. Their mapping runs across Messick's six strands of validity evidence, and their design process has three steps: identify the vulnerabilities, align outcomes and choose the twin, then develop marking that connects the two. The take-home analysis keeps its value for extended inquiry. The twin might be a short case variation, an explanation of one key decision, or a brief oral or multimedia defense.

The companion question is ownership. Ebrahimzadeh, Shibani and Buckingham Shum argue that coauthorship with generative AI undermines several forms of validity evidence, and propose **coauthorship integrity** as a source of validity evidence in its own right, violated when a student submits AI-generated content they do not understand. To check ownership at scale they report work on an **AI Viva**: a conversational agent that runs a hybrid viva voce, asking comprehension questions of controllable type and complexity, validated in depth by expert educators and assessment specialists. Weigh that against proctoring everything. A spoken defense of one's own reasoning scales where room monitoring does not, and it produces evidence about understanding.

Decide what the AI you supply is allowed to do

What matters is the difference between embedded, constrained AI and an unattached chatbot. The two produce different results.

The Open University's AIDA assistant is the best-documented embedded case: six iterative design-based studies over 18 months with 498 students and 20 staff, at an institution serving 200,000-plus learners across more than 50 countries. In an exploratory randomized trial, students using AIDA spent **twice as long** and visited more pages in their course than the control group, and **96%** wanted the assistant available in their formal studies. The same institution's experience with an external, unattached chatbot went the other way.

Lock, Arteaga and Johnson's (2025) review, 63 citations across 32 countries, adds a social condition: students who used ChatGPT *alongside* teacher tutoring perceived greater Learning Gains than those who used it alone. An assistant supplements the instructor or it replaces the relationship, and only one of those is a course design.

Two cautions deserve weight. KhanMigo's failure was not technical. Learners did not engage with the chatbot and evidence of gains was limited, which points at organizational readiness and instructional fit. The instructor side is not ready either: in a comparison of South African teacher preparation, self-reported Technological Pedagogical Content Knowledge (TPACK) for AI-integrated science teaching was **64.0%** at a campus-based university against **47.4%** at a distance university, with pedagogical knowledge the weakest domain in both (Online Teaching and Learning). Deploying an assistant into an asynchronous course does not train the people who must judge its output.

Grade the movement in a discussion

Discussion forums are where an asynchronous course builds community or quietly becomes a submission box. Two findings should shape what you automate there.

Timing is the hard part. Tsirmpas and colleagues built the PEFK corpus to compare facilitation datasets, then ran the first survey of facilitation *timing* with expert human facilitators and Large Language Models (LLMs) judges. Humans were more cautious about intervening. LLMs were excessively eager. Both were more certain when judging that facilitation was **not** needed than when judging that it was. Trained classifier models outperformed the LLM setups, and even then the existing datasets capped performance. Practical reading: keep autonomous moderation off the critical path, and if you use AI in a discussion at all, configure it to stay quiet by default.

Summaries help students navigate a forum without making them participate. With 128 university students across three iterations, Hao and Cukurova (2026) found AI-generated discussion summaries broadened exposure to peers' contributions and strengthened network connectedness, the weak ties social-capital theory calls bridging, by lowering the effort of finding meaningful posts. They did not stop viewing activity declining across the course. Summarization is a navigational scaffold.

The structure that holds up is a sequence rather than a thread: **position, challenge, reconsideration.** Students commit to an interpretation grounded in the course material, then meet another perspective, counterexample or critique, then explain whether and how their reasoning moved. What you grade is the movement between ideas. A submitted post plus two replies stopped demonstrating it the moment an agent could mine a peer's posts and impersonate a classmate's life history to order.

Because what an agent imitates is surface behavior, your own contributions become the scarce resource. Replying mechanically to dozens of individual posts is the weakest form of teaching presence; synthesizing across the discussion is the most: *three assumptions keep appearing in your analyses; several of you read*

this evidence differently; this argument is convincing until we introduce this counterexample. That is orchestration rather than message production.

The framework question underneath both is accountability. Ba, Gašević, Lim and Anderson (2026) argue that generative AI unsettles the Community of Inquiry assumption that presence indicators can be attributed to humans at all. They treat GenAI as an epistemic condition and presences as sociotechnical accomplishments whose relationship to inquiry quality depends on where human accountability sits. Concretely, decide and state who is accountable for what in each exchange instead of assuming presence arises because a forum exists.

Keep the term moving without a room to walk into

Self-paced formats assume self-regulation and rarely teach it. The evidence on which behaviors actually correlate with staying on task is unusually practical.

Surveying 530 college students with association-rule mining and clustering, Shi et al. (2026) found that self-regulated learning behaviors, **goal setting, environment structuring and time management**, co-occurred most consistently with low digital distraction, along with learner-instructor and learner-content engagement and technical competence. Reliance on peer Help-Seeking and learner-learner engagement appeared *less* often in the low-distraction profiles. Structure the environment and the schedule before you design another group activity.

Self-regulation is also not a fixed trait. Across a full semester with 75 first-year students, Song et al. (2026) found it functioning as both a stable aptitude and a fluctuating state. Individual baselines held steady while metacognitive knowledge and Well-Being declined systemically across the term, driven by curriculum demands such as major assessment deadlines. Clustering deadlines may be an efficient administrative choice, and it is also a measurable tax on the regulation your format depends on.

The intervention window is knowable. Zhang, Jeffries and Koprinska (2025) showed that interpretable machine learning on content-interaction logs predicts module-level progress and flags dropout outcomes up to **7-8 days before module deadlines** in large-scale online programming courses. That is enough notice to send a specific nudge to a specific student, which beats discovering the failure at grading time. For adult and distance learners, the AI-ALOE design guidelines add the constraint that matters most: mobile access, offline capability, and genuine asynchronous availability, since these learners study in fragments of time between other obligations.

Decide what to automate in production

Two uses have reasonable evidence behind them, and both target instructor workload.

Production cost. MAIC reframes the MOOC's "one video for N students" broadcast as "N agents for one student," using specialized teacher, assistant, classmate and analyzer agents on a shared model foundation. Its authors report collapsing course production from roughly **$25,000 and 60 hours** per MOOC to **under $2 and 30 minutes**, piloted at Tsinghua across two courses with **100,000+ learning records from 500+ students**, and released as Open Source OpenMAIC. Personalized media is the same idea at the asset level: in a large online course, Tomlinson et al. (2026) found students preferred AI-generated personalized videos

over non-personalized human-recorded ones, with the personalization effect outweighing the value placed on a human presenter.

Forum navigation. The summary scaffold above reduced the cost of locating good contributions without adding to the instructor's reading load.

Three tasks stay with you: deciding whether a piece of writing is the student's own thinking, judging whether a discussion needs intervention, and calibrating difficulty. Generated material also needs pedagogical review before it carries credit. Cheap production is a separate question from sound design.

Name the AI's role and check the student still has one

"Students may use AI" is too broad a specification to design against. Naming the role is what makes an activity designable, and roles carry consequences for presence: a study of generative AI in marketing education distinguishes **tutor, teammate and tool**, shows each influencing teaching, social and cognitive presence differently, and lists the familiar ethical exposures of data privacy, plagiarism, dependency and assessment fairness (GenAI in Marketing Education). The same model can be a Socratic questioner before an assignment, a critic after a first draft, a simulated stakeholder during a case analysis, an opponent whose argument must be rebutted, a hint-giving tutor during practice, or an editor brought in after the substantive reasoning exists. Those are different activities, and conflating them is how "AI is allowed" comes to mean "nothing was designed."

Scaffolding supplies the test. Support should help learners do what they cannot yet do alone, and should fade as competence develops. A model that keeps supplying complete solutions is doing the task. For every AI-enabled activity, you should be able to finish this sentence without hesitation:

The AI's job here is _____, while the student's job is _____.

If the second blank contains little thinking, the activity needs redesigning.

Ask them to judge an answer they did not write

AI Literacy covers critical evaluation, metacognitive judgment and knowing when to skip the tool. Self-reported confidence is a poor proxy for demonstrated competence.

One change any asynchronous course can adopt immediately: **sometimes give students the AI output yourself.** Hand over two competing answers and ask which is stronger and why. Ask for the weakest claim, the missing assumption, the unverifiable source, the plausible explanation that is nonetheless wrong. Ask what evidence would change their mind.

Framed that way, the capability being graded is whether a student can recognize an answer that deserves trust, which is closer to what the discipline requires and far harder to delegate. The verification practices are where the technique lives. What matters here is putting evaluation inside the graded task instead of leaving it as advice in a module announcement.

What instructional designers get wrong about asynchronous courses

The submission is the problem, so the submission is what needs fixing. It is also the only channel you have, which is why tightening the artifact alone changes little. Add a second channel: a process record, a recorded explanation, one unaided measurement.

Flexibility means the student owns the pacing. The format assumes self-regulation, and the 75-student semester study shows metacognitive knowledge and well-being declining as deadlines cluster. Pacing is a design decision you make for them.

A forum is participation, so I count posts. The agent demonstration above produced a post that mined peers and invented a life history; a count cannot distinguish it from a good one. The Hao and Cukurova summaries improved navigation and left viewing activity declining anyway.

Adding an assistant makes the course AI-integrated. AIDA was purpose-built, embedded and iterated over six studies; an external chatbot at the same institution went the other way, and KhanMigo's learners simply did not engage.

Process evidence means documenting everything. Collecting every prompt and every keystroke produces paperwork and little else. The version worth grading asks for a few decision points: which evidence was selected, which alternative rejected, what changed after critique.

What will come back at you

"These are adults who chose an asynchronous course. If they let AI write it, that is their decision." The choice argument would hold if the course certified nothing. It does. The ALEKS evidence shows a shortcut producing an appearance of competence that does not survive a proctored check, and the cost lands later, in the next course, the licensure exam or the job. There is an equity edge: the learners most likely to offload are often those with the least time, the group an asynchronous course exists to serve.

"Detection is the answer." Detection is contested, and the proctoring result shows why design beats policing: the harm disappeared when the conditions changed. Detection also carries false-positive costs and turns instruction into an arms race. Redesign the task and keep one unassisted measurement. See How Can I Reduce AI Cheating in My Course? and How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?.

"Teaching presence is impossible at a distance, so async is inherently inferior." Presence in an asynchronous course is designed. The CoI reconceptualization above says its indicators are sociotechnical accomplishments in the GenAI era, and the AIDA trial doubled time on task in a course with no synchronous meetings at all.

"Proctoring is surveillance and I will not impose it." A defensible position, and it leaves options open. Process-revealing artifacts, asynchronous oral assessment and the AI Viva capture reasoning without monitoring anyone's room. If you do use a proctored condition, put it in the syllabus, explain the reasoning, and keep it to the assessments that certify competence.

"Then make it all synchronous and proctored." Many students choose asynchronous study because of employment, caregiving responsibilities, disabilities or geography. Detection carries its own equity costs too: tools that flag non-native writers disproportionately produce false positives that penalize honest work (AI

Detection). The proportionate alternative is a small number of verification moments inside an otherwise flexible course: a short recorded explanation, a personalized application, a response to an instructor-selected question, an annotated decision trail, a low-stakes individual check. Verification should raise the validity of your evidence and keep the flexibility that made the format worth offering.

What the evidence does not settle

The systematic review of AI in distance education (56 articles, 2020-2025) covers personalization (24 studies), assessment and feedback (19), human-AI interaction (17) and governance and equity, and concludes that the base is short-term and cross-sectional, with little longitudinal work. The review of AI and student engagement in online learning (24 studies) is limited to one database, treats engagement only, and conflates synchronous with asynchronous contexts, so its conclusions are not asynchronous-specific. Asynchronous oral assessment rests on two studies in two courses. MAIC is a pilot. Facilitation-timing datasets cap performance even with trained classifiers. No study here follows an asynchronous cohort long enough to show whether redesigned assessment produces durable learning or only better evidence of it. All of it is strong enough to change your next course and too thin to justify a policy claim.

What to do this week

1. Pick your highest-stakes assessment and add one condition the student completes unassisted. Tell them why it exists.

2. Take the assignment AI now completes end-to-end and rewrite it so the process is the artifact: a decision log, a staged draft, a self-explanation, a comparison of two attempts.

3. Convert one major assessment to an asynchronous oral defense with embedded rubrics, and set the AI permission per task in the syllabus where students will actually read it.

4. Space the major deadlines, and block a 7-8 day pre-deadline window for contacting students whose interaction data has gone quiet.

5. Run three questions over your weakest assignment. Could an AI system complete this activity without the student understanding the material? What cognitive activity is supposed to produce the learning here? What evidence will show that the student actually performed that activity? If the first answer is yes and the other two are hard to answer, the problem sits in the learning design, and no wording of the policy will fix it.

Where to go next: the course-level rules belong in How Do I Write a Course AI Policy and Communicate It to Students?; the assessment rebuild is covered in How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?; the reliance problem underneath it in How Do I Keep Students from Over-Relying on AI?; instructor workloads and what AI realistically removes in How Can AI Save Me Time as an Instructor?; and the design-level view of embedding AI into a learning experience in How Should AI Be Designed Into the Learning Experience?.

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?
- How Do I Write a Course AI Policy and Communicate It to Students?

- How Do I Teach Students to Verify AI Output?
- How Should I Handle AI in Group and Collaborative Assignments?

How Should I Handle AI in Group and Collaborative Assignments?

The group presentation comes back polished and coherent, and not one member can explain the argument in it. Or the marks come out even, and you learn afterward that one student ran the whole thing through generative AI while three others coasted on the shared grade. Nothing in the file tells you which of those happened, and your rubric has a collaboration line that everybody met.

The answer to give a colleague: decide AI's place per task rather than per course, make the group's negotiation about AI something they submit and you grade, sequence the work so it cannot be split into parallel chatbot sessions, and keep at least one component each member answers alone. All of it is task design, and none of it has been tested against a no-AI control, so you are making a design argument rather than applying a proven fix.

The short version

1. Write the permission at the level of the task phase. Say which stages are AI-open, which are not, and why.

2. Require a short, jointly authored AI-use statement that records what the group decided not to do, and grade the reasoning.

3. Protect the stages where the group builds shared understanding: the framing, the disagreement, the reconciliation.

4. Choose the access configuration on purpose. One shared interface produces negotiated, visible use; private prompting produces flows you cannot see.

5. Keep one component each member answers for alone, and make it comprehension rather than authorship.

6. Read a group's restraint before you correct it. Declining AI can be deliberate self-regulation or plain unfamiliarity.

Write the permission per phase, not per course

Chen and Zou (2026) studied groups of three to five delivering a presentation worth 30% of the grade, under an institutional policy of "use only with explicit acknowledgment." GenAI was permitted for idea generation, language polishing, visual layout and scripting. Inside that single permissive policy, groups reached opposite conclusions with defensible reasoning on each side, and the design of the task shaped which conclusion a group reached. The study is 52 pre-service teachers in one course, and the authors ask for their patterns to be read as possible responses to design rather than as a distribution you should expect. A course-level rule does not determine what a group does.

So write the permission at the level of the artifact. Name the phases that are AI-open and the phases that are meant to be worked out without it, and tell students why the line sits there. The scoping review's design logic points the same way: if AI-mediated communication compresses negotiation and collective sensemaking, then the segments where a group builds shared understanding are the ones worth protecting (Wei and Perkins, 2026).

Be honest about the warrant in the staff meeting. Neither review claims that withholding AI improves learning outcomes. That case rests on the structure of the trade-off below, not on a measured comparison.

Make the group submit its AI negotiation

Chen and Zou's central design argument is that the negotiation of acceptable GenAI use should itself become an explicit, assessable outcome. Teams should collectively justify and document how GenAI will and will not be used, rather than leaving the norm to peer pressure or perceived risk. That artifact exists only if the group actually talked, which is what makes it worth points: it converts an unenforceable rule into reviewable student judgment.

Two reasons explain why groups intensify use, and both respond sensibly to a shared grade. Performance: students read the criteria and peer benchmarks and used AI to protect their part of the mark. Perceived safety through norms: a permissive collective climate lowered the felt risk of misuse, so groups used the tool more openly and, in the cooperation-oriented case, more dependently. If you want transparency, a stated classroom norm is more effective than a warning.

Ask for the negative as well as the positive. A statement that records what the group decided not to do, and why, tells you more than a list of tools. It also gives a group that disagrees somewhere to put the disagreement, which is usually the hard part already done.

Do not assume the document reflects a shared understanding. Korchak, Costley and Fanguy (2026) interviewed 10 postgraduate students aged 23 to 39 (mean 27.7) in a scientific writing course, where groups used GenAI through pre-planned strategies or through open, individually driven interactions coordinated in shared documents. One distinctive use was GenAI as an editorial integrator, merging parallel sections into coherent text. Their most pointed observation: students' accounts sometimes contradicted their own written reflections, and one student denied having a group strategy while describing one in writing. A strategy that is not equally visible to every member is not reliably visible to you either.

Sequence the work so it cannot be divided

Wei and Perkins (2026) ran a PRISMA-guided scoping review of 18 English-language studies published between January 2023 and March 2025, analyzed with reflexive thematic analysis and mapped across eight themes. The benefits they report are group knowledge development, idea generation, support for reflective thinking, communication efficiency, task coordination and feedback. The risks are reduced peer interaction and engagement under over-reliance, plus privacy, transparency and accuracy concerns. Their assessment is blunt: the benefits are empirically supported, while the risks around privacy, transparency, bias and accuracy are largely discussed conceptually, and much of the research is short-term or conceptual with little longitudinal work on group dynamics or cognitive development.

The trade-off governs the design. Group work became more efficient, with reduced demand for communication, negotiation and collective sensemaking, a finding the review takes from Lin et al. Efficiency gain and interaction loss can be the same mechanism, which means you cannot take the speed without the loss unless you build the negotiation back in as required work. The review concludes that group-based assessment should shift its focus from product to process.

Chen and Zou show how hard that is to arrange by accident. Three patterns of Learner Agency ran in different directions at once. Cooperation-oriented agency (five groups) intensified use to hold the work together, often feeding peers' contributions into a chatbot to decode them and align their own part; one group rebuilt its workflow as discussion, externalisation to GenAI, collective review, and re-discussion. Normative agency (seven groups) deliberately restrained use, either judging the task to demand situated knowledge AI could not reach ("AI only knows that moment when you type") or treating AI-generated sections as unfair to the groupmates who would carry them. Non-enacted agency (three groups) changed nothing, partitioning work into discrete subtasks on individual platforms while individual students used GenAI in ways they never contributed to the team.

Their rubric already required integration and coherence under a multicultural theme, each member's reflective insight tied to their own classroom contribution, and demonstrated group collaboration. Three groups still divided and conquered. A coherence criterion does not produce collaboration on its own, so change the sequence instead of the wording: put at least one stage where the whole team has to be in the same conversation, and make the output of that stage a deliverable.

Put one interface at the center, and choose it on purpose

Xu et al. (2026) observed 18 students in six groups of three working on a single shared ChatGPT-4 interface for roughly 45 minutes, and interviewed nine further students about asynchronous teamwork. With a shared, visible interface, teams co-constructed collective prompts, ran a recurring surface, evaluate and embed cycle, treated the chat as shared external memory, and openly negotiated AI's role. In asynchronous work, private prompting and output de-labeling produced opaque, privatized information flows that raised the cost of maintaining a shared cognitive model. GenAI's role shifted too, from subordinate assistant to contested teammate, and the system is cognitively involved while remaining contextually unaware of the team's shifting focus.

The practical difference is whether the prompt is a group artifact. A shared document with the prompts and outputs in it gives you something to read and gives the group something to argue with. Private prompting gives each member a different assistant and no common record.

Keep a part each member answers alone

Pair the group mark with an individual component: an oral defense of their own understanding, or a written explanation of any section they did not draft. That is also the honest answer to the free-rider problem, because it grades comprehension rather than authorship, and comprehension is what a group mark was always a proxy for.

Martínez-Peláez et al. (2025) screened 203 studies from 2023 and 2024 in the Web of Science Core Collection and included 22 under a PRISMA 2020 protocol registered in PROSPERO. They describe LLMs acting as catalysts for collaboration: idea generation, organization, peer feedback, simulated rubric-based evaluations and expert reviews, and lower participation barriers. For problem solving they report help with alternative solutions, interdisciplinary perspectives and authentic scenarios. They also note a useful inversion: LLMs often produce incomplete or incorrect responses, which pushes students to question, verify and improve the material. That exchange is what to listen for at the individual checkpoint.

Their limitations travel with the citation: a single database, journal articles only, no attention to Ethics or privacy, the first two years of the technology, and no risk-of-bias instrument applied. Read “catalysts” as a description of observed practice, not a measured outcome.

Detection is the wrong instrument for sorting individual contributions: none of these six studies tests detectors in group settings, and the individual-level problems with detection are documented elsewhere in this knowledge base. Restraint needs interpreting before it needs correcting. Chen and Zou caution that a group declining AI may be avoiding something unfamiliar rather than exercising deliberate self-regulation, and the two call for different responses: one is a teaching problem, the other is a considered position you can grade.

Simulated teammates do not settle the question either. Fang (2026) fine-tuned Large Language Models (LLMs) agents on real participant dialogue (LoRA/QLoRA adapters on LLaMA 3.2-3B) to model 48 participants across 3,824 turns and six thematic codes, then compared real and simulated discourse with Epistemic Network Analysis. The simulated network reached a distance of 0.17 from the empirical network, below the 0.30 threshold, with a permutation p-value of 0.65, statistically indistinguishable, though it slightly overemphasized Technical Constraints and Design links and under-represented Data and Performance Parameters. It is a framework paper with medium confidence, and it supports one claim: participant-specific agents can reproduce realistic collaborative discourse. It does not show that students learn more from simulated teammates.

Form the groups on what members believe, not on who is friends

Whether AI becomes a shared reference point or a lookup depends partly on how much your groups already agree. In Wang et al.’s (2026) study, fourteen pre-service teacher groups worked a 60-minute simulation inquiry with an on-demand metacognitive chatbot. Groups whose members held different preconceptions about the physics routed AI use through conceptual talk, with the AI sitting at the center of their interaction network; groups that already agreed ran a linear query-then-answer path and sustained negative evaluation of the output, which the authors partly attribute to proactive prompts arriving after consensus had formed. Both kinds of group asked the same kinds of questions, so what changed was uptake rather than volume.

Two moves follow, and both are cheap:

- Run a short pretest on the core concept and mix the response patterns across groups, rather than letting students self-select into comfortable ones.
- In groups that converge quickly, keep shared-regulation prompts on demand rather than pushed, because a nudge that arrives after agreement reads as interruption.

Treat it as a hypothesis rather than a rule. That is fourteen groups, one 60-minute task on a single topic, pre-service teachers in one country, and transcripts translated from Finnish before coding.

What instructors and administrators get wrong about this

A clear course policy settles what groups do. Chen and Zou watched groups reach opposite conclusions inside one permissive policy. The task, the rubric and the group’s own reading of the risk decided it.

A collaboration criterion produces collaboration. Their rubric named integration, coherence and demonstrated collaboration, and three groups still partitioned the work and reassembled it. Criteria describe the product; sequencing produces the interaction.

Group work's real problem is free-riding, and AI makes it worse. No study here shows that AI has worsened free-riding, or that any intervention reduces it. The fairness complaint predates the tool: Chen and Zou's restrained students treated generating their own section through AI as unfair to the groupmates who would carry it, and the performance rationale shows students protecting their share of a shared grade. Individual accountability and visible process are defensible on design grounds, and they are not proven fixes.

More AI in group work means better collaboration. Martínez-Peláez et al. describe genuine supports, and Wei and Perkins found the benefit side empirically supported while the risk side remains largely conceptual. The sharpest caution in the review is the randomized evidence showing AI produced more innovative suggestions without significantly raising participants' overall innovativeness, while homogenizing ideas and inviting cognitive offloading. Gains measured during AI-supported group work also have not been shown to transfer to collaboration without the tool.

A shared document means a shared process. Korchak, Costley and Fanguy found accounts that contradicted the written reflections, and strategies that not every member could see. Look for the decision log, not the folder.

Detection can tell you who did what. None of these studies tests it in a group setting, and a group artifact is the worst case for it: several writers, one file, and a revision history that a shared account flattens.

The objections you will hear

"Group work is already unfair, and AI makes it worse." AI changes the shape of the problem, and the fairness complaint was already inside the group before anyone opened a chatbot. What is new is how cheaply a member can produce a plausible section alone. An individual checkpoint plus a visible process has a design rationale behind it. Neither has been shown to reduce free-riding.

"I have 300 students. I cannot run oral defenses." Then do not run 300 of them. Put the individual explanation in writing for everyone, and sample oral checks where the submitted work does not match earlier work. The point is that every member knows a conversation is possible.

"I cannot grade process." You are already grading a proxy for it and calling the result product quality. Grade the artifact that exists only if the process happened: the negotiated AI-use statement, the decision log, the short individual explanation. All three are bounded and checkable, and the rubric lines are no vaguer than the ones you already write for coherence.

"Students will prompt privately whatever I specify." Some will, which is why the shared interface and the submitted statement carry more weight than the rule. Xu et al. found that a visible shared interface changed what teams did with the tool, and Chen and Zou found that a permissive climate raised open use. What you cannot do is infer the private case from the group file, so design for the visible one.

"Isn't this a policy question for the department?" The department can set the default. It cannot sequence your assignment. Chen and Zou's finding is that the same institutional policy produced different group behavior depending on the task, which puts the decision in your hands whether or not you wanted it there.

What to do this week

1. Add a half-page, jointly authored AI-use statement to the next group brief, and give the reasoning marks. Include a line for what the group decided not to use AI for.

2. Find the stage of the task that can be cut into independent pieces and reassembled. Resequence so one stage requires the whole team at once, and make that stage produce something you collect.

3. Add one individual checkpoint to the rubric: a short written explanation of a section the student did not draft, or a two-minute oral defense.

4. Name the AI-free segments in the brief and say why they are AI-free, in one sentence each.

5. Decide where the prompts will live. If the answer is “wherever each student keeps them,” you have chosen private prompting without saying so.

Where to go next

Group Work and Collaborative Learning carry the underlying evidence on group assessment and on what makes collaboration productive. How Do I Write a Course AI Policy and Communicate It to Students? covers the course-level wording students actually read, How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? covers the assessment redesign this sits inside, and Academic Integrity is where the misconduct side is handled.

Connected FAQs

- How Do I Write a Course AI Policy and Communicate It to Students?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

How Should I Incorporate AI Literacy into My Course?

Your program review says graduates need AI literacy, and nobody has told you what that means for the term you actually teach. Or the course you inherited has a session labeled “AI tools” that no one can defend, and you have to decide whether to keep it. Or you have watched a student paste a prompt, accept the first answer and submit, and you want the next assignment to interrupt that.

The bottom line: add a step to work you already grade, where students commit to their own answer first, compare it with the tool’s, and defend what they kept. Literacy that lasts is disciplinary, repeated, and assessed as judgment rather than recalled as a definition.

The short version

1. Attach the work to a task you already grade. A standalone module in week two is the weakest version of this.

2. Make students produce an answer before the tool produces one, and make the comparison the assignment.

3. Grade the evaluation and repair of AI output, not the generation of it. That competence does not transfer on its own.

4. Name the errors AI makes in your field, in your field’s language, and repeat the exercise more than once.

5. Assess judgment with a case, not confidence with a survey.

Do not add a lesson, add a step to work you already grade

The default institutional move is a standalone module, usually early in the term, on how large language models work and how to write prompts. The AI Literacy synthesis argues for a different arrangement: students develop more useful literacy when they use, question, verify, critique and decide about AI inside authentic course tasks, repeatedly. Movement toward critical evaluation is most evident where those experiences are sustained and embedded rather than delivered once (A Practical Five-Stage Continuum for AI Literacy in Higher Education).

The quantitative evidence points the same direction. A meta-analysis of 59 AI-literacy interventions found the largest effects for integrated and reflective pedagogies. It also cautions that knowledge-focused interventions show larger *measured* effects than those targeting skills, attitudes or ethics. Keep that in mind when you choose what to measure.

The other reason to build on existing work is workload. A 2026 synthesis of 72 empirical studies of generative AI in computing education finds the strongest, most replicated result in the corpus is that AI reliably raises short-term completion and reduces time on task, across 36 studies. Those gains “do not transfer to independent performance,” according to 21 studies. Students complete more while understanding less unless critical engagement with the output is structurally required (Generative AI in computing education: a systematic review and a framework for responsible integration).

Benefit also depends on prior knowledge. Well-prepared students convert AI help into durable skill. Under-prepared students risk using it as a crutch that removes productive failure. The review’s default

recommendation is graduated access: AI-free foundations first, then guided use with mandatory explanation tasks, then reflective critique. That sequence fits an existing course far more easily than a new unit does. Learning Design is where to work out the staging, and Curriculum Design is the program-level version of the same problem.

Make them commit before the tool answers

Think first, AI second. Ask students to form an initial interpretation, solution, argument, prediction or draft before they consult anything. They then compare their thinking with the output, name the agreements and discrepancies, verify the claims, and decide what to adopt. That keeps the tool from substituting for the cognitive work the assignment exists to develop, which is the concern behind Cognitive Offloading and AI Misuse and Learning Harm: immediate performance can improve while independent learning suffers.

What happens without that structure is well documented. Yan et al.'s presage-process-product study of 38 undergraduates found that 76.32% relied on a single-turn ask, get an answer, stop pattern, and 78.94% integrated generative AI only before starting or after drafting. Even mastery-oriented students defaulted to surface processes. The authors call the result an efficiency paradox, where speed is gained at the cost of the cognitive work that builds schemas, and quote a student: "the speed at which you forget it is also very fast." They locate the cause in an institutional vacuum, where instructors prohibit copying but rarely teach productive use (From cognitive outsourcing to reallocation).

Requiring process artifacts is the cheap fix. The dialogue history, a reflection note, a revision log: any of these makes the workflow visible, gives Metacognition something to attach to, and turns self-regulation into something you can grade. It also gives you the evidence a misconduct conversation would otherwise lack.

Put points on the critique

Students can annotate an AI response for factual errors, unsupported claims, bias, missing perspectives, inappropriate confidence or weak disciplinary reasoning. They can hold it against the readings, the empirical evidence, professional standards or the course rubric.

The pattern worth building a task around is plausible but imperfect output plus a student in the critic's or editor's chair. Finding the mistakes is one of the more reliable routes to calibration and higher-order thinking.

Treat that as a competence you teach, because it does not arrive with subject knowledge. In the computing-education synthesis, students performed significantly *worse* on correcting AI-generated code than on traditional programming examination tasks. That is direct evidence that evaluating and repairing output does not transfer automatically from general disciplinary skill, and that without instruction students will resubmit incorrect work without noticing. The review folds this into its VIE framework (Verification, Implementation, Equity) and argues that critical engagement should be a graded, observable component of student work, calling it "the common mechanism linking every effective intervention in the corpus."

Practical version: one rubric line for the error you expected them to catch, one for the repair, one for the justification. If the critique carries no points, it gets three sentences on the way out the door.

Make it specific to your field, and repeat it

Generic rules such as “check AI for hallucinations” are weaker than showing students what unreliable output looks like in your discipline. Fabricated citations in history. Invalid assumptions in economics. Misleading interpretations of experimental evidence in biology. Poorly justified design decisions in engineering. Superficially fluent but methodologically weak writing in psychology.

Write that list yourself, from your own marking, before the term starts. Five examples from your field will do more work than a general checklist, and they double as the error bank for the critique task above.

Repetition is the other half. One exercise in week three produces a student who has done the exercise. The same exercise in three assignments, on different material, produces a habit, and the cases in this corpus that show discipline-specific integration are the ones where the practice recurs across a course rather than sitting in a single session.

Borrow the models that already exist in your field

You do not have to invent the design. Several are documented, and each is small enough to copy.

Economics students solve a problem first, obtain a GenAI response, compare it with their reasoning, critique the AI, reflect, then discuss with peers (Fostering Generative AI Literacy in Economics).

Psychology students evaluate a ChatGPT-generated media release against a course rubric, identify the weaknesses, and revise it, which develops disciplinary and feedback literacy in the same task (Using Generative AI to Promote Psychological, Feedback, and AI Literacies).

Biology integrates the activities into disciplinary learning rather than teaching a separate technical topic (Integrating AI Literacy Education in a Biology Class). Database and design coursework uses failure analysis as the learning activity, with students analyzing AI-generated errors and iterating on prompts and solutions (The Pedagogy of AI Mistakes). The LearnAI model embeds just-in-time AI co-creation across disciplines instead of running one generic module (LearnAI: Just-in-Time AI Co-Creation Across Disciplines).

One caution comes with a number. A redesigned introductory particle-physics course allowed generative AI as an explicit partner on research-shaped problems, and an unaided written examination returned a mean of 20.6 out of 80, with only two students reaching 40 (AI in particle physics education). Assisted performance and independently retrievable knowledge are distinct achievements. The authors argue for teaching AI literacy, including verification and treating AI as a teacher rather than a copier, early, alongside dedicated unaided practice. Physics education has the fuller case.

There is also a version where students make something for a real audience. Burriss et al. had 22 eleventh-grade students compose video public service announcements about the AI Ethics issues they lived with: school surveillance, electronic “hall passes,” and algorithmic plagiarism accusation. The unit drew on Critical Posthumanist Literacy and multimodal composition. Students portrayed harm as emerging from tangled human-machine responsibility rather than a villainous tool, flipped the cheating narrative toward adults’ overreliance on faulty AI, and closed on Learner Agency (“the solution is in our reach”). The authors place storytelling and collaborative production at the center of critical AI literacy pedagogy, and argue that composing *about* AI for a real audience develops critical competence that competency scales cannot see

("Young Scholar[s] on the Beat"). That claim is an argument from one unit with 22 students, so read it as a design idea rather than an effect size.

Keep it social where it is cheap

Collaboration is the least expensive way to raise the cognitive demand of an AI task. The ICAP framework moves students from passive exposure toward active, constructive and interactive engagement. In practice: pairs compare prompts, groups debate whether an answer is trustworthy, teams jointly revise an output, or one student explains to another why a suggestion was rejected.

The evidence supports cognitively active and collaborative designs (Systematic Review of Collaborative Learning Activities for Promoting AI Literacy). The cost is a discussion structure, not a new assessment.

Assess judgment with a task

Students overestimate how well they can evaluate AI, and a self-reported confidence item will confirm the error rather than expose it. The knowledge base documents a significant mismatch between self-reported and performance-based AI literacy, and recommends performance assessment (AI Literacy Assessment: Self-Reported vs Performance Misalignment; GLAT).

Instead of a confidence item, give them something to do: detect an error, verify a source, improve an output, explain a limitation, justify why a particular use of AI is appropriate for a particular task.

Scenarios work well as the instrument, and they are easy to write. Reed et al. (2026) put vignettes to undergraduates: using AI to improve grammar in one's own draft, generating search terms before doing the reading oneself, submitting an AI-generated reflection journal without personal input, minimally editing a generated assignment. Students converged on the clear cases and diverged most where the tool did part of the intellectual work. That divergence is exactly the boundary your policy is silently relying on, so running the vignettes tells you where your course needs to say something explicit. It also measures judgment about a case rather than proficiency in the abstract.

Decide what the course cannot fix

A few limits are worth stating before someone else raises them.

Prompt engineering is not AI literacy. Students can become technically proficient while remaining poor judges of output, and some skill-oriented dimensions of AI literacy are positively associated with reported AI dependency. Operational training without self-AI Regulation in Education, academic confidence and metacognitive support can increase reliance rather than reduce it.

Interaction is a skill the tool does not supply. Brunnström and Palmqvist's eight-round demonstration of a "naive student" using a chatbot on a take-home examination found the default output "polished but pedagogically thin," and that reaching a usable learning loop took eight rounds of learner interventions ("simplify," "this is overwhelming, can you condense it?"). They name the capacity AI-interaction literacy, meaning the ability to steer, evaluate and learn from iterative interaction. Their equity conclusion is the sharp one: because unguided use imposes a competence that is unevenly distributed, generative AI "may be most

beneficial to already advantaged students" (AI-interaction literacy; How is AI impacting students?). Teaching the interaction is an equity measure as much as a pedagogical one.

Better prompting does not fix the model. In research on contextual sycophancy, AI-literacy and prompting instruction reduced direct mirroring of users' errors without completely preventing those errors from propagating into later advice (The Hidden Cost of Contextual Sycophancy; AI Sycophancy). Students need to know that instruction changes what they get, not what the system is.

Equity runs through all of it. Students arrive with different access to paid tools, different prompting experience, different language backgrounds and different digital confidence. Requiring sophisticated use without equitable access and foundational support turns prior exposure into an academic advantage, and access, skills and outcomes are separate dimensions of the digital divide. Before you design a task that requires a paid tool, check who in the room actually has one.

What instructors get wrong about this

AI literacy means teaching prompting. Prompting is the visible part. Students can become technically proficient with these tools while remaining poor judges of what comes out of them, and the dependency finding above points the same way.

One session covers it. A session can introduce vocabulary. The evidence for repeated practice on real course material is stronger, and the meta-analysis of 59 interventions found the largest effects where the work was integrated and reflective.

Students who use these tools daily can already evaluate output. Yan et al. found 76.32% of 38 undergraduates in a single-turn pattern, and the computing synthesis found students significantly worse at correcting AI-generated code than at ordinary programming examination tasks. Familiarity with the interface is not calibration.

The activity has to be about the tool. The stronger designs are about the discipline, with the tool inside it. Economics students critiquing an AI solution, psychology students revising a generated media release: the object of study stays the subject matter.

Critical evaluation transfers from subject knowledge. It does not, which is why the computing result matters. A student who can write correct code is not automatically able to diagnose incorrect code someone else wrote, and the same gap appears in prose.

Confidence is a usable proxy. Self-report and performance diverge in this literature, and the divergence is systematic enough that the knowledge base recommends performance measures. Ask for a demonstration.

What will come back at you

"There is no room in a content-heavy syllabus." Then do not add content. Attach one critique step to an existing assignment and count it once. The economics and psychology designs above take the assignment students already had and change what they do with the AI output.

"My students already know how to use ChatGPT." They know the interface. The 76.32% single-turn figure is what fluency looks like without instruction, and it is the pattern your course is meant to interrupt.

“Teaching them to use AI will just encourage more use.” It can, and the honest version of that risk is in the literature: skill-oriented training without metacognitive support is associated with greater reported dependency. That is an argument for pairing the training with reflection and unaided practice, which is what graduated access is for.

“Reflection and critique are too subjective to grade.” They are subjective when the rubric says “thoughtful.” They become gradeable when you name the error to be caught, the repair, and the justification, which is the same move as any other rubric line.

“Our students are underprepared, so AI will widen the gap.” The evidence supports the worry. Prior knowledge conditions whether AI help becomes skill, and the interaction study concludes the tools may favor already advantaged students. Graduated access, AI-free foundations and taught interaction are the responses the corpus offers, and each is something you can set up this term.

“This is the library’s job, or the writing center’s.” Those services can teach generic evaluation. Only your course can teach what a weak argument looks like in your discipline, and that is the version students carry into your assignments.

What to do this week

1. Pick one assignment you already teach and add a commit-first step: outline, prediction or draft before any tool opens.

2. Write down the three errors AI most often makes in your field, using examples from your own marking.

3. Turn one of them into a critique task with three rubric lines: catch it, repair it, justify the repair.

4. Replace one confidence question on your next survey or exit ticket with a two-sentence scenario and ask what the student would do.

5. Decide and state the access rule for your course, including which tools are permitted and whether any require a paid account.

Where to go next

What is the evidence on AI literacy interventions in higher education? is the honest assessment of how strong this base is and where it thins out. How Is AI Impacting Students? covers the student side, How Do I Teach Students to Verify AI Output? covers the verification habit students need, and How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures is the place to go if you are building the measure rather than the lesson. Cognitive Offloading explains the mechanism underneath the commit-first rule.

Connected FAQs

- How Do I Teach Students to Verify AI Output?
- How Is AI Impacting Students?
- What Is the Evidence on AI Literacy Interventions in Higher Education?

How Can AI Save Me Time as an Instructor?

It is Thursday night in week eight. Three lesson outlines are due Monday, the lab reports are half marked, and Friday's department meeting has an item on what everyone has done with AI since the August training. A colleague says the tool halved her planning time. You tried it twice, spent forty minutes repairing a worksheet, and came away thinking the whole thing was oversold.

Both of you are describing the same tool. It saves time on drafting material you were going to edit anyway, and it costs time when you aim it at a judgment about a particular student. Whether the saving becomes yours depends on a decision most instructors never make: what the recovered hours are for.

The bottom line for the meeting: hand over the first draft and keep the judgment. Lesson outlines, worked examples, discussion questions, formative quiz items, alternative explanations, rubric wording and routine administrative text are work you can specify, check and correct. Objectives, final grades and any call about a specific learner stay with you. Name what the freed hour buys, because the evidence on saving time is evidence about where the time goes.

The short version

1. List the tasks from last week that produced a document you then edited. Those are your candidates.

2. Start with structured material you can check against your own specification: exit tickets, quiz items, worked examples, a second explanation of a hard concept.

3. Write down where the recovered hour goes before you recover it.

4. Time three recurring tasks for two weeks. Your sense of the saving is unreliable in a specific, documented way.

5. Keep objective-setting, summative grades and individual student calls on your side of the line.

Start with work you were going to rewrite anyway

The strongest number in this knowledge base comes from a randomized trial summarized in How AI Is Changing Teaching Workflows. Two hundred fifty-nine science teachers using ChatGPT spent about 69% as much time on lesson preparation as the control group, a cut of roughly 31%, and blind expert reviewers found no detectable loss in quality. The teachers reallocated rather than banked it, moving the time into planning, marking and student-facing work.

A second dataset in the same work, more than 104,000 messages from over 15,000 educators, shows why the saving lands in odd places. The average prompt touches 1.7 categories at once, so a single request for a lesson plan comes back carrying differentiation and a quiz the teacher had not thought to ask for.

That is reallocation rather than reduction: what you gain from generative AI is the difference between a blank page and a draft specific enough to argue with.

Match the task to what the tool does well

Quality is uneven in a pattern stable enough to plan around. Blind reviewers preferred AI versions of lesson conclusions and exit tickets 59.7% of the time over materials designed by professionals, and preferred AI material for high school content 59.2% of the time. The saving also grows where your confidence is lowest: teaching outside your own subject is the case with the widest gap between what the tool hands you and what you would have written alone.

Two categories run the other way. On elementary-level material, humans were preferred about 65% of the time for developmental appropriateness. Targeted scaffolds for multilingual learners and students in Special Education came back neutral rather than wrong, which is worse than it sounds, since a neutral scaffold is one you rebuild from the start.

The test that predicts this before you spend an evening on it: can you state the specification precisely enough to check the output? An exit ticket on one objective, yes. Whether a paragraph suits a particular nine-year-old who reads two years behind her class, no.

Give the recovered hour a destination

The clearest evidence that the saving is real, and that it does nothing on its own, comes from a large experiment across 178 schools and roughly 19,000 high school seniors on AI-automated essay feedback. Students whose feedback came from the system gained as much as students marked by people. The human graders cost about $0.85 an essay and added no measurable benefit on top.

In the AI classrooms, students had about 35% more one-on-one conversations with teachers about writing and wrote 30% more essays. Teachers' at-home work hours fell 20%, and the share reporting their time as "very insufficient" dropped from 23% to 9%. The largest learning gains landed on the most complex writing task, the kind AI is least able to evaluate, because the teacher now had hours to spend on it.

The caveat is the sentence to carry into the meeting. The bottom quartile showed no improvement. Students furthest behind gained nothing from a teacher who merely had more room in the day, so where the hours go is the whole argument, and equitable reallocation belongs in the plan from the start rather than in a review at the end.

Measure the saving rather than feel it

Time saving is the claim instructors most reliably get wrong about themselves. Across three pre-registered studies with 2,691 participants, people underestimated how often they used AI and overestimated the time and effort it saved, reporting tasks as faster and easier while objective measures showed no difference. Using the tool earlier in a session predicted using it more later, so the error compounds inside a single afternoon (The efficiency-gain illusion: People underestimate the rate of AI use and overestimate its benefits on simple tasks).

What helps is metacognitive calibration, and the cheap version is a log. For two weeks, note start and end times on three recurring tasks, one with the tool and two without. Expect one task with a large genuine saving, several with none, and a couple where the tool added a review step that ate the gain.

Effort and capability also come apart. A within-subjects study of 13 higher-education teachers found AI access cut the perceived cognitive effort of learning design from a median of 6.33 to 3.33 (p = .004), while prompting training layered on top did not improve the quality of the designs (When Teachers Use AI Chatbots and Are Trained for It: Impact on Learning Design Quality and Cognitive Effort). Less strain on a Thursday night is a real benefit. It is not evidence the designs improved.

Keep objectives and final grades on your side

Participatory design work with six secondary teachers produced a boundary worth copying. They designed the system as a bounded expert: capable inside a narrow domain, working under supervision. They wanted help presenting content, generating practice problems and giving formative Feedback, and refused to hand over objective-setting or summative Assessment, insisting on override for ambiguous cases. What they protected is the core of the teacher's role: deciding what is worth learning and judging whether it was learned.

Grading is the task with the largest apparent payoff and the weakest portability. The OpRaise benchmark ran three frontier models against 761 authentic undergraduate psychology essays from 125 students at three UK universities, with 27 prompt configurations per model. Agreement with human degree bands ran from 35% to 65% depending on institution. Marks compressed toward the middle, so the strongest and weakest essays were graded least accurately, and the models agreed with each other far more than with human markers. The authors' central finding is that evidence gathered in one context does not transfer to another.

You can use automated essay scoring if you validate it on your own subject and students, and keep the decision with a person. AI feedback quality says what to check: speed and volume are not the same as usefulness, and the pedagogical judgment about which comment a student needs next stays with you.

What instructors get wrong

"The 31% is my number." It is 259 K-12 science teachers on lesson preparation. The direction travels; the size does not. A seminar built on discussion may save less, and a lab course with safety constraints may save nothing on the part you most wanted help with.

"Saving time is the goal." The Brazil experiment is the counterexample. Hours came free and the bottom quartile gained nothing. The goal is what the hours buy.

"A good draft means I can hand over the next step too." The six teachers drew their line at objectives and summative judgment for a reason. Quality on an exit ticket says nothing about whether the tool can decide what the exit ticket should assess.

What will come back at you

"I tried it and the output was generic." Most teachers in the research took the first result and edited it by hand rather than iterating with follow-up prompts. A second and third turn that supply your grade level, your reading, your last three quiz items and an example of what good looks like changes the output more than switching tools does. AI Literacy is the cheap investment, and prompt refinement is where it pays.

“If I get faster, the time will be refilled with meetings.” Likely, and the most common way a saving disappears. Put the destination in writing where your chair can see it, before the space fills.

“AI feedback shortchanges the students who struggle most.” The bottom quartile in Brazil gained nothing, and that is the strongest caution on this page. Pair the saving with a deliberate use. The 35% increase in one-on-one conversations is what those classrooms did with the hours, and that was a choice the teacher made.

“Grading is where my hours actually are.” It is, and it is also where the tool is least portable across institutions. Validate locally or leave it alone.

“This deskills the profession.” The Pishtari result is the honest version: perceived effort fell, and the added training did not improve design quality. Effort saved is not capability gained, and the six teachers’ boundary is a reasonable place to hold the line while you learn which of your tasks is which.

What to do this week

1. Write down the five tasks you did last week that ended in a document you then edited.

2. Pick the one with the clearest specification and draft it with the tool, timing both versions.

3. Put the recovered time into a named slot on your calendar: a conversation with a student, a second feedback pass, or reading a set of drafts properly.

4. Write your no-go list and keep it visible: objectives, final grades, anything that turns on one student’s needs.

5. Keep the log for two weeks, then decide which two tasks are permanently yours to hand over.

Where to go next

How Can AI Help Me Give Better Feedback at Scale? takes the feedback question further, and What Competencies Do Faculty Need in Regard to AI? with How Do I Design Faculty Development for AI That Actually Changes Practice? covers what a department can build so this stops depending on individual experimentation. How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? and How Can I Reduce AI Cheating in My Course? handle the assessment consequences. How AI Is Changing Teaching Workflows. is the article behind the preparation numbers, and human oversight is the principle this page turns on.

Connected FAQs

- How Can AI Help Me Give Better Feedback at Scale?
- What Competencies Do Faculty Need in Regard to AI?

How Can AI Agents Support Students and Instructors?

A vendor demo runs for forty minutes. The agent reads the syllabus, drafts next week's quiz, flags three students who have not opened the reading, and offers to email them. Your provost wants a licensing decision by the end of the month.

An agent plans, calls tools, keeps context, splits work into subtasks and adapts across turns, which is more than a chatbot does. The student-side and instructor-side roles that opens up are real. The evidence does not show that more autonomy produces more learning: in the one head-to-head study here, an agent and a chatbot tied. Put autonomy where a person checks the output, keep the planning with the learner, and score teaching quality against your own rubric.

The short version

1. Name the job before the product.

2. Start on the instructor side, where a teacher already inspects the work.

3. Treat added autonomy as a cost until evidence says otherwise.

4. Keep the planning and judging with the learner, because those are what the assignment exists to build.

5. Score the agent against your rubric, and schedule an unassisted check before the pilot ends.

Pick the job before you pick the agent

Agentic Workflows in Education names four recurring capabilities: reflection, planning, tool use and multi-agent collaboration. Each one adds a cost alongside the possibility, in interpretability, coordination, trust, latency and oversight.

The student-side roles run from adaptive tutoring and study planning through formative feedback, guided problem solving and practice generation to prerequisite recommendations and reflective metacognitive prompting. The instructor-side roles cover material development, question generation and validation, feedback triage, course analytics, instructional design, resource retrieval and orchestration of specialized sub-agents.

Two of those are safer early, because both produce an artifact a person reads before students do: a question generator paired with a validator, and drafting that a teacher edits.

Start where a human already checks the work

Tutor CoPilot, the first randomized controlled trial of a human-AI system in live tutoring, gave novice tutors real-time guidance drawn from experienced tutors' reasoning, across 900 tutors and roughly 1,800 students. Students of tutors with access were 4 percentage points more likely to master topics, rising to 9 points among the lowest-rated tutors, whose students caught up with those of better-rated tutors in the control group. It cost about $20 per tutor annually, and analysis of 550,000+ tutoring messages showed tutors shifting from giving answers to asking guiding questions. That is AI augmenting the teacher.

The agent did not teach the student. It fed a human mid-conversation, and the human decided what to say. A person in the loop and an outcome close to the work are what make the result portable to another course.

Do not assume more autonomy buys more learning

A study of 130 students in an e-commerce course found both generative AI chatbots and agents rated above traditional e-learning on learning and personalization, with no significant difference between the chatbot and the agent. Added autonomy, no added value on those measures.

That study's framework treats agents as bounded, human-supervised learning partners, with goals, checkpoints and final decisions left to people. Beyond the Agent Label makes it a AI Governance rule: autonomy should not exceed the maturity of the evidence or the strength of accountable human control, and the evidence is strongest at artifact-level outcomes, weakest at durable learning and equity.

The learner-side risk runs the same direction. An agent that plans and monitors for a student removes the practice that builds self-regulation and invites offloading. Best-practice guidance asks for intentional friction, Scaffolding that fades and human oversight. Productive friction has working examples. Constructive-conflict agents that argue with a weak design improved design outcomes in the research reviewed. Simulated peers support collaborative learning and Socratic probing, and clinical simulations let learners rehearse where a mistake is cheap.

The test for any of them: after the session, what can the student do that the agent was doing before? Handing over judgment costs the student the practice of using it.

Check the agent against your own judgment

Eight AI teaching agents deployed across a medical curriculum were ranked differently by platform-generated scores and by an independent expert rubric. The platform's third-ranked agent came last on teaching quality. Platform scores index student performance, which moves for reasons that have nothing to do with teaching.

Ask what a dashboard number counts, who wrote the rubric behind it, and what a low score would look like in student work. Pedagogical safety belongs in the same review, since a chain of agents makes it hard to say which component is accountable when an answer is wrong.

Plan for the switch-off

Randomized trials show that brief AI assistance can depress later unassisted performance, and the interval after withdrawal, cognitive washout, is almost entirely unmeasured. The synthesis behind this page draws on a scoping review of 474 studies and finds the work concentrated in higher education, STEM, short-term designs and text-based tutoring, with only a minority grounded explicitly in educational theory. A pilot that ends when the license ends has measured the wrong window.

What administrators get wrong about this

An agent is an upgraded chatbot, so the upgrade should show in outcomes. In the 130-student comparison both AI conditions beat e-learning and neither beat the other.

The dashboard ranks teaching quality. It ranks student performance, and eight agents produced a ranking that inverted the third and last places against an expert rubric.

Autonomy is the feature to buy. The proportionality rule runs the other way, and the evidence is thinnest where autonomy is largest.

Access closes the equity gap. Unequal access to capable agentic systems can widen it, and an agent reproduces training-data bias at scale.

What will come back at you

“Students will just let it do the work.” Some will, and the architecture decides how easily. Agents that plan and draft for the student invite it. Agents that require an attempt, then ask a question, do not.

“The vendor’s evaluation says it works.” Ask what the number counts. If it is platform-measured student performance, it measures the students as much as the agent.

“Nobody can say which agent is accountable in a chain.” True of most current deployments. Name an owner for the chain, log which component produced which output, and keep a human checkpoint before anything reaches a student record.

What to do this week

1. Write the job and the outcome you will judge it by, one sentence each, before the next vendor call.

2. Score one agent’s output against your rubric on ten pieces of real student work, and keep the scores.

3. Add a dated, owned unassisted task to the pilot plan.

Where to go next

What Are Best Practices for Developing an Effective AI Tutor? covers the student-facing build from objective to help ladder, and What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? covers whether the thing worked. Intelligent Tutoring and AI Literacy supply the design vocabulary this page assumes.

Connected FAQs

- What Are Best Practices for Developing an Effective AI Tutor?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?

Assessment, feedback and integrity

The largest cluster, because this is where the evidence is sharpest and where the consequences land on a student record.

How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?

You are probably holding an assignment that worked for years and now returns work you cannot defend. The grade says A; the artifact may be mostly the tool's. Or a student is contesting a low mark on grounds you cannot check, or your program is rewriting its assessment policy and asking you what should change in your course by next term.

The short answer: decide what the grade is meant to be evidence **of**, put at least one step in the assignment that the student completes without the tool, and make the rubric pay for the reasoning rather than only the product. Redesign that skips the second and third steps changes how work is produced without changing what the grade can support.

The short version

1. Write down which capability the grade represents. Independence, appropriate use of AI, or the ability to direct and judge AI are three different constructs, and one artifact cannot be evidence of all three.

2. Add one authenticated step to every high-stakes assignment: a short oral check, an in-class application, a live demonstration, or an annotated rationale. One is usually enough.

3. Set the AI boundary per task step, not per course. Inventory what the student does at each step and ask what specifically you are assessing there.

4. Put process evidence in the rubric with real points. If the rubric still rewards only the artifact, students will optimize for the artifact.

5. Assume the student most tempted to conceal, not the most conscientious one, and check which choice your rules make easiest.

Decide what the grade is evidence of

Begin by stating explicitly what capability the grade is supposed to represent. Are you assessing what a student can do independently, what they can accomplish appropriately with AI, their ability to evaluate and direct AI, or some combination of these? The knowledge base's Assessment Validity treats this as a validity problem: a polished artifact is no longer sufficient evidence that the student possesses the capability apparently demonstrated by that artifact. This is the assessment-side half of the same argument; the enforcement-side half is in How Can I Reduce AI Cheating in My Course?, and the general validity framing runs through What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?.

Say the answer in the syllabus, in the assignment sheet, and in the rubric. Students read three documents and comply with the one that is most specific. "AI use is permitted with acknowledgment" is not a statement of what you are measuring, and it gives a student no way to know whether the permitted use undercuts the thing you are grading.

The risk of construct substitution

The article From Authentic Products to Authenticated Processes calls the resulting risk **construct substitution**: the assessor attributes an AI-mediated product to the student and inadvertently measures the tool's capabilities rather than the student's. Its recommended response is to make the student's reasoning, judgment, verification, iteration, and responsibility visible through such approaches as staged submissions, annotated decision rationales, process records, feedback-use statements, oral defenses, and other forms of authenticated process evidence.

That list is a menu, and which item is cheapest depends on your class size. For a section of 25, a five-minute oral check per student per major assignment is roughly two hours of marking you may already be spending. For a lecture of 300, staged submissions and annotated rationales scale where oral defenses do not, and a sampled oral check on the work that looks anomalous is what remains practical. Choose the option you can still keep running in week ten.

Put one authenticated step in every assignment

In practice, a strong assessment architecture often combines an **AI-enabled authentic task** with some form of **independent verification**. Depending on the discipline, that might include a brief oral explanation, in-class application, live demonstration, annotated portfolio, short unassisted component, or questioning about key decisions.

The Authentic Assessment concept also stresses realistic intellectual work, cognitive challenge, student agency, feedback, and social or professional authenticity. Hardening a task against AI without making it more worth doing leaves you with the same assessment and extra work.

Walk the assignment step by step and set the boundary there

The task-level method that makes this tractable is the one McCorkle documents: inventory every step a student performs, ask of each step "what, specifically, am I assessing?", and derive the AI boundary from the answer, which is also how the expectations behind How Can I Reduce AI Cheating in My Course? become explicit and enforceable.

Run it once on your most contested assignment and write the output into the assignment sheet. A typical result separates cleanly: the early retrieval and drafting steps are where the construct lives and where the tool does the damage, while formatting, reference checking, and language editing are steps where tool use is invisible to your construct and probably should be allowed outright. Blanket permissions and blanket bans both fail because the answer genuinely differs by step.

Make the rubric pay for the process

Mohamed and Temimi reframe the same problem as one of **imperfect information** rather than morality: the student knows how the work was produced and the institution sees only the artifact plus partial traces, so the design question becomes *which student response each assessment environment makes most attractive*. Their response-region model compares three choices, no AI use, disclosed use, and hidden use, and shows that

rules, monitoring, disclosure, and redesign operate through different channels and succeed only when the most attractive response aligns with the assessment's purpose.

Two results bear directly on architecture. Deterrence runs through a detector's **discrimination** between hidden use and legitimate work, not its raw catch rate, so when false positives rise faster than true positives stronger monitoring can make concealment relatively *more* attractive. And redesign moves students toward responsible use only when the rubric actually rewards process evidence; otherwise it stays cosmetic. Their practical rule is to design for the student most tempted to conceal rather than the most conscientious one.

If a rationale paragraph, a revision log, or a reflection on a rejected AI suggestion carries no points, it will be written in five minutes and read by nobody. Give the process evidence enough weight that a student who skips it loses more than they gain by skipping it, and describe what good process evidence looks like with the same specificity you use for the product.

Per-student task variation is capability-conditional, not free

One popular no-surveillance architecture is **per-student task variation**, where each examinee gets a surface-distinct but construct-equivalent version of the same task so answers cannot usefully be shared. VARIA, a Benchmark of 600 generated variants across 60 condition cells, found frontier models clustering tightly on a joint integrity score (0.81-0.88) while non-frontier references collapse to 0.50-0.55, and that no single prompting strategy optimizes surface diversity and construct equivalence at once. Variation at scale cannot be assumed from prompting alone, so an institution should validate its own model and prompt pair before treating the guarantee as real.

For a course-level decision that means one test before you commit: generate a set of variants from one of your own tasks, have a colleague mark two of them for the same capability, and compare. If the marks diverge on the variants, the equivalence claim is not holding for your task and the shared-answer protection is paid for with unfairness.

Redesign rarely happens assignment by assignment

In a qualitative study of 12 academics and 17 students at a large Australian university, Nicola-Richmond et al. found both groups agreed assessment must change but stressed systemic friction: long lead times, large-cohort accreditation constraints, workload and cost. They concluded that redesign *takes a village*, meaning a program-wide team combining assessment-design, generative AI, subject-matter, industry and evidence expertise, with GenAI-literacy and assurance-of-learning points placed strategically across a qualification. If you are one instructor with one course, that finding is a warning about what will slow you down and a reason to bring the program lead into the first conversation rather than the last one.

The purpose matters as much as the mechanics. El Khoury and Ma argue that reform organized only around preventing misconduct is too defensive and propose **joyful assessment**, safe, emotionally responsive, empowering and supportive of student Learner Agency, in which integrity is a *consequence* of good design rather than its starting point. Their worked example uses an instructor-built AI agent to rehearse students before judgment and to produce a rubric-aligned evidence report, but the division of labor is stated plainly: the AI organizes evidence, the instructor interprets it.

What will come back at you

“I do not have the hours for oral checks.” Then do not run them on everything. One authenticated component in the highest-stakes assignment, plus a sampled check on work that looks inconsistent with earlier submissions, addresses most of the risk at a fraction of the cost. The scalable items are staged submissions and annotated rationales.

“Accreditation and program approval will not move that fast.” The study above names long lead times and large-cohort accreditation constraints as the central friction. A single course can change what happens inside an existing assessment without changing its name, its weight or its learning outcomes, and that is usually enough to start.

“This penalizes anxious students and students with disabilities.” It can. Live oral components need accommodations planned in advance, a choice of format where the construct allows it, and attention to linguistic difference and assessor bias. Verify the capability, not the performance conditions.

“We should just buy a detector.” The discrimination result argues against it as the spine of the design: if false positives rise faster than true positives, stronger monitoring makes concealment relatively more attractive. Detection may have a place in a response that also redesigns the task, and Should We Use AI Detectors? covers that argument.

“Students will use AI anyway.” They will, and the design question is which response your assignment makes easiest. If disclosure costs the student nothing and the rubric pays for process, most of them take it; if disclosure invites suspicion, concealment becomes the rational choice.

What to do this week

1. Write one sentence naming the capability your next major assignment grades. Put it on the assignment sheet.

2. Pick the single cheapest authenticated step you can sustain, and add it to that assignment.

3. Inventory the assignment’s steps and mark each one as construct-bearing or not. Allow AI where it is not, restrict it where it is.

4. Add process evidence to the rubric with points attached, and say what good looks like.

5. Take the change to your program lead and to whatever office approves accommodations, before the term starts rather than after the first appeal.

Where to go next

The validity argument behind the whole page is in Assessment Validity; the enforcement-side companion is How Can I Reduce AI Cheating in My Course?, with How Do I Write a Course AI Policy and Communicate It to Students? beside it. What Are Best Practices for Writing Instruction in the Context of AI? covers the wording students actually follow, and What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? covers whether the tool you are designing around works at all.

Connected FAQs

- Should We Use AI Detectors?
- How Can I Reduce AI Cheating in My Course?
- What Are Best Practices for Writing Instruction in the Context of AI?
- How Do I Write a Course AI Policy and Communicate It to Students?

Can I Use AI to Grade Student Work Fairly and Reliably?

You have a rubric you believe in, more submissions than hours, and a tool that returns a score plus several confident paragraphs in the time it takes to read one essay. You try it on work you already graded. Half the scores look right. One is strangely generous, one strangely harsh, and you cannot yet tell whether that is the tool or the essay.

Short answer to give a colleague: AI grading earns a place as a supervised assistant or a second reader, on tasks where you have checked it against work you have already marked. Agreement does not transfer across assessment types. In a sixteen-student pharmacy examination, Falahat et al. (2026) found near-perfect agreement on objective item types and unreliable agreement on open-ended responses. Across three English universities, the OpRaise project found AI and human assessors agreeing on the degree band between 35% and 65% of the time depending on institution, with marks compressed toward the middle. A fluent justification is not evidence that your criteria were applied. Whether the result is valid for your decision is a local question you have to answer yourself, and a person stays accountable for anything that becomes a recorded grade.

The short version

1. Name the role before you run anything: feedback assistant, second reader, or primary scorer. They need different amounts of evidence.

2. Start with the least consequential role that solves your real problem. If a deterministic key would do the job, an LLM adds risk rather than value.

3. Calibrate on work you already graded, including strong, weak, borderline and unusually structured submissions. Convenient examples prove nothing.

4. Keep the calibration set and the test set separate, or you are measuring how well you tuned the tool to familiar essays.

5. Report exact agreement, score differences and direction of bias, not a correlation. Check pass/fail boundaries specifically.

6. Tell students which role the tool plays, who decides the grade, and how to ask for review.

Decide what the AI is allowed to do

Three arrangements get called “AI grading” and they carry different obligations.

A **feedback assistant** drafts comments or flags possible omissions for you to accept, rewrite or discard. The risk is confined to comment quality, and you read everything before it reaches a student. A **second reader** proposes criterion scores or flags disagreements to structure your own marking. Its errors have to be useful rather than merely wrong: a flag that sends you back to a submission you would have marked carelessly is worth having. A **primary scorer** produces scores that become recorded grades. That is the arrangement the evidence in this knowledge base does not support beyond narrow, locally validated cases.

Choose the lowest rung that addresses your actual constraint. If your marking load comes from checking a fixed answer key, ordinary deterministic scoring is more transparent and auditable than a language model, and the pharmacy study suggests the LLM's advantage on objective items was partly an artifact of being handed the correct answers during grading. Reserve the model for work that needs interpretation, then check that interpretation.

Automated assessment covers the wider machinery of scoring, moderation and feedback generation. This page is the judgment question underneath it.

What the evidence actually shows

Agreement depends on the item type. Falahat et al. (2026) graded a mixed-format pharmacy examination completed by 16 students and reported concordance with faculty grading between 0.935 and 1.000 for multiple-choice, select-all-that-apply and fill-in-the-blank items. Agreement on subjective open-ended responses was unreliable. Two details matter more than the headline. Correct answers were supplied during grading, which flatters objective-item results, and adding a rubric did not consistently improve agreement, which undercuts the common assumption that a good rubric converts an LLM into a consistent marker. Sixteen students cannot support a claim about your course. The variation inside one examination is the transferable finding: a system that handles your multiple-choice section says nothing about your essays.

Band agreement is moderate and uneven. The OpRaise report examined authentic undergraduate psychology essays and found agreement between AI and human assessors on the UK degree band of 63% at Cambridge, 53% at Nottingham and 35% at Manchester Metropolitan. Marks were compressed toward the middle, with the tails marked least accurately: an essay a human marked 75 was scored several points lower by every AI system, and an essay marked 50 several points higher. That compression is the failure to watch for, because it damages exactly the students at the top and bottom of your distribution while leaving the middle looking fine. This is a project report rather than a peer-reviewed trial, and it is the most useful warning in the evidence base.

Your own marks are an imperfect reference. Instructors disagree with each other, and your previous score on a similar essay is a judgment, not a ground truth. Agreement with one marker establishes consistency with that marker, which is not the same as fairness. Where the stakes justify it, use a second qualified reader to adjudicate difficult cases, and treat a disagreement between the AI and a human marker as a prompt to re-read the work rather than a verdict on which side is right.

Consistency and sound judgment diverge. A model can return near-identical scores on a rerun while applying your criteria badly, because repeatability measures stability, not validity. The OpRaise tails show the pattern: the system was steady and wrong about the essays that mattered most.

Validate the procedure before it touches a grade

Work through this on previously assessed, appropriately protected submissions that span the responses you actually receive: strong, weak, borderline, incomplete, unusually structured, and correct answers expressed in an unfamiliar way.

1. Specify criteria and demand evidence. Give the assignment, rubric, scoring rules and examples of how legitimate alternative answers earn credit. Ask for concise criterion-level justifications tied to identifiable passages. Then check those justifications against the submission yourself.

2. Separate calibration from evaluation. Tune on one set, test on another. Without that split you cannot distinguish a validated procedure from a well-fitted one.

3. Measure the decisions that matter. Record exact agreement, the size and direction of score differences, and whether the model systematically awards higher or lower marks. Examine pass/fail and other consequential boundaries on their own. A high correlation can sit on top of a systematic shift.

4. Test repeatability and subgroup behavior. Rerun a subset under identical settings. Look for criterion-level errors and for language, formatting or legitimate style being mistaken for weaker understanding. Small subgroup counts support caution, not a fairness claim.

5. Write the escalation rule. Decide which cases always get human marking and how disagreements are resolved. Do not let the model's stated confidence decide; confidence needs validating against observed errors before it can carry weight.

6. Protect the workflow. Use an approved environment, minimize identifying information, and keep rubric and instructions separate from submitted content. That separation makes manipulation harder to hide. It does not make it impossible.

7. Record what would invalidate the check. Keep the model and version, prompt, rubric and settings. A model update or a rubric revision is a reason to repeat the representative checks rather than assume continuity.

Make the arrangement visible to students

Students are entitled to know what role the tool plays, who decides, and how to contest a result. Vague disclosure produces suspicion; specifics produce a workable relationship. Something like: "An approved AI tool may draft rubric comments on your draft. I review every comment and determine your grade. Contact me if a comment misrepresents your work." Then make that true.

Two failure directions need separate attention. Excessive deductions are the ones students report, and they dominate appeals. Unearned credit is the one that goes unmentioned and quietly corrupts the record. Sample for both, and include your verification hours when you judge whether the workflow saved you anything.

What will come back at you

"Humans are biased too." They are, which is why the comparison needs explicit criteria rather than a single marker's score as the standard. The OpRaise institutional spread is the argument here: if human markers at three universities produced such different band agreement with the same systems, the human reference is part of what has to be specified, not a fixed yardstick.

"The rubric makes it objective." A rubric makes expectations explicit. Applying it remains interpretation, and the pharmacy study found that supplying a rubric did not consistently improve agreement. What the rubric buys you is a checkable standard for the justifications, not a guarantee of the scores.

“I would have to check everything, which defeats the purpose.” For some tasks that is the right conclusion, and the answer is to narrow the job. Drafting comments from your own scoring notes leaves the judgment with you and removes the typing. Second-reader flags on borderline submissions concentrate your attention where it changes an outcome.

“My colleague tried it and it worked well.” Ask what they measured. Positive ratings coexist with errors in this literature routinely, and a colleague who read a few sensible outputs has run a demonstration, not a validation. The question is what their procedure would do to the essays you would notice last.

What to do this week

1. Pick one assessment and write down the single role the AI would play. Write down what evidence would let you move it one rung higher.

2. Run it on five submissions you have already graded, chosen to include a strong one, a weak one, a borderline one and one with an unusual but legitimate structure.

3. Log every disagreement with the work and the criterion, and name the errors you would consider unacceptable rather than merely wrong.

4. Test whether score differences run in a consistent direction, and check your pass/fail boundary separately.

5. Draft the student-facing disclosure paragraph and the route to review, and compare your verification time with the marking time you avoided.

Where to go next

Assessment validity is the concept that decides these questions: whether the evidence supports the inference you want to make. Automated Assessment covers the technology and its measured performance across formats, and How Can AI Help Me Give Better Feedback at Scale? handles the adjacent problem of generated comments and whether students act on them.

For what a grade should represent once students are using AI, including construct substitution and authenticated process evidence, see redesigning assessment in the AI era. For whether detection can substitute for a defensible task design, see whether to use AI detectors. For the evaluation question underneath all of it, see checking whether an educational AI works.

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can AI Help Me Give Better Feedback at Scale?
- Should We Use AI Detectors?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

How Do I Check Whether AI-Generated Quiz and Exam Questions Are Actually Good?

You ask for twenty questions from your lecture notes. They come back with answer keys, explanations, difficulty labels and Bloom's taxonomy categories, in a formatted document that looks finished. Your name is about to go on it.

Short answer to give a colleague: generated questions are candidates, not an assessment. Solve each one yourself, check what the item demands a student actually do, and find out how students respond to it before it counts. On the two largest studies in this knowledge base, the interesting signal is not that generation works but where it fails. Iterative generation inside a course-specific workflow produced usable multiple-choice exams across 71 college classes (Isley et al., 2025). In a data-science audit of 311 deployed questions, the model's difficulty labels tracked the Bloom's levels it had generated alongside them almost perfectly (Spearman $\rho = 0.90$) while tracking what students actually scored at $\rho = 0.06$ (An and Wang, 2026). The label was a description of the prompt, not a measurement of the item.

The short version

1. Write down the outcome and the evidence a satisfactory response would provide before you generate anything.

2. Build a blueprint so you can see which outcomes the set samples and how often.

3. Solve every item yourself before trusting the key, and read the explanation as a claim to be checked.

4. Ask what a student must do to answer it. A question that says "analyze" and requires recall is a recall question.

5. Treat difficulty labels as prompt metadata, not as psychometrics.

6. Pilot the items and inspect how they function, then revise the weak ones.

Start with the learning you want evidence of

Generation is cheap enough that the output format quietly becomes the specification. If your notes produce tidy multiple-choice items, you will end up measuring whether students can choose among plausible statements, whatever outcome the syllabus claims.

Specify the outcome first, then the evidence a satisfactory response would supply, then the knowledge students are expected to bring. Include the course materials, the Misconceptions about AI you expect, any permitted tools and the response format. If you want students interpreting evidence, the item has to require interpretation, and adding the word to a definition question does not do it. A long scenario can still be answerable through one familiar phrase that gives the game away.

An assessment blueprint is a table of outcomes against items, and its value is that it exposes gaps before students do. It also makes the trade-off visible: every item you generate from the easiest material is an item you did not spend on the outcome you care about most.

Review each item on six dimensions

Start with the key. Is it defensible against authoritative course content, and does the explanation hold up when you check it independently? The key and the explanation often come from the same flawed step, so checking one does not check the other.

Then ask what answering the item actually requires a student to do between reading and choosing. This is where generated items fail most often, and where the label is least reliable.

Check alignment next: does answering supply evidence for the intended outcome, or for something adjacent and easier to assess?

Read the wording as a student would. Is the needed information present, and has ambiguity unrelated to your construct been removed?

Look at the options and the scoring rules together. Are the distractors plausible and distinct from each other and from the key, and does the key recognize legitimate alternative answers that your rubric would credit?

Finally, ask who the item excludes. Reading load, cultural context, visuals and formatting can impose demands unrelated to the outcome. For a multilingual or disabled student, an item that rewards fast reading is measuring something you did not intend, and subgroup performance is where that shows up.

A second model can help you spot problems, and agreement between two models is not independent verification of correctness. They share training data and failure modes. Solve the item, then have a qualified person look at the ones that will count.

Do not let the difficulty label decide

The question-generation literature is more useful on the failure of labels than on the success of generation. An and Wang (2026) examined 378 authored questions in data-science courses, of which 311 were deployed to 54 students across 7,888 responses. The model's easy, medium and hard labels correlated with its own co-generated Bloom's levels at $\rho = 0.90$ and with empirical item difficulty at $\rho = 0.06$. Roughly 70% of the deployed items were answered correctly by every student, which left almost no variation for a difficulty label to track even in principle.

Two lessons follow. First, difficulty is a property of the interaction between an item and a population, so no label produced before administering the item can be trusted as a measured value. Second, a bank of items everyone answers correctly is not an easy assessment, it is a useless one: it carries almost no information about who knows what.

The positive case is narrower than vendor claims and worth knowing precisely. Isley et al. (2025) generated ten-question multiple-choice exams for 71 college classes, roughly 1,200 students, using a loop that generates, judges and revises each item conditioned on each course's own instructor-provided materials, then benchmarked the items against human-authored exams. That is a workflow with a reviewer inside it, run per course, not a single prompt over generic content. The support is for the workflow under those conditions, and it does not extend to whatever the same model produces from a paste of unedited notes.

Run a generate, review, pilot, revise cycle

Generate against a blueprint, and ask for the intended outcome, the key, a concise solution and the misconception each distractor is meant to catch. The annotations make the design inspectable. They are not evidence that the design is sound.

Repair before you accumulate. Delete unsupported claims, duplicate items, accidental clues in the stem, multiple defensible keys and complexity unrelated to the construct, and note what you changed, because the pattern of repairs tells you which part of the prompt to fix.

Pilot where a pilot is proportionate. Low-stakes practice, or a managed pilot inside the assessment, gives you response data. Tell students how to report an ambiguous or wrong question and read those reports, since they are your most informative error signal.

Then inspect how the items function: the proportion answering correctly, which distractors attract responses, and whether success on the item travels with performance on the rest of the assessment. An item where strong students fail and weak students succeed is a defect rather than a hard question. In a small class these statistics are unstable, so combine them with content review and student explanations instead of treating a percentage as a verdict.

Revise, and keep the record: the approved version, the outcome it serves, the key, the rationale, the review notes and the administration history. For large or high-stakes banks this is where assessment specialists and proper psychometric methods belong, and measurement expertise is not something a careful read can substitute for.

What this looks like in a course

In an introductory sociology course the outcome might be distinguishing a structural explanation from an individual one. A weak item asks students to define “structural,” which measures vocabulary recognition. A stronger candidate gives a short scenario about a family and an employment decision, then asks which explanation best identifies a structural constraint, with distractors representing plausible but different interpretations.

The instructor checks that the scenario genuinely supports the key, that no two options express the same idea, and that answering does not depend on terminology the course never introduced. A one-line follow-up, “which detail supports your choice?”, surfaces the reasoning that the selected option conceals. The adaptation is untested as an item format, and its value is narrower: the review questions above can be answered before an item is administered, and a bad key can be repaired before students see it.

For students generating their own practice questions, the same rule applies at their level: attempt the item, check the explanation against course sources, and bring the unresolvable cases to someone who knows the subject. Study practice that trains students to accept generated keys uncritically teaches the wrong habit.

What will come back at you

“It gave an answer and an explanation.” Both can repeat one mistake, and the explanation generates confidence precisely because it is fluent. Verify the reasoning against your materials, not against its own restatement.

“These are only practice questions.” Practice teaches misconceptions when wrong keys go uncorrected, and students rehearse the error as readily as the correct answer. Lower stakes change how much review is proportionate. They do not change whether accuracy matters.

“The students liked the quiz.” Enjoyment is evidence about the experience. An easy quiz that everyone finishes comfortably feels good and measures little, and the data-science audit found the items’ popularity was not accompanied by any usable difficulty signal.

“The rubric or Bloom’s tags show it hits the outcomes.” Bloom’s labels supplied by the same generation step are the least independent evidence available. The $\rho = 0.90$ against labels and $\rho = 0.06$ against student performance is exactly what that looks like when it is measured.

What to do this week

1. Choose one outcome and write the evidence a satisfactory response would provide. Then generate five items against it, asking for the key, solution and intended misconception behind each distractor.

2. Solve all five without looking at the keys, and log the ones where you and the model disagree.

3. Ask a colleague to inspect the two strongest candidates for alignment and ambiguity, and delete anything neither of you can defend.

4. Pilot the survivors with a short follow-up asking students which detail supports their choice.

5. Record what you changed and why, so the next batch starts from a better prompt rather than the same one.

Where to go next

Automated Question Generation is the concept page for generation methods and their measured quality, and Educational Measurement covers item analysis, reliability and the psychometrics that a pilot only gestures at. Both sit under assessment validity, which is the standard the whole cycle is serving.

The judgment side of the same problem belongs to AI grading, since a good item graded badly is no better than a bad item graded well. For the wider question of what a grade should represent when students can use AI, see redesigning assessment in the AI era.

Connected FAQs

- Can I Use AI to Grade Student Work Fairly and Reliably?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- Does Using AI Actually Help My Students Learn?

How Can AI Help Me Give Better Feedback at Scale?

It is week six. You have a stack of drafts, a rubric you believe in, and a growing suspicion that a third of your comments get skimmed and forgotten. A colleague mentions that a tool now comments on every draft within the hour. The department meeting needs an answer: is this an upgrade, or a faster way to produce text nobody reads?

Short answer to give a colleague: AI feedback earns its place on coverage, timeliness and consistency, inside a narrow band. Copy-editing-scale language work and rubric-guided first-pass comments are worth automating. Reach is the cheap part. In a cluster-randomized experiment with 1,176 first-year undergraduates, reflective and hybrid designs beat direct AI critique on delayed, AI-free transfer. In a randomized essay experiment with 70 students, better-rated AI feedback produced no better revisions than an experienced teacher's. What a student does with a comment decides the outcome, and feedback literacy separates the students who gain from the ones who copy.

The short version

1. Decide what counts as a win before you pilot anything: revision quality and delayed unaided performance, not the fluency of the comments.

2. Sort your own comments into language-level fixes and judgment-level calls. Only the first category is a candidate for automation.

3. Stage the sources. Self-evaluation first, peer feedback second, AI critique third. Two sources placed side by side produce passive uptake.

4. Hand the model your rubric and make it reason step by step. A bare instruction produces generic output.

5. Keep the final message, the tone and anything that becomes a record with a human.

6. Budget the hours you will spend on deletion and calibration, and compare them with the hours you freed.

Decide what counts as a win before you pilot anything

The tempting metric is the quality of what the model writes. It is also the metric that misleads.

Farrokhnia et al. (2026) randomized 70 students writing argumentative essays in Persian into three groups. Chain-of-thought prompting produced significantly higher-rated feedback (M = 12.90) than zero-shot prompting (M = 11.25, p = .01) and than an experienced human teacher (M = 11.20, p = .008). The chain-of-thought group did not revise its essays significantly more than the teacher-feedback group, which achieved comparable gains. Better comments, the same revisions. If your success criterion is comment quality, that study reads as a win. If it is what changed in the essay, it does not.

Two other signals flatter a pilot that is going badly, so fix them in advance. Student satisfaction is one. In the university-wide Deakin pilot reported by Tubino and Adachi (2022), positive average ratings coexisted with student-flagged errors, so a smiley-face survey is not accuracy evidence. Usage is the other. The Deakin tool was optional, and usage averaged roughly 13% of undergraduates and 12% of postgraduates despite almost

4,000 students having access. Proactive, high-achieving students used it more. That is what making a tool available buys you.

The outcome measure that holds up is revision quality plus delayed performance without AI. Multiple same-day resubmissions are a usable trace of whether a student engaged at all. They are not evidence that anything was learned.

Sort your comments before you automate them

Take your last set of comments and split them in two: fixes to sentences, and calls about thinking. The split tells you what to automate, and it is narrower than vendors imply.

The Deakin pilot ran in 2021 using FeedbackFruits' AI automated feedback tool across 29 units and almost 4,000 students. It works on micro-level text features: sentence length, punctuation, grammar, text structure. That supports the copy-editing stage, where the instructor sets the parameters, the student uses the tool independently, and the feedback arrives in time to be actionable. The division of labor is what scales, not the model.

Judgment-level comments are where the failure modes live. Aldino et al. (2026) collected instructor-side problems from 21 higher-education teachers: inconsistent tone (n = 7), potential misinformation (n = 5) and trust issues (n = 5). Their revision effort went into deleting exaggerated praise and generic suggestions rather than adding content. That list is your review job, and it is where the hours go.

Stage the sources instead of stacking them

The strongest design evidence comes from a multisite, cluster-randomized, longitudinal field experiment: 1,176 first-year undergraduates in 48 sections across 4 universities and 3 science domains, randomized at section level into peer-only, direct GenAI, reflective GenAI and hybrid conditions (Ateş, 2026).

The reflective condition required self-evaluation before AI critique. The hybrid ran self-evaluation, then peer feedback, then GenAI critique. Hybrid produced the highest argument-quality gains and the clearest advantage on conceptual learning. Reflective and hybrid both produced stronger feedback uptake and more self-regulated learning than direct GenAI, and both outperformed it on delayed, AI-free transfer. Direct GenAI did raise immediate argument quality above peer feedback, which is the advantage it has, and it did so with weaker transfer.

The mechanism explains why sequencing matters more than the tool. Direct critique invites passive uptake: the student reads a verdict and applies it. Reflective and hybrid designs force the student to interpret the comment, compare it against criteria, judge its relevance and then revise. Educational value depends less on AI access than on whether the feedback environment preserves learner agency and evaluative judgment during revision.

Peer feedback earns its own place in the sequence. Gu, Chen and Yan (2026) ran two parallel English classes (N = 118 first-year undergraduates in China; GenAI n = 56, peer n = 62) through three Self-Assessment cycles over one semester. GenAI Scaffolding improved feedback literacy slightly but significantly over human peer review (ANCOVA $p = 0.049$, $\eta p^2 = 0.03$). GenAI students refined prompts iteratively and verified or challenged inaccurate output. Peer-group students chose sources by social convenience and had

their evaluative judgment distorted by friendship bias. Peer review kept a distinct value for audience awareness, which is why the authors propose multi-stage designs with anonymous peer feedback rather than a replacement.

Gu et al.'s advantage was small, and they read it as real but not transformative on its own. Teacher scaffolding, prompt guidelines and worksheets did the supporting work.

Give the model a rubric, then make it show its steps

Rubric-referenced generation is the automatable part.

Farrokhnia et al.'s quality gain came from a chain-of-thought prompt that walked the model through a step-by-step evaluation against an argumentation rubric, not from a bare instruction to give feedback. Gu et al. gave their GenAI group ChatGPT-4o with pre-trained rubrics and prompt guidelines, which is what made the output checkable against stated criteria. In both cases, the prompt is where your criteria enter the system, and the reasoning trace is what lets you see whether the model applied them.

Zhan, Boud, Dawson and Yan (2025) make prompt quality the hinge of the whole process. Vague prompts yield generic, useless output, and generated comments can be hallucinated, biased or overlapping, which pushes evaluative judgment back onto the reader. Calibration is sharper still. In Farrokhnia et al., GenAI feedback quality was significantly associated with the strength of a student's initial draft, while teacher feedback quality was not. The teacher calibrated more consistently. Volume scales. Calibration does not.

Keep the last word and the record human

Becerra, Palma and Cobos (2026) describe AICoFE, which runs three independently fine-tuned models (GPT-4.1-mini, Gemini 2.5 Flash, Llama 3.1) over rubric scores and qualitative observations to produce independent draft comments. The instructor then composes the final message by selecting sentences or paragraphs, with a legend showing which model contributed what. The model drafts. The instructor delivers, and the deliverable is signed by one person who read the draft.

Aldino et al. find the same assist-then-verify pattern in ordinary practice. The Machine Learning component most often flagged "Meeting Learning Objective" as missing (20 of 21 teachers had omitted it; 16 accepted the flag) and "Student-Teacher Relationship" (14 omitted; 12 accepted). Teachers decided each suggestion on professional judgment, which is the point of putting them in the loop.

Twelve of Aldino et al.'s 21 teachers made further sentence-level revisions, and the dominant pattern was calibrating tone: editing praise down (f = 11), removing suggestions (f = 9), removing encouragement (f = 8). Revisions clustered in the relational dimension, especially Student-Teacher Relationship (f = 24). They were protecting authenticity and professional voice, and that work does not automate.

Students are the other side of that verification, and their account of the division of labor is close to the one this page recommends. In focus groups of 20 undergraduates, instructor feedback was valued for being relational, personalized and expert-driven, while AI-generated feedback read as impersonal and potentially unfair; those same students were open to a hybrid model in which the instructor reads their work and supplements the model's comments (Fong et al. (2026)). The same study found their judgments aligned with

ChatGPT's on specificity and actionability but diverged on timeliness and positivity, so the dimensions where a model's own verdict can be trusted are narrower than the full rubric.

Teach students to read the comment

Feedback literacy is a prerequisite, and it is unevenly distributed.

Hawkins, Taylor-Griffiths and Lodge (2026) had 32 psychology students do a screen-recorded 25-minute essay task with unrestricted access to ChatGPT, then watch the recording back in a video-stimulated interview. Feedback literacy was the only significant positive predictor of essay grade ($\beta = 0.46$, $p = .017$). Frequency of GenAI use, trustworthiness of the source and prior knowledge did not predict performance, a point Zhan, Wood, Carless and Yan (2026) also make in their special-issue editorial. Fewer than a third of the students compared AI output against another internet source. Half expressed deliberate AI avoidance for academic integrity or because they wanted the essay in their own words. Most requested task-level feedback, which transfers poorly to other tasks.

The extremes are visible in the pair of IELTS writers Zhan et al. describe. A low-literacy student wrote a vague prompt, got generic feedback, trusted or over-copied it, and engaged superficially. A high-literacy student wrote a criteria-referenced prompt, followed up, cross-checked sources and monitored revisions. The difference was instruction and habit, not tool access.

Tell students directly that model comments can be hallucinated, biased or overlapping, and the student owns the revision. Frame the output as a draft opinion to be judged rather than an answer to be copied. Then ask for the comparison, because fewer than a third of students make it unprompted.

What instructors get wrong about this

More comments mean more feedback. Comments are cheap to produce and expensive to absorb, and the constraint sits on the student's side of the loop. Farrokhnia et al.'s higher-rated AI comments produced no more revision than teacher comments did.

A better model will fix the generic output. The Deakin tool's failures were scope failures: sentence-level features, a narrow copy-editing band. Zhan et al. locate the fix in the prompt, the rubric or the human, not in a larger model. The pair of IELTS writers is the demonstration; same tool, different habits, different results.

Making the tool available is the intervention. Usage ran at roughly 13% of undergraduates and 12% of postgraduates when the tool was optional. The rest of the design question is what happens for the other 87%.

The time saving is automatic. Asked what the AI feedback tool gave them, 21 teachers named saving time only rarely ($n = 2$). They named reflection ($n = 14$), improved language and structure ($n = 11$) and identification of missing components ($n = 10$) far more often. Editing ($f = 32$) and removing ($f = 27$) dominated their revision work, with adding rare ($f = 8$). What appears is a draft and a diagnostic prompt. What also appears is review, calibration and verification work. The workload question is the one most often promised away, and GenAI redistributes rather than removes teacher labor.

Satisfaction ratings tell you the comments are accurate. In the Deakin pilot, positive average ratings coexisted with student-flagged errors. Sample the output against your own reading of the same drafts and log where the model was generic, wrong or flattering.

What will come back at you

“AI feedback is not personal.” Often true, and it is the reason to keep the last word human. AICoFE exists because generic model prose is not what a student should receive: the instructor selects, edits and signs the final message. The 21 teachers in Aldino et al. rewrote tone for the same reason. Personalization is your job in this design, and the model is doing the setup work.

“My students will not read feedback anyway.” They read less than we hope, and the evidence says the fix is design rather than volume. Uptake in the Deakin pilot ran at roughly 13% and 12%. Farrokhnia et al.’s higher-rated comments produced no extra revision. What moved the needle was sequencing that forces engagement, self-evaluation then peer feedback then AI critique, plus three revision cycles across a semester that produced measurable feedback-literacy differences.

“This is not what students pay for.” Then keep the AI from becoming the only voice they hear from you. The defensible version gives students more feedback moments while you spend your hours on the judgment-intensive parts: the final word, the calibration, the comments that carry your authority. What students lose under careless deployment is the coherence between criteria, comments and outcome. Specify the complementarity through sequencing, comparison, editing and governance, and the objection loses its force. Leave two sources side by side and it does not.

“I do not have time to review everything the model writes.” Then do not review everything. Automate the band where errors are cheap to catch, sentence-level language work, and sample the judgment-level output against drafts you have already graded. The Aldino numbers tell you what to look for: tone, misinformation, exaggerated praise, overlap.

What to do this week

1. Sort your own last set of comments into language-level fixes and judgment-level calls, and count each pile.

2. Write the rubric-referenced, step-by-step prompt you would hand a model, and test it against three drafts you have already graded.

3. Sample the output against your own comments and log where the model was generic, wrong or flattering.

4. Stage one assignment as self-evaluation, then peer feedback, then AI critique, and tell students the AI is a draft opinion they are expected to challenge.

5. Ask for one comparison against a second source or against the criteria, since fewer than a third of students do this unprompted.

6. Log how much of the final feedback came from the model and how much you changed. AICoFE’s curation tracking is the model for that record.

7. Watch the expert-novice split. Instructors with more than five years of experience reported more problems with the tool’s output than less-experienced colleagues did, who valued the scaffolding. If your experienced colleagues see more failures than you do, that is information about your own calibration.

Where to go next

Feedback is the umbrella concept for the whole system: provision, loop, uptake and assessment context. AI feedback quality covers what makes generated comments accurate, useful, timely and pedagogically sound, and this page is the practical middle, about which combinations of those parts produce better feedback at scale.

Questions about what a grade should mean once AI is involved, including construct substitution, authenticated process evidence and integrity rules, belong to redesigning assessment in the AI era and assessment validity rather than here. For the writing-instruction special case, see best practices for writing instruction in the context of AI.

Connected FAQs

- What Are Best Practices for Writing Instruction in the Context of AI?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- How Can AI Save Me Time as an Instructor?

How Can I Reduce AI Cheating in My Course?

It is week six. A take-home essay comes back fluent and hollow and you cannot tell whether the student wrote it. Or four submissions share a shape nobody in the room produced in September, and the integrity office wants a written account of what the assignment was measuring. Or your department voted last month to restrict Generative AI in core courses and left you to make the restriction mean something.

The answer to give a colleague: stop trying to prove who wrote the work and change the conditions under which it gets written. Detection is the weakest lever you have. The levers that hold are a task where the shortcut leaves a trace, a single unassisted step you can observe, and a short taught sequence that keeps students inside the cognitive work.

The short version

1. Take detection off the critical path. The evidence below shows it misfiring on permitted editing and missing deliberate evasion.

2. Put one unassisted, observable step into every high-stakes Assessment and give it real weight.

3. Set the AI boundary per task step, not per course, so it follows what you are grading.

4. If AI is allowed, configure it to hint rather than answer, and require a student attempt before it responds.

5. Make disclosure specific and free of penalty. Vague rules and punitive ones both push students toward concealment.

Detection will not carry the case

The Academic Integrity synthesis reports substantial limitations in AI-text detection and argues that integrity in the generative AI era is increasingly an assessment-design problem rather than simply a detection problem. Carry the numbers into the meeting where you justify this to someone who already bought a license.

In a controlled study of 642 published English abstracts, two commercial detectors flagged guideline-compliant light AI *editing* at 38-80%. They flagged unmodified 2023-25 originals at 9-15%, with non-STEM work far above STEM at $p<0.001$. After AI “humanization,” the same tools caught fewer than 4% of AI-labeled rewrites (Why AI Detection Fails for Academic Integrity). Read those three in order. Permitted use was flagged more often than prohibited use, and prohibited use was mostly invisible once someone ran it through a paraphraser. That is the integrity catch-22: the detector punishes honest assistance while enabling deliberate evasion.

The field evidence runs the same way. In a covert study, 94% of wholly AI-generated submissions injected into live online examinations across five psychology modules went undetected, and the AI work on average outscored real students (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI). Vanderbilt University disabled its licensed detector after failing to validate an advertised 1% false-positive rate, a rate that would imply roughly 750 mislabeled students among 75,000 annual submissions.

None of that establishes that detection never works. It establishes the error profile you have to live with. A flagged student is a person with an appeal, and the 642-abstract result says the flag lands hardest on students who did the permitted thing. The full argument for why this changes what a grade can support is in How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?.

Change what the assignment makes easy

The Reducing AI Misuse synthesis ranks redesign Tier-1 for a structural reason: it works whether or not a student chooses the right behavior, because it constrains the environment instead of depending on motivation.

Start with a label. The AI Assessment Scale (AIAS) gives each assignment an AI-use level, from “no AI” through “AI for brainstorming only” and “AI assistance with attribution” to “full AI use,” so the expectation is explicit and enforceable rather than inferred.

Then change the artifact. A 72-study systematic review of generative AI in computing education rates redesign as both feasible and highest-leverage, and singles out one move: add an oral or otherwise process-visible element to at least one high-stakes assessment per course. It calls that the single most effective intervention in the corpus. Detection is the thinnest area the review covers, with just 3 studies, against 60-80% of computing students reporting generative AI use in coursework, typically without explicit instructor sanction, and 70% of one national faculty sample explicitly asking for training on AI-resistant assessment design (Generative AI in computing education: A systematic review and a framework for responsible integration).

The menu, roughly in order of how well each option survives a large class.

Unassisted, in class, closed book: proctored exams, quizzes, timed writing. Weight these more heavily than you used to, because homework is the artifact AI inflates. Oral examinations and defenses work for the same reason, since real-time dialogue is hard to outsource (Reconsidering the use of oral exams and assessments: An old way to move into a new future).

Process artifacts: drafts, reasoning traces, annotated “show your thinking,” revision logs, so the *process* is visible instead of only the product (From authentic products to authenticated processes: a systematic conceptual review of authentic assessment in AI-rich higher education). Authentic tasks work alongside them: local cases, internship material, the student’s own data, anything hard to delegate (Beyond Detection: How Students Use—and Hide—AI in Online Assessments and What Authentic Tasks Can Do About It).

Per-student task variation, where each student gets a surface-distinct but construct-equivalent version, makes copying structurally useless. Treat the guarantee as capability-conditional: VARIA found frontier generators reaching only 0.81-0.88 on a joint integrity score while non-frontier models collapse to 0.50-0.55. If your variants are not equivalent, you have bought protection against sharing with unfairness between students.

Close the gap between practice and the exam

This is the part instructors skip, and it is where the causal evidence is strongest.

In a field RCT, an unguarded ChatGPT-style tutor raised assisted-practice performance by 48% and reduced unassisted exam scores by 17%. A guardrailed version, hinting instead of answering and seeded with teacher-authored problem information, eliminated the harm entirely (Generative AI without guardrails can harm learning: Evidence from high school mathematics). At larger scale, a study of 26,811 students found homework outsourcing raised homework scores 18% while lowering closed-book exam scores 20% within six months (The generative AI learning penalty: Evidence from Chinese secondary education).

Note the shape of both results. The gain and the loss land on different measures, and only one of them is the one you certify. A single RCT cannot give you the size of the effect in your course. It gives you the direction, and both studies point the same way.

If you are going to let students use a tutor, configure it before the term rather than after the first complaint:

1. Set it to give incremental, Socratic hints rather than the next answer step.

2. Seed it with correct solutions and common Misconceptions about AI so it can target errors instead of restating content.

3. Require an attempt before any output appears.

4. Apply the effortless-trap rule: if letting AI in makes the task feel effortless, it is in the wrong place.

That last rule is also where Scaffolding and Guardrails earn their keep, and where a simulated student is useful for testing your own prompt before real students meet it.

Ask students to show what they can do

You will never establish how a file was produced. You can establish, cheaply, whether the student can do what the file appears to demonstrate.

"The Best Response to Student AI Use Is Not Detection, It Is Dialog" describes the mechanisms: a two-minute one-on-one or recorded explanation of a submitted piece, a short follow-up quiz on the same material taken without tools, a request to revise a sample of their own work and explain the changes. The source is a practitioner account, so treat it as a promising practice rather than proof of effect.

Verification also decides whether your misconduct process survives an appeal. Munoz et al. (2026) analyzed actual generative AI misconduct allegation files and found that natural justice requires the student be told the allegation and given a chance to respond *before* any determination, usually in an investigative meeting or panel interview, with whatever they say entering the evidentiary record. Their evidence categories explain why this has to be built into the course: system-recorded behavioral traces exist only in supervised assessment, and weaker process evidence such as drafts, supervision meetings and presentations exists only where those were already routine. A verification habit becomes evidence you can rely on later.

Write the rule precisely too. Wright (2026) shows that prohibitions treating speech-to-text transcription and generative drafting as the same "AI use" are over-inclusive and risk sanctioning students who did not do the prohibited thing. That is a fairness problem before it is a legal one, and Legal Issues and Risks covers the rest.

Keep students in the loop while they work

Banning the tool and permitting it without structure produce the same outcome, which is students standing outside the cognitive work.

The Reducing AI Misuse synthesis sets out eight design principles for the permitted version, including: preserve cognitive friction, position AI as a provisional thinking partner rather than an authority, embed evaluation checkpoints, and require metacognitive journaling and prompt logs.

The sequence that carries those principles is short enough to print on an assignment sheet:

1. Think first. Students brainstorm, outline or draft independently before opening anything.

2. AI second. They use it to critique, extend or generate alternatives against thinking they already have.

3. Reflect third. They log what they used it for, what they accepted and rejected, and why. A prompt plus revision log is enough.

Make the declaration specific, and cheap to fill in

Replace the generic “I used AI” checkbox with a domain-specific declaration framework that maps use to cognitive stages, such as structural planning versus content generation (Structuring Transparency: Developing Domain-Specific Generative AI Declaration Frameworks in Higher Education). A coversheet that asks which stages, which tool, which prompts, and how the output was evaluated does more work than a yes or no.

Two conditions make it honest. Disclosure has to be safe, because punitive or vague policies actively drive concealment (Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher), and students weigh the risk of telling you against the risk of not ("Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education).

The arithmetic also has to favor telling. Mohamed and Temimi model this as a problem of imperfect information rather than morality. Disclosure is attractive only while the cost of honesty stays low, and because a detector’s false positives fall on honest students too, stronger monitoring can make concealment relatively more attractive whenever extra sensitivity produces more new false positives than new true positives. Read a declared use as context rather than a confession, and design for the student most tempted to conceal.

Teach the literacy you are grading

The Reducing AI Misuse synthesis ranks AI literacy and prompting instruction Tier-2, below structural change.

The measured example is a K-12 module using scenario-based prompt practice with an Large Language Models (LLMs) auto-grader. It improved actual prompting skill and raised confidence in using AI for learning by 10.4%, with 87% reporting they had learned to use AI responsibly (Learning to Use AI for Learning: Teaching Responsible Use of AI Chatbot to K-12 Students Through an AI Literacy Module).

What students actually believe is less cynical than the panic suggests. Among 504 sociology students, 65% had used generative AI for coursework, but only 3% to generate assignment text and 2% to generate a full

draft. 81% had received some AI guidance and only 46% found it very clear (Student Use of and Views on GenAI for Writing). Ambiguity, not defiance, is the practical problem, which is why a clear rule plus a taught sequence shifts more behavior than a warning does. Mulisa and Mezgebu (2026) describe students asking whether generative AI is a tool that facilitates cheating or a partner that supports learning, and that question is what your expectations should answer.

The harm worth teaching explicitly is the performance-learning gap: performance rises now, learning falls later, and the student experiences only the first. Is using artificial intelligence tools for academic work cheating? Student perceptions, ethics, and the impact on academic performance and critical thinking and "It's OK Because.": The Wild West of Student Rationalization of AI Use in Academic Writing cover the peer-norm and rationalization side, including the "everyone is doing it" defense that a clear norm deflates. For how strong this base is, see What Is the Evidence on AI Literacy Interventions in Higher Education? and What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?.

What instructors get wrong about this

A detector is insurance. Count what the premium covers: at the rate Vanderbilt could not validate, 1% of 75,000 annual submissions is 750 students mislabeled, and the 642-abstract study shows the flags clustering on permitted editing.

A ban settles the question. A ban written in the language of "AI use" catches transcription along with drafting, which means you may sanction a student for dictating their own sentence (Wright, 2026). It also tells you nothing about what that student can do.

Cheating is a motivation problem, so penalties are the tool. Motivation is real, and it is not the lever with the best evidence. Redesign ranks Tier-1 because it does not require the student to choose well, and the response-region model says to design for the student most tempted to conceal.

If I allow AI, misuse stops being my problem. Permission without guardrails produced the 48% practice gain and the 17% exam loss in the same study. Put the guardrail back and the harm disappeared.

Students already know where the line is. 81% had guidance and fewer than half found it clear. The 3% and 2% figures say most of them are not generating whole assignments; the 46% says they are guessing about the rest.

A checkbox is a declaration. A checkbox records that a student clicked. A staged declaration tells you what they did at each step, which is the only version that helps you or them.

What will come back at you

"I do not have time to redesign a course this term." Do not redesign the course. Redesign one assignment: one unassisted step, one rubric line with points. That is a two-hour change, and it is the change the 72-study review singles out.

"Oral defenses are impossible with 300 students." Then do not run 300 of them. Weight the closed-book component, require process artifacts, and sample oral checks on the submissions that look inconsistent with earlier work. Three hundred students do not need 300 conversations to change the calculus.

“I need something to show the integrity office.” Process evidence is stronger than a detector score, because Munoz et al. found that the response opportunity and the course’s own records are what the file rests on. A flagged percentage is an allegation. A recorded explanation is a record.

“Requiring declarations just burdens the honest.” It does, if disclosure invites suspicion. Keep the cost of honesty near zero: no penalty for a declared use, and a declaration read as context. The model predicts concealment precisely when honesty gets expensive.

“Students will use AI anyway.” They will, and the useful question is which response your assignment makes easiest. In a class where 65% report use and 2% report generating a full draft, most of the traffic is assistance you could be teaching rather than fraud you need to catch.

“Tightening the rules will catch students who did nothing wrong.” That is the documented failure mode, not a hypothetical. Precision is the protection: name the prohibited act, not the tool.

What to do this week

1. Rewrite the AI clause in your most contested assignment so it names specific steps and specific acts, and drop the blanket wording.

2. Add one unassisted step to that assignment and give it enough weight to matter.

3. Put a process artifact in the rubric with points attached, and describe what good looks like as precisely as you describe the product.

4. If you permit a tutor, check its configuration this week against the four settings above.

5. Tell students, in writing, that a declared use will not be penalized, and mean it.

Where to go next

How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? is the assessment-design companion, and the place to start if your question is what the grade is evidence of. Should We Use AI Detectors? handles the detector decision directly, How Do I Write a Course AI Policy and Communicate It to Students? covers the wording students actually read, and ‘A bit of chaos and madness’: The AI Assessment Scale and the work of assessment reform supplies the label scheme. On the teaching side, What Is the Evidence on AI Literacy Interventions in Higher Education? and AI Misuse and Learning Harm cover what the literacy work is worth and why the harm happens.

Connected FAQs

- Should We Use AI Detectors?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can We Address Common Misconceptions About AI in Education?
- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

Should We Use AI Detectors?

A detector score comes back flagged on a submission you have already read twice, or a colleague wants the tool switched on before the next essay deadline, or an integrity panel asks you to defend a finding that rests on a percentage. Someone in the room will say the score is only one piece of evidence. What you are deciding is narrower than the argument that follows it: whether this number can carry weight in a misconduct process at all, and what you will put in its place if it cannot.

The short answer you can repeat in the meeting: a detector score cannot ground a finding, because it cannot be validated against ground truth, cannot be cross-examined, and does not meet the balance of probabilities. Its errors repeat in patterns, and they fall hardest on honest editors and on students writing in a second language. Ask instead whether a student can demonstrate understanding of what they submitted, and fund that capacity.

The short version

1. Write into policy that detector output never triggers a consequence, never stands alone, and never grounds a finding. Put it in the policy document itself, where a panel can find it after the memo is gone.

2. Replace “did you use AI?” with “can you show me you understand this?” Use a short conversation, an early draft, or a recorded explanation.

3. Put one authenticated or unaided step into every high-stakes task, sized to the marking capacity you actually have.

4. Ask the vendor for error rates in writing, then try to reproduce them on your own submissions. Vanderbilt tried this and disabled the tool.

5. Move the money from a detection license to verification capacity and guidance. That is where the documented faculty complaint points.

Decide whether you have a finding or a question

These are two different jobs and they run on different evidence. A finding requires evidence meeting the balance of probabilities, and a detector score does not get there on its own. It cannot be validated against ground truth, because in real submissions nobody knows how the text was produced, so validation turns circular and the false-positive and false-negative rates only mean anything inside a controlled test. The tool publishes no thresholds and no training data and permits no independent replication, which leaves a flagged student with nothing to answer and you with nothing to explain (Heads we win, tails you lose: AI detectors in education, Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI).

Combining the score with other signals does not repair this. Linguistic markers, style comparisons, Large Language Models (LLMs) judgments and a student’s silence still add up to less than the standard. Silence is the one to watch: students retain the right to refuse, and refusal does not tip the scales. What you can legitimately ask is whether the student can demonstrate the learning the Assessment claims to measure, and

an oral response answers it in a way a similarity score never will (Heads we win, tails you lose: AI detectors in education).

The binary is also the wrong question. Students' work is frequently created with AI, across a hybrid continuum, and policies that say "in assessment" rarely define when an assessment begins, which leaves the judgment to whoever reads the file first (Heads we win, tails you lose: AI detectors in education).

There is a reference-data problem underneath all of it. Detectors are trained and tested on pre-generative-AI human writing, and Turnitin's own validation used 700,000 pre-2019 papers. That corpus is assumed to represent current student prose, an assumption nobody has verified and one that shifts with every model release (Heads we win, tails you lose: AI detectors in education).

Look at the accuracy numbers before you cite one

The strongest controlled test in the knowledge base examined 642 published English abstracts across four domains and two time periods. At a 0.50 threshold, two commercial detectors flagged guideline-compliant light AI editing at 38-80%, flagged unmodified 2023-25 originals at 9-15% (non-STEM far above STEM, $p<0.001$), and, once text had been run through a humanizing service, caught fewer than 4% of AI-labeled rewrites, a false-negative rate above 96%. The authors call this an integrity catch-22: the students who disclose and edit lightly are the ones the tool catches, and the students who set out to evade it are not. Their recommendation is explicit, that detector scores should never serve as standalone misconduct evidence (Why AI Detection Fails for Academic Integrity).

Reviews have stopped trying to rank the tools at all. A systematic review of 90 studies published between 2020 and 2026 reports that false-positive rates vary so widely across tools and evaluation settings that direct quantitative comparison is impossible, naming algorithmic and language bias, limited contextual understanding, surface-level linguistic features and insufficiently diverse training data among the causes (Maghami, Ho and Camilleri (2026)). The remedies it names are procedural rather than technical: transparent detection practice, human review, AI literacy, clear institutional policy and an accessible appeal route.

An independent Benchmark reaches the same place from a different direction. None of 14 tools reached 80% accuracy, and simple paraphrasing, minor editing or a humanizing service roughly halves even that performance. At realistic base rates, false positives outnumber true positives (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI).

Catch rates on wholesale generation are worse than the headline error rates suggest. In a covert field study, researchers injected wholly AI-generated submissions into a live online examination system across five psychology modules: 94% went undetected, and the AI work on average outscored the real students. Contract cheating had already shown the same structural problem, since it leaves no reliable trace to find (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI).

Accuracy also moves with the task. When researchers tested whether generative AI can detect its own output, results were dependable for programming and longer reflective writing and poor for short answers, where the model often rated its own text as more human-like than authentic student work. Minor prompt variations sharply reduced accuracy (Distinguishing Artificial from Authentic: Evaluating LLMs for Detecting LLM-Generated Content). A threshold that holds for one assignment will fail on another, and you will not know which until the appeal.

Then there is expiry. A 2026 study reframes detection as an adaptation problem: a black-box rewriting attack dropped the commercial detector Pangram to a balanced accuracy of 63.5% and an AI recall of 27.0%, and a detector trained on Llama 3.3 70B Instruct reached only 55% recall on abstracts from a newer model. Test-time adaptation recovered to 94.4% balanced accuracy and 99% recall on that same text, which is the encouraging half. The same paper shows what the fix costs: as simulated LLM adoption spreads, a fixed supervised detector's recall on human text decays from 85.9% to 73.4% across the decade. Its expiry condition is stated bluntly, that balanced accuracy cannot exceed half of one plus the total-variation distance between the human and AI distributions, so convergence of the two would defeat every learning-based detector. A validated score holds until the models move, and they move every few months (Hitting a Moving Target: Test-Time Adaptation for AI Text Detection under Continual Distribution Shift).

The comparison also depends on the task the reader is given. In a controlled design where 30 pre-2022 article introductions were rewritten across five plausible conditions, blinded human raters scored 19% overall, indistinguishable from chance, while three commercial detectors separated the same five conditions ($p < 0.001$ for all) yet agreed only weakly with one another on the absolute score, ICC 0.57 to 0.95 (Cheng et al. (2025)). That task asked raters to place text among five editing conditions rather than to pass a yes-or-no judgment on one student's essay, so it does not overturn the marker studies below, but it removes any comfort that a human in the room is the reliable instrument.

And the machine has never clearly beaten a careful reader. Leaton Gray, Edsall and Parapadakis (2025) report machine detection of AI or paraphrased text at roughly 80% against 78.4% for human reviewers, and cite evidence that AI-generated text has passed as human-authored in up to 80% of cases. That margin disappears into the error band the human already brings, which is too thin to ground a finding (AI-based digital cheating at university, and the case for new ethical pedagogies).

Work out whose work the error lands on

The features detectors read as signals of AI, meaning long-token density, academic word frequency and uniform style, are also features of competent second-language writing. Misclassification therefore follows language background rather than conduct, which makes this an equity question before it is a technical one (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI).

That skew shows up outside English too. A benchmark of 3,811 passages whose pre-ChatGPT authorship is provable found that five English-trained public detectors run as released flag 81.4% of human Kazakh passages (TMR RoBERTa) and 79.6% of published Kazakh student essays (Desklib DeBERTa), with 25.5% for Fakespot, and that recalibrating them to a 1% false-positive rate catches at most 1.3% of machine text in exchange. The study's own caveat matters when you quote it: the human passages are public pre-ChatGPT text as found rather than student essays, so its educational rates are the least certain figures it reports (Unchecked or falsely accused? Evaluating AI-generated text detectors on Kazakh).

Discipline adds another axis. Non-STEM abstracts were flagged far above STEM ones in the 642-abstract study, which reflects the writing conventions of those fields and not their authors' conduct (Why AI Detection Fails for Academic Integrity). Two widely used commercial tools measured 0.69 and 0.61 accuracy in one comparison, and both failed on hybrid human-AI text (Evaluating the accuracy and reliability of AI content detectors in academic contexts, Who wrote this? Evaluating the reliability of AI detection tools in higher education). A detector is a style test, and the style it punishes tracks language

background, discipline and register. None of those is a fact about whether a student used AI, and every one of them is a fact about the student. The wider pattern is documented in Differential Effects Across Learner Groups.

Some of the cost shows up before any hearing. Because formal processes demand detection-grade proof that is functionally unavailable, faculty end up with what one practitioner account calls “suspicion without recourse,” while students rationalize their own use and case files stall (The best response to student AI use is not detection, it is dialog). The Trust cost lands on the relationship the process depends on.

Change the question you put to the student

Grand Canyon University moved from “Did this student use AI?” to “Can this student demonstrate understanding of what they submitted?”, using short conversations, early drafts and recorded explanations, implemented institution-wide in fall 2025. The argument for it is practical: faculty are already qualified to judge understanding, and the shift hands their authority back instead of leaving them waiting for proof that will never arrive (The best response to student AI use is not detection, it is dialog).

This also changes what a student can do with the accusation. Shown the concern and asked to explain, a student can resolve it. Shown a percentage, they can only deny it.

Run the conversation so it survives review

Treat a verification conversation as a step in the process, with notice and a record, and it will hold up when someone reads the file a term later.

Start with notice. Tell the student what prompted the concern, in plain language, and say what the conversation is for. If the concern came from a detector score, say that, and say that the score is not a finding. Tell a student only that they are accused of cheating and the meeting becomes a defense of character rather than an account of the work.

Then ask about the work itself. Which claim were you trying to make in this section. Where did this evidence come from. Why did you organize it this way. What did you discard. A student who wrote the piece can answer these at the level of decisions. The student who did not write it will answer at the level of topic, and the difference shows up quickly without anyone needing to prove intent.

Keep the right to silence intact. Declining to answer concedes nothing, and a procedure that treats refusal as an admission will not survive an appeal. Record what was asked, what was answered, and what was declined.

Close with a decision you can state without the score. Either the student demonstrated the understanding the assessment measures, or there is a separate, substantive concern about the work that you can describe in your own words. If neither is true, the file ends there. That outcome is a normal one and should be written down as such, because a process that only ever records guilt teaches the next panel that suspicion is the same as a finding.

Put one step in the assignment the tool cannot sit inside

Asynchronous oral assessments, built as just-in-time prompts with brief, time-limited recorded responses graded against embedded rubrics, performed comparably to in-person multiple-choice exams in one study and significantly better in another, with students reporting more active preparation and higher perceived professional relevance. For an Administrators, the property that matters is that this scales without proctoring (Asynchronous oral assessments: Enhancing integrity, engagement, and communication in the AI era).

Redesigning the task does more work than hardening the check. A case study of undergraduate economics students found only about a third reported any AI use, with disclosure rarer still, and read non-disclosure as rational caution under ambiguous policy rather than dishonesty. Those same students favored real-world, data-based tasks as the fix (Beyond Detection: How Students Use—and Hide—AI in Online Assessments and What Authentic Tasks Can Do About It). Expecting, declaring and scrutinizing AI use beats policing it, because authenticity has to be designed rather than enforced (Beyond Detection: Redesigning Authentic Assessment in an AI-Mediated World).

Two decisions follow. Size comes first. A short oral check on every major submission is affordable in a seminar. In a lecture of three hundred, staged drafts and a sampled check on anomalous work are what survives week ten. Pick the version you can still run in the last week of term with the marking hours you have, because an authenticated step that collapses under load leaves you back with the artifact.

Points come second. If a rationale, a draft history or a reflection on a rejected AI suggestion scores nothing, it will be produced in five minutes and read by nobody, and students will optimize for the part that is graded. Give it enough weight that skipping the step costs more than doing it.

Make disclosure the cheap choice

Vague or punitive policies drive concealment. Specific declaration frameworks tied to cognitive stages, paired with an assurance that truthful disclosure is not penalized, get more information out of students than surveillance does (Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher, "Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education). The design question is which response your rules make easiest for the student who is tempted to hide, and a rule that treats a declaration as a confession has answered it badly.

Wording does most of the work here. A declaration that asks students to tick a box and then sits unread in a submission system teaches them that disclosure is theater, and the next cohort learns it faster. A declaration attached to a stage of the work, asking what the tool was used for at that stage and what the student did with the output, gives you something you can actually read, and gives the student a reason to be accurate.

Write the clauses that keep you out of a hearing

Exposure rarely starts as litigation. It surfaces first as an internal appeal or a regulator complaint, and the first thing tested is procedure. Natural justice requires that a student be told the allegation and given an opportunity to respond before any determination, and that opportunity is typically an investigative meeting or a panel interview whose record becomes evidence. Findings reached without that step are vulnerable even

where the underlying suspicion was reasonable (How strong is the evidence in generative AI-related academic misconduct allegations? A mixed-methods analysis).

Evidence standards come second. Misconduct findings need evidence meeting the balance of probabilities, and if your case cannot be stated without the detector score, the case is weak on its face (Heads we win, tails you lose: AI detectors in education). Where the case rests on style alone, an oral verification route belongs in the procedure, not in the goodwill of the panel chair.

Scope is the third. Blanket AI bans that fail to separate transcription and OCR from generative drafting can remove an assistive tool that students with conditions affecting motor control, handwriting legibility or typing accuracy depend on, several of which have been discontinued with AI transcription filling the gap. That is legal exposure as well as imprecision (Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment). Name assistive and transcription tools in the policy text.

Procurement is the fourth. Detectors store student work on third-party servers, sometimes overseas under weaker Privacy protections, which puts breach, retention and onward commercial use on your institution's risk register rather than the vendor's marketing page. Terms should cover retention, use for model training, storage location, breach notification and appeal rights (Heads we win, tails you lose: AI detectors in education). The knowledge base's account of the legal exposure is in Legal Issues and Risks, and it is honest about its limits: it documents procedures, evidence categories and instrument reliability, not litigated outcomes.

What lowers risk is procedural. Never treat output as standalone evidence or an automatic trigger. Document the standard your process applies. Give notice and a real chance to respond on the record. Offer verification when the case rests on style. Keep the audit trail that shows all of it happened.

Test the wording against four cases

Policy language fails on the cases nobody pictured when it was written. Run these four through your draft before it goes to committee, and note where the text has no answer.

A student who ran a draft through a translation tool. The policy needs to say whether translation counts as AI use, and whether it counts the same for a student writing in a second language as for one writing in a first. If it is silent, the panel will improvise, and improvisation is where the equity argument starts.

Someone who used AI to outline and wrote every paragraph themselves. Under a rule that asks whether AI touched the work, this student is in the same category as one who generated the whole submission. Under a rule tied to steps, they are not, and you can say why. That difference is the construct, and the policy has to name it.

Someone who generated the text and cannot explain it. This is the case your process is built for, and it is the one that resolves without a detector score.

A student who uses transcription because typing is unreliable. Name assistive tools as a separate category with their own route, so that an accommodation does not become an allegation.

What administrators get wrong about detectors

A vendor's published false-positive rate is a risk figure you can budget against. Vanderbilt licensed a detector advertising a 1% false-positive rate, then tried to validate the number and could not. At 75,000 annual submissions, 1% implied roughly 750 mislabelled students. The university disabled the tool (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI). A rate you cannot reproduce on your own corpus is a marketing number, and the mislabelled students are still yours to process.

Detection deters the students who would otherwise cheat. Deterrence runs through a detector's discrimination between hidden use and legitimate work, not its raw catch rate. When added sensitivity produces more new false positives than new true positives, stronger monitoring makes concealment relatively more attractive, so you spend credibility on students who did nothing wrong faster than you identify the ones who did (Assessment design under imperfect information: generative AI, disclosure, and student response in higher education). Krou et al.'s meta-analysis, cited in the same review, finds Self-Efficacy correlates negatively with cheating while actual ability does not correlate inversely with it at all, so capable students may cheat when they judge the assessment unfair. Detection is neither a reliable instrument nor an obvious deterrent (AI-based digital cheating at university, and the case for new ethical pedagogies).

A score plus a couple of indicators adds up to a case. It does not. The standard is evidence meeting the balance of probabilities, and scores combined with markers, style comparisons, LLM judgments or silence still fall short. One test worth applying is whether you would say the reasoning out loud in a hearing (Heads we win, tails you lose: AI detectors in education).

A detector license costs less than redesigning the assessment. The license is the smallest line item, and it carries data-protection exposure, procurement work, and a permanent stream of appeals built on an instrument whose error is patterned by language background. Faculty describe the experience as "suspicion without recourse," so the budget line that changes outcomes is verification capacity and guidance (The best response to student AI use is not detection, it is dialog).

The evasion market is a product of the detection regime, not a rival to it. Roe et al. (2026) catalogued 55 AI-humanizer sites and found the ones they analyzed on the first page of Google, sold on freemium tiers with affiliate programs. The sites do not market cheating: they market protection from false positives, unexplained university and corporate logos placed under the text box, 99.8%–100% success rates, and unverifiable user counts, with no site listing a registered business address. The policy consequence is that detection and evasion are two halves of one transaction — one vendor sells a classification of authorship, the other sells the promise of changing it — so removing or adding a detector changes who profits from the loop without touching the demand. What you control is the other input: whether students have a route to ask about provenance that does not start with suspicion, and whether AI Literacy covers reading commercial claims about AI the way it covers reading AI output.

A blanket ban protects the institution. Over-inclusive rules can strip an accommodation and invite the discrimination argument you were trying to avoid, because the error they produce is concentrated on identifiable groups rather than spread evenly (Transcription is not generation: Distinguishing non-generative AI tool use from academic misconduct in higher education assessment, Evaluating the accuracy and reliability of AI content detectors in academic contexts).

What will come back at you

“Our vendor advertises a 1% false-positive rate.” Vanderbilt’s licensed detector claimed exactly that, and the claim did not survive the university’s attempt to validate it. Independent benchmarks put no tool above 80% accuracy (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI). Ask for the validation study and the corpus it ran on, then ask to run it yourself.

“We only use it as one piece of evidence.” The standard is evidence meeting the balance of probabilities, and a score combined with markers, style comparisons, LLM judgments or silence still does not satisfy it (Heads we win, tails you lose: AI detectors in education). If the panel would not accept the reasoning spoken aloud, the file should not contain it.

“If we stop detecting, cheating wins.” Cheating already gets past these tools. 94% of injected AI submissions passed a live online exam unnoticed, humanizing defeats detection more than 96% of the time, and contract cheating already left no reliable trace. What detectors do catch, with measured reliability, is honest light editing and non-native prose (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI, Why AI Detection Fails for Academic Integrity).

“We only use it privately, to start a conversation.” That is the least harmful use, and it still costs something, because the students most likely to be flagged are the least likely to be misusing AI. Suspicion then lands on the wrong people before any conversation begins (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI). Grand Canyon’s answer was to stop starting from suspicion at all (The best response to student AI use is not detection, it is dialog).

“A student with nothing to hide has nothing to fear.” The 642-abstract study found compliant light editing flagged at 38-80% at a 0.50 threshold, and the Kazakh benchmark found 81.4% and 79.6% of provably human passages flagged by released detectors (Why AI Detection Fails for Academic Integrity, Unchecked or falsely accused? Evaluating AI-generated text detectors on Kazakh). A clean record offers no protection when the signal is style. That is also why the Kazakh authors flag their own educational rates as the weakest figure in the study, and why you should not quote them as a student-essay rate.

“Can we just require a declaration and treat a missing one as guilt?” A missing declaration is not evidence of hidden use, and treating it as one makes concealment rational. Specific frameworks tied to cognitive stages, with truthful disclosure protected from penalty, extract more information than surveillance does (Addressing student non-compliance in AI use declarations: implications for academic integrity and assessment in higher, "Should I Tell My Teacher?" Student AI Disclosure Practices, Stigma, and Self-Regulated Learning in Higher Education). The evidence on this page concerns what produces disclosure. It says nothing about how much cheating a declaration regime prevents.

What to do this week

1. Open your misconduct procedure and find every place a detector score could trigger a step. Write one sentence that removes the trigger, and take it to whoever owns the document.

2. Email the vendor for the validation study behind the advertised error rate, and ask what corpus it used.

3. Pick your highest-stakes assignment and add one authenticated step you can mark in the time you have.

4. Draft the three questions you will ask a flagged student, starting with what they were trying to argue and how they checked it.

5. Send the procurement and accessibility clauses to the office that signs contracts, with the retention, training-use and breach terms spelled out.

Where to go next

The design-side companion is How Can I Reduce AI Cheating in My Course?, and How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? takes the assessment argument further. How Do I Write a Course AI Policy and Communicate It to Students? covers how to word and communicate a course policy, and AI Literacy covers what students need to know to work with these tools without losing the work itself. The concept pages behind the argument are Academic Integrity, Equity and Legal Issues and Risks; the detection-specific clauses above are the institutional layer of Educational AI Policy.

Connected FAQs

- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Do I Write a Course AI Policy and Communicate It to Students?
- How Can I Reduce AI Cheating in My Course?
- How Can We Address Common Misconceptions About AI in Education?

What Are Best Practices for Writing Instruction in the Context of AI?

You are rewriting an assignment sheet and the sentence in front of you says AI is permitted with acknowledgment, which tells a student nothing about whether the tool may supply the argument. A colleague has proposed a course-wide ban and you suspect it lands hardest on the multilingual writers in the room. Or a batch of essays came back smoother than the seminar discussion behind them, and you need a rule you can defend at the next curriculum meeting.

The bottom line: name the intellectual work the assignment exists to produce, keep that step with the student, and give the tool jobs that return something the student has to judge. A rule written that way tells a student which step it protects.

The short version

1. Write one sentence naming the thinking the assignment grades, and put it where students will read it.

2. Make the student commit a claim, an interpretation, or a rough draft before the tool sees the task.

3. Set the boundary per step. Allow AI where the step is not what you grade, restrict it where it is.

4. Give AI the critic's chair, then grade what the student does with the response.

5. Keep one piece of writing the tool never touches and read the assisted work against it.

6. Say in advance what disclosure does to the grade.

Name the thinking the assignment is for

The AI boundary is the second question, and most assignment sheets answer it first. Before you decide what is allowed, finish this sentence: this assignment exists to show that the student can do X. If X is argumentation, the student has to formulate and defend the claim. If it is disciplinary interpretation, the student has to make the interpretive judgment. If it is scientific reasoning, the student has to connect evidence to a conclusion. AI that performs that work breaks the inference you want to draw from the essay, and excellent prose does not repair it. Assessment Validity treats this as a validity problem rather than a conduct problem, which is why writing education and academic integrity both end up arguing for task-level rules instead of course-level bans.

Nash and Burriss show how easily the sentence goes wrong. Across 27 preservice English teachers' classroom AI policies, 22 permitted AI for ideation and brainstorming, 22 disallowed or left unclear the use of AI to compose sentences, paragraphs or papers, and 22 said nothing at all about reading. The same teachers described ideation and revision as "thinking" while placing real thinking in the final written text. If thinking runs through planning, drafting, revising and evaluating, a policy that guards only the last product guards the wrong step, and reading needs as explicit a rule as writing.

Write the rule as a sentence about a step, then: "You may use AI to test objections to a claim you have already made. You may not use it to generate the claim or the evidence for it." A student can act on that. "AI permitted with acknowledgment" gives them nothing to act on.

Make the student commit before the tool responds

Order of operations is the most useful design choice in this literature. Chen's layer-sensitive study of 168 undergraduates in six intact classes separated four kinds of delegation: surface, structural, idea, and reasoning offloading. Open AI collaboration produced the strongest AI-supported writing and the weakest later independent performance. Delegating reasoning was the layer most negatively associated with independent higher-order thinking. A bounded condition, which restricted what students could delegate and required them to explain how they had accepted, modified, or rejected each AI suggestion, did better on independent writing, argument depth, and revision.

Treat the causal claim with care. It is quasi-experimental, with six intact classes and no random assignment of students, so classroom differences stay tangled with the treatment. The direction fits the wider cognitive offloading literature, which is why it is worth acting on, and the size of the effect is not something to quote at a committee.

On the sheet it costs one line: the student brings an interpretation, a hypothesis, an argument, or an analysis, and AI is asked to attack it. "Here are three objections to my argument" keeps the thinking with the writer. "Write my argument" does not, whatever the student does with the output afterward.

Treat the first draft as the expensive step

Assistance at different stages does different damage. In a study of 253 writers, any AI assistance reduced perceived ownership of the work, drafting assistance reduced it most, and planning assistance reduced it least. More AI-contributed text and ideas went with better essay quality and lower ownership in the same submission (the planning-to-revision ownership study). That combination is the one to plan around: a stronger essay and a weaker sense of authorship arrive together, and the second is what Learner Agency in writing rests on.

If authorship matters in your course, split the permissions. AI that prompts planning, asks what evidence the student already has, or names a counterargument the student has missed is defensible almost anywhere. AI that generates paragraphs is hard to defend where composing is the target skill. Where composing is not the target, the calculation changes.

Set the rule at each step

A sequence worth borrowing keeps AI in a consulting role and puts the reasoning with the student:

Stage	The student does	AI may	Artifact you can collect
1. Encounter evidence	Read, observe, annotate, calculate, run the experiment	Nothing, or clarification only	Notes, annotations, observations
2. Form a position	Generate interpretation, question, hypothesis, claim	Ask questions, challenge assumptions	Claim or hypothesis memo
3. Plan	Decide evidence, sequence, audience, genre	Critique an outline, suggest alternatives	Outline with rationale

Stage	The student does	AI may	Artifact you can collect
4. Draft	Produce substantive prose and reasoning	Restricted according to the learning goal	Draft and version history
5. Human response	Give and receive peer or instructor feedback	Nothing necessary	Peer comments
6. AI feedback	Ask for criterion-referenced critique	Critic, reader, counterargument generator, clarity checker	AI feedback transcript
7. Evaluate feedback	Compare peer, instructor, and AI suggestions, accept or reject with reasons	Its output is now the object of evaluation	Feedback decision memo
8. Revise	Make and justify substantive changes	Test clarity, offer alternatives	Revision
9. Verify	Check every factual or source-dependent claim	Cannot verify its own output	Sources and evidence
10. Reflect and disclose	Explain AI's role and what changed in their thinking	Nothing	Brief process reflection
11. Independent check	Explain or apply the reasoning without AI	Nothing	Oral defense, quick write, new case

This is PAIRR extended: draft, human feedback, AI feedback, comparison, revision, reflection, with an independent baseline and a tighter boundary around reasoning. Use the middle column as the assignment and the right column as what a grade can rest on.

Eleven rows is more than most assignments need. Collapse the table to the steps you can actually distinguish in class: encountering the evidence, forming a position, drafting, and revising. In that shorter version the encounter and the position are where the construct lives, drafting is the contested step, and formatting or reference checking can be permitted outright. Writing the table is how you find the two or three places where your rule has to say something, so a rule with three clauses that a student can follow beats a matrix nobody reads.

Keep human feedback in the loop

The largest classroom study here is PAIRR: 654 students across ten writing courses and three writing-intensive STEM courses. They drafted, completed peer assessment, obtained rubric-based AI feedback, compared and evaluated both sources, wrote revision plans, revised, and reflected. Fifty-eight percent preferred combined peer and AI feedback. Six percent preferred AI feedback alone. Students found AI useful for broad rubric-oriented revision advice, and peers supplied contextual knowledge and an authentic audience response.

Be exact about the claim. PAIRR measured students' experience and evaluation of feedback, not long-term learning gains, so it is strong evidence for a feedback design and weaker evidence that writing improves months later. Keep the peer step even when the AI step is faster. Much of the Feedback work happens in the comparison between the two sources, and dropping it removes the part students said they valued.

Grade what the student did with the feedback

Feedback literacy is the capacity to seek feedback, judge its quality, manage your reaction to it, and turn it into revision. Students with more of it benefit far more from AI feedback. Students who treat the output as authoritative gain less (AI Feedback Quality).

A short decision table makes that capacity visible, one row per suggestion: the AI suggestion, accept / reject / modify, why, and the rubric criterion or piece of evidence behind the call. Four columns, no essay required. It turns model output into material for evaluative judgment, and it gives you something gradeable that is not the prose.

Describe a strong row as carefully as you describe a thesis statement: it names the rubric criterion, points at a passage or a piece of evidence, and explains a change the student actually made. A row that says “good point, agreed” earns nothing. Students write to the example in front of them, so the example is the instruction.

Make disclosure cheap and specific

Students conceal AI use when policies are ambiguous, punitive, or stigmatizing, and honesty can attract suspicion (AI Use and Disclosure Statements; student rationalization research). What makes disclosure useful pedagogically is that it records decisions: what the tool was used for, what the student gave it, which suggestions mattered, what the student accepted or rejected.

Mohamed and Temimi supply the mechanism. Disclosure becomes the attractive option only when the cost of honesty stays low. Detectors produce false positives against honest students too, so heavier monitoring can make concealment relatively more attractive. Their advice is to design for the student most tempted to conceal and to read a declared use as context rather than a confession.

Two details do most of the work on the form. Ask for specific uses rather than a category, and state how a declaration will affect the grade. A student who does not know will assume the worst.

Four prompts are enough for most assignments: which step of the work the tool was used at, what the student supplied to it, which suggestions changed the draft, and which were rejected and why. That last prompt is the most informative, because a rejection with a reason is evidence of judgment and a list of accepted suggestions is not.

Adjust the rule to what your field calls writing

Composition and writing courses

Composition instructors have the strongest reason to protect the process, because drafting, rhetorical decisions, revision, audience awareness, and voice are the learning objectives rather than the display of them. Collect several independent samples early in the term, so you and the student both know what the writer can do now. Introduce AI as audience, critic, and revision partner: ask where a reader loses the thread, generate objections to a thesis, compare a draft against the rubric, flag unsupported claims, explain why a paragraph feels incoherent. The student judges each suggestion.

Keep peer review alongside AI feedback, since peers supply contextual and audience knowledge the model lacks, and evaluating the difference between the two is writerly training in itself. Be conservative about AI generating long stretches of a first draft when learning to compose is the objective, for the ownership and offloading reasons above. Avoid blanket bans on grammar, phrasing, or language assistance, which create unnecessary barriers for multilingual writers. Separate language support from intellectual authorship instead: help with expression is fine, and the student stays responsible for ideas, evidence, rhetorical decisions, and meaning. Audit the feedback itself, because Tan et al. found that identical writing drew more praise and less substantive critique when student demographic or educational attributes were included in the prompt, which puts bias mitigation inside feedback design.

Humanities and social science courses

Interpretation is usually the target capability, so make the source encounter come before the AI encounter. Students annotate the primary text, historical source, artwork, archival item, interview, or theoretical passage and form an initial reading before consulting anything. Afterward the model works as a foil: offer an alternative reading, say what evidence would challenge this interpretation, name the assumptions the argument makes, generate a reading from a contrasting theoretical perspective. The student decides which reading the text actually supports.

Assign the critique of the model as disciplinary work. Give students an AI interpretation of a poem, event, argument, or social phenomenon and ask what it notices, what it misses, which evidence supports its claims, whose perspective is absent, and where it collapses ambiguity into a smooth answer. That keeps the interpretive judgment a humanities course exists to teach. Assess the interpretive decisions and their evidential justification, and use a short conference question such as “Why did you read this passage this way rather than the alternative you rejected?” Guessing whether a sentence looks machine-written is a weaker measure, as AI detection explains.

STEM courses and lab reports

A qualification first: this knowledge base holds much stronger evidence about AI-supported academic writing generally than about laboratory-report writing in particular. Hands-on and laboratory Pedagogies and Teaching Strategies remain under-covered, including in the engineering education literature, so what follows applies writing, offloading, validity, and engineering findings to a setting those studies did not test.

Draw the boundary around scientific reasoning rather than prose as a whole. Students stay responsible for observations, raw data, calculations, uncertainty, figures, analysis choices, results, and claim-evidence reasoning. Once those exist, AI can reasonably help with organization, readability, transitions, and disciplinary conventions, which is the same surface-and-reasoning split as Chen’s study.

A report package for an AI-era lab course carries the report plus selected raw data, calculations or notebook output, a figure with a student-written interpretation, and a brief statement of how the central conclusion follows from the evidence. For high-stakes reports, ask one or two individualized follow-up questions about a graph, an anomalous result, a methodological choice, or a limitation. Do not let writing fluency stand in for conceptual understanding: automated physics scoring can underestimate conceptual understanding when linguistic expression is weaker, and that falls hardest on multilingual students (Automated Essay Scoring). If reasoning and writing are both objectives, score them separately.

Engineering courses

Professional accountability changes the wording. A review of 99 empirical engineering-education studies identified transparency, human oversight, student independence, privacy, authorship, fairness, and beneficence as recurring ethical concerns, and argued that AI ethics belongs in professional formation rather than in rule compliance alone. In a lab or design report, ask students to disclose assistance and to certify that they have verified the calculations, sources, assumptions, and safety-relevant claims.

Keep one sample the tool never touches

Assisted performance is not independent capability, and you need at least one reading of the second. Occasional withdrawal conditions are enough: brief no-AI writing, in-class interpretation, an oral explanation, a conference, spontaneous revision, or a follow-up problem that transfers the same reasoning to a new case. This matters most when the final paper carries substantial grade weight. It does not mean proctoring every assignment. A few placed samples give you and the student a baseline for interpreting the assisted work, which is the writing-specific case of the argument in How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?.

Read the two pieces side by side and ask whether the reasoning in the assisted one is also visible in the unassisted one. Where it is, the essay is doing its job as evidence. Where it is not, the assisted grade is measuring what the tool supplied. That comparison is also what you have to show a student who contests a mark, because it points at a specific piece of thinking rather than at an impression about the prose.

Decide what AI is allowed to grade

Two results that look contradictory are compatible. Carefully calibrated systems with detailed rubrics and examples can score particular tasks well, and out-of-the-box LLM grading diverges substantially from human judgment. Mathew et al. found weak human-LLM agreement that varies systematically with essay quality: models over-reward short, superficially readable essays, under-reward longer and stronger essays with minor surface errors, and cluster toward the middle of the scale. That pattern supports AI for low-stakes formative feedback, comment drafting, and triage far more than for autonomous summative grading (Automated Essay Scoring).

Students draw a similar line themselves. In an undergraduate technical communication course where ChatGPT scored handwritten writing and students were told so, all 13 participants found the feedback clear and useful for surface-level revision. Most separated feedback utility from evaluative authority: they accepted the critique and insisted the instructor decide the grade (Who Should Grade My Work? Student Perspectives on Transparent AI-Assisted Writing Assessment in Higher Education). Design human oversight as the point where AI output becomes a grade, rather than as a courtesy offered when convenient.

Judge the evidence before you rewrite the syllabus

The case for these designs is promising and not yet strong enough to justify one universal AI-writing policy. Some of the best evidence comes from substantial classroom studies such as PAIRR with its 654 students. Much of the rest rests on quasi-experiments, small experimental samples, conceptual analyses, and

2025-2026 work that is still new: Chen's bounded-writing study had 168 students but only six intact classes, the ownership study used a short experimental writing task, and a study reporting immediate quality gains after ChatGPT practice involved only 21 first-year international students and did not establish long-term transfer (Leveraging ChatGPT in academic writing: ChatGPT enhances students' writing quality, writing experience, and ownership). What the AI in Education knowledge base supports is a set of design principles, and the most reliable cross-study finding in it is to preserve student Learner Agency, evaluative judgment, independent competence, disciplinary reasoning, and human feedback while using AI to widen access to critique, practice, revision support, and linguistic assistance.

That mix has a practical consequence. Change one assignment, keep the artifact, and compare the next cohort against this one on the same measure. A rule you can revise after one term is worth more than a policy you cannot test, and the small studies above will not tell you what happens in your course.

What instructors get wrong about this

A detector will settle whether the writing is the student's. It will not. In a covert field study, 94% of AI-generated exam submissions went undetected and outscored real students, and a controlled study found detectors flagged compliant light AI editing at 38-80% while missing more than 96% of humanized rewrites (Detecting the undetectable? Reassessing academic misconduct procedures in the era of generative AI; Why AI Detection Fails for Academic Integrity). Detection answers a detection question, and validity is a different question.

A course-level policy is clearer than a per-assignment rule. The Nash and Burriss policies were course-level documents, and 22 of 27 permitted brainstorming, 22 restricted or muddied composing, and 22 were silent on reading. One document covering everything tends to be specific about the step the instructor worries about and vague about the rest.

Better prose means the writing instruction worked. The ownership study found better essay quality and lower ownership in the same submission, and Chen's open collaboration condition produced the strongest assisted writing with the weakest later independent performance. Prose quality is a product measure. What the course is for is a capability measure.

Unlimited access plus a good prompt is enough. Students who treat AI feedback as authoritative gain less from it than students with developed feedback literacy. Access to critique and the capacity to use critique are separate assets.

Banning AI protects the writing process. A ban answers a question that differs by step, and it creates barriers for multilingual writers who need language support that has nothing to do with authorship. A workable split runs between expression and intellectual responsibility.

What will come back at you

"I do not have time to read another artifact." Then make the artifact small: four columns of decision table, or five minutes of in-class writing as the independent sample. The corpus reports no marking-time data for these designs, so the workload case has to be tested on one assignment rather than assumed from this page.

“My students will use AI whatever the rule says.” They will, and the design question is which response your assignment makes easiest. A declaration that costs nothing and a rubric that pays for process make disclosure the cheaper path. That mechanism comes from modeling rather than from a trial of a disclosure policy, so treat the prediction as reasonable and unconfirmed.

“A ban is simpler, and it protects the process.” Simpler, yes. The policies above show how a single course-level rule drifts into silence on the steps that matter, and blanket language restrictions fall on students who need them most.

“Peer review is redundant now that AI responds in seconds.” Fifty-eight percent of PAIRR students preferred the combination and 6% preferred AI alone, and the reason they gave was the contextual and audience knowledge peers supplied. That measures experience, so it carries less far than a learning-gain result would.

“The model grades this task as well as I do.” Calibrated systems with detailed rubrics and worked examples can score particular tasks well. Generic grading does not, and Mathew et al. show the disagreement follows essay quality rather than scattering randomly, which is the harder kind of error to notice. Test the tool on your own marked set before it touches a grade.

“This penalizes students whose academic English is weaker.” It can, if the rule treats expression and authorship as one thing. Separate them, and audit the AI feedback for the pattern Tan et al. found, where identical writing drew more praise and less substantive critique once demographic or educational attributes were in the prompt. The corpus documents that bias. It does not report a tested fix, so your own comparison is the check.

What to do this week

1. Write the capability sentence for your next major assignment and put it on the sheet.

2. Add one line requiring the student’s claim, interpretation, or rough draft before any AI use, and say what you will collect.

3. Mark each step of that assignment as construct-bearing or not, and rewrite the AI rule so it allows the tool where the step is not graded.

4. Add a four-column feedback decision table to the rubric, with points attached.

5. Schedule one short piece of writing that no tool touches, and decide now which assignment it belongs to.

Where to go next

The assessment side of this argument, including the design of authenticated steps, is in How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?. For the policy document students actually read, see How Do I Write a Course AI Policy and Communicate It to Students?, and for the feedback tools themselves, AI Feedback Quality. How Do I Teach Students to Verify AI Output? covers what students should be checking when the model supplies a claim or a source, and the concept page Coach not crutch: Evidence that AI can improve writing skill despite reducing effort states the boundary this page keeps returning to.

Connected FAQs

- How Can AI Help Me Give Better Feedback at Scale?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Can We Address Common Misconceptions About AI in Education?

How students learn and use AI

For questions about what students actually gain, what they risk losing, and how to keep the learning with them.

Does Using AI Actually Help My Students Learn?

A student tells you the AI tutor is the reason they finally understood the material, and you have no way to check the claim. Or a pilot lands on your desk with a satisfaction survey and a screenshot of rising assignment grades, and someone wants a decision on the license by the end of the month. Or you are standing in front of a class wondering whether the tool you just told them to open is helping them practice or helping them avoid practice.

The short answer: yes, AI can help students learn, and none of the things you are most likely to see establish that it did: better assignments, faster completion, happy students, or a product called a tutor. What separates the cases where learning improves from the cases where it does not is the design of the activity and the outcome you chose to measure.

The short version

1. Name the capability first, then decide what evidence would show it changed.

2. Measure the same capability later, with the tool taken away, because that is the only measure that answers your question.

3. Put the student's own attempt before the help, and require a response to the help afterward.

4. Grade the verification: what they checked, what they rejected, what they changed.

5. Look at results by prior knowledge, because the average hides the students the design is failing.

Decide what you mean by learning before you look at any evidence

"Does AI help students learn" is not one question. It bundles at least three: does the tool raise performance while it is open, does it build capability that persists when it is closed, and does it change who ends up with that capability. A vendor report, a pilot survey, and a randomized trial can all be honest and still answer different ones.

Write the capability down before the activity. "Produce a polished report" is a different outcome from "select appropriate evidence", "explain a causal relationship", or "detect an unsupported conclusion". The assessment has to reveal the capability you intend to develop, which is the argument in educational measurement and the starting point of AI ed evaluation.

The corpus supports two claims at once, and holding both is the discipline this page asks for. A World Bank synthesis, Can EdTech Close Learning Gaps?, pooled 14 randomized studies across ten economies and estimated a positive average learning effect of 0.125 standard deviations for adaptive and AI-enabled educational technology. It also combined earlier adaptive systems with generative AI tools, found no statistically established advantage for the newer generative tools, and acknowledged considerable uncertainty in that comparison. The result supports the potential of these interventions, not a claim that any chatbot will improve learning. A positive average, in other words, is compatible with a great deal of variation and with no demonstrated edge for the thing you are actually considering.

The more useful studies are the ones that vary the design inside a single experiment. A multisite randomized study with 1,176 first-year undergraduates compared peer feedback, direct AI feedback, self-evaluation followed by AI feedback, and a hybrid sequence of self-evaluation, peer feedback, and AI critique. The reflective and hybrid conditions produced stronger delayed AI-free transfer than direct AI feedback: students did better on a new scientific argumentation task, not only on the essay they were revising. Those conditions also demanded more evaluative work and probably more time, so the study supports the complete feedback design rather than one component in it.

Check whether the gain survives the tool being taken away

This is the most informative check available to you, and it is easy to leave out of a pilot.

The clearest caution in the corpus is a randomized field experiment with nearly 1,000 high school students, Generative AI without guardrails can harm learning. A general-purpose-style interface raised assisted practice scores by 48% relative to control, and the same students then scored 17% lower on unassisted exams. A tutor configured with teacher-designed guidance and hints largely avoided that penalty. It did not produce a statistically significant improvement in unassisted exam performance over the control group. Avoiding harm and demonstrating additional learning are different achievements.

At national scale the same split shows up with a lag. The Generative AI Learning Penalty followed 26,811 Chinese secondary students in grades 7-12 over 30 months using staggered adoption. Homework scores rose 18% and completion time fell 30%, from 64 to 45 minutes. Closed-book monthly exam scores fell 20% within six months, and high-stakes entrance-exam scores fell 18-24% of baseline, but only after about two years. The losses concentrated among the roughly 81% of users whose behavior indicated homework outsourcing, while students who kept homework time comparable to non-users learned about as efficiently. Two things follow for your course: the divergence between homework and exam performance is the performance-learning gap in a national cohort, and the two-year lag means a one-semester evaluation will systematically underestimate the cost.

Computing education shows the same structure. The systematic review of 72 studies found generative AI reliably raised short-term completion and reduced time on task in 36 studies, with not a single study in the corpus documenting a negative effect on immediate performance, and those gains “do not transfer to independent performance” in 21 studies. Codex-assisted students completed twice as many tasks during learning and performed no better than controls on post-tests without AI.

Then there is the question of whether students use the help at all. A two-year randomized school experiment across 18 middle schools, One Click Away, found modest mathematics achievement gains, and students rarely engaged in substantive tutoring conversations. The authors noted that the gains resembled the gains reported for structured practice without AI, and the design combined individualized practice with AI tutoring, so it did not isolate the AI component’s contribution. A capable tutor being available is a different fact from students using it productively.

Making AI Tutoring Productive adds a sharper lesson from more than 6,000 middle school students using NUMI. AI support improved recovery after mistakes and slowed progress through questions. A three-correct-in-a-row mastery rule raised platform-defined success without, by itself, improving learning one week later. The strongest delayed-learning signal appeared when AI was embedded in the mastery workflow, and those

gains were marginally statistically significant and concentrated on particular practiced material. That is suggestive evidence for a structured approach, not a proven recipe.

Build the activity so the student does the thinking that matters

Instructional design matters more than which model you run. The design that survives these results has four turns: an attempt, help aimed at the difficulty, something the student does with the help, and a new application with the support withdrawn.

1. Ask for an initial attempt, prediction, draft, explanation, or interpretation.

2. Offer targeted assistance: a hint, an explanation, a contrasting example, or focused feedback on the point where they stalled.

3. Require a response to the assistance. They explain it, revise with it, verify it, or justify accepting and rejecting it.

4. Check a comparable problem or a different context with the support withdrawn.

That is an instructional starting point rather than a validated sequence, and the right amount and timing of support depends on the students and the task. It reflects what the Scaffolding and active learning syntheses emphasize: support that helps learners understand, practice, evaluate, and eventually perform with less of it.

Apply the principle to the objective, not mechanically to every feature. “Scaffold, do not substitute” is a good rule with a trap inside it. A complete worked example can be something students learn from, and a sequence of hints can still become something they click through without thinking. What matters is what the learner does with the assistance, which is why cognitive offloading and Help-Seeking sit at opposite ends of what the same tool can produce.

The counterexample is worth keeping in view, because it stops you from turning effort into a proxy for learning. In the preregistered experiments reported in Coach not crutch, adults who practiced revising cover letters with AI produced better no-AI writing afterward than those who practiced alone, and they expended less effort doing it. Benefits persisted at a one-day follow-up, and a second experiment found that viewing an AI-revised example produced comparable benefits to practicing with the tool. Those were brief, bounded writing tasks, not evidence of lasting improvement across all writing. They do show that less effort is not automatically less learning, and that the goal is to preserve the learning activity, not to maximize difficulty.

Make the retained thinking visible in what you grade

How students use the tool matters more than whether they have it. In a qualitative study of 38 undergraduates in unsupervised essay assessments, engagement ran from cognitive outsourcing to cognitive reallocation, the shift of effort from low-level retrieval to critical evaluation. Most students, 31 of the 38, intended to use generative AI as a learning assistant. In practice 76.32% relied on single-turn ask, get answer, stop dialogue, and 78.94% used the tool before or after drafting rather than through the task. Only 8 students worked as cognitive partners through sustained, iterative dialogue. That spectrum, from outsourcing to reallocation, is what student-AI interaction describes. One participant described the effect as “the speed at which you forget it is also very fast.”

The pedagogical lesson is that blanket permissions and blanket prohibitions both leave students guessing. What changed behavior, in that study's account, was task-specific guidance about which cognitive work students had to retain and which assistance was appropriate, the design direction developed in How Can I Reduce AI Cheating in My Course? and Reducing AI Misuse.

So make the retained thinking an artifact you can grade. In mathematics, ask for the attempted solution before help is requested, then have students use a prompt like "identify the first step I should reconsider, give me one useful hint, and ask me to try again", and require a new solution plus an explanation rather than a reproduction of the AI's answer. In writing, have students assess their draft against the rubric before requesting critique, then explain which suggestions they accepted, modified, or rejected. If argument construction is the objective, AI prose cannot stand in for evidence that the student can build an argument. If evaluating alternative revisions is the objective, comparing complete examples is appropriate. The writing education and feedback literacy pages carry the detail.

The review's design requirement is the same move at course level: verification, meaning reading, testing, modifying, explaining, and critiquing AI output, made a graded and observable component rather than an aspiration left to student discretion. And not every legitimate outcome has to be demonstrated without AI. A course may deliberately teach effective AI-supported work, in which case you assess the student's ability to select, verify, revise, and defend their use of the tool alongside whatever independent foundations the discipline requires. A Human Capability Test for Learning Outcomes in the AI Era proposes that three-way distinction between independent capability, AI-augmented performance, and verification responsibility. It is a conceptual framework, not a validated instrument.

Check who the tool helps and who it quietly drops

An average improvement can conceal students who gained nothing or hit a new barrier. The digital divide synthesis separates access to a tool from the skill needed to use it and from who ends up with a useful result, and all three matter for a course.

Prior knowledge moderates everything in the computing review: well-prepared students convert assistance into durable skill, while under-prepared students risk using it as a crutch that removes the practice they need. The national cohort study shows the same concentration in its own way, with the learning losses sitting in the 81% whose homework behavior indicated outsourcing.

For a classroom evaluation, break results out by prior knowledge, language needs, and accessibility requirements rather than reporting a course mean. Teaching students how to obtain and evaluate useful feedback is part of AI literacy, and it does not arrive with the license. When you assess independent learning, remove the assistance that supplies the target thinking and leave the accommodations that provide access to the task, which is the distinction Accessibility and equity in AI education both depend on.

Inspect the feedback students actually receive, too. A fluent response can misdiagnose the difficulty, reinforce an error, or hand over an answer where a different kind of support was needed. Use course-aligned materials, keep a route to human help, and collect no more student information than the activity requires. AI feedback quality, pedagogical safety, and Privacy cover the specifics.

Do not trust the dashboard, including your own

Platform metrics are the easiest evidence to carry into a procurement decision, and the easiest to overread. In an evaluation of eight AI teaching agents in medical education, rankings by the platform's own score diverged from an expert-validated teaching-quality rubric. The agent ranked third by the platform ranked last on rubric quality, because the platform score tracked student performance during the interaction rather than the agent's teaching behavior. A built-in metric is a hypothesis to validate.

The same skepticism applies to the evidence you generate yourself. A satisfaction survey measures satisfaction, and perceived learning is a self-report measure that the corpus documents drifting a long way from measured learning. Assignment grades measure the assignment. Neither tells you what a student can do in three weeks with the tool closed, and What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? sets out the comparison designs that get you closer.

What instructors get wrong about this

"Higher grades on the assignment mean they learned more." The two can move in opposite directions. The Guardrails experiment raised assisted practice by 48% while unassisted exams fell 17%, and the national cohort saw homework scores rise 18% while closed-book exam scores fell 20% within six months. Neither pattern would show up in a gradebook that records only the final submission.

"It is a tutor, so it is safe." Tutor is a label, and the results behind the label are mixed. The teacher-configured tutor avoided the exam penalty and did not beat the control on unassisted exams. Khanmigo produced modest gains that resembled structured practice, with little substantive tutoring taking place. NUMI's AI slowed progress through questions. A tutor can withhold solutions and still absorb the practice.

"If it feels easier, it is not teaching them anything." Wrong in both directions, which is why effort is a bad proxy. Coach not crutch found less effort with better no-AI writing a day later, so ease is not the tell. What separates the cases is whether the student did the thinking the objective names, and that is a design question rather than a difficulty setting.

"A blanket rule, or a better prompt, fixes how they use it." The 38-student study found most students in single-turn ask-and-stop mode under exactly the conditions where they had been told AI was a learning assistant. What moved behavior was guidance specific to the task and a graded requirement to verify. A policy line and a clever prompt are both inputs to that, and neither substitutes for it.

"The platform score, or the satisfaction survey, tells me it works." The eight-agent evaluation found a platform ranking that reversed under an expert rubric. Satisfaction and perceived learning are self-reports. Both are worth collecting as process information, and neither is a learning measure.

"Access is the equity problem, and we have solved access." Access is one of three lines, alongside skill and who gets a useful result. Prior knowledge decides whether help becomes skill or a crutch, and the losses in the national cohort concentrated in the group whose behavior suggested substitution rather than in the group without devices.

What will come back at you

“My students say it helps.” It probably does help with the work in front of them, and that is the finding, not a refutation of it. Ask what they can do on a similar task with the tool closed, and you get the answer that matters.

“The studies contradict each other, so why act on any of them?” They rarely contradict once you line up the outcome each one measured. The positive results tend to measure assisted performance, satisfaction, or a well-structured activity with delayed checks; the negative ones measure unassisted performance later. The Burneo synthesis makes the uncertainty explicit: 0.125 standard deviations on average across 14 trials, no established advantage for the newer generative tools. A before-and-after improvement cannot show that AI caused the gain, since students improve through the rest of the teaching, and efficacy research methods sets out the comparison designs that get you closer. Act on the design claims, which replicate, and stay open on the size of the effect, which does not.

“I have 200 students. I cannot run delayed assessments.” You need one short baseline task and one delayed item, not a study. Use the same task type three weeks later without the tool, keep the previous year’s version of the exam as a rough comparison, and sample the work that looks inconsistent with earlier submissions. That is enough to see a 48% assisted gain alongside a 17% unassisted loss if it is happening in your course.

“Khanmigo got a positive result, so tutoring works.” It got modest mathematics gains across 18 middle schools, in a design that bundled individualized practice with AI tutoring, while students rarely held substantive tutoring conversations. Read it as evidence that a well-structured practice environment can produce small gains, not as evidence that the AI component caused them.

“I cannot ban it and I cannot police it.” Correct on both counts, and neither is required. The design question is what your activity makes easy. If verification is graded, disclosure costs nothing, and the unaided check exists, most students take the path you built.

“I do not teach AI. This is not my subject.” The interference happens inside your subject, at the step where AI performs the practice your course exists to provide. That is why the fix is an assignment change rather than a new unit.

What to do this week

1. Take one activity you already run and write the capability sentence: what a student should be able to do afterward, with the tool closed.

2. Add a two-minute baseline at the start and the same kind of item three weeks later. Score both without AI in the room.

3. Change one prompt you give students from “explain this” to “give me one hint, then ask me a question”, and require a revised attempt before they move on.

4. Add one graded verification artifact: a short note on what they checked, what they rejected, and what they changed.

5. Break the result out by prior knowledge for the students you already know are struggling, and read the AI feedback a sample of them received.

Where to go next

What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? covers the measures and comparison designs behind the checks above, and AI Ed Evaluation is the practical evaluation guide. How Is AI Impacting Students? takes the Student Experience side, What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About? compresses the same evidence into instructor decisions, and Limitations in AIEd Research is the honest account of what this literature cannot yet tell you. If your question has become an assessment question, How Can I Reduce AI Cheating in My Course? is the next page.

Connected FAQs

- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- How Is AI Impacting Students?
- What Are the Top 10 Findings from AI in Education Research That Instructors Should Know About?

How Is AI Impacting Students?

You are using AI for coursework and doing fine, except that the closed-book exam felt like reading someone else's notes. Or a friend says they wrote nothing and still got an A, and you are wondering what that means for you. Or you have started asking a chatbot more questions than you ask your instructor.

The short answer, in a form you can repeat to a friend: AI is useful where you need feedback and unhelpful where you need practice. Keep the thinking step for yourself, test yourself without the tool before you submit, and be straight about what you used. The rest of this page is why that holds and what it looks like on a Tuesday night.

The short version

1. Decide before you open the tool which parts of the assignment you will do yourself.

2. Use it to get unstuck, to get Feedback, and to see a worked example. Do the reasoning yourself.

3. Before you submit, close the tab and explain your argument out loud to nobody.

4. Keep two lines of notes on what you asked and what you changed.

5. If using it is making you anxious or ashamed, treat that as information and tell someone.

Decide what the tool is for

AI can scaffold understanding when it explains, hints, and gives you practice at the level you are working at, and when it keeps you doing the cognitively important part. That version also supports Help-Seeking, because you can ask a question you would not ask in front of a room (Does using AI actually help students learn?).

Personalized, immediate, low-stakes support can raise Motivation and engagement, and self-determination theory explains why the useful version works: it feeds autonomy, competence and relatedness. The useless version does the work and leaves all three untouched. Used well, it can also build the AI Literacy, Distributed Cognition and Metacognition people mean when they talk about readiness for an AI-integrated workplace (see adaptive capabilities). None of that comes from using the tool. It comes from what you do while using it. Most students get the good and the bad effects in the same week, which is the argument on Student Experience.

Keep the step you are trying to learn

AI invites cognitive offloading, which means handing over the reasoning you were supposed to practice. The clearest case is a field RCT where an unguarded AI tutor improved practice performance and reduced later exam performance (AI Misuse and Learning Harm). You get better at the tutored task and no better at the thing the exam measures. Overuse can also wear down Metacognition and Self-Regulated Learning, so you lose the ability to tell whether you know something.

A 2026 synthesis of 72 studies in computing education puts numbers on it. Generative AI reliably raised short-term completion and reduced time-on-task across 36 studies. The gains "do not transfer to independent

performance” across 21. Benefit depended on prior knowledge: well-prepared students converted help into durable skill, and under-prepared students used it as a crutch that removed productive failure, which widened competence gaps inside one classroom (Kumar et al., systematic review).

Take that personally if you are behind in a subject. If you cannot yet tell a good explanation from a confident one, the tool is not neutral help.

Knowing it is there also changes what you are willing to struggle with. AI availability and motivation documents the reduced willingness to sit in productive failure, and passive acceptance of output can erode Learner Agency and the sense of having done the work (see the safety gap).

Test yourself without the tool

The check takes ten minutes and it is the most useful thing on this page. Close everything, take a blank page, and write the argument of your submission from memory: the claim, the two or three reasons, and what would count against it. Then open your work and compare.

If the blank page comes out close, you learned the material and the tool helped you organize it. If it comes out empty while the document is polished, you have a performance gap, and the grade will hide it until an exam or a placement does not. Go back to the section you could not reproduce, work it without help, and check again.

Be straight about what you did

AI enables new forms of academic dishonesty, and your course rules are probably less clear than the ones you grew up with. Find out in writing what your instructor allows, before the deadline, then describe what you did in plain language.

Shame and guilt around AI use push students toward hiding, and hiding costs you the one thing that resolves a concern, which is an accurate account of your process. Access is uneven as well, and that is an equity problem you did not create, though it can still land on you. If your access is thinner, the strategy here matters more, because none of it depends on which subscription you have.

When AI produces the text, the result can stop feeling like yours, and that is a real cost. It is an authorship threat to learner identity, and the competence paradox in creative fields shows the mechanism: the easier the output, the less the craft-based identity students get from making it. If you can say why this example and not that one, the work is yours no matter which sentences you typed first.

Look after the worry

AI use is associated with anxiety and stress, about being replaced, about assessment you cannot predict, and about keeping up (see comprehensive analysis of AI anxiety). Association is the right word, and the measurement literature is careful about it.

Zhang, Shi and Lu surveyed 1,484 undergraduates and found AI anxiety negatively correlated with academic motivation ($r = -0.175$) and with emotion AI Regulation in Education ($r = -0.172$), with emotion regulation partially mediating the path from anxiety to motivation (indirect effect = -0.076). Daily usage duration predicted almost nothing ($r = 0.053$). Their conclusion is that literacy instruction should pair with emotion-

regulation and metacognitive support, not simply expand tool access (Zhang et al., AI anxiety and academic motivation).

One caution before you diagnose yourself. A critical synthesis of 51 records on conversational AI finds that trust, reliance, over-reliance, attachment and dependence get routinely conflated, and that the cross-sectional correlates with loneliness, anxiety, fatigue, procrastination and weaker critical thinking do not establish causation. Frequent use is not dependence without impaired control or functional harm, so a heavy week is not a disorder (Yan, conversational AI engagement and dependence synthesis).

The emotional side can also be good. In a qualitative study of 28 nursing students and faculty, several described AI as a "companion" that gave comfort and a non-judgmental space during clinical stress (Akbaba & Calik Kus, nursing education). The comfort is real and it can shade into reliance, so the Well-Being question and the learning question need answering together. Talking to a person about the stress is the part a chatbot cannot do, and social-emotional support is a human practice first.

What students get wrong about AI and their own learning

A better submission means you learned more. The computing education synthesis found short-term completion rising across 36 studies while the gains failed to transfer across 21 (Kumar et al., systematic review), and the field RCT found practice improving while later exam performance fell (AI Misuse and Learning Harm). The document and the learning are two outputs, and only one is graded.

Using it more will fix your anxiety about it. Anxiety correlated with lower motivation and lower emotion regulation, while daily usage duration predicted almost nothing ($r = 0.053$), so more hours is not the lever (Zhang et al., AI anxiety and academic motivation). The lever in that study is emotion regulation and metacognitive support.

Everyone else is using it, so you are behind if you do not. Under-prepared students in the synthesis used the tool as a crutch and lost the failure that would have closed the gap (Kumar et al., systematic review). If you are behind, work the basics without the tool and use it to check yourself afterwards.

A lot of use means you are dependent. The synthesis of 51 records is explicit that trust, reliance, attachment and dependence get conflated, and that frequent use counts as dependence only with impaired control or functional harm (Yan, conversational AI engagement and dependence synthesis). Ask instead whether you can stop for a week and still do the work.

What your friends will say

"It is just a tool, like a calculator." A calculator removes arithmetic you already learned. The RCT and the synthesis describe a tool that can remove reasoning you have not learned yet, which is why the same use leaves one student stronger and another weaker (AI Misuse and Learning Harm, Kumar et al., systematic review).

"I only use it for editing, so it does not count." Editing is legitimate in many courses, and it is also the use that gets flagged most readily, which is an argument for disclosing it. What counts is set by your course, so get the answer in writing.

“If I stop, I will fall behind.” The short-term gains are real and the transfer is the weak part (Kumar et al., systematic review). Falling behind is measured by what you can do in a room without the tool, which is where the exam, the placement and the interview happen.

“My grades are fine, so nothing is wrong.” Grades are a performance measure, and the performance-learning gap is exactly the case where they look fine (AI Misuse and Learning Harm). If you want to know whether you learned something, ask what you could do without the tool.

What to do this week

1. Pick your next assignment and write down the one step you will do with no tool open.

2. Run the blank-page check on something you submitted last month. Ten minutes, from memory.

3. Add two lines to your workflow: what you asked the tool, and what you changed.

4. Ask your instructor, in writing, what counts as allowed use on the next assessment.

5. If the worry is the bigger problem, tell one person this week.

Where to go next

Does using AI actually help students learn? is the evidence question behind this page, and How Should I Use AI to Study and Learn Effectively? covers working routines. How Does AI Affect Student Anxiety and Well-Being, and What Can We Do? takes the anxiety side further, and Guardrails explains how a scaffold becomes a substitute. The course-design view is in How should I incorporate AI literacy into my course? and What is the evidence on AI literacy interventions in higher education?.

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Should I Use AI to Study and Learn Effectively?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?
- How Should Parents and Teachers Approach AI with Children Under 13?

How Do I Keep Students from Over-Relying on AI?

A student aces the take-home problem set and leaves half the exam blank. Someone hands in a lab report they cannot walk you through, or a block of code they cannot explain line by line. A colleague wants the tool banned in the first-year course and you are weighing what that costs the students who lean on it most.

The bottom line: over-reliance is mostly a placement problem. The designs that reduce it put the student's attempt ahead of the tool, configure the AI to hint instead of answering, make the check a required deliverable, and keep one graded moment where the tool is absent.

The short version

1. Put the student's own ideas, hypothesis, or rough draft in front of the tool before it opens.

2. Configure the AI to hint, ask, and give examples wherever the target skill is what you grade.

3. Make verification a deliverable with its own line on the assignment.

4. Keep the graded moment tool-free, and compare the assisted work against it.

5. Time the reflection prompt to the phase of the task it can still change.

6. Look at who your design leaves behind, by prior knowledge rather than by average.

Decide whether you have a problem, or just heavy use

Cognitive offloading is the transfer of a cognitive demand to an external tool, which frees limited mental resources for other work. Guo and Ye (2026) review the construct through Nelson and Naren's dynamic metacognitive model, where monitoring of difficulty drives a decision to offload to an internal or an external strategy. Offloading is a self-regulatory choice, and the failure worth worrying about is miscalibration; volume on its own tells you little.

Biswas (2026) models reliance as three actions: solve alone, accept the AI's answer unverified, or use it and verify. Calibration fails in both directions. Over-reliance is accepting wrong output, and under-reliance is discarding useful AI after it errs. Collective over-reliance is a population that has abandoned verification, and because raw over-reliance diverges from regret, heavy use is compatible with good outcomes. The student who checks every AI answer against your materials is not your problem. The one who submits a model's first draft is.

Lodge and Loble (2026) describe the mechanism as "fluency on demand": coherent, confident output that bypasses the desirable difficulties of retrieval, elaboration, and generation through which knowledge is consolidated. Their performance paradox is that assisted work feels fluent and students perform well in the moment while retaining less, which they call an illusion of competence. They name metacognitive laziness (after Fan et al. 2024), where convenience lets learners abdicate self-regulatory processes they need to develop.

Telling them apart in your own course takes a comparison rather than a number. Look for work that is better than the student's earlier work and worse than their explanation of it: a strong problem set followed by a

weak exam, a polished report the student cannot discuss, a correct answer that cannot be reproduced on a similar problem. No single pattern proves anything. Two or three together justify changing the design.

Most of what you can measure here is self-report. Gerlich (2025) surveyed 666 UK participants with 50 interviews and found AI use negatively correlated with critical thinking (r = -0.68), with offloading partially mediating (total effect b = -0.42; indirect b = -0.25). Gao, Sun and Khan (2026) used three-wave time-lagged survey data from 623 Chinese students plus educator interviews and found that effective AI use raises sustainable learning performance and over-reliance at the same time. Both designs are correlational, and both say so.

Behavioral instruments are thinner. PAUSE (Alam, 2026) is a browser-only self-check with no reliability or validity evidence, and its authors warn about item validity. The items record when and how often AI enters a workflow, not whether the student's own reasoning stayed engaged, so a student who scaffolds deliberately with AI early will honestly score as an offloader. PAUSE also cites Padmakumar et al.'s (2026) Offloading Score, which estimates the fraction of effort offloaded from behavioral logs (n = 40 developers). What you want to know is what the student can do unaided.

Put the student's attempt in front of the tool

The clearest tested sequence is "think first, ChatGPT later." Wong and Qiu (2026) assigned N = 196 students to work independently, to use ChatGPT freely, or to work in a regulated condition: generate your own ideas, collaborate with ChatGPT to improve and evaluate them, then independently refine and submit one solution. The free-use group produced more creative work on the assisted task and fell back to human-only levels on a later, harder task done without ChatGPT. The regulated group showed no immediate advantage and outperformed both other groups on independent Creativity afterward.

Prompt data explains the gap. In the regulated group, 88.6% of prompts were collaborative, and that was the only prompt type significantly correlated with later independent originality. In the free-use group, 70.9% of prompts were non-collaborative and 59.6% simply asked ChatGPT to generate ideas outright. The same tool, asked two different ways, produced two different learners.

On your assignment sheet this becomes an ordering instruction: ideas, hypotheses, or a rough draft first, then the tool. A sentence at the top of the page is enough, provided the next step collects what the student wrote.

Two classroom details decide whether the sequence holds. The first is time. If the independent phase happens outside class, some students will open the tool first and write the ideas down afterward. The second is collection. If nothing is handed in from that phase, the sequence exists on paper only. Half a page of notes, collected at the end of class, is enough to make the order real.

Configure the tool to hint instead of answer

Brcic and Frljic (2026) report the sharpest version of the placement argument. An unguarded AI helper left high-school students roughly 17% worse on an unaided exam than peers who had no tool at all. The same model rebuilt to withhold answers erased the harm, and a well-engineered tutor roughly doubled learning. Their diagnostic is usable in any course: if letting AI in makes the task feel effortless, the tool is in the wrong place.

Zohar, Bloom and Inzlicht (2026) give that argument a shape. They argue the link between effort and meaning is an inverted U, so the target is a gradient: remove overwhelming obstacles and preserve the struggles that produce comprehension and ownership, with assistance as a supplement. Their argument is a conceptual Comment with no new data, and the inverted-U relationship rests on a single empirical anchor without being quantified, so nobody can tell you where the optimum sits for a given learner.

Practically, that means guarded AI in the middle of the task, where hints, worked examples, and practice items do the work, and a secured check at the end. It also turns an AI-use policy into a per-skill placement rule, which is easier to write and easier to defend than a list of prohibitions.

A hint is a question about the student's next step, a worked example of a similar problem, or a pointer to the relevant passage. An answer is a finished sentence the student can paste. Most general-purpose chatbots produce the second by default, in fluent prose that reads like help, which is why the configuration matters more than the student's intentions.

Require the check, and make it visible

Verification is the cheapest lever with real causal support. Biswas (2026) found that making verification visible triggered a counter-cascade to near-complete verification: over-reliance fell to 0.00 and regret to 0.07. Reducing the friction of checking was the weakest lever in the same model, because the barrier is social rather than mechanical. A link to the library does not make a student check a claim.

Viberg and colleagues (2026) found the students who already do this well check output against course materials, peers, or instructors when accuracy is uncertain. That is a behavior you can require. Put one line in the assignment: what you checked, and against what. Read it as part of the grade, and the norm becomes visible to the whole class rather than to the conscientious few.

That line also gives you something to follow up. When a student writes that they checked a claim against the course text, you can ask which page. When they write that they compared with a peer, you can ask what the peer said. It costs a sentence. The follow-up question is what makes students treat it as work.

Verification also needs a scope. Checking that a claim matches the course text is a different act from rereading a sentence for grammar, and the first is where the model fails more often. Say which one the line asks for, or you will get proofreading.

Demonstrate one confident failure

Set a task whose answer the model gets confidently wrong, then have the class check that answer against the course text. It lands because the error arrives in the same voice as the correct answers. Add the evidence afterward: an unguarded helper left students roughly 17% worse on an unaided exam, and students given GPT-4 solved more problems with the tool and performed worse than controls once it was removed (PAUSE reports Bastani et al., 2025). The same source adds that Liu et al. (2026) found assistance reduced persistence in randomized controlled trials (N = 1,222).

Choose a failure that is modest and checkable, such as a citation that does not exist, a date that is wrong, or a calculation that does not close. Then ask the class to write the correction and the check they used to find it.

That written correction is the artifact, and it tells you whether they can do the check without you standing over them.

Keep the graded moment tool-free

The assisted product is a poor proxy for capability, so at least one graded moment has to happen without the tool. Wong and Qiu's (2026) later unassisted task is that measurement. Their human-only group also declined on the harder follow-up, which rules out the simple version of the fix: removing the tool without supporting the learner is not an intervention.

Alternating modes has support. PAUSE reports Kosmyna et al.'s (2025) session-four result, where brain-only participants who later used ChatGPT outperformed sustained Large Language Models (LLMs) users. Accountability works through explanation as well: Makransky et al. (2025) found that a tutoring chatbot which prompted students to connect ideas and explain their reasoning produced better assessment performance than traditional instruction.

For a course, alternate: assisted work in practice, unassisted work where it counts. Read the assisted piece as a record of performance under good conditions, and the unassisted piece as the evidence about learning. Comparing them is also the most useful conversation you can have with a student who cannot understand a mark.

Scheduling is the constraint. A tool-free moment needs a room, a time, and a task that fits in it, so the cheapest version is a short in-class piece attached to an assignment you already set. A separate exam is a larger commitment and usually not necessary for the first attempt at this.

The unassisted piece earns a second use as well: give it back at the start of the next unit, and both of you can see what survived the break.

Separate instrumental help from executive help

Viberg, Feldman-Maggor and Wong (2026) interviewed 20 STEM university students and found a four-stage process: deciding whether help is needed, choosing a source, choosing the type of help, and judging the help received. Stronger students favored instrumental help, meaning hints and explanations, over executive help, meaning direct solutions. The same study warns that using LLMs for debugging or cross-language programming can bypass independent problem solving even when students never ask for an answer.

That maps onto cognitive offloading cleanly. Instrumental use is the duplicative offloading that holds up when the tool goes away, because the student still encodes the reasoning. Executive use is the substitutive offloading that collapses when the external store is removed. Guo and Ye (2026) draw the boundary in exactly those terms: remove the store and substitutive offloaders decline severely, while duplicative offloaders keep their accuracy through internal encoding.

Write the distinction into the assignment. Ask students to label each AI use as instrumental or executive, require at least one collaborative prompt, and grade the reasoning they added after the response. In Wong and Qiu's free-use condition, the default drifted toward executive use without anyone deciding to drift.

Not all offloading is suspect. PAUSE cites Hong et al. (2025), where deliberately offloading lower-order writing tasks to free attention for analysis and revision produced larger critical-thinking gains. The test is whether the part being offloaded is the skill you are grading.

Those labels also diagnose your task. If most of a class reports executive use, the assignment is inviting it, whatever the policy says, and the next change belongs in the task rather than in the wording of the rule.

Time the prompt to the phase

Feedback that targets a stable belief works before a task starts. Feedback about immediate correctness and difficulty works during it. Guo and Ye (2026) call this timing-component matching, and it explains why a reflection due at the end of a project changes so little: by then the choices are made.

Lodge and Loble (2026) recommend integrated metacognitive prompts that make learners pause, reflect, and assess their understanding as they work, alongside Load Reduction Instruction, which manages cognitive burden while enabling progressive independence. A one-minute prediction before a hard unit, written down and compared afterward, fits that window and costs nothing to mark.

The wording of the prompt matters less than its position. Before a unit, ask what the student expects to be hard and why. During it, ask which step they are stuck on and what they have tried. An end-of-project reflection mostly records what happened, which is why it changes so little. Keep the prediction on the same page as the work, so the comparison at the end costs no filing.

Expect the risk to cluster

Lodge and Loble (2026) locate the risk in prior knowledge and self-regulation and name a **metacognitive equity gap**: using AI well requires resources that novices lack, so the students who most need the practice are the likeliest to delegate the learning itself. They report that 80% of Australian students already use AI and that two-thirds of early secondary teachers do (OECD 2025).

Age and habit correlate with the same pattern. Gerlich (2025) found participants aged 17-25 showed higher AI dependence and offloading and lower critical thinking than those aged 46 and over, and that attainment predicted better critical thinking regardless of AI use ($r = +0.34$), with a significant interaction indicating that attainment mitigates the negative effect. Gao, Sun and Khan (2026) found polychronicity, a tendency to multitask, moderates the pathway, with high-polychronicity students at greater risk.

For a section, that argues for watching the students with the weakest preparation most closely, and for checking whether your own task has created the conditions where checking stops. A demanding task paired with a capable model is the combination Biswas's model flags for the most regret, and it is easy to create by accident.

Context matters as much as person, and your course controls part of the context. Biswas (2026) shows that task difficulty and AI quality set the baseline: over-reliance rises from about 0.02 to 0.38 with difficulty, and on hard tasks it runs at 0.38 with poor AI against 0.16 with good AI. The highest regret comes from high-quality AI on hard tasks (0.441), because agents over-defer and rarely self-rely. Social proof compounds it: as visible use rises from 0 to 0.6, verification collapses from 0.29 to 0.002. Checking stops exactly where the model is strongest and the task is hardest, which is rarely where an instructor looks first.

Decide how much weight the evidence carries

Nothing in this corpus tests whether a specific over-reliance intervention holds across settings or semesters. Think-first rests on one experiment with N = 196. The withholding result comes from Brcic and Frljic's (2026) synthesis rather than from a trial of its own. The friction argument is a conceptual comment with no new data. Biswas (2026) states the limits of the model: exogenous stationary AI quality, a fixed network, stylized verification. Estimating the real values would need longitudinal traces of per-task verification rates, social-proof strength, and how trust updates after verified as against unverified use.

Measurement remains the weakest link. Survey designs dominate, and both Gerlich (2025) and Gao, Sun and Khan (2026) call for longitudinal and experimental follow-up. PAUSE has no psychometrics and was built for adults. Whether the equity gap can be closed by instruction is theorized rather than demonstrated.

That leaves you with a reasonable bet, made cheaply. Change one assignment, keep the unaided measure, and check whether the gap between assisted and unassisted work narrows. Do not rebuild a course on the strength of these numbers.

What instructors get wrong about this

The students who use it most are the ones in trouble. Frequency is what surveys capture and dashboards display, and it is not the construct. A student who checks every answer and cites your materials can use AI daily and be fine. A student who submits the first output once a week has the problem.

A ban removes the risk. The strongest results here come from placement, and the human-only arm of Wong and Qiu's experiment also declined on the harder follow-up. Removing the tool without supporting the learner leaves the difficulty where it was.

Cheaper checking will fix verification. Making the check easier was the weakest lever in Biswas's model, because the obstacle is social. A better plagiarism checker does not make a student read the source.

A usage dashboard tells me who is offloading. PAUSE's items record when and how often AI enters a workflow, and the authors flag the validity problem themselves. A careful scaffolder scores as an offloader, so acting on those numbers punishes the students you want to keep.

Fluency and satisfaction show the design is working. That is the illusion Lodge and Loble (2026) describe in their performance paradox: work feels fluent and students perform well in the moment while retaining less. Unaided performance and delayed transfer are the measures that answer the question.

Teach AI literacy to students and the problem goes away. Lodge and Loble (2026) caution that over-investing in student-facing AI literacy may be the wrong allocation, given what novices lack.

What will come back at you

"This is just good Pedagogies and Teaching Strategies with a new name." Partly. Scaffolding, formative feedback, and productive struggle are old ideas. What is newer is the ordering: visible verification beat cheaper verification, and the two moments worth protecting are the first hard attempt and the final unaided check. Do the familiar things in the new order.

“I cannot police it.” You cannot, and the evidence says not to try. Placement produced the strongest result. Design the task so that using the tool at the wrong moment shows up in the work itself, as an answer the student cannot explain or a verification step that is missing.

“My course is too large for a sequenced unit.” The cheap levers scale: a verification line, a one-minute prediction, and moving the graded check to an AI-free room. The expensive item, a fully sequenced think-first unit, can start as one assignment. Regenerate one problem set into assisted and unaided halves and see what the gap tells you.

“My students are novices. They need the help.” They need hints more than answers, and the equity finding is the reason. The students with the least prior knowledge are the most likely to delegate the reasoning, and a tool that withholds answers keeps the practice where it belongs.

“Will the weaker students not just fail the unaided check?” Sometimes they will, and that result is information rather than a verdict. A tool-free check that much of a class fails says the practice was carrying the performance, which is the thing you needed to know. Weight it as evidence, reteach what it exposes, and offer a second attempt on a parallel task. No study here tests whether reteaching after a failed unaided check recovers the learning, so that part is your professional judgment.

“Some of my students use AI as an honest scaffold. Am I supposed to stop them?” No. A student who reads a hint, tries the step, and checks the result is doing the duplicative offloading that survives the tool being removed. What you want is a task that keeps that use available and makes the executive version less rewarding, which is a matter of what the task collects and what the rubric pays for.

“The evidence is thin, so why change anything?” It is thin in specific places, which the limits above name. What is consistent across the studies is the direction: placement, visible checking, and an unaided measure. One changed assignment, with the unassisted result kept, is a small enough bet to run on that basis.

What to do this week

1. Add a verification line to the next assignment: one sentence naming what the student checked and against what.

2. Move the graded check to a moment without the tool, and grade that one.

3. Put the first hard attempt before the tool, and collect the ideas, hypothesis, or draft that comes out of it.

4. Change the tool setting you recommend so it hints rather than answers, and tell students that is what you did.

5. Run one confident AI failure live, have students catch it against the course text, and keep the correction they wrote.

Where to go next

The neighboring question, whether AI produces learning at all, is covered in Does Using AI Actually Help My Students Learn?. How Can I Reduce AI Cheating in My Course? handles integrity and the limits of detection, and How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About

What the Student Knows or Can Do? covers the assessment architecture this page assumes. For the underlying ideas, see Cognitive Offloading, Metacognition, and Desirable Difficulties.

Connected FAQs

- How Should I Use AI to Study and Learn Effectively?
- How Do I Teach Students to Verify AI Output?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?
- How Can AI Support Disabled and Neurodivergent Learners in My Course?

What Does Personalized Learning Actually Mean, and When Does It Help?

The platform promises a personalized experience for every student. It might reorder practice questions, rewrite an explanation around a student's interest in football, remember last week's conversation, or pick what the student studies next. All four get called personalization, and only one of them has been tested in anything like that form.

Short answer to give a colleague: personalization names a change to some part of the learning experience, and its value depends on three things, what is adapted, what evidence drives the adaptation, and whether the change improves the learning you intend. A familiar example or a responsive conversation can feel personal while teaching nothing. An effective adaptation can be invisible. The clearest experimental result in this knowledge base is narrow: in a five-month Python certification course across ten Taipei high schools, students randomized to adaptive problem sequencing scored about 0.150 standard deviations higher on an in-person, unassisted final exam than students with a fixed sequence and identical chatbot access (Chung et al., 2026). That supports sequencing under specified conditions. It does not validate everything sold as personalized.

The short version

1. Name which part is adapted: presentation, interest context, difficulty and support, sequence and pacing, or goals and choice.

2. Ask what evidence triggers the adaptation, and how a wrong learner model gets corrected.

3. Check whether the adaptation preserves the destination or quietly lowers it.

4. Compare against a credible alternative, not against no support at all.

5. Measure independent performance, not satisfaction with the experience.

6. Watch self-regulation. Perceived personalization has been associated with weaker self-regulation, not stronger.

Five things get called personalized learning

Presentation changes are the least controversial: shorter text, simpler vocabulary, a different format or modality. What you verify is that access and comprehension improved while the meaning survived.

Interest and context adaptations rewrite examples, analogies or professional settings around the student. Familiarity does not establish much on its own, so ask whether the context is accurate and genuinely useful for the concept.

Difficulty and support adaptations vary challenge, hints, worked examples or feedback. They earn their place when support follows demonstrated need and leaves the worthwhile effort in place.

Sequence and pacing adaptations choose the next task and how long practice continues. This is the only form with experimental support in the evidence below, and it still depends on the learner model being good enough to justify the choice.

Goals and choice adaptations let students pick a project, pathway or application. They help when the choices serve a worthwhile goal and still permit progression.

Adaptive learning is one mechanism for the third and fourth: the system changes instruction in response to information about the learner. Personalization also happens through instructor judgment, static options and learner choice. Keeping the two concepts apart matters because evidence for adaptive sequencing does not transfer to interest-based rewrites of the reading.

What the evidence shows

A specific adaptation improved unaided performance. Chung et al. built a platform coupling a guarded chatbot for Python with a Reinforcement Learning algorithm that selects the next practice problem, and deployed it with ten high schools in a five-month certification course. Students were randomized between adaptive sequencing and a fixed sequence, with both groups holding the same chatbot access, which is the design that lets sequencing claim the difference. The 0.150 standard deviation advantage appeared on an in-person, unassisted final exam. Two things are worth holding onto: the comparison isolates sequencing from access, and the outcome is unaided performance rather than engagement. What the study does not show is that personalized explanations, rewritten materials or remembered preferences help. Those were not the intervention.

Perceived personalization can travel with weaker self-regulation. Li, Lin and Qiu (2026) followed 486 Chinese undergraduates across three survey waves and found that students who perceived their adaptive environment as more personalized reported weaker self-regulated learning. Academic emotions carried much of the association, with reduced enjoyment alongside heightened anxiety and boredom accounting for more than half of the total effect. The design is observational and self-report, so it cannot establish that personalization caused the decline. It does identify the outcome a pilot must monitor, because a system that answers every uncertainty fast can remove the planning and judgment that the course is meant to build.

Interest and understanding are separate checks. The Personalized Learning synthesis discusses Bernstein and Sibia's *Flawed but Memorable*, a small qualitative preprint on interest-personalized computing analogies. Student reactions varied, and familiarity with the analogy's source domain helped them detect where the analogy broke down. The practical reading is to ask what learners already know as well as what they enjoy, and to treat reported memorability as an experience measure rather than a learning result.

Check the diagnosis before trusting the adaptation

An adaptive system can only choose a sensible next task if its estimate of the learner is any good, and the estimate rests on signals with unequal reliability. A correct answer may have been guessed, copied or reached with help. A slow response may mean an interruption or an accessibility need rather than difficulty. Stated interests say nothing about prerequisite knowledge, and self-ratings are calibrated unevenly, which is the metacognitive problem the same evidence base keeps finding.

Treat every signal as fallible evidence and keep a way to correct an inaccurate profile. Give students a route to see why a task was chosen and to say that the diagnosis is wrong. An invisible learner model that a student cannot challenge is a design defect regardless of how well it predicts.

For anyone building these systems there are two separate evaluations to run: does the learner estimate reflect the relevant capability, and does acting on it improve outcomes? A model that predicts the next answer accurately has passed the first test and neither earned nor addressed the second.

Preserve challenge, choice and a way back

Adapt the support without lowering the destination. Clarifying the directions or inserting a worked example helps a student reach a demanding outcome. Permanently diverting a struggling student to easier material prevents that outcome. Make the route back visible, and check how many students are on it, because remediation is where adaptive systems quietly lose people.

Let learners inspect and influence the recommendation. Explain why a task is being suggested, allow correction of the profile, and keep a reasonable path to the generic disciplinary explanation for the student who wants it.

Build independent checks into progression. A success streak inside a platform is a progression rule, not evidence of durable learning. Use a delayed or varied task to see whether the capability survives the removal of support, which is the same distinction over-reliance turns on.

Collect proportionate information. An interest-based example rarely needs a detailed personal history. For mastery decisions, collect evidence about the skill and define retention and access. More personal data does not automatically produce better instruction, and it does create an obligation.

What this looks like in a course

In an introductory mathematics course, a short diagnostic can separate a prerequisite misconception from an arithmetic slip. The student with the misconception gets a targeted explanation and a worked example. The other proceeds to application. Both then complete a comparable independent task, including one application in a changed context.

Students can choose among familiar application contexts while the mathematical goal stays fixed and visible. The instructor checks whether either route improved understanding, whether students can explain their reasoning, and whether anyone became stuck in remediation. Treat it as a design to pilot; no platform has been validated in this configuration.

In a reading-intensive course, a glossary or optional explanation may improve access. If disciplinary reading is itself the target, students still need supported practice with the original texts, and the syllabus should say which part of the task the adaptation is assisting.

Evaluate what personalization adds

Compare the personalized version with something credible: a well-designed common sequence, the same tutor without adaptive sequencing, or a curated menu of examples. If your personalized arm also adds more practice, more feedback and more time, the comparison cannot isolate personalization, and the honest report will say so.

Measure unaided performance, retention or transfer where you can, time and effort, learner agency and who benefits. Keep satisfaction and perceived fit as additional outcomes rather than the headline. Decide

beforehand what improvement would justify the development, monitoring and data-handling costs, because those costs are paid whether or not the effect appears.

What will come back at you

“Students prefer it, so it works.” Preference is evidence about the experience. The Chung study is the model of the alternative: same tool, same access, one difference in sequencing, and an outcome measured without the platform present.

“It remembers the student, so it is personalized.” Memory is a feature. The questions are whether the remembered information is accurate, relevant, revisable and used to make an instructionally better decision.

“Every student needs a completely different course.” Usually the useful variation is narrower: an explanation, a sequence, a hint or a context, inside shared goals. Test the smallest adaptation that addresses the need you identified.

“The personalization paradox is just students who were already struggling.” It might be, since the design cannot separate the two. That is why the pilot has to measure self-regulation directly, at more than one time point, rather than assume the association runs in the direction the marketing claims.

What to do this week

1. Choose one learning difficulty and name the adaptation you expect to address it.

2. Write the evidence that will trigger the adaptation and what happens when the evidence is wrong.

3. Specify a credible comparison and one unaided learning check.

4. Ask two students whether the recommendation was useful and whether they knew how to redirect it.

5. Note one thing the adaptation might be removing, such as productive difficulty or a decision the student should be making.

Where to go next

Personalized Learning is the concept page for the definitions, the marketing vocabulary and the evidence base, and Adaptive Learning covers the mechanism and its measurement. Intelligent Tutoring is where the learner model meets the tutor design.

For designing an activity in which personalization is one decision among several, see designing AI into the learning experience. For how to tell whether the system works before you scale it, see checking whether an educational AI works.

Connected FAQs

- How Should AI Be Designed Into the Learning Experience?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- How Do I Keep Students from Over-Relying on AI?
- Does Using AI Actually Help My Students Learn?

How Do I Teach Students to Verify AI Output?

It is the week before grades are due and two submissions cite sources that do not exist. Both students say they checked. One opened the link. The other read the paragraph and decided it sounded right. You have already told this class to verify what the chatbot gives them, and the telling did not produce the behavior.

Verification is a sequence you can build into an assignment. Decide what counts as correct before the task starts, have the student commit to an expectation in writing, send them to the record instead of their impression of the prose, and grade the record they produce. A rubric line that says “checked sources” measures none of that.

The short version

1. Write the answer key first. A check needs something to resolve against, and most verification assignments never define what correct means.

2. Require a prediction before the output appears, so the student’s reasoning exists on paper before the tool can overwrite it.

3. Name the target of every check: the author list, the venue, the year, the specific number, the specific step. “Make sure it is right” is not a check.

4. Separate the check a machine can run from the judgment only a reader can make, and teach students which one they are doing.

5. Grade the record against the key, not the effort, so that checking theater earns nothing.

6. Schedule the check inside the task. Time pressure is a documented reason students skip it.

Decide what correct means before anyone checks anything

Wei and Shang (2026), reviewing 493 deduplicated records and mapping 14 priority empirical studies, separate seven things that “critical AI use” collapses into one: epistemic evaluation, verification initiation, process quality, verification success, reliance decisions, immediate task performance, and independent learning. Your rubric says “checked sources,” which sits at step two and tells you nothing about whether the check was competent or whether it changed the student’s answer. Initiation is not success. A strong process can end inconclusive, a weak one can land on the right answer, and a student who ran a search and stayed confused scores the same as one who resolved the question.

The same review draws a second line, between Trust and reliance. Reliance calibration asks whether a reliance decision was appropriate given the actual quality of the output, which ties the judgment to one decision and one output. One audited study found that false ChatGPT information shifted participants’ reported trust and never recorded whether they later accepted or rejected a specific recommendation. Another logged accept and reject decisions on ChatGPT Feedback for 78 translation students, but with no independent expert evaluation an acceptance cannot be called appropriate and a rejection cannot be called justified. Without ground truth about output quality, reliance cannot be classified at all.

That is the design consequence, and it is the first thing to fix. Before you set a verification task, write two short descriptions: what a correct output looks like for this task, and what a plausible but wrong output looks like. One of each is enough. Students then have a standard to check against, and you have something to mark the check against other than whether the student sounds careful.

Have them commit before the tool answers

Gousopoulos (2026) builds a measurement program around *predict before you run*: the learner states what should happen, then the artifact's behavior is judged against that prediction on domain grounds rather than by whether it runs. The reasoning exists before the output does, which is what makes it gradable.

His audit of 24 studies found the same tool producing opposite outcomes under different task structures. A conventional ChatGPT setup ended significantly lower in achievement, Self-Efficacy and flow, while a condition that added verification requirements and error-reflection modules showed stronger higher-order thinking. The tool was constant across those conditions. What varied was whether the task asked the student to hold a position the tool could contradict.

In practice that is one line on the assignment sheet: before you open the tool, write down what you expect it to say and why. Then compare. Two students can produce the same paragraph and only one of them can explain where the paragraph departs from what they predicted.

Send them to the record

Denny et al. (2026) traced 113,588 references from 5,225 computing education papers published since 2021 and manually verified 828 suspicious records. They found 30 containing verifiably fabricated bibliographic information across 14 papers, all from 2025 and 2026. Thirteen were entirely invented. The other 17 combined a real title with fabricated or incorrect authorship, venue or year. At the SIGCSE Technical Symposium the count rose from 3 in the 2025 proceedings to 17 in 2026, or 2.3% of that year's proceedings papers.

Author fields fail more often than any other part of a generated reference. That single finding tells you what to ask for. "Open the source and read the author list" targets the field most likely to be wrong, and it produces a fact the student either has or does not. "Make sure sources are real" produces an assurance. Ask students to confirm authors, venue and year against the record itself. The paper asks that every cited work be verified and that any automated checker stay human-in-the-loop, which is exactly the habit a citation requirement rehearses.

Separate the check a machine can run from the judgment only a reader can make

Venetsanos (2026) sets a defensible bar for what may be checked mechanically: documented criteria, comparison against established knowledge without interpretive judgment, and a single correct answer or pre-specified acceptable alternatives. Dates, formulas, citations and calculations clear that bar. Anything interpretive fails it, and there the student's own reading is the instrument of the check.

Gousopoulos formalizes the same split as a signal-detection problem with two independent parameters. Sensitivity is the ability to discriminate correct from flawed output; criterion is where the learner sets the

threshold for rejection. Over-reliance divides along that line. Warnings, checklists and hallucination prompts shift the criterion, changing when a student rejects. Domain instruction, worked comparisons and seeded-error practice raise sensitivity, because the learner can then tell. A student who accepts flawed output may have a criterion problem or a sensitivity problem, and the two need different teaching.

The prerequisite is uncomfortable. Verification instruction is educative only where sensitivity can exceed zero, which requires enough domain knowledge to distinguish correct from incorrect output. In the same audit, novices asked to explain Large Language Models (LLMs)-generated code succeeded on roughly a third of tasks, so judging AI feedback or code against one's own reasoning is a real check only where that reasoning has substance. If your students cannot yet do the domain thinking unaided, more warnings buy nothing. Teach the content and attach the check to it.

One more warning belongs in the design: interventions that reduce inappropriate acceptance must also be checked for the unintended rejection of correct assistance. Leave room for a student to accept good output for a stated reason.

Grade the check without turning it into surveillance

Gousopoulos draws the consequence directly. If the AI can produce the artifact, the artifact cannot be the assessment, so evaluation relocates to the specification, the validation reasoning and the interpretation. His model authorship construct has four facets, specification, conceptual model, verification and interpretation, at four ordered levels from delegated to authored. The authored level requires a verifiable specification before the first prompt, rejection of output on domain grounds with a stated reason, and interpretation that goes beyond the artifact's own report of itself.

The rubric draws on materials a construction task already generates, so the same instrument is both a formative assessment and a research measure. That answers the busywork worry: you score a byproduct of an assignment you already set. Two limits belong beside it. No study among Wei and Shang's 14 priority cases measured verification success and the following reliance decision together, and few followed immediate performance with delayed retention or transfer, so the rubric rests on an analytic map rather than a validated causal sequence.

Three decisions keep this from becoming surveillance. Grade the check against adjudicated quality rather than effort, or you build an incentive to perform checking. State provenance, as Venetsanos requires: students need to know which parts of the feedback they receive were machine-verified, which were judged evaluatively, and that human judgment has primacy, because they cannot weigh feedback they cannot situate. And keep enforcement off detection tools. Bassett et al. (2026) argue that AI detection should not be used in education at all: its estimates are probabilistic and cannot be independently verified because real-world text origin is unknown, its scores do not meet the balance-of-probabilities standard integrity investigations require, and the human-versus-AI dichotomy is meaningless for work created with, rather than by, AI. Their conclusion is that detection "does not safeguard academic integrity; it undermines it." Surveillance regimes foster suspicion and erode student Trust. Keep the two senses of detection apart. Detecting AI-generated text has no defensible evidentiary role here; teaching students to detect errors in AI output is the whole exercise.

The separation is architectural, and worth telling students about. Li, Zhang and Botelho (2026) check output with a second model rather than embedding the check in the generator. A student who sees why can see why "the tool said it was right" is not a verification argument.

If you are designing the course rather than teaching it

Three findings above belong in the course build, where an instructor working alone will not reach them.

The first is a diagnostic. Run a seeded-error task: twenty items, eight with a domain-level error. It tells you whether students can discriminate at all, before you spend a term teaching a criterion they cannot use. A class that misses the seeded errors needs content review, whatever the syllabus says about critical use.

The second is placement of the warning. Vu, Cummings and Park (2026) showed a generic forewarning message immediately before two tasks to 100 US-based students, 40 domestic and 60 international EFL. Inoculated students were significantly more likely to verify the academic-source-summary task (M = 0.34 versus 0.18), while self-reported verification intentions did not move. The effect was also task-dependent: it appeared for the source-summary task but not uniformly for a mathematics quiz on exponentiation and large-number multiplication. Put the warning at the point of use, per task type, rather than once in the syllabus or the orientation module.

The third is scheduling. A syllabus that leaves verification unscheduled says it is optional, and time pressure is a documented reason students skip checks. Verification that lives inside the task, with a marked artifact attached, happens. Verification that lives in a policy paragraph does not.

If you are the student reading this

Four moves cover most of what the research asks of you.

Write your expectation before you prompt. One sentence about what the answer should be, then compare the output against it.

Open the source. Read the author list, the venue and the year against the record, because the author field is where generated references fail most often.

For anything interpretive, write the reason in your own words. A fabricated reason is as visible as a fabricated citation.

Distrust the feeling that the prose reads well. Novices asked to explain LLM-generated code succeeded on roughly a third of tasks, and a field study of student-ChatGPT quiz conversations found that following correct guidance still produced a wrong answer. What you can check is narrower than what you can read.

What instructors get wrong about this

“I already told them to check their sources.” A warning asks for a disposition. Careful students have it, hurried ones do not, and there is nothing in the sentence a student can act on at 11 p.m. with an output on screen that reads perfectly well.

“A rubric line about checking sources covers it.” That line sits at initiation and says nothing about process quality or success. A student who ran one search and gave up scores the same as a student who resolved the question, so the rubric rewards the gesture.

“If they read carefully, they will catch the errors.” Fluency carries the judgment. The audited literature shows novices at roughly a third success on explaining generated code, and the field study recorded a wrong answer that arrived through correct guidance.

“Students who say they will verify, do.” In Vu, Cummings and Park’s study, self-reported intentions did not move while enacted behavior did (M = 0.34 versus 0.18). Grade the behavior, which moved.

“The students who skip the check are the ones who do not care.” Jaidka and Cai (2026) cross ability to verify with motivation to verify, and the profiles need different remedies. The high-ability, low-motivation student is prone to complacent overtrust. The low-ability, low-motivation student is the most exposed. Two students failing the same check can need opposite teaching, and prior knowledge decides which one you are looking at.

“More warnings will fix the students who cannot tell.” Warnings move the criterion. They do not raise sensitivity, and sensitivity is what separates a student who can spot the flaw from one who cannot.

“A detector backs up the policy.” On the evidence above, a detector score fails the standard an integrity case requires, the human-versus-AI split does not hold for work made with AI, and the regime costs you the Trust you need for students to disclose anything.

What will come back at you

“They can just do it for the grade.” Partly true, so grade materials the AI cannot produce on a student’s behalf. A specification written before the first prompt, a prediction recorded before the artifact runs, a source list checked against the record, a stated domain reason for rejection: each requires the student to hold a position the generator cannot supply. A fabricated reason is as visible as a fabricated citation. Where a student has no domain knowledge to check against, verification is theater and no rubric rescues it, which is an argument for teaching the content first.

“There is no time in the syllabus.” Forewarning is one message before the task. The seeded-error task reuses a quiz you already give. The rubric rides on materials the task already generates, so it costs marking time on evidence you would otherwise lack. The alternative costs more: unverified submissions, fabricated references, and the integrity conversations that follow.

“The tool is usually right.” Then the check is cheap and the exceptions are the point. Author fields fail more often than any other part of a generated reference, 17 of the 30 fabricated items paired a real title with wrong authorship, venue or year, and 17 turned up in a single year’s symposium proceedings. Accuracy on the parts you happen to notice says nothing about the parts you do not.

“My students do not know enough to judge the output.” That is the sensitivity threshold, and it is real. Gousopoulos predicts verification instruction fails below a domain-knowledge floor, and notes that some domains furnish an external criterion, physics, chemistry, ecology and epidemiology among them, while history, literature and Ethics largely do not. Teach the domain and attach the check to it, or expect the check to become a ritual.

“This is surveillance.” It is, if you grade effort or watch how students work. Grade the artifact against the key, state which feedback was machine-checked and which was judged by a person, and leave detectors out of it.

What to do this week

1. Write the two descriptions for your next assignment: a correct output, and a plausible wrong one. That is the key the check resolves against.

2. Add the prediction line. One sentence, written before the tool is opened, compared afterward on domain grounds.

3. Replace “check your sources” with “open the record and confirm the authors, the venue and the year.”

4. Put eight seeded errors into a quiz you already give, and see which students find them.

5. Mark one verification artifact against the key, and tell the student which part of the check failed: the standard, the process, or the decision.

Where to go next

How Should I Incorporate AI Literacy into My Course? covers how to build the understanding this page puts to work, and What Is the Evidence on AI Literacy Interventions in Higher Education? covers what that literacy work is worth. How Do I Keep Students from Over-Relying on AI? handles the design side of students who lean on the tool, How Should I Use AI to Study and Learn Effectively? is the student-facing companion, and How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work? covers the version of this problem with no class meeting to schedule a check into. On the feedback students are checking, see AI Feedback Quality and Hallucination Risk.

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?
- How Should I Use AI to Study and Learn Effectively?
- How Do I Keep Students from Over-Relying on AI?
- How Should We Design and Facilitate Asynchronous Online Courses When AI Can Do the Work?

How Should I Use AI to Study and Learn Effectively?

It is 11 p.m., the problem set is due at nine in the morning, and the chat window is already open. Question four stopped making sense an hour ago. The tool will answer in ten seconds with something that reads like the work of a student who understands it, and you have to decide whether to type the assignment in or type your own mess in first.

The sentence worth carrying off this page: the same model, opened at a different point in your study process, does opposite things to your learning. Open it before you have tried, and it ends the thinking, leaving you a clean file and a thinner memory. Open it after an attempt, to quiz you, to explain what you missed, to show where your reasoning broke, and it works like a tutor. The second thing to hold on to: work that came out fine is not evidence that you learned anything. A polished submission shows what you and the model can do together. The exam, the placement, and the next course in the sequence test what you can do alone, which is what the research calls learning.

The short version

1. Write your own attempt before you open the chat, even a wrong one, and tell the tool to withhold the answer until you have one. This is the move with the strongest evidence behind it.

2. Ask for teaching: hints, explanations, worked steps, quizzes, corrections on what you produced. Keep the arguing, the sourcing, and the sentences for yourself.

3. Stay in the conversation past the first reply. Push back, ask why, ask what you got wrong.

4. Check anything you will be graded on against a source you can name, and treat fluent wording as no evidence at all.

5. End the session with the tool closed: answer from memory, out loud, and see what is missing. You find out tonight instead of in the exam hall.

Start the session with your own attempt

Akgun and Toker (2026) gave 89 undergraduates the same adaptive pretesting session and the same instructions, then seven weeks of different practice. The group whose AI probed Misconceptions about AI, demanded elaboration of thin answers, and advanced only on real conceptual engagement scored highest on the delayed posttest (M = 78.19) and put in the most practice effort (M = 0.85). Free chat with the same model scored 67.28 and 0.49, a difference of d = 0.92.

The attempt does the work even when the attempt is bad. Writing an answer activates what you already know, and it shows you the edge of it. Then the correction lands on something.

A policy you can paste into any chatbot tonight: *explain this as though I will be tested on it, quiz me one question at a time, do not give me the answer until I have attempted it, tell me what I got wrong and why.* That sentence reproduces the arrangement that produced the 78.19, and it costs nothing.

Ask for a tutor and name the job

Vague requests get vague help. Viberg, Feldman-Maggor and Wong (2026) interviewed 20 STEM students about how they sought help and found a four-stage sequence worth copying: deciding whether help was needed, choosing whom to ask, deciding what kind of help to request, and judging what came back. These students went to the model first because it was the lowest-barrier option, in one student's words "first ChatGPT, then classmates, and lastly teachers," and they asked for hints, step-by-step guidance, and concept explanations rather than finished solutions. Another described the chatbot as "a hint, an assisting tool, but not the standalone solution."

What that sounds like typed out: "I keep getting the wrong sign when I integrate by parts; here is my attempt; where does it break?" A named sticking point gets a useful reply, and "help me with this assignment" gets a draft. Ask for a worked example of one problem type, study its shape, then do the next one alone. Ask for the concept explained as though you will be tested on it, then explain it back without looking. Ask for questions, one at a time, and hold your answer until you have committed to one.

The pattern is the tool working on your understanding. Summarizing a chapter you have read, translating a source, reformatting your notes, and building practice cards are all reasonable. Deciding what your essay argues, finding the source, and writing the sentence are yours.

Stay in the conversation past the first reply

The gap between what students intend and what they do is the most consistent finding in this literature. Yan and colleagues (2026) interviewed 38 undergraduates in Japan and China while the students walked through their own chat histories for unsupervised essay assessments. Thirty-one of the 38 said they meant to use AI as a learning assistant, and they still described overreliance, mental complacency, and fast forgetting. One said "the speed at which you forget it is also very fast." A smaller group handed the whole task over, teacher assigns, student passes it to GenAI, GenAI generates, student checks formatting, student submits, and one participant described that as having "completely replaced my brain."

Only 8 of the 38 worked as what the authors call cognitive partners. They did not use less AI. Their total effort held steady and changed shape. One moved effort from searching to quality checking. Another wrote short reflection notes after every AI session to slow the fading of information retrieved instantly.

The habits that separate the two groups, as instructions to yourself:

- **Paste the problem and your attempt, not the assignment title.** 76.32% of these students followed an ask, get an answer, stop pattern, typically pasting the assessment title without saying what they needed and then resubmitting the same prompt when the reply disappointed them. Sustained, iterative dialogue appeared in 23.68%, almost all of them cognitive partners.
- **Keep it inside your own reading and writing.** 78.94% used AI either before starting or after drafting, and that detachment is the signature of the group that learned least.
- **Go past the first reply.** The Help-Seeking research shows the same shape. Amoozadeh and Alipour (2026) classified 830 prompts from 72 students across two programming tasks. The same few moves kept recurring: assertions that reported confusion, verification prompts asking whether something was right, and procedural prompts asking for the next step. Comparison, prediction,

and feature specification, the moves that make you think, stayed rare. Your own prompt history will predict your learning better than your intentions will.

Check the output against something you can name

"Critical use" is a phrase that means little until you separate the parts. Wei and Shang (2026) separate seven: epistemic evaluation, whether you start checking, how well you checked, whether the check succeeded, what you did with the output, how you performed on the task, and what you learned independently. Two of those matter more than the rest. Checking is not the same as successful checking, and a careful process can end inconclusive while a sloppy one lands on the right answer by accident. Calibrated reliance means your decision to accept or reject matched the actual quality of the output, which you cannot read off how confident the answer sounded.

Three findings make the problem concrete. Dávila et al. (2025) gave learners advice that was correct about half the time and found that how much weight they gave it varied with their prior knowledge and gender, so trust was not tracking accuracy. Zheng et al. (2025) documented a "failed application" pattern in which a student followed correct guidance correctly and still reached a wrong answer. Confidence is not a guide either: Rheu and Cho (2025) found that understanding how language models work was associated with more self-reported fact-checking, while some forms of confidence and feature knowledge were associated with less of it.

So verify anything assessed against a source you can name. The students in the Viberg study checked outputs against their coursework and their instructors, one explaining "I only go to the TA if we can't tell whether ChatGPT is making things up." When you genuinely cannot tell, mark the point unresolved and ask a person. Adopting a claim to get the page finished is how a small uncertainty becomes a wrong answer you have rehearsed.

Decide your ground rules before you need them. Pérez-Portabella and colleagues (2026) surveyed 151 undergraduates and found that ethical judgments were necessary conditions for intending to use a large language model for exam preparation, with consequentialist and deontological reasoning predicting that intention, and intention strongly predicting actual use. What you decide in advance about what you will and will not do is what your behavior follows at 11 p.m.

Let it handle logistics

Speed has legitimate uses. Kawamura (2026) built systems that adapt spoken playback to the difficulty of each segment, averaging about 1.30x, and generate Multimodal AI video summaries that cut viewing time by 53% with no statistically significant difference in quiz scores. Summarizing, translating, and planning a study schedule sit in the same category. Moving through material faster is fine. Skipping the work that changes you is the part to avoid.

The distinction is where the tool sits relative to the thinking. A summary of a chapter you have already read saves time. A summary you read instead of the chapter replaces the reading.

Finish with the tool closed

Judging a session by how it felt or how polished the output looks will mislead you. Independent learning means retention, transfer, unaided performance, and finding your own errors once the support is gone. Three tests need no researcher:

- **Close the tool and answer.** If you cannot produce the explanation or the solution with the chat shut, you have not learned it yet.
- **Test after a delay.** The seven-week posttest is what separated the conditions in the statistics study. A score taken with the conversation still on screen tells you very little.
- **Explain it out loud, from memory, with no notes.** If you need the tool's phrasing, the understanding is not yours yet.

Retrieval needs a schedule. Zhang (2026) describes Memdora, an AI spaced-repetition system built on the finding that roughly 70% of newly learned material is forgotten within 24 hours without review. It makes cards from whatever you are reading and schedules them with FSRS-6. Be precise about what that is worth: the paper reports better retention than traditional flashcard tools, and its contribution is a design and interaction taxonomy rather than a controlled retention trial. Take the spacing and retrieval as established and the specific interaction design as promising. If the app you use reports outcomes per item, read them, because per-card learning tells you more than a streak count.

What students get wrong about this

Hours in the chat are study time. The 89 undergraduates in the pretesting study spent seven weeks in different conditions with the same model. The condition that scored 78.19 was the one where the tool refused to hand over answers. The difference was the pushback.

A good answer means I understood it. Yan's students judged their own use as effective while reporting fast forgetting, and 31 of 38 said they meant to use it as a learning assistant. The output is evidence about the model. Your closed-book answer is evidence about you.

Asking for the answer is the efficient move. It is efficient at producing the artifact. In the Yan sample, the group that handed the task over produced the work and kept the least; the students who reported forgetting fastest were the much larger group who believed they were using the tool well.

Fluent means accurate. Confidence in the answer tells you nothing about its quality, and the same fluency is what makes a wrong claim easy to adopt. Verification has to be against something outside the chat.

Rereading the answer is checking. Wei and Shang's separation matters here. Whether you checked and whether the check worked are different variables, and only the second one protects your grade.

The objections you will hear

"I'm paying for this, so why not use it?" A subscription buys something better than answers, and the answers are the cheap part. You are paying for a patient tutor that will explain the same idea five ways, quiz you until you can do it cold, and tell you what went wrong with your own attempt. Most students could not have that at 11 p.m.

“Everyone else does it this way.” Most of them do it in the way these studies show working badly: 76.32% ask, get an answer, and stop; 78.94% never bring the tool into the part of the work that would have changed them. The 8 of 38 who worked as cognitive partners were not a gifted lane. Their distinguishing feature was a rule you can adopt tonight, which is that effort moves rather than disappears.

“It’s faster.” It is. That speed is the efficiency paradox: the session finishes sooner and the thing the task was for declines. Free chat in the retrieval study did less practice work (M = 0.49 against 0.85) and scored lower seven weeks later (67.28 against 78.19, d = 0.92). You will be faster tonight and slower in the exam, and you get to pick which one you want.

“I don’t know enough to attempt it first.” The attempt is how you find the edge of what you know, and pretesting helped even when the first answers were wrong. Write down what you think the question is asking and where you get stuck, then open the chat with that.

“My instructor banned it, so there is nothing to learn here.” The 38 students in the Yan study reported that their instructors forbade copying and gave almost no concrete guidance, and that vacuum pushed even well-intentioned students toward outsourcing. A ban gives you nothing to do on the day the tool is allowed, and the habits on this page are what you carry into those courses.

What to do this week

1. Pick the course where you currently paste first. For the next problem set, write a one-paragraph attempt before you open any chat, and paste the attempt along with the question.

2. Put the four-line instruction from the first section into the custom instructions of whichever tool you use, and leave it there.

3. Before your next submitted piece of work, ask the tool to quiz you on the material for ten minutes with the answers withheld. Note what you could not answer.

4. Take one topic you think you know and explain it out loud with the laptop shut. Whatever you stumble on is your revision list.

5. Check every claim you plan to submit against a named source, and write “unresolved” beside the ones you cannot.

Where to go next

How Do I Keep Students from Over-Relying on AI? covers the habits that keep the tool from replacing your judgment, How Do I Teach Students to Verify AI Output? handles the checking side in more detail, and How Is AI Impacting Students? sets out what the wider evidence says about students and these tools. If you also teach, Does Using AI Actually Help My Students Learn? is the evidence on durable learning, and How Does AI Affect Student Anxiety and Well-Being, and What Can We Do? covers what the pace of this change does to students who are trying to keep up.

Connected FAQs

- How Do I Keep Students from Over-Relying on AI?

- How Do I Teach Students to Verify AI Output?
- How Is AI Impacting Students?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

Particular learners, access and wellbeing

For instructors and support staff adapting the design to who is actually in the room, and for administrators thinking about who is not.

How Can AI Support Multilingual Learners Without Misjudging Their Knowledge or Erasing Their Voice?

A student understands the concept and needs four extra minutes to say so in English. The AI can translate the prompt, define the terminology, rehearse the explanation with them, or write the whole answer. Three of those are teaching. One is doing the assignment.

Short answer to give a colleague: decide what the language is doing in this task before you decide what the tool may do. Where language is incidental, AI can remove a barrier that has nothing to do with your construct. Where the language is the construct, the same tool bypasses the learning. The risk runs both ways at once: language support can improve access, and automated scoring can still misread the student. In one physics study, explanations of lower linguistic quality were systematically graded below expert judgment by every AI scoring approach tested, nine Machine Learning and two language-model systems across 116 secondary-school students (Feser and Tschisgale, 2026). Fluency and understanding were being scored as one thing.

The short version

1. State the role of language in the task: incidental, central, or one criterion among several.

2. Write permitted support into the instructions and criteria, and say what students must still do themselves.

3. Give targeted help before whole rewrites. Ask the tool to identify unclear meaning and offer options.

4. Require the student to compare the suggested wording against their own meaning and course sources.

5. Score conceptual reasoning and language separately when both are intended outcomes.

6. Never make an untested tool the only route to support.

Decide what the language is doing

In a biology explanation, grammar is mostly incidental to the concept being assessed. In a language course, producing and revising particular structures is the learning. In professional communication, disciplinary accuracy, audience and register all count. The same translation tool is appropriate in the first case, questionable in the second and negotiable in the third.

Write the decision down where students can read it. If students may translate directions but must produce a target-language explanation unaided, say so explicitly. If terminology support is allowed, specify what the student still has to explain and verify. Then check the arrangement against accommodation requirements and institutional policy rather than treating every form of language assistance as interchangeable. A student with a documented accommodation and a student avoiding practice can request the same thing, and only the second is your teaching problem.

What the research supports, and what it does not

Lopez and Arabadzhy (2026) reviewed 24 empirical studies of generative chatbots in language learning. Their contribution is taxonomic: every sub-affordance catalogued for pre-generative chatbots persists, and

three are new, including **translanguaging**, the deliberate movement between languages as part of learning. That is a map of reported uses and experiences rather than a pooled estimate, and the corpus is geographically concentrated, with China, Iran, Taiwan and Türkiye accounting for 19 of the 24 studies and all but one set inside formal institutions. Support for using cross-language explanation as a learning move is not support for translating every assignment.

Assessment is where the evidence gets sharper and the stakes rise. Feser and Tschisgale (2026) compared eleven automated scoring approaches against human expert scores for 116 secondary-school students' physics explanations and found systematic underestimation of conceptual understanding for linguistically weaker explanations, in every single approach. The design isolates the mechanism: the same conceptual content, expressed in weaker prose, scored lower. This is not a claim about any particular country's multilingual students, and it is exactly the pattern that makes overall scoring agreement a poor diagnostic. A scorer can agree with human markers on average while erring in a consistent direction for the students whose language is still developing.

The Multilingual Learning synthesis describes writing-screening research showing multilingual predictive-bias patterns that resemble human scoring biases. Read the three findings together and the operational lesson is narrow: neither "AI removes human bias" nor "AI adds linguistic bias" is a useful rule. What you need is a check on the task, the population and the language, at the point where a score becomes a grade.

Give the tool a specific supporting role

Start with the directions: have the tool translate or restate them in plain language, check that output against the original, and leave the student to work out what the task requires and to ask about any genuine ambiguity.

Disciplinary vocabulary works differently. Set the tool to compare meanings across languages and to generate contextual examples, then have the student explain the concept and identify the misleading equivalents.

Speaking practice calls for a bounded rehearsal with retries, with the student producing the response and demonstrating the target skill.

When revising writing, ask for a few named problems with possible fixes and keep the decision and its justification with the student.

Reading course content is the widest case. A bilingual explanation grounded in approved materials helps, provided the student checks the key claims and demonstrates understanding.

These are uses to pilot, not validated interventions. A tool that performs well in one language or one genre is not thereby reliable in another, and the review's geographic concentration means your language pair may barely be represented in the evidence.

Protect the student's meaning and voice

Ask for targeted help before asking for a rewrite, because a whole rewrite is where the student's thinking leaves the page. A request worth teaching: "Identify two places where my meaning is unclear. Explain the problem and offer options. Keep my examples and do not add claims." The student then chooses.

A sequence that keeps the work with the student:

1. Develop the explanation in whatever language or mix of languages lets the student reason, where the task permits.
2. Use approved support to examine terminology or expression.
3. Compare the suggested wording against the intended meaning and course sources.
4. Produce the required explanation and note the consequential revisions.

In a sociology assignment, a student might reason through a family-role conflict bilingually, check a short list of course terms, then write the submitted analysis in the required language, with the instructor assessing the sociological reasoning and any separately stated language criteria. In a language-learning task the same sequence would give away the assessment, and would need to preserve independent target-language production.

Avoid making “sounds like a native speaker” the standard, since it measures the student’s relationship to a dialect rather than their grasp of your subject. Specify clarity, accuracy, genre or audience instead. A polished rewrite can shift stance, drop a culturally meaningful expression, or add a claim the student never intended, and the student signs it.

Check the tool and the assessment

Review meaning, not fluency. Sample translations and explanations for technical terms, omissions, invented detail, cultural assumptions and the varieties of language your students actually use. Involve qualified language colleagues or support staff; do not make students the sole auditor of a tool you require them to use.

Separate the criteria. When both reasoning and language are intended outcomes, score them separately and check whether an AI-assisted marker is penalizing language twice, or missing correct reasoning expressed unconventionally. This is the practical form of validity for a multilingual cohort, and the subgroup question in differential effects.

Keep a route to clarification. A brief conversation, an annotated diagram or an explanation of one key decision can show what a student understands when the prose will not carry it. Choose the format that fits the construct rather than the one that is easiest to grade.

Provide workable alternatives. Students need a clear path to human language support and accessible course resources. Requiring an untested tool can add a barrier while intending inclusion, which is the same failure support for disabled and neurodivergent learners has to avoid.

What will come back at you

“Translation means the student is avoiding the work.” It depends on what the work is. Translation can enable engagement with disciplinary content it has no bearing on, and it can replace practice when independent target-language production is the outcome. Decide which you are assessing and say so.

“The AI fixed the language without changing anything else.” Check it. A rewrite that improves grammar often changes emphasis, hedges a claim, or invents support. Ask the student to name one meaningful change and say whether it preserves their intended point, which also tells you whether they read the suggestion.

“Human markers are fairer.” Human scoring carries its own language-related bias, and the multilingual writing-screening research finds automated systems reproducing patterns of it. Fairness here comes from explicit criteria, sampled subgroup evidence and a real chance to reconsider a judgment, not from who or what holds the pen.

“Our students are fine in English, so this does not apply.” The finding that matters is not a deficit claim about any group. It is that conceptual understanding expressed in weaker prose is systematically under-scored, in every method tested. That applies to rushed writers, second-language writers, and anyone whose register differs from the examiner’s.

What to do this week

1. Take one assignment and write a sentence stating what the language is doing in it.

2. Rewrite the instructions to say what support is permitted and what students must produce independently.

3. Test a translation and a terminology explanation in the languages your students actually use, and read the output for invented detail and dropped meaning.

4. Add one check that records the student’s own meaning or decision, such as a two-sentence note on a change they accepted or rejected.

5. If your rubric scores writing quality, separate that criterion from the conceptual one and re-read two submissions of each with the split in mind.

Where to go next

Multilingual Learning is the concept page for language, translanguaging and assessment in AI-mediated teaching, and assessment validity is the standard for whether a score supports the inference you are making. Differential Effects Across Learner Groups covers how to look for subgroup patterns rather than assume them.

For the writing-instruction case where language is the construct, see best practices for writing instruction. For whether automated scoring can be trusted at all in your setting, see AI grading and checking whether an educational AI works.

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?
- What Are Best Practices for Writing Instruction in the Context of AI?
- How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do?
- How Do I Teach Students to Verify AI Output?

How Can AI Support Disabled and Neurodivergent Learners in My Course?

The accommodation letter names a student, a course and a tool you have never heard of. Or a student has asked, reasonably, whether they can keep using their speech-to-text software in a timed exam, and your course AI rule says no AI of any kind. Or the accessibility office wants an answer by Friday on whether to license a reading tool, and the vendor's evidence is a testimonial from another campus.

The answer that survives all three: start from the barrier the task creates, use the tools that were actually measured, and teach whatever you adopt. Two rules matter more than any product choice. Name transcription and OCR in your AI policy as accommodations in their own right, and give the assignment structure instead of asking students to infer it. Be clear-eyed about the evidence: the strongest number on this page comes from PK-12 special-education settings using mostly pre-generative AI, and the higher-education literature is a map of what has been tried.

The short version

1. Write the functional barrier on the accommodation letter before the tool name: reading and writing, study management, attention, or social communication.

2. Start with structured instructional software, which has the measured effect, and read its confidence label before you buy the chatbot you were pitched.

3. Decide whether this is a design change or a personal accommodation. Where the barrier is shared, change the design, because that removes the disclosure step.

4. Teach the tool. An accommodation supplied without instruction is the failure mode the case law punishes.

5. Name transcription and OCR explicitly in the AI rule, so a prohibition written against generative drafting does not withdraw a student's means of producing legible work.

6. Run the trial against the barrier rather than against a satisfaction survey, and say in advance what you will count as working.

Start with the barrier the task creates

Most of what goes wrong for disabled and neurodivergent students happens at the level of a task: a reading that assumes print, a video that assumes sustained attention, a group project that assumes unspoken social rules. Those barriers recur across diagnoses, so the useful question is which functional barrier a tool removes, and a procurement question should be phrased the same way.

Diagnostic categories hide this. The scoping review below finds the literature dominated by individual accommodations and single-neurotype tools organized around formal diagnosis, while the functional differences they address cut across neurotypes. Dyslexic students tend to benefit from reduced reliance on written-only material. Autistic students and students with ADHD can both experience frequent fluctuation in focus, which makes performance sensitive to consistent structure and enough time for task switching. A tool matched to a label can miss the barrier the student in your section actually has.

The same caution applies to group statistics. Differential Effects Across Learner Groups reports a considerably larger effect for students with specific learning disabilities, intellectual and developmental disabilities, or who are deaf, than for students with autism spectrum disorder, and that difference was not statistically significant across the effect sizes.

Use what has been measured, and read the label

The strongest quantitative result on this page is also the most general, and it comes with limits you should carry into the purchase decision.

Zhang, Carter, Liu and Peng (2024) synthesized 29 (quasi-)experimental studies of AI-based interventions for students with disabilities: 239 effect sizes from 41 independent samples, a statistically significant medium overall effect on learning outcomes of Hedges' g = 0.588 (95% CI [0.349, 0.826], $p < .01$), and high between-study heterogeneity. Academic performance was the largest outcome subgroup (k = 80, g = 0.929) and social-emotional skills the smallest (k = 144, g = 0.382). Computer software, meaning speech recognition, expert systems and intelligent tutoring systems, performed strongly (k = 74, g = 0.959) and robots moderately (k = 144, g = 0.509), while intelligent VR (g = 0.528) was not significant. Publication bias was present (Egger's $\beta = 2.837$, $p < .001$); trim-and-fill reduced the estimate to g = 0.269, still significant.

Every study was PK-12. 96.6% used step-based instruction in special-education or clinical settings, and most used older rule-based AI rather than generative AI. That supports cautious adoption of structured instructional software. It does not transfer to a general-purpose chatbot, and treating it as though it does is the most expensive mistake available on this page.

Three smaller results show what a single tool can do when the barrier is narrow. Each was tested on a handful of learners, so treat them as low-cost reversible experiments rather than infrastructure.

For attention, Pimenova, Begel and colleagues (2026) segmented instructional videos after the fact into single-instruction chunks with fixed pauses. With 17 learners with ADHD and 10 without, it improved everyone and brought the ADHD participants' errors and hesitations to parity. The equalizing effect came from a lightweight transformation of the material.

For language access, Chen et al. (2026) added Visual questions (timestamps where visual information is likely to be misread) and Emotion questions (timestamps where prior Deaf and Hard of Hearing learners reported frustration) to an Large Language Models (LLMs) baseline set, producing 30 questions, ten per strategy. With 16 learners, Self-Efficacy averaged 5.70 (SD = 1.12) on a seven-point scale, and visual questions were chosen more often by Deaf than by hard-of-hearing participants.

For reading and writing, Rezazadegan et al. (2026) mined dyslexic learners' own forum discussions. Those learners valued AI for literacy support and reported uneven output quality and a lack of equitable accommodations. The inconsistency is itself a barrier: a tool that cannot be relied on adds work instead of removing it.

The higher education picture is the weakest part of the evidence and the part closest to your job. Rempel, Heimann and Prilop (2026) screened 766 records from five databases down to 40 included studies published between 2015 and 2025. Generative AI appeared in 15 of the 40 and virtual reality in 11. Barrier coverage was uneven: reading and writing (n = 13) and study management (n = 12) dominated, attention (n = 4) and social communication (n = 5) were neglected, and only 6 studies addressed more than one barrier. The

review excluded K-12 and specialized-institution settings by design, so it says nothing about younger learners. Use it to see which barriers have been addressed at your level, and which have barely been touched.

Decide whether you are changing the design or the accommodation

Universal design removes the need for a student to identify themselves as needing special provision. Accommodation requires exactly that, and the stigma is part of the cost. So when a barrier turns out to be shared, the design change is the better buy: it reaches the students who never disclose.

The segmentation result is the clearest case. A video cut into single-instruction chunks with fixed pauses improved all learners in the study, not only those with ADHD, and brought the ADHD participants' errors and hesitations to parity. That is the universal-design outcome, achieved with an edit rather than a product.

The honest limit: that is 17 learners with ADHD and 10 without, in one study, and nothing in this literature tells you how far to generalize from one classroom result, or when a student's need is distinct enough to require an individual arrangement. That judgment stays with you and the accessibility office.

Teach the tool, and put someone's name against the teaching

The documented failure is an accommodation supplied without instruction. In *W.A. v. Clarksville/ Montgomery County School System* (2024), a student given AI as an accommodation graduated unable to read, and the court found that a free, appropriate public education had not been provided.

Two things make that failure likely, and both are institutional. Shin et al. (2026) used LLM-based topic modeling and two rounds of Delphi surveys with 17 experts across 12 U.S. AI-in-education policy documents from 2015 to 2025. Educator preparation is one of their five validated themes, carrying 4 of 36 items, and the experts ranked student empowerment and AI literacy as most essential: these students should learn to use AI responsibly and independently, with guarding against over-reliance taught as part of the same skill. LUDIA's authors name the obstacle as the "knowing-doing divide": guidance exists in abundance, is written in general terms, and a barrier is always particular to this room, this week.

What the page cannot give you is a training protocol. No formal evidence-based guidelines exist to help educators or families implement AI for these learners, so the amount of instruction, its sequencing and who delivers it are judgment calls. The case law sets the floor rather than the standard: the student has to end up able to do the thing, and someone has to be accountable for getting them there.

Write transcription and OCR into the AI rule by name

Wright (2026) argues that rules treating all "AI use" alike are over-inclusive, because they do not separate speech-to-text transcription and OCR from generative drafting. Students with conditions affecting fine motor control, handwriting legibility or typing accuracy have relied on standalone voice-to-text products such as Dragon NaturallySpeaking and standalone OCR, several of which have been discontinued or degraded, with AI-powered transcription filling the functional gap.

A rule written as "no AI" can therefore withdraw the student's primary means of producing legible work. Nobody has measured the scale of that displacement yet, which is a reason to be explicit rather than to wait for the number. Name transcription and OCR as accommodations in the policy, alongside the drafting

prohibitions, so the two questions are decided separately. The exposure this creates for the institution belongs with Legal Issues and Risks.

This is a one-line fix in most documents and it is the highest-consequence line on the page.

Give structure where the assignment assumes it

Structure is the cheapest intervention here and the one most often left out of the plan. Zastudil et al. (2026) surveyed 24 neurodivergent computing students (autistic and/or ADHD) and 20 neurotypical peers, with four follow-up interviews. The neurodivergent group was uncomfortable with unstructured or ambiguous assignments and strongly preferred smaller teams that work together consistently with explicitly defined roles, coping by self-selecting roles and disclosing strategically.

That is preference data, not an effect study, and it is also the design brief students wrote for themselves. AI-mediated work carries a specific version of the risk, because a tool's interaction model can reproduce the same structural ambiguity the assignment already had. Check what the tool asks the student to decide alone before you add it to a task.

Run the trial against the barrier, and write down what you counted

Aggregate effects give you a direction. They do not tell you whether the tool works for the student in your section next week, so any trial needs a measure chosen before it starts.

Three cautions should shape that measure. The first is that subgroup ordering is suggestive rather than established: no moderator of any kind reached significance in the 2024 meta-analysis, so rankings such as teachable agents ($g = 1.100$) ahead of social-emotional coaches ($g = 0.336$), or dyadic interaction ahead of triadic ($g = 0.973$ versus $g = 0.385$), should not be treated as settled. The direction of effect is supported; the size, the design optimum and the durability of any gain are not.

The second is that this corpus describes deployments and perceptions more than measured learning. Attention ($n = 4$) and social communication ($n = 5$) are the least-studied barriers, and the scarcity of (quasi-)experimental and longitudinal designs is why the higher-education work is a scoping review rather than a meta-analysis. Coverage skews undergraduate and Global North, the search was English-language peer-reviewed work, and postgraduate students are under-represented. Engagement and satisfaction are weak indicators.

The third is that a tool which fixes one barrier may leave another. Check the tool against the specific difficulty the student reports, whether that is reading and writing, study management, attention or social communication, and evaluate against that difficulty rather than against how the student felt about the product. Ask the student what to count. Zastudil et al.'s participants and Rezazadegan et al.'s forum posters both describe their needs more precisely than the products built for them do.

What you will not find here is a validated instrument for measuring a barrier in a single course, or evidence on how long a trial should run. Both are gaps in the literature rather than failures of your search, and they are worth writing down in the review notes.

Buy for the barrier, and refuse the expensive default

Two procurement requirements come straight out of the review: state universal design and participatory development as conditions, and build tools with neurodivergent students rather than for them. The review's own sample shows how rare that is, with only 3 of 40 studies treating the environment or neurotypical peers as the object of intervention.

Then budget honestly. Assistive technology needs devices and connectivity, and tools that are free in a pilot routinely move behind a paywall. Virtual reality is the most resource-intensive option in the set, and the field is concentrated in the Global North, so its most immersive tools are the least scalable. Shin et al. flag the digital divide directly: the price of advanced AI tools can widen disparities between wealthier and poorer schools, alongside algorithmic bias and teacher-training gaps.

LUDIA is one worked version of the low-cost alternative, and its authors are unusually plain about what they have not shown. It connects educators with Universal Design for Learning while a design decision is still open, and removes access barriers by architecture: no cost, no accounts or stored chats, WCAG 2.2 Level AA conformance, and 13 machine-translated languages, though non-English versions may carry the assumptions of the English they came from. It is a thought partner rather than a solution engine, and the authors state that they hold no evidence it improves learning. They also name a limit that belongs on every deployment plan: automation bias means the educator most likely to accept a poor suggestion is the one who trusts the tool knows Universal Design for Learning. Nobody has tested its outputs for cultural or linguistic bias either.

Keep a second failure in view. Chatbot over-reliance and the cognitive overload of immersive environments are documented as inversion effects, where adding the technology lowers learning. A tool that only reproduces existing teaching in digital form should be expected to yield limited learning gains.

What instructors get wrong about this

A diagnosis tells me which tool to buy. The barriers cross diagnoses, and a tool matched to a label can miss the barrier in the room. Ask what the task assumes: print, sustained attention, unspoken social rules, a particular way of producing text.

An accommodation is a personal arrangement, so the fix belongs to the student. Some are, and the ones worth generalizing are the ones you would have designed in anyway. Segmentation helped every learner in its study. Design changes remove the disclosure step, and with it the stigma.

Engagement and satisfaction show the tool worked. They show the student liked it. This corpus is mostly deployments and perceptions, and only 6 of 40 higher-education studies served more than one barrier, so a satisfied student is not yet evidence that a barrier came down.

The tool carries the support, and teaching is an extra. The case law treats an untaught tool as the failure, and the policy experts ranked student empowerment and AI literacy as their most essential theme. Budget the teaching time with the license.

What will come back at you

"We cannot require a tool for everyone." Where the tool is a design feature, requiring it is the point. Video segmentation with fixed pauses improved all learners and brought the ADHD participants' errors and

hesitations to parity, which is the universal-design outcome that removes the need for disclosure. Accessible defaults carry the same logic: read-aloud, OCR and text-leveling tools recur in Shin et al.'s validated policy items. Their corpus also shows how far policy has to travel, since only 2 of the 12 documents specifically address learning disabilities while 18 topics present in general AI or other-disability policy, data protection, legal risk management and ethical guidelines among them, are missing from specific-learning-disability policy.

"Captioning and translation are not academic support." Captioning is a start, not the whole of language access. Chen et al.'s Visual and Emotion questions exist because a transcript alone leaves a Deaf learner reconstructing context the video never stated. The policy experts' ranking disagrees with the objection too. Their 36 validated items spread across five themes, with inclusive and personalized learning the largest at 11 (30.56%) and Ethics, equity and inclusion at 9 (25.00%), and educator preparation at 4 (11.11%), yet the experts ranked student empowerment and AI literacy most essential of the five, at 6 items (16.67%), level with assessment and research.

"Students must be independent." Independence is what the instruction is for, which is why the tool without the teaching is the failure. Shin et al.'s educator-preparation theme exists for the same reason. The scale of need is easy to understate: roughly 240 million children worldwide live with disability, about half of them out of school in low- and middle-income countries, and about a third of teachers across OECD systems report lacking the competencies to support students with specific needs. In the United States, the Assistive Technology Act (2004) and IDEA (2004) place assistive-technology evaluation inside each Individualized Education Program and require a free, appropriate public education, yet no formal evidence-based guidelines help educators or families implement AI for these learners. Independence built on an untaught tool is what the case law punishes.

"We cannot afford it." Then refuse the expensive default. Virtual reality is the most resource-intensive option in the set, and the field's most immersive tools are the least scalable. A free, privacy-preserving tool that improves the design conversation, with its authors' caveats read first, is a better opening purchase than a headset.

"The evidence is too thin to act on." Thin, and not empty. The 2024 meta-analysis gives you a direction with a wide interval and a publication-bias correction that cuts the estimate by more than half, the three single-tool studies are small, and the higher-education review measures coverage rather than effect. What that supports is the cheap and reversible move: a design change, a named accommodation, a trial with a measure agreed in advance. Deferring the decision is also a decision, and it leaves the student in front of you with whatever the default arrangement provides.

What to do this week

1. For each accommodation request on your desk, write the functional barrier beside the tool name, and check that the tool addresses that barrier rather than the diagnosis.

2. Ask whether the barrier is shared by the whole class. If it is, change the design: chunk the video, cut the ambiguity, turn on read-aloud, and give the assignment structure it was missing.

3. Add transcription and OCR to the AI rule by name, so the prohibition on generative drafting and the accommodation for producing text are decided separately.

4. Put a name and a date against the teaching: who shows the student the tool, when, and who checks that it is working.

5. Agree the measure with the student before the trial starts, and record the result in the review notes, including the case where the answer is that it did not help.

Where to go next

Universal Design for Learning covers the design approach that prevents barriers before they appear, Assistive Technology the tool layer a student uses, Accessibility whether a format can be perceived and operated at all, and Neurodiversity the lens that treats difference as diversity rather than deficit, all within the umbrella of Inclusive Learning. How Do I Keep Students from Over-Relying on AI? covers the over-reliance and inversion effects that decide whether a tool keeps helping, and incorporating equity, accessibility, privacy, ethics and pedagogical safety into AIED research covers the research-side obligations.

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Do I Keep Students from Over-Relying on AI?

How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?

A student stays behind after class and tells you that finishing the degree no longer seems worth it, because AI can already do the job they were training for. Another has gone quiet this term: fewer submissions, no questions, no presence in the seminar. You have ten minutes before your next class and no way to tell whether this needs a strategy or a referral.

The answer to give a colleague: most of what drives AI anxiety sits in career and competence rather than in the technology, and reassurance moves neither. Mastery experiences, evidence that AI-related work is worth the effort, and career adaptability are what these studies point at. A small number of students need a referral rather than a strategy, and the evidence is thinner on where that line falls than you would want.

The short version

1. Find out which fear you are dealing with. Career fear and competence doubt need different answers, and between them they carry most of the association with anxiety.

2. Stop opening with reassurance. Encouragement that leaves a student's judgment of their own capability unchanged will not move the emotion.

3. Give them a task they can succeed at, and one they have to critique. Low-stakes practice plus guided evaluation of AI output rests on better evidence than a talk about the future of work.

4. Put the job question inside the course. Career adaptability is the mechanism the strongest study here identifies, and believing in yourself did not substitute for it.

5. Know your referral route before the conversation starts, and treat hopelessness about the degree as the signal rather than frustration with a tool.

6. If someone proposes a well-being tool, ask what happens when it is wrong, and hold deployment until you have an answer.

Name the fear before you answer it

Kim et al. define AI anxiety as apprehension or fear produced by the acceleration of AI. They separate it from older automation anxiety because AI threatens cognitive and professional roles rather than manual tasks, and they name the fear of replacement by AI as its primary contributor, with uncontrolled AI growth, Privacy concerns, AI-generated misinformation and AI bias as secondary causes. Read that against the student in front of you: the one worried about being replaced is worried about the labor market they are entering, not the tool you demonstrated last week.

Career worry is the best-evidenced version of this. Üstün and Danacıoğlu (2026) surveyed 1,057 students across 35 Turkish universities and found that higher AI anxiety and more negative attitudes toward AI went with higher post-graduation job-finding anxiety. Female, social-science and second-year students reported more of it. Dağ et al. (2026) found a moderate positive correlation between AI anxiety and job-search anxiety among 821 health-sciences students ($r = 0.233$, $p < 0.001$), with AI anxiety still a significant predictor after controlling for socio-demographics ($\beta = 0.234$, $p < 0.001$). Duan et al. (2026) carried the

question through to consequences: in a structural equation model of 315 Chinese college students, AI anxiety predicted poorer career decisions directly and indirectly by undermining career adaptability, and that mediated pathway accounted for 63.35% of the total effect.

Ordinary adjustment sounds like a student saying they do not yet know how to use this well. Sit up when it sounds like there is no point in finishing, when the student withdraws instead of complaining, or when the worry is carried alone because raising it feels like admitting weakness. That last pattern is the one Bashir and Afzal (2026) describe among Pakistani university students, where disclosure carries a stigma cost.

Replace reassurance with a task they can succeed at

A two-wave survey of 547 Chinese undergraduates placed AI learning anxiety inside control-value theory (Jiang, Chen and Chen, 2026). Anxiety, on this account, comes from two appraisals. One is whether a student feels capable of handling AI-related learning tasks, measured as AI learning self-efficacy. The other is whether they judge AI useful for academic work, measured through the perceived-usefulness construct. Self-efficacy had the stronger negative association with anxiety and also predicted perceived usefulness. Perceived school support was associated with lower anxiety even with both appraisals in the model, but most of that association ran through them, leaving roughly a third as a direct link. Modeled separately, only informational support kept a reliable path to self-efficacy, which is where AI literacy training, responsible-use guidelines and reachable technical support earn their place.

The teaching that follows is unglamorous. Build mastery experiences: low-stakes practice, guided evaluation of AI outputs, feedback-driven revision. Give students concrete evidence that AI-related work is worth the effort, since value is the second appraisal and it moves with experience rather than with argument. Make your support informational, the kind that answers a question about how something works, rather than purely comforting.

Nobody in this literature tested that package against a control group. The recommendation follows from the appraisal model, and the authors are explicit that their design cannot establish causal direction, temporal precedence or causal mediation. The sample was convenience-sampled, skewed toward STEAM majors, measured with self-report, and anxiety was generally low with limited variance, which may have flattened the estimates. Treat the direction as warranted and the effect size as unknown.

Teach scrutiny, and expect engagement to rise with it

Anxiety and engagement can move together, which changes what you are trying to do. In a survey of 107 students, Kim (2026) found higher AI anxiety positively associated with verification and revision behavior ($\beta = .24$, $p < .01$), and evaluative capacity predicting active engagement ($\beta = .46$, $p < .001$). Students sorted into four regulatory types: uncritical reliance (18.7%), selective integration (34.6%), evaluative transformation (31.8%), strategic rejection (14.9%).

If anxiety can accompany the more careful behavior, then reducing the feeling is the wrong target. Teaching scrutiny and evaluative judgment turns an anxious student into a deliberate user of generative AI rather than an avoidant one. That habit is the subject of teaching students to verify AI output, and AI Literacy is the wider frame it sits in.

Put the career question in the room

Duan et al. (2026) conclude that career adaptability is the key protective mechanism, and they recommend universalizing AI literacy and career-planning courses alongside industry and education integration. Dağ et al. (2026) arrive at the same place from health sciences: strengthened programs plus AI literacy and career counseling, because AI anxiety shapes students' professional futures rather than their opinions about a tool. Neither finding comes from an intervention, so what you have is a well-argued target, not a tested program.

The other lever with evidence is emotion regulation. In a survey of 1,484 Chinese undergraduates, Zhang, Shi and Lu (2026) found AI anxiety negatively correlated with emotion regulation ($r = -0.172$) and academic Motivation ($r = -0.175$), while emotion regulation correlated positively with motivation ($r = 0.457$), all $p < 0.001$. Bootstrap analysis confirmed a negative indirect path from anxiety to motivation through emotion regulation (indirect effect = -0.076, 95% CI -0.108 to -0.047), with the direct path still significant. Daily AI use duration correlated only weakly with motivation ($r = 0.053$), which argues against reading time on tool as quality of engagement. Their recommendation is to build emotion-regulation and metacognitive support into AI literacy education, with attention to gender, since the regulation to motivation link was stronger among male students in their data.

Concretely, this can be a short written reflection before and after a graded AI-assisted task, or a short structured conversation about what a student would do if their intended role changes. Both are cheap. Neither has been tested as an anxiety intervention, and Zhang, Shi and Lu's design is cross-sectional and self-reported, so they cannot show causation.

Say what is allowed, and where help is

Silence about AI reads as prohibition to some students and as abandonment to others, and either reading feeds the appraisal problem above. Write the expectations down: what is allowed, what must be disclosed, what support exists when a student is struggling with the tool. Say them out loud in class as well. Perceived support precedes favorable appraisals, and this is the cheapest version of support you control.

Refer when the worry has stopped being about a tool and started being about the student's worth, their place in the program, or their future: hopelessness about finishing, withdrawal from work and from people, statements that they see no professional future. Anything suggesting risk to safety is an immediate referral under your institution's protocol, and not a conversation you manage alone.

Career anxiety belongs with career services, because it is a counseling matter rather than a morale problem, and Duan et al. (2026) found that self-efficacy alone did not buffer the damage to career decisions. Institutions are the level the evidence points at, with Dağ et al. (2026) recommending AI literacy and career counseling together with strengthened programs. If what you are seeing is a student blocked from using required tools by a disability or an access need, that belongs with whichever office handles accommodations at your institution, and it is a separate conversation from this one.

You also have a lever the referral form does not. Bashir and Afzal (2026) rank the teacher-student relationship second in their feature-importance analysis (10.0%), ahead of sleep quality (9.3%), depression (8.3%) and social support (7.6%). The authors present that as a hypothesis needing locally collected data. It is still a reason to make sure students know you are a route to help.

Decide whether a well-being tool belongs here

A student-facing chatbot appeals most to the students who will not raise distress with a parent, a teacher or a peer, which is exactly the disclosure pattern Bashir and Afzal (2026) describe. Their system trained a Random Forest stress classifier on 1,100 survey responses across 20 features and reached 89.09% accuracy over three severity levels, paired with a tiered Stepped Care dialogue layer in English, Urdu and Roman Urdu. Their feature-importance analysis placed blood pressure first (15.6%) and the teacher-student relationship second (10.0%), with anxiety level ninth (4.8%), which they read as evidence that student distress is multi-dimensional.

What they concede matters more than the accuracy figure. A trained classifier decides the support tier, and what happens on a harmful misclassification, how disclosures are stored, which Privacy protections apply, and how escalation to human counseling works are all left open. The boundary between human oversight and automated encouragement remains a design question. The system is not presented as clinical or therapeutic, and the conversational layer was checked with simulated inputs and informal usability testing rather than with students, on cultural appropriateness, emotional safety or satisfaction. There is no student outcome data at all.

The same pattern appears in the wider tool literature. A dissertation on AI-driven campus well-being tools (Tang, 2026) reports a survey chatbot (TigerGPT) reaching 75% usability and 81% satisfaction, and an adaptive follow-up framework (AURA) producing a +0.12 mean quality gain ($p = 0.044$, $d = 0.66$) by using reinforcement learning to choose whether to validate, specify, reflect or probe. It also describes a mental-health assessment component grounded in DSM-5 and PHQ-8 guidelines rather than black-box classification, and a stacked multi-model architecture claimed to cut hallucination risk and outperform single models on the DAIC-WOZ Benchmark. These are system-development results. They measure whether the tool does what it was designed to do, not whether a student's Well-Being improved. The 89.09% figure comes from a single held-out split, on training data that is not representative of Pakistani students, in a system built in English with prompted Urdu expressions.

Set the conditions the course cannot

The classroom moves above need institutional cover, and the policy literature around AI and social-emotional learning is thinner than the deployment ambitions. Tran, Liu and Nguyen (2026) reviewed 65 peer-reviewed papers at the AI and SEL intersection: nearly three-quarters made no mention of policy implications at all, only about one in four offered any policy recommendation, and few gave actor-specific guidance on Privacy, teacher training or resource allocation. Their WH framework asks who should act, what action is recommended, why, when, where and how strongly it is framed, and most papers left those questions unanswered. Policy engagement correlated with publication venue, which the reviewers read as an incentive structure favoring technical novelty over AI Governance, and they describe the result as a techno-solutionist trap: the technical potential is foregrounded and the conditions for responsible use go unspecified. For equity, that means plausible AI-for-SEL tools can be adopted without the privacy safeguards, teacher preparation and resource equity that adoption requires.

If you sit at the level where these decisions get made, the practical question is the same one the classroom asks. Who is accountable when the tool is wrong, what happens to what a student discloses, and who has been trained to read the output.

What instructors and administrators get wrong about this

AI anxiety is really discomfort with new technology, and it fades as familiarity grows. The drivers in these studies are career and competence appraisals: fear of replacement comes first, and AI anxiety still predicted job-search anxiety after socio-demographic controls. Daily use duration correlated with motivation at r = 0.053, so time with the tool tells you little about motivation.

Reassurance is support. Encouragement aims at the feeling, and the appraisals model says the feeling is downstream of capability and value judgments. Informational support was the only support type that kept a reliable path to self-efficacy in Jiang, Chen and Chen's model.

The goal is to bring the anxiety down. Kim (2026) found anxiety positively associated with verification and revision, and evaluative capacity predicting engagement. A calmer student who accepts the first output has not been helped.

Confidence protects students from the career damage. In Duan et al.'s model, Self-Efficacy did not buffer it. Career adaptability carried the mediated pathway.

This is a student services problem. Most of the moves on this page are instructional: low-stakes practice, guided evaluation of AI output, feedback-driven revision, and a statement of expectations students can read. Knowing the referral route is one item among them.

A well-being chatbot is the scalable answer to thin counseling capacity. Availability is real and the appeal is understandable. Accuracy on one held-out split is not evidence that a distressed student is better off, and the misclassification, storage and escalation questions have no published answers in the work cited here.

The objections you will hear

"They need to learn resilience, not accommodation." Partly right, and the confident version has the mechanism wrong. Zhang, Shi and Lu found emotion regulation correlated positively with motivation (r = 0.457) while anxiety correlated negatively with both, which is an argument for teaching regulation. But resilience as believing in yourself harder is what failed in Duan et al.'s moderation test. Resilience as rehearsal, mastery experiences and career adaptability is what the studies point toward, and none of it has been tested as a program.

"This will pass as students get used to the tools." Time on tool is not the mechanism. Daily AI use duration correlated weakly with motivation (r = 0.053) in the 1,484-student survey, and Dağ et al. (2026) found AI anxiety still predicting job-search anxiety after controlling for socio-demographics (β = 0.234, p < 0.001).

"I am a subject teacher, not a counselor." Nobody is asking you to treat anyone. Low-stakes practice, a critique task and a revision loop are ordinary instructional moves. The one finding that speaks to your position is the teacher-student relationship sitting second in Bashir and Afzal's feature-importance analysis

(10.0%), above sleep quality (9.3%) and social support (7.6%). The authors call it a hypothesis, and it is a reasonable bet for a role you already occupy.

“We have no counseling capacity, so a tool is better than nothing.” Possibly, and this page cannot settle it. What you can insist on before deployment is written answers on accuracy validation, how the support tier is decided, what happens on a harmful misclassification, how disclosures are stored, and how escalation to a human works. No answers, no deployment. A student who discloses to a tool that misfiles it may not disclose again.

“If I raise career prospects in class, I am overstepping my subject.” The alternative is that students assemble their answer from the labor market and from each other. Duan et al. recommend career-planning work as part of the academic program, and Dağ et al. recommend it alongside AI literacy. You can host the conversation without claiming expertise in it, and route the individual cases to career services.

What to do this week

1. Take one class period’s temperature in writing. Ask students what AI means for the job they are aiming at. You get the driver in their own words, and you get a list of students worth a private follow-up.

2. Replace one reassurance with one appraisal move. Swap five minutes of “you will be fine” for a task where students evaluate and correct an AI output.

3. Write your AI-use expectations down, including what is allowed, what must be disclosed, and what support exists, and read them aloud once.

4. Find your career services contact and your institution’s referral path now, before you need either, so the conversation ends with a name.

5. Before adopting any well-being or affect-aware tool, get the five written answers above. If a vendor cannot supply them, that is your answer.

Where to go next

Anxiety and Stress is the concept treatment of the emotion itself, including proctoring stress, the productive side of anxiety and educator anxiety. Well-Being covers the positive-state framing across emotional, psychological and social dimensions. For the surrounding picture, How Is AI Impacting Students? handles the general impact of AI on students, and How Do I Redesign Assessment So That a Grade Still Tells Me Something Defensible About What the Student Knows or Can Do? covers the assessment side of an institutional response. Career Development and Readiness is where the career argument continues.

Connected FAQs

- How Is AI Impacting Students?
- How Should I Use AI to Study and Learn Effectively?

How Should Parents and Teachers Approach AI with Children Under 13?

The vendor's terms say the tool is for users 13 and older. Last week a third-grade teacher showed you the poems her class generated with it, a parent emailed to ask whether the talking toy her son got for his birthday is safe, and the board wants a one-page policy before its November meeting.

Three questions are tangled in that request: what a six-year-old may do with these systems, what the school owes families whose children meet AI at home, and what to do when a ban is not the answer you can defend.

The short answer you can give the board: tier access by age, teach children how these systems are built before you hand one over, and keep an adult in the loop wherever the child cannot judge the output. A blanket ban is the option with the least evidence behind it. No study of age-based bans exists in this knowledge base, and most of this age group's exposure happens at home, where a school rule does not reach.

The short version

1. Write the rule by age band, not for K-12 as a whole. Under 9: play, making, tangible coding, and explanations of what a machine is. Ages 9 to 12: scaffolded, mostly non-generative activity on vetted platforms, plus explicit teaching about data and about what AI cannot know.

2. Put generative chat last in the sequence, and only with a named adult role and a stated purpose.

3. Vet every tool before adoption on four questions: which child-specific hazards were tested, what it does with voice and transcript data by default, what it costs families if the free tier disappears, and whether it works in the languages your families speak.

4. Publish what the school uses and how a family can ask. Disclosure is an institutional obligation.

5. Keep detection out of the enforcement plan.

Set the rule by age band

Tiered design is not something you have to invent. Wang, Chuang and Wu (2026) evaluated an age-tiered AI literacy resource built for Taiwan's K-12 system in two editions: an elementary edition for ages 9 to 12 of scaffolded, platform-based, non-generative activities, and an advanced edition for ages 13 to 18 with ethical reasoning and supervised generative AI use.

Their evaluation is a single post-exposure survey of 831 participants, and the elementary cohort rated the materials significantly higher on performance expectancy, effort expectancy, playfulness and behavioral intention, with perceived playfulness the strongest correlate of intention in both groups. The authors are explicit about the limit: roughly thirty minutes of exposure, measuring acceptance rather than learning, ethical competence or actual use. Read it as evidence that this sequence is teachable and appealing; it says nothing about whether the sequence works.

The two editions also show what the boundary is for. The elementary band gets platform-based activities that are scaffolded and non-generative, so a child learns what the system does without a system that talks back. The advanced band attaches ethical reasoning to supervised generative use. Staff who expect engagement to follow the sophistication of the tool usually find the opposite.

What the tiering buys you is a defensible order of operations. Plenty of schools run it backwards, buying the chatbot in the fall and teaching about it in the spring, and the evidence on that order is further down this page.

Start the youngest children with play, making and machines

Play With AI is a play-centered pre-K and kindergarten curriculum built on embodied play, tangible coding as a procedural bridge, guided dialogue as reflective Scaffolding, and teacher co-design as the Sustainability anchor. Across design cycles teachers' self-rated comfort rose, and children reasoned about AI as human-designed, built sequencing and debugging through tangible coding, and reflected on fairness through guided dialogue. AI-Play takes the unplugged route, with screen-free activities parents can run at home.

For the youngest, the risk is belief. Yang, Li and Lee (2025) caution that generative social robots can produce content preoperational children accept as true, that these systems are not developmentally calibrated in the feedback they give, and that their cost and availability widen existing divides. Xu, Girouard and Shi (2026) describe the mechanism as a redistribution of agency in play: control shifts toward the child-toy interaction, constraining play when the toy organizes it and enabling it when the toy follows the child's imagination. The same toy can do either, which is why the adult's presence is the design variable you control.

Adult co-use means something specific here: sitting with the child, asking what the toy or the screen just did, and keeping the making visible. Quiet monitoring from the doorway is not the same arrangement, and for a four-year-old it misses the belief problem entirely.

Teaching how machines work belongs in this band too. Tsingidou et al. (2026) find problem-based learning, storytelling and scaffolding the most-used strategies in robot-mediated computational thinking at kindergarten, with sequencing, debugging and algorithmic design the most-assessed skills, most often through TechCheck-K. Many of the tools in that literature were developed ad hoc and never validated. Skip the teaching and the risks reappear later as over-reliance.

Move 9- to 12-year-olds onto vetted, mostly non-generative work

This is the band where the curriculum evidence is strongest. Demir and Akar (2026) ran an 18-hour, 5E-based critical media literacy program for 36 Turkish fourth-graders covering data privacy, safe communication and media Ethics, with between-group Cohen's *d* of 1.12 for reading, 1.18 for writing and 1.31 for total literacy. A program that fits inside a single semester and reports effects of that size is the most encouraging result on this page.

Ages 9 to 12 get scaffolded exposure on platforms the school has vetted, with the generative parts reserved for later and supervised. Once children can read, argue and check a claim, teaching them what a system is doing becomes the work, and the tool can enter as an object of study rather than a helper.

The boundary tracks capability more than birthday. A 9-year-old who reads fluently can be taught what a training corpus is and why a system that predicts the next word can produce a confident wrong answer. A 6-year-old cannot, which is why the play and making band comes first and why the kindergarten curriculum runs through tangible coding rather than screens. Reading, argument and self-monitoring are the capacities you are really slotting children by, and age is the proxy schools can administer.

Put the rule where the exposure actually is

Assume the responsibility will be unclear unless you settle it in writing. In interviews with 33 US K-12 teachers, Xiao et al. (2026) found 10 named the parent-facing companion scenario as the most concerning, 17 said a teacher should get involved and 11 said it depends. Their visibility test left home AI use outside school jurisdiction absent observable effects, and parents came out as primarily responsible while being described as unaware or overstretched. That is a jurisdictional vacancy, and a policy written as if it did not exist governs the easy half of the problem.

Fan, Li and Zhang (2026) formalize the arrangements as additive, synergistic and compensatory models, and state plainly that the synergistic version has no supporting evidence. A working family-school arrangement has to be built on purpose, which means telling parents what to do at home rather than only what not to do.

Disclosure is the school's job, not the family's detective work. Write down which tools the school uses, what data they keep, and how a family can ask. Privacy, Pedagogical Safety and AI Use and Disclosure Statements cover the substance, and the equity, ethics, privacy and safety synthesis covers how thin most of it is in practice.

Vet the tool before you adopt it

Assume the safety layer was not built for your students. A child-safety evaluation framework grounded in expert guidance and real incident data reports that most AI safety frameworks and benchmarks target adult users despite evidence of heavy youth engagement, and that a national survey cited in that work found 72% of US adolescents had used AI companions. When three Llama Guard models were tested on education-related unsafe prompts, they struggled to identify them.

Four questions will save you a procurement cycle. Which child-specific hazards were tested? What happens to recordings, transcripts and voice data by default? What will it cost families if the free tier disappears? Does it work in the languages your families speak?

An all-girls makerspace case study (Liu et al. 2026) shows why the last three are not footnotes. Parents reported that girls became scared and spoke less in mixed-gender settings, a free image generator dropped its free functions for a paid tier the nonprofit could not absorb, and English-only prompts shut out families the program was meant to serve.

Staff confidence is a privacy control as much as a training goal. A study of early-childhood settings finds perceived usefulness and ease of use central to preschool teachers' intentions to use AI, AI Self-Efficacy a meaningful predictor, AI anxiety a deterrent, and subjective norm (colleagues and leadership) shaping intention. Staff who cannot evaluate a tool will not notice what it collects.

Give the adult a defined role

Leave the role undefined and something else takes it. ParaTutor (Luo et al. 2026) separated parent and child roles in Large Language Models (LLMs)-mediated home mathematics tutoring with 23 parent-child dyads, children aged 10 to 12, across four conditions. Generic assistance tended to displace the parent's tutoring role; the role-separated interface preserved it. Parents also struggled with the content and with how to talk about it, which is a design requirement rather than a parent failing.

Companions that read with children need the same care. Liao (2026) found a fixed peer-role AI companion produced significantly longer interactions but a lower share of words and sentences from the student, and was stronger on factual recall than on emotional or future-oriented reflection. Hence the Parent Advisor role in the proposed framework, and the support vacuum the paper names for teachers and parents.

Some of this work belongs to people regardless of what the tool can do. Raave and colleagues (2026) compared a generative AI conversational agent with human educators facilitating story-based social-emotional learning activities with a static AI child: 18 simulations per facilitator, 108 observations, rated blind to facilitator type. The agent was strong on respectful tone and routine procedural scaffolding. Human educators were stronger at deeper SEL instruction, guiding reflection and building social-emotional knowledge. Early SEL should default to complementarity, with the adult holding the reflective part.

The role needs a name on a page. Decide who sits with the child during a session, who reads what the system kept, and who answers the parent who asks what happened. In a primary classroom that is usually the classroom teacher for the first two and the principal for the third. Written down, the arrangement survives a staff absence.

Keep the child's own thinking visible

The pattern to watch is output quality rising while unaided work falls. A 26,811-student secondary analysis found homework scores rose while closed-book exam scores fell, which is why the recommendation is to monitor inputs rather than only products. In a primary classroom that means watching the drafting, the explaining and the revising, and treating a sudden polished artifact as a question rather than an achievement.

The primary writing evidence supports tools used inside instruction. A systematic review of 8 studies of AI in elementary writing instruction from 2019 to 2025 finds conversational tools supporting writing practice and Multimodal AI tools extending composition beyond text, while concluding that automated assessment still requires human oversight for fairness and accuracy. A nine-week GenAI-supported opinion-writing program with 301 Grade 5 and 6 students raised ideal writing self and academic buoyancy and lifted behavioral and emotional engagement. It did not move growth mindset, cognitive or metacognitive engagement, or organization, and the authors name the risks: over-reliance, shortcut-seeking and diminished self-monitoring.

Handle the wrong answer while the child is watching

Deleting a bad output teaches a child that outputs are either correct or forbidden. Asking how they would check it teaches the habit you want. A child whose chatbot gets a factual detail wrong can be sent to two other sources and asked which one disagrees, and the habit carries to the next system that sounds confident.

When a child says the companion "understood" them, that is the conversation to have. A system predicting the next word has no model of the child, and the useful question is what it would have needed to know in order to understand. Keep it concrete and skip the lecture on neural networks.

Fluency buys belief, which is the mechanism to watch. A Grade 5 multimodal writing study found that visualizing children's stories produced sustained gains in interpretation, analysis, evaluation and explanation, with no gain in inference: once images made meaning explicit, children reported less need to infer it. A

fluent AI answer does the same work, supplying the inference the child would otherwise have made for themselves.

Some of the hardest conversations have a vehicle. REMind uses robot-mediated applied drama for anti-bullying bystander intervention: children watch a bullying scenario enacted by social robots and rehearse defense strategies by puppeteering a robotic avatar. In a mixed-methods play-test with 18 children aged 9 to 10 it supported self-efficacy, perspective-taking and understanding the outcomes of defending. Robots and role-play carry a difficult subject with an adult in the room.

None of this is a tested intervention for teaching a child to check an AI answer. It is what the evidence on fluency, belief and role-play implies, and staff should treat it as practice rather than proof.

What you can promise the board

Arthars and colleagues (2026) reviewed 271 empirical papers on generative AI in PreK-12 and found no single GenAI effect. Affective gains are common and weak indicators of learning; the most consistent evidence concerns improved immediate performance and product quality; evidence on durable learning, transfer and sustained self-regulation is uneven. Outcomes depend on five entangled conditions, learner, tool, task, social arrangements, and cultural and institutional context. Their framework separates four pedagogical functions, learning from AI, with it, about it, or by shaping it, and asks whether a student surrenders, offloads or exercises agency.

For this age band that maps onto a sequence: about and by shaping first, from later, adult co-use wherever the child cannot yet evaluate the output, and no claims about durable learning from a good afternoon's product.

A board paper can promise a review date and a definition of success your school can actually check: lessons taught, teachers who can answer a parent's question, data requests answered in writing. Claiming a learning gain would overreach every study cited here.

There is no study of age-based bans in this knowledge base. Nothing here can settle whether the bans now appearing in some school systems work, and the honest version of that sentence belongs in your board paper. What the evidence does show is that the alternative to a ban is not laissez-faire. The study of GenAI availability versus integration found that making GenAI available without teaching students how to use it was associated with significantly lower performance on applied questions ($\omega^2 = 0.35$), while explicitly teaching its use for tasks like summarizing returned applied performance to pre-GenAI levels and exceeded baseline on one harder quiz. This age band can be taught: the fourth-grade program above produced effects of $d = 1.12$ to 1.31.

What schools get wrong

"Under 13 means no AI." The published tiering puts non-generative, scaffolded activity in the 9 to 12 band and reserves generative use for 13 and up. A school that bans everything has no curriculum in this area, and its children meet the tools at home without the lesson.

“The tool is compliant, so it is safe.” Most frameworks and benchmarks target adults, and three Llama Guard models struggled on education-related unsafe prompts. Compliance paperwork answers a procurement question. It does not answer the hazard question.

“A policy sentence is a policy.” Nash and Burriss (2026) found 26 of 27 preservice teachers permitted some AI use on teacher-specified terms and one prohibited it entirely, with limits rarely operationalized: one policy allowed AI “to get your thinking started” and then declared “this is where the line should be drawn” without saying where. A comparative analysis of institutional policies and course syllabi found institutions broadly encouraging GenAI use in 63% of 116 policies while half of 98 course syllabi prohibited it outright. A UNESCO-framework analysis of 30 universities’ policies adds that ethics and governance principles are widely adopted while inclusion, equity, internet access and environmental impact are often overlooked, with many provisions left declarative.

“Parents will cover the home half.” The 33 teachers described parents as primarily responsible and also as unaware or overstretched. The synergistic family-school model has no supporting evidence yet. It has to be built.

“Six-year-olds cannot understand how a machine works.” Children in the pre-K curriculum reasoned about AI as human-designed, built sequencing and debugging with tangible coding, and reflected on fairness through guided dialogue. The kindergarten robotics literature finds sequencing, debugging and algorithmic design among the most-assessed skills in that band. The capacity is there. The curriculum usually is not.

What will come back at you

“Ban it. It is the only defensible line.” No study of these bans exists, so nobody can tell you they work, and the enforcement path is weak. Bassett et al. (2026) argue detection should not be used in education at all: its estimates are probabilistic and unverifiable because real-world text origin is unknown, its use violates procedural fairness since detector scores do not meet the standard integrity investigations require, and detection “does not safeguard academic integrity; it undermines it,” eroding Trust. A ban also governs the least important channel, since companion apps, AI toys and family tutoring happen at home, beyond school reach.

“Everyone else’s child is already using it.” Partly true, and the figure usually quoted is about adolescents: 72% of US adolescents had used AI companions in the survey cited in the child-safety work. That is not your ten-year-old. The 271-paper review found no single GenAI effect, so what peers do tells you what is normal, not what is safe or useful.

“We are a school. Why are we running a parenting campaign?” Because the exposure is there. Ten of 33 teachers named the home companion scenario as the most concerning thing they faced, and the visibility test left it outside their jurisdiction. A school that publishes what it uses, what it recommends at home and how to ask questions governs more of the problem than one that writes a rule for its own network.

“Surveillance will keep them honest.” Mohamed and Temimi (2026) model this as imperfect information: the student knows how the work was produced and the institution sees only the artifact. Deterrence runs through a detector’s discrimination between hidden use and legitimate work rather than its raw catch rate, and when false positives rise faster than true positives, stronger monitoring makes concealment relatively

more attractive. Qu and Wang (2026) found non-disclosure among 409 undergraduates was strategic adaptation to peer norms and low interpretive trust rather than moral negligence.

“Our families cannot afford what you are recommending.” The makerspace case is the warning: a free tier disappeared into a paid tier the nonprofit could not absorb, and English-only prompts excluded families. Procurement that assumes a paid tier is a policy that widens the divide you were trying to close.

“Our teachers are not trained for any of this.” Often true, and the fix is smaller than it looks. In the pre-K curriculum, teachers’ self-rated comfort rose across design cycles, which is what co-design does that a training day does not. In early-childhood settings, self-efficacy predicts intention to use AI and anxiety deters it. Start with one lesson in one class and let the staff who run it write the guidance.

“All this caution is a moral panic about toys.” There is real uncertainty here, and the 271-paper review is the honest summary of it. The case for teaching rather than banning rests on a jurisdictional gap, a failed enforcement route, and a fourth-grade program that moved literacy by more than a standard deviation in eighteen hours.

What to do this week

1. Write the age bands into one page: what under-9s do, what 9- to 12-year-olds do, and what requires a named adult and a stated purpose.

2. Take the four vetting questions to whoever signs the software contract, and ask for answers in writing.

3. Send families a one-page note listing what the school uses, what it keeps, and who to ask.

4. Pick one non-generative activity for the youngest band and one media-literacy lesson for the 9 to 12 band, and book them into the term.

5. Strike detection from the draft policy, replace it with a rule about what the school will and will not provision, and set a review date with three things to check: what teachers used, what families asked, and whether the 9 to 12 lessons ran.

Where to go next

How Is AI Impacting Students? covers what the tools do to learning, and How Should I Incorporate AI Literacy into My Course? with AI Literacy covers what to teach. Parents and Families and Early Childhood Education hold the research base for this page, and How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? is where the privacy and safety argument continues. If your question is the assessment side for older students, Should We Use AI Detectors? and How Can I Reduce AI Cheating in My Course? take it further.

Connected FAQs

- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?
- How Should I Incorporate AI Literacy into My Course?
- How Is AI Impacting Students?

How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?

The protocol is due Friday. Section 7, on ethics, says risks will be monitored. Recruitment runs through an existing first-year course, and the limitations paragraph notes that findings may not generalize. The review panel will ask who is likely to benefit, whether disabled students can use the thing, what happens to the interaction logs, and what a harmful tutor response looks like in the data. Four questions, and none of them has a section yet.

The answer to give the panel: equity, accessibility, privacy, and pedagogical safety belong in the design and in the outcome measures from the first draft. Each changes what you recruit, instrument, and report, so attach it to a decision while the protocol is still editable.

The short version

1. Name the subgroup comparison before you collect data, and put it in the analysis plan.

2. Put disabled learners in the design session and test the actual interface.

3. Write down the privacy trade-off, including who decided it and who can reverse it.

4. Test safety across whole conversations, in your own discipline's scenarios.

5. Combine outcome data with interviews, and leave a trail a reader can inspect.

Ask who gets the benefit

The Digital Divide concept separates access, skills, and outcome divides, which means that removing the access barrier with a chatbot does not produce equitable benefit. Design for the third divide. Report subgroup outcomes and test for differential effectiveness instead of relying on the overall average (Differential Effects Across Learner Groups).

A comparative study of 45 Nigerian universities (15 federal, 15 state, 15 private) shows how they compound. Overall AI integration was moderate, M = 4.79 on a 10-point scale, range 1.83-7.83. AI Governance type did not predict it ($F(2,42) = 1.01$, $p = 0.372$). Institution age ($\beta = 0.43$, $p = 0.016$) and South-West location ($\beta = 0.31$, $p = 0.029$) did. Internal capabilities reinforced one another ($r = 0.79$-0.80), and international collaborations and industry partnerships compounded each other ($r = 0.74$), which the authors summarize as "connections beget connections." Policy frameworks were weakest (M = 4.09; only 27% of institutions scored 6 or higher), leaving a gap between formal strategy and operational curriculum activity.

Two design implications follow. Target newer institutions and underserved regions, since category does not determine capacity. And account for the Global South contexts the wider evidence base still omits.

Put disabled learners in the design room

Include learners with disabilities in design and evaluation, test actual interfaces against accessibility requirements, and provide equivalent routes to participate and to demonstrate learning. Technical compliance and inclusive teaching are separate tests, and Accessibility covers both.

A value-sensitive design study with community college students, instructors, and developers shows the work in practice. It produced 16 value-aligned features across explainability (E1-E5), human-in-the-loop control (H1-H9), and Privacy (P1-P4), and surfaced tensions rather than tidy answers: transparency against interpretability, privacy against instructional insight, learner Learner Agency against system-guided Scaffolding. Expect to adjudicate those, and record which way you went.

Decide the privacy trade-off, and name who decides

Collect the data the educational purpose needs, make data use and system limits transparent, and keep human accountability concrete. Fairness, consent, bias, explainability, learner autonomy, and the consequences of AI-mediated decisions are core dimensions of Ethics, and they conflict in practice. Students wanted control over learning analytics and affective data; instructors wanted visibility to support learning. Both positions are defensible, which is why the decision needs a named owner.

As systems take on Learner Agency, the question turns structural. A critical review of agentic AI governance argues that autonomy should not exceed the maturity of the evidence or the strength of accountable human control. It proposes a shared reporting language: autonomy levels A0-A4, oversight levels O0-O4, evidence-maturity stages M0-M5. Consequential uses (A4: admissions, grading, progression) require replicated, context-relevant validation and continuous human authority, and a high Benchmark score substitutes for neither.

Test for the harms benchmarks miss

Pedagogical safety means measuring what a benchmark will not: overreliance, answer over-disclosure, misconception reinforcement, loss of agency, suppression of Metacognition, inequitable treatment, motivational harm, and instructional misalignment. Test multi-turn interactions in discipline-specific scenarios. The Pedagogical Safety synthesis and the SafeTutors benchmark show why an accurate-seeming system can still damage learning.

Practitioners converge on a compatible design. In a participatory design study with six secondary teachers, teachers independently designed “bounded experts” rather than autonomous agents: a narrow domain, human supervision, and three protective layers in domain boundaries, content filtering, and teacher override. They welcomed AI for presenting content, supplying practice, and giving formative Feedback, and declined to delegate objective-setting or summative assessment. They framed oversight as professional responsibility.

Combine methods, and show the path from data to claim

Disaggregated quantitative outcomes can reveal differential effects. Interviews, observations, focus groups, and co-design surface barriers, harms, cultural assumptions, and learner experience that aggregate scores miss. The Research Methods in AIED synthesis treats triangulation as necessary because no single qualitative or quantitative method maximizes causal inference, ecological validity, contextual understanding, and generalizability at once.

Your own analysis needs the same discipline. The warrantability proposal argues that an AI-assisted interpretation stays inspectable, contestable, and revisable when it ships with artifacts such as source-linked topic tables, lens stacks, and evidence rivers. A fluent summary should not hide the pathway that produced it.

Keep outcome levels apart too. The agentic-AI review separates artifact outcomes, such as accuracy and feedback quality, from learner benefit. Artifact outcomes can be necessary and are never sufficient, and equity and institutional outcomes are where evidence is thinnest.

What this audience gets wrong

Equity means access. The Digital Divide concept puts skills and outcomes on the same list as access, and Adeniranye's study found capacity differing by institution age and region while governance type predicted nothing.

Accessibility is a checklist on the interface. The value-sensitive design study surfaced tensions between explainability and interpretability that no checklist resolves.

Privacy is a consent form. The design study found students and instructors wanting opposite things from the same data, and the governance review ties autonomy to evidence maturity.

Safety means the model refuses harmful requests. Pedagogical safety covers overreliance, misconception reinforcement, and lost agency, which a refusal test does not touch.

A single method answers the question. The methods synthesis is explicit that those four properties trade against each other.

What will come back at you

"We will address equity in the discussion." Then your analysis plan cannot test it. Name the subgroup comparison now, or the finding arrives after the data is closed.

"Our sample is too small for subgroup analysis." Then say what it supports and report who was in it. A null subgroup result from an underpowered sample is not evidence of equity.

"Accessibility testing is the disability office's job." Their review covers compliance. Whether a learner can demonstrate what they know inside your activity is a design question, and the design study above put students in the room for that reason.

"The data is de-identified, so privacy is handled." The design study's tensions were about control and visibility, not identifiers. Students wanted to know who sees their affective data and why.

"Our safety suite passes." On which turns? SafeTutors found teaching models degrading over long conversations, which is the length your students will actually use.

What to do this week

1. Add a subgroup paragraph to the analysis plan, naming which groups and which outcome.

2. Book one design session with disabled learners or the staff who support them, before the interface is final.

3. Write the privacy decision as a sentence with an owner: what is collected, who sees it, who can stop it.

4. Draft ten adversarial conversation turns in your subject and run them against the system.

5. Add one inspectable artifact, such as a source-linked table or a coded excerpt set, to the analysis folder.

Where to go next

Evaluating AI interventions: methods is the companion page on measures and design. Top 10 Findings for Instructors carries these constraints in findings 9 and 10, Addressing Common Misconceptions About AI in Education handles the stakeholder objections, and Research Gaps in AIED lists where the evidence is missing.

Connected FAQs

- How Can AI Support Disabled and Neurodivergent Learners in My Course?
- How Should Parents and Teachers Approach AI with Children Under 13?
- How Do We Write and Implement an Institutional AI Policy?
- What Are Notable Gaps in the Research Literature on AI in Education?

Careers and AI literacy

For curriculum designers and program leads answering students who ask what this is all for.

What Should Students Learn for Careers Where AI Is Commonplace?

A student asks why they should learn to do something a chatbot already does. A program advisory group says employers want graduates who can use AI at work. Your syllabus has to satisfy both, and neither of them has said what the graduate should be able to do unaided.

Short answer to give a colleague: teach the whole professional task, not the tool operation, and assess both the supported product and the student's independent capability. The evidence supports treating readiness as disciplinary knowledge plus judgment plus verification plus transfer, and it does not support any list of skills as a guarantee of employment. A survey of 500 US college instructors against an employer panel found the two groups agreeing on the importance of exactly one of 26 AI-related skills, *setting realistic expectations for AI-augmented work*; instructors weighted critical and responsible use while employers weighted workflow, automation and human-AI teaming (Fried, 2026). Those are reported priorities, not hiring evidence. The sharper finding for a curriculum is elsewhere: in a survey of 455 final-year students, AI literacy reached perceived employability mostly by raising career adaptability, with an indirect effect of $\beta = 0.173$ alongside a direct $\beta = 0.447$ (Hendrawan and Lestari, 2026). Adaptability is a capability you can teach. A tool tip is not.

The short version

1. Write the capability as a claim about what a graduate can do unaided, then add the supported version beside it.

2. Teach the complete task in six parts: frame, know, delegate, verify, communicate, adapt.

3. Assess the product and the judgment separately, and make the independent check proportionate.

4. Keep independent practice where it is doing work, and say why in the syllabus.

5. Distinguish immediate outcomes from later ones when you evaluate the program.

6. Treat career anxiety as a real concern and answer it with investigation, not with predictions.

What employers and instructors each emphasize

Ithaka S+R's report asked 500 US four-year-college instructors to rate 26 skills from a framework spanning seven categories, and compared their ratings to a panel of employers surveyed by the framework's authors. The disagreement is systematic rather than random: instructors ranked the limits of AI, attribution and human accountability at the top, while employers ranked workflow design, automation and human-AI teaming higher.

Two readings of that gap are tempting and both are wrong. The first is that instructors are behind the labor market. The second is that employers want compliance. A more useful reading is that each group is describing a different half of the same job, and a graduate who can only do one half is underprepared for both. A student who cannot explain why a result is wrong is no use to an employer who trusts the workflow; a student who can only critique AI output is no use to an employer who needs the task completed.

The limits of this evidence matter. These are stated priorities from surveys, and the report does not show that any curriculum produces better hires, better performance or better pay. What it does give you is a defensible reason to ask whether your students ever practice completing and checking an AI-supported workflow, as opposed to discussing it.

Teach a complete professional task

The curriculum question worth writing down is: what would a capable beginner need to do, explain and verify in this situation? Then build the task in six parts.

Frame the problem. Identify the goal, audience, constraints, available evidence and the cost of being wrong. A student who cannot recognize an underspecified request will pass it to a model and accept whatever comes back.

Bring disciplinary knowledge. Students need enough understanding to inspect the result: interpret a case, estimate a plausible answer, notice a misleading comparison, spot what is missing. Define that baseline explicitly instead of treating all independent practice as a legacy requirement.

Delegate deliberately. Decide which steps AI may assist and which need independent work or professional authorization, and be able to give the reason. Drafting routine wording and deciding what a consequential record should say are different responsibilities with different accountabilities.

Verify against evidence. Check calculations, claims, sources, assumptions and compliance with the requirement. Teach students to record how a check resolved the question. Asking the same model whether it is sure resolves nothing, a point verification practice develops directly.

Communicate and collaborate. Explain the decision to a colleague, client or supervisor: what changed, what remains uncertain, when someone else must be involved. AI-supported work still has an audience and a chain of responsibility.

Adapt and transfer. Repeat a comparable task with a different tool or a new constraint, then ask what stayed useful and what had to change. This is what makes adaptability observable rather than an adjective in a graduate attribute.

Build it into existing course work

These are adaptations of the research themes, not tested employment interventions.

Composition and business communication: have students critique and revise an AI-drafted reply to a customer complaint. The evidence of capability is naming the unsupported promises, explaining the audience choices, and defending the final wording.

A quantitative course can do the same with an AI-produced estimate for a realistic planning problem, where students construct their own estimate, state the assumptions and test plausibility.

For a spreadsheet or computing course, hand out a generated formula and synthetic data, then ask for test cases, an explanation of the references, and one failure condition.

Health professions: students evaluate a generated explanation for a fictional case against approved sources, name its limitations, and state when a qualified professional must decide.

Career exploration has its own version: compare the task composition of two occupations using credible occupational information, then plan one concrete skill-development or Help-Seeking step.

For asynchronous delivery, ask for an initial attempt, a short verification record and a two-sentence note on one consequential decision. In a lab or seminar, the explanation can happen in conversation. Use synthetic or authorized materials whenever the alternative is confidential workplace or student data.

Assess supported performance and individual understanding

A polished artifact tells you what was produced under the permitted conditions. It does not tell you what the student can do. Add a proportionate independent check: explain a decision, repair an error, adapt the work to a changed condition, or perform one foundational subtask unaided.

Choose those requirements because they support a stated capability, and say which one each assessment is measuring. Students accept independent practice when it is connected to the thing they are being prepared for; “you will need this someday” does less work than showing how the calculation is what lets them catch a wrong estimate later.

The support side has its own risk. Shojaei et al. (2026) found GenAI use positively associated with GenAI dependence, and dependence negatively associated with both critical thinking and employability in their survey model. That is an association rather than a causal claim, and it points at the design question: a course that only ever assesses supported performance may be training the dependence it reports.

For program review, separate the measures. Course performance, demonstrated AI literacy, internship-supervisor evaluation, employment status and job quality are different outcomes with different time horizons, and a single intervention cannot establish all of them. The AI literacy evidence page is the honest inventory of what intervention studies actually support.

Address career anxiety without promising certainty

Students arrive with real fears, and the survey literature on them is a description of the fears rather than a forecast of the labor market. Duan et al. (2026) found AI anxiety directly and negatively predicting career decisions, which is a finding about decision paralysis, not about jobs. The wellbeing picture covers the wider evidence.

What helps is investigation at the scale a student can act on: which tasks does this role actually contain, what does a week look like, what would I need to be able to do, who can tell me. Career services, alumni and placement staff hold that information. A tool demonstration, an instructor’s impression or a vendor’s presentation is not a labor-market forecast, and presenting one as a forecast is how programs lose their credibility with students who then check.

What will come back at you

“Students just need better prompting.” Prompting is one clause of one of the six parts. A well-specified request does not supply the knowledge needed to recognize a bad result, and the employers in the Ithaka panel were not ranking prompt craft first either.

“If workplaces allow AI, coursework should allow it.” A course also builds the capability that makes responsible use possible. Say which of the two you are assessing in each task, and the objection becomes a design question rather than a contradiction.

“The tools change too fast to teach any of this.” Teach tool-specific operations where they help and assess the durable practices: framing, checking, testing, documenting, communicating, escalating. The evidence above is about those practices, and none of it depends on which model is current.

“An AI-literacy course will improve their job prospects.” The mediation result is the caution here. AI literacy reached perceived employability directly and through adaptability, and perceived employability is not a job offer, a performance rating or a salary. The survey design cannot rule out that confident students rate themselves higher on everything.

What to do this week

1. Choose one task graduates in your program will actually face, and write the six parts for it in five lines.

2. Mark which parts the current assessment actually measures and which it assumes.

3. Add one independent check to an existing assignment: a decision explained, an error repaired, or a subtask done unaided.

4. Tell students which capability that check is for, in the assignment instructions.

5. Check whether any task in the course assesses only supported performance, and decide whether that is deliberate.

Where to go next

Career Development and Readiness is the concept page for employability, adaptability and workforce evidence, and AI Literacy covers what literacy means beyond tool operation. For building it into a specific course, see incorporating AI literacy and what competencies faculty need.

For the assessment design that makes supported and independent performance distinguishable, see redesigning assessment in the AI era and AI grading. For how to keep support from becoming dependence, see reducing over-reliance.

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?
- How Does AI Affect Student Anxiety and Well-Being, and What Can We Do?
- How Do I Keep Students from Over-Relying on AI?
- Does Using AI Actually Help My Students Learn?

What Is the Evidence on AI Literacy Interventions in Higher Education?

The provost's office wants an AI literacy outcome in every undergraduate program by next fall, and the plan on the table is a two-hour workshop plus a library tutorial module. Or a grant has funded "AI literacy" at your institution and the first committee meeting is about what to buy with it. Someone in the room will ask what students will be able to do afterward, and what settles it is a design argument.

The answer for that room, and the state of the evidence in higher education, is this: literacy grows when students critique AI output inside a real disciplinary task, repeatedly, with peers, and it grows least when they are shown what the tool does. The average effect across the intervention literature is large; the spread around that average is wider still, so your design decides more than your topic. Confidence surveys measure acceptance. If you want to claim literacy, test a performance.

The short version

1. Put the literacy inside a course students already take, on work they are already graded on.

2. Have them commit to their own answer before they see the model's.

3. Grade the critique, using the rubric you already use for the task.

4. Run it more than once across the term.

5. Count a performance task as your evidence, and keep confidence gains as a separate line.

Build the sequence around a critique

The strongest classroom example in the knowledge base comes from undergraduate psychology. Richmond and Nicholls had students grade a ChatGPT-generated media release against their own course rubric, name the errors, and revise it. Students generally saw that the prose was polished and that the content misrepresented the research aims, methods, and findings. Against the previous Peer Assessment cohort, the AI-critique group did modestly better on the script revision that followed ($d = 0.36$), with no significant advantage on the final video (Using generative AI to promote psychological, feedback, and artificial intelligence literacies in undergraduate psychology).

The literature these examples come from leans on short interventions, self-report, and design-based work, and this study carries two of those limits. The comparison was historical, so a better-prepared cohort would produce the same pattern. The advantage also appeared on the intermediate artifact and vanished on the finished one, which is what you would expect if the critique taught revision.

Beck and Brodersen built the same move into an economics course: students solve or interpret an authentic problem themselves, then obtain ChatGPT's response, compare the two, critique the AI, reflect, and discuss with peers. Their design folds AI literacy into Active Learning routines the course already ran, such as Think-Pair-Share. Its contribution is a transferable instructional design, supported by classroom use rather than an experiment (Fostering Generative AI Literacy in Economics: A Hands-on Approach).

Put it inside a course students already take

Hingle and Johri's systematic review sorts AI literacy activities with the ICAP framework: passive exposure, active manipulation, constructive generation, and interactive co-construction. Interventions appear in all four modes, and the review argues against reducing AI literacy to a one-way information session (Systematic review of collaborative learning activities for promoting AI literacy). The practices it supports are the ones you can build into an assignment: students create, critique, explain, and debate AI outputs with peers.

The NC State **AI Literacy Continuum** describes a progression from *Not Yet Engaged* and *Uncritical Use* through *Informed Use*, *Critical Evaluation*, and *Improvement*, and was implemented with more than 330 participants across courses and workshops (Beyond Tool Adoption: A Practical Five-Stage Developmental Continuum for AI Literacy in Higher Education). Its observations suggest a split: brief experiences moved students toward informed use, while critical evaluation and improvement showed up mainly in sustained, discipline-embedded work. There was no validated pre/post measure and no comparison group, so this is practice-based evidence.

Teacher education shows the same ceiling from a different angle. Le et al.'s design-based intervention was piloted with 14 master's students and evaluated with 29 Teacher Education students. Reported AI-competency Self-Efficacy rose and students shifted toward more critical pedagogical consideration of GenAI, while ethics gains reached only marginal significance. A small design-based study of that shape cannot establish competence (Development and evaluation of artificial intelligence literacy training for teacher education students).

Measure what students can do

A three-level meta-analysis of 59 studies (172 effect sizes, 7,211 participants) gives the clearest quantitative estimate available: a large overall effect ($g = 0.837$, $p < .001$). The 95% prediction interval runs from -0.292 to 1.966, which is the number to quote when someone asks whether the intervention will work in your program. Two moderators were significant. Interventions in East Asia and Europe outperformed those in North America, and knowledge-focused interventions outperformed those aimed at skills, attitudes, or ethics. Larger but non-significant effects appeared for mixed or reflective pedagogies, GenAI-supported tools, and performance-task outcomes.

The authors read their own result as an argument for moving past knowledge toward skills, practices, ethics, and attitudes, through integrated reflective pedagogy and culturally relevant design. For a committee, two implications do the work. The outcome you measure shapes the effect you find, so pick the outcome you actually care about. A prediction interval that wide argues for a local pilot.

Measurement is where most program claims fail. The validated **GLAT** performance test predicted performance on an AI-assisted higher-education task. A self-reported ChatGPT-literacy measure did not (GLAT: The generative AI literacy assessment test; How to Assess AI Literacy: Misalignment Between Self-Reported and Objective-Based Measures). Across the knowledge base, reported and demonstrated AI competence diverge substantially, which makes educational measurement and assessment validity part of the design rather than an afterthought in evaluation.

Burriss et al. sharpen what counts. Their study of 22 eleventh-grade students composing video public service announcements about AI ethics argues that existing literacy scales and competency frameworks assume

individually measurable performance, which excludes collaborative and creative expression. They propose student reflections, Multimodal AI artifacts, and civic discourse as complements to conventional measures. Their students developed critical AI-ethics understanding through collaborative critical pedagogy, and that challenges skill-list conceptions of literacy along with the instruments built on them. Fifteen of 18 end-of-unit responses affirmed new learning, and the authors note the project resists traditional summative assessment ("Young Scholar[s] on the Beat": Multimodal composition as a form of critical AI literacy pedagogy).

Acceptance measures are a separate trap. Wang, Chuang, and Wu surveyed 831 Taiwanese K-12 students and teachers after roughly 30 minutes with an age-tiered AI literacy guidebook and found a stable four-factor acceptance structure. Perceived playfulness was the strongest correlate of behavioral intention. The study measured short-term acceptance, not learning gains, ethical competence, or actual use, and the authors state that acceptance constructs "must not be used to infer learning effectiveness or implementation success" (Measuring Acceptance of Age-Tiered AI Literacy Guidebooks: A Developmentally Informed Study of K-12 Students and Teachers).

Plan for the errors that teaching will not fix

Training students to prompt or use AI better does not make them reliably critical users. In the contextual-sycophancy experiment, AI-literacy and prompting training cut how often the model mirrored participants' reasoning errors, and downstream error propagation survived the training (The Hidden Cost of Contextual Sycophancy: an AI Literacy Intervention in Human-AI Collaboration).

Read that as a boundary on what a course can promise. Literacy education cannot carry the whole safety burden, and a program that claims it will has moved the risk rather than removed it. Tool design and system-level safeguards stay in the plan.

Start where your students already are

Şan and Orhan Karsak used a psycholinguistic Word Association Test with 436 Turkish undergraduates (1,376 coded responses, inter-rater $\kappa = 0.87$) to map how students represent AI. Associations clustered around instrumental utility, with convenience ($f = 145$) and speed ($f = 110$) dominating. Algorithmic transparency, privacy, and AI Governance concepts were rare, and structurally isolated from that utility cluster (Kendall's $\tau = -0.819$). Their argument follows: an ethics module delivered into a cognitive structure with no schema to receive it will likely fail. Curricula need explicit bridges from everyday tool knowledge to ethical and governance frameworks, and micro-credentials should sequence content to close that gap instead of repeating what students already know (Knowing its name, not its nature: Word association mapping of student AI cognition and evidence-based micro-credential design in Turkish higher education).

A situated account comes from Dai and Chan's seven focus groups with 28 postgraduate researchers, who used AI unevenly across the research workflow. Use was heavier in low-stakes procedural work such as formatting, translation, and explanation, and markedly more cautious where scholarly contribution was at stake. Participants drew their own boundaries between assisting and substituting their reasoning. The authors treat AI literacy as a situated capacity rather than a static competency list, and recommend Scaffolding each

dimension across real tasks instead of enforcing binary rules (Shaping responsible GenAI use in research through AI literacy-oriented guidelines: Insights from postgraduate students).

Check the credential before you award it

Certificates and micro-credentials are where AI literacy gets delivered at scale and where evaluation is thinnest. Wu and Li built an expert-weighted indicator system (AHP and Fuzzy-AHP with Monte Carlo checks, 18 experts) for AI certificate programs. Faculty professional competence showed the largest importance-satisfaction gap, with high perceived importance (0.1976) against low current satisfaction. Their data put faculty capability ahead of technological infrastructure as the primary constraint on pedagogical change. Cross-cultural adaptability drew the lowest strategic weight (0.0735), which they read as a technology-first bias in early credentialing (Evaluation indicator system for AI certificate programs).

The question that follows is the one to put to your own program: does the credential certify durable literacy, or record attendance? And are the people teaching it equipped to judge?

What this audience gets wrong

A workshop is a curriculum. The Continuum's observations put critical evaluation and improvement in sustained, discipline-embedded work, and Le et al. moved self-efficacy without establishing competence.

Confidence is a proxy for literacy. The GLAT result is direct: a performance test predicted task performance and a self-report measure did not.

A large average effect means the program will work here. With a prediction interval from -0.292 to 1.966, the average describes the field; your cohort sits somewhere inside that range.

Literacy training makes students safe users. In the sycophancy experiment, training reduced mirroring and left error propagation intact.

Literacy is one skill that transfers across tools. Dai and Chan found researchers drawing different boundaries in different parts of one workflow.

What will come back at you

"There is no room in the curriculum." Add the critique to an assignment you already grade, the way Beck and Brodersen folded it into existing active-learning routines. A separate course costs more and teaches the same thing.

"Our students grew up with this technology." Familiarity with the tool is what Şan and Orhan Karsak measured: convenience and speed, with privacy and governance structurally detached. Fluency in using something is not understanding it.

"Just give us the effect size." $g = 0.837$, $p < .001$, from 59 studies, with a 95% prediction interval of -0.292 to 1.966. The second number is the one that governs your decision.

"We will survey students at the end of the term." Then you will have measured acceptance. Wang et al. say explicitly what that cannot support, on a sample of 831.

“The credential is the accountability mechanism.” Wu and Li found faculty competence to be the binding constraint, and cross-cultural adaptability weighted lowest. A certificate records that someone completed something.

“Our faculty are not ready to teach this.” The evidence agrees. Faculty capability was the largest gap in Wu and Li’s data, and no study on this page tests how to close it.

What to do this week

1. Choose one graded assignment and add a step where students produce their own answer before consulting AI.

2. Write the critique prompt against your existing rubric, so students grade the output on the standard you already use.

3. Schedule a second run of the same activity later in the term, in the same course.

4. Replace one end-of-term confidence question with a short performance item, and score it.

5. Ask whoever owns your micro-credential what evidence of competence it will accept, and get the answer in writing.

Where to go next

How should I incorporate AI literacy into my course? takes the design question into course planning. AI Literacy holds the concept and its measurement debate, and the research gaps page covers where this literature is still thin.

Connected FAQs

- How Should I Incorporate AI Literacy into My Course?
- How Do I Teach Students to Verify AI Output?

Building and evaluating educational AI

For developers, instructional designers and researchers shipping a tutor, a simulation or a platform into a real course.

What Are Best Practices for Developing an Effective AI Tutor?

Your tutor is three weeks from a pilot. The chat works, the model explains a derivative cleanly, and the internal demo got applause. Then someone from the teaching center asks the question your spec has no field for: after a term with this thing, will students solve a problem when it is not in the room? What you have is a feature list. What you do not have is one sentence saying what the learner must be able to do alone at the end.

A tutor is a policy wrapped around a chatbot, and the policy decides whether learning happens. Name the cognitive work the learner has to do, make the system require it (an attempt before help, a hint ladder that fades, a check the model cannot fake), and evaluate with the tutor switched off. Model quality sets how good the conversation feels. The policy decides what the student can do in June.

The short version

1. Write the objective as a claim about unaided performance, then derive every feature from it. If a feature cannot be traced to that sentence, it is a demo feature.

2. Build the learner model from evidence you can log, and store each diagnosis as a hypothesis with a confidence value rather than a fact.

3. Fix the help ladder in code, with named rungs, and make the interface charge the learner something for each step down it.

4. Ground content in your own materials and hand arithmetic, algebra and code checking to deterministic tools that cannot hallucinate.

5. Test teaching failures across whole conversations: answer leakage, sycophancy, misconception reinforcement, instructional drift.

6. Measure with a withdrawal phase and a delayed test, not a satisfaction score.

Write the objective as a claim about unaided performance

Three lists, written before anyone picks a model:

- What learners should know or be able to do afterward.
- What cognitive work they must perform themselves.
- What the tutor may do for them.

The Intelligent Tutoring literature makes the point that effectiveness depends on pedagogical design rather than model capability alone, and the failure is easy to build by accident. A tutor optimized for “finish the problem” will undermine a tutor optimized for “learn to solve the problem” while passing every functional test you write, because both produce correct final answers. The difference lives in what the student did between the question and the answer.

The second list is where development teams get concrete. Take a mastery label like “derivative mastery” and refuse to let it mean producing the correct derivative. Break it into recognizing when a derivative is appropriate, interpreting it as an instantaneous rate of change, selecting the rule, carrying out the procedure,

explaining why the choice was right, checking reasonableness, and applying it to an unfamiliar problem. Each of those is a separate thing to log, and each implies a different response when it is missing. This decomposition is also the defense against the correct-answer trap, where a learner reaches the right answer through faulty reasoning and your analytics record a success. Catching the Correct Answer Trap and When Help is Unhelpful both describe versions of that failure in production.

Build the learner model before the conversation

The learner model holds two kinds of state: per-concept estimates (limit: developing, power rule: mastered, product rule: developing, chain rule: not demonstrated) and misconception hypotheses with the evidence and confidence behind each. Keep them separate. The concept estimate is what drives difficulty selection. The hypothesis is what drives the next question.

Be careful about letting an Large Language Models (LLMs) do the diagnosis on its own. Benchmarking found that LLM tutors could recognize clearly correct reasoning while sometimes rejecting valid alternatives or accepting incorrect reasoning. A model that spots the good case and misreads the ambiguous one fails precisely the students who need the help. For consequential domains, the architecture that survives is **structured diagnosis plus flexible LLM dialogue**, the arrangement Confirming Correct, Missing the Rest describes: your own detector establishes what the student probably did, and the model writes the conversation around that finding.

Give the diagnosis an explicit sequence the model cannot skip: detect, verify, respond. The model may propose a misconception as a hypothesis, then must verify it against the student's actual work or a targeted question before the tutor responds to it. Without that step, the system invents evidence and then tutors the student for a mistake they did not make, which is both useless and slightly insulting.

Evidence worth logging, in rough order of usefulness: recent attempts with their intermediate steps, demonstrated knowledge by concept, help-seeking behavior (which is itself a signal about confidence), and self-reported confidence where you collect it. Adapt difficulty and assistance from that record, and treat the learner's latest prompt as one input to it. A single prompt is a bad estimator of what a student knows, and a tutor that reacts to it will thrash.

Fix the help ladder, then make the interface charge for it

Write the rungs down before you write a prompt, because the ladder is a product decision with named states, and a tone setting cannot express it. A workable sequence:

1. Independent attempt.
2. Metacognitive question about what the student has tried.
3. Conceptual cue.
4. Identify the relevant rule.
5. Set up part of the problem.
6. Worked intermediate step.
7. Worked solution.
8. Student explains the solution.

9. Student solves a comparable problem unaided.

Support fades as competence increases, which is the mechanism at the center of Scaffolding. Seeing a worked solution does not demonstrate mastery, so any session that reaches rung seven owes you rung nine before it counts as complete.

The causal evidence for building the ladder at all comes from a field experiment in which an unguarded GPT interface increased assisted mathematics performance and reduced subsequent unassisted exam performance. A hint-giving tutor largely removed that learning penalty (Generative AI without guardrails can harm learning). The constraint is architectural. The same model, given different help behavior, produced opposite results on the measure that matters.

A larger randomized field experiment with more than 6,000 middle-school students on a mastery-based practice platform shows what the ladder looks like in the logs. Students assigned to AI support progressed more slowly and attempted fewer questions, and they answered more accurately. The clearest mechanism was next-attempt correctness after a mistake: fewer attempts were needed to return to a correct answer. That pattern is a productive slowdown, and it is the signature a hint ladder is supposed to leave (Making AI Tutoring Productive).

The same study supplies a warning about your own dashboards. Requiring three correct answers in a row sharply raised platform-defined mastery without producing detectable gains on a delayed test a week later. The strongest delayed-test evidence appeared only where the AI sat inside the mastery workflow (coefficient 0.085), not where it was available as standalone access. If your success metric is a streak counter, you will ship a system that optimizes the streak.

Interface friction belongs in the same design pass. Unlimited hints behind a visible button turn the whole ladder into a shortcut, and premature hint requests with superficial reading are associated with lower Learning Gains. Replacing `[Hint][Hint][Hint][Show Answer]` with the questions “what have you tried?” and “what part is blocking you?” (choosing a rule, setting up the equation, doing the algebra, understanding the concept) costs one screen and routes the student to the rung they actually need. It also gives you the log data that tells you which rung they habitually skip.

Hand the checkable parts to a checker

Ground generation in instructor-approved material: textbook sections, course notes, worked examples, terminology, approved methods, notation, assignment rules, policies, and curricular resources. Retrieval-augmented generation against that corpus reduces hallucination risk and does not eliminate it, as RAG (Retrieval-Augmented Generation) sets out. Expose citations or provenance in the interface where a student might check a claim, because the citation is what makes the grounding auditable after the fact.

Grounding also does a job that accuracy metrics miss. A course has approved methods, and a tutor that introduces a mathematically valid technique the course does not use has taught the student something they will be marked down for. Retrieval from the course layer is how the tutor stays inside the method set.

For domains with formally checkable answers, add deterministic tools: calculators, symbolic mathematics systems, code execution, knowledge graphs, rule-based validators, and domain-specific solvers. The division of labor is the important part. The LLM handles explanation and dialogue. The symbolic engine verifies algebraic equivalence, derivatives, integrals, equation solutions, critical points and numerical

approximations. A wrong intermediate step that the verifier catches becomes a tutoring moment. A wrong intermediate step that nothing catches becomes a misconception the student carries into the exam.

Require the learner to act on the feedback

Feedback that says “Correct,” “Incorrect,” or “Good job” is a scoring event wearing the interface of teaching. The knowledge base treats Feedback as a provision-uptake loop: feedback supports learning when students understand it and act on it, and the second half is the half that systems usually skip. Build the tutor to name the reasoning step involved, say what needs reconsideration, give one concrete next action, and ask the learner to predict or explain before the feedback is revealed.

The sequence that carries this is learner first, AI second, learner again. The student generates, chooses, justifies, evaluates or reflects; the tutor responds; the student does something with the response. Design the turn structure so this is not optional. A system where the model can produce three paragraphs in response to one question teaches the student to ask and read.

The long-term goal is internalization. Learners should end up running the tutor’s questioning and Problem Solving strategies themselves, which is the Learner Agency argument and the reason the ladder has a top rung where the tutor is silent.

Design for what happens in turn forty

Pedagogical safety is a separate test suite from ordinary chatbot safety, and most teams ship with only the second one. Toxicity and jailbreak resistance tell you nothing about whether the tutor will hand over an answer to a student who asks twice, agree with a wrong method because the student sounded confident, drift out of the course’s method set over a long session, or push a learner into cognitive offloading. Sycophancy is the one that gets through first, because agreement reads as kindness and your preference data rewards it.

Test for answer leakage, misconception reinforcement, excessive agreement, inappropriate difficulty, offloading, biased treatment, loss of learner agency, instructional drift, and overconfidence in incorrect explanations. Run the tests on extended conversations, not single turns, because pedagogical failures accumulate: the first ten turns can be exemplary and the eleventh can undo the session. A tutor should be kind and correct at once, including when the learner insists on a misconception. Pedagogical Safety and AI Tutor Safety and Pedagogical Harms lay out the failure taxonomy.

Put the data architecture in the same design doc

Collect only learner data that is pedagogically necessary, and be able to say why each field exists. Where you keep persistent memory or a learner model, make its purpose visible to the learner, give them appropriate control over it, protect sensitive information, define retention, and route consequential decisions to an instructor or another human checkpoint. A learner model that quietly accumulates a confidence estimate a student never sees is a data protection problem and a pedagogical one.

Audit behavior across language backgrounds, ability levels, cultural contexts, Accessibility needs, and levels of prior knowledge and AI experience. Differential performance on the same objective is a bug with a student attached to it, and it will not appear in your aggregate accuracy number.

One accessibility decision deserves its own line: do not make sophisticated prompting a prerequisite for good instruction. If the tutor teaches well only when a student writes a careful prompt, you have built a system that advantages students who already know how to talk to models. The tutor should help learners formulate productive questions, which is also a Metacognition skill worth having.

Instrument the withdrawal interval

Session metrics will not tell you whether the thing works. Response accuracy, conversation length, student preference, satisfaction, task completion and engagement all rise for systems that teach nothing, because students like help and help is easy to measure. Evaluate unassisted performance, delayed retention, transfer to new problems, misconception correction, learner independence, feedback uptake, and differential effects across learner groups. AI Ed Evaluation has the methods, and The Missing Evaluation Axis makes the case that behavior is the construct.

Two studies sharpen the rule against self-report and short horizons. A pilot with 38 novice programming students found a strong association between generative AI usage and *perceived* learning ($r_s=0.802$, $p<0.001$), while the indicators of autonomous progress without instructor support scored lowest. The authors name the gap an illusion of competence and epistemic debt, and it is precisely the gap a satisfaction metric rewards (Generative AI as an Informal Cognitive Tutor).

More fundamentally, most evaluation stops at the moment assistance ends. Cognitive washout dynamics names the unmeasured post-withdrawal interval and formalizes four outcomes: elastic rebound, partial plateau, latent scaffold, and over-recovery. Its washout curve carries a recovery time constant, a recovery completeness term, and a hysteresis index comparing relearning effort to original effort. Since reversibility determines severity, the framework argues that scheduled unassisted practice should be dosed to the recovery curve rather than debated as a matter of principle. Your evaluation plan needs a withdrawal phase as well as an immediate post-test, and the randomized evidence that brief assistance depresses later unassisted performance is the reason to schedule it early.

Give teachers something to edit

Before deployment, have educators test realistic learner profiles, common misconceptions, edge cases, adversarial prompts, ambiguous responses, and long tutoring conversations. Log the pedagogical failures and feed them back into system prompts, tutoring policies, knowledge sources, Guardrails, learner-model rules and model selection. A fluent response can still be pedagogically wrong, and a teacher is the only reviewer who can see that.

Lee's systematic review of 29 K-12 studies describes what that oversight consists of and where it breaks. Teacher intervention is a repeating four-phase cycle of monitoring, judgment, intervention and orchestration. AI alerts, dashboards and automated scores "do not automatically lead to pedagogical action." The strongest teacher strategy the review finds is pedagogical translation: selecting, revising, supplementing, summarizing or deleting chatbot feedback rather than passing it through.

Two design warnings follow, and both contradict the usual roadmap. More AI information is not better: systems that continuously emit diagnostics overloaded teachers and pulled attention away from their own observation. Prioritize what is worth acting on, make it interpretable, and offer recommendations in a form a

teacher can accept, modify, defer or reject. More teacher support is not better either: delaying intervention so students can work independently is itself expertise. Structural conditions, meaning time to review data, class size, and the ability to physically reach the groups that need help, are part of the intervention rather than background logistics. A dashboard built for a teacher with no free period does not get opened.

Case one: a calculus tutor, where verification is cheap

A first-semester college calculus tutor should raise what students can solve and explain independently after it is removed, not maximize correctly completed problems. Math tutoring is especially vulnerable to over-scaffolding, premature hint use, and incorrect diagnosis of student reasoning, and all three are visible in your logs if you look (Math Education).

Grounding and verification. A six-layer build: course materials and instructor policies, then a retrieval layer, then a problem engine and learner model alongside a symbolic verifier and diagnostic engine, then a pedagogical policy layer, then conversational generation, then the student, then back into the learner model. The verifier is the reason this design is tractable. It decides whether an expression is equivalent, a derivative correct, an integral evaluated, a critical point found, and it does so without asking the model's opinion.

One interaction. For differentiating $f(x) = (x^2 + 1)\sin x$, a conventional chatbot reveals the answer. A learning-oriented tutor reasons internally that the student differentiated both components but multiplied the results, a possible product-rule-as-$f'g'$ misconception, and asks a diagnostic question first: what rule applies when two functions are multiplied? Then the student writes the product rule symbolically, sets up u and v, and only after that does the tutor verify the final expression. Notice how much of the tutoring happened before any model prose reached the student.

Multiple representations. Connect symbolic procedures to the formula, the graph, the table, a verbal interpretation, and a physical rate-of-change context. Procedural fluency and conceptual understanding look identical on a correct answer sheet and diverge on the transfer problem.

The dashboard. Expose aggregated evidence in place of opaque judgments: "product rule, 62% demonstrated mastery; common patterns, 18% omit one term, 11% multiply derivatives." Individual diagnoses go out as hypotheses with their supporting evidence, which is also what makes them reviewable by a teacher (explainability matters more to the teacher than to the student here).

The evaluation plan. Performance with the tutor, performance on comparable problems without it, delayed retention, transfer to unfamiliar problems, quality of conceptual explanation, misconception correction, appropriate against premature help seeking, answer leakage, diagnostic false-positive and false-negative rates, and differential outcomes. The comparison that decides the project is assisted against later unassisted. A student who moves from 60% to 95% with the tutor and stays at 60% alone has not been tutored.

Case two: a writing coach, where the stage decides the permission

Writing has no single correct answer, so verification is judgment and the design work moves to staging. The knowledge base frames writing as a cognitive, social and rhetorical process, which means an AI writing system can support learning and can also eliminate exactly the thinking the assignment existed to develop (Writing, Coach not crutch: Evidence that AI can improve writing skill despite reducing effort).

A capability model. Track argument (thesis specificity, claim-evidence alignment, counterargument), organization (paragraph focus, logical progression, transitions), evidence (source relevance, integration, interpretation), revision (global and sentence-level revision, feedback evaluation) and style (clarity, grammar, voice). Each becomes a separate signal in the learner model, which is what makes targeted feedback possible at all.

Ground the coach in the assignment. Retrieve the instructions, the instructor's rubric, course readings, citation requirements, genre conventions, instructor examples, and the AI-use policy, so feedback can say "your instructor's rubric asks you to connect every major claim to evidence from at least two course readings" instead of inventing generic expectations. Generic advice is the default failure of an ungrounded writing tool, and students can tell within two sessions.

Set permissions per stage. AI involvement at different stages affects perceived ownership differently. Planning support reduces ownership less than drafting support, and AI-generated drafting produces the largest decrease (From Planning to Revision). That finding converts directly into a permission table. At planning, the coach asks questions, compares positions, challenges assumptions and critiques outlines, and does not generate the argument. At drafting, the learner produces prose first and the coach develops rather than takes over. At revision, the coach diagnoses and stops there: unclear claims, missing evidence, evidence that does not support the claim, organizational problems, the draft against the rubric. At editing, after revision, it handles grammar, punctuation, concision and citation formatting.

A worked interaction. For an essay on requiring online courses, a generic system rewrites the student's paragraph into polished prose and does the intellectual work. A coach says what is working, names the main issue (the paragraph gives reasons but never explains why they justify a university-wide mandate), poses a revision question, and asks the student to finish a sentence in their own words. The argument stays where it belongs.

Prioritized feedback. One strength to preserve, one high-impact issue, one question that requires writer judgment, one concrete revision goal. Not forty comments. A student who receives forty comments triages them by length, and the triage has nothing to do with what matters.

Make the student judge the feedback. Feedback literacy is a learning objective in its own right. Ask periodically whether the learner agrees with a suggestion and why, and let them reject it. The output is evaluative judgment rather than compliance, and it is also the only defense against a coach that is confidently wrong.

Preserve voice. Distinguish errors, clarity problems, rhetorical choices and style preferences, and leave the last two alone. A coach that "corrects" rhetorical choices homogenizes writing toward whatever style the model prefers, and it does the most damage to multilingual writers and non-standard rhetorical traditions (AI feedback quality is the general version of this problem).

Learn from the revisions. Store the revision history rather than only final essays. A repeated "evidence introduced but not interpreted" pattern that improves across three essays is the most useful signal a writing system can have, and it is free.

Evaluation. Quality of AI-assisted and later unassisted writing, ability to find weaknesses in unfamiliar writing, revision quality, feedback uptake, ability to explain revisions, ownership, dependence on AI prose, preservation of voice, bias across dialects and multilingual writers, alignment with instructor judgment, and

delayed transfer. The design that answers it has three arms: writing independently, AI generating the text, and a coach. All three groups then write a new essay without AI. If the AI-generated group wins in practice and loses without it, the system improved performance rather than learning. Class-level patterns from the dashboard (41% need support on claim-evidence connection) are a formative assessment signal for the instructor.

Comparing the two builds

Design question	Calculus tutor	Writing coach
Primary learning object	Mathematical concepts and problem solving	Argumentation and writing process
Verification	Often objectively checkable	Usually requires contextual judgment
Deterministic tools	Symbolic math engine, calculator	Grammar, citation, rubric checks
Main AI role	Diagnose and scaffold reasoning	Diagnose and scaffold revision
Major risk	Giving away the solution	Writing the text for the learner
Learner action that matters	Solve and explain	Draft, evaluate, and revise
Learner model	Concepts, procedures, misconceptions	Argument, evidence, organization, revision
Key guardrail	Attempt before solution	Student prose before AI rewriting
Transfer test	New no-AI calculus problems	New no-AI writing task
Success criterion	Independent mathematical reasoning	Independent writing and evaluative judgment

Both systems use the same set of AI technologies and embody different pedagogical policies, because the disciplines require different kinds of thinking. The rule that generalizes is to identify the cognitive activity that produces the learning and design the AI to support that activity without performing it. That rule outranks any particular model, prompt, agent framework or interface.

What development teams get wrong

The pedagogy lives in the system prompt, so a careful prompt is a pedagogical design. A prompt is one layer of a policy that also includes which evidence you collect, which rung the interface offers, what the verifier checks, and what the dashboard shows. A well-written prompt on top of a learner model that stores nothing will produce a fluent tutor with no memory of the student, and the ladder will restart every session.

A better model will fix the diagnosis. The benchmarking result above found LLM tutors recognizing correct reasoning while rejecting valid alternatives and accepting incorrect ones, which is a pattern of error that scale does not obviously repair. Structured diagnosis exists because the model’s judgment is the part you cannot audit.

Satisfaction and completion prove the design works. They prove students got help. The pilot with 38 programming students found perceived learning strongly associated with usage while autonomous progress

scored lowest, and the mastery study found a streak requirement raising platform mastery with no delayed-test gain. Build the withdrawal measure into the pilot or you will learn the wrong lesson efficiently.

Retrieval makes the answers trustworthy. It reduces hallucination risk and leaves the rest of the failure surface intact: a retrieved passage can be misread, a valid technique can be wrong for the course, and the model can still be confidently wrong about a step it derived itself. Retrieval is a floor.

Passing the safety suite means it is safe for students. Ordinary safety testing covers toxicity and jailbreaks. The pedagogical failures that matter here, answer leakage and sycophancy and drift, are invisible to it, and they accumulate over a conversation rather than appearing in a single turn.

Engagement is the goal. Conversation length and session count are the cheapest metrics to instrument, which is why they get promoted to goals. The Scaffolding argument says the ideal session gets shorter as the student improves, so a rise in engagement is as likely to be a symptom.

What will come back at you

“We ship in six weeks and this is a quarter of work.” Most of the architecture is cheap. An attempt gate, a configured ladder, retrieval over notes you already have, and a log schema with a withdrawal field are days of work. The expensive items (learner model, verifier, dashboard) can start behind a feature flag for one course, and the pilot is more informative with the cheap parts done.

“Students love it and completion is up.” Both facts are consistent with a system that answers questions well and teaches nothing. The 6,000-student study found slower progress and fewer attempted questions alongside better accuracy, so a drop in completion is not automatically bad news either. Report unassisted performance next to the engagement numbers and let the two disagree in public.

“We cannot run a randomized trial.” You can run a within-student comparison without one: the same objective, assisted during the unit, tested unassisted two weeks later, with the assisted score reported beside it. That design answers the product question and needs no control arm. What it cannot tell you is the counterfactual for students who never used the tutor.

“The model is a vendor API, so the help behavior is out of our hands.” The rungs live in your orchestration layer, and the guardrail experiment’s result came from changing what the tutor was allowed to say, not from swapping models. Expect the vendor’s post-training to pull toward answering promptly, because helpfulness is what it was tuned for, and put the restraint in your own code.

“Teachers will not use another dashboard.” They will not use one that emits continuous diagnostics, which the K-12 review found pulled attention away from their own observation. Give them a small number of interpretable signals, a way to accept or reject each recommendation, and time in the week to look at them.

“We do not have discipline experts on staff.” Then the tutor will teach generic method and the course’s notation will drift within a term. A subject expert for two days at design time, writing the misconception list and the approved-method list, is the cheapest line item in the project and the one teams cut first.

What to do this week

1. Write the unaided-performance sentence for the pilot and put it in the spec, above the feature list.

2. Add an attempt gate and log it. Record whether the student attempted before the first hint, and which rung they reached.

3. Replace the hint button with the blocking-point question, and log the answer as a category.

4. Schedule one unassisted check two weeks after the unit and put it on the calendar with an owner.

5. Book two days with a subject teacher to write the misconception list and the approved-method list.

Where to go next

What Are Best Practices and Tips for Designing Effective Educational AI Software? covers the software-level rules a tutor has to satisfy, and How Should AI Be Designed Into the Learning Experience? covers where the tutor sits in a course sequence. What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? and How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? handle whether the thing works. If your problem is that the model answers too readily, How Can We Make AI Better at Supporting Learning in Our Own Subject? and How Do We Train an AI Tutor to Guide Students Rather Than Answer Them? work through the training side of the same question.

Connected FAQs

- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- How Can We Make AI Better at Supporting Learning in Our Own Subject?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- What Are Best Practices and Tips for Designing Effective Educational AI Software?

What Are Best Practices and Tips for Designing Effective Educational AI Software?

Your team has a working prototype tutor and a district demo in three weeks. Or a partner school has asked you to put a chat interface on top of its course reader, and someone says it is a two-week job. Or a procurement reviewer has sent the safety section back with one line: what exactly did you test?

The answer is narrower than most product specs assume. Educational AI works as a bounded expert under human supervision: capability confined to a defined domain, grounded in instructor-approved content rather than model memory, co-designed with the teachers and learners who use it, evaluated on sustained multi-turn interaction. That last clause is the one most teams skip. Pedagogical harm appeared in every model tested in the benchmark below, and failure rates rose from 17.7% in single-turn interactions to 77.8% in multi-turn conversations.

The short version

1. Write down what the system decides and what a teacher decides. That boundary becomes the architecture.

2. Evaluate multi-turn, discipline-aware interaction against real curriculum, not single prompts against a general safety rubric.

3. Ground responses in approved content, and keep the verifying component separate from the conversational one.

4. Treat every student submission as untrusted input, including when the system is grading it.

5. Build the attempt gate, the escalation path and the teacher override before the pilot.

6. Put accessibility and disaggregated equity testing in the spec rather than the backlog.

Decide what the system is allowed to be

Reichert and colleagues' participatory design study with six secondary teachers corrects the assumption that educational AI should be an autonomous agent. Asked to prototype classroom chatbots on paper, every teacher described a bounded expert along two dimensions. Authority boundaries kept teachers in control, because responsibility for student learning and safety cannot be delegated. Expertise boundaries reflected the AI's lack of contextual knowledge about individual students, classroom dynamics and institutional norms.

The architecture they sketched had four components (content scoping, content presentation, student adaptation, teacher oversight) on three protective layers: domain boundaries that restrict scope, content filtering that enables safe personalization, and teacher override for ambiguous cases. Delegation was selective. Mapped onto Gagné's nine events of instruction, teachers welcomed AI for presenting content, supplying practice problems and offering formative Feedback, and refused it for setting objectives or conducting summative Assessment.

Two defaults belong in the same spec: align the system to explicit learning goals, and tune it toward kind-but-correct responses rather than agreement with whoever is typing. A tutor that flatters a wrong answer has taught the student that the answer was right.

One detail is cheap now and expensive later: these teachers wanted behavioral transparency, visible limits and uncertainty cues, more than explanations of the model's reasoning. All six asked for complete conversation logging, real-time alerts and override capability, framed as professional responsibility rather than distrust. Design for that in the first sprint, because retrofitting logging into a tutor built to feel invisible is a rewrite.

Test it in conversation, not in one turn

The Pedagogical Safety synthesis makes the case that conventional safety testing is insufficient for education. A system can avoid toxic content and still cause harm by over-disclosing answers, reinforcing Misconceptions about AI, suppressing reflection, promoting dependence, or drifting from instructional goals.

The SafeTutors Benchmark puts numbers on that. Across every model tested, from 3.8B open-weight models to GPT-5-mini, pedagogical harm was universal, scale did not reliably improve safety, and failure rates escalated from 17.7% in single-turn interactions to 77.8% in multi-turn conversations. Violation patterns varied by subject. Its 11-dimension, 48-sub-risk taxonomy covers cognitive, epistemic, metacognitive, motivational-affective, developmental and equity, and instructional-alignment categories, and it works as a design checklist as well as a test suite.

Read the escalation figure as a statement about your test plan. A tutor that passes a thousand single-turn probes can fail four conversations in five once a student pushes back or asks a third time. Build the multi-turn harness before the demo.

Ground the content and separate the verifier

Grounding is an architectural decision. EduGuard, a safe retrieval-augmented tutor for introductory programming, pairs instructor-approved course retrieval with an architecturally separate claim verifier, explicit over-reliance control, and a 600-query instructor-authored benchmark spanning misconceptions, debugging, code-mixed queries and adversarial direct-answer prompts. It improved on GPT-4o-mini and Llama Socratic tutor baselines.

The transferable part is the separation: the components that verify do not converse, and the benchmark includes prompts written to extract answers rather than to check politeness. Hallucination risk covers the failure mode approved retrieval is meant to bound.

Treat student work as untrusted input

The threat model most design advice omits sits inside the artifact being assessed. Humble's (2026) adversarial red-team evaluation tested whether students could manipulate an Large Language Models (LLMs)-based grader through prompt injection in their submissions, and the manipulation worked: injections that instruct, reframe or role-play the grader shift the score without changing the work.

Keep the rubric and instructions outside the student-controlled context window, strip or flag instruction-like content, never let a submission set its own criteria, and keep a human decision on any consequential grade. A grader that reads its instructions from the text it judges has handed the rubric to the candidate.

Scaffold the work instead of completing it

A system that answers ends the thinking it was bought to support. Two pieces belong in the ticket: an attempt gate, so no output appears before the student commits something, and a human escalation path with a named destination, which for a classroom product means the teacher, in a form a teacher can act on. Scaffolding and the Socratic pattern are the product versions of what a lesson plan does by hand; What Are Best Practices for Developing an Effective AI Tutor? covers diagnosis, hint ladders and feedback in detail.

Put accessibility and equity in the spec

Accessibility requirements are concrete enough for a sprint: keyboard operability, screen-reader compatibility, captions and transcripts, appropriate contrast, usable text alternatives, and compatibility with assistive technologies. AI-generated accessibility features still need quality checking. See Accessibility.

Equity testing should examine the whole pipeline and disaggregate behavior across language, disability, culture and other relevant learner characteristics rather than relying on aggregate accuracy. A system that scores well on average and poorly for one group has shipped the failure to that group. See Bias Mitigation and Equity.

Design with the people who will use it

Ko and Hughes applied value-sensitive design to an intelligent tutoring system with community college students and instructors, a group historically left out of learning-platform design. They found value tensions to manage rather than solve: transparency versus interpretability, Privacy versus instructional insight, and student agency versus system-guided Scaffolding. Students preferred collaborative, humanized explanations to raw model transparency, and the prototype encoded 16 value-aligned features across Explainable AI, human-in-the-loop and privacy controls.

Wang, Liu and Islam's review of 28 empirical studies adds a vocabulary for choosing tools. Generative AI is used mainly for lesson planning, prompt generation and creative ideation, with AI acting as assistant or content generator far more often than as co-designer, and four affordances, efficiency, responsiveness, Creativity and equity, that teachers can use to judge which tool fits which design problem.

Both studies treat design as human-in-the-loop collaboration and as usability research rather than outreach. Both found that stakeholders surfaced requirements no accuracy benchmark would capture, which is the practical argument for paying for the sessions: the requirements you would otherwise meet in the pilot.

What design teams get wrong

Safety means content moderation. Harm in an educational product often arrives as a helpful answer at the wrong moment. SafeTutors found pedagogical harm in every model tested and failure rising to 77.8% across a conversation, which is not a category content filters are built to see.

A bigger model will fix the pedagogy. Scale did not reliably improve safety across the range from 3.8B open-weight models to GPT-5-mini.

A good retrieval index means the content is handled. EduGuard pairs retrieval with a separate verifier and tests adversarial direct-answer prompts, because grounded retrieval still leaves a path to over-disclosure.

The teacher is the fallback. All six teachers in the design study asked for logging, alerts and override as a condition of professional responsibility. A support ticket is not an override.

Enjoyment is a substitute for fit. In a 405-student survey of design graduate students (Chu & Liu (2026)), task–technology fit carried its own path into attitude ($\beta = 0.224$) beside perceived usefulness, and the characteristics of the task drove fit more than the characteristics of the tool ($\beta = 0.322$ versus 0.266). Perceived enjoyment raised ease of use and did nothing for usefulness ($\beta = -0.033$, $p = 0.483$). Delight is worth building, but it does not stand in for matching the functions to the steps of the assignment.

Accessibility is a later ticket. It sits in the spec or it becomes a rewrite, and generated alt text and captions still need a human check.

What will come back at you

“We cannot build an evaluation harness before launch.” Build a small one. The first claim you need is what happens across five turns. Take 40 real curriculum questions, run each as a five-turn conversation with a student who resists the hint, and score against the 11 dimensions. That is a defensible safety section and it fits in a sprint.

“Teachers want to edit prompts, and we cannot guarantee what they write.” Then narrow the surface they edit. The system prompt stays yours; objectives, approved content, the hint ladder and the escalation contact are theirs. The bounded-expert architecture exists so configuration stays inside a scope you can test.

“Our benchmark scores are high.” Accuracy on single-turn answers does not predict behavior across a conversation, and the benchmark that measures the second thing found 77.8% failure in multi-turn settings across every model it tested. Report both numbers, or the first will be read as the second.

“Full logging is a privacy problem.” It is, which calls for purpose limitation rather than absence. Log what a teacher needs to act on, minimize the rest, restrict access, and say in the product what is kept and for how long.

What to do this week

1. Write the authority boundary on one page: what the system decides, what the teacher decides, and which you would defend in a procurement review.

2. Turn the 11-dimension taxonomy into a test plan and run it multi-turn on 40 real questions from one course.

3. Separate the verifier from the generator in the design doc, even if the first build runs them in one process.

4. Add the attempt gate, the escalation destination and the teacher override to the queue, with names attached.

5. Put the accessibility list and one disaggregation requirement in this release’s acceptance criteria.

Where to go next

What Are Best Practices for Developing an Effective AI Tutor? covers the build, and How Should AI Be Designed Into the Learning Experience? covers the pedagogical defaults around it. For whether the thing works once deployed, see How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?; for the safety concepts behind the test plan, Pedagogical Safety and Hallucination Risk; for the procurement context, Legal Issues and Risks. - model: deepseek/deepseek-v4.1-flash-1017 role: drafting date: “2026-11-04” agent: hermes-agent

Connected FAQs

- What Are Best Practices for Developing an Effective AI Tutor?
- How Should AI Be Designed Into the Learning Experience?
- How Can We Make AI Better at Supporting Learning in Our Own Subject?

How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?

Your tutor gives the answer away. The demo did not show it, because the question was easy and the student was cooperative. The pilot logs do: a student asks twice, the model restates the method, then solves it. A teacher watches a session and says it is a chatbot with a friendly voice. Now you are deciding whether to spend a quarter of engineering time on post-training or ship with a better system prompt.

The short answer: prompting does not remove the pull toward answering, because helpfulness is what the base model was trained to produce. If guiding behavior is the product, it has to be trained, and the variable that decides the outcome is the **reward**. Write the reward against a benchmark, put step-level reasoning in the training data, and judge the training on the next pedagogical move the model chooses.

The short version

1. Test whether the prompt survives pressure before you conclude that prompting is enough. Agreement with a wrong student is the failure mode to look for.

2. Write the reward as a specification of the behavior you want, with hard negatives excluded, then check what it actually optimized.

3. Train on step-level traces. A corpus of question-and-correct-answer pairs cannot teach a model to see where a student went wrong.

4. Prefer reinforcement learning over imitation when judgment matters, and keep the intermediate stage scores.

5. Make the reward dense enough to fire on most responses, and run the evaluation on whole conversations.

Find out whether the prompt survives pressure

Prompting and general alignment training leave a pull toward agreement. Contextual sycophancy persists after both, with learners' errors still propagating into the AI's advice.

EduFrameTrap adds the detail that matters for a product decision. Models that withstand context-switch attacks still capitulate under authority or social-affective pressure and withhold corrective feedback, which is why its authors argue that "kind-but-correct" behavior should be an **explicit training requirement** rather than a preference (Sycophancy is an educational safety risk: Why LLM tutors need sycophancy benchmarks).

If your tutor's failure is agreeing with a wrong answer, prompting it not to agree is a mitigation. Run the pressure test first, record where it breaks, and use that transcript as the argument for the training budget.

Write the reward before you collect the data

A reward is a compressed specification of what you want, and models optimize whatever you actually wrote. That makes reward design the decision that sets the ceiling on everything downstream.

EduQwen's reward model **prioritized guiding responses over direct answers**, with hard-negative mining to exclude questions the base model already solved, and rollouts extended from 5 to 8 steps so that multi-step pedagogical decisions were captured. Its three-stage pipeline, initial RL then synthetic SFT then a final RL round, reached **96.52%** on the CDPK benchmark against Gemini-3 Pro's **90.55%** (Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning).

Two things follow. Expect the reward to be gamed, because it specifies less than you meant, so write it against a benchmark rather than an intuition. And keep the intermediate numbers: the first RL stage alone reached 94.13%, SFT on 40,000 self-generated responses took it to 96.20%, and the final round added the last fraction. Most of the gain arrived early, which is useful when someone asks whether the last stage was worth its cost.

Make the reward fire often enough to teach

An exact-match reward is too sparse when the thing you care about has several dimensions. SWIM's writing simulator shows the progression cleanly: rubric-grounded prompting reached a best average trait QWK of **0.577** with Claude Sonnet and **0.422** with GPT-5.4, near zero for an open 7B model; supervised fine-tuning reached **0.474 ± 0.023** for that 7B model; GRPO with a dense, trait-normalized accuracy reward reached **0.618 ± 0.005** across every trait and prompt (SWIM: Student Writing Simulation via Proficiency-Conditioned Generation).

The reward design produced that gap. A dense trait-normalized signal beats exact match in a multi-trait setting, and if your reward fires only on a perfect response, most of your training signal is silence.

Put the reasoning in the examples

The most actionable finding in this area concerns what the training data has to contain. Instruction-tuned models learned algebra Misconceptions about AI only when trained on **step-level solution traces**. Trained on final answers alone, accuracy stayed **below 30% at every data size** (Misconception Acquisition Dynamics in Large Language Models).

Two details from that study matter for anyone building either side of a tutor. The student role overgeneralized the learned error until correct examples were mixed in at ratios as low as **one in four**. The tutor role showed no such cost, holding correct accuracy from **93% to 98%** across ten jointly trained misconceptions.

A dataset of question-and-correct-answer pairs cannot teach a model to notice where a student went wrong. If you are training a tutor to diagnose, the examples need the reasoning.

Pick the training signal that matches the judgment

Supervised fine-tuning teaches the model to imitate your demonstrations. That is enough for format and not enough for judgment. LearnLM states the finding explicitly: **RL is substantially more effective than SFT alone for following nuanced pedagogical instructions in long conversations** (LearnLM: Improving Gemini for learning).

Its instruction-conditioned framing lets developers and teachers specify tutor behavior without committing to one definition of pedagogy, and co-training mixes it into Gemini's post-training stages. Experts preferred it over GPT-4o (**+31%**), Claude 3.5 Sonnet (**+11%**) and base Gemini 1.5 Pro (**+13%**).

The practical reading: if your failure is a wrong tone or a missing format, SFT is the cheap route. If your failure is choosing the wrong pedagogical move in turn twelve, the signal has to reward the choice.

Label each example with the behavior it teaches

If the supervision has to contain reasoning, the labeling scheme is a curriculum decision. A study of supervision labels found that assigning every training example one target behavior, among subject competence, curriculum grounding, diagnostic reasoning, and Scaffolding, raised scores at every model size tested, with the largest gains in scaffolding and in using a learner's history. Knowledge-state diagnosis remained the weakest behavior at **54.04%** (OmniEdu: Open Foundation Models for Learning and Teaching). Diagnosis is the hardest item on that list, so budget for it.

Data selection is a training problem of its own. Edu-QuRating adapts preference distillation to educational data curation, replacing a single "is this educational?" score with **20 rubric dimensions** covering factual accuracy, pedagogical structure and level suitability (Edu-QuRating: Multi-Dimensional Educational Data Curation with Distilled Pairwise Judgements). If you are assembling a corpus from web text, that filter decides what your model learns to sound like.

Choose the data bet you can afford

Two opposite bets define the space, and which one you take depends on what you already have.

When your data is scarce, instruction-conditioned post-training carries the behavior. LearnLM uses system-level instructions that let teachers and developers specify tutor behavior and relies on co-training rather than a large corpus of tutoring transcripts.

When you have authentic interaction data, fine-tuning on it wins. TeachLM bets that prompt engineering is a stopgap and the scarce ingredient is real learner-tutor interaction. Trained on **100,000 hours** of one-on-one sessions under rigorous anonymization, it doubles student talk time, improves questioning style, and increases dialogue turns by **50%** (TeachLM: Post-training LLMs for education using authentic learning data).

A cheaper route is distillation. Pedagogy-R1, at 1.5B and 7B, was instruction-tuned on pedagogically filtered outputs distilled from a QwQ-32B teacher, paired with Chain-of-Pedagogy prompting (Pedagogy-R1: Pedagogical Large Reasoning Model and Well-balanced Educational Benchmark).

Train the decision the student meets next

Post-training need not shape only what the model says. TACT post-trained a tutor on a 13-strategy taxonomy plus a two-axis student-move taxonomy and gained **20.30 points** over its Qwen3.5-4B backbone, with a diagnostic benchmark that **withholds the learner-state labels** available during training so the model has to infer state from the dialogue (TACT: Taxonomy-Aligned Post-Training for Pedagogically Adaptive English Tutoring).

The same logic runs through special education alignment (Special-R1: Reinforcement Learning for Special Education — Aligning LLM Tutors to Diverse Learners through Disability-Adaptive Training) and through heuristic-RL work that aligns models as Socratic guides rather than answerers (Beyond Direct Answering: Aligning Educational LLMs as Socratic Guides via Heuristic Reinforcement Learning). One platform goes further and trains the policy rather than the prose: a reinforcement-learning agent chooses the next practice problem, so what the learner does next is decided by the trained model (Effective Personalized AI Tutors via LLM-Guided Reinforcement Learning).

That last case is the test of whether you have designed a tutor or a text generator. If the model's only output is prose, the pedagogy lives in your orchestration code. If the model chooses the next task, the pedagogy is in the weights.

Test it at conversation length

Training does not make a model safe over a long conversation. SafeTutors shows that even specialized pedagogical models degrade across sustained dialogue and can commit answer over-disclosure harms (SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems). Pedagogical safety has to be measured at conversation length, including the turns where the student is wrong, persistent, or pushing.

What training teams get wrong

More prompting will eventually hold. Sycophancy persists after prompting and alignment, and authority pressure reopens the behavior that a context-switch test closed. The transcript from your own pressure test is the evidence for this in your product.

The leaderboard number is the result. 96.52% on CDPK describes performance on one benchmark's pedagogy tasks. Your students meet your curriculum, your notation, and a student who has been stuck for twenty minutes.

More data is the answer when the traces are thin. Final answers at any data size kept misconception accuracy below 30%. What changed the result was step-level reasoning in the examples; corpus size never moved it.

The student role is the hard part, so train it last. The student overgeneralized learned errors until correct examples appeared at one in four. The tutor role held 93% to 98% under the same conditions, which suggests the tutor is the easier half to train and the simulator is the one to check.

The final checkpoint is the result. The first RL stage reached 94.13% and SFT took it to 96.20%, so most of the movement happened before the last round. Keep the stage scores; they say which stage earned the gain and which one you could cut next time.

What will come back at you

"We cannot afford RL." Then start with the parts that cost nothing: step-level traces in your data, one target-behavior label per example, and a reward you have written down in words before you write it in code. The SWIM comparison shows SFT alone moving a 7B model to 0.474, which is a real gain and still short of 0.618.

“Our vendor’s model already refuses to give answers.” Vendor post-training optimizes helpfulness, and refusal to answer is not what helpfulness scores reward. Test the behavior in your own conversations; the answer is in the transcript, not the model card.

“Distillation gets us most of the way.” Pedagogy-R1 is a 1.5B and 7B distillation and it is a reasonable starting point. What it inherits is the teacher’s pedagogy, including whatever that teacher got wrong, and you will need a benchmark to see which parts transferred.

“Long-conversation testing is too expensive to run often.” Run it once per model change, with a fixed script and a fixed set of adversarial turns, and diff the transcripts. The cost is in writing the script the first time.

“The teacher said it feels like a chatbot.” That is a report about the conversation’s shape, and the conversation’s shape is a policy. Count how many turns pass before the model hands over a step.

What to do this week

1. Run the pressure test: wrong answer, student insists, student cites authority, student asks for the answer. Save the transcript.

2. Write your reward as three sentences of English, then check whether your code measures those three things.

3. Audit a sample of your training examples for step-level reasoning. Report the share that contain a wrong step and a diagnosis of it.

4. Add one target-behavior label per example, starting with scaffolding, and log the distribution.

5. Put the intermediate stage scores in the model card alongside the final one.

Where to go next

How can we make AI better at supporting learning in our own subject? asks whether training is the right lever at all, and What Are Best Practices for Developing an Effective AI Tutor? covers the interaction-design counterpart, which gets the same guiding behavior out of scaffolding and hint ladders rather than gradients. How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? covers measuring whether the behavior actually changed, and LLM Training and Fine-Tuning is the concept page behind all of it.

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- What Are Best Practices for Developing an Effective AI Tutor?
- How Can AI Agents Support Students and Instructors?

How Do We Make a Simulated Student Behave Like a Real Learner?

You have a demo on Thursday. The simulated student in it misses a fractions problem, receives one hint, and then produces the right answer with the right explanation. Someone in the room asks why a struggling learner would do that, and you do not have an answer.

Before the next demo, you need this much straight: prompting a model to play a student produces the sound of a learner. What produces the behavior is a constraint on what the simulator knows, structure in the turns, and validation against records from real learners. Only 3% of studies that simulate learners validate their simulator after use, so nobody will check this for you.

The short version

1. Write down which learners you are not simulating, and put that sentence where your users will read it.

2. Test the belief state, not the prose. Ask what the simulator says after a correction.

3. Constrain knowledge deliberately: specify the epistemic state, or remove the knowledge.

4. Script the interaction turn by turn. A better persona prompt does not fix drift.

5. Score behavioral fidelity and guidance responsiveness separately, against real learner records.

Decide what question the simulator is answering

Three jobs get collapsed under “simulated student,” and they need different machinery. Rehearsing a teacher or a tutor needs a partner that behaves plausibly under pressure. Auditing how an AI treats different learner profiles needs coverage of the profiles you care about. Predicting outcomes for a course needs a distribution of learners rather than one convincing individual. A simulator built for the first job will disappoint you on the third, and the evidence below keeps separating them.

Name the learners you are not covering

The most useful finding for anyone about to trust a simulator is about coverage. Twelve teachers who tutored Large Language Models (LLMs) students reported overly complex language, missing emotion, unnatural attentiveness, and unexplained knowledge jumps, and the simulations represented only one of four real student behavior quadrants (Martynova et al., 2026). The quadrant they covered was the easiest one to simulate.

That matters because almost nobody checks. Only 3% of studies simulating learners validate their simulator after use. If you build one and skip validation, you are in the overwhelming majority, and you are also the reason that statistic stays quotable.

Constrain what the simulator knows

A capable model cannot easily pretend to be a partial knower. Research calls this the **competence paradox**: broadly capable models asked to emulate partially knowledgeable learners produce unrealistic error patterns and learning dynamics.

The drift has a direction, and it points at the learners who most need simulating. Against student ideas drawn from 49 NGSS-aligned science lessons, six models kept most ideas inside the expected knowledge scope and roughly two-thirds at or below the target reading level, then overshot exactly where the learner was youngest. Elementary and middle-school ideas more often exceeded the target grade's knowledge scope and reading level, and the corpus leaned toward broader reasoning, more technical vocabulary, and fewer uncertainty markers ("maybe", "it seems") than the real lesson ideas (Nguyen and Cao, 2026).

Two notes from that study. Model choice is not one-dimensional, since a system that matches lesson ideas closely can still pitch them above grade. And the repair is often instructional: an explicit grade-level re-prompt lifted most models back into range.

Specify the state, or take the knowledge away

If the model knows too much, you can name the state it should be in or subtract the knowledge it should not have.

Condition on an epistemic state. A training-free framework builds each student's cognitive prototype from a Knowledge Graph and scores beam-search candidates against it, reporting a 100% improvement in simulation accuracy (Wu et al., 2025). Its quality rises with the student's cognitive level, so weaker learners remain the harder case, which is unfortunate given that they are usually the point. Modeling cognitive dynamics rather than a static persona goes further: CogEvolution's ICAP-based state updates reached $R^2LC = 0.92$ where static agents reach 0.45, and collapsed to 0.58 without its ICAP module (Zhang et al., 2026).

Remove the knowledge. Suppressing 16 targeted knowledge components in Mistral-7B dropped accuracy from about 0.75 at a 10% forgetting ratio to below 0.5 at 40%, while the base model held near 0.85. The suppressed knowledge proved recoverable through supervised relearning and coach-guided dialogue (Song, Guo & Lin, 2026). This is the closest thing to manufacturing a novice directly, and the recoverability becomes a feature if you want the simulator to learn during a session.

Script the turns, not the persona

Persona stability turns out to be an interaction-design problem rather than a model-choice one. Crossing five LLMs with three prompt designs and four ADHD-intensity personas, scripted task-anchored interactions eliminated observer-rated behavioral drift, by up to 97% against unscripted dialogue. Without explicit persona instructions, baseline student representation skewed toward high ADHD symptoms (Gonnermann-Müller, Haase & Leins, 2026).

If your simulator drifts, look at what you ask it to do turn by turn before you change models or rewrite the description of the student.

Score two things, not one

StudentSim requires two properties to hold together: **behavioral fidelity**, how well the simulator matches a student's own responses, and **guidance responsiveness**, how reliably it updates toward where the tutor's guidance leads. Its benchmark casts public learner corpora (chess, second-language English writing, mathematics) into a per-student protocol on which any simulator is fit and scored on held-out records. Domain-specific state tracking came out weak on responsiveness, and prompt-only LLM role-play came out weak on fidelity (Yang et al., 2026). A simulator can pass one test and fail the other, so report both.

As a proof of concept, a frozen StudentSim used as the reward in a chess-tutor Reinforcement Learning loop produced tutors that experts rated as more accurate, better guided, and more personalized than those trained against a frontier-LLM-simulator reward or with no RL at all. A good simulator can be the training signal as well as the measurement.

Action-level fidelity has its own limit. Student simulators reproduce observable actions without the latent reasoning behind them, and INSIDE fine-tunes models to generate an internal dialogue before each action, reaching the highest alignment between generated reasoning and real code edits at 51.8% on familiar problems and 57.9% on unseen ones, without losing action fidelity (Niousha et al., 2026). If you care why your simulated student did something, matching the action is not enough.

Validate against real learners and report the baseline

Two comparisons show what validation costs.

Benchmarking nine simulation methods against seven reference-based metrics on 382 held-out dialogues from the largest public corpus of real student-tutor mathematics dialogues, prompting trailed fine-tuning on dialogue acts (0.4998 against 0.6840), ROUGE-L (0.1648 against 0.3212), and cosine similarity (0.5460 against 0.7390). The best method tested, preference optimization on an 8B model, beat supervised fine-tuning only marginally and was worse on errors, and a three-tutor human evaluation reproduced that ranking (Scarlatos et al., 2026). The top of this ladder sits close to the middle, so the baseline you report decides how impressive your own number looks.

SWIM is the clearest comparison of prompting, fine-tuning, and reinforcement learning, because it scores each generated essay against a target trait profile rather than judging it impressionistically. Rubric-grounded prompting gave limited control even for strong proprietary models, with a best average trait QWK of 0.577 (Claude Sonnet) and 0.422 (GPT-5.4), and near zero for an open 7B model. Supervised fine-tuning on real score-essay pairs reached 0.474 ± 0.023 for that 7B model. GRPO with an Automated Essay Scoring-derived reward reached 0.618 ± 0.005, with gains holding on two independent scorers the policy never trained against (SWIM: Student Writing Simulation via Proficiency-Conditioned Generation).

Prompting also produced an idealized population rather than a realistic one: mean normalized overall score 0.74 against 0.58 for real students, and a median length of 304 words against 167. The trained models recovered the human score and length distributions without any length supervision. One thing stayed hard: authentic low-proficiency form. Trained models recovered syntax but wrote too few spelling and grammar errors, while prompting simulated weakness through superficial corruption, misspellings sprayed onto otherwise competent prose.

Surface realism is a weak test in both directions. In a blinded study, expert annotators misclassified 164 of 196 (83.7%) LLM-generated Java submissions as human-written, because the errors were functionally indistinguishable from authentic ones, and alignment with real errors then fell as problem difficulty rose (Keramati et al., 2026). Across seven models from 4B to 120B parameters, simulators flipped to the correct answer at near-uniform rates whatever feedback they received, so output similarity says nothing about the belief state behind it. Training against the **Selective Flip Score** lifted faithfulness by up to +0.56 (Do, Sonkar & Sachan, 2026).

Check whether a description would do

Before you build a cohort, check the cheaper option. For evaluating an online learning experience before students engage, predicting dropout and completion and giving design feedback, a single “describing” web agent that walks through the lesson and produces a rich description of the experience outperformed directly simulating a population of students.

The simulated students in that comparison showed far less behavioral range than real learners: across 100 agents on five test lessons they reproduced only about 4% of the paths real students took, while costing substantially more compute. The describe-then-predict pipeline achieved the best dropout-distribution prediction on a massive global CS1 course, with a mean JSD of 0.060 (Wang, Mitchell & Piech, 2025).

The boundary it draws is practical. Simulating a distribution of students may be unnecessary, or counterproductive, when the goal is outcome prediction or design critique. Simulation earns its cost when covering genuine learner variation matters, such as auditing an AI’s treatment of diverse profiles or giving a teacher something to rehearse against.

What builders get wrong about this

Surface realism is the target. An 83.7% misclassification rate for machine-written code and near-uniform answer flipping across seven models both say a human judge reading the output cannot see the property you are claiming. Test the response to a correction instead.

A better persona prompt fixes drift. Scripted task-anchored turns cut observer-rated drift by up to 97% across five models and three prompt designs. The design of the turns did the work.

A stronger base model closes the competence gap. A strong proprietary model scored 0.422 on trait QWK under prompting while a fine-tuned 7B reached 0.474, and the same six-model comparison overshot worst at the youngest grade levels. Model choice trades one fidelity axis against another.

Validation means a colleague read a transcript and thought it sounded right. The Java result shows how far that judgment travels. Validation means held-out records from real learners and a baseline you can name.

Simulating a population is the thorough option. Across 100 agents the simulations covered about 4% of the paths real students took, at substantially higher compute than the describing agent.

What will come back at you

“Teachers could not tell our simulator from a student.” In the blinded Java study, expert annotators misclassified 83.7% of machine submissions as human. That measures the annotators, and it leaves the belief state unexamined.

“Fine-tuning is out of scope for our team.” Then scope the claim to what prompting supports, and say so. Prompting set a ceiling of 0.577 for the strongest model tested and near zero for an open 7B, and it produced an idealized score distribution.

“We have no access to real learner data.” StudentSim’s protocol is built from public learner corpora in chess, second-language writing, and mathematics. Public data limits what you can claim about your own population, and it gives you a baseline, which is the thing most reports omit.

“GRPO beat supervised fine-tuning, so we should train with RL.” It did, at 0.618 against 0.474. Low-proficiency form stayed hard in both cases, with too few spelling and grammar errors, and in a separate benchmark preference optimization beat fine-tuning only marginally and lost on errors. Check which property your use case depends on.

“The weakest learners are a small slice of our users.” They are the hardest case for every method on this page, and the coverage finding says the simulations cluster in the easiest quadrant. If your simulator will be used to draw conclusions about struggling students, that gap belongs in the write-up.

What to do this week

1. Write the coverage sentence: which learners this simulator does not represent. Put it in the README and the demo notes.

2. Add one probe to your test set that corrects the simulator and checks whether it stays wrong.

3. Replace free-form persona chat in one flow with task-anchored turns, and compare drift.

4. Score one existing simulator against held-out real records on both fidelity and responsiveness, and report the two numbers separately.

5. Run the describing-agent check on the question you actually need answered before you fund a cohort.

Where to go next

Simulating Students is the full concept page. How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? covers evaluating the systems you test against a simulator, and How Can We Make AI Better at Supporting Learning in Our Own Subject? covers the training methods behind the fine-tuning results here. How Can We Address Common Misconceptions About AI in Education? takes up whether simulated students can stand in for real learners in research.

Connected FAQs

- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- How Can We Address Common Misconceptions About AI in Education?

- How Can We Make AI Better at Supporting Learning in Our Own Subject?

How Can We Make AI Better at Supporting Learning in Our Own Subject?

The ticket says “fine-tune the model on our course materials.” The budget is approved, a GPU is booked for next month, and a graduate student has been asked to assemble a dataset. Nobody on the call has asked what a plain prompt scores, or what a keyword search scores, on the same questions.

Ask those two questions first. In this knowledge base, the gap between a general model and a course-competent one is mostly a grounding and prompting problem, and the evidence for that ordering is unusually direct: a course-assistant study found retrieval, not the model, was the first-order decision, and a general model with no grounding scored *below* a plain TF-IDF baseline.

Training is real and sometimes necessary. It is the third or fourth thing to try, and the work below is ordered so that you find out which rung you actually need before you spend the quarter’s compute.

The short version

1. Log what a plain prompt scores, and what a trivial lexical method scores, before you change anything. That second number is what keeps you honest.

2. Put retrieval over your own materials in front of the model. It is the largest single gain reported here for the cost, and it is reversible.

3. Engineer the prompt against your rubric and iterate until improvement stops. The plateau is the signal that training might add something.

4. Adapt the weights with LoRA when the target is stable and narrow: a format, a rubric, a reading level, a domain vocabulary.

5. Post-train when the problem is behavior rather than content, and write the reward against a benchmark you expect to be gamed.

6. Build the training set at step level. Answer-only data does not teach a misconception.

Get a baseline you can actually beat

Before changing anything, log what a plain prompt returns. Then log what a trivial method returns.

The course knowledge-base assistant study is worth reading for this alone. A local Large Language Models (LLMs) with no retrieval reached **52.3%** accuracy. A TF-IDF baseline, a lexical method decades old, reached **55.4%**. The model was worse than the classical method.

Skip this step and you cannot tell whether your fine-tune helped. Worse, you can ship a system that a keyword search beats and only find out when a teaching assistant mentions it. Two numbers on a spreadsheet, taken in an afternoon, protect the rest of the budget.

Ground the model in your own materials

Adding retrieval-augmented generation over the course materials, with no fine-tuning at all, lifted that same system from 52.3% to **66.6%**. That gain came from an index, and it comes with a property a training run does not have: when your documents change, you re-index.

Two other results point the same way. A PRISMA review of 23 empirical studies on customizing AI for writing instruction found **prompt engineering dominant (N = 13), ahead of fine-tuning (N = 7)** (Customizing AI for writing pedagogy: a systematic review of pedagogical goals, theoretical principles, and technical design). Where a knowledge base has to stay current, retrieval is the only lever that stays current without re-running a training job.

Retrieval also has a pedagogical form. Grounding a model in your own worked examples and rubrics is how it stays inside the scaffold you designed, answering at the level you set instead of drifting into generic advice. That drift is the most common complaint about off-the-shelf tutors, and it is a retrieval problem more often than a weights problem.

Write the prompt against your rubric, and watch for the plateau

Prompt work is not a preliminary you do while waiting for the GPU. Two results show what it achieves alone:

- **Rubric-guided prompting, iteratively co-refined, raised LLM-human agreement on student design work from 54.75% to 81.25%** (Cronbach's Alpha 0.393 to 0.798), with no fine-tuning at all (From evaluation to emulation: LLMs as agents of iterative pedagogical design).
- A literature-grounded custom prompt elicited target mathematical Misconceptions about AI at **0.98** presence, against **0.40** for a broad prompt (Integrating ChatGPT in Mathematics Teacher Education: AI-Based Simulation Role-Playing to Support Practice-based Teaching).

The practical signal is the **plateau**. In the item-generation study, iterative prompt refinement stopped improving, and fine-tuning GPT-4.1 *on the optimized prompt* then added the remaining gain (How to train your dragon: Evaluating prompting and fine-tuning for GPT-based item generation in L2 listening assessment). A plateau after real prompt work is evidence that training has room to add something. Reaching for training before you hit one is guessing, and guessing costs a month.

Note what the item-generation result implies about sequencing. The fine-tune was built on the optimized prompt, so the prompt work was not wasted when the team eventually trained. The cheap rung is also the specification for the expensive one.

Adapt the weights when the target is stable and narrow

Adaptation pays when you need the model to hold a property reliably: a reading level, an output format, a domain it lacks. The recurring result is that **targeting beats size**.

- Three **8B** models fine-tuned on an expert-designed children's reading curriculum outperformed zero-shot GPT-4o and Llama 3.3 70B on difficulty-related metrics, with negligible safety issues.

The authors frame this as **controllability over scale** (Children's English reading story generation via supervised fine-tuning of compact LLMs with controllable difficulty and safety).

- A **24,795-example** instruction dataset grounded in Indian Knowledge Systems produced a **7B** fine-tune scoring **6.39** on a five-judge external panel, within **0.15** of a strong general reference model at a fraction of the deployment cost. The same base model scored **near zero on domain-specific dimensions** without the fine-tune (IKS-Instruct: A 24,000-Example Multilingual Dataset for Teaching Language Models Indian Knowledge Systems). That gap between competent generally and competent here is the whole case for domain adaptation.
- A single LoRA adapter trained on roughly **3,900** pooled graded examples brought five small open models (4B to 30B) to parity or better with a human grader across two computer-science exams (Where LLM Graders Succeed and Break: Evidence from Two Computer-Science Exams). One adapter, one dataset, several base models: that is the shape of deployment a small team can run.

The word *stable* in the heading carries the weight. Format, rubric, reading level and domain vocabulary are stable targets. Judgment-laden prose has no such target, and that is where adaptation fails, as the next two sections show.

Change the behavior when the answers are the problem

Adaptation teaches a model *what to produce*. Post-training teaches it *how to behave*. For tutoring that distinction is the whole problem: general models are post-trained on human preference for helpfulness, which means answering promptly, and teaching requires withholding the answer.

The strongest educational results in this corpus live here. EduQwen's reward model explicitly prioritized **guiding responses over direct answers**, and its three-stage pipeline reached **96.52%** on the CDPK benchmark against Gemini-3 Pro's **90.55%** (Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning). SWIM's writing simulator moved from rubric-grounded prompting (best QWK **0.577**) to supervised fine-tuning (**0.474 ± 0.023**) to reinforcement learning (**0.618 ± 0.005**) across every trait and prompt (SWIM: Student Writing Simulation via Proficiency-Conditioned Generation).

Read the SWIM numbers carefully, because the middle step went backwards. Supervised fine-tuning on demonstrations made the simulator worse than the prompt it started from, and only the reward signal recovered the loss and then beat the baseline. If your plan stops at supervised fine-tuning, the plan may be a detour.

Supervise at the step level

One finding here is easy to miss and expensive to ignore: **supervision quality beats supervision quantity**. Instruction-tuned models learned algebra misconceptions only when trained on **step-level solution traces**. Trained on final answers alone, accuracy stayed **below 30% at every data size** (Misconception Acquisition Dynamics in Large Language Models).

If your training examples are question-and-correct-answer pairs, you are training the wrong thing, and adding examples will not repair it. What you need is the intermediate work: the wrong turn, the step where

the student went astray, the correction. Collecting that is a data engineering problem with a pedagogical constraint, and it usually means logging sessions rather than scraping answer keys.

Where adaptation quietly fails

This is the part the enthusiasm skips.

Judgment-laden text. In WrAFT, the same project that fine-tuned successfully for *scoring* essays (QWK 0.84) produced truncated and unparseable output when it fine-tuned for *feedback*, while directly prompting Claude 3.7 produced the feedback teachers rated best (WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays). Fine-tuning taught the model to hit a score, and scoring was the only thing it learned.

Transfer between models. Scale is not a reliable predictor of downstream performance under LoRA adaptation, and **identical hyperparameters produced qualitatively different behavior across architectures** (AiAWE: An Open-Source LLM Automated Writing Evaluation System Using LoRA-Adapted Instruction-Tuned Models). A recipe that worked on one model is not a recipe.

Architecture over parameter count. Fine-tuning three open text-to-image models on 1,000 captioned nuclear-engineering images substantially improved Stable Diffusion XL, gave limited gains for SD-v3.5-Medium, and produced **no measurable improvement for Flux.1 at all** (NuclearDiffusion: Text-to-Image Foundation Models for Learning Nuclear Energy Concepts).

The problem was validation. A frontier untrained GPT-4 produced roughly **35%** too-general, incorrect or answer-revealing hints when authoring tutoring feedback, and its own automated quality checks disagreed with human judgment (Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models). That is a filtering problem, and a LoRA will not solve it.

The pattern across all four: adaptation reliably moves a model toward a target you can specify and score. It adds no judgment, and a pipeline that lacks a check will still ship bad output.

Budget the adaptation honestly

For the adaptation rung the bar is lower than most teams assume: **a few hundred to a few thousand examples and a single GPU**. LoRA trains a small number of added parameters and leaves the base weights frozen, so several models can be served from one adapter.

Rank is a trade-off rather than a dial to maximize. Gain per million adapter parameters fell monotonically as rank rose, and course-level alignment was a scale-and-rank decision rather than a free upgrade (LoRA Fine-Tuned Models for Control Systems Course Q&A: A Multidimensional Evaluation of Model Scale and Rank Effects).

Which layers you adapt is also a real choice. Updating **only the last four Transformer layers** of a BERT-based discourse analyzer beat both adapting only the top layer and full-depth fine-tuning (Automatic discourse relation classification and feedback optimization in English teaching based on transformer BERT model). Three configurations, three different results, and the cheapest one won.

The cost that is easy to underestimate is the evaluation, which is larger than the compute bill. See How do we know an educational AI is working correctly, not just scoring well?

Calibrate what you expect

Model and prompt choice together account for only about **15%** of the misalignment between LLMs and student learning gains, and in that study benchmark-weighting and unanimous-voting ensembles made alignment *worse* (Knowledge without Wisdom: Measuring Misalignment between LLMs and Intended Impact). Pretraining data is the dominant lever on how a model behaves, and it is the one lever you cannot pull.

None of that argues against the work above. It argues against expecting a fine-tune to fix a design problem. If the issue is that your tutor answers too readily, training may address it. If the issue is that your learners do not engage with it, training will not, and the 15% figure says the money is better spent elsewhere.

What teams get wrong

Fine-tuning is how you teach a model your course. Retrieval over your own materials took the same system from 52.3% to 66.6% with no training at all, and a prompt refined against a rubric moved agreement from 54.75% to 81.25%. Training teaches behavior and format far more reliably than it teaches content.

A bigger base model removes the need for all of this. An 8B model fine-tuned on a children's reading curriculum beat zero-shot GPT-4o and Llama 3.3 70B on difficulty metrics, and a 7B fine-tune landed within 0.15 of a strong general reference at a fraction of the deployment cost. Size and fit are different axes, and only one of them is for sale by the token.

More data will fix a training set that is built wrong. Answer-only supervision left accuracy below 30% at every data size in the misconception study. Scale does not repair a target that is missing the information the model needs.

A recipe that worked on one model will work on the next. Identical hyperparameters produced qualitatively different behavior across architectures, and the same fine-tuning method improved one image model substantially and did nothing measurable for another. Re-run the recipe on your base model or you are guessing.

Supervised fine-tuning is the safe middle step before reinforcement learning. In SWIM the supervised stage scored 0.474 against 0.577 from the prompt it replaced, and only the reward signal recovered it. The middle step can cost you a month and a regression.

What will come back at you

"The budget is approved for fine-tuning, so let us fine-tune." Spend a week on the baseline and the index first. If retrieval moves the number, the fine-tune is a later decision made with better information, and you will have a stronger case for it or a good reason to return the GPU.

"Our problem is that students do not use it." Training changes what the model produces. The 15% figure describes how much model and prompt choice account for in the misalignment with learning gains, and engagement sits outside it. Instrument where students drop out before you buy compute.

“We cannot send student work to a vendor API.” The strongest LoRA result here came from open models in the 4B to 30B range, and a single adapter served several of them. That deployment shape is available to a team with one GPU and no data processing agreement.

“Prompting is a hack; real work means training.” The review of 23 writing-instruction studies found prompting the dominant approach and fine-tuning behind it, and the largest reported gain on this page came from an index. Both the review and the course-assistant study ordered those rungs by measured gain.

“We tried prompting and it plateaued, so we need training.” That is the correct reading, and it is the one case where the climb is justified. Take the optimized prompt into the fine-tune as the item-generation team did, and expect the gain to be smaller than the prompt work was.

“Our course materials are inconsistent, so retrieval will return junk.” It will, and retrieval inherits the quality of the corpus. Cleaning the corpus is cheaper than training a model to work around it, and the gain from 52.3% to 66.6% was measured over ordinary course materials rather than a curated set.

What to do this week

1. Run a prompt-only baseline and a keyword baseline on 50 real questions from your course, and write both numbers down.

2. Point retrieval at the materials you already have and re-run the same 50, so the gain is measured against your own baseline.

3. Put the rubric into the system prompt and iterate for a week. Stop when two rounds add nothing.

4. Audit your training set for step-level traces. If it is question and answer pairs, the dataset is not ready.

5. Write the single property you need held reliably, and decide whether it is behavior or content. That decision picks the rung.

Where to go next

How do we train an AI tutor to guide students rather than answer them? covers the post-training half in detail. How do we know an educational AI is working correctly? covers how to tell whether any of it worked. What are best practices for developing an effective AI tutor? is the interaction-design side of the same goal, and What are best practices for designing educational AI software? covers the surrounding system. The full concept page is LLM Training and Fine-Tuning.

Connected FAQs

- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- What Are Best Practices for Developing an Effective AI Tutor?
- What Are Best Practices and Tips for Designing Effective Educational AI Software?

How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?

A vendor's evaluation report lands with one number at the top: agreement with human graders, 0.84. Or your pilot ends Friday and the evidence consists of a satisfaction survey plus a benchmark line copied from the model's release notes. In the meeting someone asks whether the system works, and you have a figure that sounds like an answer.

The short answer: the scores you see most often measure resemblance, and resemblance is a weaker claim than "this teaches" or even "this feedback is readable." Decide what each number is allowed to prove, score every output your system produces, and turn accuracy into a rule with a threshold, a person, and a saving attached. A number nobody can act on is not evidence.

The short version

1. Write one sentence naming what you care about, then pick a measure that reads that thing. Word overlap will not tell you whether the reasoning is right.

2. Evaluate each output separately. A strong grading score says nothing about the feedback module beside it.

3. Have a person rate about fifty outputs and compare those ratings with your automatic checker. Where the two disagree, the checker is the thing under test.

4. Replace "accuracy 0.84" with a rule: below this confidence, a human reads the response. Report the threshold, the share of work it saves, and what agreement became.

5. Test safety across whole conversations, and check any simulated student before you trust what it says about your tutor.

Decide what the number is allowed to prove

Two families of number dominate this literature. Both measure how closely your output resembles something else, which is a weaker claim than correctness.

Similarity scores (ROUGE and BLEU) compare the wording of your system's answer with the wording of a reference answer. A model that writes something close to the expected text scores well, even when its reasoning is wrong, or when a student could reach the right answer by a route that teaches nothing.

Agreement scores (QWK, quadratic weighted kappa) measure how closely the model's grades line up with a human's. A model can match the grader on the final mark while being wrong about why, and the why is the part a student learns from.

A student can reach a wrong answer by a wrong route that looks like a right one, and no similarity score notices. If reasoning is the thing you care about, the measure has to read it: a rubric applied by a person, or a check written for that particular step.

The Linear Control Systems course assistant reports this the right way. Its best configuration reached a similarity score of **0.4093** against reference answers, with the improvement measured reliably above zero, and the authors state plainly that the numbers measure wording and format (LoRA Fine-Tuned Models for

Control Systems Course Q&A: A Multidimensional Evaluation of Model Scale and Rank Effects). The score is unimpressive and the paper is still useful, because it says what the score covers.

Score every output separately

In the WrAFT project, a fine-tuned model reached an agreement score of **0.84** with human graders across 360 held-out TOEFL essays. That is a strong result for grading. The same project's model trained to write feedback produced output that was truncated and unparseable, while simply prompting a different model produced feedback teachers preferred (WrAFT: a Modularized Automated Writing Evaluation System for Argumentative Essays).

The knowledge base carries the same failure in a second form: a deployment whose grading module scored well and whose feedback arrived cut off mid-sentence and unreadable. Nothing in the headline number said so.

So list the outputs your system produces, then give each one its own measure and its own pass condition. Grading, feedback text, hint selection, and safety refusals fail in different ways, and a module-level score cannot see past its own module.

Put a person where the model is unsure

A correlation tells you the model is usually right. It does not tell you what to do on the occasions when it is not. The confidence-routing result is the cleanest template in the knowledge base, and it is short enough to copy.

Confidence turned out to be a reliable warning sign: when the model was unsure, it was more likely to be wrong (**$\beta = -0.602$, $p < .001$**). The team sent the least confident **20%** of responses to a human. That single rule raised agreement with human grades from **0.78 to 0.82** and cut manual grading work by roughly **80%** (Know when to trust: Making AI scoring more reliable for educational assessment).

Look at what the report contains: a threshold, a person, and a saving. "Agreement 0.84" contains none of those, which is why it is hard to act on and easy to argue about.

Check your automatic checker against a person

Many teams now use a second model to judge the first. The arrangement is reasonable and the second model is not automatically right.

A study that had a frontier model author hints for an intelligent tutoring system found roughly **35%** of them were too general, incorrect, or gave the answer away, and the model's own automated quality checks disagreed with human judgment about which ones were bad (Generating In-Context, Personalized Feedback for Intelligent Tutors with Large Language Models).

Practical version: take a sample of about fifty outputs, have a person rate them, and compare that with your checker's ratings. Where the two diverge, you have learned something about the checker. Keep the sample and the disagreement table, because it is also the artifact that answers a reviewer who asks how you know.

Measure the quantity itself when the task allows

The cleanest fix is to train the model on the same quantity you intend to measure. A fine-tuned model was trained to reproduce the statistical properties of test questions: how hard each item is, how well it separates stronger from weaker students. It learned those patterns rather than being told them (Multimodal item parameter estimation using simulated response probabilities). Because the target was a property of the assessment itself, the evaluation could be about that property instead of about wording.

Report the progression as well as the endpoint. SWIM's writing simulator published each stage's score side by side: rubric-based prompting **0.577**, fine-tuning **0.474 ± 0.023**, reinforcement learning **0.618 ± 0.005** (SWIM: Student Writing Simulation via Proficiency-Conditioned Generation). A reader can see from that table whether the training did anything. A single final number cannot tell them, and it hides a stage where the fine-tuned model did worse than the prompt.

Compare against something outside your project

Get a baseline first, including a cheap one. The course assistant's model with no grounding scored below a plain keyword search, which is the sort of result that changes the roadmap and costs a day to find.

An outside benchmark then tells you whether your number is any good at all. On the CDPK Pedagogies and Teaching Strategies benchmark, EduQwen reached **96.52%** against Gemini-3 Pro's **90.55%** (Application-Driven Pedagogical Knowledge Optimization of Open-Source LLMs via Reinforcement Learning and Supervised Fine-Tuning). The Pedagogy Benchmark, built from real teacher professional-development exams and covering **97 models**, found accuracy ranging from **28% to 89%** (Lelièvre et al., 2025).

On a task about teaching, models ranged from poor to good, so a benchmark result places your system somewhere inside a wide range.

Test safety over a whole conversation

Most safety testing checks a single exchange. The harms that matter in tutoring accumulate. SafeTutors found that even models built specifically for teaching degrade over a long conversation and can reveal answers they should be withholding (SafeTutors: Benchmarking Pedagogical Safety in AI Tutoring Systems).

Run the check across complete conversations, and write the test turns deliberately: the student who is wrong, the one who keeps pushing, the one who tries to talk the model out of its role. A tutor that holds for ten turns and folds on the eleventh fails the test that matters, and a per-reply suite will score it as clean.

Check the simulated student before you trust it

Generating simulated students instead of recruiting real ones makes evaluation far cheaper. A simulated student is also a measuring instrument, and it can be wrong in the ways instruments are wrong: too cooperative, too fluent, too quick to accept a hint.

The most direct test in the knowledge base benchmarked simulated and prompted students against **382 held-out dialogues** from the largest public collection of real student-tutor mathematics dialogues, using seven

measures covering language, behavior and thinking (Simulated Students in Tutoring Dialogues: Substance or Illusion?). Other work pushes on realism from different angles: INSIDE trains models to both act and think like students, and history-aware profiles condition the simulation on a student's past rather than a fixed persona (Who Am I? History-Aware Profiles for Student Simulation in Tutoring Dialogues).

If your harness is a simulated student, validate the simulator against real transcripts before you let it grade your tutor.

What evaluation teams get wrong

A high agreement score means the system is correct. It means the system grades like the grader you compared against, on the essays you compared on. WrAFT's 0.84 came with feedback that did not parse.

One number can stand for the product. Teams ship a dashboard with "accuracy 0.84" in the corner and no field for the feedback module, the hint policy, or the refusal behavior. The module-level score is the easiest number to compute and the least informative thing to report.

An outside benchmark settles whether the tool works. The Pedagogy Benchmark spread of 28% to 89% says the task family is hard and unevenly served. Your position in that range is a fact about your model. What your students can do afterward is a different fact.

A model judging a model is a cheap substitute for human ratings. It is cheap. The 35% figure and the disagreement about which hints were bad describe what a judge that was never checked will let through.

Simulated students make evaluation free. They make it cheap, and they move the cost into validation. The 382-dialogue comparison exists because the instrument needed calibrating.

What will come back at you

"We do not have annotators for this." Fifty rated outputs is enough to start. Rate them yourself if nobody else is free, and keep the sheet.

"Our benchmark score beats Gemini." It does, on CDPK, on the prompts that benchmark uses. Bring the unassisted measure next to it.

"Our automated judge agrees with our human raters." Then you have one correlation on one sample. Ask which outputs it disagreed on and read those, since that is where the failure lives.

"We cannot run a full evaluation before launch." Run the cheap three: one output scored separately, fifty outputs rated by a person, one conversation-length safety pass. The expensive items can follow the pilot.

"The system is only a demo, so evaluation is premature." A demo is the cheapest place to find out that your number measures wording. Once there is a roadmap attached to it, the same finding costs more to act on.

What to do this week

1. Write the one-sentence claim your evaluation is supposed to support. Put it at the top of the eval doc.

2. List every output the system produces and give each a row, a measure and a pass condition.

3. Pull fifty outputs, rate them yourself, and put your ratings beside the checker's.

4. Compute the confidence distribution and write the routing rule with a number in it, plus the name of the person who reads what falls below.

5. Run one safety conversation where the student is wrong, pushes back twice, and asks for the answer.

Where to go next

How can we make AI better at supporting learning in our own subject? covers the design side of the same problem. How Do We Train an AI Tutor to Guide Students Rather Than Answer Them? handles the training route to a tutoring behavior, and What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? is the instructor-facing version of this question, with What Are Best Practices for Reporting and Interpreting AI in Education Research? as the research-facing one. The methods sit under AI Ed Evaluation and LLM Training and Fine-Tuning.

Connected FAQs

- How Can We Make AI Better at Supporting Learning in Our Own Subject?
- How Do We Train an AI Tutor to Guide Students Rather Than Answer Them?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?

What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?

You ran the pilot in two sections, collected an end-of-unit survey, and have a faculty meeting in three weeks where someone will ask whether it worked. Or a reviewer has asked what your comparison condition was, and the other section did something different. Either way: what would count as evidence here?

Match the method to the claim. A survey tells you whether students liked the activity. Whether they learned needs a performance measure, and whether the AI caused the gain needs a comparison condition.

The short version

1. Write the claim in one sentence, with the outcome named. “Students who used the tutor scored higher on the unassisted exam” is testable.

2. Run a baseline, the intervention, an immediate post-measure, and a later measure taken without AI.

3. Describe the comparison condition as carefully as the treatment, even when it is your existing practice.

4. Measure assisted performance and independent learning separately, and treat any published average as a hypothesis about your class.

Pick the method your question can survive

The Research Methods in AIED page sets out what each option buys. Randomized experiments give the strongest causal inference. Quasi-experimental pre/post or matched-group designs fit intact classes and support weaker claims. Qualitative interviews, focus groups, observations, and artifact analysis reveal mechanisms and unexpected experience. Mixed methods pair outcome evidence with an explanation. Design-based research suits an instructor refining an intervention across iterations.

AI-assisted qualitative analysis belongs on that list with a condition. It reorganizes an interview corpus in minutes, so warrantability matters as much as accuracy: record the documented reorganizations that let a reader inspect, contest, and revise the pathway from data to claim.

A survey is a self-report measure: right for attitudes, wrong for learning.

Give the comparison condition a name

Three conditions make a causal claim interpretable: a precisely described treatment, a well-defined comparison condition, and a valid measure of durable learning. Weidlich et al. (2025) audited 19 ChatGPT-in-education comparisons against those criteria. Four (21%) satisfied all three. Treatment was well defined in 74%, the control group in 42%, the outcome qualified as learning in 53%.

The failure mode is easy to reproduce. A general-purpose tool introduced alongside new activities, new feedback, or a redesigned interface confounds the medium with the method, and the significant result belongs to the redesign.

Measure the outcomes you actually care about

The AI Ed Evaluation synthesis recommends unassisted learning gain, delayed retention, transfer to a new task, quality of reasoning, Misconceptions about AI, feedback uptake, and subgroup performance. Engagement, satisfaction, AI-use logs, Self-Efficacy, and perceived usefulness are reasonable secondary measures and poor substitutes for learning. Workload and time savings count as implementation outcomes, a different question.

The classroom-scale minimum is a baseline, the intervention, an immediate post-measure, and a later unassisted measure. Add a comparison condition where you can: existing practice, no AI, unrestricted AI against scaffolded AI, or two alternative designs. Score assisted and unassisted performance on separate instruments, since one rubric will blend them.

Read any number as a hypothesis

An average effect from the literature is a weak guide to one classroom. O'Neill's (2026) audit of 14 high-impact meta-analyses found that none provided a valid basis for its claims. Pooled "academic achievement" mixed test scores, motivation, Self-Efficacy, and attitudes into one estimate. Heterogeneity was extreme: I^2 ran from 77.2% to 94.4% in the 13 analyses that reported it, and 12 of those sat above 80%. All 14 assessed publication bias invalidly, and 61% of randomly vetted primary studies carried validity problems. Four analyses reported between-study variance, two reported a prediction interval, and both intervals included zero.

A convenient score can measure the wrong construct. In an evaluation of eight AI teaching agents, the agent ranked third on the platform's own score ranked last on an expert-validated rubric, because platform scores indexed student performance during the interaction. Treat a dashboard metric as a hypothesis.

What instructors get wrong

A satisfaction survey measures the learning. It measures satisfaction, which the AI Ed Evaluation synthesis lists as a secondary measure beside learning outcomes.

A pre/post gain shows the intervention worked. It shows scores rose. Whether the measure counted as learning is a separate question, and the audit found a qualifying learning outcome in 53% of the comparisons it reviewed.

Published effect sizes transfer to my class. O'Neill's 14 meta-analyses could not support the claims built on them, and both reported prediction intervals included zero.

Platform analytics measure teaching quality. Zhang's third-ranked agent was last on an expert rubric.

What will come back at you

"We already have end-of-course evaluations." They measure the course, and they run after the term you needed the answer in.

“A comparison group is impossible in an intact course.” Compare against last year’s version of the same assignment, or a second section, and describe the difference honestly. Quasi-experimental designs are weaker, and still informative when the alternative is a claim with no comparison.

“The effect size in the meta-analysis is large.” On which outcome, in whose class? Both prediction intervals O’Neill found included zero.

“Our dashboard shows strong engagement.” Engagement is a secondary measure on the AI Ed Evaluation list. Put the unassisted learning measure beside it.

What to do this week

1. Write your claim as one sentence and underline the outcome.

2. Add the later unassisted measure to the calendar, after the intervention and not the same week.

3. Write one paragraph describing the comparison condition, in the same detail as the treatment.

4. Pull the platform numbers you already have and mark each one as an artifact outcome or a learning outcome.

5. Ask one colleague to read the design and say what else changed during the term.

Where to go next

Does AI help students learn? summarizes what the outcome evidence shows, and Research Gaps in AIED covers where it thins out. How do we know an educational AI is working correctly? is the version of this question for people building or buying a system.

Connected FAQs

- Does Using AI Actually Help My Students Learn?
- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- What Are Notable Gaps in the Research Literature on AI in Education?

Research practice

For researchers reporting, reviewing or planning work in this field.

How Can AI Assist with Educational Research?

Your co-author wants a paragraph in the methods section about the AI tools the team used. Or the screening pile is longer than the deadline allows. Or a reviewer has asked, politely, whether a person read the transcripts, and you are not sure what the honest answer is.

The short answer for that meeting: AI can take search, a first screening pass, coding triage, and the drafting, and it cannot carry responsibility for what the project concludes. Decide which tasks are open to it before the project starts, verify outputs against a human standard with a named person adjudicating, and log enough that an outsider could reconstruct what happened. Most teams find the verification and logging hours are work added rather than removed.

The short version

1. Write down which research tasks may use AI and which may not, before the first search runs. Sort by stakes rather than by tool.

2. Put the automation on screening. Keep data extraction, reconciliation, and synthesis with people.

3. Settle the codebook and the rubric before an automated pass touches the data.

4. Decide what verification means and who signs it. Agreement between a model and a coder is a similarity measure, not a quality result.

5. Verify every reference by hand, authors first, whenever AI touched the writing.

6. Log prompts, model versions, and corpus versions, and budget the hours for it.

Decide what AI may touch before the project starts

The scope decision belongs in the project file rather than in someone's memory. In Dai and Chan's (2026) focus-group study, researchers who had thought about it calibrated use by stakes and intellectual centrality: heavier on low-stakes procedural work, cautious where the scholarly contribution was central. Twenty-seven of the 28 postgraduate researchers in that study had used GenAI somewhere in the workflow, including academic writing and translation, so for most teams the question is where the line sits rather than whether one exists.

Write the line as a list with a verdict for each task: literature search, abstract screening, extraction, qualitative coding, statistical analysis, drafting, reference formatting. Read that study as a map of what researchers reported doing. It is a focus-group account, not an effectiveness result.

Put the automation on screening and keep synthesis in the team

Systematic reviews are where automation has advanced furthest. Tools such as ASReview, SWIFT-Review, Covidence, AIScreenR, and MetaMate cut the procedural burden mainly at abstract screening, while data extraction, reconciliation, and synthesis stayed with human reviewers in the one team that reported its workflow (Wang et al., 2026).

Most of the benefit comes from two design decisions. Write decision rules for gray-area cases before screening starts, and keep a “maybe” category with a shared adjudication log so the same judgment gets applied to the same kind of record. Without the log, the second reviewer’s rule and the first reviewer’s rule diverge quietly, and the exclusion list stops being reproducible.

Fix the codebook before the model reads anything

Qualitative analysis is the stage where interpretation is the product. Constructs, coding rubrics, and training data are human decisions rather than model outputs (Martin et al., 2026), which means the codebook has to be settled before an automated pass runs over the corpus. The alternative is a coding scheme written around what the model happened to surface, and the themes then describe the tool’s reading of your data.

Delegation can be finer-grained than all-or-nothing. One blind-verification study classified 15 of 72 codebook items as demonstrably requiring human expertise, 12 as better served by a model, and 16 as suited to confidence-based triage. Sort your own items that way and the labor saving lands where it is safe.

Decide what verification means and who signs it

High agreement between a model and a human coder gets reported as if it established correctness. It does not. Liu et al. (2026) had an independent expert judge 855 pairwise code sets blind to source. Human-Large Language Models (LLMs) agreement (mean Jaccard 0.30) sat well below human-human agreement (0.52), yet the blind verifier preferred human and machine coding at rates it could not distinguish (51.5% against 48.5%, $p = 0.537$). In some cases human consensus encoded a shared bias the verifier rejected in favor of the model.

So the verification step needs a gold standard that is neither the model’s output nor the coder’s agreement with it, plus a named person who adjudicated the disagreements. Report both. A similarity statistic describes how closely two readings match, and it says nothing about whether either reading is right.

Search fast, then check every source yourself

Generative search summarizes, recommends, synthesizes, and converses, which unsettles the older arrangement in which the system locates and the reader interprets (Report on CHIIR 2026 Workshop on Generative AI and Academic Search (GAI&AS)). Treat it as a discovery tool. The workshop report carries two cautions: capability is uneven, with highly cited scholars reconstructed at roughly twice the rate of lower-cited peers, and a librarian described a trust gap in which students over-trusted generative search while faculty distrusted it.

Reference verification is where this becomes non-negotiable, and the failures cluster in the author field, the one that carries credit. Denny et al. (2026) audited 723,930 publications and 15,872,533 references and verified 30 fabricated references across 14 computing-education papers, all from 2025 and 2026. Seventeen of the 30 were hybrids: a real title attached to fabricated or incorrect authors. The verified count at one technical symposium rose from 3 in 2025 to 17 in 2026, in 2.3% of that year’s proceedings papers. Their total is a deliberate lower bound, and automated checkers inherit the flaws of the metadata they treat as ground truth. Check authors first.

Treat an automated score as a hypothesis to test

Automated measurement functions can look precise and predictive while remaining opaque. Martin et al. frame this with Chang's nomic-measurement problem: measuring a quantity requires a law relating it to something observable, and that law cannot be tested without already knowing the quantity. AI-derived measurement functions emerge from training data and optimization rather than from the researcher, so explainability work matters for showing whether a model tracks semantic understanding or only keywords.

The failure is concrete. In an evaluation of eight AI teaching agents, the agent ranked third by the platform's own score ranked last on an expert-validated rubric. Human-machine disagreement is systematic rather than random, and rubric operationalization often matters more than prompt craftsmanship (Tseng et al., 2026). Before an automated score becomes your instrument, validate it against a measure tied to the capability you intend to study. For the measures themselves, see What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?.

Write the method section so an outsider can audit it

Adoption has run ahead of reporting. Zabaleta and Lin (2026) analyzed 888 review-automation papers: since 2023, 38.0% of software and product papers reported no evaluation at all, against 9.3% of LLM papers, and model access was overwhelmingly proprietary (84.1%). A favorable overall assessment did not imply fitness for delegation either, since 52% of 118 positive-only LLM papers still reported a concern that the workflow fell below the bar required for its role. Their PRISMA-LLM framework separates implementation disclosure from consequence-sensitive evaluation and treats its five levels as disclosure tiers rather than risk tiers.

The practical version: name the system and its version, the prompts, the corpus version, what a human checked, and where it failed. Keep prompt-and-response logs, because a fluent generated theme list looks inevitable long before its evidentiary work has begun (Holster, 2026).

Budget the hours as well. A 115-day, single-investigator case study of a persistent research agent found the strongest pattern was capacity expansion rather than proven labor substitution: as memory and procedures accumulated, the scope of delegated work grew while the human's input did not shrink.

Run practitioner inquiry with the same rules at smaller scale

If you are a lecturer studying your own course, you are working in the corpus's thinnest strand. AI-Assisted Educational Research states this as a gap rather than a finding: AI-assisted practitioner inquiry is plausibly widespread and almost undocumented, and the review-automation and bibliometric evidence does not settle how a lecturer should study their own teaching.

What carries across is a set of dispositions:

Use AI where your local setting is not the variable. Searching your field's literature, transcribing and summarizing your own recordings, and drafting instruments or consent language all qualify.

Keep the interpretive moves. What counts as a theme, what a student's comment means, and what your classroom evidence warrants are yours to make, and the write-up should say which moves the model made and which you made (Holster, 2026).

Predefine your criteria and keep them visible. A small local study cannot recover from a construct defined after the data arrived.

Report the AI's role, the verification you did, and the limits of a single-course, single-investigator design. A workflow account is not an efficacy result.

Treat simulating a cohort as an advanced option rather than a default. Simulated learners tend to cover the easiest quadrant of real student behavior and are rarely validated after use (Simulating Students). Read How Do We Make a Simulated Student Behave Like a Real Learner? before you trust a simulator's verdict.

What researchers get wrong about this

Agreement with a human coder means the coding is right. Human-LLM agreement in the blind study was 0.30 Jaccard against 0.52 for human-human, and the blind verifier could not tell the two coding sources apart at 51.5% against 48.5%. Agreement records that two readers converged, including when they converged on the same bias.

A reference checker replaces checking references. The 30 fabricated references in the Denny audit include 17 hybrids where the title was real and the authors were not, which is exactly the case a checker trained on metadata handles worst, since the metadata is the thing that is wrong.

A favorable evaluation makes a workflow fit for your role. Of 118 positive-only LLM papers, 52% still reported a concern that the workflow fell below the bar its role required. Read the depth of the evaluation against the job you are giving it.

Prompt craft is the main lever on quality. Rubric operationalization often matters more than prompt craftsmanship in human-machine agreement, and the eight-agent evaluation ranked the same system third and last depending on whose rubric was applied.

AI takes work out of the project. The 115-day case study found delegated scope growing as the agent's memory accumulated. Verification, adjudication, and logging are the hours that grow with it.

What will come back at you

"My co-author already does this and nobody has complained." Nobody complaining is not a finding about validity. The disclosure question is separate from the quality question, and the 38.0% figure for unevaluated software papers says the field's silence is widespread.

"Two models agreed with each other, so the coding is settled." Two models sharing training data share their errors. The Liu study's blind verifier preferred machine coding at 48.5%, and what made that number interpretable was an independent judge, not the agreement itself.

"We cannot audit a proprietary model, so there is nothing to report." PRISMA-LLM asks for implementation disclosure as a tier separate from evaluation depth. System, version, prompts, what humans checked, and where it failed are all reportable for a closed model.

"The ethics committee will never approve this." Model access was proprietary in 84.1% of the papers examined, which means student text typically leaves your institution. Collect only what the educational purpose needs, check whether learner data trains the vendor's models, and prefer local or synthetic data

where sensitivity is high. How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? covers the obligations in full.

“This will be slower than doing it by hand.” For a small project it often is. The case for it rests on scope at scale, and the case against overstating it rests on the same 115-day account.

What to do this week

1. Write the task list with a verdict beside each item, and put it where the whole team can see it.

2. Add the gray-area decision rules and the adjudication log to your screening protocol before the next batch starts.

3. Pick one automated output you already rely on and validate it against a human judgment on a sample you have not looked at yet.

4. Read the last manuscript you submitted and check every author name in the reference list by hand.

5. Add a “where the AI failed” line to your methods template, so the disclosure habit is written down once.

Where to go next

The companion questions are What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? on how to measure an intervention, What Are Best Practices for Reporting and Interpreting AI in Education Research? on reporting the system and your own AI use, and What Are Notable Gaps in the Research Literature on AI in Education? on where the literature is thin. How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? covers student data, and AI-Assisted Educational Research is the full concept page behind this one.

Connected FAQs

- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- What Are Notable Gaps in the Research Literature on AI in Education?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?

What Are Best Practices for Reporting and Interpreting AI in Education Research?

Your draft has a headline number in the abstract, and a reviewer has just asked what the control group actually did. Or you are the reviewer, holding a meta-analysis whose pooled effect is 0.67 and whose methods section runs to a page and a half. Or your department is writing guidance on how staff should report AI studies and wants something more specific than "follow the standards."

Six omissions decide most of these cases: which AI system was used, what it was configured to do, what pedagogical role it played, whether humans designed or reviewed its output, what the outcome measure actually captured, and what the authors did about bias, cost and limitations. "Unassessable" is the honest verdict when they are missing, and it is a different verdict from "refuted."

The short version

1. Describe the AI as a treatment, not a vendor. Model, version, configuration, prompts, role, and who designed or reviewed the output.

2. Name the pedagogical rationale and the active comparison. A product name is not a method, and business-as-usual is not a fair control.

3. Make the measure match the claim, including whether the outcome was delayed and unaided.

4. Report the uncertainty the analysis actually has: dependent effects, between-study variance, prediction intervals, subgroup sizes, publication bias.

5. Validate every automated judgment, with a named gold standard and a named adjudicator.

6. Report the counterweights: governance, compute cost, your own AI use, null results, and only citations you have checked.

Describe the AI as a treatment someone could rebuild

This is the check most submissions fail. The RAISE framework (*Reporting AI Studies in Education*, Allison 2026) is a 30-item checklist across ten thematic domains, and its diagnostic claim is specific: submissions routinely omit which model was used, how it was configured, what role it played, and whether human actors designed or reviewed its outputs. Reviewers are then left with four unanswerable questions. What exactly was the AI doing? Was it necessary? Is this replicable? Are the learning claims credible?

RAISE runs from educational justification through API-level specification, learner-AI interaction, accessibility and cultural fit, participants and setting, human involvement, design, ethics, transparency and reproducibility, to limitations. Its companion Ethics and Risk Matrix covers risks to learner Learner Agency, equity, data AI Governance and algorithmic transparency. Hwang, Xie, Wah and Gašević (2026) offer a streamlined alternative. TEP-AIED folds Transparency, Ethics and Pedagogy into one interdependent structure, supplies a guideline table mapped to seven paper sections, and asks authors to add a Method subsection titled "Transparency, Ethics, and Pedagogy Considerations." Their reason is practical: RAISE is

comprehensive and too granular for routine empirical use. The disclosure sits under AI Use and Disclosure Statements and is what makes Privacy and Ethics claims checkable.

Educational justification comes first in RAISE because AI is not a neutral tool. Value depends on alignment between the learning problem, a theoretical rationale, and the mapping from objectives to outcome measures. O'Neill (2026) found that all but two of 14 audited meta-analyses defined the treatment as a tool, ChatGPT or GenAI or "AI" generally. A product name is not a Pedagogies and Teaching Strategies. Treating exposure to ChatGPT as one common intervention is comparable to meta-analyzing the effects of "paper."

Weidlich et al. (2025) make the same argument for primary studies. Auditing a subset of the comparisons behind a prominent meta-analysis, they found only 21% had a well-defined treatment, a control group and a valid learning measure. The reported effect size (g = 0.7) also exceeded that of purpose-built intelligent tutoring systems (0.66), and that gap is a warning sign: a treatment that beats purpose-built tutoring is probably a bundle of different things wearing one label.

The test is one question: could a competent reader rebuild your intervention from the method section alone and get the same thing?

Decide what your measure licenses you to claim

In O'Neill's evidentiary audit of 46 randomly selected primary studies, 28 (61%) presented validity concerns. Dependent-variable mismatch was the most common (n = 15), followed by independent-variable mismatch (n = 11), experimental design problems (n = 7), data extraction problems (n = 6), absence of a control group (n = 6) and nonrandom group assignment (n = 6). Multidimensional outcomes were routinely pooled as if interchangeable, with test scores, homework quality, Motivation, Self-Efficacy, attitudes and engagement collapsed into one "academic achievement" number.

Two reporting habits prevent that. State what construct the instrument measures and that it was validated for that population; Self-Report Measures shows where perception-based measures diverge from behavior, and Assessment Validity covers construct validity. Then report an outcome that does not depend on the learner's belief about the aid. Immediate task performance under assistance is not a learning gain, and cognitive offloading is the mechanism that most plausibly separates the two. The 2026 mini review of 493 records and 14 priority studies found none measured verification success and the following reliance decision together against an independently adjudicated standard of output quality, and few looked past immediate performance to delayed retention or transfer.

State the ceiling explicitly in the discussion. A study that measured a quiz taken with the tool open can support a claim about assisted performance. It cannot support a claim about what students learned, and that sentence costs one line.

Report the uncertainty your analysis actually has

For syntheses, report dependent-effect handling, between-study variance, prediction intervals and publication-bias assessment. I^2 alone will not do the work. O'Neill found reported heterogeneity severe wherever it was given, from 77.2% to 94.4% across 13 meta-analyses with 12 above 80%, and never resolved: no moderator analysis met the minimum subgroup size of ten studies. Twelve meta-analyses treated dependent effect sizes from the same study as independent, which inflates the apparent evidence.

Only four reported between-study variance (τ^2) and only two a prediction interval, and both intervals included zero. Publication bias was not validly assessed anywhere in the set.

Heterogeneity figures need their model attached, because I^2 is precision-dependent. Limitations in AIEd Research documents one synthesis at $I^2 = 82.98\%$ under a fixed-effect model and 15.75% under random effects. A reader given only the first number cannot tell how inconsistent the corpus is. Report τ^2 and a prediction interval alongside it, which is also the convention the review literature asks for.

Then discount your own headline. Bartoš et al. (2026) pooled 1,840 effect sizes from 67 meta-analyses and found that once publication bias is modeled the average effect falls to roughly one-third of the published median (SMD = 0.196 versus 0.67), with a prediction interval from -1.521 to +1.908. That interval spans substantial harm to substantial benefit for a hypothetical new study. It is the most useful number in the paper and the one most likely to be dropped from the abstract.

Say how far the claim travels

Fairness and scope fail in the same way: a large effect that means less than it appears. Eleven of the 14 audited meta-analyses set no population boundary, so “students” spanned children through medical trainees. A single course, institution, discipline or country does not license a general claim, and results for one tool rarely transfer to another.

Three explanations account for most large effects, and each is reportable. Novelty is one. Extra time on task is another. The third is a comparison condition that received business-as-usual instruction rather than an active control. Report what the control actually did, how much time each arm spent, and how novel the tool was. State the population boundary as well, because effects differ across learner groups and an unstated boundary is what lets one pooled number stand in for all of them; Differential Effects Across Learner Groups sets out the variation.

Treat the tool as a moving target. Proprietary systems change without notice, so a finding is bound to a model version, and the Benchmark that thrilled in one release may not hold in the next. Version and access date belong in the method section for that reason, not only for replicability.

Validate the automated judgments

AIED evaluation increasingly delegates scoring to models, which makes the validation procedure part of the result rather than an appendix. Khan Academy’s account of its AI tutor metrics reports that cognitive engagement is scored by an Large Language Models (LLMs) judge calibrated against human pedagogical experts at F1 0.83, and that metric movements came from more than 40 live experiments in five months rather than offline evaluation (Udeshi et al. 2026). Tseng et al. (2026) show that human-machine disagreement about pretest question quality is systematic rather than random, and that rubric operationalization matters more than rationale-first prompting.

Agreement with human coders is a separate thing from quality, and reporting it as if it were quality is a reviewer target. Liu et al. (2026) had an independent expert judge 855 pairwise code sets blind to source. Human-LLM agreement came in at a mean Jaccard of 0.30 against 0.52 for human-human agreement, while the blind verifier preferred human and machine coding at indistinguishable rates (51.5% versus 48.5%, p =

0.537). Report the calibration target, the gold standard, and who adjudicated the disagreement. Those three items are what let a reader decide how much weight the automated score can carry.

Disclose the costs and your own use

A review of all AIED 2025 conference papers found a pattern of LLM adoption without disclosure: most projects used LLMs, and fewer than a handful reported resource consumption or carbon footprint. That paper supplies an Open Source method with measuring tools for local and cloud hardware, plus a formula for estimating the computational expense of frontier models whose parameter counts are undisclosed. Its argument is that not reporting these costs is itself an ethical concern. Data governance, consent, accessibility and cultural fit belong in the same paragraph (RAISE items; Universal Design for Learning, Accessibility). How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? carries the fuller treatment.

Your own use of AI in the research process needs the same disclosure. Zabaleta and Lin's PRISMA-LLM analysis of 888 review-automation papers shows how uneven this reporting is. Since 2023, 38.0% of software and product papers reported no evaluation at all, against 9.3% of LLM papers. Mean reporting richness was 6.3 for LLM papers and 3.3 for software and product papers. 84.1% of LLM usage relied on proprietary or hosted systems, with only 4.9% open-weight. Their framework separates implementation disclosure from consequence-sensitive evaluation across five disclosure tiers, which is a workable template for describing what a tool did inside a review.

Dai and Chan (2026) add the author-side picture. Of 28 postgraduate researchers, 27 used GenAI across ideation, literature review, explanation, data processing, programming, academic writing, editing and translation, They calibrated use to stakes and disciplinary norms. Their institutions' policies addressed teaching and assessment rather than research practice, which leaves the reporting decision to the author.

Publish the null, and check every citation

Denny et al. (2026) verified 30 fabricated references across 14 papers, with the count at one technical symposium rising from 3 in 2025 to 17 in 2026, or 2.3% of that year's proceedings papers. LLM-assisted drafting makes a plausible invented citation cheap to produce, which is why the checking has to happen before submission rather than after acceptance.

The counterweights in that audit matter when you cite it. Most flagged references were benign: 229 were ACM metadata mismatches where the PDF was correct, and 188 were valid bibliographic variants. The fabricated count is a deliberate lower bound, and the benign majority is not a rounding error. Verify every entry you cannot personally check.

Reporting null and negative findings is the other half of an honest evidence base. Bartoš et al. found strong evidence of suppressed null results (every Egger test $p < .0001$) and extreme heterogeneity ($\tau = 0.869$), with no outcome, field, level or AI-role subgroup showing consistent gains. They also found no difference between studies published before and after January 2023, which undercuts the claim that modern generative tools specifically produce gains.

What researchers get wrong about this

“An effect size is a property of the modality.” There is no effect of AI in education to report. All but two of the audited meta-analyses defined the treatment as a tool name, only 21% of audited comparisons had a defined treatment, a control and a valid measure, and the pooled g = 0.7 sat above purpose-built intelligent tutoring at 0.66. An effect size belongs to a design, a population and a measurement occasion.

“The pooled mean is what will happen to my students.” The mean describes the set of studies, and nothing in it fixes any single classroom. The bias-adjusted average is SMD = 0.196 and its prediction interval runs from -1.521 to +1.908. Reported heterogeneity sits above 80% in 12 of 13 meta-analyses, and no subgroup in the larger pool showed consistent gains. A student-level change is not identifiable from either number.

“A null result means the tool does not work.” A null is a statement about a design at a given precision, and absence of a detectable effect in one study is a fact about that study. The bias-adjusted SMD = 0.196 came from a literature in which every Egger test was significant, so the defensible reading of the corpus is a small and uncertain average. No outcome, field, level or AI-role subgroup in the larger pool showed consistent gains either. The documented problem in this literature is suppression.

“One study settles it.” The base rates argue otherwise. 61% of vetted primary studies had validity concerns, one course or institution does not license a general claim, and a proprietary system is a moving target bound to a model version. A single study is a data point with a design attached.

“High agreement with human coders means the model is scoring the right thing.” Human-LLM agreement was 0.30 against 0.52 for human-human, and the blind verifier could not distinguish the two coding sets at 51.5% versus 48.5%. Agreement measures consistency with a coder, and quality is a separate question that needs a gold standard and an adjudicator.

The objections you will hear

“Reviewers want novelty, not method detail.” Journals are moving the other way. RAISE and TEP-AIED give editors a construct to require, and TEP-AIED’s Method subsection is a low-friction entry point. Method detail is what converts an unassessable paper into a citable one.

“We do not have the space.” The five disclosure tiers are reporting levels rather than risk levels, so the evaluation depth can be a sentence or two. Version, prompts and role fit in a short paragraph. Cost and governance fit in a limitations sentence.

“Everyone reports it this way.” The numbers say the norm is the problem: 61% of vetted primary studies with validity concerns, 12 of 13 meta-analyses above 80% heterogeneity, 38.0% of software and product papers with no evaluation.

“Our tool is proprietary, so we cannot report the model.” Report version, date accessed, configuration, the prompts you supplied, role and Guardrails. If the vendor will not say, that constraint belongs in the limitations as a bound on the claim.

“Reporting nulls will hurt us.” Suppressed nulls are the documented mechanism behind the SMD = 0.196 bias-adjusted average. Publishing them is what keeps your positive result readable.

What to do this week

1. Read your abstract against your method section and delete every claim the method cannot support. One sentence on the ceiling of the measure is usually enough.

2. Add the specification paragraph: model, version, access date, configuration, prompts, role, and who designed or reviewed the output.

3. Pull the τ^2, the prediction interval and the publication-bias assessment out of the appendix and into the results, or say plainly that you did not compute them.

4. Write the population boundary and the control condition into the design statement, including how much time each arm spent.

5. Verify every reference you did not personally read, and check the author field first.

Where to go next

Research Methods in AI in Education covers the design choices underneath these reporting decisions, and Limitations in AIEd Research is the catalog of failure modes with the numbers attached. Interpreting and Applying AIEd Research is the reader's side of the same problem, the evidence on durable learning is what most of these measures are trying to reach, What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? covers the measures and comparison designs, and How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? is the shorter version of the question. For the gaps this literature has not filled, see What Are Notable Gaps in the Research Literature on AI in Education?.

Connected FAQs

- How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well?
- What Are Notable Gaps in the Research Literature on AI in Education?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?

What Are Notable Gaps in the Research Literature on AI in Education?

A grant deadline is eight days out and the background section needs one sentence about what this field does not yet know. Or a colleague has told a committee that AI tutoring raises achievement, citing a two-year experiment across 18 middle schools, and you are the person who has to say what that study can carry. Or you are choosing a dissertation question and every version of it seems to have been done.

The gaps that matter are about strength, specificity, and applicability. AI can perform educational tasks; the open questions are whether a particular design produces durable benefit, for whom, through which mechanism, and under what conditions. That distinction decides two things on your desk: what to study next, and what to stop claiming in the meantime. Limitations in AIEd Research is the catalog behind this page. Evidence about intelligent tutoring systems, predictive analytics, generative AI, and autonomous agents is not interchangeable either, and research on using AI to support learning differs from research on teaching people about AI, as the AI in Education overview explains.

The short version

1. Compare the AI against a strong non-AI alternative that holds curriculum, practice, and support constant, and say what the AI added.

2. Measure delayed, unaided performance, and state that assisted performance is not a learning gain.

3. Report which component of the package did the work and which mechanism you claim.

4. Validate every automated score and simulated learner against real learners, including learners outside your development sample.

5. State the population boundary, because a pooled average does not answer an equity question.

6. Describe the arrangement well enough that someone else could rebuild it.

Choose a comparison that isolates the AI

Rigorous classroom experiments exist, so “we need randomized trials” no longer names the gap. The sharper question is whether the AI component adds value beyond additional practice, better materials, timely feedback, or more instructional support.

One Click Away reports modest achievement gains across 18 middle schools alongside limited substantive engagement with the tutor, and the authors note that the gains resembled those from structured practice without AI. That is evidence about an implemented package, and it cannot isolate what the AI inside it added.

The problem underneath is conceptual as well as empirical. “ChatGPT” names a tool, not a method. Weidlich et al. (2025) audited 19 ChatGPT-in-education comparisons: only 4 (21%) specified all three of a replicable treatment, an operationalized control, and a valid learning measure (74% well-defined treatment, 42% well-defined control, 53% a learning outcome). When new AI arrives alongside new activities, feedback, or interface design, medium and method are confounded and no effect belongs to the AI.

What would settle it: comparisons against realistic non-AI alternatives with curriculum, practice opportunities, and support held as constant as possible, plus independent replications across institution, instructor, subject, and model. Methods answer different questions here. Qualitative and design-based work explains implementation, while well-designed experiments carry the causal claims, as Efficacy Research Methods sets out.

Measure learning after the tool is gone

Improved work while using AI is not evidence of learning that survives the assistance ending. The Learning Gains and Cognitive Offloading syntheses keep drawing the same line between assisted performance, retained knowledge, independent reasoning, and transfer.

Making AI Tutoring Productive shows the measurement problem in a randomized experiment with more than 6,000 middle-school students. A three-correct-in-a-row mastery rule raised platform-defined success without, by itself, producing detectable learning gains one week later. The strongest delayed-test evidence appeared when AI sat inside the mastery workflow and concentrated on practiced material.

The remaining gap is about trajectories of capability, and one added posttest does not close it. Nobody has established retention across months, transfer across tasks, performance after withdrawal, or learners' accuracy in judging what they know, and the field has not separated failure to acquire a skill from deterioration of one already established. Offloading research still needs to show when delegation supports those trajectories and when it displaces the practice that builds them.

Find out which part of the package did the work

"AI-supported learning" usually bundles several changes: new feedback, added reflection, peer discussion, different task sequences, altered assessment incentives. A package that succeeds does not tell you which components were necessary.

Human-centered GenAI feedback design is a real advance on that question. Among 1,176 first-year undergraduates, reflective and hybrid designs outperformed direct AI feedback on delayed AI-free transfer. The hybrid condition combined self-evaluation, peer feedback, and AI critique. That separates how feedback is organized and used from whether students have access to feedback at all.

Still open: the contribution and timing of initial independent attempts, self-explanation, peer input, corrective feedback, hints, and fading assistance, and how each interacts with prior knowledge and task difficulty.

The theory gap runs alongside. Naming a learning theory is not testing one. A study needs a theoretical prediction tied to a specific system behavior and a measurable learning process, and statistical mediation informs that explanation without establishing a causal mechanism. Theory Development in AI in Education and Scaffolding carry the argument further.

Validate the measure before you interpret it

Constructs such as engagement, critical thinking, AI literacy, and personalization get measured inconsistently across this literature. Self-reports describe perceptions; they cannot stand in for demonstrated competence.

Technical accuracy, expert-rated output quality, and student learning are three different evaluation targets. Educational Measurement and AI Ed Evaluation treat those distinctions as foundational.

One gap sits inside the measurement problem: AI systems used to evaluate other AI systems. In Simulating Students or Sycophantic Problem Solving?, simulated students frequently abandoned assigned Misconceptions about AI after corrective feedback whether or not the feedback addressed the misconception, so their responses could make ineffective instruction look successful. Targeted training improved the study's faithfulness measure, and improvement on that measure is not validation against human learning.

What is missing is validation of the whole evaluation chain, from model behavior to pedagogical judgment to learner response to educational outcome, on learners and settings not used during development. Human judgment needs the same scrutiny, since agreement among raters is not evidence that the right construct was assessed.

Decide what an assessment can still certify

AI creates two connected assessment problems: it helps produce the work being assessed, and it can influence how that work is scored.

The knowledge base's study of AI agents completing assessed LMS tasks documents agents navigating a live undergraduate course and finishing assessed activities. That demonstrates a capability which challenges assumptions about student-produced evidence. It does not establish how common such use is, and it does not invalidate asynchronous assessment as a category.

The research question is which designs still support defensible conclusions about the learner. Portfolios, reflections, staged submissions, and activity logs need validation as evidence rather than being assumed to establish authorship or understanding. Studies should test combinations of evidence against independently observed competence while accounting for accessibility, workload, privacy, and student anxiety. Assessment Validity holds the detail.

For automated scoring, LLMs Do Not Grade Essays Like Humans reports systematic disagreement between out-of-the-box models and human raters. The findings are configuration-specific, and they show why internal consistency cannot carry a validity claim.

A Human Capability Test for Learning Outcomes in the AI Era proposes assessing separately what learners must do independently, what they may accomplish with AI, and what they must verify and defend. That is a framework awaiting empirical validation.

Detection is the clearest dead end in this area. Karr et al. (2026) ran two commercial detectors at $\tau = 0.50$ over 642 published English abstracts. Guideline-compliant light AI editing was flagged at 38-80%. Unmodified 2023-25 originals were flagged at 9-15%, with non-STEM work far above STEM at $p < 0.001$. After humanization the tools caught fewer than 4% of AI-labeled rewrites, a false-negative rate above 96%. A score that punishes honest assistance and misses evasion cannot ground a conclusion about a learner.

Stop reading literacy scores as evidence of behavior

AI-literacy intervention research is substantial enough to synthesize. AI Literacy Interventions in Education covers 59 studies and 7,211 participants, reports a positive average effect, and also reports substantial

variation with a wide prediction interval spanning zero. Knowledge-focused outcomes came out stronger than skills, attitudes, or ethics.

The sharper gap is whether literacy instruction changes what people do when they use AI, and another competency framework would not close it. Can learners recognize unsupported claims, verify sources, reject misleading suggestions, notice inappropriate agreement, and choose when not to delegate? Does any of that hold under time pressure, and does it transfer to unfamiliar systems and disciplines?

Settling this needs performance-based assessment combined with observation of actual decisions and delayed follow-up, with conceptual knowledge, operational proficiency, and critical judgment kept apart rather than pooled. AI Literacy and Trust Calibration supply the distinctions.

Report who the finding leaves out

Findings from one course, institution, language, or learner population rarely license decisions elsewhere, a problem the Limitations in AIEd Research synthesis treats as recurring. How effects vary across developmental stage, discipline, prior knowledge, disability, language, and resource conditions remains largely unmeasured.

Equity research also has to separate access, skills, and outcomes. The Digital Divide synthesis is clear that devices and tool access do not establish equal capacity to benefit. Does School-Based AI Education Narrow Readiness Gaps? followed 752 Hong Kong junior-secondary students: psychological readiness gaps narrowed while differences on an objective AI-literacy test persisted. Every group improved, and inequality did not close. Prior-learning profiles were not randomly assigned, so their causal role stays unknown.

Coverage is thin in specific places. Differential Effects Across Learner Groups counts the literature by population: second-language and multilingual learners and students with disabilities are the deepest strands, gender and Neurodiversity come next, first-generation and international students have one study each in this corpus, gifted and high-achieving students are effectively unstudied, and refugee, immigrant, and displaced learners appear in none. An evidence base with that shape cannot answer an equity question by aggregation.

Capacity varies inside a single national system too. Adeniranye et al. (2026) scored AI integration at 45 Nigerian universities and found moderate overall adoption ($M = 4.79$, range 1.83-7.83 on a 10-point scale), with institution type failing to predict integration once age and geography were controlled (age $\beta = 0.43$; South-West location $\beta = 0.31$). Internal capabilities intercorrelated at $r = 0.79$-0.80 and international collaborations with industry partnerships at $r = 0.74$, so connected institutions accumulate compounding advantages. Which capacity-building designs change outcomes at newer, less-connected institutions is untested.

The research priority is identifying designs that reduce differences in demonstrated capability, participation, and Learner Agency, with subgroup outcomes and burdens reported alongside average gains. Accessibility carries its own unresolved question: whether a design removes a barrier to participation or replaces a capability the learner is meant to develop. See Equity in AI Education and Accessibility.

Say who holds control, and when it changes

As systems plan, initiate actions, hold memory, and coordinate tools, the educational question becomes who should control which parts of the learning process, and when that control should shift.

Agentic AI in Education: A Scoping Review maps 474 studies and finds limited longitudinal validation, concentration in higher education and STEM, and weak educational-theory integration: only 29% of reviewed studies drew explicitly on educational theory, a finding about that corpus rather than all AIED work.

Open questions follow. Does learner-initiated help produce different outcomes from agent-initiated help? Can support be withdrawn as competence develops without loss? Do learners keep the ability to challenge the system? The Agentic AI and Human-AI Collaboration syntheses add teacher intervention and accountability in multi-agent settings, where nobody has established who answers for an agent's decision. Greater autonomy is a pedagogical design choice with an evidence base still to be built.

Test safety failures against real learners

Educational safety reaches past factual accuracy and prohibited requests. A tutor can give a correct answer while removing the learner's opportunity to reason, reinforcing a misconception, or building dependence. Pedagogical Safety covers the construct.

SafeTutors identifies failures including excessive answer disclosure and abandonment of scaffolding, with substantially more failures under multi-turn testing. Those are Benchmark findings under specified conditions, not estimates of how often harm occurs in classrooms.

What happens when those failures meet real learners over sustained use is unknown. Which ones produce temporary confusion, which produce persistent misconceptions, which reduce motivation, and which weaken independent capability has not been measured. Nor has anyone established which safeguards cut those risks without producing excessive refusal or frustration. Longer-term work also needs trust, willingness to seek human help, learner agency, and relationships with peers and teachers as outcomes. For children, that requires developmentally appropriate studies connecting system behavior to educational and relational outcomes.

Separate adoption from implementation

Technical capability does not establish that a tool gets used well, and professional development does not automatically reach students. The missing link usually runs from teacher preparation, through changed classroom practice, to student outcomes.

Pedagogy First, Technology Second is a multilevel study of 46 teachers and 2,832 students. Pedagogical AI knowledge was associated with students' perceptions and intentions, and neither measured teacher-knowledge component was directly associated with student AI-knowledge gains. Associations of that kind do not establish that a training intervention would cause better learning.

The open question is which combinations of coaching, curriculum alignment, review routines, scheduling, and institutional support produce sustained improvement, and studies need to observe enacted teaching

rather than teacher confidence or intention to adopt. Teacher AI Competency and Educational Development cover the terrain.

Comparative cost-effectiveness is a second gap. Evaluations should count verification, correction, training, supervision, maintenance, and implementation time alongside subscription and model-use costs, and compare AI-supported provision with realistic alternatives. The question worth answering is what educational benefit the complete arrangement delivers for the resources it takes.

Count governance documents as intentions

Ethical principles and governance frameworks are necessary, and their existence does not establish that they change practice or protect learners.

Agarwal et al. reviewed 25 articles and found end users largely passive in the ethics literature, with student voices essentially absent, alongside tensions among values and power asymmetries between stakeholders. That describes the reviewed literature. It is not a claim that students never take part in AIED design.

What is missing is evidence about which governance arrangements make a measurable difference. Does student and teacher participation change procurement, tool design, assessment rules, or remedies after a mistake? Do human-review procedures catch consequential errors? Are alternatives to AI use genuinely available to the people told to use it? Privacy research has a parallel gap: the educational value of additional data collection is usually assumed, and data-minimizing designs have rarely been compared with more intrusive ones on both learning and learner autonomy. See AI Governance and Privacy.

Make the study rebuildable

AIED has an unusually hard reproducibility problem. Studies omit prompts, model versions, settings, code, and instructional details, and proprietary systems can change during or after an intervention. Limitations in AIEd Research documents the pattern.

Rebuilding a study means describing the instructional arrangement as well as the model: learning tasks, content sources, permitted actions, interface, teacher support, assessment conditions, and anything that changed during deployment. Reproducing one configuration and testing whether its pedagogical principle transfers to another are separate achievements, and the reporting guidance in Efficacy Research Methods addresses both.

Synthesis needs the same care. Meta-Analysis and Systematic Review lists weak primary studies, publication bias, heterogeneous interventions, and incompatible outcomes as limits on pooled conclusions, and a single average “AI effect” hides the distinctions educators need. Reviews should separate assisted performance from independent learning, distinguish intervention types and comparison conditions, and make coding decisions auditable.

The synthesis literature is itself a gap. O’Neill’s (2026) forensic audit of 14 high-impact meta-analyses found that none provided a valid basis for its claims. No coherent construct: a tool treated as one intervention, multidimensional outcomes pooled. Publication bias was invalidly assessed in all 14. Reported I^2 ran from 77.2% to 94.4% in every analysis that reported it, with 12 of the 13 above 80%. 61% of randomly vetted primary studies carried validity concerns. Those 14 analyses collected more than 2,000 citations in roughly

16 months, and a retracted meta-analysis was still cited as authoritative in 60% of post-retraction citing papers without acknowledgment. Of 14 papers citing another audited meta-analysis whose abstract advertised a large effect of "AI education" that in fact measured teaching students about AI, only 2 cited it appropriately, 8 read it as evidence that integrating AI improves learning, and 4 were wrong in other ways. The audit asks journals to require full data transparency for meta-analyses (search protocols, coded study characteristics, extracted statistics, analytic code), asks editors not to treat a publication record as proof of reviewing competence, and asks that retractions be visible wherever an article is discovered, exported, or cited. Reproducibility covers the synthesis chain, not only the individual study.

Instructors who want the classroom-level version can follow What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?.

What researchers and instructors get wrong about this

The field lacks studies. It lacks specified ones. There are multisite experiments, randomized trials with thousands of students, and 14 high-impact meta-analyses. Only 21% of audited comparisons defined treatment, control, and outcome well enough to attribute an effect.

Naming a theory tests it. A citation to a learning theory is a framing decision. A test needs a prediction, a system behavior that implements it, and a process measure that could come out the other way.

A validated automated score is a validated outcome. Agreement with human coders establishes consistency with those coders. Simulated students improved on a faithfulness measure without being validated against human learning, and the chain from model behavior to outcome remains unbuilt.

Access is equity. In the Hong Kong study, psychological readiness gaps narrowed while objective test differences held, and every group improved without inequality closing. Devices and licenses change who can reach the tool.

More autonomy is progress. Greater agent independence is a design choice. With 29% of 474 agentic studies drawing on educational theory and limited longitudinal validation, nobody has shown that shifting control to the system improves learning.

The objections you will hear

"The gap is just that we need more randomized trials." Plenty exist now, and the problem sits upstream of design labels: a trial of a package that bundles new feedback, new tasks, and a new interface cannot attribute anything to the AI. The comparison condition is where the work is.

"I cannot run a multi-year follow-up." Then measure one delayed, unaided occasion and say what interval it covers. A week is a real finding, and the mastery-rule study got its result at one week by embedding AI in the workflow and concentrating on practiced material.

"Randomization is impossible in my course." Design-based and qualitative work answers implementation questions that trials cannot, and the field needs both. Where random assignment is possible, it still carries the causal claim.

“The pooled effect size already tells me what works.” The 14 audited meta-analyses defined the treatment as a tool, pooled incompatible outcomes, and reported I^2 above 80% in 12 of 13 analyses that gave it. The pooled number describes a set of studies with a construct problem.

“Simulated students are cheaper, so validating them can wait.” In the sycophancy study, simulated students dropped misconceptions whether or not the feedback addressed them, which is the failure mode that makes an ineffective tutor look effective.

What to do this week

1. Write the comparison condition of the study you are planning in one sentence. If it is business as usual, revise it before you revise anything else.

2. Add one delayed, unaided measure to the design and name the interval in the method section.

3. Write the population boundary into the design statement, then into the abstract, so the claim cannot travel further than the sample.

4. Take the strongest claim in your current draft and delete the version your measure cannot carry. Keep the sentence about the ceiling.

5. For any automated score or simulated learner in the study, name the human standard and the adjudicator before data collection starts.

Where to go next

What Are Best Practices for Reporting and Interpreting AI in Education Research? is the reporting counterpart to this page, and Research Methods in AI in Education covers the design choices behind each gap. What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions? handles measures and comparison designs, How Do We Know an Educational AI Is Working Correctly, Not Just Scoring Well? is the shorter version of the efficacy question, and Does Using AI Actually Help My Students Learn? collects what is known about durable learning. Theory Development in AI in Education and How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety? carry the theory and equity strands further.

Connected FAQs

- What Are Best Practices for Reporting and Interpreting AI in Education Research?
- What Measures and Research Methods Can an Instructor Use to Evaluate AI-Related Interventions?
- How Should AI in Education Research Incorporate Equity, Accessibility, Privacy, Ethics, and Pedagogical Safety?

Free Tools and Resources

A curated set of **free tools, collections, instruments and formats** for AI in education — things a reader can go and use, rather than research to read first. They are made mostly by educators, instructional designers, librarians and researchers, and many were built with AI assistance by people who are not professional developers.

Not everything here is interactive. Alongside browser tools you will find libraries of ready-made prompts and “gems”, collections of classroom activities, briefing and policy documents, assessment instruments, and open file formats. Each entry says who made it, what kind of thing it is, whether the source code is available, and what it costs to use. Every entry links to an external site this knowledge base does not control; the link-checked date records when a link was last confirmed to work. The same list lives at the knowledge base site under Resources.

Software

Claw-ED

- **Open it:** https://sirhanmacx.github.io/Claw-ED
- **Made by:** SirhanMacx (MacxLabs)
- **Source code:** https://github.com/SirhanMacx/Claw-ED
- Type: Software, Collection Of Tools · Access: Free · License: MIT (original code; third-party components keep their own terms)
- **Link checked:** 2026-09-23

Claw-ED is a local-first teaching assistant that drafts lessons from your own curriculum materials. A teacher imports their sources, asks for a lesson, and gets editable drafts along with student-facing materials and slides, generated with whichever model the teacher chooses rather than one fixed vendor.

What you can do with it

The workflow runs from import through draft, review, and export, and drafts are treated as starting points that a teacher edits rather than finished handouts. Lesson jobs are queued and recoverable, so a long generation that fails can be resumed instead of restarted, and generated artifacts can be downloaded. It also exposes its tools to an agent through an MCP server and can connect to Google Drive, so a school can wire it into existing storage and scheduling.

The project is deliberately model-agnostic. It documents local Ollama models, budget OpenRouter routes, and hosted options side by side, and its model guide is dated, which makes clear that the recommendations are catalog-based starting points rather than teacher-scored judgments of quality.

Notes and caveats

The software is free and open source under the MIT license for its original code, though third-party components keep their own terms, and running it means paying for your own model inference if you use a hosted model. The project labels itself a teacher-reviewed beta and says plainly in its README that passing its CI does not establish teaching quality across live models, which is the right way to read a green test suite in this space: it verifies the software, not the Pedagogies and Teaching Strategies. It is maintained by MacxLabs and accepts teacher-reviewed sample lessons as contributions.

Connected Concepts

Learning Design, Online Teaching and Learning, Open Source, Teacher AI Competency

Connected Resources

- Education Agent Skills

Code Viva

- **Open it:** https://code-viva.netlify.app/
- **Made by:** Code Viva
- Type: Software · Access: Free
- **Link checked:** 2026-10-24

Code Viva runs a written, timed version of an viva for every student in a programming course, about fifteen to twenty minutes each, without an instructor in the room. It reads a student's submitted code and commit history, writes four to six questions about that student's own functions, names and commits, and gives each student a personal link to answer from.

What you can do with it

Submissions come from a Gradescope export, a Canvas download zip, a folder-per-student zip, or GitHub Classroom with a read token. The instructor sets session length, question count and deadline, marks extended time at 1.25x to 3x, and reads, edits or replaces the generated questions before sending links. Questions cover recursion base cases, edge guards, data structure choices, opaque variable names, scale and tracing, sentences from the assignment spec, and commit patterns such as one bulk or late-night commit. Answers return as a response code, and the review screen shows each transcript beside a proposed 0 to 3 score with the sentences it rests on, plus a flag queue ordered by how much a conversation is warranted. Results export to CSV, and eleven demo courses let a reader try the whole loop on invented data.

Who it is for

Instructors of programming courses who want evidence that a student can explain their own code, and who would rather talk to a short list of students than to all of them; the commit questions make it a form of Process-Oriented Assessment.

Notes and caveats

Everything runs in the browser: the course sits in local storage with a JSON export, questions travel in the part of a link browsers do not send to servers, and answers come back only as codes students choose to send, so no student data reaches a third party. The question generator is rule-based rather than model-driven. By the tool's own account its code reader is heuristic, so unusual formatting or macros can hide a function, and a score can reward knowing the vocabulary rather than understanding the code, which is why scores are proposals an instructor approves and why it advises keeping the stakes low. No license and no source repository are published, and because links carry the questions they run to a few kilobytes, long enough to wrap in a learning management message box.

Connected Concepts

Oral Assessment, Process-Oriented Assessment, Academic Integrity, CS Education

DeepTutor

- **Open it:** https://github.com/HKUDS/DeepTutor
- **Made by:** HKU Data Intelligence Lab (HKUDS)
- Type: Software, Collection Of Tools · Access: Free · License: Apache 2.0
- **Link checked:** 2026-09-20

DeepTutor is the open-source implementation of the tutoring framework evaluated in the DeepTutor study, and it has grown well past that paper's scope into a general agent-native learning workspace. Tutoring, problem solving, quiz generation, mastery practice, research and visualization share one capability runtime and one session context, so the learner profile built while solving problems conditions the explanations and practice items that follow.

What you can do with it

Ten modes — Chat, Ask Questions, Quiz, Research, Visualize, Solve, Course Study, Mastery Path, Immersive Reading and Immersive Watching — run on the same runtime, drawing on reusable knowledge bases, books, drafts, notebooks, question banks and personas. Retrieval is deliberately multi-engine: versioned RAG libraries over LlamaIndex, PageIndex, GraphRAG, LightRAG or a remote LightRAG server, plus a self-hosted WeKnora base, a Tencent IMA or MarginNote library, or a linked Obsidian vault. Memory is inspectable rather than opaque: L1 traces, L2 surface summaries and L3 synthesis are visible and editable, with a Memory Graph linking each summary to the evidence behind it. A `deeptutor` binary gives a terminal REPL and streams NDJSON for any agent that wants to drive it as a tool, and an EduHub community distributes installable skills.

Who it is for

Higher-education instructors and researchers who want a deployable version of the framework the paper reports on, developers building on a pluggable runtime, and self-directed learners willing to run their own instance. Documentation lives at deeptutor.info.

Notes

Licensed Apache 2.0, at version 1.6.9 as of September 2026 with roughly 40,000 GitHub stars. The published evaluation behind it — 10.8% average improvement on personalized metrics over strong baselines and 29.4% stronger general agentic reasoning across five backbone models, on the TutorBench benchmark — is summarized on the article page, whose limitations apply here too. As with any open-source AI stack, you supply model provider keys, and a desktop or server deployment expects Python 3.11 and Node.

Connected Concepts

Agentic AI, Intelligent Tutoring, Personalized Learning, RAG (Retrieval-Augmented Generation), Open Source, Mastery Learning, Knowledge Tracing, Automated Question Generation

Connected Resources

- OpenMAIC

Gemini Notebook

- **Open it:** https://notebook.google/
- **Made by:** Google Labs
- Type: Software · Access: Free With Account, Freemium
- **Link checked:** 2026-09-22

Gemini Notebook is Google Labs' retrieval-augmented study and research assistant, known as NotebookLM until the July 2026 rename. A notebook is a set of sources the reader chooses — PDFs, documents, slides, websites, pasted text, or the transcripts of YouTube videos — and every answer the assistant gives is drawn from that material with citations back to it. Where a general-purpose chat assistant answers from its training data, Gemini Notebook answers from the reader's own shelf of documents, and that constraint is the product.

What you can do with it

Ask questions across the whole source set, summarize long documents, and follow citations to check an answer against the passage it came from. Beyond chat, Notebook produces study and presentation artifacts: Audio Overviews, a podcast-style conversation between two synthetic hosts that can be interrupted with questions; Video Overviews, including short vertical versions added in 2026; Mind Maps, Reports, Flashcards, Quizzes, Data Tables, Infographics and Slide Decks. A July 2026 update gave each notebook a secure cloud computer for running code, which extended the tool from summarizing sources toward analyzing them.

Who it is for

Self-directed learners revising from their own course materials, instructors assembling readings into a questionable digest, and researchers working through a literature set. The free tier is open to anyone with a personal Google account and is where the audience for classroom use sits; higher limits, longer sources and sharing come with the paid Workspace and Google One AI tiers.

Notes and caveats

Google states that personal-account content is not used to train its models unless the user submits feedback, that Workspace uploads, queries and responses are not used for training even when feedback is given, and that data is not shared with third parties; deleted notebooks, however, cannot be recovered. The capability claims above are the vendor's own, and a district or institution should confirm them against its data processing agreement rather than a product page. Coverage in 2026 also described a lawsuit over the voice used in generated podcasts, which Google denied, a reminder that audio outputs raise likeness questions separate from the source-grounding safeguards. Treat generated flashcards, quizzes and summaries as drafts to check against sources, and note that the free tier's limits change without notice.

Connected Concepts

RAG (Retrieval-Augmented Generation), AI Literacy, Self-Directed Learning, Retrieval, Spacing and Interleaving, Generative AI, Multimodal AI, Video in Education, Hallucination Risk

LearnHarness

- **Open it:** https://learnharness.ai
- **Made by:** Amos Blomqvist
- **Source code:** https://github.com/amosblomqvist/learnharness
- Type: Software, Ai Tutor · Access: Free · License: AGPL-3.0
- **Link checked:** 2026-11-02

LearnHarness is a desktop application for agent-assisted learning that organizes a lesson around what a learner already understands rather than around a topic list. The project describes four moves: **measure**, probing the ideas the goal depends on to find where understanding ends; **plan**, deriving a dependency map to the goal and showing it as a lesson map; **teach**, working one reasoning step at a time through a predict–explain–check rhythm so confusions are repaired before anything is built on them; and **practice**, a stream of problems targeted at the learner's own difficulties.

What you can do with it

The distinctive input is the thinking field: learners write or dictate their reasoning and uncertainty rather than only answering, which the project treats as how the agent pictures reasoning instead of a right/wrong record. It can also research questions in the background, generate visual explanations and build interactive demonstrations.

What accumulates is a knowledge graph of propositions and reasoning chains, linked back to their source sessions and read by later teaching and practice agents as context; notes can be imported. The project says the graph stores ideas and connections, not ratings of ability.

Who it is for

Independent learners working on difficult material, and instructors or developers who want to see what an agent-native AI tutor looks like when its prompts and state are inspectable. It is TypeScript, runs from source, and its tests are documented as deterministic, with no model calls.

Notes and caveats

Free covers the software, not the inference: learners bring provider keys, a subscription, a local Claude Code CLI or any OpenAI-compatible endpoint, and pay the provider with no markup; a live meter estimates known API costs only. Records, chats and keys stay on the machine as plain files, but the project warns that local storage does not mean offline processing, since model requests, optional dictation and web research all reach external services. The Windows x64 installer is unsigned, so Windows will warn. No efficacy study is reported, so the case rests on stated rationale rather than measured outcomes; the repository had roughly 4,800 stars when checked on 2 November 2026.

Connected Concepts

- Agentic AI
- Intelligent Tutoring
- Mastery Learning
- Scaffolding

Connected Resources

- DeepTutor

OnMicro.AI

- **Open it:** https://onmicro.ai/
- **Made by:** The OnMicro.AI project
- **Source code:** https://github.com/onmicroai/micro_ai
- Type: Software, Collection Of Tools · Access: Freemium · License: AGPL-3.0
- **Link checked:** 2026-09-23

OnMicro.AI is a no-code builder for education that produces narrow, purpose-built AI apps rather than open-ended chat. An instructor designs a structured workflow, controls what the app accepts and returns, publishes it as a link that students can open without accounts or licenses, and then sees aggregate use, cost, satisfaction, and accuracy for the app itself.

What you can do with it

Apps can be embedded in Canvas, Moodle, Blackboard, or any LTI-compatible platform, where grades and access can sync; the published examples include a patient-communication Simulation, a case-study feedback app that scores understanding before a student moves on, and a short language-practice challenge. Usage analytics are the reason the project gives for preferring apps to custom chatbots: a designed flow can be observed and revised, while an open chat cannot. Models from the major providers can be selected, and the platform tracks what each app costs to run.

Who it is for

It suits instructors and learning designers who want bounded, repeatable interactions, and administrators who need a supported deployment path. It is a hosted commercial service this repository documents: the source is open, and the platform is also sold as a subscription.

Notes and caveats

The free tier is limited to 10,000 AI credits and three apps; unlimited apps and advanced models start at the Pro tier, and LTI integration, single sign-on, and advanced analytics are listed at the Enterprise tier, so the features an institution most needs are the ones that carry a price. The repository is licensed **AGPL-3.0** according to its `LICENSE` file, which matters for anyone intending to self-host or modify it, and its README still says LGPL from before that change, so read the license file rather than the README. Institutions should also confirm their own data-processing terms before routing student work through a hosted third-party service.

Connected Concepts

Teacher AI Competency, Learning Design, Open Source, Intelligent Tutoring, Scaffolding, AI Literacy, Edtech Platform

Connected Resources

- Vibes DIY

OpenMAIC

- **Open it:** https://github.com/THU-MAIC/OpenMAIC
- **Made by:** Tsinghua University MAIC team
- Type: Software, Collection Of Tools · Access: Free · License: MIT
- **Link checked:** 2026-09-20

OpenMAIC is the open-source release of the MAIC multi-agent classroom described in the MAIC study: describe a topic or attach your own materials and it generates a full lesson — slides, quizzes, interactive HTML simulations and project-based activities — then delivers it through AI teachers and AI classmates who speak, draw on a whiteboard and take part in discussion. It is the code behind a classroom that can be run rather than only read about.

What you can do with it

One-click generation produces a lesson in minutes from a prompt or uploaded document, audio or video. The multi-agent layer adds classroom discussion the learner can join or be called into, roundtable debates between personas with whiteboard illustrations, and free-form Q&A where the teacher answers with slides or diagrams. Sessions support slide decks, quizzes, interactive simulations and PBL, and export as editable `.pptx` or interactive `.html`. Version 1.0.0 (August 2026) added an agent workbench: a chat-first workspace that plans and revises whole courses, durable server-backed sessions you can cancel, resume or steer, and 24 built-in skills covering slides, quizzes, interactives, images, video and voices. A `SKILL.md` package lets an agent harness build classrooms from a messaging app.

Who it is for

Instructors and course teams who want generated materials they can still edit, instructional designers prototyping multi-agent activities, and developers who need a self-hostable classroom rather than a hosted product. Schools can deploy it on Vercel or with Docker, and the project ships a hosted demo at open.maic.chat.

Notes

Licensed MIT, with an English and Chinese user guide and an active community on Discord and Feishu. It is model-neutral: you supply at least one LLM provider key, and optional local components (Lemonade for local models, FunASR for speech recognition) let you run more of the stack offline — so “free” describes the software, not the inference bill. The paper behind it appeared in the *Journal of Computer Science and Technology* (2026, DOI 10.1007/s11390-025-6000-0), and the repository had more than 38,000 stars by September 2026.

Connected Concepts

Agentic AI, Generative AI, Large Language Models (LLMs), Open Source, Project-Based Learning, Online Teaching and Learning, Personalized Learning, Teaching, Intelligent Tutoring, Simulation

Connected Resources

- DeepTutor
- LESSON.md

PAUSE: Patterns of AI Use Self-Examination

- **Open it:** https://anondo1969.github.io/pause/
- **Made by:** Mahbub Ul Alam
- **Source code:** https://github.com/anondo1969/pause
- Type: Software · Access: Free
- **Link checked:** 2026-09-20

PAUSE (Patterns of AI Use: Self-Examination) is a free self-reflection check on how AI use is shaping your own habits. It asks about the last two weeks across four areas — reasoning and critical thinking, creativity and originality, research and learning, and social and communicative capacity — adds two short thinking exercises, and returns one reading per area on a 0–100 scale plus a concrete practice to try that week. Nothing leaves the browser: no account, no upload, no analytics, and the return token that lets you compare results next month is decoded locally.

What makes it different

Every item is grounded in a published paper, and you can expand the citation on any question — before or after answering — to read the exact sentence that motivated it. It is deliberately explicit that it is a reflection tool, **not a validated psychological instrument**, and that it must not be used for clinical, educational or hiring decisions.

Who it is for

Students, instructors and researchers who want a private prompt to examine their own AI habits, and courses that want a discussion starter on Cognitive Offloading without collecting data on anyone. Because it stores nothing, it can be used in a class without an institutional data agreement — the trade-off is that it also cannot tell you anything about your students as a group.

Notes

Written by Mahbub Ul Alam (SciLifeLab Data Centre, Uppsala University); the design rationale and validation limits are documented in an accompanying preprint, and the source code is public.

Connected Concepts

Cognitive Offloading, Critical Thinking, AI Literacy, Self-Regulated Learning, Metacognition, Privacy, Cognitive Surrender

Connected Resources

- Pressing Prompts

Playlab

- **Open it:** https://www.playlab.ai/
- **Made by:** Playlab (501(c)(3) nonprofit)
- Type: Software, Collection Of Tools · Access: Free With Account
- **Link checked:** 2026-09-20

Playlab is a creator platform where educators build their own AI apps instead of choosing from someone else's template. An app is grounded in your own curriculum, rubrics and references rather than general model knowledge, runs on a model you pick (Anthropic, OpenAI, Google, Meta) with the cost visible while you build, and can draw on pre-mapped knowledge graphs for Illustrative Mathematics, OpenSciEd, state standards and OER Commons.

What you can do with it

Build and remix: start from scratch or adapt one from the community gallery (hundreds of apps, student-built ones included). Steer behavior per app — image and voice input, memory and profiles, or Avoid Answer Generation, which guides students toward an answer instead of handing it over. Also available: a document editor with Docx and Drive export, Python execution, math input and image processing. Teachers can review any student conversation, and automated flags can pause one and notify the teacher. Rosters connect through Clever, ClassLink or Google SSO.

Who it is for

K-12 teachers and districts wanting classroom controls and curriculum grounding without building infrastructure; university instructors and instructional designers wanting one custom course tool; and students aged 13 and over (guardian permission under 18) who build apps themselves. It is a 501(c)(3) nonprofit: educator accounts are free in perpetuity, while school and district tiers are paid.

Notes

Access to the builder is gated: the get-started page asks for an email address and a spot in an onboarding workshop, or an invite code. Its compliance claims (FERPA, COPPA, GDPR, CCPA, SOC 2 Type II), the promise that your work never trains outside models and the assignment of output rights to the creator belong in the data processing agreement, not only the marketing page; its capability comparison against MagicSchool and the major chatbots is Playlab's own, dated mid-2026. It grew out of end-user programming work linked to Scratch and the MIT Media Lab.

Connected Concepts

AI Literacy, Learning Design, Generative AI, RAG (Retrieval-Augmented Generation), Human-in-the-Loop, Privacy, Guardrails, Educational Technology Developers, Teacher AI Competency

Connected Resources

- TeacherServer
- EduGems

Process Feedback

- **Open it:** https://processfeedback.org/
- **Made by:** The Process Feedback project
- Type: Software · Access: Free With Account
- **Link checked:** 2026-09-23

Process Feedback is a learning-first alternative to AI detection tools. It records the writing process — time spent, revisions, copy-paste events, and whether and when AI was used — and presents it as a writing process report, shifting the question from whether a student cheated to how the work was actually done.

What you can do with it

A teacher can view a report for one student or load hundreds at once from a teacher dashboard, and students can view their own reports and reflect on them. It works in Google Docs through a browser extension, in the project's own writing space, and in LMS editors such as Canvas, with LTI integration available; a report can also be downloaded as a PDF and uploaded to any platform. The project publishes reflection prompts for guiding student self-review, guidance on reading AI-use patterns, and teacher guides.

Who it is for

It is aimed at individual teachers and students, who can use it without institutional agreements, and at institutions that need a deployment with formal support. The project states that neither it nor the software takes a position on whether students should use AI; it reports what happened and leaves evaluation to the instructor. Developers can also use the project's browser-based code editor, which records process in programming assignments.

Notes and caveats

Free covers the individual classroom workflows; institutional pricing exists separately and is tied to deployment scope, data handling, support, and compliance rather than to a per-student or per-teacher charge. Because a report shows a process rather than an intent, copy-paste alone is not misconduct — the project's own guidance says a student may be pasting their own earlier text, and that students should not be penalized merely for pasting. The adoption figures and the 5.0 Chrome Web Store rating are the project's own marketing; reviews in an extension store are not independent evidence of learning outcomes. Read the reports as evidence for a conversation, which is how the tool is designed and how the developer describes it.

Connected Concepts

Academic Integrity, Metacognition, Writing, Self-Regulated Learning, Formative Assessment, AI Detection, Process-Oriented Assessment

Connected Resources

- PAUSE: Patterns of AI Use Self-Examination

Snorkl

- **Open it:** https://snorkl.app/
- **Made by:** Snorkl
- Type: Software, Collection Of Activities · Access: Free With Account, Freemium
- **Link checked:** 2026-10-07

Snorkl is a K-12 classroom tool that asks students to explain their thinking aloud and on a whiteboard, then returns AI formative feedback on those explanations — celebrating the approach and prompting a next step, rather than issuing a grade. The design choice is the point: the student produces the reasoning, and the model responds to it, the opposite of an answer-generating tutor.

What you can do with it

Students record a voice explanation while drawing on a whiteboard. Feedback returns within seconds on that Multimodal AI response. Teachers create their own activities or draw on a library of standards-aligned ones, so the feedback criteria follow the curriculum rather than the vendor's: the FAQ says the tool supports all K-12 subjects and ages, and lists 64 languages for feedback, in either the student's spoken language or one the teacher chooses. A teacher dashboard surfaces class-level patterns such as common misconceptions and exemplars; assignments go out by LMS link or join code, with Google, Microsoft, or Clever sign-in.

Who it is for

K-12 teachers who want to hear the reasoning behind an answer, and administrators buying at school or district level. The free teacher tier requires an account, and the FAQ caps it at 20 activities and excludes Snorkl Coach. School and district plans are quote-based — no prices are published — and add unlimited activities, a school dashboard and library, support, and professional development.

Notes and caveats

Every capability claim here is the vendor's own marketing, including "trusted in 10,000+ schools worldwide", which a district should check against its data processing agreement. The vendor states that it strips personal identifiers before sending work to OpenAI under an agreement not to retain or train on it, shows students no advertising, never sells data, and holds iKeepSafe and Common Sense Privacy certifications. Snorkl also states plainly that it does not grade: it scores explanations against teacher-specified criteria as formative feedback, and the teacher keeps grading. Treat those AI judgments as formative signals subject to the usual validity and bias questions, and the environmental commitment as stated intent, not a measured offset.

Connected Concepts

Formative Assessment, AI Feedback Quality, Feedback, Multimodal AI, Speech and Voice Technologies, Learning Analytics, K-12

Vibes DIY

- **Open it:** https://vibes.diy/
- **Made by:** The Vibes DIY project
- **Source code:** https://github.com/VibesDIY/use-vibes
- Type: Software, Collection Of Tools · Access: Freemium · License: Apache-2.0
- **Link checked:** 2026-09-23

Vibes DIY turns a description written in plain words into a working web app, then keeps changing it as the creator describes what to change next. Someone who wants a bingo card generator, a scoreboard, or a small practice tool can build one without writing code, share it by link, and let others remix it from a gallery.

What you can do with it

Describe an app, keep talking to revise it, and choose whether it stays private, is shared by invitation, or is published. Some projects connect to email, documents, or social accounts, which is how a small app becomes a working assistant with a personality. The `examples/` directory in the repository holds thirty complete apps with their source, including backends and access control, and the project publishes the prompt set it uses for generation, so the technique is inspectable rather than hidden.

Who it is for

It is a general-purpose builder rather than an education product: it is useful to an instructor or student who needs a small purpose-built tool and does not want to commission software, and to a class that studies how such tools are made. The React library, the CLI, the image component, and the prompt package are open source under Apache-2.0, so a district or a course can build with them directly.

Notes and caveats

The platform has a free tier but it is credit-based: accounts get 1,000 AI credits a month, and building, editing, generating images, and in-app AI features all spend them. A subscription adds the option to buy more credits, which do not expire. Any course that intends to rely on the platform should check the current terms, since free usage is metered rather than unlimited, and should treat student-created apps as content with data-handling questions of its own.

Connected Concepts

AI Literacy, Open Source, Design Thinking, Constructivism, Learning Design, Vibe Coding

Connected Resources

- OnMicro.AI

Agent Skill

Clarity

- **Open it:** https://clarity.addy.ie/
- **Made by:** Addy Osmani
- **Source code:** https://github.com/addyosmani/clarity
- Type: Agent Skill, Software · Access: Free · License: MIT
- **Link checked:** 2026-09-24

Clarity pairs an Agent Skill with a browser editor, both built around eighteen rules for writing that "earns its reader." The skill installs into coding agents such as Claude Code and Codex with `npx skills add addyosmani/clarity`, and then works in three modes: review mode critiques a draft and leaves the file untouched, rewrite mode edits a draft in place, and interview mode asks the writer questions first and co-writes from the answers. The Feedback a writer gets is aimed at substance before style. The rules ask who the piece is for and what they already know, press for claims over subjects and specifics over abstractions, and treat padding as a problem of not knowing what the piece is for rather than of vocabulary.

The browser editor runs locally in the page and does not upload a draft. It reports the tells of machine-written prose, readability, and gaps in substance, which makes it useful for reviewing text a generative AI produced before it reaches a reader. The project is explicit that the goal is writing that stays recognizably the author's own rather than prose engineered to pass AI detection, a distinction instructors will recognize when they set a policy on AI-assisted writing.

What to know before adopting it

The repository publishes an evaluation protocol, before-and-after samples in `samples/`, and reference files behind the skill, so a reviewer can inspect how the rules behave rather than take a claim on trust; the page here does not restate any measured result. The author is Addy Osmani, the license is MIT, and the work is independent rather than a product of any institution. It is young and active: created in August 2026, 54 commits, three releases with the latest at version 0.2.1 that September, and roughly 250 stars when checked in September 2026. Three contributors have landed changes. Skill instructions load into an agent the reader already runs, so the usual prompt engineering caveats apply: the quality of the critique depends on the draft handed to it.

Connected Concepts

AI Literacy, Critical Thinking, Generative AI, Prompt Engineering, Feedback, Assessment, Writing

Connected Resources

- Education Agent Skills
- The ID Toolbox

Education Agent Skills

- **Open it:** https://github.com/GarethManning/education-agent-skills
- **Made by:** Gareth Manning
- Type: Agent Skill, Collection Of Tools · Access: Free · License: CC BY-SA 4.0
- **Link checked:** 2026-09-23

Education Agent Skills is a library of 165 agent skills for teachers, school leaders, and people building education tools. The skills are grouped into twenty domains spanning pedagogy, learning science, curriculum, assessment, and regeneration, and each one is written to be loaded by an agent rather than read as a document.

What you can do with it

Skills install into Claude Code, Codex, and Hermes, either as a plugin or by copying the folders, so the same library works across several agent surfaces. A hosted MCP server exposes the collection as tools for agents that cannot install skills locally, and the repository ships both a registry and a pre-built bundle so the server can serve the collection without reading the individual files at deploy time.

The project's distinguishing claim is its grounding: skills cite the evidence they rest on, and the repository's own history shows the discipline being enforced rather than asserted, including a merged fix that removed an unsupported attribution and corrected the description of a tested safeguard in a cited study.

Notes and caveats

The educational skills, documentation, and curriculum materials are licensed CC BY-SA 4.0, so reuse and adaptation are open while derivatives must carry the same license. Two operational details matter if you deploy it. The hosted MCP endpoint requires tokens rather than being open to anyone, and because the server serves a committed snapshot rather than the SKILL.md files, a skill you add without rebuilding and committing the bundle will not appear on the live server even after a redeploy. The library is built by Gareth Manning, an educator and curriculum designer, and the licensing terms apply to the educational content specifically.

Connected Concepts

Learning Design, AI Literacy, Active Learning, Online Teaching and Learning, Open Source, Educational Development

Connected Resources

- Claw-ED

Master Instructional Design

- **Open it:** https://github.com/narosemena/master-instructional-design
- **Made by:** Norman Arosemena
- **Source code:** https://github.com/narosemena/master-instructional-design
- Type: Agent Skill · Access: Free · License: CC BY-NC-ND 4.0
- **Link checked:** 2026-09-24

Master Instructional Design is a Claude skill that packages a working practitioner's method as an on-demand advisor: fifteen engagement modes, thirty-one reference files loaded only when relevant, and a nine-dimension audit framework spanning alignment, learner-centeredness, cognitive load, practice and transfer, feedback quality, engagement, visual design, inclusion, and consulting posture. It covers the full learning-and-development spectrum rather than course design alone, from needs and task analysis through eLearning authoring in Storyline, Rise and Captivate, facilitation and virtual workshop design, learner experience design, agile practice for L&D teams, evaluation planning with Kirkpatrick's levels and Phillips ROI, and organizational learning strategy for chief learning officers. Its reference files also carry the academic canon of the field, and it generates populated artifacts such as facilitator guides, alignment matrices and content audits, diagnosing a project before drafting anything.

The skill ships with a supporting harness: two subagents, one for intake interviews and one for evaluation architecture, hooks that route each prompt to the relevant reference file and guard its own files against accidental edits, cross-session project memory, and optional connectors for Perplexity, Google Drive and Notion that use each reader's own credentials. It installs into Claude Projects as an uploaded skill, or into Claude Code by copying the skill, hooks and agents into a project's configuration.

Terms and caveats

The license is Creative Commons BY-NC-ND 4.0, and the author's stated terms matter to most institutional readers: personal, non-commercial study and professional development are welcome, while commercial use, redistribution and white-labeling require a commercial license. The repository reports 314 of 320 points across ten self-designed challenges, which is the author's own evaluation rather than an independent one, and the same author sells consulting and workshops on the framework. The project is described as a personal endeavor unaffiliated with his employers, and its last commit dates from April 2026.

Connected Concepts

Learning Design, Design Thinking, Workplace Learning, Online Teaching and Learning, Assessment, Generative AI, Universal Design for Learning, AI Literacy

Connected Resources

- The ID Toolbox
- Education Agent Skills

Skills for Real Engineers

- **Open it:** https://github.com/mattpocock/skills
- **Made by:** Matt Pocock
- **Source code:** https://github.com/mattpocock/skills
- Type: Agent Skill, Collection Of Tools · Access: Free · License: MIT
- **Link checked:** 2026-09-24

Skills for Real Engineers is Matt Pocock's published agent-skills directory: small, composable instruction files that install into Claude Code, Codex or another agent, written to be adapted rather than adopted whole. Most of the collection serves software work, but several skills are education instruments that were built for teaching and questioning rather than for code.

The clearest example is `teach`, which runs over multiple sessions and treats the working directory as a stateful teaching workspace, so a learner's progress and open questions persist between conversations instead of restarting each time. `grill-me` and its underlying `grilling` primitive interview the user relentlessly about a plan until every branch is resolved, which is Socratic questioning as a reusable procedure rather than a conversational mood. `wait-what` responds the moment a message fails to land by re-pitching it in plain language with the missing context, a move any instructor recognizes from watching an explanation miss the first time. `writing-for-agents` covers how to write documents that an agent can follow, which is now the practical form of writing instructions for AI course material. `to-questionnaire` converts a decision into a questionnaire for whoever can answer it, `handoff` compacts a conversation into a document another agent can continue from, and `wizard` generates an interactive walkthrough for steps only a person can perform.

What to know before adopting it

Everything is open source under MIT and free to take as a starting point for local AI literacy or self-directed study. The adoption is large and fast-moving: roughly 270,000 stars and 23,000 forks when checked in September 2026, with the most recent commit on September 18, 2026. The caveat is scope. The skills assume an engineer's working context, they are organized into engineering, productivity, deprecated and in-progress buckets, so some entries are explicitly unfinished or retired, and the README doubles as a newsletter sign-up. Treat the teaching and questioning skills as the transferable part, and expect to rewrite any of them before putting one in front of students.

Connected Concepts

Socratic Method, Self-Directed Learning, Metacognition, Prompt Engineering, Generative AI, Pedagogical Agent, AI Literacy, Human AI Collaboration, Open Source, Teacher AI Competency

Connected Resources

- Clarity
- Education Agent Skills

idstack

- **Open it:** https://idstack.org/
- **Made by:** savvides
- **Source code:** https://github.com/savvides/idstack
- Type: Agent Skill, Software · Access: Free · License: MIT
- **Link checked:** 2026-09-24

idstack is an open-source collection of eleven skills for evidence-based instructional design, distributed as a Claude Code plugin with a companion Chrome side-panel extension. Rather than drafting a course, the skills audit one: they classify objectives against revised Bloom's taxonomy, check constructive alignment between objectives, activities and assessments, flag cognitive load problems, and review accessibility against WCAG 2.1 AA and Universal Design for Learning. Each recommendation carries an evidence tier, from T1 for meta-analyses and randomized trials through T5 for expert opinion. The project states that its citations draw on 108 peer-reviewed studies across eleven research domains; that count is the project's own claim, and its bibliography is published in Markdown so a reviewer can check it.

Courses enter through a Canvas API connection, an IMS Common Cartridge file, a SCORM package, a PDF export from an authoring tool, or pasted documents. A shared project manifest remembers the course across sessions, and a pipeline skill chains the design stages while skipping completed work. Reviews report against the eight Quality Matters standards and the Community of Inquiry framework, separating teaching, social and cognitive presence, then rank recommendations by severity.

What to know before adopting it

The plugin requires Claude Code and a bash shell to install; PowerShell and cmd cannot run the setup script, and Python 3 is recommended for score trends. Course data stays in the project folder on the reader's own machine, and leaves it only through an integration the user invokes, such as a Canvas API call. The Chrome extension's live inference needs the reader's own free Google AI Studio API key, though a simulation mode demonstrates it without one. The project labels itself beta at version 3.5.1.0 and warns of breaking changes between minor versions, and it is published under the savvides GitHub account rather than by a named author.

Connected Concepts

Learning Design, Design Thinking, Online Teaching and Learning, Accessibility, Universal Design for Learning, Assessment, Generative AI, Open Source

Connected Resources

- The ID Toolbox
- Education Agent Skills

Prompt Or Gem Library

EduGems

- **Open it:** https://www.edugems.ai/
- **Made by:** Eric Curts
- Type: Prompt Or Gem Library · Access: Free With Account
- **Link checked:** 2026-09-20

EduGems is a collection of pre-made prompts — "Gems" — for educators using Google Gemini. Each entry has its own page with a description and buttons to use the Gem or make your own copy, so a teacher can run a working prompt in Gemini without writing one from scratch.

What you can do with it

The library covers planning and classroom work (career caricatures, check-for-understanding activities, conference concierge, CRA math activity, SMART goals, trading cards, form analysis, Classroom and Forms headers, Jeopardy-style games, LETRS lesson planning, micro-inquiry sparks, podcast matchmaking, quiz generation), parent communication, and AI use itself — expectations statements, an AI integration coach, a prompt architect and a prompt doctor, a SAMR activity, an AI-use reflection and a Gem generator. Newest additions are listed on the front page, and teachers can submit their own for inclusion.

Notes

Curated by Eric Curts, who publishes the accompanying tutorial video, newsletter and wider edtech resources at Control Alt Achieve. Making a copy of a Gem requires a Google account and the Gemini terms come with it, so this is a library to evaluate before pointing students at it, not a tool that can be used anonymously.

Connected Concepts

Prompt Engineering, Generative AI, AI Literacy, Learning Design, Online Teaching and Learning, Teacher AI Competency

Connected Resources

- TeacherServer
- The ID Toolbox

The Pedagogical Promptbook

- **Open it:** https://edtechbooks.org/promptbook
- **Made by:** David Wiley
- Type: Prompt Or Gem Library, Ebook Or Guide · Access: Free · License: CC BY
- **Link checked:** 2026-09-24

The Pedagogical Promptbook collects prompts that carry their evidence with them. Each chapter takes one established practice, reviews the research behind it, follows the authors through the iterations that turned that research into a working prompt, reports how the prompt's performance was evaluated, and then prints the full prompt and any supporting materials. That structure distinguishes it from the prompt libraries that circulate without justification: a reader can see what a prompt was tested against and how it changed, and can decide whether the evidence applies to their own course.

Chapters span instructional design and teaching practice rather than a single subject. They include embedding cognitive apprenticeship in AI agent prompts, making pedagogical intent visible during course design, a think-pair-share variant that treats a generative AI as a collaborative peer, dialogic role-play with learning theorists for pre-service teachers, a Community of Inquiry forum autograder, formative Feedback systems for tutoring, grading help on handwritten mathematics, backward design for authentic assessment, the ARCS motivational model, constructive alignment through Bloom's taxonomy, peer tutoring for evaluating sources, and Gagné's conditions of learning.

What to know before using it

The book is open access under a CC BY license, which is the permissive end of the range for teaching materials: instructors may copy, adapt and use the prompts, including commercially, provided they attribute them properly. That makes it straightforward to localize a prompt for a specific course or agent setup, which the more restrictive licenses on similar collections do not allow. It is published on EdTech Books in 2026 with a PDF download and the DOI 10.59668/2340, edited by David Wiley. Because each chapter reports the evaluation design as well as the result, it also works as a model for instructors who want to test their own prompts instead of adopting someone else's judgment.

Connected Concepts

Learning Design, Prompt Engineering, Generative AI, Pedagogical Agent, Formative Assessment, Feedback, Authentic Assessment, Scaffolding, Metacognition, Community of Inquiry, Socratic Method, AI Literacy

Connected Resources

- Writing and Rhetoric Studies in the Loop: A GenAI Prompt Library
- The ID Toolbox

Writing and Rhetoric Studies in the Loop: A GenAI Prompt Library

- **Open it:** https://wacclearinghouse.org/books/wac-repository/wrstl/
- **Made by:** Anuj Gupta and Brian Gogan
- Type: Prompt Or Gem Library, Ebook Or Guide · Access: Free · License: CC BY-NC-ND 4.0
- **Link checked:** 2026-09-24

Writing and Rhetoric Studies in the Loop: A GenAI Prompt Library is an open-access, peer-reviewed collection that treats your prompting practice as a subject worth designing. Sixteen prompts, each contributed and tested across several GenAI platforms, pair a reusable prompt with the writing knowledge behind it: Swales' CARS model for research introductions, the three rhetorical appeals, a genre mentor for building rhetorical expertise, trauma-informed prompting for ethical course proposals, a tripartite rhetorical-linguistic-translingual approach to reducing bias, and structured AI-assisted review for revision. One prompt asks a model to speculate on how human readers will respond to a draft, a use of generative AI that puts the writer back in the position of judging an audience rather than outsourcing it.

The collection's Introduction frames a prompt as a rhetorical genre with a stake in AI alignment, and the editors' stated aim is to keep writing teachers and their students inside the loop instead of staging a contest between human and machine writing. For instructors, that makes the book usable in two directions: as a source of prompts to adapt for a course, and as readings that model how disciplinary AI literacy is argued rather than asserted. Several chapters reach past first-year composition into technical editing, business proposals, Feedback on multimodal work, and graduate fellowship writing.

What to know before using it

The whole book is free in PDF and ePub, and individual chapters are published separately with their own DOIs. Publication is July 2026 by the WAC Clearinghouse in its WAC Repository series, 402 pages, edited by Anuj Gupta and Brian Gogan, with the collection DOI 10.37514/TWR-B.2026.2999. The license is Creative Commons BY-NC-ND 4.0, so readers may view, print personal copies and link to the book, but may not reproduce it on another site or adapt it without permission; a course that wants modified prompt wording should write its own version rather than reprint these. Each chapter's prompt was tested across platforms, though the book reports no controlled comparison of outcomes, so treat the prompts as expert design rather than validated intervention.

Connected Concepts

Prompt Engineering, Writing, Generative AI, Human-in-the-Loop, AI Literacy, Bias Mitigation, Feedback, Academic Integrity

Connected Resources

- Clarity

Collection Of Tools

DrawSplat

- **Open it:** https://drawsplat.org/
- **Made by:** Miguel Guhlin
- Type: Collection Of Tools, Software · Access: Free · License: GNU AGPL-3.0-or-later (whiteboard); GPL-3.0-only (SplatWorks apps)
- **Link checked:** 2026-09-22

DrawSplat is a free, browser-based workspace that collects small single-purpose tools for teaching. Teach with the collaborative whiteboard, or open a focused environment: **GridSplat** for spreadsheets, formulas and charts, **ShowSplat** for slides, **WriteSplat** for classroom documents, **ListSplat** for simple databases, plus a quiz and flashcard studio, image editor, chart builder, video editor and Markdown studio. Saved work and preferences live in the browser's local storage, and cloud save is opt-in.

What you can do with it

- Build a lesson artifact in the browser with no install and no account.
- Draw and annotate a diagram, then export it for a handout or slide.
- Make a concept map, chart or picture graph from classroom or CSV data.
- Build quizzes, team activities and printable flashcards.
- Anonymize or trim a video before sharing it with a class.

Who it is for

Teachers and students who need a tool quickly and cannot wait for a district license, and schools that want a low-friction alternative to a stack of subscriptions. The site publishes privacy and Accessibility statements, a district addendum and a Texas compliance page, which is the paperwork a school needs before it can approve a browser tool.

Notes

The product site names no individual author and routes requests to a project inbox; DrawSplat is built by Miguel Guhlin, whose site documents its launches. The code is free in the license sense, not only the price sense: the whiteboard is GNU AGPL-3.0-or-later and the SplatWorks apps are GPL-3.0-only, with no per-seat license on student devices. Tools that read your files run locally in the browser, while cloud save and any professional-learning request do send data, so check the storage inventory page before using it with student work.

Connected Concepts

Visualization, Multimodal AI, Formative Assessment, Project-Based Learning, Accessibility, Privacy

Connected Resources

- The ID Toolbox

FPDS Apps and Resources

- **Open it:** https://fpdshc.github.io/apps/
- **Made by:** Faculty Professional Development Services at Hillsborough College
- **Source code:** https://github.com/fpdshc/apps
- Type: Collection Of Tools · Access: Free · License: MIT
- **Link checked:** 2026-10-24

FPDS Apps and Resources is the public hub for the teaching tools built and curated by Faculty Professional Development Services at Hillsborough College. Fifteen entries sit under three headings, AI, accessibility and teaching, and each one opens the tool itself.

What you can do with it

The AI section holds four conversational coaches on Playlab: an AI Teaching Coach that pairs what is blocking student success with an evidence-based strategy, an AI Literacy Design Coach that adapts AI Literacy to a course, an Academic Habits Coach for students, and the AI-Era Assignment Design Coach, which also exists as a NotebookLM notebook and a non-AI worksheet and treats assignments as a matter of balance rather than of being made AI-proof. It also carries a Canvas course of ready-made AI literacy materials, a self-paced AI Petting Zoo tour, a Gemini Gem for designing online modules, and this knowledge base. Accessibility is led by the office's own Canvas checklist, which asks what you are working with and walks pages, images, documents, slides, PDFs, video and links before a course-wide sweep; beside it are the college's Pressbooks book on digital accessibility and a Gemini Gem that writes alt text. Teaching collects a handbook course for Canvas teaching, a starter kit to copy into your own course, a course of evidence-based strategies with ready-made Canvas items, and an online teaching checklist.

Who it is for

Instructors and Educational Development staff at Hillsborough College, and instructors elsewhere looking for a worked example of a small faculty-development site built from static pages that can be copied rather than rebuilt.

Notes and caveats

Reading needs no account, and the Canvas courses and checklists it links to are public. The Playlab coaches and the Gemini Gems and notebooks are third-party services that do need one. The cards render from `apps.json`, so the full list needs JavaScript and the no-script fallback names eight of the fifteen; the short link `tinyurl.com/fpdapps` and a header QR code open it on a phone. The repository is MIT-licensed software, while the guides it links to carry their own licenses, the Pressbooks book among them under a non-commercial Creative Commons license. There is no publication schedule, so the page changes without notice.

Connected Concepts

Academic Integrity, Learning Design, Generative AI, Accessibility, Educational Development, Online Teaching and Learning, AI Literacy

Connected Resources

- EduGems
- Gemini Notebook
- LiaScript

TeacherServer

- **Open it:** https://teacherserver.com/
- **Made by:** Zafer Unal
- Type: Collection Of Tools, Software · Access: Free With Account
- **Link checked:** 2026-09-22

TeacherServer is a free collection of AI generators aimed at educators, organized into two sets: fifteen most-used tools for K-12 teachers and fifteen for college faculty, inside a total of 1,194 tools. Each tool is a form: you describe what you need, refine the response in conversation, then save or share the result.

What you can do with it

For K-12: lesson plan, worksheet, IEP goal, math word problem, reading activity, science lesson plan and science experiment generators, a phonics and reading coach, a Lexile score adjuster, a curriculum quiz maker, a historical-perspective generator and tech-ethics scenarios. For college faculty: a text proofreader, paraphraser, case study generator, research idea generator, assignment feedback, discussion prompts and a rubric generator. The site also republishes summaries of recent research on AI in education.

Notes

The project claims a locally installed AI server for speed and that data is processed locally and never stored, plus Department of Education guideline compliance; the team page names Zafer Unal, a professor at the University of South Florida, as founder and developer, alongside an advisory board of four faculty members from other universities. Those claims are still worth verifying before use with student work. Access requires registration, and there is a companion paid-later platform for building your own tools.

Connected Concepts

Generative AI, Large Language Models (LLMs), Formative Assessment, Teacher AI Competency, Online Teaching and Learning, Automated Question Generation, Higher Education, Special Education

Connected Resources

- EduGems

The ID Toolbox

- **Open it:** https://nextgenailearning.com/
- **Made by:** Curt Zilbersher
- Type: Collection Of Tools, Software · Access: Free
- **Link checked:** 2026-09-20

The ID Toolbox is a growing set of free, single-purpose utilities for the parts of instructional design that are tedious rather than creative. Nothing requires an account or an email, and the tools that read your files run entirely in the browser, so a draft course never has to be uploaded anywhere.

What you can do with it

Before you build: choose between authoring tools against weighted criteria, test whether the request really needs a course at all, estimate development time and cost from complexity and finished minutes, count course words for a translation quote, or recover the storyboard, questions and media from a published course when the source file is lost. While you build: convert and shift captions between SRT, VTT and TTML, check caption reading speed, split caption lines, pull transcripts into timed captions, audit readability and unexpanded acronyms, clean text pasted from Word or a PDF, diff a script against what the subject-matter expert changed, fix smart quotes, and check color contrast.

Why it exists

Curt Zilbersher, who has designed corporate training for twenty-eight years, describes the same small unsolved problems recurring across his career — counting narration words, finding the asset that pushed a course past an LMS limit, auditing caption coverage by hand — and is building the fixes and giving them away. The site also runs a free annual survey on how instructional designers actually spend their week.

Connected Concepts

Learning Design, Online Teaching and Learning, Formative Assessment, Educational Technology Developers, Accessibility

Connected Resources

- DrawSplat
- LESSON.md
- EduGems

teacher.dev

- **Open it:** https://www.teacher.dev/
- **Made by:** teacher.dev
- **Source code:** https://github.com/teacherdotdev
- Type: Collection Of Tools · Access: Free · License: Apache-2.0 (the app source code)
- **Link checked:** 2026-10-24

teacher.dev is a 501(c)(3) education non-profit, formerly BX Coding, that ships one small app for teachers every day and posts the build. As of October 24, 2026 the streak stood at 53 days and the gallery listed 34 free apps built with classroom teachers, most made in a single day and many local-first, with no account and no student data leaving the device.

The narrowness is the value. A review game where one student takes on the class, printable generators for grids, number lines and figures in mathematics, chemistry and physics, a word-building tool for prefixes, bases and suffixes aimed at reading and writing, a First/Then board for special education, a hall pass tracker, and a quiet-time safari where shy animals emerge as a class settles. The gallery spans ten subjects, with about 23 apps student-facing and 20 built for teachers.

What you can do with it

Filter the gallery by subject or by whether an app is student-facing or a teacher tool, then use it straight from the browser. Nothing here is a platform to adopt: each app addresses one recurring classroom moment, so a teacher takes the one that fits, and the Accessibility work appears as calm visuals, large targets and printable outputs rather than a settings panel.

Who it is for

K-12 teachers who want a tool for a specific problem without a subscription, a student account for everyone, or a data agreement to negotiate first, and special education teams wanting supports such as the First/Then board. It also suits developers looking for small, readable examples of classroom software built to a teaching need rather than to a pitch.

Notes and caveats

The pace is both the pitch and the risk. One-day builds target a real classroom problem, not a research question, so nothing here carries an evaluation and a claim about what an app does should be tested in the classroom. Thirty-two public repositories sit in the GitHub organization while the gallery lists 34, all Apache-2.0 with source available, so an app can be read and self-hosted. Local-first design is a claim to verify per app, and a teacher should confirm before putting any student-facing tool in front of a class.

Connected Concepts

Edtech Platform, Accessibility, Game-Based Learning, Student Engagement, Special Education, Student-AI Interaction, Math Education, Science Education, Physics Education, Chemistry Education, STEM Education, English Education (EAP / EFL / ESL)

Connected Resources

- FPDS Apps and Resources

Collection Of Activities

Pressing Prompts

- **Open it:** https://pressingprompts.org/
- **Made by:** Hannah Rozear, Remi Kalir and Aria Chernik
- Type: Collection Of Activities · Access: Free · License: CC BY-NC-SA 4.0
- **Link checked:** 2026-09-20

Pressing Prompts is an openly accessible teaching resource for higher education instructors who want to run critical conversations about AI. Thirteen topics sit in three clusters — *Trust and Truth* (can we trust AI, bias, disinformation), *Power and Access* (Sustainability, hidden labor, the AI divide, copyright) and *Self and Society* (whether AI harms critical thinking, privacy and surveillance, companionship and sycophancy).

What you can do with it

Each topic carries a framing question, conversation starters, structured activities with steps, materials and timing, and learning notes that surface grading criteria and preparation for the instructor without crowding the student view. Most activities include a no-AI alternative, and the project is explicit that meaningful learning about AI does not always require using AI. You can collect activities into a playlist and export it as PDF or Markdown for an LMS; no login is required and nothing is collected.

Where it came from

It began at Duke University in 2024–2025 as the AI Ethics Learning Toolkit, co-designed by undergraduates, librarians, faculty and technologists across the Center for Teaching and Learning and Duke Libraries, and relaunched after feedback and redesign by Hannah Rozear, Remi Kalir and Aria Chernik.

Connected Concepts

Critical Pedagogy, Inquiry-Based Learning, AI Literacy, Critical Thinking, Sustainability, Digital Divide, Higher Education

Connected Resources

- PAUSE: Patterns of AI Use Self-Examination

mglearn Classroom Resources

- **Open it:** https://mglearn.github.io/
- **Made by:** Miguel Guhlin, TCEA
- **Source code:** https://github.com/mglearn
- Type: Collection Of Activities, Collection Of Tools · Access: Free · License: CC BY-NC 4.0 (content), MIT (code)
- **Link checked:** 2026-09-23

mglearn is a collection of classroom-ready learning activities and tools created by Miguel Guhlin in his work as Director of Professional Development at TCEA, the Texas Computer Education Association. Each suite opens as its own self-contained site: interactive activities, teacher views, printables, and in several cases Spanish or additional language versions.

What you can do with it

The Activities Hub gathers most of the suites in one searchable place, including Critical Thinking Online Breakouts, Science Detectives, lab safety certification, literature rooms, barrier games, digital math tools, and Gen AI literacy. Language Bridge carries 22 bilingual and ESL activities for emergent bilingual students. The ELE Activity Bank holds 95 ready-to-run activities for professional learning and K–16 classrooms, each with a facilitator guide and a print-ready packet. Teacher Printables adds middle-school science labs and classroom-management materials, and the TCEA directory indexes the wider set of HTML tools, dashboards, and prompt libraries.

Who it is for

It is aimed at K–12 teachers and the professional developers who train them, with activity suites spanning prekindergarten onward. Materials are designed to work without accounts and, where they are printable, on paper.

Notes and caveats

Content is licensed CC BY-NC 4.0 and the underlying code MIT: classroom use, local hosting, and adaptation are permitted with credit, while selling the materials or bundling them into paid training requires written permission from TCEA. Works by other people are excluded from the license, and literature activities reproduce no text from copyrighted works. The project states that content and translations were produced with generative AI under editorial review, and that translations are machine-assisted and flagged for local educator review before classroom use, which is worth taking seriously before a district adopts them at scale. Every activity runs in the student’s browser with no logins and no data collection.

Connected Concepts

AI Literacy, Inclusive Learning, Multilingual Learning, Teacher AI Competency, Language Learning

Connected Resources

- Pressing Prompts

Assessment Instrument

The Institutional AI Readiness Pack

- **Open it:** https://mzyphur.github.io/ai-readiness/instruments.html
- **Made by:** Michael J. Zyphur (Instats)
- **Source code:** https://github.com/mzyphur/ai-readiness
- Type: Assessment Instrument, Collection Of Activities · Access: Free · License: CC BY 4.0
- **Link checked:** 2026-09-20

The Institutional AI Readiness Pack turns a competency framework for responsible AI in academic research into instruments a university can actually run. Each file is offered in HTML, Word and PDF, and the whole pack downloads as a zip under CC BY 4.0 with attribution — no permission needed to adapt it into your own documents.

What is in it

An **assessment suite**: a 20-cell institutional AI-readiness maturity self-assessment with a scoring workbook, a researcher and doctoral-student survey, a supervisor survey, a sixty-rung gap-analysis worksheet and action ladder, and a board and council one-pager. **Role briefings** for senior research leadership, deans of research, graduate-school leadership and research-integrity committees. A **policy library** with a model institutional AI-in-research policy and an AI-use disclosure standard, both meant to be rewritten.

Who it is for

Research leaders, committees and policy offices that need an evidence-based picture of how AI is used and governed across a research environment and a way to track change over time. It accompanies *Responsible AI in Academic Research: A Competency Framework for Research Training*, which defines five dimensions of readiness, and was written by Michael J. Zyphur, director of Instats.

Connected Concepts

AI Governance, Educational AI Policy, Change Management, Academic Integrity, AI Use and Disclosure Statements

Open Format Or Specification

LESSON.md

- **Open it:** https://lesson.md/
- **Made by:** Dan Bashaw (LXD Integral)
- Type: Open Format Or Specification, Agent Skill · Access: Free
- **Link checked:** 2026-09-20

LESSON.md is an open format for block-based eLearning content: a Markdown file with YAML frontmatter and `:::` directives for text, images and knowledge checks, readable by a person and parseable by any tool. It exists because course content is usually locked inside one authoring tool, and because large language models can only help with lessons they can actually read.

What you can do with it

Write a lesson in any text editor and import it into any tool that supports the format, without copy-paste and reformatting. Interactive pieces — multiple-choice knowledge checks with attempt limits and answer-level feedback — are expressed as simple properties rather than a GUI. A companion `ASSESSMENT.md` at a bundle root becomes the course's scored Assessment. The project also ships a `lesson-md` skill that teaches Claude, Codex or another agent the format, so describing a course in plain language returns lessons, assessments and a full bundle.

Who it is for

Instructional designers and course creators who want their content to survive a tool change, eLearning vendors who want an import and export format their users already understand, and anyone building AI-assisted authoring on top of a readable format. Contributors include Dan Bashaw of LXD Integral, and the format has a public changelog up to v1.8.

Connected Concepts

Learning Design, Open Source, Online Teaching and Learning, Multimodal AI, Educational Technology Developers, Assessment, Edtech Platform

Connected Resources

- The ID Toolbox
- LiaScript

LiaScript

- **Open it:** https://liascript.github.io/
- **Made by:** André Dietrich and contributors
- **Source code:** https://github.com/LiaScript/LiaScript
- Type: Open Format Or Specification, Software, Collection Of Tools · Access: Free · License: BSD-3-Clause
- **Link checked:** 2026-09-24

LiaScript is an extended Markdown dialect plus an interpreter for it. One plain text file becomes an interactive course: the same document can be read as a narrative, played as slides, or worked through as a course, all in the browser. Nothing needs installing to write or to read one.

What you can do with it

Quizzes come in the forms a teacher expects, including multiple choice, matrix questions, text input, dropdowns, and gap texts, written directly in Markdown. Code blocks can be made editable and runnable for programming tutorials, and a macro system wraps JavaScript libraries into reusable blocks so interactive diagrams need no code from each author. A course is hosted wherever the author already keeps text, with no service to be locked into, and everything runs client-side, so a loaded course works offline. The LiaScript Exporter packages one as SCORM for Moodle, ILIAS, and other learning management systems.

The teaching agent for building courses

The project also publishes a **teaching agent** for authoring LiaScript courses, licensed under the Boost Software License 1.0. Four agents for teaching, visual design, learner review, and publishing work around a single project file holding the course state, with a define-first workflow: objectives, audience, and didactics are settled before any material is written, and validation gates follow. A draft can be reviewed from a named learner persona to check cognitive load and assumed prior knowledge. The agent is editor-agnostic, generating configurations for Claude Code, Copilot, Codex, Cursor, or a web chat from one specification, and the repository doubles as a worked example, holding a six-unit course on the EU NIS2 Directive and a document describing how it was produced.

Notes and caveats

LiaScript is free, with no paid tier and no account requirement, and is developed in the open under BSD-3-Clause, so institutions can self-host and modify it. The Live Classroom feature deserves a look before you rely on it at scale, since real-time synchronisation uses a shared service rather than purely local rendering. The teaching agent is young and lightly adopted, so treat it as a working prototype rather than a supported product.

Connected Concepts

Learning Design, Open Source, Online Teaching and Learning, Active Learning, CS Education, Edtech Platform

Connected Resources

- LESSON.md

Ebook Or Guide

AI + OER Case Studies: A DOERS Project

- **Open it:** https://open.library.okstate.edu/ai-oercasestudies/
- **Made by:** Kathy Essmiller (editor), with 22 contributing authors
- Type: Ebook Or Guide, Case Study Collection · Access: Free · License: CC BY 4.0 for the collection, with a separate Creative Commons license chosen by each author
- **Link checked:** 2026-10-28

AI + OER Case Studies is an open anthology edited by Kathy Essmiller and published by Oklahoma State University Libraries in 2026, collecting eleven cases on where generative AI meets open educational resources in higher education. It grew out of a 2025 report for DOERS, Driving OER Sustainability for Student Success, a consortium of 45 higher-education systems covering more than 1,000 colleges.

What you can do with it

Read it as a set of project accounts rather than an evaluation. The book runs in three parts, Shared Values, Shared Practice and Shared Future, and the editor maps each chapter onto one of four policy priorities from the earlier report: centering students, engaging critically with generative AI, keeping policy pedagogically driven, and attending to all learners. Chapters include the City University of New York's route from a planned policy to published guidelines for generative AI in OER creation, constrained by a federated campus structure and a union contract; a human-in-the-loop revision of an open technical-communication textbook; co-creating institutional AI policy with students; and system-wide professional development across AI and OER. It ships as a Pressbooks book with EPUB, PDF and XHTML downloads.

Who it is for

Policy staff and library OER leads drafting guidance for a whole system, AI literacy coordinators planning professional development, and instructors or course designers adapting a textbook or a writing assignment. Each chapter was peer reviewed by invited scholars, and the cases were chosen for implications beyond one course.

Notes and caveats

Chapter licensing is the trap. The collection is CC BY 4.0, but individual authors retain copyright and chose their own Creative Commons licenses, so a chapter can be more restrictive than the book page suggests; the textbook-revision chapter is CC BY-NC-SA 4.0, and reuse has to check the chapter rather than the front matter. Authors had no required AI disclosure procedure, so most chapters discuss their process in passing, generally following the OER Commons guidance. By editorial choice each chapter keeps its author's disciplinary voice, punctuation and regional spelling, so the prose does not read uniformly. Above all, every chapter documents one local project and no two share an instrument or a comparison, so the volume offers practice to adapt rather than evidence to cite.

Connected Concepts

- Open Education
- Generative AI
- Educational AI Policy
- Change Management
- AI Literacy

AI Infused Assignment Playbook

- **Open it:** https://zenodo.org/records/23218828
- **Made by:** Sarah Lewis
- Type: Ebook Or Guide, Collection Of Activities, Assessment Instrument · Access: Free · License: CC BY 4.0
- **Link checked:** 2026-10-10

The **AI Infused Assignment Playbook** is a practical guide from Sarah Lewis (Barry University, social work) for instructors who want to integrate generative AI with intention rather than bolting it onto existing assignments. It pairs a pedagogical foundation — learning goals, critical thinking, student agency, transparency, and appropriate boundaries for AI use — with adaptable assignment templates, design frameworks, prompts, examples and implementation guidance that instructors can use across disciplines. The goal is explicitly not to prescribe one approach to AI but to help educators design learning experiences in which AI use is purposeful, transparent, and aligned with what students are expected to learn and demonstrate.

What you can do with it

The playbook is organized around a thesis in Chapter 1 that learning is *network construction*, not information accumulation — the offloading question at the center of AI literacy debate — so the real question is whether AI supports or bypasses that network-building work. Every assignment is built from five formative design principles: **structured prompts, not vague AI use** (students identify their purpose, relevant concepts, current understanding and the specific help they seek *before* they are allowed to prompt); **critical evaluation of AI outputs** (students document what they accept, modify and reject, and justify it); **documentation and transparency** (prompts, AI-response excerpts, decision logs and rationales make use assessable); **metacognitive reflection**; and **knowledge verification** via short closed-note checks.

Chapter 3 ships a fully worked sample assignment (AI-Enhanced Iterative Writing) plus sixteen condensed template entries — AI Dialogue Reflection, AI Literature Review Assistant, AI Bias Detection, AI Study Partner Reflection, AI-Assisted Self-Assessment, AI Debate Partner, AI Client Simulation, AI Scenario Testing, AI-Facilitated Group Project, Peer Review with AI Comparison, Professional AI Use Policy Development, and a Transparent AI Integration Portfolio. Appendix A provides an AI–Human Collaboration Log for capturing the process. Faculty can take single assignments à la carte or adopt a cluster as an AI-infused spine for a whole course.

Who it is for

Instructors across disciplines, especially in higher education and professional programs (the author writes from social work, and nursing/healthcare are named as parallel contexts), plus faculty developers and those preparing accreditation evidence. It assumes students are already using AI and that the responsible response is to bring that use into the open, structure it, and teach students to use AI well rather than hope they avoid it.

Notes and caveats

This is a practical guide, not an empirical study; its claims about student AI use rest on cited external sources (BestColleges, Campbell, Digital Education Council, Flaherty) rather than new data. The “network construction” framework and the “illusion of understanding” framing are drawn from the wider literature (Wigmore et al.; Williamson et al.) and are presented as pedagogical rationale, not tested outcomes of the playbook itself. The assignments are authored templates — none is reported with effect sizes, so they should be treated as designs to adapt and evaluate locally. Published 2026-10-07, v1, on Zenodo under CC BY 4.0; free to download without an account. As of ingestion the record shows only ~35 views and ~14 downloads, so it has seen little external use or peer review yet.

Connected Concepts

- AI Literacy
- Critical Thinking
- Cognitive Offloading
- Metacognition
- Academic Integrity
- Formative Assessment
- Authentic Assessment
- Curriculum Design
- AI Use and Disclosure Statements
- Prompt Engineering

Connected Resources

- The Pedagogical Promptbook
- Student Guide to AI
- Process Feedback
- The ID Toolbox

Building Intelligent Textbooks

- **Open it:** https://dmccreary.github.io/intelligent-textbooks/
- **Made by:** Dan McCreary
- **Source code:** https://github.com/dmccreary/intelligent-textbooks
- Type: Ebook Or Guide, Collection Of Activities · Access: Free · License: MIT (site content); CC BY-SA for MicroSims
- **Link checked:** 2026-10-10

The **Intelligent Textbooks** site is Dan McCreary's step-by-step guide to building *intelligent textbooks* — online textbooks that go beyond static PDFs by adding search, site navigation, a glossary of terms, a table of contents, quiz management, rendered formulas, social-media previews, link checking, and an easy-to-visualize **concept graph** showing all the concepts in a course and their dependencies. The guide argues that many courses today can benefit from high-quality online textbooks with these features, and it shows how to build them using the MkDocs build system paired with the Material theme and generative AI to create and maintain the content.

The defining move is that the textbook is *authored in Markdown and generated by AI*, a concrete instance of the AI-assisted authoring pattern applied to course content: rather than hand-maintaining a large site, you describe the course and let generative AI produce and maintain the pages, with the toolchain handling navigation, search and the concept graph. A companion Claude Code Skills library claims to automate over 90% of the tasks required to build a level-2 textbook from a course description.

A corollary resource: MicroSims

The natural companion to this guide is McCreary's **MicroSims** library at https://dmccreary.github.io/microsims/ (source: github.com/dmccreary/microsims), which supplies the interactive simulations an intelligent textbook embeds. A *MicroSim* (micro-simulation) is a simple interactive simulation generated with AI to help teachers explain a concept, and it can be embedded in an intelligent textbook or any site that accepts an `iframe`. MicroSims are distinctive for three reasons: **AI-assisted generation** (standardized design patterns turn a natural-language description of a simulation into a shareable asset), **universal embedding** (a single HTML `iframe` element drops one into any page), and **transparent, modifiable code** (no black box — one click opens the sim in a web editor, and a Creative Commons license lets most teachers use them without license fees). The term was coined by Valerie Lockhart in 2023 after she found teachers and students could build simulations with the p5.js JavaScript library with little or no training.

The project also publishes a JSON Schema for MicroSim metadata so AI tools can generate searchable descriptors, with a faceted MicroSim registry on the roadmap. A research paper describing the framework — *MicroSims: A Framework for AI-Generated, Scalable Educational Simulations with Universal Embedding and Adaptive Learning Support* — is on arXiv (2511.19864). Sample simulations include Bouncing Ball, Projectile Motion, String Harmonics, Conway's Game of Life, Euler's Formula, and a stock-market returns chart, each running live on the site.

Who it is for

Instructors and instructional designers who want to build or maintain a course textbook, especially in higher education and professional training, plus faculty developers and anyone using generative AI to author educational content. It suits educators who are comfortable with a Markdown-and-Git workflow (or willing to learn it) and who want the AI to handle the site plumbing — search, navigation, concept graph — so they can focus on the pedagogy.

Notes and caveats

This is a practitioner's guide and toolchain, not a peer-reviewed study — it presents a workflow and its own educational rationale ("intelligent textbooks guide students through concepts on their quest for knowledge") rather than evidence of learning outcomes. The MicroSim research paper is the closest thing to empirical backing, and it is self-published on arXiv. Both projects are open source (the intelligent-textbooks repo reports an MIT license and 38 stars; MicroSims reports a Creative Commons license and 13 stars) and actively maintained. Concept graphs and glossary-first structure are genuinely useful for discoverability, but the guide assumes a fairly technical authoring workflow — MkDocs, Git, and generative-AI tooling — which may be a barrier for some faculty. As of ingestion the registry for MicroSims is still only on the roadmap, so finding a specific existing simulation relies on the site's own search and navigation.

Connected Concepts

- Curriculum Design
- Learning Design
- Pedagogical Patterns
- Generative AI
- Simulation
- Knowledge Graph
- Vibe Coding
- Open Source
- Design Thinking
- Educational Development

Connected Resources

- The Pedagogical Promptbook
- The ID Toolbox
- Claw-ED

Campus AI Development

- **Open it:** https://campusaidev.com/home.dc
- **Made by:** Campus AI Development
- Type: Ebook Or Guide · Access: Free
- **Link checked:** 2026-10-24

Campus AI Development is a free web guide on building software with AI in higher education, written from the institution's side of the question: what a campus needs to know about the tools its own people build. It accompanies the Campus AI Framework, which decides whether an initiative proceeds, and covers how that initiative then gets built.

What you can do with it

A four-step path runs from whether the work is worth building, through the review route it needs, to build-buy-reuse economics, to six questions that pick one of five approaches and that approach's minimum controls; where the answers disagree, the strictest one wins. The approaches form a spectrum from Vibe Coding to multi-agent work under human gates and audit trails, compared on who reads the code, what counts as verification, which data the work may touch, and what it costs to own. A reference section adds low-code and enterprise platforms, builder scenarios, case studies, hypothetical discussion cases, and a thirteen-question AI Governance checklist.

Who it is for

Central and research IT that supplies platforms and review; governance offices covering security, privacy, accessibility, data governance, legal and procurement; CIOs, provosts and deans deciding what to fund; and the staff, faculty, researchers and students who build their own tools.

Notes and caveats

It calls itself an independent personal project, not institutional policy or legal advice; named institutions appear because they published accounts of their practice, not as endorsements, and the discussion cases are composites. Its legal examples are American (FERPA, ADA Title II, GLBA) and dated where they appear, though it argues the path, the questions, the data levels and the approaches do not depend on them. Its evidence page links every study, setting gains on one bounded task beside slowdowns for experienced maintainers on their own code, and it admits that trial data covers code suggestion rather than spec-driven or multi-agent work, so the case for more structure rests on practice and compliance logic. No reuse license is stated. Sibling sites campusdatagov.com and campusairegistry.com carry the data governance and agent registry parts, so this is a good entry to Educational AI Policy work but not a substitute for it.

Connected Concepts

- AI Governance

- Educational AI Policy
- Vibe Coding

Connected Resources

- Campus AI Framework

Campus AI Framework

- **Open it:** https://campusaiframework.com/sites
- **Made by:** Joe Sabado
- Type: Ebook Or Guide, Collection Of Tools · Access: Free · License: CC BY-NC-SA 4.0
- **Link checked:** 2026-09-28

The Campus AI Framework is a higher-education-native operating model for AI strategy and governance, published by Joe Sabado. It sets out eight AI Governance-facing institutional pillars — from campus mission and AI principles through policies, governance, engagement, readiness, roles and implementation — four application domains where AI is put to work (teaching, learning and student success; research and innovation; operations and infrastructure; student and community engagement), and an AI Strategic Compass for choosing and sequencing initiatives.

What you can do with it

The pillars name what an institution has to build; the Compass is the selection instrument, scoring candidates against strategic fit, ethics and compliance, financial viability, operational efficiency, efficacy and evidence, and stakeholder impact, and tracking them through a screen-score-select-plan- track-reflect cycle with KPIs, OKRs and efficacy measures. Working tools include a maturity assessment for readiness and capability, a tool evaluation matrix, and a governance guide. It is aimed at AI policy and strategy work rather than at classroom practice, and it treats AI literacy for everyone, competency by role and fluency for leaders as separate readiness needs. The site's tabbed diagram view maps each pillar to the companion sites that carry it further.

Who it is for

Cabinet leaders, provosts and CIOs deciding what to back; AI leads and governance committees sequencing the work; organizational change and adoption as the recurring theme; and unit-level practitioners who need a first concrete step. The site routes the three audiences to different entry points rather than one linear read.

Notes and caveats

The framework and site are licensed **CC BY-NC-SA 4.0**, so adaptation is permitted for non-commercial use with attribution and share-alike; the site supplies its own suggested attribution. Its alignment with OECD, NIST, ISO/IEC 42001, the EU AI Act, FERPA and HIPAA is the publisher's own comparison and should be read as such. The companion sites are separate projects, several by the same author, and are worth knowing as a set: Campus AI Exchange is the hub, holding interactive maps of institutional AI policies and classroom guidance, AI governance self-assessment, data governance and AI positions maps, and a resource library. Around it sit campusaigovernance.com (nine AI governance domains), campusairisks.com (the NIST AI Risk Management Framework applied to those domains), campusaioperations.com, campusairegistry.com, a unit-level AI adoption plan template, and a briefing on agentic AI for executives. The Strategic Compass also circulates as a shared Google document, which needs a Google account to open. A short optional onboarding

question about role and institution appears on entry; email is optional and the whole site is readable without it.

Connected Concepts

- Educational AI Policy
- Change Management
- AI Literacy
- AI Governance

Connected Resources

- Campus AI Development

Integrating AI in TVET: a practical guide for institutions

- **Open it:** https://unesdoc.unesco.org/ark:/48223/pf0000398609
- **Made by:** Congkun Yang, Wenxi Wu and Hannes Tegelbeckers for UNESCO-UNEVOC
- Type: Ebook Or Guide · Access: Free · License: CC BY-SA 3.0 IGO
- **Link checked:** 2026-10-28

Integrating AI in TVET is a UNESCO-UNEVOC guide for institutions that train technicians, tradespeople and other skilled workers, developed with the UNEVOC Network and international TVET experts and published open access in 2026. It is a normative document: principles, a phased institutional path and working instruments, not a report on what AI does to vocational learning.

What you can do with it

Three annexes carry the usable material. Annex A is an AI readiness self-reflection tool for a small cross-functional team: seven dimensions running from leadership and governance through data readiness, curriculum, partnerships and funding, each scored on four maturity levels from not yet started to established, ending with a few feasible first steps. Annex B is an illustrative AI risk register. Annex C is an indicator framework in seven domains mirroring the institutional chapters, each with sub-themes, key indicators and candidate data sources such as policy version history, tracer surveys and staff surveys. The teaching chapter adds a ladder for how far AI enters a task: AI-aware learning, where learners examine how AI is reshaping a trade without using it; AI- supported, where AI plans or prepares while the learner performs the task; and AI-enhanced, where it supports work in progress. Chapter 5.5 aligns staff and learner AI competency with UNESCO’s own frameworks for teachers and students.

Who it is for

Leaders of TVET institutions deciding what to do first, teachers and trainers who need a defensible line between where AI helps and where unaided practice stays essential, and qualification staff revising occupational standards. The recommendations chapter is sorted by audience, so each can begin in its own section.

Notes and caveats

It is guidance, not evaluation. The guide reports no outcome data, and its institutional examples, a content-integrated AI learning model at the College of the North Atlantic in Canada and Kenya’s 2023 TVET industrial attachment standard, are descriptive case boxes sourced to project reports, not independent trials. The annexes call themselves indicative; the maturity scale is a discussion aid, not a measurement instrument. Safety-critical and regulated occupations get a chapter, but it argues a position on human oversight rather than offering regulation-level detail. The CC BY-SA 3.0 IGO license permits adaptation and republication with attribution and share-alike.

Connected Concepts

- Vocational Education and Training
- AI Literacy
- Workplace Learning
- Change Management
- Educational AI Policy
- Equity

Learning Design Wiki

- **Open it:** http://wiki.learningdesignalliance.org/
- **Made by:** Learning Design Alliance
- **Source code:** https://github.com/Learning-Design-Alliance/learning-wiki
- Type: Ebook Or Guide, Collection Of Activities · Access: Free · License: CC BY-SA 4.0 for the content, MIT for the code
- **Link checked:** 2026-10-24

The **Learning Design Wiki** splits the design of teaching into separable parts and binds each part to the studies behind it, carrying 170 principles, 1,057 elements, 54 patterns, 1,010 designs, 1,903 products and programs, and 6,700 strategies as of October 2026. Every element and pattern links to claims, and every claim to a source, so a reader working on instructional design can start from a principle, drop to the elements it implies, and arrive at the citation.

The evidence layer is the part worth knowing. The wiki's own report counts 6,849 distinct studies behind 26,495 claims, of which 31% are experiments or systematic reviews and 2% are pre-registered trials or well-powered meta-analyses. It also reports that 98% of claims rest on a single study, and that only 24% of the studies print an effect size for the finding being cited.

What you can do with it

Browse by knowledge type rather than keyword. Principles state a design commitment, elements are the instructional building blocks, patterns assemble elements into a lesson-level design, designs apply a pattern to a named setting, and strategies are the finer moves. Claim pages list the studies bearing on one question as rows in a table instead of averaging them, so disagreement stays visible.

Who it is for

Instructional designers and instructors who want a design decision with its evidence attached, and researchers who want a mapped corpus of learning theories in design terms. Teams building generative AI design assistants can use it as a structured reference, since the site publishes a machine-readable bundle rather than a set of web pages.

Notes and caveats

Read the trust panel on every page. Language models maintain the wiki under one human maintainer, no person has checked any page, and the site labels a page a well-sourced lead rather than a finding. Claims carry a design tier, an effect size code and a rigour code, and "no effect size printed" means the source reported none, not that none exists. Content is CC BY-SA 4.0, so reuse must carry the same license, and the code is MIT.

Connected Concepts

Learning Design, Pedagogical Patterns, Theories and Frameworks, AI-Assisted Educational Research, Limitations in AIEd Research, Interpreting and Applying AIEd Research

Student Guide to AI

- **Open it:** https://studentguidetoai.org/
- **Made by:** Elon University Imagining the Digital Future Center, AAC&U and The Princeton Review
- Type: Ebook Or Guide, Collection Of Activities, Assessment Instrument · Access: Free · License: CC BY-NC-SA 4.0
- **Link checked:** 2026-09-28

The Student Guide to Artificial Intelligence is a free publication series from Elon University's Imagining the Digital Future Center, the American Association of Colleges and Universities and, since 2026, The Princeton Review. Three editions build on each other: an introduction to AI tools for college students in 2024, practical guidance on skills, ethics, academic integrity and careers in 2025, and in 2026 *Human Wisdom for the Age of AI*, a field guide that turns away from tool instruction toward the human capacities that AI literacy is often reduced to.

What you can do with it

The 2026 field guide works through ten capacities — curiosity, critical thinking, focused and deep thinking, creativity, emotional and social intelligence, communications, wisdom, ethics, adaptability and self identity — each set against a thinker from the past, plus a bonus module on contemporary scholars. Every capacity has a companion teacher's guide module with lesson suggestions, worksheets and discussion questions, downloadable individually or as one combined PDF, and usable in any order. The series also ships a scenario-based **Human Wisdom Self-Assessment**: anonymous, no right or wrong answers, with options ordered along a continuum from relying on AI immediately through working with it as a co-pilot to leading with your own judgment. Its authors position it as a formative diagnostic to run before reading the guide and discuss rather than a test.

Who it is for

Undergraduates in any discipline, and upper secondary students. Faculty, academic support staff, librarians and student affairs educators get the module set and the discussion prompts; the guide is deliberately discipline-neutral, which is why institutions use it for first-year seminars, faculty development and shared vocabulary across separate AI initiatives.

Notes and caveats

The guide is formatively framed and says so: scores are a snapshot of habits, not a grade, a trait or a prediction, and students are told not to share them publicly.

The framing around AI rests on cited survey and experimental evidence that outsourcing effort can leave students retaining less — which is the offloading question the guide is written to counter, not to settle. The field guide PDF sits behind a short form asking name, role, institution and email; the teacher's guide modules and the pedagogical framework paper download directly. The interactive version runs in Gemini

Notebook and needs a Google account. Publisher figures of more than 40,000 PDF downloads across about 4,000 institutions in 180 countries, and over 130 custom campus editions, are theirs, as are the endorsements from ALA, NASPA, EDUCAUSE, OLC, CAA, the Gardner Institute and RTI International.

Connected Concepts

- AI Literacy
- Critical Thinking
- Cognitive Offloading
- Academic Integrity
- Metacognition